OPENNURSING.CA • CANADIAN NURSING OPEN EDUCATIONAL RESOURCE

First Edition • 2026

Medical-Surgical Nursing

A Canadian Open Text

Evidence-Informed Adult Acute Care Across Canadian Health Systems

ARCHITECTURE OF THE TEXT — NINE CLINICAL UNITS • THIRTY-SIX CHAPTERS

Unit I • Ch. 1–6
Foundations, Indigenous Cultural Safety, Fluids, Sepsis, Pain & Shock

Unit II • Ch. 7–11
Perioperative Care, Older Adults, Oncology, Palliative Care & Substance Use

Unit III • Ch. 12–15
Respiratory Assessment, Oxygen Therapy, COPD, Asthma, ARDS & PE

Unit IV • Ch. 16–19
Cardiovascular Assessment, Dysrhythmias, ACS, Heart Failure & Vascular Care

Unit V • Ch. 20–23
Hematology, Transfusion, Immunity, HIV, Diabetes & Endocrine Disorders

Unit VI • Ch. 24–26
Upper & Lower Gastrointestinal, Hepatic, Biliary & Pancreatic Nursing Care

Unit VII • Ch. 27–29
Acute Kidney Injury, Chronic Kidney Disease, Dialysis, Urology & Reproductive Health

Unit VIII • Ch. 30–32
Neurologic Assessment, Increased ICP, Stroke, TBI, SCI & Chronic Neurologic Care

Unit IX • Ch. 33–36
Musculoskeletal Trauma, Orthopedics, Arthritis, Wounds, Burns, Eye & Ear Care

Andrew Lee, BEd, BN, MN, RN, CCN(C)
Professor of Nursing • Loyalist College, Belleville, Ontario

36 CHAPTERS • 245 FIGURES • 1,310 QUESTIONS

Creative Commons CC BY-NC-SA 4.0 International

Medical-Surgical Nursing: A Canadian Open Text

Evidence-Informed Adult Acute Care Across Canadian Health Systems

Andrew Lee, BEd, BN, MN, RN, CCN(C)

Professor of Nursing • School of Health, Human and Justice Studies
Loyalist College, Belleville, Ontario, Canada

Certification: Canadian Nurses Association Certification in Cardiovascular Nursing — CCN(C)
Online Portal: https://opennursing.ca • **Contact:** andrewleenl@gmail.com

Copyright, Open Licence & Clinical Notice

Title: *Medical-Surgical Nursing: A Canadian Open Text* (First Edition, October 2026)
Author: Andrew Lee, BEd, BN, MN, RN, CCN(C), Professor of Nursing, Loyalist College, Belleville, Ontario
Online Home: https://opennursing.ca

CREATIVE COMMONS OPEN LICENCE • CC BY-NC-SA 4.0

Free to Share and Adapt for Non-Commercial Nursing Education

Unless otherwise noted in individual figure credit lines, this textbook is licensed under a **Creative Commons Attribution-NonCommercial-ShareAlike 4.0 International Licence (CC BY-NC-SA 4.0)**. You are free to copy, redistribute, remix, and adapt this work for non-commercial educational purposes, provided appropriate credit is given to **Andrew Lee, BEd, BN, MN, RN, CCN(C)** and any derivative works are shared under the same licence.

Suggested Citation: Lee, A. (2026). *Medical-Surgical Nursing: A Canadian Open Text* (1st ed.). Loyalist College. https://opennursing.ca (CC BY-NC-SA 4.0).

Canadian Clinical Practice & Medication Notice

Nursing practice, diagnostic protocols, and drug therapies evolve continuously. While every chapter has been verified against current Canadian clinical practice guidelines, provincial and territorial regulatory standards, and the Health Canada Drug Product Database as of October 2026, clinicians and students must always verify medication dosages, contraindications, reconstitution instructions, and infusion rates against current official Canadian product monographs, institutional formularies, and employer policies before administration.

Statement on Indigenous Health Data & OCAP® Principles

Whenever epidemiological or clinical studies involving First Nations, Inuit, or Métis peoples are discussed across this textbook, findings are contextualized within the historical and ongoing impacts of colonization, Indian hospitals, residential schools, and systemic racism in health care, and interpreted in respect of the First Nations principles of **Ownership, Control, Access, and Possession (OCAP®)** (OCAP® is a registered trademark of the First Nations Information Governance Centre [FNIGC]).

Indigenous Land Acknowledgement

This open textbook was authored in Belleville and Brighton, Ontario, on the traditional, ancestral, and treaty lands of the Anishinaabeg, Huron-Wendat, and Haudenosaunee peoples, adjacent to the Tyendinaga Mohawk Territory (Mohawks of the Bay of Quinte). As nurses and educators working across Turtle Island, we commit to enacting the Truth and Reconciliation Commission of Canada Calls to Action 18 through 24, Joyce's Principle, and culturally safe, anti-racist care at every bedside.

STATEMENT ON OPEN EDUCATION • OPENNURSING.CA *Author's Statement*

§ Why This Book Is Open

> *"Higher education shall be equally accessible to all on the basis of merit."*
>
> — *Universal Declaration of Human Rights*, Article 26 (United Nations, 1948)

Knowledge that heals belongs to everyone it might help. A patient never asks what their nurse could afford to learn; they hope only that the nurse knows enough to keep them safe. A barrier between a student and that knowledge is, in the end, a barrier between a patient and good care.

Nursing rests on a moral claim: every person has equal worth, and care should follow need rather than wealth or place. We cannot teach that principle honestly from a book only some students can afford. Cost falls hardest on those already carrying the most, and removing it is a matter of fairness, not charity.

For this reason, *Medical-Surgical Nursing: A Canadian Open Text* is free to read, download and print, under a Creative Commons Attribution-NonCommercial-ShareAlike 4.0 International licence (CC BY-NC-SA 4.0). Instructors may adapt it, provided what they build stays open. Openness also means access: the book is designed to meet Ontario's accessibility requirements (AODA) and WCAG 2.1 Level AA, so that no student is shut out by disability.

Open education rests on the belief that we learn best together. If you find an error, a barrier or a way to improve this book, please tell me (andrewleenl@gmail.com). Each correction is a small act of care for the next student, and for the patients that student will serve.

Andrew Lee, BEd, BN, MN, RN, CCN(C)
Professor of Nursing, Loyalist College

Reference: United Nations. (1948). *Universal declaration of human rights*. https://www.un.org/en/about-us/universal-declaration-of-human-rights

Preface & Pedagogical Architecture

For decades, Canadian Bachelor of Science in Nursing (BScN) and Practical Nursing (RPN/LPN) students have been asked to learn adult medical-surgical nursing from expensive commercial textbooks written for the United States health care market—or from lightly edited adaptations that retain US conventional laboratory units, FDA drug trade names, insurance-driven discharge models, and US scope-of-practice rules. **Medical-Surgical Nursing: A Canadian Open Text** was written from the ground up to give Canadian nursing students a rigorous, free, genuinely Canadian clinical text.

How This Textbook Supports Canadian Nursing Curricula

Architectural Feature	Clinical & Educational Design
100% Canadian SI Units & DPD Drugs	Every laboratory value uses Canadian SI units (mmol/L, µmol/L, g/L), and every medication is verified against the Health Canada Drug Product Database (recognizing Canadian generic names such as salbutamol, epinephrine, furosemide, and dimenhydrinate).
Dual-Track Core & Going Deeper Design	Core sections cover entry-to-practice competencies shared by all nursing students (NCLEX-RN, REx-PN, and CPNRE), while *Going Deeper* callouts and **[RN]** questions address complex multisystem titration and unstable acute care.
RN / RPN / LPN Scope in Practice	Applies CNO's Scope of Practice framework (authority, competence, and context) and BCCNM, CRNA, OIIQ, and Atlantic/Prairie regulatory standards to real bedside assignment and consultation decisions.
36 Unfolding Practice Stories	Each chapter follows a unique named Canadian nurse (18 RNs and 18 RPNs/LPNs) and adult patient from presentation through discharge across urban tertiary centres, rural community hospitals, and northern nursing stations.
1,310 Licensure Review Questions	Every chapter concludes with 30 to 40 NCLEX-RN, REx-PN, and CPNRE clinical judgment questions—including linked unfolding case studies—complete with option-by-option rationales.

MEDICAL-SURGICAL NURSING: A CANADIAN OPEN TEXT *Contents*

TOC Brief Contents (Units I–IX • Chapters 1–36)

Chapter	Unit / Chapter Title	Page
UNIT I — Foundations of Canadian Medical-Surgical Practice		**1**
Chapter 1	Medical-Surgical Nursing in Canada	2
Chapter 2	Equity, Cultural Safety and Indigenous Health in Adult Care	35
Chapter 3	Fluids, Electrolytes and Acid–Base Balance	67
Chapter 4	Inflammation, Infection and Sepsis	97
Chapter 5	Pain	125
Chapter 6	Recognizing Deterioration and Shock	152
UNIT II — Cross-Cutting Clinical Priorities in Adult Care		**178**
Chapter 7	Perioperative Nursing	179
Chapter 8	Older Adults in Acute Care	206
Chapter 9	Cancer Care	234
Chapter 10	Palliative and End-of-Life Care	264
Chapter 11	Substance Use in Acute Care	290
UNIT III — Respiratory Nursing Care		**317**
Chapter 12	Respiratory Assessment and Oxygen Therapy	318
Chapter 13	Lower Respiratory Infections and Lung Cancer	349
Chapter 14	Obstructive and Restrictive Lung Disease	380
Chapter 15	Acute Respiratory Failure and Pulmonary Embolism	409
UNIT IV — Cardiovascular & Vascular Nursing Care		**438**
Chapter 16	Cardiac Assessment and Dysrhythmias	439
Chapter 17	Coronary Artery Disease and Acute Coronary Syndromes	476
Chapter 18	Heart Failure, Valvular and Inflammatory Heart Disease	504
Chapter 19	Hypertension and Vascular Disorders	538
UNIT V — Hematologic, Immunologic & Endocrine Care		**568**
Chapter 20	Hematologic Disorders and Transfusion	569
Chapter 21	Immunity, Allergy and HIV	601
Chapter 22	Diabetes	635
Chapter 23	Thyroid, Parathyroid, Adrenal and Pituitary Disorders	665
UNIT VI — Gastrointestinal, Hepatic, Biliary & Pancreatic Care		**695**
Chapter 24	Upper Gastrointestinal Disorders and Nutrition	696

Chapter	Unit / Chapter Title	Page
Chapter 25	Lower Gastrointestinal Disorders	727
Chapter 26	Liver, Biliary and Pancreatic Disorders	759
UNIT VII — Renal, Urologic & Reproductive Health Care		**790**
Chapter 27	Acute Kidney Injury and Chronic Kidney Disease	791
Chapter 28	Urinary Tract and Prostate Disorders	822
Chapter 29	Reproductive and Breast Health in Adult Care	852
UNIT VIII — Neurologic & Cerebrovascular Nursing Care		**882**
Chapter 30	Neurologic Assessment and Increased Intracranial Pressure	883
Chapter 31	Stroke	913
Chapter 32	Traumatic Brain and Spinal Cord Injury and Chronic Neurologic Disorders	943
UNIT IX — Musculoskeletal, Integumentary & Sensory Care		**975**
Chapter 33	Musculoskeletal Trauma and Orthopedic Surgery	976
Chapter 34	Arthritis and Connective Tissue Disorders	1008
Chapter 35	Skin, Wounds and Burns	1040
Chapter 36	Eye and Ear Disorders	1075
Back Matter — Adult SI Lab Values, Cumulative Glossary (1651 Terms), Figure Credits (245 Figures) & Subject Index		**1105**

MEDICAL-SURGICAL NURSING: A CANADIAN OPEN TEXT *Section Guide*

§ Detailed Table of Contents & Section Guide

UNIT I — Foundations of Canadian Medical-Surgical Practice p. 1

01 Medical-Surgical Nursing in Canada p. 2
Introduction • 1.1 What Medical-Surgical Nursing Is • 1.2 Where Adults Receive Care in Canada • 1.3 The Medical-Surgical Team and Scope of Practice • 1.4 Clinical Judgment: The Clinical Judgment Measurement Model • 1.5 Professional, Legal and Ethical Foundations • 1.6 Safety and Quality in Medical-Surgical Care • 1.7 Partnering with Patients Across Transitions • 1.8 Using This Book

02 Equity, Cultural Safety and Indigenous Health in Adult Care p. 35
Introduction • 2.1 Health Equity and the Determinants of Health • 2.2 Cultural Safety, Humility and Trauma- and Violence-Informed Care • 2.3 First Nations, Inuit and Métis Health • 2.4 Rights, Policy and Data • 2.5 Caring for Other Equity-Deserving Adults • 2.6 Equity in Everyday Medical-Surgical Practice

03 Fluids, Electrolytes and Acid–Base Balance p. 67
Introduction • 3.1 Body Fluids and How They Are Regulated • 3.2 Fluid Volume Deficit and Excess • 3.3 IV Fluids and Fluid Management • 3.4 Sodium Imbalances • 3.5 Potassium Imbalances • 3.6 Calcium, Magnesium and Phosphate • 3.7 Acid–Base Balance

04 Inflammation, Infection and Sepsis p. 97
Introduction • 4.1 Inflammation and Healing • 4.2 Infection: Recognition and Diagnostics • 4.3 Infection Prevention and Control on the Unit • 4.4 Antibiotic-Resistant Organisms and C. difficile • 4.5 Antimicrobial Stewardship and the Nurse • 4.6 Sepsis

05 Pain p. 125
Introduction • 5.1 Understanding Pain • 5.2 Pain Assessment • 5.3 Multimodal and Non-Opioid Analgesia • 5.4 Opioids: Safe Use in Hospital • 5.5 Patients Living With Chronic Pain or Opioid Use Disorder

06 Recognizing Deterioration and Shock p. 152
Introduction • 6.1 Recognizing Clinical Deterioration • 6.2 Early Warning Scores and Escalation • 6.3 Shock: How It Develops • 6.4 Hypovolemic and Cardiogenic Shock • 6.5 Distributive and Obstructive Shock • 6.6 Nursing Care of the Patient in Shock

UNIT II — Cross-Cutting Clinical Priorities in Adult Care p. 178

07 Perioperative Nursing p. 179
Introduction • 7.1 The Perioperative Journey • 7.2 Preoperative Assessment and Preparation • 7.3 Consent and the Day of Surgery • 7.4 Anesthesia and Sedation • 7.5 Care After Anesthesia (PACU) • 7.6 Postoperative Care and Complications

08 Older Adults in Acute Care p. 206
Introduction • 8.1 Aging, Frailty and Acute Care • 8.2 Delirium • 8.3 Dementia and Depression in Hospital • 8.4 Falls and Functional Decline • 8.5 Medications in Older Adults • 8.6 Restraints, Capacity and Transitions

09 Cancer Care p. 234
Introduction • 9.1 Cancer Biology • 9.2 Cancer in Canada: Risk, Prevention and Screening • 9.3 Cancer Treatments • 9.4 Oncologic Emergencies • 9.5 Safe Handling of Hazardous Drugs • 9.6 Living With Cancer: Support and Survivorship

10 Palliative and End-of-Life Care p. 264
Introduction • 10.1 The Palliative Approach • 10.2 Advance Care Planning and Goals of Care • 10.3 Managing Symptoms • 10.4 Medical Assistance in Dying • 10.5 The Last Days and Care After Death • 10.6 Grief and Caring for Ourselves

11 Substance Use in Acute Care p. 290
Introduction • 11.1 Substance Use, Stigma and Health • 11.2 Screening and Brief Intervention in Hospital • 11.3 Alcohol Withdrawal • 11.4 Opioid Toxicity and Withdrawal • 11.5 Stimulants, Cannabis and Other Substances • 11.6 Harm Reduction and Transitions

UNIT III — Respiratory Nursing Care p. 317

12 Respiratory Assessment and Oxygen Therapy p. 318
Introduction • 12.1 Breathing and Gas Exchange: A Brief Review • 12.2 Focused Respiratory Assessment • 12.3 Pulse Oximetry and Other Measures • 12.4 Oxygen Therapy • 12.5 Airway Clearance • 12.6 Artificial Airways and Tracheostomy Care

13 Lower Respiratory Infections and Lung Cancer p. 349
Introduction • 13.1 Community-Acquired Pneumonia • 13.2 Hospital-Acquired and Aspiration Pneumonia • 13.3 Influenza, COVID-19 and RSV • 13.4 Tuberculosis • 13.5 Lung Cancer • 13.6 Pleural Effusion and Empyema

14 Obstructive and Restrictive Lung Disease p. 380
Introduction • 14.1 Obstructive and Restrictive Patterns • 14.2 Asthma • 14.3 Inhaled Medications and Devices • 14.4 Chronic Obstructive Pulmonary Disease • 14.5 Smoking and Vaping Cessation • 14.6 Bronchiectasis, Interstitial Lung Disease and Sleep Apnea

15 Acute Respiratory Failure and Pulmonary Embolism p. 409
Introduction • 15.1 Acute Respiratory Failure • 15.2 Acute Respiratory Distress Syndrome • 15.3 Non-invasive and Mechanical Ventilation • 15.4 Pneumothorax and Chest Injury • 15.5 Chest Tubes and Chest Drainage • 15.6 Pulmonary Embolism

UNIT IV — Cardiovascular & Vascular Nursing Care p. 438

16 Cardiac Assessment and Dysrhythmias p. 439
Introduction • 16.1 The Heart and Its Rhythm: A Brief Review • 16.2 Focused Cardiovascular Assessment • 16.3 Cardiac Tests • 16.4 Cardiac Monitoring and Reading a Rhythm Strip • 16.5 Common Dysrhythmias and How to Respond • 16.6 Atrial Fibrillation and Flutter • 16.7 Heart Blocks, Pacemakers and Implantable Devices

17 Coronary Artery Disease and Acute Coronary Syndromes p. 476
Introduction • 17.1 Atherosclerosis and Cardiovascular Risk • 17.2 Stable Angina and Chronic Coronary Disease • 17.3 Recognizing Acute Coronary Syndromes • 17.4 Early Treatment and Complications of ACS • 17.5 Care Around PCI and CABG • 17.6 Cardiac Rehabilitation and Living With Coronary Disease

18 Heart Failure, Valvular and Inflammatory Heart Disease p. 504
Introduction • 18.1 Heart Failure: How It Develops • 18.2 Recognizing and Managing Worsening Heart Failure • 18.3 Medications and Devices • 18.4 Self-Management and Transitions • 18.5 Valvular Heart Disease • 18.6 Infective Endocarditis • 18.7 Pericarditis, Myocarditis and Cardiomyopathies

19 Hypertension and Vascular Disorders p. 538
Introduction • 19.1 Hypertension: Measurement and Risk • 19.2 Treating Hypertension • 19.3 Hypertensive Emergencies and Acute Aortic Syndromes • 19.4 Peripheral Arterial Disease • 19.5 Abdominal Aortic Aneurysm • 19.6 Venous Disease and VTE • 19.7 Anticoagulation

UNIT V — Hematologic, Immunologic & Endocrine Care p. 568

20 Hematologic Disorders and Transfusion p. 569
Introduction • 20.1 Blood and Its Tests • 20.2 Anemias • 20.3 Sickle Cell Disease and Thalassemia • 20.4 Bleeding and Clotting Disorders • 20.5 Leukemia, Lymphoma and Myeloma • 20.6 Blood Components and Transfusion

21 Immunity, Allergy and HIV p. 601
Introduction • 21.1 The Immune System: A Focused Review • 21.2 Hypersensitivity and Allergy • 21.3 Immunodeficiency and the Immunocompromised Patient • 21.4 HIV: Infection, Testing and Prevention • 21.5 Living With HIV: Treatment and Nursing Care • 21.6 Autoimmunity and Adult Immunization

22 Diabetes p. 635
Introduction • 22.1 Glucose Regulation and Types of Diabetes • 22.2 Monitoring Glucose • 22.3 Insulin and Non-Insulin Medications • 22.4 Hypoglycemia • 22.5 Hyperglycemic Emergencies: DKA and HHS • 22.6 Diabetes in Hospital, Complications and Living Well

23 Thyroid, Parathyroid, Adrenal and Pituitary Disorders p. 665
Introduction • 23.1 Endocrine Feedback and Testing • 23.2 Thyroid Disorders • 23.3 Thyroid and Parathyroid Surgery • 23.4 Adrenal Disorders • 23.5 Pituitary Disorders and Water Balance

UNIT VI — Gastrointestinal, Hepatic, Biliary & Pancreatic Care p. 695

24 Upper Gastrointestinal Disorders and Nutrition p. 696
Introduction • 24.1 Digestion and Nutrition Assessment • 24.2 Enteral and Parenteral Nutrition • 24.3 Dysphagia and Texture-Modified Diets • 24.4 GERD, Gastritis and Peptic Ulcer Disease • 24.5 Upper Gastrointestinal Bleeding • 24.6 Obesity and Bariatric Surgery

25 Lower Gastrointestinal Disorders p. 727
Introduction • 25.1 Bowel Function, Constipation and Diarrhea • 25.2 Inflammatory Bowel Disease • 25.3 Diverticular Disease and Appendicitis • 25.4 Bowel Obstruction and Ileus • 25.5 Colorectal Cancer Care • 25.6 Ostomy Care and Teaching

26 Liver, Biliary and Pancreatic Disorders p. 759
Introduction • 26.1 The Liver, Biliary Tree and Pancreas • 26.2 Viral Hepatitis and Steatotic Liver Disease • 26.3 Cirrhosis and Its Complications • 26.4 Alcohol-Related Liver Disease, Acute Liver Failure and Transplant • 26.5 Gallbladder and Biliary Disease • 26.6 Acute and Chronic Pancreatitis

UNIT VII — Renal, Urologic & Reproductive Health Care p. 790

27 Acute Kidney Injury and Chronic Kidney Disease p. 791
Introduction • 27.1 Kidney Function and Kidney Tests • 27.2 Acute Kidney Injury • 27.3 Chronic Kidney Disease • 27.4 Dialysis • 27.5 Kidney Transplant • 27.6 Kidney Health in Canada and Living Well With CKD

28 Urinary Tract and Prostate Disorders p. 822
Introduction • 28.1 Urinary Tract Infection • 28.2 Urinary Catheters and CAUTI Prevention • 28.3 Urinary Retention and Incontinence • 28.4 Kidney Stones • 28.5 Benign Prostatic Hyperplasia and Prostate Surgery • 28.6 Prostate and Bladder Cancer

29 Reproductive and Breast Health in Adult Care p. 852
Introduction • 29.1 Sexual Health in Medical-Surgical Care • 29.2 Breast Cancer Care • 29.3 Gynecologic Conditions and Surgery • 29.4 Menopause and Midlife Health • 29.5 Sexually Transmitted and Blood-Borne Infections • 29.6 Erectile Dysfunction and Gender-Affirming Care

UNIT VIII — Neurologic & Cerebrovascular Nursing Care p. 882

30 Neurologic Assessment and Increased Intracranial Pressure p. 883
Introduction • 30.1 The Nervous System: A Focused Review • 30.2 Focused Neurologic Assessment • 30.3 Neurologic Diagnostics • 30.4 Increased Intracranial Pressure • 30.5 Seizures and Status Epilepticus • 30.6 Headache, Central Nervous System Infections and Brain Tumours

31 Stroke p. 913
Introduction • 31.1 Understanding Stroke • 31.2 Recognizing Stroke and Code Stroke • 31.3 Hyperacute Treatment • 31.4 Hemorrhagic Stroke • 31.5 Stroke Unit Care • 31.6 Rehabilitation, Transitions and Living After Stroke

32 Traumatic Brain and Spinal Cord Injury and Chronic Neurologic Disorders p. 943
Introduction • 32.1 Traumatic Brain Injury and Concussion • 32.2 Spinal Cord Injury • 32.3 Multiple Sclerosis • 32.4 Parkinson Disease • 32.5 Myasthenia Gravis and Guillain–Barré Syndrome • 32.6 Amyotrophic Lateral Sclerosis and Living With Progressive Neurologic Disease

UNIT IX — Musculoskeletal, Integumentary & Sensory Care p. 975

33 Musculoskeletal Trauma and Orthopedic Surgery p. 976
Introduction • 33.1 Fractures and Their Care • 33.2 Complications After Musculoskeletal Injury • 33.3 Osteoporosis and Bone Health • 33.4 Hip Fracture in Older Adults • 33.5 Joint Replacement and Spine Surgery • 33.6 Amputation • 33.7 Mobility and Safe Patient Handling

34 Arthritis and Connective Tissue Disorders p. 1008
Introduction • 34.1 Joints, Inflammation and Arthritis in Canada • 34.2 Osteoarthritis • 34.3 Rheumatoid Arthritis • 34.4 Gout • 34.5 Lupus and Other Connective Tissue Disorders • 34.6 Medicines for Inflammatory Arthritis • 34.7 Living Well With Chronic Arthritis

35 Skin, Wounds and Burns p. 1040
Introduction • 35.1 Skin Structure and Assessment • 35.2 Pressure Injuries • 35.3 Wound Healing and Wound Care • 35.4 Surgical Wounds and Skin Infections • 35.5 Burns • 35.6 Skin Cancer and Other Common Skin Conditions

36 Eye and Ear Disorders p. 1075
Introduction • 36.1 Vision and Eye Assessment • 36.2 Cataract, Glaucoma and Other Causes of Vision Loss • 36.3 Eye Emergencies, Trauma and Eye Surgery • 36.4 Hearing and Ear Assessment • 36.5 Communication Access, Hearing Aids and Cochlear Implants • 36.6 Ear Disorders and Ear Surgery

I Foundations of Canadian Medical-Surgical Practice

UNIT CLINICAL SCOPE & INTEGRATION

Establishes the legal, ethical, regulatory, and physiological foundations of adult acute-care nursing across Canada. Chapters 1 through 6 examine the Canada Health Act, provincial and territorial RN/RPN/LPN scopes of practice, Indigenous cultural safety and TRC Calls to Action 18–24, fluid/electrolyte and acid–base balance in SI units, infectious disease and sepsis, acute and chronic pain stewardship, and early recognition of clinical deterioration and shock.

Contents of UNIT I

Chapter	Chapter Title	Visual Assets	Page
Chapter 1	Medical-Surgical Nursing in Canada	11 Figs • 6 Tbls	p. 2
Chapter 2	Equity, Cultural Safety and Indigenous Health in Adult Care	3 Figs • 5 Tbls	p. 35
Chapter 3	Fluids, Electrolytes and Acid–Base Balance	6 Figs • 4 Tbls	p. 67
Chapter 4	Inflammation, Infection and Sepsis	4 Figs • 4 Tbls	p. 97
Chapter 5	Pain	2 Figs • 4 Tbls	p. 125
Chapter 6	Recognizing Deterioration and Shock	4 Figs • 4 Tbls	p. 152

01 Medical-Surgical Nursing in Canada

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Describe medical-surgical nursing and the settings and transitions in which adults receive care in Canada.
2. Explain how the Canada Health Act and provincial and territorial delivery shape adults' access to hospital and community care, using Ontario as the example.
3. Compare the roles of registered nurses, practical nurses, nurse practitioners and unregulated care providers on a medical-surgical team, using authority, competence and context.
4. Apply the six cognitive skills of the Clinical Judgment Measurement Model to a change in an adult patient's condition.
5. Explain how the CNO Code of Conduct, the CNA Code of Ethics for Nurses (2025), and consent, privacy and documentation requirements guide daily practice.
6. Describe the patient safety systems that protect adults in hospital and the nurse's part in them.
7. Use teach-back, professional interpreters and discharge planning to partner with patients and families across transitions in care.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2	Clinician; Coordinator	Foundations of Practice
3	Coordinator; Collaborator; Professional	Collaborative Practice; Legal Practice
4	Clinician; Scholar	Foundations of Practice
5	Professional; Advocate	Ethical Practice; Legal Practice; Professional Practice
6	Leader; Clinician	Professional Practice; Foundations of Practice
7	Educator; Communicator; Collaborator	Collaborative Practice

Introduction

Every day, adults arrive on hospital units across Canada with pneumonia, a flare of chronic obstructive pulmonary disease (COPD), a new hip or a failing heart. In 2024–2025, Canadian hospitals recorded about 3.14 million acute inpatient stays. After giving birth, the most common reasons for a stay were COPD and bronchitis, then pneumonia (Canadian Institute for Health Information [CIHI], 2026a). Caring for these adults before, during and after hospital is the work of medical-surgical nursing.

The people in those beds are older than they once were. On July 1, 2026, one in five people in Canada (20.0%) was 65 or older (Statistics Canada, 2026). In 2021, people 65 and older made up 18.5% of the population but accounted for 43.2% of health spending (CIHI, 2023). Many live with **multimorbidity**, meaning two or more chronic conditions at once. In the 2017–2018 Canadian Community Health Survey, about 37% of seniors living in the community reported at least two of ten common chronic diseases, a figure the Public Health Agency of Canada (PHAC) calls a conservative estimate (PHAC, 2020). A British Columbia study that used health administrative records and counted 25 conditions found that more than 60% of adults 65 and older met this definition in 2019/2020 (Ferris et al., 2025).

For the nurse, this means a patient admitted for one problem usually brings several others, a long medication list, a family who wants to help and questions about what happens after discharge. This chapter sets the foundation for that work: what medical-surgical nursing is, where adults receive care in Canada, and the legal and ethical rules that guide every nurse.

1.1 What Medical-Surgical Nursing Is

Adult Health Across Acute and Chronic Illness

Medical-surgical nursing is the nursing care of adults who are acutely ill, who are living through a flare-up (exacerbation) of a chronic illness, or who need surgery and support to recover from it. The name comes from two kinds of hospital units. On a medical unit, patients are treated mainly with medications, monitoring and other non-surgical therapies for problems such as heart failure or infection. On a surgical unit, patients are preparing for or recovering from an operation.

In practice, the line blurs. An older adult recovering from bowel surgery may also have heart failure, diabetes and early dementia. Medical-surgical nurses therefore need broad knowledge of every body system and strong skills in noticing when a patient's condition is changing. The same knowledge is used outside hospital wards, in day surgery, rehabilitation, home care and virtual care.

The Illness Trajectory

The **illness trajectory** is the path a health condition takes over time and the care a person needs along the way. This book uses five broad phases:

- **Prevention and health promotion:** lowering risk before disease starts or worsens, such as through vaccination or smoking cessation.
- **Acute illness:** a new problem, a sudden worsening of a chronic one, or planned surgery.
- **Recovery and rehabilitation:** regaining strength, function and independence.
- **Chronic disease management:** living well with a long-term condition through self-management and follow-up.
- **End of life:** comfort and support for the person and family when cure is no longer the goal (Chapter 10).

The path is rarely straight. A person with COPD may go from stable self-management to an emergency admission and back home several times in a year, and each admission is a chance to prevent the next one. The condition chapters of this book follow the same order: prevention, acute care, recovery and discharge, long-term management and, where relevant, palliative needs.

Patient- and Family-Centred Care

Patient- and family-centred care is a way of working in which patients, the people they call family, and health care providers act as partners as care is planned, given and evaluated (Institute for Patient- and Family-Centered Care [IPFCC], n.d.; Registered Nurses' Association of Ontario [RNAO], 2015). It sees the patient as a whole person with values and goals, not as a diagnosis. The patient decides who counts as family, whether a spouse, friend or chosen family member, and how much each person takes part. Its core ideas are respect and dignity, sharing complete and usable information, supporting participation at the level the patient chooses, and collaboration (IPFCC, n.d.).

Figure 1.1 A nurse measures a patient's blood pressure at the bedside. Regular, careful assessment underlies every other part of medical-surgical nursing care. (credit: “Blood Pressure Monitoring” by NIH Clinical Center/Flickr, CC BY 2.0)

Healthcare Excellence Canada (HEC) uses the term **essential care partner** for a person the patient (or substitute decision-maker; see section 1.5) names to give the physical, psychological and emotional support the patient considers important; this role differs from that of a visitor (HEC, n.d.-a). HEC also involves patients and caregivers with lived experience as partners in improving services (HEC, n.d.-b). On a unit, this looks like bedside shift report that includes the patient, asking "What matters most to you?", and inviting the named partner to discharge teaching.

The Nurse's Work on a Medical-Surgical Unit

The nurse's core work includes the following (Figure 1.1):

- **Assessment:** gathering and interpreting physical, mental, social and spiritual data, and learning what the patient wants.
- **Surveillance:** watching for small changes over time so that deterioration is caught early (Chapter 6).
- **Medication administration:** giving medications safely, monitoring effects and reconciling lists at each transition.
- **Teaching:** preparing patients and families for self-care, starting on admission.
- **Coordination:** connecting care across shifts, the interprofessional team and community services.
- **Advocacy:** speaking up for the patient's wishes, safety and rights.

Registered nurses (RNs) and practical nurses (PNs), who are called registered practical nurses (RPNs) in Ontario and **licensed practical nurses (LPNs)** in most other provinces and territories (see section 1.3), share much of this work. How it is divided on a unit depends on each nurse's authority, competence and the practice context, including employer policy and provincial or territorial rules.

1.2 Where Adults Receive Care in Canada

The Canada Health Act

The **Canada Health Act** is the federal law that sets the conditions provinces and territories must meet to receive full federal cash contributions for health care. The Act declares that the main objective of Canadian health care policy is to protect, promote and restore residents' physical and mental well-being and to make reasonable access to health services possible without cost or other obstacles getting in the way (Canada Health Act, 1985, s. 3). It deals mainly with **insured health services**: medically necessary hospital services, medically required physician services, and surgical-dental procedures that need a hospital. Hospital services include a standard ward bed, nursing care, diagnostic tests, drugs given in hospital, and operating room and anesthesia services (s. 2). Provincial and territorial plans must meet five criteria (Table 1.1) and must not allow extra-billing or user charges for insured services (ss. 7–12, 18–19).

Table 1.1 The five criteria of the Canada Health Act in plain language (Canada Health Act, 1985)

Criterion	What it means	What it means for patients
Public administration	A public authority accountable to the government runs the plan on a non-profit basis and is subject to audit.	Insured hospital and physician care is paid by a public plan, not a for-profit insurer.
Comprehensiveness	The plan covers all insured services provided by hospitals and physicians, and surgical-dental services that need a hospital.	Medically necessary hospital and physician care, including tests and drugs given in hospital, is covered.
Universality	All insured residents are entitled to insured services on the same terms.	Every eligible resident has the same basic coverage.
Portability	New residents wait no more than three months for coverage, and the plan keeps paying when residents are temporarily away.	A resident who falls ill while visiting another province is covered by the home plan.
Accessibility	Services are offered on uniform terms, and charges or other barriers must not block reasonable access.	Patients are not billed at the point of care for insured hospital and physician services.

Many services adults need after discharge fall outside the Act. Each province and territory decides whether and how to cover outpatient prescription drugs, home care, dental care, vision care and ambulance services, often for groups such as seniors, children and people receiving social assistance; others pay themselves or use private insurance (Health Canada, 2025). The federal Canadian Dental Care Plan now also helps with dental costs for eligible residents who have no access to dental insurance and an adjusted family net income under $90,000 (Employment and Social Development Canada, 2026). In Ontario, the Ontario Drug Benefit program covers people 65 and older and some younger groups, with deductibles and co-payments for some (Government of Ontario,

2026a). A drug given free in hospital may cost money at the pharmacy, so the nurse asks early whether the patient can afford discharge prescriptions.

Provincial, Territorial and Federal Roles

Provinces and territories run their insurance plans, decide eligibility and covered services, deliver most care and regulate health professions, including nursing. The federal government administers the Canada Health Act, funds care through transfers and serves certain groups directly, including First Nations people living on reserve, Inuit, eligible veterans and serving Canadian Armed Forces members (Health Canada, 2025). Three federal bodies matter most to nurses:

- **Health Canada:** administers the Canada Health Act and regulates health products such as drugs.
- **Public Health Agency of Canada:** promotes health, works to prevent chronic and infectious disease and injury, and prepares for and responds to public health emergencies (PHAC, 2025).
- **Indigenous Services Canada (ISC):** employs nurses in nursing stations and health centres, mostly in First Nations communities that are remote or isolated (ISC, n.d.-b), and runs the **Non-Insured Health Benefits (NIHB)** program. NIHB covers registered First Nations and recognized Inuit for pharmacy, vision, dental, mental health counselling, medical supplies and equipment, and medical transportation not covered by other plans (ISC, n.d.-a). Chapter 2 discusses Indigenous health services further.

Ontario as an Example

Each province and territory organizes care differently, so agency names will vary. Ontario's main parts are:

- **Ontario Health:** a provincial agency created in 2019 that oversees health care delivery and performance (Government of Ontario, 2025b). Its six regions plan, fund and monitor local care (Ontario Health, 2026a).
- **Ontario Health Teams (OHTs):** groups of local providers, such as hospitals, primary care, home care and long-term care, that work as one team; 58 OHTs cover the province (Government of Ontario, 2026c; Ontario Health, 2026b).
- **Public hospitals:** each is a separate, independent corporation with its own governing board, operating under the Public Hospitals Act, 1990 (Government of Ontario, 2023a).
- **Ontario Health atHome:** formed June 28, 2024, from the 14 Home and Community Care Support Services organizations; it coordinates home and community care and long-term care placement (Government of Ontario, 2024; Ontario Public Appointments Secretariat, n.d.).
- **Long-term care homes:** 24-hour nursing and personal care for adults who need it, governed by the Fixing Long-Term Care Act, 2021 (Government of Ontario, 2025a).
- **Primary care:** family physicians and nurse practitioners (NPs), often in teams (Ontario Ministry of Health, 2025).
- **Public health units:** 29 boards of health that deliver local programs such as immunization and infectious disease control (Government of Ontario, 2026d).



Figure 1.2 A nurse checks an older man's blood pressure in his home. Medical-surgical nursing continues after discharge through home care, telephone follow-up and remote monitoring. (credit: “Telehealth - Older man and nurse using blood pressure” by Tunstall Telehealthcare/Flickr, CC BY 2.0)

Where Medical-Surgical Nurses Work

Settings include medical and surgical inpatient units; step-down units for patients who need closer monitoring but not intensive care; day surgery and ambulatory clinics; the emergency department, where admitted patients may be held while waiting for a bed; rehabilitation; home care; and virtual care, such as telephone follow-up or remote monitoring after discharge (Figure 1.2).

Transitions and Alternate Level of Care

A **transition in care** is any move between settings or teams: admission, transfer or discharge. Information, medications and plans can be lost at each one, so the nurse confirms changes and makes sure the next team and the patient know the plan. Discharge planning begins at admission.

Alternate level of care (ALC) describes a patient who still occupies a hospital bed but no longer needs acute care and is waiting for a better-suited setting, such as long-term care, rehabilitation or home with supports. In Ontario, a physician (or another designated professional) makes the designation (Ontario Health, 2021). In 2024–2025, 6.1% of hospital stays in Canada included ALC days (CIHI, 2026a). These waits reduce beds for new admissions; Chapter 8 discusses how nurses protect older adults during them.

CANADIAN CONTEXT

Care Far from Home

Because surgical, specialist and hospital services are concentrated in larger centres, adults in rural, remote and northern communities often travel to a regional or southern centre for surgery, specialist care or admission. A nurse in a remote nursing station may stabilize a patient and arrange transfer by air or road (Figures 1.3 and 1.4). For registered First Nations and recognized Inuit, the NIHB medical transportation benefit can cover travel to the nearest appropriate facility for care not available at home, along with meals, lodging and, when a medical or legal need exists, an approved escort. Prior approval may be required (ISC, 2019, 2025). Ontario's Northern Health Travel Grant partly repays eligible northern residents who travel at least 100 km one way to the nearest specialist or ministry-funded health facility for care not available locally (Government of Ontario, 2026b).

Travel separates people from family, language, food and community. Inuit patients travelling from Nunavut to Ottawa for cancer care reported having little say or support in decisions and leaned on their escorts for everyday choices (Jull et al., 2021). The nurse can ask who is travelling with the patient, include the escort in teaching, arrange an interpreter and plan the trip home early. Chapter 2 explores these issues further.

Figure 1.3 (a) Qikiqtani General Hospital, the territorial hospital in Iqaluit, Nunavut. (b) Tammaativvik, a boarding home in Iqaluit for Inuit patients who travel from other communities for care at the hospital. (credit: (a) “Qikiqtani General Hospital” by OhanaUnited/Wikimedia Commons, CC BY-SA 4.0; (b) “Tammaativvik boarding home” by OhanaUnited/Wikimedia Commons, CC BY-SA 4.0)

Figure 1.4 An Ornge helicopter departs St. Michael's Hospital in Toronto. Ornge provides air ambulance service and medical transport in Ontario for people who are critically ill or injured (Ornge, n.d.). (credit: "Ornge Agusta Westland AW 139 C-GYNN" by BriYYZ/Wikimedia Commons, CC BY-SA 2.0)

1.3 The Medical-Surgical Team and Scope of Practice

On a medical-surgical unit, no nurse works alone. A patient recovering from bowel surgery may see a registered nurse, a practical nurse, a personal support worker, a physician, a physiotherapist and a pharmacist before lunch. Safe care depends on each person knowing what they may do, what they are able to do well, and what the setting allows. This section introduces the team and then explains how Ontario nurses decide whether an activity is within their scope.

The Nursing Team

In Ontario, the College of Nurses of Ontario (CNO) regulates three categories of nurse: RNs, RPNs and NPs. All three practise nursing, and all three must meet CNO's practice standards. They differ in entry education, in the controlled acts the law gives them, and in the depth of knowledge that underpins their practice.

An RN enters practice with a baccalaureate degree in nursing, and an RPN with a practical nursing diploma (CNO, n.d.-g). Outside Ontario, most provinces and territories call the practical nurse an LPN (see section 1.1). The letters RPN also mean something else in much of the country. In the four western provinces, Yukon and several other jurisdictions, RPN stands for **registered psychiatric nurse**, a separate regulated profession (CIHI, 2026c). This book uses "PN" for the general role and "RPN" only for Ontario's registered practical nurse.

An NP is an RN with graduate-level education who has added legislated authority to diagnose, order tests and prescribe. Since July 1, 2026, Ontario has registered NPs in a single class instead of by specialty (CNO, n.d.-i). On a medical-surgical unit, an NP may manage a group of inpatients alongside physicians, depending on the hospital.

The nursing team also includes **unregulated care providers (UCPs)**, people who give care but are not regulated under the Regulated Health Professions Act, 1991 (RHPA). UCPs have no legally defined scope of practice. Their employer sets their role and the tasks they may do (CNO, n.d.-k). In Ontario, the most common UCP is the **personal support worker (PSW)** (Figure 1.5). Since

December 1, 2024, PSWs can choose to register with the Health and Supportive Care Providers Oversight Authority (HSCPOA). Registration is voluntary, the title is not protected, and the authority sets no scope of practice. A nurse's accountability is the same whether or not a PSW is registered (CNO, 2024). Other provinces differ. Since February 2, 2026, Alberta has regulated health care aides under its Health Professions Act, through the College of Licensed Practical Nurses and Health Care Aides of Alberta, and the title "health care aide" is now protected (College of Licensed Practical Nurses and Health Care Aides of Alberta [CLHA], n.d.; Government of Alberta, n.d.). The nurse therefore checks the rules where they work. Table 1.2 summarizes the Ontario nursing team.

Figure 1.5 A health care assistant helps a patient with fluids. Unregulated care providers, such as PSWs in Ontario, give much of the personal care on medical-surgical units, within the role their employer sets. (credit: “A healthcare assistant pouring water for a patient” by Adrian Wressell, Heart of England NHS FT/Wellcome Collection, CC BY 4.0)

Table 1.2 Members of the medical-surgical nursing team in Ontario (CNO, n.d.-g, n.d.-i, n.d.-k, 2024)

Role	Regulated by (Ontario)	Entry education	Typical medical-surgical responsibilities
Registered nurse (RN)	College of Nurses of Ontario	Baccalaureate degree in nursing	Assesses and plans care for an assigned group of patients, including those whose condition is complex or changing; leads or coordinates care; acts as a resource for RPNs and other team members; may be charge nurse
Registered practical nurse (RPN)	College of Nurses of Ontario	Practical nursing diploma	Assesses, plans, gives and evaluates care for an assigned group of patients; consults the RN or another team member as a patient's needs change; may lead and direct UCPs
Nurse practitioner (NP)	College of Nurses of Ontario	RN plus graduate-level NP education	Assesses, diagnoses, orders tests and treatments, and prescribes within NP scope; collaborates with physicians and nurses in managing inpatients
Personal support worker (PSW), an unregulated care provider	Not regulated under the RHPA; voluntary registration with HSCPOA	Set by the employer	Helps with hygiene, mobility, eating and toileting; measures and reports findings when the employer's role description allows; reports changes to the nurse

The Interprofessional Team

Nurses are at the bedside around the clock, so they often notice change first and connect the team. Physicians, including hospitalists (physicians who care for hospital inpatients) and surgeons, diagnose and direct medical and surgical treatment. Pharmacists review medication orders, check for interactions and advise on dosing. Physiotherapists and occupational therapists help patients regain mobility and daily function and plan for safe discharge. Dietitians assess nutrition and plan feeding. Social workers support patients and families with coping, finances and discharge arrangements. Respiratory therapists manage airways, oxygen and ventilation and often attend urgent calls. Spiritual care providers support patients and families of any faith or none. Good collaboration means sharing findings early and respecting each person's expertise.

Scope of Practice: Authority, Competence and Context

Scope of practice is the range of activities a nurse is permitted and able to perform safely. CNO's Scope of Practice standard, in effect since July 1, 2023, asks every nurse to consider three things before acting: authority, competence and context (CNO, 2025e). A nurse needs all three. Having legal authority does not make an activity safe if the nurse lacks the skill, and having the skill does not help if the setting does not allow it.

Authority comes from law. The RHPA sets the framework for all regulated health professions in Ontario and lists **controlled acts**, activities that can cause harm if done by someone without the right training and that only authorized people may perform. The Nursing Act, 1991 describes nursing practice and authorizes RNs and RPNs to perform five controlled acts. These include a procedure below the dermis or a mucous membrane, giving a substance by injection or inhalation, and putting an instrument, hand or finger beyond specified body openings (CNO, 2025e). For most controlled acts, a nurse needs an **authorizing mechanism**. An order may be a **direct order**, given for one patient (usually in writing), or a **directive**, written by an authorized provider in advance to apply to any patient who meets set conditions. Through **delegation**, a professional who holds the authority for a controlled act, and can perform it competently, passes that authority to someone who does not hold it. Through **initiation**, a regulation under the Nursing Act, 1991 lets RNs and RPNs decide on their own to perform certain acts, such as some wound care. Initiation is not available everywhere. Nurses cannot initiate controlled acts in public hospitals, because the Public Hospitals Act, 1990 requires orders for treatment there (CNO, 2025e). Since December 4, 2023, RNs who complete CNO-approved education may prescribe certain medications. This authority is not part of entry-level practice and cannot be used in public hospitals (CNO, n.d.-d; Government of Ontario, 2023b). Finally, an employer may narrow a nurse's scope through policy but can never widen it beyond what the law and CNO allow.

Competence is the knowledge, skill and judgment needed to perform an activity safely. It belongs to the individual nurse and changes over time. Two nurses with the same title may have different competence. Each nurse reflects on their practice, identifies learning needs and takes part in CNO's Quality Assurance Program, which the RHPA requires (CNO, 2025e). A nurse who is not competent to perform an activity does not perform it. Instead, the nurse seeks help, learns the skill or transfers care.

Context is the setting in which care happens: the patient's needs, the unit, employer policy, staffing, equipment and the support available. A nurse may be authorized and competent to do something that is still unsafe on a particular unit at a particular time. When an employer policy conflicts with a CNO standard, the nurse's first accountability is to the standard (CNO, 2025e). Table 1.3 turns the three elements into questions.

Table 1.3 Authority, competence and context: questions the nurse asks before acting (CNO, 2025e)

Element	Questions to ask	Example on a surgical unit
Authority	Is this a controlled act? Is it authorized to my category of nurse? Do I have an order, a directive or delegation? Does setting-specific law apply?	An RPN finds that a surgical wound needs irrigation and packing. This is a controlled act the RPN is authorized to perform, but in a public hospital the RPN needs an order and cannot initiate it.
Competence	Do I know why this is being done, its risks and what to watch for? Have I done it before and kept my skill current? Can I manage what might go wrong?	An RN has never cared for a patient with a new epidural infusion. The RN asks the educator for teaching and a colleague's support before taking the assignment.
Context	Do employer policies allow it here? Are the right equipment, staff and backup available? Has the patient's condition changed what is needed?	An RPN's patient becomes unstable at night. Policy requires the RN to assume care when a patient meets rapid response criteria, so the RPN consults the RN at once.

Assignment, Consultation and Escalation

CNO's Scope of Practice standard applies to every nurse, whatever the category. It does not divide patients into "RN patients" and "RPN patients." It asks every nurse to judge whether the patient's condition calls for the activity and to consult or transfer care when that is needed for safety (CNO, 2025e). Many hospitals build assignment rules on top of this. A common employer practice is to assign patients whose condition is unstable or changing quickly to RNs and to expect RPNs to consult the RN as a patient's needs change. These are employer decisions, not CNO rules, and they vary between hospitals.

One rule applies to everyone. Any nurse who sees a patient deteriorating acts at once and escalates. The RPN who notices a falling blood pressure does not wait for the RN to discover it. The RPN begins care within their scope, tells the RN and calls for help using the unit's escalation process. Chapter 6 covers early warning scores, structured communication and rapid response in full.

Nurses also assign work to UCPs. When assigning a task, the nurse is accountable for assessing the patient, the environment and the risks, and for confirming that the UCP can do the task. If the task is new to the UCP, the nurse teaches or supervises, and afterward the nurse follows up (CNO, n.d.-k). A nurse may also delegate a controlled act the nurse is authorized and competent to perform, such as an injection, if the delegation requirements are met. The nurse remains responsible for the decision and for the patient's ongoing nursing care (CNO, 2025e, 2026b).

Standards change. On September 24, 2026, CNO's Council approved revised Scope of Practice and Medication standards that take effect March 1, 2027. Under the revisions, an authorized provider must assess a patient before writing an order for that patient, and the rules for delegation are spelled out more clearly. Aesthetic services get their own rules: a nurse who delegates an aesthetic procedure must be on site for all of it, and any treatment there that involves a prescription drug or a controlled act needs an order for the individual patient, not a directive. Some things do not change. A nurse who delegates is still accountable for the patient's ongoing care, and RNs and RPNs still need no delegation to carry out the controlled acts the law already gives them (CNO, 2026b, 2026d). Students should check CNO's website for the current version of any standard.

SCOPE IN PRACTICE

Who Cares for Mr. Desjardins Now?

Mr. Desjardins, 68, is on postoperative day 1 after an open colectomy. At 0200, the RPN assigned to him finds a heart rate of 128, a blood pressure of 88/52, cool hands and a urine output of 10 mL in the last hour.

- **Authority:** The RPN is authorized to give intravenous (IV) fluids and injections when they are ordered, so authority is not the barrier. In a public hospital, though, every new treatment still needs an order.
- **Competence:** The RPN can recognize that this is shock until proven otherwise. Depending on the RPN's own knowledge and experience, managing a patient whose condition is changing minute by minute, while also caring for four other patients, may be more than the RPN can safely do alone.
- **Context:** The hospital's policy says that a patient who meets rapid response criteria is cared for by an RN, with the RPN's help. The surgeon is in the operating room.

The RPN stays with Mr. Desjardins, checks that his IV is running as ordered and calls the RN to the bedside. The RN takes over his care and calls the rapid response team. The RPN gives an SBAR (Situation, Background, Assessment, Recommendation) handover, then continues to help. In another hospital or province, the policy might divide the work differently. In every setting, the nurse who sees the change acts and escalates.

PRACTICE STORY

The Night Mrs. Kowalski Changed

Names and details are fictional; this is a composite story.

Nurse: Danielle Thériault, RPN. Years in practice: 7. Setting: medical unit, community hospital, eastern Ontario.

Mrs. Kowalski, 86, was on day 2 of treatment for pneumonia. At the start of my night shift she was chatty and told me about her great-grandchildren. She was on 2 L/min of oxygen by nasal prongs.

At 0300 I went in for vital signs. She was picking at her blanket and asked me why her late husband had not come to visit. I knew from her daughter that this was not her normal. Her respiratory rate was 28, up from 18 at 2300. Her oxygen saturation was 89%, her heart rate 108 and her temperature 38.3 °C. Her blood pressure was 112/64, lower than her usual.

On their own, none of these numbers looked dramatic. Together, they worried me. I checked her prongs, sat her up and went to find Marco, the RN on our side of the unit.

I used SBAR. "Situation: Mrs. Kowalski in room 14 has new confusion and her respiratory rate has gone from 18 to 28 since 2300. Background: she's 86, day 2 of treatment for pneumonia, on 2 litres. Assessment: her sats are 89%, heart rate 108, temperature 38.3, and her pressure is lower than her baseline. I think she's getting worse, maybe sepsis. Recommendation: I'd like you to see her now, and I think she meets our rapid response criteria."

Marco came straight away and called the rapid response team. The respiratory therapist increased her oxygen, and the physician ordered blood work and a chest X-ray. Under our unit's policy, Marco took over her care, and I helped while keeping up with my

other patients.

In the morning, Mrs. Kowalski was more settled. Her daughter thanked me for noticing. I told her that noticing is part of the job, but so is knowing when to bring in someone else.

Reflect: Which of the three elements of scope (authority, competence or context) led Danielle to consult the RN rather than keep managing Mrs. Kowalski's care alone? What would she do if the RN was busy with another emergency?

1.4 Clinical Judgment: The Clinical Judgment Measurement Model

Every chapter of this book asks the same question: what should the nurse notice, think and do next? This section introduces the framework the book uses to answer it.

What Clinical Judgment Is

Clinical judgment is the reasoning a nurse uses to make sense of a patient's situation and decide how to respond. It draws on knowledge, experience and what the nurse observes. The National Council of State Boards of Nursing (NCSBN), the organization that develops the National Council Licensure Examination (NCLEX), describes clinical judgment as the observable result of critical thinking and decision-making, and as a repeating process rather than a single act (NCSBN, 2026). A nurse who notices that a postoperative patient is more restless, links it to a rising heart rate, considers bleeding and acts on that concern is using clinical judgment. So is the nurse who later checks whether the action worked.

Clinical judgment matters on medical-surgical units because patients' conditions change, sometimes slowly and sometimes fast. A single abnormal value may mean little, but a pattern of small changes can signal serious trouble. Good judgment links the signs and turns them into timely action.

The NCSBN Clinical Judgment Measurement Model

NCSBN created the **Clinical Judgment Measurement Model (CJMM)** to measure clinical judgment in a licensing exam. The work grew from NCSBN's 2013–2014 practice analysis, which found that newly licensed nurses were increasingly expected to make complex decisions (NCSBN, n.d.-c). The model drew on research in nursing, cognitive psychology and decision science. Building it took the work of over 100 nursing experts and response data from over 200,000 NCLEX candidates (NCSBN, n.d.-a). After more than a decade of research, NCSBN launched the **Next Generation NCLEX (NGN)**, built on the model, on April 1, 2023 (NCSBN, 2023).

The CJMM is a measurement tool. NCSBN states that the model does not define or redefine clinical judgment and does not replace the nursing process (NCSBN, n.d.-a). Its value for students is that it breaks clinical judgment into six skills that can be practised and assessed one at a time.

Figure 1.6 A nurse records a patient's vital signs, including oxygen saturation from a finger probe. Recognizing cues begins with accurate, regular assessment. (credit: “A nurse carrying out observations on a patient” by Adrian Wressell, Heart of England NHS FT/Wellcome Collection, CC BY 4.0)

The Six Cognitive Skills

- **Recognize cues:** The nurse identifies which information matters. A **cue** is any piece of patient data, such as a vital sign, a laboratory value, a symptom or a family member's comment, that may signal a problem. The nurse separates normal from abnormal and relevant from irrelevant (Figure 1.6).

- **Analyze cues:** The nurse groups related cues and links them to the patient's condition. Fever, a productive cough and crackles in one lung base belong together. The nurse begins to form a **hypothesis**, a possible explanation that fits the cues.
- **Prioritize hypotheses:** The nurse ranks the possible explanations by how likely and how dangerous each is, and how urgently each must be addressed.
- **Generate solutions:** The nurse names the outcomes they want and identifies actions that would achieve them, including actions that would rule a hypothesis in or out.
- **Take action:** The nurse carries out the chosen actions, which include interventions, communication with the team and documentation.
- **Evaluate outcomes:** The nurse compares what happened with what was expected and decides whether to continue, change or escalate the plan.

The six skills form a cycle, not a straight line. New cues appear during evaluation, and the nurse begins again. Table 1.4 applies each skill to one patient.

Table 1.4 The six cognitive skills of the CJMM applied on a medical unit (NCSBN, 2026)

Skill	What the nurse does	Example
Recognize cues	Picks out the findings that matter from everything available	A 74-year-old admitted with heart failure has gained 1.8 kg since yesterday, has new ankle edema and is short of breath lying flat
Analyze cues	Links findings to each other and to the patient's history	The nurse connects weight gain, edema and orthopnea with fluid overload from worsening heart failure
Prioritize hypotheses	Ranks explanations by likelihood, risk and urgency	Fluid overload affecting breathing is ranked above a less urgent concern such as poor appetite
Generate solutions	Sets expected outcomes and plans actions within scope	Raise the head of the bed, check oxygen saturation, review fluid intake and the medication record, and plan to notify the physician
Take action	Carries out the plan, communicates and documents	The nurse positions the patient, reports findings using SBAR, carries out new orders and records assessments
Evaluate outcomes	Compares results with expected outcomes and adjusts	Two hours later, breathing is easier and urine output has risen; the nurse continues to monitor and reports that the plan is working

Clinical Judgment and the Nursing Process

Students often ask how the CJMM fits with the nursing process (assessment, analysis or diagnosis, planning, implementation and evaluation). The two are closely related. NCSBN built the model on a nursing process and did not intend it to replace one (NCSBN, n.d.-a). NCSBN does not publish a step-by-step match, but the two line up roughly as follows. Recognizing and analyzing cues happen during assessment and analysis. Prioritizing hypotheses and generating solutions happen during planning. Taking action is implementation, and evaluating outcomes is evaluation. The CJMM adds detail inside the nursing process. It makes the thinking between the steps visible, especially the step of ranking possible explanations before choosing what to do.

How This Book and the Licensing Exams Use the Model

This book uses the six skills as its teaching framework for nursing care. In every clinical chapter, the nursing care sections move from cues, through possible explanations and priorities, to actions and evaluation. Clinical Judgment boxes work through one patient step by step.

Each licensing exam assesses this kind of reasoning in its own way. The NCLEX for RNs (NCLEX-RN) is built on the CJMM. Every candidate answers three case studies of six linked items, one item for each skill in order, along with stand-alone items (NCSBN, 2021, 2026). Practical nursing exams test the same reasoning in traditional formats. The Regulatory Exam – Practical Nurse (REx-PN), which practical nursing graduates write to register in Ontario and British Columbia, uses multiple-choice, multiple-response, calculation, exhibit and graphic items. Its 2027 test plan expects candidates to apply clinical decision-making and critical thinking (NCSBN, 2027). The Canadian Practical Nurse Registration Examination (CPNRE), used in the other provinces and territories except Quebec, presents 40% to 60% of its multiple-choice questions as case-based items tied to a scenario, and it tests

critical thinking as one of three cognitive levels (CLHA, 2026). Whichever exam a student writes, practising the six skills on real patient situations is good preparation.

CLINICAL JUDGMENT

Postoperative Day 1 After a Bowel Resection

Ms. Okonkwo, 58, weighs 75 kg and is on postoperative day 1 after a sigmoid resection. Her orders say to notify the surgeon if urine output is below 30 mL/h for two hours.

- **Recognize cues:** At 1000, her heart rate is 118 (76 before surgery), blood pressure 104/66 (130/80 before surgery), respiratory rate 22, temperature 37.8 °C and oxygen saturation (SpO2) 95% on room air. Urine output has been 15 mL/h for the past two hours. She rates her abdominal pain 7/10. Her abdomen is more distended than at 0600. Her hemoglobin this morning was 104 g/L, down from 131 g/L before surgery.
- **Analyze cues:** Tachycardia, a lower blood pressure and low urine output suggest reduced circulating volume. The fall in hemoglobin, rising pain and distension raise further concerns.
- **Prioritize hypotheses:** Hypovolemia, from bleeding or from fluid shifts, is the most urgent hypothesis. Anastomotic leak and early sepsis are less likely on day 1 but dangerous, so they stay on the list. Uncontrolled pain can raise heart rate but does not explain the falls in blood pressure and hemoglobin.
- **Generate solutions:** Expected outcomes are a heart rate below 100, urine output at or above the ordered minimum and stable hemoglobin. Planned nursing actions: reassess vital signs, the wound and any drain; check that the IV is patent and running at the ordered rate; check for urinary retention as policy allows; and notify the surgeon now.
- **Take action:** The nurse calls the surgical resident using SBAR and asks for an assessment. The resident orders a fluid bolus and blood work, and the nurse carries out the orders and documents. The nurse also treats her pain as ordered.
- **Evaluate outcomes:** One hour later, her heart rate is 102, her blood pressure 114/70 and her urine output 35 mL for that hour. Repeat hemoglobin is 101 g/L. She is improving but not stable. The nurse continues close monitoring and will call again if her heart rate climbs, her urine output falls or her abdomen worsens.

GOING DEEPER

Inside the CJMM and Next Generation NCLEX Items

Required for RN students; optional for PN students.

The CJMM is drawn in layers, from the broadest context to the most specific factors (Muntean & Betts, 2026; NCSBN, n.d.-a).

- **Layer 0:** The context. A patient has needs, and the nurse must make decisions about them.
- **Layer 1:** Clinical judgment as a whole, which is too broad to measure directly.
- **Layer 2:** A repeating loop of forming hypotheses, refining hypotheses, and acting and evaluating.
- **Layer 3:** The six cognitive skills. This is the level at which NCLEX items are written and classified.
- **Layer 4:** Factors that shape judgment. Some are in the environment (such as time pressure, resources or the medical record) and some are in the person (such as knowledge, skills or level of experience) (Betts et al., 2019; NCSBN, 2020).

NGN items appear in two ways. A **case study** presents one patient whose information unfolds over six items, ordered from recognizing cues to evaluating outcomes (NCSBN, 2021, 2026). **Stand-alone items** stand on their own. Two stand-alone formats, the bow-tie and the trend item, each ask the candidate to use several skills at once (NCSBN, 2021; Simpson et al., 2023). Item formats include extended multiple response, matrix or grid, drag and drop, drop-down (both with cloze, or fill-in-the-blank, versions), highlight, bow-tie and trend (Betts et al., 2019; Boev, 2022; NCSBN, 2022). Items with more than one correct answer can earn partial credit. NCSBN uses three rules (Muntean & Betts, 2026; NCSBN, n.d.-b). Under plus/minus scoring, a point is gained for each correct choice and lost for each incorrect one, with a floor of zero. Under zero/one scoring, each correct response earns a point and incorrect ones cost nothing. Under rationale scoring, a point is earned only when both parts of a linked pair, such as a cause and its effect, are correct.

1.5 Professional, Legal and Ethical Foundations

This section is the book's main reference for nursing law and ethics. Ontario is the worked example; details differ elsewhere, and Quebec, a civil law jurisdiction, sets out consent to care in its Civil Code.

Self-Regulation and the College of Nurses of Ontario

In Ontario, nursing is a **self-regulated profession**: the government allows the profession to govern itself on condition that it puts the public interest first. CNO became an independent regulatory college in 1963 (CNO, 2023) and now regulates RNs, RPNs and NPs (see section 1.3) under the RHPA and the Nursing Act, 1991 (CNO, n.d.-a). CNO exists to protect the public, not to advocate for nurses: it sets entry requirements and practice standards, runs a quality assurance program and acts on concerns about nurses' conduct (CNO, n.d.-j).

CNO's **Code of Conduct**, the overarching practice standard, applies to every Ontario nurse in every role and setting, and CNO considers a breach of it professional misconduct (CNO, n.d.-b). Its six principles, in summary (CNO, 2026a):

- Respect patients' dignity, privacy and informed decisions.
- Give inclusive, culturally safe care through cultural humility (Chapter 2).
- Give safe, competent care within one's competence and scope.
- Collaborate respectfully with the team, including online.
- Act with integrity in patients' best interests, including privacy, boundaries and protection from abuse.
- Maintain public confidence in nursing, including by reporting errors, unsafe or unethical conduct and system problems, whether or not harm resulted.

The CNA Code of Ethics

The Canadian Nurses Association (CNA) released its *Code of Ethics for Nurses* on July 14, 2025, replacing the 2017 code. It applies to all regulated nurses: licensed and registered practical nurses, RNs, NPs and registered psychiatric nurses (CNA, 2025a). It is organized around seven values, each with guiding principles (CNA, 2025b) (Table 1.5).

Table 1.5 The seven values of the CNA Code of Ethics for Nurses (2025) in medical-surgical practice (Values from CNA, 2025b; examples are original)

Value	Example in medical-surgical practice
Honouring the dignity and autonomy of all people	A capable, informed patient declines a feeding tube after a stroke; the nurse respects the decision and keeps offering support.
Valuing relationships and humanizing care	Before a below-knee amputation, the nurse asks what worries the patient most and what matters to them in recovery.
Maintaining integrity and accountability in nursing practice	A nurse who realizes a scheduled antibiotic dose was missed reports it at once and completes an incident report.
Pursuing truth and reconciliation	A Cree patient asks for an Indigenous patient navigator and a smudging ceremony; the nurse arranges both and considers how past harms may affect trust (Chapter 2).
Promoting social justice	For a patient without stable housing being discharged after cellulitis, the nurse raises wound care needs with the team and requests a social work referral.
Providing competent professional nursing practice	Assigned an unfamiliar chest drainage system, the nurse reviews the policy and asks an experienced colleague to check the set-up.
Preserving privacy and confidentiality	The nurse discusses a new cancer diagnosis in a private room and does not open the chart of a neighbour admitted to another unit.

Consent and Capacity

Ontario's Health Care Consent Act, 1996 (HCCA) requires consent to treatment, except in an emergency as the Act allows. **Informed consent** is valid when it relates to the treatment, is informed, is voluntary and is not obtained by misrepresentation or fraud. It is informed when the person has received what a reasonable person would need to know about the treatment's nature, expected benefits, material risks and side effects, alternatives and the likely results of not having it, and has had their questions answered (CNO, 2025b; HCCA, 1996). Consent may be express or implied (such as holding out an arm for a blood pressure check) and may be withdrawn at any time.

The practitioner who proposes a treatment obtains consent: the surgeon for surgery, the nurse for nursing treatments such as a dressing change. One practitioner may obtain consent to a plan of treatment for the whole team (CNO, 2025b).

Capacity means a person can understand the information relevant to a treatment decision and appreciate the reasonably foreseeable consequences of deciding or not deciding. Capacity is presumed unless there are reasonable grounds to believe otherwise; it is treatment-specific, can change over time and has no minimum age (CNO, 2025b). A patient with delirium may be unable to decide about surgery yet able to accept help with a meal.

When a patient is incapable for a treatment, a **substitute decision-maker (SDM)** decides. The HCCA ranks who may act: a court-appointed guardian of the person; an attorney for personal care (named under the Substitute Decisions Act, 1992); a representative appointed by the Consent and Capacity Board; a spouse or partner; a child aged 16 or older, or a parent (or children's aid society); a parent with only a right of access; a brother or sister; and any other relative. The highest-ranked person who is capable, available and willing acts; the Public Guardian and Trustee decides when no one else can. The SDM follows any applicable wish the patient expressed while capable and at least 16; otherwise, the SDM decides in the patient's best interests (CNO, 2025b).

In an emergency (apparent severe suffering, or risk of serious bodily harm without prompt treatment), treatment may begin without consent if waiting for an incapable patient's SDM would prolong the suffering or risk, or if a communication barrier cannot be overcome despite reasonable efforts. It may not be given if there are reasonable grounds to believe the patient, while capable and at least 16, expressed a wish to refuse it. Efforts to reach the SDM or to communicate continue (CNO, 2025b; HCCA, 1996).

Witnessing a consent signature is not obtaining consent. CNO's position is that whoever requires the consent should obtain the signature, which has no value unless the patient was informed (CNO, n.d.-h). If a patient does not understand or has changed their mind, the nurse does not proceed, tells the practitioner who proposed the treatment, advocates for the patient and documents.

Privacy and Confidentiality

Ontario's Personal Health Information Protection Act, 2004 (PHIPA) protects personal health information. A **health information custodian** is a person or organization, such as a hospital, that has custody or control of that information while providing care. Nurses employed by a hospital are usually its **agents**, acting on its behalf (CNO, 2025a).

The **circle of care** is not a term defined in PHIPA. It is shorthand for situations in which custodians may assume a patient's implied consent to collect, use or share information among custodians for the patient's care, provided the patient has not withheld or withdrawn consent (Information and Privacy Commissioner of Ontario [IPC], 2015). Family members and friends are not custodians, so the nurse generally needs the consent of the capable patient (or the SDM) before discussing the patient's health with them.

Patients may restrict how their information is shared, informally called a **lockbox**. If locked information is reasonably necessary for care, the custodian must tell the receiving custodian that information has been withheld, without revealing it (IPC, 2005).

Snooping, looking at records without a professional reason, is a privacy breach whatever the motive. Custodians must notify affected patients and report certain breaches to the IPC, including any breach for which they must report a regulated professional to that professional's college (IPC, n.d.). Nurses access only the records of patients in their care, never share passwords and report breaches to their workplace privacy contact (CNO, 2025a). They do not post about patients on social media, because a post can identify a patient even without a name.

Documentation

CNO's revised Documentation standard took effect February 1, 2026 (CNO, 2025c). Its three principles are communication, documentation requirements and information security. The nurse documents at the time of care or soon after, never before (Figure 1.7); labels late entries with the date and time of the care; corrects errors without deleting the original; records only care the nurse gave (unless a designated recorder is used); and uses their own login. The nurse also checks technology-generated content for accuracy, obtains the patient's consent before using artificial intelligence for documentation and uses discrimination-free language.

Professional Boundaries

On March 1, 2026, CNO's Professional Boundaries and Nurse-Client Relationships standard replaced the Therapeutic Nurse-Client Relationship standard (CNO, 2025d). It asks nurses to build therapeutic relationships, keep **professional boundaries** (the line where a therapeutic relationship would become personal) and protect patients from all forms of abuse. Keeping boundaries is always the nurse's responsibility, whatever the patient does; both under-involvement (such as avoiding a demanding patient) and over-involvement (such as favouritism) can harm. Nurses do not connect with patients on personal social media, and they generally avoid gifts, accepting at most a token gift and never asking for one.

CNO describes Ontario as having a zero-tolerance standard for sexual abuse of patients by health care providers (CNO, n.d.-c). Any sexual relationship, touching or remark of a sexual nature toward a patient is sexual abuse, whether or not the patient agreed, and, for these rules, a person remains a patient for one year after the relationship ends (CNO, 2025d). Under the Health Professions Procedural Code (Schedule 2 to the RHPA), a nurse who has reasonable grounds, gained in practice, to believe that another regulated health professional (including another nurse) has sexually abused a patient must report in writing to that professional's college within 30 days, or immediately if abuse is likely to continue. The report may name the patient only with the patient's written consent (CNO, n.d.-f; RHPA, 1991).

Figure 1.7 A nurse documents in the electronic health record on a mobile workstation in the patient's room. The patient's face and the screen have been blurred to protect privacy. (credit: modification of "Princess Alexandra Hospital nurse with mobile computer work station" by Kgbo/Wikimedia Commons, CC BY-SA 4.0)

Declining or Discontinuing Care

CNO's Discontinuing or Declining to Provide Care standard requires nurses to provide care that is inclusive, culturally safe and non-discriminatory, and never to abandon or neglect a patient (CNO, 2026c). A nurse may object to specific care on grounds of conscience or religion, but not out of fear, prejudice or convenience. The nurse raises the objection early, does not leave the patient without care, helps transfer care to a provider who does not object and documents the reasons and steps taken. If no alternative can be arranged, the patient's right to care comes first. Chapter 10 discusses medical assistance in dying.

1.6 Safety and Quality in Medical-Surgical Care

Hospitals are generally safe, but harm still happens. In 2025–2026, 1 in 17 acute care hospital stays in Canada involved at least one harmful event, as measured by an indicator of unintended, potentially preventable harm (data exclude Quebec and patients with mental health and substance use diagnoses). The most common were electrolyte and fluid imbalance, urinary tract infection, delirium and pneumonia (CIHI, 2026b).

Patient Safety Incidents

Canada uses shared terms for safety events (Incident Analysis Collaborating Parties, 2012). A **patient safety incident** is an event or circumstance that led to, or could have led to, unnecessary harm to a patient. There are three types:

- **Harmful incident:** the incident reached the patient and caused harm. This term replaces "adverse event."

- **No-harm incident:** the incident reached the patient, but no harm could be detected.
- **Near miss:** the incident did not reach the patient.

Disclosure

Disclosure is the process of telling a patient (or SDM) about a patient safety incident. Canadian guidelines say harmful incidents must always be disclosed. For a no-harm incident, providers consider whether a reasonable patient in that situation would want to be told. Disclosing a near miss is a matter of judgment (Disclosure Working Group, 2011). The first conversation happens as soon as reasonably possible. It shares the facts known so far, includes an apology and explains what will happen next. The most responsible practitioner usually leads it, and the nurses involved often take part. In Ontario, an apology is not an admission of legal fault (Apology Act, 2009).

Just Culture and Systems Thinking

Most incidents arise from weaknesses in systems, not from careless individuals. Look-alike packaging, interruptions, unclear orders and short staffing set up capable nurses to fail. A systems approach asks how and why the safeguards failed. A **just culture** treats honest mistakes and system-induced errors with support and learning, while still holding people accountable for reckless choices (Incident Analysis Collaborating Parties, 2012). Reporting is how organizations learn. As section 1.5 notes, the Code of Conduct expects nurses to report errors, unsafe practice and system problems whether or not harm occurred (CNO, 2026a). Each nurse follows the employer's incident reporting process, reports promptly and records the patient's condition and care in the health record. In many organizations the incident report is a separate document that is not referred to in the chart; employer policy sets the rule.

Figure 1.8 A nurse prepares medications from a locked medication cart. Each medication is checked against the order and the patient before it is given. (credit: “Nurse during a drug administration on a UK hospital ward” by Adrian Wressell, Heart of England NHS FT/Wellcome Collection, CC BY 4.0)

Medication Safety

The Institute for Safe Medication Practices Canada (ISMP Canada) studies medication incidents and publishes ways to prevent them. **High-alert medications** are drugs whose errors are especially likely to cause serious harm. Errors with them are not necessarily more frequent, but their effects are more severe. Examples include insulin, opioids, anticoagulants, chemotherapy and parenteral nutrition. Safeguards include standardization, restricted access, warning labels and alerts, and built-in redundancies such as **independent double checks** (ISMP Canada, n.d.-b). In an independent double check, a second practitioner verifies the drug, dose, route and pump settings against the order and does any calculation separately, without seeing the first nurse's answer. The two results are then compared before the drug is given (ISMP Canada, 2016). A check done side by side is less effective, because the second person tends to confirm what they are shown. Even a true double check is not foolproof, so it is one safeguard among several (Figure 1.8).

Canada also has a federal reporting rule. Under the Protecting Canadians from Unsafe Drugs Act (2014), known as Vanessa's Law, hospitals have been required since December 16, 2019 to report serious adverse drug reactions and medical device incidents to Health Canada in writing within 30 calendar days of first documenting them. A reaction is serious if it requires or prolongs hospitalization, causes a congenital malformation, causes persistent or significant disability, is life-threatening or results in death. The duty falls on the hospital, but nurses help by recognizing and clearly documenting suspected reactions (Health Canada, 2023).

CLINICAL SAFETY

Abbreviations and Dose Designations That Cause Errors

ISMP Canada keeps a "Do Not Use" list of abbreviations, symbols and dose designations that have led to serious errors. ISMP Canada advises against them in any medication communication (ISMP Canada, 2006). Examples:

- **"U" for unit:** a handwritten U can look like 0 or 4, turning 4 units into 40. Write "unit."
- **"IU" for international unit:** it can be read as IV or 10. Write "unit."
- **Trailing zero (5.0 mg):** if the decimal point is missed, the dose reads as 50 mg. Write "5 mg."
- **Missing leading zero (.5 mg):** a missed decimal point turns the dose into 5 mg. Write "0.5 mg."
- **"µg" for microgram:** it can be mistaken for mg, a 1,000-fold error. Write "mcg."
- **"D/C":** it can mean discharge or discontinue. Write the full word.
- **Abbreviated drug names, such as "MS" or "MSO4":** these can mean morphine or magnesium sulfate. Write the full generic name.

If an order contains a dangerous abbreviation, the nurse clarifies it with the prescriber before acting.

Infection Prevention and Communication

Routine practices are the infection prevention measures used with every patient during all care. They include risk assessment before each interaction, hand hygiene, personal protective equipment, control of the environment and administrative controls (Provincial Infectious Diseases Advisory Committee [PIDAC], 2025). Hand hygiene is the single most important of these. Ontario's four moments are before first contact with the patient or the patient's surroundings, before an aseptic procedure, after a risk of body fluid exposure, and after contact with the patient or the patient's surroundings. Alcohol-based hand rub is preferred unless hands are visibly soiled (PIDAC, 2014). Chapter 4 covers infection prevention in full.

Poor communication contributes to many incidents, especially at handover, when care passes between shifts, units or settings. Structured tools give each handover a predictable shape so that important information is less likely to be missed. Chapter 6 teaches SBAR and escalation in detail.

Hospital-Acquired Harms

Many harms that start in hospital can be prevented by nursing care. Table 1.6 lists common ones and points to where this book covers them.

Table 1.6 Common hospital-acquired harms and where this book covers them (Original table)

Harm	Why adults in hospital are at risk	Chapter
Falls	Unfamiliar surroundings, sedating medications, low blood pressure on standing, urgency, delirium, and IV lines and tubes that tether the patient	Chapter 8
Pressure injuries	Immobility, long surgeries, friction and shear, moisture, poor nutrition and reduced sensation	Chapter 35
Delirium	Acute illness, older age, dementia, poor sleep, dehydration, some medications and devices such as urinary catheters	Chapter 8
Health care-associated infections	Urinary catheters, central lines, surgical wounds, ventilation and antibiotic exposure	Chapter 4
Fluid and electrolyte imbalance	IV fluids, diuretics, fasting before procedures, vomiting and changes in kidney function	Chapter 3
Venous thromboembolism	Reduced mobility, major surgery, cancer and dehydration	Chapters 7 and 19
Medication incidents	Many medications and prescribers, high-alert drugs, interruptions and changes at transfer and discharge	This chapter and the body-system chapters
Functional decline	Bed rest, restricted mobility, poor nutrition and devices that discourage walking	Chapter 8

Figure 1.9 A hospital identification band. The nurse confirms at least two person-specific identifiers, such as name and date of birth, before giving a medication or treatment (Health Standards Organization, 2024). Identifying details have been blurred. (credit: modification of “Wrist Identification Band” by Whoisjohngalt/Wikimedia Commons, CC BY-SA 4.0)

Quality Improvement Programs

Choosing Wisely Canada works with professional groups to identify tests and treatments that add little value and may cause harm. Its nursing list was developed by CNA (CNA, 2024). Two items apply to almost every surgical unit. Indwelling urinary catheters should not be inserted, or left in place, without a daily assessment of whether they are still needed, because catheters can lead to urinary tract infection, sepsis and delirium. Extra sheets and pads should not be layered under patients on a pressure-redistribution surface, because they reduce its ability to protect the skin.

Accreditation Canada, which accredits many Canadian hospitals, uses **Required Organizational Practices (ROPs)**: standardized practices that an organization must have in place to improve patient safety and reduce risk. ROPs cover areas such as patient identification, the "Do Not Use" abbreviations list, high-alert medications, information transfer at care transitions, falls and pressure injury prevention, and **medication reconciliation** at care transitions, described in section 1.7 (Health Standards Organization, 2024). Nurses meet ROPs every day through their employer's policies, such as completing a medication history on admission or checking two identifiers on the patient's identification band before giving a medication (Figure 1.9).

1.7 Partnering with Patients Across Transitions

Patients are most at risk when they move: from home to hospital, from one unit to another, and from hospital back to the community. As section 1.2 notes, information, medications and plans can be lost at each transition in care, and responsibilities can become unclear. Nurses can make these transitions safer by working with patients and their families as partners.

Health Literacy

Health literacy is a person's ability to find, understand, judge and share health information in ways that support and improve their health (Rootman & Gordon-El-Bihbety, 2008). It depends on the person's skills but also on the situation. A patient who is in pain, frightened, unwell or learning in a second language may struggle with information they would normally manage well. General literacy skills vary widely. In a 2022 international survey, 19% of Canadian adults aged 16 to 65 scored at the two lowest literacy levels (Statistics Canada, 2024). For that reason, nurses use clear communication with every patient rather than trying to guess who needs it.

Practical strategies include:

- **Plain language:** use common words ("blood thinner," then the drug name), short sentences and two or three key points per session.
- **Teach-back:** ask the patient to explain or show, in their own words, what they will do at home, such as "Tell me how you will take this pill when you get home." Teach-back checks how clearly the nurse explained, not how smart the patient is. It works better than asking "Do you understand?" (Agency for Healthcare Research and Quality [AHRQ], 2023).
- **Written and visual support:** use materials written at an easy reading level, with pictures, in the patient's preferred language.

Language Access

Patients with limited English or French need a **professional interpreter**, in person, by video or by telephone, for consent discussions, assessments and teaching. Use of professional interpreters is associated with better communication and clinical care than use of untrained (ad hoc) interpreters (Karliner et al., 2007). Family members, and children especially, should not interpret clinical information: they may leave out or soften bad news, lack medical vocabulary and compromise the patient's privacy.

French is an official language in Canada. Francophone patients may not ask for French services, for example because they expect none to be available. An **active offer** means the provider makes services in French visible and available from the first contact, so the patient does not have to ask. Ontario's French Language Services Act, modernized in 2021, makes the active offer central to French-language services. A regulation on the active offer took effect on April 1, 2023 (Ministry of Francophone Affairs, 2023). The Act applies to the provincial government and its agencies, and to designated organizations, including some hospitals (French Language Services Act, 1990). Société Santé en français, a national network of French-language health networks, offers active offer training (Société Santé en français, n.d.). Simple actions help: greet patients in both languages ("Hello, bonjour"), wear a badge that shows the languages the nurse speaks, and record the patient's preferred language.

Figure 1.10 A weekly pill organizer. A best possible medication history asks how the patient actually takes each medication at home, including what goes into an organizer like this one. (credit: “Heptagonal objects A weekly medicine box” by יוחי טייס/Wikimedia Commons, CC BY-SA 4.0)

Discharge Planning and Medication Reconciliation

As section 1.2 notes, discharge planning begins at admission. On the first day, the nurse asks where the patient lives, who helps at home, how the patient managed before admission and what might delay going home. Planning early helps avoid ALC days (see section 1.2), spent in hospital after acute care is no longer needed, while the patient waits for home care or another setting (CIHI, n.d.).

Medication reconciliation is a structured process in which health care providers, patients and families together make sure that accurate, complete medication information goes with the patient at each transition in care (ISMP Canada, n.d.-c). It starts with a **best possible medication history**: a structured interview with the patient or family plus at least one other reliable source, such as the community pharmacy or a provincial drug record (Figure 1.10). The history covers every medication taken, including non-prescription drugs, vitamins and herbal products. The team compares this history with admission orders, again at transfer between units and again at discharge, and resolves each difference. At discharge, the patient receives an updated medication list and learns what has started, stopped or changed.

Involving Families and Caregivers

Family members and other caregivers often provide much of the care after discharge. In keeping with patient- and family-centred care (see section 1.1), the nurse asks the capable patient who should take part in teaching and planning and what may be shared, and involves those people with the patient's consent. If the patient is incapable, the nurse works with the SDM.

PATIENT EDUCATION

Questions to Ask About Your Medications

ISMP Canada developed a short tool called "5 Questions to Ask About Your Medications" with the Canadian Patient Safety Institute (now part of HEC), Patients for Patient Safety Canada, the Canadian Pharmacists Association and the Canadian Society of Hospital Pharmacists. It invites patients and caregivers to ask about five topics: changes to their medications, which medications to continue, proper use, monitoring and follow-up (ISMP Canada, n.d.-a). The tool is designed for times of change, such as leaving hospital, seeing a doctor or pharmacist, or starting home care. It is available in several languages at https://www.safemedicationuse.ca.

Before discharge, the nurse can show the tool to the patient and the caregiver and encourage them to bring it to their next pharmacy or clinic visit. The nurse then uses teach-back: "Tell me which of your old pills you will stop taking, and why."

LIFESPAN CONSIDERATIONS

Older Adults in Hospital

Older adults are especially vulnerable to the harms of a hospital stay.

- **Functional decline:** many older adults lose the ability to perform a basic activity of daily living, such as bathing, dressing or getting out of bed, during an acute stay. This loss, called hospitalization-associated disability, often persists after discharge (Covinsky et al., 2011). Bed rest, catheters and waiting for help to walk all contribute. Getting the patient up early and often, as ordered, is a key nursing intervention (Figure 1.11).
- **Delirium:** it is among the most common harms in Canadian hospitals (see section 1.6). Nurses screen for it, prevent it and recognize it.
- **Polypharmacy:** older adults often take many medications from several prescribers, which raises the risk of interactions and falls. Careful medication reconciliation is essential.
- **ALC:** a long wait in hospital for home care, long-term care or another setting (see section 1.2) adds to the risks above.

Chapter 8 covers the care of older adults in acute care in depth.

Figure 1.11 An older adult walks with a walking frame and a physiotherapist. Getting up early and often during a hospital stay helps prevent hospitalization-associated disability. (credit: "Female physiotherapist with elderly female patient" by Adrian Wressell, Heart of England NHS FT/Wellcome Collection, CC BY 4.0)

1.8 Using This Book

This book serves two groups of students. RN students prepare for the NCLEX-RN. Practical nursing students prepare for the REx-PN in Ontario and British Columbia, or for the CPNRE in the other provinces and territories except Quebec (see section 1.4). The core text is written for both groups and stands on its own. Going Deeper boxes add the extra depth expected of RN students. End-of-chapter questions are tagged [Core] for all students or [RN] for RN-level content.

Boxes support the text:

- **Going Deeper:** RN-level depth; optional for PN students.
- **Scope in Practice:** applies authority, competence and context to a clinical situation.
- **Canadian Context:** Canadian laws, programs, data and health system features.
- **Clinical Judgment:** works through one patient using the six skills of the CJMM.
- **Clinical Safety:** warnings and practices that prevent harm.
- **Patient Education:** plain-language teaching for patients and families.
- **Lifespan Considerations:** differences for older adults and other age groups.
- **Medications:** key drug classes, nursing actions and monitoring.
- **Practice Story:** a composite first-person account from a nurse, with questions for reflection.

The CJMM described in section 1.4 is the reasoning framework throughout the book. The NCLEX-RN is built on it, and the REx-PN and CPNRE test the same kind of reasoning in traditional item formats. Laboratory values use units from the International System of Units (SI), such as mmol/L, which Canadian laboratories report. Reference ranges vary between laboratories, so nurses always use the range on their own laboratory's report. Drugs are named by their Canadian generic names, and brand names appear only where they help recognition.

Ontario is the worked example for law, regulation and scope of practice. Students in other provinces and territories should check the matching rules where they will practise. This book does not replace employer policy, provincial or territorial law, regulatory college standards or current product monographs. When they differ from this book, they take precedence.

The NCLEX-RN and REx-PN test nursing knowledge and judgment, not provincial law or health system structure. In Ontario, CNO tests that knowledge separately through its **Jurisprudence Examination**. This online, open-book examination covers the legislation, by-laws, practice standards and guidelines that apply to Ontario nurses (CNO, n.d.-e). The legal and professional content in this chapter is a starting point for that examination, not a substitute for studying CNO's own documents.

Chapter 1 Summary

1.1 What Medical-Surgical Nursing Is

- Medical-surgical nursing is the care of adults with acute illness, exacerbations of chronic illness, or surgery and recovery, in hospital and across other settings.
- The illness trajectory (prevention, acute illness, recovery and rehabilitation, chronic management, end of life) is not linear; people may cycle through it many times.
- Patient- and family-centred care is built on partnership; the patient defines family and chooses how others take part.
- Essential care partners provide support the patient values and differ from visitors.
- The nurse's core work includes assessment, surveillance, medication administration, teaching, coordination and advocacy.

1.2 Where Adults Receive Care in Canada

- The Canada Health Act sets five criteria (public administration, comprehensiveness, universality, portability, accessibility) for insured hospital and physician services.
- Outpatient drugs, home care, dental, vision and ambulance coverage vary by province or territory (with a federal dental plan for some uninsured residents), which affects discharge planning.
- Provinces and territories deliver most care; Health Canada, PHAC and Indigenous Services Canada (including NIHB) have federal roles.
- In Ontario, Ontario Health, its six regions, Ontario Health Teams, public hospitals, Ontario Health atHome, long-term care, primary care and public health units work together; other provinces organize care differently.
- ALC describes patients who no longer need acute care but are waiting for another setting; 6.1% of Canadian hospital stays in 2024–2025 included ALC days.

1.3 The Medical-Surgical Team and Scope of Practice

- In Ontario, CNO regulates RNs (baccalaureate entry), RPNs (practical nursing diploma entry) and NPs (graduate-level education; a single class since July 1, 2026). Outside Ontario, practical nurses are usually LPNs, and RPN can also mean registered psychiatric nurse.
- PSWs are unregulated care providers in Ontario, with voluntary registration through HSCPOA. Alberta has regulated health care aides since February 2, 2026, so rules vary by province.
- CNO's Scope of Practice standard asks every nurse to have authority, competence and context before acting. Authority comes from the RHPA and the Nursing Act, through orders, directives, delegation or initiation. Initiation and RN prescribing (in force since December 4, 2023) are not available in public hospitals.

- CNO does not divide patients into RN and RPN patients. Assigning unstable patients to RNs is a common employer practice. Every nurse who sees deterioration acts and escalates.
- Revised Scope of Practice and Medication standards, approved September 24, 2026, take effect March 1, 2027. They clarify delegation and add requirements for patient-specific orders and aesthetic services.

1.4 Clinical Judgment: The Clinical Judgment Measurement Model

- Clinical judgment is how the nurse interprets a situation and decides what to do. It is a repeating process, not a single decision.
- NCSBN built the CJMM to measure clinical judgment. It underpins the Next Generation NCLEX, launched April 1, 2023.
- The six skills are recognize cues, analyze cues, prioritize hypotheses, generate solutions, take action and evaluate outcomes. They fit within the nursing process rather than replacing it.
- This book uses the six skills to teach nursing care in every clinical chapter.
- The NCLEX-RN is built on the CJMM. The REx-PN and CPNRE test the same reasoning through traditional and case-based multiple-choice formats.

1.5 Professional, Legal and Ethical Foundations

- CNO regulates Ontario nurses to protect the public; its Code of Conduct sets six principles that apply to every nurse in every setting.
- The CNA *Code of Ethics for Nurses* (2025) is organized around seven values, from dignity and autonomy to privacy and confidentiality.
- Under the HCCA, valid consent relates to the treatment, is informed and voluntary, and is not obtained by fraud; the practitioner who proposes a treatment obtains consent, and nurses obtain consent for their own nursing care.
- Capacity is presumed and treatment-specific, with no fixed age; incapable patients have an SDM chosen from a ranked list, and emergency treatment without consent is narrowly limited.
- PHIPA allows implied consent within the circle of care among custodians only; patients may lockbox information, and snooping is a reportable breach.
- CNO's revised Documentation (February 1, 2026) and Professional Boundaries and Nurse-Client Relationships (March 1, 2026) standards, the zero-tolerance approach to sexual abuse (with mandatory reporting under the RHPA) and the duty not to abandon patients shape daily practice.

1.6 Safety and Quality in Medical-Surgical Care

- In 2025–2026, 1 in 17 acute care hospital stays in Canada (excluding Quebec) involved at least one harmful event, many of them preventable.
- Patient safety incidents are harmful, no-harm or near misses; harmful incidents are always disclosed, and Ontario's Apology Act, 2009 protects apologies.
- A just culture and systems thinking support reporting and learning from incidents.
- High-alert medications need extra safeguards such as independent double checks; dangerous abbreviations must never be used; hospitals must report serious adverse drug reactions to Health Canada within 30 days under Vanessa's Law.
- Routine practices, structured handover, Choosing Wisely recommendations and Accreditation Canada ROPs help prevent hospital-acquired harms.

1.7 Partnering with Patients Across Transitions

- Nurses use plain language and teach-back with every patient, because health literacy varies and falls with illness and stress.
- Professional interpreters, not family members, support clinical communication; the active offer makes French-language services available without the patient having to ask.
- Discharge planning starts at admission, and medication reconciliation at admission, transfer and discharge prevents medication errors.
- Older adults are at high risk of functional decline, delirium, polypharmacy harms and long ALC stays.

1.8 Using This Book

- One core text serves RN (NCLEX-RN) and PN (REx-PN or CPNRE) students; Going Deeper boxes and [RN] questions add RN-level depth, and the CJMM frames clinical reasoning for all.
- Nine box types, the CJMM, SI units, Canadian generic drug names and Ontario examples organize the book.
- Employer policy, provincial law, college standards and product monographs take precedence; Ontario law is tested on CNO's Jurisprudence Examination.

Key Terms (56)

active offer: Making services in French visible and available from the first contact so that Francophone patients do not have to ask for them.

agent: Under PHIPA, a person, such as a nurse employed by a hospital, who handles personal health information on behalf of a health information custodian.

alternate level of care (ALC): A designation for a patient who remains in a hospital bed but no longer needs acute care and is waiting for a more suitable setting.

authorizing mechanism: A legal means, such as an order, a directive or delegation, that gives a nurse authority to perform a controlled act or other activity the nurse cannot start alone.

best possible medication history: A medication history built from a structured interview with the patient or family and at least one other reliable source, covering all prescribed and non-prescribed medications.

Canada Health Act: The federal law that sets the criteria and conditions provincial and territorial health insurance plans must meet to receive full federal cash contributions for insured health services.

capacity: The ability to understand information relevant to a specific treatment decision and to appreciate the reasonably foreseeable consequences of deciding or not deciding; it is presumed and treatment-specific, and it can change over time.

circle of care: A common term, not defined in PHIPA, for situations in which custodians may assume a patient's implied consent to share personal health information with one another for the patient's health care.

clinical judgment: The reasoning a nurse uses to interpret a patient's situation and decide how to respond, observed as the result of critical thinking and decision-making.

Clinical Judgment Measurement Model (CJMM): NCSBN's layered framework for measuring clinical judgment on the NCLEX; its core is six cognitive skills from recognizing cues to evaluating outcomes.

Code of Conduct: CNO's overarching practice standard; it summarizes the behaviour and ethical conduct the public can expect from every Ontario nurse.

competence: The knowledge, skill and judgment an individual nurse needs to perform an activity safely; it changes over time and is maintained through continuing learning.

controlled act: An activity listed in the Regulated Health Professions Act, 1991 that may cause harm and that only authorized people may perform.

cue: A piece of patient information, such as a sign, symptom, test result or comment, that may signal a problem.

delegation: Passing the authority for a controlled act from a regulated professional who holds it, and can perform the act competently, to someone who does not hold it; the delegating professional stays accountable.

direct order: An order given for one specific patient, usually in writing and verbally only in limited situations.

directive: An order written in advance by an authorized provider for an activity that applies to any patient who meets specified conditions.

disclosure: The process of telling a patient or substitute decision-maker that a patient safety incident occurred, what is known and what will happen next.

essential care partner: A person the patient or substitute decision-maker identifies to give the physical, psychological and emotional support the patient considers important, whose role differs from that of a visitor.

harmful incident: A patient safety incident that reached the patient and caused harm.

health information custodian: Under PHIPA, a person or organization, such as a hospital, that has custody or control of personal health information while providing health care.

health literacy: A person's ability to find, understand, judge and share health information in ways that support and improve their health.

high-alert medication: A drug, such as insulin, an opioid or an anticoagulant, whose errors are especially likely to cause serious harm.

hypothesis: A possible explanation for a group of cues that the nurse tests against further information.

illness trajectory: The path a health condition takes over time, from prevention through acute illness, recovery, chronic management and end of life, and the care needed at each point.

independent double check: A safety check in which a second practitioner separately verifies a medication, dose, route, calculation and pump settings against the order without seeing the first practitioner's result, before the results are compared.

informed consent: Agreement to a treatment that relates to that treatment, is given voluntarily, is not obtained by misrepresentation or fraud, and is based on information about the treatment's nature, benefits, risks, side effects, alternatives and the consequences of refusing it.

initiation: The authority, set out in regulation, for RNs and RPNs to decide on their own to perform certain controlled acts without an order; not available in Ontario public hospitals.

insured health services: Under the Canada Health Act, medically necessary hospital services, medically required physician services and surgical-dental services that require a hospital.

Jurisprudence Examination: CNO's online, open-book examination on the legislation, by-laws, practice standards and guidelines that apply to Ontario nurses.

just culture: An organizational culture that responds to honest errors with learning and system improvement while holding people accountable for reckless choices.

licensed practical nurse (LPN): The title for a practical nurse in most Canadian provinces and territories outside Ontario.

lockbox: An informal term for a patient's instruction that limits how some or all of their personal health information may be used or shared.

medical-surgical nursing: The nursing care of adults who are acutely ill, living through an exacerbation of a chronic illness, or preparing for or recovering from surgery, in hospital and across other settings.

medication reconciliation: A structured process in which providers, patients and families make sure accurate, complete medication information goes with the patient at admission, transfer and discharge.

multimorbidity: Living with two or more chronic health conditions at the same time.

near miss: A patient safety incident that did not reach the patient.

Next Generation NCLEX (NGN): The version of the NCLEX, launched in April 2023, that uses case studies and new item formats to measure clinical judgment.

no-harm incident: A patient safety incident that reached the patient without detectable harm.

Non-Insured Health Benefits (NIHB): An Indigenous Services Canada program that covers specified health benefits, including medical transportation, for registered First Nations and recognized Inuit when other plans do not.

Ontario Health Team: A group of local providers, such as hospitals, primary care, home and community care and long-term care, that plans and delivers connected care for patients in a local area of Ontario.

patient safety incident: An event or circumstance that led to, or could have led to, unnecessary harm to a patient.

patient- and family-centred care: An approach to planning, giving and evaluating care built on partnership among patients, the people they define as family, and health care providers.

personal support worker (PSW): In Ontario, the most common unregulated care provider; PSWs may register voluntarily with the Health and Supportive Care Providers Oversight Authority, which sets no scope of practice.

professional boundaries: The limits that keep a nurse-patient relationship therapeutic rather than personal; keeping them is always the nurse's responsibility.

professional interpreter: A trained interpreter who conveys health information accurately and confidentially between languages; preferred over family members.

registered psychiatric nurse: A separately regulated nursing profession, found in the western provinces, Yukon and several other jurisdictions, that also uses the letters RPN.

Required Organizational Practices (ROPs): Standardized patient safety practices that organizations accredited by Accreditation Canada must have in place.

routine practices: The infection prevention and control practices used with every patient during all care, including risk assessment, hand hygiene, personal protective equipment, environmental controls and administrative controls.

scope of practice: The range of activities a nurse is permitted and able to perform safely, shaped by authority, competence and context.

self-regulated profession: A profession that the government allows to govern its own members, on condition that it acts in the public interest; in Ontario, nursing is regulated through the College of Nurses of Ontario.

snooping: Accessing a person's health information without a professional reason; a privacy breach whatever the motive.

substitute decision-maker (SDM): The person who makes a treatment decision for a patient who is incapable for that decision, chosen according to the ranked list in Ontario's Health Care Consent Act, 1996.

teach-back: A technique in which the patient or caregiver explains or shows, in their own words, what they have been taught; it checks how clearly the nurse taught.

transition in care: Any move of a patient between settings or care teams, including admission, transfer and discharge.

unregulated care provider (UCP): A care provider who is not regulated under the Regulated Health Professions Act, 1991 and has no legally defined scope of practice; in Ontario, most often a personal support worker.

Licensure Review & Clinical Judgment Questions (30)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

1. [CORE] A 58-year-old patient in Ontario with no private drug plan is being discharged after treatment for a heart attack. The patient says, "My pills were free in here. Will the new prescriptions be free at home too?" Which response by the nurse is most accurate?

a. "Yes. The Canada Health Act requires every province to pay for all prescribed medications you need."

b. "Hospital drugs are covered; home drug coverage depends on provincial programs. Let's check."

c. "No. Once you leave hospital, no prescription drugs are ever publicly covered in Canada."

d. "Yes. Under portability, your hospital coverage continues for three months after discharge."

Answer: b — Drugs given in hospital are part of insured hospital services under the Canada Health Act, but coverage of drugs taken at home is decided by each province or territory and often depends on age, income or other criteria (section 1.2). Option a is wrong because the Act does not require coverage of outpatient prescriptions. Option c is wrong because provinces do run public drug programs, such as the Ontario Drug Benefit program for people 65 and older and some younger groups. Option d misstates portability, which concerns coverage when residents move or travel, not coverage after discharge.

2. [CORE] A resident of Nova Scotia develops appendicitis while visiting family in Ontario and has an emergency appendectomy in an Ontario hospital. The patient is not billed, and the hospital is paid through the patient's home provincial plan. Which Canada Health Act criterion does this situation best illustrate?

a. Universality

b. Comprehensiveness

c. Portability

d. Public administration

Answer: c — Portability requires provinces to keep paying for insured services when residents are temporarily away from home (section 1.2, Table 1.1). Universality (a) means all insured residents are covered on the same terms, not coverage while travelling. Comprehensiveness (b) concerns which services are covered. Public administration (d) concerns how the plan is run, by a public, non-profit authority.

3. [CORE] An 84-year-old patient is medically stable after surgery for a hip fracture and is waiting for a bed in a long-term care home. The patient's son asks what it means that his mother has been "designated ALC." Which explanation by the nurse is accurate?

a. "It means she will be discharged home later today without services."

b. "It means she no longer needs any nursing care or monitoring while she waits."

c. "It means she has been formally admitted to a rehabilitation program."

d. "It means she no longer needs acute care and is waiting for another setting."

Answer: d — Alternate level of care (ALC) describes a patient who remains in a hospital bed but no longer needs the intensity of acute care and is waiting for a more suitable setting, such as long-term care (section 1.2). Option a is wrong because ALC patients are waiting for a place to go, not being sent home without support. Option b is wrong because ALC patients still need nursing care and are often at risk while they wait. Option c is wrong because rehabilitation is one possible destination, not what the ALC designation itself means.

4. [CORE] A capable 72-year-old patient with heart failure has named her neighbour as her essential care partner. Which actions by the nurse reflect patient- and family-centred care? Select all that apply.

a. Asking the patient how she would like her neighbour involved in her care

b. Planning the discharge destination with the neighbour while the patient is asleep

c. Inviting the neighbour, with the patient's agreement, to join the discharge teaching

d. Explaining the plan of care in clear, complete terms the patient can use

e. Asking the neighbour to leave during care because she is not a relative

f. Asking the patient what matters most to her about going home

Answer: a, c, d, f — Patient- and family-centred care rests on partnership, respect, information sharing and participation at the level the patient chooses (section 1.1). The patient decides who counts as family and how they take part (a), essential care partners can join teaching with the patient's agreement (c), complete and usable information supports participation (d), and asking what matters most respects the patient's goals (f). Option b leaves a capable patient out of her own decision. Option e is wrong because the patient, not the nurse, defines family, and an essential care partner's role differs from that of a visitor.

5. [CORE] A nurse on a surgical unit in Ontario is preparing a patient for discharge. The patient will need dressing changes at home for several weeks. Which organization coordinates publicly funded home and community care for this patient?

a. Ontario Health atHome

b. The local public health unit

c. The Public Health Agency of Canada

d. Health Canada

Answer: a — Since June 28, 2024, Ontario Health atHome has coordinated home and community care across Ontario, including care coordination and placement services (section 1.2). Public health units (b) deliver population programs such as immunization and infectious disease control, not individual home care. The Public Health Agency of Canada (c) is a federal agency focused on health promotion, disease prevention and public health emergencies. Health Canada (d) administers the Canada Health Act and regulates health products; it does not arrange home care.

6. [CORE] A registered First Nations patient from a remote community in northwestern Ontario is ready for discharge after surgery at a regional hospital and needs to fly home. Which program is most likely to cover the cost of this travel?

a. The portability criterion of the Canada Health Act

b. Ontario Health atHome

c. The Non-Insured Health Benefits program

d. The Public Health Agency of Canada's emergency fund

Answer: c — The Non-Insured Health Benefits (NIHB) program, run by Indigenous Services Canada, covers medical transportation for registered First Nations and recognized Inuit to reach medically necessary care not available in their community, and prior approval may be needed (section 1.2, Canadian Context box). Portability (a) concerns provincial insurance coverage while residents are away from their home province, not travel costs. Ontario Health atHome (b) coordinates home and community care, not medical travel. The Public Health Agency of Canada (d) works on population health and emergencies and does not fund individual patient travel.

Case: Mr. Arthur Lindqvist (Questions 7–12): Mr. Arthur Lindqvist, 79, is on a surgical unit on postoperative day 2 after a hip hemiarthroplasty for a fractured hip. Yesterday he was alert and oriented and walked with a walker and physiotherapy. At 0800 today the RPN finds him restless and oriented to person only. Vital signs: temperature 38.2 °C, heart rate 116, respiratory rate 28, blood pressure 118/70 (his baseline is 134/78), SpO2 88% on room air. He has a moist cough with yellow sputum and crackles at the right lung base. His hip dressing is dry. He rates his hip pain 3/10 at rest. Laboratory results: white blood cell count 14.6 × 10^9/L (yesterday 9.1 × 10^9/L), hemoglobin 112 g/L (yesterday 114 g/L), sodium 138 mmol/L.

7. [CORE] Which findings require immediate follow-up? Select all that apply.

a. Respiratory rate 28
b. SpO2 88% on room air
c. New confusion and restlessness
d. Hemoglobin 112 g/L
e. Hip pain 3/10 at rest
f. Temperature 38.2 °C

Answer: a, b, c, f — Recognize cues (section 1.4). A rapid respiratory rate, low oxygen saturation, a new change in mental status and fever are abnormal and new, and together they point to a patient who is deteriorating. The hemoglobin is close to yesterday's value, so it does not suggest new bleeding. Pain of 3/10 at rest is well controlled and expected after hip surgery.

8. [CORE] Which group of cues best supports a respiratory infection as the cause of Mr. Lindqvist's change?

a. Stable hemoglobin, a dry hip dressing, controlled pain at rest and a normal sodium level
b. Normal sodium, a blood pressure below his usual baseline, restlessness and his advanced age
c. Fever, moist cough, right basal crackles and rising white cell count
d. His age, his recent hip surgery, his reduced mobility and his use of a walker

Answer: c — Analyze cues (section 1.4). Fever, a productive cough, localized crackles and a rising white cell count belong together and fit a lung infection, such as a pneumonia after surgery. Option a groups cues that argue against bleeding but say nothing about infection. Option b mixes unrelated findings, and a normal sodium does not support any hypothesis here. Option d lists risk factors, not cues of a current problem.

9. [CORE] Which hypothesis should the RPN treat as the priority?

a. Acute pain related to the surgical incision
b. Impaired gas exchange from a likely lung infection
c. Risk for falls related to new confusion
d. Constipation related to reduced mobility

Answer: b — Prioritize hypotheses (section 1.4). Low oxygen saturation, a fast respiratory rate and new confusion show that breathing and oxygen delivery are affected now, so this is both likely and dangerous. Pain is controlled. Falls are a real risk, but they follow from the confusion, which is itself likely caused by low oxygen and infection. Constipation is not urgent and is not supported by the cues.

10. [CORE] Which actions should the RPN plan at this point? Select all that apply.

a. Raise the head of the bed and help him sit upright
b. Report to the RN and the most responsible provider and use the rapid response process if criteria are met
c. Give the next scheduled opioid dose early to settle his restlessness
d. Reassess vital signs and level of consciousness often
e. Restrict his oral fluids to protect his lungs
f. Coach him to take deep breaths and cough
g. Apply wrist restraints so he does not pull at his tubing

Answer: a, b, d, f — Generate solutions (section 1.4). Sitting upright and deep breathing help ventilation. Escalation is required because he is deteriorating (section 1.3), and frequent reassessment will show whether he is getting better or worse. Giving an opioid early could slow his breathing and worsen confusion. Fluids should not be restricted without an order, and he may need more fluid with fever. Restraints are not a first response to restlessness and can increase harm and agitation.

11. [CORE] The physician sees Mr. Lindqvist and orders oxygen titrated to a target saturation, a chest X-ray, a sputum specimen and an IV antibiotic. Which action should the nurse take first?

a. Arrange transport to the imaging department
b. Collect a sputum specimen
c. Call his daughter to update her
d. Apply oxygen and titrate to the target

Answer: d — Take action (section 1.4). His most urgent problem is low oxygen, so oxygen comes first. The X-ray and sputum specimen are needed but can follow within minutes; the order in which cultures and the antibiotic are done follows the orders and hospital policy (Chapter 4). Updating his family matters but does not come before treating hypoxemia.

12. [CORE] Two hours later, which finding best shows that the plan is working?

a. Respiratory rate 20, SpO2 94% on ordered oxygen, oriented to person and place
b. Heart rate 124, temperature 38.6 °C and a moist cough that is now producing more sputum
c. Urine output of 15 mL/h for each of the past two hours, with darker, concentrated urine
d. Now drowsy, wakes only when spoken to loudly, and no longer pulls at his oxygen tubing

Answer: a — Evaluate outcomes (section 1.4). A slower respiratory rate, better oxygen saturation and improving orientation show that the actions are working, though monitoring continues. A rising heart rate and fever, low urine output and a falling level of consciousness all show worsening and call for further escalation.

13. [CORE] An RPN in an Ontario public hospital finds that a patient's only peripheral IV has infiltrated. There is no order to restart it. The RPN is competent to insert IVs and knows the regulation allows nurses to initiate peripheral venipuncture with 0.9% sodium chloride in some situations. What should the RPN do?

a. Insert a new IV now, because the regulation allows nurses to initiate this controlled act

b. Get an order or use a directive, since initiation is not allowed in public hospitals

c. Ask the RN to insert it, because only RNs may start peripheral IVs

d. Insert the IV once the charge nurse gives verbal permission for it to be done on this shift

Answer: b — Authority (section 1.3). Initiation is not available in public hospitals under the Public Hospitals Act, 1990, so the RPN needs an order or a directive. Option a ignores the setting. Option c is wrong because RPNs are authorized to perform this controlled act with an order. A charge nurse's permission is not an authorizing mechanism.

14. [CORE] An RPN is assigned a patient who returns from surgery with a chest tube. The RPN has never cared for a chest tube drainage system and has had no teaching on it. What is the best action?

a. Read the manufacturer's leaflet on the drainage system carefully and then carry on with the assignment as given

b. Refuse to care for the patient and leave the unit's other nurses to decide among themselves who will take over

c. Ask the PSW to watch the drainage system closely during the shift and report any bubbling or change in the drainage

d. Tell the charge nurse, ask for teaching and support, and consult or transfer care until competent

Answer: d — Competence (section 1.3). A nurse who lacks the knowledge, skill and judgment for an activity does not perform it alone. The nurse seeks help and learning and makes sure the patient is safe in the meantime. A leaflet does not give competence. Walking away without a safe handover leaves the patient at risk. Monitoring a chest tube needs nursing assessment and cannot simply be handed to a UCP.

15. [CORE] Which statement about scope and assignment for Ontario nurses is accurate?

a. An employer can limit a nurse's scope through policy but cannot expand it beyond what law and CNO allow

b. CNO's standards require that RPNs be assigned only patients whose condition is stable and predictable

c. CNO's three-factor framework of client, nurse and environment decides which nurse cares for each patient

d. When an employer policy conflicts with a CNO practice standard, the nurse's first duty is to follow the policy

Answer: a — Context (section 1.3). Employers may narrow, but never widen, a nurse's scope. Assigning stable patients to RPNs is a common employer practice, not a CNO rule. The three-factor framework was retired in 2023. When a policy conflicts with a CNO standard, the nurse's first accountability is to the standard.

16. [CORE] A nurse notes that a patient has a temperature of 38.5 °C, a heart rate of 110 and a new productive cough, and links them as signs of a possible pneumonia. Which CJMM skill is the nurse using?

a. Recognize cues

b. Prioritize hypotheses

c. Analyze cues

d. Generate solutions

Answer: c — Analyze cues (section 1.4). Grouping cues and linking them to a possible explanation is analyzing cues. Recognizing cues is noticing that the findings matter. Prioritizing hypotheses ranks several explanations. Generating solutions plans actions.

17. [RN] In which layer of the CJMM do the six cognitive skills sit?

a. Layer 0

b. Layer 1

c. Layer 3

d. Layer 4

Answer: c — Going Deeper box (section 1.4). Layer 3 holds the six cognitive skills and is the level at which NCLEX items are written. Layer 0 is the context of the patient's needs, Layer 1 is clinical judgment as a whole, and Layer 4 holds environmental and individual factors.

18. [RN] An NGN item has four correct options and is scored by the plus/minus rule. A candidate selects three correct options and one incorrect option. How many points does the candidate earn?

a. 2 points

b. 3 points

c. 0 points

d. 1 point

Answer: a — Going Deeper box (section 1.4). Under plus/minus scoring, the candidate gains a point for each correct choice and loses one for each incorrect choice, so 3 − 1 = 2. Three points ignores the deduction. Zero would apply only if deductions equalled or exceeded correct choices. One point miscounts the deduction.

19. [RN] Which statement about Next Generation NCLEX items is accurate?

a. Bow-tie items appear only inside the six-item case studies, never on their own as stand-alone items

b. Case studies have now replaced all stand-alone items, so every item belongs to a case

c. Every item, including select-all items, is scored only as fully right or fully wrong

d. Each case study has six items on one patient, one for each cognitive skill in order

Answer: d — Going Deeper box (section 1.4). An NGN case study follows one patient through six items from recognizing cues to evaluating outcomes. Bow-tie and trend are stand-alone formats. Stand-alone items still appear alongside case studies. Items with more than one correct answer can earn partial credit.

Case: Mr. Paul Lavoie (Questions 20–23): Mr. Paul Lavoie, 72, is admitted to a surgical unit in an Ontario hospital for an elective right total hip replacement. He lives with his wife. He has a valid power of attorney for personal care that names his daughter, Monique. Kiran Dhillon, RPN, is assigned to his care.

20. [CORE] On the morning of surgery, the surgeon asks the RPN to "get Mr. Lavoie's consent form signed." When the RPN brings the form, Mr. Lavoie says, "The surgeon never told me what could go wrong." What is the RPN's best action?

a. Explain the usual risks of hip replacement surgery to him and then witness his signature.

b. Hold the form and tell the surgeon that Mr. Lavoie needs more information.

c. Ask him to sign now, because the signature only confirms that he is the right patient.

d. Ask his wife, who is at the bedside, to sign the consent form for him instead.

Answer: b — The practitioner who proposes a treatment is responsible for obtaining informed consent, including explaining material risks (section 1.5). A signature means little if the patient is not informed, so the nurse holds the form and advocates for the patient to get the information. Option a takes on the surgeon's responsibility and the nurse may not know the specific risks of this surgery. Option c ignores the patient's statement and misstates what the signature represents. Option d is wrong because Mr. Lavoie is presumed capable, so no substitute decision-maker is involved.

21. [CORE] On the second night after surgery, Mr. Lavoie becomes acutely confused and cannot understand information about a proposed blood transfusion. The physician proposing the transfusion finds him incapable with respect to this decision. Monique is available and willing to act. Who should give or refuse consent?

a. His wife, because a spouse ranks first among family members.

b. The surgeon, because the transfusion is medically needed.

c. His daughter, Monique, as his attorney for personal care.

d. The RPN, because the nurse knows his wishes and condition best.

Answer: c — Under the HCCA hierarchy, an attorney for personal care ranks above a spouse, so Monique is his substitute decision-maker (section 1.5). Option a would apply only if no higher-ranked person were available and willing. Option b is wrong because the situation is not described as an emergency, and the surgeon proposes treatment but does not consent on the patient's behalf. Option d is wrong because nurses do not act as SDMs for their patients.

22. [CORE] Monique consents, and the transfusion begins. Two days later, Mr. Lavoie's confusion has cleared and he is assessed as capable. During a second ordered unit of red blood cells, he says, "I don't want any more blood. Please stop it." What should the RPN do first?

a. Stop the transfusion and notify the prescriber.

b. Continue, because his daughter already consented.

c. Slow the infusion rate until his daughter can be reached.

d. Remind him that the hemoglobin result shows he needs the blood.

Answer: a — A capable person may withdraw consent at any time, and once Mr. Lavoie is capable, he makes his own decisions (section 1.5). The RPN stops the transfusion, keeps the IV access as policy directs, tells the prescriber and documents. Option b is wrong because the SDM's authority ends when the patient regains capacity for the decision. Option c continues treatment without consent. Option d may be part of a later conversation but pressures him and delays respecting his decision.

23. [CORE] The next morning, Mr. Lavoie agrees to have his vital signs checked but refuses his scheduled wound dressing change. What is the RPN's most appropriate response?

a. Ask the surgeon to speak with him and obtain consent for the dressing change.

b. Change the dressing anyway, because he consented to all care on admission.

c. Record that he is non-compliant and try again at the end of the shift.

d. Explore his reasons, explain the risks of refusing and respect his decision.

Answer: d — The nurse is responsible for obtaining consent for nursing care the nurse proposes, and consent is specific to each treatment (section 1.5). Exploring his reasons may reveal a concern, such as pain, that the nurse can address, and informing him of the consequences makes his decision informed. Option a passes the nurse's responsibility to another practitioner. Option b relies on general consent that does not cover a specific procedure he is refusing now. Option c uses a judgmental label and does not explore or inform.

24. [CORE] A capable patient on a medical unit is admitted with pneumonia. Her adult son telephones the nurse and asks for her latest chest X-ray results. The patient has not said who may receive information. What should the nurse do?

a. Share the results, because family members are part of the circle of care.

b. Tell the son that privacy law forbids sharing any information with family.

c. Ask the physician to call the son with the results.

d. Ask the patient whether she agrees to sharing the results with her son.

Answer: d — The circle of care allows custodians to assume implied consent only when sharing information with other health information custodians for the patient's care (section 1.5). A son is not a custodian, so the capable patient's consent is needed. Option a misstates the circle of care. Option b is wrong because sharing is allowed with consent. Option c still discloses information without the patient's consent.

25. [CORE] At 1600, a nurse realizes she did not document a dressing change she completed at 1000. What is the correct way to record it?

a. Write a late entry that states the time the dressing was actually changed.

b. Insert the note between the 0900 and 1100 entries so the record stays in time order.

c. Ask the nurse on the next shift to document it.

d. Leave it undocumented, because the care plan shows the dressing was due.

Answer: a — CNO's Documentation standard requires late entries to be clearly labelled and to state when the care happened (section 1.5). Option b makes the entry look as if it was written at the time of care, which misrepresents the record. Option c breaks the rule that nurses document only care they personally provided. Option d leaves the record incomplete, and a care plan shows what was planned, not what was done.

26. [CORE] A patient whom the nurse cared for after a bowel resection was discharged last week. He sends the nurse a friend request on her personal social media account with the message "Thanks for everything!" What is the nurse's best action?

a. Accept the request, because the therapeutic relationship ended at discharge.

b. Accept the request but avoid discussing his health or his care online.

c. Decline the request and, if needed, kindly explain why she cannot accept.

d. Report the patient's message to the hospital's security department.

Answer: c — CNO's Professional Boundaries and Nurse-Client Relationships standard expects nurses not to connect with patients on personal social media, and keeping boundaries is always the nurse's responsibility (section 1.5). Options a and b turn a recent therapeutic relationship into a personal one; discharge a week earlier does not make that appropriate, and avoiding health topics online does not remove the boundary problem. Option d overreacts to a friendly gesture that is not a threat.

27. [CORE] A nurse gives a patient a dose of metoprolol that was ordered for the patient in the next bed. The nurse discovers the error within minutes. The patient's vital signs stay within normal limits, and no harm is detected. How is this event classified?

a. Near miss

b. No-harm incident

c. Harmful incident

d. Adverse drug reaction

Answer: b — A no-harm incident reached the patient but caused no detectable harm (section 1.6). Option a is wrong because a near miss is caught before it reaches the patient. Option c is wrong because no harm occurred. Option d is wrong because an adverse drug reaction is a harmful, unintended response to a drug, and no harmful response occurred; the event is classified by whether it reached the patient and caused harm.

28. [CORE] A nurse has programmed an IV insulin infusion and asks a colleague for an independent double check. Which action by the colleague shows a true independent double check?

a. Watching the first nurse program the pump and agreeing that all the settings look correct

b. Reading the first nurse's written calculation and confirming that the math is right

c. Signing the medication record after the first nurse reads the order and settings aloud

d. Working out the rate alone from the order, then comparing it with the pump settings

Answer: d — In an independent double check, the second practitioner verifies the order, drug, dose and pump settings and does the calculation separately, without seeing the first result. Only then are the two results compared (section 1.6). Options a, b and c expose the checker to the first nurse's work, so the checker tends to confirm what is shown rather than catch an error.

29. [CORE] A nurse is preparing discharge teaching about a new anticoagulant for a patient who speaks Punjabi and has limited English. The patient's 15-year-old granddaughter offers to interpret. What is the nurse's best action?

a. Accept the granddaughter's offer, because the patient trusts her.

b. Book a professional interpreter and include the granddaughter if the patient wishes.

c. Give the patient a written English handout and ask the granddaughter to translate it at home.

d. Teach slowly in English and ask the patient whether she understands.

Answer: b — Professional interpreters improve communication and quality of care, and family members, especially children, should not interpret clinical information (section 1.7). The granddaughter can still take part as a caregiver if the patient agrees. Options a and c rely on a young family member who may lack medical vocabulary and may leave out information. Option d relies on asking "Do you understand?", which does not confirm understanding, and does not overcome the language barrier.

30. [RN] A patient on an Ontario medical unit develops a severe skin reaction to a newly started antibiotic. The reaction extends his hospital stay by six days. The nurse documents the reaction in the health record on Monday. Which statement about reporting under Vanessa's Law is accurate?

a. The prescribing physician must personally report the reaction to Health Canada within 15 days.

b. Reporting is voluntary, because the antibiotic was prescribed and given correctly.

c. The hospital must report it to Health Canada within 30 days of Monday's documentation.

d. It must be reported only if the patient dies or is left with a permanent disability.

Answer: c — Since December 16, 2019, hospitals must report serious adverse drug reactions in writing to Health Canada within 30 calendar days of first documentation in the hospital (section 1.6). The reaction is serious because it prolonged hospitalization. Nurses contribute by recognizing and documenting it. Option a names the wrong reporter and the wrong time limit. Option b is wrong because the rule covers serious adverse drug reactions regardless of whether the drug was prescribed and given correctly. Option d omits other criteria for a serious reaction, including prolonged hospitalization.

References

Agency for Healthcare Research and Quality. (2023). *Tool: Teach-back*. https://www.ahrq.gov/teamstepps-program/curriculum/communication/tools/teachback.html

Apology Act, 2009, S.O. 2009, c. 3. https://www.ontario.ca/laws/statute/09a03

Betts, J., Muntean, W., Kim, D., Jorion, N., & Dickison, P. (2019). Building a method for writing clinical judgment items for entry-level nursing exams. *Journal of Applied Testing Technology, 20*(S2), 21–36. https://www.ncsbn.org/public-files/Building_a_Method_for_Writing_Clinical_Judgment_It.pdf

Boev, C. (2022). Psychometric analysis and evaluation of Next Gen item types: Enhanced hot spot. *Nurse Educator, 47*(6), E154–E155. https://doi.org/10.1097/NNE.0000000000001275

Canada Health Act, R.S.C. 1985, c. C-6. https://laws-lois.justice.gc.ca/eng/acts/c-6/FullText.html

Canadian Institute for Health Information. (2023). *Health spending in Canada: Has spending on seniors changed?* https://indicatorlibrary.cihi.ca/en/has-health-spending-on-seniors-changed

Canadian Institute for Health Information. (2026a). *Hospital stays in Canada, 2024–2025*. https://www.cihi.ca/en/hospital-stays-in-canada-2024-2025

Canadian Institute for Health Information. (2026b, September 24). *Patient harm in Canadian hospitals? It does happen*. https://www.cihi.ca/en/patient-harm-in-canadian-hospitals-it-does-happen

Canadian Institute for Health Information. (2026c, July 23). *Registered psychiatric nurses*. https://www.cihi.ca/en/registered-psychiatric-nurses

Canadian Institute for Health Information. (n.d.). *Hospital stay extended until home care services or supports ready*. https://www.cihi.ca/en/indicators/hospital-stay-extended-until-home-care-services-or-supports-ready

Canadian Nurses Association. (2024). *Twelve tests and treatments to question in nursing*. Choosing Wisely Canada. https://choosingwiselycanada.org/recommendation/nursing/

Canadian Nurses Association. (2025a, July 14). *CNA releases revamped Code of Ethics for Nurses* [News release]. https://www.cna-aiic.ca/en/blogs/cn-content/2025/07/14/cna-releases-revamped-coe-for-nurses

Canadian Nurses Association. (2025b). *Code of ethics for nurses*. https://www.cna-aiic.ca/en/nursing/regulated-nursing-in-canada/nursing-ethics/2025-coe

College of Licensed Practical Nurses and Health Care Aides of Alberta. (2026). *CPNRE 2025 annual report: Pass rates for the Canadian Practical Nurse Registration Examination in Alberta*. https://www.clha.com/wp-content/uploads/2026/03/CPNRE-Annual-Report-2025-ID-222892.pdf

College of Licensed Practical Nurses and Health Care Aides of Alberta. (n.d.). *HCA regulation FAQs*. https://www.clha.com/hca/hcas/hca-faqs/

College of Nurses of Ontario. (2023, June 20). *CNO celebrates 60th anniversary*. https://cno.org/news/cno-celebrates-60th-anniversary

College of Nurses of Ontario. (2024, October 10). *News to use* [Employer newsletter]. https://www.cno.org/Assets/CNO/Documents/Protect-the-public/erg-news-to-use-202410.pdf

College of Nurses of Ontario. (2025a). *Confidentiality and privacy: Personal health information* [Practice standard]. https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41069_privacy.pdf

College of Nurses of Ontario. (2025b). *Consent* [Practice guideline]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41020_consent.pdf

College of Nurses of Ontario. (2025c). *Documentation* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41001_documentation.pdf

College of Nurses of Ontario. (2025d). *Professional boundaries and nurse-client relationships* [Practice standard]. https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41033_therapeutic.pdf

College of Nurses of Ontario. (2025e). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026a). *Code of conduct* [Practice standard]. https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49040_code-of-conduct.pdf

College of Nurses of Ontario. (2026b, October 14). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

College of Nurses of Ontario. (2026c). *Discontinuing or declining to provide care* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/ps-discontinuing-or-declining-to-provide-care-en.pdf

College of Nurses of Ontario. (2026d). *Scope of practice* [Practice standard; in effect March 1, 2027]. https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice-march-2027.pdf

College of Nurses of Ontario. (n.d.-a). *About CNO*. https://cno.org/what-is-cno/about-cno

College of Nurses of Ontario. (n.d.-b). *Code of conduct FAQs*. https://cno.org/protect-the-public/code-of-conduct-for-nurses/code-of-conduct-faqs

College of Nurses of Ontario. (n.d.-c). *Employer's toolkit: Sexual abuse prevention – Introduction*. https://cno.org/en/protect-public/employer-resources/employers-toolkit-sexual-abuse-prevention/introduction

College of Nurses of Ontario. (n.d.-d). *FAQs: RN prescribing*. https://cno.org/en/learn-about-standards-guidelines/rn-prescribing/faqs-rn-prescribing

College of Nurses of Ontario. (n.d.-e). *Jurisprudence examination*. https://cno.org/become-a-nurse/examinations/jurisprudence-examination

College of Nurses of Ontario. (n.d.-f). *Legal obligations*. https://cno.org/protect-the-public/file-a-report/reporting-guide/legal-obligations

College of Nurses of Ontario. (n.d.-g). *Nursing education*. https://cno.org/become-a-nurse/registration-requirements/nursing-education/nursing-education

College of Nurses of Ontario. (n.d.-h). *Obtaining informed consent*. https://cno.org/standards-learning/ask-practice/obtaining-informed-consent

College of Nurses of Ontario. (n.d.-i). *A single classification of nurse practitioners (NPs)*. https://cno.org/standards-learning/nurse-practitioners/a-single-classification-of-nurse-practitioners-nps

College of Nurses of Ontario. (n.d.-j). *Welcome to CNO*. https://cno.org/en/for/welcome-to-cno

College of Nurses of Ontario. (n.d.-k). *Working with unregulated care providers*. https://cno.org/standards-learning/ask-practice/working-with-unregulated-care-providers

Covinsky, K. E., Pierluissi, E., & Johnston, C. B. (2011). Hospitalization-associated disability: "She was probably able to ambulate, but I'm not sure." *JAMA, 306*(16), 1782–1793. https://doi.org/10.1001/jama.2011.1556

Disclosure Working Group. (2011). *Canadian disclosure guidelines: Being open with patients and families*. Canadian Patient Safety Institute. https://healthcareexcellence.ca/en/resources/canadian-disclosure-guidelines

Employment and Social Development Canada. (2026). *Do you qualify: Canadian Dental Care Plan*. https://www.canada.ca/en/services/benefits/dental/dental-care-plan/qualify.html

Ferris, J. K., Prangnell, A., Wagar, B., Choi, A., Simkin, J., Woods, R. R., Sbihi, H., Harder, K., & Smolina, K. (2025). Trends and inequalities in multimorbidity from 2001/2002 to 2019/2020: A population-based study in British Columbia. *Health Reports, 36*(3), 3–16. https://doi.org/10.25318/82-003-x202500300001-eng

Fixing Long-Term Care Act, 2021, S.O. 2021, c. 39, Sched. 1. https://www.ontario.ca/laws/statute/21f39

French Language Services Act, R.S.O. 1990, c. F.32. https://www.ontario.ca/laws/statute/90f32

Government of Alberta. (n.d.). *Health care aide program*. https://www.alberta.ca/health-care-aide-program

Government of Ontario. (2023a). *Ontario's public hospitals*. https://www.ontario.ca/page/ontarios-public-hospitals

Government of Ontario. (2023b). *Schedule: Order in Council 1604/2023*. https://www.ontario.ca/page/schedule-order-council-16042023

Government of Ontario. (2024). *Connected care update — June 21, 2024*. https://www.ontario.ca/document/connected-care-updates/connected-care-update-june-21-2024

Government of Ontario. (2025a). *Explore your care options*. https://www.ontario.ca/page/explore-your-care-options

Government of Ontario. (2025b). *Ontario Health agency*. https://www.ontario.ca/page/ontario-health-agency

Government of Ontario. (2026a). *Get coverage for prescription drugs*. https://www.ontario.ca/page/get-coverage-prescription-drugs

Government of Ontario. (2026b). *Northern Health Travel Grant program*. https://www.ontario.ca/page/northern-health-travel-grant-program

Government of Ontario. (2026c). *Ontario Health Teams*. https://www.ontario.ca/page/ontario-health-teams

Government of Ontario. (2026d). *Ontario public health standards: Requirements for programs, services, and accountability*. https://www.ontario.ca/page/ontario-public-health-standards-requirements-programs-services-and-accountability

Health Canada. (2023). *Mandatory reporting of serious adverse drug reactions and medical device incidents by hospitals: Guidance document*. https://www.canada.ca/en/health-canada/services/drugs-health-products/medeffect-canada/adverse-reaction-reporting/mandatory-hospital-reporting/drugs-devices/guidance.html

Health Canada. (2025). *About Canada's health care system*. https://www.canada.ca/en/health-canada/services/canada-health-care-system.html

Health Care Consent Act, 1996, S.O. 1996, c. 2, Sched. A. https://www.ontario.ca/laws/statute/96h02

Health Standards Organization. (2024). *Required organizational practices: 2024 handbook* (HSO R01002:2024 [E]). https://professionals.wrha.mb.ca/files/long.term_.care_.-accrreditation-AC-ROPhandbook2024.pdf

Healthcare Excellence Canada. (n.d.-a). *Essential Together*. https://healthcareexcellence.ca/en/what-we-do/all-programs/essential-together

Healthcare Excellence Canada. (n.d.-b). *Patient partnerships and engagement*. https://healthcareexcellence.ca/en/what-we-do/all-programs/patient-partnerships-and-engagement

Incident Analysis Collaborating Parties. (2012). *Canadian incident analysis framework*. Canadian Patient Safety Institute. https://healthcareexcellence.ca/en/resources/patient-safety-incident-analysis

Indigenous Services Canada. (2019). *Non-Insured Health Benefits (NIHB) Program for First Nations and Inuit: Medical transportation policy framework (interim)*. https://www.sac-isc.gc.ca/eng/1579891130443/1579891286837

Indigenous Services Canada. (2025). *Non-Insured Health Benefits program for First Nations and Inuit: Medical transportation benefits*. https://www.sac-isc.gc.ca/eng/1574177172364

Indigenous Services Canada. (n.d.-a). *About the Non-Insured Health Benefits program*. https://www.sac-isc.gc.ca/eng/1576790320164

Indigenous Services Canada. (n.d.-b). *Working as a nurse in a First Nations community*. https://www.sac-isc.gc.ca/eng/1572873725033

Information and Privacy Commissioner of Ontario. (2005). *Lock-box fact sheet* (Fact Sheet No. 8). https://ipc.on.ca/en/media/1666/download

Information and Privacy Commissioner of Ontario. (2015). *Circle of care: Sharing personal health information for health-care purposes*. https://ipc.on.ca/media/1617/download

Information and Privacy Commissioner of Ontario. (n.d.). *Report a health privacy breach*. https://www.ipc.on.ca/en/health-organizations/report-a-privacy-breach

Institute for Patient- and Family-Centered Care. (n.d.). *Patient- and family-centered care*. https://ipfcc.org/about/pfcc.html

Institute for Safe Medication Practices Canada. (2006). *Do not use: Dangerous abbreviations, symbols and dose designations*. https://www.ismp-canada.org/download/ISMPC_List_of_Dangerous_Abbreviations.pdf

Institute for Safe Medication Practices Canada. (2016). *Frequently asked questions (FAQs): Independent double checks*. https://www.ismp-canada.org/download/ocil/FAQ-IDC-high-risk-meds-1Nurse.pdf

Institute for Safe Medication Practices Canada. (n.d.-a). *5 questions to ask about your medications*. https://www.ismp-canada.org/medrec/5questions.htm

Institute for Safe Medication Practices Canada. (n.d.-b). *High-alert medications*. https://www.ismp-canada.org/LTC/high-alert-medications.htm

Institute for Safe Medication Practices Canada. (n.d.-c). *Medication reconciliation (MedRec)*. https://ismp-canada.org/medrec

Jull, J., Sheppard, A. J., Hizaka, A., Inuit Medical Interpreter Team, Barton, G., Doering, P., Dorschner, D., Edgecombe, N., Ellis, M., Graham, I. D., Habash, M., Jodouin, G., Kilabuk, L., Koonoo, T., Roberts, C., & Mamisarvik Healing Centre Team. (2021). Experiences of Inuit in Canada who travel from remote settings for cancer care and impacts on decision making. *BMC Health Services Research, 21*(1), Article 328. https://doi.org/10.1186/s12913-021-06303-9

Karliner, L. S., Jacobs, E. A., Chen, A. H., & Mutha, S. (2007). Do professional interpreters improve clinical care for patients with limited English proficiency? A systematic review of the literature. *Health Services Research, 42*(2), 727–754. https://doi.org/10.1111/j.1475-6773.2006.00629.x

Ministry of Francophone Affairs. (2023). *2023 report on Francophone affairs*. Government of Ontario. https://www.ontario.ca/page/2023-report-francophone-affairs

Muntean, W., & Betts, J. (2026). *Clinical judgment assessment: Unfolding case studies and NCLEX results* [Presentation transcript, 2026 NCSBN Scientific Symposium]. National Council of State Boards of Nursing. https://www.ncsbn.org/public-files/videos/Transcript_2026scisymp_muntean-betts.pdf

National Council of State Boards of Nursing. (2020, Summer). *Next Generation NCLEX news*. https://www.ncsbn.org/public-files/NGN_Summer20_Eng_05.pdf

National Council of State Boards of Nursing. (2021, Fall). *Next Generation NCLEX news*. https://www.ncsbn.org/public-files/NGN_Fall21_English_Final.pdf

National Council of State Boards of Nursing. (2022, Spring). *Leader to leader*. https://www.ncsbn.org/public-files/LTL_Spring2022.pdf

National Council of State Boards of Nursing. (2023). *NCSBN launches Next Generation NCLEX exam*. https://www.ncsbn.org/news/ncsbn-launches-next-generation-nclex-exam

National Council of State Boards of Nursing. (2026). *NCLEX-RN test plan* [Effective April 2026]. https://www.nclex.com/files/2026_RN_Test%20Plan_English-F.pdf

National Council of State Boards of Nursing. (2027). *RExPN test plan* [Effective January 2027]. https://www.ncsbn.org/public-files/2027_RExPN-TestPlan.pdf

National Council of State Boards of Nursing. (n.d.-a). *Clinical judgment measurement model*. https://www.nclex.com/clinical-judgment-measurement-model.page

National Council of State Boards of Nursing. (n.d.-b). *Frequently asked questions*. https://www.nclex.com/faqs.page

National Council of State Boards of Nursing. (n.d.-c). *Next Generation NCLEX (NGN)*. https://www.nclex.com/next-generation-nclex.page

Nursing Act, 1991, S.O. 1991, c. 32. https://www.ontario.ca/laws/statute/91n32

Ontario Health. (2021). *Alternate level of care (ALC) days expressed as a percentage of all inpatient days in the same period* [Indicator library]. https://indicatorlibrary.hqontario.ca/Indicator/Detailed/ALC-days-expressed-percentage-inpatient-days-same-period-EN/EN

Ontario Health. (2026a). *Ontario Health regions*. https://www.ontariohealth.ca/system/regions

Ontario Health. (2026b). *Ontario Health Teams*. https://www.ontariohealth.ca/system-planning/ontario-health-teams

Ontario Ministry of Health. (2025). *Ontario's primary care action plan, January 2025*. https://www.ontario.ca/page/ontarios-primary-care-action-plan-january-2025

Ontario Public Appointments Secretariat. (n.d.). *Ontario Health atHome*. https://www.pas.gov.on.ca/Home/Agency/828

Ornge. (n.d.). *Learn more about Ornge*. https://www.ornge.ca/about-us

Personal Health Information Protection Act, 2004, S.O. 2004, c. 3, Sched. A. https://www.ontario.ca/laws/statute/04p03

Protecting Canadians from Unsafe Drugs Act (Vanessa's Law), S.C. 2014, c. 24. https://laws-lois.justice.gc.ca/eng/AnnualStatutes/2014_24/

Provincial Infectious Diseases Advisory Committee. (2014). *Best practices for hand hygiene in all health care settings* (4th ed.). Public Health Ontario. https://www.publichealthontario.ca/-/media/documents/bp-hand-hygiene.pdf

Provincial Infectious Diseases Advisory Committee. (2025). *Routine practices and additional precautions in all health care settings* (3rd ed., 4th rev.). Public Health Ontario. https://www.publichealthontario.ca/-/media/documents/bp-rpap-healthcare-settings.pdf

Public Health Agency of Canada. (2020). *Aging and chronic diseases: A profile of Canadian seniors*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/aging-chronic-diseases-profile-canadian-seniors-report.html

Public Health Agency of Canada. (2025). *Public Health Agency of Canada mandate*. https://www.canada.ca/en/public-health/corporate/mandate.html

Public Hospitals Act, R.S.O. 1990, c. P.40. https://www.ontario.ca/laws/statute/90p40

Registered Nurses' Association of Ontario. (2015). *Person- and family-centred care* (Clinical best practice guidelines). https://rnao.ca/media/3244/download

Regulated Health Professions Act, 1991, S.O. 1991, c. 18. https://www.ontario.ca/laws/statute/91r18

Rootman, I., & Gordon-El-Bihbety, D. (2008). *A vision for a health literate Canada: Report of the Expert Panel on Health Literacy*. Canadian Public Health Association. https://www.cpha.ca/sites/default/files/uploads/resources/healthlit/execsum_e.pdf

Simpson, A., Boev, C., & Dambaugh, L. (2023). Next generation NCLEX stand-alone items: Bowtie & trend. *Teaching and Learning in Nursing, 18*(3), 415–418. https://doi.org/10.1016/j.teln.2023.01.005

Société Santé en français. (n.d.). *Société Santé en français*. https://santefrancais.ca/en/

Statistics Canada. (2024, December 10). Literacy, numeracy and adaptive problem-solving skills of Canadians: Results from the 2022 Programme for the International Assessment of Adult Competencies. *The Daily*. https://www150.statcan.gc.ca/n1/daily-quotidien/241210/dq241210a-eng.htm

Statistics Canada. (2026, September 23). Canada's population estimates: Age and gender, 2026. *The Daily*. https://www150.statcan.gc.ca/n1/daily-quotidien/260923/dq260923a-eng.htm

Substitute Decisions Act, 1992, S.O. 1992, c. 30. https://www.ontario.ca/laws/statute/92s30

02 Equity, Cultural Safety and Indigenous Health in Adult Care

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain how the social and structural determinants of health shape adults' illness, access to care and outcomes in Canada.
2. Distinguish cultural awareness, competence, humility and safety, and apply trauma- and violence-informed care on a medical-surgical unit.
3. Describe First Nations, Inuit and Métis health using a distinctions-based, strengths-based approach that names colonial structures and Indigenous-specific racism.
4. Apply the Truth and Reconciliation Commission's Calls to Action 18 to 24, the United Nations Declaration on the Rights of Indigenous Peoples, Joyce's Principle and the First Nations principles of OCAP® to nursing practice.
5. Adapt care for racialized, 2SLGBTQI+ and disabled adults, newcomers and refugees, and adults experiencing homelessness or poverty.
6. Recognize bias, including race-based clinical tools, and respond to discrimination through advocacy and reporting.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 3	Advocate; Clinician; Scholar	Foundations of Practice; Collaborative Practice
2, 5	Advocate; Communicator; Clinician	Ethical Practice; Collaborative Practice
4	Advocate; Professional; Leader	Ethical Practice; Legal Practice
6	Advocate; Professional; Scholar	Ethical Practice; Professional Practice

Introduction

Two patients with the same diagnosis can leave the same unit with very different chances of recovering. One goes home to a stocked kitchen, a drug plan and a partner who drives. The other cannot afford the new prescriptions, lives two bus transfers from the clinic and has no one to check the wound. The treatment was the same, but the conditions the patient goes home to are not. This chapter treats those conditions as clinical facts, because they shape adherence, readmission, complications and trust as surely as a laboratory value does.

Equity is also a patient-safety issue inside the hospital. Anti-Black racism in clinical interactions and institutional policies, for example, is linked to health disparities, poorer quality of care and patient mistrust (Registered Nurses' Association of Ontario [RNAO], 2026). A patient who has been dismissed before may delay reporting new pain or leave before treatment is finished. The College of Nurses of Ontario (CNO) expects every nurse in Ontario to assess each patient's risk of health inequities and act to secure the best possible outcomes (CNO, 2026).

This chapter begins with health equity and the determinants of health, then explains cultural safety, cultural humility and trauma- and violence-informed care. It then turns to First Nations, Inuit and Métis health (section 2.3); the rights, policies and data principles that guide nurses (section 2.4); care of other equity-deserving adults (section 2.5); and equity in everyday medical-surgical practice (section 2.6). Every later chapter applies this lens. Risk factors use Canadian data and name structural causes, findings are described on a range of skin tones, and Canadian Context boxes show how care differs by place and community.

2.1 Health Equity and the Determinants of Health

Most of what makes people healthy or unwell happens outside hospitals. Medical-surgical nurses see the results in who is admitted, how sick they are on arrival and what waits for them at discharge.

Equity and Equality

Equality means giving everyone the same thing. **Equity** means giving people what they need so that each person has a fair chance at good outcomes. A unit that hands every patient the same printed discharge sheet treats patients equally. A unit that offers the sheet in the patient's language, checks that the patient can afford the medications and arranges a ride to the follow-up clinic is working toward equity.

The Public Health Agency of Canada (PHAC) describes **health equity** as a fair opportunity for every person to reach their best possible health, regardless of the social and structural conditions of their lives (PHAC, 2026a). Differences in health between groups are **health inequalities**; they become **health inequities** when they are systematic and could plausibly be prevented or reduced by collective action; such differences may be judged unjust (PHAC, 2018). The National Collaborating Centre for Determinants of Health (NCCDH) adds that inequities are unfair, avoidable and modifiable, because they stem from choices about how resources and opportunities are allocated (NCCDH, 2023). Inequities are not accidents of biology or personal failings; they come from conditions that people, including health care providers, can change.

Determinants of Health

The **determinants of health** are the conditions that shape the health of individuals and populations; PHAC now groups them into two levels (PHAC, 2026a).

Social determinants of health are the everyday conditions of people's lives. PHAC's examples include income and education; decent, safe and secure work that pays a living wage; community and social support, including access to health care; adequate, affordable housing; accessible public spaces; and freedom from discrimination and violence where people live (PHAC, 2026a). PHAC's longstanding list names 12 interrelated key determinants: income and social status, social support networks, education and literacy, employment and working conditions, social environments, physical environments, personal health practices and coping skills, healthy child development, biology and genetic endowment, health services, gender, and culture (PHAC, 2022). Even personal health practices are shaped by social and economic conditions (PHAC, 2022).

PHAC also recognizes perspectives on the determinants from First Nations, Inuit and Métis Peoples, and from Critical Race Theory and Two-Spirit, lesbian, gay, bisexual, transgender, queer and intersex (2SLGBTQI+) scholarship (see section 2.5), which help explain how racism, colonialism and discrimination can lead to different health outcomes (PHAC, 2026a). Section 2.3 returns to First Nations, Inuit and Métis perspectives.

Structural Determinants and Intersectionality

Structural determinants of health are the large systems that shape society, including how resources and opportunities are distributed. They include governments at every level; the systems that run education, health care, immigration and finance; labour markets; and international agreements. Their laws, policies and institutional practices shape the everyday conditions described above (PHAC, 2026a). Colonial policies, institutional racism and the rules that set income supports or drug coverage are all structural determinants. They explain why social determinants are not shared evenly: low income, for example, follows patterns these systems set.

Intersectionality is a way of understanding how a person's social positions, such as race, gender, disability, age, sexual orientation, immigration status and income, combine to shape their experiences of advantage and disadvantage. The legal scholar Kimberlé Crenshaw introduced the term in 1989, showing that treating race and sex as separate categories hid the discrimination Black women faced (Crenshaw, 1989). An older racialized woman (see section 2.5) with a disability who speaks limited English may meet barriers that no single label explains, so the nurse looks at the whole person.

Determinants in Canadian Data

A few national figures show the size of these issues:

- **Food insecurity: Food insecurity** means a household cannot count on enough food because money is short. In 2024, 24.0% of Canadians (about 9.8 million people) lived in a household with marginal, moderate or severe food insecurity in the 12 months before the interview. Almost half (44.4%) of people in one-parent families were affected. Rates were higher for racialized people (30.4%; provinces only) than for non-racialized people (21.0%), and for Indigenous people aged 15 and older (34.7%) than for non-Indigenous people (22.4%); the survey does not cover reserves or other Indigenous settlements in the provinces (Statistics Canada, 2026a). PHAC points to systemic inequities such as racism, colonialism and discrimination as causes of differences like these (PHAC, 2026a).
- **Poverty:** About 4.5 million people (11.0% of the population) had incomes below Canada's Official Poverty Line in 2024. The line is set using the Market Basket Measure (Statistics Canada, 2026a).
- **Homelessness:** Coordinated point-in-time counts in 74 communities, held mostly in October and November 2024, identified nearly 60,000 people experiencing homelessness (defined in section 2.5). A one-night count understates homelessness over a year, and Quebec did not take part (Housing, Infrastructure and Communities Canada [HICC], 2025a). In the counts' survey (preliminary results), 28% of respondents had spent one or more nights in a hospital or other health facility during the previous year (HICC, 2025b).
- **The income gradient:** In 2023, health-adjusted life expectancy (the years a person can expect to live in good health) at birth was 61.9 years in the lowest neighbourhood income quintile and 70.0 years in the highest, a gap of 8.1 years; income was measured by neighbourhood, not household (Statistics Canada, 2026b).
- **Medication cost:** In a 2021 survey of adults in the provinces, 9% of those who had taken or been prescribed a medication in the previous 12 months did not take it as prescribed because of cost. The rate was 17% among people without prescription insurance and 7% among those with coverage (Cortes & Smith, 2022).

Determinants on the Medical-Surgical Unit

Determinants show up at the bedside. A patient discharged on a new anticoagulant with no drug plan may stretch doses to make the supply last. A patient with no car may miss the wound check that would catch an infection early. A person experiencing homelessness may be discharged after surgery to a shelter that closes by day, with nowhere to rest or keep dressings clean. A patient with diabetes and an empty fridge is at risk of hypoglycemia once a new insulin dose starts. Caregivers who work shifts may not be able to learn tube feeding or ostomy care before discharge, and virtual follow-up assumes a device, data, privacy and the skill to use them.

Starting at admission, the nurse asks every patient about these conditions rather than guessing who needs to be asked; asking everyone in the same respectful way avoids stereotyping and normalizes the questions (Table 2.1). With the patient's consent, answers go to the team so that social work, pharmacy and discharge planners can act: checking public drug programs, arranging transport or choosing a dressing the patient can manage. Chapter 1 covers discharge planning, medication reconciliation, health literacy and language access (section 1.7) and alternate level of care and medical travel (section 1.2); this chapter adds the equity questions that make those plans work.

Table 2.1 Determinants of health and questions the nurse can ask on admission and before discharge (Original table; determinants from PHAC, 2022, 2026a)

Determinant	Why it matters in medical-surgical care	Questions the nurse can ask
Income and drug coverage	New prescriptions, dressings and devices may cost more than the patient can pay, leading to skipped doses or unfilled prescriptions.	"Some people find it hard to pay for medications. Is cost a worry for you?" "Do you have a drug plan through work, the province or another program?"
Food security	Healing, blood glucose control and medications taken with food all depend on regular, adequate meals.	"In the past year, have you worried about food running out before there was money to buy more?" "Will you be able to get the foods we talked about?"
Housing	A safe, stable place to recover affects wound care, mobility, rest and infection risk.	"Where will you stay after you leave hospital?" "Are there stairs, and can you get to a bathroom and a bed?" "Is your housing safe and secure for you right now?"

Determinant	Why it matters in medical-surgical care	Questions the nurse can ask
Employment and working conditions	Lost wages, unsafe or physical work and lack of paid sick leave can push patients to return to work too soon.	"What kind of work do you do?" "Will taking time off affect your income or your job?"
Social support and caregiving	Recovery often depends on help at home, and patients may themselves be caregivers for others.	"Who can help you at home in the first few weeks?" "Is anyone counting on you for care, such as a child, partner or parent?"
Transportation and distance	Follow-up visits, laboratory tests and pharmacy trips require a way to get there, especially in rural and remote areas.	"How will you get to your follow-up appointments?" "How far is the nearest pharmacy or clinic?"
Digital access	Virtual visits, patient portals and remote monitoring need a device, data, privacy and the skills to use them.	"Do you have a phone or computer you can use for a video visit?" "Would a phone call or in-person visit work better for you?"
Literacy and language	Understanding instructions and asking questions depend on clear communication in the patient's preferred language (see Chapter 1, section 1.7).	"What language do you prefer for health information?" "How do you like to learn new things: reading, watching or doing?"
Safety, discrimination and past care experiences	Violence at home, or past experiences of discrimination in health care, affect trust, disclosure and willingness to return for care.	"Is there anything about your past experiences with health care that would help us care for you?" "Do you feel safe where you live?"

2.2 Cultural Safety, Humility and Trauma- and Violence-Informed Care

How the nurse behaves in each encounter shapes whether a patient feels able to speak up, trust the plan and come back.

Where Cultural Safety Came From

Cultural safety emerged in Aotearoa New Zealand in the late 1980s, when Māori nursing students and teachers saw that nursing education had to confront racism and the unequal health outcomes Māori faced (Nursing Council of New Zealand [NCNZ], n.d.). The Māori nurse and educator Irihapeti Ramsden led the work. The Nursing Council resolved in 1991 to bring cultural safety into nursing curricula, and from 1992 nursing and midwifery programs had to include it (NCNZ, 2013). Ramsden chose "safety" deliberately to give power to the person receiving care, who judges whether a service is safe to use; cultural safety is about the nurse, not the patient's culture (Ramsden, 2002).

In Canada, the Aboriginal Nurses Association of Canada (now the Canadian Indigenous Nurses Association) published a 2009 framework for cultural competence and cultural safety in nursing education, guided by a steering committee that included the Canadian Association of Schools of Nursing (CASN) and the Canadian Nurses Association (CNA); it asks nurses to accept that the people they care for decide whether care is culturally safe (Hart-Wasekeesikaw, 2009). In July 2015, the chief executive officers of all British Columbia health authorities signed a commitment to cultural safety and humility (First Nations Health Authority [FNHA], n.d.-b).

Cultural Safety and Cultural Humility

The FNHA describes cultural safety as an outcome of respectful engagement that works to correct the power imbalances in health care, so that patients receive care free of racism and discrimination and feel safe. **Cultural humility** is the process that leads there: ongoing reflection on personal and systemic biases, with the provider as a learner about the patient's experience (FNHA, n.d.-a). Humility builds the trust and respect that make safety possible (FNHA, n.d.-b).

Power is central to both. A patient in a gown, in pain, with staff controlling information, medications and discharge, has little power; humility asks the nurse to notice and reduce that imbalance. Tervalon and Murray-García (1998) proposed humility, a lifelong commitment to self-evaluation, correcting power imbalances and partnering with communities, as a better goal than **cultural competence** seen as mastery of a fixed body of knowledge.

Only the patient can say whether care felt culturally safe; good intentions are not enough. Cultural awareness and sensitivity focus on the "other" culture, whereas cultural safety turns the focus to the provider and the system (Chief Public Health Officer Health Professional Forum, 2023) (Table 2.2).

Table 2.2 From cultural awareness to cultural safety (Chief Public Health Officer Health Professional Forum, 2023; FNHA, n.d.-a; Tervalon & Murray-García, 1998; original wording and examples)

Concept	What it means	What it looks like in practice
Cultural awareness	Noticing that cultures differ; an early step that asks nothing of the provider's own self-reflection.	The nurse knows that patients on the unit may hold beliefs about illness that differ from the nurse's own.
Cultural sensitivity	Accepting that differences deserve respect and adjusting one's manners to what the other person finds courteous.	The nurse asks how a patient prefers to be addressed and avoids assumptions about family roles.
Cultural competence	Examining how one's own cultural values shape care, and building knowledge and skills to plan care that fits a person's beliefs; limited if culture is treated as a checklist of traits.	The nurse learns about fasting practices and works with the team to adjust medication times for a patient who is fasting.
Cultural humility	A lifelong process of self-reflection on personal and systemic biases and privilege, approaching each person as the expert on their own life.	After a patient declines a treatment, the nurse asks what matters to the patient and reflects on whether the nurse's own assumptions shaped the conversation.
Cultural safety	An outcome, judged by the patient, in which care is free of racism and discrimination and power imbalances are addressed.	A patient says she felt heard and respected and would come back to this hospital; the team changed its routines when patients said what felt unsafe.

Professional Expectations

In Ontario, the second principle of the CNO Code of Conduct states that nurses provide inclusive, culturally safe care by practising cultural humility. Nurses reflect on how their privileges, biases, values and power affect the nurse–patient relationship, do not act on stereotypes, and seek feedback on their practice. They meet language, cultural and communication needs, use preferred names, titles and pronouns, assess risk for health inequities, build on strengths, act against discrimination, and keep learning about Indigenous health, determinants of health, cultural safety, humility and anti-racism (CNO, 2026).

Two values in the CNA *Code of Ethics for Nurses* (2025) apply directly (see Chapter 1, section 1.5, for all seven). Under "pursuing truth and reconciliation," nurses commit to truth and reconciliation and value bringing First Nations, Inuit and Métis knowledge into their practice. Under "promoting social justice," they consider the social determinants of health and advocate for everyone's freedom from oppression, racism and discrimination (CNA, 2025).

Anti-Racist Practice

Anti-racism is any approach that reduces power differences in ways that benefit racialized groups (Chief Public Health Officer Health Professional Forum, 2023). Being "not racist" is passive; anti-racist practice names racism, including systemic racism, and works to change it. In 2021, CNA and other nursing organizations released a joint declaration that nurses would no longer be silent about anti-Black racism, with principles and actions for which the profession would be accountable (CNA, 2021). RNAO's 2026 best practice guideline, focused on Black nurses and nursing students, recommends interactive, dialogue-based education and formal mentorship, calls for zero-tolerance policies and notes that intersecting factors such as gender identity, class and disability compound racism (RNAO, 2026).

On a medical-surgical unit, anti-racist practice includes:

- questioning assumptions, such as judging reported pain by appearance or labelling a patient "drug-seeking" without assessment;
- never treating race as a biological explanation for a finding, but asking what exposure, condition or barrier explains it;
- speaking up, and reporting through proper channels (see section 2.6), when a colleague's words or actions are discriminatory;
- giving every patient the same thorough assessment, explanation and pain management.

Trauma- and Violence-Informed Care

Many adults in hospital have lived through violence, such as childhood abuse, intimate partner violence, war or the harms of residential schools and other colonial policies; for some it is ongoing. **Trauma- and violence-informed care (TVIC)** recognizes the links between violence, trauma and health, and aims to increase safety, control and resilience for the people receiving care (PHAC, 2025). Adding "violence" to the older term trauma-informed care highlights ongoing violence and systemic or structural violence, such as racism and colonization, not only past events (PHAC, 2025; Wathen & Varcoe, 2021). TVIC does not require disclosure; the nurse does not need to know a patient's history to provide it (PHAC, 2025).

PHAC and EQUIP Health Care name four principles (EQUIP Health Care, n.d.; PHAC, 2025):

- **Understand trauma and violence** and their effects on people's lives and behaviour.
- **Make care settings safe** physically, emotionally and culturally, for patients and staff.
- **Offer choice, collaboration and connection.**
- **Build on strengths and capacity** to support coping and resilience.

On a medical-surgical unit, the principles become everyday actions:

- **Explain before touching.** Say what will happen and why, ask permission and check in throughout, especially for intimate or invasive care such as urinary catheters, nasogastric tubes, perineal care and breast or chest examination.
- **Offer real choices.** Where possible, let the patient choose the timing of a bath, who is present, a position or a pause.
- **Protect privacy.** Knock, close curtains, drape well and limit who is in the room.
- **Recognize possible triggers.** A raised voice, being held still, a dark room, a closed door or someone entering at night may cause fear; agitation may be a trauma response, not "non-compliance."
- **Avoid restraint wherever possible.** Restraint removes control and can be deeply distressing; try alternatives and follow the employer's least-restraint policy (see Chapter 8 for delirium).
- **Respond well to disclosure.** If a patient shares an experience of violence, believe and affirm them, express concern for their safety and offer supports according to employer policy.

2.3 First Nations, Inuit and Métis Health

First Nations, Inuit and Métis patients are on every medical-surgical unit. Their health is shaped by the determinants in section 2.1 and by laws and institutions, hospitals among them, that the Canadian state built to control, assimilate and segregate them. This section covers the three Peoples, colonial history, racism and Indigenous-led care.

Distinctions-Based Language

A **distinctions-based approach** recognizes First Nations, Inuit and Métis as distinct Peoples with their own histories, languages, governments, rights and priorities. Section 35 of the Constitution Act, 1982 affirms existing Aboriginal and treaty rights and defines Aboriginal peoples as including the "Indian, Inuit and Métis peoples" (Constitution Act, 1982, s. 35). "Indian" survives in law; nurses use the terms people use for themselves.

In the 2021 Census, 1,807,250 people (5.0% of the population) identified as Indigenous: 1,048,405 as First Nations, 624,220 as Métis and 70,545 as Inuit (single identities). The average age was 33.6 years, against 41.8 for non-Indigenous people (Statistics Canada, 2022b).

First Nations are many distinct Nations, each with its own language, laws and protocols; the Assembly of First Nations refers to more than 600 First Nations communities (Assembly of First Nations [AFN], n.d.).

Inuit are the Indigenous People of **Inuit Nunangat**, a homeland of land, water and ice spanning 72% of Canada's coastline and about 40% of its land area, in four regions: the Inuvialuit Settlement Region (Northwest Territories), Nunavut, Nunavik (northern Quebec) and Nunatsiavut (northern Labrador) (Inuit Tapiriit Kanatami [ITK], n.d.-a). One person is an Inuk; two or more are Inuit.

In 2021, Inuit Nunangat was home to 69.0% of Inuit, a share that is falling as more live in cities such as Ottawa, Edmonton and Montréal (Statistics Canada, 2022b).

The **Métis** are a distinct Indigenous People who emerged from the 18th-century fur trade, with their own culture, language (Michif) and nationhood. Their Homeland includes the Prairie provinces and parts of Ontario, British Columbia, the Northwest Territories and the northern United States (Métis National Council [MNC], n.d.-a). Being Métis is not the same as mixed ancestry; Métis governments keep citizenship registries, which can differ from self-identified census counts (MNC, n.d.-b).

"Status" is a legal category, not an identity. **Indian status** means being registered under the **Indian Act**, the federal law that has governed First Nations since 1876. There is no federal register for Inuit or Métis (Indigenous Services Canada [ISC], n.d.-a). In 2021, 71.8% of First Nations people had Registered or Treaty Indian status, and 40.6% of them lived on reserve (Statistics Canada, 2022b). A First Nations person without status is no less First Nations. Status matters clinically: the **Non-Insured Health Benefits (NIHB)** program, which pays for medically necessary drugs, dental and vision care, counselling, supplies and medical transportation not covered by other plans, serves registered First Nations people and recognized Inuit (ISC, n.d.-c; Table 2.3).

Table 2.3 First Nations, Inuit and Métis Peoples: key distinctions for nurses (original table; AFN, n.d.; FNHA, 2022; Government of the Northwest Territories, 2021; ISC, n.d.-a, n.d.-c, 2026b, 2026c; ITK, n.d.-a, n.d.-b; Manitoba Métis Federation, 2021; Métis Nation British Columbia, 2024; Métis Nation–Saskatchewan, 2024; MNC, n.d.-a, n.d.-b, n.d.-c; Statistics Canada, 2022b)

Peoples	Who they are	National organization	Federal health programs that may apply	Notes for nurses
First Nations	Many distinct Nations across Canada, each with its own language, laws and protocols; may live on reserve, in rural areas or in cities; may or may not have status under the Indian Act	Assembly of First Nations, which takes direction from First Nations in Assembly through resolutions; many regional and treaty organizations also represent First Nations	Non-Insured Health Benefits (NIHB) for people registered under the Indian Act; Jordan's Principle for First Nations children; nursing stations and health centres in many remote communities; in British Columbia, the First Nations Health Authority runs many programs, including health benefits transferred from NIHB for First Nations residents	Ask which Nation or community the patient belongs to; ask about protocols for ceremony, family and Elders rather than assuming; patients without status are not eligible for NIHB
Inuit	The Indigenous People of Inuit Nunangat (Inuvialuit Settlement Region, Nunavut, Nunavik, Nunatsiavut); many now live in southern cities; Inuktut is widely spoken	Inuit Tapiriit Kanatami, whose voting board members are the four regional Inuit land claims organizations	NIHB for Inuit whom a land claim organization recognizes; Inuit Child First Initiative for Inuit children	Use "Inuk" for one person and "Inuit" for more than one; offer an Inuktut interpreter (see Chapter 1, section 1.7); patients may be far from home for care (see Chapter 1, section 1.2)
Métis	A distinct People with roots in the fur trade, its own culture and the Michif language; Homeland centred on the Prairie provinces	Métis National Council, whose Governing Members are the Otipemisiwak Métis Government (Alberta) and the Métis Nation of Ontario; the Manitoba Métis Federation (2021), Métis Nation–Saskatchewan (2024) and Métis Nation British Columbia (2024) announced their withdrawal from the Council	Not eligible for NIHB; provincial or territorial health coverage applies; the Northwest Territories runs a Métis Health Benefits program	Do not assume a Métis patient has federal benefits; check drug and equipment coverage early in discharge planning; ask about supports offered by the patient's Métis government

Colonial History and Health

The 1876 Indian Act combined earlier laws and gave the federal government sweeping power over First Nations status, reserve lands, governance and education (Canadian Museum of History, n.d.). Canada imposed band councils and banned ceremonies, among them the Potlatch and the Sun Dance (Truth and Reconciliation Commission of Canada [TRC], 2015a).

Residential schools were church-run, government-funded schools that removed Indigenous children from their families to assimilate them. The federal government estimates that at least 150,000 First Nations, Métis and Inuit children attended; the last federally supported schools closed in the late 1990s. The TRC called this cultural genocide and documented poor diets, poorly heated and ventilated buildings, abuse, and deaths no other school system would have tolerated (TRC, 2015a). A scoping review of 61 studies linked attendance with poorer health, chronic and infectious disease, mental distress, substance use and suicidal behaviour in Survivors and their descendants (Wilk et al., 2017). These **intergenerational effects** pass through disrupted families, lost languages and unresolved trauma.

Hospitals were part of this system. From 1936 to 1981, Canada operated 33 **Indian hospitals**. They began as racially segregated facilities to isolate Indigenous people with tuberculosis (TB) and limit its spread to non-Indigenous people, then became segregated general hospitals, with admission based on Indigenous status. Approving a class action settlement in 2025, the Federal Court noted that patients experienced physical and sexual abuse; the representative plaintiffs also said patients were restrained to their beds without medical reason (*Hardy v. Canada (Attorney General)*, 2025). Canada has said it "profoundly regret[s] the abuse and the destruction of culture" in these hospitals (Crown-Indigenous Relations and Northern Affairs Canada [CIRNAC], 2025a).

From the 1940s to the 1960s, Inuit were screened for TB without consent and sent south for months or years in sanatoria. Children were separated from parents, families often were not told where relatives were, and some who died were buried in the South, not always in marked graves. Canada apologized in 2019 and, with Inuit organizations, created the Nanilavut ("let's find them") Initiative to help families find information about relatives (Prime Minister of Canada, 2019).

In the **Sixties Scoop**, between the 1960s and the 1980s, child welfare authorities removed Indigenous children from their homes and placed many in non-Indigenous foster and adoptive homes; in 2017, Canada reached an agreement in principle to settle claims that it failed to protect their Indigenous identity (Indigenous and Northern Affairs Canada, 2017). Communities were also moved: in the 1950s, Inuit families from Inukjuak and Pond Inlet were relocated more than 1,000 km to the High Arctic without adequate shelter and supplies, for which Canada apologized in 2010 (CIRNAC, 2010).

These policies are within living memory: an older patient may have attended a residential school, been treated in an Indian hospital or sent south for TB, or have a parent who never came home; for that patient, hospital can mean separation, restraint and not returning. Fear, reluctance to stay overnight or distrust of consent forms are reasonable responses, not "non-compliance." The nurse explains each step, keeps family close and respects the patient's decisions (see section 2.2).

Indigenous-Specific Racism in Health Care

Indigenous-specific racism is the particular stereotyping, bias and prejudice directed at Indigenous Peoples, rooted in settler colonialism, that keeps power imbalances and unequal outcomes in place (Turpel-Lafond, 2020). It works through individual behaviour and seemingly neutral routines.

In 2020, British Columbia (BC) appointed a reviewer after allegations that emergency staff were guessing Indigenous patients' blood alcohol levels as a "game." The review, *In Plain Sight*, heard from almost 9,000 people; it found no organized game but widespread Indigenous-specific racism and discrimination across BC health care. Only 16% of Indigenous survey respondents reported no discrimination on eight measures, and 35% of responding health workers had personally witnessed discrimination against Indigenous patients or families. Stereotypes cast Indigenous patients as drinkers, drug-seeking, less worthy of care or "frequent flyers." The review linked racism to avoided care, harm and death, and made 24 recommendations (Government of British Columbia, 2020; Turpel-Lafond, 2020).

In September 2008, Brian Sinclair, a 45-year-old Indigenous man and double amputee who used a wheelchair, was sent to the Health Sciences Centre emergency department in Winnipeg about a blocked urinary catheter. After speaking to a triage aide, he waited 34 hours without assessment or treatment and died in the waiting room of peritonitis from a bladder infection. The inquest found the death avoidable, found no evidence that he was intoxicated, and noted that staff wrongly assumed he was homeless; it made 63 recommendations (Manitoba Ombudsman, 2019; Provincial Court of Manitoba, 2014). A *CMAJ* news report noted that some staff had assumed he was drunk or homeless, and Indigenous health conference speakers objected that the inquest would address patient flow, not profiling and stereotyping (Vogel, 2015).

In September 2020, Joyce Echaquan, a 37-year-old Atikamekw woman, died at the hospital in Joliette, Quebec, after livestreaming a video in which staff made degrading remarks to her. The coroner found that she was quickly labelled as dependent on narcotics without any explained clinical basis, and did not receive the close monitoring ordered while she was restrained. The coroner concluded that racism and prejudice contributed to her death, that it could have been avoided, and that the Quebec government should recognize systemic racism in its institutions (Kamel, 2021).

CLINICAL SAFETY

Racism Is a Patient Safety Issue

Racism causes harm through ordinary clinical shortcuts. When a team assumes that an Indigenous patient is intoxicated, drug-seeking or "just waiting for a ride," it stops looking for other causes. Hypoglycemia, stroke, sepsis, head injury and hypoxia can all look like intoxication. Brian Sinclair's death, described earlier in this section, shows where these shortcuts lead.

Every nurse:

- **Assesses fully:** vital signs, level of consciousness, blood glucose and the presenting complaint, for every patient, every time.
- **Documents objectively:** records what was seen, heard and measured ("speech slurred; capillary glucose 2.4 mmol/L"), not labels ("drunk," "drug-seeking").
- **Escalates:** reports abnormal or worsening findings at once and uses rapid response criteria when they are met (see Chapter 6).
- **Speaks up:** challenges stereotyping comments, supports the patient, and acts on discrimination, including reporting it through the employer's process, as the CNO Code of Conduct requires (see sections 2.2 and 2.6).

Health Outcomes in Context

Health gaps are real, and they result from policy, not individual choices or biology.

- **Life expectancy:** Among people living in private households, life expectancy at age 1 in 2011 was 8.9 years shorter for First Nations men and 9.6 years shorter for First Nations women than for non-Indigenous men and women; the gaps were 4.5 and 5.0 years for Métis and 11.4 and 11.2 years for Inuit. The authors cite colonization, racism, intergenerational trauma and other determinants (Tjepkema et al., 2019). Estimates for 2016 to 2021, released since, show trends that varied by region and group (Statistics Canada, 2025).
- **Tuberculosis:** In 2024, TB incidence was 186.9 per 100,000 among Inuit and 0.4 per 100,000 among non-Indigenous people born in Canada (PHAC, 2026b). TB spreads in crowded homes; in 2021, 52.9% of Inuit in Inuit Nunangat lived in crowded housing, compared with 9.4% of non-Indigenous people (Statistics Canada, 2022a). The Inuit Tuberculosis Elimination Framework names inadequate housing, food insecurity, poverty, stigma and the legacy of past TB policy as drivers, and sets an Inuit-led goal of eliminating TB in Inuit Nunangat by 2030 (ITK, 2018b, 2026).
- **Diabetes:** In the First Nations Regional Health Survey (2015–2016), age-standardized diabetes prevalence among First Nations adults on reserve and in northern communities was 19.2% (First Nations Information Governance Centre [FNIGC], 2018). Diabetes Canada's guideline, citing the World Health Organization, ranks colonization first among the social determinants of Indigenous health, acting through forced relocation, residential schools and discriminatory child welfare laws, with poverty and accumulated stress adding to the burden (Crowshoe et al., 2018; see Chapter 22). The survey itself is a strength: a national health survey that First Nations themselves govern and carry out (FNIGC, 2018).

Strengths and Indigenous-Led Care

Culture, language and land protect health. First Nations adults in land-based activities report greater physical or spiritual balance, and daily language users greater spiritual balance; culture and language are sources of healing and resilience (National Collaborating Centre for Aboriginal Health, 2016). Many Inuit continue to speak Inuktut and harvest country foods (ITK, n.d.-a).

In 2013, the FNHA, the first province-wide health authority of its kind, took over federal First Nations health programs in BC; its services include traditional healing (Government of British Columbia, n.d.). In Ontario, Indigenous Primary Health Care Organizations (formerly Aboriginal Health Access Centres) are Indigenous-governed, community-led teams that blend traditional healing with clinical care (Ontario Ministry of Health & Ontario Health, 2026).

London Health Sciences Centre's policy affirms Indigenous patients' right to ceremony, citing TRC Call to Action 22, and offers a liquid smudge to patients on oxygen (London Health Sciences Centre, 2025); Quinte Health designates smudging spaces and states that no one should be pressured to smudge (Quinte Health, 2022). **Indigenous patient navigators** support patients and families; at Hamilton's Juravinski Cancer Centre, the navigator joins patients at visits, helps arrange interpretation and transport, and links patients to traditional, spiritual and cultural services (Hamilton Health Sciences, n.d.).

At the bedside, the nurse:

- **Asks, does not assume:** asks how the patient identifies, their Nation or community, their preferred language, and whether they would like ceremony, traditional medicines, an Elder or a healer; not everyone does.

Figure 2.1 Braided sweetgrass (Hierochloe odorata), one of the sacred medicines used in First Nations, Inuit and Métis smudging and healing ceremonies. (credit: “Braided Sweet Grass” by Jamfam1000/Wikimedia Commons, CC BY-SA 4.0)

Figure 2.2 The health centre in Cambridge Bay, Nunavut. When a patient from a northern or remote community is discharged, the nurse connects with the community's health centre so that care continues at home. (credit: “38 Health centre” by CambridgeBayWeather/Wikimedia Commons, CC BY-SA 4.0)

- **Includes family:** asks who should be involved in decisions; family may include extended kin and community (see Chapter 1, section 1.5).
- **Respects protocols:** handles medicine bundles, eagle feathers and other sacred items only with permission, and follows the patient's or Elder's direction (Figure 2.1).
- **Uses supports:** involves the Indigenous patient navigator, spiritual care and the ceremony policy, including fire and oxygen safety.
- **Plans transitions with community:** connects with the patient's health centre, nursing station or Indigenous primary care team before discharge (Figure 2.2).

CANADIAN CONTEXT

Joyce's Principle

After Joyce Echaquan's death, the Council of the Atikamekw of Manawan and the Atikamekw Nation Council published a brief in November 2020. **Joyce's Principle** aims to guarantee every Indigenous person equitable access, free of discrimination, to all health and social services, and the right to the highest possible level of physical, mental, emotional and spiritual health. It also calls for Indigenous traditional and living knowledge to be recognized and respected in every aspect of health (Council of the Atikamekw of Manawan & Atikamekw Nation Council, 2020).

The brief asks governments to recognize the systemic racism Indigenous people face in health and social services. It asks health organizations to adopt the principle, ensure cultural safety, train staff in programs developed with Indigenous people and actively oppose racism. Professional regulators and schools are asked to build the principle into training and continuing education. The principle is inspired by Article 24 of the United Nations Declaration on the Rights of Indigenous Peoples (see section 2.4).

> For the nurse, Joyce's Principle means treating every Indigenous patient's account of symptoms as credible, involving family and traditional knowledge when the patient wishes, and refusing to stay silent when a colleague demeans a patient.

2.4 Rights, Policy and Data

Several national documents set out what Indigenous Peoples are owed in health care and what health professionals must do. Nurses meet them in hospital policies, accreditation standards and their own professional codes (see section 2.2).

The TRC's Health Calls to Action

In 2015, the TRC issued 94 **Calls to Action**, specific steps to redress the legacy of residential schools and advance reconciliation. Calls 18 to 24 address health (TRC, 2015b). Table 2.4 summarizes them in plain language, with examples of what a nurse can do. Call 24 speaks directly to nursing: every nursing and medical student should take a course on Indigenous health that covers the history and legacy of residential schools, the United Nations Declaration on the Rights of Indigenous Peoples, Treaties and Aboriginal rights, and Indigenous teachings and practices, with skills-based training in anti-racism, human rights, conflict resolution and intercultural competency. CASN and the Canadian Indigenous Nurses Association have set out strategies for schools to respond to Calls 23 and 24, including community partnerships, resident Elders and cultural safety training (CASN, 2020).

Table 2.4 The TRC's health Calls to Action and what nurses can do (original summary and examples; TRC, 2015b)

Call to Action	What it asks (summary)	What a nurse can do
18	Federal, provincial, territorial and Indigenous governments acknowledge that the current state of Indigenous health is a direct result of past Canadian government policies, including residential schools, and recognize Indigenous health rights under international law, the Constitution and Treaties	Learn the colonial history behind health gaps; explain gaps by their causes, not by individual blame
19	The federal government sets measurable goals to close health gaps and reports progress every year on indicators such as life expectancy, chronic disease, mental health and access to services	Read gap data critically (see the Going Deeper box); support community-led monitoring
20	The federal government recognizes and addresses the distinct health needs of Métis, Inuit and off-reserve Indigenous people, to address jurisdictional disputes	Check coverage early for Métis, non-status and urban patients; advocate when jurisdiction delays care
21	The federal government gives lasting funding to Indigenous healing centres that address residential school harms, with priority for Nunavut and the Northwest Territories	Know local Indigenous healing and wellness services and refer patients who want them
22	Those who can effect change in the health system recognize the value of Indigenous healing practices and use them with Indigenous healers and Elders when patients ask	Offer ceremony, traditional medicines and Elder visits; follow the facility policy; involve the navigator
23	Governments increase the number of Indigenous health professionals, help them stay in Indigenous communities and give every health professional cultural competency training	Mentor and support Indigenous students and colleagues; complete cultural safety training
24	Medical and nursing schools require every student to take a course on Indigenous health, history, rights and teachings, with anti-racism and related skills training	Take courses seriously; bring what is learned into practice; speak up about racism

UNDRIP and the Federal Act

The **United Nations Declaration on the Rights of Indigenous Peoples (UNDRIP)**, adopted by the United Nations General Assembly in 2007, sets minimum standards for the rights of Indigenous Peoples. Article 24 affirms Indigenous Peoples' right to their traditional medicines and health practices, Indigenous individuals' right to all social and health services without discrimination, and their equal right to "the highest attainable standard of physical and mental health." Under Article 23, Indigenous Peoples have the

right to take an active part in shaping the health programs that affect them and, where possible, to run those programs through their own institutions (United Nations, 2007).

Canada's United Nations Declaration on the Rights of Indigenous Peoples Act received Royal Assent on June 21, 2021. It affirms the Declaration as an international human rights instrument that applies in Canadian law. It requires the federal government, working "in consultation and cooperation with Indigenous peoples," to make federal laws consistent with the Declaration, to prepare an action plan within two years, and to report on progress every year (United Nations Declaration on the Rights of Indigenous Peoples Act, 2021). The action plan, released on June 21, 2023, contains 181 measures (Department of Justice Canada, 2023).

Missing and Murdered Indigenous Women and Girls

The National Inquiry into Missing and Murdered Indigenous Women and Girls released its final report, *Reclaiming Power and Place*, on June 3, 2019, with 231 Calls for Justice (CIRNAC, 2025b). Calls for Justice 7.1 to 7.9 are addressed to health and wellness service providers. Among other things, they call for treating Indigenous Peoples as the experts on their own healing; supporting healing from intergenerational, multigenerational and complex trauma; backing Indigenous-led prevention; revitalizing Indigenous health, child-care and Elder-care practices; paying for healing programs and for services offered in Indigenous languages; ongoing training for health workers on Indigenous realities; and helping more Indigenous people enter health and wellness careers (CIRNAC, 2025b; National Inquiry into Missing and Murdered Indigenous Women and Girls, 2019). Nurses also apply these calls when they respond safely to disclosures of violence (see section 2.2).

Jordan's Principle and the Inuit Child First Initiative

Jordan's Principle aims to ensure that First Nations children can get essential government services without gaps or delays because of their identity or where they live; in February 2026, Canada committed funding to renew it to March 31, 2027 (ISC, 2026c). The **Inuit Child First Initiative** helps Inuit children get the health, social and educational services and supports they need; its funding was also renewed to March 31, 2027, while Canada and Inuit partners develop a long-term, Inuit-led approach (ISC, 2026b). Adult patients may be parents or caregivers of children with complex needs, so the nurse may mention these programs when a parent's admission threatens a child's care.

Data Sovereignty

Data sovereignty is the right of a People to govern data about themselves. **The First Nations Principles of OCAP®** state that First Nations have Ownership of, Control over, Access to and Possession of data about their communities. Ownership means a community owns its information collectively. Control means First Nations have the right to control research and information management that affects them. Access means First Nations can reach data about themselves wherever they are held and decide who else may. Possession means the physical stewardship of the data (FNIGC, n.d.). OCAP® applies specifically to First Nations. Inuit set out their own approach in the National Inuit Strategy on Research, one of whose priorities is to "ensure Inuit access, ownership, and control over data and information" (ITK, 2018a). The Métis National Council's 2025 Métis Nation Data Strategy affirms Métis governments' sovereignty over Métis data (MNC, 2025).

For nurses, data sovereignty matters when they read and cite First Nations, Inuit or Métis statistics, join quality improvement projects or research that includes Indigenous patients, or collect identity data on admission. The nurse asks whether the community approved the use of its data, uses data from Indigenous-governed sources where they exist, explains to patients why identity questions are asked and how answers are protected, and never shares community-level data without the agreement of the Nation or organization that governs it. OCAP® is a registered trademark of the First Nations Information Governance Centre (FNIGC).

GOING DEEPER

Reading Indigenous Health Data Critically

Required for registered nurse (RN) students; optional for practical nurse (PN) students.

RNs use statistics in care plans, unit education and quality projects, so they need to read Indigenous health data with care.

- **Distinctions:** an "Indigenous" average can hide large differences. In 2024, TB incidence per 100,000 was 186.9 among Inuit, 13.5 among First Nations and 1.3 among Métis (PHAC, 2026b). For Inuit living in Inuit Nunangat, ITK reports 246.4 per 100,000 (ITK, 2026). Geography and source change the number.

- **Who is counted:** the regional health survey covers First Nations people on reserve or in northern communities (FNIGC, 2018). Life expectancy studies cover only people in private households, leaving out people in collective dwellings such as institutions and shelters (Statistics Canada, 2025; Tjepkema et al., 2019). In 2021, 63 reserves and settlements were not fully counted in the census (Statistics Canada, n.d.).
- **Denominators:** census identity is self-reported and can change between censuses, so trends may reflect who identifies, not only who becomes ill (Statistics Canada, 2025).
- **Framing:** deficit-only lists invite blame. Pair each gap with its structural cause and with community strengths.
- **Governance:** check whether the data were used with community approval and under OCAP® or other Indigenous data principles.

Before using a statistic, the RN asks: Which People and place does it describe? Who was left out? What does it compare against? What causes does it name? Who owns these data, and did they agree to this use?

2.5 Caring for Other Equity-Deserving Adults

Sections 2.3 and 2.4 address First Nations, Inuit and Métis Peoples separately because of their distinct history and rights. Many other adults meet barriers to safe care that come from systems and from how people are treated, not from who they are. The groups overlap (see intersectionality, section 2.1), and Table 2.5 summarizes barriers and nursing actions.

Racialized Patients and Anti-Black Racism

Race is a social category, not a biological one: societies sort people by features such as skin colour, name, accent or origin and treat the groups unequally, a process called **racialization**. The Ontario Human Rights Commission uses **racialized** for a person treated this way and calls terms such as "visible minority" outdated (Ontario Human Rights Commission [OHRC], n.d.-b). A gap between racial groups points to exposure to racism, not to biology (RNAO, 2026).

Anti-Black racism is the discrimination, stereotyping and prejudice that people of African descent face. It is built into Canadian institutions and is often so normal that it goes unseen (RNAO, 2026). Section 2.2 summarizes RNAO's 2026 guideline *Addressing Anti-Black Racism in Nursing*.

Inequities also show up in outcomes. A Statistics Canada study linked 2016 census responses to hospital records for people aged 10 to 74, excluding Quebec residents and First Nations, Inuit and Métis respondents. In every year from 2016–2017 to 2021–2022, after adjusting for age, sex, income, education and immigrant status, the Black population had higher odds than the non-racialized population of hospitalization for conditions that good primary care can usually prevent; the authors suggest barriers to quality primary care as a reason (Brobbey et al., 2025).

On the unit, in addition to the anti-racist practices in section 2.2, the nurse:

- assesses skin by touch as well as sight, because redness and cyanosis are harder to see on darker skin (see Chapter 35);
- questions tools built on racial categories (see the Going Deeper box in section 2.6);
- documents behaviour objectively, avoiding labels such as "aggressive" or "non-compliant" that follow the patient (see the Clinical Safety box in section 2.3).

2SLGBTQI+ Patients

2SLGBTQI+ stands for Two-Spirit, lesbian, gay, bisexual, transgender, queer and intersex, with the plus sign for people who use other terms. "2S" is placed first in recognition that **Two-Spirit** people, an Indigenous identity, formed the first of these communities (Women and Gender Equality Canada [WAGE], 2024). **Gender identity** is a person's inner sense of being a man, a woman, both or neither. A **transgender** person's gender identity differs from the sex assigned at birth; a **cisgender** person's matches it (WAGE, 2024). In the 2021 Census, about 1 in 300 people aged 15 or older were transgender or non-binary (Statistics Canada, 2022c). Since 2012, Ontario's Human Rights Code has protected gender identity and gender expression (OHRC, n.d.-a).

Inclusive care starts at intake:

- **Chosen name and pronouns.** A **chosen name** is the name a person uses, which may differ from their legal name. As CNO's Code of Conduct expects, the nurse asks every patient for their name and pronouns, uses them and records them where possible (CNO, 2026); a mistake calls for a brief apology.
- **Sex assigned at birth only when it matters.** Custodians may collect only the personal health information that is reasonably needed (Information and Privacy Commissioner of Ontario, n.d.). The nurse asks about sex assigned at birth, anatomy or surgeries only when the answer changes care, and explains why.
- **Privacy.** Sexual orientation and gender history are personal health information, shared only with team members who need them for care.
- **Partners and chosen family.** The patient names their support people, such as partners, friends or **chosen family** (people a person treats as family), and a capable patient decides what they are told. The substitute decision-maker ranking includes a spouse or partner of any gender (see Chapter 1, section 1.5).

In a 2026 federal research summary on 2SLGBTQI+ adults aged 55 and older, about 80% of those surveyed had experienced discrimination; many feared mistreatment in care, separation from partners and having to hide their identity again (Employment and Social Development Canada, 2026). Rainbow Health Ontario offers provider training and clinical resources (Rainbow Health Ontario, n.d.); Chapter 29 covers gender-affirming surgery aftercare.

People with Disabilities

Under the Accessible Canada Act (2019), a **disability** is any impairment, such as a physical, mental, sensory or communication impairment, that, when it meets a barrier, prevents a person from taking part fully and equally in society. Barriers can be physical, attitudinal, informational or built into policies. This book uses person-first language, but many Deaf and autistic people prefer identity-first terms; the nurse follows the patient's preference.

- The Act aims for a barrier-free Canada in federal jurisdiction by 2040 and recognizes American, Quebec and Indigenous sign languages as the primary languages of deaf people (Accessible Canada Act, 2019).
- Ontario's Accessibility for Ontarians with Disabilities Act, 2005 (AODA) sets standards for organizations such as hospitals; its 2023 review called missing the 2025 goal of an accessible Ontario a near certainty and found poorer experiences for people with disabilities in health care (Accessibility for Ontarians with Disabilities Act, 2005; Donovan, 2023).
- Ontario's Human Rights Code adds a **duty to accommodate**: health care and other services are adjusted to the person, with dignity, short of undue hardship (OHRC, 2016).

Accommodation on the unit includes:

- **Communication supports:** a sign language interpreter booked early (see Chapter 1, section 1.7), facing a patient who lipreads, written or pictorial materials and extra time.
- **Service animals:** welcomed, following hospital policy, when easily identified (such as by a vest) or confirmed in a note from a regulated health professional; where another law bars animals from an area, staff offer another way to meet the need (Government of Ontario, 2026c).
- **Equipment:** mobility aids, hearing aids and communication devices kept within reach and never moved without asking, and an adapted call bell, such as a soft-touch pad, in place before the nurse leaves.

In **supported decision-making**, trusted people help a person understand choices and express a decision that stays the person's own; in **substitute decision-making**, someone else decides for a person who is incapable (see Chapter 1, section 1.5). Ontario law does not formally recognize supported decision-making (Law Commission of Ontario, 2017), but nurses can apply it: speak directly to the patient, use the patient's own ways of communicating, slow down and involve familiar supporters without letting them take over (Sullivan et al., 2018).

Diagnostic overshadowing is blaming new symptoms on a known diagnosis, such as a disability or mental illness, so that the real cause is missed (Hallyburton, 2022; Sullivan et al., 2018). New agitation in a man with an intellectual disability may be pain from urinary retention, so the nurse compares findings with his baseline, asks supporters what has changed and looks for physical causes first.

Newcomers and Refugees

Coverage for newcomers depends on immigration status and province. Ontario has no waiting period: people eligible for the Ontario Health Insurance Plan (OHIP) are covered right away (Government of Ontario, 2025).

The **Interim Federal Health Program (IFHP)** gives refugees, refugee claimants and certain others limited, temporary coverage until they qualify for provincial or territorial insurance, including hospital and physician care, tests, most drugs on the provincial formulary and some supplemental services (Immigration, Refugees and Citizenship Canada [IRCC], 2026b). Since May 1, 2026, beneficiaries pay $4 per prescription and 30% of the cost of other eligible supplemental services, such as dental care; basic hospital and physician care remains fully covered (IRCC, 2026a).

Many refugees have survived violence or dangerous journeys; most recover once they are safe, and pressing for disclosure may do more harm than good (Pottie et al., 2011). The nurse uses the trauma- and violence-informed approach in section 2.2 and a professional interpreter (see Chapter 1, section 1.7).

People Experiencing Homelessness or Living in Poverty

The *Canadian Definition of Homelessness* describes **homelessness** as lacking stable, permanent and suitable housing, with no immediate prospect, means or ability to obtain it. It arises from systemic barriers, too little affordable housing, personal challenges, and racism and discrimination, and it includes people in shelters or couch surfing as well as those sleeping outside (Gaetz et al., 2012). Section 2.1 gives the latest national count.

Without housing, conditions such as cellulitis, foot wounds and frostbite are harder to prevent and treat. In a Toronto study, hospital and shelter workers said discharges to shelters were undermined by poor follow-up care, hard-to-get shelter beds and little communication between the two (Jenkinson et al., 2022). Discharge planning starts on admission (see Chapter 1, section 1.7) and covers:

- **Shelter by night and day:** many shelters close in the daytime, so the social worker contacts the shelter, a respite program or a housing worker early; the team avoids late-evening discharges.
- **A plan that fits:** leg elevation and dressing changes are hard without a bed or bathroom, so the team simplifies care and arranges community follow-up.
- **Belongings:** listed and stored on admission, because losing identification or a phone cuts people off from care.
- **Medications and food:** coverage checked early (see the Patient Education box), a simple regimen in blister packs and a plan for meals.
- **Contact:** a phone number, shelter or drop-in centre where the team can reach the patient.

Figure 2.3 A mobile community health and wellness clinic van, one model used to bring primary care, wound care and harm reduction directly to underserved neighbourhoods. (credit: “Mobile health van - 2021-08-27 - Sarah Stierch” by Sarah Stierch [Missvain]/Wikimedia Commons, CC BY 4.0)

Partners include shelter and outreach workers, community health centres and peer workers; harm reduction is part of care for patients who use substances (see Chapter 11) (Figure 2.3).

Weight-Inclusive Care

Canada's adult obesity guideline describes obesity as a chronic disease in which excess body fat impairs health, and warns that weight bias in health care can worsen the care that people living with obesity receive. **Weight stigma** is the devaluing of people because of their body size. Providers should examine their own attitudes, avoid judgmental words and practices, not assume that a complaint is caused by weight, and ask permission before discussing weight or taking measurements (Wharton et al., 2020): "Is it all

right with you if we talk about your weight today?" When weight is needed for safe care, such as a weight-based dose, the nurse explains why and weighs the patient in private.

Equipment matters for safety and dignity. A cuff that is too small gives falsely high blood pressure readings: in one US trial, a regular cuff on an arm that needed an extra-large cuff raised systolic readings by about 20 mm Hg on average (Ishigami et al., 2023). The nurse uses a correctly sized cuff and arranges right-sized beds, chairs, commodes, gowns and lifts before the patient arrives.

Table 2.5 Adapting medical-surgical care for equity-deserving adults (Original table)

Group	Common barriers	What the nurse can do
Racialized patients	Racism in interactions and systems; symptoms dismissed or undertreated; assessment tools validated mainly on lighter skin; mistrust after past experiences	Assess pain and other symptoms in the same way for every patient; assess skin by touch as well as sight; question race-based assumptions and tools; document behaviour objectively; act on discrimination
2SLGBTQI+ patients	Wrong name or pronouns; intrusive questions; disclosure of identity without consent; partners or chosen family excluded	Ask every patient for name and pronouns and use them; ask about sex assigned at birth only when it changes care; share identity information only as needed; involve the people the patient names
People with disabilities	Inaccessible equipment, call bells and information; communication needs unmet; assumptions about capacity; diagnostic overshadowing	Arrange interpreters and communication supports early; keep mobility and communication devices within reach; welcome service animals per policy; presume capacity and support the patient's decisions; look for physical causes of change
Newcomers and refugees	Limited or temporary health coverage; co-payments; language barriers; past trauma; unfamiliar systems	Use professional interpreters and teach-back; explain each step and offer choices; refer to social work about IFHP or OHIP; avoid pressing for trauma histories
People experiencing homelessness or poverty	No safe place to recover; lost belongings and identification; cost of medications and supplies; poor access to food; no reliable phone	Start discharge planning on admission; store belongings safely; simplify the regimen and check coverage; link with shelters, outreach and community health centres; offer harm reduction
People living with obesity	Weight stigma; symptoms blamed on weight; equipment that does not fit; inaccurate measurements	Ask permission before discussing weight; weigh in private; use a correctly sized cuff; prepare right-sized beds, gowns, chairs and lifts in advance

PATIENT EDUCATION

Paying for Medications After Discharge

A prescription that is never filled cannot work. Before discharge, the nurse asks, "Is cost a worry for you?" and shares this plain-language guide for patients and families in Ontario.

- **Ontario Drug Benefit (ODB):** You are enrolled automatically on the first day of the month after you turn 65. You may also be covered at a younger age if you get Ontario Works or the Ontario Disability Support Program, live in a long-term care home, receive professional services through home and community care, are 24 or younger with no private plan, or are enrolled in the Trillium Drug Program (Government of Ontario, 2026a).
- **Trillium Drug Program:** If you do not qualify for the ODB, no plan pays all of your drug costs, and your prescriptions cost about 4% or more of your household's after-tax income, you can apply. You pay a yearly deductible based on income, then up to $2 for each prescription filled (Government of Ontario, 2026b).
- **Non-Insured Health Benefits:** Registered First Nations people and recognized Inuit are covered for many medications not covered by other plans (ISC, n.d.-b).
- **Interim Federal Health Program:** Refugees and refugee claimants who are covered pay $4 per prescription (IRCC, 2026a).
- **National pharmacare:** Under the federal Pharmacare Act (2024), Canada pays for no-cost coverage of some contraception and diabetes medications, but only in provinces and territories that sign an agreement. As of October 24, 2026, Health Canada listed agreements with four (British Columbia, Manitoba, Prince Edward Island and Yukon); Ontario was not one of them (Health Canada, 2024, 2026).
- **Ask for help:** Your pharmacist can check your coverage and suggest lower-cost options. The hospital social worker can help you apply for programs.

2.6 Equity in Everyday Medical-Surgical Practice

Equity is not a separate task added to a busy shift. It shows up in how the nurse assesses, documents, plans discharge and speaks up. This section brings the chapter's ideas to the bedside.

Implicit Bias and Diagnostic Overshadowing

Implicit bias is an attitude or stereotype that works outside a person's awareness and shapes judgments without the person intending it. A systematic review found evidence of implicit bias among physicians and nurses in almost all included studies, at levels similar to the general public. In several studies, higher implicit bias was linked to poorer interactions with Black patients or to treatment decisions that favoured White patients (FitzGerald & Hurst, 2017). Having implicit bias does not make a nurse a bad person; acting on it without checking does harm.

Pain care is where bias is easiest to see. A meta-analysis of US emergency department studies published between 1990 and 2018 found that Black patients with acute pain were less often given analgesia than White patients; the result for Hispanic patients leaned the same way but was not statistically significant (Lee et al., 2019). Canadian evidence is consistent. In the Indigenous Peoples' Survey of BC's *In Plain Sight* review (section 2.3), 35% of Indigenous respondents said they always received medication when they needed or asked for it, compared with 58% of non-Indigenous respondents (Turpel-Lafond, 2020). Diagnostic overshadowing (section 2.5) is a related trap: a new symptom is blamed on a known label, such as a disability, a mental illness, substance use or weight.

The nurse can slow down these quick judgments:

- Believe the patient's report of pain, assess it fully and treat it according to the plan (see Chapter 5).
- Ask, "Would I respond the same way if this patient were someone else?"
- Compare findings with the patient's own baseline, not with a stereotype.
- Use structured tools, such as early warning scores, consistently for every patient (see Chapter 6).

Screening for Social Needs

Social needs affect whether a plan of care can work. On admission and again before discharge, the nurse asks about income and drug coverage, food, housing, support, transportation, digital access, language and safety, using the kinds of questions in Table 2.1 (section 2.1). The nurse explains why the questions are asked, accepts "I'd rather not say," documents needs in neutral language and refers to the social worker or community partners. Screening without a plan to respond can feel intrusive, so the nurse knows the referral pathways before asking.

Speaking Up and Reporting Discrimination

CNO's Code of Conduct expects nurses to act to prevent discrimination and to respond when they see discrimination against a patient. Nurses also report errors and unsafe or unethical conduct to the appropriate authority, such as the employer or CNO (CNO, 2026). In practice, the nurse:

- addresses a disrespectful comment directly when it is safe to do so, often privately and calmly ("That comment isn't how we talk about patients here");
- puts the patient's safety and dignity first, which may mean changing an assignment;
- reports through the employer's process, such as a safety report, the manager or a human rights or equity office;
- documents the facts of care objectively in the health record, without opinions about colleagues.

Some situations carry legal reporting duties, such as the mandatory report of sexual abuse of a patient by a regulated health professional (see Chapter 1, section 1.5). Patients have their own routes. In Ontario, a patient or caregiver first raises a concern with the hospital's patient relations office. If the concern is not resolved, Patient Ombudsman, a provincial office, can help resolve complaints about care in public hospitals, home care, long-term care homes and community surgical and diagnostic centres (Patient Ombudsman, n.d.). Concerns about an individual nurse's practice can go to CNO.

GOING DEEPER

Race in Clinical Algorithms

Required for RN students; optional for PN students.

Some clinical formulas and devices carry racial assumptions that can harm patients.

Estimated glomerular filtration rate (eGFR). The 2009 Chronic Kidney Disease Epidemiology Collaboration (CKD-EPI) creatinine equation added a correction that raised eGFR for patients recorded as Black. In practice, that could make kidney disease look milder and delay referral. In 2021, new CKD-EPI equations were developed without race (Inker et al., 2021). The 2024 Kidney Disease: Improving Global Outcomes (KDIGO) guideline advises, in Practice Point 1.2.4.2, that the use of race in calculating eGFR should be avoided (KDIGO CKD Work Group, 2024). Canadian authors have called for **race-free equations** nationally, noting that Black people in Canada are referred later for kidney care (Parekh et al., 2022). Some Canadian laboratories have moved to the 2021 equation; Alberta Precision Laboratories, for example, began reporting it on January 20, 2026 (Alberta Precision Laboratories, 2026). Chapter 27 discusses eGFR in detail.

Pulse oximetry. In two large US cohorts, **occult hypoxemia**, an arterial oxygen saturation (SaO_2) below 88% despite a pulse oximeter reading (SpO_2) of 92% to 96%, occurred nearly three times as often in Black patients as in White patients (Sjoding et al., 2020). Health Canada warns that oximeter readings may be less accurate for people with dark skin (Health Canada, 2022).

What the nurse does:

- Assess the whole patient: respiratory rate, work of breathing, level of consciousness and trend, not the SpO_2 number alone.
- When signs and the reading disagree, report it; an arterial blood gas may be ordered to measure oxygenation directly (Health Canada, 2022).
- Report device problems through the hospital, which must report serious medical device incidents to Health Canada (Health Canada, 2023).

LIFESPAN CONSIDERATIONS

Older Residential School Survivors in Hospital

Many First Nations, Inuit and Métis older adults are Survivors of residential schools (see section 2.3), and many more were raised by Survivors. In the schools, children were separated from their families and from brothers and sisters, their hair was cut, their own clothes were replaced with school clothing, some were given numbers, their languages were suppressed and daily life was strictly controlled (TRC, 2015a). A hospital can echo that experience: uniforms, rules, locked doors, restraints, being told when to eat and sleep, separation from family, and staff who do not speak the patient's language.

Trauma- and violence-informed actions (section 2.2) include asking how the patient wants to be addressed and who they want with them; explaining each step; offering a professional interpreter (see Chapter 1, section 1.7); flexible visiting; avoiding restraint; welcoming Elders, ceremony and traditional foods according to the patient's wishes and hospital policy; and involving the Indigenous patient navigator where there is one.

Supports include the Indian Residential Schools Resolution Health Support Program, which offers cultural, emotional and counselling support to Survivors and their families; the 24-hour National Indian Residential School Crisis Line (1-866-925-4419); and the Hope for Wellness Help Line (1-855-242-3310), which serves all Indigenous people by phone or online chat (ISC, 2026a).

PRACTICE STORY

Hearing What Mr. Peters Wasn't Saying

Names and details are fictional; this is a composite story.

Nurse: Megan Kowalchuk, RN. Years in practice: 9. Setting: surgical unit, regional hospital, northwestern Ontario.

Mr. Peters was 74 and had flown in from a fly-in First Nation in northwestern Ontario for a bowel resection. On the first day after surgery, every time I asked about his pain, he said "two" and looked away. He wasn't using his incentive spirometer, and he refused to walk. His heart rate was 104, his blood pressure 152/90 and his respiratory rate 22, and he held his abdomen whenever he shifted in bed.

His nephew, travelling with him as his escort, stopped me in the hall. "He says 'okay' to be polite," he told me. "He uses English for everyday things. For something this important, he thinks in Oji-Cree." He added that his uncle hadn't wanted to bother the nurses, because the last time he was in a hospital, years ago, he was told to stop complaining.

I called our Indigenous patient navigator and booked an interpreter. With the interpreter beside us, Mr. Peters described pain that felt like a knife when he coughed or moved. I gave the hydromorphone that was ordered as needed and called the surgeon, who

added regular acetaminophen. An hour later he rated his pain as 4, did his breathing exercises and walked to the door with me. His heart rate was 88.

After that, I changed how I assessed him. I asked about his pain through the interpreter, with his nephew there when he wanted him; watched what he could do, not only the number he gave; and told him that reporting pain helps him heal.

The navigator and I also planned his trip home. We confirmed his medical travel and his nephew's escort travel, sent a discharge summary to the nursing station, and checked that the nursing station had the dressing supplies and could remove his staples. We made sure his pain medications could be filled before his flight.

On his last day, he shook my hand and spoke to his nephew, who translated: "You listened."

Reflect: What made the care Mr. Peters received early on unsafe for him, and who should judge whether his care was culturally safe? Within the RN's scope, what could I have done on the first day, before the escort spoke up?

Chapter 2 Summary

2.1 Health Equity and the Determinants of Health

- Equality gives everyone the same; equity gives people what they need for a fair chance at good outcomes.
- Health inequities are systematic, avoidable and unjust differences in health produced by how resources and power are distributed, not by biology or personal choice.
- PHAC describes social determinants (everyday conditions such as income, work, housing and freedom from discrimination) and structural determinants (the systems, laws and policies that shape those conditions); intersectionality explains how social positions combine.
- Canadian data show large inequities: 24.0% of Canadians lived in food-insecure households in 2024, and health-adjusted life expectancy differed by 8.1 years between the lowest and highest neighbourhood income groups in 2023.
- On medical-surgical units, determinants affect medication affordability, food, housing, caregiving, transport and digital access after discharge; the nurse asks every patient about them, from admission onward.

2.2 Cultural Safety, Humility and Trauma- and Violence-Informed Care

- Cultural safety came from Māori nursing students and teachers in Aotearoa New Zealand, led by Irihapeti Ramsden; it is defined by the person receiving care, not by the provider.
- Cultural humility is the ongoing self-reflective process; cultural safety is the outcome; both centre on power.
- The CNO Code of Conduct (principle 2) requires culturally safe, inclusive care through cultural humility, and the CNA Code (2025) includes pursuing truth and reconciliation and promoting social justice.
- Anti-racist practice is active: questioning assumptions, never treating race as biology, speaking up about and reporting discrimination.
- Trauma- and violence-informed care creates safety, choice and control without requiring disclosure, for example by explaining before touching, protecting privacy and avoiding restraint.

2.3 First Nations, Inuit and Métis Health

- First Nations, Inuit and Métis are distinct Peoples; nurses use a distinctions-based approach and the terms people use for themselves. Indian status is a legal category, not an identity, and it affects eligibility for federal health benefits.
- The Indian Act, residential schools, Indian hospitals, TB evacuations of Inuit, the Sixties Scoop and forced relocations harmed health across generations and explain why some patients, especially older adults, fear or distrust hospitals.
- Indigenous-specific racism is well documented in Canadian health care, as *In Plain Sight* (BC) and the deaths of Brian Sinclair and Joyce Echaquan show; assumptions such as intoxication delay diagnosis and cause harm.
- Health gaps, such as shorter life expectancy, high TB incidence among Inuit and high diabetes prevalence in First Nations communities, come from structural causes such as crowded housing, poverty, loss of land and racism, not from individual choices or biology.

- Culture, language, land and Indigenous-led services support health. The nurse asks about ceremony, family and Elders, respects protocols, involves the navigator and never assumes.

2.4 Rights, Policy and Data

- TRC Calls to Action 18 to 24 address health; Call 22 supports Indigenous healing practices when patients ask, and Call 24 asks nursing and medical schools to require a course on Indigenous health for every student.
- UNDRIP Article 24 affirms the right to traditional medicines and to health services without discrimination; the federal UNDRIP Act (2021) requires laws to align with the Declaration, and its 2023 action plan has 181 measures.
- The National Inquiry into Missing and Murdered Indigenous Women and Girls, in Calls for Justice 7.1 to 7.9, asks health providers to treat Indigenous Peoples as the experts on their own healing and to support trauma-informed, Indigenous-led care.
- Jordan's Principle and the Inuit Child First Initiative, both funded to March 31, 2027, support First Nations and Inuit children; adult patients may be their parents or caregivers.
- OCAP®, the National Inuit Strategy on Research and the Métis Nation data strategy affirm that Indigenous Peoples govern their own data; nurses read and use these data critically and with community agreement.

2.5 Caring for Other Equity-Deserving Adults

- Race is a social category, not a biological one; anti-Black racism is built into institutions and shows up in outcomes such as higher odds of avoidable hospitalization for Black people.
- Inclusive care for 2SLGBTQI+ patients means asking every patient's name and pronouns, asking about sex assigned at birth only when it changes care, protecting privacy and involving the support people the patient names.
- Disability arises when an impairment meets a barrier; nurses accommodate communication, mobility and service animal needs, support patients' own decisions and guard against diagnostic overshadowing.
- The Interim Federal Health Program gives temporary coverage to refugees and refugee claimants, with co-payments for prescriptions and supplemental services since May 1, 2026; eligible Ontario residents have OHIP coverage with no waiting period.
- Safe discharge for people experiencing homelessness starts on admission and plans for shelter, belongings, medications, food and follow-up with community partners.
- Weight-inclusive care asks permission before discussing weight and provides correctly sized equipment, including blood pressure cuffs.

2.6 Equity in Everyday Medical-Surgical Practice

- Implicit bias is common among health professionals and can affect assessment and treatment, including pain care; nurses check their judgments and assess every patient the same way.
- Nurses screen for social needs on admission and before discharge, using questions like those in Table 2.1, and have a referral plan before they ask.
- CNO expects nurses to act when they see discrimination; nurses address it, report it through employer processes and know patients' complaint routes, including Patient Ombudsman.
- Race-free eGFR equations and awareness of occult hypoxemia with pulse oximetry show why nurses question tools and assess the whole patient.

Key Terms (58)

2SLGBTQI+: An umbrella term for Two-Spirit, lesbian, gay, bisexual, transgender, queer and intersex people and others who are sexually and gender diverse; "2S" is placed first in recognition that Two-Spirit people formed the first of these communities.

anti-Black racism: The discrimination, stereotyping and prejudice that people of African descent face, built into the policies, practices and institutions of Canadian society and often unseen because it is so normal.

anti-racism: Active practice that names racism, including racism built into systems, and works to reduce the power differences that disadvantage racialized people.

Calls to Action: The 94 specific steps issued by the Truth and Reconciliation Commission of Canada in 2015 to redress the legacy of residential schools and advance reconciliation; Calls 18 to 24 address health.

chosen family: People a person chooses as family, such as close friends or partners, who may provide support in place of or alongside relatives by birth.

chosen name: The name a person uses, which may differ from the name on a health card or other legal record.

cisgender: Describes a person whose gender identity matches the sex they were assigned at birth.

cultural competence: The ability to reflect on one's own cultural values and to build the knowledge and skills to plan care that respects other people's values and beliefs.

cultural humility: A lifelong process of self-reflection on one's own biases, privilege and power, in which the provider approaches each person as a learner.

cultural safety: An outcome, judged by the person receiving care, in which care is respectful, free of racism and discrimination, and attentive to power imbalances in the health system.

data sovereignty: The right of a People to govern the collection, ownership and use of data about themselves.

determinants of health: The conditions and factors, social, economic, physical, biological and structural, that shape the health of individuals and populations.

diagnostic overshadowing: Attributing a new symptom to an existing diagnosis, such as a disability or mental illness, so that the real cause is missed.

disability: An impairment of any kind, such as a physical, mental, cognitive, sensory, learning or communication impairment, that, when it meets a barrier, prevents a person from taking part fully and equally in society.

distinctions-based approach: An approach that recognizes First Nations, Inuit and Métis as distinct Peoples with their own histories, rights, governments and priorities, instead of treating them as one group.

duty to accommodate: The obligation under human rights law to adjust services to an individual's disability-related needs in ways that respect dignity and support full participation, short of undue hardship.

equality: Giving every person the same resources or treatment, whatever their needs.

equity: Giving people what they need so that each person has a fair chance at good outcomes.

First Nations: The many distinct Indigenous Nations across Canada, each with its own language, laws and protocols; a First Nations person may or may not have Indian status.

food insecurity: Not being able to count on enough food, in quantity or quality, because money is short.

gender identity: A person's internal sense of their own gender, such as being a man, a woman, both or neither.

health equity: A state in which every person has a fair opportunity to reach their best possible health, regardless of the social and structural conditions of their lives.

health inequality: A measurable difference in health between groups of people.

health inequity: A systematic difference in health between groups that is avoidable and unjust because it results from how resources, power and opportunities are distributed.

homelessness: The situation of a person, family or community that lacks stable, permanent and suitable housing and has no immediate prospect, means or ability to obtain it.

implicit bias: An attitude or stereotype that operates outside a person's awareness and shapes judgments and actions without the person intending it.

Indian Act: The federal law, first passed in 1876, that defines who is registered as an "Indian" and has governed many aspects of First Nations life, including reserves and band governance.

Indian hospitals: Racially segregated federal hospitals for Indigenous patients, operated from 1936 to 1981 and first set up to isolate people with tuberculosis; patients experienced abuse in them.

Indian status: The legal standing of a First Nations person registered under the Indian Act; a legal category, not an identity.

Indigenous patient navigator: A hospital or health-system staff member who supports Indigenous patients and families, improves communication with the care team and connects patients with cultural, spiritual and community services.

Indigenous-specific racism: The particular stereotyping, bias and prejudice directed at Indigenous Peoples, rooted in settler colonialism, that sustains power imbalances and unequal outcomes.

intergenerational effects: Harms of colonial policies that pass from one generation to the next, for example through disrupted families, lost languages and unresolved trauma.

Interim Federal Health Program (IFHP): A federal program, run by Immigration, Refugees and Citizenship Canada, that provides limited, temporary health coverage to eligible refugees, refugee claimants and certain others until they qualify for provincial or territorial insurance.

intersectionality: A way of understanding how a person's social positions, such as race, gender, disability, age, income and immigration status, combine to shape experiences of advantage and disadvantage.

Inuit: The Indigenous People of Inuit Nunangat, many of whom now also live in southern cities; one person is an Inuk.

Inuit Child First Initiative: A federal initiative that helps Inuit children get the health, social and educational services and supports they need.

Inuit Nunangat: The Inuit homeland of land, water and ice, made up of the Inuvialuit Settlement Region, Nunavut, Nunavik and Nunatsiavut.

Jordan's Principle: A principle that aims to ensure First Nations children can get essential government services without gaps or delays caused by their identity or where they live.

Joyce's Principle: A principle set out in 2020 by the Council of the Atikamekw of Manawan and the Atikamekw Nation Council, after the death of Joyce Echaquan, that aims to guarantee Indigenous people equitable access to health and social services without discrimination, and respect for Indigenous knowledge in health.

Métis: A distinct Indigenous People who emerged from the 18th-century fur trade, with their own culture, language (Michif) and nationhood; being Métis is not the same as having mixed ancestry.

Non-Insured Health Benefits (NIHB): A federal program that pays for medically necessary benefits not covered by other plans, such as prescription drugs, dental and vision care, counselling, supplies and equipment, and medical transportation, for registered First Nations people and recognized Inuit.

OCAP®: The First Nations principles of Ownership, Control, Access and Possession, which state that First Nations govern data about their communities; a registered trademark of the First Nations Information Governance Centre.

occult hypoxemia: Low arterial oxygen saturation (below 88%) that is hidden by a pulse oximeter reading in the normal-looking range (92% to 96%).

race: A social category that sorts people by features such as skin colour, name or origin and ranks them unequally; it is not a biological measure.

race-free equations: Equations for estimated glomerular filtration rate (eGFR) that do not use race, such as the 2021 CKD-EPI equations.

racialization: The process by which a society treats races as real and distinct and ranks them unequally, with effects on people's economic, political and social lives.

racialized: Describes a person or group that society treats as belonging to a race and treats unequally because of it; preferred over older terms such as "visible minority."

residential schools: Church-run, government-funded schools that removed at least 150,000 First Nations, Inuit and Métis children from their families to assimilate them; the last federally supported schools closed in the late 1990s.

Sixties Scoop: The removal of many Indigenous children from their families by child welfare authorities, from about the 1960s to the 1980s, and their placement in non-Indigenous foster and adoptive homes.

social determinants of health: The everyday conditions in which people live and work, such as income, education, work, housing, social support and freedom from discrimination and violence.

structural determinants of health: The large systems, laws, policies and institutional practices, such as governments, labour markets and health, education, immigration and financial systems, that shape how resources and opportunities are distributed and so shape the social determinants.

substitute decision-making: An approach in which another person makes a decision on behalf of a person who is incapable of making it.

supported decision-making: An approach in which trusted people help a person understand choices and express a decision, while the decision remains the person's own.

transgender: Describes a person whose gender identity differs from the sex they were assigned at birth.

trauma- and violence-informed care (TVIC): An approach to care that recognizes the links between violence, trauma and health, including ongoing and structural violence, and focuses on creating safety, choice and control without requiring disclosure.

Two-Spirit: An English umbrella term used by some Indigenous people for an identity rooted in their own cultures, which may include gender, spiritual and sexual identity.

United Nations Declaration on the Rights of Indigenous Peoples (UNDRIP): A declaration adopted by the United Nations General Assembly in 2007, which sets minimum standards for Indigenous rights, including the right to traditional medicines and to health services without discrimination (Article 24).

weight stigma: The social devaluing of people because of their body size, which can show up as stereotypes, judgmental language and equipment or practices that do not fit them.

Licensure Review & Clinical Judgment Questions (30)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

1. [CORE] A 61-year-old patient is ready for discharge after treatment for a new diagnosis of type 2 diabetes. During teaching, the patient says, "Some weeks I skip meals so the rent gets paid." Which action by the nurse is the priority before discharge?

a. Give the patient a printed meal plan from Diabetes Canada and review it with teach-back.

b. Document that the patient is likely to be non-adherent to the diet.

c. Report the food insecurity to the team and request social work and pharmacy input.

d. Advise the patient to take the new glucose-lowering medication only on days when meals are eaten.

Answer: c — The patient has described food insecurity, a determinant that can raise the risk of hypoglycemia with some glucose-lowering drugs and of poor glucose control; with the patient's agreement, the nurse shares it so the team can address income supports, food programs and medication choice before discharge (section 2.1, Table 2.1). A meal plan (a) assumes the patient can buy the food. Labelling the patient non-adherent (b) blames the patient for a structural problem and does not change the plan. Advising the patient to change the dose schedule (d) is outside the nurse's authority without an order and could be unsafe.

2. [CORE] A nurse is admitting a 47-year-old patient for an elective hip replacement. Which actions reflect an equity-oriented approach to admission? Select all that apply.

a. Ask the patient how they will get to follow-up appointments after discharge.

b. Ask about drug coverage only if the patient appears to have a low income.

c. Ask whether the patient cares for anyone at home who will need help while they recover.

d. Ask who will be at home to help in the first weeks after surgery.

e. Ask the same questions about housing and food of every patient, in a respectful way.

f. Wait until the day of discharge to ask about stairs and bathroom access at home.

Answer: a, c, d, e — Transport (a), caregiving responsibilities (c), help at home (d) and asking every patient the same questions (e) identify determinants early so the team can plan (section 2.1, Table 2.1). Asking about drug coverage only when a patient "appears" to have low income (b) relies on stereotypes and misses people whose needs are not visible. Discharge planning begins at admission (see Chapter 1, section 1.7), so waiting until the day of discharge (f) leaves no time to arrange equipment or services.

3. [CORE] A medical unit is updating its discharge process. Which change best reflects equity rather than equality?

a. Every patient receives the same printed discharge booklet in English, with a copy for the family.

b. Each patient is asked about language, drug costs and transport, and teaching is adjusted to fit.

c. Every patient receives a 10-minute discharge teaching session from a nurse at the same time of day.

d. Follow-up appointments are booked for all patients at the hospital's main clinic in the same time slot.

Answer: b — Equity means giving people what they need to have a fair chance at good outcomes; asking each patient about language, drug costs and transport and adjusting teaching to fit does this (section 2.1). Options a, c and d give everyone the same thing, which is equality. Identical resources can leave some patients, such as those with limited English, no drug plan or no transport, without what they need.

4. [CORE] Which statement by a nurse best shows cultural humility rather than cultural competence?

a. "I took a course on the beliefs of different cultural groups, so I know what this patient will want."

b. "I keep a list of the main cultural practices of groups on our unit, so I can apply the right ones to each patient I care for."

c. "I treat every patient exactly the same, so culture does not affect my care."

d. "I asked the patient what matters to her, and I am thinking about how my own assumptions shaped our talk."

Answer: d — Cultural humility is ongoing self-reflection on one's own biases, with the patient treated as the expert on their own life (section 2.2, Table 2.2). Options a and b describe a knowledge-based view of competence that can reduce culture to a checklist and lead to stereotyping. Option c ignores how differences in power and experience affect care, and treating everyone the same is equality, not safety.

5. [CORE] A nurse is about to insert an indwelling urinary catheter in a 34-year-old patient after surgery. As the nurse begins, the patient tenses, pulls the sheet up and says, "Wait." What should the nurse do first?

a. Stop, acknowledge the request, explain each step and ask what would help the patient feel in control.

b. Continue quickly so the procedure is over sooner and causes less distress.

c. Ask the patient directly whether they have a history of sexual abuse, so the nurse can plan the rest of their care.

d. Call another staff member to help hold the patient's legs in position so the catheter can be inserted safely.

Answer: a — Trauma- and violence-informed care builds safety and control: the nurse stops, respects the request, explains, and offers choices such as a pause or a different position (section 2.2). Continuing (b) overrides the patient's request and could retraumatize them; consent can be withdrawn at any time (see Chapter 1, section 1.5). Asking about abuse history (c) is not needed, because TVIC does not require disclosure. Holding the patient still (d) is a possible trigger and would proceed without consent.

6. [CORE] A First Nations patient tells the nurse, "The way the night staff talked to me last night didn't feel safe. They acted like I was just here for the pills." What is the best initial response by the nurse?

a. "I'm sure they didn't mean it that way. Night shift is very busy."

b. "If you're unhappy with your care, you should make a formal complaint to the patient relations office downstairs."

c. "Thank you for telling me. Can you tell me more about what happened and what would help you feel safer here?"

d. "I'll speak to the night nurse about this and ask her to come and apologize to you when she is back on shift tonight."

Answer: c — Only the patient can say whether care felt culturally safe; the nurse listens, believes the patient, thanks them for the feedback and asks what would help, and then acts and reports according to policy (section 2.2). Option a defends staff and dismisses the patient's experience. Option b passes responsibility on before the nurse has heard the concern, although the patient may be told about this option later. Option d decides on a solution without asking the patient what they want.

7. [CORE] A nurse is caring for a 72-year-old woman who is racialized, uses a wheelchair, lives alone on a fixed income and speaks limited English. She has been readmitted with heart failure. A colleague says, "She's just not following her plan." Which understanding should guide the nurse's response?

a. Her readmission is best explained by her age, so the plan should focus on her heart failure.

b. Her social positions and circumstances combine to create barriers to following the plan, and those barriers need to be assessed.

c. Her limited English is the only barrier, so a professional interpreter will solve the problem.

d. Her readmission shows a lack of motivation, so the discharge teaching should stress the serious risks of not following her heart failure plan.

Answer: b — Intersectionality describes how several social positions, such as race, disability, age, income and language, combine to shape barriers; the nurse assesses each barrier, such as cost, access to the pharmacy, mobility and understanding, rather than blaming the patient (section 2.1). Age (a) and language (c) each explain only part of her situation, although an interpreter is still needed (see Chapter 1, section 1.7). Option d attributes the readmission to personal choice and ignores the conditions shaping it.

8. [CORE] A 72-year-old First Nations patient is recovering from a bowel resection on a surgical unit. He receives oxygen at 2 L/min by nasal cannula. His daughter asks whether an Elder can come to smudge with him tomorrow. What is the best response by the nurse?

a. "Smudging isn't possible on this unit while your father is on oxygen, so the Elder could visit after he goes home instead."

b. "Thank you. I'll ask the Indigenous patient navigator and spiritual care to arrange it under our ceremony policy, including oxygen safety."

c. "You can go ahead tomorrow. I'll turn his oxygen off for a few minutes while the Elder smudges at the bedside."

d. "I'll need a physician's order before any ceremony can take place in his room, so I'll ask at rounds."

Answer: b — TRC Call to Action 22 and hospital policies support ceremony when patients ask, and the safe route is through the navigator, spiritual care and the facility's policy, which covers fire and oxygen safety, for example a liquid smudge or another space (section 2.3). Refusing outright (a) denies a right the facility can usually accommodate. Turning oxygen off without an order or a plan (c) is unsafe and bypasses policy. Ceremony is arranged through the facility's policy, not by a physician's order (d), although the team plans it together.

9. [CORE] A nurse is admitting several Indigenous patients during a shift. Which actions reflect respectful, distinctions-based practice? Select all that apply.

a. Asking each patient how they identify and which Nation or community they are from

b. Recording "Aboriginal" for every Indigenous patient so the chart is consistent

c. Referring to one Inuit patient as "an Inuk woman"

d. Assuming an Inuk patient from Nunavik prefers to speak Inuktut and booking an interpreter without asking

e. Asking a Métis patient about drug coverage early in discharge planning

f. Telling a colleague that "our Indigenous patients" usually want to smudge

Answer: a, c, e — Asking how a person identifies (a) and using the People's own terms, such as Inuk for one person (c), are distinctions-based. Métis patients are not eligible for NIHB, so checking coverage early (e) prevents a gap at discharge (section 2.3, Table 2.3). A single blanket term (b) erases distinctions, and "Aboriginal" is now kept mostly for legal and historical names. Language preference must be asked, not assumed (d); the nurse offers an interpreter (Chapter 1, section 1.7). Possessive phrasing ("our Indigenous patients") and generalizing about ceremony (f) are disrespectful and assume practices that differ between Nations and people.

10. [CORE] Which patient qualifies for Non-Insured Health Benefits (NIHB)?

a. A Métis citizen registered with her Métis government who lives in Toronto

b. A First Nations man who is not registered under the Indian Act

c. An Inuk woman recognized by Nunavut Tunngavik Incorporated who now lives in Ottawa

d. A woman who identified as Indigenous on the 2021 Census

Answer: c — NIHB covers residents of Canada who are First Nations people registered under the Indian Act, Inuit whom an Inuit land claim organization recognizes, and children under 2 whose parent is eligible; living outside Inuit Nunangat does not change eligibility (section 2.3, Table 2.3). Métis people are not eligible (a). A First Nations person without registration is not eligible, though no less First Nations (b). Census self-identification does not establish eligibility (d).

11. [CORE] A 54-year-old First Nations man is brought to the emergency department after he was found sitting outside a shopping centre. His speech is slurred and he is drowsy. A colleague says, "He's probably drunk again. Let him sleep it off in the hallway." What should the nurse do first?

a. Ask the man's family whether he has a history of alcohol use.

b. Let him rest on a hallway stretcher and recheck his condition in 2 hours.

c. Ask security to stay with him in case he becomes aggressive.

d. Assess him fully, including vital signs, level of consciousness and capillary blood glucose.

Answer: d — Slurred speech and drowsiness can come from hypoglycemia, stroke, head injury, sepsis or hypoxia, so a full assessment comes first, and abnormal findings are escalated (section 2.3, Clinical Safety box; Chapter 6). Asking about alcohol (a) follows the stereotype instead of the cues. Leaving him unassessed (b) repeats the error that led to Brian Sinclair's death. Calling security (c) treats him as a threat without evidence. The nurse should also challenge the colleague's comment.

12. [CORE] During care, a nurse hears a colleague tell a First Nations patient, "You people always exaggerate your pain to get drugs." The patient turns away and says nothing. What should the nurse do?

a. Stay with the patient, reassess her pain, and report the comment through the unit's process for reporting racism.

b. Wait until the end of the shift, then talk with the colleague privately and decide together whether the comment needs to be reported.

c. Ask the patient whether she wants to make a complaint before taking any action.

d. Write in the chart that the patient appears to be seeking drugs, so the next shift is aware.

Answer: a — The nurse's first duty is the patient's safety and dignity: support her, reassess the pain as credible, and report racism as the CNO Code of Conduct and Joyce's Principle expect (sections 2.2 and 2.3). Delaying (b) leaves the patient exposed and lets the behaviour go unaddressed. The patient may choose to complain, but the nurse's duty to report does not depend on her deciding to (c). Charting a label (d) repeats the kind of unfounded label that harmed Joyce Echaquan and is not objective documentation.

13. [CORE] A medical unit wants to respond to TRC Call to Action 22. Which action fits this call best?

a. Collect Indigenous identity on every admission so the unit can report its numbers.

b. Set up a clear process for patients to request Elders, healers and traditional medicines.

c. Send every Indigenous patient to the patient navigator at admission, whether or not they ask.

d. Require all staff to complete a course on Treaties and Aboriginal rights.

Answer: b — Call 22 asks the health system to recognize Indigenous healing practices and use them with healers and Elders when patients request it (section 2.4, Table 2.4). Collecting identity data (a) does not address healing practices and must follow data principles. Mandatory referral (c) removes the patient's choice. Staff training (d) relates more closely to Calls 23 and 24.

14. [CORE] A nurse on a hospital quality committee wants to present wound-healing outcomes for patients from a nearby First Nation at a conference. Which action follows the First Nations Principles of OCAP®?

a. Seek approval and involvement from the First Nation's leadership or health centre before using the data.

b. Remove patient names and other identifiers; once the data are de-identified, community approval is not needed.

c. Use the data freely because they were collected in the hospital's own records under its privacy policies.

d. Ask the First Nations Information Governance Centre for permission on the community's behalf.

Answer: a — Under OCAP®, the First Nation collectively owns and controls data about its community and decides how they are used, so the nurse seeks the community's approval and involvement (section 2.4). De-identifying individuals (b) does not remove the community's collective interest. Where the data are stored (c) does not decide who governs them. FNIGC holds the OCAP® trademark but cannot consent on behalf of a particular community (d).

15. [CORE] A 78-year-old Inuk woman from Nunavut is admitted to a southern hospital with pneumonia. She is restless, keeps asking to go home and refuses to stay overnight. Through an interpreter, she says her mother was sent south for tuberculosis and never came back. What is the best response by the nurse?

a. Reassure her that patients are no longer sent away for long periods the way her mother was, so she has nothing to worry about.

b. Ask for a psychiatry consultation to assess her anxiety before treatment continues.

c. Acknowledge her experience, explain the plan and when she may go home, and ask who she would like with her.

d. Explain that refusing to stay overnight will be documented as non-compliance with her treatment plan.

Answer: c — Her fear is a reasonable response to a real history of TB evacuations, so the nurse acknowledges it, keeps her informed, brings family and supports such as the Indigenous patient navigator close, and respects her choices (section 2.3; section 2.2 on trauma- and violence-informed care). Brushing the history aside (a) dismisses her experience. Treating the response as a psychiatric problem (b) pathologizes a reasonable fear. Threatening a label (d) is coercive and damages trust.

16. [RN] An RN preparing a unit education session finds the statement "Indigenous people in Canada have a TB rate many times higher than other Canadians." Which questions should the RN ask before using it? Select all that apply.

a. Does the figure separate First Nations, Inuit and Métis?

b. Which people and places were included, such as on reserve, in Inuit Nunangat or only private households?

c. Does the source name the structural causes, such as crowded housing?

d. Were the data used with the agreement of the communities that govern them?

e. Is the number large enough to persuade staff that the issue matters?

f. Does the statistic show that the group has a genetic risk for TB?

Answer: a, b, c, d — Aggregated "Indigenous" figures hide differences: 2024 TB incidence ranged from 1.3 per 100,000 among Métis to 186.9 among Inuit (a). Coverage and geography change the number (b). Naming causes avoids blame (c), and data governance respects OCAP® and Inuit and Métis data principles (d) (section 2.4, Going Deeper box). Choosing a figure for its impact (e) is not a test of its quality. Health gaps are not explained by race as biology (f); they reflect housing, poverty and history.

Case: Mr. Leonard Fraser (Questions 17–26): Mr. Leonard Fraser, 58, has been on a medical unit in an Ontario city for 4 days with cellulitis of the right lower leg. He was treated with intravenous antibiotics and will be switched to oral cephalexin capsules, four times a day, for 7 more days. Today: temperature 37.2 °C, heart rate 84, blood pressure 132/78, respiratory rate 16, SpO_2 97% on room air. White blood cell count 9.1 × 10^9/L (15.6 × 10^9/L on admission); random glucose 6.4 mmol/L; creatinine 92 µmol/L. The redness, warmth and swelling have shrunk well inside the border marked on admission. Mr. Fraser has slept at an overnight shelter for 8 months. The shelter opens at 2000 and closes at 0800. He says, "My boots leak, and I have nowhere to put my feet up." He has an Ontario health card but no drug plan, and he has lost his medications twice this year when his backpack was stolen. His phone has no data plan.

17. [CORE] The nurse reviews Mr. Fraser's information on the planned day of discharge. Which findings threaten a safe discharge? Select all that apply.

a. He must leave the shelter at 0800 each day.

b. His temperature is 37.2 °C.

c. He has no drug plan for the cephalexin.

d. His medications have been stolen before.

e. His white blood cell count has fallen to 9.1 × 10^9/L.

f. He cannot keep his legs elevated or his feet dry.

Answer: a, c, d, f — Recognizing cues means picking out the findings that matter for the decision at hand (see section 2.5 and Chapter 1, section 1.4). Having nowhere to rest in the day (a), no drug coverage (c), a history of stolen medications (d) and no way to elevate his leg or keep his feet dry (f) all threaten his recovery after he leaves. A temperature of 37.2 °C (b) is within normal limits, and a falling white blood cell count (e) shows the infection is responding; neither threatens the discharge.

18. [CORE] Which statement best explains how Mr. Fraser's housing situation relates to his cellulitis?

a. Wet feet and having nowhere to rest or elevate his leg raise his risk of the infection coming back.

b. His housing has no bearing on his leg once he has finished the full antibiotic course.

c. His cellulitis was caused mainly by poor hygiene choices that discharge teaching can correct.

d. His risk of cellulitis is high mainly because of his age, which cannot be changed.

Answer: a — Analyzing cues links findings to their likely causes. Homelessness exposes his skin to moisture, swelling and injury, and makes leg elevation and wound care hard, which raises the risk of recurrence (section 2.5). Option b ignores the conditions he returns to. Option c blames the individual rather than naming the structural cause; the Canadian Definition of Homelessness stresses that systemic barriers drive homelessness. Option d names a fixed factor and misses the main, changeable one.

19. [CORE] Which concern should the team address first in Mr. Fraser's discharge plan?

a. Teaching him to recognize the signs of a fungal infection between the toes.

b. Arranging a follow-up visit with a dermatologist within 3 months.

c. Making sure he can get, keep and take the full course of cephalexin.

d. Helping him join a smoking cessation program.

Answer: c — Prioritizing hypotheses means choosing the most important and urgent problem. An incomplete antibiotic course risks treatment failure and readmission, and three of his cues (no drug plan, stolen medications, nowhere to stay in the day) threaten it (section 2.5). Option a is useful, because foot care can prevent recurrence, but less urgent. Option d addresses a problem the case does not mention. Option b is a long-term step that does not address the immediate risk.

20. [CORE] Which actions should the nurse include when planning Mr. Fraser's discharge with the team? Select all that apply.

a. Ask the social worker to check his eligibility for drug coverage and help pay for the first fill.

b. Arrange for the shelter or a respite program to offer a daytime place to rest and elevate his leg.

c. Discharge him at 1930 so that he arrives just as the shelter opens.

d. Ask the prescriber and pharmacist whether a simpler regimen or blister packaging is possible.

e. Arrange new, dry socks and footwear through a hospital or community program.

f. Tell him to come back to the emergency department if he has any questions at all.

Answer: a, b, d, e — Generating solutions means planning actions that fit the patient's real situation (section 2.5). Securing coverage and the first fill (a), a daytime place to rest (b), a regimen he can manage (d) and dry footwear (e) all address his barriers. Option c creates a late-evening discharge, which the team should avoid; it leaves him exposed if the shelter has no bed. Option f sends routine questions to the emergency department instead of arranging follow-up, such as a community clinic or outreach nurse.

21. [CORE] On the morning of discharge, Mr. Fraser says, "I'll just go. I've never been able to get pills paid for, and the shelter doesn't want sick people." What should the nurse do first?

a. Document that he is non-compliant with the discharge plan.

b. Acknowledge his worry and tell him what has been arranged for his medications and shelter.

c. Remind him that he will need to be readmitted if he does not take his antibiotics.

d. Ask a family member to persuade him to stay.

Answer: b — Taking action starts with a respectful, trauma- and violence-informed response that builds trust (sections 2.2 and 2.5). Acknowledging his past experience and explaining the concrete plan gives him real information and choice. Option a uses a stigmatizing label and does nothing to solve the problem. Option c uses fear rather than support. Option d brings in another person without his consent, and he has not named anyone.

22. [CORE] Mr. Fraser returns for a follow-up visit 5 days later at a community health centre. Which finding best shows that the discharge plan is working?

a. He says the hospital staff treated him with respect during his stay.

b. He reports that his leg feels "about the same" as it did at discharge.

c. He has been placed on a waiting list for a unit in social housing.

d. He takes his doses from his blister pack, and the redness has shrunk since discharge.

Answer: d — Evaluating outcomes compares results with the goals of care: completing the antibiotic and continued healing (section 2.5). Option d shows both. Option a is welcome but does not show that he is taking the antibiotic or that the infection is healing. Option b suggests no improvement and needs further assessment. Option c is valuable for his long-term health but does not show that the infection is resolving.

23. [CORE] The admission record shows a first name that Sam does not use. Which action should the RPN take first?

a. Call him by the name on his health card, because it is his legal name.

b. Ask him what name and pronouns he uses, and use them.

c. Avoid using any name until the record is changed.

d. Ask his partner what he would like to be called.

Answer: b — CNO's Code of Conduct expects nurses to use the name, title and pronouns a patient prefers (section 2.5). The nurse asks the patient directly and records the chosen name where the record allows, while still using the legal name and two identifiers for patient identification. Option a ignores his identity and the CNO expectation. Option c is awkward and impersonal. Option d asks someone else when Sam is capable of answering for himself.

24. [CORE] During the admission interview, the RPN is completing the nursing assessment. When is it appropriate to ask about Sam's sex assigned at birth or his past surgeries?

a. Only when the answer would change his care, explaining why the question is asked.

b. At every admission, because curiosity helps nurses learn about transgender patients.

c. Never, because such questions are always discriminatory.

d. Only after his partner leaves the room, without explaining the reason.

Answer: a — Custodians may collect only the personal health information that is reasonably necessary, so the nurse asks about anatomy or past surgeries only when it affects care, such as an anatomy-specific assessment, and explains why (section 2.5). Option b collects information for the nurse's interest, not the patient's care. Option c could miss information that is clinically needed. Option d may be appropriate for privacy if Sam wants it, but leaving out the explanation makes the question feel intrusive.

25. [CORE] After surgery, Sam is drowsy but capable. Daniel asks the RPN how the surgery went. What should the RPN do?

a. Refuse, because only relatives by birth or marriage can receive information.

b. Share the information, because partners are part of the circle of care.

c. Ask Sam whether he agrees to the RPN sharing information with Daniel.

d. Tell Daniel to ask the surgeon.

Answer: c — A capable patient decides who receives his health information, and partners and family members are not health information custodians (Chapter 1, section 1.5; section 2.5). Option a is wrong and discriminatory; the patient, not the type of relationship, decides who his support people are. Option b misstates the circle of care. Option d delays the answer and still requires Sam's consent.

26. [CORE] At handover, a colleague jokes about Sam's identity in a voice that can be heard in the hallway. What is the RPN's best response?

a. Ignore the comment so that handover finishes on time.

b. Tell Sam what the colleague said so that he can complain.

c. Write an account of the colleague's comment in Sam's health record.

d. Address the comment calmly with the colleague and report it through the employer's process.

Answer: d — The Code of Conduct expects nurses to take action when they see discrimination against a patient (section 2.6). Speaking to the colleague and using the employer's reporting process protects Sam and future patients. Option a lets discrimination continue. Option b may cause Sam distress and shifts the burden onto him; he can still be supported if he raises a concern himself. Option c misuses the health record, which documents care, not opinions about colleagues.

27. [CORE] A patient on a surgical unit tells the nurse that she felt dismissed and judged by staff during her stay and wants to make a complaint. What should the nurse tell her about the usual first step in Ontario?

a. File a complaint directly with Patient Ombudsman before speaking to anyone at the hospital.

b. Wait until after discharge, because complaints cannot be made during a hospital stay.

c. Contact the hospital's patient relations office, and go to Patient Ombudsman if the concern is not resolved.

d. Write a letter to the College of Nurses of Ontario, which handles all hospital complaints.

Answer: c — Patient Ombudsman asks people to try to resolve the concern with the organization first and becomes involved if it is not resolved (section 2.6). The nurse also reports her own concerns about discrimination through the employer's process. Option a skips the hospital's process. Option b is false and delays the response. Option d is wrong because CNO handles concerns about individual nurses, not hospital complaints in general.

28. [RN] A laboratory changes from the 2009 race-adjusted CKD-EPI creatinine equation to the 2021 race-free equation. What is the likely effect for a Black patient with chronic kidney disease whose results were previously reported with the race adjustment?

a. The reported eGFR will be lower, which may lead to earlier referral for kidney care.

b. The reported eGFR will be higher, so the kidney disease will appear milder than before.

c. The measured serum creatinine value will fall because the calculation has changed.

d. The patient's actual kidney function will improve as a result of the change.

Answer: a — The race correction in the 2009 equation raised eGFR for patients recorded as Black, which could make kidney disease look milder and delay referral; removing it gives a lower reported eGFR in that situation (Going Deeper box, section 2.6). Option b describes the effect of the old correction, not of the change. Option c is wrong because the equation changes only the calculation, not the measured creatinine. Option d confuses a change in reporting with a change in the patient's kidney function.

29. [RN] A patient with darker skin has pneumonia and is receiving oxygen at 2 L/min by nasal prongs. The pulse oximeter reads 94%, but the patient is newly confused, has a respiratory rate of 28 and is using accessory muscles. What should the RN do first?

a. Document the SpO_2 and reassess in 4 hours, because 94% is acceptable.

b. Escalate to the prescriber now and anticipate an arterial blood gas.

c. Move the probe to another finger and record whichever reading is higher.

d. Remove the oxygen to see whether the saturation stays the same.

Answer: b — Pulse oximeters can overestimate oxygen saturation in people with darker skin, and occult hypoxemia can hide behind readings of 92% to 96% (Going Deeper box, section 2.6). The RN treats the reading as possibly inaccurate: new confusion, tachypnea and accessory muscle use are signs of deterioration that need urgent escalation, and an arterial blood gas measures oxygenation directly. Option a ignores the clinical signs. Option c picks the most reassuring number rather than assessing the patient. Option d is unsafe in a patient who is deteriorating.

30. [RN] An RN notices that one model of pulse oximeter on the unit often gives readings that do not match patients' arterial blood gas results. What should the RN do?

a. Stop using every pulse oximeter on the unit until the manufacturer has inspected them.

b. Subtract 4% from each reading from this model before documenting it.

c. Tell patients that readings from this model are unreliable and they should ignore them.

d. Report the problem through the hospital's incident reporting process.

Answer: d — Hospitals must report serious medical device incidents to Health Canada, and the nurse's report through the hospital's process starts that review (Going Deeper box, section 2.6). Option a removes a useful monitoring tool without a plan. Option b invents a correction that has not been validated. Option c alarms patients without fixing the problem.

References

Hardy v. Canada (Attorney General), 2025 FC 1140. https://decisions.fct-cf.gc.ca/fc-cf/decisions/en/528458/1/document.do

Accessibility for Ontarians with Disabilities Act, 2005, S.O. 2005, c. 11. https://www.ontario.ca/laws/statute/05a11

Accessible Canada Act, S.C. 2019, c. 10. https://laws-lois.justice.gc.ca/eng/acts/A-0.6/page-1.html

Alberta Precision Laboratories. (2026, January 19). *Estimated glomerular filtration rate (eGFR) calculation update for adult patients* [Laboratory bulletin]. https://albertahealthservices.ca/assets/wf/lab/if-lab-hp-bulletin-2026-01-19-estimated-glomerular-filtration-rate-egfr-calculation-update-for-adult-patients.pdf

Assembly of First Nations. (n.d.). *Assembly of First Nations* [Home page]. Retrieved October 24, 2026, from https://www.afn.ca/Home/

Brobbey, A., Sharma, V., & Mazereeuw, M. (2025). Avoidable hospitalizations among racialized groups in Canada: Results from the 2016 Canadian Census Health and Environment Cohort. *Health Reports, 36*(3) (Statistics Canada Catalogue No. 82-003-X). https://doi.org/10.25318/82-003-x202500300002-eng

Canadian Association of Schools of Nursing. (2020). *Framework of strategies for nursing education to respond to the Calls to Action of Canada's Truth and Reconciliation Commission*. https://www.casn.ca/wp-content/uploads/2020/11/EN-TRC-RESPONSE-STRATEGIES-FOR-NURSING-EDUCATIONTRC-Discussion-Paper-Revised-Final.pdf

Canadian Museum of History. (n.d.). *The Indian Act* [Blog post]. Retrieved October 24, 2026, from https://historymuseum.ca/blog/?p=10287

Canadian Nurses Association. (2021, November 15). *Nurses commit to action against anti-Black racism in nursing and health care* [News release]. https://www.cna-aiic.ca/en/blogs/cn-content/2021/11/15/nurses-commit-to-action-against-anti-black-racism

Canadian Nurses Association. (2025). *Code of ethics for nurses*. https://www.cna-aiic.ca/en/nursing/regulated-nursing-in-canada/nursing-ethics/2025-coe

Chief Public Health Officer Health Professional Forum. (2023). *Common definitions on cultural safety* (Cat. No. H22-4/22-2021E-PDF). Public Health Agency of Canada. https://www.canada.ca/content/dam/hc-sc/documents/services/publications/health-system-services/chief-public-health-officer-health-professional-forum-common-definitions-cultural-safety/definitions-en2.pdf

College of Nurses of Ontario. (2026). *Code of conduct* [Practice standard]. https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49040_code-of-conduct.pdf

Constitution Act, 1982, s. 35, being Schedule B to the Canada Act 1982 (UK), 1982, c. 11. https://laws-lois.justice.gc.ca/eng/const/page-12.html

Cortes, K., & Smith, L. (2022, November 2). Pharmaceutical access and use during the pandemic. *Insights on Canadian Society* (Statistics Canada Catalogue No. 75-006-X). https://www150.statcan.gc.ca/n1/pub/75-006-x/2022001/article/00011-eng.htm

Council of the Atikamekw of Manawan & Atikamekw Nation Council. (2020). *Joyce's Principle* [Brief]. https://principedejoyce.com/sn_uploads/principe/Joyce_s_Principle_brief___Eng.pdf

Crenshaw, K. (1989). Demarginalizing the intersection of race and sex: A Black feminist critique of antidiscrimination doctrine, feminist theory and antiracist politics. *University of Chicago Legal Forum, 1989*(1), 139–167. https://chicagounbound.uchicago.edu/uclf/vol1989/iss1/8

Crown-Indigenous Relations and Northern Affairs Canada. (2010). *Apology for the Inuit High Arctic relocation*. https://www.rcaanc-cirnac.gc.ca/eng/1100100016115

Crown-Indigenous Relations and Northern Affairs Canada. (2025a, March 6). *Final agreement reached to resolve Hardy class action* [News release]. https://www.canada.ca/en/crown-indigenous-relations-northern-affairs/news/2025/03/final-agreement-reached-to-resolve-hardy-class-action.html

Crown-Indigenous Relations and Northern Affairs Canada. (2025b). *2024–2025 Federal Pathway annual progress report: Reporting on the Calls for Justice*. https://www.rcaanc-cirnac.gc.ca/eng/1750353001767

Crowshoe, L., Dannenbaum, D., Green, M., Henderson, R., Naqshbandi Hayward, M., & Toth, E. (2018). Type 2 diabetes and Indigenous peoples. *Canadian Journal of Diabetes, 42*(Suppl. 1), S296–S306. https://doi.org/10.1016/j.jcjd.2017.10.022

Department of Justice Canada. (2023, June 21). *An important step in upholding the human rights of Indigenous peoples in Canada* [News release]. https://www.canada.ca/en/department-justice/news/2023/06/an-important-step-in-upholding-the-human-rights-of-indigenous-peoples-in-canada.html

Donovan, R. (2023). *2023 legislative review of the Accessibility for Ontarians with Disabilities Act, 2005*. Government of Ontario. https://www.ontario.ca/page/2023-legislative-review-accessibility-ontarians-disabilities-act-2005

Employment and Social Development Canada. (2026). *Research summary: Helping 2SLGBTQI+ older adults to age in place*. https://www.canada.ca/en/employment-social-development/corporate/reports/research/summary-2slgbtqi-older-adults.html

EQUIP Health Care. (n.d.). *Principles of trauma- and violence-informed care (TVIC)*. Retrieved October 24, 2026, from https://gtvincubator.uwo.ca/wp-content/uploads/2024/10/EQUIP_TVICprinciples_Oct2024.pdf

First Nations Health Authority. (2022, May 6). *Briefing to the House of Commons Standing Committee on Indigenous and Northern Affairs: Study of administration and accessibility of Indigenous peoples to the Non-Insured Benefits program* [Brief]. https://www.ourcommons.ca/Content/Committee/441/INAN/Brief/BR11756885/br-external/FirstNationsHealthAuthority-e.pdf

First Nations Health Authority. (n.d.-a). *Cultural safety and humility*. Retrieved October 24, 2026, from https://fnha.ca/services-and-support/culturally-grounded-care/cultural-safety-and-humility/

First Nations Health Authority. (n.d.-b). *Declaration of commitment on cultural safety and humility in health services*. https://www.fnha.ca/Documents/Declaration-of-Commitment-on-Cultural-Safety-and-Humility-in-Health-Services.pdf

First Nations Information Governance Centre. (2018, March 14). *New report provides unprecedented look at trends over time in the health and well-being of First Nations communities* [News release]. https://fnigc.ca/news/new-report-provides-unprecedented-look-at-trends-over-time-in-the-health-and-well-being-of-first-nations-communities/

First Nations Information Governance Centre. (n.d.). *The First Nations principles of OCAP®*. Retrieved October 24, 2026, from https://fnigc.ca/ocap-training/

FitzGerald, C., & Hurst, S. (2017). Implicit bias in healthcare professionals: A systematic review. *BMC Medical Ethics, 18*(1), Article 19. https://doi.org/10.1186/s12910-017-0179-8

Gaetz, S., Barr, C., Friesen, A., Harris, B., Hill, C., Kovacs-Burns, K., Pauly, B., Pearce, B., Turner, A., & Marsolais, A. (2012). *Canadian definition of homelessness*. Canadian Observatory on Homelessness Press. https://homelesshub.ca/wp-content/uploads/2024/04/COH-Canadian-Definition-of-Homelessness.pdf

Government of British Columbia. (2020, November 30). *Review recommends steps to solve widespread racism in B.C. health care* [News release]. https://news.gov.bc.ca/releases/2020HLTH0330-001976

Government of British Columbia. (n.d.). *First Nations Health Authority*. Retrieved October 24, 2026, from https://www2.gov.bc.ca/gov/content/health/about-bc-s-health-care-system/partners/health-authorities/first-nations-health-authority

Government of Ontario. (2025). *Apply for OHIP and get a health card*. https://www.ontario.ca/page/apply-ohip-and-get-health-card

Government of Ontario. (2026a). *Get coverage for prescription drugs*. https://www.ontario.ca/page/get-coverage-prescription-drugs

Government of Ontario. (2026b). *Get help with high prescription drug costs*. https://www.ontario.ca/page/get-help-high-prescription-drug-costs

Government of Ontario. (2026c). *How to make customer service accessible*. https://www.ontario.ca/page/how-make-customer-service-accessible

Government of the Northwest Territories. (2021, May 26). *GNWT announces changes to Métis Health Benefits Policy* [News release]. https://www.gov.nt.ca/en/newsroom/gnwt-announces-changes-metis-health-benefits-policy

Hallyburton, A. (2022). Diagnostic overshadowing: An evolutionary concept analysis on the misattribution of physical symptoms to pre-existing psychological illnesses. *International Journal of Mental Health Nursing, 31*(6), 1360–1372. https://doi.org/10.1111/inm.13034

Hamilton Health Sciences. (n.d.). *Indigenous Cancer Care Program*. Retrieved October 24, 2026, from https://www.hamiltonhealthsciences.ca/areas-of-care/cancer-care/cancer-services/indigenous-cancer-care-program/

Hart-Wasekeesikaw, F. (2009). *Cultural competence and cultural safety in nursing education: A framework for First Nations, Inuit and Métis nursing*. Aboriginal Nurses Association of Canada. https://hdl.handle.net/10133/719

Health Canada. (2022). *Pulse oximeters: For health care providers*. https://www.canada.ca/en/health-canada/services/drugs-medical-devices/pulse-oximeters/health-care-providers.html

Health Canada. (2023). *Mandatory reporting of serious adverse drug reactions and medical device incidents by hospitals: Guidance document*. https://www.canada.ca/en/health-canada/services/drugs-health-products/medeffect-canada/adverse-reaction-reporting/mandatory-hospital-reporting/drugs-devices/guidance.html

Health Canada. (2024, October 10). *Government of Canada passes legislation for a first phase of national universal pharmacare* [News release]. https://www.canada.ca/en/health-canada/news/2024/10/government-of-canada-passes-legislation-for-a-first-phase-of-national-universal-pharmacare.html

Health Canada. (2026). *National pharmacare bilateral agreements*. https://www.canada.ca/en/health-canada/corporate/transparency/health-agreements/national-pharmacare-bilateral-agreements.html

Housing, Infrastructure and Communities Canada. (2025a). *Everyone Counts 2024: Highlights report part 1 – Enumeration of homelessness* (Cat. No. T94-54/2025-1E-PDF). https://housing-infrastructure.canada.ca/homelessness-sans-abri/reports-rapports/pit-counts-dp-2024-highlights-p1-eng.html

Housing, Infrastructure and Communities Canada. (2025b). *Everyone Counts 2024: Highlights report part 2 – Survey of people experiencing homelessness* (Cat. No. T94-54/2025-2E-PDF). https://housing-infrastructure.canada.ca/homelessness-sans-abri/reports-rapports/pit-counts-dp-2024-highlights-p2-eng.html

Immigration, Refugees and Citizenship Canada. (2026a, January 27). *Changes to the Interim Federal Health Program* [Notice]. https://www.canada.ca/en/immigration-refugees-citizenship/news/notices/changes-ifhp.html

Immigration, Refugees and Citizenship Canada. (2026b). *Guide 5568: Application for Interim Federal Health Program coverage*. https://www.canada.ca/en/immigration-refugees-citizenship/services/application/application-forms-guides/guide-5568-application-interim-federal-health-program-coverage.html

Indigenous and Northern Affairs Canada. (2017, October 6). *Sixties Scoop agreement in principle* [Backgrounder]. https://www.canada.ca/en/indigenous-northern-affairs/news/2017/10/sixties_scoop_agreementinprinciple.html

Indigenous Services Canada. (2026a). *Indian Residential Schools Resolution Health Support Program*. https://sac-isc.gc.ca/eng/1581971225188/1581971250953

Indigenous Services Canada. (2026b, February 19). *Minister Gull-Masty announces new support to empower Inuit and strengthen Northern communities* [News release]. https://www.canada.ca/en/indigenous-services-canada/news/2026/02/minister-gull-masty-announces-new-support-to-empower-inuit-and-strengthen-northern-communities.html

Indigenous Services Canada. (2026c, February 26). *Minister Gull-Masty announces $1.55 billion for Jordan's Principle* [News release]. https://www.canada.ca/en/indigenous-services-canada/news/2026/02/minister-gull-masty-announces-155-billion-for-jordans-principle.html

Indigenous Services Canada. (n.d.-a). *About Indian status*. Retrieved October 24, 2026, from https://sac-isc.gc.ca/eng/1100100032463/1572459644986

Indigenous Services Canada. (n.d.-b). *About the Non-Insured Health Benefits program*. Retrieved October 24, 2026, from https://www.sac-isc.gc.ca/eng/1576790320164

Indigenous Services Canada. (n.d.-c). *Who is eligible for the Non-Insured Health Benefits (NIHB) program for First Nations and Inuit*. Retrieved October 24, 2026, from https://sac-isc.gc.ca/eng/1574187596083/1576511384063

Information and Privacy Commissioner of Ontario. (n.d.). *Collection, use and disclosure of personal health information*. Retrieved October 24, 2026, from https://www.ipc.on.ca/health-organizations/collection-use-and-disclosure-of-personal-health-information/

Inker, L. A., Eneanya, N. D., Coresh, J., Tighiouart, H., Wang, D., Sang, Y., Crews, D. C., Doria, A., Estrella, M. M., Froissart, M., Grams, M. E., Greene, T., Grubb, A., Gudnason, V., Gutiérrez, O. M., Kalil, R., Karger, A. B., Mauer, M., Navis, G., … Levey, A. S. (2021). New creatinine- and cystatin C–based equations to estimate GFR without race. *New England Journal of Medicine, 385*(19), 1737–1749. https://doi.org/10.1056/NEJMoa2102953

Inuit Tapiriit Kanatami. (2018a, March 22). *Inuit release National Inuit Strategy on Research* [News release]. https://itk.ca/newsreleasenisr/

Inuit Tapiriit Kanatami. (2018b, December 10). *Inuit Tuberculosis Elimination Framework released* [News release]. https://itk.ca/?p=11645

Inuit Tapiriit Kanatami. (2026). *World TB Day 2026 in Inuit Nunangat* [Fact sheet]. https://itk.ca/wp-content/uploads/2026/03/ITK_TB-Elimination-Map_World-TB_Day.pdf

Inuit Tapiriit Kanatami. (n.d.-a). *About Canadian Inuit*. Retrieved October 24, 2026, from https://www.itk.ca/about-canadian-inuit/

Inuit Tapiriit Kanatami. (n.d.-b). *Our vision*. Retrieved October 24, 2026, from https://itk.ca/?p=6194

Ishigami, J., Charleston, J., Miller, E. R., III, Matsushita, K., Appel, L. J., & Brady, T. M. (2023). Effects of cuff size on the accuracy of blood pressure readings: The Cuff(SZ) randomized crossover trial. *JAMA Internal Medicine, 183*(10), 1061–1068. https://doi.org/10.1001/jamainternmed.2023.3264

Jenkinson, J. I. R., Hwang, S. W., Strike, C., & Di Ruggiero, E. (2022). "We don't have a good system for people who don't have a home and don't need a hospital": Contextualizing the hospital discharge process for people experiencing homelessness in Toronto, Canada. *SSM – Qualitative Research in Health, 2*, Article 100056. https://doi.org/10.1016/j.ssmqr.2022.100056

Kamel, G. (2021). *Rapport d'enquête concernant le décès de Joyce Echaquan* [Investigation report on the death of Joyce Echaquan] (Dossier 2020-00275). Bureau du coroner du Québec. https://www.coroner.gouv.qc.ca/fileadmin/contenu/Enquêtes_publiques/Joyce_Echaquan/2020-EP00275-9.pdf

Kidney Disease: Improving Global Outcomes CKD Work Group. (2024). KDIGO 2024 clinical practice guideline for the evaluation and management of chronic kidney disease. *Kidney International, 105*(4S), S117–S314. https://doi.org/10.1016/j.kint.2023.10.018

Law Commission of Ontario. (2017). *Legal capacity, decision-making and guardianship: Final report – Executive summary*. https://lco-cdo.org/wp-content/uploads/CG-Executive-Summary-English.pdf

Lee, P., Le Saux, M., Siegel, R., Goyal, M., Chen, C., Ma, Y., & Meltzer, A. C. (2019). Racial and ethnic disparities in the management of acute pain in US emergency departments: Meta-analysis and systematic review. *The American Journal of Emergency Medicine, 37*(9), 1770–1777. https://doi.org/10.1016/j.ajem.2019.06.014

London Health Sciences Centre. (2025). *Indigenous healing and cultural practices* [Policy]. https://www.lhsc.on.ca/media/14288/download

Manitoba Métis Federation. (2021, September 29). *MMF withdraws from MNC: Focus on being the national voice for the Red River Métis* [News release]. https://www.mmf.mb.ca/news/mmf-withdraws-from-mnc-focus-on-being-the-national-voice-for-the-red-river-metis

Manitoba Ombudsman. (2019, March 11). *Recommendations re inquest report for Brian Lloyd Sinclair*. https://www.ombudsman.mb.ca/uploads/document/files/brian-sinclair-final-report-en.pdf

Métis Nation British Columbia. (2024, November 30). *Métis Nation British Columbia withdraws from the Métis National Council* [News release]. https://mnbc.ca/node/4506

Métis National Council. (2025). *Métis Nation data strategy*. https://www.metisnation.ca/wp-content/uploads/2025/12/Consolidated_Me_tis_Nation_Data_Strategy_Final_15_10_2025_3_56.pdf

Métis National Council. (n.d.-a). *About us*. Retrieved October 24, 2026, from https://www.metisnation.ca/about/about-us

Métis National Council. (n.d.-b). *Citizenship*. Retrieved October 24, 2026, from https://www.metisnation.ca/about/citizenship

Métis National Council. (n.d.-c). *Governance*. Retrieved October 24, 2026, from https://www.metisnation.ca/about/governance

Métis Nation–Saskatchewan. (2024, September 19). *Métis Nation–Saskatchewan withdraws from Métis National Council* [News release]. https://mns.ca/uploads/wp-content/uploads/2024/09/Sept-19-2024-MNS-leaves-MNC-.pdf

National Collaborating Centre for Aboriginal Health. (2016). *Culture and language as social determinants of First Nations, Inuit, and Métis health* [Fact sheet]. https://www.ccnsa-nccah.ca/docs/determinants/FS-CultureLanguage-SDOH-FNMI-EN.pdf

National Collaborating Centre for Determinants of Health. (2023). *Let's talk: Health equity* (2nd ed.). St. Francis Xavier University. https://nccdh.ca/images/uploads/NCCDH_Lets_Talk_Health_Equity_EN_June5.pdf

National Inquiry into Missing and Murdered Indigenous Women and Girls. (2019). *Reclaiming power and place: The final report of the National Inquiry into Missing and Murdered Indigenous Women and Girls*. https://www.mmiwg-ffada.ca/final-report/

Nursing Council of New Zealand. (2013). *Bibliographic timeline of the introduction of cultural safety into nursing education in New Zealand 1988–2012*. https://www.nursingcouncil.org.nz/common/Uploaded%20files/Public/Publications/other_reports/NCNZ_Cultural_Safety_Feb_2013.pdf

Nursing Council of New Zealand. (n.d.). *Te Tiriti o Waitangi, Māori health, kawa whakaruruhau, cultural safety: Guidance for nursing education and practice*. Retrieved October 24, 2026, from https://nursingcouncil.org.nz/NCNZ/About-section/Cultural-Safety-Guidance.aspx

Ontario Human Rights Commission. (2016). *Policy on ableism and discrimination based on disability*. https://www.ohrc.on.ca/en/policy-ableism-and-discrimination-based-disability

Ontario Human Rights Commission. (n.d.-a). *Gender identity and gender expression*. Retrieved October 24, 2026, from https://www.ohrc.on.ca/en/your-rights/code-grounds/gender-identify-gender-expression

Ontario Human Rights Commission. (n.d.-b). *Racial discrimination, race and racism (fact sheet)*. Retrieved October 24, 2026, from https://www.ohrc.on.ca/en/racial-discrimination-race-and-racism-fact-sheet

Ontario Ministry of Health & Ontario Health. (2026). *Interprofessional primary care team (IPCT) expansion – 2027-2028 call instructions: Instructions for Indigenous-led providers and teams*. https://www.ontario.ca/files/2026-09/moh-ipct-2027-2028-expansion-call-instructions-indigenous-en-2026-09-28.pdf

Parekh, R. S., Perl, J., Auguste, B., & Sood, M. M. (2022). Elimination of race in estimates of kidney function to provide unbiased clinical management in Canada. *CMAJ, 194*(11), E421–E423. https://doi.org/10.1503/cmaj.210838

Patient Ombudsman. (n.d.). *Before you make a complaint*. Retrieved October 24, 2026, from https://www.patientombudsman.ca/Complaints/Before-You-Make-a-Complaint

Pharmacare Act, S.C. 2024, c. 24. https://laws-lois.justice.gc.ca/eng/acts/P-13.2/page-1.html

Pottie, K., Greenaway, C., Feightner, J., Welch, V., Swinkels, H., Rashid, M., Narasiah, L., Kirmayer, L. J., Ueffing, E., MacDonald, N. E., Hassan, G., McNally, M., Khan, K., Buhrmann, R., Dunn, S., Dominic, A., McCarthy, A. E., Gagnon, A. J., Rousseau, C., … Canadian Collaboration for Immigrant and Refugee Health. (2011). Evidence-based clinical guidelines for immigrants and refugees. *CMAJ, 183*(12), E824–E925. https://doi.org/10.1503/cmaj.090313

Prime Minister of Canada. (2019, March 8). *Statement of apology on behalf of the Government of Canada to Inuit for the management of the tuberculosis epidemic from the 1940s–1960s*. https://www.pm.gc.ca/en/news/2019/03/08/statement-apology-behalf-government-canada-inuit-management-tuberculosis-epidemic

Provincial Court of Manitoba. (2014). *In the matter of The Fatality Inquiries Act and in the matter of Brian Lloyd Sinclair, deceased* [Inquest report]. https://www.manitobacourts.mb.ca/site/assets/files/1051/brian_sinclair_inquest_-_dec_14.pdf

Public Health Agency of Canada. (2018). *Key health inequalities in Canada: A national portrait – Executive summary*. https://www.canada.ca/en/public-health/services/publications/science-research-data/key-health-inequalities-canada-national-portrait-executive-summary.html

Public Health Agency of Canada. (2022). *What makes Canadians healthy or unhealthy?* https://www.canada.ca/en/public-health/services/health-promotion/population-health/what-determines-health/what-makes-canadians-healthy-unhealthy.html

Public Health Agency of Canada. (2025). *Trauma and violence-informed approaches to policy and practice*. https://www.canada.ca/en/public-health/services/publications/health-risks-safety/trauma-violence-informed-approaches-policy-practice.html

Public Health Agency of Canada. (2026a). *Health equity and determinants of health*. https://www.canada.ca/en/public-health/services/health-promotion/population-health/what-determines-health.html

Public Health Agency of Canada. (2026b). *Tuberculosis disease surveillance: TB trends* [Data dashboard]. Health Infobase. https://health-infobase.canada.ca/tuberculosis/epidemiology-report.html

Quinte Health. (2022). *Smudging process* (Policy No. 3.2.22). https://quintehealth.ca/wp-content/uploads/2023/07/3.2.22-Corporate-Smudging-Process.pdf

Rainbow Health Ontario. (n.d.). *What we do*. Retrieved October 24, 2026, from https://www.rainbowhealthontario.ca/about/what-we-do/

Ramsden, I. M. (2002). *Cultural safety and nursing education in Aotearoa and Te Waipounamu* [Doctoral thesis, Victoria University of Wellington]. https://ir.wgtn.ac.nz/items/f23b0721-a705-404b-b5cf-7c4fb9c6c115

Registered Nurses' Association of Ontario. (2026). *Addressing anti-Black racism in nursing* [Best practice guideline]. https://rnao.ca/bpg/guidelines/addressing-anti-Black-racism-in-nursing

Sjoding, M. W., Dickson, R. P., Iwashyna, T. J., Gay, S. E., & Valley, T. S. (2020). Racial bias in pulse oximetry measurement. *New England Journal of Medicine, 383*(25), 2477–2478. https://doi.org/10.1056/NEJMc2029240

Statistics Canada. (2022a). *Housing conditions among First Nations people, Métis and Inuit in Canada from the 2021 Census* (Census in Brief, Catalogue No. 98-200-X2021007). https://www12.statcan.gc.ca/census-recensement/2021/as-sa/98-200-X/2021007/98-200-X2021007-eng.cfm

Statistics Canada. (2022b, September 21). Indigenous population continues to grow and is much younger than the non-Indigenous population, although the pace of growth has slowed. *The Daily*. https://www150.statcan.gc.ca/n1/daily-quotidien/220921/dq220921a-eng.htm

Statistics Canada. (2022c, September 14). *Understanding who we are: Sex at birth and gender of people in Canada*. https://www150.statcan.gc.ca/n1/pub/11-627-m/11-627-m2022049-eng.htm

Statistics Canada. (2025, June 3). *Life expectancy at birth of Indigenous populations in Canada, 2006-2011, 2011-2016 and 2016-2021* (Indigenous Peoples Thematic Series, Catalogue No. 41-20-0002). https://www150.statcan.gc.ca/n1/pub/41-20-0002/412000022025013-eng.htm

Statistics Canada. (2026a, April 29). Canadian Income Survey, 2024. *The Daily*. https://www150.statcan.gc.ca/n1/daily-quotidien/260429/dq260429a-eng.htm

Statistics Canada. (2026b, January 9). Health-adjusted life expectancy in Canada: Recent trends at birth and age 65 years, 2019, 2020 and 2023. *The Daily*. https://www150.statcan.gc.ca/n1/daily-quotidien/260109/dq260109b-eng.htm

Statistics Canada. (n.d.). *Incompletely enumerated reserves and settlements* [2021 Census of Population]. Retrieved October 24, 2026, from https://www12.statcan.gc.ca/census-recensement/2021/ref/iers-repd-eng.cfm

Sullivan, W. F., Diepstra, H., Heng, J., Ally, S., Bradley, E., Casson, I., Hennen, B., Kelly, M., Korossy, M., McNeil, K., Abells, D., Amaria, K., Boyd, K., Gemmill, M., Grier, E., Kennie-Kaulbach, N., Ketchell, M., Ladouceur, J., Lepp, A., … Witherbee, S. (2018). Primary care of adults with intellectual and developmental disabilities: 2018 Canadian consensus guidelines. *Canadian Family Physician, 64*(4), 254–279. https://www.cfp.ca/content/64/4/254

Tervalon, M., & Murray-García, J. (1998). Cultural humility versus cultural competence: A critical distinction in defining physician training outcomes in multicultural education. *Journal of Health Care for the Poor and Underserved, 9*(2), 117–125. https://doi.org/10.1353/hpu.2010.0233

Tjepkema, M., Bushnik, T., & Bougie, E. (2019). Life expectancy of First Nations, Métis and Inuit household populations in Canada. *Health Reports, 30*(12), 3–10. https://doi.org/10.25318/82-003-x201901200001-eng

Truth and Reconciliation Commission of Canada. (2015a). *Honouring the truth, reconciling for the future: Summary of the final report of the Truth and Reconciliation Commission of Canada*. https://ehprnh2mwo3.exactdn.com/wp-content/uploads/2021/01/Executive_Summary_English_Web.pdf

Truth and Reconciliation Commission of Canada. (2015b). *Truth and Reconciliation Commission of Canada: Calls to action*. https://nctr.ca/wp-content/uploads/2021/01/Calls_to_Action_English2.pdf

Turpel-Lafond, M. E. (2020). *In plain sight: Addressing Indigenous-specific racism and discrimination in B.C. health care* (Summary report). Addressing Racism Review. https://engage.gov.bc.ca/app/uploads/sites/613/2020/11/In-Plain-Sight-Summary-Report.pdf

United Nations Declaration on the Rights of Indigenous Peoples Act, S.C. 2021, c. 14. https://laws-lois.justice.gc.ca/eng/acts/u-2.2/FullText.html

United Nations. (2007). *United Nations Declaration on the Rights of Indigenous Peoples* (A/RES/61/295). https://www.un.org/development/desa/indigenouspeoples/wp-content/uploads/sites/19/2018/11/UNDRIP_E_web.pdf

Vogel, L. (2015). Is your hospital culturally safe? *CMAJ, 187*(1), E13. https://doi.org/10.1503/cmaj.109-4953

Wathen, C. N., & Varcoe, C. (2021). *Trauma- & violence-informed care (TVIC): A tool for health & social service organizations & providers*. EQUIP Health Care; Gender, Trauma & Violence Knowledge Incubator. https://gtvincubator.uwo.ca/wp-content/uploads/2025/10/TVIC_Tool_Updated_Oct25.pdf

Wharton, S., Lau, D. C. W., Vallis, M., Sharma, A. M., Biertho, L., Campbell-Scherer, D., Adamo, K., Alberga, A., Bell, R., Boulé, N., Boyling, E., Brown, J., Calam, B., Clarke, C., Crowshoe, L., Divalentino, D., Forhan, M., Freedhoff, Y., Gagner, M., … Wicklum, S. (2020). Obesity in adults: A clinical practice guideline. *CMAJ, 192*(31), E875–E891. https://doi.org/10.1503/cmaj.191707

Wilk, P., Maltby, A., & Cooke, M. (2017). Residential schools and the effects on Indigenous health and well-being in Canada: A scoping review. *Public Health Reviews, 38*, Article 8. https://doi.org/10.1186/s40985-017-0055-6

Women and Gender Equality Canada. (2024). *2SLGBTQI+ terminology: Glossary and common acronyms*. https://www.canada.ca/en/women-gender-equality/free-to-be-me/2slgbtqi-plus-glossary.html

03 Fluids, Electrolytes and Acid–Base Balance

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain how the body regulates water, electrolytes and acid–base balance, including osmosis, antidiuretic hormone, the renin–angiotensin–aldosterone system, the kidneys and the lungs.
2. Recognize, analyze and prioritize cues of fluid volume deficit and excess in adults, especially older adults.
3. Compare common intravenous solutions and apply safe practices for giving intravenous fluids and electrolytes, including concentrated potassium.
4. Explain the causes, manifestations and nursing care of sodium and potassium imbalances, including electrocardiogram changes.
5. Describe calcium, magnesium and phosphate imbalances, including refeeding syndrome.
6. Identify the four primary acid–base disorders from a blood gas and link each to its common causes.
7. Teach patients and families to prevent and recognize fluid and electrolyte problems at home.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 4, 5, 6	Clinician; Scholar	Foundations of Practice
2	Clinician; Coordinator	Foundations of Practice; Collaborative Practice
3	Clinician; Leader	Foundations of Practice; Professional Practice
7	Educator; Communicator	Foundations of Practice; Collaborative Practice

Introduction

Every patient on a medical-surgical unit depends on a stable internal environment. Water, electrolytes and acids must stay within narrow limits for cells, nerves and the heart to work. Illness, surgery, medications and treatments disturb that balance every day. A patient who vomits for two days, an older adult who stops drinking during a heat wave, a patient with heart failure who gains weight, and a patient after bowel surgery receiving intravenous (IV) fluids all need a nurse who can recognize early cues and act before harm occurs.

Nurses play a central part in this work. They measure intake and output, weigh patients, give and monitor IV fluids and electrolytes, interpret laboratory results, and notice early changes in vital signs or mental status. Errors with IV fluids and concentrated electrolytes can cause serious harm, so safe practice also matters.

This chapter begins with how the body regulates fluid (section 3.1), then covers fluid volume deficit and excess (section 3.2) and IV fluids and fluid management (section 3.3). Later sections address sodium, potassium, calcium, magnesium and phosphate imbalances and acid–base balance. Shock is covered in Chapter 6, fluids in sepsis in Chapter 4, heart failure in Chapter 18, diabetic emergencies in Chapter 22 and kidney disease in Chapter 27.

3.1 Body Fluids and How They Are Regulated

Total Body Water and Fluid Compartments

Water makes up about 50% to 60% of an adult's body weight (Danziger & Zeidel, 2015). It is held in two main compartments. **Intracellular fluid (ICF)** is the water inside cells, and it accounts for about two-thirds of body water. **Extracellular fluid (ECF)** is

all the water outside cells, about one-third of the total. The ECF has two main parts. **Interstitial fluid** bathes the cells in the tissues and makes up most of the ECF. **Intravascular fluid** is the plasma, the liquid part of blood. Plasma is the smallest compartment, but it maintains blood pressure, so even small losses from it matter.

Water moves freely between compartments. When the body gains or loses pure water (water without sodium), most of the change ends up inside cells, and only a small share stays in the blood vessels (Danziger & Zeidel, 2015).

Osmosis, Osmolality and Tonicity

Osmosis is the movement of water across a membrane from an area of lower solute concentration to one of higher solute concentration. **Osmolality** is the concentration of dissolved particles per kilogram of water, reported in mOsm/kg. A typical adult serum osmolality is about 275 to 295 mOsm/kg, although reference ranges vary by laboratory (University of Ottawa, 2022). Product labels for IV fluids usually report **osmolarity**, the concentration per litre of solution (mOsmol/L).

Tonicity is the effect a fluid has on cell volume. It depends only on solutes that cannot cross cell membranes freely, mainly sodium in the ECF. Urea and, when insulin is present, glucose cross into cells easily, so they add to osmolality but not to tonicity (Danziger & Zeidel, 2015). An **isotonic** fluid has about the same tonicity as plasma, so cells keep their size. A **hypotonic** fluid has a lower tonicity, so water moves into cells and they swell. A **hypertonic** fluid has a higher tonicity, so water moves out of cells and they shrink. Brain cells are especially affected by these shifts, so a change in tonicity can show as headache, nausea, lethargy or seizures (Baxter Corporation, 2018c).

Starling Forces

Fluid exchange between plasma and the interstitial space depends on **Starling forces**. Capillary hydrostatic pressure, the pressure of blood against the vessel wall, pushes fluid out of the capillary. Plasma oncotic pressure, created mainly by albumin and other plasma proteins, holds fluid in the vessel (Woodcock & Michel, 2021). Current research shows that in most tissues, capillaries filter a small amount of fluid out continuously but do not draw much back in. Instead, the lymphatic system returns that fluid to the circulation. **Edema**, excess fluid in the interstitial space, forms when filtration rises, for example from high venous pressure, inflammation or fluid overload, or when lymphatic drainage cannot keep up (Woodcock & Michel, 2021).

Thirst and Antidiuretic Hormone

Special nerve cells in and near the hypothalamus called osmoreceptors sense the tonicity of the blood. When plasma osmolality rises, these cells shrink and send signals that trigger thirst and the release of **antidiuretic hormone (ADH)**, also called vasopressin (Danziger & Zeidel, 2015). ADH is made in the hypothalamus and stored in the posterior pituitary gland. In the kidney's collecting ducts, it causes water channels called aquaporins to move to the cell surface, so more water returns to the blood and the urine becomes more concentrated. When osmolality falls, ADH release stops and the kidneys excrete dilute urine.

Rising osmolality is the most sensitive trigger for ADH. A fall in the blood volume or pressure that the body senses, detected by stretch receptors in the heart, large arteries and kidneys, also increases ADH release. This happens in dehydration and bleeding, and in conditions such as heart failure and cirrhosis, in which the body senses low effective volume even though total body water is high (Danziger & Zeidel, 2015). In those patients, ADH can lower serum sodium by holding on to water.

The Renin–Angiotensin–Aldosterone System

The **renin–angiotensin–aldosterone system (RAAS)** protects blood pressure and sodium balance. Cells in the kidney's afferent arterioles release the enzyme renin when renal blood flow falls, when sympathetic nerves are activated, or when less sodium chloride reaches a sensing area of the nephron (Klabunde, 2022). Renin starts a chain of reactions that produces angiotensin II. Angiotensin II constricts blood vessels, increases sodium reabsorption in the kidney, stimulates thirst and ADH release, and signals the adrenal cortex to release **aldosterone**. Aldosterone causes the kidneys to keep more sodium, and water follows sodium (Klabunde, 2022). Common medications such as angiotensin-converting enzyme (ACE) inhibitors and spironolactone act on this system.

Natriuretic Peptides

The heart has its own counterweight to the RAAS. When the atria or ventricles are stretched by extra volume, heart muscle cells release **natriuretic peptides**: atrial natriuretic peptide (ANP) from the atria and B-type natriuretic peptide (BNP) mainly from the

ventricles. These peptides increase sodium and water excretion, reduce renin release (and therefore angiotensin II and aldosterone), and widen blood vessels (Klabunde, 2023). Their blood levels rise in states of volume excess, so BNP and N-terminal pro-BNP are used as markers of heart failure (Chapter 18).

The Kidneys' Role

The kidneys carry out the instructions of all these systems, adjusting how much water and sodium they return to the blood. A healthy kidney can make small amounts of concentrated urine to save water or large amounts of dilute urine to remove it. Urine output is therefore a key bedside measure, and a falling hourly output can be an early warning of hypovolemia or acute kidney injury (Chapter 27).

Age-Related Changes

With aging, the kidneys become less able to concentrate urine, and thirst weakens, so the signal to drink comes late or not at all (Parkinson et al., 2023). Older adults are also at higher risk of hyponatremia from glucose-containing IV fluids (Baxter Corporation, 2021). Section 3.2 describes how these changes appear in practice.

3.2 Fluid Volume Deficit and Excess

Fluid Volume Deficit

Fluid volume deficit (hypovolemia) is a loss of ECF volume. It may occur alone or with changes in serum sodium. The term **dehydration** is often used loosely, but strictly it means loss of water more than sodium, which raises serum osmolality. Research in older adults uses a directly measured serum osmolality above 300 mOsm/kg as the reference standard for low-intake dehydration (Parkinson et al., 2023).

Causes fall into three groups:

- **Losses:** vomiting, diarrhea, nasogastric suction, drains, fistulas, bleeding, burns, fever and heavy sweating, and excess urine from diuretics or high blood glucose.
- **Poor intake:** nausea, nil-by-mouth orders, swallowing difficulty, cognitive impairment, reduced mobility or lack of help to drink.
- **Third spacing:** a shift of fluid out of the circulation into spaces where it cannot support blood pressure, such as the bowel wall and lumen in bowel obstruction, the abdomen in ascites, or inflamed tissue after burns, pancreatitis or major surgery. Inflammation increases capillary filtration (Woodcock & Michel, 2021), so the patient can be edematous and hypovolemic at the same time.

Fluid Volume Excess

Fluid volume excess (hypervolemia) is too much sodium and water in the ECF. It usually occurs when the body cannot excrete what it takes in. Common causes are heart failure (Chapter 18), acute kidney injury or chronic kidney disease (Chapter 27) and liver cirrhosis (Chapter 26), in which the RAAS and ADH are activated and the kidneys hold on to sodium and water. Excess IV fluid can also cause it in hospital, especially in older or frail patients and those with heart or kidney disease (National Institute for Health and Care Excellence [NICE], 2017a). High sodium intake and some medications, such as corticosteroids, can add to the load.

Recognizing the Cues

No single finding confirms a fluid imbalance. The nurse looks for a pattern across vital signs, physical findings, intake and output, weight and laboratory results (Table 3.1).

In hypovolemia, the heart rate rises to maintain cardiac output, and blood pressure falls later. **Orthostatic hypotension** is a fall in systolic blood pressure of at least 20 mm Hg, or diastolic pressure of at least 10 mm Hg, within 3 minutes of standing (Fedorowski et al., 2017). A rise in pulse of 30 beats/min or more on standing, or dizziness so severe that the patient cannot stand, suggests a large blood loss (McGee et al., 1999). The nurse measures orthostatic vital signs only when it is safe to do so, with help nearby, because

the patient may faint. Moist mucous membranes argue against hypovolemia, while a dry axilla supports it (McGee et al., 1999). Urine becomes scant and concentrated, and weight falls.

Some popular signs are weak. Capillary refill time and skin turgor have not been shown to detect hypovolemia in adults (McGee et al., 1999), and skin turgor is not accurate in older adults, whose skin loses elasticity with age (Parkinson et al., 2023). A systematic review of 67 bedside tests in older adults found that no single test was reliable, so the nurse combines findings (Hooper et al., 2015). Mental status matters: dehydration is a risk factor for delirium, so new confusion, drowsiness or agitation in an older adult calls for a check of fluid status (Registered Nurses' Association of Ontario [RNAO], 2016).

Figure 3.1 Pitting edema of the lower leg: pressing with a finger leaves dents that fill slowly. (credit: “Oedema, finger marks” by John Campbell/Flickr, public domain)

In hypervolemia, weight rises, often before edema is visible. **Edema** may be pitting, leaving an indentation after pressure (Figure 3.1), and collects in dependent areas: the ankles and lower legs in a patient who sits or stands, and the sacrum and back in a patient in bed. Swelling can be harder to see on darker skin, so the nurse also looks for taut, shiny skin and deep marks along the sock line, and presses to check for pitting (Mukwende et al., 2020). Fluid in the lungs causes shortness of breath, a faster respiratory rate, crackles on auscultation and falling oxygen saturation. **Jugular venous distension**, visible filling of the neck veins with the head of the bed at 30 to 45 degrees, reflects high venous pressure. Blood pressure may rise, and the pulse may feel full.

Colour changes need care on all skin tones. Pallor and cyanosis are harder to see on darker skin. The nurse checks the conjunctivae and palms for pallor and the oral mucous membranes for cyanosis, and compares findings with the patient's usual colour (Mukwende et al., 2020).

Laboratory Findings

Laboratory results support the clinical picture:

- **Urine specific gravity** reflects urine concentration. A typical range is 1.005 to 1.030 (University Health Network, n.d.). It rises in hypovolemia as the kidneys conserve water, unless kidney disease or diuretics interfere.
- **Urea** (reported as blood urea nitrogen, BUN, in the United States) is about 2.5 to 8.0 mmol/L in adults, and **creatinine** about 35 to 88 µmol/L in females and 62 to 106 µmol/L in males (University of Ottawa, 2022). In hypovolemia, urea often rises more than creatinine because the kidneys reabsorb more urea when blood flow is low (Malugari et al., 2024). A rising creatinine signals reduced kidney function.
- **Hematocrit**, the proportion of blood made up of red cells, is about 0.38 to 0.50 L/L (University of Ottawa, 2022). It rises when plasma volume falls (hemoconcentration) and falls when plasma is diluted.
- **Serum osmolality** rises with water loss and falls with water excess.

All reference ranges vary by laboratory; the nurse uses the range on the patient's report.

Table 3.1 Fluid volume deficit and excess compared (McGee et al., 1999; Mukwende et al., 2020; NICE, 2017a; Parkinson et al., 2023)

Feature	Fluid volume deficit	Fluid volume excess
Common causes	Vomiting, diarrhea, bleeding, diuretics, poor intake, third spacing	Heart failure, kidney failure, cirrhosis, excess IV fluid
Weight	Falls over hours to days	Rises over hours to days, often before edema appears

Feature	Fluid volume deficit	Fluid volume excess
Heart rate and blood pressure	Heart rate rises; blood pressure falls, with orthostatic changes	Blood pressure may rise; pulse may feel full
Breathing and lungs	Lungs clear; breathing may be fast if shock develops	Shortness of breath, crackles, falling oxygen saturation
Neck veins	Flat when lying down	Distended with head raised 30 to 45 degrees
Skin and mucous membranes	Dry mouth and axilla; skin turgor unreliable in older adults	Pitting edema in dependent areas; taut, shiny skin and deep sock marks, which help on darker skin where swelling is harder to see
Urine	Low volume, concentrated, high specific gravity	Volume varies with cause; may be low in kidney or heart failure
Laboratory results	Hematocrit and urea may rise; serum osmolality high if water loss	Hematocrit and serum sodium may fall from dilution
Mental status	Confusion, drowsiness or agitation, especially in older adults	Confusion if sodium falls or oxygenation worsens

Nursing Care Using Clinical Judgment

The six skills of the Clinical Judgment Measurement Model (see Chapter 1, section 1.4) guide care for both imbalances.

Recognize and analyze cues. Accurate measurement comes first. The nurse records all intake (oral fluids, tube feeds, IV fluids, IV medications and flushes) and all output (urine, vomit, drainage, stool if liquid) and totals them each shift. **Daily weights** are a key bedside measure of change in body fluid over a short period. Because 1 L of water weighs about 1 kg, a change of 1 kg in a day mostly reflects fluid gained or lost. To be useful, weights must be taken at the same time each day (usually early morning before breakfast), on the same scale, with similar clothing and bedding. The nurse compares the weight with the previous day's, not just with the admission weight, and reports a change that meets the prescriber's parameters.

Prioritize hypotheses and generate solutions. The nurse asks which problem is most urgent: is circulation threatened, or are the lungs filling with fluid? Expected outcomes might be a heart rate under 100, stable blood pressure without orthostatic symptoms, urine output at or above the ordered minimum, clear lungs and a stable weight.

Take action for a deficit. Mild deficits are treated by mouth when possible. The nurse offers drinks the patient likes, at regular times, within reach, and helps patients who cannot drink without assistance. If oral intake is not enough, the prescriber orders IV fluids (section 3.3) and the nurse gives them as ordered. The nurse also treats the cause, as ordered, for example with antiemetics, and plans safety measures, because orthostatic hypotension and confusion raise the risk of falls.

Take action for an excess. The prescriber may order a fluid restriction, sodium restriction and a diuretic. The nurse spreads restricted fluid across the day, offers ice chips and mouth care for thirst, and counts all fluids, including those with medications. Raising the head of the bed eases breathing. Edematous skin breaks down easily, so the nurse repositions the patient regularly, supports swollen limbs and inspects pressure points (Chapter 35).

Diuretics are the main drugs for fluid excess. Loop diuretics such as furosemide act quickly and strongly. They can cause low potassium, sodium, magnesium and calcium, and an overly brisk diuresis can lower blood pressure, on standing or suddenly (JAMP Pharma Corporation, 2022). The nurse checks blood pressure and electrolyte results before giving a dose, watches urine output and weight afterward, and reports ringing in the ears, which has been reported with furosemide (JAMP Pharma Corporation, 2022). Electrolyte effects of diuretics are discussed in later sections of this chapter.

Evaluate outcomes and escalate. The nurse checks whether the plan is working: vital signs, urine output, lung sounds, weight and mental status. Every nurse who notices deterioration acts at once. Warning signs include a rising heart rate with falling blood pressure, urine output below the ordered minimum, new or worsening confusion, increasing shortness of breath, falling oxygen saturation or new crackles. The nurse stays with the patient, gets help, and reports using SBAR (Situation, Background, Assessment, Recommendation), calling the rapid response team when criteria are met (Chapter 6). A practical nurse (PN), called a registered practical nurse (RPN) in Ontario, consults the registered nurse (RN) as the patient's needs change.

CLINICAL JUDGMENT

An Older Adult With Dehydration

Mrs. Hélène Bouchard, 86, is admitted to a medical unit from home after a week of hot weather. She lives alone and takes hydrochlorothiazide for hypertension.

- **Recognize cues:** Her heart rate is 108 and blood pressure 104/62 lying. On standing with help, her blood pressure falls to 84/52 and she feels faint. Temperature is 37.4 °C. Her mouth and axillae are dry. Her daughter says she is "not herself" and has been mixing up the days. She has passed 120 mL of dark urine in 4 hours. Her weight is 54.2 kg. Results: sodium 147 mmol/L, urea 14.8 mmol/L, creatinine 128 µmol/L (82 µmol/L three months ago), hematocrit 0.47 L/L, serum osmolality 312 mOsm/kg.
- **Analyze cues:** Tachycardia, orthostatic hypotension, low urine output, a high osmolality and a urea raised out of proportion to the creatinine point to fluid volume deficit with water loss. New confusion suggests delirium.
- **Prioritize hypotheses:** Hypovolemia with possible acute kidney injury (her creatinine is about 1.5 times her last known value) is the priority. Delirium and falls are linked risks. Infection is less likely but stays on the list.
- **Generate solutions:** Goals are a heart rate under 100, no orthostatic symptoms, urine output at or above the ordered minimum and a return to her usual thinking.
- **Take action:** The nurse reports to the prescriber using SBAR. The prescriber orders an IV crystalloid bolus, then a maintenance infusion, holds the hydrochlorothiazide and orders repeat blood work. The nurse starts strict intake and output, daily weights, delirium screening and falls precautions, and offers drinks every hour while awake.
- **Evaluate outcomes:** Four hours later, her heart rate is 92, blood pressure 118/66 lying, and urine output 45 mL/h. She is calmer but still unsure of the date. The nurse continues monitoring and follows up the repeat results.

LIFESPAN CONSIDERATIONS

Older Adults and Fluid Balance

Older adults are the group most at risk of fluid volume deficit. Thirst weakens with age, and the kidneys cannot concentrate urine as well, so water is lost even when intake is low (Parkinson et al., 2023). Diuretics, limited mobility, cognitive impairment, fear of incontinence and needing help to drink add to the risk (Parkinson et al., 2023).

Extreme heat is a particular danger. Health Canada (2024) lists older adults among the groups most affected and names drug classes that reduce the body's ability to cope with heat, including diuretics, ACE inhibitors, beta blockers and antipsychotics. In British Columbia's 2021 extreme heat event, 619 deaths were identified as heat-related; 67% of those who died were 70 or older, 56% lived alone, and 98% died indoors (Government of British Columbia, 2022).

Dehydration is a recognized risk factor for delirium (RNAO, 2016). New confusion in an older adult calls for assessment of fluid status, not an assumption of dementia (Chapter 8).

PATIENT EDUCATION

Daily Weights and Fluid Limits at Home

Patients with heart failure, kidney disease or liver disease may be asked to weigh themselves at home. The nurse teaches:

- Weigh yourself every morning before breakfast, on the same scale, wearing similar clothing. Write the number down.
- Compare today's weight with yesterday's. A quick gain usually means your body is holding fluid, before you see swelling.
- Call your care team if your weight goes above the limit they gave you. British Columbia's heart failure zones guide tells patients to call their health care provider if they gain more than 2 kg (4 lb) over 2 consecutive days or more than 2.5 kg (5 lb) in 1 week (Guidelines and Protocols Advisory Committee, 2023). Follow the numbers your own team gives you.
- If you have a fluid limit, measure your cups so you know how much they hold. Count soup, ice and other foods that melt.
- Call 9-1-1 if you have severe trouble breathing.

The nurse uses teach-back to check understanding (see Chapter 1, section 1.7). Chapter 18 describes heart failure self-care in detail.

3.3 IV Fluids and Fluid Management

Why IV Fluids Are Given

IV fluids are prescribed like medications. They have benefits and risks, and each needs an order that states the type of fluid, the rate and the volume (NICE, 2017a). They are given only when a patient's needs cannot be met by mouth or by feeding tube, and stopped as soon as possible (NICE, 2017a). This chapter draws on NICE's guideline from the United Kingdom because it gives a clear framework for IV fluid therapy in adults in hospital. The guideline organizes IV fluid therapy around five purposes, called the 5 Rs (NICE, 2017a):

- **Resuscitation:** rapid restoration of circulating volume in a patient with signs of hypovolemia, such as a systolic blood pressure below 100 mm Hg, heart rate above 90 beats/min, or capillary refill longer than 2 seconds or cold extremities.
- **Routine maintenance:** meeting daily needs for water, electrolytes and some glucose in a patient who cannot eat or drink.
- **Replacement:** making up existing deficits or ongoing losses, such as from vomiting, drains or a stoma.
- **Redistribution:** managing fluid in patients whose fluid has shifted, such as those with edema, sepsis or kidney, liver or heart disease. These patients often need expert input.
- **Reassessment:** regular review of the patient's fluid status and of the plan.

The nurse uses these purposes to understand an order and to judge whether the patient's response is what the prescriber intended.

Crystalloids

Crystalloids are solutions of water with electrolytes, glucose or both. They are grouped by tonicity (Table 3.2).

Isotonic crystalloids stay in the ECF and expand both the interstitial and intravascular spaces. They are used for resuscitation and replacement. **0.9% sodium chloride** (normal saline) contains 154 mmol/L of sodium and 154 mmol/L of chloride (Omega Laboratories, 2020). Its chloride content is higher than plasma's, and hyperchloremic metabolic acidosis has been reported with similar products (Omega Laboratories, 2020). **Ringer's lactate** provides, per litre, 130 mmol of sodium, 109 mmol of chloride, 4 mmol of potassium, 1.4 mmol of calcium and 28 mmol of lactate, which the body converts to bicarbonate (Baxter Corporation, 2018d). **Balanced solutions** such as Plasma-Lyte A have an electrolyte content closer to plasma; Plasma-Lyte A contains sodium 140 mmol/L, potassium 5 mmol/L, magnesium 1.5 mmol/L, chloride 98 mmol/L, and acetate and gluconate as buffers (Baxter Corporation, 2019a). NICE (2017a) recommends a crystalloid with 130 to 154 mmol/L of sodium for resuscitation, given as a 500 mL bolus in under 15 minutes, followed by reassessment.

Dextrose solutions provide water and some calories. 5% dextrose in water is isotonic in the bag, but once the body uses the glucose, what remains is free water. It is therefore physiologically hypotonic and can lower serum sodium (Baxter Corporation, 2021). It is not used for resuscitation (NICE, 2017a).

Hypotonic crystalloids, such as **0.45% sodium chloride** (sodium 77 mmol/L), move water into cells (Baxter Corporation, 2018b). Hypotonic and dextrose-containing fluids are used in some maintenance regimens, with close monitoring of sodium. Combinations such as 5% dextrose in 0.45% sodium chloride are hypertonic in the bag (406 mOsmol/L, above the normal range of about 280 to 310 mOsmol/L) but hypotonic once the glucose is used (Baxter Corporation, 2018c).

Hypertonic crystalloids, such as **3% sodium chloride** (sodium 513 mmol/L), draw water out of cells (Baxter Corporation, 2018a). They are used for severe, symptomatic hyponatremia (see the sodium section later in this chapter). The Canadian monograph warns that the solution can damage veins and recommends a large central vein. It also warns that rapid correction of sodium can cause serious neurologic harm (Baxter Corporation, 2018a). Accreditation standards limit where concentrated sodium chloride is stocked, and hospital policy restricts where and how 3% sodium chloride is given (Accreditation Canada, 2021).

Colloids

Colloids contain large molecules that stay mostly in the blood vessels and raise plasma oncotic pressure. **Albumin**, made from pooled human plasma, is a colloid that comes as 5% and 25% solutions. The 5% solution is about isotonic with plasma, while the 25% solution is hyperoncotic, with about four times the oncotic effect of plasma (CSL Behring Canada, 2025). Its uses include

restoring blood volume, shock and burns. During hypovolemia, crystalloids restore volume nearly as well as colloids (Woodcock & Michel, 2021), and NICE (2017a) advises against tetrastarch for resuscitation. Albumin can cause circulatory overload, so the nurse monitors blood pressure, pulse, lung sounds and urine output and stops the infusion at the first signs of overload (CSL Behring Canada, 2025).

Table 3.2 Common IV solutions (Baxter Corporation, 2018a, 2018b, 2018c, 2018e, 2019a, 2021; CSL Behring Canada, 2025; NICE, 2017a; Omega Laboratories, 2020)

Solution	Tonicity	Common uses	Nursing cautions
0.9% sodium chloride	Isotonic	Resuscitation and replacement	Fluid overload; high chloride with large volumes can cause metabolic acidosis
Ringer's lactate	Close to isotonic (272 mOsmol/L, slightly below plasma)	Resuscitation, replacement, surgery and burns	Contains potassium and calcium; do not give with ceftriaxone in the same line; caution in severe liver disease
Plasma-Lyte A (balanced solution)	Isotonic	Resuscitation and replacement	Contains potassium; caution in kidney failure and with potassium-sparing drugs
5% dextrose in water	Isotonic in the bag; hypotonic once glucose is used	Source of water and some calories	Not for resuscitation; can lower sodium and raise glucose
0.45% sodium chloride	Hypotonic	Maintenance in some regimens; diluent	Can lower sodium; risk of cerebral edema; watch for headache, nausea, confusion
5% dextrose in 0.45% sodium chloride	Hypertonic in the bag; hypotonic once glucose is used	Maintenance in some regimens	Hyponatremia with high volumes; hyperglycemia; do not run with blood
3% sodium chloride	Hypertonic	Severe symptomatic hyponatremia	High-alert; central line recommended; frequent sodium checks; too-rapid correction causes neurologic harm
Albumin 5% or 25%	Colloid (25% is hyperoncotic)	Blood volume restoration, shock, burns	Made from human plasma; circulatory overload; stop at first signs of overload

Monitoring Patients Receiving IV Fluids

Patients receiving IV fluids need their fluid status, urea, creatinine and electrolytes, and fluid balance charts reviewed at least daily, and more often when the patient's condition calls for it (NICE, 2017a). At the bedside the nurse:

- checks vital signs, mental status and oxygen saturation at the frequency ordered or set by policy;
- listens to lung sounds and looks for edema and jugular venous distension;
- totals intake and output and weighs the patient as ordered;
- reviews electrolyte, glucose, urea and creatinine results and reports values outside the ordered parameters;
- confirms that the infusion matches the order: right fluid, right rate and right volume, on a pump where policy requires one (Figure 3.2).

Risks of IV Fluid Therapy

Fluid overload. Large volumes or rapid infusions can cause hypervolemia, with pulmonary and peripheral edema (Baxter Corporation, 2018d). Older and frail adults and those with heart or kidney disease are at highest risk. NICE (2017a) suggests lower maintenance volumes for these groups. New shortness of breath, crackles, a falling oxygen saturation or rapid weight gain call for prompt action and escalation.

Hyponatremia from hypotonic fluids. Many hospitalized patients, especially after surgery, release ADH for reasons other than osmolality (non-osmotic ADH release), so they cannot excrete free water normally (Baxter Corporation, 2018c). Giving hypotonic or dextrose-containing fluids to these patients can lower sodium quickly. Acute hyponatremia can cause brain swelling, with headache, nausea, vomiting, lethargy and seizures, and can lead to permanent brain injury (Baxter Corporation, 2018c). Children, older adults,

women and postoperative patients are at higher risk (Baxter Corporation, 2018c). NICE (2017a) notes that prescribing more than 2.5 L of maintenance fluid a day increases the risk. Any new headache, nausea or confusion in a patient on IV fluids should prompt the nurse to check the sodium result and report.

Infiltration and extravasation. Infiltration occurs when IV fluid leaks into the tissue around the vein, usually because the catheter has moved or the vein is damaged. **Extravasation** is leakage of a drug or solution that can damage tissue, such as concentrated potassium, hypertonic solutions or some chemotherapy drugs (Baxter Corporation, 2018a, 2019b; RNAO, 2021). Signs include swelling, coolness, tightness, pain or burning at the site and an infusion that slows. On darker skin, redness may not be visible, so the nurse compares the site with the other limb for swelling, warmth or coolness and firmness. If infiltration or extravasation is suspected, the nurse stops the infusion (Baxter Corporation, 2019a), assesses the site and follows policy, which may include removing the catheter, elevating the limb and notifying the prescriber.

Figure 3.2 An electronic infusion pump delivers IV fluid at a set rate. The nurse checks the fluid, rate and volume on the pump against the order. (credit: "Electronic infusion device (EID)" by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

IV Site Care

The nurse assesses the peripheral IV site regularly (Figure 3.3). RNAO (2021) recommends a peripheral IV care protocol that includes at least a daily review of the device by health providers, together with patients and families. The nurse looks for redness, cording, swelling or pain that suggests **phlebitis**, inflammation of the vein, or infiltration. The nurse avoids areas of flexion where possible and does not use peripheral catheters for solutions with an osmolarity above 900 mOsmol/L or continuous vesicant therapy (RNAO, 2021). The nurse teaches the patient to report pain, swelling or leaking at the site (RNAO, 2021). Chapter 4 describes infection prevention for vascular access devices.



Figure 3.3 A peripheral IV catheter in the forearm, held in place with a clear dressing so the site can be seen. The nurse looks at the site and the skin around it at every assessment. (credit: "Peripheral intravenous (IV) catheter (PIV)" by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

SCOPE IN PRACTICE

Who Starts, Adjusts and Gives IV Fluids and Electrolytes

The College of Nurses of Ontario (CNO) Scope of Practice standard asks nurses to consider authority, competence and context (see Chapter 1, section 1.3).

- **Authority:** Inserting a peripheral IV is a procedure below the dermis, and giving IV fluids and drugs is administering a substance by injection. RNs and RPNs are authorized to perform both controlled acts with an order or directive, and cannot initiate them in a public hospital (CNO, 2025b). Nurses accept only orders that are clear, complete and appropriate, and follow up with the prescriber when an order is not (CNO, 2025a). "KCl 40 mmol IV now" is incomplete: it gives no diluent or rate (Institute for Safe Medication Practices Canada [ISMP Canada], 2005).
- **Competence:** The nurse needs the knowledge, skill and judgment for the specific activity, including the drug's purpose, risks and monitoring (CNO, 2025a). Many employers require extra education before nurses insert IVs, use central lines, give IV push drugs or manage high-alert infusions. These are employer requirements, not CNO rules.
- **Context:** The nurse considers whether the practice setting has the resources to support safe care. Employer policy may limit, but never widen, scope (CNO, 2025b). An RPN consults the RN as needs change; any nurse who notices deterioration acts at once. Rules differ by province or territory. Revised CNO standards take effect March 1, 2027 (CNO, 2026).

CLINICAL SAFETY

Concentrated Potassium Is a High-Alert Medication

IV potassium is a high-alert medication (see Chapter 1, section 1.6). Too much, given too fast, can cause life-threatening hyperkalemia and cardiac arrest, which may develop with no warning symptoms (Baxter Corporation, 2019b).

- **Never IV push.** Potassium salts must never be given by IV push (Baxter Corporation, 2018e).
- **Use premixed solutions.** ISMP Canada (2005) recommends standardized premixed potassium solutions on nursing units, stored apart from plain IV fluids, and oral potassium whenever possible.
- **Concentrates stay out of patient care areas.** Accreditation Canada's Required Organizational Practice (ROP) on concentrated electrolytes limited formats such as potassium salts of 2 mmol/mL or more in patient care areas, allowing them only where a committee approved them with safeguards (Accreditation Canada, 2021). In the 2024 ROPs, this practice is consolidated into the ROP on managing high-alert medications, and the former stand-alone ROP is being phased out (*2024 Required Organizational Practices*, 2024; Health Standards Organization, 2024). Hospital policy names the products kept on each unit.
- **Infusion pump.** Give IV potassium only by a calibrated infusion device, slowly and at a controlled rate (Baxter Corporation, 2019b).
- **Rate and concentration.** The monograph for premixed potassium chloride in 0.9% sodium chloride states that infusion rates generally stay at or below 10 mmol/h and 120 mmol/day, and that without cardiac monitoring the rate should not go above 20 mmol/h (Baxter Corporation, 2018e). Other monographs give different limits. Higher concentrations are given by central line (Baxter Corporation, 2019b). Hospital policy sets the limits for each unit.
- **Double check.** Perform an independent double check as policy requires, and check the site often for pain or infiltration.

3.4 Sodium Imbalances

Sodium is the main cation of the extracellular fluid (ECF). Serum sodium mostly reflects water relative to sodium, so a sodium disorder is usually a water disorder (Yun et al., 2023; section 3.1). A typical adult serum sodium is about 136 to 144 mmol/L, although reference ranges vary by laboratory (University of Ottawa, 2022). Because water follows solute across cell membranes, sodium changes alter cell volume, and the brain, enclosed in the skull, is most at risk.

Hyponatremia

Hyponatremia is a serum sodium below the reference range. The European clinical practice guideline grades it as mild (130 to 135 mmol/L), moderate (125 to 129 mmol/L) or profound (below 125 mmol/L) (Spasovski et al., 2014). As serum sodium falls, water moves into cells and brain cells swell.

The guideline sorts causes by the patient's ECF volume, which the nurse assesses using the cues in section 3.2 (Spasovski et al., 2014):

- **Low ECF volume:** vomiting, diarrhea, third spacing, adrenal insufficiency and diuretics.
- **Normal ECF volume:** SIADH (described next), secondary adrenal insufficiency, hypothyroidism and unrecognized diuretic use.

- **High ECF volume:** heart failure (Chapter 18), cirrhosis (Chapter 26) and nephrotic syndrome, in which the body holds water as well as sodium.
- **Too much water for the solute taken in:** very high water intake or a very low-solute diet. In hospital, prescribing more than 2.5 litres of IV fluid a day increases the risk (National Institute for Health and Care Excellence [NICE], 2017a). Hypotonic solutions such as 0.45% sodium chloride can cause acute hyponatremia with brain swelling, especially in older adults and after surgery (Baxter Corporation, 2018b; section 3.3).

In the **syndrome of inappropriate antidiuretic hormone secretion (SIADH)**, which the guideline calls the syndrome of inappropriate antidiuresis, antidiuretic hormone (ADH; section 3.1) keeps acting even though the plasma is dilute. The kidneys keep reabsorbing water, the urine stays concentrated, and the patient looks neither dry nor overloaded. Triggers common on medical-surgical units include pneumonia and small cell lung cancer (Chapter 13), stroke, head injury and subarachnoid hemorrhage, and drugs such as selective serotonin reuptake inhibitor (SSRI) antidepressants, carbamazepine, opioids and some cancer drugs. Nausea, pain, stress and general anesthesia are strong non-specific stimuli, so SIADH is a risk after surgery (Spasovski et al., 2014). It is a diagnosis of exclusion. Typical findings are a serum osmolality below 275 mOsm/kg, urine osmolality above 100 mOsm/kg, urine sodium above 30 mmol/L and a normal volume status, with no adrenal, thyroid, pituitary or kidney cause and no recent diuretic use (Spasovski et al., 2014).

Diuretics often contribute, and patients do not always know they take one (Spasovski et al., 2014). The Canadian monograph for hydrochlorothiazide warns that dilutional hyponatremia may occur in patients with edema in hot weather (Sanis Health, 2026).

Manifestations depend on how low the sodium is and how fast it fell. The guideline lists nausea without vomiting, confusion and headache as moderately severe symptoms, and vomiting, cardiorespiratory distress, deep somnolence, seizures and coma as severe symptoms (Spasovski et al., 2014). In an older adult, new confusion may be the first cue.

Diagnostics include serum sodium and osmolality, urine osmolality (the guideline's first step), urine sodium, and tests to exclude thyroid and adrenal causes (Spasovski et al., 2014).

Nursing Care for Hyponatremia

The nurse applies the CJMM (Chapter 1, section 1.4):

- **Recognize and analyze cues:** level of consciousness, orientation, headache, nausea and vomiting; volume status; the medication list (thiazides, SSRIs, carbamazepine, opioids); and all oral and IV intake.
- **Prioritize:** severe or moderately severe symptoms are an emergency that needs immediate treatment, whatever the cause (Spasovski et al., 2014; Society for Endocrinology, 2022). The nurse stays with the patient, gets help, reports using SBAR and calls the rapid response team if criteria are met (Chapter 6). A PN consults the RN as the patient's needs change.
- **Generate solutions and act:** for severe symptoms, the prescriber orders small boluses of 3% hypertonic saline with close monitoring, aiming for a rise of about 5 mmol/L in the first hour (Society for Endocrinology, 2022). Without severe symptoms there is time to find and treat the cause: volume replacement for losses (section 3.3), stopping a causative drug as ordered, or fluid restriction, the suggested first-line treatment for SIADH (Spasovski et al., 2014). The nurse helps the patient keep to a fluid limit by spreading it over the waking hours, offering mouth care and explaining why it matters. Confused patients need falls precautions (Chapter 8) and, if seizures are a risk, precautions as policy directs.
- **Evaluate outcomes:** the nurse tracks sodium results at the ordered times, intake and output, and neurologic status, and reports a fast rise at once (see the Clinical Safety box).

Older adults often take several sodium-lowering drugs, so medication review is essential.

> CLINICAL SAFETY
>
> **Correcting Sodium Too Quickly**
>
> When hyponatremia develops slowly, brain cells adapt over about 24 to 48 hours by moving solutes out, so they swell less (Spasovski et al., 2014). Once the brain has adapted, a rise in sodium that is too fast can damage the myelin that insulates nerve fibres: **osmotic demyelination syndrome (ODS)** (Society for Endocrinology, 2022). Signs include altered consciousness, difficulty speaking (dysarthria) and swallowing (dysphagia), limb weakness, and in severe cases coma or a "locked-in" state (Almeida-

Arvizu et al., 2025). Reported risk factors include a sodium below 120 mmol/L, low potassium, chronic alcohol use, malnutrition and liver disease (Almeida-Arvizu et al., 2025).

- **Know the limits:** expert guidance sets a limit on the rise in sodium: at most 10 mmol/L in the first 24 hours and at most 8 mmol/L in each later 24 hours (Society for Endocrinology, 2022). These are limits, not targets.
- **Monitor:** sodium at the ordered intervals (one guidance suggests 6 hours, 12 hours, then daily), strict intake and output, and a sudden rise in dilute urine output, which can signal a rapid sodium rise (Society for Endocrinology, 2022).
- **Escalate:** report a rise nearing the limit at once. The prescriber may stop treatment and order hypotonic fluid, with or without desmopressin (Society for Endocrinology, 2022).

Hypernatremia

Hypernatremia is a serum sodium above the reference range, defined in one review as above 145 mmol/L. It usually means the body has too little water for its sodium, which makes the ECF hyperosmolar and draws water out of cells (Yun et al., 2023).

- **Water loss not replaced:** water can be lost through the kidneys or other routes. People who depend on others for drinks, such as a person with advanced dementia, after a stroke, or under sedation, are at greatest risk. Older adults are also at risk because thirst perception declines with age-related changes in brain osmoreceptors (Yun et al., 2023).
- **Kidney water loss:** central or nephrogenic diabetes insipidus (Chapter 23), and osmotic diuresis from high blood glucose (Chapter 22) (Yun et al., 2023).
- **Sodium gain:** less often, from hypertonic sodium-containing treatments or accidental sodium loading (Yun et al., 2023).

Manifestations range from thirst, weakness, muscle irritability, brisk reflexes and lethargy to confusion, seizures and coma. When hypernatremia develops within 48 hours, brain cells shrink quickly and the stretched blood vessels can rupture and bleed (Yun et al., 2023).

Nursing care focuses on replacing water as ordered (by mouth, as free water through a feeding tube, or as an IV hypotonic or dextrose solution; section 3.3) and treating the cause. For chronic hypernatremia (present more than 48 hours or of unknown duration), one review advises lowering sodium by less than 0.5 mmol/L per hour (12 mmol/L per day), with repeated sodium measurements to guide treatment (Yun et al., 2023). The nurse offers fluids often to patients who cannot get their own, records intake and output and daily weights, monitors neurologic status, gives frequent mouth care and reports new confusion or seizures at once. Prevention matters most: a hydration plan for every dependent patient, and extra attention during extreme heat (section 3.2).

3.5 Potassium Imbalances

Potassium is the main cation inside cells. The gradient between high intracellular and low extracellular potassium sets the electrical state of nerve and muscle cells, so small changes in serum potassium can disturb muscle strength and heart rhythm. A typical adult serum potassium is about 3.5 to 5.1 mmol/L, although ranges vary by laboratory (University of Ottawa, 2022). Platelets release potassium as blood clots, so a serum result reads about 0.2 to 0.5 mmol/L above a plasma result; this is one reason laboratories set different ranges for each sample type (Alberta Health Services, 2013).

Hypokalemia

Hypokalemia is a serum potassium below the reference range; a level below 2.5 mmol/L is severe and can be life-threatening (Kardalas et al., 2018). Causes include:

- **Kidney loss:** loop and thiazide diuretics are a common cause (Kardalas et al., 2018; see the Medications box).
- **Gastrointestinal loss:** vomiting and diarrhea.
- **Shift into cells:** insulin, sympathetic stimulation and thyrotoxicosis move potassium from the blood into cells (Kardalas et al., 2018). Refeeding has the same effect (section 3.6).
- **Low magnesium:** more than half of patients with clinically significant hypokalemia also have a magnesium deficit, and their hypokalemia often resists replacement until magnesium is corrected (Kardalas et al., 2018).

Manifestations include leg cramps, muscle weakness and, in severe cases, ascending paralysis. Constipation, paralytic ileus and respiratory failure are signs of severe hypokalemia, and muscle breakdown (rhabdomyolysis) can occur (Kardalas et al., 2018). On the electrocardiogram (ECG), the ST segment becomes depressed, the T wave flattens, a U wave (a small rounded wave after the T wave) becomes prominent, and the QT interval may lengthen. These changes raise the risk of dysrhythmias, fainting and sudden death (Kardalas et al., 2018; Chapter 16). Low potassium and low magnesium also make digoxin toxicity more likely (Sanis Health, 2026).

Nursing care. The nurse recognizes cues by assessing muscle strength, bowel function, breathing effort and heart rhythm, and reviews the patient's diuretics, digoxin and magnesium result. Potassium should be replaced gradually, by mouth when possible. IV replacement is used when the level is below 2.5 mmol/L or the patient cannot take it orally, with repeated potassium levels and cardiac monitoring as the rate and hospital policy require (Kardalas et al., 2018; Baxter Corporation, 2018e). IV potassium is a high-alert medication; the safety rules are in the Clinical Safety box in section 3.3. The nurse also expects magnesium to be checked and corrected.

Hyperkalemia

Hyperkalemia is a serum potassium above the reference range. The UK Kidney Association guideline defines it as 5.5 mmol/L or higher and grades it as mild (5.5 to 5.9 mmol/L), moderate (6.0 to 6.4 mmol/L) or severe (6.5 mmol/L or higher) (Alfonzo et al., 2026). Causes include:

- **Reduced kidney excretion:** acute kidney injury and chronic kidney disease (Chapter 27); people with diabetes or heart failure are at higher risk.
- **Drugs:** angiotensin-converting enzyme (ACE) inhibitors and angiotensin receptor blockers, spironolactone, amiloride, trimethoprim, nonsteroidal anti-inflammatory drugs (NSAIDs) and potassium supplements (Alfonzo et al., 2026).
- **Other causes:** acidosis and poorly controlled diabetes (Alfonzo et al., 2026), and release of potassium from large numbers of damaged cells, as in tumour lysis syndrome (Emergency Care BC, 2024; Chapter 9).
- **Too much given:** potassium infused too fast (Baxter Corporation, 2019b).

Hyperkalemia can develop quickly and cause no symptoms before a dangerous rhythm (Baxter Corporation, 2019b); some patients report generalized weakness. Typical ECG changes are tall, peaked T waves, flattened P waves and a widened QRS complex (Figure 3.4). Severe hyperkalemia can cause a slow wide-complex rhythm, a sine-wave pattern, ventricular tachycardia and cardiac arrest (Alfonzo et al., 2026). A normal ECG does not rule hyperkalemia out (AA Pharma, 2025).



Figure 3.4 A 12-lead ECG from a patient with a serum potassium of 7.0 mmol/L, showing tall, peaked T waves. (credit: "ECG Hyperkalaemia peaked T waves serum potassium 7.0" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Pseudohyperkalemia

Pseudohyperkalemia is a high potassium result caused by the sample, not the patient. Red cells, platelets or white cells release potassium after the blood is drawn. Causes include hemolysis from a difficult draw or small needle, a prolonged tourniquet, fist clenching, very high platelet or white cell counts, and delays or rough handling in transport (Le & Geary, 2020; Alfonzo et al., 2026). The nurse draws samples gently from a good vein and sends them promptly. An unexpected result is repeated, but the nurse still assesses the patient and reports it. A high potassium with ECG changes is treated as real.

Treating Hyperkalemia

Treatment follows a sequence (Alfonzo et al., 2026):

- **Protect the heart:** IV calcium (calcium gluconate or calcium chloride) is given when ECG changes are present. It counters the effect of high potassium on the heart (SteriMax, 2025) but does not lower the potassium level, so the next steps are still needed.
- **Shift potassium into cells:** IV insulin with glucose (dextrose), with nebulized salbutamol as an add-on. Sodium bicarbonate is not routinely recommended.
- **Remove potassium:** an oral potassium binder such as sodium zirconium cyclosilicate, or dialysis for patients with kidney failure.
- **Monitor:** potassium is rechecked at intervals over the next 24 hours because it can rebound.

The guideline advises an urgent 12-lead ECG for any inpatient with potassium of 6.0 mmol/L or higher, and continuous cardiac monitoring at 6.5 mmol/L or higher or with any ECG change (Alfonzo et al., 2026). Nursing actions include:

- **Calcium:** the Canadian monograph calls for ECG and vital sign monitoring during IV calcium gluconate, a slow rate, and a secure line, because extravasation can cause tissue necrosis. IV calcium is contraindicated in patients taking cardiac glycosides such as digoxin, so the nurse tells the prescriber if the patient takes one (SteriMax, 2025).
- **Insulin with dextrose:** this can cause hypoglycemia, so the nurse checks capillary glucose often for several hours, as ordered (Alfonzo et al., 2026).
- **Binders:** sodium zirconium cyclosilicate starts lowering potassium about an hour after a dose, so it is not an emergency treatment on its own. Each dose contains sodium, so the nurse watches for edema (AstraZeneca Canada, 2026).
- **Prevention:** holding potassium-raising drugs as ordered and reviewing them before discharge.

MEDICATIONS

Diuretics and Potassium

- **Loop diuretic (furosemide):** strong, fast diuresis. It can lower potassium, sodium, magnesium and calcium, and too vigorous a diuresis can cause orthostatic or acute hypotension. Tinnitus and reversible hearing loss have been reported (JAMP Pharma Corporation, 2022).
- **Thiazide diuretic (hydrochlorothiazide):** can cause low potassium and low sodium. It reduces calcium excretion and increases magnesium excretion (Sanis Health, 2026).
- **Potassium-sparing diuretics (spironolactone; amiloride):** conserve potassium and can cause hyperkalemia, especially in older adults, people with diabetes or kidney impairment, and with ACE inhibitors or angiotensin receptor blockers. Patients taking spironolactone avoid potassium supplements, salt substitutes and high-potassium foods unless the prescriber advises otherwise (Pfizer Canada, 2022; AA Pharma, 2025).

Nursing actions:

- Review the potassium and sodium results before giving a dose, and report abnormal values.
- Weigh the patient daily, at the same time and on the same scale (section 3.2).
- Check lying and standing blood pressure, and teach the patient to rise slowly.
- Give doses at a consistent time each day (Sanis Health, 2026), and plan the timing with the patient so that night-time urination does not disrupt sleep.
- Teach the signs to report: muscle cramps or weakness, palpitations, dizziness and ringing in the ears.

PRACTICE STORY

A Weak Morning

Names and details are fictional; this is a composite story.

Nurse: Grace Mensah, RPN. Years in practice: 7. Setting: medical unit, community hospital, Ontario.

Mr. Albert Lachance is 84. He came in four days ago with heart failure, and his IV furosemide was increased two days ago. Yesterday he walked to the bathroom with his walker. This morning he could not lift his legs to swing them out of bed. "My legs feel like rubber," he told me.

His radial pulse was irregular, so I counted his apical pulse for a full minute: 96 and irregular. His blood pressure was 104/62, lower than his usual 128/74. He had not had a bowel movement in three days. His morning blood work had just come back: potassium 2.9 mmol/L, down from 3.6 mmol/L two days ago. His magnesium had not been drawn.

I knew his weakness and new irregular pulse could be his potassium, and that low potassium can lead to dangerous rhythms. I stayed with him, put his call bell in his hand and asked a colleague to find our RN, Sam. When Sam came, I used SBAR (Chapter 6). "Situation: Mr. Lachance in bed 12 has new leg weakness and an irregular apical pulse of 96. Background: he's 84, admitted with heart failure, and his IV furosemide went up two days ago. Assessment: his potassium is 2.9, down from 3.6, his pressure is 104/62 and he's constipated. I'm worried about his rhythm. Recommendation: could you assess him now and call the physician? He may need an ECG, cardiac monitoring, potassium replacement and a magnesium level."

Sam assessed him and called the hospitalist. The orders came quickly: a 12-lead ECG, which showed flattened T waves and U waves, telemetry, oral and IV potassium replacement, a magnesium level, and a review of his furosemide dose. Sam took over the IV potassium. I gave his oral potassium, kept him in bed with the bed alarm on and checked on him every hour.

By evening his potassium was 3.5 mmol/L and he could lift his legs again.

Reflect: Which of my actions were within my scope as an RPN, and at what point did Mr. Lachance's changing condition call for the RN to take over parts of his care? How might employer policy change who gives his IV potassium?

3.6 Calcium, Magnesium and Phosphate

Calcium, magnesium and phosphate share regulation by parathyroid hormone (PTH), vitamin D and the kidneys, so a problem with one often disturbs another. All five electrolytes in this chapter are summarized at the end of this section (Table 3.3).

Calcium

About half of the calcium in plasma is **ionized calcium**, the free, physiologically active form. About 40% travels bound to proteins, chiefly albumin, and about 10% is bound to small anions (Yap & Goldwasser, 2022). A typical adult total calcium is about 2.12 to 2.52 mmol/L and ionized calcium about 1.14 to 1.28 mmol/L, although ranges vary by laboratory (University of Ottawa, 2022).

Because so much calcium travels on albumin, a low albumin lowers the total calcium even when ionized calcium is normal. An albumin-adjusted ("corrected") calcium allows for this, but such estimates often perform poorly and ignore pH (Yap & Goldwasser, 2022). Hydrogen ions reduce calcium binding to albumin, so acidosis raises the ionized fraction and alkalosis lowers it (Yap & Goldwasser, 2022). In critical illness, or when results do not fit, ionized calcium is more reliable.

Hypocalcemia is a calcium below the reference range. In hospital, the most common cause is parathyroid damage during thyroid surgery (Chapter 23). Others include severe vitamin D deficiency, parathyroid surgery, low magnesium, pancreatitis, rhabdomyolysis and large-volume transfusion (Society for Endocrinology Clinical Committee, 2013). In chronic kidney disease, retained phosphate reduces activated vitamin D and leads to hypocalcemia (Sridharan, 2023). Furosemide can also lower calcium (JAMP Pharma Corporation, 2022).

Low calcium makes nerves and muscles overexcitable. Early cues are tingling around the mouth and fingertips; muscle spasm, tetany, laryngeal spasm, seizures, a prolonged QT interval and dysrhythmias can follow. Symptoms usually appear when adjusted calcium falls below about 1.9 mmol/L, depending on how fast it falls (Society for Endocrinology Clinical Committee, 2013). Two bedside signs suggest latent tetany:

- **Chvostek's sign:** twitching of the facial muscles when the facial nerve is tapped. It is less specific than Trousseau's sign (Rehman & Wunder, 2011).
- **Trousseau's sign:** spasm of the hand (the knuckles flex, the finger joints straighten and the thumb draws across the palm) within 3 minutes of inflating a blood pressure cuff above systolic pressure (Figure 3.5). It can be absent in true hypocalcemia and is positive in 1% to 4% of healthy people (Rehman & Wunder, 2011).



Figure 3.5 A re-creation of the hand posture of a positive Trousseau's sign: the wrist and knuckles flex, the fingers straighten and the thumb draws in. (credit: “Trousseau's Sign of Latent Tetany” by Tmdswan/Wikimedia Commons, CC BY-SA 4.0)

Severe or symptomatic hypocalcemia is an emergency, treated with IV calcium gluconate under ECG monitoring, with magnesium checked and corrected (Society for Endocrinology Clinical Committee, 2013). The nurse follows the precautions in section 3.5 (SteriMax, 2025). Milder cases receive oral calcium and vitamin D as ordered. After thyroid or parathyroid surgery, the nurse asks about tingling at every assessment.

Hypercalcemia is a calcium above the reference range. About 90% of cases are due to primary hyperparathyroidism (Chapter 23) or cancer (Chapter 9). Less common causes include thiazides, lithium, excess vitamin D and immobilization (Walsh et al., 2016). Symptoms include thirst, frequent urination, nausea, constipation and confusion; severe hypercalcemia can cause kidney injury, stones, pancreatitis, a shortened QT interval, dysrhythmias and coma. An adjusted calcium above 3.5 mmol/L needs urgent correction (Walsh et al., 2016). Treatment starts with IV 0.9% sodium chloride, then an IV bisphosphonate if needed. The nurse monitors intake and output, weight, lung sounds and mental status, because older adults and people with kidney impairment can become overloaded during rehydration (Walsh et al., 2016; section 3.2).

Magnesium

A typical adult serum magnesium is about 0.74 to 1.03 mmol/L, varying by laboratory (University of Ottawa, 2022).

Hypomagnesemia is common with alcohol use disorder (Chapter 11), diabetes and chronic gastrointestinal disease. Loop and thiazide diuretics, digoxin, aminoglycosides and long-term proton pump inhibitors increase magnesium loss (Bobrowicz et al., 2024). Refeeding also lowers magnesium (see below). Manifestations include numbness, muscle cramps, tetany, seizures and dysrhythmias (Bobrowicz et al., 2024). About half of patients with hypomagnesemia also have hypokalemia, which may not correct until magnesium is replaced. Low magnesium also suppresses PTH, causing hypocalcemia that resists calcium replacement (Bobrowicz et al., 2024). Magnesium is replaced by mouth or, for acute deficiency, as IV magnesium sulfate (Sandoz Canada, 2026).

Hypermagnesemia is a risk whenever magnesium is given, especially to patients with kidney impairment; the Canadian monograph for magnesium sulfate advises caution in impaired kidney function (Sandoz Canada, 2026). Rising levels cause flushing and hypotension, then loss of deep tendon reflexes, respiratory depression and, at very high levels, heart block. Flushing can be hard to see on darker skin, so the nurse also asks about warmth. Before each dose, the monograph advises checking that the patellar reflex is present, respirations are at least 16 per minute and urine output was at least 100 mL in the previous 4 hours. Lost patellar reflexes are an early sign of toxicity; IV calcium gluconate reverses respiratory depression or heart block (Sandoz Canada, 2026). The nurse stops the infusion and reports at once.

Phosphate

A typical adult serum phosphate is about 0.81 to 1.58 mmol/L, varying by laboratory (University of Ottawa, 2022).

Hypophosphatemia occurs especially when a malnourished person starts eating again, and in alcohol use disorder (Fung & Rimmer, 2005). Phosphate is needed for cell energy and for red cells to release oxygen. Severe deficiency can cause muscle weakness, respiratory failure from diaphragm weakness, heart failure, dysrhythmias, red cell breakdown (hemolysis), rhabdomyolysis and seizures. Replacement is oral or IV as ordered; too much IV phosphate can cause low calcium and tetany (Fung & Rimmer, 2005).

Hyperphosphatemia is most often caused by chronic kidney disease, because failing kidneys retain phosphate (Sridharan, 2023). It also occurs when large numbers of cells break down, as in tumour lysis syndrome (Emergency Care BC, 2024; Chapter 9). Phosphate itself causes few symptoms, but calcium falls, so the nurse watches for hypocalcemia. In chronic kidney disease, care includes limiting high-phosphate foods such as soft drinks and processed foods, and taking phosphate binders with meals (Sridharan, 2023; Chapter 27).

Refeeding Syndrome

Refeeding syndrome is a fall of 10% or more in serum phosphate, potassium or magnesium, with or without organ dysfunction, within 5 days of starting or greatly increasing nutrition in a person who has been starved or malnourished (da Silva et al., 2020). Carbohydrate raises insulin, which drives phosphate, potassium and magnesium into cells (Fung & Rimmer, 2005), causing heart failure, dysrhythmias, respiratory failure or death. Thiamine stores are often low as well.

High-risk patients include those with very low body mass index (BMI), recent unintentional weight loss, little or no intake for many days, low prefeeding potassium, phosphate or magnesium, an alcohol or other substance use disorder, an eating disorder such as anorexia nervosa, or past bariatric surgery (NICE, 2017b; da Silva et al., 2020). Prevention is a team task (Chapter 24):

- **Identify risk** at admission with a nutrition screen, and check potassium, phosphate and magnesium before feeding begins.
- **Give thiamine before feeding** begins, or before dextrose-containing IV fluids are started, in a patient at risk (da Silva et al., 2020; NICE, 2017b).
- **Start low and go slow:** feeding starts at a reduced energy level and is increased over several days (NICE, 2017b; da Silva et al., 2020).
- **Monitor:** electrolytes twice a day for the first 3 days when risk is high (da Silva et al., 2020), plus fluid balance, heart rhythm and breathing (NICE, 2017b). The nurse reports falling levels, new edema, shortness of breath or an irregular pulse.

Table 3.3 Electrolyte imbalances at a glance (Alfonzo et al., 2026; Bobrowicz et al., 2024; Fung & Rimmer, 2005; Kardalas et al., 2018; Sandoz Canada, 2026; Society for Endocrinology Clinical Committee, 2013; Spasovski et al., 2014; University of Ottawa, 2022; Walsh et al., 2016; Yun et al., 2023)

Imbalance	Typical adult range (varies by laboratory)	Common causes	Key signs	Nursing actions
Low sodium (hyponatremia)	Sodium 136–144 mmol/L	SIADH, diuretics, heart failure, large volumes of hypotonic fluid, vomiting and diarrhea	Nausea, headache, confusion, seizures	Neurologic checks, fluid restriction if ordered, report a fast rise in sodium
High sodium (hypernatremia)	Sodium 136–144 mmol/L	Water loss not replaced, impaired thirst or access to water, diabetes insipidus, high glucose	Thirst, weakness, lethargy, confusion, seizures	Offer and replace water as ordered, intake and output, lower sodium gradually
Low potassium (hypokalemia)	Potassium 3.5–5.1 mmol/L	Loop and thiazide diuretics, vomiting, diarrhea, insulin, low magnesium	Weakness, cramps, constipation, flat T waves and U waves	Cardiac monitoring, oral replacement when possible, IV safety rules, check magnesium
High potassium (hyperkalemia)	Potassium 3.5–5.1 mmol/L	Kidney injury or disease, potassium-sparing diuretics, ACE inhibitors, acidosis	Often none; weakness, peaked T waves, wide QRS	Cardiac monitoring, IV calcium, insulin with glucose and glucose checks, rule out hemolysis
Low calcium (hypocalcemia)	Total 2.12–2.52 mmol/L; ionized 1.14–1.28 mmol/L	Thyroid or parathyroid surgery, vitamin D deficiency, low magnesium, kidney disease	Tingling, tetany, Chvostek's and Trousseau's signs, long QT	Report tingling, IV calcium with ECG monitoring, check magnesium
High calcium (hypercalcemia)	Total 2.12–2.52 mmol/L; ionized 1.14–1.28 mmol/L	Primary hyperparathyroidism, cancer, thiazides, immobility	Thirst, polyuria, constipation, confusion, short QT	IV rehydration, watch for fluid overload, mobilize as able
Low magnesium (hypomagnesemia)	Magnesium 0.74–1.03 mmol/L	Alcohol use disorder, diuretics, long-term proton pump inhibitors, refeeding	Cramps, tetany, seizures, dysrhythmias; low potassium and calcium	Replace magnesium as ordered, recheck potassium and calcium
High magnesium (hypermagnesemia)	Magnesium 0.74–1.03 mmol/L	IV magnesium, kidney impairment	Flushing, low blood pressure, lost reflexes, slow breathing	Check reflexes, respirations and urine output; stop infusion and report
Low phosphate (hypophosphatemia)	Phosphate 0.81–1.58 mmol/L	Refeeding, alcohol use disorder	Weakness, breathing difficulty, heart failure, hemolysis	Refeeding precautions, replace as ordered, monitor breathing
High phosphate (hyperphosphatemia)	Phosphate 0.81–1.58 mmol/L	Chronic kidney disease, tumour lysis syndrome, excess phosphate replacement	Few direct signs; signs of low calcium	Phosphate binders with meals, diet teaching, watch for low calcium

3.7 Acid–Base Balance

Enzymes, heart muscle and nerve cells work only within a narrow range of hydrogen ion concentration, measured as **pH**. The pH scale runs in the opposite direction to hydrogen ions: as hydrogen ions rise, pH falls. Normal metabolism produces acid every day, so the body must buffer and remove it continuously (Hamm et al., 2015). A blood pH below the normal range is **acidemia** and a pH above it is **alkalemia**. The processes that push pH in those directions are called **acidosis** and **alkalosis**. A patient can have more than one process at once, which is why the pH reflects their combined effect (Farley & Licari, 2019).

How the Body Keeps pH Normal

Three systems work together:

- **Buffers** are chemicals that take up or release hydrogen ions within seconds. The main buffer in the blood is the bicarbonate system: bicarbonate (HCO_3^-) combines with hydrogen ions to form carbonic acid, which breaks down into water and carbon dioxide (CO_2).
- **The lungs** control CO_2, which acts as an acid in the blood. Faster, deeper breathing removes CO_2 and raises pH; slower, shallower breathing retains CO_2 and lowers pH. Changes in breathing begin to alter pH within minutes (Farley & Licari, 2019).
- **The kidneys** control bicarbonate. They reabsorb almost all the bicarbonate filtered from the blood and make new bicarbonate to replace what is used in buffering acids from metabolism (Hamm et al., 2015). The kidneys' response is slow, taking 2 to 4 days to reach its full effect (Farley & Licari, 2019).

An **arterial blood gas (ABG)** measures pH, the partial pressure of carbon dioxide (**$PaCO_2$**), the partial pressure of oxygen (PaO_2) and bicarbonate (HCO_3^-). Typical adult arterial values are a pH of 7.35 to 7.45 and a $PaCO_2$ of 35 to 45 mm Hg (Farley & Licari, 2019; University of Ottawa, 2022), and an HCO_3^- of 22 to 26 mmol/L (Farley & Licari, 2019). Reference ranges vary by laboratory; for example, one Canadian list gives an arterial pH range of 7.38 to 7.46 and an HCO_3^- range of 22 to 27 mmol/L (Medical Council of Canada, 2024). The nurse therefore uses the range on the patient's report. A venous blood gas is sometimes drawn instead; its HCO_3^- and lactate agree well with arterial values only when results are near normal (Farley & Licari, 2019). Oxygenation and PaO_2 are covered in Chapter 12. An ABG sample is arterial (Figure 3.6), so after the puncture the nurse applies firm pressure to the site and checks it and the circulation beyond it, as policy directs.



Figure 3.6 (a) Blood samples in syringes: venous blood is darker and arterial blood brighter red. (b) A blood gas analyzer, which measures pH, blood gases and electrolytes in a small sample of blood. (credit: (a) “Venous and arterial blood rotated and cropped” by Wesalius/Wikimedia Commons, CC BY 4.0; (b) “Cobas221A” by J3D3/Wikimedia Commons, CC BY-SA 3.0)

The Four Primary Disorders

A **respiratory** disorder starts with a change in $PaCO_2$, and a **metabolic** disorder starts with a change in HCO_3^- (Table 3.4).

- **Respiratory acidosis** (high $PaCO_2$) occurs when breathing is too slow or too shallow to remove CO_2. Causes include opioid and benzodiazepine sedation, chronic obstructive pulmonary disease (COPD; Chapter 14), severe asthma or pneumonia, and neuromuscular weakness (Farley & Licari, 2019; Chapter 15).
- **Respiratory alkalosis** (low $PaCO_2$) occurs when breathing removes too much CO_2. Causes include pain, anxiety, fever, pneumonia, pulmonary embolism (Chapter 15) and pulmonary edema (Farley & Licari, 2019). A rising respiratory rate is also an early warning sign of sepsis (Chapter 4).

- **Metabolic acidosis** (low HCO_3^-) occurs when acids build up or bicarbonate is lost. Acids build up in lactic acidosis from poor tissue perfusion (Chapters 4 and 6), diabetic ketoacidosis (Chapter 22) and kidney failure (Chapter 27). Bicarbonate is lost in diarrhea (Farley & Licari, 2019).
- **Metabolic alkalosis** (high HCO_3^-) occurs when acid is lost or bicarbonate is retained, as in vomiting, high nasogastric drainage, loop and thiazide diuretics, and volume depletion (Farley & Licari, 2019).

Table 3.4 The four primary acid–base disorders (Farley & Licari, 2019)

Disorder	pH	Primary change	Common causes	Nursing focus
Respiratory acidosis	Below 7.35	$PaCO_2$ above 45 mm Hg	Opioid or sedative excess, COPD, severe pneumonia, neuromuscular weakness	Sedation level, respiratory rate and depth, airway, escalate early
Respiratory alkalosis	Above 7.45	$PaCO_2$ below 35 mm Hg	Pain, anxiety, fever, pneumonia, pulmonary embolism	Find and treat the cause, assess for hypoxemia and sepsis, coach slow breathing only once serious causes are ruled out
Metabolic acidosis	Below 7.35	HCO_3^- below 22 mmol/L	Lactic acidosis, diabetic ketoacidosis, kidney failure, diarrhea	Perfusion, glucose, urine output, potassium, rapid deep breathing as a cue
Metabolic alkalosis	Above 7.45	HCO_3^- above 26 mmol/L	Vomiting, nasogastric suction, diuretics, volume depletion	Fluid replacement as ordered, potassium, accurate drainage measurement

Identifying the Primary Disorder

The core method has three steps (Farley & Licari, 2019):

1. **Look at the pH.** Below 7.35 is acidemia; above 7.45 is alkalemia.

2. **Look at the $PaCO_2$.** If it is abnormal, a respiratory process is present. A high $PaCO_2$ pushes toward acidosis; a low $PaCO_2$ pushes toward alkalosis.

3. **Look at the HCO_3^-.** If it is abnormal, a metabolic process is present. A low HCO_3^- pushes toward acidosis; a high HCO_3^- pushes toward alkalosis.

The primary disorder is the one that matches the direction of the pH. Two examples:

- A pH of 7.26, $PaCO_2$ of 58 mm Hg and HCO_3^- of 25 mmol/L show acidemia with a high $PaCO_2$ and a normal HCO_3^-: respiratory acidosis.
- A pH of 7.50, $PaCO_2$ of 42 mm Hg and HCO_3^- of 32 mmol/L show alkalemia with a high HCO_3^- and a normal $PaCO_2$: metabolic alkalosis.

If both $PaCO_2$ and HCO_3^- are abnormal, the value that matches the pH is the primary disorder, and the other value usually reflects the body's response. Judging that response is RN-level content (see the Going Deeper box). When results do not fit this simple pattern, or the pH is normal but other values are not, the nurse reports them rather than guessing.

Nursing Care and Escalation

The ABG result supports what the nurse sees at the bedside. The nurse recognizes cues such as a falling level of consciousness, slow or shallow breathing, rapid deep breathing, new confusion, dysrhythmias and changes in potassium. An oxygen saturation that looks normal does not rule out a high $PaCO_2$, especially in a patient receiving oxygen. The nurse analyzes cues by linking the result to the history: a patient who received opioids, a patient with diabetes and high glucose, a patient with heavy nasogastric drainage. Care treats the cause, not the number: reversing opioid oversedation, supporting ventilation, restoring perfusion, treating ketoacidosis or replacing losses. For respiratory disorders, the nurse positions the patient upright, encourages deep breathing and coughing where appropriate, and monitors sedation before giving more opioid. For metabolic disorders, the nurse measures all losses accurately and monitors intake and output, glucose and electrolytes. Older adults have less respiratory and kidney reserve, so they may decompensate faster. Acid–base changes also move potassium. Acidosis can raise serum potassium (Alfonzo et al., 2026), so the

nurse watches the potassium closely as acidosis is corrected. Every nurse who finds a deteriorating patient acts at once and escalates using SBAR and the rapid response team (Chapter 6). A PN consults the RN when ABG results are abnormal or the patient's condition changes.

GOING DEEPER

Interpreting a Blood Gas Fully

Required for RN students; optional for PN students.

Compensation. The body responds to a primary disorder by changing the other system in the opposite direction: the lungs adjust $PaCO_2$ for a metabolic disorder within minutes to hours, and the kidneys adjust HCO_3^- for a respiratory disorder over 2 to 4 days (Farley & Licari, 2019). In metabolic acidosis, the $PaCO_2$ falls; in chronic respiratory acidosis, the HCO_3^- rises. When pH is still abnormal but the other value has begun to move, compensation is partial. Published formulas predict the expected compensation (Farley & Licari, 2019).

Mixed disorders. If the second value moves the wrong way, or more or less than predicted, a second primary disorder is present. A high $PaCO_2$ and a low HCO_3^- together mean both respiratory and metabolic acidosis. A normal pH does not exclude a problem: two opposing disorders can cancel out (Farley & Licari, 2019).

Anion gap. In metabolic acidosis, the anion gap estimates unmeasured anions: sodium minus (chloride plus HCO_3^-). Some laboratories add potassium. Normal ranges differ between laboratories and methods (Kraut & Madias, 2007); one review gives 8 to 16 mmol/L for the formula that includes potassium (Farley & Licari, 2019). A high gap points to added acid: lactate, ketones, kidney failure or toxins. A normal gap points to bicarbonate loss, as in diarrhea. Albumin is the main unmeasured anion, so each 10 g/L fall in albumin lowers the gap by about 2.3 to 2.5 mmol/L and can hide a high gap (Kraut & Madias, 2007; Farley & Licari, 2019).

Lactate. A high lactate is a common cause of a high gap and a marker of poor perfusion (Chapters 4 and 6).

Worked example. A patient with sepsis has pH 7.29, $PaCO_2$ 28 mm Hg, HCO_3^- 13 mmol/L, sodium 138 mmol/L and chloride 100 mmol/L. The low pH and low HCO_3^- show metabolic acidosis; the low $PaCO_2$ is partial respiratory compensation. The anion gap is 138 − (100 + 13) = 25 mmol/L, which is high. With a high lactate, this fits lactic acidosis.

CANADIAN CONTEXT

Lab Values in SI Units

Canadian laboratories report results in SI units, while many US sources use conventional units. When reading a US source, convert before comparing:

- **Sodium and potassium:** 1 mEq/L equals 1 mmol/L, so 140 mEq/L is 140 mmol/L.
- **Glucose:** divide mg/dL by 18 (multiply by 0.0555) to get mmol/L, so 180 mg/dL is about 10.0 mmol/L.
- **Creatinine:** multiply mg/dL by 88.4 to get µmol/L, so 1.0 mg/dL is 88.4 µmol/L (Labcorp, n.d.).

The 2027 REx-PN test plan lists the laboratory values candidates are expected to know: sodium, potassium, glucose, glycosylated hemoglobin (HbA1c), creatinine, blood urea nitrogen (BUN), total cholesterol, hemoglobin, hematocrit, platelets, white blood cell count, international normalized ratio (INR), prothrombin time, partial and activated partial thromboplastin times, and ABGs (pH, PO_2, PCO_2, SaO_2 and HCO_3^-) (National Council of State Boards of Nursing, 2026). Reference ranges still vary by laboratory, and Canadian clinical chemists are working to harmonize them (Bohn et al., 2023). The nurse always uses the range printed on the patient's report.

Chapter 3 Summary

3.1 Body Fluids and How They Are Regulated

- Water is about 50% to 60% of adult body weight; about two-thirds is inside cells and one-third outside, in interstitial fluid and plasma.
- Tonicity, set mainly by sodium, decides whether water moves into or out of cells; isotonic, hypotonic and hypertonic fluids have different effects.
- Starling forces govern exchange between plasma and tissues; edema forms when filtration exceeds lymphatic drainage.
- Thirst, ADH, the RAAS and natriuretic peptides regulate water and sodium, and the kidneys carry out their signals.

- Older adults have weaker thirst and less ability to concentrate urine, which raises their risk of dehydration.

3.2 Fluid Volume Deficit and Excess

- Deficit results from losses, poor intake or third spacing; excess usually results from heart, kidney or liver failure or excess IV fluid.
- No single cue is reliable; the nurse combines vital signs, orthostatic changes, urine output, weight, lung sounds, edema, mental status and laboratory results.
- Skin turgor and capillary refill are unreliable in adults, especially older adults; swelling, pallor and cyanosis can be harder to see on darker skin.
- Accurate intake and output and daily weights on the same scale at the same time are core nursing measures.
- Care includes oral or IV replacement for deficit, and fluid and sodium restriction, diuretics, positioning and skin care for excess, with prompt escalation of deterioration.

3.3 IV Fluids and Fluid Management

- IV fluids are prescribed like medications and need a complete order; the 5 Rs (resuscitation, routine maintenance, replacement, redistribution, reassessment) explain their purpose.
- Isotonic crystalloids are used for resuscitation; dextrose and hypotonic solutions can lower sodium; 3% sodium chloride is a hypertonic high-alert fluid.
- Monitoring includes vital signs, lung sounds, intake and output, weight and electrolyte, urea and creatinine results.
- Main risks are fluid overload, hyponatremia from hypotonic fluids, and infiltration or extravasation.
- Concentrated potassium is never given by IV push; premixed solutions, limited stocking of concentrates, infusion pumps, rate limits and independent double checks per policy keep patients safe.

3.4 Sodium Imbalances

- Serum sodium mainly reflects water balance; a typical adult range is about 136 to 144 mmol/L, varying by laboratory.
- Hyponatremia has many causes, including SIADH, diuretics, heart failure and too much hypotonic fluid; severe symptoms such as vomiting, seizures or coma are an emergency.
- Chronic hyponatremia must be corrected slowly: the rise is limited to 10 mmol/L in the first 24 hours and 8 mmol/L in each later 24 hours, to avoid osmotic demyelination.
- Hypernatremia usually means water loss that has not been replaced, especially in older or dependent adults; water is replaced gradually as ordered.

3.5 Potassium Imbalances

- Small changes in potassium affect muscles and the heart; hypokalemia flattens T waves and causes U waves, and hyperkalemia causes peaked T waves and a wide QRS.
- Diuretics, vomiting, diarrhea and low magnesium cause hypokalemia; replacement is oral when possible, and IV potassium follows the high-alert rules in section 3.3.
- Hyperkalemia from kidney injury or potassium-sparing drugs is treated with IV calcium, insulin with glucose, removal of potassium and close monitoring of potassium and glucose.
- Hemolysis can cause pseudohyperkalemia, but a high potassium with ECG changes is always treated as real.

3.6 Calcium, Magnesium and Phosphate

- Ionized calcium is the active fraction; low albumin lowers total calcium, and ionized calcium is more reliable when results do not fit.
- Hypocalcemia causes tingling, tetany, Chvostek's and Trousseau's signs and long QT; hypercalcemia, usually from hyperparathyroidism or cancer, causes thirst, polyuria, constipation and confusion.

- Low magnesium often travels with low potassium and low calcium; magnesium sulfate toxicity is detected by lost reflexes, slow breathing and low urine output.
- Refeeding syndrome is prevented by identifying risk, giving thiamine before feeding, starting nutrition slowly and monitoring phosphate, potassium and magnesium.

3.7 Acid–Base Balance

- Buffers act in seconds, the lungs adjust $PaCO_2$ in minutes, and the kidneys adjust bicarbonate over days.
- Typical arterial values are pH 7.35 to 7.45, $PaCO_2$ 35 to 45 mm Hg and HCO_3^- 22 to 26 mmol/L; ranges vary by laboratory.
- To identify the primary disorder, look at the pH, then find the $PaCO_2$ or HCO_3^- change that matches its direction.
- The nurse treats the ABG as one part of the bedside assessment and escalates deterioration at once.

Key Terms (58)

acidemia: A blood pH below the normal range.

acidosis: A process that adds acid or removes base, tending to lower pH.

albumin: A plasma protein, also given as a colloid solution made from pooled human plasma, that raises plasma oncotic pressure and holds fluid in the blood vessels.

aldosterone: A hormone from the adrenal cortex that causes the kidneys to keep sodium, and with it water.

alkalemia: A blood pH above the normal range.

alkalosis: A process that removes acid or adds base, tending to raise pH.

anion gap: A calculated value (sodium minus chloride and bicarbonate, with or without potassium) that estimates unmeasured anions; a high gap suggests added acid.

antidiuretic hormone (ADH): A hormone, also called vasopressin, released from the posterior pituitary when osmolality rises or blood volume falls; it makes the kidneys return more water to the blood.

arterial blood gas (ABG): A test of arterial blood that measures pH, $PaCO_2$, PaO_2 and bicarbonate.

balanced solution: An isotonic crystalloid, such as Plasma-Lyte A, whose electrolyte content is closer to plasma than that of 0.9% sodium chloride.

buffer: A chemical system, such as bicarbonate and carbonic acid, that takes up or releases hydrogen ions to limit changes in pH.

Chvostek's sign: Twitching of the facial muscles when the facial nerve is tapped; a sign of hypocalcemia, though less specific than Trousseau's sign.

colloid: An IV solution containing large molecules, such as albumin, that stay mostly in the blood vessels.

compensation: The body's response to a primary acid–base disorder, in which the other system (lungs or kidneys) changes in the opposite direction to move pH back toward normal.

crystalloid: An IV solution of water with electrolytes, glucose or both.

daily weight: A weight taken at the same time each day on the same scale with similar clothing, used to track short-term changes in body fluid.

edema: Excess fluid in the interstitial space.

extracellular fluid (ECF): All body water outside the cells, made up mainly of interstitial fluid and plasma.

extravasation: Leakage of a drug or solution that can damage tissue from a vein into the surrounding tissue.

fluid volume deficit: A loss of extracellular fluid volume (hypovolemia).

fluid volume excess: Too much sodium and water in the extracellular fluid (hypervolemia).

hypercalcemia: A serum calcium above the reference range.

hyperkalemia: A serum potassium above the reference range; it can cause peaked T waves and fatal dysrhythmias.

hypernatremia: A serum sodium above the reference range, usually from too little water relative to sodium.

hypertonic: Having a higher tonicity than plasma, so water moves out of cells.

hypocalcemia: A serum calcium below the reference range, causing nerve and muscle overexcitability.

hypokalemia: A serum potassium below the reference range; it can cause weakness, ileus and dysrhythmias.

hypomagnesemia: A serum magnesium below the reference range, often with low potassium and low calcium.

hyponatremia: A serum sodium below the reference range, usually from too much water relative to sodium.

hypotonic: Having a lower tonicity than plasma, so water moves into cells.

infiltration: Leakage of IV fluid from the vein into the surrounding tissue.

interstitial fluid: Fluid in the spaces between cells in the tissues.

intracellular fluid (ICF): Body water inside the cells, about two-thirds of the total.

intravascular fluid: The fluid within blood vessels; the plasma.

ionized calcium: The free, physiologically active fraction of plasma calcium, about half of the total.

isotonic: Having about the same tonicity as plasma, so cells keep their size.

jugular venous distension: Visible filling of the neck veins with the head raised 30 to 45 degrees, a sign of high venous pressure.

metabolic acidosis: An acid–base disorder with a low pH caused by a primary fall in bicarbonate.

metabolic alkalosis: An acid–base disorder with a high pH caused by a primary rise in bicarbonate.

natriuretic peptides: Hormones (ANP and BNP) released by stretched heart muscle that increase sodium and water excretion and oppose the renin–angiotensin–aldosterone system.

orthostatic hypotension: A fall in systolic blood pressure of at least 20 mm Hg, or diastolic of at least 10 mm Hg, within 3 minutes of standing.

osmolality: The concentration of dissolved particles per kilogram of water, reported in mOsm/kg.

osmolarity: The concentration of dissolved particles per litre of solution, reported in mOsmol/L.

osmosis: Movement of water across a membrane from an area of lower to higher solute concentration.

osmotic demyelination syndrome (ODS): Damage to the myelin of brain nerve fibres caused by too rapid a rise in serum sodium in chronic hyponatremia.

$PaCO_2$: The partial pressure of carbon dioxide in arterial blood, the respiratory component of an ABG.

phlebitis: Inflammation of a vein, often related to IV therapy.

pseudohyperkalemia: A falsely high potassium result caused by release of potassium from blood cells after the sample is drawn.

refeeding syndrome: A fall of 10% or more in serum phosphate, potassium or magnesium, with or without organ dysfunction, within 5 days of starting or increasing nutrition after starvation or malnutrition.

renin–angiotensin–aldosterone system (RAAS): A hormone system, started by renin from the kidney, that raises blood pressure and keeps sodium and water.

respiratory acidosis: An acid–base disorder with a low pH caused by a primary rise in $PaCO_2$ from inadequate breathing.

respiratory alkalosis: An acid–base disorder with a high pH caused by a primary fall in $PaCO_2$ from excessive breathing.

Starling forces: The hydrostatic and oncotic pressures that govern fluid movement between plasma and the interstitial space.

syndrome of inappropriate antidiuretic hormone secretion (SIADH): Continued ADH action despite dilute plasma, causing water retention and hyponatremia in a patient with normal volume status.

third spacing: A shift of fluid out of the circulation into spaces where it cannot support blood pressure, such as the bowel, abdomen or inflamed tissue.

tonicity: The effect of a fluid on cell volume, determined by solutes that cannot cross cell membranes freely.

Trousseau's sign: Spasm of the hand and wrist within 3 minutes of inflating a blood pressure cuff above systolic pressure; a sign of hypocalcemia.

urine specific gravity: A measure of urine concentration compared with water.

Licensure Review & Clinical Judgment Questions (30)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mr. Tomas Silva (Questions 1–4): Mr. Tomas Silva, 68, is on day 2 after a bowel resection on a surgical unit in an Ontario hospital, cared for by an RPN. He is nil by mouth and receiving 0.9% sodium chloride with potassium chloride 20 mmol/L at 80 mL/h by pump through a left forearm peripheral IV. His morning serum potassium is 3.3 mmol/L; vital signs are at his baseline.

1. [CORE] The surgeon writes a new order: "KCl 40 mmol IV now." What should the RPN do first?

a. Ask pharmacy for a vial of concentrated potassium chloride to dilute on the unit

b. Contact the surgeon to clarify the diluent, volume and infusion rate

c. Give the dose slowly by IV push over 10 minutes

d. Ask the RN to give the dose because potassium is a high-alert medication

Answer: b — The order gives no diluent, volume or rate, so the RPN does not carry it out and follows up with the prescriber (section 3.3, Scope in Practice box). Concentrated potassium is kept out of patient care areas, and premixed solutions are used instead (a). Potassium is never given by IV push (c). RPNs are authorized to give IV medications with an order; the problem is the order, not the nurse's category (d).

2. [CORE] The surgeon rewrites the order as potassium chloride 20 mmol in a premixed minibag from pharmacy, to infuse over 2 hours. Which action best reflects safe practice for this high-alert medication?

a. Have a second nurse independently check the drug, dose, rate and pump settings

b. Run the minibag by gravity and count the drip rate every 15 minutes

c. Program the pump while a second nurse watches and confirms the numbers on the screen

d. Hang the minibag without a pump because it will finish within 2 hours

Answer: a — In an independent double check, done as policy requires, the second nurse verifies the drug, dose, rate and pump settings without seeing the first nurse's work (section 3.3; Chapter 1, section 1.6). Watching the first nurse program the pump (c) is not independent. IV potassium needs a calibrated infusion device, so gravity infusion (b) and running without a pump (d) are unsafe.

3. [CORE] Thirty minutes into the minibag infusion, Mr. Silva says his arm "burns." The skin around the IV site is swollen, cool and tight compared with his other arm. What should the RPN do first?

a. Stop the infusion and assess the site
b. Slow the infusion rate by half and reassess in an hour
c. Apply a warm compress and continue the infusion
d. Flush the catheter firmly to confirm it is still patent

Answer: a — Swelling, coolness, tightness and burning suggest infiltration of a solution that can damage tissue, so the RPN stops the infusion, assesses the site and follows policy, including notifying the prescriber (section 3.3). Slowing the rate (b), continuing with a compress (c) or flushing firmly (d) pushes more fluid into the tissue.

4. [CORE] That afternoon, Mr. Silva's blood pressure is 92/54 (124/76 this morning), heart rate 116, and urine output 15 mL/h for 2 hours. He is newly confused. Which action by the RPN is most appropriate?

a. Continue hourly vital signs, because the patient remains on the RPN's assignment
b. Increase the IV rate to 150 mL/h to treat the low blood pressure
c. Stay with him, get help and report at once to the RN and surgeon using SBAR
d. Ask the charge nurse to arrange a transfer to a higher level of care, then report the findings

Answer: c — Falling blood pressure, tachycardia, low urine output and new confusion signal deterioration. Every nurse who notices deterioration acts at once and escalates, calling the rapid response team if criteria are met; the RPN also consults the RN as needs change (section 3.2; Scope in Practice box, section 3.3). Routine checks (a) delay care. Increasing the rate (b) needs an order. Arranging a transfer before reporting (d) delays treatment.

5. [CORE] A nurse is assessing a 78-year-old patient with heart failure. Which findings are cues of fluid volume excess? Select all that apply.

a. Weight gain of 2.1 kg over 2 days
b. Crackles at both lung bases
c. Distended neck veins with the head of the bed at 45 degrees
d. Deep sock marks and tight, shiny skin over the ankles
e. Dry axillae and dry oral mucous membranes
f. A fall in systolic blood pressure of 24 mm Hg on standing

Answer: a, b, c, d — Rapid weight gain (a), crackles (b), jugular venous distension (c) and edema, which may show as tight, shiny skin and deep sock marks (d), are cues of fluid excess (section 3.2, Table 3.1). Dry axillae and mucous membranes (e) and orthostatic hypotension (f) are cues of deficit.

6. [CORE] A patient weighed 72.4 kg at 0600 yesterday and 74.0 kg at 0600 today on the same scale. Intake for 24 hours was 2,400 mL and output 1,350 mL. How should the nurse interpret these findings?

a. The gain is normal day-to-day variation from meals
b. The patient is probably retaining fluid and needs further assessment
c. The scale is probably wrong, so the patient should be reweighed on a bed scale
d. The patient is likely developing a fluid volume deficit

Answer: b — Because 1 L of water weighs about 1 kg, a gain of 1.6 kg in a day mostly reflects fluid, and a positive measured balance of about 1 L supports this (unmeasured intake may explain the rest). The nurse assesses lung sounds and edema and reports per the ordered parameters (section 3.2). Food does not explain a gain this large (a). Weighing at the same time on the same scale makes results comparable; switching scales (c) would not. Weight gain does not suggest a deficit (d).

7. [CORE] A 59-year-old patient has vomited for 2 days. Blood pressure is 88/50 and heart rate 118. The prescriber orders a fluid bolus. Which solution should the nurse expect?

a. 5% dextrose in water
b. 0.45% sodium chloride
c. 3% sodium chloride
d. 0.9% sodium chloride

Answer: d — Resuscitation uses an isotonic crystalloid with 130 to 154 mmol/L of sodium, such as 0.9% sodium chloride, which stays in the ECF (section 3.3, Table 3.2). 5% dextrose in water (a) becomes free water that moves into cells. 0.45% sodium chloride (b) is hypotonic and expands the circulation poorly. 3% sodium chloride (c) is reserved for severe symptomatic hyponatremia.

8. [CORE] An 82-year-old patient receiving 0.9% sodium chloride at 125 mL/h after hip surgery becomes short of breath, with a respiratory rate of 28, oxygen saturation 89% and new crackles. What should the nurse do first?

a. Document the findings and recheck the respiratory rate and oxygen saturation in one hour
b. Encourage the patient to cough, breathe deeply and use the incentive spirometer every hour
c. Sit the patient upright, slow the infusion as policy allows and call for help
d. Ask the patient to limit oral fluids for the rest of the shift and record all intake

Answer: c — These cues suggest fluid overload with fluid in the lungs, which needs immediate action and escalation (section 3.3). Sitting upright eases breathing, slowing the infusion as policy allows limits further overload, and the nurse calls for help. Waiting an hour (a) delays care. Coughing and deep breathing (b) do not treat overload. Limiting oral fluids (d) does not address the IV fluid or the urgent breathing problem.

9. [CORE] On day 1 after surgery, a 45-year-old patient receiving 5% dextrose in 0.45% sodium chloride at 125 mL/h has a headache, nausea and new confusion. Which laboratory result is most important for the nurse to check?

a. Potassium
b. Hemoglobin
c. Glucose
d. Sodium

Answer: d — Hypotonic and dextrose-containing fluids can lower sodium quickly after surgery, when ADH release is often increased; this patient is receiving about 3 L a day. Headache, nausea and confusion suggest hyponatremia with brain swelling (section 3.3). Potassium (a), hemoglobin (b) and glucose (c) matter but do not explain this pattern as well.

Case: Mrs. Lillian Okafor (Questions 10–15): Mrs. Lillian Okafor, 81, is admitted to a medical unit in an Ontario hospital after 3 days of vomiting and diarrhea with poor fluid intake. She takes spironolactone and an ACE inhibitor for heart failure. On admission she is drowsy but oriented. Vital signs: temperature 37.4 °C, heart rate 54 and regular, respiratory rate 18, blood pressure 102/60 mm Hg (her baseline is 136/78 mm Hg), oxygen saturation (SpO_2) 96% on room air. Her mucous membranes are dry. Laboratory results: potassium 6.6 mmol/L (no hemolysis reported), sodium 133 mmol/L, creatinine 172 µmol/L (92 µmol/L three months ago), urea 15.8 mmol/L, glucose 6.4 mmol/L, HCO_3^- 19 mmol/L. A 12-lead ECG shows peaked T waves.

10. [CORE] Which findings require immediate follow-up? Select all that apply.

a. Potassium 6.6 mmol/L
b. Peaked T waves on the ECG
c. Glucose 6.4 mmol/L
d. Creatinine 172 µmol/L, up from 92 µmol/L
e. Blood pressure 102/60 mm Hg
f. SpO_2 96% on room air

Answer: a, b, d, e — Recognize cues (sections 3.2 and 3.5). Severe hyperkalemia with ECG changes is life-threatening. The rising creatinine shows a sudden fall in kidney function, and the blood pressure is well below her baseline, fitting volume loss. A glucose of 6.4 mmol/L is not an urgent concern. An SpO_2 of 96% on room air is acceptable.

11. [CORE] Which combination of factors most likely explains Mrs. Okafor's high potassium?

a. Vomiting and diarrhea that removed potassium-rich fluid from the gastrointestinal tract
b. Reduced kidney function from volume loss, plus two drugs that reduce potassium excretion
c. A high-sodium diet at home combined with several days of poor fluid intake
d. Hemolysis of the blood sample caused by a difficult or prolonged blood draw

Answer: b — Analyze cues (section 3.5). Volume loss lowered kidney blood flow (the creatinine has nearly doubled), and spironolactone and ACE inhibitors both reduce potassium excretion. Vomiting and diarrhea lose potassium, so they would lower it (a). Sodium intake does not explain a high potassium (c). No hemolysis was reported, and peaked T waves show the high potassium is real (d).

12. [CORE] Which problem should the nurse treat as the priority?

a. Fluid volume deficit related to vomiting and diarrhea
b. Risk for falls related to drowsiness and low blood pressure
c. Risk for a life-threatening dysrhythmia related to hyperkalemia
d. Deficient knowledge about heart failure medications

Answer: c — Prioritize hypotheses (section 3.5). A potassium of 6.6 mmol/L with peaked T waves can progress quickly to a fatal rhythm. Fluid deficit (a) is real and contributes, but the immediate threat to life is cardiac. Falls (b) and teaching (d) matter but come later.

13. [CORE] Which orders should the nurse anticipate for Mrs. Okafor? Select all that apply.

a. Continuous cardiac monitoring
b. IV calcium gluconate
c. IV insulin with dextrose, with frequent glucose checks
d. Oral potassium chloride with breakfast
e. Holding spironolactone and the ACE inhibitor
f. IV isotonic crystalloid to restore volume

Answer: a, b, c, e, f — Generate solutions (section 3.5). Calcium protects the heart when ECG changes are present, and insulin with dextrose shifts potassium into cells, with glucose checks because of the hypoglycemia risk. Monitoring is needed at this level. Holding drugs that raise potassium and restoring volume to improve kidney function treat the causes. Oral potassium (d) would make her hyperkalemia worse.

14. [CORE] Mrs. Okafor receives IV insulin with dextrose. Which nursing action is most important over the next several hours?

a. Check capillary blood glucose at the ordered intervals
b. Encourage her to drink at least 2 litres of fluid
c. Assess for Chvostek's and Trousseau's signs every hour
d. Offer high-potassium foods once her nausea settles

Answer: a — Take action (section 3.5). Insulin can cause hypoglycemia for several hours after it is given, so the nurse checks glucose as ordered. Large oral fluid volumes (b) are not ordered and may not suit a patient with heart failure. Chvostek's and Trousseau's signs (c) assess low calcium, not this risk. High-potassium foods (d) are inappropriate.

15. [CORE] Which findings 6 hours later best show that treatment is working?

a. Potassium 6.3 mmol/L, glucose 3.6 mmol/L, heart rate 52
b. Potassium 5.2 mmol/L, T waves no longer peaked, urine output 45 mL/h
c. Potassium 4.0 mmol/L, new confusion, urine output 10 mL/h
d. Potassium 5.6 mmol/L, peaked T waves, blood pressure 98/58 mm Hg

Answer: b — Evaluate outcomes (section 3.5). A falling potassium, a normalizing ECG and adequate urine output show response to both the shift therapy and rehydration. Option a shows little change and hypoglycemia. Option c has new confusion and oliguria, which need escalation even with a normal potassium. Option d shows persistent ECG changes and low blood pressure.

16. [CORE] A patient taking furosemide has a potassium of 2.8 mmol/L. Which ECG change should the nurse expect?

a. Tall, peaked T waves
b. A widened QRS complex with a sine-wave pattern
c. A shortened QT interval
d. Flattened T waves with prominent U waves

Answer: d — Hypokalemia flattens the T wave, depresses the ST segment and makes U waves prominent (section 3.5). Peaked T waves (a) and a sine-wave pattern (b) are signs of hyperkalemia. A shortened QT (c) is linked with hypercalcemia (section 3.6).

17. [CORE] A patient with chronic hyponatremia had a sodium of 116 mmol/L at 0800 and is being treated in a monitored unit. At 1800 the sodium is 127 mmol/L and the urine output has risen sharply. What should the nurse do first?

a. Document the result as a good response and continue the plan
b. Encourage oral fluids to replace the urine output
c. Recheck the sodium at the next routine morning draw
d. Report the rise to the prescriber at once

Answer: d — The sodium has risen 11 mmol/L in 10 hours, already beyond the recommended limit of 10 mmol/L in the first 24 hours, and the rising dilute urine output suggests it is still climbing (section 3.4, Clinical Safety box). Rapid correction risks osmotic demyelination, so the nurse reports at once. Option a misreads the danger. The nurse does not give unordered fluids (b). Waiting until morning (c) delays action.

18. [CORE] A patient with severe malnutrition and alcohol use disorder started tube feeding 2 days ago. Which result most suggests refeeding syndrome?

a. Phosphate 0.42 mmol/L, down from 0.95 mmol/L on admission
b. Sodium 144 mmol/L, up from 140 mmol/L
c. Potassium 4.6 mmol/L, unchanged from admission
d. Albumin 30 g/L, unchanged from admission

Answer: a — Refeeding syndrome is a fall in phosphate, potassium or magnesium within 5 days of starting nutrition (section 3.6). A drop of more than half in phosphate is a severe fall. The small sodium rise (b) is within range. The unchanged potassium (c) and albumin (d) do not suggest refeeding syndrome.

19. [CORE] A patient who received IV morphine for pain is difficult to rouse. ABG: pH 7.24, $PaCO_2$ 60 mm Hg, HCO_3^- 25 mmol/L. Which disorder is present?

a. Metabolic acidosis
b. Respiratory acidosis
c. Respiratory alkalosis
d. Metabolic alkalosis

Answer: b — The pH is low (acidemia), the $PaCO_2$ is high and matches the pH, and the HCO_3^- is normal: respiratory acidosis from opioid-related hypoventilation (section 3.7). Metabolic acidosis (a) would show a low HCO_3^-. Both alkaloses (c, d) need a high pH.

20. [CORE] A patient after bowel surgery has had nasogastric suction for 4 days. ABG: pH 7.51, $PaCO_2$ 44 mm Hg, HCO_3^- 34 mmol/L. Which disorder is present?

a. Respiratory alkalosis
b. Metabolic acidosis
c. Metabolic alkalosis
d. Respiratory acidosis

Answer: c — The pH is high, the HCO_3^- is high and matches the pH, and the $PaCO_2$ is normal: metabolic alkalosis from loss of gastric acid (section 3.7). Respiratory alkalosis (a) would show a low $PaCO_2$. The two acidoses (b, d) need a low pH.

21. [CORE] The nurse teaches a patient newly prescribed spironolactone. Which statement shows a need for more teaching?

a. "I'll use a salt substitute instead of regular salt."
b. "I'll go for my blood tests when they're due."
c. "I'll get up slowly if I feel dizzy."
d. "I'll call if my muscles feel weak or my heart races."

Answer: a — The spironolactone monograph advises patients to avoid salt substitutes, potassium supplements and high-potassium foods because of the risk of hyperkalemia (section 3.5, Medications box). Regular blood tests (b), rising slowly (c) and reporting weakness or palpitations (d) are correct.

22. [CORE] A patient with small cell lung cancer has a sodium of 124 mmol/L, mild fatigue, no nausea, headache or confusion, and no signs of fluid deficit or excess. Urine osmolality is high. Which order should the nurse anticipate first?

a. Fluid restriction
b. A 1-litre bolus of 0.9% sodium chloride
c. IV furosemide
d. Encouraging extra oral fluids

Answer: a — These findings suggest SIADH, and fluid restriction is the suggested first-line treatment (section 3.4). Without volume loss, a saline bolus (b) is not the first choice. Furosemide (c) is not the first-line treatment. Extra fluids (d) would lower the sodium further.

23. [CORE] Four hours after a total thyroidectomy, a patient reports tingling around the mouth and in the fingertips. What should the nurse do first?

- **a.** Reassure the patient that this is expected after anesthesia
- **b.** Assess for other signs of hypocalcemia and report promptly
- **c.** Give the next dose of oral calcium early
- **d.** Encourage slow, deep breathing into a paper bag

Answer: b — Perioral and fingertip tingling are early cues of hypocalcemia, the most common cause of which in hospital is parathyroid damage during thyroid surgery (section 3.6). The nurse assesses for spasm and Trousseau's sign and reports so calcium can be checked. Reassurance (a) misses a dangerous cause. The nurse does not change a dose time without an order (c). Rebreathing (d) is not a treatment for hypocalcemia.

24. [CORE] A patient receiving an IV magnesium sulfate infusion has absent patellar reflexes and a respiratory rate of 11. What should the nurse do first?

- **a.** Slow the infusion by half and reassess in an hour
- **b.** Document the findings as an expected effect
- **c.** Give oral fluids to increase urine output
- **d.** Stop the infusion and report at once

Answer: d — Loss of the patellar reflex and slowed breathing are signs of magnesium toxicity (section 3.6). The nurse stops the infusion and escalates; IV calcium gluconate reverses respiratory depression. Slowing the infusion (a) or documenting only (b) delays care, and oral fluids (c) do not treat toxicity.

25. [CORE] A patient's potassium is reported as 6.1 mmol/L with a comment that the sample was hemolyzed. The patient feels well, and a 12-lead ECG is normal. Which action is best?

- **a.** Ignore the result because hemolysis makes it invalid
- **b.** Give the patient's scheduled oral potassium supplement
- **c.** Report the result and expect a carefully drawn repeat sample
- **d.** Start continuous cardiac monitoring and ask for IV calcium

Answer: c — Hemolysis can falsely raise potassium (pseudohyperkalemia), but a real rise must be ruled out (section 3.5). The nurse reports the result and a repeat sample is drawn gently and sent promptly. Ignoring it (a) is unsafe. Giving potassium (b) before the result is clarified could cause harm. Emergency treatment (d) is not indicated with a normal ECG and a likely false result, though it would be if the ECG were abnormal.

26. [CORE] A patient with advanced dementia, unable to get drinks without help, has a sodium of 152 mmol/L. Which nursing action is most important?

- **a.** Restrict free water intake to 1 litre a day
- **b.** Add extra table salt to the patient's meals
- **c.** Offer water often and record all intake
- **d.** Request an order for a hypertonic saline bolus

Answer: c — Hypernatremia in a dependent person usually reflects too little water (section 3.4). Regular offering of fluids and accurate records address the cause. Restricting water (a), adding salt (b) and hypertonic saline (d) would all raise the sodium further.

27. [RN] A patient with diabetic ketoacidosis has pH 7.25, $PaCO_2$ 28 mm Hg, HCO_3^- 12 mmol/L. Which interpretation is correct?

- **a.** Respiratory alkalosis with partial metabolic compensation
- **b.** Metabolic acidosis with partial respiratory compensation
- **c.** Mixed metabolic and respiratory acidosis
- **d.** Metabolic acidosis with full respiratory compensation

Answer: b — The low pH and low HCO_3^- show metabolic acidosis; the low $PaCO_2$ is the lungs blowing off CO_2 in the expected opposite direction (section 3.7, Going Deeper). The pH is still low, so compensation is partial, not full (d). A respiratory alkalosis would raise the pH (a). A mixed acidosis would show a high $PaCO_2$ (c).

28. [RN] A patient with sepsis who received opioids has pH 7.08, $PaCO_2$ 56 mm Hg, HCO_3^- 16 mmol/L. Which interpretation is correct?

- **a.** Respiratory acidosis with metabolic compensation
- **b.** Metabolic acidosis with respiratory compensation
- **c.** Mixed respiratory and metabolic acidosis
- **d.** Metabolic alkalosis with respiratory acidosis

Answer: c — Both values push toward acidosis: the $PaCO_2$ is high and the HCO_3^- is low (section 3.7, Going Deeper). Compensation would move the second value in the opposite direction, so options a and b are wrong. HCO_3^- is low, not high, so there is no metabolic alkalosis (d). A mixed disorder like this causes severe acidemia and needs urgent escalation.

29. [RN] A patient with metabolic acidosis has sodium 140 mmol/L, chloride 104 mmol/L and HCO_3^- 12 mmol/L. The laboratory calculates the anion gap without potassium. What is the anion gap, and what does it suggest?

- **a.** 24 mmol/L, suggesting added acid such as lactate or ketones
- **b.** 12 mmol/L, suggesting bicarbonate loss from diarrhea
- **c.** 36 mmol/L, suggesting a laboratory error
- **d.** 116 mmol/L, suggesting severe kidney failure

Answer: a — Anion gap = 140 − (104 + 12) = 24 mmol/L, which is high and points to added acid such as lactate, ketones, kidney failure or toxins (section 3.7, Going Deeper). Option b simply repeats the HCO_3^- value. Option c subtracts chloride but leaves out HCO_3^-. Option d adds chloride and HCO_3^- but does not subtract them from sodium.

30. [RN] A patient with sepsis has a calculated anion gap of 13 mmol/L, which is within the laboratory's normal range, but the albumin is 20 g/L. How should the nurse interpret this?

- **a.** The normal gap rules out lactic acidosis
- **b.** The low albumin has raised the gap falsely
- **c.** Albumin has no effect on the anion gap
- **d.** The low albumin may be hiding a high anion gap

Answer: d — Albumin is the main unmeasured anion, so a low albumin lowers the gap by about 2.3 to 2.5 mmol/L for each 10 g/L fall (section 3.7, Going Deeper). An albumin about 20 g/L below a typical 40 g/L adds back about 5 mmol/L, giving an adjusted gap near 18 mmol/L, which would be high, so the nurse checks the lactate and reports. A normal gap does not rule out lactic acidosis here (a). Low albumin lowers the gap; it does not raise it (b), and it does affect it (c).

References

2024 Required Organizational Practices (ROPs): Update note. (2024, May 14). Qmentum Global for Canadian Accreditation. https://professionals.wrha.mb.ca/files/long.term_.care_.-accrreditation-updatenote-2024.pdf

AA Pharma. (2025). *Midamor (comprimés de chlorhydrate d'amiloride)* [Product monograph, French-language version]. https://pdf.hres.ca/dpd_pm/00081068.PDF

Accreditation Canada. (2021). *Required organizational practices: 2021 handbook*. https://vitalitenb.ca/images/files/documents/medecins/2021_rop_handbook.pdf

Alberta Health Services. (2013). *Potassium reference range change* [Laboratory bulletin, Edmonton Zone]. https://www.albertahealthservices.ca/assets/wf/lab/wf-lab-bulletin-potassium-reference-range-change-final.pdf

Alfonzo, A., Harrison, A., Baines, R., Chu, A., Mann, S., & MacRury, M. (2026). *Clinical practice guideline: Treatment of acute hyperkalaemia in adults* (Updated version July 2026). UK Kidney Association. https://www.ukkidney.org/sites/default/files/documents/FINAL%20VERSION%20-%20UKKA%20CLINICAL%20PRACTICE%20GUIDELINE%20-%20MANAGEMENT%20OF%20HYPERKALAEMIA%20IN%20ADULTS%20-%20UPDATED%20JULY%202026_0.pdf

Almeida-Arvizu, A., Vega-Vega, O., Rincón-Pedrero, R., & del Toro-Cisneros, N. (2025). Pontine and extrapontine myelinolysis: Risk factors and characterization of patients diagnosed in three decades in a tertiary center. *Revista de Investigación Clínica, 77*(1), 1–5. https://doi.org/10.24875/RIC.24000213

AstraZeneca Canada. (2026). *Lokelma (sodium zirconium cyclosilicate) powder for oral suspension* [Product monograph]. https://pdf.hres.ca/dpd_pm/00084061.PDF

Baxter Corporation. (2018a). *3% and 5% sodium chloride injections, USP* [Product monograph]. https://pdf.hres.ca/dpd_pm/00046297.PDF

Baxter Corporation. (2018b). *Chlorure de sodium injectable à 0,45 %, USP* [Sodium chloride injection 0.45%, USP; Product monograph]. https://pdf.hres.ca/dpd_pm/00048911.PDF

Baxter Corporation. (2018c). *Dextrose and sodium chloride injection, USP* [Product monograph]. https://pdf.hres.ca/dpd_pm/00050933.PDF

Baxter Corporation. (2018d). *Lactate de Ringer USP, injectable* [Lactated Ringer's injection USP; Product monograph]. https://pdf.hres.ca/dpd_pm/00050043.PDF

Baxter Corporation. (2018e). *Potassium chloride in 0.9% sodium chloride injection, USP* [Product monograph]. https://pdf.hres.ca/dpd_pm/00049126.PDF

Baxter Corporation. (2019a). *PLASMA-LYTE A (une solution d'électrolytes) injectable* [PLASMA-LYTE A (an electrolyte solution) injection; Product monograph]. https://pdf.hres.ca/dpd_pm/00052288.PDF

Baxter Corporation. (2019b). *Potassium chloride injection* [Product monograph]. https://pdf.hres.ca/dpd_pm/00049372.PDF

Baxter Corporation. (2021). *Potassium chloride in 5% dextrose injection, USP* [Product monograph]. https://pdf.hres.ca/dpd_pm/00061808.PDF

Bobrowicz, M., Pachucki, J., & Popow, M. (2024). Hypomagnesaemia leading to parathyroid dysfunction, hypocalcaemia, and hypokalaemia as a complication of long-term treatment with a proton pump inhibitor: A literature review. *Endokrynologia Polska, 75*(4), 359–365. https://doi.org/10.5603/ep.98576

Bohn, M. K., Bailey, D., Balion, C., Cembrowski, G., Collier, C., De Guire, V., Higgins, V., Jung, B., Mohammed Ali, Z., Seccombe, D., Taher, J., Tsui, A. K. Y., Venner, A., & Adeli, K. (2023). Reference interval harmonization: Harnessing the power of big data analytics to derive common reference intervals across populations and testing platforms. *Clinical Chemistry, 69*(9), 991–1008. https://doi.org/10.1093/clinchem/hvad099

College of Nurses of Ontario. (2025a). *Medication* [Practice standard]. https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41007_medication.pdf

College of Nurses of Ontario. (2025b). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026, October 14). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

CSL Behring Canada. (2025). *Alburex 5 and Alburex 25 (albumin [human])* [Product monograph]. https://pdf.hres.ca/dpd_pm/00078348.PDF

da Silva, J. S. V., Seres, D. S., Sabino, K., Adams, S. C., Berdahl, G. J., Citty, S. W., Cober, M. P., Evans, D. C., Greaves, J. R., Gura, K. M., Michalski, A., Plogsted, S., Sacks, G. S., Tucker, A. M., Worthington, P., Walker, R. N., & Ayers, P. (2020). ASPEN consensus recommendations for refeeding syndrome. *Nutrition in Clinical Practice, 35*(2), 178–195. https://doi.org/10.1002/ncp.10474

Danziger, J., & Zeidel, M. L. (2015). Osmotic homeostasis. *Clinical Journal of the American Society of Nephrology, 10*(5), 852–862. https://doi.org/10.2215/CJN.10741013

Emergency Care BC. (2024, May 21). *Tumor lysis syndrome* [Clinical summary]. https://emergencycarebc.ca/clinical_resource/clinical-summary/tumor-lysis-syndrome/

Farley, K. J., & Licari, E. (2019). A structured approach to acid–base interpretation. *Medical Journal of Australia, 211*(7), 308–311.e1. https://doi.org/10.5694/mja2.50344

Fedorowski, A., Hamrefors, V., Sutton, R., van Dijk, J. G., Freeman, R., Lenders, J. W. M., & Wieling, W. (2017). Do we need to evaluate diastolic blood pressure in patients with suspected orthostatic hypotension? *Clinical Autonomic Research, 27*(3), 167–173. https://doi.org/10.1007/s10286-017-0409-7

Fung, A. T., & Rimmer, J. (2005). Hypophosphataemia secondary to oral refeeding syndrome in a patient with long-term alcohol misuse. *Medical Journal of Australia, 183*(6), 324–326. https://doi.org/10.5694/j.1326-5377.2005.tb07066.x

Government of British Columbia. (2022, June 7). *Enhanced alert system, risk mitigation needed for resilience in future heat events* [News release]. https://news.gov.bc.ca/releases/2022PSSG0042-000903

Guidelines and Protocols Advisory Committee. (2023). *Appendix B: Heart failure zones reference guide*. In *Heart failure – diagnosis and management*. Province of British Columbia. https://www2.gov.bc.ca/assets/gov/health/practitioner-pro/bc-guidelines/hf_appendixb.pdf

Hamm, L. L., Nakhoul, N., & Hering-Smith, K. S. (2015). Acid–base homeostasis. *Clinical Journal of the American Society of Nephrology, 10*(12), 2232–2242. https://doi.org/10.2215/CJN.07400715

Health Canada. (2024). *Extreme heat and human health: For pharmacists and pharmacist technicians*. https://www.canada.ca/en/health-canada/services/publications/healthy-living/extreme-heat-human-health-pharmacists-technicians.html

Health Standards Organization. (2024). *Required organizational practices: 2024 handbook* (HSO R01002:2024 [E]). https://professionals.wrha.mb.ca/files/long.term_.care_.-accrreditation-AC-ROPhandbook2024.pdf

Hooper, L., Abdelhamid, A., Attreed, N. J., Campbell, W. W., Channell, A. M., Chassagne, P., Culp, K. R., Fletcher, S. J., Fortes, M. B., Fuller, N., Gaspar, P. M., Gilbert, D. J., Heathcote, A. C., Kafri, M. W., Kajii, F., Lindner, G., Mack, G. W., Mentes, J. C., Merlani, P., … Hunter, P. (2015). Clinical symptoms, signs and tests for identification of impending and current water-loss dehydration in older people. *Cochrane Database of Systematic Reviews*, 2015(4), Article CD009647. https://doi.org/10.1002/14651858.CD009647.pub2

Institute for Safe Medication Practices Canada. (2005). *Potassium chloride safety recommendations*. https://www.ismp-canada.org/download/PotassiumChlorideSafetyRecommendations2005.pdf

JAMP Pharma Corporation. (2022). *Furosemide special injection (furosemide injection USP)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00065979.PDF

Kardalas, E., Paschou, S. A., Anagnostis, P., Muscogiuri, G., Siasos, G., & Vryonidou, A. (2018). Hypokalemia: A clinical update. *Endocrine Connections, 7*(4), R135–R146. https://doi.org/10.1530/EC-18-0109

Klabunde, R. E. (2022, December 13). *Renin-angiotensin-aldosterone system*. CV Physiology. https://www.cvphysiology.com/Blood%20Pressure/BP015

Klabunde, R. E. (2023, October 30). *Atrial and brain natriuretic peptides*. CV Physiology. https://www.cvphysiology.com/Blood%20Pressure/BP017

Kraut, J. A., & Madias, N. E. (2007). Serum anion gap: Its uses and limitations in clinical medicine. *Clinical Journal of the American Society of Nephrology, 2*(1), 162–174. https://doi.org/10.2215/CJN.03020906

Labcorp. (n.d.). *SI unit conversion table*. https://www.labcorp.com/resource/si-unit-conversion-table

Le, R. D., & Geary, S. P. (2020). A case of hyperkalemia versus pseudohyperkalemia in chronic lymphocytic leukemia. *Clinical Practice and Cases in Emergency Medicine, 4*(2), 208–210. https://doi.org/10.5811/cpcem.2020.3.46481

Malugari, A. R., Kumar K, M., & Silambanan, S. (2024). Role of blood urea nitrogen to creatinine ratio in the assessment of hypovolemia who have undergone major surgeries: A cross-sectional study. *Egyptian Journal of Internal Medicine, 36*, Article 97. https://doi.org/10.1186/s43162-024-00363-z

McGee, S., Abernethy, W. B., III, & Simel, D. L. (1999). Is this patient hypovolemic? *JAMA, 281*(11), 1022–1029. https://doi.org/10.1001/jama.281.11.1022

Medical Council of Canada. (2024). *List of normal lab values*. https://mcc.ca/examinations-assessments/resources-to-help-with-exam-prep/normal-lab-values/

Mukwende, M., Tamony, P., & Turner, M. (2020). *Mind the gap: A handbook of clinical signs in Black and Brown skin*. St George's, University of London. https://iiif.wellcomecollection.org/file/b32878382_0001.pdf

National Council of State Boards of Nursing. (2026). *2027 REx-PN test plan* [Effective January 1, 2027]. https://www.ncsbn.org/public-files/2027_RExPN-TestPlan.pdf

National Institute for Health and Care Excellence. (2017a). *Intravenous fluid therapy in over 16s in hospital* (Clinical guideline CG174; published 2013, last updated 2017). https://www.nice.org.uk/guidance/cg174

National Institute for Health and Care Excellence. (2017b). *Nutrition support for adults: Oral nutrition support, enteral tube feeding and parenteral nutrition* (Clinical guideline CG32; original work published 2006; last updated August 4, 2017). https://www.nice.org.uk/guidance/cg32

Omega Laboratories. (2020). *0.9% sodium chloride injection USP* [Product monograph]. https://pdf.hres.ca/dpd_pm/00057018.PDF

Parkinson, E., Hooper, L., Fynn, J., Howard Wilsher, S., Oladosu, T., Poland, F., Roberts, S., Van Hout, E., & Bunn, D. (2023). Low-intake dehydration prevalence in non-hospitalised older adults: Systematic review and meta-analysis. *Clinical Nutrition, 42*(8), 1510–1520. https://doi.org/10.1016/j.clnu.2023.06.010

Pfizer Canada. (2022). *Aldactone (spironolactone tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00068609.PDF

Registered Nurses' Association of Ontario. (2016). *Delirium, dementia, and depression in older adults: Assessment and care* (2nd ed.). https://rnao.ca/bpg/guidelines/assessment-and-care-older-adults-delirium-dementia-and-depression

Registered Nurses' Association of Ontario. (2021). *Vascular access* (2nd ed.). https://rnao.ca/bpg/guidelines/Vascular_Access

Rehman, H. U., & Wunder, S. (2011). Trousseau sign in hypocalcemia. *CMAJ, 183*(8), E498. https://doi.org/10.1503/cmaj.100613

Sandoz Canada. (2026). *Magnesium sulfate injection USP* [Product monograph]. https://pdf.hres.ca/dpd_pm/00083832.PDF

Sanis Health. (2026). *Hydrochlorothiazide tablets USP* [Product monograph]. https://pdf.hres.ca/dpd_pm/00083924.PDF

Society for Endocrinology Clinical Committee. (2013). *Emergency endocrine guidance: Acute hypocalcaemia (for use in adult patients)*. https://gloshospitals.nhs.uk/media/documents/Emergency_Guidance_Acute_Hypocalcaemia_in_Adults.pdf

Society for Endocrinology. (2022). *Emergency management of severe and moderately severely symptomatic hyponatraemia in adult patients* [Endocrine emergency guidance; S. Ball, J. Barth, M. Levy, & Society for Endocrinology Clinical Committee]. https://www.endocrinology.org/media/xhrhxhxm/emergency-management-of-severe-and-moderately-severely-symptomatic-hyponatraemia-in-adult-patients-2022.pdf

Spasovski, G., Vanholder, R., Allolio, B., Annane, D., Ball, S., Bichet, D., Decaux, G., Fenske, W., Hoorn, E. J., Ichai, C., Joannidis, M., Soupart, A., Zietse, R., Haller, M., van der Veer, S., Van Biesen, W., & Nagler, E. (2014). Clinical practice guideline on diagnosis and treatment of hyponatraemia. *European Journal of Endocrinology, 170*(3), G1–G47. https://doi.org/10.1530/EJE-13-1020

Sridharan, K. (2023). Chronic kidney disease mineral and bone disorder: A guide for general practice. *Australian Journal of General Practice, 52*(1–2), 52–57. https://doi.org/10.31128/AJGP-03-22-6365

SteriMax. (2025). *Calcium gluconate injection USP 10%* [Product monograph]. https://pdf.hres.ca/dpd_pm/00078717.PDF

University Health Network. (n.d.). *Urinalysis, routine* [Laboratory test dictionary]. https://forms.uhn.ca/LabDictionary/Public/View?lid=315

University of Ottawa, Faculty of Medicine. (2022). *Lab results* [Reference values]. https://www.uottawa.ca/faculty-medicine/sites/g/files/bhrskd401/files/2023-05/Lab%20Results%20Template_2022_final-EN.pdf

Walsh, J., Gittoes, N., Selby, P., & Society for Endocrinology Clinical Committee. (2016). Society for Endocrinology endocrine emergency guidance: Emergency management of acute hypercalcaemia in adult patients. *Endocrine Connections, 5*(5), G9–G11. https://doi.org/10.1530/EC-16-0055

Woodcock, T. E., & Michel, C. C. (2021). Advances in the Starling principle and microvascular fluid exchange; consequences and implications for fluid therapy. *Frontiers in Veterinary Science, 8*, Article 623671. https://doi.org/10.3389/fvets.2021.623671

Yap, E., & Goldwasser, P. (2022). Can ionized calcium-estimating equations replace albumin-corrected calcium? A narrative review. *Journal of Laboratory and Precision Medicine, 7*, Article 13. https://doi.org/10.21037/jlpm-22-16

Yun, G., Baek, S. H., & Kim, S. (2023). Evaluation and management of hypernatremia in adults: Clinical perspectives. *Korean Journal of Internal Medicine, 38*(3), 290–302. https://doi.org/10.3904/kjim.2022.346

04 Inflammation, Infection and Sepsis

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain the acute inflammatory response and the phases of wound healing, and identify factors that delay healing.
2. Recognize local and systemic cues of infection, including atypical presentations in older adults, and describe the nurse's role in specimen collection and in reviewing common blood tests.
3. Apply routine practices and additional precautions, including the point-of-care risk assessment, hand hygiene and safe use of personal protective equipment.
4. Describe the nurse's role in outbreaks and in reporting diseases of public health significance in Ontario.
5. Describe common antibiotic-resistant organisms and Clostridioides difficile infection, and the precautions and care each needs.
6. Explain the nurse's role in antimicrobial stewardship, including assessing a reported penicillin allergy and teaching safe antibiotic use.
7. Recognize early cues of sepsis, escalate promptly and carry out first-hour nursing care consistent with the 2026 Surviving Sepsis Campaign guideline.
8. Distinguish RN and RPN roles in infection and sepsis care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 5	Clinician; Scholar	Foundations of Practice
3, 4	Clinician; Leader; Advocate	Foundations of Practice; Professional Practice
6	Educator; Leader	Foundations of Practice; Collaborative Practice
7, 8	Clinician; Coordinator; Communicator	Foundations of Practice; Collaborative Practice; Accountability

Introduction

Infection is one of the most common complications on a medical-surgical unit. Patients arrive already ill, many are older adults, and most receive treatments that break the body's defences: surgery, intravenous (IV) catheters, urinary catheters, drains and medications that suppress immunity. A **health care-associated infection (HAI)** is an infection a person acquires while receiving health care (Provincial Infectious Diseases Advisory Committee [PIDAC], 2025). In a 2024 point prevalence survey of adult inpatients in 62 acute care hospitals in the Canadian Nosocomial Infection Surveillance Program, 8.1% of patients had at least one HAI on the survey day, almost unchanged from 8.4% in 2017 (Mitchell et al., 2025).

Nurses are at the bedside when infection begins. They clean their hands, choose protective equipment, care for devices and wounds, and notice the first cues: a warm, swollen incision, a new fever, a patient who is "not himself." Early recognition matters because an infection that is missed can progress to sepsis, a life-threatening emergency covered in section 4.6.

This chapter begins with inflammation and healing (section 4.1), then covers recognizing infection and its diagnostics (section 4.2) and infection prevention and control on the unit (section 4.3). Later sections address antibiotic-resistant organisms and *Clostridioides difficile*, antimicrobial stewardship and sepsis.

4.1 Inflammation and Healing

The Acute Inflammatory Response

Inflammation is the body's protective response to tissue injury or infection. It brings fluid, proteins and white blood cells to the injured area, contains and removes the cause, and prepares the tissue for repair. Microorganisms, surgery, trauma, burns, loss of blood supply and chemicals can all start it. This section covers only the innate (non-specific) response; immunity is covered in Chapter 21.

The response follows a similar sequence whatever the trigger. Receptors on cells detect damaged tissue or microbes, signalling pathways switch on, chemical messengers are released, and white cells are drawn to the site (Chen et al., 2018).

Vascular phase. Small blood vessels near the injury widen, so more blood flows to the area. The walls of the smallest vessels then become leaky. Plasma, proteins and fluid move out into the tissue, forming an **exudate** (Chen et al., 2018). The extra blood flow causes redness and heat; the leaked fluid causes swelling.

Cellular phase. White cells leave the bloodstream through the vessel walls and move toward the injury, following chemical signals. Neutrophils arrive first, followed by monocytes, which mature into macrophages in the tissue; lymphocytes and mast cells follow (Chen et al., 2018). Neutrophils and macrophages engulf and destroy microbes and dead cells. Pus is a thick exudate made of these cells, debris and microbes.

Figure 4.1 Cellulitis of the toes and forefoot. Spreading redness and swelling are local signs of inflammation and infection; on darker skin, redness can be harder to see, so the nurse also checks warmth, swelling and pain.

Chemical mediators. Mast cells release histamine and prostaglandins, which widen vessels and increase their leakiness. Immune cells release **cytokines**, small proteins that carry signals between cells. Some cytokines, such as interleukin-1β, interleukin-6 and tumour necrosis factor-α, promote inflammation; others damp it down (Chen et al., 2018). When cytokines reach the bloodstream in large amounts, they produce whole-body effects.

Local and Systemic Signs

The local signs of inflammation are redness, heat, swelling, pain and loss of function (Chen et al., 2018). Redness is harder to see on darker skin. On many skin tones, inflammation does not look red, so the nurse looks for any change from the surrounding skin or the same area on the other side and relies on warmth, swelling, skin tightness and pain (Wounds International, 2023). Warmth is felt by comparing the area with nearby skin, using the same hand. Good lighting and asking the patient what is normal for their skin help on every skin tone (Figure 4.1).

Systemic signs appear when inflammation is widespread or caused by infection. They include fever, a raised white cell count, malaise, fatigue and loss of appetite. The blood also contains more acute-phase proteins, such as C-reactive protein (Chen et al., 2018; see section 4.2). Table 4.1 summarizes these signs and what the nurse assesses.

Table 4.1 Local and systemic signs of inflammation and infection (BC Provincial Nursing Skin and Wound Committee, 2011; Chen et al., 2018; Evans et al., 2015; High et al., 2009; Wounds International, 2023)

Sign	What causes it	What the nurse assesses and documents
Redness (erythema)	Widened vessels bring more blood to the area	Colour compared with surrounding skin and the other side; on darker skin, any change in colour rather than redness; size of the affected area and whether it is spreading

Sign	What causes it	What the nurse assesses and documents
Heat	Increased blood flow to the area	Warmth compared with nearby skin and the other side, using the same hand
Swelling (edema)	Fluid and proteins leak from vessels into the tissue	Size or limb circumference, tightness, shine, firmness; change since the last assessment
Pain or tenderness	Chemical mediators and swelling stimulate nerve endings	Pain score, location and character; pain that is new or increasing rather than settling
Loss of function	Pain and swelling limit movement and use	Range of motion, ability to bear weight or use the limb, effect on mobility and self-care
Drainage (exudate)	Fluid, cells and debris leave the tissue; pus contains white cells and microbes	Amount, colour, consistency and odour; type (serous, bloody, purulent); drainage from incisions or drains
Fever	Cytokines raise body temperature as part of the response	Temperature, route, time and trend; recent antipyretic doses; comparison with the patient's baseline
Raised white cell count	Bone marrow releases more white cells, mostly neutrophils	White cell count and differential, and the trend over days
Malaise, fatigue, poor appetite	Circulating cytokines affect the whole body	Energy, intake, ability to do usual activities; in older adults, new confusion, falls or functional decline
Faster heart and breathing rates	Fever and infection raise the body's demand for oxygen	Vital signs trend; new or worsening changes, which may signal sepsis (section 4.6)

Acute and Chronic Inflammation

Acute inflammation is short-lived. Neutrophils dominate, the cause is removed, and the response switches off as neutrophils leave and macrophages shift from attacking to repairing (Chen et al., 2018). **Chronic inflammation** persists when the cause is not removed or the response fails to switch off. Macrophages and lymphocytes dominate, and ongoing damage and scarring can follow. Uncontrolled acute inflammation can become chronic and contribute to many chronic diseases (Chen et al., 2018), such as rheumatoid arthritis (Chapter 34) and wounds that fail to heal (Chapter 35).

Phases of Wound Healing

Wound healing has four overlapping phases, which must occur in the right order and time frame (Guo & DiPietro, 2010):

- **Hemostasis:** injured vessels constrict, platelets clump, and a fibrin clot seals the wound.
- **Inflammation:** neutrophils and then macrophages clear bacteria and debris; macrophages also release signals that start repair.
- **Proliferation:** fibroblasts lay down new collagen, new capillaries grow, and moist red granulation tissue fills the wound. Skin cells move across the surface, and the wound edges pull together.
- **Maturation (remodelling):** collagen is reorganized and the scar strengthens, flattens and fades over months.

In a closed surgical incision, a **healing ridge** is a normal sign of the proliferation phase. It is a firm, slightly swollen area under the incision line caused by new collagen. It starts on about postoperative days 2 to 4, should run the full length of the incision by days 5 to 9, and gradually softens and flattens over the following weeks (BC Provincial Nursing Skin and Wound Committee, 2011). A missing ridge is a warning sign, because it can be followed by separation of the incision (dehiscence) or infection (BC Provincial Nursing Skin and Wound Committee, 2011).

Healing by Primary, Secondary and Tertiary Intention

- **Healing by primary intention:** the wound edges are brought together with sutures, staples or tape, and the wound heals without needing to fill with granulation tissue, as in most surgical incisions.
- **Healing by secondary intention:** the edges cannot be closed, so the wound heals by filling with granulation tissue from the base up, as in a pressure injury or an opened, infected incision. Healing takes longer and leaves a larger scar.

- **Healing by tertiary intention (delayed primary closure):** the wound is left open for about 4 to 6 days, then closed before granulation tissue forms. Surgeons use it most often for contaminated or infected wounds (BC Provincial Nursing Skin and Wound Committee, 2011).

Factors That Delay Healing

Many factors can disturb one or more phases of healing (BC Provincial Nursing Skin and Wound Committee, 2011; Guo & DiPietro, 2010):

- **Diabetes:** high blood glucose impairs white cell function and circulation (Chapter 22).
- **Poor nutrition:** healing depends on protein and energy; one Canadian guideline notes that healing is impaired when serum albumin is below 35 g/L (BC Provincial Nursing Skin and Wound Committee, 2011; Chapter 24).
- **Smoking:** reduces oxygen delivery to the wound.
- **Older age:** healing is slower, and older adults more often have other conditions that delay it.
- **Medications:** systemic corticosteroids, nonsteroidal anti-inflammatory drugs, antineoplastic drugs and anticoagulants.
- **Other factors:** infection, poor blood flow or oxygenation, anemia, obesity, poor mobility, and long surgery or heavy blood loss.

The nurse identifies these factors on admission and before surgery and plans care to reduce them. Wound assessment and care are covered in Chapter 35.

4.2 Infection: Recognition and Diagnostics

The Chain of Infection

An **infection** occurs when microorganisms enter the body's tissues and multiply there (PIDAC, 2025). A person can also carry an organism that grows on or in the body without invading tissue or causing illness, which is called **colonization** (PIDAC, 2025); colonized patients can still spread the organism to others.

The **chain of infection** (also called the chain of transmission) is a model of how infection spreads. Transmission happens only when all six links are present, so breaking any one link stops it (PIDAC, 2025). The links and the nurse's actions are:

- **Infectious agent:** bacteria, viruses, fungi or parasites. The nurse helps identify the agent early with correct specimens and gives treatment as ordered.
- **Reservoir:** where the agent lives and multiplies, such as people, equipment, surfaces or water. The nurse cleans shared equipment, supports environmental cleaning, and stays home when ill.
- **Portal of exit:** how the agent leaves the reservoir, such as respiratory secretions, stool, blood or wound drainage. The nurse covers draining wounds, contains body fluids and teaches respiratory etiquette.
- **Mode of transmission:** how the agent travels, by contact, droplets or the airborne route. Hand hygiene, personal protective equipment and additional precautions break this link (section 4.3).
- **Portal of entry:** how the agent enters a new host, such as broken skin, mucous membranes or invasive devices. The nurse uses aseptic technique, cares for devices and asks daily whether each device is still needed. A Choosing Wisely Canada nursing recommendation warns against inserting or keeping an indwelling urinary catheter without daily assessment (Canadian Nurses Association, 2024).
- **Susceptible host:** a person who cannot resist the agent. The nurse supports immunization, nutrition, mobility, skin integrity and blood glucose control.

Host Risk Factors in Hospital

Patients on medical-surgical units are susceptible for several reasons:

- **Invasive devices:** IV and central venous catheters, urinary catheters, drains and breathing tubes bypass the skin and mucous membranes. In the Canadian surveys, bloodstream infections increased between 2017 and 2024, and central line-associated bloodstream infections roughly doubled (Mitchell et al., 2025).

- **Surgery:** an incision breaks the skin, and anesthesia and immobility raise the risk of pneumonia and urinary tract infection (Chapter 7).
- **Immunosuppression:** chemotherapy, corticosteroids, transplant medications, human immunodeficiency virus (HIV) infection and some chronic illnesses blunt the body's defences (Chapters 9 and 21).
- **Older age:** older adults often have several chronic conditions and may show infection differently. In one study of adults with bacteremia (bacteria in the blood), atypical symptoms such as new confusion, falls or declining function became more common with age (Wester et al., 2013).

Fever

Fever is a rise in body temperature that is a core part of the body's response to infection; cytokines such as interleukin-6 help trigger it (Evans et al., 2015). There is no single threshold used everywhere; hospital policy sets the value that triggers action. A guideline for evaluating new fever in critically ill adults suggests oral or rectal temperatures over less reliable sites, such as axillary, tympanic or temporal artery readings, when no central temperature device is in place (O'Grady et al., 2023). Older adults may not mount a high fever. A guideline for older adults in long-term care defines fever as a single oral temperature above 37.8 °C, repeated oral temperatures above 37.2 °C or rectal temperatures above 37.5 °C, or a rise of more than 1.1 °C above the person's baseline (High et al., 2009).

Antipyretics such as acetaminophen and ibuprofen lower temperature. A patient who received one for pain may have a normal temperature despite infection. The nurse checks the medication record when interpreting a temperature, and remembers that the absence of fever does not rule out infection.

Specimen Collection for Cultures

A **culture** grows organisms from a specimen so the laboratory can identify them and test which antimicrobials work against them (culture and sensitivity). The nurse collects specimens with aseptic technique, labels them at the bedside, and sends them promptly. When possible, cultures are collected before the first antimicrobial dose, as long as this does not delay treatment (Figure 4.2).

- **Blood cultures:** for an adult with suspected bacteremia, at least two sets are collected from separate sites (Alberta Precision Laboratories, 2024; O'Grady et al., 2023). Drawing from two sites helps the laboratory tell skin contamination from true infection, and the volume of blood is the most important factor in detecting bacteria (Alberta Precision Laboratories, 2024). In suspected sepsis, blood cultures are collected promptly, preferably before the first antimicrobial dose (Prescott et al., 2026). The nurse follows the hospital's skin antisepsis and bottle-filling procedure.
- **Urine from an indwelling catheter:** the nurse cleans the sampling port, clamps the tubing below it briefly, and withdraws urine from the port with a syringe. Urine is never taken from the drainage bag, and the closed drainage system is not opened (Alberta Precision Laboratories, n.d.).
- **Wound swabs:** a swab for culture is taken as ordered when a wound shows three or more signs of infection or is not improving with treatment (BC Provincial Nursing Skin and Wound Committee, 2011, 2015). In the Levine technique, the nurse cleanses the wound thoroughly with sterile normal saline or sterile water, then rotates the swab for 5 seconds over a 1 cm^2 area of viable (living) wound bed, pressing hard enough to draw out tissue fluid. Pus, slough and dead tissue are not swabbed because they can give misleading results; if no viable tissue is visible, the nurse does not take the swab and consults the prescriber or wound clinician (BC Provincial Nursing Skin and Wound Committee, 2015).
- **Stool for C. difficile:** only unformed stool is tested (PIDAC, 2013b; see section 4.4).

Blood Tests

- **White blood cell count and differential:** a typical adult reference range is 3.5 to 10.5 × 10^9/L, with segmented neutrophils 2.0 to 7.5 × 10^9/L (University of Ottawa, 2022); ranges vary by laboratory. Bacterial infection often raises the neutrophil count, sometimes with more immature band forms. A low count can also signal severe infection or a weakened immune system.
- **C-reactive protein (CRP):** an acute-phase protein whose blood level rises with inflammation (Chen et al., 2018). It is not specific to infection, so the trend over time is more useful than a single value.

- **Procalcitonin:** a blood marker of bacterial infection. For critically ill adults, a guideline suggests measuring it alongside clinical assessment when the likelihood of bacterial infection is low to intermediate, and supports using biomarkers to help decide when antibiotics can be stopped (O'Grady et al., 2023). Current sepsis guidelines suggest that clinicians decide whether to start antimicrobials on clinical evaluation rather than procalcitonin (Prescott et al., 2026).
- **Lactate:** a marker of tissue hypoxia and organ dysfunction, central to sepsis screening (section 4.6; acid–base in Chapter 3, section 3.7).



Figure 4.2 A blood culture bottle that has turned cloudy because organisms are growing in it. The laboratory then identifies the organism and tests which antimicrobials work against it.

CLINICAL JUDGMENT

A Surgical Site Infection on Postoperative Day 4

Mrs. Lucia Mendes, 67, has type 2 diabetes and is on postoperative day 4 after an open bowel resection. She has medium-brown skin.

Recognize cues: At 0800 her temperature is 38.4 °C (37.0 °C yesterday), heart rate 104, respiratory rate 20, blood pressure 128/76 (her baseline) and oxygen saturation (SpO2) 96% on room air. She is alert and oriented. Incision pain is 6/10, up from 3/10. The skin along the lower third of the incision is a deeper brown than the surrounding skin, swollen, firm, tight and warmer than the upper incision. Cloudy, yellow, foul-smelling drainage stains the dressing. White blood cell count is 13.8 × 10^9/L (9.2 × 10^9/L on day 2); capillary glucose is 12.4 mmol/L.

Analyze cues: Local signs (colour change, warmth, swelling, purulent drainage, rising pain) plus systemic signs (fever, rising heart rate and white cell count) point to infection. A healing ridge would be firm but would not drain pus or worsen.

Prioritize hypotheses: A surgical site infection is most likely. Early sepsis must be considered because her heart rate and temperature are rising. High glucose may slow healing.

Generate solutions: Report promptly to the surgeon using SBAR (Situation, Background, Assessment, Recommendation; Chapter 6); request orders for a wound swab, blood cultures and antibiotics; screen for sepsis using the hospital's tool; increase vital sign frequency.

Take action: The nurse reports, collects the wound swab and blood cultures as ordered, then gives the first antibiotic dose without delay. The nurse applies a dry dressing as ordered and reports the glucose.

Evaluate outcomes: Four hours later, temperature is 37.9 °C, heart rate 96 and mentation unchanged. The nurse documents the extent of the colour change and plans to escalate at once if blood pressure falls, breathing quickens or confusion appears.

4.3 Infection Prevention and Control on the Unit

Routine Practices

Routine practices are the infection prevention and control (IPAC) practices used with every patient, during all care, whether or not an infection is known or suspected. They are the minimum standard for all patients (Public Health Ontario [PHO], n.d.-c). Chapter 1, section 1.6, introduced them; this section covers them in full. PIDAC (2025) groups routine practices into five elements:

- **Risk assessment** before each interaction with a patient or the patient's environment.
- **Hand hygiene.**
- **Personal protective equipment (PPE).**
- **Control of the environment:** patient placement, cleaning, and engineering controls such as sinks, hand rub dispensers and ventilation.
- **Administrative controls:** policies and procedures, education for staff, healthy workplace policies (such as staying home when ill and staff immunization), respiratory etiquette, and monitoring compliance with feedback.

Point-of-Care Risk Assessment

A **point-of-care risk assessment (PCRA)** is the quick check a health care provider makes before every interaction to judge the risk of spreading or acquiring infection, and to choose the right actions. It considers the task, the patient and the environment. The risk can change during care, so the assessment is repeated as care goes on (PIDAC, 2025). Before entering, the nurse asks:

- Will my hands, skin or clothing touch blood, body fluids, secretions, excretions, non-intact skin, mucous membranes or contaminated equipment or surfaces?
- Could the task cause splashes or sprays?
- Does the patient have signs of a possible infection, such as new cough, fever, diarrhea, vomiting, rash or draining wounds?
- Could the patient be carrying an antibiotic-resistant organism?
- Can the patient follow hand hygiene and respiratory etiquette?

The answers decide which PPE to wear, where the patient should be placed, and whether additional precautions are needed. Published tables list the minimum precautions for each condition; the PCRA can call for more (PIDAC, n.d.).

Hand Hygiene

Hand hygiene is removing or killing microorganisms on the hands, with alcohol-based hand rub (ABHR) or with soap and running water. It is central to every other routine practice. Ontario's Ministry of Health launched the Just Clean Your Hands program for hospitals in 2008 (PHO, n.d.-b). It teaches four moments for hand hygiene (Ontario Ministry of Health and Long-Term Care, 2011; Figure 4.3):

- **Moment 1, before initial contact with the patient or the patient's environment:** on entering, before touching the patient or anything around them. This protects the patient from organisms on the provider's hands.
- **Moment 2, before an aseptic procedure:** immediately before tasks such as changing a dressing, providing mouth care, drawing blood or giving IV medication. This protects the patient from organisms, including their own, entering the body.
- **Moment 3, after a risk of body fluid exposure:** immediately afterward, including after removing gloves. This protects the provider and the health care environment.
- **Moment 4, after contact with the patient or the patient's environment:** on leaving. This protects the provider and the next patient.

ABHR is the preferred method when hands are not visibly soiled (PIDAC, 2025). It works quickly and can be placed at the point of care. Soap and water is needed when hands are visibly soiled. It is also preferred after caring for a patient with *C. difficile* infection when a dedicated staff sink is immediately available, because soap and water is thought to remove the bacterium's spores better than ABHR; if no staff sink is close by, ABHR is used after glove removal. Hand hygiene is never done at the patient's sink (PIDAC,

2013b; see section 4.4). Gloves never replace hand hygiene. The nurse also helps patients clean their hands, for example before meals and after using the toilet.

Figure 4.3 A wall-mounted alcohol-based hand rub dispenser in a hospital in the United States. (credit: "Purell hand sanitizer device at Memorial Regional Hospital" by Claudia Brauer/Wikimedia Commons, CC BY 2.0)

Personal Protective Equipment

Personal protective equipment (PPE) is clothing and equipment that act as a barrier between the provider and infectious material. The PCRA guides the choice. PPE is put on just before the interaction and removed promptly afterward (PIDAC, 2025).

- **Gloves:** worn when hands may touch blood, body fluids, mucous membranes, non-intact skin or contaminated items. Gloves are single-use and specific to one task. They are changed between tasks on the same patient, such as moving from a soiled to a clean site.
- **Gowns:** worn when splashes or sprays are likely or when clothing may touch the patient or contaminated surfaces. A gown should have long sleeves with cuffs and be tied at the neck and waist (PIDAC, 2025).
- **Facial protection:** a mask with eye protection (goggles, a face shield or a mask with a visor) protects the mucous membranes of the eyes, nose and mouth during tasks likely to splash, such as suctioning. It is also worn within 2 metres of a coughing patient. Prescription glasses alone are not eye protection (PIDAC, 2025).
- **N95 respirator:** a close-fitting respirator that filters 95% of particles about 1 micron in size. It protects the wearer from breathing in small infectious particles (PIDAC, 2025). Each provider must be fit-tested at least every two years, and again if the face piece or the person's face changes. The wearer does a seal check every time it is put on (PIDAC, 2025; PHO, 2024).

CLINICAL SAFETY

Removing PPE Safely

Taking PPE off is the moment of highest risk. The outside of gloves, gown, eye protection and mask may be contaminated, and a hurried or out-of-order removal can transfer organisms to the nurse's skin, face or clothing. PIDAC (2025) calls for removal to follow a formal protocol exactly. Public Health Ontario's recommended sequence (PHO, 2024) is:

- **Gloves first:** remove them without letting bare skin touch the outside of the glove.
- **Gown:** untie, pull it away from the body, roll it inside out and discard it.
- **Hand hygiene.**
- **Eye protection:** remove it by lifting it up and away from the face without touching the front.
- **Mask or N95 respirator:** remove it by the ear loops or straps, pulling forward and away from the face.
- **Hand hygiene** again.

When only gloves and a gown are worn, as for contact precautions, hand hygiene follows removal of the gown (PHO, 2024). Hand hygiene uses ABHR, or soap and water if hands are visibly soiled. Each item goes straight into the correct waste or reprocessing container. The nurse follows the hospital's posted sequence and location for removal, which may differ for an N95 respirator.

Additional Precautions

Additional precautions are measures used on top of routine practices for certain organisms or clinical presentations (PIDAC, 2025). The three types are contact, droplet and airborne precautions, and some infections need a combination. Precautions start as soon as an infection is suspected from the patient's symptoms, not when test results return. For example, contact precautions begin at the

onset of diarrhea, before *C. difficile* results are known (PIDAC, 2013b). A sign at the door tells everyone entering what is required. Table 4.2 compares the precautions.

- **Contact precautions** reduce spread by direct contact with the patient or indirect contact with the patient's surroundings and equipment. They are used for antibiotic-resistant organisms such as methicillin-resistant *Staphylococcus aureus* (MRSA), vancomycin-resistant enterococci (VRE) and carbapenemase-producing Enterobacterales (CPE), covered in section 4.4.
- **Droplet precautions** are for organisms spread by large respiratory droplets, produced by coughing or sneezing, which travel a short distance before falling.
- **Airborne precautions** are for organisms carried on very small particles that stay suspended in the air and can travel on air currents (PIDAC, 2025).
- **Droplet and contact precautions** combine all elements of both, for organisms such as common respiratory viruses that spread by droplets and by contaminated hands and surfaces (PHO, n.d.-a).

Table 4.2 Additional precautions compared (PHO, n.d.-a; PIDAC, 2025, n.d.)

Precaution	How the organism spreads	Examples	Room	PPE and key actions
Contact	Direct contact with the patient, or indirect contact with contaminated surfaces and equipment	MRSA, VRE, CPE, C. difficile, norovirus, acute infectious gastroenteritis	Single room (with own toilet for diarrhea), or shared with patients who have the same laboratory-confirmed organism	Gown and gloves on entering; dedicated equipment; enhanced cleaning for C. difficile and VRE
Droplet	Large respiratory droplets travel a short distance (within about 2 metres) and land on mucous membranes	Pertussis, invasive meningococcal disease, mumps	Single room, or at least 2 metres from others with the curtain drawn	Mask and eye protection within 2 metres; dedicated equipment; patient wears a mask outside the room
Droplet and contact	Droplets plus contaminated hands, surfaces and equipment	Influenza, respiratory syncytial virus, COVID-19, invasive group A streptococcal wound infection	Single room	All droplet and contact elements combined: gown, gloves, mask and eye protection
Airborne	Small particles stay suspended in the air and travel on air currents	Pulmonary tuberculosis, measles, chickenpox, disseminated shingles (measles also needs droplet and contact precautions; chickenpox and disseminated shingles also need contact precautions)	Airborne infection isolation room (negative pressure) with the door kept closed	Fit-tested, seal-checked N95 respirator (for measles, also gloves, gown and eye protection); only staff with presumptive immunity care for patients with measles, chickenpox or disseminated shingles; patient wears a mask outside the room

An **airborne infection isolation room (AIIR)**, also called a negative pressure room, is designed and ventilated to keep airborne organisms from spreading beyond it (PIDAC, 2025). When airborne spread is suspected, the patient moves as soon as possible to a single room, ideally a negative pressure room (PIDAC, 2025).

Visitors receive teaching on hand hygiene. Visitors who help with care follow the same precautions as staff (PIDAC, 2013b). Additional precautions can leave patients feeling lonely or stigmatized. The nurse explains why the precautions are needed, keeps the call bell in reach, and checks on the patient as often as on any other patient. Precautions stop only when the criteria for the organism are met, in consultation with the IPAC team.

Cleaning the Environment and Shared Equipment

Organisms survive on bed rails, call bells, commodes, vital sign machines and glucometers, so the environment is a reservoir. Control of the environment is one of the five elements of routine practices (PIDAC, 2025). Shared equipment is cleaned and disinfected between patients with a hospital-approved product, following the manufacturer's instructions and hospital policy. Patients

on contact precautions have dedicated equipment that stays in the room. Rooms of patients with *C. difficile* or VRE need enhanced cleaning (PIDAC, 2025). For *C. difficile*, PIDAC recommends a sporicidal agent, cleaning twice daily, and double cleaning at discharge or transfer (PIDAC, 2013b). Nurses work with environmental services staff, report spills and soiled items promptly, and never move used equipment from one room to another without cleaning it.

Outbreaks and the Nurse's Role

An **outbreak** is a rise in cases of an infection above what is expected in a particular place and time. Each infection has its own outbreak definition. In Ontario, for example, a confirmed respiratory infection outbreak in a public hospital is defined as two or more patients with health care-associated, test-confirmed acute respiratory infection whose symptoms began within 48 hours of each other and who share an epidemiological link (for example, the same unit) that suggests spread within the hospital. Cases among staff alone do not make an outbreak. Either the hospital or the medical officer of health can declare an outbreak (Ontario Ministry of Health, 2024).

The nurse's role is to:

- **Recognize:** notice clusters, such as two patients on the same unit with new diarrhea or a new cough, or several staff members ill with similar symptoms.
- **Act and report:** start additional precautions based on symptoms, collect specimens as ordered, and report promptly to the charge nurse and the IPAC team.
- **Follow outbreak measures:** the IPAC team and public health may direct measures such as stricter precautions, cohorting, closing the unit to admissions, limiting visits, or enhanced cleaning. The nurse follows them consistently and explains them to patients and families.
- **Protect others:** stay home when ill and report symptoms to occupational health.

> CANADIAN CONTEXT
>
> **Reportable Diseases and Outbreaks in Ontario**
>
> In Ontario, the *Health Protection and Promotion Act* and its regulations require reports of certain infections to the medical officer of health for the area. Ontario Regulation 135/18 lists these designated **diseases of public health significance**. Examples are tuberculosis, measles, CPE and invasive group A streptococcal disease. The list also includes outbreaks of respiratory infection and of gastroenteritis in institutions and public hospitals, and *C. difficile* outbreaks in public hospitals (Peel Region, n.d.).
>
> Public health unit guidance names laboratories, physicians, and the administrators of hospitals, schools and institutions among those who must report suspected or confirmed cases (Middlesex-London Health Unit, 2026). Some diseases must be reported immediately; others by the next working day (Peel Region, n.d.). Each hospital's policy sets out how it meets its reporting duties and how it works with the local public health unit during an outbreak. A nurse who suspects a reportable disease or a cluster tells the charge nurse and the IPAC team at once and follows that policy. Each province and territory has its own public health law and list of reportable diseases; nurses learn the rules where they work.

4.4 Antibiotic-Resistant Organisms and C. difficile

Some bacteria survive the drugs meant to kill them. An **antibiotic-resistant organism (ARO)** is a microorganism that has changed so that one or more antibiotics that once treated it no longer work well against it. Resistance spreads mainly through the overuse and misuse of antimicrobial drugs, because each exposure gives resistant strains an advantage over susceptible ones. Infections caused by AROs are linked to longer hospital stays, more complications and more deaths (Canadian Nurses Association [CNA], n.d.; Public Health Agency of Canada [PHAC], 2017).

A person can carry an ARO on the skin, in the nose or in the bowel without being ill. This is colonization (section 4.2); when the organism invades tissue and causes illness, the person has an infection. The difference matters for care: a colonized patient has no symptoms but can still pass the organism to others, so the same precautions apply to both (PIDAC, 2013a).

Three Organisms to Know

- **Methicillin-resistant Staphylococcus aureus (MRSA):** a strain of *S. aureus* that resists methicillin and related beta-lactam antibiotics. It lives on the skin and in the front of the nose. In hospitals it travels mainly on the briefly contaminated hands of health care workers, and on shared equipment and surfaces (Canadian Nosocomial Infection Surveillance Program [CNISP], 2026; PIDAC, 2013a).
- **Vancomycin-resistant enterococci (VRE):** enterococci are bowel bacteria; VRE no longer respond to vancomycin. The patient's bowel is the main reservoir, and the room becomes more heavily contaminated when the patient has diarrhea (PIDAC, 2013a).
- **Carbapenemase-producing organisms (CPO):** bacteria that make carbapenemases, enzymes that make carbapenem antibiotics ineffective, which leaves few treatment options. The best-known group is the **carbapenemase-producing Enterobacterales (CPE)**, which colonize the lower bowel. CPE spread by direct and indirect contact, and sinks and drains have been the source of some hospital outbreaks (CNISP, 2026; PIDAC, 2013a).

The key features of each organism, and of *C. difficile*, are compared in Table 4.3.

What Canadian Surveillance Shows

The **Canadian Nosocomial Infection Surveillance Program (CNISP)**, run by PHAC with sentinel hospitals across the country, tracks healthcare-associated infections and resistance. Its most recent report covers 2020 to 2024, with 109 sentinel acute care hospitals taking part across 10 provinces and 1 territory. Over those five years, rates of MRSA bloodstream infection and *C. difficile* infection stayed stable. Rates of VRE bloodstream infection rose significantly, from 0.30 to 0.42 per 10,000 patient days. Carbapenemase-producing Enterobacterales infections remained uncommon but rose significantly, from 0.05 to 0.20 per 10,000 patient days, with yearly cases climbing from 39 to 218 (CNISP, 2026). These figures describe participating hospitals, not every hospital in Canada.

Screening on Admission

Many hospitals screen patients for AROs on admission. Screening usually targets risk factors such as a previous positive result, a stay in any health care facility within the past year, health care received outside Canada, transfer from another facility, or contact with a unit having an outbreak (PIDAC, 2013a). MRSA screening uses swabs of the nose and the perianal or groin area, plus any wounds or device sites; VRE and CPE screening uses a rectal swab or stool. Who is screened, which organisms are included and when precautions start are set by each hospital's IPAC team, so the nurse follows local policy. A patient at high risk may be placed on Contact Precautions while results are pending. Contact Precautions and personal protective equipment are taught in section 4.3. Patients with CPE need a single room with their own toilet or commode and dedicated equipment (PIDAC, 2013a).

Clostridioides difficile Infection

Clostridioides difficile (often shortened to *C. difficile*) is a gram-positive, anaerobic bacterium that releases toxins in the colon. It is the most common cause of infectious diarrhea acquired in Canadian health care settings. Illness ranges from mild diarrhea to severe inflammation of the colon (pseudomembranous colitis), bowel perforation and sepsis (PHAC, 2013; Figure 4.4).



Figure 4.4 (a) *Clostridioides difficile* bacteria from a stool sample, seen with a scanning electron microscope. (b) Methicillin-resistant *Staphylococcus aureus* (MRSA, gold) and a dead human neutrophil (red), with colour added. (credit: (b) "Scanning electron micrograph of Methicillin-resistant Staphylococcus aureus (MRSA) and a dead Human neutrophil" by NIAID/Wikimedia Commons, CC BY 2.0)

The organism forms **spores**: dormant, thick-walled forms that survive for months on surfaces, resist many chemical disinfectants and become active again once swallowed. Spores move from patient to patient by the fecal–oral route, carried on hands and on contaminated equipment, bed rails and especially bathrooms (PHAC, 2013; PIDAC, 2013b).

Risk factors. Recent antibiotic use is the strongest risk factor, because antibiotics disturb the normal bowel bacteria that keep *C. difficile* in check. Other factors include proton pump inhibitors, hospitalization, chemotherapy, bowel disease or bowel surgery, and immune-suppressing drugs after transplant. Older age and a previous episode increase the risk of severe disease (PIDAC, 2013b).

Recognition and testing. For *C. difficile* testing, diarrhea means loose or watery stool that takes the shape of its container, is unusual for the patient and has no other likely cause, such as a laxative. The patient may also have fever, cramping, abdominal tenderness or nausea. The nurse sends a stool specimen as soon as diarrhea begins. Only unformed stool is tested; formed stool is not sent, and testing is not repeated to prove cure (PIDAC, 2013b).

Precautions. The nurse starts Contact Precautions at the first episode of unexplained diarrhea, without waiting for results. The patient needs a single room with a dedicated toilet, or a dedicated commode, and dedicated equipment such as a blood pressure cuff and stethoscope (PHAC, 2013). Hand hygiene changes: spores resist many chemicals, and soap and running water are preferred over ABHR because washing physically removes spores from the hands. The nurse removes gloves and washes at a staff sink, never the patient's sink. If no staff sink is close by, the nurse uses ABHR and then washes with soap and water as soon as a staff sink is available (PHAC, 2013; PIDAC, 2013b). Environmental services clean the room with a sporicidal agent, such as a chlorine-based product of 1,000 parts per million or more (PHAC, 2013; PIDAC, 2013b). Precautions usually continue until the patient has had no diarrhea for at least 48 hours and the room has had a final sporicidal cleaning, decided with IPAC (PIDAC, 2013b).

Nursing care. The nurse records the number, volume and character of stools and watches fluid balance, since diarrhea can quickly cause dehydration and potassium loss, especially in older adults (see Chapter 3). The perineal skin needs gentle cleansing after each stool and a barrier product to prevent breakdown. Disposable bedpans reduce spread. The nurse asks the prescriber to review antibiotics, proton pump inhibitors and any laxatives still ordered. Worsening abdominal pain or distension, high fever, a falling blood pressure or a sudden stop in diarrhea with a swelling abdomen can signal severe disease and need immediate escalation. Treatment and other bowel disorders are covered in Chapter 25.

Table 4.3 Common antibiotic-resistant organisms and C. difficile (PHAC, 2013; PIDAC, 2013a, 2013b)

Organism	How it spreads in hospital	Precautions	Nursing points
MRSA	Hands of staff after touching a colonized patient; shared equipment and surfaces	Contact Precautions; single room preferred	Screen as hospital policy directs (nose, perianal or groin, wounds); colonized patients can spread it without symptoms

Organism	How it spreads in hospital	Precautions	Nursing points
VRE	From bowel carriage to hands, equipment and surfaces; more spread when the patient has diarrhea	Contact Precautions; single room with own toilet or commode	Clean high-touch surfaces; take extra care with toileting and incontinence care
CPO (including CPE)	Direct and indirect contact from bowel carriage; sinks and drains have caused outbreaks	Contact Precautions; single room with own toilet or commode; dedicated equipment	Ask about health care received outside Canada; contacts may need screening; few antibiotics remain effective
C. difficile	Spores on hands, equipment and surfaces, mainly bathrooms; fecal–oral route	Contact Precautions from first diarrhea; dedicated equipment; sporicidal cleaning	Wash with soap and water at a staff sink; test only unformed stool; manage fluids and perineal skin

4.5 Antimicrobial Stewardship and the Nurse

Antimicrobial stewardship is the coordinated effort to use antimicrobial drugs only when they are needed, and then to choose the right drug, dose, route and duration. Its goals are better patient outcomes, fewer adverse drug reactions, fewer cases of *C. difficile* infection and slower growth of resistance (Alberta Health Services [AHS], n.d.). Every unnecessary course of antibiotics exposes the patient to side effects and gives resistant bacteria an advantage, as section 4.4 explains. Accreditation Canada lists an antimicrobial stewardship program as a required organizational practice for acute care sites (AHS, n.d.).

Stewardship is often pictured as the work of infectious disease physicians and pharmacists, but nurses give most doses, collect most specimens and spend the most time with patients. The CNA has published a pan-Canadian framework of stewardship competencies for all categories of nurses. It names roles such as monitoring for infection and side effects, acting as stewards of laboratory testing, recording allergies accurately, preventing infection and teaching patients (CNA, n.d.).

Before and at the First Dose

- **Collect cultures first, without causing delay.** When an infection is suspected, the nurse collects ordered cultures before the first dose whenever this can be done quickly. Antibiotics can sterilize a specimen within hours and hide the cause. In serious infection, the dose is not held back for a culture that cannot be collected promptly (Prescott et al., 2026).
- **Collect good specimens.** A contaminated blood culture or a urine sample sent without symptoms can lead to treatment the patient does not need. Careful technique and specimen collection only when indicated are part of stewardship (CNA, n.d.).
- **Give the first dose on time.** A first dose that waits on the unit for hours undoes the benefit of a fast diagnosis. This matters most in sepsis, where minutes count (section 4.6).

While the Patient Is on Antimicrobials

- **Monitor the response.** The nurse tracks temperature, heart rate, white blood cell count, wound or sputum changes and how the patient feels, and reports whether the patient is improving.
- **Watch for adverse effects.** Rash, new diarrhea, signs of *C. difficile* infection, infusion-site problems and changes in kidney function are reported promptly.
- **Prompt an IV-to-oral review.** A switch from intravenous to oral therapy shortens hospital stays and reduces catheter complications such as line infection and clots. Patients are usually candidates when they are afebrile, their white cell count is returning to normal, they are clinically improving and they can eat and absorb oral drugs (PHO, 2016). The nurse who notices these signs raises the question with the prescriber or pharmacist; some hospitals have approved criteria-based switch programs.
- **Ask about duration and results.** When culture results return, the nurse makes sure the prescriber has seen them so that therapy can be narrowed to target the organism. Guidelines favour narrowing treatment once the organism is known and, when the source is controlled, shorter courses over longer ones (Prescott et al., 2026). Asking "What is the planned stop date?" at rounds is a simple stewardship act.

Assessing a Reported Penicillin Allergy

Penicillin allergy labels are common in health records, and most do not hold up when they are assessed. The Ontario Medical Association's Section on Allergy states that more than 80% of people whose penicillin allergy is suspected may be safely delabelled (Ontario Medical Association [OMA], 2025). A wrong label pushes prescribers toward alternative antibiotics, and delabelling has been linked to less antibiotic resistance and fewer *C. difficile* infections (Atkinson et al., 2023).

The nurse's role is a careful history, not a judgment. An **allergy** is an immune reaction, such as hives, swelling of the lips or throat, wheezing or a severe skin reaction. An **intolerance** is an expected side effect, such as nausea, diarrhea, abdominal pain or headache. Side effects are not allergic reactions (OMA, 2025). The nurse asks:

- Which drug was it, and when?
- What exactly happened, how soon after the dose, and how was it treated?
- Has the patient taken a penicillin, such as amoxicillin, since then without trouble?
- Is the "allergy" really a family member's reaction?

The nurse documents the answers in the patient's own words and shares them with the prescriber or pharmacist. The nurse never removes or changes an allergy label alone. Delabelling is a decision made by a prescriber or an allergist, sometimes after a supervised oral challenge or skin testing, following hospital policy (OMA, 2025). Allergy and drug reactions are covered further in Chapter 21.

PATIENT EDUCATION

Taking Antibiotics Safely

- Antibiotics treat bacteria. They do not help colds, flu or most sore throats, which are caused by viruses.
- Take each dose at the times and for the number of days your prescriber or pharmacist tells you. Do not stop early or change the dose on your own. If you feel better and wonder whether you still need it, ask first.
- Never share antibiotics, and never take someone else's or an old leftover supply.
- Take unused antibiotics back to a pharmacy. Do not keep them or flush them.
- If you miss a dose, check the medication label or call your pharmacist. Do not take two doses at once unless you are told to.
- Call your health care provider if you get a rash, swelling, trouble breathing or any reaction that worries you. For trouble breathing or swelling of the face or throat, call 9-1-1.
- New watery diarrhea during or after a course of antibiotics needs a call to your provider.

Sources: PHAC (2014, 2017).

4.6 Sepsis

Sepsis is "life-threatening organ dysfunction caused by a dysregulated host response to infection" (Singer et al., 2016, p. 801). "Dysregulated" is the key idea: the body's own response to an infection, not only the microbe, injures organs far from the source (Singer et al., 2016). Sepsis can start from any infection, such as pneumonia, a urinary tract infection, a wound or an abdominal leak after surgery. It is a medical emergency, and the nurse is usually the first to see it.

Definitions

The Third International Consensus Definitions (Sepsis-3) set the current definitions (Singer et al., 2016):

- **Sepsis:** suspected or confirmed infection plus acute organ dysfunction, measured as a rise of 2 or more points in the **Sequential Organ Failure Assessment (SOFA) score**. In patients with suspected infection, this change carries an in-hospital mortality of about 10%.
- **Septic shock:** a subset of sepsis in which circulatory, cellular and metabolic changes are severe enough to raise the risk of death substantially. Clinically, the patient needs a vasopressor to keep the mean arterial pressure (MAP) at 65 mm Hg or higher and has a serum lactate above 2 mmol/L, even after adequate fluid resuscitation. More than 40% of these patients die in hospital.

Older definitions used the **systemic inflammatory response syndrome (SIRS)** criteria: abnormal temperature, fast heart rate, fast breathing and an abnormal white cell count. Sepsis-3 dropped SIRS as part of the definition. Many patients in hospital meet SIRS criteria without infection or poor outcomes, while some patients with infection and organ failure do not meet them (Singer et al., 2016). SIRS criteria may still help identify infection, and some hospitals use them in screening. The older term "severe sepsis" is no longer used.

Sepsis in Canada

Sepsis is a common contributor to death. A Statistics Canada analysis of death certificates found that in 2011 about 1 in 18 deaths in Canada involved sepsis, as either the underlying or a contributing cause. From 2009 to 2011, death rates involving sepsis rose with age and were highest in people 85 and older (Navaneelan et al., 2016). Because the analysis relied on codes for septicemia, the authors note it may undercount sepsis.

Who Is at Risk

Anyone with an infection can develop sepsis, but risk is higher with (Healthcare Excellence Canada [HEC], n.d.):

- older age (see the Lifespan Considerations box);
- chronic disease, with or without organ dysfunction;
- weakened immune defences, from disease or from immune-suppressing drugs;
- implanted or invasive devices, such as intravascular catheters;
- changes to normal anatomy that block a passage or breach a sterile body space, such as an obstructed urinary tract;
- pregnancy.

People who cannot describe their symptoms often present later in their illness (HEC, n.d.).

Structural factors also shape risk. Living far from hospital, as many people in rural, remote and northern communities do, including many First Nations and Inuit communities, can delay assessment and treatment. Barriers such as language, cost of travel and past experiences of racism in health care can delay a person from seeking care (see Chapter 2). The nurse takes a person's concern seriously at first contact.

Recognizing Sepsis Early

Sepsis rarely announces itself with one dramatic sign. More often, several small changes appear together over hours. Trends matter more than single values: a respiratory rate that climbs from 16 to 24 over a shift is a warning, even if no single reading looks alarming. The nurse compares each finding with the patient's own baseline and takes concerns from family members and colleagues seriously, because they often notice changes first. Table 4.4 links each cue to its meaning and to the nurse's action. Key cues include:

- **Temperature:** fever, or a low temperature; a low temperature is a sign of serious illness, not reassurance, and in septic patients it is linked to higher mortality than a normal temperature or fever (Rumbus et al., 2017).
- **Heart rate and breathing:** a rising heart rate and a rising respiratory rate. Respiratory rate is one of the qSOFA items (see Screening Tools) and is easy to overlook if it is not counted carefully.
- **Blood pressure:** a falling systolic pressure or MAP compared with the patient's baseline.
- **Mental status:** new confusion, drowsiness, agitation or "just not themselves," often reported first by family.
- **Skin and perfusion:** cool, clammy skin; slow capillary refill; mottling. **Mottling** is a patchy, lace-like discolouration that usually begins around the knees. On lighter skin it appears purple or blue; on darker skin it can be hard to see, and a study of mottling scores excluded patients with dark skin for that reason (Dumas et al., 2019). The nurse therefore does not rely on colour alone: they press the nail bed or fingertip to time capillary refill, feel whether the knees, hands and feet are cooler than the trunk, and compare findings with the patient's usual appearance and the family's observations.
- **Urine output:** low or falling output, a sign that the kidneys are underperfused.
- **Oxygenation:** falling oxygen saturation or a rising oxygen need.
- **Laboratory values:** a **lactate** level above 2 mmol/L (the reference range varies by laboratory), rising creatinine, a falling platelet count, or a white cell count that is high or low. Lactate and acid–base balance are taught in Chapter 3, section 3.7.

Sepsis is a clinical diagnosis. No single test rules it in or out (Prescott et al., 2026).

Screening Tools

Hospitals use screening tools to catch sepsis earlier, and Ontario hospitals use different ones. The **quick SOFA (qSOFA)** score gives one point each for a respiratory rate of 22 breaths per minute or more, altered mentation, and a systolic blood pressure of 100 mm Hg or less; two or more points flag a higher risk of a poor outcome (Singer et al., 2016). qSOFA is specific but not sensitive: in the original study only about one in four infected patients scored 2 or more, so many patients who were developing sepsis scored lower (Evans et al., 2021). For this reason, the Surviving Sepsis Campaign recommended against qSOFA as a single screening tool in 2021 (Evans et al., 2021). Its 2026 update, for acutely ill hospital patients, recommends screening with the National Early Warning Score (NEWS or NEWS2), the Modified Early Warning Score (MEWS) or SIRS in preference to qSOFA when one tool is used alone (strong recommendation, moderate certainty; Prescott et al., 2026). A positive qSOFA should still prompt assessment. Early warning scores are taught in Chapter 6.

First-Hour Care

Treatment follows the most recent Surviving Sepsis Campaign guideline (Prescott et al., 2026). The guideline grades a **strong** recommendation ("we recommend") as one most clinicians should follow, and a **conditional** recommendation ("we suggest") as one that depends on the patient and setting. The first steps the nurse will see and help deliver are:

- **Measure lactate.** The guideline suggests measuring blood lactate in possible, probable or definite sepsis, and in septic shock, and, when lactate is raised or the patient is in shock, using repeat measurements to guide resuscitation (both conditional, low certainty).
- **Blood cultures before antimicrobials.** Cultures are collected as soon as possible and, when it can be done, before the first antimicrobial dose (strong, low certainty). Collecting cultures must not delay the first dose.
- **Give antimicrobials quickly.** For septic shock, or probable or definite sepsis, antimicrobials are given at once, ideally within 1 hour of the team recognizing it (strong, very low certainty). When sepsis is only possible and the patient is not in shock, the team does a rapid, time-limited assessment and, if infection is still a concern, gives antimicrobials no later than 3 hours after sepsis was first suspected (conditional, very low certainty).
- **Fluids for low perfusion.** For sepsis-induced hypoperfusion (for example, low blood pressure or a high lactate) or septic shock, the guideline suggests at least 30 mL/kg of crystalloid, given intravenously, within the first 3 hours (conditional, low certainty), with frequent reassessment to avoid giving too little or too much. Crystalloids are recommended as first-line fluid (strong, moderate certainty), with balanced crystalloids suggested over 0.9% sodium chloride (conditional, moderate certainty). IV fluids are taught in Chapter 3, section 3.3.
- **Vasopressors if hypotension persists.** If blood pressure stays low after the first fluid bolus, vasopressors are started; the guideline recommends an initial MAP target of 65 mm Hg (strong, moderate certainty) and suggests 60 to 65 mm Hg for adults 65 and older (conditional, low certainty). Shock and vasopressors are taught in Chapter 6.
- **Find and control the source.** Draining an abscess, removing an infected device or repairing a leak is done early, ideally within 6 hours of diagnosis (conditional, very low certainty).

Nursing Priorities and Escalation

The Clinical Judgment Measurement Model (CJMM; Chapter 1, section 1.4) gives the nurse's thinking a clear shape. The nurse **recognizes** cues and trends, not single values; **analyzes** them by asking, "Could this be infection causing organ dysfunction?"; and **prioritizes** perfusion and oxygenation. **Generating solutions** and **taking action** mean escalating at once, through the rapid response team or the most responsible provider as hospital policy directs, using SBAR (see Chapter 6). They also mean preparing for cultures, lactate and IV access, and giving antimicrobials and fluids as soon as they are ordered or allowed by a medical directive. The nurse **evaluates** by reassessing vital signs, mental status, skin perfusion and urine output often. The nurse also listens for crackles and watches for rising work of breathing or falling oxygen saturation, which can mean fluid overload.

Documenting exact times matters: when sepsis was first suspected, when the provider was called, and when cultures, lactate, antimicrobials and fluids were given. Many hospitals audit these times. If the patient does not improve, or the response team's plan is

not working, the nurse escalates again. Early talk about goals of care, which the guideline suggests within 72 hours (conditional; Prescott et al., 2026), helps patients and families make informed choices (see Chapter 10).

Life After Sepsis

Surviving sepsis is often the start of a long recovery. About half of survivors recover fully or nearly fully. About one in six have severe, lasting physical or cognitive impairment, and about one in three die within the following year (Prescott & Angus, 2018). New problems are common: weakness and new limits in daily activities, memory and thinking problems, anxiety, depression and post-traumatic stress symptoms. About 40% of survivors are readmitted within 90 days, most often for another infection, heart failure or kidney problems (Prescott & Angus, 2018). Researchers use the term **post-sepsis syndrome** for this emerging pattern of lasting physical, cognitive and psychological effects, with a higher risk of death and poorer quality of life (Mostel et al., 2019).

Before discharge, the nurse:

- screens for new limits in mobility, swallowing, thinking and mood, and asks for referrals to physiotherapy, occupational therapy or speech-language pathology;
- supports medication reconciliation, so that hospital-only drugs stop and long-term drugs restart at the right doses;
- teaches the patient and family the signs of a new infection and when to seek care;
- explains in plain words what happened in hospital, and names sepsis on the discharge teaching, so the patient can tell future providers;
- arranges follow-up, with mental health and peer support where available.

The guideline also suggests offering follow-up services after critical illness, physical rehabilitation after discharge for survivors who needed prolonged mechanical ventilation, and services that support mental health after discharge (conditional, low certainty; Prescott et al., 2026).

Table 4.4 Sepsis: cues to recognize and first-hour nursing actions (Singer et al., 2016; Rumbus et al., 2017; Prescott et al., 2026)

What the nurse sees	Why it matters	Nursing action
Rising respiratory rate (22 breaths per minute or more)	A qSOFA item; may reflect acidosis, lung injury or poor perfusion; easy to miss	Count for a full minute; check oxygen saturation; screen for sepsis; escalate
New confusion, drowsiness or agitation	The brain is underperfused; in older adults this may be the only sign	Compare with baseline and family report; screen for sepsis and delirium; escalate
Heart rate rising above the patient's baseline	Compensation for low blood volume or vasodilation	Trend vital signs; look for other cues; escalate if sepsis is possible
Low or falling blood pressure; MAP under 65 mm Hg	Organs are not perfused; may signal septic shock	Escalate immediately; prepare IV access and fluids as ordered
Fever or a low temperature	Both occur in sepsis; a low temperature carries a worse outlook	Measure core temperature where possible; look for a source of infection
Cool skin, slow capillary refill, mottling at the knees	Blood is diverted from the skin; mottling is hard to see on darker skin	Time capillary refill; compare limb and trunk temperature; reassess after fluids
Low or falling urine output	The kidneys are underperfused	Measure output hourly as ordered; check for retention; report
Lactate above 2 mmol/L	Marks severity and risk of death; repeat values guide care	Draw as ordered; report at once; arrange repeat measurement
Suspected infection with any of the above	Antimicrobials and cultures are time-critical	Collect blood cultures without delay; give the first antimicrobial dose on time
Crackles, rising work of breathing or falling oxygen saturation after fluids	Possible fluid overload or lung injury	Stop and reassess; raise the head of the bed; escalate before giving more fluid

SCOPE IN PRACTICE

Sepsis Screening, Blood Cultures and Escalation

Every nurse, RN or practical nurse, screens for sepsis, acts at once on concerning cues and escalates. Hospital policy sets how the rapid response team is called, but no classification of the patient changes the duty to escalate.

Collecting blood cultures, drawing a lactate or starting IV fluids and antimicrobials depends on the three parts of CNO's Scope of Practice standard (see Chapter 1, section 1.3):

- **Authority:** the nurse needs an order or a medical directive. In an Ontario public hospital, nurses do not initiate controlled acts on their own authority, so sepsis protocols often rely on medical directives, which name the nurses who may carry them out.
- **Competence:** the nurse must have the knowledge, skill and judgment for the procedure, such as aseptic venipuncture and culture technique, and for the patient's condition.
- **Context:** employer policy decides who collects cultures; in some hospitals laboratory staff do so, and a directive may name RNs only. Rules also differ by province or territory.

When an RPN suspects sepsis, the patient's needs have changed. The RPN escalates at once and consults the RN, who assesses the patient. The RPN keeps contributing care within their own scope.

GOING DEEPER

Inside Sepsis: Dysregulated Response, Lactate and SOFA

Required for RN students; optional for PN students.

In sepsis, the host's response becomes the problem. Sensing microbial products and damaged cells, immune and endothelial cells release inflammatory and anti-inflammatory messengers at once. These messengers alter cardiovascular, nervous, hormonal, metabolic and clotting pathways. Organs can fail even though relatively few of their cells die (Singer et al., 2016).

The endothelium, the inner lining of blood vessels, is central. Activated endothelial cells become sticky and clot-promoting. The glycocalyx, the protective sugar-rich layer on the vessel wall, is shed, and the gaps between cells widen. Fluid and protein leak into the tissues (capillary leak), causing edema that raises tissue pressure and worsens perfusion. Small clots and stiffer red cells obstruct capillaries. Blood flow in the microcirculation can stay poor even after blood pressure is restored, so a normal MAP does not prove that organs are perfused (Joffre et al., 2020).

Lactate is often explained as a product of oxygen-starved cells, and tissue hypoxia does contribute. Much of the rise in sepsis, however, likely comes from stress hormones: epinephrine stimulates faster glycolysis even when oxygen is available. Whatever the cause, a high or rising lactate signals more severe illness and a higher risk of death (Garcia-Alvarez et al., 2014). Lactate is not a direct measure of perfusion and is read in clinical context (Evans et al., 2021).

The SOFA score grades six organ systems: respiratory (ratio of arterial oxygen to inspired oxygen), coagulation (platelets), liver (bilirubin), cardiovascular (MAP and vasopressor need), central nervous system (Glasgow Coma Scale) and renal (creatinine and urine output). Sepsis-3 defines organ dysfunction as an acute rise of 2 or more points, assuming a baseline of zero unless the patient had organ dysfunction before (Singer et al., 2016).

LIFESPAN CONSIDERATIONS

Sepsis in Older Adults

Older adults have the highest death rates involving sepsis in Canada (Navaneelan et al., 2016), and their sepsis is easy to miss. In a hospital study of patients with bloodstream infections, unusual (atypical) symptoms were reported in about 36% of patients younger than 65, 54% of those aged 65 to 84 and 64% of those 85 and older. Reduced consciousness, falls and vague complaints became more common with age. A general decline in health predicted early organ failure (Wester et al., 2013).

The nurse looks for:

- new or worse confusion, which may be the first sign (see delirium in Chapter 8);
- a fall, new incontinence or a sudden loss of mobility;
- a fever that is mild or absent, or a low temperature;
- a respiratory rate or heart rate above the person's usual values.

Knowing the person's baseline is essential, so the nurse asks family and caregivers what is new. Urinary and respiratory infections are the most common sources in this group (Wester et al., 2013).

PRACTICE STORY

"She Said He Wasn't Himself"

Names and details are fictional; this is a composite story.

Nurse: Daniel Okafor, RN. Years in practice: 9. Setting: surgical unit, community hospital, Ontario.

It was just after 1500 on a busy day shift when Mei-Lin, an RPN I've worked beside for years, stopped me in the hallway. Her patient, Mr. Lalonde, was 74 and on day 3 after a bowel resection. "He wasn't himself at lunch," she said. "He called me by his daughter's name. His respiratory rate is 24, and he's only had 80 mL of urine since 1100." She had already rechecked his vital signs and wanted me to see him.

Mr. Lalonde was restless and picking at his blanket. His temperature was 38.3 °C, heart rate 116, blood pressure 98/56 mm Hg and oxygen saturation 92% on room air. His knees and feet were cool, and his capillary refill was about 4 seconds. His abdomen was more tender than at morning rounds. Our sepsis screen was positive.

I called the rapid response team and gave an SBAR report, saying clearly that I was concerned about sepsis with a possible abdominal source. While we waited, Mei-Lin started oxygen per protocol and stayed with him, reassuring him and his wife. I placed a second IV and collected blood cultures and a lactate under our sepsis medical directive.

The team arrived within minutes. The lactate came back at 3.6 mmol/L. The surgical resident ordered a crystalloid bolus and a broad-spectrum antibiotic, and the first dose was running 40 minutes after Mei-Lin first raised her concern. We planned to remeasure his lactate and recorded his urine output hourly. An imaging scan that evening found a leak at the bowel join, and he went back to the operating room.

Mr. Lalonde recovered and went home two weeks later. Before discharge, his wife told me she had also noticed he "wasn't himself" that morning. I added a line to my practice: ask the family what they've noticed.

Reflect: How did Mei-Lin's decision to act on subtle changes, and to consult the RN, fit her role and scope? What could the team do to make it easier for families to raise concerns early?

Chapter 4 Summary

Introduction

- In a 2024 Canadian survey, 8.1% of adult inpatients in participating acute care hospitals had at least one health care-associated infection on the survey day.

4.1 Inflammation and Healing

- Acute inflammation has a vascular phase (vessels widen and leak, causing redness, heat and swelling) and a cellular phase (neutrophils, then macrophages, clear microbes and debris).
- Local signs are redness, heat, swelling, pain and loss of function; on darker skin, the nurse looks for colour change and relies on warmth, swelling, tightness and pain. Systemic signs include fever, a raised white cell count and malaise.
- Wounds heal through hemostasis, inflammation, proliferation and maturation; a healing ridge along an incision is normal by days 5 to 9.
- Wounds heal by primary, secondary or tertiary intention; diabetes, poor nutrition, smoking, older age and medications such as corticosteroids delay healing.

4.2 Infection: Recognition and Diagnostics

- Infection spreads through a chain of six links; nurses break the chain with hand hygiene, PPE, cleaning, device care and support for the host's defences.
- Invasive devices, surgery, immunosuppression and older age raise the risk of infection in hospital; older adults may show confusion or decline rather than fever.
- Antipyretics can hide fever, and the absence of fever does not rule out infection.
- Two sets of blood cultures from separate sites are collected before antimicrobials when this does not delay treatment; catheter urine comes from the sampling port, never the bag; wound swabs use the Levine technique.

- The white cell count and differential, CRP and procalcitonin support clinical judgment but do not replace it; lactate is discussed with sepsis.

4.3 Infection Prevention and Control on the Unit

- Routine practices apply to every patient: risk assessment, hand hygiene, PPE, control of the environment and administrative controls.
- Before each interaction, a point-of-care risk assessment guides the choice of PPE, placement and precautions.
- Hand hygiene follows the four moments; alcohol-based hand rub is preferred unless hands are visibly soiled or after care of a patient with C. difficile, when soap and water at a staff sink is preferred.
- Contact, droplet, droplet and contact, and airborne precautions start on suspicion of infection; airborne precautions need a negative pressure room and a fit-tested N95 respirator.
- PPE removal follows a set sequence with hand hygiene, because removal is the highest-risk moment.
- Nurses recognize clusters, report to the IPAC team, and follow outbreak measures; Ontario law requires designated diseases and hospital outbreaks to be reported to public health.

4.4 Antibiotic-Resistant Organisms and C. difficile

- AROs, including MRSA, VRE and carbapenemase-producing organisms, spread mainly by contact; colonized patients can spread them without symptoms.
- CNISP data for 2020 to 2024 show stable MRSA bloodstream infection and C. difficile infection rates, and significant rises in VRE bloodstream infections and CPE infections.
- Admission screening for AROs targets risk factors and follows each hospital's IPAC policy.
- C. difficile spores survive on surfaces and resist many chemicals; soap and water are preferred over alcohol-based hand rub because they physically remove spores, so the nurse washes at a staff sink.
- C. difficile care includes Contact Precautions from the first diarrhea, dedicated equipment, sporicidal cleaning, testing of unformed stool only, fluid balance and perineal skin care.

4.5 Antimicrobial Stewardship and the Nurse

- Stewardship means using antimicrobials only when needed, at the right drug, dose, route and duration, to limit resistance, C. difficile and adverse effects.
- Nurses support stewardship by collecting cultures before the first dose without delaying it, giving first doses on time and monitoring response and adverse effects.
- Nurses prompt reviews of IV-to-oral switches, culture results and stop dates.
- Most penicillin allergy labels are not true allergies; the nurse takes a detailed history, and prescribers or allergists make delabelling decisions.
- Patients learn to take antibiotics as directed, never share or save them, and report rash or diarrhea.

4.6 Sepsis

- Sepsis-3 defines sepsis as infection with organ dysfunction (a SOFA rise of 2 or more points); septic shock adds vasopressor need and a lactate above 2 mmol/L despite fluids.
- Early cues include a rising respiratory rate, new confusion, low blood pressure, fever or low temperature, poor perfusion, low urine output and a high lactate; mottling is harder to see on darker skin.
- qSOFA is not recommended as a single screening tool; the 2026 guideline recommends NEWS, NEWS2, MEWS or SIRS instead, and hospitals use a range of screening tools.
- The 2026 Surviving Sepsis Campaign guideline recommends blood cultures before antimicrobials when this causes no delay and antimicrobials immediately (ideally within 1 hour) for probable sepsis or shock; it suggests lactate measurement and at least 30 mL/kg of crystalloid within 3 hours for hypoperfusion.
- Every nurse escalates suspected sepsis at once; the RPN consults the RN.

- Many survivors have lasting physical, cognitive and mental health effects and need follow-up.

Key Terms (46)

acute inflammation: A short-lived inflammatory response, dominated by neutrophils, that removes the cause of injury and then resolves.

additional precautions: Infection control measures used on top of routine practices for certain organisms or clinical presentations; contact, droplet and airborne precautions.

airborne infection isolation room (AIIR): A single room designed and ventilated (negative pressure) to keep airborne organisms from spreading beyond it.

airborne precautions: Precautions for organisms carried on small particles that stay suspended in the air; they require a negative pressure room with the door closed and a fit-tested N95 respirator.

allergy (drug): an immune reaction to a drug, such as hives, swelling, wheezing or a severe skin reaction.

antibiotic-resistant organism (ARO): a microorganism that has changed so that one or more antibiotics that once treated it no longer work well against it.

antimicrobial stewardship: coordinated actions to use antimicrobials only when needed, with the right drug, dose, route and duration, to improve outcomes and limit harm and resistance.

C-reactive protein (CRP): An acute-phase protein whose blood level rises with inflammation of any cause; it is not specific to infection.

Canadian Nosocomial Infection Surveillance Program (CNISP): the Public Health Agency of Canada's surveillance program, with sentinel hospitals, for healthcare-associated infections and antimicrobial resistance.

carbapenemase-producing organism (CPO): a bacterium that makes enzymes that break down carbapenem antibiotics, leaving few effective drugs; carbapenemase-producing Enterobacterales (CPE) are the main group.

chain of infection: A model of the six links needed for infection to spread (agent, reservoir, portal of exit, mode of transmission, portal of entry, susceptible host); breaking any link stops transmission.

chronic inflammation: Inflammation that persists because the cause is not removed or the response fails to switch off, with ongoing tissue damage and scarring.

Clostridioides difficile: a spore-forming, toxin-producing anaerobic bacterium that causes diarrhea and colitis, most often after antibiotic use.

colonization: The presence of an organism on or in the body without signs of illness; a colonized person can still spread the organism.

contact precautions: Precautions for organisms spread by direct or indirect contact; they include a gown, gloves, dedicated equipment and, usually, a single room.

cytokines: Small proteins released by immune cells that carry signals between cells and promote or damp down inflammation.

diseases of public health significance: Infections that Ontario law says must be reported to the area's medical officer of health.

droplet precautions: Precautions for organisms spread by large respiratory droplets over a short distance; they include a mask and eye protection within 2 metres and a single room or spatial separation.

exudate: Fluid, proteins and cells that leave blood vessels and collect in inflamed tissue.

fever: A rise in body temperature that occurs as part of the inflammatory response; the threshold for action is set by policy, and older adults may have lower readings.

hand hygiene: Removing or killing microorganisms on the hands with alcohol-based hand rub or soap and running water.

healing by primary intention: Healing of a wound whose edges are brought together with sutures, staples or tape, without the need for granulation tissue.

healing by secondary intention: Healing of an open wound that fills with granulation tissue from the base up.

healing by tertiary intention: Healing of a wound that is left open for several days and then closed (delayed primary closure), often used for contaminated wounds.

healing ridge: A firm area of new collagen under a healing incision that is a normal sign of the proliferation phase.

health care-associated infection (HAI): An infection a person acquires while receiving health care.

infection: Entry of microorganisms into body tissues, where they multiply.

inflammation: The body's protective response to tissue injury or infection, which brings fluid, proteins and white cells to the area, removes the cause and prepares for repair.

intolerance (drug): an expected, non-immune side effect of a drug, such as nausea, diarrhea or headache.

lactate: a product of glucose metabolism; a level above 2 mmol/L in sepsis marks greater severity and risk of death.

methicillin-resistant Staphylococcus aureus (MRSA): a strain of S. aureus that resists methicillin and related antibiotics; spread mainly by contact.

mottling: patchy, lace-like skin discolouration, usually starting at the knees, that signals poor skin perfusion; harder to see on darker skin.

N95 respirator: A close-fitting respirator that filters 95% of particles about 1 micron in size; it must be fit-tested and seal-checked.

outbreak: A rise in cases of an infection above what is expected in a particular place and time, defined for each infection.

personal protective equipment (PPE): Clothing and equipment, such as gloves, gowns, masks, respirators and eye protection, that form a barrier between the provider and infectious material.

point-of-care risk assessment (PCRA): A check made before every patient interaction of the task, the patient and the environment to judge the risk of transmission and choose the right precautions.

post-sepsis syndrome: lasting physical, cognitive and psychological problems after surviving sepsis.

procalcitonin: A blood marker used with clinical assessment when the likelihood of bacterial infection is uncertain and to help decide when antibiotics can be stopped.

quick SOFA (qSOFA): a three-item bedside score (respiratory rate 22 or more, altered mentation, systolic blood pressure 100 mm Hg or less); not recommended as a single screening tool.

routine practices: The infection prevention and control practices used with every patient during all care: risk assessment, hand hygiene, PPE, control of the environment and administrative controls.

sepsis: Organ dysfunction that threatens life, caused by the body's dysregulated response to an infection.

septic shock: a subset of sepsis with severe circulatory, cellular and metabolic changes; clinically, a vasopressor is needed to keep MAP at 65 mm Hg or higher and lactate is above 2 mmol/L despite adequate fluids.

Sequential Organ Failure Assessment (SOFA) score: a score that grades dysfunction in six organ systems; a rise of 2 or more points with infection defines sepsis.

spore: a dormant, hardy form of a bacterium that survives for months on surfaces and resists many disinfectants; hand washing with soap and water is preferred because it physically removes spores.

systemic inflammatory response syndrome (SIRS): a set of criteria (temperature, heart rate, respiratory rate, white cell count) once used to define sepsis; no longer part of the definition.

vancomycin-resistant enterococci (VRE): bowel bacteria (enterococci) that no longer respond to vancomycin.

Licensure Review & Clinical Judgment Questions (30)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mr. Gérard Fournier (Questions 1–4): Mr. Gérard Fournier, 76, has been on a medical unit in an Ontario hospital for 5 days, receiving IV antibiotics for pneumonia. He shares a four-bed room and bathroom. Since last evening he has had five loose, watery stools; this morning his stool test is positive for C. difficile. An RPN is caring for him.

1. [CORE] Which action should the RPN take first?

a. Ask Mr. Fournier to use the shared bathroom after his roommates

b. Wait for a second positive stool test before starting additional precautions or moving him to another room

c. Place Mr. Fournier on contact precautions and arrange a single room with its own toilet

d. Place a droplet precautions sign on the room door

Answer: c — C. difficile spreads by contact with stool, spores and contaminated surfaces. Contact precautions start at the onset of diarrhea, ideally in a single room with its own toilet (sections 4.3 and 4.4). Option a is wrong because a shared bathroom spreads spores whatever the order of use. Option b is wrong because precautions start on symptoms, not after repeat testing. Option d is wrong because C. difficile is not spread by droplets.

2. [CORE] After perineal care, the RPN removes the gown and gloves. Which hand hygiene action is best?

a. Wash hands with soap and water at a dedicated staff sink

b. Use alcohol-based hand rub, which removes spores better than soap and water

c. Wash hands at the sink in Mr. Fournier's bathroom

d. Skip hand hygiene, because gloves were worn throughout care

Answer: a — Soap and running water removes C. difficile spores better than alcohol-based hand rub, so handwashing at a dedicated staff sink is preferred (section 4.3). Option b reverses this; hand rub is used only when a staff sink is not immediately available. Option c is wrong because hand hygiene is never done at a patient's sink. Option d is wrong because gloves do not replace hand hygiene; hands can be contaminated during glove removal.

3. [CORE] Which equipment and environmental actions are appropriate for Mr. Fournier? Select all that apply.

a. Keep a dedicated stethoscope and blood pressure cuff in his room

b. Use a dedicated commode if a private bathroom is not available

c. Clean the shared glucometer with an alcohol wipe, as for other patients

d. Disinfect any shared item leaving the room with a product approved for C. difficile

e. Move the unit's vital signs machine between rooms and clean it at shift end

f. Confirm his room and bathroom are cleaned twice daily with a sporicidal agent

Answer: a, b, d, f — C. difficile care calls for dedicated equipment, a dedicated commode when there is no private bathroom, disinfection of shared items before they leave the room, and twice-daily sporicidal cleaning (section 4.3). Option c is wrong because alcohol does not reliably kill spores. Option e is wrong because equipment is cleaned between patients, not at the end of the shift.

4. [CORE] Mr. Fournier's daughter visits daily and helps him wash. Which instruction should the RPN give her?

a. "You can use his bathroom, because family members are not at risk."

b. "Visitors do not need any precautions, because gowns and gloves are required only for the health care workers who look after him."

c. "Please wear an N95 respirator whenever you are in his room."

d. "Please wash your hands with soap and water when you leave, and wear a gown and gloves when you help him wash."

Answer: d — Visitors who provide care follow the same precautions as staff: here, hand hygiene plus a gown and gloves (section 4.3). Option a is wrong because visitors should not use the patient's bathroom. Option b is wrong because visitors who help with care can carry spores. Option c is wrong because C. difficile is not airborne.

5. [CORE] A 58-year-old patient is admitted with cellulitis of the right lower leg. Which findings are systemic signs of infection? Select all that apply.

a. Temperature 38.6 °C
b. Warmth over the right shin compared with the left
c. White blood cell count 14.2 × 10^9/L
d. Swelling of the right calf
e. Fatigue and loss of appetite
f. Pain in the right leg when walking

Answer: a, c, e — Fever, a raised white cell count and malaise reflect a whole-body response (section 4.1). Options b, d and f are local signs: warmth, swelling, and pain with loss of function at the site.

6. [CORE] A nurse removes an indwelling urinary catheter that is no longer needed. Which link in the chain of infection does this action break?

a. Reservoir
b. Portal of exit
c. Mode of transmission
d. Portal of entry

Answer: d — An indwelling catheter gives organisms a direct route into the bladder, so removing it closes a portal of entry (section 4.2). Option a is wrong because the reservoir is where the organism lives and multiplies. Option b is wrong because the portal of exit is how organisms leave a reservoir. Option c is wrong because mode of transmission is how organisms travel, which hand hygiene and PPE interrupt.

7. [CORE] A surgical patient has a new temperature of 38.7 °C and chills. The prescriber orders two sets of blood cultures and an IV antibiotic now. Which action is correct?

a. Give the antibiotic first and collect the blood cultures with the next morning's blood work
b. Collect two sets of blood cultures from separate sites, then give the antibiotic without delay
c. Draw both sets from one site at the same time to reduce the number of skin punctures
d. Collect one set now and the second set after the antibiotic infusion is complete

Answer: b — Two sets from separate sites, collected before the first dose when this does not delay treatment, best identify the organism and separate contamination from true infection (section 4.2). Option a is wrong because antibiotics given first can stop bacteria growing in the culture. Option c is wrong because two sites are needed to recognize skin contamination. Option d is wrong because a set drawn after the antibiotic has a lower yield.

8. [CORE] A 44-year-old patient is admitted with a 6-week cough, night sweats and a chest X-ray suggesting pulmonary tuberculosis. Which precautions should the nurse implement?

a. Droplet precautions in a shared room, with the curtain drawn and a surgical mask for anyone within 2 metres
b. Contact precautions with a gown and gloves for all care
c. Airborne precautions in a negative pressure room, door closed, with fit-tested N95 respirators
d. Routine practices, with a surgical mask worn by staff within 2 metres of the patient

Answer: c — Pulmonary tuberculosis spreads on small particles that stay suspended in the air, so airborne precautions start on suspicion: a negative pressure room with the door closed and a fit-tested, seal-checked N95 respirator (section 4.3). Option a is wrong because droplet precautions and a shared room do not stop airborne spread. Option b is wrong because tuberculosis is not mainly spread by contact. Option d is wrong because a surgical mask does not protect the wearer from airborne particles.

9. [CORE] A nurse is about to empty a full urinary drainage bag for a patient with no known infection and expects urine may splash. Based on a point-of-care risk assessment, which PPE should the nurse wear?

a. Gloves, a gown, and a mask with eye protection
b. An N95 respirator and gloves
c. No PPE, because the patient has no known infection
d. Gloves only, because routine practices apply only to blood

Answer: a — The point-of-care risk assessment asks whether hands, clothing or mucous membranes may be exposed to body fluids; an expected splash calls for gloves, a gown and facial protection (section 4.3). Option b is wrong because this task produces no airborne particles and an N95 gives no eye protection. Option c is wrong because routine practices apply to every patient. Option d is wrong because routine practices cover all body fluids, not only blood.

Case: Mrs. Rose Bérubé (Questions 10–15): Mrs. Rose Bérubé, 84, was admitted to a medical unit yesterday with dysuria, frequency and dehydration after a fall at home. Her weight is 52 kg. A urine culture is pending; an oral antibiotic was ordered late last evening, and the first dose is due at 0900. At 0800 today her daughter says, "Mom isn't making sense this morning." Assessment: temperature 35.9 °C, heart rate 114, respiratory rate 26, blood pressure 92/54 mm Hg (MAP 67 mm Hg; yesterday 132/76), oxygen saturation 93% on room air. She is oriented to person only (yesterday fully oriented). Her skin is cool, with capillary refill of about 4 seconds. Urine output is 60 mL over the past 4 hours. Laboratory results: white blood cells 16.4 × 10^9/L, creatinine 172 µmol/L (yesterday 94 µmol/L), lactate 3.8 mmol/L.

10. [CORE] The nurse reviews Mrs. Bérubé's findings. Which findings need immediate follow-up? Select all that apply.

a. Temperature 35.9 °C
b. Respiratory rate 26 breaths per minute
c. Oriented to person only
d. Urine output 60 mL over 4 hours
e. Dysuria and frequency on admission
f. Lactate 3.8 mmol/L

Answer: a, b, c, d, f — A low temperature (a), fast breathing (b), new confusion (c), low urine output (d) and a lactate above 2 mmol/L (f) are new changes suggesting organ dysfunction and possible sepsis (section 4.6, Table 4.4). Dysuria and frequency (e) explain the likely source but are not a new change this morning.

11. [CORE] The nurse analyzes the cues. Which explanation best fits Mrs. Bérubé's current findings?

a. A new stroke causing confusion and low blood pressure
b. Dehydration alone, which will correct with oral fluids
c. An expected side effect of her oral antibiotic
d. Sepsis, with organ dysfunction from a urinary source

Answer: d — A urinary infection plus new confusion, fast breathing, low blood pressure, rising creatinine, low urine output and a high lactate points to sepsis with organ dysfunction (section 4.6). Dehydration (b) may add to her low blood pressure but does not explain the low temperature, high white cell count and lactate, and oral fluids would not be enough. A stroke (a) does not explain the infection cues. Her antibiotic (c) has not yet been given.

12. [CORE] Which concern should the nurse treat as the highest priority?

a. Risk of another fall because of her confusion
b. Risk of skin breakdown from reduced mobility
c. Poor tissue perfusion from possible septic shock
d. Knowledge gap about her urinary tract infection

Answer: c — Low blood pressure, cool skin, slow capillary refill, low urine output and a high lactate show poor organ perfusion, a life-threatening problem that comes first (section 4.6). Falls (a) and skin breakdown (b) are real risks but come after perfusion. Teaching (d) waits until she is stable.

13. [CORE] The nurse calls the rapid response team. Which orders should the nurse expect for Mrs. Bérubé in the first hour? Select all that apply.

a. Blood cultures collected before the first antimicrobial dose, if this causes no delay
b. A broad-spectrum intravenous antimicrobial given as soon as possible
c. A crystalloid fluid bolus with frequent reassessment
d. Holding all antimicrobials until the urine culture result is known
e. A repeat lactate measurement
f. Acetaminophen and a recheck of vital signs in 4 hours

Answer: a, b, c, e — The guideline supports blood cultures before antimicrobials when this causes no delay (a), antimicrobials immediately, ideally within 1 hour, for probable sepsis (b), crystalloid for hypoperfusion with frequent reassessment (c) and repeat lactate (e) (section 4.6). Waiting for the urine culture (d) would delay treatment by a day or more. A 4-hour recheck (f) ignores the urgency, and her temperature is low.

14. [CORE] Blood cultures have been collected, and the pharmacy has sent the first dose of the prescribed intravenous antimicrobial. A second set of blood cultures has also been ordered, but the laboratory says it cannot come for 60 minutes. What should the nurse do?

a. Give the antimicrobial now and report the delay in the second set
b. Hold the antimicrobial until the second set of cultures has been collected
c. Change the antimicrobial to the oral route so it can be given sooner
d. Give half the dose now and the rest after the second set is collected

Answer: a — Collecting cultures must not delay the first dose in probable sepsis (section 4.6). One set is already collected, so the nurse gives the dose now and reports the delay (a). Holding the dose (b) loses an hour in an emergency. Changing the route (c) is a prescriber's decision. Splitting the dose (d) is not ordered and would underdose her.

15. [CORE] Three hours later, Mrs. Bérubé has received about 1,500 mL of crystalloid and her antimicrobial. Which findings show that her condition is improving? Select all that apply.

a. New crackles at both lung bases
b. MAP 72 mm Hg
c. Repeat lactate 2.1 mmol/L
d. Oxygen saturation 89% on 2 L/min oxygen
e. Urine output 30 mL in the past hour
f. Oriented to person and place

Answer: b, c, e, f — A higher MAP (b), a falling lactate (c), better urine output (e) and clearer thinking (f) show improved perfusion (section 4.6). New crackles (a) and low oxygen saturation on oxygen (d) suggest fluid overload or lung injury and need escalation before more fluid (Table 4.4).

16. [CORE] A patient with MRSA colonization is on Contact Precautions. Which action by the nurse is correct?

a. Wearing a gown and gloves only when touching the patient's wound
b. Removing precautions once the patient has no signs of infection
c. Wearing an N95 respirator for all care in the room
d. Using a dedicated stethoscope and blood pressure cuff in the room

Answer: d — Dedicated equipment stops MRSA travelling to others on shared items (d) (sections 4.3 and 4.4). Under Contact Precautions, gown and gloves are worn for contact with the patient and environment, not only the wound (a). A colonized patient can spread MRSA without symptoms (b). MRSA spreads by contact, so an N95 respirator is not routinely needed (c) (section 4.3).

17. [CORE] After caring for a patient with C. difficile infection, the nurse removes gloves and gown. What should the nurse do next?

a. Use alcohol-based hand rub, then leave the room
b. Wash hands with soap and water at the patient's sink
c. Wash hands with soap and water at a staff sink
d. Put on new gloves instead of performing hand hygiene

Answer: c — Soap and running water remove spores mechanically, so the nurse washes at a staff sink (c) (section 4.4). Hand rub (a) is used only when no staff sink is close by, followed by washing soon after. The patient's sink (b) can re-contaminate the hands. Gloves (d) never replace hand hygiene.

18. [CORE] A patient receiving antibiotics has had two loose, watery stools that take the shape of the container since breakfast. The patient takes no laxatives. What should the nurse do first?

a. Start Contact Precautions and send a stool specimen
b. Wait for a third stool before taking any action
c. Send a formed stool specimen later to confirm the result
d. Give an antidiarrheal drug from the patient's home supply

Answer: a — Contact Precautions start at the first unexplained diarrhea, without waiting for more stools or results, and an unformed stool is sent promptly (a) (section 4.4). Waiting (b) lets spores spread. Formed stool is not tested (c). Giving an unordered drug (d) is unsafe; the diarrhea is reported to the prescriber.

19. [CORE] A patient with a carbapenemase-producing Enterobacterales (CPE) infection is admitted. Which measures should the nurse expect? Select all that apply.

a. A single room with a dedicated toilet or commode
b. Sharing the commode with the patient in the next bed once it is wiped
c. Contact Precautions for care
d. Dedicated patient care equipment
e. Routine walks in the unit hallway to promote mobility
f. Asking whether the patient has received health care outside Canada

Answer: a, c, d, f — CPE needs a single room with its own toilet or commode (a), Contact Precautions (c) and dedicated equipment (d) (section 4.4). Care outside Canada is a screening risk factor (f). Sharing a commode (b) spreads bowel organisms. Under Contact Precautions, time outside the room is limited, so mobility is planned with the IPAC team rather than through routine hallway walks (e).

20. [CORE] A patient on day 4 of intravenous antibiotics for pneumonia has been afebrile for 48 hours, is eating meals and has a white cell count returning to normal. Which action by the nurse best supports antimicrobial stewardship?

a. Continue the IV antibiotic because the course was ordered for 7 days
b. Change the IV antibiotic to an oral form at the next dose
c. Ask the prescriber or pharmacist whether an IV-to-oral switch is appropriate
d. Hold the antibiotic because the infection has resolved

Answer: c — The patient meets common IV-to-oral criteria, so the nurse prompts a review (c) (section 4.5). Continuing without question (a) misses a chance to reduce catheter complications. Changing the route (b) or holding the drug (d) without an order is outside the nurse's authority.

21. [CORE] On admission, a patient says, "I'm allergic to penicillin. It upset my stomach when I was a teenager." What should the nurse do?

a. Document the reaction and its timing in detail and share it with the prescriber
b. Remove the penicillin allergy from the record, since nausea is not an allergy
c. Record the allergy as "penicillin: anaphylaxis" to be safe
d. Tell the patient that all penicillin allergies go away after 10 years

Answer: a — The nurse records exactly what happened and when, and shares it so the prescriber or pharmacist can assess the label (a) (section 4.5). Stomach upset sounds like an intolerance, but the nurse does not remove a label alone (b); delabelling is done by a prescriber or allergist under policy. Recording a reaction that did not happen (c) is inaccurate and leads to unneeded alternative antibiotics. Statement (d) promises something the nurse cannot know.

22. [CORE] A patient with suspected pneumonia has a new order for blood cultures and an IV antibiotic. Which order of actions is best?

a. Give the antibiotic, then collect cultures at the next routine laboratory round
b. Collect blood cultures promptly, then give the antibiotic without delay
c. Wait for the chest X-ray result before collecting cultures or giving the antibiotic
d. Collect cultures, then give the antibiotic when the culture result returns

Answer: b — Cultures collected before the first dose give the best chance of identifying the organism, and the dose follows without delay (b) (sections 4.5 and 4.6). Giving the antibiotic first and waiting hours for cultures (a) can sterilize the specimen. Waiting for imaging (c) or culture results (d) delays treatment.

23. [CORE] An 88-year-old resident admitted from long-term care has a temperature of 36.8 °C. The family says she has been more confused since yesterday and fell this morning. She has a urinary catheter. How should the nurse interpret these findings?

a. Infection is unlikely because she has no fever
b. The new confusion and fall may be early signs of infection or sepsis
c. Confusion is expected at her age and needs no action
d. The fall explains her confusion, so only a neurologic check is needed

Answer: b — In older adults, fever may be mild or absent, and new confusion, falls and functional decline may be the first signs of infection or sepsis; a urinary catheter adds risk (section 4.6, Lifespan Considerations box). A normal temperature does not rule out infection (a). New confusion is never simply age (c). A head injury must be considered (d), but the nurse also screens for sepsis.

24. [CORE] A nurse on a surgical unit is reviewing the hospital's sepsis screening tool. Which statement about the quick SOFA (qSOFA) score is accurate?

a. A qSOFA score of 0 or 1 rules out sepsis in a patient with a suspected infection
b. qSOFA is the screening tool that all Ontario hospitals are required to use
c. qSOFA cannot be scored until a serum lactate result is available from the laboratory
d. qSOFA is not recommended as a single screening tool because it misses many patients

Answer: d — qSOFA is specific but not sensitive, so the Surviving Sepsis Campaign advises against it as a single screening tool (d) (section 4.6). A low score does not rule out sepsis (a). Ontario hospitals use different tools (b). qSOFA uses no laboratory value (c).

25. [CORE] An RPN finds that a postoperative patient has a new respiratory rate of 28, a heart rate of 122 and new confusion. The RN is busy with another patient. What should the RPN do first?

a. Recheck the vital signs in 1 hour before telling anyone

b. Escalate at once to the RN and to the rapid response team per policy

c. Document the findings and report them at the end of the shift

d. Wait for the RN to finish with the other patient before taking any action

Answer: b — Every nurse who notices deterioration acts at once and escalates; the RPN consults the RN as the patient's needs change (b) (Scope in Practice box; Chapter 1, section 1.3). Waiting an hour (a), until shift end (c) or until the RN is free (d) delays care for possible sepsis.

26. [CORE] Which statement by a nurse about first-hour sepsis care is accurate?

a. "For probable sepsis, the antimicrobial should be given immediately, ideally within an hour."

b. "Fluids are given only after the blood culture results return."

c. "Lactate is drawn once at the end of resuscitation to confirm recovery."

d. "Vasopressors are started before any fluid in every patient with sepsis."

Answer: a — The guideline strongly recommends antimicrobials immediately, ideally within 1 hour, for probable or definite sepsis (a) (section 4.6). Fluids are not delayed for cultures (b). Lactate is measured early and repeated (c). Vasopressors usually follow an initial fluid bolus when hypotension persists (d).

27. [RN] A patient with pneumonia had a baseline SOFA score of 0. Today the platelet count has fallen and the creatinine has risen, raising the SOFA score to 3. How does the nurse interpret this under Sepsis-3?

a. The patient has SIRS but not sepsis

b. The patient meets the definition of septic shock

c. SOFA changes are not relevant until a lactate is available

d. The patient meets the definition of sepsis

Answer: d — Sepsis-3 defines sepsis as infection with an acute rise of 2 or more SOFA points (d) (Going Deeper box). SIRS (a) no longer defines sepsis. Septic shock (b) also requires vasopressor need and a lactate above 2 mmol/L despite fluids. The SOFA change stands without a lactate (c).

28. [RN] A patient's lactate is 4.1 mmol/L, although oxygen saturation is 97% and MAP is 70 mm Hg. A student asks how lactate can be high when oxygenation looks normal. Which explanation is best?

a. "The result must be a laboratory error, because lactate rises only with hypoxia."

b. "Stress hormones such as epinephrine can speed up glycolysis and raise lactate even when oxygen is available."

c. "Lactate rises only when the liver has failed completely and can no longer clear it from the blood."

d. "A high lactate is a direct and reliable measure of how much blood is reaching each of the organs."

Answer: b — Much of the lactate rise in sepsis likely comes from adrenergic stimulation of glycolysis, though hypoxia also contributes (b) (Going Deeper box). Lactate does not rise only with hypoxia (a) or complete liver failure (c). It marks severity, but it does not directly measure perfusion (d).

29. [RN] After 2 L of crystalloid, a patient in septic shock has new generalized edema, yet the blood pressure remains low. Which mechanism best explains these findings?

a. Injury to the endothelium and glycocalyx lets fluid leak from vessels into tissues

b. The kidneys are retaining sodium and water because the patient is now overhydrated

c. The crystalloid given was hypotonic, so most of it moved into the patient's cells

d. Edema shows that the circulating blood volume is now adequate

Answer: a — Endothelial activation and glycocalyx shedding let fluid and protein leak into tissues (capillary leak) while the circulation stays underfilled (a) (Going Deeper box). Sodium retention from overhydration (b) does not explain persistent low pressure. Crystalloids used in sepsis are isotonic (c). Edema does not mean the circulation is filled (d); the leaked fluid is outside the vessels.

30. [RN] Which patient meets the Sepsis-3 clinical criteria for septic shock?

a. Suspected infection, MAP 62 mm Hg before any fluid has been given, lactate 1.6 mmol/L

b. Pneumonia, MAP 70 mm Hg after fluids with no vasopressor needed, lactate 3.2 mmol/L

c. Urinary infection, norepinephrine needed to keep MAP at 65 mm Hg after adequate fluids, lactate 3.0 mmol/L

d. Cellulitis, temperature 39.2 °C, heart rate 124, respiratory rate 24, white cells 18 × 10^9/L

Answer: c — Septic shock requires a vasopressor to keep MAP at 65 mm Hg or higher and a lactate above 2 mmol/L despite adequate fluids (c) (section 4.6). Patient a has had no fluids and a normal lactate. Patient b needs no vasopressor. Patient d meets SIRS criteria, which no longer define sepsis.

References

Alberta Health Services. (n.d.). *Antimicrobial Stewardship Program (ASP)*. https://www.albertahealthservices.ca/info/Page9674.aspx

Alberta Precision Laboratories. (2024). *Laboratory bulletin: Blood culture ordering and best practice advisory*. https://www.albertahealthservices.ca/assets/wf/lab/if-lab-hp-bulletin-blood-culture-ordering-and-best-practice-advisory.pdf

Alberta Precision Laboratories. (n.d.). *Catheter collection for urine culture: Guidelines for physicians or other health care providers* (MI6173). https://www.albertahealthservices.ca/assets/wf/lab/if-lab-tc-cal-catheter-collection-mi6173.pdf

Atkinson, A., Poliquin, V., & Elwood, C. (2023). Penicillin allergy delabelling in pregnancy. *CMAJ*, *195*(12), E452–E453. https://doi.org/10.1503/cmaj.220973

BC Provincial Nursing Skin and Wound Committee. (2011). *Guideline: Assessment and treatment of surgical wounds healing by primary and secondary intention in adults & children*. https://www.clwk.ca/get-resource/surgical-wounds-incision-surgical-dehiscence-guideline

BC Provincial Nursing Skin and Wound Committee. (2015). *Procedure: Swab for culture & susceptibility (C & S) in suspected wound infection*. https://www.picnet.ca/wp-content/uploads/Procedure-Wound-Culture-and-Susceptibility-June-2015.pdf

Canadian Nosocomial Infection Surveillance Program. (2026). Healthcare-associated infections and antimicrobial resistance in Canadian acute care hospitals, 2020–2024. *Canada Communicable Disease Report*, *52*(5), 205–222. https://doi.org/10.14745/ccdr.v52i05a05

Canadian Nurses Association. (2024). *Twelve tests and treatments to question in nursing*. Choosing Wisely Canada. https://choosingwiselycanada.org/recommendation/nursing/

Canadian Nurses Association. (n.d.). *Antimicrobial resistance*. https://cna-aiic.ca/en/nursing/antimicrobial-resistance

Chen, L., Deng, H., Cui, H., Fang, J., Zuo, Z., Deng, J., Li, Y., Wang, X., & Zhao, L. (2018). Inflammatory responses and inflammation-associated diseases in organs. *Oncotarget, 9*(6), 7204–7218. https://doi.org/10.18632/oncotarget.23208

Dumas, G., Lavillegrand, J.-R., Joffre, J., Bigé, N., Bastos de-Moura, E., Baudel, J.-L., Chevret, S., Guidet, B., Maury, E., Amorim, F., & Ait-Oufella, H. (2019). Mottling score is a strong predictor of 14-day mortality in septic patients whatever vasopressor doses and other tissue perfusion parameters. *Critical Care*, *23*, Article 211. https://doi.org/10.1186/s13054-019-2496-4

Evans, L., Rhodes, A., Alhazzani, W., Antonelli, M., Coopersmith, C. M., French, C., Machado, F. R., Mcintyre, L., Ostermann, M., Prescott, H. C., Schorr, C., Simpson, S., Wiersinga, W. J., Alshamsi, F., Angus, D. C., Arabi, Y., Azevedo, L., Beale, R., Beilman, G., … Levy, M. (2021). Surviving Sepsis Campaign: International guidelines for management of sepsis and septic shock 2021. *Intensive Care Medicine*, *47*(11), 1181–1247. https://doi.org/10.1007/s00134-021-06506-y

Evans, S. S., Repasky, E. A., & Fisher, D. T. (2015). Fever and the thermal regulation of immunity: The immune system feels the heat. *Nature Reviews Immunology, 15*(6), 335–349. https://doi.org/10.1038/nri3843

Garcia-Alvarez, M., Marik, P., & Bellomo, R. (2014). Sepsis-associated hyperlactatemia. *Critical Care*, *18*(5), Article 503. https://doi.org/10.1186/s13054-014-0503-3

Guo, S., & DiPietro, L. A. (2010). Factors affecting wound healing. *Journal of Dental Research, 89*(3), 219–229. https://doi.org/10.1177/0022034509359125

Healthcare Excellence Canada. (n.d.). *Hospital harm: Sepsis*. https://www.healthcareexcellence.ca/en/resources/hospital-harm-is-everyones-concern/hospital-harm-improvement-resource/sepsis-introduction

High, K. P., Bradley, S. F., Gravenstein, S., Mehr, D. R., Quagliarello, V. J., Richards, C., & Yoshikawa, T. T. (2009). Clinical practice guideline for the evaluation of fever and infection in older adult residents of long-term care facilities: 2008 update by the Infectious Diseases Society of America. *Clinical Infectious Diseases, 48*(2), 149–171. https://doi.org/10.1086/595683

Joffre, J., Hellman, J., Ince, C., & Ait-Oufella, H. (2020). Endothelial responses in sepsis. *American Journal of Respiratory and Critical Care Medicine*, *202*(3), 361–370. https://doi.org/10.1164/rccm.201910-1911TR

Middlesex-London Health Unit. (2026). *Reporting diseases of public health significance*. https://www.healthunit.com/health-care-professionals/infectious-diseases-for-healthcare-providers/reporting-diseases-of-public-health-significance/

Mitchell, R., Lee, D., Bartoszko, J., Lybeck, C., Benoit, M.-È., Comeau, J., Ellison, J., Frenette, C., Happe, J., Haslam, N., Lee, B., Mertz, D., Smith, S. W., Thirion, D., Wong, A., Science, M., & Hota, S. (2025). Trends in healthcare-associated infections and antimicrobial-resistant organisms among adults in Canadian acute care hospitals: Findings from four point prevalence surveys, 2002 to 2024. *Infection Control & Hospital Epidemiology, 46*(10), 984–991. https://doi.org/10.1017/ice.2025.10259

Mostel, Z., Perl, A., Marck, M., Mehdi, S. F., Lowell, B., Bathija, S., Santosh, R., Pavlov, V. A., Chavan, S. S., & Roth, J. (2019). Post-sepsis syndrome – an evolving entity that afflicts survivors of sepsis. *Molecular Medicine*, *26*, Article 6. https://doi.org/10.1186/s10020-019-0132-z

Navaneelan, T., Alam, S., Peters, P. A., & Phillips, O. (2016). *Deaths involving sepsis in Canada* (Health at a Glance, Catalogue No. 82-624-X). Statistics Canada. https://www150.statcan.gc.ca/n1/pub/82-624-x/2016001/article/14308-eng.htm

O'Grady, N. P., Alexander, E., Alhazzani, W., Alshamsi, F., Cuellar-Rodriguez, J., Jefferson, B. K., Kalil, A. C., Pastores, S. M., Patel, R., van Duin, D., Weber, D. J., & Deresinski, S. (2023). Society of Critical Care Medicine and the Infectious Diseases Society of America guidelines for evaluating new fever in adult patients in the ICU. *Critical Care Medicine, 51*(11), 1570–1586. https://doi.org/10.1097/CCM.0000000000006022

Ontario Medical Association. (2025). *Pathways to appropriate penicillin allergy (de)labelling: Support tool for primary care physicians* (Version 2). https://www.oma.org/siteassets/oma/media/pagetree/pps/running/news/pathways-to-appropriate-penicillin-allergy-delabelling.pdf

Ontario Ministry of Health and Long-Term Care. (2011). *Your 4 moments for hand hygiene* [Just Clean Your Hands poster series]. Queen's Printer for Ontario. https://www.publichealthontario.ca/-/media/documents/4-moments-poster-series.pdf

Ontario Ministry of Health. (2024). *Respiratory infection outbreaks in institutions and public hospitals* (Infectious Diseases Protocol, Appendix 1: Case definitions and disease-specific information). https://www.ontario.ca/files/2024-11/moh-ophs-respiratory-infection-outbreaks-en-2024-11-01.pdf

Peel Region. (n.d.). *Reportable communicable diseases*. https://peelregion.ca/business/infection-prevention-control/reportable-communicable-diseases

Prescott, H. C., & Angus, D. C. (2018). Enhancing recovery from sepsis: A review. *JAMA*, *319*(1), 62–75. https://doi.org/10.1001/jama.2017.17687

Prescott, H. C., Antonelli, M., Alhazzani, W., Møller, M. H., Alshamsi, F., Azevedo, L. C. P., Belley-Cote, E., De Waele, J., Derde, L., Dionne, J. C., Evans, L., Gershengorn, H. B., Hodgson, C. L., Honarmand, K., Kesecioglu, J., McIntyre, L., Mer, M., Nunnally, M. E., Oczkowski, S. J. W., … Coopersmith, C. M. (2026). Surviving Sepsis Campaign: International guidelines for management of sepsis and septic shock 2026. *Intensive Care Medicine, 52*(5), 863–936. https://doi.org/10.1007/s00134-026-08361-1

Provincial Infectious Diseases Advisory Committee. (2013a). *Annex A: Screening, testing and surveillance for antibiotic-resistant organisms (AROs) in all health care settings* (Rev. ed.). Public Health Ontario. https://www.publichealthontario.ca/-/media/documents/aros-screening-testing-surveillance.pdf

Provincial Infectious Diseases Advisory Committee. (2013b). *Annex C: Testing, surveillance and management of Clostridium difficile in all health care settings*. Public Health Ontario. https://www.publichealthontario.ca/-/media/Documents/C/2013/cdiff-testing-surveillance-management.pdf

Provincial Infectious Diseases Advisory Committee. (2025). *Routine practices and additional precautions in all health care settings* (3rd ed., 4th rev.). Public Health Ontario. https://www.publichealthontario.ca/-/media/Documents/B/2012/bp-rpap-healthcare-settings.pdf

Provincial Infectious Diseases Advisory Committee. (n.d.). *Clinical syndromes/conditions with required level of precautions* [Appendix N excerpt]. Public Health Ontario. https://www.publichealthontario.ca/-/media/Documents/R/2012/rpap-clinical-syndromes.pdf

Public Health Agency of Canada. (2013). *Clostridium difficile infection: Infection prevention and control guidance for management in acute care settings*. https://www.canada.ca/en/public-health/services/infectious-diseases/nosocomial-occupational-infections/clostridium-difficile-infection-prevention-control-guidance-management-acute-care-settings.html

Public Health Agency of Canada. (2014). *Antibiotic resistance: Questions & answers* [Brochure]. https://www.canada.ca/content/dam/phac-aspc/images/services/antibiotic-antimicrobial-resistance/antibiotic-resistance-awareness-materials/brochure-web-eng.pdf

Public Health Agency of Canada. (2017). *Help reduce antibiotic resistance*. https://www.canada.ca/en/public-health/services/antimicrobial-resistance/awareness-resources/help-reduce-antibiotic-resistance.html

Public Health Ontario. (2016). *Antimicrobial stewardship strategy: Intravenous to oral conversion*. https://www.publichealthontario.ca/-/media/documents/A/2016/asp-iv-oral-conversion.pdf

Public Health Ontario. (2024). *Recommended steps: Personal protective equipment (PPE)* [Infographic]. https://www.publichealthontario.ca/-/media/Documents/nCoV/ipac/ppe-recommended-steps.pdf

Public Health Ontario. (n.d.-a). *Additional precautions* [Lanyard card]. https://www.publichealthontario.ca/-/media/Documents/L/2013/lanyard-additional-precautions-diseases.pdf

Public Health Ontario. (n.d.-b). *Just Clean Your Hands: Hospitals*. https://www.publichealthontario.ca/en/Health-Topics/Infection-Prevention-Control/Hand-Hygiene/JCYH/JCYH-Hospitals

Public Health Ontario. (n.d.-c). *Routine practices and additional precautions*. https://www.publichealthontario.ca/en/Health-Topics/Infection-Prevention-Control/Routine-Practices-Additional-Precautions

Rumbus, Z., Matics, R., Hegyi, P., Zsiboras, C., Szabo, I., Illes, A., Petervari, E., Balasko, M., Marta, K., Miko, A., Parniczky, A., Tenk, J., Rostas, I., Solymar, M., & Garami, A. (2017). Fever is associated with reduced, hypothermia with increased mortality in septic patients: A meta-analysis of clinical trials. *PLoS ONE*, *12*(1), Article e0170152. https://doi.org/10.1371/journal.pone.0170152

Singer, M., Deutschman, C. S., Seymour, C. W., Shankar-Hari, M., Annane, D., Bauer, M., Bellomo, R., Bernard, G. R., Chiche, J.-D., Coopersmith, C. M., Hotchkiss, R. S., Levy, M. M., Marshall, J. C., Martin, G. S., Opal, S. M., Rubenfeld, G. D., van der Poll, T., Vincent, J.-L., & Angus, D. C. (2016). The Third International Consensus Definitions for Sepsis and Septic Shock (Sepsis-3). *JAMA*, *315*(8), 801–810. https://doi.org/10.1001/jama.2016.0287

University of Ottawa. (2022). *Lab results* [Reference values template aligned with Medical Council of Canada values]. Faculty of Medicine. https://www.uottawa.ca/faculty-medicine/sites/g/files/bhrskd401/files/2023-05/Lab%20Results%20Template_2022_final-EN.pdf

Wester, A. L., Dunlop, O., Melby, K. K., Dahle, U. R., & Wyller, T. B. (2013). Age-related differences in symptoms, diagnosis and prognosis of bacteremia. *BMC Infectious Diseases, 13*, Article 346. https://doi.org/10.1186/1471-2334-13-346

Wounds International. (2023). *Wound care and skin tone made easy*. https://woundsinternational.com/wp-content/uploads/2023/05/MULTI23_ME_SkinTones_WINT-web.pdf

05 Pain

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain how pain is produced and modulated, and distinguish nociceptive, neuropathic and nociplastic pain and acute from chronic pain.
2. Assess pain in adults who can self-report, using valid tools and goals based on function.
3. Assess pain in adults who cannot self-report, including people living with dementia and critically ill patients.
4. Plan multimodal analgesia that combines drug and non-drug measures, with safety checks for acetaminophen, NSAIDs and adjuvant analgesics.
5. Give opioids safely by monitoring sedation and breathing, and recognize and escalate opioid-induced respiratory depression.
6. Care for patients living with chronic pain or opioid use disorder, including those on opioid agonist treatment, without stigma.
7. Teach patients and families about pain plans and opioid safety at home.
8. Distinguish RN and RPN roles in pain care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 4	Clinician; Scholar	Foundations of Practice
2, 3, 6	Clinician; Advocate	Foundations of Practice; Ethical Practice
5, 8	Clinician; Leader	Foundations of Practice; Professional Practice
7	Educator; Communicator	Foundations of Practice; Collaborative Practice

Introduction

Pain is one of the most common reasons people come to hospital, and one of the most common sources of distress once they are there. On a medical-surgical unit, patients have pain from surgery, injuries, procedures and acute illness. Many also arrive with long-standing pain that started well before this admission.

Getting pain care right matters in both directions. Pain is more than a sensation: it can bring fear, anxiety, poor sleep, fatigue and low mood, and it can interfere with physical and mental functioning (Registered Nurses' Association of Ontario [RNAO], 2025). Too much medication, or the wrong combination, also causes harm: combining opioids with gabapentin, pregabalin, benzodiazepines or alcohol, for example, raises the risk of slowed breathing and overdose (Health Canada, 2019).

Nurses are with patients around the clock, so they assess pain often. They give analgesics, offer non-drug measures, watch for adverse effects and speak up when the plan is not working. This chapter covers how pain works (section 5.1), pain assessment (5.2), multimodal and non-opioid analgesia (5.3), safe opioid use in hospital (5.4) and pain care for people living with chronic pain or opioid use disorder (5.5). Perioperative pain care is covered in Chapter 7, cancer pain in Chapter 9, end-of-life symptom control in Chapter 10, and opioid toxicity and withdrawal in Chapter 11.

5.1 Understanding Pain

Defining Pain

In 2020, the International Association for the Study of Pain (IASP) revised its definition of **pain** for the first time since 1979. Pain is now described as an unpleasant sensory and emotional experience that is linked to, or resembles one linked to, actual or potential tissue damage (Raja et al., 2020). The word "resembling" matters: a person can have real pain even when no injury can be found.

The IASP added notes to the definition that shape nursing practice (IASP, n.d.-b; Raja et al., 2020):

- Pain is always a personal experience, shaped by biological, psychological and social factors.
- Pain is not the same as **nociception**, the nervous system's process of detecting and encoding harmful stimuli. Nerve activity alone cannot tell anyone how much a person hurts.
- People learn what pain means through their own life experiences.
- Each person's own account of their pain deserves respect.
- Pain usually protects the body, but it can also harm function and well-being.
- Words are only one way to express pain. A person who cannot speak or communicate may still be in pain.

For the nurse, these notes mean starting from belief, and finding other ways to recognize pain when a person cannot describe it (section 5.2).

How Pain Signals Travel

The path from injury to awareness of pain has four linked processes.

Transduction is the first step. Specialized nerve endings called **nociceptors** respond to strong heat, pressure or chemical stimuli and convert them into electrical signals (IASP, n.d.-b).

Transmission carries the signal inward. Sensory nerve fibres carry it to the dorsal horn of the spinal cord. There they connect with neurons whose fibres cross to the other side and rise in the spinothalamic tract to the thalamus and on to the brain (Ossipov et al., 2010).

Perception is the point at which the person becomes aware of pain. No single "pain centre" exists. Areas involved in sensation, emotion and thinking are activated together, which helps explain why fear, mood and memory change how pain feels (Ossipov et al., 2010).

Modulation is the nervous system's ability to turn pain signals up or down. Pathways that descend from the brainstem, including the periaqueductal grey and the rostral ventromedial medulla, can inhibit or enhance signals arriving at the spinal cord. These pathways use chemical messengers such as serotonin and noradrenaline. The body's own opioids, called **endogenous opioids**, are part of this system. Naloxone, an opioid blocker, reverses the pain relief produced by stimulating these brain areas (Ossipov et al., 2010). Modulation also explains why expectation matters: hope of relief can reduce pain, and fear and anxiety can increase it.

Pain signalling can also become more sensitive. In **peripheral sensitization**, nerve endings near damaged tissue fire more easily. In **central sensitization**, neurons in the spinal cord and brain respond more strongly than usual to normal or even weak input (IASP, n.d.-b). Two clinical signs follow. **Allodynia** is pain from a stimulus that normally does not hurt, such as light touch from bed linen. **Hyperalgesia** is more pain than expected from a stimulus that normally hurts (IASP, n.d.-b). Loss of descending inhibition, or too much descending facilitation, may help keep these changes going in some chronic pain conditions (Ossipov et al., 2010).

Types of Pain

The IASP describes three types of pain by mechanism (IASP, n.d.-b). Many patients have more than one type at the same time.

- **Nociceptive pain** comes from actual or threatened damage to tissue other than nerves, with a nervous system that works normally. **Somatic pain** arises in skin, muscle, bone or joints; it is often well localized and sharp or aching, as with a surgical incision or a fractured hip. **Visceral pain** arises in internal organs, such as with a bowel obstruction or a distended bladder; it is

often harder to pinpoint than somatic pain. Pain can also be felt in a body region away from the site of the harmful stimulus, which is called **referred pain** (Jin et al., 2023). Pain from the heart is a familiar example (see Chapter 17).

- **Neuropathic pain** results from damage to, or disease of, the nerves that carry sensation (IASP, n.d.-b). Patients often describe burning or electric shock-like pain, tingling, numbness or pain from light touch. Examples include painful diabetic neuropathy, pain after shingles (postherpetic neuralgia) and pain after an amputation (Colloca et al., 2017).
- **Nociplastic pain** arises from altered pain processing, without clear evidence of tissue damage or nerve disease to explain it (IASP, n.d.-b). It can occur together with nociceptive pain (IASP, n.d.-b).

Acute and Chronic Pain

Acute pain begins suddenly, usually after injury, illness, surgery or trauma, and acts as a warning. It usually settles as the cause heals (RNAO, 2025). **Chronic pain** is pain that lasts, or keeps returning, for longer than 3 months (Treede et al., 2019). In the IASP classification used in the World Health Organization's *International Classification of Diseases*, 11th revision (ICD-11), chronic pain falls into two groups. In **chronic primary pain**, the pain is a condition in its own right, as in fibromyalgia or nonspecific low back pain. In **chronic secondary pain**, the pain stems from another disease, such as cancer, nerve injury or arthritis (Treede et al., 2019).

Chronic postsurgical pain is pain that begins or worsens after surgery, outlasts normal healing and is still present at least 3 months later (Schug et al., 2019). It is under-recognized and under-treated (Schug et al., 2019). The sensitization processes described above may help explain how pain can outlast the injury that started it.

Pain in Canada

The Canadian Pain Task Force (2021) estimated that 7.6 million people in Canada, or about one in five people of all ages, have chronic pain, based on Health Canada's analysis of the 2019 Canadian Community Health Survey. About one in three people over 65 have chronic pain. Groups the Task Force named as disproportionately affected include older adults, women, Indigenous Peoples, Veterans, people with low incomes, people with mental health or substance use disorders, workers in the trades and transportation, some racialized and ethnic communities, sexually and gender diverse people, people with disabilities and survivors of trauma or violence (Canadian Pain Task Force, 2021). Its first report described older survey data in which Indigenous Peoples had the highest rates of chronic pain. It noted that many Indigenous people describe physical pain as secondary to emotional pain caused by racism, colonization, the early deaths of family members and dispossession, and that discrimination keeps people from getting the help they need (Canadian Pain Task Force, 2019).

Chronic pain is often invisible to others, and many people living with it report feeling disbelieved and stigmatized (Canadian Pain Task Force, 2021). Access to specialized care is uneven. The median wait for a multidisciplinary pain clinic was still about 5.5 months in 2017–2018, 91% of these clinics were in urban areas, and most non-drug treatments were paid for through private insurance or out of pocket (Canadian Pain Task Force, 2019).

CANADIAN CONTEXT

An Action Plan for Pain in Canada

Health Canada set up the Canadian Pain Task Force in 2019 to advise on better prevention and management of chronic pain. It released three reports, in 2019, 2020 and 2021. The final report, *An Action Plan for Pain in Canada*, set six goals (Canadian Pain Task Force, 2021):

- treat pain as a public health priority and coordinate action across jurisdictions;
- give people equitable, consistent access to timely, evidence-informed, person-centred pain care;
- build knowledge, skills and education about pain for people living with pain and for health professionals;
- strengthen pain research;
- use data to monitor pain and improve health system quality;
- improve equitable access for populations disproportionately affected by pain.

The plan calls for pain care that is equity-oriented, trauma- and violence-informed and biopsychosocial. It names legitimizing pain as essential to fighting stigma.

For nurses, the plan becomes concrete at the bedside: believing the patient's report, asking about goals as well as scores, offering non-drug options, and noticing when bias or cost blocks access to care. See Chapter 2 for cultural safety.

5.2 Pain Assessment

Self-Report Comes First

When a person can communicate, their own report is the reference standard for pain assessment (RNAO, 2025). Observers, including experienced nurses, cannot reliably judge from appearance how much someone hurts. A patient who is smiling, sleeping or talking on the phone may still have severe pain.

The **numeric rating scale (NRS)** is the default self-report tool in this book. The nurse asks the patient to rate pain from 0 (no pain) to 10 (the worst pain imaginable). A **verbal descriptor scale** asks the patient to choose a word, such as none, mild, moderate or severe; some people, including some older adults, find words easier than numbers. The **Faces Pain Scale–Revised (FPS-R)** shows six faces scored 0 to 10; the person chooses the face that matches how much they hurt (Hicks et al., 2001). It was developed for children (IASP, n.d.-a). In a study of older adults in acute care in the United States, most of whom were African American or Hispanic, nearly all participants could use the FPS-R, and those with cognitive impairment most often preferred it (Ware et al., 2006). The FPS-R is free for clinical use if it is not changed, but reproducing it in print requires permission (IASP, n.d.-a).

Whatever tool is chosen, the nurse uses the same one each time so that scores can be compared, and records which tool was used. Pain is assessed at rest and with activity, such as turning, coughing, deep breathing or walking. A patient may rate pain 2 out of 10 in bed but 8 out of 10 when trying to cough after abdominal surgery. The second number guides care.

A Complete Pain Assessment

Screening asks whether pain is present. A **comprehensive pain assessment** explores its nature in depth (RNAO, 2025). It is done on admission, when a new pain appears and when pain changes. RNAO (2025) suggests a structured mnemonic, such as OPQRSTUV, so that nothing is missed. A complete assessment covers:

- **Onset and timing:** when the pain began, whether it is constant or comes and goes, and how long episodes last.
- **Location:** where it hurts and whether it spreads; the patient can point or mark a body diagram.
- **Quality:** the patient's own words, such as aching, cramping, stabbing or burning.
- **Intensity:** the score at rest and with movement, now and at its best and worst.
- **Aggravating and relieving factors:** what makes it worse or better, including medications, positions and heat or cold.
- **Effects on function, sleep and mood:** what the pain stops the patient from doing.
- **The patient's goals and the meaning of the pain:** what they hope to be able to do, and what they fear the pain means.
- **Treatment history:** analgesics taken before admission and their effects, including over-the-counter drugs, prescribed opioids, opioid agonist treatment, cannabis, alcohol and other substances (section 5.5).

RNAO (2025) asks providers to consider biological, psychological, social and cultural factors, the person's preferences and input from family. Function-based goals are often more useful than a target number. "Able to walk to the bathroom with a walker," "able to cough and deep breathe every hour" or "able to sleep 4 hours" tell the team whether pain care is working in ways that matter for recovery.

The nurse also listens for features of neuropathic pain, such as burning or electric shock-like sensations, tingling, numbness, or pain from light touch (allodynia) (Colloca et al., 2017). The nurse reports these features to the prescriber, because neuropathic pain may need different medications (section 5.3).

Culture, Language and Trust

People express pain in different ways. Some speak about it freely; others stay quiet, minimize it or describe it in spiritual or emotional terms. The nurse asks rather than assumes, and avoids stereotypes about how any group "should" react to pain. When the patient's preferred language is not English, the nurse uses a professional interpreter rather than family members for assessment (see Chapter 1, section 1.7). RNAO (2025) states that organizations should give health providers access to reliable translation services.

Bias in pain care is documented in Canada. The *In Plain Sight* review in British Columbia found widespread Indigenous-specific racism in health care. It described Indigenous patients being presumed intoxicated, being presumed to have ulterior motives when they needed pain medication, and having pain minimized, ignored or left untreated, sometimes with staff openly invoking a stereotype of Indigenous people as drug-seeking (Turpel-Lafond, 2020). RNAO (2025) asks providers to reflect on their implicit and explicit biases toward Black, Indigenous and racialized people and other underserved groups, and to give care that is culturally safe and trauma- and violence-informed. Chapter 2 (sections 2.2 and 2.3) explains these approaches.

Sexually and gender diverse people and people with disabilities are among the groups more affected by chronic pain (Canadian Pain Task Force, 2021). Past experiences of dismissal can make a patient slow to report pain. Using the patient's chosen name and pronouns, asking about communication needs and adapting tools, such as a large-print scale, all build the trust that honest reporting depends on.

Adults Who Cannot Self-Report

Some adults cannot give a reliable self-report, including people living with advanced dementia, people who are critically ill, sedated or unconscious, people with acute brain injury or stroke, and people at the end of life (RNAO, 2025). For these patients, the nurse must rely on other ways of inferring pain (Herr et al., 2019). The nurse combines several sources of information:

- **Try for self-report first.** Even a yes or no, a head nod, a hand squeeze or an eye blink may work (RNAO, 2025).
- **Consider likely causes.** Recent surgery, fractures, wounds and procedures commonly cause pain, and a full bladder or constipation can cause distress.
- **Observe behaviour with a validated tool.** Observational tools are needed when self-report is not possible (RNAO, 2025).
- **Ask people who know the patient.** Family and caregivers can describe usual behaviour and changes. Their estimates may be too low or too high, so they add to, rather than replace, other information (RNAO, 2025).
- **Treat likely pain and watch the response.** When pain is likely, the nurse gives the prescribed analgesic and reassesses the behaviours afterward, as after any pain treatment (RNAO, 2025).

The **Pain Assessment in Advanced Dementia (PAINAD) scale** was developed for people living with advanced dementia (Warden et al., 2003). The nurse observes five items: breathing, negative vocalization, facial expression, body language and consolability. Each is scored 0 to 2, for a total of 0 to 10 (Resnick et al., 2021). In a study of nursing home residents with moderate to severe dementia, the scale worked the same way for Black and White residents (Resnick et al., 2021).

The **Critical-Care Pain Observation Tool (CPOT)** was first validated in Quebec in 105 adults after cardiac surgery (Gélinas et al., 2006). It scores four behaviours: facial expression, body movements, muscle tension, and either compliance with the ventilator (for intubated patients) or vocalization (for others). Each is scored 0 to 2, for a total of 0 to 8 (Afenigus, 2024). In a later study of intubated adults after cardiac surgery, a cutoff score above 2 during turning detected pain with a sensitivity of 86% and a specificity of 78% (Gélinas et al., 2009).

With either tool, observing during care, such as turning or washing, can reveal pain that is not seen at rest. In the CPOT validation study, scores were higher during turning than at rest (Gélinas et al., 2006).

Behavioural tools show whether pain is likely, not how severe it feels to the person. Vital signs on their own are not reliable indicators of pain. Heart rate and blood pressure may rise during painful procedures, but their value in pain assessment is questionable (Afenigus, 2024), and they also change with fever, fluid loss, anxiety and medications. RNAO (2025) advises minimizing reliance on changes in vital signs alone.

PAINAD and CPOT score behaviours, not skin colour. Colour changes such as flushing or pallor can be harder to see on darker skin (Mukwende et al., 2020), so the nurse relies on cues that are visible on every skin tone: grimacing, frowning, clenched jaw, tense or rigid posture, guarding a body part, rubbing a site, restlessness and resisting care.

Reassessment and Documentation

Pain is reassessed after every drug or non-drug intervention (RNAO, 2025), at the interval set by employer policy for the drug and route. RNAO (2025) also recommends screening at least once a shift for inpatients, after changes in condition, before and after

procedures and before discharge. When pain is not improving or is getting worse, the nurse tells the team and escalates (RNAO, 2025).

Documentation records the tool used, the score at rest and with activity, the patient's description and function, interventions and the response. When opioids are given, sedation level and breathing are recorded too (section 5.4). Documentation follows the College of Nurses of Ontario (CNO) documentation standard (Chapter 1). Table 5.1 compares the main assessment tools.

Table 5.1 Pain assessment tools for adults (Hicks et al., 2001; Warden et al., 2003; Gélinas et al., 2006, 2009; Ware et al., 2006; Resnick et al., 2021; Afenigus, 2024; RNAO, 2025)

Tool	Who it is for	What it measures	Score range	Nursing points
Numeric rating scale (NRS)	Adults who can understand and use numbers	Pain intensity by self-report	0 (no pain) to 10 (worst pain imaginable)	Default tool in this book; ask at rest and with movement; use the same tool each time
Verbal descriptor scale	Adults who prefer words to numbers, including some older adults	Pain intensity by self-report, chosen from a short list of words	Categories such as none, mild, moderate, severe	Record the word chosen, not a converted number; use the same scale each time
Faces Pain Scale–Revised (FPS-R)	Developed for children; usable by many older adults, including some with cognitive impairment	Pain intensity by pointing to one of six faces	0 to 10 in steps of 2	Ask how much it hurts, not how the face looks; free for clinical use unaltered; permission needed to reproduce
Pain Assessment in Advanced Dementia (PAINAD)	Adults living with advanced dementia who cannot self-report	Five behaviours: breathing, negative vocalization, facial expression, body language, consolability	0 to 10 (each item 0 to 2)	Observe during care such as turning; shows likely pain, not its severity; rule out other causes of distress
Critical-Care Pain Observation Tool (CPOT)	Critically ill adults who cannot self-report, intubated or not	Four behaviours: facial expression, body movements, muscle tension, ventilator compliance or vocalization	0 to 8 (each item 0 to 2)	Score above 2 suggests pain; assess at rest and during procedures; do not rely on vital signs

CLINICAL JUDGMENT

Pain in an Older Adult Living With Dementia

Names and details are fictional; this is a composite story.

An 86-year-old woman living with advanced dementia had surgical repair of a hip fracture yesterday. On the evening shift she is restless, calling out and pulling at her gown. She cannot use a number scale.

- **Recognize cues:** She grimaces and holds her breath when turned, pushes the nurse's hands away from her hip and cannot be settled by talking. Her daughter says she is usually calm in the evening. Her last dose of analgesic was 7 hours ago, and she has not voided since her urinary catheter was removed 6 hours ago.
- **Analyze cues:** Her PAINAD score during turning is 7 out of 10. Pain is likely, but agitation after surgery can also come from delirium, a full bladder, low oxygen or infection.
- **Prioritize hypotheses:** Unrelieved incision pain is the most likely cause. Urinary retention and early delirium must be ruled out at the same time.
- **Generate solutions:** Check vital signs and oxygen saturation, scan the bladder per policy, review analgesic orders and plan to reassess with the same tool.
- **Take action:** Oxygen saturation and temperature are normal. The bladder scan shows a large volume, so the nurse follows the retention protocol and reports to the prescriber. The nurse gives the prescribed analgesic, repositions her with a pillow between her knees and dims the lights. The nurse also reports the new agitation, because delirium screening is needed (Chapter 8).
- **Evaluate outcomes:** When the analgesic is expected to have taken effect, her PAINAD score during turning is 2. She is resting and holds her daughter's hand. The nurse documents the scores, actions and response and plans scheduled reassessment.

See Chapter 1, section 1.4, for the clinical judgment model.

5.3 Multimodal and Non-Opioid Analgesia

Why Multimodal

Multimodal analgesia combines different medications, procedures and non-drug measures that act on different parts of the pain pathway (Health Quality Ontario, 2018). Because each one works differently, the combination can relieve pain better than one drug alone. Ontario's quality standard on opioid prescribing for acute pain states that most acute pain, including pain after surgery, can be treated successfully with non-opioid medications combined with physical or psychological measures. Compared with an opioid-based approach, this combination gives better pain control with less opioid use and fewer adverse effects. Opioids are added only when appropriate (Health Quality Ontario, 2018).

The nurse's part is practical. When a non-opioid is ordered on a regular schedule, giving each dose on time keeps relief steady. When it is ordered as needed, the nurse offers it before pain becomes severe and before planned activities, such as physiotherapy or a dressing change. Table 5.2 summarizes the options and the safety checks for each.

Acetaminophen

Acetaminophen relieves mild to moderate pain and reduces fever (B. Braun of Canada, 2023). Acetaminophen, a **nonsteroidal anti-inflammatory drug (NSAID)** or both together are first-line choices for many types of acute pain in people without contraindications (Health Quality Ontario, 2018). Acetaminophen's main serious risk is liver injury.

The Canadian product monograph for intravenous acetaminophen sets the maximum for adults who weigh at least 50 kg and have no added risk of liver toxicity at 4,000 mg in 24 hours. Below 50 kg, dosing is based on weight. When liver function is impaired or other risk factors for liver toxicity are present, the monograph says a lower daily total of 3,000 mg may be appropriate (B. Braun of Canada, 2023). It names chronic alcohol use, malnutrition and dehydration among those risk factors.

The maximum includes acetaminophen from every source and every route: oral, rectal and intravenous (B. Braun of Canada, 2023). Most reported cases of liver injury involve doses above the daily limit, often from more than one acetaminophen-containing product (B. Braun of Canada, 2023). Acetaminophen is "hidden" in many combination products, including cold and flu remedies and some prescription opioid tablets. The nurse checks the medication administration record and the patient's own medications for every source, totals the daily dose, and teaches the patient to read labels at home.

NSAIDs and COX-2 Inhibitors

NSAIDs reduce pain and inflammation by blocking cyclooxygenase (COX) enzymes, which lowers prostaglandin production (GlaxoSmithKline Consumer Healthcare ULC, 2025). Examples include ibuprofen, naproxen and ketorolac. Celecoxib is a COX-2 inhibitor, an NSAID that acts mainly on one form of the enzyme. The Canadian celecoxib monograph describes risks that apply across the class (Nora Pharma, 2026):

- **Gastrointestinal ulcers and bleeding,** which can occur without warning. Risk is higher with a past ulcer or bleed, older age, long-term use, heavy alcohol use, smoking, and use with anticoagulants, antiplatelet drugs including low-dose acetylsalicylic acid (ASA), oral corticosteroids or selective serotonin reuptake inhibitors.
- **Kidney injury,** especially with existing kidney disease, dehydration, heart failure, liver disease, older age, and use with angiotensin-converting enzyme (ACE) inhibitors, angiotensin receptor blockers (ARBs) or diuretics. NSAIDs can also raise potassium.
- **Cardiovascular events,** including heart attack and stroke, with risk rising with dose and duration. Sodium and fluid retention can raise blood pressure and worsen heart failure.
- **Bleeding with anticoagulants,** such as warfarin.

The celecoxib monograph's contraindications include severe kidney impairment, active gastrointestinal bleeding, severe uncontrolled heart failure, the period around coronary artery bypass graft surgery, the third trimester of pregnancy, and a history of asthma, hives or other allergic reactions after taking ASA or another NSAID (Nora Pharma, 2026). Before each dose, the nurse checks kidney function and urine output, signs of bleeding (black stools, vomiting blood, bruising), blood pressure, fluid status and the medication list. Kidney function and electrolytes are covered in Chapter 3.

Adjuvant Analgesics

An **adjuvant analgesic** is a drug whose main use is not pain relief but which relieves some types of pain, especially neuropathic pain. Ontario's acute pain standard lists the anticonvulsants gabapentin and pregabalin and the antidepressants amitriptyline, nortriptyline and duloxetine among non-opioid options (Health Quality Ontario, 2018). Patients may not expect an anticonvulsant or antidepressant to be ordered for pain, so the nurse explains why it is being used.

Gabapentin and pregabalin, called **gabapentinoids**, need special care. Health Canada (2019) warns that taking them with opioids raises the risk of opioid overdose; the combination can slow breathing and cause increased sleepiness, dizziness, fainting and death. Benzodiazepines and alcohol can also raise the risk. When a patient receives a gabapentinoid with an opioid, the nurse monitors sedation and breathing as closely as for an opioid alone (section 5.4).

Local and Regional Anesthesia

Local anesthetics block nerve signals where they are applied. A surgeon may infiltrate the wound at the end of surgery. An anesthesiologist may inject near a nerve or group of nerves (a nerve block), sometimes leaving a catheter for a continuous infusion, or give medication into the epidural space for chest, abdominal or lower limb surgery. These interventional techniques are one part of multimodal analgesia (Health Quality Ontario, 2018). They also bring specific risks, such as numbness, weakness and low blood pressure. Monitoring is described in section 5.4.

Non-Drug Measures

Non-drug measures are part of the plan, not an afterthought. Ontario's quality standard lists self-management measures (heat, ice, massage, stretching and rest), professional measures (positioning, splints, bracing, physiotherapy and transcutaneous electrical nerve stimulation) and psychological measures (relaxation, guided imagery and cognitive behavioural therapy) (Health Quality Ontario, 2018). RNAO (2025) names physiotherapy, massage, relaxation and education among strategies to help prevent pain after surgery. It calls for an integrated approach that combines drug and non-drug strategies to fit each person and family; this good practice statement was not based on a formal evidence review.

On a medical-surgical unit, the nurse can:

- position the patient with pillows to support painful areas and change position regularly;
- teach the patient to splint an abdominal or chest incision with a pillow when coughing;
- help with early, planned movement, timed after an analgesic dose;
- apply heat or cold as ordered, with a cloth barrier, for a limited time, checking the skin, and avoiding them where sensation or circulation is reduced;
- coach slow breathing and relaxation, and offer distraction, such as music or conversation;
- protect sleep by clustering care and reducing noise and light at night;
- explain what to expect, which reduces fear and builds the patient's sense of control.

Table 5.2 Multimodal analgesia: options and nursing safety checks (Health Quality Ontario, 2018; Health Canada, 2019; B. Braun of Canada, 2023; Nora Pharma, 2026)

Approach	Examples	How it helps	Nursing safety checks
Acetaminophen	Acetaminophen by mouth, rectally or intravenously	Relieves mild to moderate pain and fever; first-line for many types of acute pain	Total daily dose from all products and routes; lower limit with liver disease or risk factors; check combination products
NSAIDs and COX-2 inhibitors	Ibuprofen, naproxen, ketorolac, celecoxib	Reduce pain and inflammation	Kidney function and urine output; bleeding; blood pressure and fluid status; anticoagulants, ACE inhibitors, ARBs, diuretics
Gabapentinoids	Gabapentin, pregabalin	Non-opioid options, especially for neuropathic pain	Sedation, dizziness, slowed breathing, especially with opioids; fall risk

Approach	Examples	How it helps	Nursing safety checks
Antidepressants for neuropathic pain	Duloxetine, amitriptyline, nortriptyline	Non-opioid options, especially for neuropathic pain	Drowsiness, dizziness, falls; explain why an antidepressant is used for pain
Local and regional anesthesia	Wound infiltration, nerve blocks, epidural analgesia	Block pain signals at the site or nerve	Sensation, movement, blood pressure, catheter site; see section 5.4
Opioids	See section 5.4	Relieve moderate to severe pain when other measures are not enough	Sedation and respiratory monitoring; see section 5.4
Non-drug measures	Positioning, splinting, early movement, heat, cold, relaxation, distraction, sleep, education	Reduce pain, fear and muscle tension; support function	Skin checks with heat and cold; avoid where sensation is reduced; match to patient preference

LIFESPAN CONSIDERATIONS

Older Adults and Pain

About one in three people over 65 in Canada live with chronic pain (Canadian Pain Task Force, 2021). About half of people living with dementia have pain, which often goes unrecognized and untreated (Resnick et al., 2021). The nurse asks every older adult about pain directly, offers a verbal descriptor scale if numbers are hard, and uses PAINAD when self-report is not possible. Family members who know the person's usual behaviour add valuable information (RNAO, 2025).

Older adults are more sensitive to medication harms:

- NSAIDs: older adults tolerate ulcers and bleeding less well, and most fatal gastrointestinal events reported with celecoxib occurred in older adults. Older age also raises the risk of kidney injury. The monograph advises considering a lower starting dose with close supervision (Nora Pharma, 2026).
- Gabapentinoids with opioids: the sleepiness, dizziness and fainting that Health Canada (2019) warns about can lead to a fall.

The nurse reviews kidney function, watches for new confusion, constipation and unsteadiness, and reports them promptly. Chapter 8 covers delirium and falls.

5.4 Opioids: Safe Use in Hospital

Opioids remain essential for moderate to severe acute pain when non-opioid and non-drug measures (section 5.3) are not enough. They are also among the drugs most often involved in serious medication incidents. This section explains how opioids work and how the nurse keeps patients who receive them safe.

How Opioids Work

An **opioid** is a drug that acts on the body's opioid receptors to relieve pain. The receptor that matters most for pain relief is the **mu-opioid receptor**. Mu receptors are concentrated in the parts of the brain and spinal cord that modulate pain, and morphine and similar drugs act mainly there (BGP Pharma, 2015). When an opioid binds to these receptors, fewer pain signals pass upward through the spinal cord, and the brain responds less strongly to the signals that do arrive.

The same receptors explain the adverse effects. Opioids cause drowsiness and, at higher levels, slow and shallow breathing. Mu receptors in the wall of the gut slow bowel movement, which is why constipation is so common; drugs that block only these gut receptors are an option when laxatives have not worked (Crockett et al., 2019). Nausea, itching and difficulty passing urine are also common. Morphine can release histamine from cells, which adds to itching and flushing (Fresenius Kabi Canada, 2019).

Morphine, hydromorphone, oxycodone and fentanyl are **full agonists**: they switch the mu receptor fully on, and their effects keep increasing as the dose rises. Buprenorphine, used mainly to treat opioid use disorder (section 5.5), is a **partial agonist**: it activates the mu receptor, but less fully (Indivior UK, 2025).

Opioids Used in Canadian Hospitals

Table 5.3 lists the opioids nurses most often give for pain in Canadian hospitals, with their routes and key safety points. Routes include oral, intravenous (IV), subcutaneous, intramuscular and transdermal; patient-controlled and epidural routes are described in the Going Deeper box.

A few points deserve emphasis. Codeine has little effect until the liver enzyme CYP2D6 converts it to morphine. Some people, called ultra-rapid metabolizers, make this conversion faster and more completely than others, so a usual dose can produce an unexpected morphine overdose (Health Canada, 2013). Tramadol carries a similar warning: ultra-rapid metabolizers form its stronger active metabolite quickly, which can cause life-threatening respiratory depression (Health Canada, 2017). Because no one can tell from the bedside how a patient metabolizes these drugs, the nurse watches every patient for oversedation.

Morphine is broken down into metabolites that the kidneys excrete. One of them, morphine-6-glucuronide, is itself active and builds up in people with kidney disease (BGP Pharma, 2015). The nurse reviews kidney function (Chapter 3) and reports rising creatinine. Hydromorphone and oxycodone also need caution in kidney or liver impairment (Purdue Pharma, 2023; Sandoz Canada, 2025).

Fentanyl patches release the drug slowly over days. They are meant only for patients who already take a substantial daily amount of opioid for long-term pain. They are contraindicated for acute or perioperative pain and in **opioid-naive** patients, those not already taking opioids regularly, at any strength (Teva Canada, 2022).

Table 5.3 Opioids commonly used for pain in Canadian hospitals (Health Canada product monographs)

Opioid	Common routes	Points for nursing safety
Morphine	Oral (immediate- and sustained-release); IV, subcutaneous and intramuscular injection	An active metabolite builds up in kidney impairment, so sedation can increase over days; may release histamine, causing itching or flushing
Hydromorphone	Oral tablets; IV, subcutaneous and intramuscular injection; PCA	High-alert drug often confused with morphine; written HYDROmorphone in tall man lettering; several injectable concentrations exist; caution in kidney or liver impairment
Oxycodone	Oral	Tablets are swallowed whole, never cut, crushed or chewed; caution in kidney or liver impairment
Fentanyl	Transdermal patch; injection, mainly in critical care, anesthesia and procedures	Patch only for opioid-tolerant patients with long-term pain; contraindicated for acute or perioperative pain and in opioid-naive patients; heat and fever increase absorption; used patches folded sticky sides together and returned to a pharmacy
Codeine	Oral, including products combined with acetaminophen	Converted to morphine by CYP2D6; ultra-rapid metabolizers may form enough morphine to overdose; Health Canada advises alternatives in children under 12
Tramadol	Oral	Converted by CYP2D6 to a stronger metabolite; ultra-rapid metabolizers are at risk of life-threatening respiratory depression
Tapentadol	Oral	Acts on mu receptors and blocks norepinephrine reuptake; risk of serotonin syndrome with other serotonergic drugs and of seizures; not used within 14 days of a monoamine oxidase inhibitor

Opioid-Induced Respiratory Depression

Opioid-induced respiratory depression (OIRD) is a reduced drive and effort to breathe caused by an opioid. Breathing becomes slower, shallower or irregular, carbon dioxide builds up, and untreated OIRD can progress to respiratory arrest and death. The Institute for Safe Medication Practices Canada (ISMP Canada) and coroners' and medical examiners' offices in four provinces reviewed deaths from 2007 to 2012. Of the 115 deaths in which a medication incident may have contributed to or caused the death, opioids were involved in 54 (47%), more than any other drug class (ISMP Canada, 2014).

Respiratory depression is generally preceded by sedation (The Joint Commission, 2012). As the opioid level in the brain rises, the patient becomes drowsier before breathing slows to a dangerous degree. Increasing sleepiness is therefore the nurse's earliest warning, and the time to act.

Every hospitalized patient who receives opioids for acute pain carries some risk, so every patient's risk is assessed and reassessed (Jungquist et al., 2020). The risk is higher with the following (Chincholkar, 2020; ISMP Canada, 2014; Purdue Pharma, 2023; The Joint Commission, 2012):

- **Patient factors:** no recent opioid use; older age, with risk rising in each decade after 60; obstructive sleep apnea, other sleep disorders or snoring; obesity; lung or heart disease; and kidney or liver impairment, which slow drug clearance.
- **Treatment factors:** recent surgery, especially upper abdominal or chest surgery; longer general anesthesia; dose increases or a switch to another opioid; use of other drugs that cause drowsiness, for example benzodiazepines, gabapentinoids or sedating antihistamines; and more than one opioid order left active at the same time.
- **Environment of care:** the setting and how often the patient can be watched also affect risk (Jungquist et al., 2020).

Older adults need special attention, because these factors often occur together (Chapter 8).

Monitoring Sedation and Breathing

The nurse assesses sedation and breathing before giving an opioid, again at the intervals the order set or policy sets, and more often after a dose increase or a change of opioid (Jungquist et al., 2020; The Joint Commission, 2012). The assessment includes:

- **Sedation level:** how awake the patient is and how easily they rouse.
- **Breathing:** respiratory rate counted carefully, depth, regularity, pauses, and snoring or noisy breathing.
- **Oxygen saturation (SpO2):** with supplemental oxygen, SpO2 can stay normal while carbon dioxide builds up, so a normal reading can be falsely reassuring (The Joint Commission, 2012).
- **Colour:** a bluish or greyish tinge is a late sign and may be harder to see on darker skin, so the nurse also looks at the lips, tongue, gums and inside of the mouth.

For higher-risk patients, policy may call for continuous pulse oximetry or **capnography**, which measures exhaled carbon dioxide and detects hypoventilation directly (The Joint Commission, 2012).

A **sedation scale** gives nurses a shared language for drowsiness. The Pasero Opioid-induced Sedation Scale (POSS) is widely used outside critical care (Pasero, 2009). In summary, the scale sorts patients into two groups. Patients who are fully awake, sleeping but easy to wake, or a little sleepy yet quick to rouse are at a safe level. Patients who keep nodding off, even while talking, or who can barely be roused are not, and the nurse acts at once. Intensive care units use the Richmond Agitation-Sedation Scale (RASS) instead.

When sedation increases, the nurse holds further opioid doses, wakes the patient, coaches deep breathing, reassesses and notifies the prescriber or RN. If the patient responds minimally or breathing is inadequate, the nurse calls for help at once, supports the airway and gives naloxone according to the order, medical directive and policy (Table 5.4). Rapid response is covered in Chapter 6, and naloxone and opioid toxicity in Chapter 11.

Table 5.4 Recognizing and responding to opioid-induced sedation and respiratory depression (based on Pasero, 2009; Jungquist et al., 2020; The Joint Commission, 2012)

What the nurse sees	What it may mean	Nursing actions
Fully awake, or sleeping but opens eyes to a normal voice and stays awake	Safe level of sedation	Continue the pain plan; give opioid as ordered when needed; reassess at the intervals policy sets
A little sleepy, but wakes with a word and joins in the conversation	Still safe; watch for a downward trend	Continue the plan; reassess sooner after each opioid dose or dose increase
Keeps nodding off, even while talking, but can be woken	Too sedated; respiratory depression may follow	Hold opioid doses (including PCA doses, per policy); rouse and coach deep breaths; check breathing and SpO2; notify the prescriber or RN; stay close and recheck often; use non-opioid analgesia as ordered
Hard to wake; little or no reaction to voice or a firm touch	Dangerously sedated; breathing may stop	Stop all opioids; call for help (rapid response per policy); stay; stimulate; open and support the airway and breathing; give naloxone per order or medical directive

What the nurse sees	What it may mean	Nursing actions
Slow, shallow or irregular breathing, pauses or snoring; SpO2 falling or exhaled carbon dioxide rising	Respiratory depression (hypoventilation)	Act as for a patient who is hard to wake: stop opioids, call for help, support breathing, give naloxone per order; do not rely on raising oxygen alone

CLINICAL SAFETY

When the Patient Is Too Sleepy

Increasing sleepiness is the first and most important cue of opioid-induced respiratory depression. Breathing usually slows only after the patient has become hard to keep awake (The Joint Commission, 2012).

- If a patient keeps drifting off while talking with the nurse, hold the next opioid dose, wake them fully, coach deep breaths, check breathing and SpO2, and notify the prescriber or RN.
- If the patient barely responds, call for help immediately, stay, support breathing and give naloxone according to the order or medical directive.
- Do not wake a sleeping patient only to offer an as-needed (PRN) opioid. Do wake the patient to assess sedation and breathing when the plan or policy calls for it.
- Be wary of the phrase "sleeping comfortably." A patient who is truly asleep wakes easily and stays awake. A patient who cannot stay awake may be oversedated.
- Remember that SpO2 can look normal on supplemental oxygen while carbon dioxide rises.
- Tell the next nurse at handover about any increase in sedation, even if it has settled.

High-Alert Medication Safety

Opioids are **high-alert medications**: errors with them are more likely to cause serious harm (ISMP Canada, n.d.; Chapter 1, section 1.6). In ISMP Canada's (2014) analysis of opioid-related deaths linked to medication incidents, hydromorphone figured in over a third of the incidents reviewed. Patterns included morphine and hydromorphone mix-ups caused by similar names and doses, and small doses drawn from high-concentration vials; in one case, 4 mg was given instead of 0.4 mg (ISMP Canada, 2013). Others were an old opioid order left active alongside a new one, pump programming errors, crushed long-acting tablets, and PRN doses given routinely (ISMP Canada, 2014; Figure 5.1).



Figure 5.1 (a) A patient-controlled analgesia (PCA) pump with a morphine cassette for intravenous use. (b) A pump set up for an epidural infusion of fentanyl with bupivacaine; the label reads “Epidural Use Only.” These labels are from the United States; Canadian products are labelled differently. (credit: (a) “PCA-02” and (b) “PCA-01” by DiverDave/Wikimedia Commons, CC BY-SA 3.0)

Safeguards work at several levels:

- Tall man lettering (HYDROmorphone) and separate storage for morphine and hydromorphone.
- Limiting high-concentration products on units, and supplying dosage forms that match the doses usually ordered (ISMP Canada, 2013, 2014).
- Order sets that set monitoring parameters and when to act.
- **Independent double checks** of dose calculations, pump programming and administration, as policy requires (ISMP Canada, 2014, 2016).
- **Smart pumps** with dose-error reduction software (The Joint Commission, 2012).

SCOPE IN PRACTICE

Opioids, PCA and Epidural Analgesia

CNO's Scope of Practice standard explains nursing roles through authority, competence and context (College of Nurses of Ontario, 2025; Chapter 1, section 1.3).

- **Authority:** Both RNs and RPNs give controlled substances, including opioids, when there is an order or a medical directive that applies. Nurses do not initiate opioids in a public hospital.
- **Competence:** Before giving an opioid, the nurse needs the knowledge and skill to assess pain, sedation and breathing, and to recognize and respond to oversedation.
- **Context:** Managing patient-controlled analgesia (PCA) or epidural analgesia depends on employer policy, the nurse's education and the patient's needs. Some hospitals limit these to RNs with added education; others prepare RPNs for parts of the care. When a patient's condition changes or becomes less predictable, the RPN consults the RN.

- **Every nurse escalates:** Any nurse who notices increasing sedation or slow breathing acts at once and calls for help, whoever is assigned to the patient.

Employer policy and the province or territory matter. CNO's revised Scope of Practice and Medication standards take effect March 1, 2027 (College of Nurses of Ontario, 2026).

GOING DEEPER

PCA, Epidural Analgesia and Morphine Milligram Equivalents

Required for RN students; optional for PN students.

Patient-controlled analgesia (PCA) uses a programmable pump. The patient presses a button to receive a set **demand dose**. A **lockout interval** blocks further doses until the last one has had time to act, and the pump may also cap the total over a set period. PCA has a built-in safety check: a patient who becomes too drowsy stops pressing the button. A continuous **basal infusion** removes that check, because the drug keeps flowing even when the patient is sleepy, so a patient with a basal infusion needs especially close monitoring of sedation and breathing.

PCA by proxy happens when someone other than the patient, such as a family member or a staff member, presses the button. It bypasses the safety check and has caused serious harm (The Joint Commission, 2004). The nurse teaches the patient and visitors that only the patient presses the button.

Epidural analgesia delivers local anesthetic, often with an opioid, through a catheter into the epidural space. As policy directs, the nurse monitors pain, sedation and breathing; sensory and motor block in the legs; blood pressure; and the catheter site. Anticoagulant doses, such as enoxaparin, are timed around catheter insertion and removal. New back pain, numbness or weakness in the legs, or new bowel or bladder problems can signal a spinal or epidural hematoma. This bleeding around the spinal cord can cause lasting or permanent paralysis and needs urgent diagnosis and treatment, so the nurse reports these signs immediately (sanofi-aventis Canada, 2021).

Morphine milligram equivalents (MME) express different opioids as an equivalent amount of oral morphine. This makes it possible to compare total opioid exposure. For example, fentanyl patches are only for patients already taking at least 60 mg of morphine equivalents a day (Teva Canada, 2022). The 2017 Canadian guideline for chronic non-cancer pain recommends keeping new prescriptions below 90 mg morphine equivalents daily and suggests below 50 mg (Busse et al., 2017). Conversions between opioids are the work of prescribers and pharmacists, not nurses.

Constipation and Other Effects

Constipation affects nearly all patients who take opioids regularly (Fresenius Kabi Canada, 2019). Traditional laxatives are first-line treatment for opioid-induced constipation (Crockett et al., 2019). For this reason, a **bowel regimen** is usually ordered as soon as regular opioids begin. This is a scheduled plan, often a stimulant laxative, an osmotic laxative or both. The nurse assesses the usual bowel pattern, last bowel movement, distension and fluid intake, encourages movement, and reports no bowel movement despite the regimen.

Nausea is managed with antiemetics as ordered and by reducing opioid needs through multimodal analgesia (section 5.3). Itching is common, especially with morphine; the nurse reports it rather than assuming it is an allergy. Opioids can cause urinary retention (Fresenius Kabi Canada, 2019). The nurse monitors voiding and assesses the bladder as policy directs, especially after surgery. Drowsiness and dizziness also raise the risk of falls, particularly in older adults (Chapter 8).

Tolerance, Physical Dependence and Opioid Use Disorder

Three terms are often confused, and the confusion harms patients.

- **Tolerance:** the need for more of a drug to get the same effect, or a smaller effect from the same dose, after repeated use.
- **Physical dependence:** the body's adaptation to a drug, so that stopping it suddenly or cutting the dose quickly causes withdrawal symptoms.
- **Opioid use disorder (OUD):** a problematic pattern of opioid use that causes significant problems or distress. Under the criteria of the *Diagnostic and Statistical Manual of Mental Disorders*, fifth edition (DSM-5), it is diagnosed when at least 2 of 11 criteria are present within a year, such as craving, unsuccessful attempts to cut down, and continued use despite harm. Severity is mild (2 to 3 criteria), moderate (4 to 5) or severe (6 or more) (Centers for Disease Control and Prevention [CDC], 2024).

Tolerance and physical dependence are expected after regular opioid use. Under the diagnostic criteria, they do not count toward OUD in a person who takes opioids only as medically supervised (CDC, 2024). A patient who needs a higher dose, or feels unwell when a dose is late, is not showing addiction. Tapering is gradual, because fast reductions can increase pain and cause withdrawal (Busse et al., 2017).

Words matter. Health Canada (2022) advises person-first, medically accurate language, such as "person with opioid use disorder," instead of "addict," "abuser" or "clean," because stigmatizing words drive people away from care and contribute to poorer care. "Drug-seeking" is a similar label that assumes a motive. The nurse documents what was observed instead: "requested analgesia 40 minutes before due; rates pain 8 out of 10 when walking."

Figure 5.2 A take-home naloxone kit as distributed in British Columbia. (credit: "NaloxoneKit" by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

Opioids at Discharge

Ontario's quality standard *Opioid Prescribing for Acute Pain*, for people 15 years and older, calls for prescribing the weakest immediate-release opioid that works, at the lowest dose that relieves the pain (Health Quality Ontario, 2018). Three days or less is often enough, and more than 7 days is rarely needed. Methadone, fentanyl patches and extended-release opioids are not recommended for acute pain. Patients and families should receive information about benefits and harms, safe storage and safe disposal, and a plan for tapering and stopping (Figure 5.2).

Since October 23, 2018, pharmacies and prescribers who dispense prescription opioids must provide a warning sticker and a patient information handout; opioids given under supervision in hospital are exempt (Health Canada, 2018). The sticker warns of dependence, addiction and overdose, and the handout describes signs of overdose and safe storage.

The nurse reconciles medications (Chapter 1, section 1.7), teaches the patient to return unused opioids to a pharmacy, and tells patients about free take-home naloxone kits. In Ontario, pharmacies in the Ontario Naloxone Program for Pharmacies supply them at no cost to people at risk of overdose and to their family and friends, without a health card (Ontario Ministry of Health, 2025). Naloxone is covered in Chapter 11.

PATIENT EDUCATION

Opioids at Home

The nurse teaches the patient and family to:

- Take the opioid only as prescribed and only while pain needs it. Use acetaminophen, an anti-inflammatory if allowed, ice, rest and movement first.
- Follow the tapering plan, and never take extra doses or doses closer together.
- Report severe drowsiness, confusion, slow or shallow breathing, or trouble staying awake. Family should call 9-1-1 if they cannot wake the person.
- Prevent constipation with the prescribed laxative, fluids and activity.
- Avoid alcohol, sleeping pills, cannabis and other sedating drugs unless the prescriber approves.
- Not drive or operate machinery while drowsy or after a dose increase.
- Store opioids locked and out of sight, away from children, teens, visitors and pets, and never share them.
- Return unused opioids and used patches to a pharmacy; do not flush them or put them in the garbage.
- Get a free naloxone kit from a pharmacy and show family where it is kept.
- Call the prescriber or pharmacist with questions about pain, side effects or stopping.

5.5 Patients Living With Chronic Pain or Opioid Use Disorder

Many adults admitted to hospital already live with chronic pain, take long-term opioids, or have opioid use disorder. Their pain is real, and it is often harder, not easier, to treat. This section explains how the nurse adapts pain care for these patients and builds the trust that care depends on.

Chronic Pain in Hospital

A patient who takes medications for chronic pain at home usually continues them in hospital unless there is a clear reason to stop, such as oversedation, a new kidney problem or surgery that prevents swallowing. The nurse confirms the home regimen through medication reconciliation (Chapter 1, section 1.7), including the drug, dose, timing and last dose taken. Stopping a long-term opioid abruptly can cause withdrawal and worse pain; when a dose must be reduced, it is done gradually (Busse et al., 2017).

Acute pain from surgery or injury comes on top of the chronic pain. A patient who regularly takes opioids has tolerance, so usual doses may give little relief. Ontario's quality standard calls for these patients to receive care from clinicians with pain expertise. Any short-term increase in opioids should come with a plan to return to the previous dose (Health Quality Ontario, 2018). Multimodal analgesia (section 5.3) is especially valuable here.

The nurse asks about the patient's own pain plan: what usually works, what goals matter, and which activities they want to manage. Function, such as walking to the bathroom, doing breathing exercises or sleeping, is often a more useful goal than a pain score of zero. The 2017 Canadian guideline on opioids for chronic non-cancer pain remains the national reference (Busse et al., 2017). At discharge, the nurse makes sure the patient's usual prescriber learns of any change to the regimen, so that the plan to return to the previous dose is carried out in the community.

Opioid Agonist Treatment and Acute Pain

Opioid agonist treatment (OAT) treats opioid use disorder with a long-acting opioid that prevents withdrawal and cravings. Canada's 2024 national guideline recommends **buprenorphine** and **methadone** as preferred first-line options. Slow-release oral morphine is a second-line option (Yakovenko et al., 2024). Buprenorphine is often given as buprenorphine-naloxone, dissolved under the tongue. It is also available as Sublocade, an extended-release injection under the skin given only by a health care professional. Its monograph advises non-opioid analgesia whenever possible for acute pain, and this advice extends to anyone who has received it within the past 6 months (Indivior UK, 2025).

A patient on OAT usually continues it in hospital. Ontario's quality standard states that people taking methadone or buprenorphine-naloxone continue it during acute pain (Health Quality Ontario, 2018). Before giving the first hospital dose, the team confirms the current dose and whether today's dose was already taken, by calling the community pharmacy or prescriber (College of Physicians & Surgeons of Manitoba [CPSM], 2023). This step prevents a double dose or a dangerous gap. Methadone stays in the body a long time, so a patient who receives too much needs prolonged monitoring (ISMP Canada, 2014).

The daily OAT dose is the baseline that prevents withdrawal; it does not provide significant relief of acute pain (CPSM, 2023). Patients on OAT therefore usually need additional analgesia for acute pain. Multimodal measures come first. When opioids are needed, they are added to the OAT, and because of tolerance, higher doses may be required (CPSM, 2023; Indivior UK, 2025). Undertreating acute pain in patients on OAT is poor care, and it rests partly on misconceptions that can be corrected (Alford et al., 2006). The nurse advocates for an addiction medicine or acute pain service consultation when one is available. The nurse also keeps monitoring sedation and breathing, because tolerance does not remove risk.

Stigma, Trust and Harm Reduction

In a Vancouver study, people who use drugs and had left hospital against medical advice described stigma, feeling neglected, and poorly managed pain and withdrawal in the emergency department. Some said these experiences made them less willing to come back for care (Mayer et al., 2023). Stigma also works through policies and routines, not only through individual attitudes (Health Canada, 2022).

The nurse counters this with trauma-informed, non-judgmental care (Chapter 2). Many patients who use drugs have past experiences of being dismissed or mistreated in health care, and First Nations, Inuit and Métis patients may also have faced Indigenous-specific

racism (Chapter 2, sections 2.2 and 2.3). The nurse believes and assesses the patient's report of pain and asks about withdrawal symptoms. The nurse explains the plan, including when the next dose is due and why, and follows through on what was promised. Small, reliable actions rebuild trust. Person-first language in conversation, handover and documentation shows respect and shapes how colleagues see the patient.

Harm reduction means practical steps that reduce the harms of substance use without requiring a person to stop using. In hospital, it can include treating withdrawal promptly, offering naloxone and teaching, and connecting the patient with community services. The nurse involves addiction medicine, social work, or an Indigenous patient navigator or liaison when the patient wants this. These partners can bridge gaps in trust that the unit cannot bridge alone. Canada's 2024 guideline states that evidence-based harm reduction belongs across the continuum of care (Yakovenko et al., 2024).

When a Patient Wants to Leave

When a patient who uses drugs says they want to leave before treatment is finished, the nurse treats this as a cue, not a confrontation. The nurse asks why. Poorly managed pain or withdrawal and feeling judged or dismissed are among the experiences people describe before leaving (Mayer et al., 2023). Many of these can be fixed. The nurse reassesses pain and withdrawal, tells the RN or most responsible practitioner right away, and asks the team to review the plan.

If the patient still chooses to leave, the nurse respects a capable person's decision (consent and capacity are covered in Chapter 1, section 1.5). The nurse also works to make leaving safer. Steps, according to policy, include:

- Offering a naloxone kit and teaching.
- Offering harm reduction supplies.
- Arranging prescriptions and a follow-up plan with the patient's OAT provider or primary care.
- Telling the patient they are welcome to return.

For a patient on OAT, the team communicates directly with the community prescriber and pharmacy, so the patient's next dose is not missed. Any opioid prescription for acute pain is kept short, to match the patient's follow-up at the OAT clinic (CPSM, 2023). The nurse documents the discussion and the patient's own words. Withdrawal management and starting OAT are covered in Chapter 11.

> **PRACTICE STORY**
>
> **"Nobody Believes I'm Hurting"**
>
> *Names and details are fictional; this is a composite story.*
>
> Nurse: Renata Kowalczyk, RPN. Years in practice: 6. Setting: surgical unit, community hospital, Ontario.
>
> Mr. Desmond Ferris was 41 and two days out from a repair of a fractured ankle. At handover I heard, "He's on methadone, so he's probably just looking for more." When I walked in, he was sitting rigid on the edge of the bed, his foot elevated, his jaw tight.
>
> "Nobody believes I'm hurting," he said. "They act like I'm here to get high."
>
> I sat down and asked him to tell me about the pain. He rated it 9 out of 10, worse on movement, and he hadn't been able to get to the bathroom without help. His chart showed his methadone had been given each morning since admission, but nobody had documented confirming his community dose. I called his pharmacy, which confirmed that the dose matched and that his last dose there was the morning he was injured. That was one less worry.
>
> Then I went to my RN, Joel, with what I had: his pain score, his function, his vital signs and his sedation level: wide awake, with no sign of drowsiness. I explained that his methadone was holding off withdrawal, not treating his surgical pain. Joel agreed the plan wasn't working. Together we called the surgical resident and asked about scheduled acetaminophen and an anti-inflammatory, ice and elevation, a review of his opioid order, and an addiction medicine consult.
>
> The consult team came that afternoon. By evening, Mr. Ferris was walking to the bathroom with a walker. Before I left, he said, "Thanks for not treating me like a junkie." I told him he shouldn't have had to thank anyone for that.
>
> The next morning, I raised the handover comment with our manager. I didn't want to blame anyone; I wanted us to talk about how we hand over patients on OAT.
>
> Reflect: Which parts of Mr. Ferris's care were within Renata's scope as an RPN, and when was consulting the RN the right step? How could the unit change its handover language for patients on OAT?

Chapter 5 Summary

Introduction

- Pain is a common reason for admission and a major source of distress; both under-treatment and over-treatment cause harm.
- Nurses assess pain, give analgesics and non-drug measures, monitor for adverse effects and escalate when the plan is not working.

5.1 Understanding Pain

- The IASP (2020) defines pain as an unpleasant sensory and emotional experience; each person's report of pain deserves respect, and inability to communicate does not rule out pain.
- Pain signals involve transduction, transmission, perception and modulation; descending pathways and endogenous opioids can turn signals down or up.
- Peripheral and central sensitization make the nervous system more responsive, producing allodynia and hyperalgesia.
- Pain is nociceptive (somatic or visceral), neuropathic or nociplastic; chronic pain lasts or keeps returning for longer than 3 months.
- About one in five people in Canada live with chronic pain, and some groups are disproportionately affected; stigma and uneven access are common.

5.2 Pain Assessment

- Self-report is the reference standard; the 0–10 numeric rating scale is the default, with verbal descriptor and faces scales as alternatives.
- A comprehensive assessment covers pain's features, its effect on function, sleep and mood, the patient's goals and all analgesics and substances used.
- Bias in pain care is documented in Canada; nurses use interpreters, reflect on their own biases and give culturally safe care.
- For adults who cannot self-report, nurses attempt self-report, look for causes, use PAINAD (advanced dementia) or CPOT (critical illness), involve family and reassess after treatment; vital signs alone are not reliable indicators.
- Pain is reassessed after each intervention and documented with the tool, score, function and, with opioids, sedation and breathing.

5.3 Multimodal and Non-Opioid Analgesia

- Multimodal analgesia combines non-opioid drugs and non-drug measures, adding opioids only when needed, to improve relief and reduce opioid harms.
- The Canadian intravenous acetaminophen monograph sets an adult maximum of 4,000 mg in 24 hours for adults of at least 50 kg (3,000 mg may be appropriate with liver risk factors), counting every product and route.
- NSAIDs carry risks of gastrointestinal bleeding, kidney injury, cardiovascular events and bleeding with anticoagulants; the nurse checks kidney function, bleeding and the medication list.
- Gabapentinoids help neuropathic pain but increase the risk of slowed breathing and overdose with opioids.
- Positioning, splinting, early movement, heat and cold, relaxation, distraction, sleep and education are part of every plan.

5.4 Opioids: Safe Use in Hospital

- Opioids relieve pain mainly through mu-opioid receptors in the brain and spinal cord; the same receptors cause sedation, respiratory depression and constipation.
- Key drug points: codeine and tramadol depend on CYP2D6 metabolism, morphine metabolites build up in kidney impairment, and fentanyl patches are never used for acute pain or in opioid-naive patients.
- Increasing sedation usually comes before respiratory depression. The nurse assesses sedation, breathing and SpO2, remembering that SpO2 can look normal on supplemental oxygen.

- At unacceptable sedation, the nurse holds opioids, rouses the patient, escalates, and calls for help and gives naloxone per order when the patient barely responds.
- Opioids are high-alert medications; safeguards include tall man lettering, standard concentrations, independent double checks and smart pumps.
- Tolerance and physical dependence are expected with regular use and are not opioid use disorder; discharge teaching covers short courses, tapering, safe storage, disposal and naloxone.

5.5 Patients Living With Chronic Pain or Opioid Use Disorder

- Patients with chronic pain usually continue their home regimen; long-term opioids are never stopped abruptly, and function-based goals guide care.
- Patients on methadone or buprenorphine continue OAT after the dose is confirmed with the community pharmacy or prescriber.
- OAT prevents withdrawal but does not treat acute pain through the day, so additional multimodal analgesia, and opioids when needed, are usually required.
- Stigma leads to undertreated pain and early departure from hospital; trauma-informed care, person-first language and harm reduction build trust.
- When a patient wants to leave, the nurse explores reasons, escalates, and offers naloxone, harm reduction supplies and follow-up.

Key Terms (55)

acute pain: pain of recent onset, usually from injury, illness, surgery or trauma, that settles as the cause heals

adjuvant analgesic: a drug whose main use is not pain relief but which relieves some types of pain, especially neuropathic pain

allodynia: pain from a stimulus that does not normally cause pain, such as light touch

bowel regimen: a scheduled laxative plan started with regular opioids to prevent constipation.

buprenorphine: a partial mu-opioid agonist used as a first-line opioid agonist treatment, often combined with naloxone or given as an extended-release injection.

capnography: continuous measurement of exhaled carbon dioxide, which detects hypoventilation directly.

central sensitization: increased responsiveness of pain neurons in the spinal cord and brain to normal or weak input

chronic pain: pain that lasts, or keeps returning, for longer than 3 months

chronic postsurgical pain: pain that begins or worsens after surgery and persists beyond healing, at least 3 months after surgery

comprehensive pain assessment: an in-depth assessment of pain's onset, location, quality, intensity, timing, aggravating and relieving factors, effects on function, the person's goals and treatment history

COX-2 inhibitor: an NSAID that acts mainly on the COX-2 form of the enzyme, such as celecoxib

Critical-Care Pain Observation Tool (CPOT): an observational tool scoring four behaviours from 0 to 8 for critically ill adults who cannot self-report

endogenous opioids: the body's own opioid substances, which help reduce pain signals

epidural analgesia: delivery of a local anesthetic, often with an opioid, through a catheter into the epidural space.

Faces Pain Scale–Revised (FPS-R): a self-report scale of six faces scored 0 to 10, developed for children

full agonist: an opioid that fully activates the mu receptor, with effects that keep increasing as the dose rises.

gabapentinoid: gabapentin or pregabalin, anticonvulsants used for neuropathic pain that raise the risk of opioid overdose and slowed breathing when combined with opioids

harm reduction: practical measures that reduce the harms of substance use without requiring the person to stop using.

high-alert medication: a drug that is more likely to cause serious harm when an error occurs, such as an opioid or insulin.

hyperalgesia: more pain than expected from a stimulus that normally causes pain

independent double check: a check in which a second practitioner separately verifies a drug, dose, calculation or pump setting before administration.

methadone: a long-acting full opioid agonist used as a first-line opioid agonist treatment; its long duration of action calls for prolonged monitoring after excess doses.

modulation: the nervous system's ability to increase or decrease pain signals, largely through pathways descending from the brainstem

morphine milligram equivalent (MME): a way of expressing different opioids as an equivalent amount of oral morphine, so that total opioid exposure can be compared.

mu-opioid receptor: the opioid receptor most responsible for pain relief, found in pain-modulating areas of the brain and spinal cord and in the gut wall.

multimodal analgesia: the combined use of medications, procedures and non-drug measures that act on different parts of the pain pathway

naloxone: an opioid antagonist that reverses opioid effects, including respiratory depression.

neuropathic pain: pain resulting from damage to, or disease of, the nerves that carry sensation

nociception: the nervous system's process of detecting and encoding harmful stimuli; it is not the same as pain

nociceptive pain: pain from actual or threatened damage to tissue other than nerves, with a normally working nervous system

nociceptor: a sensory nerve ending that responds to strong heat, pressure or chemical stimuli and converts them into nerve signals

nociplastic pain: pain from altered pain processing without clear tissue damage or nerve disease to explain it

nonsteroidal anti-inflammatory drug (NSAID): a drug that reduces pain and inflammation by blocking cyclooxygenase enzymes

numeric rating scale (NRS): a self-report scale on which the patient rates pain from 0 (no pain) to 10 (worst pain imaginable)

opioid: a drug that acts on the body's opioid receptors to relieve pain; adverse effects include sedation, respiratory depression and constipation.

opioid agonist treatment (OAT): treatment of opioid use disorder with a long-acting opioid, such as methadone or buprenorphine, that prevents withdrawal and cravings.

opioid use disorder (OUD): a problematic pattern of opioid use causing significant problems or distress, diagnosed when at least 2 of 11 criteria occur within a year.

opioid-induced respiratory depression (OIRD): reduced drive and effort to breathe caused by an opioid, leading to carbon dioxide build-up and possibly respiratory arrest; usually preceded by increasing sedation.

opioid-naive: describes a patient who has not been taking opioids regularly.

pain: an unpleasant sensory and emotional experience linked to, or resembling one linked to, actual or potential tissue damage (IASP definition, 2020)

Pain Assessment in Advanced Dementia (PAINAD) scale: an observational tool scoring five behaviours from 0 to 10 for people living with advanced dementia who cannot self-report

partial agonist: a drug, such as buprenorphine, that activates the mu receptor less fully than a full agonist.

patient-controlled analgesia (PCA): a programmable pump that lets a patient give themselves set doses of analgesic, limited by a lockout interval.

PCA by proxy: unauthorized pressing of a PCA button by someone other than the patient, which bypasses the pump's safety check.

perception: the point at which a person becomes aware of pain, involving areas of the brain for sensation, emotion and thinking

peripheral sensitization: increased responsiveness of nerve endings near damaged tissue, so they fire more easily

physical dependence: the body's adaptation to a drug, so that stopping suddenly or reducing the dose quickly causes withdrawal.

referred pain: pain felt in a body region away from the site of the harmful stimulus, such as pain from an internal organ felt elsewhere

sedation scale: a structured tool for rating how drowsy a patient is, such as the Pasero Opioid-induced Sedation Scale outside critical care or the Richmond Agitation-Sedation Scale in intensive care.

somatic pain: nociceptive pain arising in skin, muscle, bone or joints, often well localized

tolerance: the need for more of a drug to produce the same effect after repeated use.

transduction: the conversion of a harmful stimulus into an electrical signal by nociceptors

transmission: the movement of pain signals from the periphery through the spinal cord to the brain

verbal descriptor scale: a self-report scale on which the patient chooses a word, such as mild, moderate or severe, to describe pain intensity

visceral pain: nociceptive pain arising in internal organs, often harder to locate than somatic pain

Licensure Review & Clinical Judgment Questions (30)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mr. Ernest Pelletier (Questions 1–4): Mr. Ernest Pelletier, 84, lives with advanced dementia and has osteoarthritis of both knees. He was admitted to a medical unit in an Ontario hospital 2 days ago with pneumonia. He speaks only a few words and cannot use a number scale. An RPN is caring for him on the day shift.

1. [CORE] The RPN wants to assess Mr. Pelletier for pain. Which approach is most appropriate?

a. Ask him to rate his pain from 0 to 10 and record the number he says

b. Use the Pain Assessment in Advanced Dementia (PAINAD) scale while helping him turn and wash

c. Use the Critical-Care Pain Observation Tool (CPOT) while he rests quietly in bed between care activities

d. Record his heart rate and blood pressure as the main indicators of pain

Answer: b — PAINAD is designed for people living with advanced dementia who cannot self-report, and observing during care such as turning reveals more than observing at rest (section 5.2). Option a is wrong because he cannot reliably use a number scale; a number given without understanding is not a valid self-report. Option c is wrong because the CPOT is for critically ill adults, and observing only at rest can miss pain. Option d is wrong because vital signs change for many reasons and are not reliable indicators of pain.

2. [CORE] Which finding most strongly suggests that Mr. Pelletier is in pain?

a. He sleeps for 2 hours after lunch

b. His face looks flushed compared with yesterday

c. His heart rate is 92 beats per minute and his temperature is 38.1 °C

d. He grimaces and guards his knees when his legs are moved

Answer: d — Grimacing and guarding a painful area when it is moved are behavioural cues of pain that can be seen on any skin tone (section 5.2). Option a is wrong because sleep does not rule out pain. Option b is wrong because colour changes are unreliable, can be hard to see on darker skin and may reflect fever. Option c is wrong because a raised heart rate and temperature may be explained by his pneumonia, and vital signs alone are not reliable signs of pain.

3. [CORE] Mr. Pelletier's PAINAD score is 6 during morning care. The RPN gives his prescribed analgesic. What should the RPN do next?

a. Repeat PAINAD during movement once the drug should be working, and document the result

b. Reassess at the end of the shift using a 0 to 10 numeric rating scale

c. Document the dose given and reassess only if his family reports that he seems uncomfortable

d. Wait until the next scheduled dose and then repeat the PAINAD score

Answer: a — Pain is reassessed after each intervention, at the interval set by policy, with the same tool and during the activity that caused pain, and the result is documented (section 5.2). Option b is wrong because the timing is too late and he cannot use a numeric scale. Option c is wrong because reassessment is the nurse's responsibility; family input adds to it but does not replace it. Option d is wrong because waiting until the next dose leaves the effect of this dose unknown.

4. [CORE] The next afternoon, Mr. Pelletier's PAINAD score rises from 2 to 8. He is newly unable to bear weight on his right leg after being found sitting on the floor beside his bed. What is the RPN's priority action?

a. Give an extra dose of the as-needed analgesic now and recheck his PAINAD score at the end of the shift

b. Reassure him and his daughter that his arthritis often flares in hospital

c. Keep him in bed, assess the leg and promptly consult the RN and the prescriber

d. Record the score and ask the next shift to repeat the PAINAD assessment

Answer: c — A sudden rise in pain score, inability to bear weight and a possible fall suggest a new injury, such as a fracture, that needs urgent assessment. An RPN who notices a change like this acts at once, consults the RN as the patient's needs change, and informs the prescriber (section 5.2; Chapter 1, section 1.3). Option a is wrong because treating the score without finding the cause could hide a serious injury. Option b is wrong because it assumes a cause without assessment. Option d is wrong because it delays escalation.

5. [CORE] A nurse is reviewing the medication list of a 72-year-old patient before giving a prescribed dose of naproxen. Which factors increase this patient's risk of harm from an NSAID? Select all that apply.

a. History of a bleeding stomach ulcer

b. Daily use of a diuretic and an ACE inhibitor

c. Taking warfarin

d. Daily acetaminophen use within the recommended limit

e. Vomiting and poor fluid intake for 2 days

f. Normal kidney function on recent blood work

Answer: a, b, c, e — A past ulcer or bleed raises the risk of gastrointestinal bleeding; a diuretic and an ACE inhibitor, and dehydration, raise the risk of kidney injury; and anticoagulants such as warfarin raise the risk of serious bleeding (section 5.3). Option d is wrong because acetaminophen within the daily limit does not add to NSAID risks. Option f is wrong because normal kidney function lowers, rather than raises, the risk of kidney injury.

6. [CORE] A patient who weighs 70 kg receives scheduled acetaminophen after surgery. At home he takes a cold and flu medicine and a prescription tablet that combines an opioid with acetaminophen. Which teaching is most important?

a. Acetaminophen is safe at any dose because it is sold without a prescription

b. Acetaminophen should be taken only on an empty stomach

c. The daily maximum counts acetaminophen from every product, so he should check all labels

d. Combination products contain too little acetaminophen to add meaningfully to his daily total

Answer: c — The maximum daily dose includes acetaminophen from all products and routes, and most liver injury involves exceeding that limit, often with more than one product (section 5.3). Option a is wrong because acetaminophen can cause serious liver injury. Option b is wrong because no such rule applies; the key risk is total dose. Option d is wrong because combination products can add substantially to the total.

7. [CORE] A patient with diabetes describes burning, electric pain in both feet that is worse at night and says the bed sheets hurt to touch. Which type of pain is this most likely to be?

a. Neuropathic pain
b. Visceral pain
c. Referred pain
d. Somatic nociceptive pain

Answer: a — Burning, electric pain and pain from light touch (allodynia) are typical of neuropathic pain, which results from disease of the nerves carrying sensation, as in diabetic neuropathy (section 5.1). Option b is wrong because visceral pain comes from internal organs, not from nerve disease. Option c is wrong because referred pain is pain felt away from its source, such as pain from an internal organ felt elsewhere in the body. Option d is wrong because somatic pain arises from damage to skin, muscle, bone or joints, not from nerve disease.

8. [CORE] An RPN is caring for a patient on day 2 after bowel surgery whose pain has been well controlled. The patient now reports new, severe abdominal pain rated 9 out of 10 that is not relieved by the prescribed analgesic, and the abdomen is distended. Which action is most appropriate for the RPN?

a. Give a second dose of the as-needed analgesic earlier than ordered
b. Apply a heating pad to the abdomen and reassess in 2 hours
c. Encourage the patient to walk in the hallway to relieve gas pain
d. Stay with the patient, complete a focused assessment, and consult the RN and prescriber promptly

Answer: d — New, severe, unrelieved pain with abdominal distension after surgery is a change in condition that may signal a complication. Every nurse who notices deterioration acts and escalates; the RPN consults the RN as the patient's needs change and informs the prescriber, following employer policy (section 5.2; Chapter 1, section 1.3). Option a is wrong because giving a dose outside the order is not within the nurse's authority and could hide a complication. Option b is wrong because heat delays assessment of a possible complication. Option c is wrong because it assumes a minor cause without assessment.

9. [CORE] A patient says, "My pain is 8 out of 10," but is laughing with visitors. Which response by the nurse is best?

a. Record a lower score that matches the patient's behaviour
b. Accept the rating, ask what the pain stops them doing, and offer treatment
c. Tell the patient that the pain must be lower than 8 because they are laughing
d. Ask the visitors to estimate how much pain the patient seems to be having

Answer: b — The patient's self-report is the reference standard and deserves respect; people cope with pain in different ways, and function-based questions guide treatment (sections 5.1 and 5.2). Option a is wrong because the nurse records the patient's report, not the nurse's impression. Option c is wrong because it dismisses the report and damages trust. Option d is wrong because proxy reports are used only when a patient cannot self-report.

Case: Mr. Lionel Gagnon (Questions 10–15): Mr. Lionel Gagnon, 68, had an open bowel resection under general anesthesia yesterday afternoon. He has obstructive sleep apnea and uses CPAP at home, but his machine is still at home. His weight is 112 kg, with a body mass index of 38. He receives hydromorphone by PCA with no basal infusion, and gabapentin was started this morning. He did not take opioids before admission. At 2200 he was fully awake, with a respiratory rate of 18, SpO2 96% on 2 L/min of oxygen by nasal cannula, and pain 4 out of 10. At 0200 the nurse finds him drifting off in the middle of answering questions. His respiratory rate is 10 and shallow, with loud snoring and brief pauses. SpO2 is 94% on 2 L/min. His temperature is 37.4 °C, heart rate 84 and blood pressure 128/74 mm Hg. The PCA history shows he pressed the button 14 times in the past 4 hours. His abdominal dressing is dry, and he rates his pain 3 out of 10 when roused.

10. [CORE] The nurse reviews Mr. Gagnon's 0200 findings. Which findings need immediate follow-up? Select all that apply.

a. Drifts off in the middle of answering questions
b. Respiratory rate of 10 and shallow
c. Temperature 37.4 °C
d. Loud snoring with brief pauses in breathing
e. Dry abdominal dressing
f. Pain 3 out of 10 when roused

Answer: a, b, d — Falling asleep mid-conversation is advancing sedation, the earliest sign of opioid-induced respiratory depression (a). A slow, shallow respiratory rate (b) and snoring with pauses (d) suggest hypoventilation and airway obstruction (section 5.4, Table 5.4). A temperature of 37.4 °C (c) is not a fever and is common the day after surgery. A dry dressing (e) is expected. Pain of 3 out of 10 (f) shows the pain is controlled; it is not a concern in itself.

11. [CORE] The nurse analyzes the cues. Which combination of factors best explains Mr. Gagnon's risk of opioid-induced respiratory depression?

a. A normal blood pressure, a normal heart rate and a pain score of only 3 out of 10 when roused
b. Use of PCA without a basal infusion, together with a dry and intact abdominal surgical dressing
c. Supplemental oxygen at 2 L/min by nasal cannula and a temperature of 37.4 °C overnight
d. Untreated sleep apnea, obesity, age, abdominal surgery, no prior opioids and added gabapentin

Answer: d — Sleep apnea, obesity, older age, recent abdominal surgery, being opioid-naive and a gabapentinoid added to an opioid are all recognized risk factors, and they add together (d) (section 5.4). Normal blood pressure and heart rate do not raise risk (a). PCA without a basal infusion is the safer setup, and the dressing is unrelated (b). Oxygen does not cause respiratory depression, though it can mask it, and the temperature is unrelated (c).

12. [CORE] Which problem is the priority for Mr. Gagnon at 0200?

a. Acute postoperative pain that is not controlled by the current PCA settings
b. Postoperative infection at the surgical site
c. Advancing opioid-induced sedation with hypoventilation
d. Fluid volume deficit after bowel surgery

Answer: c — Advancing sedation, slow shallow breathing and pauses point to opioid-induced sedation and respiratory depression, which can progress to respiratory arrest (c) (section 5.4). His pain is controlled at 3 out of 10 (a). There is no fever, and the dressing is dry (b). His heart rate and blood pressure are normal, and nothing suggests hypovolemia (d).

13. [CORE] Which actions should the nurse plan for Mr. Gagnon now? Select all that apply.

a. Pause PCA doses according to policy and remove the button from his reach
b. Rouse him fully and coach him to take deep breaths
c. Increase oxygen to 6 L/min and reassess in 1 hour
d. Notify the RN or prescriber immediately with the findings
e. Ask his daughter to press the PCA button if he seems uncomfortable while asleep
f. Begin continuous SpO2 monitoring, or capnography where available, as policy allows
g. Give a PRN dose of lorazepam to help him sleep

Answer: a, b, d, f — Holding further opioid (a), waking him and coaching deep breaths (b), escalating at once (d) and closer monitoring (f) match the actions for unacceptable sedation (section 5.4, Table 5.4). Raising oxygen and waiting an hour (c) can mask rising carbon dioxide while the patient deteriorates. Having a family member press the button (e) is PCA by proxy and bypasses the safety check. A benzodiazepine (g) would deepen sedation and respiratory depression.

14. [CORE] At 0215, Mr. Gagnon responds only to a firm shake and his respiratory rate is 6. What should the nurse do first?

a. Stay with him, call for help and stimulate him while supporting his airway
b. Leave the room to find the prescriber and ask for a naloxone order
c. Remove his oxygen to see what his SpO2 is on room air
d. Document the findings in detail, then recheck his sedation and breathing in 15 minutes

Answer: a — Minimal response with a respiratory rate of 6 is an emergency. The nurse stays, calls for help (rapid response per policy), stimulates and supports the airway and breathing, then gives naloxone per order or medical directive (a) (section 5.4). Leaving the patient alone (b) delays help. Removing oxygen (c) worsens hypoxemia. Waiting 15 minutes (d) risks respiratory arrest.

15. [CORE] Naloxone is given according to the medical directive, and the PCA remains paused. Which findings 30 minutes later show that the interventions have been effective? Select all that apply.

a. He is awake and speaks in full sentences
b. Respiratory rate 15, regular and of normal depth
c. He falls asleep while the nurse is asking a question
d. SpO2 96% on 2 L/min, with no snoring or pauses
e. He rates his pain 9 out of 10 and is restless
f. He wakes easily to voice and stays awake

Answer: a, b, d, f — Being awake and conversing (a), a normal respiratory rate and depth (b), good SpO2 without obstructed breathing (d), and waking easily and staying awake (f) show that sedation and breathing have improved (section 5.4, Table 5.4). Falling asleep mid-question (c) means sedation persists and needs further action. Severe pain and restlessness (e) suggest the naloxone also reversed his analgesia; this needs reassessment and a new plan, likely with more non-opioid analgesia, not a return to the old plan.

16. [CORE] An RPN is caring for a postoperative patient whose hydromorphone PCA is managed by an RN, as hospital policy requires. The RPN finds the patient dozing off mid-sentence, with a respiratory rate of 10. What is the RPN's best action?

a. Document the findings and mention them to the RN at the next break

b. Wake the patient, check breathing and SpO2, and notify the RN immediately

c. Wait for the RN to complete the next scheduled PCA assessment and report then

d. Increase the PCA lockout interval on the pump

Answer: b — Every nurse who notices deterioration acts at once and escalates. The RPN wakes the patient, assesses breathing and oxygenation, and consults the RN right away (b) (section 5.4, Scope in Practice box). Delaying the report (a, c) risks progression to respiratory arrest. Changing pump settings (d) is outside this RPN's role under the policy and requires an order.

17. [CORE] A new graduate RPN asks about RPN practice with opioids in an Ontario hospital. Which response is accurate?

a. "Only RNs may give controlled substances; RPNs give non-opioid analgesics."

b. "CNO requires that RPNs care only for patients who are stable and predictable."

c. "RPNs give opioids on an order or medical directive. Whether they manage PCA or epidurals depends on employer policy, their education and the patient's needs."

d. "RPNs may start an opioid on their own judgment if the patient's pain is severe."

Answer: c — Authority, competence and context determine practice. RPNs give opioids on an order or medical directive, and employer policy, education and patient needs shape PCA and epidural care (c) (section 5.4, Scope in Practice box). RPNs are not barred from giving controlled substances (a). Assigning by stability is a common employer practice, not a CNO rule (b). Nurses do not initiate opioids in a public hospital (d).

18. [CORE] A patient started regular oxycodone yesterday after a hip fracture repair. Which order should the nurse expect to accompany it?

a. A scheduled stimulant laxative, osmotic laxative or both

b. A fluid restriction of 1 L per day to prevent urinary retention

c. A fibre supplement alone, given only if no bowel movement for 5 days

d. An antidiarrheal to be given as needed for any loose stools

Answer: a — Nearly everyone on regular opioids becomes constipated, and laxatives are first-line, so a scheduled bowel regimen usually starts with regular opioids (a) (section 5.4). Fluid restriction (b) would worsen constipation and does not prevent urinary retention. Waiting 5 days and relying on fibre alone (c) lets constipation become established, and fibre without enough fluid can make it worse in a less mobile patient. An antidiarrheal (d) would worsen opioid-induced constipation.

19. [CORE] A patient has taken hydromorphone for 3 weeks after major trauma. He now needs a slightly higher dose for the same relief, and he becomes sweaty and achy when a dose is late. He has no craving and takes the drug only as prescribed. How should the nurse interpret these findings?

a. Opioid use disorder, because he now needs more of the drug

b. An allergic reaction to hydromorphone that causes sweating

c. Drug-seeking behaviour that should be reported to the prescriber

d. Tolerance and physical dependence, both expected with regular use

Answer: d — Needing more drug for the same effect is tolerance, and withdrawal symptoms when a dose is late reflect physical dependence. Both are expected with regular use (d) (section 5.4). Under the diagnostic criteria, needing more of the drug (tolerance) and withdrawal do not count toward OUD when opioids are taken only as medically supervised, and he shows no other criteria (a). Sweating and aching are withdrawal symptoms, not allergy (b). "Drug-seeking" is a stigmatizing label, and his behaviour does not warrant it (c).

20. [CORE] A patient is being discharged after an appendectomy with a 3-day supply of an immediate-release opioid. Which statements by the patient show understanding of the teaching? Select all that apply.

a. "I'll take acetaminophen regularly and use the opioid only if I still need it."

b. "I'll keep the pills in my kitchen drawer so they're easy to find."

c. "I'll bring any leftover pills back to the pharmacy."

d. "A glass of wine at night will help me sleep while I'm taking these."

e. "My wife will call 9-1-1 if she can't wake me."

f. "If the pain gets worse, I'll take two pills at a time."

Answer: a, c, e — Using non-opioid analgesia first (a), returning unused opioids to a pharmacy (c) and knowing that unrousable sleepiness is an emergency (e) are correct (section 5.4, Patient Education box). Opioids should be locked and out of sight, not easy to find (b). Alcohol adds to sedation and respiratory depression (d). Doubling doses (f) is unsafe; worsening pain needs a call to the prescriber.

21. [CORE] A patient on methadone for opioid use disorder is admitted with a fractured femur. Which plan is most appropriate?

a. Confirm the dose with the pharmacy, continue methadone, and add analgesics, including opioids

b. Stop the methadone, because the opioids ordered for the fracture pain will prevent withdrawal

c. Continue the methadone and manage the fracture pain only with ice, splinting and positioning

d. Double the methadone dose to treat the pain, and avoid giving any other opioid in hospital

Answer: a — OAT continues in hospital once the dose is confirmed. It prevents withdrawal but does not treat acute pain through the day, so additional analgesia, including opioids when needed, is usually required (a) (section 5.5). Stopping methadone (b) causes withdrawal and destabilizes recovery. Non-drug measures alone (c) undertreat a fracture. The prescriber, not a fixed rule, sets methadone doses, and doubling them (d) risks dangerous accumulation.

22. [CORE] Which handover statement about the patient in bed 4 uses non-stigmatizing language?

a. "She's an addict, but she has been clean for a year now."

b. "She's a drug seeker; she keeps asking for her PRN early."

c. "She's a heroin abuser who is now on methadone."

d. "She has opioid use disorder and takes methadone; she asked for her PRN 30 minutes early with pain at 8 out of 10."

Answer: d — Person-first, medically accurate language and objective description of behaviour (d) avoid stigma (section 5.4). "Addict" and "clean" (a), "drug seeker" (b) and "abuser" (c) are labels that Health Canada advises against, because they contribute to poorer care and lead people to avoid seeking it.

23. [CORE] A prescriber's order reads "fentanyl patch for postoperative pain" for an opioid-naive patient after knee surgery. What should the nurse do?

a. Apply the patch and monitor sedation every 4 hours

b. Apply the patch and cover it with a heating pad to speed absorption

c. Hold the patch and clarify the order with the prescriber

d. Cut the patch in half to reduce the dose

Answer: c — Fentanyl patches are contraindicated for acute or perioperative pain and in opioid-naive patients at any strength, so the nurse clarifies the order (c) (section 5.4, Table 5.3). Applying it (a) risks serious respiratory depression. Heat increases fentanyl absorption and is dangerous (b). Patches are not cut (d).

24. [CORE] Why does the nurse watch a patient who receives codeine for oversedation, even when the patient takes a usual dose?

a. Codeine is converted to morphine only in people who have kidney disease

b. Some people convert codeine to morphine unusually fast and completely

c. Codeine causes oversedation only when it is combined with acetaminophen

d. Codeine has no effect on breathing, so sedation is the only risk

Answer: b — Codeine works after the liver enzyme CYP2D6 converts it to morphine, and ultra-rapid metabolizers can form enough morphine to overdose on usual doses (b) (section 5.4). This conversion happens in everyone, not only in people with kidney disease (a). The overdose risk comes from the morphine formed, with or without acetaminophen (c). Like all opioids, codeine can slow breathing (d).

25. [CORE] A patient receiving regular morphine has a creatinine that has doubled since admission. On day 3 the patient is increasingly drowsy, although the dose has not changed. What is the most likely explanation?

a. Tolerance has developed, so the same dose now has a stronger effect

b. Opioid use disorder has developed after three days of regular use

c. An allergic reaction to morphine is developing and is causing the drowsiness

d. An active morphine metabolite is building up as kidney function falls

Answer: d — Morphine-6-glucuronide is active and is excreted by the kidneys; it builds up when kidney function falls, increasing sedation over days (d) (section 5.4). Tolerance (a) reduces, not increases, the effect of the same dose. Increasing sedation on an unchanged dose is not a sign of OUD (b). Drowsiness is not an allergic reaction (c).

26. [CORE] A patient receiving IV hydromorphone is on 4 L/min of oxygen by nasal cannula. SpO2 is 98%, but the patient is hard to rouse and breathes 8 times a minute. Which statement best explains the nurse's concern?

a. Oxygen can keep SpO2 normal while carbon dioxide builds up from slow breathing

b. An SpO2 of 98% on oxygen confirms that the patient's breathing is adequate

c. The pulse oximeter is probably malfunctioning and should be replaced before anything else

d. The oxygen flow is suppressing the drive to breathe and should be stopped

Answer: a — With supplemental oxygen, SpO2 can stay normal while hypoventilation lets carbon dioxide build up, so sedation and respiratory rate are the key cues and capnography can detect the problem directly (a) (section 5.4). A normal SpO2 does not prove adequate ventilation (b). Replacing the probe (c) delays action on a clear clinical problem. The opioid, not the oxygen, is causing the slow breathing, and stopping oxygen would worsen hypoxemia (d).

27. [RN] A patient on hydromorphone PCA is pressing the button often, and the pump records many attempts but fewer doses delivered. What explains this?

a. The pump is malfunctioning and is not delivering the programmed demand doses at all

b. A basal infusion is running and is replacing the demand doses he requests

c. The lockout interval blocks doses until the previous dose has had time to act

d. The patient is receiving doses each time the button is pressed

Answer: c — The lockout interval prevents another demand dose until the last one has had time to work, so attempts can exceed delivered doses (c) (section 5.4, Going Deeper box). The pattern is expected and does not mean the pump is faulty (a). A basal infusion runs continuously and does not replace demand doses (b). If every press delivered a dose (d), attempts would equal doses. Many attempts can signal uncontrolled pain, and the nurse reassesses.

28. [RN] A patient has a thoracic epidural infusion and received enoxaparin as ordered. Four hours after the catheter is removed, the patient reports new numbness and weakness in both legs. What is the nurse's priority?

a. Report the findings immediately as a possible spinal or epidural hematoma

b. Reposition the patient, elevate the legs and reassess sensation and strength in 2 hours

c. Apply warm packs to the legs

d. Give the next dose of enoxaparin as scheduled

Answer: a — New numbness or weakness after epidural catheter use in a patient receiving an anticoagulant suggests a spinal or epidural hematoma, which can cause permanent paralysis and needs urgent diagnosis and treatment (a) (section 5.4, Going Deeper box). Waiting (b) delays treatment. Warm packs (c) do not address the cause. Another anticoagulant dose (d) could worsen bleeding and should be held pending urgent review.

29. [RN] A nursing student asks what morphine milligram equivalents (MME) are used for. Which answer is accurate?

a. They let nurses convert a patient from one opioid to another at the bedside

b. They state each opioid as an equivalent amount of oral morphine, to compare total exposure

c. They measure how sedated a patient is

d. They set one maximum safe daily dose for each opioid that applies to every adult patient

Answer: b — MME express different opioids in morphine terms so that total opioid exposure can be compared, for example against guideline thresholds (b) (section 5.4, Going Deeper box). Conversions are done by prescribers and pharmacists, not nurses at the bedside (a). Sedation is measured with a sedation scale (c). Thresholds guide prescribing but do not set a safe maximum for every patient (d).

30. [RN] A visitor tells the nurse, "When Dad moans in his sleep, I press his pain button so he doesn't wake up hurting." What is the nurse's best response?

a. "That's helpful; it keeps his pain under control."

b. "Only your dad should press the button. When he is too sleepy to press it, that is a safety signal that he has had enough medicine."

c. "Please press it no more than once an hour, so he doesn't get too much medicine."

d. "It's fine to press it, as long as his breathing seems normal and he isn't snoring."

Answer: b — PCA by proxy bypasses the safety check that a drowsy patient stops pressing the button, and it has caused serious harm. Only the patient presses the button (b) (section 5.4, Going Deeper box). Praising the practice (a) or limiting how often it is done (c) still allows proxy dosing. Family members cannot reliably judge breathing or sedation (d), and the nurse reassesses the patient's pain and sedation.

References

Afenigus, A. D. (2024). Evaluating pain in non-verbal critical care patients: A narrative review of the critical care pain observation tool and its clinical applications. *Frontiers in Pain Research*, *5*, Article 1481085. https://doi.org/10.3389/fpain.2024.1481085

Alford, D. P., Compton, P., & Samet, J. H. (2006). Acute pain management for patients receiving maintenance methadone or buprenorphine therapy. *Annals of Internal Medicine, 144*(2), 127–134. https://doi.org/10.7326/0003-4819-144-2-200601170-00010

B. Braun of Canada. (2023). *Acetaminophen Injection, 10 mg/mL* [Product monograph]. https://pdf.hres.ca/dpd_pm/00069718.PDF

BGP Pharma ULC. (2015). *Kadian (morphine sulphate sustained release capsules) product monograph*. https://pdf.hres.ca/dpd_pm/00031792.PDF

Busse, J. W., Craigie, S., Juurlink, D. N., Buckley, D. N., Wang, L., Couban, R. J., Agoritsas, T., Akl, E. A., Carrasco-Labra, A., Cooper, L., Cull, C., da Costa, B. R., Frank, J. W., Grant, G., Iorio, A., Persaud, N., Stern, S., Tugwell, P., Vandvik, P. O., & Guyatt, G. H. (2017). Guideline for opioid therapy and chronic noncancer pain. *CMAJ, 189*(18), E659–E666. https://doi.org/10.1503/cmaj.170363

Canadian Pain Task Force. (2019). *Canadian Pain Task Force report: June 2019*. Health Canada. https://www.canada.ca/en/health-canada/corporate/about-health-canada/public-engagement/external-advisory-bodies/canadian-pain-task-force/report-2019.html

Canadian Pain Task Force. (2021). *Canadian Pain Task Force report: March 2021. An action plan for pain in Canada*. Health Canada. https://www.canada.ca/en/health-canada/corporate/about-health-canada/public-engagement/external-advisory-bodies/canadian-pain-task-force/report-2021.html

Centers for Disease Control and Prevention. (2024). *Opioid use disorder: Diagnosis*. https://www.cdc.gov/overdose-prevention/hcp/clinical-care/opioid-use-disorder-diagnosis.html

Chincholkar, M. (2020). Gabapentinoids: Pharmacokinetics, pharmacodynamics and considerations for clinical practice. *British Journal of Pain, 14*(2), 104–114. https://doi.org/10.1177/2049463720912496

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026, October 14). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

College of Physicians & Surgeons of Manitoba. (2023). *Recommendations for the in-hospital care of individuals with opioid use disorder* (Manitoba opioid agonist therapy recommended practice manual, section 1.8). https://cpsm.mb.ca/assets/PrescribingPracticesProgram/In%20Hospital%20Care%20Issues%20Section.pdf

Colloca, L., Ludman, T., Bouhassira, D., Baron, R., Dickenson, A. H., Yarnitsky, D., Freeman, R., Truini, A., Attal, N., Finnerup, N. B., Eccleston, C., Kalso, E., Bennett, D. L., Dworkin, R. H., & Raja, S. N. (2017). Neuropathic pain. *Nature Reviews Disease Primers*, *3*, Article 17002. https://doi.org/10.1038/nrdp.2017.2

Crockett, S. D., Greer, K. B., Heidelbaugh, J. J., Falck-Ytter, Y., Hanson, B. J., Sultan, S., & American Gastroenterological Association Institute Clinical Guidelines Committee. (2019). American Gastroenterological Association Institute guideline on the medical management of opioid-induced constipation. *Gastroenterology, 156*(1), 218–226. https://doi.org/10.1053/j.gastro.2018.07.016

Fresenius Kabi Canada. (2019). *Morphine sulfate injection USP (Simplist) product monograph*. https://pdf.hres.ca/dpd_pm/00051159.PDF

GlaxoSmithKline Consumer Healthcare ULC. (2025). *Advil tablets and caplets (ibuprofen tablets USP, 200 mg)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00078327.PDF

Gélinas, C., Fillion, L., Puntillo, K. A., Viens, C., & Fortier, M. (2006). Validation of the Critical-Care Pain Observation Tool in adult patients. *American Journal of Critical Care*, *15*(4), 420–427. https://doi.org/10.4037/ajcc2006.15.4.420

Gélinas, C., Harel, F., Fillion, L., Puntillo, K. A., & Johnston, C. C. (2009). Sensitivity and specificity of the Critical-Care Pain Observation Tool for the detection of pain in intubated adults after cardiac surgery. *Journal of Pain and Symptom Management*, *37*(1), 58–67. https://doi.org/10.1016/j.jpainsymman.2007.12.022

Health Canada. (2013, June 6). *Health Canada's review recommends codeine only be used in patients aged 12 and over*. https://recalls-rappels.canada.ca/en/alert-recall/health-canada-s-review-recommends-codeine-only-be-used-patients-aged-12-and-over

Health Canada. (2017). *Health product InfoWatch – February 2017: Tramadol-containing products*. https://www.canada.ca/en/health-canada/services/drugs-health-products/medeffect-canada/health-product-infowatch/health-product-infowatch-february-2017-4.html

Health Canada. (2018, October 1). *Notice to stakeholders – Opioid warning sticker and patient information handout requirements come into force on October 23, 2018*. https://www.canada.ca/en/health-canada/services/drugs-health-products/drug-products/announcements/opioids-warning-sticker-patient-handout.html

Health Canada. (2019, September 17). *Health Canada advises Canadians to exercise caution when taking gabapentin or pregabalin with opioids* [Advisory]. https://canadiensensante.gc.ca/recall-alert-rappel-avis/hc-sc/2019/71003a-eng.php

Health Canada. (2022). *Stigma: Why words matter* [Fact sheet]. https://www.canada.ca/en/health-canada/services/publications/healthy-living/stigma-why-words-matter-fact-sheet.html

Health Quality Ontario. (2018). *Opioid prescribing for acute pain: Care for people 15 years of age and older* [Quality standard]. https://ontariohealth.ca/clinical/quality-standards

Herr, K., Coyne, P. J., Ely, E., Gélinas, C., & Manworren, R. C. B. (2019). Pain assessment in the patient unable to self-report: Clinical practice recommendations in support of the ASPMN 2019 position statement. *Pain Management Nursing*, *20*(5), 404–417. https://doi.org/10.1016/j.pmn.2019.07.005

Hicks, C. L., von Baeyer, C. L., Spafford, P. A., van Korlaar, I., & Goodenough, B. (2001). The Faces Pain Scale–Revised: Toward a common metric in pediatric pain measurement. *Pain*, *93*(2), 173–183. https://doi.org/10.1016/S0304-3959(01)00314-1

Indivior UK. (2025). *Sublocade (buprenorphine extended-release injection) product monograph*. https://pdf.hres.ca/dpd_pm/00082639.PDF

Institute for Safe Medication Practices Canada. (2013). HYDROmorphone remains a high-alert drug. *Ontario Critical Incident Learning, 2*. https://www.ismp-canada.org/download/ocil/ISMPCONCIL2013-2_HYDROmorphoneRemainsAHighAlertDrug.pdf

Institute for Safe Medication Practices Canada. (2014). *Opioid-related deaths associated with medication incidents: Findings of a multi-incident analysis*. https://www.ismp-canada.org/download/OpioidStewardship/Opioid-Related_Deaths_Associated_with_Medication_Incidents_Nov2014.pdf

Institute for Safe Medication Practices Canada. (2016). *Frequently asked questions (FAQs): Independent double checks*. https://www.ismp-canada.org/download/ocil/FAQ-IDC-high-risk-meds-1Nurse.pdf

Institute for Safe Medication Practices Canada. (n.d.). *High-alert medications*. https://www.ismp-canada.org/LTC/high-alert-medications.htm

International Association for the Study of Pain. (n.d.-a). *Faces Pain Scale – Revised (FPS-R)*. Retrieved October 25, 2026, from https://www.iasp-pain.org/resources/faces-pain-scale-revised/

International Association for the Study of Pain. (n.d.-b). *Terminology*. Retrieved October 25, 2026, from https://www.iasp-pain.org/resources/terminology/

Jin, Q., Chang, Y., Lu, C., Chen, L., & Wang, Y. (2023). Referred pain: Characteristics, possible mechanisms, and clinical management. *Frontiers in Neurology*, *14*, Article 1104817. https://doi.org/10.3389/fneur.2023.1104817

Jungquist, C. R., Quinlan-Colwell, A., Vallerand, A., Carlisle, H. L., Cooney, M., Dempsey, S. J., Dunwoody, D., Maly, A., Meloche, K., Meyers, A., Sawyer, J., Singh, N., Sullivan, D., Watson, C., & Polomano, R. C. (2020). American Society for Pain Management Nursing guidelines on monitoring for opioid-induced advancing sedation and respiratory depression: Revisions. *Pain Management Nursing, 21*(1), 7–25. https://doi.org/10.1016/j.pmn.2019.06.007

Mayer, S., Langheimer, V., Nolan, S., Boyd, J., Small, W., & McNeil, R. (2023). Emergency department experiences of people who use drugs who left or were discharged from hospital against medical advice. *PLoS ONE, 18*(2), Article e0282215. https://doi.org/10.1371/journal.pone.0282215

Mukwende, M., Tamony, P., & Turner, M. (2020). *Mind the gap: A handbook of clinical signs in Black and Brown skin*. St George's, University of London. https://iiif.wellcomecollection.org/file/b32878382_0001.pdf

Nora Pharma. (2026). *NRA-Celecoxib (celecoxib capsules)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00084512.PDF

Ontario Ministry of Health. (2025). *Updated Executive Officer notice: Ontario Naloxone Program for Pharmacies*. https://www.ontario.ca/files/2025-05/moh-executive-officer-notice-en-2025-05-07.pdf

Ossipov, M. H., Dussor, G. O., & Porreca, F. (2010). Central modulation of pain. *Journal of Clinical Investigation*, *120*(11), 3779–3787. https://doi.org/10.1172/JCI43766

Pasero, C. (2009). Assessment of sedation during opioid administration for pain management. *Journal of PeriAnesthesia Nursing, 24*(3), 186–190. https://doi.org/10.1016/j.jopan.2009.03.005

Purdue Pharma. (2023). *Dilaudid (HYDROmorphone hydrochloride) product monograph*. https://pdf.hres.ca/dpd_pm/00072218.PDF

Raja, S. N., Carr, D. B., Cohen, M., Finnerup, N. B., Flor, H., Gibson, S., Keefe, F. J., Mogil, J. S., Ringkamp, M., Sluka, K. A., Song, X.-J., Stevens, B., Sullivan, M. D., Tutelman, P. R., Ushida, T., & Vader, K. (2020). The revised International Association for the Study of Pain definition of pain: Concepts, challenges, and compromises. *Pain*, *161*(9), 1976–1982. https://doi.org/10.1097/j.pain.0000000000001939

Registered Nurses' Association of Ontario. (2025). *Pain: Prevention, assessment and management* (4th ed.). https://rnao.ca/node/2828

Resnick, B., Van Haitsma, K., Kolanowski, A., Galik, E., Boltz, M., Ellis, J., Behrens, L., Eshraghi, K., Renn, C. L., & Dorsey, S. G. (2021). Invariance of the PAINAD scale between the Black and White residents living with dementia. *Frontiers in Pain Research*, *2*, Article 757654. https://doi.org/10.3389/fpain.2021.757654

Sandoz Canada. (2025). *Supeudol (oxycodone hydrochloride tablets) product monograph*. https://pdf.hres.ca/dpd_pm/00080231.PDF

sanofi-aventis Canada. (2021). *Lovenox (enoxaparin sodium injection) product monograph*. https://pdf.hres.ca/dpd_pm/00062844.PDF

Schug, S. A., Lavand'homme, P., Barke, A., Korwisi, B., Rief, W., Treede, R.-D., & IASP Taskforce for the Classification of Chronic Pain. (2019). The IASP classification of chronic pain for ICD-11: Chronic postsurgical or posttraumatic pain. *Pain*, *160*(1), 45–52. https://doi.org/10.1097/j.pain.0000000000001413

Teva Canada. (2022). *Teva-Fentanyl (fentanyl transdermal system) product monograph*. https://pdf.hres.ca/dpd_pm/00066268.PDF

The Joint Commission. (2004). Patient controlled analgesia by proxy. *Sentinel Event Alert, 33*. https://psnet.ahrq.gov/issue/patient-controlled-analgesia-proxy

The Joint Commission. (2012). Safe use of opioids in hospitals. *Sentinel Event Alert, 49*. https://opioidhalo.masimo.com/siteassets/us/documents/pdf/sea_49_opioids_8_2_12.pdf

Treede, R.-D., Rief, W., Barke, A., Aziz, Q., Bennett, M. I., Benoliel, R., Cohen, M., Evers, S., Finnerup, N. B., First, M. B., Giamberardino, M. A., Kaasa, S., Korwisi, B., Kosek, E., Lavand'homme, P., Nicholas, M., Perrot, S., Scholz, J., Schug, S., … Wang, S.-J. (2019). Chronic pain as a symptom or a disease: The IASP Classification of Chronic Pain for the International Classification of Diseases (ICD-11). *Pain*, *160*(1), 19–27. https://doi.org/10.1097/j.pain.0000000000001384

Turpel-Lafond, M. E. (Aki-Kwe). (2020). *In plain sight: Addressing Indigenous-specific racism and discrimination in B.C. health care* [Summary report]. Addressing Racism Review. https://engage.gov.bc.ca/app/uploads/sites/613/2020/11/In-Plain-Sight-Summary-Report.pdf

Warden, V., Hurley, A. C., & Volicer, L. (2003). Development and psychometric evaluation of the Pain Assessment in Advanced Dementia (PAINAD) scale. *Journal of the American Medical Directors Association*, *4*(1), 9–15. https://doi.org/10.1097/01.JAM.0000043422.31640.F7

Ware, L. J., Epps, C. D., Herr, K., & Packard, A. (2006). Evaluation of the Revised Faces Pain Scale, Verbal Descriptor Scale, Numeric Rating Scale, and Iowa Pain Thermometer in older minority adults. *Pain Management Nursing*, *7*(3), 117–125. https://doi.org/10.1016/j.pmn.2006.06.005

Yakovenko, I., Mukaneza, Y., Germé, K., Belliveau, J., Fraleigh, R., Bach, P., Poulin, G., Selby, P., Goyer, M.-È., Brothers, T. D., Rehm, J., Hodgins, D. C., Stewart, S. H., Wood, E., & Bruneau, J. (2024). Management of opioid use disorder: 2024 update to the national clinical practice guideline. *CMAJ, 196*(38), E1280–E1290. https://doi.org/10.1503/cmaj.241173

06 Recognizing Deterioration and Shock

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Recognize early cues of clinical deterioration, including trends, changes in mental status, and the concerns of patients and families.
2. Explain how early warning scores support, but do not replace, nursing judgment.
3. Escalate concerns promptly and clearly using SBAR, rapid response teams and the hospital's escalation pathway.
4. Explain how shock harms the body, its stages, and the four types: hypovolemic, cardiogenic, distributive and obstructive.
5. Recognize and give first care for hypovolemic, cardiogenic, anaphylactic and obstructive shock, as ordered and per hospital policy.
6. Give first care for anaphylaxis, including intramuscular epinephrine, and teach the patient before discharge.
7. Distinguish RN and RPN roles in caring for patients who are deteriorating or in shock, using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 4	Clinician; Scholar	Foundations of Practice
3, 7	Communicator; Coordinator; Leader	Collaborative Practice; Professional Practice
5, 6	Clinician; Educator	Foundations of Practice

Introduction

In a large United States registry of in-hospital cardiac arrests on general wards and telemetry or step-down units, 59.4% of patients had at least one abnormal heart rate, respiratory rate or systolic blood pressure in the 1 to 4 hours before the arrest, and the risk of death rose with each additional abnormal sign (Andersen et al., 2016). A review of respiratory rate monitoring described earlier research in which a rate above 24 breaths per minute was often recorded as long as 24 hours before a serious adverse event (Cretikos et al., 2008). Those hours are a window for rescue.

The nurse, at the bedside more than anyone else on the team, is often first to notice a change. This chapter shows how to recognize **clinical deterioration** (a worsening of the patient's physiological condition that can lead to serious harm or death if untreated) and how to act on it. Section 6.1 covers early cues, 6.2 early warning scores and escalation, and 6.3 how shock develops; sections 6.4 to 6.6 cover the types of shock and nursing care.

Sepsis is covered in Chapter 4, pulse oximetry across skin tones in Chapter 12, pulmonary embolism in Chapter 15, acute coronary syndromes and heart failure in Chapters 17 and 18, transfusion in Chapter 20, and neurogenic shock in Chapter 32.

6.1 Recognizing Clinical Deterioration

Failure to Rescue

In 1992, Silber and colleagues studied deaths after surgery. They separated two questions: how often patients developed a complication, and how often patients who developed one then died. They called the second measure **failure to rescue**: death after a complication (Silber et al., 1992). Complication rates were linked mainly to characteristics of the patients, while failure to rescue was linked more strongly to characteristics of the hospital and depended less on how sick patients were on admission (Silber et al.,

1992). In other words, some complications will happen, but whether a patient survives one depends a great deal on the care around them, including how quickly the team notices the problem and responds.

Cues are missed for many reasons. A finding that has been slightly off all shift can start to seem normal for that patient. A heavy assignment leaves less time to look closely. Vital sign sets may be incomplete: the respiratory rate, in particular, is the sign most often left out of the record, even in patients whose main problem is respiratory (Cretikos et al., 2008). Night shifts carry their own risks, discussed later in this section. Finally, a nurse may hesitate to call a busy physician or to question a plan that a senior colleague made. Each of these is a system problem as well as a personal one, and Chapter 1, section 1.6 describes the safety culture that helps teams address them.

Early Cues

Deterioration usually shows first as small changes in breathing, thinking, perfusion or urine output rather than as a falling blood pressure.

- **Respiratory rate and effort:** An abnormal respiratory rate helps predict serious events such as cardiac arrest (Cretikos et al., 2008). An adult breathing more than 20 times a minute is probably unwell, and one breathing more than 24 times a minute may be critically ill (Cretikos et al., 2008). The nurse also notes effort: use of neck and shoulder muscles, speaking in short phrases, or a patient who must sit upright to breathe. Oxygen saturation measured by pulse oximetry (SpO2) does not replace counting the respiratory rate, because the two give different information (Cretikos et al., 2008).
- **Mental status:** New confusion, restlessness, agitation or unusual drowsiness can signal poor oxygen delivery to the brain. When it is unclear whether confusion is new, it is treated as new until proven otherwise (Royal College of Physicians [RCP], 2017). Chapter 8 describes delirium in older adults.
- **Urine output:** Output below 0.5 mL/kg/h is one of the body's "windows" on poor perfusion (Vincent & De Backer, 2013).
- **Skin:** Skin that is cool, clammy or mottled, with slow capillary refill, suggests that blood is being diverted away from the skin (Cecconi et al., 2014).
- **Heart rate:** A rising heart rate is often an early compensating response.
- **Blood pressure:** A fall in blood pressure is frequently a late sign, because the body works hard to hold it steady (see section 6.3).

Colour changes look different on different skin tones, and visual assessment alone is unreliable (Pusey-Reid et al., 2023). On dark skin, cyanosis may make the lips, tongue and the skin around the mouth look grey or whitish, and a bluish tint may show in the nail beds, conjunctivae, palms and soles. Pallor may appear as ash-grey mucous membranes, or the conjunctivae and the lining of the mouth may look pale (Pusey-Reid et al., 2023). The nurse checks these sites in natural or halogen light rather than fluorescent light, compares with an unaffected area and with the patient's own baseline, and pairs what is seen with what is felt: skin temperature, moisture and capillary refill. Chapter 12 explains how skin pigmentation can affect pulse oximeter readings.

Table 6.1 groups common cues with what they may mean and the nurse's first actions (Table 6.1).

Table 6.1 Cues of deterioration, what they may mean and first nursing actions (Cretikos et al., 2008; Vincent & De Backer, 2013; Cecconi et al., 2014; RCP, 2017)

Cue	What it may mean	First nursing actions
Respiratory rate above 20 per minute, or rising; more effort to breathe	Hypoxemia, acidosis, sepsis, pain, fluid overload or a developing lung problem	Count for a full minute; check SpO2 and effort; sit the patient up; complete a full set of vital signs; escalate if above 24 or rising
Falling SpO2 or a new or increased need for oxygen	Worsening gas exchange or ventilation	Check probe and waveform; assess breathing and colour; apply or adjust oxygen per order or policy; escalate
Heart rate rising or above 100 per minute	Pain, fever, fluid or blood loss, sepsis, dysrhythmia or early compensation for shock	Check rhythm and blood pressure; look for bleeding and fluid losses; review trends; escalate if sustained or rising
Systolic blood pressure falling, or well below the patient's usual value	Compensation is failing; possible shock	Repeat the reading manually; check perfusion and level of consciousness; escalate urgently

Cue	What it may mean	First nursing actions
New confusion, agitation or drowsiness	Poor brain perfusion or oxygenation, low glucose, sepsis, drug effect or delirium	Assess level of consciousness and glucose; keep the patient safe; treat as new until proven otherwise; escalate
Cool, clammy, mottled or grey skin; slow capillary refill	Blood diverted from the skin to vital organs	Compare with baseline and other sites; check temperature of limbs; escalate with other findings
Urine output below 0.5 mL/kg/h	Poor kidney perfusion, low volume or urinary retention	Check catheter or bladder; total intake and output; escalate if it continues
New fever, an unusually low temperature or new rigors	Infection or sepsis; low temperature can be a sign of severe illness	Complete a full set of vital signs; use sepsis screening (Chapter 4, section 4.6); escalate
New or worse pain, or a new symptom such as chest pain	A new complication such as bleeding, ischemia or a leak	Assess the pain fully; check vital signs; do not attribute it to the known diagnosis without review; escalate

Trends Matter More Than Single Readings

A single reading tells the nurse where the patient is; a trend tells the nurse where the patient is heading. A heart rate of 98 beats per minute may be reassuring in one patient, but it is a warning in a patient whose rate was 70 at the start of the shift. The nurse compares each set of vital signs with the previous ones and with the patient's usual values, such as a blood pressure that normally runs high (Figure 6.1).

Figure 6.1 (a) A bedside monitor showing heart rate, oxygen saturation and blood pressure for a simulated patient. (b) A pulse oximeter with a finger sensor. Monitors show single readings; the nurse looks at the trend over time. (credit: (b) "Pulse oximeter" by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Several mildly abnormal signs together can matter more than one very abnormal sign. In the registry study described in the introduction, each additional abnormal vital sign before a cardiac arrest was linked with a higher risk of death (Andersen et al., 2016). An adult on a general ward with a respiratory rate above 24 per minute needs close monitoring and review even when every other sign is normal (Cretikos et al., 2008).

Incomplete sets hide trends. A missing respiratory rate removes one of the most useful predictors of serious events (Cretikos et al., 2008). The rate is best counted while the patient is resting and unaware of being counted, over a full minute, because breathing often speeds up once a patient knows it is being watched (Gandevia & McKenzie, 2008). A guessed or rounded number defeats the purpose.

Listening to Patients and Families

Nurses' worry is a real cue. A systematic review of 18 studies found that nurses' worry or concern was triggered by signs such as changes in breathing, circulation or mentation, agitation, new pain, a recovery that is not following the expected path, and patients saying they feel unwell, and that it sometimes appeared before vital signs changed (Douw et al., 2015). Some nurses in the included studies were simply convinced that something was wrong without being able to say why. That feeling is a reason to look harder and

to ask for help, not a reason for embarrassment. The authors noted that some rapid response systems allow worry alone as a calling criterion (Douw et al., 2015).

Patients and families also notice change. A family member who says "this isn't like her" is reporting a change from baseline that no chart contains. Some hospitals give patients and families a direct way to call for help when they feel their concern is not being heard. At St. Paul's Hospital in Vancouver, Providence Health Care's Code H let patients and families phone a clinical resource nurse who was not part of their care team; in a survey, 85% of the patients and families who responded said they felt safer knowing Code H existed (Parsons et al., 2015). In the United States, the Condition Help model asks patients and families to call when there is an emergency and staff can't be reached, when they see a change the care team is not recognizing, or when care breaks down or the plan is unclear (Eden et al., 2017). Language barriers, past experiences of racism and distrust of hospitals can all make a patient or family slower to speak up. Culturally safe care, described in Chapter 2, helps make it safe to raise a concern.

Vital Sign Frequency and Night Shifts

How often vital signs are measured depends on orders, hospital policy and the patient's condition. Policy sets a minimum, not a maximum: when a patient's condition changes, the nurse measures more often. Early warning scores also set monitoring frequency (section 6.2).

Nights need extra care. In a large English hospital study, fewer vital sign sets were recorded overnight, and many patients with high early warning scores in the late evening had no further observations recorded for the next 6 hours (Hands et al., 2013). Sicker patients were checked again sooner, but not as soon as the hospital's own protocol required (Hands et al., 2013). Fewer staff, sleeping patients and reluctance to wake a physician can all delay action. A patient who is hard to rouse at 0300 is not necessarily "just sleeping."

CLINICAL JUDGMENT

A Quiet Change Overnight

Names and details are fictional; this is a composite story.

Mr. Tomas Kowalski, 72, is on day 2 after a bowel resection for colon cancer. At 2200 his vital signs are near his baseline. At 0200 the registered nurse (RN), Grace, finds him picking at his blankets and asking to go home.

- **Recognize cues:** His respiratory rate is 26 per minute (18 at 2200), heart rate 112 (88), blood pressure 104/62 mm Hg (128/76), temperature 38.3 °C. He is newly confused. His urine output has been 80 mL over the past 4 hours.
- **Analyze cues:** The cues fit together: faster breathing, rising heart rate, falling blood pressure, fever and new confusion. They are not explained by pain alone.
- **Prioritize hypotheses:** Grace considers sepsis from a leak at the bowel join, pneumonia, a blood clot in the lung and delirium. Sepsis is the most dangerous possibility that fits.
- **Generate solutions:** She needs urgent medical review. His early warning score has reached the hospital's threshold for urgent review, and new confusion alone triggers one.
- **Take action:** She stays with him, sits him up and checks his oxygen saturation. She asks a colleague to watch him while she calls the surgical resident using SBAR (Situation, Background, Assessment, Recommendation; Table 6.2), reads back the orders, and calls the rapid response team as the hospital's protocol requires.
- **Evaluate outcomes:** Within the hour, the team draws a lactate and blood cultures and starts fluids and antibiotics. Grace rechecks his vital signs every 15 minutes and documents the times of each call. By 0400 his respiratory rate is 22 and his blood pressure is 118/70 mm Hg. A computed tomography (CT) scan later confirms a leak, and he returns to the operating room.

6.2 Early Warning Scores and Escalation

How Early Warning Scores Work

An **early warning score** turns routine vital signs into a single number that reflects how sick a patient is. It is the core of a **track-and-trigger system**: the nurse tracks the score over time, and preset scores trigger a defined response, such as more frequent monitoring or a call for urgent review.

A widely used example is the **National Early Warning Score 2 (NEWS2)**, published by the Royal College of Physicians of London in 2017 and endorsed in England as the standard system for acutely ill adults (RCP, 2017). NEWS2 scores seven items: respiratory rate, oxygen saturation, whether the patient is receiving supplemental oxygen, systolic blood pressure, pulse rate, level of consciousness and temperature. Each measured parameter earns more points the further it moves from normal, and receiving oxygen adds points of its own (RCP, 2017).

Two features deserve attention. First, oxygen saturation has a second scale for patients whose blood gases have confirmed hypercapnic respiratory failure (a build-up of carbon dioxide), usually from chronic obstructive pulmonary disease (COPD), and whose prescribed saturation target is 88% to 92%. A competent clinical decision maker chooses this scale and records the decision (RCP, 2017). Second, consciousness is scored with ACVPU: alert, new confusion, responds to voice, responds to pain, unresponsive. NEWS2 added new confusion to the consciousness scale because a new change in mental state can signal serious illness (RCP, 2017).

The score triggers a response in two ways. The aggregate score is sorted into low, medium and high bands, and each band calls for a faster and more senior response, from assessment by a competent registered nurse at the low end to emergency assessment by a team with critical care skills at the high end. In addition, a single parameter that earns the top score of 3 triggers urgent review even when the total is low (RCP, 2017). The score also sets minimum monitoring frequency, which rises to continuous monitoring for the highest scores (RCP, 2017). The official charts, which may be used only unaltered and with acknowledgement, are available from the Royal College of Physicians website (RCP, 2017); nurses follow the version and thresholds their hospital has adopted.

Canada has its own score. The **Hamilton Early Warning Score (HEWS)** was developed through a quality improvement process at hospitals affiliated with Hamilton Health Sciences in Ontario (Skitch et al., 2018). It scores vital signs and level of consciousness and adds a delirium screen and graded points for the amount of supplemental oxygen (Skitch et al., 2018; Xu et al., 2015). Among 5,491 patients seen by a rapid response team at two Canadian hospitals, HEWS predicted in-hospital death about as well as NEWS2 (Fernando et al., 2019).

What Scores Cannot Do

An early warning score supports clinical judgment; it does not replace it. The NEWS2 report is clear that clinical concern about a patient warrants urgent review, whatever the score (RCP, 2017). Scores have known limits:

- **Chronic abnormal values:** A patient with long-standing lung disease may always score points for low saturation, which can blunt the score's meaning (RCP, 2017).
- **Medications:** A beta-blocker limits the rise in heart rate that normally signals trouble. In a laboratory model of blood loss, blocking this response reduced people's tolerance of the loss (Schiller et al., 2017).
- **Groups excluded:** NEWS2 is not intended for people under 16 or for pregnant people, and it may be unreliable after spinal cord injury (RCP, 2017).
- **Missed patients:** No score catches everyone. In a study of 5,491 patients seen by a rapid response team, a NEWS2 of 5 or more had a sensitivity of 84.5% for in-hospital death: it flagged most, but not all, of the patients who went on to die (Fernando et al., 2019).

A low score with a worried nurse is still a reason to escalate.

Rapid Response and Critical Care Outreach

A **rapid response team (RRT)** brings critical care skills to a patient on a general unit before a cardiac arrest occurs. Teams often include a critical care nurse, a respiratory therapist and a physician (Tran et al., 2020). In Ontario, many hospitals call them **Critical Care Response Teams (CCRTs)**. They were introduced as part of the province's Critical Care Strategy after the 2003 outbreak of severe acute respiratory syndrome (SARS), starting at four sites and growing quickly. Each team was led by an intensivist, with intensive care unit (ICU) nurses or respiratory therapists as responders (Salenieks & Reynolds, 2008). Critical Care Services Ontario, the provincial body that supports critical care planning, is now part of Ontario Health (Critical Care Services Ontario, n.d.).

Each hospital sets its own calling criteria. Criteria commonly include abnormal vital signs or early warning scores, and some systems also accept a nurse's worry alone as a reason to call (Douw et al., 2015). Many policies allow any staff member to call, and

some allow patients and families to call (section 6.1). In Ontario's early rollout, teams also followed up patients after discharge from the ICU (Salenieks & Reynolds, 2008).

Escalation Pathways

Escalation means moving a concern to a person or team who can act on it, quickly enough to matter. Every hospital has a pathway, and the nurse learns it on the first day on a unit. A typical pathway runs from the charge nurse, to the most responsible provider (the physician or nurse practitioner (NP) in charge of the patient's care), to the rapid response team. A patient who is not breathing, has no pulse or is about to arrest needs the hospital's emergency code (often "code blue") at once; the nurse does not work through the other steps first.

When a concern is not addressed, the nurse continues up the chain of command: call again, call the charge nurse, call the next most senior physician, or call the rapid response team directly. Policies exist to protect patients, and the nurse is accountable for following through until the patient receives the care needed.

Communicating Concern

SBAR stands for Situation, Background, Assessment and Recommendation. It gives the caller and the listener a shared, predictable structure, which helps both stay aware of the patient's situation (Haig et al., 2006). SBAR was first adapted for acute care by clinicians at Kaiser Permanente, and its spread drew on work with the Institute for Healthcare Improvement (Toronto Rehabilitation Institute, 2010). A systematic review found moderate evidence that SBAR improves patient safety, strongest for telephone calls between nurses and physicians, though high-quality studies are lacking (Müller et al., 2018). SBAR is this book's standard tool for both escalation and handover (Table 6.2):

- **Situation:** who is calling, about which patient, and the problem in one sentence.
- **Background:** the facts the listener needs to understand the problem.
- **Assessment:** what the nurse found and what the nurse thinks is happening.
- **Recommendation:** what the nurse is asking for, and by when.

Before calling, the nurse has the chart, recent vital signs, medications and laboratory results at hand (Toronto Rehabilitation Institute, 2010). When the listener does not seem to grasp the urgency, plain critical language helps: "I'm concerned," "I'm uncomfortable," "This is unsafe" (Toronto Rehabilitation Institute, 2010). Some teams teach these three phrases by their first letters, CUS. Other structured tools, such as I-PASS for shift handover, are used in some hospitals.

Closed-loop communication means the receiver repeats back the message and the sender confirms it, so both know it was understood. For telephone orders, the nurse writes the order directly into the record as it is given and reads the entire order back, spelling out drug names, and calls back if anything is unclear (Koczmara et al., 2006). The nurse then documents the escalation: the time of each call, who was called, what was reported, the response and the patient's condition afterward (see Chapter 1, section 1.5).

Table 6.2 SBAR: parts and a worked example (original)

Part	What to include	Example (Mr. Kowalski, section 6.1)
Situation	Your name, role and unit; the patient's name and room; the problem in one sentence	"This is Grace, RN on 5 West. I'm calling about Tomas Kowalski in room 12. I'm concerned he may be developing sepsis."
Background	Age, admitting problem or surgery and date; relevant history; recent changes	"He is 72, day 2 after a bowel resection. He has hypertension. His vital signs were stable at 2200."
Assessment	Current vital signs and trends; key findings; what you think is happening	"His respiratory rate is 26, up from 18. Heart rate 112, blood pressure 104/62, temperature 38.3. He is newly confused and his urine output is low. His early warning score has reached the urgent review threshold. I am worried this is sepsis, possibly from a leak."
Recommendation	What you need, how soon, and what you will do meanwhile; confirm the plan	"I need you to see him now. Should I draw a lactate and blood cultures? I will recheck vital signs every 15 minutes. Can you be here within 15 minutes? If not, I will call the rapid response team."

SCOPE IN PRACTICE

Every Nurse Escalates

Recognizing and escalating deterioration is every nurse's responsibility. Using the College of Nurses of Ontario (CNO) framework of authority, competence and context (Chapter 1, section 1.3):

- **Authority:** No order is needed to assess a patient, stay with them, call for help or call the rapid response team when policy allows. Every nurse who notices deterioration acts at once and escalates.
- **Competence:** RNs and registered practical nurses (RPNs) both learn to recognize cues and report them clearly. As a patient's needs change, the RPN consults the RN, who may take on more of the care. The RPN does not wait for that consultation to escalate an emergency; many policies allow the RPN to call the rapid response team directly.
- **Context:** Employer policy sets who may call the team, the escalation pathway and how care is reassigned. Some employers assign patients by stability, but this is a common employer practice, not a CNO rule. Rules also differ by province or territory, where practical nurses may be called licensed practical nurses (LPNs).

The question is never "Is this my patient?" but "Who needs to know, right now?"

6.3 Shock: How It Develops

What Shock Is

Shock is a life-threatening failure of the circulation in which cells cannot get or use enough oxygen (Cecconi et al., 2014; Vincent & De Backer, 2013). Every type of shock creates a gap between the oxygen the tissues need and the oxygen they receive (Standl et al., 2018). Without enough oxygen, cells switch to anaerobic metabolism, which produces far less energy and generates lactate. A rising blood lactate is therefore a marker of tissue hypoperfusion (Vincent & De Backer, 2013). Chapter 3, section 3.7 explains lactic acidosis, and Chapter 4, section 4.6 explains how lactate is used in sepsis.

Low blood pressure is common in shock but is not required to diagnose it (Cecconi et al., 2014). Instead, clinicians look through three "windows" on perfusion: the skin (cold, clammy, mottled), the kidneys (urine output below 0.5 mL/kg/h) and the brain (confusion, disorientation or reduced alertness) (Cecconi et al., 2014; Vincent & De Backer, 2013).

When blood pressure is low in adults with shock, the systolic pressure is typically below 90 mm Hg or the mean arterial pressure (MAP, explained below) below 70 mm Hg, usually with a fast heart rate (Vincent & De Backer, 2013). Lactate is normally about 1 mmol/L; a level above 1.5 mmol/L suggests acute circulatory failure, and levels in shock are typically above 2 mmol/L (Cecconi et al., 2014; Vincent & De Backer, 2013). A single value is less useful than the direction of repeated values, so lactate is measured more than once (Cecconi et al., 2014). Reference ranges vary by laboratory.

Mean arterial pressure (MAP) is the average pressure in the arteries over one cardiac cycle, and it reflects the pressure driving blood into the organs (Meaney et al., 2000). Because the heart spends longer in diastole than in systole, MAP is closer to the diastolic pressure than to the systolic. A common estimate is the diastolic pressure plus one third of the pulse pressure (the difference between systolic and diastolic) (Meaney et al., 2000). For a blood pressure of 120/60 mm Hg, the pulse pressure is 60, one third of that is 20, and the estimated MAP is 80 mm Hg. Most monitors calculate MAP automatically. For adults with septic shock, the Surviving Sepsis Campaign recommends starting with a MAP goal of 65 mm Hg rather than aiming higher (Prescott et al., 2026).

The Body's Compensation

When circulation falters, the body defends blood pressure. Pressure sensors in the large arteries (baroreceptors) detect the drop and increase sympathetic nervous system activity (Schiller et al., 2017). The heart rate rises, and blood vessels in the skin, gut and kidneys constrict, which is why the skin becomes cool and pale. Hormones add to this response. The renin–angiotensin–aldosterone system and antidiuretic hormone (ADH, also called vasopressin) constrict vessels and help the kidneys hold onto sodium and water (Schiller et al., 2017). Chapter 3 explains these hormones.

These responses work well enough that blood pressure can stay near normal while the patient loses a large amount of blood or while perfusion fails. In laboratory studies of simulated blood loss, a fast heart rate was one of the main reasons people tolerated the loss (Schiller et al., 2017). This is why a normal blood pressure does not rule out shock and why a rising heart rate, a falling urine output

and new restlessness deserve attention. In a patient with long-standing high blood pressure, a reading that looks normal may already be low for that person (Vincent & De Backer, 2013).

Compensation has limits. A patient taking a beta-blocker cannot raise the heart rate normally, so one of the earliest cues may be missing and tolerance of blood loss may be lower (Schiller et al., 2017). When compensation finally fails, blood pressure can fall suddenly. In the same laboratory studies, the final collapse came with a sharp slowing of the heart rate (Schiller et al., 2017). A heart rate that drops in a patient who has been tachycardic and hypotensive is therefore not a sign of improvement until proven otherwise; the nurse calls for help at once.

Stages

Nursing and medical education often describe shock as passing through three overlapping stages. The stages are a teaching framework rather than a formal classification, and they blur in real patients, but they help explain why early action matters. The physiology behind them is the compensation, and its failure, described above (Schiller et al., 2017; Vincent & De Backer, 2013).

- **Compensated shock:** Compensating mechanisms keep blood pressure near normal. The patient may have a fast heart rate, faster breathing, cool skin, anxiety or restlessness and a falling urine output. Treating the cause at this stage gives the best chance of full recovery.
- **Progressive (decompensated) shock:** Compensation can no longer keep up. Blood pressure falls, and signs of organ hypoperfusion become clear: confusion, very low urine output, mottled skin and a rising lactate (Cecconi et al., 2014). In laboratory studies, the change from compensation to decompensation can be sudden (Schiller et al., 2017).
- **Refractory (irreversible) shock:** Shock persists despite fluids and vasopressors, and damage to cells and organs may be permanent. Survival becomes unlikely.

For the nurse, the lesson is that the best time to act is the compensated stage, when the signs are subtle and blood pressure is still reassuring. The longer hypoperfusion lasts, the more organs it can injure.

Four Types of Shock

Shock has four main mechanisms, and a patient can have more than one at the same time (Vincent & De Backer, 2013). Among 1,600 patients with shock enrolled in one large treatment trial, 62% had septic shock, 16% cardiogenic, 16% hypovolemic, 4% other distributive and 2% obstructive (Vincent & De Backer, 2013). Table 6.3 compares the four types (Table 6.3), and sections 6.4 and 6.5 give the details.

Hypovolemic shock occurs when the volume of blood or fluid in the vessels is too low to fill the heart. Losses may be external, such as bleeding after trauma or surgery, or internal, such as bleeding into the abdomen or large fluid shifts after burns (Standl et al., 2018; Vincent & De Backer, 2013).

Cardiogenic shock occurs when the heart itself fails as a pump. The usual cause is a large myocardial infarction; others include end-stage cardiomyopathy, severe valve disease, myocarditis and dysrhythmias (Vincent & De Backer, 2013). Chapters 17 and 18 cover these conditions.

Distributive shock occurs when blood vessels lose their tone and dilate, so the existing blood volume no longer fills the circulation. Sepsis is by far the most common cause; anaphylaxis and neurogenic shock after spinal cord injury are others (Standl et al., 2018). Cardiac output is usually high in distributive shock, but it can fall if severe illness also depresses the heart muscle, so one patient can have features of two types at once (Vincent & De Backer, 2013). Chapter 4 covers septic shock.

Obstructive shock occurs when something physically blocks blood flow into or out of the heart. Causes include a large pulmonary embolism, cardiac tamponade (fluid compressing the heart) and tension pneumothorax (Vincent & De Backer, 2013). It can look like cardiogenic shock at the bedside, but it needs different treatment aimed at removing the obstruction (Standl et al., 2018).

Table 6.3 The four types of shock compared (Vincent & De Backer, 2013; Cecconi et al., 2014; Standl et al., 2018)

Type	Main problem	Common causes	Typical skin and key cues

Type	Main problem	Common causes	Typical skin and key cues
Hypovolemic	Too little volume in the vessels to fill the heart	Bleeding from trauma, surgery or the gastrointestinal tract; vomiting and diarrhea; burns	Cool, pale or grey, clammy skin; fast heart rate; low urine output; visible or hidden blood or fluid loss
Cardiogenic	The heart cannot pump enough blood	Myocardial infarction, cardiomyopathy, severe valve disease, myocarditis, dysrhythmias	Cool, clammy skin; chest pain or a known heart condition; breathlessness and signs of fluid backing up into the lungs
Distributive	Blood vessels dilate and lose tone	Sepsis (most common), anaphylaxis, spinal cord injury (neurogenic)	Skin may be warm early, then cool and mottled; fever or low temperature in sepsis; hives and airway swelling in anaphylaxis; slow heart rate in neurogenic shock
Obstructive	Blood flow into or out of the heart is blocked	Pulmonary embolism, cardiac tamponade, tension pneumothorax	Cool, clammy skin; sudden breathlessness or chest pain; findings of the underlying cause; needs the obstruction removed

CANADIAN CONTEXT

Triage in Canadian Emergency Departments

Many patients admitted to medical and surgical units arrive through the emergency department, where nurses sort them with the **Canadian Triage and Acuity Scale (CTAS)**. CTAS has five levels: 1, resuscitation; 2, emergent; 3, urgent; 4, less urgent; and 5, non-urgent (Murray et al., 2004). A national advisory committee of the Canadian Association of Emergency Physicians (CAEP) and the National Emergency Nurses Association (NENA) maintains the scale. In 2025 the committee completed a multi-year update of the scale's guidelines and teaching materials (Canadian Association of Emergency Physicians [CAEP], 2026).

A CTAS level describes how sick a patient appeared on arrival. It does not predict how the patient will be hours later. The nurse who receives a patient from the emergency department reviews the trend of vital signs since triage, completes a full set on arrival, and escalates any change, even if the patient was triaged as less urgent. Triage itself requires separate training.

6.4 Hypovolemic and Cardiogenic Shock

This section applies the types of shock from section 6.3 to two that often develop on medical and surgical units: loss of volume and failure of the heart as a pump.

Hypovolemic Shock

Hypovolemic shock develops when so much fluid leaves the circulation that too little blood returns to the heart. With less blood filling the ventricles, stroke volume and cardiac output fall (Cecconi et al., 2014). **Hemorrhagic shock** is hypovolemic shock caused by bleeding. Bleeding may follow surgery or a procedure, come from the gastrointestinal (GI) tract, or follow trauma such as a fall. Non-hemorrhagic causes include vomiting, diarrhea, large drain or ostomy losses, excessive diuresis, and fluid shifts in burns, pancreatitis or bowel obstruction (Chapter 3, section 3.2).

As volume falls, the sympathetic nervous system speeds the heart and narrows the blood vessels of the skin, gut and kidneys, helped by hormones such as angiotensin and vasopressin (Schiller et al., 2017). These responses can keep blood pressure near normal while bleeding continues. Tolerance varies widely between people, and when compensation fails, blood pressure can drop suddenly (Schiller et al., 2017). The nurse therefore acts on early cues and never waits for hypotension.

The cues tend to appear in this order, although every patient is different:

- **Rising heart rate.** Sympathetic tachycardia is one of the body's main defences against blood loss (Schiller et al., 2017). The trend matters more than any single value (section 6.1).
- **Narrowing pulse pressure. Pulse pressure** is the difference between the systolic and diastolic pressures. As stroke volume falls and the vessels tighten, the gap shrinks (for example, from 130/80 to 112/90 mm Hg). A narrow pulse pressure is a recognized sign of poor perfusion (Chioncel et al., 2020).

- **Cool, pale, clammy or mottled skin and slow capillary refill** (Cecconi et al., 2014). Pallor is harder to see on darker skin, so the nurse checks the conjunctivae, palms and oral mucous membranes and compares them with the patient's usual colour (Chapter 2).
- **Anxiety, restlessness, then confusion,** as blood flow to the brain falls (Cecconi et al., 2014).
- **Falling urine output.** Output below 0.5 mL/kg/h is a sign that the kidneys are underperfused (Cecconi et al., 2014).
- **Hypotension,** a late sign that compensation is failing (Schiller et al., 2017).

A lactate above 2 mmol/L supports tissue hypoperfusion (Cecconi et al., 2014; Chapter 3, section 3.7).

Bleeding is not always visible. The nurse checks the dressing and the sheets under the patient, measures drain output, and looks for swelling around a surgical or puncture site, vomited blood, black stools or a growing abdomen. A dry dressing does not rule out bleeding into the abdomen, bowel or tissues.

When hypovolemic shock is suspected, the nurse calls for help at once through the RRT or the most responsible provider, as policy directs, and reports with SBAR (section 6.2). The nurse then carries out ordered actions and those allowed by medical directives:

- **Airway, breathing and oxygen.** Oxygen is given if saturation is low (Chapter 12).
- **Intravenous (IV) access.** Large-bore access lets fluid and blood run quickly.
- **Blood work.** In major bleeding, the group and screen sample comes first, so blood can be crossmatched. Other tests include a complete blood count (hemoglobin and platelets), the international normalized ratio (INR), fibrinogen, electrolytes, ionized calcium, a blood gas and lactate, repeated at least hourly (Callum et al., 2019).
- **Fluids and blood.** Crystalloid boluses are given as ordered (Chapter 3, section 3.3). For major bleeding, hospitals use a **massive hemorrhage protocol** that rapidly delivers blood components. An Ontario regional protocol template calls for uncrossmatched red cells at the bedside within 10 minutes of activation, warmed IV fluids and blood components, and temperature checks with measures to keep the patient at 36 °C or warmer; ordered tranexamic acid is given as soon as IV access allows, within 3 hours of injury or of protocol activation (Callum et al., 2019). Transfusion is taught in Chapter 20.
- **Position.** The patient lies flat. Teams may raise the legs briefly (passive leg raising) to test whether more fluid would help (Cecconi et al., 2014).
- **Monitoring.** Vital signs and level of consciousness are checked often, and urine output hourly, with a catheter if ordered.
- **Stopping the source.** Fluids and blood buy time until surgery, endoscopy or interventional radiology controls the bleeding (Callum et al., 2019). The nurse prepares the patient and records when the protocol starts and ends.

The team sets the blood pressure target; in uncontrolled bleeding without head injury, a lower pressure may be accepted until bleeding stops (Cecconi et al., 2014).

Cardiogenic Shock

Cardiogenic shock is shock caused by a primary heart problem: the heart cannot pump enough blood to meet the body's needs, so tissues are underperfused and lactate rises (Chioncel et al., 2020). Acute myocardial infarction (MI) is the classic cause, although its share is falling: a European position statement reports that acute coronary syndromes caused about 81% of cases a decade earlier but about one third in a recent cardiac intensive care dataset (Chioncel et al., 2020). Other causes include myocarditis, cardiomyopathy and dysrhythmias (Cecconi et al., 2014).

When the pump fails, blood backs up while too little moves forward. Most patients with MI-related cardiogenic shock are "cold and wet": poorly perfused and congested (van Diepen et al., 2017). The cues include:

- low blood pressure, often a systolic pressure below 90 mm Hg for more than 30 minutes or a need for drugs to support it; perfusion can be poor even before the pressure falls (Chioncel et al., 2020; van Diepen et al., 2017);
- cool, clammy extremities, a narrow pulse pressure, dizziness, confusion and reduced urine output (Chioncel et al., 2020);
- signs of congestion in the lungs, such as worsening shortness of breath and falling oxygen saturation; a chest X-ray helps assess congestion (Chioncel et al., 2020);
- chest pain and electrocardiogram (ECG) changes when MI is the cause (Chapter 17), and dysrhythmias (Chapter 16).

Fluids need caution. A small fluid challenge is tried only when there are no signs of congestion (Chioncel et al., 2020), because extra volume can flood the lungs when the heart cannot move it forward. Before and after any ordered fluid, the nurse listens to the lungs, checks oxygen saturation and reports any worsening at once.

Cardiogenic shock needs urgent escalation: in-hospital mortality is roughly 30% to 60%, and nearly half of these deaths occur within 24 hours (Chioncel et al., 2020). A 12-lead ECG is done at once, followed by continuous cardiac monitoring, urgent echocardiography, troponin and lactate (Chioncel et al., 2020). Shock from an acute coronary syndrome calls for early opening of the blocked artery (van Diepen et al., 2017). The patient moves quickly to an ICU or coronary care unit, often at a centre with a round-the-clock cardiac catheterization laboratory (Chioncel et al., 2020), where drugs to support the circulation are started (section 6.6). The team also discusses goals of care and palliative care with the patient and family (van Diepen et al., 2017; Chapter 10). Acute coronary syndromes and heart failure are covered in Chapters 17 and 18.

6.5 Distributive and Obstructive Shock

In distributive shock, blood vessels lose their tone and widen, so the circulating blood no longer fills the enlarged space. Blood pressure falls even though the heart's output is usually normal or high (Cecconi et al., 2014). Its three main causes are sepsis, anaphylaxis and spinal cord injury. Obstructive shock, discussed at the end of this section, has a different cause: something physically blocks blood flow into or out of the heart.

Septic Shock

Sepsis is life-threatening organ dysfunction that results from a dysregulated host response to infection. **Septic shock** is the subset of sepsis in which circulatory and metabolic changes are severe enough to raise the risk of death substantially. Clinically, the patient needs a vasopressor to keep the MAP at 65 mm Hg or higher and has a serum lactate above 2 mmol/L, even after adequate fluid resuscitation. In this group, hospital mortality is above 40% (Singer et al., 2016). Septic shock is a form of distributive shock, in which infection leads to loss of vascular tone (Cecconi et al., 2014). Screening, the first hour of care and fluid resuscitation are taught in Chapter 4, section 4.6; vasopressors are covered in section 6.6.

Anaphylaxis

Anaphylaxis is a severe, potentially life-threatening allergic reaction, the most serious form of acute systemic allergic reaction (Cardona et al., 2020). Its signs start suddenly and progress over minutes, usually in two or more body systems (Public Health Agency of Canada [PHAC], 2023a). Mediators released from immune cells widen blood vessels and make capillaries leak, so fluid leaves the circulation and blood pressure falls; airway smooth muscle also contracts (Mylan Specialty, 2024). The immune basis of allergy is explained in Chapter 21.

The World Allergy Organization (WAO) considers anaphylaxis highly likely when either of two criteria is met (Cardona et al., 2020):

- a sudden illness, developing over minutes to several hours, that involves the skin, mucous membranes or both (for example, widespread hives, itching or flushing, or swollen lips, tongue or uvula), together with significant symptoms in at least one other body system, such as the breathing or circulatory system; or
- sudden low blood pressure, bronchospasm or throat (laryngeal) involvement after contact with an allergen that is known, or highly likely, to affect that patient, even without skin signs.

Drugs are among the most frequent triggers of anaphylaxis, and many are given in hospital. Antibiotics, contrast media used for imaging, analgesics, biologic drugs and chemotherapy can all cause anaphylaxis, as can latex and antiseptic skin preparations (Cardona et al., 2020). In a national audit of anaphylaxis during anesthesia in the United Kingdom, the culprits identified most often were antibiotics, neuromuscular blocking agents, chlorhexidine and a blue dye used in surgery. Reactions to antibiotics and neuromuscular blockers began quickly, while reactions to chlorhexidine and the dye were delayed (Harper et al., 2018). Any first dose of an IV drug therefore calls for close watching in the first minutes.

The cues can involve every system (Association des allergologues et immunologues du Québec [AAIQ], 2020; PHAC, 2023a):

- **Skin and mucosa:** hives, itching, flushing, warmth, and swelling of the face, eyelids, lips or tongue (Figure 6.2).

- **Airway and breathing:** throat tightness, a hoarse voice, trouble swallowing, cough, wheeze and shortness of breath.
- **Circulation:** dizziness, fainting, a weak and fast pulse, pale or bluish skin and low blood pressure.
- **GI:** nausea, cramping, vomiting and diarrhea.
- **Other:** anxiety, a sense of doom and a metallic taste.

Skin signs are common but not universal. They are present in about 80% to 90% of reactions (PHAC, 2023a) and absent in 10% to 20%, which can delay recognition (Cardona et al., 2020). During anesthesia, low blood pressure was the most common first sign (Harper et al., 2018). On darker skin, redness may not look red, so flushing and hives are easy to miss (Wounds International, 2023). The nurse looks and feels for raised welts and swelling, compares areas of skin, and asks the patient about itching and throat tightness.

Figure 6.2 Raised red welts on light skin during a skin reaction, similar to hives. On darker skin, redness can be harder to see. (credit: "Rash" by Enochlau/Wikimedia Commons, CC BY-SA 3.0)

Speed saves lives. Epinephrine given intramuscularly (IM) is the first-line treatment (Cardona et al., 2020; Li et al., 2021), and there is no absolute contraindication to it in anaphylaxis (Cardona et al., 2020). The first actions happen together, not one after another (PHAC, 2023a), and they are summarized in Table 6.4. The standard adult dose is described in the Medications box.

Table 6.4 First actions in anaphylaxis (original summary of AAIQ, 2020; Cardona et al., 2020; PHAC, 2023a, 2023b)

Step	Nursing action	Why
Remove the trigger	Stop the infusion at once and disconnect the tubing that holds the drug; keep the IV access	Less of the allergen reaches the patient
Call for help	Use the call bell or emergency call; activate the rapid response or code team as policy directs	Several people are needed for drugs, monitoring and the airway
Give epinephrine	Give IM epinephrine into the mid-anterolateral thigh without delay, per order, medical directive or protocol; record the time	Reverses vasodilation, capillary leak and bronchospasm
Position	Lay the patient flat with legs raised; sit them up if breathing is hard; turn them onto their side if vomiting; never stand or sit them up suddenly	Keeps blood returning to the heart; sudden upright posture can cause collapse
Support breathing	Give oxygen; watch the airway for swelling, hoarseness or noisy breathing	Airway swelling can progress within minutes
Support circulation	Give IV fluid boluses as ordered for low blood pressure	Replaces fluid that has leaked out of the vessels
Monitor and repeat	Check blood pressure, heart rate and rhythm, breathing and oxygen saturation continuously; repeat epinephrine as ordered if symptoms persist	Most patients improve after one or two doses
Observe and record	Document the reaction, every drug and time, and the response; flag the allergy	Symptoms can return, and the trigger must never be given again

Antihistamines may ease itching and hives, and corticosteroids are often ordered too (Cardona et al., 2020). Antihistamines have no role in treating breathing or circulation problems in anaphylaxis, and an antihistamine must never be used in place of epinephrine or delay it (PHAC, 2023a).

After the first reaction settles, symptoms can come back without new exposure. This **biphasic reaction** occurs in up to 23% of patients (PHAC, 2023a). There is no agreed length of observation (Cardona et al., 2020); a Canadian emergency plan advises

observation in hospital, generally for about 4 to 6 hours, as the emergency physician decides (AAIQ, 2020). On a medical unit, the nurse continues frequent assessments and teaches the patient to report any returning itching, throat tightness or breathing difficulty at once.

The nurse documents the reaction, the suspected trigger and the treatment (Chapter 1, section 1.5), updates the allergy record and allergy band as hospital policy directs, and reports the event through the hospital's reporting system. Only about half of patients who have anaphylaxis are referred to an allergist, although referral helps identify the cause and plan prevention (Cardona et al., 2020). The nurse advocates for referral. Epinephrine autoinjectors are indicated for people at increased risk of anaphylaxis, including those who have had it before (Mylan Specialty, 2024), so the prescriber decides whether the patient needs one at discharge. As of October 2026, the Health Canada Drug Product Database lists EpiPen and EpiPen Jr autoinjectors and an epinephrine nasal spray (neffy) as marketed, while other autoinjectors sold in earlier years, such as Allerject and Emerade, are no longer marketed (Health Canada, n.d.). Teaching is described in the Patient Education box in section 6.6.

MEDICATIONS

Epinephrine for Anaphylaxis

Epinephrine acts on alpha-adrenergic receptors to tighten blood vessels, which counters vasodilation and capillary leak and raises blood pressure. Its beta-adrenergic effects relax airway smooth muscle, easing wheeze and shortness of breath (Mylan Specialty, 2024).

- **Route and site:** IM, into the mid-anterolateral thigh (vastus lateralis), through clothing if needed with an autoinjector (Figure 6.3). The deltoid is not recommended (PHAC, 2023a). Never inject into the buttock, fingers, hands or feet (Mylan Specialty, 2024).
- **Standard adult dose:** Canadian guidance gives 0.01 mg/kg of the 1 mg/mL solution, to a maximum of 0.5 mg. For people older than 12 years who weigh 46 kg or more, the dose is 0.5 mg, which is 0.5 mL of the 1 mg/mL solution (PHAC, 2023a, 2023b; Li et al., 2021). Autoinjectors deliver a fixed dose.
- **Repeat:** as ordered if symptoms persist or worsen. PHAC advises repeating every 5 minutes if symptoms persist, and the EpiPen monograph allows a repeat every 5 to 15 minutes (Mylan Specialty, 2024; PHAC, 2023a).
- **Expected effects:** fast heart rate, palpitations, pallor, anxiety, headache, nausea and vomiting (Mylan Specialty, 2024).
- **Safety:** Check the concentration: only the 1 mg/mL solution is used for IM injection. Never give the IM dose intravenously; an accidental IV dose can cause a sharp rise in blood pressure and bleeding in the brain (Mylan Specialty, 2024). Record the time of every dose (PHAC, 2023a).

Neurogenic Shock

Neurogenic shock is low blood pressure with a slow heart rate, without another cause, after a spinal cord injury. It follows cervical or high-thoracic cord injuries, which suddenly cut the sympathetic nerve output that keeps vessels toned and the heart rate up, leaving parasympathetic activity, which slows the heart, unopposed (SCIRE Professional, 2022). In one study it was present at first emergency department presentation in about 19% of people with cervical cord injuries (SCIRE Professional, 2022). The slow heart rate helps the nurse tell it apart from hypovolemic shock. Spinal cord injury and its care are covered in Chapter 32.

Obstructive Shock

In obstructive shock, the heart muscle and blood volume may be normal, but something blocks the filling or emptying of the heart, so cardiac output falls (Cecconi et al., 2014). The three main causes can progress quickly and need urgent treatment by a physician or other authorized provider.

Tension pneumothorax is air trapped in the pleural space under rising pressure. It collapses the lung and squeezes the great veins and heart. Compared with patients breathing on their own, patients receiving assisted ventilation more often develop low oxygen levels, low blood pressure and cardiac arrest, often within minutes (Roberts et al., 2015). Cues include sudden, worsening shortness of breath, falling oxygen saturation, a fast heart rate and falling blood pressure. Many signs taught as "classic" may be absent (Leigh-Smith & Davies, 2003), so the nurse acts on the pattern and never waits for a full set of signs.

Cardiac tamponade is fluid or blood in the pericardial sac that presses on the heart and stops it from filling. Causes include bleeding after cardiac surgery or procedures, pericarditis, cancer and trauma. Beck's triad describes three classic findings: low blood

Figure 6.3 An epinephrine autoinjector held in the fist, with the blue safety release at the top and the orange tip pointing down toward the outer thigh. (credit: “Adrenalina autoinyector9” by AngelHM/Wikimedia Commons, CC BY-SA 4.0)

pressure, distended neck veins and muffled heart sounds. A fast heart rate, shortness of breath and cool extremities are also common. Echocardiography is the key test, and fluids or drugs to support the heart must not replace or delay drainage of the fluid by pericardiocentesis or surgery (Jensen et al., 2017).

A **massive pulmonary embolism** blocks blood flow through the lungs and strains the right side of the heart (Cecconi et al., 2014). It is covered in Chapter 15.

The nurse's role in all three is to recognize the pattern, call the rapid response or code team at once, give oxygen, keep the patient continuously monitored, bring the equipment the team will need, such as a chest tube or pericardiocentesis tray and the ultrasound machine, and report with SBAR. Definitive treatment is done by physicians or other authorized providers.

6.6 Nursing Care of the Patient in Shock

Whatever the type of shock, the nurse's actions follow the same pattern: find poor perfusion early, call for help, support the airway, breathing and circulation, and watch closely to see whether treatment is working.

Priorities

The Clinical Judgment Measurement Model (CJMM; Chapter 1, section 1.4) gives these actions a clear shape.

- **Recognize cues.** The nurse looks through three "windows" on perfusion: the skin (cold, clammy, mottled or slow to refill), the kidneys (urine output below 0.5 mL/kg/h) and the brain (new anxiety, confusion or drowsiness). Shock can be present before blood pressure falls (Cecconi et al., 2014). Trends in early warning scores matter more than single values (section 6.2).
- **Analyze cues.** The nurse asks which type of shock fits: a fast heart rate after surgery suggests bleeding; signs of congestion after an MI suggest pump failure; hives after a new drug suggest anaphylaxis; a slow heart rate after a neck injury suggests neurogenic shock (section 6.3).
- **Prioritize hypotheses.** Airway and breathing come first, then circulation.
- **Generate solutions and take action.** The nurse calls for help early, through the RRT or the most responsible provider as policy directs. While help comes, the nurse gives oxygen (Figure 6.4), secures IV access and gives fluids or blood as ordered (Chapter 3, section 3.3; Chapter 20). Continuous ECG and oxygen saturation monitoring begins, with frequent blood pressure checks. The nurse measures urine output hourly, inserting a urinary catheter if ordered, and checks a point-of-care glucose, because a low or high glucose can also change mental status (Chapter 22). Ordered tests often include lactate, a complete blood count, electrolytes, creatinine, clotting tests and a blood gas (Chapter 3, section 3.7). Lactate is repeated, because its trend shows whether perfusion is improving (Cecconi et al., 2014).
- **Evaluate outcomes.** Improvement shows as clearer thinking, warmer skin, a slower heart rate, better urine output and a falling lactate. After each fluid bolus, the nurse listens for crackles and watches oxygen saturation, because too much fluid can cause lung congestion (Chapter 4, section 4.6).

Vasopressors and the Nurse's Role

A **vasopressor** is a drug that tightens blood vessels to raise blood pressure. Vasopressors are used when fluids alone do not restore an adequate MAP (Cecconi et al., 2014). For septic shock, the 2026 Surviving Sepsis Campaign guideline recommends norepinephrine as the first-line vasopressor (strong recommendation) and a starting MAP target of 65 mm Hg rather than a higher one (strong recommendation, moderate certainty). It suggests a starting range of 60 to 65 mm Hg for adults aged 65 and older (conditional recommendation, low certainty), and it suggests starting vasopressors peripherally to restore the MAP rather than delaying until central venous access is secured (conditional recommendation, very low certainty) (Prescott et al., 2026). Norepinephrine may also be preferred in cardiogenic shock because it causes fewer dysrhythmias (van Diepen et al., 2017).

Figure 6.4 A non-rebreather mask with its reservoir bag, used to give high-concentration oxygen as ordered. (credit: "Non re-breather mask" by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

A central venous catheter is preferred for vasopressor infusions, and patients whose shock needs vasopressors usually have an arterial line for continuous blood pressure monitoring in the ICU (Cecconi et al., 2014). The nurse's responsibilities include:

- **Infusion site.** A peripheral infusion runs through a large vein, preferably at the inner elbow (antecubital vein). The nurse inspects the site often for free flow and for swelling or blanching along the vein. **Extravasation** (leakage of the drug into the tissues) can cause tissue injury, so the nurse stops the infusion into that site and follows hospital policy, which may include an ordered antidote injected into the area (Juno Pharmaceuticals, 2023).
- **Blood pressure.** The norepinephrine prescribing information advises checking blood pressure every 2 minutes from the start until the target is reached, then every 5 minutes while the infusion continues (Juno Pharmaceuticals, 2023).
- **Line safety.** The infusion runs on a pump through a labelled line that the nurse traces from bag to patient at every handover. The nurse never flushes a vasopressor line or pushes other drugs through it, because anything pushed through the line also pushes the drug left in the tubing into the patient faster than intended (Institute for Safe Medication Practices Canada [ISMP Canada], 2014).
- **Never stop suddenly.** The infusion is reduced gradually, as ordered (Juno Pharmaceuticals, 2023).

Vasopressor infusions are usually managed in critical care by nurses with added education. Who may care for them depends on authority, competence and context, and on employer policy and the province or territory (Chapter 1, section 1.3).

Supporting the Patient and Family

Shock is frightening. Patients in anaphylaxis may describe a sense of doom (AAIQ, 2020), and patients in any type of shock may be anxious, short of breath or confused. The nurse speaks calmly, explains each step in plain words, and stays at the bedside or makes sure someone else does. Families are told what is happening and where to wait, and someone is named to update them. When the patient or family speaks a language other than the nurse's, the nurse uses a professional interpreter rather than a family member for clinical information (Chapter 2). Many patients in shock are moved to the ICU. The nurse prepares them and their family for the move, hands over with SBAR (section 6.2), and documents the events, the times and the patient's response (Chapter 1, section 1.5).

GOING DEEPER

Hemodynamics and Titrating Vasopressors

Required for RN students; optional for PN students.

Cardiac output is the volume of blood the heart pumps each minute: heart rate × **stroke volume** (the volume ejected with each beat). Stroke volume depends on three factors:

- **Preload:** how much the ventricle is filled and stretched before it contracts.
- **Afterload:** the resistance the ventricle must pump against.
- **Contractility:** the strength of the contraction itself.

Blood pressure depends on cardiac output and on **systemic vascular resistance** (SVR), the resistance to flow created by the tone of the small arteries. When cardiac output falls, the body raises SVR by vasoconstriction, which is why the skin turns cool.

Each type of shock has a typical pattern (Cecconi et al., 2014; van Diepen et al., 2017):

- **Hypovolemic:** low preload and low cardiac output; SVR rises.
- **Cardiogenic:** low cardiac output with high filling pressures, because blood backs up; SVR is usually high, but it varies.
- **Distributive:** low SVR from vasodilation; cardiac output is usually normal or high.
- **Obstructive:** low cardiac output from blocked filling or emptying; pressures on the right side rise in pulmonary embolism.

Vasopressors raise SVR. Drugs that strengthen contraction (inotropes) are added only when cardiac output stays low and perfusion stays poor after filling has been optimized (Cecconi et al., 2014). Titration is an ICU skill:

- The prescriber orders a MAP target and the limits for titration; the nurse adjusts within the order and hospital policy.
- Changes are small and stepwise, with blood pressure rechecked often, every few minutes after each change (Juno Pharmaceuticals, 2023), usually from an arterial line.
- Perfusion is judged on several measures together, never on one number (Cecconi et al., 2014).
- Infusions are weaned gradually, never stopped abruptly (Juno Pharmaceuticals, 2023).
- Extravasation is managed at once according to policy.

LIFESPAN CONSIDERATIONS

Older Adults in Shock

Shock can hide in older adults.

- **Blunted heart rate.** Beta-blockers weaken the sympathetic rise in heart rate that helps people tolerate blood loss (Schiller et al., 2017), so a heart rate of 84 does not rule out shock. In a national audit of anaphylaxis during anesthesia, taking a beta-blocker or angiotensin-converting enzyme inhibitor was linked to worse outcomes (Harper et al., 2018).
- **"Normal" blood pressure may be low.** In a large study of injured adults over 65, those with a systolic pressure of 90 to 109 mm Hg had odds of death similar to those below 90 mm Hg (Brown et al., 2015). The nurse compares each value with the patient's usual pressure, especially in long-standing hypertension. Targets are individualized: a higher MAP may suit some people with chronic hypertension (Cecconi et al., 2014), while lower targets are suggested for adults 65 and older in septic shock (Prescott et al., 2026).
- **Confusion as the first sign.** New confusion may be the earliest sign of poor brain perfusion and needs urgent assessment (Cecconi et al., 2014; Chapter 8).
- **Vein choice.** Leg and hand veins are avoided for norepinephrine infusions in older adults (Juno Pharmaceuticals, 2023).

PATIENT EDUCATION

Living With an Epinephrine Autoinjector

The nurse teaches the patient, and family if the patient wishes, using a trainer device if available:

- **Use it early.** Give epinephrine as soon as a reaction starts, whether anaphylaxis is known or only suspected. If you have asthma and trouble breathing, use the epinephrine before your inhaler (AAIQ, 2020).
- **Where.** Inject into the outer thigh, through clothing if needed. Never inject into the buttock, hands or feet (Mylan Specialty, 2024).
- **Call 9-1-1** and tell the dispatcher it is a life-threatening allergic reaction. If symptoms have not improved, a second dose may be given as soon as 5 minutes after the first (AAIQ, 2020). Ask your prescriber how many devices to carry.

- **Go to hospital, ideally by ambulance,** even when symptoms are mild or seem to be gone, because they can return (AAIQ, 2020).
- **Care of the device.** Keep it at room temperature, protected from light, and do not refrigerate it, following your device's instructions (Mylan Specialty, 2024). Check the expiry date regularly. Take a used device to a pharmacist or physician for disposal and replacement (AAIQ, 2020).
- **Prevent the next reaction.** Know your trigger, tell every health care provider, and see your allergist (Cardona et al., 2020).

PRACTICE STORY

"Her Lips Were Swelling"

Names and details are fictional; this is a composite story.

Nurse: Luc Vaillancourt, RN. Years in practice: 5. Setting: medical unit, community hospital, Ontario.

Mrs. Teresa Lindqvist was 62 and had been admitted with pneumonia. I hung her first dose of an IV antibiotic at 1500, checked her allergy band (no known allergies), and stayed for the first few minutes, as I always do with a first dose. At about 1506 she rubbed her neck and said her throat felt "scratchy." When I looked closer, her lips were swelling and her voice had gone hoarse.

I clamped the line, disconnected the tubing and pressed the emergency call button. Amira Haddad, an RPN on our team, was in the room within seconds. I asked her to call the rapid response team and bring the anaphylaxis kit. Mrs. Lindqvist's blood pressure was 86/50 mm Hg, her heart rate 128, and she was wheezing. Our hospital has an anaphylaxis medical directive, so I drew up epinephrine from a 1 mg/mL ampoule, checked the concentration aloud with Amira, and gave it into her outer thigh. Amira noted the time.

Mrs. Lindqvist said she couldn't breathe lying down, so we raised the head of the bed and kept her legs up. Amira put her on oxygen and, as the directive allowed, started a fresh bag of saline through the IV. Five minutes later her wheeze was no better, so I gave a second dose. The team arrived, and within 20 minutes her pressure was 118/72 and her voice was clearer.

What stays with me is how fast it moved: under two minutes from her first words to the first dose. We could only do that because Amira and I divided the work without discussing it. Afterward I documented every time and drug, updated her allergy record and band, and filed an incident report. I also asked the physician about an allergist referral and an autoinjector for discharge.

Reflect: Under the same medical directive, could Amira have given the epinephrine herself? What would authority, competence and context require? What made the teamwork in this story fast?

Chapter 6 Summary

Introduction

- In a large registry, most patients had at least one abnormal vital sign in the 1 to 4 hours before an in-hospital cardiac arrest, which gives the team a window to act.
- The nurse is often first to notice a change and is central to rescue.

6.1 Recognizing Clinical Deterioration

- Failure to rescue is death after a complication; it is linked more to the hospital than to the patient, so how quickly the team recognizes and responds matters.
- Early cues include a rising respiratory rate, new confusion, falling urine output, cool or mottled skin and a rising heart rate; falling blood pressure is often late.
- Colour changes look different on different skin tones; check lips, mucous membranes, conjunctivae and nail beds and compare with baseline.
- Trends matter more than single readings; count the respiratory rate for a full minute.
- Nurses' worry and patients' and families' concerns are valid cues, and night shifts need extra vigilance.

6.2 Early Warning Scores and Escalation

- Early warning scores such as NEWS2 and the Canadian HEWS turn vital signs into a score that triggers a defined response.
- Scores support but never replace judgment; escalate any concern, even with a low score.

- Rapid response teams (in Ontario, Critical Care Response Teams) bring critical care skills to the bedside.
- Follow the escalation pathway and the chain of command until the patient gets the care needed.
- Use SBAR, critical language, closed-loop communication and read-back, and document every escalation.

6.3 Shock: How It Develops

- Shock is circulatory failure in which cells cannot get or use enough oxygen; lactate rises as cells switch to anaerobic metabolism.
- MAP reflects organ perfusion pressure; the initial target in septic shock is 65 mm Hg.
- Sympathetic and hormonal compensation can keep blood pressure normal early, so a normal pressure does not rule out shock.
- Shock is often taught as three overlapping stages (compensated, progressive and refractory), a teaching framework rather than a formal classification.
- The four types are hypovolemic, cardiogenic, distributive and obstructive.

6.4 Hypovolemic and Cardiogenic Shock

- Hypovolemic shock follows loss of blood (hemorrhagic shock) or other body fluid; compensation can hold blood pressure near normal while losses continue.
- Cues usually appear as a rising heart rate, narrowing pulse pressure, cool skin, anxiety or confusion and falling urine output; hypotension is late.
- The nurse calls for help early, secures IV access, sends group and screen and other blood work, gives fluids and blood as ordered, and prepares for bleeding control.
- Cardiogenic shock is pump failure, classically after an acute MI; patients are often cool and congested.
- Fluids are given cautiously in cardiogenic shock; escalation, a 12-lead ECG, echocardiography and transfer to a specialized unit are urgent.

6.5 Distributive and Obstructive Shock

- In distributive shock, vessels lose tone; causes are sepsis, anaphylaxis and spinal cord injury.
- Septic shock requires a vasopressor to keep the MAP at 65 mm Hg or higher and a lactate above 2 mmol/L despite adequate fluids (Chapter 4).
- Anaphylaxis is treated first with IM epinephrine into the mid-anterolateral thigh; the standard adult dose (older than 12 years, 46 kg or more) is 0.5 mg (0.5 mL of 1 mg/mL). Antihistamines never replace it.
- Skin signs are absent in some reactions and redness is harder to see on darker skin; symptoms can return in a biphasic reaction.
- Neurogenic shock causes hypotension with a slow heart rate after a cervical or high-thoracic cord injury.
- Tension pneumothorax, cardiac tamponade and massive pulmonary embolism cause obstructive shock; the nurse recognizes the pattern and escalates at once.

6.6 Nursing Care of the Patient in Shock

- The CJMM guides care: look for poor perfusion in the skin, kidneys and brain, prioritize the airway, breathing and circulation, and call for help early.
- Urine output below 0.5 mL/kg/h and a rising lactate signal poor perfusion; repeated lactate shows the trend.
- Norepinephrine is the first-line vasopressor in septic shock, with an initial MAP target of 65 mm Hg.
- The nurse monitors vasopressor sites for extravasation, checks blood pressure often, never flushes the line and never stops the infusion abruptly.
- Calm explanations, presence, professional interpreters and a clear SBAR handover support patients and families.

Key Terms (37)

afterload: the resistance the ventricle must pump against to eject blood.

anaphylaxis: a severe, potentially life-threatening allergic reaction with sudden onset, usually involving two or more body systems.

biphasic reaction: a return of anaphylaxis symptoms after the first reaction has settled, without new exposure to the trigger.

Canadian Triage and Acuity Scale (CTAS): Canada's five-level emergency department triage scale, maintained by a national committee of CAEP and NENA.

cardiac output: the volume of blood the heart pumps each minute; heart rate × stroke volume.

cardiac tamponade: fluid or blood in the pericardial sac that compresses the heart and prevents it from filling.

cardiogenic shock: Shock caused by failure of the heart as a pump.

clinical deterioration: A worsening of a patient's physiological condition that can lead to serious harm or death if it is not recognized and treated.

closed-loop communication: An exchange in which the receiver repeats back the message and the sender confirms it, so both know it was understood.

compensated shock: An early stage of shock in which the body's responses keep blood pressure near normal while signs such as a fast heart rate and cool skin appear.

distributive shock: Shock caused by loss of blood vessel tone and widespread vasodilation, as in sepsis, anaphylaxis or spinal cord injury.

early warning score: A number calculated from routine vital signs that reflects how sick a patient is and how urgently a response is needed.

epinephrine autoinjector: a prefilled, spring-loaded device that injects a fixed dose of epinephrine into the thigh muscle for emergency treatment of anaphylaxis.

escalation: Moving a concern about a patient to a person or team who can act on it, quickly enough to make a difference.

extravasation: leakage of an infused drug out of the vein into the surrounding tissues.

failure to rescue: Death of a patient after a complication that develops in hospital; used as a measure of how well a hospital recognizes and treats complications.

Hamilton Early Warning Score (HEWS): A Canadian early warning score developed at hospitals affiliated with Hamilton Health Sciences that adds a delirium screen and graded oxygen scoring to vital signs and level of consciousness.

hemorrhagic shock: hypovolemic shock caused by bleeding.

hypovolemic shock: Shock caused by too little blood or fluid volume in the vessels.

massive hemorrhage protocol: a hospital protocol that rapidly delivers blood components to a patient with life-threatening bleeding until the bleeding is controlled.

mean arterial pressure (MAP): The average arterial pressure over one cardiac cycle, reflecting the pressure that drives blood into the organs; commonly estimated as diastolic pressure plus one third of the pulse pressure.

neurogenic shock: low blood pressure with a slow heart rate after a cervical or high-thoracic spinal cord injury, caused by loss of sympathetic tone.

NEWS2: The National Early Warning Score 2 (Royal College of Physicians, 2017), which scores respiratory rate, oxygen saturation, supplemental oxygen, systolic blood pressure, pulse, level of consciousness (including new confusion) and temperature.

obstructive shock: Shock caused by a physical blockage of blood flow into or out of the heart, as in pulmonary embolism, cardiac tamponade or tension pneumothorax.

preload: how much the ventricle is filled and stretched before it contracts.

progressive (decompensated) shock: The stage of shock in which compensation fails, blood pressure falls and organ hypoperfusion becomes evident.

pulse pressure: the difference between the systolic and diastolic blood pressures.

rapid response team: A team with critical care skills that assesses and treats deteriorating patients on general units before cardiac arrest; in Ontario, often called a Critical Care Response Team (CCRT).

refractory (irreversible) shock: Shock that persists despite fluids and vasopressors, with cell and organ damage that may be permanent.

SBAR: A structured communication tool: Situation, Background, Assessment, Recommendation.

septic shock: a subset of sepsis in which a vasopressor is needed to keep the MAP at 65 mm Hg or higher and the lactate is above 2 mmol/L despite adequate fluids.

shock: A life-threatening failure of the circulation in which cells cannot get or use enough oxygen.

stroke volume: the volume of blood the ventricle ejects with each beat.

systemic vascular resistance: the resistance to blood flow created by the tone of the small arteries.

tension pneumothorax: air trapped in the pleural space under rising pressure, which collapses the lung and impairs blood return to the heart.

track-and-trigger system: A system in which nurses track a patient's early warning score over time and preset scores trigger a defined response, such as more frequent monitoring or urgent review.

vasopressor: a drug that constricts blood vessels to raise blood pressure.

Licensure Review & Clinical Judgment Questions (30)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Asha Mensah (Questions 1–4): Asha Mensah, 66, was admitted to a medical unit yesterday with a kidney infection and is receiving intravenous (IV) antibiotics. At 0400, the registered practical nurse (RPN) caring for her finds her restless and trying to climb out of bed. At 2300 her vital signs were: respiratory rate 18, heart rate 92, blood pressure 132/78 mm Hg, temperature 37.9 °C, SpO2 96% on room air. Now they are: respiratory rate 28, heart rate 118, blood pressure 108/64 mm Hg, temperature 38.7 °C, SpO2 93% on room air. Her daughter, who is staying overnight, says, "She's not making sense. This isn't like her."

1. [CORE] Which finding is the most important early cue that Ms. Mensah is deteriorating?

a. Temperature of 38.7 °C, because fever confirms that the infection is not responding to antibiotics

b. Respiratory rate of 28 per minute together with new confusion

c. Blood pressure of 108/64 mm Hg, because it is below her usual value

d. Oxygen saturation of 93% on room air

Answer: b — An adult with a respiratory rate above 24 per minute may be critically ill, and new confusion signals poor brain perfusion or oxygenation; together they point to serious deterioration (section 6.1). Option a: fever is a cue, but it does not by itself show deterioration or confirm antibiotic failure. Option c: the fall in blood pressure matters, but blood pressure often falls late, and 108/64 is not yet the most telling sign. Option d: a saturation of 93% is a cue to act on, but the respiratory rate and new confusion change earlier and more sharply here.

2. [CORE] What should the RPN do first?

a. Give acetaminophen for the fever as ordered and reassess in 1 hour

b. Document the findings and report them to the RN at the 0700 handover

c. Ask the daughter to stay with her mother while the RPN looks up her laboratory results

d. Stay with Ms. Mensah, keep her safe and have the RN and physician notified now

Answer: d — Every nurse who notices deterioration acts at once and escalates; the RPN keeps the patient safe and consults the RN as her needs change (section 6.2, Scope in Practice box). Option a: treating the fever does not address the deterioration and delays escalation. Option b: waiting 3 hours could allow shock to progress. Option c: reviewing results is useful but should not delay escalation, and the family should not be left responsible for a deteriorating patient.

3. [CORE] The RPN prepares an SBAR report. Which statement belongs in the Assessment part?

a. "Her breathing and heart rate have risen sharply since 2300, she is newly confused, and I am worried she may be developing sepsis."

b. "I am calling about Asha Mensah in room 8 on the medical unit, who has become restless and newly confused tonight."

c. "She is 66, was admitted yesterday with a kidney infection, and is receiving IV antibiotics; her vital signs at 2300 were near normal."

d. "Please come and assess her within 15 minutes, and tell me whether you want a lactate and blood cultures drawn."

Answer: a — The Assessment states what the nurse found, including trends, and what the nurse thinks is happening (section 6.2, Table 6.2). Option b is the Situation: who is calling, about whom, and the problem. Option c is Background. Option d is a Recommendation.

4. [CORE] The RPN reports to the RN, who is caring for a patient in another room and says she will come "in a few minutes." Twenty minutes later, Ms. Mensah's blood pressure is 96/58 mm Hg and her respiratory rate is 30. What should the RPN do?

a. Wait for the RN, because the RN is responsible for deciding whether to call for help

b. Recheck the vital signs in 1 hour, because the RN has already been informed

c. Call the rapid response team as hospital policy allows and inform the RN and charge nurse

d. Ask the daughter whether she would like to call the patient's family physician

Answer: c — When a concern is not addressed and the patient keeps deteriorating, the nurse continues up the escalation pathway; many policies let any staff member, including the RPN, call the rapid response team directly (section 6.2). Option a: the RPN's duty to escalate does not depend on the RN's response. Option b: waiting an hour while the blood pressure falls is unsafe. Option d: a family physician outside the hospital cannot provide urgent care, and escalation is the nurse's responsibility.

5. [CORE] Which findings are early cues that a hospitalized adult may be deteriorating? Select all that apply.

a. A respiratory rate that has risen from 16 to 24 per minute over 4 hours

b. New restlessness in a patient who was calm earlier in the shift

c. Urine output of 15 mL/h for 3 hours in a 70-kg patient

d. A blood pressure that is stable at the patient's usual value

e. Cool, clammy hands with slow capillary refill

f. A patient who reports sleeping well and eating breakfast

Answer: a, b, c, e — A rising respiratory rate, new restlessness, urine output below 0.5 mL/kg/h (35 mL/h for a 70-kg adult) and cool, clammy skin with slow capillary refill are all early cues (section 6.1, Table 6.1). Option d: a blood pressure at the patient's usual value is not a cue, although a normal pressure does not rule out early shock. Option f: sleeping well and eating are reassuring findings.

6. [CORE] A patient's early warning score is 2, which is in the lowest band. The nurse is worried because the patient "looks different" and says he feels something is wrong. What should the nurse do?

a. Reassure the patient, because his score does not meet the threshold for review

b. Repeat the score in 4 to 6 hours as the monitoring schedule suggests

c. Ask the patient to call if he feels worse

d. Complete a full assessment and escalate the concern despite the low score

Answer: d — Early warning scores support but do not replace clinical judgment; concern about a patient should prompt review whatever the score, and nurses' worry and patients' reports of feeling unwell are recognized cues (sections 6.1 and 6.2). Option a: a low score does not rule out deterioration. Option b: the monitoring schedule is a minimum, not a reason to wait when the nurse is concerned. Option c: this shifts responsibility to the patient and delays assessment.

7. [CORE] A patient is bleeding slowly after surgery. Her heart rate has risen from 80 to 115 per minute, her skin is cool and pale, and she is anxious. Her blood pressure is 124/76 mm Hg, close to her baseline. Which stage of shock do these findings best fit?

a. No shock, because her blood pressure is normal

b. Compensated shock

c. Progressive (decompensated) shock

d. Refractory (irreversible) shock

Answer: b — In compensated shock, sympathetic and hormonal responses keep blood pressure near normal while heart rate rises and the skin becomes cool and pale (section 6.3). Option a: a normal blood pressure does not rule out shock. Option c: progressive shock involves falling blood pressure and clear signs of organ hypoperfusion. Option d: refractory shock persists despite fluids and vasopressors.

8. [CORE] A patient's son tells the nurse, "Dad's not himself. He's usually sharp, and today he keeps losing his train of thought." The vital signs taken 1 hour ago were within normal limits. What is the best response?

a. "Thank you for telling me. I'll assess him now and compare with how he was earlier."

b. "His vital signs were normal an hour ago, so there's no need to worry."

c. "Older people often get a bit confused in hospital. It should settle."

d. "I'll make a note of it and the doctor can look at it on rounds tomorrow."

Answer: a — A family member's report of change from baseline is a valid cue, and confusion that may be new is treated as new until proven otherwise (section 6.1). Option b: normal readings an hour ago do not rule out a change now. Option c: confusion should never be assumed to be "normal" for age; it may be delirium or a sign of deterioration. Option d: delaying assessment until the next day could miss serious illness.

9. [CORE] A registered practical nurse (RPN) on an Ontario surgical unit finds a patient who is suddenly breathless and hypotensive. Which statement about the RPN's role is correct?

a. The RPN must transfer the patient's care to an RN before taking any action.

b. Because CNO rules limit RPNs to stable patients, the RPN may not care for this patient.

c. The RPN acts at once, escalates according to policy, and consults the RN as the patient's needs change.

d. The RPN should wait for the patient's most responsible provider to arrive before calling anyone else.

Answer: c — Every nurse who notices deterioration acts at once and escalates; the RPN consults the RN as the patient's needs change, within employer policy (section 6.2, Scope in Practice box). Option a: immediate action and escalation come first. Option b: assigning patients by stability is a common employer practice, not a CNO rule. Option d: waiting delays care; escalation pathways allow calls to the rapid response team.

Case: Ms. Grace Okonkwo (Questions 10–15): Ms. Grace Okonkwo, 46, was admitted to a medical unit this morning with cellulitis of her left lower leg. She weighs 70 kg and reported no known drug allergies. At 1330 her vital signs were temperature 37.8 °C, heart rate 88, respiratory rate 18, blood pressure 128/78 mm Hg and oxygen saturation 97% on room air. At 1400 the nurse starts the first dose of an IV antibiotic. At 1408 Ms. Okonkwo calls the nurse and says, "My throat feels tight and I'm itchy all over. Something terrible is happening." Assessment: heart rate 124, respiratory rate 28, blood pressure 84/46 mm Hg, oxygen saturation 91% on room air, wheezes in both lungs and a hoarse voice. Her lips and eyelids are swollen. On her dark brown skin, raised welts on her chest and arms are easier to feel than to see. She is nauseated. Her left leg is red-brown, warm and swollen, as it was this morning.

10. [CORE] Which findings at 1408 require immediate follow-up? Select all that apply.

a. Hoarse voice and a tight throat

b. Blood pressure 84/46 mm Hg

c. Warm, swollen left lower leg

d. Swollen lips and eyelids

e. Temperature 37.8 °C at 1330

f. No known drug allergies on admission

g. Oxygen saturation 91% with wheezes

Answer: a, b, d, g — A hoarse voice and tight throat (a) suggest airway swelling. A blood pressure of 84/46 mm Hg (b) is a sharp fall from her baseline and shows poor perfusion. Swelling of the lips and eyelids (d) is angioedema of the skin and mucosa. Low oxygen saturation with wheezes (g) shows bronchospasm. All are new since 1330 (section 6.5). The warm, swollen leg (c) and mild temperature (e) are unchanged findings of her cellulitis. Having no known allergies (f) does not rule out a first reaction and needs no action in itself.

11. [CORE] The nurse analyzes the cues. Which explanation best fits Ms. Okonkwo's findings?

a. Sepsis from cellulitis that is causing low blood pressure and fast breathing

b. A panic attack triggered by worry about her hospital admission

c. Anaphylaxis to the IV antibiotic started 8 minutes earlier

d. A vasovagal reaction caused by the insertion of her IV catheter

Answer: c — Sudden skin and mucosal signs together with breathing difficulty and low blood pressure within minutes of a new IV drug meet the WAO criteria for anaphylaxis (c) (section 6.5). Sepsis (a) does not cause hives, lip swelling and wheeze within minutes of a drug. A panic attack (b) does not cause hypotension, welts or swelling. A vasovagal reaction (d) causes a slow heart rate and pallor, not tachycardia, wheeze and angioedema.

12. [CORE] Which problem is the priority for Ms. Okonkwo?

a. Nausea and the risk of aspiration if she vomits
b. Airway compromise and shock from anaphylaxis
c. Spread of infection from the cellulitis
d. Anxiety about her sudden change in condition

Answer: b — A swelling airway, bronchospasm and hypotension can lead to respiratory and cardiac arrest within minutes, so airway and circulation come first (b) (section 6.5). Nausea (a) and anxiety (d) are real but are part of the reaction and improve when it is treated. The cellulitis (c) still needs treatment, but it is not the immediate threat.

13. [CORE] Which actions should the nurse take now? Select all that apply.

a. Stop the antibiotic infusion and disconnect the tubing
b. Call for help and activate the rapid response team
c. Give IM epinephrine into the mid-anterolateral thigh per the medical directive
d. Give an oral antihistamine and recheck her in 15 minutes
e. Help her stand at the bedside to ease her breathing
f. Flush the IV line quickly to keep it open
g. Raise the head of the bed while keeping her legs up, and give oxygen

Answer: a, b, c, g — Stopping the trigger (a), calling for help (b), giving IM epinephrine at once (c) and positioning for breathing while supporting circulation, with oxygen (g), are first actions (Table 6.4). An antihistamine (d) does not treat breathing or circulation problems and must not delay epinephrine. Standing or sitting up suddenly (e) can cause collapse. Flushing the line (f) would push the antibiotic left in the tubing into her vein; the tubing is disconnected and access kept with a new line.

14. [CORE] The nurse prepares epinephrine from a 1 mg/mL ampoule. Which order is correct for Ms. Okonkwo's first dose?

a. 0.5 mL of the 1 mg/mL solution, IV push over 1 minute
b. 5 mL of the 1 mg/mL solution, IM into the deltoid
c. 0.5 mL of the 1 mg/mL solution, injected subcutaneously into the abdomen
d. 0.5 mL of the 1 mg/mL solution, IM into the mid-anterolateral thigh

Answer: d — The standard adult dose is 0.5 mg, which is 0.5 mL of the 1 mg/mL solution, given IM into the mid-anterolateral thigh (d) (Medications box). The IM dose must never be given IV (a), because it can cause a sharp rise in blood pressure and bleeding in the brain. Option b is ten times the dose and uses a site that is not recommended. The subcutaneous route (c) is not the recommended route.

15. [CORE] At 1440 the nurse evaluates Ms. Okonkwo after two doses of epinephrine, oxygen and an IV fluid bolus. Which findings best show that treatment is effective?

a. Blood pressure 116/70 mm Hg, no wheezes, normal voice, oxygen saturation 96%
b. Heart rate 112 with palpitations, and she says she feels anxious
c. Hives fading after an antihistamine, blood pressure 88/50 mm Hg
d. Calm and drowsy, respiratory rate 10, oxygen saturation 89%

Answer: a — A restored blood pressure, cleared wheeze, normal voice and good oxygen saturation (a) show that perfusion and the airway have improved (section 6.5). A fast heart rate, palpitations and anxiety (b) are expected effects of epinephrine and do not show whether the reaction is controlled. Fading hives with persistent hypotension (c) mean the reaction is not controlled. Drowsiness with slow breathing and low saturation (d) signals deterioration and needs escalation.

16. [CORE] On the evening after a bowel resection, a patient's heart rate has risen from 82 to 114 over 4 hours. Blood pressure has changed from 128/78 to 116/94 mm Hg. The patient is restless and the skin is cool. The abdominal dressing is dry. Which interpretation is correct?

a. The findings are reassuring because the blood pressure is still above 90 mm Hg systolic
b. The patient may be bleeding and is compensating; this needs urgent escalation
c. The restlessness is most likely pain, so analgesia is the first step
d. A dry dressing shows that the drop in blood pressure has another cause

Answer: b — A rising heart rate, a pulse pressure that has narrowed from 50 to 22, cool skin and restlessness are early cues of hypovolemic shock while blood pressure is still maintained (b) (section 6.4). Hypotension is a late sign (a). Pain (c) does not explain the narrowing pulse pressure and cool skin, and assuming pain delays escalation. Bleeding can be internal, so a dry dressing (d) does not rule it out.

17. [CORE] A patient with an acute MI has blood pressure 82/54 mm Hg, cool clammy skin and confusion. A chest X-ray shows pulmonary congestion, and oxygen saturation has fallen from 95% to 89%. Which action by the nurse is most appropriate?

a. Lower the head of the bed flat and raise the legs to improve venous return
b. Start a rapid 1 L crystalloid bolus under an existing order for "fluid for hypotension"
c. Escalate urgently and report the congestion before any fluid is given
d. Encourage oral fluids to correct the low blood pressure

Answer: c — This is cardiogenic shock with congestion. Fluids are given cautiously, and a fluid challenge is tried only when there are no signs of congestion, so the nurse escalates urgently and reports the congestion before any fluid (c) (section 6.4). Lying flat with legs raised (a) adds to the load on the failing heart and worsens breathing. A rapid 1 L bolus (b) can worsen pulmonary congestion. Oral fluids (d) will not correct shock and are unsafe in a confused patient.

18. [CORE] A patient admitted after a fall has a new spinal cord injury at the level of the sixth cervical vertebra. Blood pressure is 82/48 mm Hg and heart rate 48. Which type of shock best fits these findings?

a. Neurogenic shock from loss of sympathetic tone
b. Hypovolemic shock from bleeding at the injury site
c. Cardiogenic shock from a heart attack during the fall
d. Obstructive shock from a tension pneumothorax

Answer: a — Hypotension with a slow heart rate after a cervical cord injury fits neurogenic shock, caused by loss of sympathetic output and unopposed parasympathetic activity (a) (section 6.5). Hypovolemic shock (b) usually causes a fast heart rate. Cardiogenic shock (c) and tension pneumothorax (d) typically cause tachycardia and other cues, such as congestion or sudden breathlessness, that are not described.

19. [CORE] Four hours after cardiac surgery, a patient's chest tube drainage suddenly stops. Blood pressure falls to 78/50 mm Hg, the neck veins are distended and the heart sounds are muffled. What should the nurse do first?

a. Milk and strip the chest tube to restore drainage and recheck in 30 minutes

b. Give a fluid bolus and reassess the blood pressure before calling the surgeon

c. Document the findings and continue to monitor every 15 minutes

d. Call for immediate help as policy directs and report suspected tamponade

Answer: d — Hypotension, distended neck veins and muffled heart sounds (Beck's triad) after cardiac surgery suggest cardiac tamponade, which needs immediate escalation for drainage (d) (section 6.5). Waiting 30 minutes (a) or monitoring alone (c) delays life-saving treatment, and stripping a chest tube is not a substitute for escalation. Fluids (b) should not delay drainage.

20. [CORE] Which patient meets the clinical criteria for septic shock?

a. Pneumonia, lactate 1.4 mmol/L, MAP 70 mm Hg after 2 L of crystalloid

b. Urinary infection, lactate 3.4 mmol/L, MAP 64 mm Hg after adequate fluids, norepinephrine started to reach 65 mm Hg

c. Cellulitis, lactate 2.8 mmol/L, MAP 68 mm Hg after adequate fluids, no vasopressor needed

d. Abdominal infection, lactate 2.4 mmol/L, MAP 60 mm Hg before any fluids have been given

Answer: b — Septic shock requires a vasopressor to keep the MAP at 65 mm Hg or higher and a lactate above 2 mmol/L despite adequate fluids (b) (section 6.5; Chapter 4, section 4.6). Patient a has a normal lactate and needs no vasopressor. Patient c needs no vasopressor. Patient d has not yet had fluid resuscitation.

21. [CORE] A patient in septic shock is receiving norepinephrine through a peripheral IV in the forearm. Which action by the nurse is correct?

a. Flush the norepinephrine line with saline each hour to keep it patent

b. Give an IV antibiotic through the norepinephrine line to avoid another IV start

c. Inspect the site often and stop the infusion into that site if swelling or blanching appears

d. Stop the norepinephrine at once when the MAP reaches 75 mm Hg

Answer: c — The nurse inspects a peripheral vasopressor site often and acts at once on extravasation according to policy (c) (section 6.6). Flushing the line (a) or pushing another drug through it (b) would push the vasopressor in the tubing into the patient faster than intended. A vasopressor is reduced gradually as ordered, never stopped abruptly (d).

22. [CORE] A patient in shock weighs 80 kg. Urine output was 30 mL in each of the past 2 hours. Which interpretation is correct?

a. Output is below 0.5 mL/kg/h, a sign of poor kidney perfusion that should be reported

b. Output is adequate because it is at least 30 mL in every hour

c. Output cannot be judged until a full 24-hour total is available

d. Output is low only if the patient also has a raised serum potassium

Answer: a — For an 80 kg patient, 0.5 mL/kg/h is 40 mL/h, so 30 mL/h is below it and signals underperfused kidneys (a) (section 6.6). A fixed 30 mL/h threshold (b) ignores body weight. Hourly output is the measure used in shock; waiting 24 hours (c) delays action. Low output is significant on its own (d).

23. [CORE] An 81-year-old who takes a beta-blocker and has long-standing hypertension (usual blood pressure 150/86 mm Hg) has had a GI bleed. Heart rate is 84 and blood pressure 106/64 mm Hg. She is newly confused. Which interpretation is best?

a. Her vital signs are within normal limits, so the confusion is probably delirium from an unfamiliar setting

b. A heart rate of 84 shows that she is not losing a significant amount of blood

c. Her blood pressure is well above 90 mm Hg systolic, so shock is unlikely

d. She may be in shock: the beta-blocker can blunt tachycardia, and her pressure is well below her usual

Answer: d — Beta-blockers weaken the heart rate response to blood loss, and a pressure of 106/64 mm Hg is far below her usual 150/86 mm Hg; new confusion may reflect poor brain perfusion (d) (Lifespan Considerations box). Assuming delirium (a) or relying on the heart rate (b) or a systolic cut-off of 90 mm Hg (c) could miss shock in an older adult.

24. [CORE] The nurse teaches a patient who has been prescribed an epinephrine autoinjector after anaphylaxis. Which statement shows the patient understands?

a. "If I use the autoinjector and feel better, I won't need to go to the hospital."

b. "I will use it at the first sign of a reaction, call 9-1-1, and go to the hospital even if I feel better."

c. "I will take an antihistamine first and use the autoinjector only if that doesn't work."

d. "I will keep it in the refrigerator so that it lasts longer."

Answer: b — Epinephrine is used as soon as a reaction starts, whether known or suspected, followed by a call to 9-1-1 and a hospital visit even if symptoms ease, because they can return (b) (Patient Education box). Skipping hospital care (a) misses a biphasic reaction. An antihistamine (c) must never delay epinephrine. Autoinjectors are kept at room temperature, not refrigerated (d).

25. [CORE] An RPN on a surgical unit finds that a patient's heart rate has risen from 88 to 122 since the last check, the blood pressure has fallen from 124/76 to 98/80 mm Hg, and the drain has filled with bright red blood. The RN assigned to the team is on a break. What should the RPN do?

a. Recheck the vital signs in 30 minutes, then report to the RN when the RN returns

b. Change the drain bag and record the volume, then continue the rest of the assessment

c. Call for help at once as policy directs, and inform the RN

d. Ask the patient's family to watch for any further change while the RPN finishes other care

Answer: c — Every nurse who notices deterioration acts at once and escalates; the RPN calls for help directly, through the rapid response team or the most responsible provider as policy directs, and consults the RN as the patient's needs change (c) (section 6.4; Chapter 1, section 1.3). Waiting for the RN (a), focusing on the drain (b) or delegating monitoring to the family (d) delays care for likely hemorrhagic shock.

26. [CORE] A hospital's anaphylaxis medical directive authorizes nurses who have completed its anaphylaxis education to give IM epinephrine. An RPN who has completed that education finds a patient in anaphylaxis. Which statement about the RPN's scope is correct?

a. The RPN may give the epinephrine under the directive, because the RPN has the authority, competence and context to do so

b. The RPN must wait for an RN to give the epinephrine, because only RNs can act in emergencies

c. The RPN may give the epinephrine only after a physician gives a verbal order for this patient

d. The RPN may not give the epinephrine, because the patient's condition is unstable

Answer: a — Under CNO's Scope of Practice standard, the RPN considers authority (here, the medical directive), competence (the completed education) and context; with all three in place, the RPN can act (a) (section 6.5; Chapter 1, section 1.3). Nothing limits emergency action to RNs (b). The directive provides the authority, so a separate verbal order is not required (c). Patient instability does not bar an RPN from life-saving action authorized by a directive (d); employer policy and province or territory matter.

27. [RN] Which hemodynamic pattern is typical of distributive shock?

a. Low cardiac output, high filling pressures and high SVR

b. Low cardiac output, low filling pressures and high SVR

c. Low cardiac output with high right-sided pressures

d. Low SVR with a normal or high cardiac output

Answer: d — Distributive shock is caused by loss of vascular tone, which lowers SVR; cardiac output is usually normal or high (d) (Going Deeper box). Option a describes cardiogenic shock, option b hypovolemic shock and option c obstructive shock from pulmonary embolism.

28. [RN] An ICU nurse is titrating norepinephrine to a MAP target of 65 mm Hg. The MAP is now 78 mm Hg. Which action follows safe titration principles?

a. Stop the infusion now, because the MAP is above target, and recheck it in 15 minutes

b. Reduce the rate in a small step within the ordered limits and recheck the blood pressure within minutes

c. Leave the rate unchanged until the next scheduled vital signs

d. Reduce the rate to half and recheck the MAP in 1 hour

Answer: b — Titration uses small steps within the ordered limits, with frequent rechecks (b) (Going Deeper box). Stopping abruptly (a) or making a large cut (d) can cause rebound hypotension, and waiting an hour misses the response. Leaving the rate unchanged (c) ignores the order to titrate to the target.

29. [RN] Why does a patient in hypovolemic or cardiogenic shock usually have cool, pale skin?

a. Systemic vascular resistance falls, so blood pools in the skin

b. Cardiac output rises, which moves heat away from the skin too quickly

c. Vasoconstriction raises systemic vascular resistance and diverts blood away from the skin

d. The skin receives more blood than usual, but the blood carries less oxygen

Answer: c — When cardiac output falls, the sympathetic system constricts vessels, raising SVR and moving blood away from the skin toward vital organs (c) (Going Deeper box). Falling SVR (a) is the distributive pattern. Cardiac output falls in these types of shock (b). Skin blood flow falls, not rises (d).

30. [RN] A patient's heart rate is 125 beats/min and stroke volume is 40 mL. Which statement is correct?

a. Cardiac output is 5.0 L/min; the fast heart rate is keeping cardiac output up despite a low stroke volume

b. Cardiac output is 3.1 L/min; the patient's stroke volume is normal for an adult

c. Cardiac output is 50 L/min, which is very high and suggests distributive shock

d. Cardiac output cannot be calculated without knowing the systemic vascular resistance

Answer: a — Cardiac output equals heart rate times stroke volume: 125 × 40 mL = 5,000 mL, or 5.0 L/min (a). The tachycardia is compensating for a low stroke volume (Going Deeper box). Option b uses the wrong product and calls a low stroke volume normal. Option c misplaces the decimal. SVR is not needed to calculate cardiac output (d).

References

Andersen, L. W., Kim, W. Y., Chase, M., Berg, K. M., Mortensen, S. J., Moskowitz, A., Novack, V., Cocchi, M. N., Donnino, M. W., & American Heart Association's Get With The Guidelines–Resuscitation Investigators. (2016). The prevalence and significance of abnormal vital signs prior to in-hospital cardiac arrest. *Resuscitation, 98*, 112–117. https://doi.org/10.1016/j.resuscitation.2015.08.016

Association des allergologues et immunologues du Québec. (2020). *Anaphylaxis emergency plan* [Form]. Canadian Society of Allergy and Clinical Immunology. https://csaci.ca/wp-content/uploads/2020/08/Anaphylaxis_Emergency_Plan_with_EpiPen_and_ALLERJECT_instructions_May-2020_a.pdf

Brown, J. B., Gestring, M. L., Forsythe, R. M., Stassen, N. A., Billiar, T. R., Peitzman, A. B., & Sperry, J. L. (2015). Systolic blood pressure criteria in the National Trauma Triage Protocol for geriatric trauma: 110 is the new 90. *Journal of Trauma and Acute Care Surgery*, *78*(2), 352–359. https://doi.org/10.1097/TA.0000000000000523

Callum, J. L., Yeh, C. H., Petrosoniak, A., McVey, M. J., Cope, S., Thompson, T., Chin, V., Karkouti, K., Nathens, A. B., Murto, K., Beno, S., Pendergrast, J., McDonald, A., MacDonald, R., Adhikari, N. K. J., Alam, A., Arnold, D., Barratt, L., Beckett, A., … Pavenski, K. (2019). A regional massive hemorrhage protocol developed through a modified Delphi technique. *CMAJ Open*, *7*(3), E546–E561. https://doi.org/10.9778/cmajo.20190042

Canadian Association of Emergency Physicians. (2026). *CTAS National Advisory Committee* [2025–2026 annual report]. https://www.caep.ca/2026-annual-report/ctas-nac-committee

Cardona, V., Ansotegui, I. J., Ebisawa, M., El-Gamal, Y., Fernandez Rivas, M., Fineman, S., Geller, M., Gonzalez-Estrada, A., Greenberger, P. A., Sanchez Borges, M., Senna, G., Sheikh, A., Tanno, L. K., Thong, B. Y., Turner, P. J., & Worm, M. (2020). World Allergy Organization anaphylaxis guidance 2020. *World Allergy Organization Journal*, *13*(10), Article 100472. https://doi.org/10.1016/j.waojou.2020.100472

Cecconi, M., De Backer, D., Antonelli, M., Beale, R., Bakker, J., Hofer, C., Jaeschke, R., Mebazaa, A., Pinsky, M. R., Teboul, J. L., Vincent, J. L., & Rhodes, A. (2014). Consensus on circulatory shock and hemodynamic monitoring. Task force of the European Society of Intensive Care Medicine. *Intensive Care Medicine, 40*, 1795–1815. https://doi.org/10.1007/s00134-014-3525-z

Chioncel, O., Parissis, J., Mebazaa, A., Thiele, H., Desch, S., Bauersachs, J., Harjola, V.-P., Antohi, E.-L., Arrigo, M., Ben Gal, T., Celutkiene, J., Collins, S. P., DeBacker, D., Iliescu, V. A., Jankowska, E., Jaarsma, T., Keramida, K., Lainscak, M., Lund, L. H., … Seferovic, P. (2020). Epidemiology, pathophysiology and contemporary management of cardiogenic shock: A position statement from the Heart Failure Association of the European Society of Cardiology. *European Journal of Heart Failure*, *22*(8), 1315–1341. https://doi.org/10.1002/ejhf.1922

Cretikos, M. A., Bellomo, R., Hillman, K., Chen, J., Finfer, S., & Flabouris, A. (2008). Respiratory rate: The neglected vital sign. *Medical Journal of Australia, 188*(11), 657–659. https://doi.org/10.5694/j.1326-5377.2008.tb01825.x

Critical Care Services Ontario. (n.d.). *Critical Care Services Ontario*. Retrieved October 25, 2026, from https://criticalcareontario.ca/

Douw, G., Schoonhoven, L., Holwerda, T., Huisman-de Waal, G., van Zanten, A. R. H., van Achterberg, T., & van der Hoeven, J. G. (2015). Nurses' worry or concern and early recognition of deteriorating patients on general wards in acute care hospitals: A systematic review. *Critical Care, 19*, Article 230. https://doi.org/10.1186/s13054-015-0950-5

Eden, E. L., Rack, L. L., Chen, L. W., & Bump, G. M. (2017). Condition Help: A patient- and family-initiated rapid response system. *Journal of Hospital Medicine, 12*(3), 157–161. https://doi.org/10.12788/jhm.2697

Fernando, S. M., Fox-Robichaud, A. E., Rochwerg, B., Cardinal, P., Seely, A. J. E., Perry, J. J., McIsaac, D. I., Tran, A., Skitch, S., Tam, B., Hickey, M., Reardon, P. M., Tanuseputro, P., & Kyeremanteng, K. (2019). Prognostic accuracy of the Hamilton Early Warning Score (HEWS) and the National Early Warning Score 2 (NEWS2) among hospitalized patients assessed by a rapid response team. *Critical Care, 23*, Article 60. https://doi.org/10.1186/s13054-019-2355-3

Gandevia, S. C., & McKenzie, D. K. (2008). Respiratory rate: The neglected vital sign [Letter to the editor]. *Medical Journal of Australia, 189*(9), 531–532. https://doi.org/10.5694/j.1326-5377.2008.tb02165.x

Haig, K. M., Sutton, S., & Whittington, J. (2006). SBAR: A shared mental model for improving communication between clinicians. *Joint Commission Journal on Quality and Patient Safety, 32*(3), 167–175. https://doi.org/10.1016/S1553-7250(06)32022-3

Hands, C., Reid, E., Meredith, P., Smith, G. B., Prytherch, D. R., Schmidt, P. E., & Featherstone, P. I. (2013). Patterns in the recording of vital signs and early warning scores: Compliance with a clinical escalation protocol. *BMJ Quality & Safety, 22*(9), 719–726. https://doi.org/10.1136/bmjqs-2013-001954

Harper, N. J. N., Cook, T. M., Garcez, T., Farmer, L., Floss, K., Marinho, S., Torevell, H., Warner, A., Ferguson, K., Hitchman, J., Egner, W., Kemp, H., Thomas, M., Lucas, D. N., Nasser, S., Karanam, S., Kong, K.-L., Farooque, S., Bellamy, M., & McGuire, N. (2018). Anaesthesia, surgery, and life-threatening allergic reactions: Epidemiology and clinical features of perioperative anaphylaxis in the 6th National Audit Project (NAP6). *British Journal of Anaesthesia*, *121*(1), 159–171. https://doi.org/10.1016/j.bja.2018.04.014

Health Canada. (n.d.). *Drug Product Database*. Retrieved October 25, 2026, from https://health-products.canada.ca/dpd-bdpp/

Institute for Safe Medication Practices Canada. (2014). Multiple IV infusions: Risks and recommendations. *Ontario Critical Incident Learning*, (11). https://www.ismp-canada.org/download/ocil/ISMPCONCIL2014-11_MultipleIV-Infusions.pdf

Jensen, J. K., Poulsen, S. H., & Mølgaard, H. (2017). Cardiac tamponade: A clinical challenge. *E-Journal of Cardiology Practice*, *15*(17). https://escardio.org/Journals/E-Journal-of-Cardiology-Practice/Volume-15/Cardiac-tamponade-a-clinical-challenge

Juno Pharmaceuticals. (2023). *Norepinephrine bitartrate injection 1 mg/mL* [Prescribing information]. https://pdf.hres.ca/dpd_pm/00076038.PDF

Koczmara, C., Jelincic, V., & Perri, D. (2006). Communication of medication orders by telephone: "Writing it right." *Dynamics, 17*(1), 20–24. https://www.ismp-canada.org/download/caccn/CACCN-Spring06.pdf

Leigh-Smith, S., & Davies, G. (2003). Tension pneumothorax: Eyes may be more diagnostic than ears. *Emergency Medicine Journal*, *20*(5), 495–496. https://doi.org/10.1136/emj.20.5.495

Li, L. D. X., Abrams, E. M., Lavine, E., Hildebrand, K., & Mack, D. P. (2021). CSACI position statement: Transition recommendations on existing epinephrine autoinjectors. *Allergy, Asthma & Clinical Immunology*, *17*, Article 130. https://doi.org/10.1186/s13223-021-00634-2

Meaney, E., Alva, F., Moguel, R., Meaney, A., Alva, J., & Webel, R. (2000). Formula and nomogram for the sphygmomanometric calculation of the mean arterial pressure. *Heart, 84*(1), 64. https://doi.org/10.1136/heart.84.1.64

Murray, M., Bullard, M., & Grafstein, E. (2004). Revisions to the Canadian Emergency Department Triage and Acuity Scale implementation guidelines. *Canadian Journal of Emergency Medicine, 6*(6), 421–427. https://doi.org/10.1017/S1481803500009428

Mylan Specialty. (2024). *EpiPen and EpiPen Jr (epinephrine injection USP) auto-injectors* [Product monograph]. Pfizer Canada. https://pdf.hres.ca/dpd_pm/00075941.PDF

Müller, M., Jürgens, J., Redaèlli, M., Klingberg, K., Hautz, W. E., & Stock, S. (2018). Impact of the communication and patient hand-off tool SBAR on patient safety: A systematic review. *BMJ Open, 8*(8), Article e022202. https://doi.org/10.1136/bmjopen-2018-022202

Parsons, S., Elliott, C., & Murray, B. (2015, October 1). The Code Help project. *Canadian Nurse*. https://community.cna-aiic.ca/dev-cn-en/blogs/cn-content/2015/10/01/the-code-help-project

Prescott, H. C., Antonelli, M., Alhazzani, W., Møller, M. H., Alshamsi, F., Azevedo, L. C. P., Belley-Cote, E., De Waele, J., Derde, L., Dionne, J. C., Evans, L., Gershengorn, H. B., Hodgson, C. L., Honarmand, K., Kesecioglu, J., McIntyre, L., Mer, M., Nunnally, M. E., Oczkowski, S. J. W., … Coopersmith, C. M. (2026). Surviving Sepsis Campaign: International guidelines for management of sepsis and septic shock 2026. *Intensive Care Medicine, 52*(5), 863–936. https://doi.org/10.1007/s00134-026-08361-1

Public Health Agency of Canada. (2023a). *Anaphylaxis and other acute reactions following vaccination: Canadian Immunization Guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-2-vaccine-safety/page-4-early-vaccine-reactions-including-anaphylaxis.html

Public Health Agency of Canada. (2023b). *Dosage of intramuscular EPINEPHrine 1:1000 (1 mg/mL) solution, by age or weight*. https://www.canada.ca/en/public-health/services/publications/vaccines-immunization/dosage-intramuscular-epinephrine-solution-age-weight.html

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43.

Roberts, D. J., Leigh-Smith, S., Faris, P. D., Blackmore, C., Ball, C. G., Robertson, H. L., Dixon, E., James, M. T., Kirkpatrick, A. W., Kortbeek, J. B., & Stelfox, H. T. (2015). Clinical presentation of patients with tension pneumothorax: A systematic review. *Annals of Surgery*, *261*(6), 1068–1078. https://doi.org/10.1097/SLA.0000000000001073

Royal College of Physicians. (2017). *National Early Warning Score (NEWS) 2: Standardising the assessment of acute-illness severity in the NHS* [Updated report of a working party]. https://www.rcp.ac.uk/improving-care/resources/national-early-warning-score-news-2/

Salenieks, M. E., & Reynolds, S. F. (2008). Critical care response team. *ICU Management & Practice, 8*(1). https://healthmanagement.org/c/icu/IssueArticle/5248

Schiller, A. M., Howard, J. T., & Convertino, V. A. (2017). The physiology of blood loss and shock: New insights from a human laboratory model of hemorrhage. *Experimental Biology and Medicine, 242*(8), 874–883. https://doi.org/10.1177/1535370217694099

SCIRE Professional. (2022). *Neurogenic shock*. Spinal Cord Injury Research Evidence. https://scireproject.com/evidence/cardiovascular-complications-acute-phase/cardiovascular-complications/neurogenic-shock/

Silber, J. H., Williams, S. V., Krakauer, H., & Schwartz, J. S. (1992). Hospital and patient characteristics associated with death after surgery: A study of adverse occurrence and failure to rescue. *Medical Care, 30*(7), 615–629. https://doi.org/10.1097/00005650-199207000-00004

Singer, M., Deutschman, C. S., Seymour, C. W., Shankar-Hari, M., Annane, D., Bauer, M., Bellomo, R., Bernard, G. R., Chiche, J.-D., Coopersmith, C. M., Hotchkiss, R. S., Levy, M. M., Marshall, J. C., Martin, G. S., Opal, S. M., Rubenfeld, G. D., van der Poll, T., Vincent, J.-L., & Angus, D. C. (2016). The Third International Consensus Definitions for Sepsis and Septic Shock (Sepsis-3). *JAMA*, *315*(8), 801–810. https://doi.org/10.1001/jama.2016.0287

Skitch, S., Tam, B., Xu, M., McInnis, L., Vu, A., & Fox-Robichaud, A. (2018). Examining the utility of the Hamilton early warning scores (HEWS) at triage: Retrospective pilot study in a Canadian emergency department. *Canadian Journal of Emergency Medicine, 20*(2), 266–274. https://doi.org/10.1017/cem.2017.21

Standl, T., Annecke, T., Cascorbi, I., Heller, A. R., Sabashnikov, A., & Teske, W. (2018). The nomenclature, definition and distinction of types of shock. *Deutsches Ärzteblatt International, 115*(45), 757–768. https://doi.org/10.3238/arztebl.2018.0757

Toronto Rehabilitation Institute. (2010). *SBAR: A shared structure for effective team communication. An implementation toolkit* (2nd ed.). https://uhn.ca/torontorehab/education/sbar/documents/sbar_toolkit.pdf

Tran, A., Fernando, S. M., McIsaac, D. I., Rochwerg, B., Mok, G., Seely, A. J. E., Kubelik, D., Inaba, K., Kim, D. Y., Reardon, P. M., Shen, J., Tanuseputro, P., Thavorn, K., & Kyeremanteng, K. (2020). Predictors of mortality and cost among surgical patients requiring rapid response team activation. *Canadian Journal of Surgery, 63*(6), E598–E605. https://doi.org/10.1503/cjs.017319

van Diepen, S., Katz, J. N., Albert, N. M., Henry, T. D., Jacobs, A. K., Kapur, N. K., Kilic, A., Menon, V., Ohman, E. M., Sweitzer, N. K., Thiele, H., Washam, J. B., & Cohen, M. G. (2017). Contemporary management of cardiogenic shock: A scientific statement from the American Heart Association. *Circulation*, *136*(16), e232–e268. https://doi.org/10.1161/CIR.0000000000000525

Vincent, J.-L., & De Backer, D. (2013). Circulatory shock. *New England Journal of Medicine, 369*(18), 1726–1734. https://doi.org/10.1056/NEJMra1208943

Wounds International. (2023). *Wound care and skin tone made easy*. https://woundsinternational.com/wp-content/uploads/2023/05/MULTI23_ME_SkinTones_WINT-web.pdf

Xu, M., Tam, B., Thabane, L., & Fox-Robichaud, A. (2015). A protocol for developing early warning score models from vital signs data in hospitals using ensembles of decision trees. *BMJ Open, 5*(9), Article e008699. https://doi.org/10.1136/bmjopen-2015-008699

II Cross-Cutting Clinical Priorities in Adult Care

UNIT CLINICAL SCOPE & INTEGRATION

Addresses five clinical domains that intersect every adult medical-surgical inpatient unit: safe perioperative and perianesthesia nursing care, age-friendly acute care for older adults (delirium, dementia, falls, and polypharmacy), medical-surgical oncology and systemic therapy safety, palliative care and Medical Assistance in Dying (MAID), and trauma-informed substance use care and harm reduction.

Contents of UNIT II

Chapter	Chapter Title	Visual Assets	Page
Chapter 7	Perioperative Nursing	4 Figs • 4 Tbls	p. 179
Chapter 8	Older Adults in Acute Care	3 Figs • 4 Tbls	p. 206
Chapter 9	Cancer Care	6 Figs • 3 Tbls	p. 234
Chapter 10	Palliative and End-of-Life Care	0 Figs • 3 Tbls	p. 264
Chapter 11	Substance Use in Acute Care	4 Figs • 3 Tbls	p. 290

07 Perioperative Nursing

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Describe the phases of perioperative care, the settings in which surgery happens and the perioperative team.
2. Complete a focused preoperative assessment, including medications, frailty, obstructive sleep apnea and anesthesia risk.
3. Prepare patients for surgery, including fasting, skin preparation, teaching and the preoperative checklist.
4. Explain the nurse's role in informed consent and in the Surgical Safety Checklist.
5. Compare types of anesthesia and sedation, and recognize anesthesia emergencies.
6. Provide safe postanesthesia care, including airway, temperature, postoperative nausea and vomiting, pain and handover.
7. Prevent, recognize and escalate common postoperative complications, including venous thromboembolism, using enhanced recovery principles.
8. Distinguish RN and RPN roles in perioperative care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 5	Clinician; Scholar	Foundations of Practice
3, 6, 7	Clinician; Educator; Coordinator	Foundations of Practice; Collaborative Practice
4, 8	Advocate; Professional; Collaborator	Legal Practice; Professional Practice

Introduction

Surgery touches the lives of many adults in Canada. One person walks into a day surgery clinic for cataract removal and is home by supper. Another is admitted for a knee replacement, and a third arrives through the emergency department needing an operation that cannot wait. Whatever the procedure, the patient's safety depends on careful preparation, clear communication and close monitoring before, during and after the operation.

Perioperative nursing is the care nurses give across this whole span. Nurses work in preadmission clinics, same-day surgery units, operating rooms, postanesthesia care units, surgical inpatient units and the community. In every setting, the nurse assesses, teaches, advocates and watches for early signs that something is going wrong.

This chapter follows the patient through surgery. Section 7.1 describes the perioperative journey and the team. Section 7.2 covers preoperative assessment and preparation, and Section 7.3 covers consent, the day of surgery and the Surgical Safety Checklist. Sections 7.4 to 7.6 continue with anesthesia and sedation, postanesthesia care, postoperative complications, venous thromboembolism (VTE) prophylaxis and enhanced recovery after surgery (ERAS). Related topics live elsewhere: consent, scope and teamwork (Chapter 1), surgical site infection (Chapter 4), pain (Chapter 5), deterioration and shock (Chapter 6), delirium (Chapter 8), VTE treatment (Chapter 19), bowel surgery and ostomies (Chapter 25) and orthopedic surgery (Chapter 33).

7.1 The Perioperative Journey

Three Phases

Nurses usually describe surgery in three phases. The **preoperative** phase starts when the patient and surgeon decide to operate and ends when the patient is transferred to the operating room (OR). The **intraoperative** phase covers the time in the OR, from arrival to

transfer to the recovery area. The **postoperative** phase begins with admission to the recovery area and continues until the patient has recovered, whether in hospital, at home or both.

Most patients wake in a **postanesthesia care unit (PACU)**, a unit that gives short-term care immediately after operations and invasive procedures (British Columbia Ministry of Health, 2024). The Canadian Anesthesiologists' Society (CAS) guidelines require one in every facility that provides anesthesia (Dobson et al., 2026). PACU care is often described in phases: Phase I is close, continuous monitoring as the patient emerges from anesthesia, and Phase II is lighter monitoring for stable patients nearing discharge criteria. The phase reflects the patient's physiological recovery, not the room they are in (College of Physicians and Surgeons of British Columbia [CPSBC], 2026). Postanesthesia care is taught in section 7.5.

Ambulatory surgery (day surgery) means the patient goes home on the day of the procedure, with written instructions and a responsible adult (Dobson et al., 2026). **Inpatient surgery** means the patient stays in hospital afterwards. Many patients having major elective surgery come in under **same-day admission**: they prepare at home, arrive on the morning of the operation and are admitted afterwards. Their teaching usually happens weeks earlier, so the nurse on the day of surgery checks that the preparation actually happened.

The Perioperative Team

Surgical care is teamwork, and the general principles of collaboration and scope are covered in Chapter 1, section 1.3. The surgical team includes several roles:

- **Surgeon:** decides with the patient whether to operate, obtains informed consent and performs the procedure.
- **Anesthesiologist:** assesses the patient, plans and gives the anesthetic, and directs early recovery. The CAS guidelines also recognize family practice anesthesia physicians, family physicians who have completed an accredited postgraduate anesthesia program, as anesthesia providers (Dobson et al., 2026).
- **Anesthesia assistant:** a formally designated team member with specific training in anesthesia assistance, whose tasks are approved by the department of anesthesia and the facility (Dobson et al., 2026).
- **Perioperative nurses:** the scrub nurse works within the sterile field, handling instruments and keeping counts; the circulating nurse works outside it, coordinating the room, documenting and advocating for a patient who cannot speak under anesthesia. The Operating Room Nurses Association of Canada (ORNAC) publishes national standards for perioperative nursing (ORNAC, 2023).
- **PACU, surgical unit and community nurses:** monitor emergence from anesthesia, then continue recovery care, teaching and discharge planning.

Access and Wait Times

Timely access is part of safe surgery. The Canadian Institute for Health Information (CIHI) reports wait times for priority procedures, including median and 90th percentile waits and the percentage of patients treated within benchmarks (CIHI, n.d.). For planned hip and knee replacement, the benchmark is surgery within 26 weeks (182 days) of the date the patient was ready to be treated; for cataract surgery, it is within 16 weeks (112 days). CIHI's indicator pages give these results for each province (CIHI, 2026a, 2026b). Waiting is also a chance to prepare: prehabilitation (section 7.2) can start early.

Where a person lives also shapes access. Many people in rural, remote and northern communities, including many First Nations, Inuit and Métis people, travel long distances for surgery, away from family and support (Chapter 1, section 1.2; Chapter 2). The nurse plans for travel, escorts, follow-up close to home and the cost of repeated trips.

7.2 Preoperative Assessment and Preparation

The Preoperative Assessment

The preoperative assessment finds risks that can be reduced and gives the teams what they need to plan. It may happen in a preadmission clinic, by telephone or on the day of surgery. The CAS guidelines direct the anesthesia history to include past medical and surgical problems, medications taken now and recently, drug reactions, past problems with anesthesia, and any family history of

reactions to anesthesia (Dobson et al., 2026). Family history matters because some serious reactions, such as malignant hyperthermia (discussed later in this chapter), are inherited. The nurse asks, "Has anyone in your family had a bad reaction to an anesthetic?" and records the answer exactly.

The nurse's assessment usually covers:

- **Heart and lungs:** chest pain, shortness of breath, palpitations, recent respiratory infection, and baseline vital signs and oxygen saturation.
- **Functional capacity:** how much activity the patient manages, such as climbing a flight of stairs without stopping.
- **Smoking, vaping, alcohol and other substance use:** asked without judgment (Chapter 11).
- **Possibility of pregnancy:** with testing when indicated by policy.
- **Cognition:** baseline memory, orientation and decision-making, so that later changes can be recognized and consent supported (section 7.3).
- **Supports:** who will drive the patient home and help afterwards, and barriers such as distance or cost.

Frailty is reduced physiological reserve that leaves a person less able to recover from a stressor such as surgery. It is common in older adults but is not the same as age. The Clinical Frailty Scale, a Canadian tool, is taught in Chapter 8. Identifying frailty early helps the team plan support from the start.

Obstructive sleep apnea (OSA) is repeated collapse of the upper airway during sleep, which interrupts breathing. Much OSA is undiagnosed (Chung et al., 2016), and it matters because anesthetics, sedatives and opioids relax the airway and blunt breathing. The **STOP-Bang** questionnaire, from the University Health Network in Toronto, is a quick screening tool with eight yes-or-no items. Four are questions: loud snoring, daytime tiredness, breathing pauses or choking noticed by someone else, and high blood pressure, treated or not. Four are facts: body mass index above 35 kg/m², age over 50 years, neck circumference above 40 cm, and male sex. Each "yes" scores one point. A score of 0 to 2 suggests low risk of moderate to severe OSA, 3 or 4 an intermediate risk, and 5 to 8 a high risk; certain combinations move an intermediate score to high (Chung et al., 2016). A high score does not diagnose OSA. It flags a patient the anesthesia team needs to know about.

The anesthesiologist summarizes overall health with the **American Society of Anesthesiologists (ASA) Physical Status** classification, which the CAS guidelines direct to be recorded for every patient (Dobson et al., 2026):

- **ASA I:** a healthy person.
- **ASA II:** mild systemic disease, such as well-controlled hypertension.
- **ASA III:** severe systemic disease, such as poorly controlled diabetes or chronic obstructive pulmonary disease.
- **ASA IV:** severe systemic disease that constantly threatens life, such as sepsis.
- **ASA V:** a critically ill patient who is expected to die without the operation.
- **ASA VI:** a person declared dead by neurological criteria whose organs are being recovered for donation.

Adding "E" marks emergency surgery, where delay would significantly increase the threat to life or a body part (Canadian Anesthesiologists' Society, 2025). The class describes the patient, not the risk of the operation.

Reviewing Medications

A complete medication history includes prescription and over-the-counter drugs, natural health products, and drugs taken only occasionally or by weekly injection. The nurse confirms each product with the patient and documents what was taken and when. Some medications continue through surgery and some are paused. **The plan for each medication comes from the prescriber or the anesthesia team, not the nurse.** The nurse finds the medications that matter, makes sure the team knows, and teaches the patient the plan (Table 7.1).

Anticoagulants and antiplatelet drugs force a trade-off: continuing them raises bleeding risk, and stopping them raises the risk of clots, stroke or stent thrombosis. The team weighs these risks for each patient, sometimes drawing on clinical guidance from Thrombosis Canada (Thrombosis Canada, n.d.). Anticoagulation is taught in Chapter 19.

Diabetes medications need a plan because fasting and surgical stress change glucose control (Chapter 22). Two newer drug classes need special attention. Health Canada reviewed reports of diabetic ketoacidosis (DKA) after surgery in people taking sodium-glucose cotransporter-2 (SGLT2) inhibitors, such as empagliflozin, dapagliflozin and canagliflozin; Health Canada recommends stopping these drugs temporarily before surgery, is working with manufacturers to update the Canadian product monographs, and recommends monitoring for DKA afterwards (Health Canada, n.d.-b). Glucagon-like peptide-1 (GLP-1) receptor agonists, such as semaglutide, dulaglutide, liraglutide and tirzepatide, slow stomach emptying. Health Canada found a possible link between these drugs and pulmonary aspiration during general anesthesia or deep sedation, and the CAS has warned that some patients taking them arrive with food still in the stomach despite fasting (Canadian Anesthesiologists' Society, 2023; Health Canada, n.d.-a).

The plan for opioids and opioid agonist treatment (OAT), such as methadone or buprenorphine, is made with the prescriber and pain team (Chapter 5). Every allergy is recorded with the reaction it caused, because a rash and anaphylaxis call for very different precautions (Chapter 6).

Table 7.1 Preoperative medication review: what to ask and why (Canadian Anesthesiologists' Society, 2023; Health Canada, n.d.-a, n.d.-b; Thrombosis Canada, n.d.)

Medication group	Examples	Why it matters	Nursing action
Anticoagulants	Warfarin, apixaban, rivaroxaban, dabigatran; heparins	Continuing them raises bleeding risk; stopping them raises clot risk	Ask what was taken and when; document; confirm the team's plan; teach the patient that plan
Antiplatelet drugs	Acetylsalicylic acid, clopidogrel, ticagrelor	Bleeding risk must be balanced against the risk of stent thrombosis or stroke	Ask about recent stents or heart attacks; document; confirm the plan with the prescriber or anesthesia team
Insulin	Long-acting and rapid-acting insulins	Fasting and surgical stress change insulin needs; risk of low or high glucose	Ask about usual doses and last dose; check glucose as ordered; confirm the plan; teach signs of low glucose
SGLT2 inhibitors	Empagliflozin, dapagliflozin, canagliflozin	Linked to diabetic ketoacidosis after surgery, including in patients who stopped the drug only shortly before	Ask about last dose; report if taken against instructions; watch for DKA after surgery as ordered
GLP-1 receptor agonists	Semaglutide, dulaglutide, liraglutide, tirzepatide	Slowed stomach emptying may leave food in the stomach despite fasting, raising aspiration risk	Ask specifically, including weekly injections and weight-loss use; make sure the anesthesia team knows
Opioids and opioid agonist treatment	Methadone, buprenorphine, prescribed opioids	Interruption risks withdrawal and poorly controlled pain	Confirm current treatment and prescriber; ensure the pain team knows; see Chapter 5
Natural health products	Herbal remedies, supplements, vitamins	Patients may not mention them; some can interact with prescribed drugs	Ask directly; document; let the pharmacist and anesthesia team review
All other regular medications	Blood pressure, heart, seizure and mental health drugs	Some are taken on the morning of surgery and some are not	Confirm each against the anesthesia team's instructions; document the last dose

CLINICAL JUDGMENT

A Medication Question on the Morning of Surgery

Gloria Tremblay, 68, arrives at 0630 for a scheduled bowel resection. She has type 2 diabetes. At her preadmission visit she was told to stop her SGLT2 inhibitor before surgery, and the instructions are in her chart.

- **Recognize cues:** While reviewing her medications, the nurse asks when she last took each one. Gloria says, "I took my usual pills yesterday morning. I forgot that one was supposed to stop." She is alert and oriented, with stable vital signs. She says she has been thirsty since starting her bowel preparation.
- **Analyze cues:** The drug was taken inside the window her team set. Fasting, bowel preparation and the stress of surgery all add to the risk of ketoacidosis described for this drug class.
- **Prioritize hypotheses:** The most important concern is that she could develop diabetic ketoacidosis around surgery. Other possibilities include dehydration from the bowel preparation.

- **Generate solutions:** The decision to proceed, delay or order tests belongs to the anesthesia team and surgeon. The nurse's options are to report promptly and clearly, and to have the information ready.
- **Take action:** The nurse calls the anesthesiologist and then the surgeon using SBAR (Situation, Background, Assessment, Recommendation; Chapter 6), giving the drug name, when it was last taken, the instructions she had received, her vital signs and her symptoms. The nurse carries out any orders, such as blood tests, and documents the conversation. The nurse reassures Gloria without blaming her.
- **Evaluate outcomes:** The nurse confirms that the plan is clear to the team and to Gloria and records it. If surgery is delayed, the nurse asks Gloria what made the instructions hard to follow, and helps the team find a clearer way to give them.

Tests Before Surgery

Preoperative tests should answer a question about the patient, not be ordered by routine. Choosing Wisely Canada's anesthesiology recommendations, developed with the CAS, advise against baseline blood work (complete blood count, coagulation tests or serum biochemistry) and against a baseline electrocardiogram (ECG) for people without symptoms having low-risk non-cardiac surgery. They also advise against a baseline chest X-ray for people without symptoms unless it is part of a surgical or cancer workup, and against resting echocardiography and cardiac stress testing for people without symptoms having non-cardiac surgery of low or intermediate risk (Choosing Wisely Canada, 2025). A careful history and physical examination usually find what routine tests would, and unneeded tests can lead to further testing that does not help. Tests are still done when the patient's conditions, medications or surgery call for them (Dobson et al., 2026).

Fasting and Carbohydrate Loading

Fasting before anesthesia lowers the chance that stomach contents will be inhaled into the lungs while protective reflexes are dulled. The current CAS guidelines set minimum fasting times before elective procedures: six hours after any meal that includes solid food, and two hours after clear fluids for adults, with separate times for infants and children. Unless there is a reason not to, the CAS encourages adults to keep drinking clear fluids, such as water, pulp-free juice, carbohydrate drinks, and black tea or coffee, until two hours before elective surgery (Dobson et al., 2026).

These are minimums, not targets. The old habit of "nothing by mouth after midnight" often leaves patients fasting far longer than needed, and the Enhanced Recovery After Surgery (ERAS) Society's colorectal guideline strongly recommends following modern fasting guidelines rather than fasting overnight (Gustafsson et al., 2019). Some patients, such as those taking GLP-1 receptor agonists, may be given different instructions. **The nurse teaches the patient to follow the anesthesia team's instructions** and, on the day of surgery, asks exactly what was eaten or drunk and when. Anything outside the instructions is reported to the anesthesia team, who decide what happens next.

In ERAS pathways, patients may be given a carbohydrate drink before surgery. The ERAS colorectal guideline strongly recommends these drinks, based on moderate evidence that they improve well-being and reduce insulin resistance and low-quality evidence that they reduce complications or speed recovery; the recommendation is weak for people with well-controlled diabetes or obesity (Gustafsson et al., 2019). The drink is given only as ordered on the pathway. ERAS is discussed later in the chapter.

Skin Preparation

The World Health Organization (WHO) regards a bath or shower with plain or antimicrobial soap before surgery as good clinical practice; the nurse teaches bathing as hospital policy directs. Hair is left in place unless it must be removed, and then only with clippers. WHO strongly discourages shaving at any time, whether before surgery or in the OR, because shaving carries a higher risk of surgical site infection than clipping or leaving hair in place (World Health Organization, 2018). Surgical site infection is taught in Chapter 4.

Prehabilitation and Teaching

Prehabilitation means improving a patient's physical and mental fitness in the weeks before surgery so they have more reserve to recover, often through exercise, nutrition and psychological support. The ERAS colorectal guideline found moderate evidence that multimodal prehabilitation improves functional capacity but low-quality evidence that it improves outcomes after surgery, so it is not yet a mandatory pathway element. Stopping smoking has stronger support: the guideline recommends stopping at least four weeks

before surgery to reduce lung and wound-healing complications (Gustafsson et al., 2019). The nurse offers cessation support at every contact.

The same guideline strongly recommends routine, dedicated preoperative counselling (Gustafsson et al., 2019). Teaching covers:

- **Deep breathing and coughing:** slow, deep breaths and effective coughs to open the small airways and clear secretions, with a pillow pressed over the incision (splinting) to reduce pain.
- **Incentive spirometer:** a hand-held device that shows the patient how deeply they are breathing in, encouraging slow, full breaths, if the hospital uses one (Figure 7.1).
- **Leg exercises:** ankle pumps and foot circles to keep blood moving in the legs while in bed.
- **Early mobilization:** sitting up, standing and walking as soon as the team allows, with help.



Figure 7.1 An incentive spirometer, which encourages slow, deep breaths after surgery.

- **The pain plan:** how pain will be assessed and treated, and why reporting it early helps (Chapter 5).
- **What to expect:** where the patient will wake up and what tubes or drains may be in place.

The nurse uses plain language, demonstrates, and asks the patient to explain or show the skill back (teach-back); pictures and short written steps help patients with limited literacy. For patients who prefer a language other than English, the nurse uses a qualified interpreter, not a family member (Chapter 1, section 1.7).

7.3 Consent and the Day of Surgery

The Nurse's Role in Consent

Informed consent for surgery is obtained by the surgeon, who explains the procedure, its risks and benefits, the alternatives, and what happens if the patient declines. The law on consent, capacity and substitute decision-makers in Ontario's *Health Care Consent Act, 1996*, is taught in Chapter 1, section 1.5; this section covers how that law plays out on the day of surgery.

The nurse's role is to check, not to obtain, consent. The nurse confirms that consent is documented, that the procedure and side named on the form match the booking and the patient's own words, and that the patient understands what will happen. A simple question works well: "Can you tell me in your own words what operation you are having today?" If the patient cannot describe it, has new questions about risks or alternatives, or says they feel pressured, the nurse tells the surgeon before the patient goes to the OR. The nurse does not try to explain the surgeon's part of the discussion or reassure the patient into signing.

Consent can be withdrawn at any time, including on the stretcher outside the OR. If a patient says they no longer want the operation, the nurse stops preparations and informs the surgeon and anesthesiologist at once. If the nurse doubts that a patient can make the decision, for example because of new confusion or the effects of sedating medication, the nurse reports this; the surgeon assesses capacity, and a substitute decision-maker may be needed. When the patient's preferred language is not English, a qualified interpreter takes part in the consent discussion, and this is documented. Many hospitals allow nurses to witness the patient's signature; witnessing means confirming who signed, not confirming that the patient understood the surgery.

Final Preparation

On the morning of surgery, the nurse works through the hospital's preoperative checklist. The exact items vary, but a typical checklist confirms:

- **Identity:** two patient identifiers checked against the wristband and chart, with the patient taking part (Chapter 1, section 1.6).
- **Allergies:** documented and shown on an allergy band.
- **Consent:** signed, matching the booked procedure and side, and understood.
- **Site marking:** the operative site marked as policy requires, typically by the surgeon or a member of the surgical team, with the patient awake and taking part.
- **Fasting:** the times of last food and last clear fluid, compared with the instructions.
- **Medications:** given or held as ordered; any medication taken against instructions reported.
- **Baseline vital signs, weight and glucose:** recorded, with any abnormal or changed finding reported before transfer.
- **Personal items:** jewellery, glasses, hearing aids, dentures and prostheses removed or kept according to policy, and stored safely. Hearing aids and glasses may stay until anesthesia begins so the patient can communicate.
- **Voiding:** the patient has emptied the bladder unless a catheter is planned.
- **Test results and blood products:** ordered results on the chart; blood bank sample sent if required.

Religious and cultural items, such as a medicine bundle, a religious medal, a turban or a kirpan, deserve respect. The nurse asks what the item means to the patient, follows policy and the patient's wishes about whether it can stay with them, how it can be secured, and when it will be returned, and documents the plan. Chapter 2 discusses cultural safety.

Finally, the nurse gives a structured handover to the OR team, sharing anything the checklist did not show: anxiety, a hearing impairment, a medication question, or a family member waiting for a call. Any change in the patient's condition, such as new chest pain, a fast or irregular pulse, or new confusion, is reported before transfer, not left for the OR team to find.

Figure 7.2 A surgical team at work in an operating room. Before the first incision, the team pauses for the time-out. (credit: "AfS surgical team at the operating room" by Almondbite3/Wikimedia Commons, CC BY-SA 4.0)

The Surgical Safety Checklist

The **Surgical Safety Checklist** is a structured set of checks that the whole surgical team completes together at set points during each operation. It grew out of the WHO's Safe Surgery Saves Lives program. In a study at eight hospitals in eight cities around the world, Haynes and colleagues (2009) compared 3,733 patients having non-cardiac surgery before the checklist was introduced with 3,955 patients afterwards. During the hospital stay, up to 30 days after surgery, deaths dropped from 1.5% of patients to 0.8%, and inpatient complications from 11.0% to 7.0% (Haynes et al., 2009; Figure 7.2).

In Canada, the Canadian Patient Safety Institute (CPSI, now part of Healthcare Excellence Canada) and the Royal College of Physicians and Surgeons of Canada led a Canadian adaptation with partner organizations (Alberta Health Services, 2012; Healthcare Excellence Canada, n.d.). The Canadian checklist has three phases, summarized in Table 7.2. The **briefing** happens before anesthesia begins; the **time-out**, before the skin incision; and the **debriefing**, before the patient leaves the OR (Health Standards Organization [HSO], 2024). Hospitals adapt the checklist to their own settings, so the nurse learns the version used locally.

The checklist works only if people speak. Any team member who sees a mismatch, a missing item or a safety concern is expected to say so, and the team pauses until it is resolved. Speaking up in a hierarchy is hard, and Chapter 6 discusses tools that help.

Table 7.2 The Surgical Safety Checklist's three phases (summary based on the Canadian version) (Alberta Health Services, 2012; HSO, 2024)

Phase	When	Main checks (summarized)	The nurse's part

Phase	When	Main checks (summarized)	The nurse's part
Briefing	Before anesthesia begins	Who the patient is, what operation and where, consent, allergies, fasting, airway or aspiration concerns, equipment and positioning needs	Confirms identity, consent and allergies with the patient awake; raises concerns from the preoperative assessment
Time-out	Just before the skin incision	Team members name themselves and their roles; surgeon, anesthesiologist and nurse confirm patient, procedure and site aloud; expected critical events, antibiotic and VTE prophylaxis, imaging	Takes part aloud; stops the process if anything does not match
Debriefing	At the end of the operation, before the patient leaves the OR	Name of the procedure done, counts of sponges, needles and instruments, specimen labels, equipment problems, recovery plan	Confirms counts and specimen labels; contributes to the handover plan for the PACU

CANADIAN CONTEXT

The Surgical Safety Checklist in Canada

Use of a safe surgery checklist is a Required Organizational Practice (ROP) in the HSO standards that Accreditation Canada uses to accredit health care organizations. The ROP calls for the team to agree on a three-phase checklist and use it for every surgical procedure in the OR, for compliance to be monitored, and for the results of evaluating its use to be shared with the team and used to improve (HSO, 2024).

An Ontario study looked at what happened after hospitals adopted the checklist. Urbach and colleagues (2014) compared about 109,000 procedures in the three months before each hospital adopted it with about 106,000 in the three months after, at 101 hospitals. The adjusted risk of dying within 30 days of surgery or during the hospital stay was 0.71% before and 0.65% after, and the adjusted complication rate was 3.86% before and 3.82% after; neither change was statistically significant (Urbach et al., 2014). Results like these suggest that how a team uses the checklist matters, not only whether it has been adopted; the ROP likewise asks organizations to evaluate its use and act on the results.

SCOPE IN PRACTICE

Consent, Checklists and Perioperative Roles

The College of Nurses of Ontario (CNO) Scope of Practice standard frames every perioperative role in terms of authority, competence and context (Chapter 1, section 1.3).

- **Authority:** The surgeon has the authority and duty to obtain informed consent for surgery. Neither registered nurses (RNs) nor registered practical nurses (RPNs) obtain it, but both can verify that consent is documented and understood, witness signatures where policy allows, report doubts and stop preparation if consent is withdrawn.
- **Competence:** Perioperative and PACU care require added education. Whether an RPN works in the scrub role, in a preoperative clinic or in the PACU depends on that nurse's education and competence, employer policy and the patient's needs.
- **Context:** Rules differ by setting and by province or territory. For example, accreditation standards for non-hospital surgical facilities in British Columbia require two registered nurses in the PACU whenever a patient is receiving care there (CPSBC, 2026). Assigning patients by stability is a common employer practice, not a CNO rule.

Every nurse who notices deterioration, such as a falling oxygen saturation or new confusion, acts at once and escalates. The RPN consults the RN as the patient's needs change, and every team member can call a pause during the Surgical Safety Checklist.

7.4 Anesthesia and Sedation

The anesthesiologist chooses the type of anesthesia with the patient, based on the surgery, the patient's health (section 7.2) and the patient's wishes. Many patients receive more than one type. Table 7.3 compares the main types.

General Anesthesia

General anesthesia is a drug-induced state of unconsciousness from which the patient cannot be roused, even by pain (ASA, 2024). Because the patient often cannot keep the airway open or breathe adequately, and circulation may be affected, the anesthesia team

supports both (ASA, 2024), keeping the airway open with an endotracheal tube in the trachea or a supraglottic airway that sits above the larynx. Drugs that relax or paralyze the muscles are added when the surgery needs them.

Common after-effects include drowsiness, sore throat or hoarseness, nausea and vomiting, shivering and short-lived confusion (section 7.5). Rarely, a patient remembers events during anesthesia (awareness): a United Kingdom national audit found about 1 report for every 19,000 general anesthetics, and explanation and reassurance seemed to help (Cook et al., 2014). The nurse listens without dismissing the report and informs the anesthesia team.

Neuraxial and Regional Anesthesia

Neuraxial anesthesia places local anesthetic near the spinal cord. In **spinal anesthesia**, one injection into the cerebrospinal fluid in the lower back produces rapid, dense numbness and weakness of the lower body. In **epidural anesthesia**, local anesthetic is given into the epidural space, usually through a thin catheter that can stay in place for repeat doses and pain relief after surgery (epidural analgesia; Chapter 5, section 5.4). A **peripheral nerve block** is an injection of local anesthetic near the nerves that supply one limb or area; a catheter may continue the block as an infusion.

Neuraxial blocks also affect the sympathetic nerves, so blood pressure can fall, and they affect bladder control (section 7.6). After any block, the nurse:

- checks that sensation and movement return in the expected pattern and time, and reports a block that spreads higher, weakness that returns after it had resolved, or new back pain at once (Chapter 5, section 5.4);
- checks blood pressure and has the patient sit and dangle the legs before first standing;
- monitors voiding;
- protects a numb limb, which cannot feel pressure, heat or injury, by positioning, padding and checking the skin;
- prevents falls: after a leg block the patient walks only with help;
- plans ordered analgesia before the block wears off (Chapter 5).

Local Anesthesia and Procedural Sedation

In **local infiltration**, the surgeon or another provider injects local anesthetic into the tissue at the site of a minor procedure, and the patient stays awake. The total dose of local anesthetic from all sources is recorded to reduce the risk of toxicity (Dobson et al., 2026).

Procedural sedation uses drugs to depress consciousness for a procedure such as an endoscopy or a cardioversion. The ASA (2024) describes sedation as a continuum:

- **Minimal sedation:** the patient is relaxed and answers normally when spoken to. Thinking and coordination may be slowed, but breathing and circulation are unaffected.
- **Moderate sedation:** the patient is drowsy but responds purposefully to voice or a light touch, keeps the airway open without help and breathes adequately.
- **Deep sedation:** the patient cannot be roused easily and responds purposefully only to repeated or painful stimulation. The patient may need help to keep the airway open, and breathing may become inadequate.

Because a patient can slip deeper than intended, whoever gives sedation must be able to rescue a patient from the next level (ASA, 2024).

The nurse who monitors sedation has no other task. Beforehand, the nurse records baseline vital signs, oxygen saturation (SpO2) and level of consciousness, confirms fasting (section 7.2), allergies and consent (section 7.3), and checks that oxygen, suction, airway equipment and the emergency cart are ready. During the procedure, the nurse watches:

- airway patency and the rate and depth of breathing;
- SpO2 and, where policy requires, **capnography**, the continuous measurement of exhaled carbon dioxide (end-tidal CO2), which the CAS guidelines require for moderate or deep sedation provided under them (Dobson et al., 2026);
- level of sedation, with the scale the facility uses;
- heart rate, blood pressure and the ECG, as ordered.

If the patient becomes hard to rouse, snores, stops breathing or desaturates, the nurse stimulates the patient, opens the airway as taught, tells the provider to stop and calls for help. Monitoring continues until the patient meets the facility's recovery criteria. Whether a nurse may give the sedating drugs depends on authority, competence and context, including employer policy and the province or territory (Chapter 1, section 1.3).

Anesthesia Emergencies

The nurse recognizes these rare, life-threatening emergencies early, calls for help and stays with the patient.

- **Malignant hyperthermia (MH)** is an inherited muscle reaction triggered by volatile anesthetic gases and succinylcholine (Glahn et al., 2024). Early cues include an unexplained rise in end-tidal CO2, a fast heart rate, rapid breathing, muscle stiffness, sweating and mottled skin; a rapid temperature rise often comes later (Glahn et al., 2024).
- **Local anesthetic systemic toxicity (LAST)** occurs when local anesthetic reaches a toxic level in the blood and affects the brain and heart. Early cues include a metallic taste, changes in hearing such as ringing in the ears, and agitation; seizures and heart rhythm problems may follow. LAST can begin with heart problems alone or appear 30 to 60 minutes after an injection, and infusions carry risk for days (Neal et al., 2018).
- **Laryngospasm** is a sustained closure of the vocal cords that partly or fully blocks the airway, for example as a patient wakes (Gavel & Walker, 2014; section 7.5).

The nurse calls the anesthesia or code team, stops any local anesthetic infusion, supports the airway and gives oxygen as policy directs. CAS requires an MH kit wherever triggering agents are used, and LAST cognitive aids and lipid emulsion 20% wherever nerve blocks or infusions of local anesthetic are given (Dobson et al., 2026).

Table 7.3 Types of anesthesia and sedation compared (ASA, 2024; Brouwer et al., 2021; Dobson et al., 2026; Neal et al., 2018)

Type	What it does	Examples of use	Nursing points afterward
General anesthesia	Drug-induced unconsciousness; the patient cannot be roused; the anesthesia team supports breathing and circulation	Major abdominal, chest and neurosurgical procedures	Airway, breathing and SpO2; drowsiness; nausea and vomiting; temperature; sore throat; confusion on waking
Spinal anesthesia	One injection of local anesthetic into the cerebrospinal fluid; dense numbness and weakness of the lower body	Hip and knee replacement; lower-abdominal surgery	Return of movement and sensation; low blood pressure; urinary retention; falls on first standing
Epidural anesthesia	Local anesthetic given into the epidural space, usually through a catheter that can stay in for pain relief	Major abdominal and chest surgery; continued as epidural analgesia	Level of the block; blood pressure; leg strength; catheter site; new back pain or weakness reported at once (Chapter 5)
Peripheral nerve block	Local anesthetic injected near the nerves to one limb or area; sometimes continued by infusion	Shoulder, hand, knee and foot surgery	Protect the numb limb; falls; pain plan before the block wears off; watch for LAST with infusions
Local infiltration	Local anesthetic injected into tissue at the site; the patient stays awake	Skin lesion removal; minor procedures	Bleeding at the site; total dose recorded; LAST cues if large amounts were used
Procedural sedation	Drugs depress consciousness on a continuum from minimal to deep sedation	Endoscopy; cardioversion; fracture reduction	Airway, breathing, SpO2 and capnography as policy requires; sedation level; recovery criteria; a responsible adult for the trip home

GOING DEEPER

Malignant Hyperthermia and Local Anesthetic Systemic Toxicity

Required for RN students; optional for PN students.

Malignant hyperthermia. In people with an inherited susceptibility, volatile anesthetic gases or succinylcholine cause abnormally high calcium levels inside muscle cells, so the muscles contract and burn energy uncontrollably (Malignant Hyperthermia Association of the United States [MHAUS], n.d.-b). Carbon dioxide and heat build up. Later signs include high potassium, very high creatine kinase, dark urine from myoglobin, severe dysrhythmias and clotting failure (Glahn et al., 2024). No single sign is specific, so the team looks for a pattern.

Anesthesia leads treatment as soon as MH is suspected: the team stops all triggering agents, ventilates with high-flow 100% oxygen, calls for help, gives intravenous (IV) dantrolene (marketed in Canada; Health Canada, 2026) and cools the patient. Nurses fetch the MH kit, prepare dantrolene as directed, apply cooling, draw blood and record events. Monitoring continues for at least 24 hours in a critical care or recovery unit because signs can return (Glahn et al., 2024). The MHAUS hotline (1-800-644-9737) gives health professionals 24-hour emergency advice (MHAUS, n.d.-b). Afterward, the triggers are recorded as adverse reactions, the patient is referred for testing, relatives are told and a medical alert bracelet is advised (MHAUS, n.d.-a).

Local anesthetic systemic toxicity. Local anesthetics block sodium channels in nerve and heart tissue. Risk rises with older age, low muscle mass, heart disease (especially conduction problems, ischemia and heart failure), liver disease and the site and total dose of the block (Neal et al., 2018). Airway management comes first, because low oxygen and high carbon dioxide worsen toxicity. Seizures are treated, usually with a benzodiazepine, and the physician leads early lipid emulsion 20% therapy and modified advanced life support. After LAST, monitoring continues for at least 2 hours after a brief seizure and 4 to 6 hours after cardiovascular instability (Neal et al., 2018, 2021).

7.5 Care After Anesthesia (PACU)

Patients recover from anesthesia in the PACU under close observation; every facility providing anesthesia must have one (Dobson et al., 2026).

Phases of Postanesthesia Care

As section 7.1 explains, recovery moves from **Phase I**, with continuous monitoring and close nursing care until the airway, breathing, circulation and consciousness are stable, to **Phase II**, with less frequent monitoring as a stable patient nears discharge criteria (CPSBC, 2026). Some patients may go straight to another unit that can give the right level of care, if documented (Dobson et al., 2026). Staffing follows need: British Columbia's Phase I minimum ratios, based on national perianesthesia nursing standards, range from two nurses for one critically ill or unstable patient to one nurse for two conscious, stable patients without complications (British Columbia Ministry of Health, 2024).

The anesthesiologist comes with the patient and hands over care to the PACU nurse in a structured way (Dobson et al., 2026). It covers what happened during surgery and anesthesia, relevant history such as sleep apnea, and the plan for pain and nausea. Continuous pulse oximetry is required early in recovery, capnography is required for intubated or deeply sedated patients, and alarms stay on with limits suited to the patient (Dobson et al., 2026).

Airway and Breathing

Airway obstruction is an urgent early risk: in a drowsy patient, the relaxed tongue can fall back against the throat. Cues include snoring or noisy breathing, little or no airflow and a falling SpO2. The nurse rouses the patient, uses a jaw thrust as taught, inserts an oral airway if trained and policy allows, gives oxygen as ordered and calls the anesthesia team if the obstruction does not clear at once.

Laryngospasm, a sustained closure of the vocal cords, can partly or completely block the airway as a patient emerges from anesthesia, and it can quickly cause hypoxemia and a slow heart rate (Gavel & Walker, 2014). Breathing becomes noisy, or breathing efforts move no air at all. The nurse calls the anesthesia team at once and gives oxygen as taught while help comes.

Hypoventilation, slow or shallow breathing, can follow residual anesthetic, opioids or incompletely reversed muscle relaxants; rising sedation is an early warning (Chapter 5, section 5.4). Hypoxemia, a low blood oxygen level, can also follow atelectasis, aspiration or fluid overload. Patients with obstructive sleep apnea or a high STOP-Bang score (section 7.2) are more sensitive to opioids and sedatives, so the nurse keeps them upright or side-lying when allowed, on continuous oximetry and using their own continuous positive airway pressure (CPAP) machine as ordered.

Circulation and Temperature

Low blood pressure may come from residual anesthetic, a neuraxial block, opioids or a fluid deficit, but bleeding is always considered: the nurse compares readings with baseline and checks the dressing, drains and the bed under the patient (Chapter 6, section 6.4). New dysrhythmias are reported (Chapter 16).

Inadvertent perioperative hypothermia is an unplanned core temperature below 36.0 °C around the time of surgery (National Institute for Health and Care Excellence [NICE], 2016). Anesthesia blunts temperature control. Canadian guidelines call for warming to target a core temperature of 36 °C to 37 °C, unless hypothermia is planned, and active warming equipment must be immediately available (Dobson et al., 2026). The NICE (2016) guideline advises measuring temperature on arrival in recovery and every 15 minutes, using forced-air warming when the temperature is below 36.0 °C and not transferring the patient to the ward until it is 36.0 °C or higher.

Postoperative Nausea and Vomiting

Postoperative nausea and vomiting (PONV) affects about 30% of patients having elective surgery and up to 80% of some high-risk patients (Elvir-Lazo et al., 2020). The simplified Apfel score counts four risk factors: female sex, not smoking, a history of PONV or motion sickness, and opioids after surgery. Risk rises from about 10% with no factors to about 80% with all four. Other risk factors include age under 50, volatile anesthetics, longer anesthesia and some procedures, such as laparoscopic, gallbladder and other intra-abdominal surgery (Elvir-Lazo et al., 2020).

Current guidance is to assess each patient's risk, reduce baseline risk and give patients at moderate or high risk preventive drugs that work in different ways (Elvir-Lazo et al., 2020; Gan et al., 2020). When PONV occurs within 6 hours after surgery despite preventive drugs, the rescue drug should come from a different drug class (Elvir-Lazo et al., 2020). The nurse asks about nausea rather than waiting for vomiting, gives ordered antiemetics, keeps suction at the bedside, moves the patient slowly and supports opioid-sparing pain relief (Chapter 5). A drowsy patient who vomits is turned onto the side or sat up to protect the airway. Nausea can also begin after a day-surgery patient goes home (Elvir-Lazo et al., 2020).

Pain and Emergence Delirium

Pain is assessed as soon as the patient can respond and treated as described in Chapter 5, so the patient can breathe deeply and move.

Some patients wake confused, restless or agitated; others are confused but quiet and drowsy. This **emergence delirium** begins during or soon after waking from general anesthesia. In a study of 915 adults aged 65 to 90 after major surgery, 37% had it in the PACU, most often the quiet (hypoactive) type, and it was linked to later postoperative delirium (Zhang et al., 2020). Agitation can lead to falls and pulled lines. The nurse first looks for problems that can be corrected, such as hypoxemia, pain, cold, a full bladder, low blood pressure and low blood glucose. The nurse stays with the patient, reorients calmly, protects lines and the wound, and reports to the anesthesia team. Confusion that persists or begins later is assessed as delirium (Chapter 8).

Readiness to Leave the PACU

The anesthesiologist decides when a patient leaves the PACU, though facility policy may delegate this (Dobson et al., 2026). Many units use a version of the Aldrete recovery score (Aldrete & Kroulik, 1970; Aldrete, 1995). It rates five areas from 0 to 2: how many limbs the patient can move on request, the quality of breathing, blood pressure compared with the pre-anesthesia value, level of consciousness, and oxygenation. A total of 9 or more is commonly used, along with controlled pain and nausea, a temperature of 36.0 °C or higher and, after neuraxial anesthesia, a regressing block. Before going home, day-surgery patients must meet the facility's criteria, checked with a validated tool, for example the modified Postanesthetic Discharge Scoring System (Dobson et al., 2026).

For transfer to an inpatient unit, the PACU nurse gives handover with SBAR (Chapter 6, section 6.2), including PACU events, vital-sign trends, the last analgesic and antiemetic doses, intake and output, wound and drains, and any block. The receiving nurse completes a full assessment on arrival.

7.6 Postoperative Care and Complications

On the surgical unit, the nurse supports recovery and catches the complications in Table 7.4 early.

The First Postoperative Day

On arrival from the PACU, the nurse checks the airway, breathing, circulation, level of consciousness, vital signs, SpO2, pain, nausea, dressing and drains, IV infusion, urine output and, after a block, sensation and movement. Vital signs are repeated as ordered

and as policy requires, more often in the first hours. Temperature is measured on arrival and then with routine observations (NICE, 2016). Each set of vital signs feeds the early warning score, and a rising score triggers escalation (Chapter 6, section 6.1).

The nurse tracks fluid balance: IV fluids, oral intake, urine, drains and vomiting (Chapter 3). In enhanced recovery pathways, drinking and eating start early; the ERAS colorectal guideline states that an oral diet can usually begin within 4 hours after surgery (Gustafsson et al., 2019). The patient sits up and walks early, with help.

Respiratory Complications

Atelectasis is the collapse of small air sacs (alveoli) in part of the lung. After surgery, shallow breathing from pain, opioids, anesthesia and lying still lets the lung bases collapse. Cues include reduced breath sounds at the bases, faster breathing and a falling SpO2. Postoperative pneumonia is infection of the lung tissue; fever, a productive cough, crackles, rising respiratory rate, falling SpO2 and new confusion in an older adult are cues (Chapter 13).

Prevention centres on getting the patient upright and walking. The nurse encourages deep breaths and coughs several times an hour while awake, with a pillow pressed over an abdominal or chest incision to splint it, and gives enough pain relief to make this possible. Incentive spirometers are still widely used (section 7.2), but a Cochrane review of upper abdominal surgery found low-quality evidence that they prevented lung complications no better than deep breathing, physiotherapy or no treatment (do Nascimento Junior et al., 2014). The nurse therefore treats the spirometer as one tool among several and never as a substitute for walking. A falling SpO2 with faster breathing is reported. A sudden fall with chest pain or a racing heart raises the question of pulmonary embolism.

Venous Thromboembolism

Surgery raises the risk of **venous thromboembolism (VTE)**: a deep vein thrombosis (DVT) in the leg or pelvis, or a pulmonary embolism (PE) when a clot travels to the lungs. Immobility, injury to veins and the body's clotting response to surgery all contribute; major orthopedic, abdominal and cancer surgery carry high risk. Each surgical patient's VTE and bleeding risks are assessed with a recognized tool on admission and again when the patient's condition changes (NICE, 2019). Not every surgical patient needs prophylaxis; the method depends on the patient, the surgery and the bleeding risk (Anderson et al., 2019).

Prevention has three parts:

- **Early mobilization and hydration.** Walking and leg exercises keep blood moving, and dehydration is avoided (NICE, 2019).
- **Mechanical prophylaxis. Intermittent pneumatic compression (IPC)** devices are sleeves that inflate in cycles to squeeze the legs and push blood toward the heart. They are worn for as much of the time as possible until the patient is mobile. Anti-embolism stockings must be measured and fitted, removed daily for skin checks and avoided in patients with peripheral arterial disease, nerve damage with loss of feeling, or fragile skin (NICE, 2019).
- **Anticoagulant prophylaxis.** When VTE risk outweighs bleeding risk, the prescriber orders an anticoagulant, often a low-molecular-weight heparin. Some patients continue it at home; for example, after major cancer surgery in the abdomen, prophylaxis may be extended to 28 days (Gustafsson et al., 2019; NICE, 2019). The nurse gives it on time, watches for bleeding and teaches injection technique when needed. Because heparins come from animal sources, the nurse tells the prescriber when a patient objects for religious or ethical reasons, so an alternative can be considered (NICE, 2019).

DVT may cause swelling, pain, warmth and redness of one calf or thigh. Redness is harder to see on darker skin, so the nurse compares both legs for swelling, warmth and tenderness. PE may cause sudden shortness of breath, chest pain that worsens with breathing, a fast heart rate, rapid breathing, a falling SpO2, anxiety, coughing up blood or fainting. With suspected PE, the nurse stays with the patient, raises the head of the bed, gives oxygen as ordered, calls the rapid response team or the most responsible provider and reports with SBAR (Chapter 6; Chapters 15 and 19). The leg is never massaged.

Urinary Retention

Postoperative urinary retention is the inability to empty a full bladder after surgery. In one study of 936 general surgery patients, spinal anesthesia, surgery lasting 60 minutes or more, age 60 or older, a small bladder capacity and a bladder volume of 250 mL or more on the first PACU scan predicted the need for a catheter (Brouwer et al., 2021). The ERAS colorectal guideline adds male sex, epidural analgesia and pelvic surgery (Gustafsson et al., 2019). Many patients feel no urge: 71% of those who needed a catheter in

that study did not (Brouwer et al., 2021). The nurse therefore relies on time since the last void, suprapubic fullness or discomfort, restlessness and, in older adults, new confusion, and uses a bladder scanner as policy allows. If the bladder is full and the patient cannot void, the nurse reports it and catheterizes as ordered. An overstretched bladder can be damaged, temporarily or permanently (Brouwer et al., 2021). Indwelling catheters come out early; in low-risk patients after colorectal surgery, on the first day after surgery (Gustafsson et al., 2019). Catheter-associated urinary tract infection is covered in Chapter 4 (Figure 7.3).



Figure 7.3 A nurse opens the package of a sterile indwelling urinary catheter. A catheter is inserted only on an order and removed as early as possible. (credit: "Choose smallest catheter size possible" by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Bowel Function and Ileus

After surgery, the bowel recovers in stages; passing gas, then stool, and tolerating food show that it is working. **Postoperative ileus** is a temporary slowing of bowel movement after surgery. Cues include abdominal distension and discomfort, nausea and vomiting, no gas or stool, and poor tolerance of food. The nurse reports these cues, keeps the patient fasting if ordered, inserts or manages a nasogastric tube if ordered, and monitors fluids and electrolytes, especially potassium (Chapter 3).

ERAS measures that help prevent ileus include limiting opioids, minimally invasive surgery, avoiding routine nasogastric tubes, careful fluid therapy, early eating and walking (Gustafsson et al., 2019). Chewing gum is not recommended as a routine part of ERAS for colorectal surgery, because a large multicentre trial found no benefit (Gustafsson et al., 2019). Ostomy care is in Chapter 25.

Wound Complications

A **hematoma** is a collection of blood under the incision. Cues include swelling, bruising, tightness and increasing pain. The nurse marks and reports it; after neck surgery, such as thyroid surgery, a hematoma can obstruct the airway, so swelling there is reported at once (Iliff et al., 2022). Surgical site infection is covered in Chapter 4. The nurse looks at the incision at each assessment (Figure 7.4).

Dehiscence is the separation of the edges of a closed surgical incision, with or without exposure of the tissues, organs or implants beneath it (World Union of Wound Healing Societies [WUWHS], 2018). It usually occurs 4 to 14 days after surgery. Major risk factors include obesity, diabetes, smoking, emergency surgery, age over 65, a long operation, perioperative hypothermia and wound infection. A sudden increase in pain or in serosanguineous drainage (thin, pink fluid) from the incision may be the first warning (WUWHS, 2018). **Evisceration** is the protrusion of abdominal organs through a dehisced wound, a surgical emergency (Clinical Safety box).

Bleeding and Delirium

Bleeding after surgery may be visible, in dressings and drains, or hidden in the abdomen, chest or tissues. A rising heart rate, narrowing pulse pressure, restlessness and falling urine output can appear before blood pressure falls. The nurse escalates at once and follows the approach to hemorrhage and hypovolemic shock in Chapter 6, section 6.4.

Postoperative delirium is an acute disturbance of attention and thinking that usually begins in the first days after surgery and is common in older adults. Pain, hypoxemia, infection, urinary retention, constipation, poor sleep and some drugs can trigger it. The nurse screens for delirium, treats causes with the team and uses the prevention measures in Chapter 8.

Figure 7.4 A surgical incision closed with staples, 7 days after shoulder surgery. (credit: "Surgical staples2" by Llywrch/Wikimedia Commons, CC BY-SA 2.5)

Enhanced Recovery After Surgery

Enhanced recovery after surgery (ERAS) is a set of evidence-based practices across the whole surgical journey that reduce the stress of surgery and speed recovery. The ERAS Society publishes guidelines for many surgeries. Its colorectal guideline includes (Gustafsson et al., 2019):

- teaching and counselling before admission, and prehabilitation (exercise and nutrition before surgery), for which evidence is still developing;
- avoiding prolonged fasting, with clear fluids, including carbohydrate drinks, closer to surgery (follow the anesthesia team's instructions; section 7.2);
- preventing PONV and hypothermia;
- opioid-sparing multimodal analgesia (Chapter 5);
- avoiding routine nasogastric tubes and giving fluids carefully;
- early oral intake, early mobilization and early removal of urinary catheters;
- thromboprophylaxis; and
- auditing how well the team follows the pathway.

Nurses carry much of ERAS: they teach the patient what to expect, get the patient drinking, eating and walking, manage pain, remove catheters on schedule and record whether each element happened.

Going Home

After day surgery, the patient must meet the facility's discharge criteria and be accompanied home, or to a place such as a hotel, by a responsible adult. Patients are told not to drive or operate hazardous machinery for 24 hours, and they receive written instructions on pain and complications (Dobson et al., 2026). Inpatients go home with teaching on medications, including anticoagulant injections, wound care, activity, signs to report and whom to call (NICE, 2019), and with a follow-up appointment.

Rural, remote and northern patients may live hours from the hospital that did their surgery. The nurse plans before discharge: medications and dressing supplies the patient can get locally, home care or a community health nurse for wound care, a virtual follow-up when possible, and clear advice on where to go if problems arise. First Nations and Inuit patients who travelled from their communities for surgery may need coordination with medical travel and the community's nursing station, arranged in a culturally safe way (Chapter 2). An interpreter is used for discharge teaching when needed (Chapter 1, section 1.7).

Table 7.4 Common postoperative complications: timing, cues and first nursing actions (Brouwer et al., 2021; Gustafsson et al., 2019; NICE, 2019; WUWHS, 2018)

Complication	Typical timing	Cues	First nursing actions
Hypoxemia and atelectasis	Often in the PACU and first days	Falling SpO2; faster breathing; reduced breath sounds at the bases; drowsiness	Sit up; deep breathing and coughing; oxygen as ordered; check sedation; report a falling trend
Pneumonia	Often after the first few days	Fever; productive cough; crackles; rising respiratory rate; new confusion	Assess; report; obtain ordered tests; mobilize; oxygen as ordered (Chapter 13)
Hemorrhage	Often in the first 24 hours	Rising heart rate; narrowing pulse pressure; restlessness; soaked dressing or high drain output; falling urine output	Call for help; apply pressure to visible bleeding; lie flat; IV access; SBAR (Chapter 6)

Complication	Typical timing	Cues	First nursing actions
Urinary retention	First hours after surgery or catheter removal	No void; suprapubic fullness; restlessness; often no urge	Bladder scan as policy allows; report; catheterize as ordered
Ileus	First days	Distension; nausea and vomiting; no gas or stool	Report; fasting and nasogastric tube if ordered; fluids and electrolytes
Surgical site infection	Usually days after surgery, sometimes after discharge	Redness, warmth, swelling, pain, drainage; fever	Assess and report; swab or culture as ordered (Chapter 4)
Dehiscence or evisceration	Usually days 4 to 14	Sudden pain or pink drainage; wound edges apart; organs visible	Stay; call for help; cover with sterile saline-moistened dressing; nothing by mouth (Clinical Safety box)
Deep vein thrombosis	Any time from the first days to weeks, including after discharge	One-sided leg swelling, pain, warmth, redness	Do not massage; report; prepare for ordered tests (Chapter 19)
Pulmonary embolism	Any time from the first days to weeks, including after discharge	Sudden breathlessness; pleuritic chest pain; fast heart rate; falling SpO2; anxiety	Stay; raise head of bed; oxygen as ordered; rapid response; SBAR (Chapter 15)
Delirium	Often in the first days	Inattention; fluctuating confusion; agitation or unusual drowsiness	Look for causes (oxygen, pain, bladder, infection); keep safe; report (Chapter 8)

CLINICAL SAFETY

Wound Evisceration

Evisceration usually follows dehiscence of an abdominal incision. The patient may report that something "gave way" or feel a sudden gush of pink fluid, and loops of bowel or other tissue may be visible in the wound. It is a surgical emergency. First actions, as hospital policy directs:

- Stay with the patient and call for help; ask a colleague to notify the surgeon and, if the patient is unstable, the rapid response team.
- Cover the exposed organs with sterile dressings moistened with sterile normal saline, and keep them moist. Do not try to push the organs back.
- Position the patient to reduce tension on the abdomen, for example lying with the head of the bed slightly raised and knees bent, as policy directs.
- Keep the patient fasting (nothing by mouth) in preparation for surgery.
- Monitor vital signs, SpO2 and level of consciousness for signs of shock (Chapter 6).
- Reassure the patient, prepare for return to the operating room and document the time, findings and actions.

LIFESPAN CONSIDERATIONS

Older Adults and Surgery

Frailty, not age alone, predicts how well an older adult recovers from surgery (section 7.2).

- **Delirium prevention:** keep glasses and hearing aids in place, orient the patient often, protect sleep, get the patient up and walking early, keep the patient eating and drinking, treat pain, and avoid drugs that can trigger delirium, such as some sedatives and anticholinergics, unless the prescriber decides they are needed (Chapter 8).
- **Hidden causes of confusion:** a full bladder, low oxygen and constipation can all appear as restlessness or confusion.
- **Hypothermia:** older adults may lose heat quickly in the operating room and PACU, so the nurse measures temperature and warms actively (NICE, 2016).
- **Kidney function:** kidney reserve falls with age, which affects fluid balance and drug clearance. The nurse tracks urine output and creatinine as ordered (Chapter 3).
- **Falls:** nerve blocks, opioids, low blood pressure on standing and new surroundings all raise risk. Keep the call bell, glasses and walking aid within reach, and help with the first walks (Chapter 8).
- **Wound healing:** age over 65 is a risk factor for dehiscence (WUWHS, 2018).

PATIENT EDUCATION

Going Home After Day Surgery

- **Getting home:** A responsible adult must take you home. Follow the hospital's instructions about how long someone should stay with you.
- **For 24 hours:** Do not drive or use machinery or power tools (Dobson et al., 2026). Avoid alcohol, and do not sign legal papers or make important decisions until you are thinking clearly; your instructions will say for how long.
- **Pain:** Take your pain medicines as your written plan says. Start before a nerve block wears off if you were told to.
- **Your wound:** Keep the dressing clean and dry, and follow the instructions for showering and changing it.
- **Call your surgeon's office or the number on your instructions if you have:** a fever, increasing redness, swelling or drainage from the wound, bleeding that soaks the dressing, vomiting that will not stop, or you cannot pass urine.
- **Call 9-1-1 if you have:** sudden shortness of breath, chest pain, coughing up blood, or heavy bleeding. Pain, swelling or warmth in one calf also needs urgent attention, because it can be a sign of a blood clot.

PRACTICE STORY

"He Just Wasn't Himself"

Names and details are fictional; this is a composite story.

Nurse: Tanya Beaulieu, RPN. Years in practice: 8. Setting: orthopedic surgical unit, community hospital, Ontario.

Mr. Walter Zielinski was 84 and had his hip fracture repaired under spinal anesthesia the morning before. His daughter told us he did the crossword every morning. His catheter came out at 1000.

At 2200 I found him pulling at his blanket and trying to swing his good leg over the bed rail. He called me by his late wife's name. His vital signs were close to his baseline: heart rate 96, blood pressure 148/82 mm Hg, temperature 37.2 °C, SpO2 95% on room air. He said his hip "wasn't too bad." His intake and output record showed no void since the catheter came out.

His lower abdomen felt firm above the pubic bone. Our policy lets nurses do a bladder scan when retention is suspected, so I scanned him: about 850 mL. I lowered the bed and asked the nursing assistant to sit with him while I found Priya Nair, the RN on our team. She came to assess him with me and paged the surgical resident. We reported with SBAR, and the resident ordered an in-and-out catheterization and a delirium assessment. I inserted the catheter and drained just over 800 mL.

Within an hour he was calmer and fell asleep. In the morning he still mixed up the day, so the team kept the delirium prevention plan going: his glasses and hearing aids, his daughter's visits, getting up for breakfast and a voiding schedule with bladder scans.

I keep thinking about how easy it would have been to call it "sundowning" and ask for something to settle him. He couldn't tell us his bladder was full. His behaviour was the only way he could tell us something was wrong.

Reflect: What cues suggested that Mr. Zielinski's confusion had a treatable cause? Which parts of this situation did the RPN manage within her own authority and competence, and why did she consult the RN as his needs changed?

Chapter 7 Summary

Introduction

- Perioperative nurses work in preadmission clinics, same-day surgery, the OR, the PACU, surgical units and the community.
- This chapter follows the patient from the decision to operate through recovery; related topics are taught in Chapters 1, 4, 5, 6, 8, 19, 25 and 33.

7.1 The Perioperative Journey

- Surgery has preoperative, intraoperative and postoperative phases; PACU care moves from Phase I (close monitoring) to Phase II (approaching discharge) according to physiological recovery.
- Ambulatory surgery patients go home the same day with written instructions and a responsible adult; many inpatients come in under same-day admission.
- The team includes surgeons, anesthesiologists (and family practice anesthesia physicians), anesthesia assistants, scrub and circulating nurses, PACU nurses and surgical unit nurses.

- CIHI reports wait times against benchmarks, such as 26 weeks for hip and knee replacement and 16 weeks for cataract surgery; rural, remote and northern patients often travel for surgery.

7.2 Preoperative Assessment and Preparation

- The assessment covers past anesthesia problems and family history, heart and lungs, functional capacity, substance use, pregnancy possibility, cognition, frailty and supports.
- STOP-Bang screens for obstructive sleep apnea; the ASA Physical Status classification describes overall health.
- The prescriber or anesthesia team sets the plan for anticoagulants, antiplatelets, insulin, SGLT2 inhibitors, GLP-1 receptor agonists and opioid agonist treatment; the nurse asks, documents, confirms and teaches.
- Routine tests are not recommended for people without symptoms having low-risk surgery.
- The CAS minimum fasting times for adults are six hours after a meal containing solids and two hours after clear fluids; patients follow the anesthesia team's instructions.
- Hair is removed only if needed, with clippers; teaching covers breathing, coughing and splinting, leg exercises, early mobilization, pain and what to expect.

7.3 Consent and the Day of Surgery

- The surgeon obtains consent; the nurse checks it is documented and understood and reports doubts or a withdrawal at once.
- The preoperative checklist confirms identity, allergies, consent, site marking, fasting, medications, baseline findings and personal items; changes in condition are reported before transfer.
- The Surgical Safety Checklist has three phases: briefing before anesthesia, time-out before incision and debriefing before the patient leaves the OR.
- A large international study linked the checklist to fewer deaths and complications; an Ontario study after adoption found no significant change, so how teams use it matters.

7.4 Anesthesia and Sedation

- General anesthesia causes a loss of consciousness from which the patient cannot be roused; the anesthesia team supports the airway, breathing and circulation.
- Spinal and epidural anesthesia and nerve blocks numb part of the body; afterward the nurse checks movement, sensation, blood pressure and voiding, protects numb limbs and prevents falls.
- Procedural sedation lies on a continuum; the monitoring nurse watches the airway, breathing, SpO2, capnography where required and level of sedation, and acts at once if sedation becomes too deep.
- Whether a nurse may give sedation depends on authority, competence and context, including employer policy and province or territory.
- Malignant hyperthermia, local anesthetic systemic toxicity and laryngospasm are rare emergencies; the nurse recognizes early cues and calls for help.

7.5 Care After Anesthesia (PACU)

- Phase I care supports recovery of the airway, breathing, circulation and consciousness; Phase II prepares day-surgery patients to go home.
- A structured handover from the anesthesiologist, continuous oximetry and capnography for intubated or deeply sedated patients are Canadian requirements.
- Airway obstruction, laryngospasm and hypoventilation are urgent early risks; patients with sleep apnea need extra vigilance.
- Hypothermia is a core temperature below 36.0 °C; the nurse warms actively and measures temperature often.
- PONV risk rises with female sex, not smoking, a history of PONV or motion sickness and postoperative opioids.
- PACU discharge uses written criteria such as an Aldrete-type score, followed by an SBAR handover.

7.6 Postoperative Care and Complications

- The first postoperative day focuses on regular assessment, early warning scores, fluid balance, pain control, early eating and early walking.
- Walking, deep breathing and coughing prevent atelectasis; evidence that incentive spirometry alone prevents lung complications is weak.
- VTE prevention combines risk assessment, early mobilization, mechanical devices and ordered anticoagulants; suspected PE is escalated at once.
- Urinary retention is often silent; bladder scanning as policy allows and early catheter removal are key.
- Ileus, dehiscence and evisceration need prompt recognition; evisceration is a surgical emergency.
- ERAS pathways depend on nurses for teaching, nutrition, mobilization and catheter removal; discharge planning includes a responsible adult after day surgery and tailored plans for rural and northern patients.

Key Terms (44)

ambulatory surgery: Surgery after which the patient goes home on the same day; also called day surgery or same-day surgery.

anesthesia assistant: A formally designated team member with specific training in anesthesia assistance who carries out tasks approved by the department of anesthesia and the facility.

ASA Physical Status classification: A six-class system used by anesthesiologists to describe a patient's overall health before anesthesia, with "E" added for emergency surgery.

atelectasis: collapse of the small air sacs (alveoli) in part of the lung, common after surgery when breathing is shallow.

briefing: The checklist phase completed before anesthesia begins.

capnography: continuous measurement of the carbon dioxide in exhaled breath (end-tidal CO2), used to monitor breathing.

debriefing: The checklist phase completed at the end of an operation, before the patient is moved out of the operating room, covering counts, specimens, equipment problems and the recovery plan.

dehiscence: separation of the edges of a closed surgical incision, with or without exposure of the tissues or organs beneath.

emergence delirium: confusion, restlessness, agitation or unusual quietness and drowsiness that begins during or soon after waking from general anesthesia.

enhanced recovery after surgery (ERAS): a set of evidence-based practices across the surgical journey that reduce the stress of surgery and speed recovery.

epidural anesthesia: local anesthetic given into the epidural space, usually through a catheter that can stay in place for pain relief after surgery.

evisceration: protrusion of abdominal organs through a dehisced surgical wound; a surgical emergency.

frailty: Reduced physiological reserve that leaves a person less able to recover from a stressor such as surgery.

general anesthesia: a drug-induced state of unconsciousness from which the patient cannot be roused, even by pain.

hematoma: a collection of blood in the tissues, such as under a surgical incision.

inadvertent perioperative hypothermia: an unplanned core body temperature below 36.0 °C around the time of surgery.

incentive spirometer: A hand-held device that shows how deeply a patient breathes in, encouraging slow, full breaths.

informed consent: Agreement to treatment given by a capable person after receiving the information a reasonable person would need, free of pressure; for surgery, obtained by the surgeon.

inpatient surgery: Surgery after which the patient is admitted to hospital.

intermittent pneumatic compression (IPC): leg sleeves that inflate in cycles to squeeze the legs and move blood toward the heart, used to prevent venous thromboembolism.

intraoperative: The phase from arrival in the operating room until transfer to the recovery area.

local anesthetic systemic toxicity (LAST): a toxic reaction of the brain and heart when local anesthetic reaches a high level in the blood.

local infiltration: injection of local anesthetic into the tissue at the site of a minor procedure.

malignant hyperthermia (MH): an inherited, life-threatening hypermetabolic reaction of skeletal muscle triggered by volatile anesthetic gases and succinylcholine.

neuraxial anesthesia: anesthesia produced by placing local anesthetic near the spinal cord, as in spinal and epidural anesthesia.

obstructive sleep apnea (OSA): Repeated collapse of the upper airway during sleep that interrupts breathing.

perioperative nursing: Nursing care given across the whole surgical experience, from the decision to operate through recovery.

peripheral nerve block: injection of local anesthetic near a nerve or group of nerves that supply one limb or area.

postanesthesia care unit (PACU): A unit that gives short-term, closely monitored care immediately after operations and invasive procedures.

postoperative: The phase from admission to the recovery area until the patient has recovered.

postoperative ileus: a temporary slowing of bowel movement after surgery.

postoperative nausea and vomiting (PONV): nausea, retching or vomiting after anesthesia and surgery.

postoperative urinary retention: inability to empty a full bladder after surgery.

prehabilitation: Improving physical and mental fitness in the weeks before surgery to build reserve for recovery.

preoperative: The phase from the decision to operate until transfer to the operating room.

procedural sedation: the use of drugs to depress consciousness so a patient can tolerate a procedure, on a continuum from minimal to deep sedation.

same-day admission: Arrival from home on the morning of surgery, with admission to a surgical unit afterwards.

site marking: Marking the operative site on the patient's skin before surgery, as policy requires, to prevent wrong-site surgery.

spinal anesthesia: a single injection of local anesthetic into the cerebrospinal fluid that numbs and weakens the lower body.

splinting: Pressing a pillow or hands over an incision to reduce pain during coughing or movement.

STOP-Bang: An eight-item yes-or-no screening questionnaire for obstructive sleep apnea.

Surgical Safety Checklist: A structured set of checks completed aloud by the whole surgical team at three set points during each operation.

time-out: The checklist phase completed just before the skin incision, in which the team confirms patient, procedure and site aloud.

venous thromboembolism (VTE): a blood clot in a vein, including deep vein thrombosis and pulmonary embolism.

Licensure Review & Clinical Judgment Questions (30)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mei-Ling Chen (Questions 1–4): Mei-Ling Chen, 58, arrives at the same-day surgery unit at 0700 for a laparoscopic cholecystectomy scheduled for 1000. She has type 2 diabetes, takes metformin and a weekly semaglutide injection, and speaks fluent English. The nurse is completing her preoperative preparation.

1. [CORE] While the nurse reviews the consent form, Ms. Chen says, "The surgeon was in a hurry. I'm not really sure what they are taking out or why." What is the nurse's best action?

a. Explain the risks and benefits of cholecystectomy using the hospital's teaching sheet.

b. Remind Ms. Chen that she has already signed and that the form is legally valid.

c. Inform the surgeon before transfer that Ms. Chen does not understand the procedure.

d. Ask Ms. Chen's spouse to explain the operation to her while she waits.

Answer: c — The surgeon obtains informed consent, and a patient who cannot describe the operation may not have given informed consent, so the nurse reports this to the surgeon before the patient goes to the OR (c). Explaining risks and benefits is the surgeon's role in the consent discussion; the nurse's teaching sheet cannot replace it (a). A signature alone does not prove understanding, and pressing the patient ignores her concern (b). A family member cannot carry out the surgeon's duty to inform (d). See section 7.3.

2. [CORE] Ms. Chen tells the nurse, "I had a slice of toast with peanut butter at 0600, and a glass of water at 0630." Her fasting instructions followed the anesthesia team's usual guidance. What should the nurse do?

a. Report the times and what she ate to the anesthesia team before she goes to the OR.

b. Document the intake and continue preparation, because surgery is still three hours away.

c. Tell Ms. Chen that her surgery is cancelled and arrange for her to go home.

d. Remove the water from the record, because clear fluids do not count toward fasting.

Answer: a — The CAS guidelines set a minimum of six hours after a meal containing solids; toast at 0600 falls inside that window for a 1000 surgery, so the nurse reports exactly what was eaten and when to the anesthesia team, who decide what happens next (a). Continuing without reporting ignores a breach of the fasting minimum (b). The nurse does not cancel surgery; the anesthesia team and surgeon decide (c). Clear fluids are allowed until two hours before, but they are still recorded accurately, not removed from the record (d). See section 7.2.

3. [CORE] Ms. Chen mentions that she took her weekly semaglutide injection two days ago. Why is it important that the anesthesia team knows this?

a. Semaglutide strongly increases the risk of bleeding during laparoscopic surgery.

b. Semaglutide is linked to diabetic ketoacidosis when surgery is done under fasting.

c. Semaglutide must be given again in the PACU to prevent high blood glucose.

d. Semaglutide slows stomach emptying, so food may remain despite usual fasting.

Answer: d — GLP-1 receptor agonists such as semaglutide slow gastric emptying; Health Canada found a possible link with pulmonary aspiration during general anesthesia or deep sedation, so the anesthesia team needs to know (d). Bleeding risk is the concern with anticoagulants and antiplatelets, not GLP-1 receptor agonists (a). The perioperative ketoacidosis warning applies to SGLT2 inhibitors (b). The nurse does not plan postoperative doses; any plan comes from the prescriber (c). See section 7.2 and Table 7.1.

4. [CORE] The nurse completes the preoperative checklist for Ms. Chen. Which finding must the nurse report to the anesthesia team and surgeon before transfer to the OR?

a. She emptied her bladder at 0915 and declined a urinary catheter.

b. Her pulse is 122 beats per minute and irregular; at 0700 it was 76 and regular.

c. Her wedding ring is taped in place according to hospital policy.

d. Her capillary glucose is 6.8 mmol/L, similar to her usual readings.

Answer: b — A new fast, irregular pulse is a change in condition that must be reported before transfer, not left for the OR team to find (b). Voiding before surgery is expected, and a catheter was not planned (a). Securing a ring according to policy is acceptable (c). A glucose value similar to her usual readings is not a change that needs urgent reporting (d). See section 7.3.

5. [CORE] A nurse is teaching a patient in a preadmission clinic who is scheduled for abdominal surgery. Which points belong in the teaching? Select all that apply.

a. Hold a pillow firmly over the incision when coughing.

b. Pump the ankles and circle the feet regularly while in bed.

c. Avoid coughing for the first two days to protect the incision.

d. Take slow, deep breaths, using an incentive spirometer if one is provided.

e. Stay in bed until the day after surgery to let the incision rest.

f. Tell the nurse early when pain makes it hard to breathe deeply or walk.

Answer: a, b, d, f — Splinting with a pillow reduces pain during coughing (a); ankle pumps and foot circles keep blood moving in the legs (b); slow, deep breaths, with an incentive spirometer where used, open the small airways (d); and reporting pain early lets the team treat it so the patient can breathe deeply and move (f). Avoiding coughing allows secretions to build up (c). Staying in bed delays the early mobilization that teaching should encourage (e). See section 7.2.

6. [CORE] The surgical team asks the nurse to prepare a patient's abdomen, which has heavy hair growth, before surgery. Which action follows current guidance?

a. Shave the area with a new disposable razor just before the patient goes to the OR.

b. Remove hair with clippers, only if the surgical team says removal is necessary.

c. Shave the area the evening before so any small cuts have time to heal.

d. Apply a depilatory cream to the whole abdomen as a routine step.

Answer: b — The WHO recommends leaving hair in place or, if removal is truly necessary, using clippers (b). Shaving causes small skin breaks and is strongly discouraged at any time, whether just before surgery or the night before (a, c). Routine hair removal of any kind, including depilatory cream, is not recommended when removal is not needed (d). See section 7.2.

7. [CORE] A nurse is screening patients for obstructive sleep apnea with the STOP-Bang questionnaire. Which patient has the highest STOP-Bang score?

a. A 45-year-old woman who snores loudly and feels tired during the day.

b. A 38-year-old man with a body mass index of 37 kg/m² and no other findings.

c. A 70-year-old woman with treated hypertension and a neck circumference of 36 cm.

d. A 62-year-old man who snores loudly and has a neck circumference of 43 cm.

Answer: d — The 62-year-old man scores four points: loud snoring, age over 50, neck circumference over 40 cm and male sex (d). The 45-year-old woman scores two, for snoring and tiredness (a). The 38-year-old man scores two, for body mass index above 35 kg/m² and male sex (b). The 70-year-old woman scores two, for hypertension and age over 50; her neck circumference is under 40 cm (c). See section 7.2.

8. [CORE] A student nurse asks when the time-out phase of the Surgical Safety Checklist takes place. Which response is accurate?

a. "It takes place in the preoperative unit, when the nurse completes the hospital checklist."

b. "It takes place in the operating room before anesthesia is started."

c. "It takes place just before the skin incision, with the team confirming aloud."

d. "It takes place before the patient leaves the OR, when counts are confirmed."

Answer: c — The time-out happens just before the skin incision; team members introduce themselves and the surgeon, anesthesiologist and nurse confirm the patient, procedure and site aloud (c). The preoperative unit checklist is a separate hospital process (a). The briefing takes place before anesthesia begins (b). The debriefing, including counts, takes place before the patient leaves the OR (d). See section 7.3 and Table 7.2.

9. [CORE] A registered practical nurse (RPN) in an Ontario hospital asks whether she can work in the postanesthesia care unit. Which response best reflects the CNO's approach to scope?

a. "It depends on your education and competence, employer policy and the patients' needs."

b. "CNO rules allow RPNs to care only for stable patients, so PACU work is not permitted."

c. "RPNs may work there only if they obtain the surgical consent for each of their patients."

d. "Any nurse can work in the PACU, because perioperative care needs no added education."

Answer: a — CNO frames scope in terms of authority, competence and context, so the RPN's role in the PACU depends on her education and competence, employer policy and patient needs (a). Assigning by stability is a common employer practice, not a CNO rule (b). The surgeon obtains surgical consent; no nurse does (c). PACU care requires added education and competence (d). See section 7.3, Scope in Practice box.

Case: Mrs. Lucille Arsenault (Questions 10–15): Mrs. Lucille Arsenault, 71, had a right total knee arthroplasty under spinal anesthesia yesterday morning. She has hypertension and a body mass index of 34 kg/m². She is receiving ordered anticoagulant prophylaxis, IPC sleeves and oral analgesics, including an opioid. At 0800 today her vital signs were temperature 37.4 °C, heart rate 84, respiratory rate 18, blood pressure 138/76 mm Hg and SpO2 95% on room air. She has spent most of the day in bed, saying she is "too sore and too sleepy" to use her incentive spirometer, and her IPC sleeves were removed for physiotherapy at 1100 and not put back on. At 1530 she calls the nurse and says, "All of a sudden I can't get my breath, and it hurts on the right side of my chest when I breathe in." Assessment: heart rate 118, respiratory rate 28, blood pressure 112/70 mm Hg, temperature 37.6 °C, SpO2 89% on room air. She is anxious and restless. Breath sounds are reduced at both bases. Her right knee dressing is dry, and the right leg is swollen as expected after surgery. Her left calf is tender and slightly larger than it was this morning.

10. [CORE] Which findings at 1530 require immediate follow-up? Select all that apply.

a. SpO2 89% on room air

b. Swelling of the right leg below the dressing

c. Heart rate 118 with a respiratory rate of 28

d. Sudden chest pain that worsens on breathing in

e. Temperature 37.6 °C

f. New tenderness and enlargement of the left calf

g. Body mass index of 34 kg/m²

Answer: a, c, d, f — A fall in SpO2 to 89% (a), a sharp rise in heart rate and breathing rate (c), sudden pleuritic chest pain (d) and new tenderness and swelling of the opposite calf (f) are new changes that need action now (section 7.6). Swelling of the operated leg (b) is expected after knee arthroplasty and is unchanged. A temperature of 37.6 °C (e) is a slight rise that is common after surgery and is not the most urgent finding. Her body mass index (g) is a risk factor, not a new finding that needs follow-up.

11. [CORE] The nurse analyzes the cues. Which finding most strongly favours pulmonary embolism over atelectasis as the cause of Mrs. Arsenault's low SpO2?

a. Reduced breath sounds at both lung bases

b. Sudden breathlessness with pleuritic pain and a newly tender left calf

c. Reluctance to use the incentive spirometer

d. Sleepiness after taking an opioid analgesic

Answer: b — Sudden breathlessness with pleuritic chest pain, together with signs of a possible DVT in the other leg (b), points to PE (section 7.6). Reduced breath sounds at the bases (a) and poor use of the incentive spirometer (c) fit atelectasis, which usually develops more gradually. Opioid sleepiness (d) can cause hypoventilation but does not explain sudden pleuritic pain, tachycardia and a tender calf.

12. [CORE] Which hypothesis is the priority?

a. Opioid-related sedation causing shallow breathing

b. Atelectasis from staying in bed

c. Anxiety about her slow recovery

d. Pulmonary embolism causing impaired gas exchange

Answer: d — Pulmonary embolism (d) can cause rapid deterioration and death, and her cues fit it best, so it is the priority hypothesis even before tests confirm it (section 7.6). Opioid sedation (a) and atelectasis (b) may contribute but do not explain the sudden pleuritic pain and calf findings, and acting on them first could delay treatment. Anxiety (c) is a response to her symptoms, not the cause of hypoxemia.

13. [CORE] Which actions should the nurse include in the plan of care now? Select all that apply.

a. Stay with Mrs. Arsenault and call for help through the rapid response team or the most responsible provider

b. Massage the left calf to relieve the tenderness

c. Raise the head of the bed and give oxygen as ordered or as the medical directive allows

d. Encourage her to walk in the hallway to open her lungs

e. Report using SBAR, including her SpO2 trend and the left calf findings

f. Prepare her for ordered diagnostic tests, such as imaging of the chest and legs

g. Give the next scheduled opioid dose early to relieve the chest pain

Answer: a, c, e, f — The nurse stays and escalates (a), supports oxygenation (c), gives a clear SBAR report that includes the key cues (e) and prepares for ordered tests (f) (section 7.6; Chapter 6). Massaging the calf (b) could dislodge a clot. Walking (d) helps prevent atelectasis but is unsafe with suspected PE and hypoxemia. An early opioid dose (g) could depress breathing and mask her symptoms; pain relief is given as ordered after the team assesses her.

14. [CORE] The nurse has called the rapid response team. While waiting, which action should the nurse take first?

a. Apply oxygen as the directive allows and recheck SpO2

b. Reapply the IPC sleeves to both legs to prevent another clot

c. Coach her to use the incentive spirometer 10 times

d. Document the 1530 assessment in the electronic record

Answer: a — Oxygenation is the immediate threat, so applying oxygen as authorized and rechecking SpO2 (a) comes first (section 7.6). Reapplying IPC sleeves (b) is not appropriate on a leg with a suspected clot until the team decides. Incentive spirometry (c) does not treat PE. Documentation (d) is completed once the patient is safe.

15. [CORE] Mrs. Arsenault is started on treatment for a confirmed pulmonary embolism. Which finding 2 hours later shows that her condition is improving?

a. SpO2 92% on room air with a heart rate of 120

b. Respiratory rate 30 and she says she feels "a bit calmer"

c. SpO2 95% on ordered oxygen, heart rate 96, respiratory rate 20 and less chest pain

d. Blood pressure 100/62 mm Hg and she is now drowsy

Answer: c — Better SpO2, slower heart and breathing rates and less pain (c) show improving gas exchange and circulation (section 7.6). An SpO2 of 92% with a persistent heart rate of 120 (a) and a respiratory rate of 30 (b) show that she is still in distress, whatever she reports. Falling blood pressure with new drowsiness (d) suggests deterioration and needs urgent escalation.

16. [CORE] A patient had a knee arthroscopy under spinal anesthesia 2 hours ago and is now on the surgical day-care unit. He wants to get up to use the washroom. What should the nurse do first?

a. Help him walk to the washroom, because walking soon after surgery helps prevent complications such as blood clots

b. Offer a urinal and tell him he must stay in bed until tomorrow morning

c. Check the return of movement and sensation in his legs and his blood pressure before helping him sit up

d. Give an ordered opioid, because standing will increase his knee pain

Answer: c — After spinal anesthesia, the nurse confirms that movement and sensation have returned and checks blood pressure, because weakness and hypotension can cause a fall (c) (section 7.4). Walking before checking (a) risks a fall. Bed rest until tomorrow (b) is unnecessary and delays recovery. An opioid before standing (d) adds sedation and hypotension and does not address the main safety risk.

17. [CORE] During a colonoscopy under moderate sedation, the monitoring nurse finds that the patient responds only when the nurse rubs his sternum, his SpO2 has fallen from 96% to 89%, and the capnography waveform has flattened. What should the nurse do first?

a. Stimulate the patient, open the airway as taught and tell the physician to stop the procedure while calling for help

b. Record the change and reassess the patient's sedation level and SpO2 in 5 minutes

c. Ask the physician to give another dose of sedative because the patient is about to move and the procedure is nearly done

d. Turn off the capnography alarm because the patient is still breathing

Answer: a — The patient has slipped into deep sedation with poor ventilation, so the nurse acts on the airway and breathing at once, has the procedure stopped and calls for help (a) (section 7.4). Waiting 5 minutes (b) allows hypoxemia to worsen. More sedative (c) would deepen sedation further. A flattened waveform shows inadequate breathing, and alarms must stay on (d).

18. [CORE] Which patient has the highest risk of postoperative nausea and vomiting?

a. A 68-year-old man who smokes, having a hernia repair under local anesthesia

b. A 55-year-old man who does not smoke, having a hip replacement under spinal anesthesia with a nerve block

c. A 45-year-old woman who smokes, having a hand procedure under a nerve block with no opioids planned

d. A 34-year-old woman who does not smoke, has motion sickness and will receive opioids after laparoscopic surgery

Answer: d — She has all four simplified Apfel risk factors (female sex, not smoking, motion sickness, postoperative opioids), plus age under 50 and laparoscopic surgery (d) (section 7.5). The patient in (a) has no Apfel factors other than possible opioids and is having local anesthesia. The patient in (b) has one or two factors. The patient in (c) is female but smokes and will not receive opioids.

19. [CORE] A patient arrives in the PACU after a 3-hour bowel resection. His temperature is 35.6 °C and he is shivering. Which action is most appropriate?

a. Give him one extra cotton blanket and recheck his temperature in 4 hours, once he is more awake

b. Start forced-air warming as ordered or as policy directs, and recheck his temperature every 15 minutes

c. Transfer him to the surgical unit, where he can warm up in a quiet room

d. Hold all warming until the surgeon has seen him and confirmed that warming is safe

Answer: b — A core temperature below 36.0 °C is inadvertent perioperative hypothermia; active warming and frequent temperature checks are needed (b) (section 7.5). A single blanket with a recheck in 4 hours (a) is too little, too late. The patient should not leave the PACU until his temperature is at least 36.0 °C (c). Warming does not need to wait for the surgeon (d).

20. [CORE] The PACU nurse is preparing to transfer a patient to the surgical unit after abdominal surgery under general anesthesia. Which finding means the patient is not yet ready to leave?

a. He opens his eyes when spoken to and answers questions

b. His blood pressure is within 10 mm Hg of his preoperative value

c. His SpO2 drops to 88% on room air whenever he dozes off

d. He moves all four limbs on request

Answer: c — Desaturation when he dozes (c) shows that his breathing is not yet adequate without support; he needs further assessment and the anesthesia team should be told (section 7.5). Responding to voice (a), stable blood pressure close to baseline (b) and moving all four limbs (d) are findings that support readiness for discharge from the PACU.

21. [CORE] Six hours after hip surgery under spinal anesthesia, a 78-year-old man has not voided since his catheter was removed in the PACU. He is restless and keeps trying to get out of bed, but denies needing to urinate. His vital signs are stable. What should the nurse do next?

a. Scan his bladder as policy allows and report the result and his restlessness to the most responsible provider or RN as appropriate

b. Ask the prescriber for a sedative, because he denies needing to void and his restlessness puts him at risk of falling

c. Encourage him to drink 1 L of water to stimulate voiding

d. Reassess him at the end of the shift, because many patients take several more hours to void after spinal anesthesia

Answer: a — Spinal anesthesia and age raise the risk of retention, and many patients with a full bladder feel no urge, so the nurse checks the bladder and reports the findings (a) (section 7.6). A sedative (b) treats the behaviour instead of the cause, and a full bladder can itself cause restlessness. Extra fluid (c) would overfill a bladder that cannot empty. Waiting until the end of the shift (d) risks bladder damage and worsening confusion.

22. [CORE] On day 3 after a bowel resection, a patient has a distended abdomen, has vomited twice and has not passed gas. Which action should the nurse take?

a. Encourage her to chew gum, because chewing gum is a routine part of ERAS for restarting the bowel after surgery

b. Encourage her to eat a full meal to stimulate the bowel

c. Give the ordered opioid more often, because her abdominal discomfort is keeping her from walking

d. Report the findings and keep her fasting as ordered while monitoring fluids and electrolytes

Answer: d — These cues suggest postoperative ileus. The nurse reports them, follows orders for fasting and possibly a nasogastric tube, and monitors fluids and electrolytes (d) (section 7.6). The ERAS colorectal guideline does not recommend chewing gum as a routine measure (a). A full meal (b) would increase vomiting. More frequent opioids (c) slow the bowel further.

23. [CORE] A patient is going home on anticoagulant injections after major abdominal cancer surgery. Which statement shows that the teaching has been effective?

a. "If my calf swells, I'll rub it gently until it goes down."

b. "I'll keep giving the injections for as long as my surgeon prescribed them, even when I feel well."

c. "I can stop the injections once I'm walking around the house, because walking keeps my blood moving."

d. "If I suddenly get short of breath, I'll rest and call the surgeon's office in the morning."

Answer: b — Prophylaxis after major abdominal cancer surgery may continue for weeks, and the patient must finish the prescribed course (b) (section 7.6). A swollen calf should never be rubbed (a); it needs urgent assessment. Walking does not replace a prescribed anticoagulant course (c). Sudden shortness of breath may be a pulmonary embolism and needs 9-1-1, not rest and a call in the morning (d).

24. [CORE] A patient on day 6 after a laparotomy coughs and says, "Something just gave way." The nurse sees loops of bowel in the open incision. What should the nurse do first?

a. Stay with the patient, call for help, and cover the bowel with sterile dressings moistened with sterile normal saline

b. Gently push the bowel back into the abdomen with a sterile gloved hand, then apply a dry dressing

c. Leave the room to page the surgeon, then return to take vital signs and check the wound

d. Give the patient a drink of water to ease the cough

Answer: a — Evisceration is a surgical emergency: the nurse stays, calls for help and protects the organs with a sterile saline-moistened dressing (a) (section 7.6, Clinical Safety box). Pushing the bowel back (b) can injure it and introduce infection. Leaving the patient (c) is unsafe; a colleague pages the surgeon. The patient must have nothing by mouth (d) in preparation for surgery.

25. [CORE] The nurse is reviewing discharge teaching with a patient after cataract surgery under procedural sedation. Which statement needs further teaching?

a. "My son is driving me home and will stay with me tonight."
b. "I'll call the number on my instructions if my pain gets worse instead of better."
c. "I'll drive myself to the pharmacy this evening to pick up my eye drops."
d. "I won't sign any legal papers until tomorrow."

Answer: c — Patients are told not to drive for 24 hours after anesthesia or sedation (c) (section 7.6). Having a responsible adult take her home and stay (a), calling about worsening pain (b) and putting off important decisions (d) are correct.

26. [CORE] An RPN on a surgical unit is caring for a patient on day 1 after bowel surgery. At 1000, the patient's SpO2 is 90% on room air (95% at 0600), respiratory rate 24, and the patient says breathing "feels harder." The RN on the team is in another patient's room. What is the RPN's most appropriate action?

a. Encourage incentive spirometry and recheck the SpO2 at the next scheduled set of vital signs this afternoon
b. Document the findings and mention them to the RN at noon, once the RN has finished with the other patient
c. Wait until the patient's early warning score reaches the rapid response threshold
d. Sit the patient up, apply oxygen if a medical directive allows, and consult the RN now, escalating directly if the patient worsens

Answer: d — Every nurse who notices deterioration acts at once and escalates; the RPN consults the RN as the patient's needs change, and calls for help directly if the patient worsens (d) (section 7.6; Chapter 1, section 1.3). Waiting for the next scheduled check (a) or until noon (b) delays care. The nurse escalates on clinical concern and need not wait for the score to reach a threshold (c) (Chapter 6).

27. [RN] During a laparoscopic cholecystectomy under general anesthesia with a volatile agent, which findings are early cues of malignant hyperthermia? Select all that apply.

a. An unexplained rise in end-tidal CO2
b. Heart rate rising without another explanation
c. Rigidity of the jaw muscles after succinylcholine
d. Bradycardia
e. Falling end-tidal CO2
f. Profuse sweating and mottled skin

Answer: a, b, c, f — An unexplained rise in end-tidal CO2 (a), inappropriate tachycardia (b), masseter rigidity after succinylcholine (c) and sweating with mottled skin (f) are early cues (section 7.4, Going Deeper). MH causes tachycardia, not bradycardia (d). Hypermetabolism raises CO2 production, so end-tidal CO2 rises, not falls (e). A high temperature is often a later sign.

28. [RN] The anesthesiologist suspects malignant hyperthermia in a patient in the operating room. Which action by the team comes first?

a. Apply cooling blankets and wait to see whether the temperature falls
b. Stop the volatile anesthetic and succinylcholine, and ventilate with high-flow 100% oxygen
c. Send blood for genetic testing for MH susceptibility
d. Finish the surgery quickly before treating the patient

Answer: b — Treatment begins with removing the triggers and hyperventilating with 100% oxygen while dantrolene is prepared (b) (section 7.4, Going Deeper). Cooling (a) is part of treatment but does not stop the reaction, and waiting delays it. Genetic testing (c) comes after recovery. The surgeon is told so surgery can be stopped or postponed; finishing first (d) delays treatment.

29. [RN] Fifteen minutes after an ultrasound-guided nerve block for shoulder surgery, a patient in the block area says, "I have a metal taste in my mouth and my ears are ringing." He is restless. What do these cues suggest?

a. Early local anesthetic systemic toxicity
b. A vasovagal reaction to the needle
c. Expected effects of a successful nerve block
d. Malignant hyperthermia

Answer: a — A metallic taste, ringing in the ears and agitation are early central nervous system cues of LAST; seizures and heart rhythm problems can follow (a) (section 7.4). A vasovagal reaction (b) causes pallor, slow heart rate and fainting, not altered taste or hearing. A successful block (c) causes numbness of the limb, not these symptoms. MH (d) is triggered by volatile anesthetics and succinylcholine, not local anesthetics.

30. [RN] A patient receiving a continuous femoral nerve block infusion on day 2 after knee replacement becomes confused, then has a seizure. Which action should the nurse take first?

a. Give lipid emulsion from the LAST kit without waiting for the physician
b. Increase the nerve block infusion rate to treat the patient's pain
c. Stop the local anesthetic infusion, call for help, and protect and support the airway
d. Leave the patient to find the LAST checklist

Answer: c — The nurse stops the source of local anesthetic, calls for help and makes airway management the first priority, because low oxygen and high carbon dioxide worsen toxicity (c) (section 7.4, Going Deeper). Lipid emulsion (a) is given early, but it is ordered and led by the physician. Increasing the infusion (b) would worsen toxicity. The nurse stays with the patient and sends someone else for the checklist and kit (d).

References

Alberta Health Services. (2012). *Safe Surgery Checklist frequently asked questions (FAQs)*. Surgery Strategic Clinical Network. https://albertahealthservices.ca/assets/about/scn/ahs-scn-surg-ssc-faq.pdf

Aldrete, J. A. (1995). The post-anesthesia recovery score revisited. *Journal of Clinical Anesthesia, 7*(1), 89–91. https://doi.org/10.1016/0952-8180(94)00001-K

Aldrete, J. A., & Kroulik, D. (1970). A postanesthetic recovery score. *Anesthesia & Analgesia, 49*(6), 924–934. https://doi.org/10.1213/00000539-197011000-00020

American Society of Anesthesiologists. (2024). *Statement on continuum of depth of sedation: Definition of general anesthesia and levels of sedation/analgesia*. https://www.asahq.org/standards-and-practice-parameters/statement-on-continuum-of-depth-of-sedation-definition-of-general-anesthesia-and-levels-of-sedation-analgesia

Anderson, D. R., Morgano, G. P., Bennett, C., Dentali, F., Francis, C. W., Garcia, D. A., Kahn, S. R., Rahman, M., Rajasekhar, A., Rogers, F. B., Smythe, M. A., Tikkinen, K. A. O., Yates, A. J., Baldeh, T., Balduzzi, S., Brożek, J. L., Etxeandia-Ikobaltzeta, I., Johal, H., Neumann, I., … Dahm, P. (2019). American Society of Hematology 2019 guidelines for management of venous thromboembolism: Prevention of venous thromboembolism in surgical hospitalized patients. *Blood Advances, 3*(23), 3898–3944. https://doi.org/10.1182/bloodadvances.2019000975

British Columbia Ministry of Health. (2024). *Minimum nurse-to-patient ratio: Post anesthesia care unit definition*. https://www2.gov.bc.ca/assets/gov/health/practitioner-pro/minimum-nurse-to-patient-ratios/mnpr_post-anesthesia_care_unit.pdf

Brouwer, T. A., van Roon, E. N., Rosier, P. F. W. M., Kalkman, C. J., & Veeger, N. (2021). Postoperative urinary retention: Risk factors, bladder filling rate and time to catheterization: An observational study as part of a randomized controlled trial. *Perioperative Medicine, 10*(1), Article 2. https://doi.org/10.1186/s13741-020-00167-z

Canadian Anesthesiologists' Society. (2023, June). *CAS medication safety bulletin: Semaglutide*. https://www.cas.ca/CASAssets/Documents/Advocacy/Semaglutide-bulletin_final.pdf

Canadian Anesthesiologists' Society. (2025). *Appendix 2: American Society of Anesthesiologists physical status classification*. https://www.cas.ca/CASAssets/Documents/Practice-Resources/Guidelines/Appendix-2_2025.pdf

Canadian Institute for Health Information. (2026a). *Joint replacement wait times* [Indicator]. https://www.cihi.ca/en/indicators/joint-replacement-wait-times

Canadian Institute for Health Information. (2026b). *Wait times for cataract surgery (percentage meeting benchmark)* [Indicator]. https://www.cihi.ca/en/indicators/wait-times-for-cataract-surgery-percentage-meeting-benchmark

Canadian Institute for Health Information. (n.d.). *Explore wait times for priority procedures across Canada*. Retrieved October 25, 2026, from https://www.cihi.ca/en/explore-wait-times-for-priority-procedures-across-canada

Choosing Wisely Canada. (2025). *Anesthesiology: Seven tests and treatments to question*. https://choosingwiselycanada.org/recommendation/anesthesiology/

Chung, F., Abdullah, H. R., & Liao, P. (2016). STOP-Bang questionnaire: A practical approach to screen for obstructive sleep apnea. *Chest, 149*(3), 631–638. https://doi.org/10.1378/chest.15-0903

College of Physicians and Surgeons of British Columbia. (2026). *Accreditation standards: Post-anesthesia care* (Version 3.1). Non-Hospital Medical and Surgical Facilities Accreditation Program. https://www.cpsbc.ca/files/pdf/NH-AS-Post-anesthesia-Care.pdf

Cook, T. M., Andrade, J., Bogod, D. G., Hitchman, J. M., Jonker, W. R., Lucas, N., Mackay, J. H., Nimmo, A. F., O'Connor, K., O'Sullivan, E. P., Paul, R. G., Palmer, J. H. M. G., Plaat, F. F., Radcliffe, J. J., Sury, M. R. J., Torevell, H. E., Wang, M., Hainsworth, J., & Pandit, J. J. (2014). 5th National Audit Project (NAP5) on accidental awareness during general anaesthesia: Patient experiences, human factors, sedation, consent, and medicolegal issues. *British Journal of Anaesthesia, 113*(4), 560–574. https://doi.org/10.1093/bja/aeu314

do Nascimento Junior, P., Módolo, N. S. P., Andrade, S., Guimarães, M. M. F., Braz, L. G., & El Dib, R. (2014). Incentive spirometry for prevention of postoperative pulmonary complications in upper abdominal surgery. *Cochrane Database of Systematic Reviews*, 2014(2), Article CD006058. https://doi.org/10.1002/14651858.CD006058.pub3

Dobson, G. R., Bak, A. B., Chau, A., Denomme, J., Fuda, G., Mc Donnell, C., Milkovich, R., Milne, A. D., Murdoch, J., Sparrow, K., Subramani, Y., & Young, C. (2026). Guidelines to the practice of anesthesia: Revised edition 2026. *Canadian Journal of Anesthesia, 73*(1), 13–60. https://doi.org/10.1007/s12630-026-03075-w

Elvir-Lazo, O. L., White, P. F., Yumul, R., & Cruz Eng, H. (2020). Management strategies for the treatment and prevention of postoperative/postdischarge nausea and vomiting: An updated review. *F1000Research, 9*, Article 983. https://doi.org/10.12688/f1000research.21832.1

Gan, T. J., Belani, K. G., Bergese, S., Chung, F., Diemunsch, P., Habib, A. S., Jin, Z., Kovac, A. L., Meyer, T. A., Urman, R. D., Apfel, C. C., Ayad, S., Beagley, L., Candiotti, K., Englesakis, M., Hedrick, T. L., Kranke, P., Lee, S., Lipman, D., … Philip, B. K. (2020). Fourth consensus guidelines for the management of postoperative nausea and vomiting. *Anesthesia & Analgesia, 131*(2), 411–448. https://doi.org/10.1213/ANE.0000000000004833

Gavel, G., & Walker, R. W. M. (2014). Laryngospasm in anaesthesia. *Continuing Education in Anaesthesia Critical Care & Pain, 14*(2), 47–51. https://doi.org/10.1093/bjaceaccp/mkt031

Glahn, K., Girard, T., Hellblom, A., Hopkins, P., Johannsen, S., Rueffert, H., Snoeck, M., Urwyler, A., & European Malignant Hyperthermia Group. (2024). *Recognising and managing a malignant hyperthermia crisis (v2024)*. European Malignant Hyperthermia Group. https://www.emhg.org/recommendations-1/2024/11/4/recognising-and-managing-a-malignant-hyperthermia-crisis-v2024

Gustafsson, U. O., Scott, M. J., Hubner, M., Nygren, J., Demartines, N., Francis, N., Rockall, T. A., Young-Fadok, T. M., Hill, A. G., Soop, M., de Boer, H. D., Urman, R. D., Chang, G. J., Fichera, A., Kessler, H., Grass, F., Whang, E. E., Fawcett, W. J., Carli, F., … Ljungqvist, O. (2019). Guidelines for perioperative care in elective colorectal surgery: Enhanced Recovery After Surgery (ERAS®) Society recommendations: 2018. *World Journal of Surgery, 43*(3), 659–695. https://doi.org/10.1007/s00268-018-4844-y

Haynes, A. B., Weiser, T. G., Berry, W. R., Lipsitz, S. R., Breizat, A.-H. S., Dellinger, E. P., Herbosa, T., Joseph, S., Kibatala, P. L., Lapitan, M. C. M., Merry, A. F., Moorthy, K., Reznick, R. K., Taylor, B., & Gawande, A. A. (2009). A surgical safety checklist to reduce morbidity and mortality in a global population. *New England Journal of Medicine, 360*(5), 491–499. https://doi.org/10.1056/NEJMsa0810119

Health Canada. (2026). *Drug Product Database: Dantrolene sodium* [Database entry, drug codes 14017 and 101921; accessed October 25, 2026]. https://health-products.canada.ca/dpd-bdpp/

Health Canada. (n.d.-a). *Summary safety review: Glucagon-like peptide 1 receptor agonists (GLP-1 RAs): Assessing the potential increased risk of pulmonary aspiration in patients undergoing procedures requiring general anesthesia or deep sedation*. Retrieved October 25, 2026, from https://dhpp.hpfb-dgpsa.ca/review-documents/resource/SSR1773942015728/

Health Canada. (n.d.-b). *Summary safety review: Sodium-glucose cotransporter-2 (SGLT2) inhibitors*. Retrieved October 25, 2026, from https://dhpp.hpfb-dgpsa.ca/review-documents/resource/SSR1724175682293

Health Standards Organization. (2024). *Required organizational practices 2024 handbook* (HSO R01002:2024 [E]). https://professionals.wrha.mb.ca/files/long.term_.care_.-accrreditation-AC-ROPhandbook2024.pdf

Healthcare Excellence Canada. (n.d.). *About us*. Retrieved October 25, 2026, from https://healthcareexcellence.ca/about/about-us

Iliff, H. A., El-Boghdadly, K., Ahmad, I., Davis, J., Harris, A., Khan, S., Lan-Pak-Kee, V., O'Connor, J., Powell, L., Rees, G., & Tatla, T. S. (2022). Management of haematoma after thyroid surgery: Systematic review and multidisciplinary consensus guidelines from the Difficult Airway Society, the British Association of Endocrine and Thyroid Surgeons and the British Association of Otorhinolaryngology, Head and Neck Surgery. *Anaesthesia*, *77*(1), 82–95. https://doi.org/10.1111/anae.15585

Malignant Hyperthermia Association of the United States. (n.d.-a). *Post-MH event plan and counseling*. Retrieved October 25, 2026, from https://www.mhaus.org/healthcare-professionals/after-a-crisis/post-mh-event-plan-and-counseling/

Malignant Hyperthermia Association of the United States. (n.d.-b). *What is MH / MHAUS?* Retrieved October 25, 2026, from https://www.mhaus.org/about/what-is-mh-mhaus

National Institute for Health and Care Excellence. (2016). *Hypothermia: Prevention and management in adults having surgery* (Clinical guideline CG65; published 2008, updated 2016). https://www.nice.org.uk/guidance/cg65

National Institute for Health and Care Excellence. (2019). *Venous thromboembolism in over 16s: Reducing the risk of hospital-acquired deep vein thrombosis or pulmonary embolism* (NICE guideline NG89; published 2018, updated 2019). https://www.nice.org.uk/guidance/ng89

Neal, J. M., Barrington, M. J., Fettiplace, M. R., Gitman, M., Memtsoudis, S. G., Mörwald, E. E., Rubin, D. S., & Weinberg, G. (2018). The third American Society of Regional Anesthesia and Pain Medicine practice advisory on local anesthetic systemic toxicity: Executive summary 2017. *Regional Anesthesia & Pain Medicine, 43*(2), 113–123. https://doi.org/10.1097/AAP.0000000000000720

Neal, J. M., Neal, E. J., & Weinberg, G. L. (2021). American Society of Regional Anesthesia and Pain Medicine Local Anesthetic Systemic Toxicity checklist: 2020 version. *Regional Anesthesia & Pain Medicine, 46*(1), 81–82. https://doi.org/10.1136/rapm-2020-101986

Operating Room Nurses Association of Canada. (2023). *The ORNAC standards, guidelines, and position statements for registered nurses* (16th ed.). https://www.csagroup.org/store/product/2430812/

Thrombosis Canada. (n.d.). *Thrombosis Canada* [Website]. Retrieved October 25, 2026, from https://thrombosiscanada.ca/

Urbach, D. R., Govindarajan, A., Saskin, R., Wilton, A. S., & Baxter, N. N. (2014). Introduction of surgical safety checklists in Ontario, Canada. *New England Journal of Medicine, 370*(11), 1029–1038. https://doi.org/10.1056/NEJMsa1308261

World Health Organization. (2018). *Global guidelines for the prevention of surgical site infection* (2nd ed.). https://www.who.int/publications/i/item/9789241550475

World Union of Wound Healing Societies. (2018). *Consensus document. Surgical wound dehiscence: Improving prevention and outcomes*. Wounds International. https://woundsinternational.com/wp-content/uploads/2023/02/3bc56168ce170d2745c58ebf922a75e1.pdf

Zhang, Y., He, S.-T., Nie, B., Li, X.-Y., & Wang, D.-X. (2020). Emergence delirium is associated with increased postoperative delirium in elderly: A prospective observational study. *Journal of Anesthesia, 34*(5), 675–687. https://doi.org/10.1007/s00540-020-02805-8

08 Older Adults in Acute Care

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Distinguish normal aging from disease, and explain how frailty shapes the risks of acute care.
2. Recognize, prevent and manage delirium, and distinguish it from dementia and depression.
3. Provide person-centred care for people living with dementia, including responding to responsive behaviours and partnering with caregivers.
4. Screen for depression in older adults and respond to signs of risk.
5. Prevent falls and functional decline in hospital, and respond safely after a fall.
6. Identify potentially inappropriate medications for older adults and explain the nurse's role in deprescribing.
7. Apply least-restraint principles, Ontario restraint law, and capacity and consent principles in caring for older adults.
8. Plan safe transitions from hospital, including support for caregivers.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 4, 6	Clinician; Scholar	Foundations of Practice
3, 5, 8	Clinician; Advocate; Coordinator	Foundations of Practice; Collaborative Practice
7	Advocate; Professional	Legal Practice; Ethical Practice

Introduction

On any medical or surgical unit in Canada, many of the patients in the beds are older adults. Almost one in five people in Canada was 65 or older on July 1, 2025 (Statistics Canada, 2025), and people in later life are often the ones admitted with pneumonia, heart failure, a fractured hip or a planned joint replacement. Hospital care can cure the illness that brought an older person in and still leave them worse off. Delirium, falls, loss of strength and loss of independence can all start during a stay that was meant to help.

This chapter prepares the nurse to protect older adults from those harms. Section 8.1 describes aging, frailty and the hazards of the hospital stay. Section 8.2 covers delirium in full, and section 8.3 covers dementia and depression in hospital. Sections 8.4 to 8.6 continue with falls and functional decline, safer use of medications, restraint minimization, elder abuse and transitions out of hospital. Related topics live elsewhere: consent, capacity and substitute decision-makers (Chapter 1), infection in older adults (Chapter 4), pain assessment in people living with dementia (Chapter 5), postoperative delirium (Chapter 7), palliative care (Chapter 10), alcohol withdrawal (Chapter 11) and pressure injuries (Chapter 35).

8.1 Aging, Frailty and Acute Care

An Aging Canada

Canada's population is getting older. On July 1, 2025, 8,108,467 people in Canada were aged 65 or older, which was 19.5% of the population; the share ranged from 5.2% in Nunavut to 25.2% in Newfoundland and Labrador (Statistics Canada, 2025). The oldest group is growing quickly. The 2021 Census counted more than 861,000 people aged 85 or older, 12% more than in 2016, and Statistics Canada (2022) projects that this group could roughly triple, to nearly 2.5 million people, by 2046.

Normal Aging and Disease

The most important age-related change for acute care is a loss of **physiological reserve**, the spare capacity that organs draw on under stress. An older person may manage well day to day yet have little margin when illness, surgery or a new drug adds strain.

Several age-related changes affect hospital care:

- **Kidneys:** the number of working nephrons falls with age. In carefully screened healthy kidney donors, glomerular filtration rate (GFR) fell by about 6.3 mL/min/1.73 m² per decade (Denic et al., 2016). Because older adults usually have less muscle, a serum creatinine in the reference range can hide reduced kidney function, which matters for drug dosing and for the risk of acute kidney injury (Denic et al., 2016).
- **Thirst and fluids:** older adults usually drink enough in daily life, but when they are short of fluid or heat-stressed they feel less thirsty and drink less, so fluid balance recovers more slowly (Kenney & Chiu, 2001). An older patient who is ill, confused or unable to reach a cup can become dehydrated quickly (see Chapter 3).
- **Temperature:** fever may be lower or absent in an older adult with a serious infection; atypical presentation of infection is taught in Chapter 4.
- **Skin, senses and sleep:** thinner skin breaks down more easily (Chapter 35); vision and hearing loss make a strange ward harder to understand; sleep becomes lighter, and hospital noise disturbs it further.

None of these changes is a disease. New confusion, incontinence, falls or a sudden inability to walk are not "just old age"; they signal that something is wrong. Assuming otherwise is a form of **ageism**: stereotyping, prejudice or discrimination against people because of their age. In care, ageism looks like talking to the daughter instead of the patient or offering less treatment without asking what the person wants.

Frailty

Frailty is a state in which a lifetime of small declines across many body systems has used up the body's reserves, so that a minor stressor, such as a urinary tract infection or a new drug, causes a large and sometimes lasting change in health (Clegg et al., 2013). Frailty is linked to falls, disability, hospital admission and death, and recognizing it helps the team match treatment to the person and plan goal-directed care (Clegg et al., 2013). Frailty is related to age but is not the same thing; many very old people are not frail.

The **Clinical Frailty Scale (CFS)** is a Canadian tool that summarizes an older adult's overall fitness or frailty after a clinical encounter. It came out of the Canadian Study of Health and Aging (Rockwood et al., 2005). It is not a questionnaire. The clinician uses judgment to place the person on a nine-level scale, from very fit to terminally ill, according to how they manage mobility, daily activities and their illnesses (Geriatric Medicine Research, Dalhousie University, n.d.). Version 2.0, released in 2020, made small changes to the level names and descriptions (Rockwood & Theou, 2020).

The CFS rates the person's usual state before the current illness, so the nurse asks family how the person was managing before they became sick. It has not been widely validated in younger people or in people with a stable disability affecting one body system, and it requires clinical judgment (Rockwood & Theou, 2020). Teams use the score to anticipate risk and guide conversations about goals of care, never by itself as a reason to withhold treatment.

Hospital-Associated Disability

Hospital-associated disability is a new loss of the ability to carry out a basic activity of daily living, such as bathing, dressing or walking across a room, that appears during a hospital stay and is not caused directly by the illness itself. Covinsky et al. (2011) describe it as common in hospitalized older adults, and it can develop even when the illness that brought the person in is treated successfully.

Much of this disability comes from the hospital routine. Bed rest causes rapid muscle loss, intravenous poles and urinary catheters discourage walking, and patients are often helped with tasks they could do themselves (Covinsky et al., 2011). The nurse counters these harms by recording how the person managed before admission, getting them up and walking early and often, encouraging them to wash and dress themselves, removing tethering devices as soon as possible, and starting discharge planning on admission. Falls and mobility are taught in section 8.4.

Alternate Level of Care

Alternate level of care (ALC) describes a patient who no longer needs the intensity of hospital care but stays in a hospital bed until a more suitable setting is available, such as rehabilitation, complex continuing care, home care or long-term care (Canadian Institute for Health Information [CIHI], 2026a; Canada's Drug Agency, 2025). In 2024–2025, 6.1% of acute inpatient hospital stays in Canada included ALC days (CIHI, 2026a). Because ALC patients stay longer, their share of hospital days is larger: in 2022–2023, patients designated ALC accounted for an estimated 17.0% of hospital days, ranging from 6.8% to 26.1% across provinces and territories (Canada's Drug Agency, 2025).

Older adults are the most common group of ALC patients (Canada's Drug Agency, 2025), and a long wait in an acute care bed is not harmless. ALC patients are at risk of hospital-acquired infection and of deconditioning and loss of function, and people living with frailty or dementia face added risks of falls and delirium (Canada's Drug Agency, 2025). ALC status is a reason to keep the person moving, engaged and eating, and to keep the care plan active rather than custodial.

Diverse Older Adults

Life experience shapes how older adults meet the health system. Indigenous older adults may carry the effects of residential schools and racism in health care, along with strengths of family, community, language and culture. In many First Nations, Inuit and Métis communities, Elder is a role the community gives for knowledge and wisdom, not a word for any older person; the nurse asks how the patient wishes to be addressed and whether they want family, an Elder or an Indigenous patient navigator involved (see Chapter 2).

Many older 2SLGBTQI+ adults grew up when their identities were criminalized or treated as illness, and some hide who they are from care providers; the nurse asks inclusively about family and supports, which may include a partner or chosen family. Older newcomers may speak little English or French, and professional interpreters, not relatives, are used for clinical conversations (see Chapter 1, section 1.7). For older adults from rural, remote and northern communities, discharge planning must account for distance, travel and local services.

CANADIAN CONTEXT

An Aging Population and Hospital Care

Canada's oldest age group is growing quickly. Statistics Canada (2022) projects that the number of people aged 85 or older could roughly triple between 2021 and 2046, to nearly 2.5 million. This is the age group most likely to live with frailty, dementia and several chronic conditions at once.

Hospitals already feel the pressure. In 2022–2023, patients designated ALC used an estimated 17.0% of hospital days in Canada; older adults are the most common group of ALC patients, many of them waiting for rehabilitation, home care or long-term care (Canada's Drug Agency, 2025). When acute beds are full, emergency departments back up and surgeries are delayed.

Nurses can help in practical ways:

- Ask about the patient's usual function and home supports on admission, and record them.
- Get older patients out of bed and walking early, unless there is a clear reason not to.
- Start discharge planning on day one, with the patient, family and team.
- Keep ALC patients active and engaged so they do not lose the abilities they will need in the next setting.

8.2 Delirium

What Delirium Is

Delirium is a sudden disturbance of attention and awareness, with changes in thinking, memory, perception or language, that develops over hours to days, tends to come and go during the day, and is caused by a medical condition, a drug or several factors together (Wilson et al., 2020). The *Diagnostic and Statistical Manual of Mental Disorders*, fifth edition (DSM-5), is the most widely used reference standard for diagnosis (Wilson et al., 2020). The core problem is inattention: the person cannot focus, follow a conversation or keep track of a question.

Delirium is common in hospital and often missed. The Registered Nurses' Association of Ontario (RNAO, 2016) reports that it affects up to half of hospitalized older adults, with higher rates in intensive care, after hip fracture and after surgery such as cardiac surgery. Across 17 studies of the 4AT in older adults in acute medicine, surgery, a care home and emergency departments, delirium was present in 24.2% of assessments overall (Tieges et al., 2021).

Delirium is dangerous. In a meta-analysis of older patients followed after discharge, delirium was linked with a higher risk of death (adjusted hazard ratio 1.95), admission to a care institution (odds ratio 2.41) and, in two studies followed for about four years, a much higher risk of dementia (Witlox et al., 2010). Delirium also increases the risk of falls and loss of function. Because it signals that the brain is failing under stress from an underlying illness, new delirium is treated as an urgent change in condition that the nurse reports at once.

Three Subtypes

Delirium is described by how the person behaves:

- **Hyperactive delirium:** the person is restless, agitated or fearful, may pull at lines and tubes, try to climb out of bed, or see and hear things that are not there. It is noticed quickly because it disrupts care.
- **Hypoactive delirium:** the person is quiet, drowsy, slow to respond and withdrawn, moves little and eats little. It is often missed because the person seems calm or tired (National Institute for Health and Care Excellence [NICE], 2023), and it can be mistaken for depression (RNAO, 2016).
- **Mixed delirium:** the person moves between the two patterns, sometimes within the same shift.

The hypoactive form is the one the nurse must look for deliberately. A patient who "slept all day", stopped eating or "isn't herself" needs an assessment for delirium, not a quiet room.

Risk Factors and Precipitants

Delirium usually results from the meeting of a vulnerable brain and one or more triggers (Wilson et al., 2020). The more vulnerable the person, the smaller the trigger needed to tip them into delirium.

Predisposing factors are present before admission. NICE (2023) identifies people as at risk if they are 65 or older, have past or present cognitive impairment or dementia, have a current hip fracture, or are severely ill. Frailty, vision or hearing impairment and a previous episode of delirium add to the risk.

Precipitating factors are new insults during the illness or stay:

- infection, hypoxia, dehydration and electrolyte changes such as hyponatremia (Chapters 3 and 4);
- pain that is not recognized or treated (Chapter 5);
- surgery and anesthesia (Chapter 7);
- urinary retention and constipation;
- sleep loss, immobility, and urinary catheters or other tethering devices;
- drugs, especially those with anticholinergic effects, benzodiazepines and other sedatives, and opioids (section 8.5);
- withdrawal from alcohol or sedatives (Chapter 11).

Often several causes act together, so finding one does not end the search.

Screening

Delirium is easier to recognize when the nurse knows the person's usual self. On admission, the nurse asks family or caregivers how the person normally thinks, talks and manages, then uses a validated tool to screen people at risk. NICE (2023) advises checking for risk factors when people first present to hospital and observing all patients at least daily for recent changes, and RNAO (2016) recommends assessment at least daily and whenever a change is noticed. Many hospitals screen each shift; the nurse follows employer policy.

The **Confusion Assessment Method (CAM)** is the main screening tool used in this book (Inouye et al., 1990). It asks the assessor to judge four features after a brief interaction and cognitive test:

- an acute change from the person's baseline, or a course that fluctuates during the day;
- inattention;
- disorganized thinking;
- an altered level of consciousness, either reduced (drowsy, hard to rouse) or heightened (hyperalert).

The first two features form the core. A screen is positive when both core features are present together with at least one of the other two (Inouye et al., 1990). In its original study, the CAM took less than five minutes. Assessors are trained to use the tool as its developers intend.

The **4AT** is a brief alternative that usually takes less than two minutes and is designed for routine use in everyday clinical practice (Bellelli et al., 2014; Tieges et al., 2021). It looks at the person's alertness, a short orientation test, a simple attention task and whether there has been an acute change or fluctuation, and a higher score suggests possible delirium. A review of 17 studies found that it detects delirium accurately in older adults across several settings (Tieges et al., 2021).

A positive screen is not a diagnosis. It is a finding that the nurse reports promptly so the prescriber can assess the patient and search for the cause.

Table 8.1 Delirium, dementia and depression compared (RNAO, 2016; NICE, 2023; Wilson et al., 2020)

Feature	Delirium	Dementia	Depression
Onset	Sudden, over hours to days	Slow, over months to years	Over weeks to months, often after loss or illness
Course	Comes and goes during the day; often worse at night	Gradual, steady decline	Persistent low mood most of the day
Attention	Poor; cannot focus or follow a conversation	Usually intact until later stages	May be reduced; effort is poor
Consciousness	Altered; drowsy or hyperalert	Clear until late stages	Clear
Thinking	Disorganized, rambling or illogical	Memory loss and trouble with reasoning and language	Slowed; negative and hopeless thoughts
Mood	Fearful, irritable, flat or changeable	Varies; may be anxious or apathetic	Sad, empty or irritable; loss of interest and pleasure
Reversibility	Often reversible when the cause is treated; recovery may be slow or incomplete	Progressive; not reversible	Treatable; usually improves with care
What the nurse does first	Reports at once and looks for causes	Learns the person's history, routines and needs	Asks about thoughts of suicide and reports

The three conditions can occur together. Delirium often develops in a person already living with dementia, and hypoactive delirium can look like depression (RNAO, 2016) (Table 8.1).

Preventing Delirium

Much delirium in hospital can be prevented with simple, consistent care. The Hospital Elder Life Program (HELP) tested a **multicomponent prevention** approach in 852 patients aged 70 or older admitted to hospital. The intervention targeted six risk factors: cognitive impairment, sleep loss, immobility, vision impairment, hearing impairment and dehydration. Delirium developed in 9.9% of patients on the intervention unit and 15.0% of those receiving usual care (matched odds ratio 0.60), and intervention patients had fewer days and episodes of delirium (Inouye et al., 1999). A later meta-analysis of 14 studies found that multicomponent programs lowered the odds of delirium (odds ratio 0.47) and of falls (odds ratio 0.38) (Hshieh et al., 2015). RNAO (2016) recommends a tailored, non-drug, multicomponent prevention plan for every person at risk.

Prevention depends on the whole team doing the basics every day, on every shift (Table 8.2). Avoiding unnecessary moves between rooms and units also helps the person stay oriented (NICE, 2023).

Table 8.2 Multicomponent delirium prevention: what the nurse does (Inouye et al., 1999; NICE, 2023; RNAO, 2016)

Area	Nursing actions	Why
Orientation and engagement	Introduce yourself and your role; keep a clock and calendar in view; talk about the day; encourage visits and familiar activities	Helps the person make sense of a strange place
Vision and hearing	Make sure glasses, hearing aids and dentures are in use, clean and working; check for ear wax; face the person and speak clearly	The brain misreads what it cannot see or hear
Sleep	Group night-time care; dim lights and reduce noise; offer a warm drink, toileting and comfort instead of a sleeping pill	Sleep loss worsens attention and mood
Hydration and nutrition	Keep drinks within reach and offer them often; help with meal set-up and feeding; check dentures; track intake	Dehydration and poor intake are common triggers
Bowel and bladder	Avoid or remove urinary catheters early; check for retention and constipation; offer regular toileting	Retention, constipation and catheters can provoke delirium
Mobility	Get the person up and walking early and often; do range-of-motion exercises for those who cannot walk	Immobility weakens body and mind
Pain	Assess pain regularly, including non-verbal signs in people who cannot report it (Chapter 5)	Untreated pain is a trigger
Medications and oxygen	Ask for a medication review; question new sedatives and drugs with anticholinergic effects; check oxygen saturation	Drugs and hypoxia are frequent causes

Caring for a Patient With Delirium

Care has five parts. First, the nurse reports the change promptly and clearly, using SBAR (see Chapter 6), and in Ontario an RPN consults the RN as the patient's needs change. Second, the team looks for and treats the causes (NICE, 2023). The nurse supports this by checking vital signs, oxygen saturation and blood glucose, looking for signs of infection, checking for urinary retention and constipation, assessing pain, reviewing recent medications with the pharmacist and prescriber, and asking about alcohol use.

Third, the nurse keeps the person safe while respecting their dignity. Calm, short explanations, reorientation, a quiet well-lit room, a familiar staff member and a family member at the bedside often do more than any drug. Physical and chemical restraints increase harm and are used only as a last resort (section 8.6). Fourth, the nurse continues all the prevention measures in Table 8.2, because they also help the person recover.

Fifth, medications are used carefully. Antipsychotics do not treat delirium itself (Wilson et al., 2020) and are not given routinely. Guidelines reserve them for short-term use when a person is severely distressed or is a danger to themselves or others and calming approaches have not worked (Gage & Hogan, 2014; NICE, 2023). Antipsychotics carry added risk in people with Parkinson disease or dementia with Lewy bodies (Gage & Hogan, 2014; NICE, 2023). Benzodiazepines and other sedative-hypnotics are not a first choice for delirium or agitation in older adults; benzodiazepines are reserved for situations such as alcohol withdrawal, which is taught in Chapter 11 (Canadian Geriatrics Society, 2025).

Delirium is usually temporary (NICE, 2023), but symptoms can persist, and some people do not return to their earlier level of function (Gage & Hogan, 2014; Witlox et al., 2010). The nurse explains this to the patient and family, records the episode in the discharge summary, and makes sure the diagnosis reaches the person's primary care record (NICE, 2023).

CLINICAL JUDGMENT

A Quiet Change After Surgery

Names and details are fictional; this is a composite story.

Rosa Ferreira, 82, is on day 2 after surgical repair of a hip fracture. On admission she was chatty, lived alone and used a cane. Today the night nurse reports that she was "tired" and "slept well". At 1000 she is curled in bed with her breakfast untouched.

Recognize cues: Mrs. Ferreira opens her eyes to her name but drifts off mid-sentence. She cannot say the days of the week backwards. Her lower abdomen is full, and she has passed little urine since her catheter was removed yesterday. Her temperature is 37.4 °C. The medication record shows a sleep aid with strong anticholinergic effects given at 2300.

Analyze cues: The change is new, she cannot hold attention, and she is drowsier than normal.

Prioritize hypotheses: Hypoactive delirium is the leading concern. Possible causes include urinary retention, the sleep aid, pain, infection and dehydration.

Generate solutions: Complete the CAM, do a bladder scan, assess pain, check oxygen saturation and recent intake, and call her son about her usual self.

Take action: The CAM is positive. The bladder scan shows a large volume. The nurse reports to the surgical resident using SBAR and receives an order for catheterization and a review of her sleep medication. The nurse asks her son to visit with her glasses and hearing aid.

Evaluate outcomes: The nurse repeats the CAM each shift. Over the next two days, Mrs. Ferreira becomes more alert, walks to the bathroom with help and eats half her meals. The team continues prevention measures, tells her son that recovery may take a few weeks, and documents the episode for her discharge plan.

PATIENT EDUCATION

Families as Partners in Preventing Delirium

Families know the person best and are often the first to notice that something is wrong. The nurse invites them to help:

- Bring in glasses, hearing aids, dentures and walking aids, and make sure they are used (Figure 8.1).
- Bring a few familiar things from home, such as photos or a favourite blanket.
- Tell staff about the person's usual self: how they think and talk, their routines, what calms them and what upsets them.
- Talk about the day, the date and family news, and help the person stay in touch with home.
- Help with meals and drinks, and with walking when staff say it is safe.
- Tell the nurse at once about any sudden change, such as new confusion, unusual sleepiness, or the person "not being themselves".

Delirium is common and usually improves, but it can be frightening for the person and the family. The nurse explains what it is, that the person is not "going crazy", and that recovery may be slower than the illness that caused it.

Figure 8.1 Placing a hearing aid. Glasses and hearing aids that are in use, clean and working help prevent delirium and falls, and help the person take part in care.

8.3 Dementia and Depression in Hospital

Dementia

Dementia is an umbrella term for conditions in which memory and other thinking abilities decline gradually and steadily, enough to interfere with daily life (RNAO, 2016). Types include Alzheimer disease, vascular dementia, Lewy body dementia and frontotemporal dementia, and some people have mixed dementia, a combination of more than one type (Public Health Agency of Canada [PHAC], 2026). Symptoms differ from one person to the next.

Dementia is common in older patients. Canadian surveillance data from 2013–2014 (excluding Saskatchewan) found that 7.1% of people aged 65 and older were living with diagnosed dementia, rising to 24.6% of those aged 85 and older, and that about two-thirds of seniors with dementia were women (PHAC, 2017). The age-standardized rate of new diagnoses among people aged 65 and older fell from 1,507 to 1,411 per 100,000 between 2012–2013 and 2022–2023 (PHAC, 2026), but the number of people affected keeps growing as the population ages.

Hospital is a hard place for a person living with dementia. New noise, faces and routines, combined with acute illness, put them at high risk of delirium; when delirium develops on top of dementia, the change can be mistaken for "the dementia getting worse" (RNAO, 2016). Pain is often under-recognized because the person may not be able to describe it, and is assessed with tools such as the Pain Assessment in Advanced Dementia (PAINAD) scale (see Chapter 5, section 5.2). Decisions about treatment involve the person as far as they are able, along with their substitute decision-maker (see Chapter 1, section 1.5).

Person-Centred Care

Person-centred care means knowing the patient as a whole person, honouring their choices and sharing decisions with them and those close to them (RNAO, 2016). For a person living with dementia, it begins with learning who they are: their life history and work, the name they like to be called, their routines for waking, eating, bathing and sleeping, what comforts them, and what has upset them before. Many hospitals use a short "about me" form that family completes and that stays at the bedside.

Family and other care partners are part of the care team. They can explain what the person's words and actions mean, help at mealtimes and calm the person through frightening moments. Consistent staff, a predictable routine and plain communication help too. The nurse approaches from the front, introduces themselves each time, speaks in short sentences, gives one step at a time, allows time to answer and pays attention to tone and body language.

Responsive Behaviours

Responsive behaviours are the actions, words and gestures through which a person living with dementia, a mental health or substance use condition, or another neurological condition reacts to something that matters to them in their surroundings, whether personal, social or physical (Behavioural Supports Ontario [BSO], n.d.). Examples include calling out, pacing, repeating the same question, resisting care, grabbing, hitting and sexually expressive actions. The term is preferred by people living with these conditions because it puts the focus on what can be changed (BSO, n.d.). The behaviour is often a way of communicating an unmet need (BSO, n.d.), such as pain, fear, hunger, thirst, a full bladder, boredom, cold, a noisy room or an unfamiliar person doing intimate care.

The nurse treats a responsive behaviour as a clue. The first step is to look for a trigger: when did it start, what was happening, and is the person ill, in pain or developing delirium? Non-drug approaches come first (RNAO, 2016): meet the need, change the approach or the environment, try again later, involve someone familiar, and offer meaningful activity. Behavioural Supports Ontario teams and geriatric mental health services can advise on complex situations.

Antipsychotics have a small role and real risks. In 2005, Health Canada warned that older adults with dementia treated with atypical antipsychotics for behavioural symptoms had a higher risk of death than those given placebo (about 1.6 times higher), mostly from heart-related events and infections such as pneumonia (Health Canada, 2005). Antipsychotics also carry particular risks for people living with Lewy body dementia or Parkinson disease (Gage & Hogan, 2014; NICE, 2023). A 2025 Canadian guideline on behavioural and psychological symptoms of dementia includes recommendations on deprescribing (reducing or stopping) antipsychotics and other psychotropic drugs (Hatch et al., 2025). The nurse reports a new or worsening behaviour, documents what was tried, and asks for regular review of any antipsychotic.

Depression

Depression is a sustained disturbance of mood, often with loss of interest or pleasure, that changes how a person thinks, feels and functions (RNAO, 2016). It is not a normal part of aging. RNAO (2016) estimates that it affects about 15% of older adults living in the community and about 35% of those in long-term care facilities.

In older adults, depression does not always look like sadness. Signs that should prompt screening include many physical complaints, new anxiety, ongoing trouble sleeping, refusing to eat or neglecting personal care, and complaints about memory (Canadian Coalition for Seniors' Mental Health [CCSMH], 2021). Hypoactive delirium and early dementia can look similar, so the nurse checks for delirium first (Table 8.1). When depression is suspected, a validated screening tool is used, such as the Geriatric Depression Scale (GDS) or the Patient Health Questionnaire-9 (PHQ-9) (CCSMH, 2021; RNAO, 2016).

Depression in later life carries a risk of suicide. RNAO (2016) notes that depression can lead to death by suicide, particularly among men older than 85. When depression is suspected or present, the nurse asks directly and calmly about thoughts of self-harm or suicide (CCSMH, 2021); research has not found that asking about suicide increases suicidal thoughts (Dazzi et al., 2014). A patient who has thoughts of suicide needs immediate safety measures and urgent assessment (RNAO, 2016): the nurse stays with the person or arranges close observation, removes items that could cause harm, and reports at once to the RN, prescriber or mental health team according to policy. The 9-8-8: Suicide Crisis Helpline, launched across Canada on November 30, 2023, offers support by phone call or text 24 hours a day in English and French (PHAC, 2023). When there is an immediate risk to safety, the nurse calls 9-1-1 or the hospital's emergency team.

8.4 Falls and Functional Decline

Falls and loss of function are common, often preventable harms of a hospital stay for older adults.

Falls in Older Adults

The RNAO defines a **fall** as an unintentional event that ends with a person resting on the ground, the floor or another lower level, whether or not an injury occurs (RNAO, 2017). Several risk factors usually act together.

Canadian surveillance data show the size of the problem (PHAC, 2024):

- In 2017–2018, 5.8% of adults aged 65 and older living in households reported a serious injury from a fall in the previous 12 months.
- Outside Quebec, yearly fall-related hospitalizations of adults aged 65 and older rose 47% between 2008/2009 and 2019/2020, to 72,392. The rate stayed near 15 per 1,000, so the rise reflects a larger older population.
- Throughout this period, about 87% of injury-related hospitalizations in this age group were due to falls.
- In 2019, 5,581 Canadians aged 65 and older died from a fall.

A hip fracture was involved in 34% of fall-related hospitalizations of older adults in 2019/2020 (PHAC, 2024; Chapter 33). Older adults hospitalized after a fall stayed, on average, about 5 days longer in acute care and about 4 days longer as ALC patients than those hospitalized for any cause (PHAC, 2024; see section 8.1). A fall can also leave a lasting **concern about falling**, the term the World Falls Guidelines prefer to "fear of falling"; the person may then avoid activity, which weakens muscles and balance further (Montero-Odasso et al., 2022).

A fall in hospital may be the first sign of a new illness, such as pneumonia or a heart attack without chest pain (Montero-Odasso et al., 2022; Chapter 4), so the nurse treats it as a possible cue of deterioration.

Risk Factors

Risk factors are **intrinsic** (within the person) or **extrinsic** (in the environment, equipment or care). The main ones are linked to nursing actions in the table that follows (Table 8.3).

- **Intrinsic:** a previous fall; gait, balance and strength problems; delirium, dementia and depression; orthostatic hypotension and dizziness; impaired vision or hearing; urgency, incontinence and nocturia; foot problems and pain; neurological conditions such as Parkinson's disease; and medications, especially drugs that act on the brain or lower blood pressure (Montero-Odasso et al., 2022).
- **Extrinsic:** clutter, poor lighting and wet floors; unsafe footwear; intravenous (IV) lines, drains, catheters and oxygen tubing; a bed left high or unlocked; and a call bell or walking aid out of reach (RNAO, 2017).

The nurse screens every adult for fall risk at admission and after any significant change in health, using fall history, observed gait and mobility, and clinical judgment (RNAO, 2017). Neither RNAO (2017) nor the World Falls Guidelines support a risk score alone in hospitals; the latter recommend a multifactorial assessment of each hospitalized adult over 65 (Montero-Odasso et al., 2022). Where policy requires a tool, the nurse completes it and then acts on the person's specific risks.

Table 8.3 Fall risk factors and nursing actions (Montero-Odasso et al., 2022; RNAO, 2012, 2017)

Risk factor	Why it raises risk	Nursing actions
Previous fall	Signals risk factors that are still present; two or more falls in a year marks high risk	Ask about falls at admission; flag the risk in handover; request a multifactorial assessment
Gait, balance and strength problems	Among the most consistent predictors of future falls; bed rest weakens muscles quickly	Walk with the patient; keep the walking aid within reach; refer to physiotherapy
Delirium, dementia and depression	Impair attention, judgment and memory of safety teaching	Screen for delirium (section 8.2); orient; involve family; round often; avoid restraints

Risk factor	Why it raises risk	Nursing actions
Orthostatic hypotension	Blood pressure falls on standing, causing dizziness or fainting	Measure lying and standing blood pressure; teach slow position changes; report results
Impaired vision or hearing	Hazards and instructions are missed, especially at night	Keep glasses and hearing aids on and clean; use a night light; speak face to face
Urgency, incontinence and nocturia	Hurried, unsupervised trips to the bathroom, often in the dark	Offer scheduled toileting, including before sleep; keep the path clear; answer call bells quickly
Medications that act on the brain or lower blood pressure	Cause drowsiness, poor balance or a drop in blood pressure	Review the medication list with the prescriber and pharmacist; watch closely after new doses (section 8.5)
Unsafe footwear and environment	Slippery socks, clutter, wet floors and poor lighting cause trips and slips	Provide non-slip footwear; clear clutter; dry spills; light the room
Lines, tubes and bed set-up	Tubing tethers or trips the person; a high or unlocked bed increases the drop	Keep the bed low and locked; secure tubing; ask daily whether each line is still needed

Preventing Falls

Universal fall precautions are basic safety measures used for every patient, whatever the risk (RNAO, 2017). Examples include keeping the call bell, glasses, hearing aids, walking aid and drinks within reach; a low bed with the brakes locked; good lighting, including a night light; clear paths to the bathroom; non-slip footwear; and regular rounding to anticipate toileting, pain and repositioning needs (RNAO, 2012, 2017).

For patients at higher risk, the team adds **targeted interventions** matched to the person's risk factors (Montero-Odasso et al., 2022; RNAO, 2017):

- **Supervised, progressive mobility,** with referral to physiotherapy for strength and balance (Figure 8.2).
- **Scheduled toileting,** including before sleep.
- **Orthostatic vital signs: orthostatic hypotension** is a sustained fall in systolic blood pressure of at least 20 mm Hg, or in diastolic blood pressure of at least 10 mm Hg, within 3 minutes of standing (Fedorowski et al., 2017). Blood pressure is measured after at least 5 minutes lying down, then on standing as soon as possible and each minute up to 3 minutes, while asking about dizziness (Montero-Odasso et al., 2022). The nurse reports a positive result and teaches the patient to sit before standing.

Figure 8.2 A two-wheeled folding walker used to support balance and safe mobilization in hospital and at home. (credit: “Walker. frame” by High Plains Drifter/Wikimedia Commons, Public domain)

- **Medication review** with the prescriber to reduce or stop drugs linked to falls (RNAO, 2017; section 8.5).
- **Hip protectors,** which can be considered for people at risk of hip fracture after discussing benefits and drawbacks with them (RNAO, 2017) (Figure 8.3).
- **Low beds and alarms:** a low bed reduces injury if the person rolls out, and an alarm can alert staff when a person at risk gets up (RNAO, 2012), but only if someone responds quickly.
- **Delirium prevention** (section 8.2), which may also reduce falls (Montero-Odasso et al., 2022).

Figure 8.3 A hip protector: fitted underwear with a pad over the outer hip to cushion a fall. Hip protectors can be considered for people at risk of hip fracture after a discussion of benefits and drawbacks. (credit: "AHIP Protector" by Lkshlzr/Wikimedia Commons, CC BY-SA 3.0)

Restraints and sedating drugs are not fall prevention: RNAO (2017) cautions that they can cause harm, and the World Falls Guidelines recommend against physical restraints to prevent falls in care homes (Montero-Odasso et al., 2022). The nurse teaches the patient and family in their preferred language (RNAO, 2017).

After a Fall

The nurse stays, calls for help and assesses before anyone moves the patient (see the Clinical Safety box). RNAO (2017) recommends examining for injury, treating, monitoring for injuries that appear later, and completing a **post-fall assessment** with the team. Dizziness, palpitations or a brief loss of consciousness before the fall suggest a cause such as syncope that needs medical evaluation. An injury needing treatment, being unable to get up alone for an hour or more, or two or more falls in the past year marks high risk and calls for a multifactorial assessment (Montero-Odasso et al., 2022).

A patient taking an anticoagulant such as apixaban or warfarin (Chapter 19) who strikes the head can bleed inside the skull with few signs at first. In the United Kingdom, NICE head injury guideline advises considering a computed tomography (CT) scan of the head within 8 hours of the injury for such patients, even without other signs (NICE, 2023, as cited in Royal College of Emergency Medicine et al., 2023). Canadian hospitals set their own protocols, and imaging is ordered by the prescriber, so the nurse reports the fall and the anticoagulant to the prescriber at once, starts neurological observations as policy directs (Chapter 30), watches for headache, vomiting, drowsiness, confusion or weakness (Chapter 32), and escalates any decline (Chapter 6).

A **post-fall huddle** is a short team meeting soon after a fall to work out why it happened and change the plan; RNAO (2017) includes one in an example post-fall review. The nurse documents the facts objectively, completes an incident report and informs the family or substitute decision-maker (SDM). Reporting supports learning, not blame (Chapter 1, section 1.6).

CLINICAL SAFETY

After a Fall

- **Stay and call for help.** Do not lift the patient yet.
- **Assess airway, breathing, circulation and responsiveness.** If the patient is unresponsive or not breathing normally, call the emergency team.
- **Check for injury before moving.** Look for a head strike, bleeding, pain, deformity, or a shortened or outward-turned leg. Keep the patient still if a spinal injury is possible.
- **Assess neurological status.** Check level of consciousness, orientation, pupils and limb movement, and compare with baseline.
- **Ask about anticoagulants.** Check the medication record. An anticoagulated patient with a possible head strike needs urgent notification of the prescriber.
- **Notify.** Report to the RN or charge nurse and the prescriber using SBAR (Situation, Background, Assessment, Recommendation; Chapter 6).
- **Lift safely.** Use a mechanical lift or enough trained staff, as policy directs.
- **Monitor.** Take vital signs and neurological observations as ordered or as policy directs, and watch for delayed signs.
- **Huddle.** Review what happened with the team and update the plan.
- **Document and report.** Record facts objectively and complete an incident report.

- **Inform the family or SDM.**

Preventing Functional Decline

Functional decline is a loss of the ability to carry out daily activities such as walking, bathing, dressing and toileting (hospital-associated disability is explained in section 8.1). Bed rest contributes to delirium, pressure injuries, pneumonia and muscle loss; estimates suggest an older person can lose 1% to 5% of muscle strength for each day without moving, yet older patients on medical units have been observed out of bed for a median of only about 4% of the day (Liu et al., 2018).

MOVE ON (Mobilization of Vulnerable Elders in Ontario) was a staff-focused program on general medical units in 14 Ontario academic hospitals. Teams assessed each older patient's mobility within 24 hours of admission, got patients moving at least three times daily, and progressed activity to match each person's ability. Afterward, more patients were out of bed each day and median length of stay was shorter (Liu et al., 2018).

The nurse also helps the patient sit in a chair for meals and walk to the bathroom; screens food and fluid intake and helps with eating; asks that a urinary catheter be removed once it is no longer needed (Chapter 7); groups night-time care to protect sleep (section 8.2); and relieves pressure on the skin (Chapter 35).

8.5 Medications in Older Adults

Why Older Adults Are More Sensitive

Older adults are at greater risk of adverse drug reactions, partly because they take more drugs and live with more chronic conditions, and partly because aging changes how the body handles drugs (CIHI, 2026b). On average, kidney filtration declines with age, so drugs cleared by the kidneys can build up; body fat rises while total body water falls, which changes how drugs spread through the body; and liver mass decreases (Hurria & Lichtman, 2008). Older adults also seem to be at higher risk of harm from sedative drugs (Pottie et al., 2018), and an adverse effect can look different in them: low blood glucose may show as dizziness, weakness or confusion rather than sweating and tremor (Farrell et al., 2017). The Going Deeper box explains these changes.

Polypharmacy

Polypharmacy is the use of many medications at the same time. A systematic review found that the most common definition was five or more medications daily, but most definitions were simple counts, and the authors called for a shift toward the idea of "appropriate polypharmacy" (Masnoon et al., 2017). The count is a prompt for review, not a verdict: a person with several chronic conditions may need many drugs, while a person taking two may be taking one that harms them.

In Canada, 1 in 4 seniors (people aged 65 and older) had prescriptions from 10 or more unique drug classes during 2021, based on public drug program claims (CIHI, 2022). The share rose with age, from 18.2% of seniors aged 65 to 74 to 36.4% of those aged 85 and older (CIHI, 2022; these figures exclude Quebec). In 2021, 42.5% of long-term care residents in the provinces reporting data were prescribed an antipsychotic (CIHI, 2022).

Each added drug raises the chance of side effects and interactions. A **prescribing cascade** starts when an adverse drug effect is mistaken for a new condition and treated with another drug, which can cause further effects (Rochon & Gurwitz, 1997). For example, a drug that causes ankle swelling may lead to a diuretic, and the diuretic may then cause urgency and a rushed trip to the bathroom at night. The nurse helps break cascades by asking, whenever a new symptom appears, whether a medication could be the cause, and by noting when the symptom began in relation to medication changes.

Potentially Inappropriate Medications

A **potentially inappropriate medication (PIM)** is a drug that, for most older adults, is ineffective, carries an unnecessarily high risk, or has a safer alternative (CIHI, 2026b). Two explicit tools help prescribers, pharmacists and nurses find PIMs during a medication review:

- The **American Geriatrics Society (AGS) Beers Criteria**, last updated in 2023, list medications to avoid or use with caution in adults aged 65 and older in most settings of care other than hospice and end-of-life care (American Geriatrics Society Beers

Criteria Update Expert Panel, 2023). The criteria fall into five groups: medications generally best avoided; medications to avoid with certain conditions; medications to use with caution; harmful drug combinations; and medications to avoid or adjust when kidney function is reduced (Health in Aging Foundation, 2023). CIHI uses the Beers list to track PIM prescribing to Canadian seniors (CIHI, 2026b).

- **STOPP/START** version 3, a European consensus, contains 133 STOPP criteria (Screening Tool of Older Persons' Prescriptions), which flag drugs that may be causing harm, and 57 START criteria (Screening Tool to Alert to Right Treatment), which flag helpful drugs that may have been missed (O'Mahony et al., 2023). The criteria are organized by body system, with added sections on fall risk, opioids and drugs with anticholinergic effects.

Both tools support clinical judgment rather than replace it (Health in Aging Foundation, 2023; O'Mahony et al., 2023). A listed drug may still be the right choice for a particular person, and patients should talk with their prescriber before stopping any medication. Drug groups that often need review are summarized below (Table 8.4). The nurse does not stop a drug independently; the nurse notices, reports, teaches and advocates.

Table 8.4 Medication groups that often need review in older adults (sources as cited in each row)

Medication group	Examples marketed in Canada	Main concern	Nursing actions
Benzodiazepine receptor agonists (benzodiazepines and Z-drugs)	zopiclone; benzodiazepines	Drowsiness, poor balance, falls, fractures, memory problems and motor vehicle crashes (Pottie et al., 2018)	Ask about sleep aids; offer non-drug sleep measures; report daytime drowsiness or falls; support a prescriber-led taper
First-generation antihistamines	diphenhydramine	Anticholinergic effects: confusion, constipation, urinary retention and falls (Braithwaite et al., 2023)	Ask about over-the-counter sleep and nausea products; question as-needed orders for sleep; watch for confusion and retention
Other drugs with strong anticholinergic effects	oxybutynin	Effects add up across drugs; linked with delirium, falls and cognitive decline (Braithwaite et al., 2023)	Count all anticholinergic drugs; assess bowels, bladder and cognition; report new confusion
Antipsychotics in people living with dementia	quetiapine	Limited benefit for responsive behaviours; higher risk of stroke and death (Bjerre et al., 2018; Canadian Geriatrics Society, 2025)	Look for causes of behaviour first (section 8.3); use non-drug approaches; monitor during a prescriber-led taper
Sulfonylureas and insulin	insulin; sulfonylureas, especially long-acting ones	Hypoglycemia, which may present as confusion, weakness or dizziness and can lead to falls (Farrell et al., 2017)	Check blood glucose as ordered; recognize atypical signs; report low values and poor intake (Chapter 22)
Nonsteroidal anti-inflammatory drugs (NSAIDs)	prescription and over-the-counter NSAIDs, including cyclooxygenase-2 (COX-2) inhibitors	Raised blood pressure, fluid retention and worsening kidney function in people with hypertension, heart failure or chronic kidney disease (Canadian Society of Nephrology, 2025)	Ask about over-the-counter use; monitor blood pressure, weight and kidney function; report swelling or reduced urine output
Opioids combined with other drugs that act on the brain	any opioid taken with a benzodiazepine receptor agonist or a gabapentinoid (a drug used for nerve pain)	Added sedation, impaired balance and falls (Montero-Odasso et al., 2022; Chapter 5)	Assess sedation and breathing; time mobility safely; report excessive drowsiness at once

MEDICATIONS

Deprescribing a Sleeping Pill

Benzodiazepine receptor agonists (BZRAs) include benzodiazepines and the "Z-drugs" such as zopiclone. In older adults, they are linked with drowsiness, poor balance, falls, fractures, memory and thinking problems, and motor vehicle crashes, and their benefit

for sleep may fade within about 4 weeks (Pottie et al., 2018). A Canadian guideline recommends offering a slow taper to adults aged 65 and older who take a BZRA for insomnia, however long they have used it (Pottie et al., 2018).

- **Tapering is planned by the prescriber** with the patient; sudden stopping is avoided. No schedule is given here.
- **Withdrawal effects** such as anxiety, irritability, sweating and poor sleep are usually mild and short-lived (Pottie et al., 2018).
- **Non-drug help:** good sleep habits during the taper, and cognitive behavioural therapy for insomnia (CBT-I) if insomnia persists (Pottie et al., 2018).
- **The nurse** asks about all sleep aids, including over-the-counter products; reduces noise, light and night-time interruptions; teaches; and monitors and reports withdrawal effects.

Deprescribing

Deprescribing is the planned and supervised process of lowering the dose of, or stopping, a drug that may be doing harm or is no longer helping (Pottie et al., 2018). It is part of good prescribing, not a withdrawal of care. Deprescribing.org, a Canadian initiative whose partners include the Bruyère Research Institute and the University of Toronto, publishes evidence-based guidelines and algorithms for several drug classes, including benzodiazepine receptor agonists, proton pump inhibitors, antipsychotics and antihyperglycemics (deprescribing.org, n.d.).

The process usually involves reviewing why each drug was started, weighing its current benefits and harms against the person's goals, agreeing on a plan with the patient and family, tapering slowly when needed, and monitoring for a return of symptoms or for withdrawal effects (Bjerre et al., 2018; Pottie et al., 2018). The prescriber leads any change. Decisions are shared, and people who understand the reason and know what to expect are more willing to take part (Pottie et al., 2018).

The nurse's role includes:

- taking an accurate medication history, including over-the-counter drugs, sleep aids and natural health products;
- noticing possible adverse effects, such as new confusion, drowsiness, dizziness, falls, constipation, urinary retention or low blood glucose, and reporting them;
- advocating for a medication review after a fall or an episode of delirium (RNAO, 2017);
- teaching the patient and family why a change is proposed and what to watch for;
- monitoring during a taper, for example for anxiety and poor sleep after a sedative is reduced, or for returning distress after an antipsychotic is reduced (Bjerre et al., 2018; Pottie et al., 2018). Nurses are among the professionals who can do this follow-up (Pottie et al., 2018).

Transitions and Medication Reconciliation

Moves between settings are high-risk times for medication errors. Medication reconciliation and the best possible medication history are explained in Chapter 1, section 1.6. For older adults, the Canadian Geriatrics Society (2025) advises against prescribing any medication without a medication reconciliation review. At discharge, the nurse teaches from the reconciled list, explains which drugs were started, changed or stopped and why, and checks understanding with teach-back. A pill organizer or a pharmacy blister pack can help a person who takes many drugs or has memory problems, and the community pharmacist can continue the review and support a taper. The nurse makes sure the updated list reaches the next care provider and the family.

GOING DEEPER

Pharmacokinetics in Older Adults and Anticholinergic Burden

Required for RN students; optional for PN students.

Kidney function. GFR falls on average with age, although not in everyone. Serum creatinine comes from muscle, so an older adult with low muscle mass produces less of it, and a creatinine within the reference range can hide reduced kidney function (Hurria & Lichtman, 2008). Prescribers use the estimated GFR (eGFR) and the person's clinical picture when choosing and adjusting drugs cleared by the kidneys (Chapter 27).

Body composition. With age, the proportion of body fat rises and total body water falls. Fat-soluble drugs therefore spread through a larger volume, while water-soluble drugs spread through a smaller one (Hurria & Lichtman, 2008). A larger volume of distribution lengthens a drug's half-life, so a fat-soluble sedative can keep acting long after the dose. Water-soluble drugs can reach higher blood levels from the same dose.

Albumin. Many drugs travel in the blood bound to albumin, and only the unbound drug acts. Low albumin, common in acute illness and poor nutrition, changes how albumin-bound drugs are distributed (Hurria & Lichtman, 2008); more drug may be left unbound, so effects may be stronger than expected.

Liver. Liver mass decreases with age, although how much this slows drug metabolism is debated (Hurria & Lichtman, 2008).

Anticholinergic burden is the cumulative effect of all the drugs a person takes that have anticholinergic properties (Braithwaite et al., 2023). Effects include dry mouth, blurred vision, constipation and urinary retention, and a higher burden is linked with delirium, falls and cognitive and physical decline. Several scales score the burden, such as the Anticholinergic Cognitive Burden scale (Boustani et al., 2008) and the Drug Burden Index, with no clear guidance about which one to choose (Braithwaite et al., 2023). Drugs with mild effects can add up, so the nurse looks at the whole list.

8.6 Restraints, Capacity and Transitions

Least Restraint

A **restraint** is anything that restricts a person's movement or behaviour in a way the person cannot easily undo (RNAO, 2012). Restraints take three forms:

- **Physical restraint:** an object placed on or close to the body that limits movement and that the person cannot easily remove, such as mitts, wrist ties, or a lap or seat belt (RNAO, 2012).
- **Environmental restraint:** keeping a person in a limited area, such as a locked room or unit (RNAO, 2012).
- **Chemical restraint:** a medication given to control behaviour (RNAO, 2012), rather than to treat a diagnosed condition.

By this definition, raised bed rails that stop a person from getting out of bed when they wish to are a restraint.

Restraints can increase agitation, raise the risk of falls and injury, cause skin breakdown and, in some cases, death (RNAO, 2012); they are also linked with aspiration pneumonia and can keep a person from food and fluids (Canadian Geriatrics Society, 2025). An Ontario coroner's committee reviewed the death of an older man with cognitive impairment who slid down a reclining chair and was asphyxiated by its thigh belt; there was no recorded order or reassessment (College of Physicians and Surgeons of Ontario [CPSO], 2023). The Canadian Geriatrics Society (2025) advises against using physical restraints for the behavioural symptoms of delirium and dementia.

Least restraint means trying alternatives first and, if a restraint cannot be avoided, using the least restrictive form for the shortest possible time (RNAO, 2012). In Ontario hospitals, restraint use is governed by the *Patient Restraints Minimization Act, 2001*. Each hospital must have restraint policies that encourage alternatives; restrained patients must be monitored and reassessed; staff must be trained; and records must be kept (CPSO, 2023). Only a physician or a person specified by regulation may write an order to restrain (*Patient Restraints Minimization Act, 2001*). A hospital may restrain a patient when needed to prevent serious bodily harm to the patient or others, or under a plan of treatment the patient or SDM has consented to (CPSO, 2023; *Patient Restraints Minimization Act, 2001*). The Act keeps a caregiver's common law duty to restrain when immediate action is needed to prevent serious bodily harm (*Patient Restraints Minimization Act, 2001*). Outside such an emergency, if the patient cannot consent, the SDM decides (RNAO, 2012).

Alternatives start with finding the reason for the behaviour: pain (assessed with the PAINAD scale where needed; Chapter 5, section 5.2), a full bladder, constipation, hunger, fear or delirium (sections 8.2 and 8.3). The nurse then tries walking with the person, regular toileting, music or other enjoyable activities, a low bed, an alarm, and a family member, volunteer or sitter at the bedside (Canadian Geriatrics Society, 2025; RNAO, 2012).

If a restraint is used, it follows the order and policy: the team monitors closely, offers food, fluids and toileting often, reassesses regularly, removes the restraint at the earliest safe time and documents each step (CPSO, 2023; RNAO, 2012).

SCOPE IN PRACTICE

Restraints and Least-Restraint Care

Authority, competence and context guide every nurse's role in restraint decisions (Chapter 1, section 1.3).

- **Authority:** In Ontario hospitals, the *Patient Restraints Minimization Act, 2001* and the hospital's policy set when a restraint may be used. Only a physician or a person specified by regulation may write the order. In an emergency, when immediate action is needed to prevent serious bodily harm, the Act preserves the caregiver's common law duty to act (*Patient Restraints Minimization Act, 2001*); the nurse then follows hospital policy for notification, orders and documentation.
- **Competence:** Both RNs and registered practical nurses (RPNs) apply least-restraint principles: they assess causes of behaviour, try alternatives, apply only devices they have been trained to use, monitor the person and document. Each nurse uses only the skills they have.
- **Context:** As a patient's needs change, for example new agitation, delirium or a fall, the RPN consults the RN, and every nurse who notices deterioration acts at once and escalates (Chapter 6). Assigning patients by stability is a common employer practice, not a College of Nurses of Ontario (CNO) rule.
- Employer policy and the province or territory matter. Outside Ontario, other laws and policies apply.

Capacity and Substitute Decision-Makers

Consent, capacity and SDMs under Ontario's *Health Care Consent Act, 1996* are explained in Chapter 1, section 1.5. Two points matter most for older adults. First, capacity concerns a specific decision at a specific time, so a diagnosis of dementia does not by itself mean a person cannot decide. Second, delirium can make capacity come and go: a person who could not decide yesterday may be capable today, so the team reassesses before each new decision. The nurse reports changes in cognition, helps the person take part as fully as possible (choosing their most alert time of day; using glasses, hearing aids and an interpreter), and involves the SDM when the person is incapable for a decision.

Elder Abuse

Elder abuse is any act, single or repeated, or failure to act appropriately that harms or distresses an older person within a relationship in which trust is expected (World Health Organization [WHO], 2024). It may be physical, sexual, psychological or emotional, or financial, or take the form of neglect or abandonment (WHO, 2024). Possible cues include injuries that do not fit the explanation given, fear or withdrawal around a particular person, poor hygiene or weight loss, missed medications, and sudden changes in finances.

When abuse is suspected, the nurse:

- makes sure the person is safe, calling 9-1-1 for immediate danger (Elder Abuse Prevention Ontario [EAPO], n.d.);
- speaks with the person privately, with a professional interpreter if needed (Chapter 1, section 1.7);
- documents objectively, in the person's own words (Chapter 1, section 1.5);
- follows hospital policy, which usually involves a social worker;
- respects a capable person's choices about next steps while offering information and support.

Ontario's reporting duties depend on where the person lives. Anyone, including regulated health professionals, who knows or suspects that a resident of a long-term care home or a retirement home has been or may be harmed by abuse, neglect, improper care or financial misuse must report it, even if the information would otherwise be confidential (Community Legal Education Ontario [CLEO], 2025). Reports about long-term care homes go to the Director at the ministry, under the *Fixing Long-Term Care Act, 2021*, and reports about retirement homes go to the Registrar of the Retirement Homes Regulatory Authority, under section 75 of the *Retirement Homes Act, 2010* (CLEO, 2025). Ontario law sets no reporting duty when the older adult lives elsewhere, such as in their own home, although job duties or a professional code may create one (CLEO, 2025). The Seniors Safety Line (1-866-299-1011) offers confidential support 24 hours a day, with interpreters in more than 200 languages (EAPO, n.d.).

Planning Safe Transitions

Discharge planning begins at admission. The nurse learns about the person's home, function before the illness, supports and goals, and shares the fall risk and plan with the next provider at each transition (RNAO, 2017). In Ontario, Ontario Health atHome, formed on June 28, 2024, from the 14 former Home and Community Care Support Services organizations, provides home and community care, care coordination, information and referrals, and placement services for long-term care homes (Government of Ontario, n.d.). A person who no longer needs acute care but cannot yet safely leave may be designated ALC (section 8.1).

Family and friends often carry much of the care, and caring can take a physical, emotional and financial toll, often called **caregiver strain**. The nurse asks caregivers how they are coping, includes them in teaching, and connects them with care coordinators and community supports. Before discharge, the nurse confirms follow-up appointments, the reconciled medication list (section 8.5), fall prevention at home, and the warning signs that should prompt a call to the primary care provider or 9-1-1.

PRACTICE STORY

"She Wanted to Go Home"

Names and details are fictional; this is a composite story.

Nurse: Joanne Mercier, RN. Years in practice: 9. Setting: medical unit, community hospital, Ontario.

At 0200, Mrs. Rosa Esposito, 87, was at the nursing station in her gown, clutching her purse. "I have to go home. My husband is waiting." Mrs. Esposito is a person living with dementia who was admitted two days earlier with pneumonia, and since yesterday she had new delirium. A colleague said, "Let's get an order for a belt before she falls."

I knew a restraint would not answer the question of why she was up. I walked with her down the hall, and she settled a little. When I offered the bathroom, she could not void, and she grimaced and held her lower abdomen. Her PAINAD score showed pain. A bladder scan, done under our policy, showed a large volume of urine. On her medication record I saw she had been given diphenhydramine at 2200 for sleep.

I called the physician on call using SBAR. She ordered an in-and-out catheter and discontinued the diphenhydramine. Then I phoned her daughter, who is her SDM. She told me her father died years ago, and that when her mother is anxious she talks about going home to him. She suggested Italian music and talking about her garden. Our policy allowed a sitter for the rest of the night. After the catheter, with music playing and the sitter beside her, Mrs. Esposito slept by 0400. In the morning, her daughter brought photos from home, and the team reviewed all her medications.

Looking back, her responsive behaviour was telling us something. Restraining her would have hidden urinary retention and pain caused partly by a drug we gave her, and it could have made her delirium worse.

Reflect: What cues pointed to a physical cause for Mrs. Esposito's behaviour? If an RPN had been caring for her, when should the RPN have consulted the RN, and who could order a restraint under the Act and hospital policy?

Chapter 8 Summary

Introduction

- Older adults make up a large share of medical-surgical patients, and almost one in five people in Canada is 65 or older.
- A hospital stay can bring delirium, falls and loss of function, even when the illness is treated successfully.

8.1 Aging, Frailty and Acute Care

- Aging reduces physiological reserve; changes in kidney function, thirst, temperature response, skin, senses and sleep affect acute care, but new confusion or loss of function is never "just old age".
- Frailty is reduced reserve and increased vulnerability to stressors; the Clinical Frailty Scale rates the person's usual state and requires clinical judgment.
- Hospital-associated disability is common in older patients; early, frequent mobility and self-care, fewer tethering devices and early discharge planning help prevent it.
- Patients designated alternate level of care, among whom older adults are the most common group, face deconditioning, infection, falls and delirium while they wait.
- Care is shaped by each person's history and identity, including Indigenous, 2SLGBTQI+, newcomer and rural or northern older adults.

8.2 Delirium

- Delirium is an acute, fluctuating disturbance of attention and awareness with an underlying cause; it is common, often missed and linked to death, institutional care and dementia.
- Hypoactive delirium is quiet and easily mistaken for tiredness or depression.

- Delirium arises when triggers such as infection, drugs, retention, constipation, pain, surgery or sleep loss act on a vulnerable person.
- The CAM and the 4AT are brief screens; a positive screen is reported promptly so the cause can be found.
- Multicomponent, non-drug prevention reduces delirium and falls.
- Care means finding and treating causes, keeping the person safe without restraints where possible, involving family, and avoiding routine antipsychotics and not using benzodiazepines as a first choice.

8.3 Dementia and Depression in Hospital

- Dementia is common in older patients and greatly raises the risk of delirium; pain is often under-recognized.
- Person-centred care starts with knowing the person and working with family as partners.
- Responsive behaviours often communicate unmet needs; non-drug approaches come first, and antipsychotics carry serious risks in dementia.
- Depression in older adults may appear as withdrawal, poor intake or physical complaints; the nurse asks directly about suicide, keeps the person safe and reports at once.

8.4 Falls and Functional Decline

- Falls cause about 87% of injury-related hospitalizations of Canadians aged 65 and older (outside Quebec), and about a third of fall-related hospitalizations involve a hip fracture.
- Falls usually result from several intrinsic and extrinsic risk factors; a risk score alone does not replace assessing the person's own risks.
- Universal fall precautions apply to every patient; targeted interventions such as scheduled toileting, orthostatic vital signs and medication review are added for those at higher risk. Restraints are not fall prevention.
- After a fall, the nurse assesses before moving the patient and escalates urgently when a patient taking an anticoagulant may have struck the head.
- Early, frequent mobility, as in MOVE ON, together with help to eat, drink, toilet and sleep, helps prevent functional decline.

8.5 Medications in Older Adults

- Changes in kidney function, body composition, the liver and the brain make older adults more sensitive to drugs and their adverse effects.
- One in four Canadian seniors was prescribed 10 or more drug classes in 2021; a new symptom may be a drug effect that starts a prescribing cascade.
- The Beers Criteria and STOPP/START help identify potentially inappropriate medications but support, rather than replace, clinical judgment.
- Deprescribing is planned with the patient and led by the prescriber; the nurse finds adverse effects, teaches, advocates for review and monitors during tapering.
- Safe transitions depend on medication reconciliation, teach-back and sharing the updated list with the community pharmacist and next providers.

8.6 Restraints, Capacity and Transitions

- Restraints may be physical, environmental or chemical; they cause harm, and least-restraint care tries alternatives first.
- In Ontario hospitals, the Patient Restraints Minimization Act, 2001 and hospital policy govern restraint use, orders, monitoring and documentation.
- Capacity is decision-specific and may fluctuate with delirium, so it is reassessed for each decision, and the SDM is involved when the person is incapable.
- Reporting suspected harm to residents of long-term care and retirement homes is mandatory in Ontario; for older adults in the community, the nurse ensures safety, documents and supports a capable person's choices.

- Discharge planning starts at admission and includes caregivers, Ontario Health atHome and clear teaching.

Key Terms (37)

4AT: a brief delirium screening test, usually taking less than two minutes, that looks at alertness, orientation, attention and acute change.

ageism: stereotyping, prejudice or discrimination against people because of their age.

alternate level of care (ALC): the designation for a patient who no longer needs hospital-level care but stays in hospital until a better-suited place, such as home care or long-term care, is available.

anticholinergic burden: The cumulative effect of all the drugs a person takes that have anticholinergic properties.

Beers Criteria: The American Geriatrics Society's list of medications to avoid or use with caution in adults aged 65 and older, last updated in 2023.

caregiver strain: The physical, emotional and financial toll that caring for a family member or friend can take on the caregiver.

chemical restraint: A medication given to control behaviour rather than to treat a diagnosed condition.

Clinical Frailty Scale (CFS): a Canadian, judgment-based nine-level scale that summarizes an older adult's usual fitness or frailty after a clinical encounter.

concern about falling: Worry about falling, the term the World Falls Guidelines prefer to "fear of falling"; it can lead a person to avoid activity and lose strength and balance.

Confusion Assessment Method (CAM): a widely used delirium screening approach that judges acute change or fluctuation, inattention, disorganized thinking and level of consciousness.

delirium: a sudden, fluctuating disturbance of attention and awareness, with changes in thinking or perception, caused by a medical condition, a drug or several factors together.

dementia: a group of conditions in which memory and other thinking abilities decline gradually and steadily enough to interfere with daily life.

deprescribing: The planned and supervised process of lowering the dose of, or stopping, a drug that may be doing harm or is no longer helping.

depression: a sustained disturbance of mood, often with loss of interest or pleasure, that changes how a person thinks, feels and functions.

elder abuse: Any act, single or repeated, or failure to act appropriately that harms or distresses an older person within a relationship in which trust is expected; it may be physical, sexual, psychological or emotional, or financial, or take the form of neglect or abandonment.

fall: An unintentional event that ends with a person resting on the ground, the floor or another lower level, whether or not an injury occurs.

frailty: a state in which accumulated decline across many body systems has used up physiological reserve, so that a minor stressor can cause a large, sometimes lasting change in health.

functional decline: Loss of the ability to carry out daily activities such as walking, bathing, dressing and toileting.

hospital-associated disability: a new loss of ability to perform a basic activity of daily living that develops during a hospital stay and is not caused directly by the illness itself.

hyperactive delirium: delirium in which the person is restless, agitated or fearful and may have hallucinations.

hypoactive delirium: delirium in which the person is quiet, drowsy, slow and withdrawn; it is often missed.

least restraint: Trying alternatives first and, if a restraint cannot be avoided, using the least restrictive form for the shortest possible time.

mixed delirium: delirium in which the person moves between hyperactive and hypoactive patterns.

multicomponent prevention: a bundle of non-drug measures, such as orientation, sensory aids, sleep, hydration, nutrition and mobility, used together to prevent delirium.

orthostatic hypotension: A sustained fall in systolic blood pressure of at least 20 mm Hg, or in diastolic blood pressure of at least 10 mm Hg, within 3 minutes of standing.

person-centred care: care built on knowing the patient as a whole person, honouring their choices and sharing decisions with them and those close to them.

physiological reserve: the spare capacity that body systems draw on when illness, surgery or other stress adds strain.

polypharmacy: The use of many medications at the same time, most often defined as five or more medications daily.

post-fall assessment: A structured assessment after a fall to find injuries, including delayed ones, and the causes of the fall.

post-fall huddle: A short team meeting held soon after a fall to work out why it happened and change the plan to prevent another.

potentially inappropriate medication (PIM): A drug that, for most older adults, is ineffective, carries an unnecessarily high risk or has a safer alternative.

prescribing cascade: A sequence in which an adverse drug effect is mistaken for a new condition and treated with another drug.

responsive behaviours: actions, words and gestures through which a person living with dementia or another neurological, mental health or substance use condition reacts to something that matters to them in their surroundings, often communicating an unmet need.

restraint: Anything that restricts a person's movement or behaviour in a way the person cannot easily undo, whether physical, environmental or chemical.

STOPP/START: European criteria that flag drugs that may harm older adults (STOPP) and helpful drugs that may have been missed (START); version 3 was published in 2023.

targeted interventions: Fall prevention measures matched to a person's own risk factors, such as scheduled toileting, supervised mobility or medication review.

universal fall precautions: Basic safety measures used for every patient regardless of fall risk, such as a low, locked bed, a call bell within reach, good lighting and non-slip footwear.

Licensure Review & Clinical Judgment Questions (30)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Joseph Tremblay (Questions 1–4): Joseph Tremblay, 79, was admitted 3 days ago with community-acquired pneumonia. His daughter says he lives with his wife, manages his own medications and does the crossword daily. This morning he is lying still with his eyes closed, has eaten nothing since yesterday and answers questions slowly. The night nurse charted "slept well, settled." The RPN caring for him is assessing him at 0900.

1. [CORE] Which finding most strongly suggests that Mr. Tremblay may have hypoactive delirium rather than ordinary tiredness?

a. He is lying still with his eyes closed at 0900.

b. He drifts off mid-answer and cannot keep track of the question.

c. He is 79 years old and was admitted with community-acquired pneumonia.

d. His daughter says he does the crossword every day.

Answer: b — Inattention, losing track partway through a question, is the core feature of delirium and separates it from tiredness (section 8.2). Lying still with eyes closed (a) can occur with ordinary fatigue and is not specific. Age and pneumonia (c) are risk factors, not signs that delirium is present. The crossword history (d) describes his baseline; it helps judge change but is not itself a sign of delirium.

2. [CORE] The RPN completes the Confusion Assessment Method (CAM). Which combination of findings would make the screen positive?

a. Disorganized thinking and an altered level of consciousness, with no change from baseline

b. Inattention and disorganized thinking, with steady behaviour all week

c. An acute change from baseline and an altered level of consciousness, with good attention

d. An acute change from baseline, inattention and drowsiness

Answer: d — A positive CAM requires both core features, an acute change or fluctuating course and inattention, plus either disorganized thinking or an altered level of consciousness; drowsiness is an altered level of consciousness (section 8.2). Option a lacks both core features. Option b lacks acute change or fluctuation. Option c lacks inattention, which is required.

3. [CORE] The CAM is positive. Which action should the RPN take first?

a. Report the change to the RN and prescriber promptly using SBAR, including vital signs and oxygen saturation.

b. Let Mr. Tremblay sleep until lunch and reassess him then.

c. Ask the prescriber for a sedative so he rests better tonight.

d. Apply bed rails on both sides so he cannot get up alone.

Answer: a — New delirium is an urgent change in condition; the nurse reports it at once with the data the team needs to search for causes such as hypoxia or worsening infection, and in Ontario the RPN consults the RN as the patient's needs change (section 8.2). Letting him sleep (b) delays finding a treatable cause. Sedatives (c) are not a first choice for delirium in older adults and do not address the cause. Full bed rails (d) are a form of restraint that increases harm and do not address the cause (sections 8.2 and 8.6).

4. [CORE] Mr. Tremblay's wife asks how she can help. Which response by the RPN is best?

a. "It would be best for the family to stay away until he is less confused, so that he can rest quietly without visitors."

b. "Please correct him firmly every time he says something that is not true, so that he learns where he is."

c. "Bring his glasses and hearing aid, sit and talk with him about home, and tell us if he seems different."

d. "His confusion is part of getting older, so there is not much that family members can do to help him."

Answer: c — Families help prevent and ease delirium by supporting vision and hearing, orientation and familiar company, and by reporting changes because they know the person's usual self (section 8.2). Keeping family away (a) removes a calming, orienting presence. Arguing or correcting firmly (b) increases distress; gentle reorientation works better. Delirium is not a normal part of aging (d) and often improves when its causes are treated.

5. [CORE] A nurse is planning care to prevent delirium for an 84-year-old patient admitted with a urinary tract infection. Which actions belong in a multicomponent prevention plan? Select all that apply.

a. Make sure the patient's glasses and hearing aids are in use.

b. Keep the patient on bed rest until the infection has cleared.

c. Offer fluids often and keep a drink within reach.

d. Group overnight care to protect sleep.

e. Request a sleeping pill at bedtime as a routine.

f. Walk the patient to the bathroom several times a day.

Answer: a, c, d, f — Multicomponent prevention supports vision and hearing (a), hydration (c), sleep (d) and mobility (f), as shown in Table 8.2 (section 8.2). Bed rest (b) causes deconditioning and raises delirium risk. Routine sleeping pills (e) are not recommended; sedative-hypnotics are not a first choice for older adults, and non-drug sleep measures are used instead.

6. [CORE] The nurse reads that a patient has a Clinical Frailty Scale (CFS) score in the frail range. How should the nurse interpret this?

a. The patient should not receive active treatment for the current illness.

b. The score describes how unwell the patient is today because of the acute illness.

c. The patient has less reserve, so a minor stressor may cause a large change in health.

d. The score is a measure of the patient's age and will rise each year.

Answer: c — Frailty means reduced physiological reserve and greater vulnerability to stressors, which helps the team anticipate risk and plan goal-directed care (section 8.1). The CFS is never by itself a reason to withhold treatment (a). It rates the person's usual state before the current illness, not today's acute status (b). Frailty is related to age but is not the same as age (d).

7. [CORE] A patient living with dementia starts calling out and pulling at her gown each afternoon. What should the nurse do first?

a. Look for an unmet need, such as pain, a full bladder, hunger or a noisy room.

b. Ask the prescriber for an antipsychotic to use when she calls out.

c. Move her to a room at the far end of the hall where she disturbs fewer people.

d. Document that she has problem behaviours in the afternoon.

Answer: a — Responsive behaviours are often a way of communicating an unmet need, so the first step is to look for a trigger and meet the need with non-drug approaches (section 8.3). Antipsychotics (b) carry serious risks in older adults with dementia and are not first-line. Isolating her (c) does not address the cause and may increase distress. "Problem behaviours" (d) is stigmatizing language; the nurse describes the behaviour and its context.

8. [CORE] A 76-year-old man recovering from a heart attack has been withdrawn and eating little. He tells the nurse, "My family would be better off without me." What is the nurse's best response?

a. "You have a lot to live for. Let's think about your grandchildren."

b. "Many people feel low after a heart attack; it will pass when you go home."

c. "I will mention this to your doctor at the next rounds."

d. "Are you having thoughts of ending your life?"

Answer: d — When depression or suicide risk is suspected, the nurse asks directly and calmly about suicidal thoughts, then ensures safety and reports at once (section 8.3). Reassurance (a) dismisses his feelings and does not assess risk. Telling him it will pass (b) minimizes a possible risk; depression in later life carries a risk of suicide, especially among older men. Waiting for rounds (c) delays urgent assessment and safety measures.

9. [CORE] In an Ontario hospital, an RPN is caring for a patient whose 4AT screen this afternoon suggests possible delirium. The patient was alert and oriented this morning. Which action reflects safe practice?

a. Continue the current care plan and recheck at the end of the shift.

b. Report promptly to the RN and prescriber and consult the RN about the patient's changing needs.

c. Wait for the patient's family to visit and confirm whether the confusion is new before reporting it.

d. Give the as-needed sedative that is already ordered, then document the patient's response in the chart.

Answer: b — Every nurse who notices a change acts at once and escalates; under CNO's Scope of Practice standard the RPN considers authority, competence and context, and consults the RN as the patient's needs change (Chapter 1, section 1.3; section 8.2). Waiting until the end of the shift (a) or for family (c) delays finding a treatable cause. A sedative (d) is not a first choice for delirium in older adults and does not address the cause; employer policy and province or territory also shape the RPN's role.

Case: Mr. Walter Bergeron (Questions 10–15): Mr. Walter Bergeron, 84, was admitted to a medical unit 3 days ago with pneumonia. He has atrial fibrillation treated with apixaban, hypertension, benign prostatic hyperplasia with nocturia, and mild cognitive impairment, and he walks with a walker. At 2200 he was alert and oriented to person, place and time; his blood pressure lying down was 132/76 mm Hg. At 0315 the nurse finds him sitting on the floor halfway between his bed and the bathroom, without his walker. He is wearing hospital socks, there is urine on the floor, the bed is in the high position, and the call bell is clipped to the far side of the bed. He says, "I had to go, and I hit my head on the table." There is a 3 cm red, swollen area on his right forehead. He knows where he is but not the day or time. Heart rate 96 and irregular (unchanged from his baseline), blood pressure 118/70 mm Hg, respiratory rate 20, SpO2 93% on 2 L/min oxygen by nasal prongs (unchanged since the evening), temperature 37.6 °C, capillary blood glucose 6.8 mmol/L. His pupils are equal and react to light, and he moves all four limbs. His left wrist is swollen and painful.

10. [CORE] Which findings require immediate follow-up? Select all that apply.

a. The swollen area on his forehead after striking his head

b. Taking apixaban

c. Irregular heart rate of 96

d. Disorientation to day and time

e. The swollen, painful left wrist

f. Capillary blood glucose of 6.8 mmol/L

g. SpO2 93% on 2 L/min oxygen

Answer: a, b, d, e — A head strike with visible swelling (a) in a patient taking an anticoagulant (b) raises concern for bleeding inside the skull, and disorientation that was not present at 2200 (d) is a new change in mental status (section 8.4). A swollen, painful wrist (e) may be a fracture. The irregular heart rate (c) is unchanged from his baseline atrial fibrillation. A glucose of 6.8 mmol/L (f) does not explain the fall or the confusion. His SpO2 (g) is unchanged since the evening on the same oxygen, so it is not the most urgent finding, although the nurse keeps monitoring it.

11. [CORE] The nurse analyzes the cues. Why does Mr. Bergeron's apixaban increase the nurse's concern?

a. It explains why he needed to get up to the bathroom at night.

b. It raises the risk of bleeding inside the skull, which may show few early signs.

c. It makes his new disorientation an expected effect of the drug, so no further neurological assessment is needed.

d. It means his wrist must be splinted before any other assessment.

Answer: b — An anticoagulant increases the risk of bleeding inside the skull after a head strike, and the person may look well at first (section 8.4). His need to get up at night (a) comes from nocturia related to his prostate, not from the anticoagulant. New disorientation after a head strike (c) must be treated as a possible head injury, not dismissed as a drug effect. The wrist needs care (d), but the anticoagulant matters mainly because of bleeding risk, and splinting does not come before assessing for a head injury.

12. [CORE] Which hypothesis should the nurse treat as the priority?

a. A fracture of the left wrist

b. Urinary urgency from benign prostatic hyperplasia

c. Worsening delirium caused by his pneumonia

d. Bleeding inside the skull after the head strike

Answer: d — A possible intracranial bleed (d) is life-threatening, and his cues (head strike, anticoagulant, new disorientation) fit it, so it is the priority even before imaging (section 8.4). A wrist fracture (a) needs care but is not life-threatening. Urgency (b) explains why he got up but is not the most dangerous problem. Delirium from pneumonia (c) is possible, but assuming it could delay recognizing a bleed.

13. [CORE] Which action should the nurse take first?

a. Help him back to bed with another staff member so that he is warm, comfortable and safe.

b. Give his ordered as-needed analgesic for the wrist pain.

c. Stay with him, call for help, and assess him for injuries before he is moved.

d. Complete the incident report now, while the details of the fall are still fresh.

Answer: c — The nurse stays, calls for help and assesses before anyone moves the patient, so that injuries such as a fracture or spinal injury are not made worse (section 8.4, Clinical Safety box). Lifting him at once (a) could worsen an unrecognized injury. Pain relief (b) is appropriate later but does not come before assessment. The incident report (d) is completed after the patient is safe and assessed.

14. [CORE] After the initial assessment, which actions are appropriate? Select all that apply.

a. Notify the prescriber at once using SBAR, reporting the head strike, the apixaban and his new disorientation.

b. Start neurological observations as ordered or as policy directs.

c. Decide independently to skip his next apixaban dose.

d. Move him back to bed with a mechanical lift or enough trained staff.

e. Prepare him for a CT scan of the head if it is ordered.

f. Apply wrist restraints so he cannot get up again tonight.

g. Inform his substitute decision-maker of the fall as policy directs.

Answer: a, b, d, e, g — Urgent notification (a), neurological observations (b), a safe lift (d), preparation for ordered imaging (e) and informing the SDM (g) are all part of post-fall care for an anticoagulated patient with a head strike (section 8.4). Changing anticoagulant therapy (c) is a prescriber decision; the nurse reports and follows orders. Restraints (f) increase agitation and injury and are not fall prevention (sections 8.4 and 8.6).

15. [CORE] Mr. Bergeron's CT scan shows no bleeding, and a toileting schedule, a low bed and non-slip footwear are added to his plan. At 0600, which finding shows that his condition requires immediate escalation?

a. He has vomited twice and is harder to rouse than at 0400.

b. His splinted wrist pain is 3 out of 10.

c. He asks when breakfast will arrive.

d. He knows where he is but not the time, as at 0315.

Answer: a — New vomiting and a falling level of consciousness (a) are signs of a serious change, such as bleeding inside the skull, and the nurse escalates at once even though the earlier scan was normal (section 8.4; Chapter 6). Mild, controlled wrist pain (b) and asking for breakfast (c) are reassuring. Disorientation that is unchanged from 0315 (d) still needs monitoring, but it is not a new decline.

16. [CORE] An 80-year-old patient admitted with heart failure walks independently and has no history of falls. Which action is a universal fall precaution for this patient?

a. Placing a bed alarm before the patient goes to sleep

b. Requesting a physiotherapy assessment of the patient's gait and balance

c. Keeping the bed low and locked with the call bell within reach

d. Fitting the patient with hip protectors

Answer: c — Universal fall precautions, such as a low, locked bed and a call bell within reach, apply to every patient whatever the risk level (section 8.4). A bed alarm (a), a physiotherapy gait assessment (b) and hip protectors (d) are targeted interventions for people with identified risk factors.

17. [CORE] A 77-year-old reports dizziness when getting up. After lying down for 5 minutes, the patient's blood pressure is 138/80 mm Hg. Which standing reading meets the definition of orthostatic hypotension?

a. 116/76 mm Hg at 1 minute

b. 130/74 mm Hg at 1 minute

c. 128/78 mm Hg at 3 minutes

d. 134/72 mm Hg at 3 minutes

Answer: a — Orthostatic hypotension is a sustained fall of at least 20 mm Hg systolic or 10 mm Hg diastolic within 3 minutes of standing (section 8.4). A reading of 116/76 mm Hg (a) is a 22 mm Hg systolic fall. Option b is a fall of 8/6 mm Hg, option c a fall of 10/2 mm Hg, and option d a fall of 4/8 mm Hg; none meets the threshold.

18. [CORE] An 88-year-old woman admitted with cellulitis walked with a cane at home. On day 2 she says she would rather rest in bed until she feels better. Which plan best prevents functional decline?

a. Bed rest until the antibiotic course is finished, with a bedpan at night so that she can save her energy

b. A urinary catheter so that she does not need to get up at night

c. Keeping her in bed until a physiotherapist has assessed her and cleared her for any activity out of bed

d. Assessing her mobility today, then helping her walk at least three times a day and sit up for meals

Answer: d — Early mobility assessment, walking at least three times a day and sitting up for meals reflect the MOVE ON approach and help prevent hospital-associated decline (section 8.4). Bed rest and a bedpan (a) speed loss of strength. A catheter (b) adds infection risk and further limits movement. Waiting for physiotherapy before any activity (c) delays mobility that nurses can safely support.

19. [CORE] A nursing student asks about the AGS Beers Criteria and the STOPP/START criteria. Which response is accurate?

a. "They list drugs that are banned for anyone over 65."

b. "They help identify medications that may cause harm, but a listed drug may still be right for a particular person."

c. "They are meant mainly for people receiving hospice and end-of-life care."

d. "The nurse should hold any medication on the list until the prescriber has reviewed it and written a new order."

Answer: b — Both tools support clinical judgment during medication review, and a listed drug may still be appropriate for an individual (section 8.5). They do not ban drugs (a). The Beers Criteria exclude hospice and end-of-life care (c). The nurse does not hold medications independently because they appear on a list (d); the nurse reports concerns and advocates for review.

20. [CORE] An 82-year-old who has taken zopiclone every night for years says, "I've heard these pills cause falls. Should I just stop them tonight?" Which response by the nurse is best?

a. "Let's talk with your prescriber about a plan to reduce it slowly, because stopping suddenly can cause withdrawal effects."

b. "Yes, stopping tonight is safest because you are in hospital."

c. "Because you have taken it for so many years, your body has adjusted, and the fall risk no longer applies to you."

d. "You could switch to an over-the-counter sleep aid instead."

Answer: a — Deprescribing a BZRA is a slow, prescriber-led taper planned with the patient, and the nurse supports the patient in raising it (section 8.5). Stopping abruptly (b) can cause withdrawal effects. Long-term use does not remove the risk (c). Many over-the-counter sleep aids contain first-generation antihistamines with anticholinergic effects (d).

21. [CORE] A 79-year-old man received diphenhydramine at 2200 for sleep. At 0200 he is newly confused and restless, has not voided since 1800, and his lower abdomen is distended. Which action is most appropriate?

a. Give a second dose of diphenhydramine to help him settle.

b. Apply mitts so that he does not pull at his gown or his intravenous line.

c. Assess his bladder as policy directs and report the findings and the possible drug effect to the prescriber.

d. Document the behaviour, reorient him, and reassess him with the team at morning rounds.

Answer: c — New confusion with urinary retention after a first-generation antihistamine suggests anticholinergic effects; the nurse assesses the bladder and escalates (section 8.5). A second dose (a) would worsen the problem. Mitts (b) are a restraint and do not address the cause. Waiting until morning (d) delays treatment of retention and delirium.

22. [CORE] An 86-year-old woman is going home after a fall. In hospital, her zopiclone was stopped, her diuretic was changed, and a new medication was started. Which nursing action best supports safe medication use at home?

a. Giving her the hospital medication administration record to keep

b. Telling her to resume all the medications she took before admission

c. Asking her daughter to sort the pills into an organizer once they are home

d. Reviewing the reconciled list with her using teach-back and sharing it with her pharmacist

Answer: d — Teaching from the reconciled list, checking understanding with teach-back and sharing the list with the community pharmacist support a safe transition (section 8.5; Chapter 1, section 1.6). A hospital administration record (a) is not a discharge medication list. Resuming all pre-admission drugs (b) would restart the stopped zopiclone and the old diuretic. Leaving sorting to the daughter (c) without teaching invites errors.

23. [CORE] An RPN is caring for an 84-year-old woman living with dementia whose condition had been stable. Tonight she is newly restless and trying to climb out of bed. A colleague suggests wrist restraints "to keep her safe." What should the RPN do?

a. Apply wrist restraints as suggested and tell the RN about them at the end of the shift.

b. Look for causes such as pain or a full bladder, try alternatives, and consult the RN about her change in condition.

c. Ask the pharmacy to send a sedative to settle her.

d. Raise all four bed rails so that she cannot climb out of bed and fall during the night.

Answer: b — A change in condition calls for assessment of causes, least-restraint alternatives and consultation with the RN (section 8.6, Scope in Practice box). A restraint needs an order from an authorized practitioner under the Act and policy, and waiting until the end of the shift (a) delays consultation. A sedative used to control behaviour (c) is a chemical restraint and needs a prescriber's assessment. Raised bed rails that keep her in bed (d) act as a restraint and do not address the cause of her restlessness.

24. [CORE] An 81-year-old man with delirium from pneumonia was found incapable of a treatment decision 2 days ago, and his daughter, his SDM, gave consent. Today he is alert and oriented, and a new treatment is proposed. Which statement is correct?

a. His daughter must make all his treatment decisions until discharge, because she has already consented once.

b. Once a person is found incapable, that finding lasts for the whole admission.

c. His capacity should be reassessed for the new decision, because capacity can return as delirium clears.

d. Capacity needs to be assessed only for decisions about surgery.

Answer: c — Capacity is decision-specific and can change as delirium clears, so it is reassessed for each new decision (section 8.6; Chapter 1, section 1.5). The SDM decides only when the person is incapable for that decision (a). Incapacity is not fixed for a whole admission (b). Capacity applies to every treatment decision, not only surgery (d).

25. [CORE] A capable 78-year-old woman who lives in her own home with her son tells the nurse that he has been taking money from her bank account and that she is afraid to go home. Which action is most appropriate?

a. Make sure she is safe, document her words objectively, follow hospital policy, and offer information such as the Seniors Safety Line.

b. Report her son to the police right away without discussing it with her, because Ontario law requires all suspected abuse of older adults to be reported.

c. Tell her son what she said so that the family can resolve it together.

d. Reassure her that money matters are a private family issue.

Answer: a — The nurse ensures safety, documents objectively, follows policy (often involving social work) and supports a capable person's choices with information and resources (section 8.6). Ontario law sets no reporting duty for abuse of an older adult living in the community (b); mandatory reporting applies to residents of long-term care and retirement homes, and a person in immediate danger needs 9-1-1. Telling the son (c) could put her at greater risk and breach her privacy. Dismissing financial abuse (d) leaves her unprotected.

26. [CORE] Which action best begins safe discharge planning for an older adult admitted after a fall at home?

a. Contacting Ontario Health atHome the day before discharge, once the date is confirmed

b. Asking only the patient about supports at home, to protect privacy

c. Recommending long-term care placement for every older adult admitted after a fall at home

d. Learning at admission about the person's home, function and caregivers, and sharing the fall risk and plan

Answer: d — Discharge planning starts at admission and includes the person's function, home and caregivers, with fall risk and the plan shared at each transition (section 8.6). Waiting until the day before discharge (a) leaves too little time to arrange services. With the patient's consent, caregivers are usually part of planning (b). Long-term care (c) is not the default after a fall; most people can return home with the right supports.

27. [RN] An 89-year-old woman who weighs 45 kg and has low muscle mass has a serum creatinine within the laboratory's reference range. Which interpretation is most accurate?

a. Her kidney function is normal, so drugs cleared by the kidneys need no review.

b. Low muscle mass can keep creatinine low, so her kidney function may be worse than it appears.

c. Creatinine rises with age, so her normal result means her kidneys are working better than expected.

d. In older adults, creatinine mainly reflects liver function rather than kidney function.

Answer: b — Creatinine comes from muscle, so low muscle mass can keep it within the reference range even when filtration is reduced; prescribers use the eGFR and the clinical picture (section 8.5, Going Deeper box). A normal creatinine does not rule out reduced function (a). Creatinine production falls, not rises, with lower muscle mass (c). Creatinine is a marker of kidney, not liver, function (d).

28. [RN] An 83-year-old receives a highly fat-soluble sedative. Compared with a younger adult, which change is most likely?

a. A smaller volume of distribution and a shorter effect

b. Faster clearance because liver mass increases with age

c. Dilution of the drug in a higher proportion of body water

d. A larger volume of distribution, so sedation may last longer

Answer: d — Body fat increases with age, so fat-soluble drugs spread through a larger volume, which lengthens the half-life and prolongs effects such as sedation (section 8.5, Going Deeper box). The volume of distribution of a fat-soluble drug increases rather than decreases (a). Liver mass decreases, not increases, with age (b). Total body water falls with age (c).

29. [RN] A 76-year-old takes oxybutynin daily and was given diphenhydramine for sleep. Which statement about anticholinergic burden is accurate?

a. The anticholinergic effects of the drugs add up, raising the risk of confusion, retention and falls.

b. Only drugs with strong anticholinergic effects count; drugs with mild effects can be ignored.

c. In older adults, anticholinergic effects are limited to dry mouth.

d. A score on an anticholinergic burden scale can replace a clinical assessment of the patient.

Answer: a — Anticholinergic burden is the cumulative effect of all drugs with anticholinergic properties, and a higher burden is linked with delirium, falls and decline (section 8.5, Going Deeper box). Drugs with mild effects add to the total (b). Effects go well beyond dry mouth (c). Scales support but do not replace assessment, and there is no clear guidance on which scale to use (d).

30. [RN] An 85-year-old with a serum albumin of 25 g/L after weeks of poor intake starts a drug that is highly bound to albumin. Which understanding should guide the nurse's monitoring?

a. Low albumin binds more of the drug, so its effect will be weaker and shorter.

b. Albumin levels do not affect how drugs act.

c. More of the drug may be unbound and active, so effects may be stronger than expected.

d. The kidneys will clear the drug faster, so its effect will be shorter.

Answer: c — Only unbound drug is active, and low albumin can leave more of a highly bound drug unbound, so the nurse watches for stronger effects and reports them (section 8.5, Going Deeper box). Less albumin means less binding, not more (a). Albumin does affect the distribution of bound drugs (b). Low albumin does not speed kidney clearance (d).

References

American Geriatrics Society Beers Criteria Update Expert Panel. (2023). American Geriatrics Society 2023 updated AGS Beers Criteria® for potentially inappropriate medication use in older adults. *Journal of the American Geriatrics Society*, *71*(7), 2052–2081. https://doi.org/10.1111/jgs.18372

Behavioural Supports Ontario. (n.d.). *Who we serve*. https://www.behaviouralsupportsontario.ca/35/Who_We_Serve/

Bellelli, G., Morandi, A., Davis, D. H. J., Mazzola, P., Turco, R., Gentile, S., Ryan, T., Cash, H., Guerini, F., Torpilliesi, T., Del Santo, F., Trabucchi, M., Annoni, G., & MacLullich, A. M. J. (2014). Validation of the 4AT, a new instrument for rapid delirium screening: A study in 234 hospitalised older people. *Age and Ageing, 43*(4), 496–502. https://doi.org/10.1093/ageing/afu021

Bjerre, L. M., Farrell, B., Hogel, M., Graham, L., Lemay, G., McCarthy, L., Raman-Wilms, L., Rojas-Fernandez, C., Sinha, S., Thompson, W., Welch, V., & Wiens, A. (2018). Deprescribing antipsychotics for behavioural and psychological symptoms of dementia and insomnia: Evidence-based clinical practice guideline. *Canadian Family Physician*, *64*(1), 17–27. https://www.cfp.ca/content/64/1/17

Boustani, M., Campbell, N., Munger, S., Maidment, I., & Fox, C. (2008). Impact of anticholinergics on the aging brain: A review and practical application. *Aging Health*, *4*(3), 311–320. https://doi.org/10.2217/1745509X.4.3.311

Braithwaite, E., Todd, O. M., Atkin, A., Hulatt, R., Tadrous, R., Alldred, D. P., Pirmohamed, M., Walker, L., Lawton, R., & Clegg, A. (2023). Interventions for reducing anticholinergic medication burden in older adults—A systematic review and meta-analysis. *Age and Ageing*, *52*(9), Article afad176. https://doi.org/10.1093/ageing/afad176

Canada's Drug Agency. (2025). Alternate level of care in Canada: Evidence assessment report (Health Technology Review). *Canadian Journal of Health Technologies, 5*(6). https://canjhealthtechnol.ca/index.php/cjht/article/download/OP0557/OP0557

Canadian Coalition for Seniors' Mental Health. (2021). *Canadian guidelines on prevention, assessment and treatment of depression among older adults: 2021 guideline update*. https://ccsmh.ca/wp-content/uploads/2021/06/CCSMH_Depression_Guidelines_FINAL_EN.pdf

Canadian Geriatrics Society. (2025). *Geriatrics: Twelve tests and treatments to question* [Choosing Wisely Canada recommendations]. https://choosingwiselycanada.org/recommendation/geriatrics/

Canadian Institute for Health Information. (2022). *Changes in drug prescribing to seniors in Canada*. https://www.cihi.ca/en/changes-in-drug-prescribing-to-seniors-in-canada

Canadian Institute for Health Information. (2026a). *Hospital stays in Canada, 2024–2025*. https://www.cihi.ca/en/hospital-stays-in-canada-2024-2025

Canadian Institute for Health Information. (2026b). *Potentially inappropriate medication prescribed to seniors* [Indicator]. https://www.cihi.ca/en/indicators/potentially-inappropriate-medication-prescribed-to-seniors

Canadian Society of Nephrology. (2025). *Nephrology* [Choosing Wisely Canada recommendations]. https://choosingwiselycanada.org/recommendation/nephrology/

Clegg, A., Young, J., Iliffe, S., Olde Rikkert, M., & Rockwood, K. (2013). Frailty in elderly people. *The Lancet, 381*(9868), 752–762. https://doi.org/10.1016/S0140-6736(12)62167-9

College of Physicians and Surgeons of Ontario. (2023, June). Adopt least restraint principles. *Dialogue*. https://dialogue.cpso.on.ca/articles/adopt-least-restraint-principles

Community Legal Education Ontario. (2025). *When does elder abuse have to be reported?* https://www.cleo.on.ca/en/publications/elderab/when-does-elder-abuse-have-be-reported

Covinsky, K. E., Pierluissi, E., & Johnston, C. B. (2011). Hospitalization-associated disability: "She was probably able to ambulate, but I'm not sure." *JAMA, 306*(16), 1782–1793. https://doi.org/10.1001/jama.2011.1556

Dazzi, T., Gribble, R., Wessely, S., & Fear, N. T. (2014). Does asking about suicide and related behaviours induce suicidal ideation? What is the evidence? *Psychological Medicine, 44*(16), 3361–3363. https://doi.org/10.1017/S0033291714001299

Denic, A., Glassock, R. J., & Rule, A. D. (2016). Structural and functional changes with the aging kidney. *Advances in Chronic Kidney Disease, 23*(1), 19–28. https://doi.org/10.1053/j.ackd.2015.08.004

deprescribing.org. (n.d.). *Deprescribing guidelines and algorithms*. https://deprescribing.org/resources/deprescribing-guidelines-algorithms/

Elder Abuse Prevention Ontario. (n.d.). *Help and support for older adults facing abuse*. https://eapon.ca/wp-content/uploads/2021/09/EAPO_Helpandsupport_2022.pdf

Farrell, B., Black, C., Thompson, W., McCarthy, L., Rojas-Fernandez, C., Lochnan, H., Shamji, S., Upshur, R., Bouchard, M., & Welch, V. (2017). Deprescribing antihyperglycemic agents in older persons: Evidence-based clinical practice guideline. *Canadian Family Physician*, *63*(11), 832–843. https://www.cfp.ca/content/63/11/832

Fedorowski, A., Hamrefors, V., Sutton, R., van Dijk, J. G., Freeman, R., Lenders, J. W. M., & Wieling, W. (2017). Do we need to evaluate diastolic blood pressure in patients with suspected orthostatic hypotension? *Clinical Autonomic Research*, *27*(3), 167–173. https://doi.org/10.1007/s10286-017-0409-7

Fixing Long-Term Care Act, 2021, S.O. 2021, c. 39, Sched. 1. https://www.ontario.ca/laws/statute/21f39

Gage, L., & Hogan, D. B. (2014). *2014 CCSMH guideline update: The assessment and treatment of delirium*. Canadian Coalition for Seniors' Mental Health. https://ccsmh.ca/wp-content/uploads/2016/03/2014-ccsmh-Guideline-Update-Delirium.pdf

Geriatric Medicine Research, Dalhousie University. (n.d.). *Clinical Frailty Scale*. https://www.dal.ca/sites/gmr/our-tools/clinical-frailty-scale.html

Government of Ontario. (n.d.). *Ontario Health atHome* [Agency profile]. Public Appointments Secretariat. https://www.pas.gov.on.ca/Home/Agency/828

Hatch, S., Seitz, D. P., Bruneau, M.-A., Ewa, V., Feldman, S., Goldberg, Y., Goodarzi, Z., Herrmann, N., Hewitt Colborne, D., Henri-Bhargava, A., Ismail, Z., Kirkham, J., Kumar, S., Lanctôt, K. L., Thompson, W., Porter, J. A., & Watt, J. A. (2025). The Canadian Coalition for Seniors' Mental Health Canadian clinical practice guidelines for assessing and managing behavioural and psychological symptoms of dementia (BPSD). *Canadian Geriatrics Journal, 28*(1), 91–102. https://doi.org/10.5770/cgj.28.820

Health Canada. (2005, June 22). *Atypical antipsychotic drugs and dementia: Advisories, warnings and recalls for health professionals* [Archived advisory]. https://recalls-rappels.canada.ca/en/alert-recall/atypical-antipsychotic-drugs-and-dementia-advisories-warnings-and-recalls-health

Health in Aging Foundation. (2023). *The 2023 updated AGS Beers Criteria®*. American Geriatrics Society. https://healthinaging.org/medications-older-adults/medications-older-adults-should-avoid

Hshieh, T. T., Yue, J., Oh, E., Puelle, M., Dowal, S., Travison, T., & Inouye, S. K. (2015). Effectiveness of multicomponent nonpharmacological delirium interventions: A meta-analysis. *JAMA Internal Medicine, 175*(4), 512–520. https://doi.org/10.1001/jamainternmed.2014.7779

Hurria, A., & Lichtman, S. M. (2008). Clinical pharmacology of cancer therapies in older adults. *British Journal of Cancer*, *98*(3), 517–522. https://doi.org/10.1038/sj.bjc.6604201

Inouye, S. K., Bogardus, S. T., Jr., Charpentier, P. A., Leo-Summers, L., Acampora, D., Holford, T. R., & Cooney, L. M., Jr. (1999). A multicomponent intervention to prevent delirium in hospitalized older patients. *New England Journal of Medicine, 340*(9), 669–676. https://doi.org/10.1056/NEJM199903043400901

Inouye, S. K., van Dyck, C. H., Alessi, C. A., Balkin, S., Siegal, A. P., & Horwitz, R. I. (1990). Clarifying confusion: The Confusion Assessment Method. A new method for detection of delirium. *Annals of Internal Medicine, 113*(12), 941–948. https://doi.org/10.7326/0003-4819-113-12-941

Kenney, W. L., & Chiu, P. (2001). Influence of age on thirst and fluid intake. *Medicine and Science in Sports and Exercise, 33*(9), 1524–1532. https://doi.org/10.1097/00005768-200109000-00016

Liu, B., Moore, J. E., Almaawiy, U., Chan, W.-H., Khan, S., Ewusie, J., Hamid, J. S., & Straus, S. E. (2018). Outcomes of Mobilisation of Vulnerable Elders in Ontario (MOVE ON): A multisite interrupted time series evaluation of an implementation intervention to increase patient mobilisation. *Age and Ageing*, *47*(1), 112–119. https://doi.org/10.1093/ageing/afx128

Masnoon, N., Shakib, S., Kalisch-Ellett, L., & Caughey, G. E. (2017). What is polypharmacy? A systematic review of definitions. *BMC Geriatrics*, *17*, Article 230. https://doi.org/10.1186/s12877-017-0621-2

Montero-Odasso, M., van der Velde, N., Martin, F. C., Petrovic, M., Tan, M. P., Ryg, J., Aguilar-Navarro, S., Alexander, N. B., Becker, C., Blain, H., Bourke, R., Cameron, I. D., Camicioli, R., Clemson, L., Close, J., Delbaere, K., Duan, L., Duque, G., Dyer, S. M., … Zijlstra, G. A. R. (2022). World guidelines for falls prevention and management for older adults: A global initiative. *Age and Ageing*, *51*(9), Article afac205. https://doi.org/10.1093/ageing/afac205

National Institute for Health and Care Excellence. (2023). *Delirium: Prevention, diagnosis and management in hospital and long-term care* (Clinical guideline CG103). https://www.nice.org.uk/guidance/cg103

O'Mahony, D., Cherubini, A., Guiteras, A. R., Denkinger, M., Beuscart, J.-B., Onder, G., Gudmundsson, A., Cruz-Jentoft, A. J., Knol, W., Bahat, G., van der Velde, N., Petrovic, M., & Curtin, D. (2023). STOPP/START criteria for potentially inappropriate prescribing in older people: Version 3. *European Geriatric Medicine*, *14*(4), 625–632. https://doi.org/10.1007/s41999-023-00777-y

Patient Restraints Minimization Act, 2001, S.O. 2001, c. 16. https://www.ontario.ca/laws/statute/01p16

Pottie, K., Thompson, W., Davies, S., Grenier, J., Sadowski, C. A., Welch, V., Holbrook, A., Boyd, C., Swenson, R., Ma, A., & Farrell, B. (2018). Deprescribing benzodiazepine receptor agonists: Evidence-based clinical practice guideline. *Canadian Family Physician*, *64*(5), 339–351. https://www.cfp.ca/content/64/5/339

Public Health Agency of Canada. (2017). *Dementia in Canada, including Alzheimer's disease: Highlights from the Canadian Chronic Disease Surveillance System*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/dementia-highlights-canadian-chronic-disease-surveillance.html

Public Health Agency of Canada. (2023, November 30). *Government of Canada launches three-digit suicide crisis helpline* [News release]. https://www.canada.ca/en/public-health/news/2023/11/government-of-canada-launches-three-digit-suicide-crisis-helpline.html

Public Health Agency of Canada. (2024). *Surveillance report on falls among older adults in Canada*. https://www.canada.ca/en/public-health/services/publications/healthy-living/surveillance-report-falls-older-adults-canada.html

Public Health Agency of Canada. (2026). *A dementia strategy for Canada: Together we achieve – 2025 annual report*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/dementia-strategy-together-we-achieve-2025.html

Registered Nurses' Association of Ontario. (2012). *Promoting safety: Alternative approaches to the use of restraints* [Health education fact sheet]. https://rnao.ca/media/5749/download

Registered Nurses' Association of Ontario. (2016). *Delirium, dementia, and depression in older adults: Assessment and care* (2nd ed.). https://rnao.ca/bpg/guidelines/assessment-and-care-older-adults-delirium-dementia-and-depression

Registered Nurses' Association of Ontario. (2017). *Preventing falls and reducing injury from falls* (4th ed.). https://rnao.ca/bpg/guidelines/prevention-falls-and-fall-injuries

Retirement Homes Act, 2010, S.O. 2010, c. 11. https://www.ontario.ca/laws/statute/10r11

Rochon, P. A., & Gurwitz, J. H. (1997). Optimising drug treatment for elderly people: The prescribing cascade. *BMJ*, *315*(7115), 1096–1099. https://doi.org/10.1136/bmj.315.7115.1096

Rockwood, K., & Theou, O. (2020). Using the Clinical Frailty Scale in allocating scarce health care resources. *Canadian Geriatrics Journal, 23*(3), 254–259. https://doi.org/10.5770/cgj.23.463

Rockwood, K., Song, X., MacKnight, C., Bergman, H., Hogan, D. B., McDowell, I., & Mitnitski, A. (2005). A global clinical measure of fitness and frailty in elderly people. *CMAJ, 173*(5), 489–495. https://doi.org/10.1503/cmaj.050051

Royal College of Emergency Medicine, Association of Ambulance Chief Executives, British Geriatrics Society, Society of British Neurological Surgeons, & UK Hospital at Home Society. (2023). *Position statement on the 2023 NICE head injury guidelines regarding asymptomatic patients on anticoagulation or antiplatelet treatment*. https://rcem.ac.uk/wp-content/uploads/2024/03/Nice_Head_Injury_Position_Statement_October_2023.pdf

Statistics Canada. (2022). *A portrait of Canada's growing population aged 85 and older from the 2021 Census* (Census in Brief, Catalogue no. 98-200-X2021004). https://www12.statcan.gc.ca/census-recensement/2021/as-sa/98-200-x/2021004/98-200-x2021004-eng.cfm

Statistics Canada. (2025, September 24). Canada's population estimates: Age and gender, July 1, 2025. *The Daily*. https://www150.statcan.gc.ca/n1/daily-quotidien/250924/dq250924a-eng.htm

Tieges, Z., MacLullich, A. M. J., Anand, A., Brookes, C., Cassarino, M., O'Connor, M., Ryan, D., Saller, T., Arora, R. C., Chang, Y., Agarwal, K., Taffet, G., Quinn, T., Shenkin, S. D., & Galvin, R. (2021). Diagnostic accuracy of the 4AT for delirium detection in older adults: Systematic review and meta-analysis. *Age and Ageing, 50*(3), 733–743. https://doi.org/10.1093/ageing/afaa224

Wilson, J. E., Mart, M. F., Cunningham, C., Shehabi, Y., Girard, T. D., MacLullich, A. M. J., Slooter, A. J. C., & Ely, E. W. (2020). Delirium. *Nature Reviews Disease Primers, 6*(1), Article 90. https://doi.org/10.1038/s41572-020-00223-4

Witlox, J., Eurelings, L. S. M., de Jonghe, J. F. M., Kalisvaart, K. J., Eikelenboom, P., & van Gool, W. A. (2010). Delirium in elderly patients and the risk of postdischarge mortality, institutionalization, and dementia: A meta-analysis. *JAMA, 304*(4), 443–451. https://doi.org/10.1001/jama.2010.1013

World Health Organization. (2024, June 15). *Abuse of older people* [Fact sheet]. https://www.who.int/news-room/fact-sheets/detail/abuse-of-older-people

09 Cancer Care

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain how cancer develops and spreads, and the language of staging and grading.
2. Describe the burden of cancer in Canada and its risk factors, including inequities in access to care.
3. Explain Canadian screening programs and the nurse's role in prevention and early detection.
4. Describe surgery, radiation and systemic therapies, their common adverse effects and nursing care.
5. Recognize and escalate oncologic emergencies, including febrile neutropenia, tumour lysis syndrome, hypercalcemia, spinal cord compression, superior vena cava syndrome and extravasation.
6. Handle hazardous drugs and body fluids safely.
7. Support patients and families through diagnosis, treatment and survivorship using person-centred, culturally safe care.
8. Distinguish RN and RPN roles in cancer care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 4	Clinician; Scholar	Foundations of Practice
3, 7	Educator; Advocate	Foundations of Practice; Ethical Practice
5, 6, 8	Clinician; Leader; Professional	Foundations of Practice; Professional Practice

Introduction

Cancer touches almost every family in Canada. *Canadian Cancer Statistics 2025* estimates that about 2 in 5 people in Canada will develop cancer during their lifetime, and cancer is still the country's leading cause of death (Canadian Cancer Statistics Advisory Committee, 2025). Because cancer and its treatments can affect any body system, nurses meet people with cancer on every unit: a surgical patient recovering from a bowel resection, a medical patient admitted with pneumonia partway through chemotherapy, an older adult whose fall reveals a bone metastasis, or a person in the emergency department with a fever a week after treatment.

This chapter gives the nurse a foundation for that care. Section 9.1 explains how cancer develops, spreads and is diagnosed. Section 9.2 describes the burden of cancer in Canada, prevention, screening and inequities in care. Section 9.3 introduces the main treatments and their adverse effects. Sections 9.4 to 9.6 cover oncologic emergencies, the safe handling of hazardous drugs, and living with and beyond cancer. Related topics live elsewhere: hypercalcemia, electrolytes and vascular access devices (Chapter 3), infection prevention and sepsis (Chapter 4), pain (Chapter 5), palliative care (Chapter 10), and cancers of the lung (Chapter 13), blood (Chapter 20), colon and rectum (Chapter 25), and breast and reproductive organs (Chapter 29).

9.1 Cancer Biology

From Normal Cells to Cancer

Healthy tissues renew themselves under tight control. A cell divides only when it receives signals to do so, and it passes checkpoints in the cell cycle where damaged deoxyribonucleic acid (DNA) is detected and repaired. When the damage is too great to fix, the cell dies by **apoptosis**, an orderly, programmed cell death. Cancer arises when changes build up in the genes that govern these steps (National Cancer Institute [NCI], 2024).

Carcinogenesis is the multistep process by which a normal cell becomes a cancer cell. Two families of genes matter most. A **proto-oncogene** is a normal gene that promotes cell growth and division; when it is mutated or overactive it becomes an oncogene, which pushes the cell to divide without the usual signals. A **tumour suppressor gene** normally slows division, repairs DNA or triggers apoptosis; when both copies are lost or disabled, the cell loses its brakes. A single change is rarely enough; several usually accumulate over years (NCI, 2024), which helps explain why about 9 in 10 cancers in Canada are diagnosed in people over 50 (Canadian Cancer Society, 2025a).

Most of these changes are acquired during life, from random copying errors or from **carcinogens**, agents that damage DNA. Examples include chemicals in tobacco smoke, ultraviolet (UV) radiation from the sun and viruses such as human papillomavirus (HPV) (NCI, 2024).

A smaller share of cancers, up to about 10%, are linked to inherited genetic variants present in every cell from birth (NCI, 2024). The *BRCA1* and *BRCA2* genes, for example, make proteins that repair damaged DNA. A person who inherits a harmful variant in one copy still has a working second copy, but if that copy is lost in a breast or ovarian cell, the cell can no longer repair its DNA well, and cancer becomes far more likely (NCI, n.d.-a). **Lynch syndrome** is an inherited condition caused by a harmful variant in one of the DNA mismatch repair genes (or a deletion in the nearby *EPCAM* gene). It is passed on in an autosomal dominant pattern and raises the risk of colorectal, endometrial and several other cancers, although not everyone with a variant develops cancer (Idos & Valle, 2021). A family history of several relatives with related cancers, or cancer at a young age, is shared with the team so that genetic counselling can be considered.

Hallmarks of Cancer

Cancers differ by tissue and by person, yet they share a common set of acquired capabilities. Hanahan and Weinberg (2011) organized these into the "hallmarks of cancer" framework. In plain terms, cancer cells keep themselves growing without outside permission, ignore signals that would normally stop them, avoid self-destruction, keep dividing indefinitely, recruit a blood supply, and invade and spread. Genetic instability and chronic inflammation help cells gain these traits, and cancer cells also change how they use energy and learn to hide from the immune system (Hanahan & Weinberg, 2011). Hanahan (2022) proposed further dimensions, such as the ability of cancer cells to change identity and the role of microbes and aging cells around the tumour. The framework matters at the bedside because many newer treatments aim at one hallmark; immune checkpoint inhibitors, for example, undo the cancer's escape from the immune system (section 9.3).

Benign and Malignant Tumours; Metastasis

A **neoplasm**, or tumour, is an abnormal mass of tissue that grows beyond normal control. A **benign** tumour usually grows slowly, resembles its tissue of origin and stays where it started, often within a capsule, though it can still harm by pressing on nearby structures, as inside the skull. A **malignant** tumour (cancer) is made of cells that look and behave less like normal tissue, invade surrounding structures and can spread. Cancers are often named by the tissue they arise in: carcinomas from epithelial cells, sarcomas from connective tissue, and leukemias and lymphomas from blood-forming and lymphatic cells.

Metastasis is the spread of cancer from its primary site to a distant site, where it forms a new tumour. To metastasize, cells must break away, invade nearby tissue, enter lymph or blood vessels, survive in the circulation and then settle and grow in a new tissue (Hanahan & Weinberg, 2011). Cancer spreads by three main routes:

- **Lymphatic spread:** cells travel to regional lymph nodes first, such as the axillary nodes in breast cancer.
- **Blood-borne spread:** cells reach distant organs; the bones, liver, lungs and brain are common sites.
- **Seeding:** cells shed across a body cavity, such as the peritoneal cavity in ovarian cancer.

A metastatic tumour keeps the identity of the primary cancer. Breast cancer that has spread to bone is still breast cancer, and it is treated as breast cancer.

Grading, Staging and Diagnosis

Two terms describe a cancer for treatment planning. The **grade** describes how abnormal the cancer cells look under a microscope compared with normal cells, which reflects how well differentiated they are (Figure 9.1). Low-grade cancers look more like normal tissue and tend to grow slowly; high-grade cancers tend to grow faster. The **stage** describes how far the cancer extends in the body.

Most solid tumours are staged with the **TNM (tumour, node, metastasis)** system of the Union for International Cancer Control (UICC), now in its ninth edition (2025), and the matching system of the American Joint Committee on Cancer: T describes the size and local extent of the primary tumour, N whether regional lymph nodes are involved, and M whether there is distant metastasis (UICC, n.d.). The TNM findings are combined into stage groups, usually from 0 to IV. Stage strongly predicts outcome. Among people in Canada (outside Quebec) diagnosed from 2010 to 2017, five-year net survival for female breast cancer was 100% at stage I and 23% at stage IV (Statistics Canada, 2023).



Figure 9.1 Cancer cells under the microscope (squamous cell carcinoma of the skin). In this poorly differentiated, high-grade example, the cells look very different from normal skin cells and grow into the surrounding tissue. (credit: "Micrograph of clear-cell squamous-cell carcinoma" by Valerie R. Yanofsky, Stephen E. Mercer and Robert G. Phelps/Wikimedia Commons, CC BY 4.0)

A **biopsy**, the removal of tissue for examination by a pathologist, confirms the diagnosis and gives the cancer type, grade and often biomarkers that guide treatment (NCI, n.d.-h). Imaging, such as computed tomography (CT), magnetic resonance imaging (MRI) and positron emission tomography (PET), shows the extent of disease. A **tumour marker** is a substance made by cancer cells, or by the body in response to cancer, that can be measured in blood, urine or tissue. Examples are prostate-specific antigen (PSA), carcinoembryonic antigen (CEA) in colorectal cancer and cancer antigen 125 (CA-125) in ovarian cancer. Tumour markers are most useful for following response to treatment and watching for recurrence. They have clear limits: benign conditions can raise them, not everyone with a cancer has a raised level, and most blood markers perform poorly for screening (NCI, n.d.-h).

Waiting for a confirmed diagnosis is often the hardest time for patients and families. The nurse explains what each test is for and when results are expected, names a contact person, asks how the person is coping and reports distress to the team.

9.2 Cancer in Canada: Risk, Prevention and Screening

The Burden of Cancer

Canadian Cancer Statistics 2025 estimates that 254,800 people in Canada would be diagnosed with cancer in 2025 and that 87,400 would die from it (Canadian Cancer Statistics Advisory Committee, 2025). Over a lifetime, about 2 in 5 people in Canada are expected to be diagnosed with cancer and about 1 in 4 to die of it, and males and females have an equal chance of a diagnosis. Cancer is still Canada's leading cause of death, and it is far ahead of any other cause of premature death. Lung, breast, prostate and colorectal cancers together were expected to make up almost half of the cancers diagnosed in 2025 (Canadian Cancer Statistics Advisory Committee, 2025). There is good news too. Five-year net survival, with all cancers combined, has risen from 55% in the early 1990s to an estimated 64%, and death rates have fallen for most cancer types (Canadian Cancer Society, 2025a; Canadian Cancer Statistics Advisory Committee, 2025).

CANADIAN CONTEXT

Cancer Statistics and Inequities

Canadian Cancer Statistics is produced by the Canadian Cancer Statistics Advisory Committee in partnership with the Public Health Agency of Canada, Statistics Canada and the Canadian Cancer Society. The data come from provincial and territorial cancer registries, which feed the Canadian Cancer Registry. A full report appears every second year; in between, a special report and projections for the current year are released. The 2026 projections were published as a peer-reviewed article in the *CMAJ* (Brenner et al., 2026).

National averages can hide large gaps. In a study of Registered First Nations people in Ontario from 1991 to 2010, all-cancer death rates were higher than among other people in Ontario (rate ratio 1.08 for males and 1.23 for females), and cervical cancer

> death rates among First Nations women aged 30 and older were nearly three times higher (Jamal et al., 2021). The study was carried out in close collaboration with the Chiefs of Ontario under the First Nations principles of OCAP® (Jamal et al., 2021). These gaps reflect colonial policies, distance from services and unequal access to screening and care, not biology. Progress is also uneven: after a long decline from 1984 to 2005, cervical cancer incidence has stopped falling, even as Canada works toward eliminating cervical cancer by 2040 (Canadian Cancer Society, 2025a).

Risk Factors and Prevention

Age is the strongest risk factor that cannot be changed, followed by inherited variants (section 9.1). Many other risk factors can be changed. The Canadian Population Attributable Risk of Cancer (ComPARe) study estimated that between 33% and 37% of cancers diagnosed in 2015 among adults aged 30 and older, up to about 70,000 cases, were attributable to modifiable risk factors (Poirier et al., 2019). The Canadian Cancer Society (n.d.) summarizes this as about 4 in 10 cancer cases that could be prevented through healthy living and protective policies.

- **Tobacco:** the leading preventable cause; tobacco is responsible for about 18% of the cancers diagnosed in Canada (Canadian Cancer Society, n.d.).
- **Physical inactivity and excess body weight:** next in line after tobacco among the factors ComPARe studied (Canadian Cancer Society, n.d.).
- **Alcohol:** a cause of at least seven kinds of cancer, including breast and colorectal cancer, and of nearly 7,000 cancer deaths in Canada each year; the 2023 *Canada's Guidance on Alcohol and Health* advises not drinking alcohol to reduce cancer risk and, for people who choose to drink, keeping to a low weekly limit (Canadian Partnership Against Cancer [CPAC], 2023).
- **UV radiation:** sun exposure is among the leading preventable causes (Canadian Cancer Society, n.d.), and melanoma incidence in females has risen about 2.1% a year since 1994 (Canadian Cancer Society, 2025a).
- **Radon:** a natural radioactive gas that can collect in homes. Health Canada (2026) calls radon the leading cause of lung cancer in people who do not smoke and estimates that it causes about 16% of lung cancers and more than 3,000 deaths from lung cancer in Canada every year. The Canadian guideline for indoor radon is 200 becquerels per cubic metre (Bq/m^3), and Health Canada recommends a long-term test of 3 months, ideally in fall or winter. Smoking adds to the danger: the lung cancer risk from radon is even higher in people who smoke.
- **Infections:** seven infections caused about 3.7% of cancers diagnosed among adults in Canada in 2015; HPV and *Helicobacter pylori* accounted for the most cases, followed by Epstein-Barr virus and hepatitis B and C (Volesky et al., 2019).

Many infection-related cancers can be prevented. Vaccination prevents HPV and hepatitis B infection, *H. pylori* can be treated with antibiotics, and hepatitis C can be treated (Volesky et al., 2019). High-risk HPV types that persist in the body can lead to cancers of the cervix, oropharynx, anus, penis, vagina and vulva. The National Advisory Committee on Immunization (NACI) strongly recommends HPV vaccination for everyone aged 9 to 26 and states that people aged 27 and older may be vaccinated after shared decision-making; the schedule depends on age and immune status (Public Health Agency of Canada [PHAC], 2024).

Every nursing contact is a chance for prevention. The nurse asks about tobacco use and offers cessation support, checks immunization status, and gives brief, non-judgmental information about alcohol, activity, sun protection and radon testing.

Screening

Screening means testing people who have no symptoms in order to find cancer, or changes that may become cancer, at an earlier and more treatable stage. Screening also has harms: false-positive results, anxiety, further tests and procedures, and **overdiagnosis**, the detection of cancers that would never have caused symptoms or death. Overdiagnosis leads to treatment that cannot help the person. For this reason, recommendations weigh benefits against harms, and many call for shared decision-making. Screening is for people without symptoms. A person with a breast lump, rectal bleeding or a persistent cough needs prompt diagnostic testing, not a screening test.

Two kinds of guidance apply in Canada. The Canadian Task Force on Preventive Health Care published national recommendations for primary care until it ended its mandate on March 31, 2026 (Canadian Task Force on Preventive Health Care, 2026). On June 10, 2026, the Public Health Agency of Canada announced a new National Advisory Committee on Preventive Health Services, which replaces the Task Force and will lead work on new preventive health guidelines, including for cancer screening (PHAC, 2026). The

Task Force's final guidelines remain its most recent published recommendations. For breast screening, that is the 2018 guideline (Klarenbach et al., 2018); the 2024 draft update was never finalized and has been archived (Canadian Task Force on Preventive Health Care, 2024). Provinces and territories run their own organized screening programs, and their rules often differ from the Task Force's. Ontario's programs serve as the worked example (Table 9.1).

In Ontario, several program changes are recent. Since October 8, 2024, people aged 40 to 49 can refer themselves to the Ontario Breast Screening Program, which offers publicly funded screening to people aged 40 to 74 who are women, Two-Spirit, trans or nonbinary (Ontario Health, 2024). On March 3, 2025, the Ontario Cervical Screening Program began using HPV testing in place of the Pap test, which allows most people to be screened every 5 years (Ontario Health, 2025; Ontario Ministry of Health, 2025). The Ontario Lung Screening Program uses low-dose CT for people with a long smoking history; five sites were added in March 2026, for a total of 15 (Ontario Health, 2026a). Program rules change often, so the nurse checks the current rules in the patient's own province or territory (Figures 9.2 and 9.3).



Figure 9.2 A mammogram, the breast screening test, labelled to show normal fibroglandular tissue, a calcification and a mass. (credit: "Low intensity mass on mammography MLO view" by Cerevisae/Wikimedia Commons, CC BY-SA 4.0)

Figure 9.3 A home stool test kit for bowel cancer screening (Australia's national program, 2022). Provincial programs mail similar kits for a fecal immunochemical test; contents and instructions vary by program. (credit: "Bowel cancer Home Test Kit Instructions and test tubes in Australia, 2022" by Kgbo/Wikimedia Commons, CC BY-SA 4.0)

Table 9.1 Cancer screening in Canada at a glance (Bacchus et al., 2016; Canadian Task Force on Preventive Health Care, 2013, 2016; Klarenbach et al., 2018; Ontario Health, 2024, 2025, 2026; Ontario Health [Cancer Care Ontario], n.d.-a; Ontario Ministry of Health, 2025); check your province or territory

Cancer	Test	Who and how often (Canadian Task Force)	Ontario program (as of 2026)	Nursing role
Breast	Mammography	2018 guideline: ages 50 to 74, every 2 to 3 years; ages 40 to 49, not routinely, with the choice left to the person after discussing benefits and harms. A 2024 draft update was never finalized.	Ontario Breast Screening Program: ages 40 to 74, every 2 years; self-referral from age 40 since October 8, 2024; High Risk program for ages 30 to 69 with yearly mammogram and MRI	Explain benefits and harms; support decisions at ages 40 to 49; help people book; ask about family history that may mean higher risk
Cervical	HPV test (cells collected from the cervix by a clinician)	2013 guideline: ages 25 to 69, every 3 years; written before HPV-based screening	Ontario Cervical Screening Program: HPV testing since March 3, 2025; from age 25 for anyone with a cervix who has ever had sexual contact; most people every 5 years; most can end screening at 65 to 69 after a negative result	Include trans men and nonbinary people with a cervix; explain that HPV-vaccinated people still need screening; offer a trauma-informed approach
Colorectal	Fecal immunochemical test (FIT); colonoscopy for higher risk	2016 guideline: ages 50 to 74, a stool test (FIT or guaiac) every 2 years or a flexible sigmoidoscopy once every 10 years; colonoscopy not used as the first screening test	ColonCancerCheck: FIT every 2 years, ages 50 to 74, average risk; colonoscopy for people with a parent, sibling or child with colorectal cancer, beginning at age 50, or 10 years earlier than the age at which the relative was diagnosed, whichever comes first	Teach FIT collection; stress follow-up colonoscopy after an abnormal FIT; send people with symptoms for diagnosis, not screening
Lung	Low-dose CT	2016 guideline: ages 55 to 74 with at least 30 pack-years who currently smoke or stopped within the past 15 years, yearly for up to 3 years, only where expert care is available; no chest X-ray screening	Ontario Lung Screening Program: ages 55 to 80 who have smoked daily for at least 20 years (not necessarily in a row); eligibility set by a risk assessment (2% or higher over 6 years); clinician or self-referral; 15 sites	Take a smoking history; refer for cessation support; explain that the scan is part of a program with follow-up

Equity in Cancer Care

Cancer outcomes in Canada are shaped by where people live, their income, their language and how they are treated by the health system (Chapter 2). First Nations, Inuit and Métis have each described their own priorities for cancer care. The *Canadian Strategy for Cancer Control 2019–2029* includes three priorities identified by First Nations, Inuit and Métis: culturally appropriate care closer to home, peoples-specific and self-determined cancer care, and research and data systems governed by First Nations, Inuit or Métis (CPAC, 2019). Actions differ by people: for Inuit, for example, they include care closer to home and better medical travel policies. Gaps in outcomes reflect structural causes, including colonial policies, underfunded community services and racism in health care, not individual choices or biology. When First Nations data are used, the First Nations principles of OCAP® (ownership, control, access and possession) guide how they are collected and shared. The nurse builds on community strengths, such as Indigenous navigators where available and traditional healing practices the patient chooses, and practises cultural safety (Chapter 2).

Other groups face barriers too:

- **Rural, remote and northern residents:** radiation and specialized treatment are offered in a limited number of centres, so people may travel long distances or stay away from home for weeks. The *Canadian Strategy* calls for rural and remote communities to have the resources to serve their people (CPAC, 2019). The nurse asks about travel, lodging, cost and who will support the person.
- **Newcomers and people who speak neither English nor French:** they may not know that screening exists or is free. The nurse uses professional interpreters, not family members, and offers translated material.

- **2SLGBTQI+ people:** Ontario's screening programs explicitly include Two-Spirit, trans and nonbinary people (Ontario Health, 2024, 2025). The nurse asks which organs a person has rather than assuming from gender, uses the person's name and pronouns, and recognizes that past mistreatment may make an exam frightening.
- **People with disabilities:** mammography and cervical screening may need accessible equipment, positioning help, extra time or communication supports. The nurse plans these ahead so the person is not turned away.

9.3 Cancer Treatments

Surgery

Surgery remains a core cancer treatment, and it serves several purposes:

- **Diagnostic and staging:** a biopsy, or removal of lymph nodes to see whether cancer has spread.
- **Curative:** removal of the whole tumour with a margin of normal tissue.
- **Debulking:** removal of as much tumour as is safely possible when it cannot all be removed, so that other treatments work better.
- **Reconstructive:** restoring form or function, as in breast reconstruction.
- **Palliative:** relieving symptoms such as bowel obstruction, bleeding or pain when cure is not possible.
- **Risk-reducing:** removing an organ at very high risk, as some people with a harmful *BRCA* variant choose to do.

Surgery is often combined with other treatments. **Neoadjuvant** therapy is given before surgery to shrink a tumour; **adjuvant** therapy is given after surgery to destroy cancer cells that may remain. Perioperative nursing care is covered in Chapter 7.

Figure 9.4 A radiation therapist marks a custom mesh mask fitted to a patient model. For radiation to the head or neck, the mask holds the head in the same position for each treatment.

Radiation Therapy

Radiation therapy uses high-energy radiation to damage the DNA of cancer cells. Cells whose DNA damage cannot be repaired stop dividing or die. The effect is not immediate: damage builds over days to weeks of treatment, and cancer cells keep dying for weeks or months after treatment ends (NCI, n.d.-f). Treatment is usually given in many small daily sessions over several weeks.

External beam radiation is delivered by a machine, usually a linear accelerator, that aims radiation at the tumour from outside the body. The patient lies still for a few minutes and feels nothing. Because no radioactive source is placed in the body, a person treated with external beam radiation is not radioactive afterward and can safely be close to other people (NCI, n.d.-d). **Brachytherapy** places a sealed radioactive source, such as seeds, ribbons or capsules, inside or next to the tumour. While a source is in place, the patient gives off radiation. Some radiation is given as an unsealed liquid, by mouth or intravenously, and for a time the patient's body fluids are radioactive (NCI, n.d.-f). For sealed and unsealed sources, the nurse follows the hospital's radiation safety policy and the radiation safety officer's instructions, which apply the principles of limiting time near the source, keeping distance and using shielding (Figure 9.4).

Radiation affects normal tissue in the treatment area, so most effects are local:

- **Fatigue:** common, builds as treatment goes on and may take weeks or months to resolve (NCI, n.d.-f).
- **Skin reactions:** redness, dryness, itching and peeling in the treated area usually appear 1 to 4 weeks after treatment starts and are often worst 2 to 3 weeks after the last treatment (Alberta Health Services, 2026).
- **Site-specific effects:** mouth sores and dry mouth with head and neck treatment, painful swallowing with chest treatment, and diarrhea or bladder irritation with pelvic treatment.

Late effects can appear months or years later and depend on the area treated, so survivorship care plans include follow-up for them (section 9.6).

PATIENT EDUCATION

Preparing for Radiation Therapy

- **What to expect:** a planning visit comes first, then short daily treatments, usually on weekdays. The machine does not touch you, and after external beam treatment you are not radioactive.
- **Skin care in the treated area:** follow your treatment team's instructions. Wash daily with lukewarm water and a mild cleanser, and pat dry with a soft towel. Use the moisturizer your team suggests; unscented, water-based products are usual.
- **Avoid heat and friction:** skip hot tubs, saunas and steam rooms. Wear loose clothing made of soft, natural fabric.
- **Sun protection:** keep the treated skin out of the sun; cover it, and use sunscreen with a sun protection factor (SPF) of 30 or higher when your team says it is safe to apply.
- **Shaving and deodorant:** use an electric razor and avoid waxing. Ask before using deodorant on the treated area.
- **Fatigue:** plan rest, keep up light activity and accept help.
- **When to call:** open, weeping or very painful skin; fever, foul odour, pus or redness spreading beyond the treated area. Skin reactions may peak 2 to 3 weeks after treatment ends, so keep caring for the area.

(Alberta Health Services, 2026; NCI, n.d.-f, n.d.-h)

Chemotherapy

Chemotherapy uses cytotoxic drugs that kill cancer cells or slow their growth, along with other rapidly dividing cells (NCI, n.d.-c). Some drugs act mainly at one phase of the cell cycle; others damage cells at any phase. Drugs are often combined, and they are usually given in **cycles**: a period of treatment followed by a rest period that lets healthy cells recover (NCI, n.d.-c).

Because chemotherapy cannot fully tell cancer cells from healthy cells that divide quickly, its common adverse effects arise in those tissues. Damage to the bone marrow causes **myelosuppression**, a fall in white blood cells, red blood cells and platelets. Each count drops to its lowest point, the **nadir**, at a time after treatment that varies with the drug, and then recovers. A low neutrophil count leaves the person open to serious infection; fever may be the only sign, and febrile neutropenia is an emergency (section 9.4 and Chapter 4). Damage to the lining of the mouth and gut causes **mucositis**, nausea and diarrhea, and damage to hair follicles causes **alopecia** (hair loss) (NCI, n.d.-c). Fatigue is the most common effect of all (NCI, n.d.-c).

Chemotherapy can be given by mouth, intravenously, by injection into muscle or under the skin, into the spinal fluid (intrathecal), into the abdomen (intraperitoneal), into an artery or onto the skin (NCI, n.d.-c). Some intravenous drugs are **vesicants**, which can blister and destroy tissue if they leak out of the vein, and others are irritants; extravasation is covered in section 9.4 and safe handling in section 9.5. Drug classes include alkylating agents, antimetabolites, anthracyclines, taxanes and platinum agents. Regimens and doses are set by the oncology team and are beyond the scope of this text.

The common adverse effects of systemic therapy, and the related nursing care, are summarized below (Table 9.2).

Table 9.2 Common adverse effects of systemic therapy and nursing care (Cancer Care Ontario, 2012, 2018; Herrstedt, Clark-Snow, et al., 2024; Loprinzi et al., 2020; NCI, n.d.-c, n.d.-e; Ontario Health [Cancer Care Ontario], n.d.-b; Schneider et al., 2021)

Effect	Why it happens	What the nurse assesses	Nursing care and teaching

Effect	Why it happens	What the nurse assesses	Nursing care and teaching
Myelosuppression: neutropenia	Treatment damages rapidly dividing bone marrow cells	Temperature, signs of infection (which may be subtle), neutrophil count, timing since last treatment	Teach hand hygiene and infection avoidance; teach the person to check their temperature when unwell and to call the cancer centre or go to emergency at once for a fever at the level in their written instructions; report fever immediately (section 9.4)
Myelosuppression: anemia	Fewer red blood cells are produced	Fatigue, shortness of breath, dizziness, pallor (check conjunctivae and nail beds on darker skin), hemoglobin	Pace activity, prevent falls, report breathlessness or chest pain; transfusion as prescribed (Chapter 20)
Myelosuppression: thrombocytopenia	Fewer platelets are produced	Bruising, petechiae (easier to see in the mouth and conjunctivae on darker skin), bleeding gums, blood in urine or stool, platelet count	Use a soft toothbrush and an electric razor; avoid injury; report bleeding promptly
Nausea and vomiting	Treatment acts on the gut and on the brain's vomiting pathways; risk depends on the drugs	Nausea, vomiting, intake, hydration, weight, anticipatory nausea	Give preventive antiemetics on schedule as prescribed, chosen by the treatment's emetic risk; small frequent meals; report vomiting that prevents keeping fluids or medicines down
Mucositis	Treatment damages the fast-renewing lining of the mouth and gut	Mouth at each visit (redness, ulcers, white patches), pain, ability to eat and swallow	Brush gently with a soft brush after meals and at bedtime; rinse often with a bland salt and baking soda rinse; avoid alcohol-based mouthwash, tobacco, alcohol and spicy, acidic or hard foods; manage pain
Diarrhea or constipation	Gut lining damage; some targeted and immune therapies; antiemetics, opioids and inactivity cause constipation	Stool frequency and form, hydration, abdominal pain, blood in stool	Fluids; follow the team's bowel plan; report diarrhea that is new or severe, especially with immunotherapy
Fatigue	Effects of cancer and treatment, anemia, poor sleep, low mood	Severity, impact on daily life, possible treatable causes	Balance rest with regular light activity; plan priorities; screen for anemia, depression and poor sleep
Alopecia	Treatment damages hair follicles	Feelings about hair loss and body image	Prepare the person ahead; offer head coverings and resources; protect the scalp from sun and cold; hair usually regrows after treatment
Peripheral neuropathy	Some drugs, such as taxanes and platinum agents, damage peripheral nerves	Numbness, tingling or pain in hands and feet; balance; fine motor skills	Report early so the team can consider changing treatment; teach fall prevention and foot inspection; test water temperature by another means
Skin and nail changes	Targeted therapies and some chemotherapy affect skin and nail cells	Rash, dryness, itching, nail and cuticle changes, signs of infection	Gentle cleansing, moisturizers, sun protection; report spreading or painful rash
Immune-related adverse events	Immune checkpoint inhibitors let the immune system attack healthy organs	New diarrhea or abdominal pain, cough or breathlessness, yellowing of skin or eyes, rash, severe fatigue, headache, dizziness	Teach the person to report any new symptom early, even months after treatment ends; report the same day; treatment may be held and corticosteroids started

Targeted Therapy, Immunotherapy and Hormone Therapy

Targeted therapy acts on specific proteins that drive the growth and spread of cancer cells. Most people need biomarker testing of the tumour to show that it carries the target (NCI, n.d.-g). Small-molecule drugs, such as kinase inhibitors, enter cells and are usually taken by mouth. Monoclonal antibodies are laboratory-made proteins that attach to targets on cancer cells and are usually given

intravenously. Common adverse effects include diarrhea, liver problems, rash and dry skin, nail changes, high blood pressure and problems with clotting and wound healing (NCI, n.d.-g). Oral anticancer drugs are handled at home as hazardous drugs, and the nurse checks how the person stores them, takes them and disposes of them (section 9.5).

Immunotherapy helps the immune system fight cancer. **Immune checkpoint inhibitors** block the signals that cancer cells use to switch off T cells. Because they take the brakes off the immune system, they can cause an **immune-related adverse event**, an inflammatory reaction in a healthy organ. Common examples are colitis (diarrhea), pneumonitis (cough, breathlessness), hepatitis, endocrine disorders affecting the thyroid, pituitary or adrenal glands, and rash (Schneider et al., 2021). These reactions can begin at any time, can progress quickly and may appear months after treatment stops (Cancer Care Ontario, 2018). Depending on severity, the team may hold the drug and start corticosteroids (Schneider et al., 2021). The nurse teaches the person to report any new symptom early and to tell every health care provider, including in the emergency department, that they have received immunotherapy.

Hormone therapy slows or stops the growth of cancers that depend on hormones, mainly breast and prostate cancers. Some drugs block the body's production of a hormone; others block its action (NCI, n.d.-e). Examples are tamoxifen and aromatase inhibitors for breast cancer and androgen deprivation therapy for prostate cancer. Adverse effects include hot flashes, sexual changes, mood changes, fatigue and, with some drugs, weakened bones (NCI, n.d.-e).

Chimeric antigen receptor (CAR) T-cell therapy collects the patient's own T cells, engineers them in a laboratory to recognize cancer cells and infuses them back; it is used for certain blood cancers. Its serious effects include **cytokine release syndrome**, a surge of inflammatory signals causing high fever and a sharp drop in blood pressure that can be fatal, and neurologic toxicity with confusion or trouble speaking (NCI, n.d.-b). Hematopoietic stem cell transplant is described in Chapter 20. Both are delivered in specialized centres.

LIFESPAN CONSIDERATIONS

Older Adults With Cancer

Most cancers in Canada are diagnosed in older adults, yet age alone says little about how a person will tolerate treatment. The American Society of Clinical Oncology recommends a **geriatric assessment** for people aged 65 and older receiving chemotherapy, because it finds problems that routine oncology assessment misses (Mohile et al., 2018). At a minimum it covers function, other illnesses, falls, depression, cognition and nutrition. Tools such as the Cancer and Aging Research Group (CARG) and Chemotherapy Risk Assessment Scale for High-Age Patients (CRASH) scores estimate the risk of severe chemotherapy toxicity. The results should shape a plan that addresses both the cancer and other health problems, and they are shared with the person and their caregivers (Mohile et al., 2018).

- **Frailty:** frail older adults may need adjusted treatment and early supportive care (Chapter 8).
- **Polypharmacy:** the nurse reviews all medicines, including non-prescription and natural products, for interactions with oral anticancer drugs.
- **Cognition:** the nurse uses teach-back, gives written instructions and involves a support person with the patient's consent.
- **Caregivers:** older spouses who are caregivers may have health needs of their own; the nurse asks about them.



Figure 9.5 A single-lumen peripherally inserted central catheter (PICC) before insertion. (credit: “Peripherally inserted central catheter (PICC) with one lumen” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)



Figure 9.6 An implanted port under the skin of the upper chest, shown on a training manikin. (credit: "Chest with ICVC inserted" by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Vascular Access for Treatment

Repeated intravenous treatment, blood sampling and the use of vesicants often call for a central venous access device. An **implanted port** is a small reservoir placed under the skin of the chest or arm, joined to a catheter that ends in a large central vein; it is reached through the skin with a special non-coring needle. A **peripherally inserted central catheter (PICC)** is inserted in an arm vein and threaded to a central vein (Figures 9.5 and 9.6). The care of these devices is taught in Chapter 3.

Before each use, the nurse assesses the site for redness, swelling, tenderness or drainage, looks for swelling of the arm, neck or face that could signal a clot, and confirms that the device flushes easily and gives a blood return. Fever in a person with a central line may mean a line infection and is reported at once. Accessing an implanted port and giving cancer drugs through any device require specific education and employer authorization. The nurse follows employer policy, which differs between settings and provinces or territories; in Ontario, provincial standards name the RN as the nurse who gives systemic cancer treatment (section 9.5).

9.4 Oncologic Emergencies

An **oncologic emergency** is a sudden, life-threatening problem caused by cancer or its treatment. Some come from the treatment itself, such as infection when white blood cells are low. Others come from the tumour pressing on a vital structure or releasing substances into the blood. Each one can worsen within hours, so the nurse must know the early cues, act at once and escalate. The main emergencies are compared in Table 9.3.

Febrile Neutropenia

Febrile neutropenia is fever in a person whose neutrophils are low, most often after chemotherapy. Neutrophils are the white blood cells that fight bacteria first, and myelosuppressive treatment lowers them most at the nadir (section 9.3). The **absolute neutrophil**

count (ANC) is the number of neutrophils per litre of blood. Definitions differ slightly from one guideline to another, so the nurse uses the hospital's own definition. In Ontario, people receiving cancer treatment are told to contact their team or go to the nearest emergency department if their oral temperature is above 38.3 °C at any time, or above 38.0 °C for at least 1 hour (Ontario Health [Cancer Care Ontario], n.d.-b). Other Canadian guidance is similar. Health PEI (2025), for example, defines fever as a single oral temperature of 38.3 °C, or a temperature of 38.0 °C or higher that lasts over 1 hour, and neutropenia as an ANC at or below 0.5×10^9/L, or below 1.0×10^9/L and expected to fall below 0.5×10^9/L within 48 hours. Alberta's guideline uses a neutrophil threshold of below 0.5×10^9/L (Alberta Health Services [AHS], 2014), and the American Society of Clinical Oncology (ASCO) and Infectious Diseases Society of America (IDSA) guideline uses nearly the same fever thresholds (Taplitz et al., 2018).

An Ontario guideline panel describes fever during systemic cancer treatment as common, potentially serious and in need of prompt assessment (Krzyzanowska et al., 2016). With few neutrophils, the body cannot mount its usual inflammatory response. Pus, redness, swelling and infiltrates on a chest X-ray may be faint or absent, so fever may be the only sign of a serious infection (see Chapter 4, section 4.2). A patient may also simply feel unwell, have chills or seem newly confused.

Febrile neutropenia is a medical emergency. The ASCO and IDSA guideline advises assessment within about 15 minutes of triage and the first dose of empirical antibiotics within 1 hour of triage (Taplitz et al., 2018). Health PEI (2025) likewise sets a target of antibiotics within 1 hour of presentation and warns against waiting for test results. The nurse:

- measures a full set of vital signs, checks level of consciousness and looks for a source, including the mouth, skin, perianal area and every line site;
- notifies the physician or nurse practitioner (NP) at once and uses the unit's febrile neutropenia order set if one exists;
- draws blood cultures before antibiotics without delaying them: one set from each lumen of a central line plus one peripheral set, or two peripheral sets (Health PEI, 2025), with urine and other cultures as ordered;
- starts the ordered broad-spectrum intravenous (IV) antibiotic and records the time.

Febrile neutropenia can progress to sepsis and septic shock. Falling blood pressure, rising heart and breathing rates, a high lactate level or new confusion call for the sepsis response and first-hour care in Chapter 4, section 4.6, and escalation in Chapter 6.

Prescribers estimate the risk of serious complications with a validated score such as the **Multinational Association for Supportive Care in Cancer (MASCC) risk index**; a few low-risk patients may be treated as outpatients in experienced centres (AHS, 2014; Taplitz et al., 2018). The nurse is not expected to calculate the score. Alberta's guideline advises against a rectal examination in neutropenic patients (AHS, 2014), so the nurse follows unit policy before using the rectal route for any purpose.

Teaching begins before the first treatment. Patients keep a working thermometer at home and know whom to call at any hour. They call at once for a temperature that meets the threshold their cancer centre gives, or for chills or feeling unwell, rather than waiting until morning (Taplitz et al., 2018).

CLINICAL JUDGMENT

A Fever Ten Days After Chemotherapy

Names and details are fictional; this is a composite story.

Mr. Hamid Rahimi, 66, was admitted to a medical unit with dehydration 10 days after his second cycle of chemotherapy for lymphoma.

- **Recognize cues:** At 0200 he says he feels cold and shaky. His temperature is 38.5 °C, heart rate 108 beats/min, blood pressure 112/68 mm Hg and respiratory rate 22 breaths/min. That afternoon his ANC was 0.3×10^9/L. He has a port in his chest. The nurse finds no redness at the port, no cough and no sore mouth, so there is no obvious source.
- **Analyze cues:** He is at his expected nadir. A fever above the threshold with an ANC this low meets the definition of febrile neutropenia.
- **Prioritize hypotheses:** Infection that could progress to sepsis comes first. A drug or transfusion reaction is less likely; he has received neither tonight.
- **Generate solutions:** Antibiotics within 1 hour; cultures first if they cause no delay; a search for the source; closer monitoring.
- **Take action:** The nurse calls the physician on call with an SBAR report (Chapter 6), starts the febrile neutropenia order set, draws blood cultures from both lumens of his port and a peripheral vein and hangs the ordered antibiotic at 0240.

- **Evaluate outcomes:** At 0330 his blood pressure is 108/66 mm Hg and he is alert. The nurse checks vital signs often, watches for signs of sepsis (Chapter 4, section 4.6) and hands over the time the antibiotic started. The next morning the nurse checks that the team has reviewed the culture results and that the next antibiotic dose is given on time. Mr. Rahimi is reminded to report chills at once.

Tumour Lysis Syndrome

Tumour lysis syndrome (TLS) is a group of metabolic problems that occurs when many cancer cells break open at once and spill their contents into the blood faster than the kidneys can clear them. It usually follows the start of treatment, but it can happen on its own in a fast-growing tumour (Enríquez Enríquez, 2024).

Risk is highest with a large tumour burden and with cancers that respond quickly to treatment, such as some acute leukemias and high-grade lymphomas. Other risk factors include a very high white blood cell count, a high lactate dehydrogenase level, bulky disease and kidney disease before treatment (Enríquez Enríquez, 2024).

The typical pattern is high potassium, high phosphate, high uric acid, low calcium and a rising creatinine level. The mechanism and the formal criteria are in the Going Deeper box. Many patients have no symptoms at first. Cues include nausea, muscle cramps or twitching, palpitations or an irregular pulse, falling urine output and new confusion or seizures.

Prevention is planned before treatment begins. The team orders generous IV hydration to keep urine flowing and a drug that lowers uric acid. **Allopurinol** blocks the enzyme that makes uric acid. **Rasburicase** is an enzyme that turns uric acid into a substance the kidneys excrete easily; it must not be given to people with glucose-6-phosphate dehydrogenase (G6PD) deficiency, because it can cause hemolysis (Enríquez Enríquez, 2024).

The nurse monitors intake and output closely, weighs the patient daily and reports falling urine output at once. The nurse also follows laboratory results, which may be ordered every 4 to 6 hours at first, and places the patient on a cardiac monitor as ordered. Potassium and calcium imbalances and their treatment are taught in Chapter 3, sections 3.5 and 3.6.

GOING DEEPER

Tumour Lysis Syndrome

Required for RN students; optional for PN students.

When cancer cells break apart, they release potassium, phosphate and nucleic acids into the blood. The body breaks the nucleic acids down to xanthine, which the enzyme xanthine oxidase converts to uric acid (Enríquez Enríquez, 2024).

Each product causes harm in a different way:

- **Potassium:** A high level makes heart cells unstable. Electrocardiogram (ECG) changes and dangerous dysrhythmias, including cardiac arrest, can follow.
- **Phosphate:** Phosphate binds calcium. Blood calcium falls, causing tingling, muscle cramps, tetany, seizures and dysrhythmias. Calcium phosphate crystals also form in tissues, including the kidneys.
- **Uric acid:** Uric acid and xanthine crystals, with calcium phosphate, block the kidney tubules. Reduced blood flow to the kidneys and inflammation add to the injury (Enríquez Enríquez, 2024).

The result can be **acute kidney injury**. As the kidneys fail, they clear even less potassium and phosphate, so the levels rise further.

The **Cairo–Bishop criteria** are widely used to define TLS (Cairo & Bishop, 2004). Laboratory TLS means two or more of these changes in the period that runs from 3 days before until 7 days after the start of treatment: high uric acid, high potassium, high phosphate or low calcium, each either beyond a set limit or changed by 25% from baseline. Clinical TLS means laboratory TLS plus kidney injury (creatinine at least 1.5 times the upper limit of normal), a dysrhythmia or sudden death, or a seizure (Cairo & Bishop, 2004; Enríquez Enríquez, 2024).

The RN reviews each laboratory result as it arrives, compares it with baseline and reports trends early. The RN also watches the cardiac monitor for changes linked to high potassium, such as peaked T waves (Chapter 3, section 3.5), and checks urine output hourly when ordered.

Hypercalcemia of Malignancy

Hypercalcemia of malignancy is the most common metabolic complication of cancer (El-Hajj Fuleihan et al., 2023). It occurs most often with breast, lung and kidney cancers and multiple myeloma. There are three main causes:

- many tumours release **parathyroid hormone–related peptide (PTHrP)**, which drives bone breakdown even with no bone metastases;
- cancer in the bone breaks down bone directly;
- some lymphomas make active vitamin D, which raises calcium absorption from the gut (El-Hajj Fuleihan et al., 2023).

Cues develop gradually and are easy to blame on cancer or its treatment. Mild hypercalcemia can cause fatigue, constipation and trouble thinking. Higher or fast-rising levels cause polyuria, thirst and kidney failure (El-Hajj Fuleihan et al., 2023). Polyuria causes dehydration, which raises the calcium further. The nurse reports these cues and checks the calcium result, corrected for albumin or as an ionized value (Chapter 3, section 3.6).

Treatment is led by the team. IV fluids come first. An IV bisphosphonate such as zoledronic acid, or denosumab, then slows bone breakdown (El-Hajj Fuleihan et al., 2023). The nurse gives fluids as ordered, monitors intake and output, lung sounds and weight for fluid overload, and keeps the confused patient safe from falls.

Malignant Spinal Cord Compression

Malignant spinal cord compression occurs when a tumour in the spine, usually a metastasis, presses on the spinal cord or the nerve roots below it. The pressure can cause weakness, loss of sensation and loss of bladder and bowel control.

Back pain is often the first cue. Pain that is severe and unrelenting, keeps getting worse, increases with coughing, sneezing or straining, or wakes the person at night suggests spinal metastases in anyone with current or past cancer (National Institute for Health and Care Excellence [NICE], 2023). Cues of cord compression include limb weakness, difficulty walking, numbness or tingling, pain that radiates along a nerve, and new bladder or bowel problems (NICE, 2023).

NICE (2023) treats new neurological cues in a person with cancer as an oncological emergency, with an MRI without delay and no later than 24 hours after the cues appear. The nurse reports these cues at once and does not wait for the next round. The team may give a corticosteroid such as dexamethasone to reduce swelling while planning radiation or surgery. The nurse:

- assesses strength, sensation, gait and bladder and bowel function, and compares them with baseline;
- keeps the spine aligned and limits movement as ordered until the team has assessed spinal stability;
- nurses the patient lying flat if ordered, since this lowers weight bearing on the spine (NICE, 2023);
- reports any new or worsening weakness or numbness at once;
- manages pain (Chapter 5) and prevents pressure injury (Chapter 35) and venous thromboembolism (VTE; Chapter 7).

Superior Vena Cava Syndrome

Superior vena cava syndrome occurs when a tumour or a clot narrows the superior vena cava, which carries blood from the head, neck and arms to the heart. Most cases are caused by cancer, especially lung cancer and lymphoma. The rest are mostly linked to central lines or pacemaker leads (Chow et al., 2024).

Blood backs up in the upper body. Cues include a feeling of fullness in the head, swelling of the face, neck and arms, and shortness of breath. The neck and chest-wall veins may stand out as collateral veins enlarge. These veins are easier to see on lighter skin; on darker skin, the nurse looks for swelling, a tight collar or rings, and asks about changes the patient has noticed. Symptoms often worsen when the patient lies flat or bends forward (Chow et al., 2024).

Severe swelling of the larynx, blockage of the central airway and swelling of the brain are the life-threatening complications (Chow et al., 2024). The nurse helps the patient sit up, gives oxygen as ordered and escalates any new noisy breathing, change in voice or decline in consciousness at once. The team confirms the diagnosis and may treat with stenting, radiation or systemic therapy (Chow et al., 2024).

Extravasation

Extravasation is the leakage of an IV drug out of the vein into the surrounding tissue. A **vesicant** is a drug that can cause blistering, ulcers and tissue death if it leaks. An **irritant** causes pain or inflammation at the site or along the vein, usually without lasting tissue damage. Some irritants behave like vesicants, and a 2025 guideline from the Oncology Nursing Society (ONS) and ASCO treats them the same way (Thomas et al., 2025).

Extravasation seems to occur more often with peripheral IV lines than with central venous access devices (Thomas et al., 2025). Early cues include pain, swelling and redness at the site; on darker skin, redness may be hard to see, so the nurse compares the site with the other arm and asks about pain, tightness and warmth. Later, blistering, ulcers and tissue death can develop (Thomas et al., 2025). The nurse checks the site before and often during every vesicant infusion and teaches the patient to report any discomfort at once. The steps that follow are in the Clinical Safety box.

CLINICAL SAFETY

Extravasation

Act at the first sign, following the organization's policy and the drug's protocol (Thomas et al., 2025):

- Stop the infusion at once. Leave the needle or catheter in place.
- Try to withdraw as much drug as possible with a syringe through the device, then disconnect the tubing.
- Notify the prescriber. Give an antidote only if one is ordered for that drug.
- Apply cold or warm compresses only as the drug's protocol directs. Cold suits some drugs and warmth others, so never guess.
- Elevate the limb.
- Mark the edges of the area and photograph the site if policy calls for it.
- Document the drug, the estimated amount, the time, the site's appearance, the actions taken and the patient's response, and complete an incident report.
- Teach the patient to keep the site clean and dry, avoid tight clothing and report increasing pain, blistering or fever. Arrange follow-up of the site over the following days and weeks.

Table 9.3 Oncologic emergencies: cues and first nursing actions (AHS, 2014; Chow et al., 2024; El-Hajj Fuleihan et al., 2023; Enríquez Enríquez, 2024; NICE, 2023; Thomas et al., 2025; Taplitz et al., 2018)

Emergency	Who is at risk	Cues	First nursing actions
Febrile neutropenia	People receiving myelosuppressive treatment, especially near the nadir	Temperature meeting the fever threshold; chills; feeling unwell; new confusion; few signs of infection	Assess within minutes; notify the prescriber; cultures, then IV antibiotics within 1 hour; watch for sepsis
Tumour lysis syndrome	Large, fast-growing, treatment-sensitive cancers such as some leukemias and lymphomas; kidney disease	Often none at first; nausea; cramps or twitching; palpitations; low urine output; seizures	Hydrate as ordered; give uric acid–lowering drugs; strict intake and output; cardiac monitoring; report lab changes
Hypercalcemia	Breast, lung and kidney cancers, myeloma, bone metastases	Fatigue; constipation; confusion; polyuria; thirst	Report cues; check calcium; IV fluids as ordered; watch for fluid overload; fall safety
Spinal cord compression	Cancers that spread to bone	New or worsening back pain; weakness; numbness; difficulty walking; bladder or bowel changes	Report at once; neurological checks; keep spine aligned; prepare for urgent MRI
Superior vena cava syndrome	Lung cancer, lymphoma, central lines	Swelling of face, neck and arms; head fullness; dyspnea; visible chest veins; worse lying flat	Sit patient up; oxygen as ordered; assess airway; escalate any breathing or consciousness change
Extravasation	Vesicant or irritant infusions, especially through peripheral lines	Pain, swelling, redness at the site; later blistering	Stop infusion; aspirate through the device; notify; follow the drug's protocol; document

9.5 Safe Handling of Hazardous Drugs

Nurses protect themselves, their co-workers and patients' families from exposure to hazardous drugs. Small, repeated exposures through the skin or by breathing in drug particles are the main concern.

What Makes a Drug Hazardous

A **hazardous drug** is a drug that can harm the people who handle it. Ontario's safe handling guideline uses the National Institute for Occupational Safety and Health (NIOSH) definition: a drug is hazardous if it has any one of six features (Kennedy et al., 2022):

- it damages genetic material (genotoxicity);
- it can cause cancer (carcinogenicity);
- it can cause birth defects (teratogenicity);
- it impairs fertility or harms reproduction;
- it damages organs at low doses;
- its structure and toxicity resemble drugs already known to be hazardous.

Exposure can happen at any step: unpacking deliveries, preparing and giving the drug, cleaning a spill, and handling waste, linen and body fluids (Kennedy et al., 2022). Many antineoplastic drugs meet this definition. The definition is not limited to cancer drugs, so the nurse checks the organization's hazardous drug list rather than assuming that only cancer drugs need precautions.

Protecting Staff

The Ontario Health (Cancer Care Ontario) guideline on safe handling of hazardous drugs sets out how staff should be protected at each step, from receiving the drug to disposing of waste (Kennedy et al., 2022). Its main points for nurses are:

- **Gloves:** Use powder-free gloves tested for use with chemotherapy, not vinyl. Wear two pairs to give IV, subcutaneous and liquid oral hazardous drugs; one pair is enough for solid tablets. Change gloves at once if they tear or are contaminated, and every 30 minutes unless the manufacturer states otherwise.
- **Gowns:** Wear a disposable, low-permeability gown with long sleeves, tight cuffs and a back closure. Remove gloves and gown without touching their outer surfaces, so the skin is not contaminated.
- **Eye and face protection:** Use face protection, such as a face shield, whenever splashing is possible. Ordinary eyeglasses, and even side-shielded safety glasses, do not give the eyes enough protection from splashes.
- **Closed-system drug-transfer devices:** A **closed-system drug-transfer device (CSTD)** is a device that connects drug containers and tubing so that drug cannot escape into the air or onto the skin. CSTDs reduce contamination but do not replace other precautions.
- **Labelling:** Hazardous drugs, their containers and their waste carry the "Cytotoxic" symbol or word, as legislation requires.
- **Spills:** Spill kits must be available wherever hazardous drugs are stored, carried, given or used, including the home. All staff who handle these drugs are trained to use them; a large spill calls for the organization's emergency code.
- **Waste:** Hazardous waste goes into labelled cytotoxic containers, never into regular biomedical waste.
- **Training:** Only trained staff carry, give and dispose of hazardous drugs, and training is repeated and documented each year.

Staff who are pregnant, breastfeeding or chestfeeding, or trying to conceive must be told about the reproductive risks. The guideline advises organizations to consider alternative duties for them (Kennedy et al., 2022). Occupational health and employer policy guide the process.

Body Fluids After Treatment

Many hazardous drugs and their by-products leave the body in urine, stool, vomit and other fluids. Ontario guidance asks staff handling these fluids, soiled linen or equipment from a patient who received a hazardous drug to wear two pairs of gloves and a gown, plus face protection if splashing is possible. These precautions apply for at least 48 hours after the drug is given, and longer

for some drugs, such as cyclophosphamide (Kennedy et al., 2022). Soiled incontinence products go into cytotoxic waste. Contaminated linen goes into a sealed bag and is washed separately.

Patients often receive treatment as outpatients, so families may handle body fluids at home. Organizations are expected to have a process for hazardous waste from the home that includes teaching patients and caregivers (Kennedy et al., 2022). The nurse reviews the cancer centre's written home instructions with the patient and family. These usually cover wearing gloves to clean up body fluids, washing soiled laundry separately and contacting the centre about a spill.

SCOPE IN PRACTICE

Who Gives Cancer Treatments

Scope rests on **authority, competence and context** (Chapter 1, section 1.3).

- **Authority:** Giving chemotherapy and immunotherapy needs an order and the employer's authorization. Employer policy and the province or territory decide which nurses may do so.
- **Competence:** Specialized education is required. The Canadian Association of Nurses in Oncology (CANO/ACIO) publishes standards and competencies for RNs who care for people receiving systemic therapy (Canadian Association of Nurses in Oncology, 2023). In Ontario, the Ontario Health (Cancer Care Ontario) competence standards state that "the RN is the appropriate nurse role to administer systemic treatment" (Ontario Health [Cancer Care Ontario], n.d.-c). The RN completes a recognized chemotherapy and immunotherapy course, shows competence on the provincial skills checklist and then completes a competency maintenance course every 24 months. A nurse who has not yet finished the course receives added training and supervised practice from the employer, and nurses use only the skills in which they have shown competence.
- **Context:** Practice settings differ. Rules and roles vary by province or territory and by organization, so the nurse follows the employer's policy.

Whatever the setting, RNs and RPNs both monitor patients during and after treatment, teach and handle hazardous drugs safely. The RPN consults the RN as the patient's needs change. Any nurse who notices deterioration, such as fever in a patient with neutropenia, acts and escalates at once.

9.6 Living With Cancer: Support and Survivorship

Cancer affects every part of a person's life, often for years. Nurses screen for symptoms and distress, support self-care during treatment and help people move into life after treatment.

Distress and Symptom Screening

Distress is an unpleasant emotional experience, with psychological, social, spiritual, practical or physical causes, that can make it harder to cope with cancer. It ranges from normal sadness and worry to disabling depression or anxiety (CPAC, 2012). CPAC describes distress as the sixth vital sign, to be monitored as routinely as temperature, pulse, blood pressure, breathing and pain (CPAC, 2012).

Distress screening is the routine use of a short standard tool to find patients who need more assessment or support. CPAC (2012) recommends screening every person with cancer at entry to care and at key points: diagnosis, the start and end of treatment, recurrence, advanced disease and other life transitions. Two tools form the core:

- The **Edmonton Symptom Assessment System–revised (ESAS-r)** asks the patient to rate nine common symptoms, such as pain, tiredness, nausea, anxiety and depression, on a scale from 0 (none) to 10 (worst possible) (Watanabe et al., 2011).
- The **Canadian Problem Checklist** asks about emotional, practical and physical concerns that a symptom scale misses (CPAC, 2012).

In Ontario, patients are encouraged to complete the ESAS-r through **Your Symptoms Matter** before each visit to the cancer centre, or when their team suggests (Ontario Health [Cancer Care Ontario], n.d.-d). A score is the start of a conversation, not a diagnosis. The nurse asks about high or rising scores, assesses further, agrees on a plan with the patient and refers to the right service, such as social work, psychosocial oncology, a dietitian or spiritual care (CPAC, 2012).

Nutrition, Fatigue and Exercise

Cancer-related fatigue is a distressing, lasting sense of physical, emotional or mental exhaustion that is out of proportion to recent activity and gets in the way of daily life (AHS, 2017). Rest does not fix it. The nurse screens for fatigue with the ESAS-r tiredness score and looks for causes that can be treated, such as anemia, pain, poor sleep, depression, infection, thyroid problems and medications (AHS, 2017).

Activity helps. Canadian guidance advises encouraging every patient to stay as active as they safely can during and after treatment. Walking suits most people, and a mildly fatigued patient can build up gradually toward 150 minutes of activity a week. More severe fatigue needs screening by a qualified exercise professional, or medical clearance, first (AHS, 2017). Energy conservation, pacing and occupational therapy also help.

Poor appetite, taste changes, mouth sores and nausea can all lead to weight loss. When a patient reports poor appetite with weight loss or reduced intake, the nurse uses a validated malnutrition screening tool and refers to a registered dietitian (AHS, 2017). Preventing nausea is covered in the Medications box.

MEDICATIONS

Preventing Chemotherapy-Induced Nausea and Vomiting

Nausea and vomiting are easier to prevent than to treat. Each treatment is classed by its emetic risk (how likely it is to cause vomiting), and the prescriber orders scheduled antiemetics to match (Herrstedt, Celio, et al., 2024). For treatments with the highest emetic risk, the Multinational Association for Supportive Care in Cancer (MASCC) and the European Society for Medical Oncology (ESMO) recommend four drugs together (Herrstedt, Celio, et al., 2024):

- a **5-HT3 receptor antagonist**, such as ondansetron;
- a **neurokinin-1 (NK1) receptor antagonist**, such as aprepitant;
- a **corticosteroid**, dexamethasone;
- **olanzapine**.

Nursing points:

- Give preventive antiemetics on schedule, before treatment and on the days that follow, not only when nausea starts.
- Ask about nausea, vomiting and intake each shift. Report breakthrough nausea promptly so the prescriber can add a drug from another class.
- Teach patients to take home antiemetics as prescribed and to call if they cannot keep fluids down.
- Check the product monograph for each drug's adverse effects and interactions.

Sexual Health and Fertility

Cancer and its treatment can affect fertility, sexual function and body image. ASCO advises that people with cancer be assessed and counselled about risks to their fertility at diagnosis and during survivorship (Su et al., 2025). **Fertility preservation** means storing sperm, eggs, embryos or reproductive tissue, or protecting reproductive organs, so that a person may have biological children later. The options should be discussed before cancer treatment starts, and anyone interested or unsure should be referred promptly to a reproductive specialist (Su et al., 2025). Sperm, egg and embryo freezing are well established. Some time to act is often available, so the nurse makes sure the conversation happens and the referral is made early.

Sexual changes are common and often go unspoken. Scars, hair loss, weight change, vaginal dryness, low desire and erection problems can all affect intimacy (Canadian Cancer Society [CCS], 2025b). The nurse asks about sexual health in a private, matter-of-fact way, uses inclusive language and offers referral to a counsellor or sex therapist. Patients follow the team's advice on contraception during treatment, because many cancer drugs can cause birth defects (Kennedy et al., 2022).

Survivorship

More people now live for years after a cancer diagnosis. Ontario Health's (2026) quality standard on cancer survivorship calls for:

- a regular, at least yearly, assessment of each survivor's needs;
- an individualized care plan that is kept up to date;

- coordinated transitions between the cancer team and primary care;
- psychosocial support for survivors and their care partners;
- education about follow-up and late effects;
- accessible, equitable care that is culturally and linguistically responsive.

A **survivorship care plan** is a written summary of the person's diagnosis and treatment plus a plan for follow-up. It lists scheduled visits and tests, signs of recurrence to report, possible late and long-term effects and advice on staying well (CCS, 2025b). Follow-up often moves from the oncologist to the family physician or NP over time. The plan helps that handover.

Late effects can appear months or years after treatment. Examples include fatigue, lymphedema, nerve damage, bone loss, memory changes and early menopause (CCS, 2025b). **Fear of recurrence** is common, especially in the first year and around follow-up visits. For most people it eases with time, but for some it disrupts sleep or daily life (CCS, 2025b). Most survivors who can work go back to their jobs, often gradually, and employers must make reasonable accommodations (CCS, 2025b).

The nurse links patients and caregivers with supports: patient navigators, including Indigenous patient navigators (Chapter 2); the Canadian Cancer Society's Cancer Information Helpline (1-888-939-3333) and online community; and local peer support groups (CCS, 2025b). Caregivers carry heavy loads and are screened and supported too (Ontario Health, 2026b).

> **PRACTICE STORY**
>
> **"Just a Little Fever"**
>
> *Names and details are fictional; this is a composite story.*
>
> Nurse: Tessa Morin, RPN. Years in practice: 6. Setting: medical unit, community hospital, Ontario.
>
> Mr. Halvorsen, 68, came back to our unit four days after his chemotherapy for lymphoma with diarrhea and dehydration. By day 9 he was eating better and talking about going home. At 1500 I brought his afternoon pills. He smiled and said, "I'm just a little warm, nothing to fuss over. My wife worries enough."
>
> His temperature was 38.4 °C. His heart rate was 104, up from 82 at noon. I looked at the morning bloodwork: neutrophils 0.4 × 10^9/L. Nine days after chemotherapy, a low count, and now a fever. I had learned that a fever might be the only sign of a serious infection in someone with almost no neutrophils.
>
> I went straight to Kwame, the RN on my team that day, instead of rechecking in an hour as I might for someone else. He agreed and paged the physician while I repeated the vitals and looked at Mr. Halvorsen's PICC site, mouth and skin. The physician ordered the febrile neutropenia order set. Kwame drew blood cultures from the PICC and a peripheral vein, and the first antibiotic was running at 1540, well within the hour.
>
> That evening Mr. Halvorsen's blood pressure dipped to 98/60. Because we had started early, the team was already watching. He needed IV fluids and several days of antibiotics, and his cultures grew a bacterium in his blood.
>
> I think about how easy it would have been to accept "just a little warm." He did not want to be a bother. Now I teach my patients that calling about a fever after chemotherapy is never a bother.
>
> Reflect: How did Tessa's knowledge of the chemotherapy nadir change what she did with an ordinary-sounding complaint? Using authority, competence and context, which actions were Tessa's own, and why was consulting the RN at once the right step?

Chapter 9 Summary

Introduction

- About 2 in 5 people in Canada are expected to develop cancer in their lifetime, and cancer is the leading cause of death in Canada.
- Nurses meet people with cancer on every unit; this chapter covers biology, prevention and screening, treatment, safe handling, emergencies and survivorship.

9.1 Cancer Biology

- Cancer develops as changes accumulate in proto-oncogenes, tumour suppressor genes and DNA repair genes; most changes are acquired, and up to about 10% of cancers are linked to inherited variants such as *BRCA1/2* or Lynch syndrome.
- The hallmarks framework describes the shared capabilities cancer cells acquire, several of which are targets of newer treatments.
- Malignant tumours invade and metastasize by lymphatic spread, blood-borne spread and seeding; a metastasis keeps the identity of the primary cancer.
- Grade describes how abnormal the cells look; stage, often TNM-based, describes extent and strongly predicts survival.
- Biopsy confirms the diagnosis; tumour markers mainly help monitor treatment and recurrence and are poor screening tools.

9.2 Cancer in Canada: Risk, Prevention and Screening

- *Canadian Cancer Statistics 2025* estimated 254,800 new cases and 87,400 deaths in 2025; lung, breast, prostate and colorectal cancers make up almost half of diagnoses.
- Between 33% and 37% of cancers in adults aged 30 and older in 2015 were attributable to modifiable risk factors, led by tobacco; radon, alcohol, UV radiation and infections are other targets for prevention.
- Screening finds cancer earlier but carries harms, including overdiagnosis; recommendations weigh both and support shared decisions.
- The Canadian Task Force ended its mandate on March 31, 2026, and a new National Advisory Committee on Preventive Health Services was announced on June 10, 2026; provincial programs, such as Ontario's, set the rules people actually use, so nurses check their own province or territory.
- Inequities in cancer outcomes for First Nations, Inuit and Métis, rural residents, newcomers, 2SLGBTQI+ people and people with disabilities have structural causes; nurses reduce barriers and practise cultural safety.

9.3 Cancer Treatments

- Surgery can diagnose, stage, cure, debulk, reconstruct, palliate or reduce risk, and it is often combined with neoadjuvant or adjuvant therapy.
- Radiation damages cancer cell DNA; external beam does not make the patient radioactive, while sealed and unsealed sources require radiation safety precautions.
- Chemotherapy harms fast-dividing normal cells, causing myelosuppression, mucositis, nausea, alopecia and fatigue; fever during neutropenia is an emergency.
- Targeted therapy, immune checkpoint inhibitors and hormone therapy have distinct adverse effects; immune-related adverse events can appear months after treatment and must be reported early.
- Implanted ports and PICCs are assessed before each use, and accessing them or giving cancer drugs requires education and employer authorization; in Ontario, provincial standards name the RN as the nurse who gives systemic cancer treatment.

9.4 Oncologic Emergencies

- Febrile neutropenia is fever with a very low neutrophil count. In Ontario, people on cancer treatment seek care for an oral temperature above 38.3 °C at any time or above 38.0 °C for at least 1 hour; definitions vary slightly, so follow the hospital's definition. Fever may be the only sign of infection.
- Assess at once, draw cultures without delay and give the first IV antibiotic within 1 hour of triage; watch for sepsis (Chapter 4, section 4.6).
- Tumour lysis syndrome causes high potassium, phosphate and uric acid, low calcium and kidney injury; prevention is hydration and uric acid–lowering drugs, with close monitoring of urine output, laboratory results and heart rhythm.
- Hypercalcemia causes fatigue, constipation, confusion, polyuria and thirst; IV fluids come first.
- New or worsening back pain in a person with cancer may be the first cue of spinal cord compression; neurological changes are an emergency needing MRI within 24 hours.

- Superior vena cava syndrome causes swelling of the face, neck and arms with dyspnea; sit the patient up and escalate. For extravasation, stop the infusion, aspirate through the device, notify and follow the drug's protocol.

9.5 Safe Handling of Hazardous Drugs

- Hazardous drugs can damage genes, cause cancer or birth defects, harm fertility or damage organs; they include many antineoplastic drugs and some others.
- For IV administration, wear two pairs of chemotherapy-tested gloves and a protective gown, with face protection if splashing is possible; use CSTDs, labelling, spill kits and cytotoxic waste as policy directs.
- Precautions with body fluids continue for at least 48 hours after a hazardous drug, longer for some drugs; teach families the cancer centre's home instructions.
- Giving cancer treatments requires specialized education and employer authorization; in Ontario, provincial competence standards name the RN as the appropriate nurse role, and every nurse monitors, teaches and escalates.

9.6 Living With Cancer: Support and Survivorship

- Distress is the sixth vital sign; screen with the ESAS-r and Canadian Problem Checklist, then talk, assess and refer.
- Cancer-related fatigue is not relieved by rest; look for treatable causes and encourage safe activity; screen nutrition and refer to a dietitian.
- Prevent nausea with scheduled antiemetics matched to emetic risk.
- Discuss fertility risks and preservation before treatment and refer early; ask about sexual health and body image.
- Survivorship care plans, transition to primary care, attention to late effects, fear of recurrence and return to work, and support for caregivers help people live well after treatment.

Key Terms (48)

absolute neutrophil count (ANC): The number of neutrophils per litre of blood, reported in × 10^9/L.

adjuvant therapy: treatment given after surgery to destroy cancer cells that may remain.

apoptosis: orderly, programmed cell death that removes damaged or unneeded cells.

brachytherapy: radiation therapy in which a sealed radioactive source is placed inside or next to a tumour.

Cairo–Bishop criteria: A widely used set of laboratory and clinical criteria that define tumour lysis syndrome.

Canadian Problem Checklist: A screening checklist of emotional, practical and physical concerns used with the ESAS-r.

cancer-related fatigue: A distressing, persistent sense of physical, emotional or mental exhaustion, out of proportion to activity and not relieved by rest.

carcinogen: an agent, such as a chemical, radiation or a virus, that can damage DNA and cause cancer.

carcinogenesis: the multistep process by which a normal cell becomes a cancer cell.

chemotherapy: treatment with cytotoxic drugs that kill cancer cells or slow their growth, along with other rapidly dividing cells.

closed-system drug-transfer device (CSTD): A device that connects drug containers and tubing so that hazardous drug cannot escape into the air or onto the skin.

cytokine release syndrome: a surge of inflammatory signals after some immune therapies, such as CAR T-cell therapy, causing high fever and low blood pressure.

distress: Emotional, social, spiritual, practical or physical suffering that makes coping with cancer harder; called the sixth vital sign.

distress screening: Routine use of a short standard tool to identify people with cancer who need further assessment or support.

Edmonton Symptom Assessment System–revised (ESAS-r): A tool in which patients rate nine common symptoms from 0 to 10.

external beam radiation: radiation delivered from a machine outside the body and aimed at the tumour; the patient does not become radioactive.

extravasation: Leakage of an IV drug out of the vein into the surrounding tissue.

fear of recurrence: Worry that cancer will return, common after treatment and sometimes severe enough to disrupt daily life.

febrile neutropenia: Fever in a person with a low neutrophil count, usually after chemotherapy; a medical emergency treated with IV antibiotics within 1 hour.

fertility preservation: Storing sperm, eggs, embryos or reproductive tissue, or protecting reproductive organs, before or after cancer treatment so that a person may have biological children later.

grade: a description of how abnormal cancer cells look under a microscope, reflecting how well differentiated they are.

hazardous drug: A drug that can harm people who handle it because it may damage genes, cause cancer or birth defects, harm fertility, damage organs at low doses, or resembles drugs with these effects.

hormone therapy: cancer treatment that blocks the production or action of hormones that some cancers need to grow.

hypercalcemia of malignancy: A high blood calcium level caused by cancer, often through parathyroid hormone–related peptide or bone metastases.

immune checkpoint inhibitor: a drug that blocks signals cancer cells use to switch off T cells, allowing the immune system to attack the cancer.

immune-related adverse event: an inflammatory reaction in a healthy organ caused by immune checkpoint inhibitor therapy, such as colitis, pneumonitis, hepatitis, endocrine disorders or rash.

irritant: A drug that causes pain or inflammation at the IV site or along the vein, usually without lasting tissue damage.

malignant spinal cord compression: Pressure on the spinal cord or nerve roots from cancer in the spine, causing pain and possible loss of strength, sensation and bladder or bowel control.

metastasis: spread of cancer from its primary site to a distant site, where it forms a new tumour.

mucositis: inflammation and ulceration of the lining of the mouth or gastrointestinal tract caused by cancer treatment.

Multinational Association for Supportive Care in Cancer (MASCC) risk index: A validated score prescribers use to estimate the risk of serious complications in febrile neutropenia.

myelosuppression: reduced production of blood cells by the bone marrow, causing neutropenia, anemia and thrombocytopenia.

nadir: the lowest point that a blood count reaches after a cancer treatment.

neoadjuvant therapy: treatment given before surgery to shrink a tumour.

oncologic emergency: A sudden, life-threatening problem caused by cancer or its treatment that needs immediate recognition and action.

overdiagnosis: detection through screening of a cancer that would never have caused symptoms or death.

parathyroid hormone–related peptide (PTHrP): A substance released by some tumours that increases bone breakdown and raises blood calcium.

proto-oncogene: a normal gene that promotes cell growth and division and can become a cancer-driving oncogene when mutated.

screening: testing people without symptoms to find cancer or precancerous changes early.

stage: a description of the size and extent of a cancer in the body, including spread to lymph nodes or distant sites.

superior vena cava syndrome: Swelling of the face, neck and arms with shortness of breath caused by narrowing of the superior vena cava by a tumour or clot.

survivorship care plan: A written summary of a person's cancer diagnosis and treatment with a plan for follow-up, signs to report, late effects and wellness.

targeted therapy: treatment that acts on specific proteins that drive the growth and spread of cancer cells.

TNM: an international staging system describing the primary tumour (T), regional lymph nodes (N) and distant metastasis (M).

tumour lysis syndrome (TLS): Metabolic imbalances (high potassium, phosphate and uric acid, low calcium) and possible kidney injury caused by the rapid breakdown of many cancer cells.

tumour marker: a substance made by cancer cells, or by the body in response to cancer, that can be measured to help monitor the disease.

tumour suppressor gene: a gene that normally slows cell division, repairs DNA or triggers apoptosis; loss of its function allows uncontrolled growth.

vesicant: a drug that can blister and destroy tissue if it leaks out of a vein.

Licensure Review & Clinical Judgment Questions (30)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Marisol Ferreira (Questions 1–4): Marisol Ferreira, 52, has stage III colon cancer and will start outpatient intravenous chemotherapy at a regional cancer centre next week. She lives with her husband and two teenagers and works as a bookkeeper. The nurse meets with her and her husband for pre-treatment teaching.

1. [CORE] Ms. Ferreira asks what she should do if she feels unwell at home between treatments. Which instruction is most appropriate?

a. "Take acetaminophen for any fever, rest at home, and call the clinic during office hours if the fever lasts more than 2 days."

b. "If you feel unwell, check your temperature, and for a fever at the level in your written instructions, call the cancer centre or go to emergency at once."

c. "Fever is expected for the first few days after each treatment, so you only need to call if you also develop a rash."

d. "Wait until your next scheduled blood test, because your neutrophil count will show whether a fever needs any treatment at all."

Answer: b — Neutropenia can make fever the only sign of a serious infection, so the person checks her temperature when unwell and seeks care at once for a fever at the threshold her cancer centre gives (section 9.3; febrile neutropenia in section 9.4). Treating the fever and waiting (a) masks the sign and delays urgent care. Fever is not an expected effect to tolerate at home (c). Waiting for a scheduled blood test (d) delays assessment and treatment of a possible emergency.

2. [CORE] The nurse teaches Ms. Ferreira how to prevent and manage mouth sores. Which plan reflects current guidance?

a. Rinse several times a day with a store-bought alcohol-based mouthwash so the mouth stays as free of germs as possible.

b. Stop brushing the teeth during treatment and use only mouthwash until treatment ends.

c. Rinse with club soda several times a day and choose tart fruits and juices to keep the mouth moist.

d. Brush gently with a soft toothbrush after meals and at bedtime, and rinse often with a bland salt and baking soda rinse.

Answer: d — Gentle brushing with a soft brush and frequent bland salt and baking soda rinses keep the mouth clean without irritating it (section 9.3). Alcohol-based mouthwash (a) dries and irritates tissue that is already fragile. Stopping brushing (b) allows plaque and infection to build up. Club soda is acidic, and tart or acidic foods irritate the mouth, so both are avoided (c).

3. [CORE] Ms. Ferreira is given prescriptions for antiemetics to take on a schedule for several days after treatment. She says, "I don't like taking pills, so I'll take them only if I feel sick." Which response is best?

a. "These medicines work best when taken on the schedule you were given, even if you feel well, because they are meant to prevent nausea."

b. "That is a good plan, since nausea after treatment is usually mild and does not need treatment."

c. "You can stop eating and drinking for a day after each treatment instead, so there is nothing to bring up."

d. "If you vomit, take a double dose of your antiemetic with your next meal."

Answer: a — Antiemetics are chosen according to the emetic risk of the treatment and are meant to prevent nausea, so they are taken as scheduled (section 9.3). Waiting until nausea starts (b) makes it harder to control. Withholding food and fluids (c) risks dehydration and does not prevent nausea. Changing doses on her own (d) is unsafe; she should call the cancer centre if she cannot keep fluids or medicines down.

4. [CORE] Ms. Ferreira's husband asks how to protect the family at home after each treatment. Which instruction is appropriate?

a. "Family members should avoid hugging or kissing her, and sleep in a separate room, until her course of treatment is finished."

b. "She should use disposable dishes and cutlery for the whole course of treatment."

c. "For about 48 hours after each treatment, she should close the toilet lid and flush twice, and anyone cleaning up her body fluids should wear disposable gloves."

d. "Her clothing and bedding should be thrown away if they touch her skin during the first week after each treatment."

Answer: c — Cancer drugs remain in body fluids for about 48 hours (longer for some drugs), so precautions focus on toilet use, gloves for cleaning up body fluids and washing soiled laundry separately (Easty et al., 2015; Waterloo Regional Health Network Cancer Centre, 2025; safe handling in section 9.5). Hugging and kissing are safe, and separate rooms are not needed (a). Disposable dishes are not needed (b). Linens are washed separately, not discarded (d).

5. [CORE] A nurse is teaching a community group about cancer prevention. Which of the following are modifiable risk factors for cancer? Select all that apply.

a. Smoking cigarettes

b. An inherited harmful *BRCA2* variant

c. Living in a home with a high radon level that has not been tested

d. Being 70 years of age

e. Physical inactivity

f. Drinking alcohol

Answer: a, c, e, f — Tobacco, physical inactivity and alcohol are modifiable risk factors linked to many cancers, and radon exposure can be found by testing and reduced (section 9.2). An inherited variant (b) cannot be changed, although risk can be managed through screening and risk-reducing options. Age (d) is the strongest risk factor, but it cannot be modified.

6. [CORE] A patient says, "The doctor told me my cancer is high grade, so that means it has spread everywhere." Which response by the nurse best explains the difference between grade and stage?

a. "Grade and stage mean the same thing; both describe how far the cancer has spread through the body."

b. "High grade means the cancer is in its earliest stage and has not spread."

c. "Grade tells how many lymph nodes are involved, and stage tells how fast the cells divide."

d. "Grade describes how abnormal the cells look under the microscope; stage describes the size of the tumour and whether it has spread."

Answer: d — Grade reflects how differentiated the cancer cells are, and stage, often expressed with TNM, describes the extent of the cancer in the body (section 9.1). They are separate measures (a). A high grade says nothing about early stage (b). Option c reverses and confuses the two: lymph node involvement is part of stage, and growth rate relates to grade.

7. [CORE] A patient receiving external beam radiation to the chest asks how to care for the skin in the treatment area. Which instruction is appropriate?

a. Apply a heating pad to the area each evening to relieve tightness.

b. Wash the area daily with lukewarm water and a mild cleanser, and pat it dry with a soft towel.

c. Scrub off the skin markings and any dry skin with a loofah each day.

d. Leave the area uncovered in direct sun to help the skin heal.

Answer: b — Gentle daily washing with lukewarm water and a mild cleanser, followed by patting dry, protects irritated skin (section 9.3). Heat (a) and friction (c) worsen radiation skin reactions, and the team's markings must be kept. Treated skin must be protected from the sun (d).

8. [CORE] A patient finished their last dose of an immune checkpoint inhibitor 3 months ago. They call the clinic to report five or six watery stools a day for 2 days and mild abdominal cramping. Which response by the nurse is most appropriate?

a. "Take an over-the-counter antidiarrheal, drink extra fluids, and call back if the diarrhea continues for another week."

b. "This cannot be related to your treatment, because it ended 3 months ago."

c. "This could be a reaction to your immunotherapy; I am letting the oncology team know now so you can be assessed today."

d. "Diarrhea is an expected effect of immunotherapy, so increase your fibre and fluids and it should settle on its own."

Answer: c — Immune-related colitis can begin months after the last dose and can progress quickly, so new diarrhea is reported and assessed the same day; the team may hold treatment and start corticosteroids (section 9.3). Self-treating and waiting (a, d) delays care for a potentially serious inflammatory reaction. Option b is incorrect because immune-related adverse events can appear long after treatment stops.

9. [CORE] On a medical unit in Ontario, the charge nurse asks a registered practical nurse (RPN) to hang a patient's scheduled intravenous chemotherapy because the oncology nurses are busy. Hospital policy, following provincial standards, authorizes only RNs who have completed chemotherapy education to give these drugs. What is the RPN's best action?

a. Decline, explain that hospital policy limits chemotherapy to RNs with this education, and tell the charge nurse so an authorized RN can be found.

b. Give the chemotherapy, because it has been ordered and any nurse on the unit may give a medication that has been ordered for the patient.

c. Ask an experienced RPN colleague to watch and coach while the RPN hangs the chemotherapy for the first time.

d. Delay the treatment until the next day without telling anyone, so that an oncology nurse can give it in the morning.

Answer: a — Under CNO's Scope of Practice standard, nurses accept only the activities they have the authority, competence and context to perform. In Ontario, Ontario Health (Cancer Care Ontario) competence standards name the RN, with recognized education and validated skills, as the nurse who gives systemic cancer treatment, and employer policy sets who is authorized; other provinces, territories and employers may differ (Ontario Health [Cancer Care Ontario], n.d.-c; sections 9.3 and 9.5; Chapter 1, section 1.3). Option b ignores the authority and competence required. A colleague who is not authorized either (c) cannot supply the missing authority or competence. Delaying treatment without communicating (d) is unsafe; the RPN informs the charge nurse so care can be arranged.

Case: Ms. Lucie Arsenault (Questions 10–15): Ms. Lucie Arsenault, 58, comes to the emergency department at 1410 with chills. She had her third cycle of chemotherapy for breast cancer 9 days ago. At triage her temperature is 38.7 °C, heart rate 114 beats/min, blood pressure 102/64 mm Hg, respiratory rate 24 breaths/min and SpO_2 95% on room air. She has an implanted port. A point-of-care count later shows neutrophils 0.2×10^9/L.

10. [CORE] Which finding is most important for the triage nurse to recognize as a cue to possible febrile neutropenia?

a. Her blood pressure of 102/64 mm Hg at triage

b. Her temperature 9 days after chemotherapy

c. Her SpO_2 of 95% on room air

d. The presence of an implanted port

Answer: b — A temperature at or above the threshold during the expected nadir after chemotherapy is the key cue to febrile neutropenia (section 9.4). Blood pressure (a) is lower than ideal but is not, by itself, a cue to neutropenia. An SpO_2 of 95% (c) is acceptable and points to no specific problem. A port (d) is a possible infection source, but it is not the cue that signals neutropenia.

11. [CORE] The nurse reviews the results: temperature 38.7 °C and neutrophils 0.2×10^9/L. How should the nurse analyze these cues?

a. They suggest a viral illness that needs rest and fluids.

b. They are expected after chemotherapy and need no action.

c. They show a transfusion reaction.

d. They meet the definition of febrile neutropenia.

Answer: d — A temperature of 38.7 °C with an ANC of 0.2×10^9/L meets every Canadian definition of febrile neutropenia, a medical emergency (section 9.4). A viral illness (a) cannot be assumed, and treating it as minor would delay antibiotics. Low counts are expected at the nadir, but fever with them is never "no action" (b). She has received no transfusion (c).

12. [CORE] Which hypothesis should the nurse place first?

a. Infection that may progress to sepsis
b. Dehydration from poor oral intake
c. Anxiety about starting her next cancer treatment
d. Expected fatigue from chemotherapy

Answer: a — With almost no neutrophils, fever means probable infection, which can quickly become sepsis; it is the most life-threatening possibility (section 9.4; Chapter 4, section 4.6). Dehydration (b) may add to her tachycardia but does not explain the fever. Anxiety (c) and fatigue (d) do not cause fever and would be dangerous explanations to accept.

13. [CORE] Which plan best matches Canadian and ASCO/IDSA guidance for Ms. Arsenault?

a. Hold antibiotics until blood culture results confirm a bacterial infection.
b. Give acetaminophen now and recheck her temperature in one hour before calling.
c. Draw blood cultures and give the first IV antibiotic within 1 hour of triage.
d. Arrange discharge home with an oral antibiotic once her temperature comes down.

Answer: c — Guidance calls for prompt assessment, blood cultures that do not delay treatment and the first antibiotic dose within 1 hour of triage (section 9.4). Waiting for culture results (a) delays treatment by days. Treating the fever and rechecking (b) hides the cue and loses time. Outpatient care (d) is only for selected low-risk patients after assessment, and she is already showing signs of instability.

14. [CORE] At 1450, before the antibiotic is hung, her blood pressure is 84/48 mm Hg, heart rate 128 beats/min and lactate 3.6 mmol/L. What should the nurse do first?

a. Recheck the blood pressure manually in 15 minutes.
b. Escalate at once and start the sepsis response, including IV fluids and the antibiotic as ordered.
c. Document the change carefully in the chart and report it to the oncology team at the next shift handover.
d. Encourage her to drink more fluids.

Answer: b — Hypotension, rising heart rate and a high lactate signal possible septic shock. The nurse escalates immediately and starts first-hour sepsis care (section 9.4; Chapter 4, section 4.6; Chapter 6). Waiting to recheck (a) and reporting at handover (c) delay care. Oral fluids (d) are too slow and not enough for shock.

15. [CORE] After IV fluids and antibiotics, which finding best shows that Ms. Arsenault is responding?

a. Her neutrophil count is still 0.2×10^9/L.
b. She says she feels "a bit better" but is now drowsy and hard to rouse.
c. Her temperature is 38.9 °C and her heart rate has risen to 120 beats/min.
d. Her blood pressure is 108/66 mm Hg; she is alert; lactate is falling.

Answer: d — A higher blood pressure, normal alertness and a falling lactate show improved perfusion (section 9.4; Chapter 4, section 4.6). Neutrophils (a) recover over days and do not reflect the response to fluids and antibiotics. New drowsiness (b) is a warning sign, not improvement. Ongoing fever and tachycardia (c) show no response.

16. [CORE] A patient with a high-grade lymphoma started chemotherapy yesterday. Which finding should the nurse report as a possible cue to tumour lysis syndrome?

a. Blood pressure 138/84 mm Hg, up slightly from 130/80 mm Hg yesterday
b. Mild hair thinning
c. Urine output of 15 mL/h for the past 3 hours and muscle twitching
d. A temperature of 37.4 °C

Answer: c — Falling urine output and muscle twitching suggest kidney injury and low calcium, both part of tumour lysis syndrome (section 9.4). This blood pressure (a) is mildly high but not a specific cue. Hair thinning (b) is an expected effect of chemotherapy. A temperature of 37.4 °C (d) is normal.

17. [CORE] A patient with breast cancer and bone metastases has new constipation, increased thirst, frequent urination and confusion. Which problem should the nurse suspect?

a. Hypercalcemia of malignancy
b. Superior vena cava syndrome
c. Febrile neutropenia
d. Extravasation

Answer: a — Constipation, thirst, polyuria and confusion are classic cues of hypercalcemia, which is common with breast cancer and bone metastases (section 9.4). Superior vena cava syndrome (b) causes swelling of the face and arms and dyspnea. Febrile neutropenia (c) needs a fever and low neutrophils. Extravasation (d) is a problem at an IV site.

18. [CORE] A patient with prostate cancer says his mid-back pain has been getting worse for two weeks, wakes him at night and is worse when he coughs. His leg strength is normal today. What is the nurse's best action?

a. Give the ordered analgesic and reassess the pain at the next scheduled round of checks.
b. Encourage him to walk more to loosen his back muscles.
c. Tell him that back pain is common with age.
d. Report the pain promptly as a possible early cue of spinal cord compression.

Answer: d — Progressive back pain that disturbs sleep or worsens with coughing in a person with cancer may be the first cue of spinal metastases, before weakness appears; it needs prompt reporting and urgent assessment (section 9.4). Analgesia (a) is appropriate but does not replace reporting. Walking more (b) could be unsafe if the spine is unstable. Blaming age (c) ignores a serious cue.

19. [CORE] A patient with lung cancer has new facial and neck swelling and is short of breath. Which nursing action is the priority?

a. Lay the patient flat in bed so that the patient can rest comfortably.
b. Help the patient sit up, give oxygen as ordered and escalate.
c. Start an IV in the patient's right arm.
d. Apply cool compresses to the face.

Answer: b — These cues suggest superior vena cava syndrome; symptoms worsen lying flat and the airway can be threatened, so the nurse sits the patient up, gives oxygen as ordered and escalates (section 9.4). Lying flat (a) worsens symptoms. Starting an IV (c) is not the priority while the airway may be at risk. Cool compresses (d) do not treat the obstruction.

20. [CORE] During a peripheral infusion of a vesicant, the patient reports pain and the nurse sees swelling at the site. What should the nurse do first?

a. Remove the IV catheter at once.

b. Slow the infusion rate and observe the site closely for 15 minutes.

c. Stop the infusion and leave the catheter in place.

d. Apply a warm compress to the site.

Answer: c — The first step is to stop the infusion and leave the catheter in place so that drug can be withdrawn through it (section 9.4). Removing the catheter first (a) loses the chance to aspirate. Slowing the infusion (b) lets more vesicant reach the tissue. Warm or cold compresses (d) are used only as the specific drug's protocol directs, and only after the first steps.

21. [CORE] The nurse is preparing to give an IV hazardous drug. Which personal protective equipment does Ontario guidance recommend?

a. Two pairs of chemotherapy-tested gloves and a protective gown

b. One pair of vinyl gloves

c. A surgical mask and eyeglasses only

d. One pair of nitrile gloves and a clean, long-sleeved cloth laboratory coat

Answer: a — For IV administration, Ontario's guideline recommends two pairs of chemotherapy-tested gloves and a low-permeability gown, plus face protection if splashing is possible (section 9.5). Vinyl gloves (b) are not recommended. A mask and eyeglasses (c) do not protect the skin, and glasses do not protect the eyes from splashes. One pair of gloves is not enough for IV administration, and a cloth coat (d) is not a low-permeability gown.

22. [CORE] A patient received IV chemotherapy 12 hours ago. A personal support worker asks how to handle the patient's soiled incontinence brief. What should the nurse tell them?

a. Place it in the regular garbage with bare hands.

b. No special precautions are needed, since they apply only during the infusion itself.

c. Place it in the biomedical waste bin while wearing one pair of disposable gloves.

d. Wear two pairs of gloves and a gown, and place it in the cytotoxic waste container.

Answer: d — For at least 48 hours after a hazardous drug, staff wear two pairs of gloves and a gown to handle body fluids, and soiled briefs go into cytotoxic waste (section 9.5). Regular garbage and bare hands (a) expose staff. Precautions continue after the infusion (b). Biomedical waste (c) is the wrong stream, and one pair of gloves is not enough.

23. [CORE] A patient's Your Symptoms Matter report shows an anxiety score of 8 out of 10, up from 3 last month. What is the nurse's best response?

a. File the report in the chart for the oncologist's next visit.

b. Discuss the score with the patient, assess further and refer if needed.

c. Tell the patient that anxiety is normal with cancer.

d. Ask the patient to complete the tool again next month.

Answer: b — A screening score opens a conversation; a high or rising score calls for further assessment, a shared plan and referral if needed (section 9.6). Filing it (a) or waiting a month (d) leaves the need unmet. Dismissing it as normal (c) ignores real distress.

24. [CORE] A 29-year-old patient newly diagnosed with Hodgkin lymphoma is scheduled to start chemotherapy next week. Which action reflects current guidance on fertility?

a. Plan the fertility discussion for after treatment ends, when the patient is less overwhelmed.

b. Advise the patient that fertility cannot be preserved once a cancer diagnosis is made.

c. Discuss fertility risks and options before treatment and refer promptly if interested or unsure.

d. Wait for the patient to raise the topic, so the discussion respects their privacy and readiness.

Answer: c — ASCO advises counselling about fertility risks at diagnosis and discussing preservation before treatment starts, with prompt referral to a reproductive specialist (section 9.6). Waiting until after treatment (a) may close options. Established methods exist (b). Waiting for the patient (d) means many people are never offered a choice.

25. [CORE] A patient finishing treatment for colorectal cancer asks what a survivorship care plan is for. Which reply is best?

a. "It summarizes your treatment and plans your follow-up, including signs to report and late effects."

b. "It lists the chemotherapy treatments you will need over the coming year."

c. "It is only needed if your cancer comes back and you need more treatment later on."

d. "It replaces your follow-up visits with your health care team, so you won't need to come in."

Answer: a — A survivorship care plan summarizes treatment and lays out follow-up, signs of recurrence, late effects and wellness advice, supporting the transition to primary care (section 9.6). It is not a treatment schedule (b). It is for every survivor, not only after recurrence (c). It guides visits; it does not replace them (d).

26. [CORE] On an Ontario medical unit, an RPN is caring for a patient receiving IV chemotherapy. The RPN notes a temperature of 38.5 °C. Which action best reflects scope and escalation?

a. Wait until the RN returns from break, then decide together what to do next.

b. Recheck the temperature in 4 hours.

c. Start the febrile neutropenia order set alone, without telling anyone on the team.

d. Consult the RN at once and make sure the prescriber is notified without delay.

Answer: d — Every nurse who notices a cue of deterioration acts at once and escalates; the RPN consults the RN as the patient's needs change (section 9.5; Chapter 1, section 1.3). Waiting (a, b) delays antibiotics in a possible emergency. Acting alone without informing the team (c) breaks communication and may exceed the RPN's authority under employer policy.

27. [RN] A patient is on day 2 of induction chemotherapy for acute leukemia. Which laboratory pattern is consistent with tumour lysis syndrome?

a. Low potassium, low phosphate, high calcium, low uric acid

b. Low uric acid, high calcium, low creatinine, low potassium

c. High potassium, high phosphate, high uric acid, low calcium

d. High sodium, high glucose, low potassium

Answer: c — Dying cells release potassium, phosphate and nucleic acids (which form uric acid), and phosphate binds calcium, so calcium falls (section 9.4, Going Deeper). Option a is nearly the reverse. Option b shows none of the expected rises. Option d describes changes unrelated to cell lysis.

28. [RN] Why does calcium fall in tumour lysis syndrome?

a. Released phosphate binds calcium, and the complex deposits in tissues.

b. Uric acid crystals block the absorption of calcium from the gut.

c. Potassium released from dying cells pushes calcium into healthy cells.

d. The kidneys excrete extra calcium in the urine.

Answer: a — High phosphate binds calcium, lowering blood calcium and forming calcium phosphate deposits, including in the kidneys (section 9.4, Going Deeper). Uric acid (b) does not block calcium absorption. Potassium (c) does not move calcium into cells. Kidney injury in TLS lowers excretion; it does not increase calcium loss (d).

29. [RN] Which mechanism best explains acute kidney injury in tumour lysis syndrome?

a. Antibodies made against tumour proteins attack the glomeruli.

b. Low blood calcium constricts the renal arteries and cuts blood flow.

c. High potassium directly destroys the cells of the renal tubules.

d. Uric acid and calcium phosphate crystals block the kidney tubules.

Answer: d — Crystals of uric acid, xanthine and calcium phosphate obstruct the tubules, and reduced renal blood flow and inflammation add to the injury (section 9.4, Going Deeper). TLS is not an antibody process (a). Low calcium (b) is not the main cause of kidney injury. High potassium (c) threatens the heart, not the tubules.

30. [RN] A patient with tumour lysis syndrome has a potassium of 6.4 mmol/L. Which risk is the RN most concerned about?

a. Seizures caused by a low sodium level

b. A life-threatening cardiac dysrhythmia

c. Hyperglycemia from reduced insulin release

d. Respiratory alkalosis from rapid breathing

Answer: b — High potassium makes heart cells unstable and can cause dangerous dysrhythmias and cardiac arrest, so the RN watches the cardiac monitor and reports at once (section 9.4, Going Deeper; Chapter 3, section 3.5). Sodium (a) is not the issue here. Hyperglycemia (c) and respiratory alkalosis (d) are not caused by high potassium.

References

Alberta Health Services. (2014). *Management of febrile neutropenia in adult cancer patients* (Clinical Practice Guideline SUPP-004, Version 3). https://www.albertahealthservices.ca/assets/info/hp/cancer/if-hp-cancer-guide-adult-febrile-neutropenia.pdf

Alberta Health Services. (2017). *Cancer-related fatigue* (Clinical Practice Guideline SUPP-008, Version 1). https://www.albertahealthservices.ca/assets/info/hp/cancer/if-hp-cancer-guide-supp008-fatigue.pdf

Alberta Health Services. (2026). *Radiation dermatitis* (Clinical Practice Guideline SUPP-025, Version 2). https://www.albertahealthservices.ca/assets/info/hp/cancer/if-hp-cancer-guide-supp025-radiation-dermatitis.pdf

Bacchus, C. M., Dunfield, L., Connor Gorber, S., Holmes, N. M., Birtwhistle, R., Dickinson, J. A., Lewin, G., Singh, H., Klarenbach, S., Mai, V., & Tonelli, M. (2016). Recommendations on screening for colorectal cancer in primary care. *CMAJ*, *188*(5), 340–348. https://doi.org/10.1503/cmaj.151125

Brenner, D. R., Gillis, J., Demers, A. A., Ellison, L. F., Ng, C., Zhang, S. X., Finley, C., Fitzgerald, N., Saint-Jacques, N., Shack, L., Turner, D., Urquhart, R., & Woods, R. R. (2026). Projected estimates of cancer in Canada in 2026. *CMAJ*, *198*(14), E526–E534. https://doi.org/10.1503/cmaj.252152

Cairo, M. S., & Bishop, M. (2004). Tumour lysis syndrome: New therapeutic strategies and classification. *British Journal of Haematology, 127*(1), 3–11. https://doi.org/10.1111/j.1365-2141.2004.05094.x

Canadian Association of Nurses in Oncology. (2023). *Standards and competencies for oncology nursing practice in systemic therapy*. https://www.cano-acio.ca/page/Systemic_Therapy

Canadian Cancer Society. (2025a). *7 cancer trends to know in 2025*. https://cancer.ca/en/about-us/stories/2025/7-cancer-trends-to-know-in-2025

Canadian Cancer Society. (2025b). *Life after cancer treatment*. https://cdn.cancer.ca/-/media/files/cancer-information/resources/publications/life-after-cancer/32060-life-after-cancer-treatment-en.pdf

Canadian Cancer Society. (n.d.). *Prevention statistics*. https://cancer.ca/en/research/cancer-statistics/prevention-statistics

Canadian Cancer Statistics Advisory Committee in collaboration with the Canadian Cancer Society, Statistics Canada and the Public Health Agency of Canada. (2025). *Canadian cancer statistics 2025*. Canadian Cancer Society. https://cdn.cancer.ca/-/media/files/research/cancer-statistics/2025-statistics/2025_pdf_final_en.pdf

Canadian Partnership Against Cancer. (2012). *Screening for distress, the 6th vital sign: A guide to implementing best practices in person-centred care*. https://dev.partnershipagainstcancer.ca/wp-content/uploads/2018/12/Screening-Distress-6th-Vital-Sign-EN.pdf

Canadian Partnership Against Cancer. (2019). *Canadian strategy for cancer control 2019–2029: At a glance*. https://www.partnershipagainstcancer.ca/wp-content/uploads/2019/06/Canadian-Strategy-Cancer-Control-2019-2029-At-A-Glance-EN.pdf

Canadian Partnership Against Cancer. (2023, January 17). *Canadian Partnership Against Cancer supports Canada's updated Guidance on Alcohol and Health*. https://www.partnershipagainstcancer.ca/news-events/news/article/ccsa-guidance-on-alcohol-and-health/

Canadian Task Force on Preventive Health Care. (2013). Recommendations on screening for cervical cancer. *CMAJ*, *185*(1), 35–45. https://doi.org/10.1503/cmaj.121505

Canadian Task Force on Preventive Health Care. (2016). Recommendations on screening for lung cancer. *CMAJ*, *188*(6), 425–432. https://doi.org/10.1503/cmaj.151421

Canadian Task Force on Preventive Health Care. (2024). *Breast cancer (update): Draft recommendations* [Archived draft]. https://canadiantaskforce.ca/wp-content/uploads/2024/05/Breast-Cancer-Update-Draft-Recommendations.pdf

Canadian Task Force on Preventive Health Care. (2026). *Canadian Task Force on Preventive Health Care* [Archived website]. https://canadiantaskforce.ca/

Cancer Care Ontario. (2012). *Mucositis in adults with cancer: Screening and assessment and care map*. https://www.cancercareontario.ca/system/files_force/symptoms/CCOOralMucositisAlgorithm.pdf?download=1

Cancer Care Ontario. (2018). *Immune checkpoint inhibitor toxicity management clinical practice guideline*. https://www.cancercareontario.ca/fr/content/immune-checkpoint-inhibitor-toxicity-management-clinical-practice-guideline

Chow, R., Simone, C. B., II, & Rimner, A. (2024). Management of malignant superior vena cava syndrome. *Annals of Palliative Medicine, 13*(3), 620–626. https://doi.org/10.21037/apm-23-573

Easty, A. C., Coakley, N., Cheng, R., Cividino, M., Savage, P., Tozer, R., & White, R. E. (2015). Safe handling of cytotoxics: Guideline recommendations. *Current Oncology*, *22*(1), 27–37. https://doi.org/10.3747/co.21.2151

El-Hajj Fuleihan, G., Clines, G. A., Hu, M. I., Marcocci, C., Murad, M. H., Piggott, T., Van Poznak, C., Wu, J. Y., & Drake, M. T. (2023). Treatment of hypercalcemia of malignancy in adults: An Endocrine Society clinical practice guideline. *The Journal of Clinical Endocrinology & Metabolism, 108*(3), 507–528. https://doi.org/10.1210/clinem/dgac621

Enríquez Enríquez, M. J. (2024). Síndrome de lisis tumoral: Artículo de revisión [Tumor lysis syndrome: Review article]. *Oncología (Ecuador), 34*(2), 68–76. https://doi.org/10.33821/743

Hanahan, D. (2022). Hallmarks of cancer: New dimensions. *Cancer Discovery*, *12*(1), 31–46. https://doi.org/10.1158/2159-8290.CD-21-1059

Hanahan, D., & Weinberg, R. A. (2011). Hallmarks of cancer: The next generation. *Cell*, *144*(5), 646–674. https://doi.org/10.1016/j.cell.2011.02.013

Health Canada. (2026). *Radon: What you need to know*. https://www.canada.ca/en/health-canada/services/environmental-workplace-health/reports-publications/radon-what-you-need-to-know.html

Health PEI. (2025). *Febrile neutropenia in high-risk adults*. https://src.healthpei.ca/sites/src.healthpei.ca/files/Health_PEI_Febrile_Neutropenia_Approved_March_2025.pdf

Herrstedt, J., Celio, L., Hesketh, P. J., Zhang, L., Navari, R., Chan, A., Saito, M., Chow, R., & Aapro, M. (2024). 2023 updated MASCC/ESMO consensus recommendations: Prevention of nausea and vomiting following high-emetic-risk antineoplastic agents. *Supportive Care in Cancer, 32*(1), Article 47. https://doi.org/10.1007/s00520-023-08221-4

Herrstedt, J., Clark-Snow, R., Ruhlmann, C. H., Molassiotis, A., Olver, I., Rapoport, B. L., Aapro, M., Dennis, K., Hesketh, P. J., Navari, R. M., Schwartzberg, L., Affronti, M. L., Garcia-Del-Barrio, M. A., Chan, A., Celio, L., Chow, R., Fleury, M., Gralla, R. J., Giusti, R., … Scotté, F. (2024). 2023 MASCC and ESMO guideline update for the prevention of chemotherapy- and radiotherapy-induced nausea and vomiting. *ESMO Open*, *9*(2), Article 102195. https://doi.org/10.1016/j.esmoop.2023.102195

Idos, G., & Valle, L. (2021). Lynch syndrome. In M. P. Adam, S. Bick, G. M. Mirzaa, et al. (Eds.), *GeneReviews®*. University of Washington, Seattle. https://www.ncbi.nlm.nih.gov/books/NBK1211/

Jamal, S., Jones, C., Walker, J., Mazereeuw, M., Sheppard, A. J., Henry, D., & Marrett, L. D. (2021). Cancer in First Nations people in Ontario, Canada: Incidence and mortality, 1991 to 2010. *Health Reports*, *32*(6). https://doi.org/10.25318/82-003-x202100600002-eng

Kennedy, K., Vu, K., Coakley, N., Daley-Morris, J., Forbes, L., Hartzell, R., Lessels, D., & the Nursing Guideline Development Group. (2022). *Safe handling of hazardous drugs* (PEBC Guideline No. 16-3, Version 3). Ontario Health (Cancer Care Ontario). https://www.cancercareontario.ca/sites/ccocancercare/files/guidelines/full/pebc16-3v3f.pdf

Klarenbach, S., Sims-Jones, N., Lewin, G., Singh, H., Thériault, G., Tonelli, M., Doull, M., Courage, S., Jaramillo Garcia, A., & Thombs, B. D. (2018). Recommendations on screening for breast cancer in women aged 40–74 years who are not at increased risk for breast cancer. *CMAJ*, *190*(49), E1441–E1451. https://doi.org/10.1503/cmaj.180463

Krzyzanowska, M. K., Walker-Dilks, C., Atzema, C., Morris, A., Gupta, R., Halligan, R., Kouroukis, T., & McCann, K. (2016). Approach to fever assessment in ambulatory cancer patients receiving chemotherapy: A clinical practice guideline. *Current Oncology, 23*(4), 280–285. https://doi.org/10.3747/co.23.3098

Loprinzi, C. L., Lacchetti, C., Bleeker, J., Cavaletti, G., Chauhan, C., Hertz, D. L., Kelley, M. R., Lavino, A., Lustberg, M. B., Paice, J. A., Schneider, B. P., Lavoie Smith, E. M., Smith, M. L., Smith, T. J., Wagner-Johnston, N., & Hershman, D. L. (2020). Prevention and management of chemotherapy-induced peripheral neuropathy in survivors of adult cancers: ASCO guideline update. *Journal of Clinical Oncology*, *38*(28), 3325–3348. https://doi.org/10.1200/JCO.20.01399

Mohile, S. G., Dale, W., Somerfield, M. R., Schonberg, M. A., Boyd, C. M., Burhenn, P. S., Canin, B., Cohen, H. J., Holmes, H. M., Hopkins, J. O., Janelsins, M. C., Khorana, A. A., Klepin, H. D., Lichtman, S. M., Mustian, K. M., Tew, W. P., & Hurria, A. (2018). Practical assessment and management of vulnerabilities in older patients receiving chemotherapy: ASCO guideline for geriatric oncology. *Journal of Clinical Oncology*, *36*(22), 2326–2347. https://doi.org/10.1200/JCO.2018.78.8687

National Cancer Institute. (2024). *The genetics of cancer*. https://www.cancer.gov/about-cancer/causes-prevention/genetics

National Cancer Institute. (n.d.-a). *BRCA gene changes: Cancer risk and genetic testing*. https://www.cancer.gov/about-cancer/causes-prevention/genetics/brca-fact-sheet

National Cancer Institute. (n.d.-b). *CAR T cells: Engineering patients' immune cells to treat their cancers*. https://www.cancer.gov/about-cancer/treatment/research/car-t-cells

National Cancer Institute. (n.d.-c). *Chemotherapy to treat cancer*. https://www.cancer.gov/about-cancer/treatment/types/chemotherapy

National Cancer Institute. (n.d.-d). *External beam radiation therapy for cancer*. https://www.cancer.gov/about-cancer/treatment/types/radiation-therapy/external-beam

National Cancer Institute. (n.d.-e). *Hormone therapy to treat cancer*. https://www.cancer.gov/about-cancer/treatment/types/hormone-therapy

National Cancer Institute. (n.d.-f). *Radiation therapy to treat cancer*. https://www.cancer.gov/about-cancer/treatment/types/radiation-therapy

National Cancer Institute. (n.d.-g). *Targeted therapy to treat cancer*. https://www.cancer.gov/about-cancer/treatment/types/targeted-therapies

National Cancer Institute. (n.d.-h). *Tumor markers*. https://www.cancer.gov/about-cancer/diagnosis-staging/diagnosis/tumor-markers-fact-sheet

National Institute for Health and Care Excellence. (2023). *Spinal metastases and metastatic spinal cord compression* (NICE Guideline NG234). https://www.nice.org.uk/guidance/ng234

Ontario Health (Cancer Care Ontario). (n.d.-a). *Cancer screening toolkit*. https://www.cancercareontario.ca/sites/ccocancercare/files/assets/OH-cancer-screening-toolkit-complete-print.pdf

Ontario Health (Cancer Care Ontario). (n.d.-b). *Mouth care during cancer treatment*. https://cancercareontario.ca/sites/ccocancercare/files/assets/CCOMouthCareCancerTreatment.pdf

Ontario Health (Cancer Care Ontario). (n.d.-c). *Systemic cancer treatment administration: Initial and continuing competence standards for registered nurses—Frequently asked questions*. https://www.cancercareontario.ca/system/files_force/derivative/FAQAdminCompetencyStandards.pdf

Ontario Health (Cancer Care Ontario). (n.d.-d). *Your Symptoms Matter – General symptoms*. Retrieved October 25, 2026, from https://cancercareontario.ca/node/33316

Ontario Health. (2024, October 8). *Ontario increases access to breast cancer screening by lowering starting age*. https://www.ontariohealth.ca/news/breast-cancer-screening-lowering-starting-age

Ontario Health. (2025). *Ontario introduces new cervical screening test to better prevent cervical cancer*. https://www.ontariohealth.ca/news/ontario-introduces-new-cervical-screening-test-to-better-prevent-cervical-cancer

Ontario Health. (2026a). *More Ontarians can now access lung cancer screening*. https://ontariohealth.ca/news/lung-cancer-screening-access

Ontario Health. (2026b). *Placemat for cancer survivorship*. https://www.ontariohealth.ca/content/dam/ontariohealth/documents/filter-list/qs/placemat-cancer-survivorship-en.pdf

Ontario Ministry of Health. (2025, March 3). *Bulletin 250203—Ontario Cervical Screening Program update: HPV (human papillomavirus) testing* [OHIP InfoBulletin]. https://www.ontario.ca/document/ohip-infobulletins-2025/bulletin-250203-ontario-cervical-screening-program-update-hpv

Poirier, A. E., Ruan, Y., Volesky, K. D., King, W. D., O'Sullivan, D. E., Gogna, P., Walter, S. D., Villeneuve, P. J., Friedenreich, C. M., & Brenner, D. R. (2019). The current and future burden of cancer attributable to modifiable risk factors in Canada: Summary of results. *Preventive Medicine*, *122*, 140–147. https://doi.org/10.1016/j.ypmed.2019.04.007

Public Health Agency of Canada. (2024). *Summary of NACI statement of July 24, 2024: Updated recommendations on human papillomavirus vaccines*. https://www.canada.ca/en/public-health/services/publications/vaccines-immunization/national-advisory-committee-immunization-summary-updated-recommendations-hpv-vaccines.html

Public Health Agency of Canada. (2026, June 10). *New National Advisory Committee to support preventive health care in Canada* [News release]. https://www.canada.ca/en/public-health/news/2026/06/new-national-advisory-committee-to-support-preventive-health-care-in-canada.html

Schneider, B. J., Naidoo, J., Santomasso, B. D., Lacchetti, C., Adkins, S., Anadkat, M., Atkins, M. B., Brassil, K. J., Caterino, J. M., Chau, I., Davies, M. J., Ernstoff, M. S., Fecher, L., Ghosh, M., Jaiyesimi, I., Mammen, J. S., Naing, A., Nastoupil, L. J., Phillips, T., … Bollin, K. (2021). Management of immune-related adverse events in patients treated with immune checkpoint inhibitor therapy: ASCO guideline update. *Journal of Clinical Oncology*, *39*(36), 4073–4126. https://doi.org/10.1200/JCO.21.01440

Statistics Canada. (2023, January 18). *Health Reports, January 2023* [The Daily]. https://www150.statcan.gc.ca/n1/daily-quotidien/230118/dq230118d-eng.htm

Su, H. I., Lacchetti, C., Letourneau, J., Partridge, A. H., Qamar, R., Quinn, G. P., Reinecke, J., Smith, J. F., Tesch, M., Wallace, W. H., Wang, E. T., & Loren, A. W. (2025). Fertility preservation in people with cancer: ASCO guideline update. *Journal of Clinical Oncology, 43*(12), 1488–1515. https://doi.org/10.1200/JCO-24-02782

Taplitz, R. A., Kennedy, E. B., Bow, E. J., Crews, J., Gleason, C., Hawley, D. K., Langston, A. A., Nastoupil, L. J., Rajotte, M., Rolston, K., Strasfeld, L., & Flowers, C. R. (2018). Outpatient management of fever and neutropenia in adults treated for malignancy: American Society of Clinical Oncology and Infectious Diseases Society of America clinical practice guideline update. *Journal of Clinical Oncology, 36*(14), 1443–1453. https://doi.org/10.1200/JCO.2017.77.6211

Thomas, T., Clark, C., Backler, C., Bohlke, K., Centofanti, D., Jotwani, A. C., Cope, D. G., Dalton, K. A., Gochett, C. G., Henney, V., King, G., Moore, D. C., Dzimitrowicz McManus, H., Anderson, H. M., Moriarty, K. A., DiValerio Gibbs, K., & Morgan, R. L. (2025). ONS/ASCO guideline on the management of antineoplastic extravasation. *Clinical Journal of Oncology Nursing, 29*(5), 384–399. https://doi.org/10.1188/25.CJON.384-399

Union for International Cancer Control. (n.d.). *TNM classification of malignant tumours*. https://www.uicc.org/what-we-do/sharing-knowledge/tnm

Volesky, K. D., El-Zein, M., Franco, E. L., Brenner, D. R., Friedenreich, C. M., Ruan, Y., & ComPARe Study Team. (2019). Cancers attributable to infections in Canada. *Preventive Medicine*, *122*, 109–117. https://doi.org/10.1016/j.ypmed.2019.03.035

Watanabe, S. M., Nekolaichuk, C., Beaumont, C., Johnson, L., Myers, J., & Strasser, F. (2011). A multicenter study comparing two numerical versions of the Edmonton Symptom Assessment System in palliative care patients. *Journal of Pain and Symptom Management, 41*(2), 456–468. https://doi.org/10.1016/j.jpainsymman.2010.04.020

Waterloo Regional Health Network Cancer Centre. (2025). *Key information when starting treatment: Intravenous chemotherapy*. https://www.wrhn.ca/wp-content/uploads/2025/10/2.-PEMWRHNCC0048_IntravenousChemotherapy_AODA_Dec2025_FINAL.pdf

10 Palliative and End-of-Life Care

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain the palliative approach to care and how it differs from specialist palliative care and end-of-life care.
2. Support advance care planning and goals-of-care conversations, applying Ontario law on substitute decision-makers and noting how other provinces differ.
3. Assess and manage common symptoms in serious illness: pain, dyspnea, nausea, constipation, delirium, fatigue and respiratory secretions.
4. Describe Canada's medical assistance in dying law, its eligibility criteria and safeguards, and nurses' roles and rights, including conscientious objection.
5. Recognize the signs that death is approaching and provide comfort care to the patient and family.
6. Provide culturally safe care after death, including coroner notification and tissue and organ donation requirements.
7. Support grieving families and care for one's own wellbeing.
8. Distinguish RN, RPN and NP roles in palliative care and medical assistance in dying using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 3, 5	Clinician; Scholar	Foundations of Practice
2, 4, 8	Advocate; Professional; Communicator	Legal Practice; Ethical Practice
6, 7	Advocate; Collaborator	Ethical Practice; Collaborative Practice

Introduction

For most people, death now comes at the end of a progressive illness, such as cancer, heart failure, chronic lung disease or dementia, rather than suddenly (Murray et al., 2005). The Canadian Institute for Health Information (CIHI) reported that 58% of people who died in 2021–2022 in Ontario, Alberta, British Columbia and Yukon were identified in CIHI's data as receiving palliative care; of those who received some form of palliative care, 61% received it in hospital only (CIHI, 2023). Medical-surgical nurses therefore care for dying patients and their families on every adult unit, not only on palliative care units.

Every nurse gives palliative care: easing breathlessness, asking a family what matters most and making sure a patient's wishes reach the team are all palliative care. Section 10.1 explains palliative care and how it is organized in Canada. Section 10.2 covers advance care planning and goals of care, and section 10.3 the common symptoms of serious illness. Sections 10.4 to 10.6 address medical assistance in dying (MAID), care in the last days and after death, and grief and nurse self-care. Related topics live elsewhere: consent and substitute decision-makers (Chapter 1), pain and opioids (Chapter 5), delirium and dementia (Chapter 8), cancer (Chapter 9), chronic obstructive pulmonary disease (COPD) (Chapter 14) and heart failure (Chapter 18).

10.1 The Palliative Approach

What Palliative Care Is

The World Health Organization (WHO) describes palliative care as an approach that aims to raise the quality of life of patients and their families facing a life-threatening illness. It works by identifying problems early, assessing them carefully and treating pain and other physical, psychosocial and spiritual concerns (WHO, 2020). Health Canada's *Framework on Palliative Care in Canada* adopts

this definition and applies it to people of all ages (Health Canada, 2018). In this book, **palliative care** means care that aims to relieve suffering and improve quality of life for people who have a life-limiting illness and for those close to them.

The patient and family together are the unit of care, and care can begin at diagnosis, alongside treatments meant to control the disease. The Canadian Hospice Palliative Care Association (CHPCA) model places the patient and family at the centre of eight domains of possible suffering: disease management, physical, psychological, social, spiritual, practical, end-of-life care and death management, and loss and grief (CHPCA, 2013). The domains work as an assessment checklist: a patient whose pain is controlled may still be worried about money or struggling with questions of meaning.

End-of-life care is the part of palliative care given when death is expected in the near future. In Canada, "hospice care" and "palliative care" refer to the same thing; **hospice** is often used for care given in the community, and a hospice residence is one setting for care near the end of life (CHPCA, n.d.).

The *Framework* also describes a **palliative approach** to care: the core elements of palliative care are built into everyday care by providers who are not palliative specialists, early in the illness and in every setting. All providers, regulated or not, are expected to have foundational palliative skills, with specialists supporting them as needed (Health Canada, 2018). **Specialist palliative care** is given by interprofessional teams with advanced training, such as consult teams, palliative care units and hospice programs. The medical-surgical nurse provides the palliative approach and asks for a specialist consult when symptoms or distress remain hard to control.

Illness Trajectories

An **illness trajectory** is the usual pattern of a person's function over time as a serious illness progresses. Lynn and Adamson (2003) described three common patterns, and Murray et al. (2005) linked them to palliative care planning:

- **Short period of evident decline (typical of cancer):** Function stays fairly good for a long time, then falls steeply over the final weeks.
- **Long-term limitation with intermittent exacerbations (typical of heart failure and COPD):** Serious flare-ups bring the person to hospital over years, each may leave them weaker, and death can come suddenly during one.
- **Prolonged dwindling (typical of frailty and dementia):** Function declines slowly from a low level, often over many years.

The trajectories matter for timing. In cancer, the decline is fairly predictable but fast, so conversations should not wait for it. In organ failure, any exacerbation might be the last, so goals of care are discussed early and revisited after each admission. In frailty and dementia, the person may lose capacity long before death, so advance care planning happens while they can still share their wishes, and caregivers need support over many years (Lynn & Adamson, 2003). Trajectories give patients and families a broad sense of what lies ahead, which can help them feel more in control (Murray et al., 2005).

Access in Canada

CIHI's 2023 report used data from Ontario, Alberta, British Columbia and Yukon (CIHI, 2023):

- In 2021–2022, 58% of people who died (about 89,000) were identified in CIHI's data as receiving palliative care, up from 52% in 2016–2017 (Ontario and Alberta only).
- Of those, 61% received it in hospital only and 36% received palliative home care. Overall, 13% of all deaths took place at home with the support of palliative home care.
- Half of patients died within 22 days after CIHI's data first identified them as palliative, so identification often comes late.
- People with palliative home care spent fewer days in hospital in their last year (an average of 18 versus 28 days).
- 77% of people with cancer were identified as palliative, while people with dementia were the least likely to receive palliative care in their last year of life (39%); people aged 85 and older were less likely than younger people to receive it.

Palliative needs are often recognized too late, especially in people without cancer. Noticing them earlier is part of the palliative approach.

CANADIAN CONTEXT

A National Framework for Palliative Care

In December 2017, Parliament passed the *Framework on Palliative Care in Canada Act*, which required the federal Minister of Health to develop a national framework in consultation with the provinces, territories and palliative care providers (Health Canada, 2023). The *Framework on Palliative Care in Canada* was tabled on December 4, 2018. Its vision is that everyone in Canada who has a life-limiting illness can live well right up to the end of life, and it sets four priority areas: education and training for providers and caregivers, support for providers and caregivers, research and data, and equitable access (Health Canada, 2018).

The *Action Plan on Palliative Care* (2019) followed, with five goals: public awareness of palliative care and advance care planning; better skills and supports for providers, families and communities; better data and research; better access for underserved populations; and better access to culturally sensitive palliative care in Indigenous communities (Health Canada, 2019).

For nurses, the most direct effects are educational. The *Framework* supports developing mandatory palliative care courses in undergraduate health provider programs and expects every provider to have skills in the palliative approach, and the *Action Plan* called for a national interdisciplinary competency framework (Health Canada, 2018, 2019).

Equity and Culturally Safe Palliative Care

Access to palliative care is not equal, and the causes are mostly structural. CIHI (2023) cites Canadian research suggesting that people of colour and recent immigrants may have poorer access and that many First Nations people lack access to palliative care programs. Because CIHI's data lack details such as race, religion and language, these gaps cannot be fully measured.

First Nations, Inuit and Métis peoples. For many Indigenous Peoples, dying and death are a social and spiritual event honoured collectively, with roles for family, Elders, Knowledge Carriers and healers (Canadian Partnership Against Cancer [CPAC], 2022). Colonization and the residential school system continue to shape health and trust in health care (CPAC, 2022). Receiving care, and dying, at home is a central part of culturally safe end-of-life care, yet high transportation costs and inflexible travel policies can keep many Inuit from being with their families at the end of life (CPAC, 2024). The nurse uses a distinctions-based approach, asks the patient and family what they need, and supports Indigenous-led and community-based care. In Ontario, for example, Indigenous Navigators support and advocate for First Nations, Inuit, Métis and urban Indigenous patients with cancer and their families, including coordinating access to palliative and supportive care and attending to cultural and spiritual needs (Ontario Health, n.d.). Elders and Knowledge Carriers can be involved where available and when the patient wishes (Chapter 2).

Rural and remote communities. Rural palliative patients were more often admitted to hospital mainly for palliative care than urban patients (36% versus 29%) (CIHI, 2023). Early planning for home supports, medications and after-hours crises can help a person stay home if they wish.

People experiencing homelessness. A Canadian study described barriers to end-of-life care for people who are poor or unhoused: the daily struggle to survive, the normalizing of early death, lack of identification, providers' risk concerns and siloed services (Stajduhar et al., 2019). CIHI (2023) found that palliative patients experiencing homelessness were more likely to have longer hospital stays and to wait longer for discharge to a more suitable setting.

2SLGBTQI+ people and chosen family. Many people rely on partners, friends or chosen family. In Ontario, these people can act as substitute decision-makers only if they rank highest in the legal hierarchy or are named in a power of attorney for personal care (Hospice Palliative Care Ontario [HPCO], n.d.). The nurse asks every patient who they consider family and encourages planning that names the right person.

Newcomers and language. Serious news needs a professional interpreter, not a family member (Chapter 1, section 1.7), and the nurse asks how the patient prefers to receive information.

10.2 Advance Care Planning and Goals of Care

Three Different Conversations

Ontario's guidance separates three conversations that are often blurred together (HPCO, n.d.):

- **Advance care planning (ACP):** a voluntary process in which a capable person confirms or chooses their future substitute decision-maker and shares their wishes, values and beliefs about future care. It can happen at any age and in any state of health.
- **Goals of care:** a discussion, when a person is seriously ill, about their current illness, its likely course and what matters most to them, so that treatment options can be matched to their goals. It involves the patient or, if the patient is incapable, the substitute decision-maker, and it often takes more than one conversation.
- **Informed consent:** a decision about a specific treatment, made at the time it is proposed, by the capable patient or, if the patient is incapable of that decision, by the substitute decision-maker.

The distinction matters because, in Ontario, wishes are not consent. Wishes guide the substitute decision-maker but cannot replace a decision by a person; a written form alone is not consent, apart from limited emergencies under the *Health Care Consent Act, 1996* (HPCO, n.d.). Wishes apply only if the person becomes incapable and should be reviewed after any major change in health. Chapter 1, section 1.5, explains capacity, the hierarchy and the emergency exception.

Substitute Decision-Makers and Powers of Attorney

A **substitute decision-maker (SDM)** is the person who makes health care decisions for a patient who is incapable of making a particular decision. In Ontario, a person who wants someone other than the highest-ranked relative to be their SDM prepares a **power of attorney for personal care**, a legal document under the *Substitute Decisions Act, 1992* that names an attorney to make personal care decisions, including health care, if the person becomes incapable (HPCO, n.d.). To make one, the person must be at least 16 years old and mentally capable, and it must be signed in front of two eligible witnesses (Government of Ontario, 2025; Ontario Ministry of the Attorney General, 2020). It is used only while the person is incapable, and for treatment decisions a health practitioner must first find the person incapable of that decision. The term "living will" is not used in Ontario law, although people may write down their wishes, including inside the power of attorney (Ontario Ministry of the Attorney General, 2020).

An SDM does not decide on the basis of their own preferences. They must follow the wishes the person expressed while capable that apply to the situation, unless following them is impossible. If no applicable wish is known, the SDM decides in the person's best interests, considering their values, beliefs and well-being (HPCO, n.d.; Ontario Ministry of the Attorney General, 2020). The **Consent and Capacity Board** is an independent Ontario tribunal that hears disputes about capacity and substitute decisions, including disputes about withdrawing life-sustaining treatment (College of Physicians and Surgeons of Ontario [CPSO], 2023a).

Other provinces and territories use different laws and terms. In Alberta, a **personal directive** names an agent who will make personal decisions that are not financial, and it takes effect only after the person is found to lack capacity (Government of Alberta, 2025). In British Columbia, a representation agreement names a representative, and an advance directive gives health care instructions that providers must follow when they address the care needed (Government of British Columbia, 2025). The nurse learns the law and employer policy where they practise.

Serious Illness Conversations

A **serious illness conversation** is a planned discussion with a seriously ill person about their understanding of the illness, their prognosis, their goals and fears, and the trade-offs they would or would not accept. The Serious Illness Conversation Guide, developed by Ariadne Labs and adopted by the BC Centre for Palliative Care, gives a structure that many Canadian teams use (Ariadne Labs, 2017). In plain terms, the clinician:

- **Sets up the conversation:** explains its purpose and asks permission to talk.
- **Explores understanding:** asks what the person knows about their illness and how much information they want.
- **Shares information:** gives an honest outlook that holds both hope and worry, then pauses to let the person react.
- **Explores what matters:** goals, worries and fears, what gives the person strength, abilities so important that life without them would be unacceptable, trade-offs they would make for more time, and how much their family knows.
- **Closes and documents:** summarizes, recommends a plan that fits the person's priorities, affirms ongoing support, and records the conversation where other providers can find it.

Nurses often hear the first cues: a patient who says "I never want to go back to intensive care" or a daughter who asks "Is he dying?" The nurse responds with curiosity, starts or invites a conversation about values, prepares the patient and family for a team meeting,

sits in to clarify and support, and follows up. In Ontario, physicians are expected to begin goals-of-care discussions for patients with a significant illness who are at risk of deterioration, including explaining prognosis and treatment options (CPSO, 2023b); nurses support that discussion within their scope (Chapter 1, section 1.3). A professional interpreter is used whenever language is a barrier. Cultural safety means asking, not assuming: some patients want every detail, while others prefer that information go through family (Chapter 2). The nurse documents what was discussed, the patient's own words where helpful, and who took part.

Resuscitation Decisions

Cardiopulmonary resuscitation (CPR) is far less successful than many people expect. Only about 12% to 25% of patients who have a cardiac arrest in hospital survive to discharge, even with prompt CPR and defibrillation (Ottawa Hospital Research Institute, 2019). A Canadian-led systematic review and meta-analysis found that active cancer and chronic kidney disease (high-certainty evidence) and age 60 or older (low-certainty evidence) were associated with lower odds of survival (Fernando et al., 2019).

In Ontario, the CPSO policy *Decision-Making for End-of-Life Care* states that a physician may write an order not to provide CPR when they judge that its risk of harm outweighs its potential benefit. Because the decision is not considered a treatment, the patient's or SDM's consent is not required (CPSO, 2023b); the CPSO's companion *Advice to the Profession* links this position to a 2019 Ontario Superior Court decision, *Wawrzyniak v. Livingstone* (CPSO, 2023a). The physician must still consider the patient's wishes and values, tell the patient or SDM that the order will be written, explain the diagnosis, prognosis and reasons, and describe the care that will continue. If the patient or SDM disagrees, the physician may still write the order but must make reasonable efforts to support them, for example by identifying the reason for the disagreement, offering supportive services and, where available, a second opinion or an ethics consultation (CPSO, 2023b). Withdrawing other life-sustaining treatments is handled differently: the CPSO notes that in *Cuthbertson v. Rasouli* (2013), the Supreme Court of Canada affirmed that the Consent and Capacity Board is the appropriate body to decide disagreements between physicians and SDMs about withdrawing such treatment (CPSO, 2023a).

The nurse's role is practical and protective:

- Know each patient's code status at the start of every shift, and confirm that the written order matches what was discussed.
- Clarify at once with the physician or nurse practitioner (NP) when the order is missing, unclear or conflicts with what the patient or family says.
- Explain that a no-CPR order does not mean "no care": assessment, symptom relief and treatments that fit the goals continue.
- Include code status in every handover and transfer.

10.3 Managing Symptoms

Assessing Symptoms

Symptoms are best assessed regularly and systematically, using the patient's own report whenever possible (Hui et al., 2021). The revised Edmonton Symptom Assessment System (ESAS-r), described in Chapter 9, rates common symptoms on a 0 to 10 scale. The Palliative Performance Scale (PPS) is often used alongside it to describe function. When a patient cannot self-report, the nurse uses an observational tool, such as the Pain Assessment in Advanced Dementia (PAINAD) scale for pain (Chapter 5) or the Respiratory Distress Observation Scale for breathlessness (Hui et al., 2021). Skin colour changes such as cyanosis or pallor are harder to see on darker skin, so the nurse also checks the lips, oral mucosa and nail beds and relies on the patient's report and breathing pattern (Chapter 12).

Cicely Saunders, who trained as a nurse, social worker and physician, observed that dying patients' pain often opened onto other kinds of suffering. She called this **total pain**: suffering with physical, psychological, social, emotional and spiritual parts (Clark, 1999). A patient whose pain "won't settle" may also be afraid, grieving or worried about their family. The nurse assesses all these parts and involves social work, spiritual care and other team members.

Pain

Pain is one of the most feared symptoms of serious illness. Its assessment and its treatment with non-opioids, opioids and adjuvant analgesics are covered in Chapter 5. WHO (2020) describes opioids as essential for managing pain and notes that they can also ease

breathlessness. Started at a low dose, adjusted to the patient's response and monitored, opioids are a safe, standard treatment. Patients and families often worry about addiction, about "saving" opioids for later or about opioids hastening death; the Going Deeper box in section 10.5 examines these fears. Whenever an opioid is started, a laxative plan is started too (Chapter 5). The nurse reassesses pain after each dose, reports pain that stays uncontrolled, and remembers that unrelieved pain may also be total pain, needing more than an analgesic.

Dyspnea

Dyspnea is the subjective experience of breathing discomfort. In serious illness it may come from the disease itself (lung tumour, pleural effusion, advanced COPD or heart failure), from a new problem such as pneumonia, anemia or pulmonary embolism, or from anxiety, which both causes and worsens breathlessness. Reversible causes are treated when treatment fits the patient's goals (Hui et al., 2021). Because breathlessness is subjective, the nurse asks the patient to rate it, for example on a 0 to 10 scale, and asks what triggers it and what it stops them from doing; oxygen saturation and respiratory rate alone do not show how distressing it is (Hui et al., 2021).

Non-drug measures come first and continue throughout:

- **Airflow:** A fan directed at the face, specifically the cheek, is recommended by the American Society of Clinical Oncology (ASCO) guideline, based on evidence of intermediate quality (Hui et al., 2021).
- **Position:** Sitting upright or leaning forward on a table.
- **Breathing and relaxation:** Pursed-lip breathing, relaxation and distraction may help, although the evidence is weaker (Hui et al., 2021).
- **Presence:** A calm nurse who stays, speaks slowly and explains each step can ease the fear that feeds breathlessness.

When these are not enough, systemic opioids are the drug class that the ASCO guideline recommends for dyspnea in advanced cancer, with close monitoring (Hui et al., 2021). Oxygen should be available for breathless patients who are hypoxemic (oxygen saturation of 90% or less on room air); when saturation is above 90%, the same guideline does not recommend oxygen, and a fan is offered instead. Benzodiazepines are not first-line treatment for dyspnea; they may be considered for anxiety related to breathlessness when opioids and non-drug measures are not enough (Hui et al., 2021). COPD and heart failure are discussed in Chapters 14 and 18.

Nausea, Vomiting and Constipation

Nausea and vomiting in advanced illness usually have identifiable causes, and several can occur together. Causes can be grouped as chemical or metabolic (drugs such as opioids, hypercalcemia, kidney or liver failure, infection), gastrointestinal (slow gastric emptying, bowel obstruction, constipation), cerebral (raised intracranial pressure, anxiety) and vestibular (nausea triggered by movement) (Cancer Care Ontario, 2010). The prescriber chooses an antiemetic that matches the likely cause; for example, a prokinetic drug for slow gastric emptying or a corticosteroid for raised intracranial pressure (Table 10.1). For persistent nausea, the antiemetic is usually given regularly rather than only as needed, and a second drug acting on a different receptor may be added (Cancer Care Ontario, 2010). Bowel obstruction must be ruled out. Nursing measures include small, frequent, bland meals; cool or room-temperature foods; removing strong smells; fresh air; and mouth care after vomiting (Cancer Care Ontario, 2010).

Constipation is defined largely by the patient's experience, and it can cause pain, nausea, delirium and great distress (Larkin et al., 2008, 2018). Causes include opioids and many other drugs, immobility, weakness, low food and fluid intake, metabolic problems and lack of privacy. Because almost every patient taking an opioid needs a laxative, laxatives are started preventively, usually a softening agent with a stimulant; bulk-forming fibre is generally avoided in frail, seriously ill patients because it can worsen obstruction when fluid intake is low (Larkin et al., 2008). A peripherally acting opioid-receptor antagonist may be used when opioid-induced constipation does not respond to laxatives (Larkin et al., 2018). The nurse assesses bowel patterns every day, offers privacy and a commode rather than a bedpan where possible, and reports no bowel movement for more than 3 days, or as the unit's bowel protocol directs.

Delirium, Fatigue, Anorexia and Cachexia

Delirium is common in serious illness and is covered in Chapter 8. Its causes are sought and treated when that fits the patient's goals. In the last days of life, delirium may be part of dying and not reversible; this **terminal delirium** is managed for comfort and safety, as described in section 10.5. Fatigue is also nearly universal. The nurse looks for treatable contributors, such as anemia, poor sleep, depression or medications, and helps the patient spend limited energy on what matters most to them (Chapter 9 discusses cancer-related fatigue).

Loss of appetite (anorexia) distresses families as much as patients. **Cachexia** is a syndrome of ongoing loss of skeletal muscle, with or without loss of fat, driven by reduced intake and abnormal metabolism; it cannot be fully reversed by usual nutritional support and leads to steadily worsening function (Fearon et al., 2011). An ASCO guideline suggests dietitian counselling, does not recommend routine tube feeding or parenteral nutrition in advanced cancer, and supports a brief trial of a corticosteroid or a progesterone analogue for patients with loss of appetite or weight (Roeland et al., 2020). The nurse offers small portions of preferred foods without pressure and helps families find other ways to show care.

Artificial nutrition and hydration (tube feeding and intravenous or subcutaneous fluids) near the end of life is a medical treatment. Starting, continuing or stopping it is a values-based decision made through goals-of-care discussions and informed consent from the patient or SDM. Thirst and hunger near death are often brief, and mouth care eases dryness (Lam & Lam, 2014).

Respiratory Secretions

In the last hours or days of life, some patients develop **respiratory secretions** that cause a noisy, rattling sound with each breath, often called the "death rattle." It occurs when saliva and secretions pool in the upper airway because the person can no longer swallow or cough effectively; it is reported in about half of dying patients (Moons et al., 2024). In an observational study of 71 dying patients, those with a rattle showed no more signs of respiratory distress than those without it (Campbell & Yarandi, 2013). Families, however, often find the sound very distressing (Moons et al., 2024).

Care focuses on comfort and on the family:

- Reposition the patient on their side, with the head raised slightly, to help secretions drain.
- Give gentle mouth care. Deep suctioning is generally avoided because it can cause discomfort and rarely helps for long.
- Explain to the family that the sound is a natural part of dying and that, based on current evidence, it does not appear to cause the patient distress. Invite them to sit close, hold the person's hand and keep talking to them.
- Watch for true respiratory distress, such as grimacing, restlessness or laboured breathing, and treat it.

Anticholinergic (antisecretory) drugs may be ordered. They seem to work best when started early, and they often do not quiet breathing once the rattle is established (Campbell & Yarandi, 2013; Moons et al., 2024).

Table 10.1 Common symptoms in serious illness: causes, comfort measures and drug classes (Cancer Care Ontario, 2010; Hui et al., 2021; Larkin et al., 2008; Moons et al., 2024; Roeland et al., 2020)

Symptom	Common causes	Comfort measures	Drug classes the team may use
Pain	Tumour growth, bone or nerve involvement, procedures, immobility, constipation; psychological, social and spiritual distress (total pain)	Repositioning, supportive surfaces, relaxation, presence; attention to fears and spiritual needs	Non-opioid analgesics, opioids and adjuvant analgesics (Chapter 5)
Dyspnea	Lung tumour, pleural effusion, advanced COPD or heart failure, pneumonia, anemia, pulmonary embolism, anxiety	Fan directed at the face, upright or forward-leaning position, pursed-lip breathing, relaxation, calm presence	Opioids; oxygen if hypoxemic; a benzodiazepine for related anxiety when other measures fail; treatment of reversible causes
Nausea and vomiting	Opioids and other drugs, hypercalcemia, kidney or liver failure, slow gastric emptying, bowel obstruction, constipation, raised intracranial pressure, anxiety, motion	Small frequent bland meals, cool foods, no strong odours, fresh air, mouth care after vomiting	Chosen by cause: dopamine antagonists (including prokinetics), antihistamines, corticosteroids, serotonin (5-HT3) antagonists, benzodiazepines for anticipatory nausea

Symptom	Common causes	Comfort measures	Drug classes the team may use
Constipation	Opioids and other drugs, immobility, weakness, low intake, metabolic problems, lack of privacy	Daily bowel assessment, privacy, commode rather than bedpan, fluids and activity as tolerated	Softening (osmotic) and stimulant laxatives, often together; rectal measures if needed; peripherally acting opioid-receptor antagonists for opioid-induced constipation that does not respond
Delirium	Drugs, infection, dehydration, metabolic changes, hypoxia, urinary retention, constipation, the dying process	Calm, well-lit room by day, reorientation, family presence, glasses and hearing aids, safety measures (Chapter 8)	Treatment of reversible causes when it fits the goals; antipsychotics for distressing symptoms in selected patients (Chapter 8)
Fatigue	Disease progression, anemia, poor sleep, depression, drugs, cachexia	Energy conservation, rest periods, planning activities that matter most	Treatment of contributing causes, such as anemia or depression (Chapter 9)
Anorexia and cachexia	Tumour-related metabolic change, nausea, mouth problems, taste changes, constipation, low mood	Small portions of preferred foods, no pressure to eat, mouth care, dietitian referral, family teaching	Brief trial of a corticosteroid or a progesterone analogue in some patients with advanced cancer
Respiratory secretions	Saliva and secretions pooling in the upper airway when the person can no longer swallow or cough	Side-lying position, gentle mouth care, explanation and support for the family; deep suctioning generally avoided	Anticholinergic (antisecretory) drugs, which seem to work best when started early

CLINICAL JUDGMENT

Breathless at Night

Names and details are fictional; this is a composite story.

Gerald Bouchard, 78, has advanced COPD and is on a medical unit after his third admission this year. With his wife present, he has agreed with the team on goals of care focused on comfort, and he has a no-CPR order. At 0200, he presses the call bell, sitting slumped low in bed.

- **Recognize cues:** He speaks in three-word phrases, uses his neck muscles to breathe and rates his breathlessness 8 out of 10. His respiratory rate is 30, he is afebrile and his oxygen saturation is within the range ordered for him. He says, "I'm scared I'll suffocate."
- **Analyze cues:** His breathlessness is being worsened by his position and by panic. Nothing points to a new cause such as fever, chest pain or a sudden change in his chest sounds.
- **Prioritize hypotheses:** Relieving distressing dyspnea comes first, while watching for any new, reversible problem.
- **Generate solutions:** Sit him upright and leaning forward, direct a handheld fan at his face, coach pursed-lip breathing and stay with him. Give the as-needed opioid ordered for breathlessness.
- **Take action:** The nurse does all of this, speaking slowly and calmly, and dims the lights.
- **Evaluate outcomes:** After 30 minutes, he rates his breathlessness 4 out of 10, his respiratory rate is 22 and he is easy to rouse. The nurse continues to monitor his sedation and breathing (Chapter 5). If his symptoms had not eased, or if new signs had appeared, the nurse would notify the physician or NP at once; comfort-focused goals do not remove the duty to escalate (Chapter 6). He asks the nurse to call his wife in the morning. The nurse documents the episode and the response and adds a fan to his care plan.

LIFESPAN CONSIDERATIONS

Palliative Care for Older Adults and People Living With Dementia

Older adults, and people with dementia in particular, are less likely to receive palliative care. CIHI found that people aged 85 and older were less likely than younger adults to receive palliative care in their last year of life, and that people with dementia were the least likely to receive palliative care (39%), whereas 77% of people with cancer were identified as palliative (CIHI, 2023). Pain is often missed in people who cannot describe it, so the nurse uses an observational tool such as PAINAD (Chapter 5). Eating difficulties are part of the natural course of advanced dementia. In one large cohort, 85% of people with advanced dementia had them. Choosing Wisely Canada advises against recommending feeding tubes in advanced dementia and suggests offering oral feeding instead; careful hand-feeding appears to be as good as tube feeding for complications and survival (Lam & Lam, 2014).

> These choices are best discussed with the person while they can still take part, and with their SDM well before a crisis admission; in one trial, a video decision aid gave SDMs more knowledge and less distress about feeding choices (Lam & Lam, 2014). Chapter 8 covers dementia, delirium and frailty.

10.4 Medical Assistance in Dying

Medical assistance in dying (MAID) is legal across Canada. Under the Criminal Code, it takes one of two forms, both at the person's request: a physician or NP gives the person a substance that causes death (**clinician-administered MAID**), or a physician or NP prescribes or provides a substance that the person takes themselves (**self-administered MAID**) (College of Nurses of Ontario [CNO], 2025). This book does not describe methods, drugs or doses. This section describes the law as of October 25, 2026. Because the law is changing, the nurse checks the current Criminal Code and CNO guidance before relying on any detail here.

The Law in Canada

In February 2015, the Supreme Court of Canada's decision in *Carter v. Canada* required Parliament to change the Criminal Code's prohibition on assisted dying (Department of Justice Canada, 2026). Bill C-14 received royal assent in June 2016 and placed the rules for MAID in sections 241.1 to 241.4 of the Criminal Code. After a Quebec court ruled in 2019 (*Truchon*) that limiting MAID to people whose natural death was reasonably foreseeable was unconstitutional, Bill C-7, in force in March 2021, removed that limit and created two sets of safeguards (CNO, 2025; Department of Justice Canada, 2026).

Aiding a person to die by suicide remains an offence. Physicians and NPs who provide MAID, and anyone who helps them, are exempt only when they act in accordance with section 241.2 (Criminal Code, 1985, s. 241). Ontario follows the federal eligibility rules and safeguards (Government of Ontario, 2024). Quebec also has its own statute, the *Act respecting end-of-life care* (CQLR, c. S-32.0001), which adds provincial rules.

Eligibility

A person must meet every one of these criteria (Criminal Code, 1985, s. 241.2(1)):

- qualify for publicly funded health services in Canada, or would qualify apart from a minimum period of residence or waiting period;
- be 18 or older and capable of making decisions about their own health;
- have a grievous and irremediable medical condition;
- make a voluntary request that is not the result of outside pressure;
- give informed consent after learning about the ways their suffering could be relieved, including palliative care.

A **grievous and irremediable medical condition** has three parts, all of which must be present: an illness, disease or disability that is serious and incurable; an advanced, irreversible decline in capability; and enduring physical or psychological suffering that the person finds intolerable and that cannot be relieved in a way they consider acceptable (Criminal Code, 1985, s. 241.2(2)). Since 2021, a **reasonably foreseeable natural death** is no longer an eligibility criterion; it decides which safeguards apply. The request and consent must come from the person. A substitute decision-maker cannot request or consent to MAID for someone else (see Chapter 1, section 1.5).

Under section 241.2(2.1), a mental illness does not count as an illness, disease or disability for eligibility, so a person whose mental illness is their only underlying medical condition is not eligible. The exclusion does not cover neurocognitive or neurodevelopmental disorders (Department of Justice Canada, 2026). Bill C-62 (S.C. 2024, c. 1), which received royal assent on February 29, 2024, extended the exclusion until March 17, 2027. On October 7, 2026, Justice Minister Sean Fraser said that the government would not go ahead with the expansion and intends to introduce legislation later in the fall of 2026 to keep the exclusion in place indefinitely (Rana, 2026). As of October 25, 2026, no such bill had been introduced. Students should check the current law, because this part may change soon.

Safeguards

Health Canada's reports call the two pathways **Track 1** (natural death is reasonably foreseeable) and **Track 2** (natural death is not reasonably foreseeable). Both require a written request signed before an independent witness, two independent assessments and the chance to withdraw; Track 2 adds further steps (Table 10.2). The witness must be an adult who understands the request and does not benefit from the death or run the facility. A paid health or personal care worker, including a nurse, may act as witness unless they are assessing or providing MAID (Criminal Code, 1985, s. 241.2(5), (5.1); CNO, 2025).

In Track 2, at least 90 clear days must pass between the start of the first assessment and the day MAID is provided. The period may be shortened only when both assessments are complete and both practitioners consider the person's loss of capacity imminent (Criminal Code, 1985, s. 241.2(3.1)). If neither assessor has expertise in the condition causing the suffering, they must consult someone who does. The person must also be told about counselling, mental health and disability supports, community services and palliative care.

Just before MAID is provided, the person must have the chance to withdraw and must confirm consent. In Track 1 only, a person at risk of losing capacity before the chosen date may arrange in writing for a **waiver of final consent**, often called Audrey's Amendment. The arrangement no longer applies if the person, after losing capacity, shows refusal or resistance through words, sounds or gestures; reflexes and other involuntary movements do not count (Department of Justice Canada, 2026).

Practitioners report MAID requests and assessments under federal monitoring regulations, which since January 1, 2023, also collect data on race, Indigenous identity and disability so that inequality can be studied (Department of Justice Canada, 2026). In Ontario, NPs also report every MAID death to the Office of the Chief Coroner (CNO, 2025).

Table 10.2 MAID eligibility and safeguards: Track 1 and Track 2 compared (Department of Justice Canada, 2026; Criminal Code, 1985)

Element	Track 1: natural death reasonably foreseeable	Track 2: natural death not reasonably foreseeable
Eligibility criteria	Same five criteria for both tracks: government-funded health services; 18 or older and capable; grievous and irremediable condition; voluntary request; informed consent. Mental illness as the sole underlying condition is excluded until March 17, 2027 (check for changes)	Same as Track 1
Written request and witness	Signed and dated request before one independent witness; the person is told they may withdraw at any time	Same as Track 1
Assessments	Two independent physicians or NPs each confirm in writing that the criteria are met	Two independent physicians or NPs; added discussion of means to relieve suffering and agreement that the person has seriously considered them
Minimum assessment period	None (the former 10-day reflection period was removed in 2021)	At least 90 clear days from the start of the first assessment to the day MAID is provided; shorter only if both assessments are complete and loss of capacity is imminent
Expertise consultation	Not required	Required if neither assessor has expertise in the condition causing the suffering
Final consent and waiver	Express consent just before provision; may be waived by written arrangement if loss of capacity is a risk	Express consent just before provision; no waiver
Reporting	Practitioners report under federal monitoring regulations; in Ontario, MAID deaths are reported to the Office of the Chief Coroner	Same as Track 1

MAID in Numbers

Health Canada's *Sixth Annual Report on Medical Assistance in Dying in Canada* describes 2024 (Health Canada, 2025). That year, 16,499 people received MAID, which was 5.1% of all deaths in Canada and 6.9% more than in 2023. Of these, 15,767 (95.6%) were Track 1 and 732 (4.4%) were Track 2. Cancer was the most common underlying condition in Track 1 (63.6%), while neurological

and "other" conditions were cited most often in Track 2. In both tracks, the most commonly reported source of suffering was loss of the ability to take part in meaningful activities. NPs made up 6.8% of the 2,266 practitioners who provided MAID.

Nurses and MAID

Only physicians and NPs may assess eligibility and provide MAID. An NP who provides MAID also reports it and ensures that unused medication is safely disposed of (CNO, 2025). RNs and RPNs may not assess eligibility or give the substance. They may help the physician or NP, for example by inserting an intravenous line when ordered, and they teach, comfort and support the patient and family before, during and after MAID. The Criminal Code protects anyone who helps a physician or NP provide MAID lawfully (Criminal Code, 1985, s. 241(3)).

Counselling a person to die by suicide remains a criminal offence. However, a health care professional who gives information about the lawful provision of MAID commits no offence (Criminal Code, 1985, s. 241(5.1)). Nurses who give information must not encourage or pressure a patient to choose MAID (CNO, 2025). When a patient raises MAID, the nurse listens, explores what lies behind the question, answers factually and tells the NP or physician so that all options, including palliative care, can be offered. In Ontario, the provincial **Care Coordination Service** gives information about MAID and other options at the end of life and accepts self-referrals as well as referrals from clinicians (Government of Ontario, 2024).

No one can be compelled to provide or assist with MAID (Criminal Code, 1985, s. 241.2(9)). A nurse who declines for reasons of conscience is making a **conscientious objection**. CNO (2025) expects the nurse not to share the objection with the patient or express moral judgments, to transfer the patient's care to another nurse or provider (the employer can help find one), and to keep giving all other nursing care until a replacement takes over. The patient is never abandoned. Physicians and NPs who object must refer the patient in a timely manner to another physician or NP who provides MAID (CNO, 2025; Government of Ontario, 2024).

The nurse documents care, teaching and the patient's own words about any request (Chapter 1, section 1.5). The nurse uses neutral terms such as "MAID", avoids language that judges the person's choice and respects every patient and family, whatever they decide. MAID can affect nurses deeply, whatever their views; debriefing and peer support help (section 10.6).

> **SCOPE IN PRACTICE**
>
> **Nurses' Roles in MAID and Pronouncing Death**
>
> CNO's Scope of Practice standard asks every nurse to consider authority, competence and context (Chapter 1, section 1.3).
>
> - **Authority:** The Criminal Code allows only physicians and NPs to assess eligibility and provide MAID. RNs and RPNs may aid them, give information and give care, and may act as an independent witness, but may never give the substance (CNO, 2025).
> - **Competence:** The nurse takes part only in activities they have the knowledge, skill and judgment to do safely, such as intravenous (IV) insertion, family support and teaching.
> - **Context:** Employer policy may narrow these roles, and the law and regulator guidance differ by province and territory.
> - **Conscientious objection:** Hand care over to another nurse or provider (the employer can help), say nothing judgmental, and keep giving other care until a replacement takes over.
> - **Pronouncing death:** In Ontario, no legal requirement bars RNs or RPNs from pronouncing death; the nurse checks the employer's policy on who may do it (CNO, n.d.-a). **Pronouncement of death** is different from certifying death.
> - **Certifying death:** NPs may complete the medical certificate of death in broad circumstances, including in hospitals. Since July 1, 2025, RNs (General Class) may certify certain expected deaths, but not in public hospitals and never after MAID (CNO, n.d.-b). Physicians also certify death.

10.5 The Last Days and Care After Death

In the last days of life, care focuses fully on comfort, dignity and the people at the bedside. This section builds on the goals-of-care conversations in section 10.2 and the symptom management in section 10.3. It describes how the nurse recognizes that death is near, gives comfort care, and acts when death occurs.

Recognizing That Death Is Near

Some signs appear days or weeks before death, and others usually appear only in the last few days. The Registered Nurses' Association of Ontario (RNAO, 2011) lists common signs of imminent death. They include:

- sleeping much of the time, and a lower level of consciousness not explained by another cause;
- progressive weakness and being bedbound;
- difficulty swallowing and taking little food or fluid;
- changes in breathing pattern, including pauses (**apnea**) and **Cheyne-Stokes respiration**, a cycle of deepening and then shallower breaths followed by a pause;
- noisy breathing from secretions in the throat;
- cooling and mottling of the extremities;
- less urine, or darker urine;
- **delirium** with no reversible cause.

In a study of 357 people with advanced cancer in two palliative care units, reduced consciousness, low function and trouble swallowing liquids appeared early but did not predict the timing of death well. Five signs mostly appeared in the final 3 days of life and strongly predicted death within that time: no radial pulse, breathing with movement of the jaw, reduced urine output, Cheyne-Stokes breathing and noisy breathing from secretions, often called the "death rattle" (Hui et al., 2014). Noisy breathing affects about one in three dying people; across studies, death followed its onset after a median of 11 to 28 hours (Lokker et al., 2014).

Mottling is a patchy, lace-like discolouration of the skin caused by poor blood flow, often first seen over the knees. It can be hard to see on darker skin; one study of mottling excluded patients with dark skin because it could not be scored (Bourcier et al., 2017). The nurse does not rely on colour alone: they feel the hands, feet and knees for coolness and compare them with the trunk, look at the nail beds and lips, and ask the family what they have noticed (see Chapter 4, section 4.6).

Restlessness near death has many causes. **Terminal restlessness** is agitation or delirium in the last days that has no reversible cause. Before using that label, the nurse looks for causes that can be treated, such as pain, a full bladder, constipation or a medication effect (see section 10.3 and Chapter 8).

When these signs appear, the nurse tells the physician or NP and the family. The team then reviews orders so that they match the patient's goals.

Comfort Care

Comfort care keeps what helps and stops what does not. With the physician or NP, and as policy and orders allow, the team stops interventions that no longer serve the patient's goals. Examples include routine vital signs, blood tests, repositioning schedules designed to prevent problems in the future rather than to give comfort, and medications that no longer give a benefit. Interventions that relieve symptoms continue (Table 10.3).

- **Mouth care:** Moisten and clean the mouth and lips often; a dry mouth is common when a person breathes through the mouth and takes little fluid.
- **Positioning:** Turn the person for comfort, and place them on their side with the head slightly raised to help secretions drain.
- **Skin and eyes:** Keep skin clean and dry and use pressure-relieving surfaces; moisten dry eyes.
- **Medications:** Give them by a route the person can tolerate. When swallowing fails, the team often uses the **subcutaneous** route, as single doses or a continuous subcutaneous infusion, through a small indwelling needle or catheter.
- **Presence and privacy:** Offer a private room if possible, flexible visiting and a chair or bed for family.
- **Spiritual care:** Ask what matters to the patient and family, offer the chaplain or the family's own spiritual leader, and respect cultural and religious practices (RNAO, 2011; see Chapter 2).
- **Family teaching:** Explain what is happening and what to expect, and check what the family has understood (RNAO, 2011).

No studies have tested suctioning, repositioning or explanation for noisy breathing in the dying person (Lokker et al., 2014). Deep suctioning is invasive and is generally avoided. Gentle suction of the mouth only, repositioning and calm explanation are reasonable

comfort measures.

Table 10.3 Signs that death is approaching and comfort actions (Hui et al., 2014; Lokker et al., 2014; RNAO, 2011)

Sign	What the family may notice	Comfort actions
More sleep, less response	Hard to wake; may not open eyes or speak	Keep talking to the person gently; encourage the family to sit close, hold hands and speak to them
Little or no intake; trouble swallowing	Stops eating and drinking; coughs with sips	Stop oral intake that causes coughing; frequent mouth and lip care; explain that loss of appetite is part of dying
Breathing changes	Pauses in breathing; deep then shallow breaths; jaw moves with each breath	Raise head of bed; explain the pattern to the family; give opioid for distressing breathlessness as ordered
Noisy breathing from secretions	Gurgling or rattling sound with each breath	Turn onto side; gentle mouth suction only; give anticholinergic as ordered; explain that the sound probably does not distress the person
Cool, mottled skin	Hands, feet and knees cool, blotchy or darker; harder to see on dark skin	Light covers; avoid heating pads; check nail beds, lips and limb temperature
Less urine	Little urine; dark urine	Check for a full bladder; keep skin clean and dry; use pads or a catheter if more comfortable
Restlessness or agitation	Picking at covers, moaning, trying to get up	Look for pain or a full bladder; calm, quiet room; familiar voices; medication as ordered; tell the prescriber

MEDICATIONS

Anticipatory Medications at End of Life

Anticipatory medications are drugs ordered in advance, before symptoms arise, so that a dying person can get relief at any hour without waiting for a new order. Professionals believe the practice gives reassurance, controls symptoms and prevents crisis transfers to hospital, but a systematic review found the research evidence for these benefits inadequate (Bowers et al., 2019). They are typically ordered for five common symptoms: pain, breathlessness, nausea and vomiting, agitation, and noisy respiratory secretions (Bowers et al., 2023). The prescriber chooses a drug class for each (see section 10.3):

- an opioid for pain and for breathlessness;
- an antiemetic for nausea and vomiting;
- an antipsychotic, or sometimes a benzodiazepine, for terminal delirium or agitation, as the prescriber decides;
- an anticholinergic (antimuscarinic) for respiratory secretions; evidence that these drugs reduce noisy breathing is weak (Lokker et al., 2014).

Most are given subcutaneously. The nurse:

- assesses the symptom and looks for reversible causes first;
- gives the drug as ordered;
- evaluates and documents the effect;
- tells the prescriber if relief is inadequate;
- teaches the family what each drug is for.

When Death Occurs

When the patient dies, the nurse notes the time of death and follows policy on who pronounces death (see the Scope in Practice box in section 10.4). The nurse informs the physician or NP and the family, if they are not present, using the contact plan agreed on earlier (RNAO, 2011). Family members need time with the person. The nurse offers privacy, a chair and the chance to touch, hold or pray.

Some deaths must be reported to the coroner. In Ontario, these include deaths that occur suddenly and unexpectedly and deaths that appear to result from an accident, suicide or homicide (Government of Ontario, 2026). A coroner may also become involved when there are concerns about the care a person received before death. A death that appears to result from a fall, which is an accident, is

reported even when the patient was receiving palliative care. If a family member raises concerns about the care or treatment the person received, CNO advises nurses not to certify the death, and the threshold for involving the coroner is low (CNO, n.d.-b). The nurse escalates any doubt to the physician or NP and follows hospital policy.

Ontario hospitals designated under the *Gift of Life Act* (1990) must notify Ontario Health (Trillium Gift of Life Network) of patient deaths, and of patients who meet referral indicators before death. For patients who are not on a ventilator, these indicators include a planned discussion about withdrawing or limiting life-sustaining therapy, planned palliation and expected death within an hour. For these patients, notification after death is due within 1 hour. Some patients who cannot donate organs may still be able to donate tissue (Trillium Gift of Life Network, n.d.). Staff do not raise donation with the family before Trillium has checked eligibility and registered consent. If the family asks, the nurse offers to connect them with a donation specialist.

The care of the body follows hospital policy and the wishes of the patient and family. Practices differ widely, so the nurse asks rather than assumes. Some families want to wash or dress the body themselves or with members of their faith community. Some want a spiritual leader present, prayers said, or the body moved quickly so that burial can take place soon. Others want the body left undisturbed for a time. The nurse removes lines and tubes as policy allows; if the death is reportable to the coroner, the nurse checks policy first, because lines and tubes may need to stay in place. The nurse gently closes the eyes and mouth, and labels and documents the body and belongings carefully.

PATIENT EDUCATION

What Families Can Expect in the Last Days

- Your family member will sleep more and may be hard to wake. Keep talking to them gently; your voice and touch can still bring comfort.
- They will eat and drink very little. This is part of dying, not starvation. Small sips or mouth swabs keep the mouth moist.
- Breathing may change. There may be pauses, or deep breaths followed by shallow ones.
- A gurgling sound may come from saliva in the throat. Experts doubt that this sound distresses the dying person (Lokker et al., 2014), but it can upset those who hear it. Turning them onto their side may help.
- Hands and feet may feel cool and change colour. A light blanket is enough.
- They may become restless. Tell the nurse; there are things that help.
- Call the nurse at any time if you are worried. At home, keep the palliative team's 24-hour number close by.
- It is all right to rest, eat and step out. Some people die when their family has left the room for a moment, and that is no one's failure.

GOING DEEPER

Palliative Sedation and the "Double Effect" Myth

Required for RN students; optional for PN students.

Palliative sedation is the closely monitored use of medications to reduce consciousness, in proportion to need, so as to relieve refractory suffering in a person with a life-limiting disease (Surges et al., 2024). Refractory means it cannot be relieved by other means or is intolerable to the patient. Canadian palliative care physicians published a consensus framework for continuous palliative sedation (Dean et al., 2012); the revised European framework stresses these points:

- **Proportionality:** Drugs are titrated to the lowest dose that gives adequate relief, and lighter or intermittent sedation comes first where possible.
- **Monitoring:** Comfort and sedation are assessed with tools such as the Richmond Agitation-Sedation Scale–Palliative version, and the rationale and planned depth are documented.
- **Aim:** To ease suffering that nothing else relieves, never to end life sooner. This sets it apart from MAID, which ends life at a capable person's request.

Many people believe that end-of-life opioids or sedation hasten death. A systematic review found that palliative sedation, when properly indicated and used, was not associated with shorter survival (Maltoni et al., 2012). A review of opioids given to control symptoms in advanced cancer and the last days of life likewise found no link with survival (López-Saca et al., 2013). No randomized trials exist, so this evidence has limits.

The **principle of double effect** holds that an act aimed at a good effect can be acceptable despite a foreseen but unintended harmful effect. The harm must not be the means to the good, and the act must be proportionate. Some authors argue that the

> principle does not fit palliative sedation, because properly used sedation has not been shown to hasten death and intentions are often mixed (Faris et al., 2021; Maltoni et al., 2012). Fear of hastening death should not stop a nurse from giving ordered symptom relief.

10.6 Grief and Caring for Ourselves

Death ends one person's life and changes many others. Families grieve, and so do nurses. This section describes grief and bereavement, and how nurses care for themselves and one another.

Grief and Bereavement

Grief is the emotional, physical and spiritual response to loss. **Bereavement** is the state of having lost someone through death. **Anticipatory grief** begins before the death, as the patient and family face losses that are coming: abilities, roles, plans and, finally, life. Families may feel sadness, guilt, relief and exhaustion all at once. The nurse acknowledges these feelings as normal.

Grief usually brings intense sadness, longing, disturbed sleep and trouble concentrating for a time, and it eases gradually. Typical grief is not a disorder, and most people's grief lessens without treatment (American Psychiatric Association [APA], n.d.). In 2022, the APA added **prolonged grief disorder** to the *Diagnostic and Statistical Manual of Mental Disorders*, fifth edition, text revision (DSM-5-TR). It describes grief that stays intense and disabling long after a death: at least 12 months for adults (6 months for children and adolescents). Along with intense longing for, or preoccupation with, the person who died, the person has at least three of these symptoms nearly every day for at least the last month:

- a sense that part of themselves has died;
- strong disbelief about the death;
- avoiding reminders that the person has died;
- intense emotional pain;
- difficulty re-engaging with people and activities;
- emotional numbness;
- a sense that life is meaningless;
- intense loneliness.

The grief causes significant distress or impairment and lasts longer than the person's cultural, religious or social norms would lead others to expect. An estimated 4% to 15% of adults who are bereaved have persistent symptoms (APA, n.d.). Grief-focused psychotherapy can help. The nurse does not diagnose the disorder but can recognize grief that is not easing and suggest the person speak with their primary care provider.

Grief is expressed in many ways. Mourning rituals, the expression of emotion and beliefs about what happens after death vary across cultures, faiths and families, and suffering takes its meaning from these traditions (RNAO, 2011; see Chapter 2). Some families grieve openly and loudly; others grieve quietly or in private. Neither pattern shows more or less love, and the nurse asks rather than assumes.

At the bedside, the nurse supports families by explaining what is happening, inviting them to take part in care if they wish, and allowing time after the death. Before the family leaves, the nurse gives practical information on next steps and on bereavement resources, such as hospital or hospice bereavement programs and the Canadian Virtual Hospice (virtualhospice.ca).

Nurses' Wellbeing

Caring for dying patients is meaningful work, and it is also demanding. Nurses grieve patients they have known, especially after long admissions, sudden deaths or deaths that did not go as hoped. A death at work can also stir up a nurse's own past losses. RNAO (2011) encourages nurses to reflect on their own attitudes and feelings about death, because this self-awareness supports both their care and their own coping.

Moral distress was first described as knowing the right thing to do while institutional constraints make acting on it nearly impossible (Jameton, as cited in Morley et al., 2020). Researchers now describe it more broadly. It is psychological distress, such as anger, frustration, guilt or powerlessness, caused by a moral event: a constraint, a conflict, a dilemma, uncertainty or tension (Morley et al., 2020). In end-of-life care, it can arise when treatment seems to prolong suffering, when symptoms are poorly controlled, or when staffing prevents a nurse from being present. Unaddressed, it is linked to withdrawal from patients and to nurses leaving their jobs or the profession (Morley et al., 2020).

Compassion fatigue describes the emotions and behaviours that can result from repeatedly learning about, and caring for, other people's suffering and trauma. It overlaps with burnout and secondary traumatic stress. Heavy workloads, low resilience and long, intense stress raise the risk. Supportive colleagues, adequate staffing and a positive practice environment lower it (Noor et al., 2025).

RNAO (2011) recommends that nurses' education include self-care and coping strategies and reflection on death and dying, and that organizations recognize nurses' wellbeing as a critical part of quality end-of-life care. Helpful supports include:

- a brief team debrief or pause after a death;
- peer support and mentorship;
- the employer's employee and family assistance program;
- spiritual care staff;
- clear ethics consultation for moral questions;
- sleep, rest, exercise and time away from work.

A nurse who notices lasting sadness, numbness, irritability or dread about going to work is encouraged to speak with a manager, colleague or health professional.

> PRACTICE STORY
>
> **"We Sat With Her"**
>
> *Names and details are fictional; this is a composite story.*
>
> Nurse: Priya Raman, RN. Years in practice: 6. Setting: medical unit, community hospital, Ontario.
>
> Mrs. Halina Sobczak was 91, and her goals were comfort only. At 0200 her breathing became wet and noisy, and she began pulling at her blanket and calling out in Polish. Her only son lived in Calgary.
>
> I checked her first: no full bladder, no grimace when I moved her, a mouth that was very dry. I turned her onto her side, cleaned her mouth and gave the anticholinergic and the antipsychotic from her anticipatory orders. I paged the NP to say that she was now actively dying and that her son needed to know.
>
> Martin, the RPN on my team, stayed with her while I called her son. He asked if he could see her. Our unit had a tablet for video calls, and I booked a Polish interpreter by phone so that he could understand everything I said and ask his own questions. On the screen he said goodbye to her in Polish. Her hand moved on the sheet when she heard his voice. Afterward, he asked for one thing: that a rosary from her bag be placed in her hands and that someone pray with her. Martin found the rosary. The night chaplain came and prayed with her, and the interpreter stayed on the line so that her son could pray too.
>
> By 0400 she was calm and quiet. Martin and I took turns sitting with her between our other patients. She died at 0520 with my hand on her shoulder. I phoned her son, and the interpreter helped us through that call.
>
> Driving home, I cried. I had only known her for one night. At our huddle the next evening, our manager asked how the night had gone, and Martin said, "We sat with her." It helped to say it out loud.
>
> Reflect: How did the RN and the RPN share this patient's care, and which tasks fell within each nurse's scope? What supports would help you after a night like this?

Chapter 10 Summary

Introduction

- For most people in Canada, death follows a progressive illness, and many receive palliative care in hospital only (CIHI, 2023).
- Every nurse gives palliative care; this chapter covers the palliative approach, planning, symptoms, MAID, the last days and grief.

10.1 The Palliative Approach

- Palliative care relieves physical, psychological, social and spiritual suffering for patients and families, from diagnosis onward, not only at the end of life.
- The palliative approach builds palliative principles into everyday care by all providers, with specialists for complex needs.
- Three illness trajectories (cancer, organ failure, frailty and dementia) guide when to start and revisit conversations.
- CIHI found that 58% of people who died in 2021–2022 in four jurisdictions were identified as receiving palliative care, often late and, for most, in hospital only; people with dementia and those aged 85 and older were less likely to receive it.
- Equitable care is distinctions-based for First Nations, Inuit and Métis peoples and attends to rural residents, people experiencing homelessness, chosen family and language.

10.2 Advance Care Planning and Goals of Care

- In Ontario, advance care planning, goals-of-care discussions and informed consent are separate conversations; wishes are not consent.
- SDMs follow applicable wishes the person expressed while capable, otherwise the person's best interests; a power of attorney for personal care names a chosen SDM.
- Other provinces use instruments such as Alberta's personal directive and British Columbia's advance directive and representation agreement.
- Nurses notice cues, start and support serious illness conversations, use professional interpreters and document what matters to the patient.
- Under CPSO policy, a no-CPR order does not require consent, but the physician must inform, explain and support; the nurse confirms and clarifies code status.

10.3 Managing Symptoms

- Symptoms are assessed regularly with self-report tools such as ESAS-r, or observational tools when the patient cannot report, and with attention to total pain.
- For dyspnea, a fan to the face, positioning, breathing techniques and calm presence come first; opioids are the main drug class, and oxygen is for hypoxemia.
- Antiemetics are matched to the cause of nausea, and laxatives are started whenever an opioid is started.
- Cachexia cannot be fully reversed by feeding; artificial nutrition and hydration is a values-based treatment decision.
- Noisy respiratory secretions near death do not appear to distress the patient; repositioning, mouth care and family explanation are the core of care.

10.4 Medical Assistance in Dying

- MAID is legal across Canada under the Criminal Code (Bill C-14, 2016; Bill C-7, 2021). It may be clinician-administered or self-administered, and only physicians and NPs may assess and provide it.
- Eligibility: government-funded health services; 18 or older and capable; a grievous and irremediable condition; a voluntary request; and informed consent. Mental illness as the sole underlying condition is excluded until March 17, 2027, and the government announced on October 7, 2026, that it intends to extend the exclusion indefinitely. Check the current law.
- Track 1 (natural death reasonably foreseeable) and Track 2 (not reasonably foreseeable) both need a witnessed written request and two independent assessments. Track 2 adds expert consultation when needed, discussion of other means of relief and at least 90 clear days. Final consent may be waived only in Track 1.
- In 2024, MAID was provided to 16,499 people (5.1% of deaths in Canada); 4.4% were Track 2.
- RNs and RPNs may aid, inform and care, but never counsel or encourage MAID or give the substance. Nurses who object transfer care through the employer without abandoning the patient. Ontario's Care Coordination Service accepts self-referrals.

10.5 The Last Days and Care After Death

- Signs that death is near include more sleep, little intake, breathing pauses, noisy secretions, cool mottled skin, less urine and restlessness. Reduced urine output, Cheyne-Stokes breathing and noisy breathing strongly suggest death within about 3 days.
- Mottling is hard to see on darker skin, so check temperature, nail beds and lips as well.
- Comfort care stops interventions that no longer help and focuses on mouth care, positioning, subcutaneous medications, presence and teaching. Anticipatory medications are ordered in advance so that relief can be given at any hour.
- In Ontario, reportable deaths (for example, sudden, unexpected or accidental deaths) go to the coroner, and designated hospitals notify Trillium Gift of Life Network of deaths and of referral indicators. Ask the family about cultural and religious practices for care of the body.
- Palliative sedation is proportional and monitored, and it differs from MAID. Properly used opioids and sedation have not been shown to shorten life (Going Deeper).

10.6 Grief and Caring for Ourselves

- Anticipatory grief begins before death. Typical grief is not a disorder, and its expression varies across cultures and families.
- Prolonged grief disorder (DSM-5-TR) is disabling grief lasting at least 12 months in adults and exceeding cultural norms.
- Nurses experience grief, moral distress and compassion fatigue. Debriefing, peer support, employee assistance and self-care help, and organizations share responsibility for nurses' wellbeing.

Key Terms (43)

advance care planning (ACP): A voluntary process in which a capable person confirms or chooses a substitute decision-maker and shares wishes, values and beliefs about future care; in Ontario it is not consent.

anticipatory grief: Grief that begins before a death, as the patient and family face coming losses.

anticipatory medications: Drugs ordered in advance for expected end-of-life symptoms so that relief can be given at any hour.

apnea: A pause in breathing.

artificial nutrition and hydration: Nutrition and fluids given by tube or by the intravenous or subcutaneous route; a medical treatment that requires a values-based decision and consent.

bereavement: The state of having lost someone through death.

cachexia: A syndrome of continuing skeletal muscle loss (with or without loss of fat) that usual nutritional support cannot fully reverse and that steadily worsens function.

Care Coordination Service: Ontario's provincial service that gives information about MAID and other options at the end of life and connects people, including those who refer themselves, with physicians and NPs who provide MAID.

Cheyne-Stokes respiration: A cyclic breathing pattern of deepening and then shallower breaths followed by a pause.

clinician-administered MAID: The form of MAID in which a physician or NP gives the substance.

compassion fatigue: The emotions and behaviours that can result from repeatedly learning about, and caring for, other people's suffering and trauma.

conscientious objection: A health professional's refusal, for reasons of conscience or religion, to take part in a lawful service such as MAID; nurses must transfer care without abandoning the patient.

Consent and Capacity Board: An independent Ontario tribunal that hears disputes about capacity findings, substitute decision-making and withdrawal of life-sustaining treatment.

dyspnea: The subjective experience of breathing discomfort.

end-of-life care: The part of palliative care given when death is expected in the near future, focused on comfort, dignity and family support.

goals of care: A discussion during a serious illness about the illness, its likely course and what matters most to the person, used to match treatment options to the person's goals.

grief: The emotional, physical and spiritual response to loss.

grievous and irremediable medical condition: An illness, disease or disability that is serious and incurable, with an advanced, irreversible decline in capability and enduring, intolerable suffering that cannot be relieved under conditions the person considers acceptable.

hospice: In Canada, a term used interchangeably with palliative care and often applied to community-based care; a hospice residence is one setting for care near the end of life.

illness trajectory: The typical pattern of a person's function over time as a serious illness progresses, such as the patterns seen in cancer, organ failure and frailty or dementia.

medical assistance in dying (MAID): Under the Criminal Code, a physician or NP either giving a person, at their request, a substance that causes death, or prescribing or providing one that the person takes themselves.

moral distress: Psychological distress, such as guilt, anger or powerlessness, caused by a moral event such as a constraint, conflict, dilemma or uncertainty.

mottling: Patchy, lace-like discolouration of the skin caused by poor perfusion, often seen first around the knees; hard to see on darker skin.

palliative approach: The integration of core palliative care principles into everyday care by all providers, early in a serious illness and in every setting, with specialists supporting complex needs.

palliative care: Care that aims to prevent and relieve suffering and improve quality of life for people who have a life-limiting illness and for those close to them, from diagnosis onward.

palliative sedation: The closely monitored use of medications to reduce consciousness, in proportion to need, so as to relieve refractory suffering in a person with a life-limiting disease.

personal directive: In Alberta, a legal document naming an agent who will make personal decisions that are not financial; it takes effect only after the person is found to lack capacity.

power of attorney for personal care: In Ontario, a legal document under the Substitute Decisions Act, 1992 that names an attorney to make personal care decisions, including health care, if the person becomes incapable.

principle of double effect: The ethical principle that an act aimed at a good effect may be acceptable even if a harmful effect is foreseen but not intended, provided the harm is not how the good is achieved and the act is proportionate.

prolonged grief disorder: A DSM-5-TR diagnosis of intense, disabling grief lasting at least 12 months after a death in adults (6 months in children and adolescents) and exceeding cultural norms.

pronouncement of death: Determining and recording that a person has died; distinct from certifying the cause of death on the medical certificate of death.

reasonably foreseeable natural death: The test that decides which set of MAID safeguards applies; it is no longer an eligibility criterion.

respiratory secretions: Saliva and secretions that pool in the upper airway near death, causing noisy breathing (the "death rattle") when the person can no longer swallow or cough effectively.

self-administered MAID: The form of MAID in which the person takes a substance prescribed or provided by a physician or NP.

serious illness conversation: A structured discussion with a seriously ill person about understanding, prognosis, goals, fears, sources of strength and acceptable trade-offs, used to guide future care.

specialist palliative care: Care given by interprofessional teams with advanced palliative training, usually for patients with complex needs.

substitute decision-maker (SDM): The person who makes health care decisions for a patient who is incapable of making a particular decision.

terminal delirium: Delirium in the last days of life that is part of the dying process and usually not reversible; care focuses on comfort and safety.

terminal restlessness: Agitation or delirium in the last days of life that has no reversible cause.

total pain: Cicely Saunders's concept of suffering with physical, psychological, social, emotional and spiritual parts.

Track 1: The MAID pathway for a person whose natural death is reasonably foreseeable.

Track 2: The MAID pathway for a person whose natural death is not reasonably foreseeable; it adds consultation with an expert when neither assessor has expertise in the condition, discussion of other means of relief and at least 90 clear days from the first assessment to provision.

waiver of final consent: A written arrangement, available only in Track 1, that allows MAID to proceed on a set date if the person loses capacity, unless they refuse or resist by words, sounds or gestures; also called Audrey's Amendment.

Licensure Review & Clinical Judgment Questions (30)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Tomas Reyes (Questions 1–4): Tomas Reyes, 84, has advanced heart failure and lives alone in Kingston, Ontario. He was admitted to a medical unit 5 days ago and has become drowsy and confused; the physician has found him incapable of making treatment decisions. Two years ago, Mr. Reyes made a power of attorney for personal care naming his niece, Lena, as his attorney. He also has a son who lives in another province. The team has arranged a goals-of-care meeting with Lena.

1. [CORE] The physician proposes inserting a feeding tube for Mr. Reyes. From whom must the team obtain consent?

a. Mr. Reyes's son, because he is Mr. Reyes's closest living relative

b. No one, because Mr. Reyes wrote down his wishes when he was capable

c. Lena, because she is named as his attorney for personal care

d. The physician, who may decide in an incapable patient's best interests

Answer: c — In Ontario, consent for a treatment proposed for an incapable patient comes from the substitute decision-maker at the time of the decision, and a person named in a power of attorney for personal care ranks above relatives (section 10.2; Chapter 1, section 1.5). The son (a) ranks below the named attorney. Written wishes (b) guide the SDM but are not consent. The physician (d) proposes treatment but does not consent on the patient's behalf outside the limited emergency exception.

2. [CORE] At the meeting, Lena says, "I can't lose him. I want everything done, even a breathing machine." Last year Mr. Reyes told her he would not want to be kept alive on machines if he could no longer recognize his family. Which response by the nurse is most appropriate?

a. "This is hard. What do you think your uncle would want, based on what he told you when he was well?"

b. "As his attorney, you should decide based on what feels right to you as his closest family member."

c. "Because he told you his wishes, the team will make the decision and you will not have to choose."

d. "Perhaps his son should make this decision, since you are finding it too difficult to decide."

Answer: a — An SDM must follow wishes the person expressed while capable that apply to the situation, and decide in the person's best interests only when no applicable wish is known (section 10.2). Acknowledging her distress and asking what he would want guides Lena toward that duty (a). Her own preferences (b) are not the standard. The team does not take over the decision (c); wishes guide the SDM, who still gives or refuses consent. The son (d) does not replace the named attorney simply because the decision is difficult.

3. [CORE] Which action best reflects the nurse's role in Mr. Reyes's goals-of-care meeting?

a. Telling Lena how many weeks Mr. Reyes is likely to live before the physician joins the meeting

b. Asking Lena to sign a form agreeing to the no-CPR order so the team has her consent

c. Leaving the meeting to the physician because goals-of-care discussions are outside nursing practice

d. Sharing what the nurse has observed, checking Lena's understanding and exploring Mr. Reyes's values with her

Answer: d — Nurses support goals-of-care discussions by contributing observations, clarifying understanding, exploring values and following up (section 10.2). Prognosis and treatment options are explained by the physician or NP, so the nurse does not give a time estimate alone (a). Under the CPSO policy, a no-CPR order does not require consent, although the physician must inform and discuss it, so a consent form is not the nurse's task (b). Nurses have a central role in these conversations, so stepping away (c) is not appropriate.

4. [CORE] After the meeting, the physician's progress note says that a no-CPR order was discussed with Lena, but there is no order in the chart, and the unit board lists Mr. Reyes as "full code." What should the nurse do first?

a. Change the board to "no CPR," because the progress note documents the discussion

b. Contact the physician now to clarify and confirm the code status order

c. Wait until morning rounds to raise it, because Mr. Reyes is stable at the moment

d. Ask Lena to put Mr. Reyes's wishes about resuscitation in writing so the nurse can update the board

Answer: b — A missing or conflicting code-status order must be clarified at once with the physician or NP (b); the nurse then documents the clarification and includes code status in handover (section 10.2). The nurse cannot act on a progress note in place of an order (a). Waiting (c) leaves a mismatch that could lead to the wrong response in an arrest. A written statement from the SDM (d) is not an order and does not resolve the conflict.

5. [CORE] A patient with advanced lung cancer is short of breath at rest. Her oxygen saturation is 95% on room air. Which non-drug measures should the nurse include in her care? Select all that apply.

a. Direct a handheld fan toward her face.

b. Start oxygen at a high flow rate to relieve her breathlessness.

c. Help her sit upright, leaning forward on an over-bed table.

d. Coach her in pursed-lip breathing and relaxation.

e. Stay with her and speak in a calm, slow voice.

f. Lower the head of the bed so that she can rest flat.

g. Keep the room door closed and turn up the heat.

Answer: a, c, d, e — Airflow from a fan to the face, an upright or forward-leaning position, breathing and relaxation techniques and a calm presence are recommended comfort measures for dyspnea (section 10.3). Oxygen (b) is not recommended for breathlessness when saturation is above 90% on room air, and oxygen is a drug, not a non-drug measure. Lying flat (f) usually worsens breathlessness. A warm, closed room (g) reduces airflow and often worsens the sensation.

6. [CORE] Which statement best describes the palliative approach to care?

a. Transferring a patient to a palliative care unit once curative treatment has stopped

b. Building palliative care principles into everyday care by all providers, early in a serious illness

c. Caring for a patient during the last days of life, when death is expected within hours to days

d. Referring every patient with a life-limiting illness to a specialist palliative care team at diagnosis

Answer: b — The palliative approach brings the core elements of palliative care into care given by all providers, early and in every setting, with specialists supporting them as needed (section 10.1). Waiting until curative treatment stops (a) delays care the patient could already benefit from. Care in the last days (c) describes end-of-life care, only one part of palliative care. Referring everyone to specialists (d) is neither necessary nor possible; generalists provide most of the palliative approach.

7. [CORE] A patient with severe COPD has just been discharged after his third hospital admission this year. He has not talked with anyone about his future care. Based on his likely illness trajectory, which plan is most appropriate?

a. Delay advance care planning until his function declines steadily, because the timing of death in COPD is predictable.

b. Wait until he loses the capacity to make decisions, then hold a goals-of-care meeting with his family.

c. Focus on goals-of-care discussions only if he is diagnosed with lung cancer, because COPD is not a life-limiting illness.

d. Start advance care planning now and revisit it after each exacerbation, because any flare-up could be life-threatening.

Answer: d — Organ failure such as COPD typically follows long-term limitation with intermittent exacerbations, and death can come suddenly during one of them, so planning starts early and is revisited after each admission (section 10.1). The timing of death in COPD is hard to predict (a). Waiting until he loses capacity (b) removes his own voice from the planning. Advanced COPD is a life-limiting illness that warrants a palliative approach (c).

8. [CORE] A patient with advanced heart failure has an order for a low-dose opioid as needed for breathlessness. His daughter says, "I don't want him to have morphine. I'm afraid he'll get addicted, or that it will kill him." Which response by the nurse is best?

a. "Many families worry about that. With a low starting dose and careful monitoring, it is a safe, standard treatment. What worries you most?"

b. "There is no chance of any side effects at the low dose he has been ordered, so you do not need to worry about it."

c. "We will save the morphine until he is very close to death, because that is when it will help him the most."

d. "If you are worried, I will stop the morphine order right away, and we will use oxygen for his breathing instead."

Answer: a — The nurse acknowledges the fear, explains that low-dose opioids adjusted to the response and monitored are a safe, standard treatment for dyspnea, and invites further discussion (section 10.3). Claiming no side effects (b) is false; opioids cause effects such as constipation and need monitoring. Saving opioids for the end (c) leaves him breathless now and feeds a common myth. The nurse cannot cancel an order (d), and oxygen helps only if he is hypoxemic.

9. [CORE] An RPN in Ontario is caring for a patient with advanced cancer whose goals of care focus on comfort. The patient has been settled for 2 days. Now the patient has a new fever, a respiratory rate of 32 and sudden pain in one leg, and the family is upset. What is the RPN's best action?

a. Continue the current plan, because comfort-focused goals mean new findings do not need to be reported

b. Ask the family to decide whether the changes should be reported to the physician

c. Provide immediate comfort, consult the RN about the change in condition and notify the physician or NP according to policy

d. Transfer care of the patient to another RPN, because a palliative patient whose condition changes is outside RPN scope

Answer: c — Every nurse who notices a change acts at once and escalates, and the RPN consults the RN when a patient's needs change; employer policy sets how the physician or NP is notified (section 10.3; Chapter 1, section 1.3). Comfort-focused goals (a) do not remove the duty to report new findings, which may have a treatable or symptom-relieving response. The decision to report (b) belongs to the nurse, not the family. Caring for palliative patients is within RPN practice (d); what changes is the need to consult the RN as the patient's needs change.

Case: Mrs. Evelyn Baptiste (Questions 10–15): Mrs. Evelyn Baptiste, 88, has advanced lung cancer and is on a medical unit. Her goals of care are comfort only, and there is a do-not-resuscitate order. Anticipatory subcutaneous orders include an opioid, an antipsychotic and an anticholinergic, as needed. At 0300 her breathing is noisy and gurgling, with pauses of up to 20 seconds. She is moaning, picking at her sheets and trying to climb out of bed. She has taken nothing by mouth for 2 days and has not voided for 9 hours. Her feet and knees are cool. Her daughter, at the bedside, is crying and says, "She's choking. Please do something."

10. [CORE] Which findings are cues that Mrs. Baptiste may be in the last hours to days of life? Select all that apply.

a. Pauses in breathing of up to 20 seconds

b. Her daughter crying at the bedside

c. Cool feet and knees

d. No oral intake for 2 days

e. Noisy, gurgling breathing

f. A do-not-resuscitate order on the chart

Answer: a, c, d, e — Apnea, cool extremities, very low intake and noisy breathing from secretions are common signs that death is near (section 10.5; Table 10.3). The daughter's distress (b) is an important cue for family support, but it is not a sign of the patient's dying. A do-not-resuscitate order (f) reflects a decision about care, not a physical sign.

11. [CORE] The nurse analyzes Mrs. Baptiste's restlessness. Which finding most needs follow-up before the restlessness is attributed to the dying process?

a. Her age of 88 years

b. Pauses in her breathing

c. No urine output for 9 hours

d. Her lung cancer diagnosis

Answer: c — Terminal restlessness is a label used only after reversible causes are ruled out; a full bladder from urinary retention is a common, treatable cause of agitation (section 10.5). Less urine is also expected near death, but the nurse checks the bladder before deciding. Age (a) and diagnosis (d) do not explain new agitation. Breathing pauses (b) are a sign of dying, not a cause of restlessness.

12. [CORE] The nurse finds no distended bladder. Which concern has the highest priority now?

a. Distress from agitation that may include pain

b. Dehydration needing intravenous fluids

c. Aspiration pneumonia needing antibiotics

d. Low oxygen saturation needing frequent monitoring

Answer: a — Her goals are comfort, so relieving distress from agitation, which may include pain, comes first (sections 10.3 and 10.5). Intravenous fluids (b), antibiotics (c) and frequent oxygen monitoring (d) aim to treat or measure problems rather than relieve suffering. They do not match her goals, and some could add to her burden.

13. [CORE] Which interventions fit Mrs. Baptiste's goals of care? Select all that apply.

a. Deep suctioning through the nose every hour

b. Turning her onto her side with the head slightly raised

c. Giving the ordered anticholinergic for secretions

d. Checking vital signs every hour

e. Mouth care and moistening her lips

f. Starting a bolus of intravenous fluids

Answer: b, c, e — Side-lying, the ordered anticholinergic and mouth care are comfort measures for noisy breathing and a dry mouth (section 10.5; Table 10.3). Deep suctioning (a) is invasive, and no studies show that it helps. Hourly vital signs (d) and intravenous fluids (f) do not serve comfort-only goals, and fluids may add to secretions.

14. [CORE] The daughter says again, "She's choking." Which response by the nurse is best?

a. "Don't worry. She can't hear you or feel anything now, so there's no need to talk to her."

b. "I'll call the physician to come and suction her lungs so that she can breathe more easily."

c. "This sound means she is in pain, so I'll give her more of her medicine right away."

d. "The sound comes from saliva she can no longer clear. It probably doesn't distress her. Let's turn her onto her side together."

Answer: d — Explaining the cause and involving the family in comfort care eases distress, and evidence suggests the sound is unlikely to distress the dying person (section 10.5; Lokker et al., 2014). Option a is false reassurance and discourages the daughter from speaking to her mother. Deep suction (b) is invasive and has no evidence of benefit. Noisy breathing is not a sign of pain (c).

15. [CORE] One hour after the nurse's actions, which finding shows that the plan is working?

a. Her breathing is still gurgling, and she is still pulling at the sheets.

b. She is lying still with a relaxed face, and her daughter is holding her hand.

c. Her respiratory rate has risen to 28 breaths/min.

d. She has started to take sips of water.

Answer: b — Relief of agitation, a relaxed face and a family able to stay close show that the comfort goals are met (section 10.5). Continued agitation (a) and rapid breathing (c) show distress that calls for reassessment and a call to the prescriber. Sips of water (d) are not the goal and may cause coughing in a person who can no longer swallow safely.

16. [CORE] Under the Criminal Code as of October 25, 2026, which person meets one of the eligibility criteria for MAID?

a. A capable 17-year-old with a serious, incurable illness who asks for MAID

b. An adult whose substitute decision-maker requests MAID on the adult's behalf

c. An adult whose only underlying medical condition is major depression that has not improved with treatment

d. A capable adult with an incurable disease who is in an advanced state of irreversible decline

Answer: d — A grievous and irremediable condition includes an illness, disease or disability that is serious and incurable, with an advanced state of irreversible decline (section 10.4). The person must be at least 18 (a). The request must come from the person, not a substitute decision-maker (b). Mental illness as the sole underlying condition is excluded until at least March 17, 2027, and the government plans to extend that exclusion (c).

17. [CORE] A patient whose natural death is not reasonably foreseeable has made a written request for MAID. Which safeguard applies to this patient but not to a patient whose death is reasonably foreseeable?

a. A minimum of 90 clear days between the start of the first assessment and provision

b. A written request signed and dated in front of an independent witness

c. Two independent written assessments by physicians or NPs

d. A chance to withdraw consent immediately before MAID is provided

Answer: a — Track 2 requires at least 90 clear days for assessments, unless loss of capacity is imminent and both assessments are complete (section 10.4; Table 10.2). A witnessed written request (b), two independent assessments (c) and the chance to withdraw (d) apply in both tracks.

18. [CORE] A patient asks the RPN, "What is MAID, and could I get it?" Which response is most appropriate?

a. "You should think about MAID, given how much you are suffering."

b. "Nurses aren't allowed to talk about MAID. Please ask your doctor."

c. "I can tell you what MAID is. Can you tell me what's making you ask? I'll also let your NP know so that you can talk about all your options."

d. "You don't qualify, because your illness is not terminal."

Answer: c — Nurses may give factual information about lawful MAID, explore the question and inform the prescriber, without encouraging the patient (section 10.4). Option a encourages MAID, which CNO forbids and which may amount to counselling. Option b is inaccurate, because the Criminal Code allows health care professionals to give information. Only physicians and NPs assess eligibility, and a terminal illness is not required (d).

19. [CORE] An RN with a conscientious objection to MAID is assigned to a patient who is scheduled to receive MAID tomorrow. What should the RN do?

a. Tell the patient about the objection so that they understand why a different nurse will be caring for them.

b. Ask the charge nurse or manager to transfer the patient's care, and keep giving other care until another nurse takes over.

c. Refuse the assignment and leave the unit until a replacement is found.

d. Arrange for the patient to be assessed by a second NP.

Answer: b — CNO expects the nurse to hand care over to another nurse or provider, working with the employer as needed, and to keep giving all other care until a replacement takes over, without abandoning the patient (section 10.4). The objection must not be shared with the patient (a). Leaving the unit (c) abandons the patient. Ordering assessments (d) is not the RN's role.

20. [CORE] Which sign most strongly suggests that a patient with advanced cancer may die within the next 3 days?

a. Sleeping more during the day
b. Eating less than usual
c. Needing help to walk
d. Greatly reduced urine output

Answer: d — Reduced urine output was one of five signs that appeared mostly in the final 3 days of life and were highly specific for death within that time (section 10.5; Hui et al., 2014). More sleep (a), less eating (b) and weakness (c) often appear earlier, so they predict timing poorly.

21. [CORE] The nurse is assessing perfusion in a dying patient with dark skin. Which approach is best?

a. Feel the hands, feet and knees for coolness, compare them with the trunk, and check the nail beds and lips.
b. Document "no mottling" if no purple pattern is visible on the knees.
c. Use the pulse oximeter reading alone to judge perfusion.
d. Skip perfusion assessment, because colour changes cannot be seen on dark skin.

Answer: a — Mottling can be hard to see on darker skin, so the nurse adds temperature, comparison with the trunk, nail beds, lips and the family's observations (section 10.5). Relying on colour (b) may miss changes. Oximetry (c) does not show skin perfusion, and readings may be unreliable when perfusion is poor. Skipping the assessment (d) leaves the family without preparation.

22. [CORE] A palliative patient in an Ontario hospital dies 1 day after an unwitnessed fall in which she fractured her hip. What should the nurse do?

a. Remove all lines and tubes and prepare the body for the family.
b. Ask the family whether they would like an autopsy.
c. Notify the physician or NP so that the death can be reported to the coroner, and leave lines and tubes in place as policy directs.
d. Complete the medical certificate of death, because the death was expected.

Answer: c — A death that may have resulted from an accident is reportable to the coroner, even when the patient was receiving palliative care (section 10.5). Removing lines (a) may interfere with an investigation. Autopsy decisions (b) rest with the coroner in a reportable death. RNs cannot certify deaths in Ontario hospitals, and an RN may certify only expected deaths without unexpected events, so this death is not one a nurse may certify (d).

23. [CORE] An Ontario hospital patient who is not on a ventilator has a planned family meeting to discuss stopping life-sustaining treatment. The family has not mentioned donation. What is the nurse's responsibility?

a. Tell the family that their relative is too ill to donate organs or tissue.
b. Make sure the team notifies Trillium Gift of Life Network according to hospital policy before donation is discussed.
c. Ask the family to decide about donation before the meeting.
d. Wait to notify Trillium until the family raises the subject of donation.

Answer: b — Designated Ontario hospitals must notify Trillium Gift of Life Network when a patient meets one of its referral indicators, such as a planned discussion to withdraw life-sustaining therapy. Trillium checks eligibility before anyone raises donation with the family (section 10.5). Nurses do not decide eligibility (a) or raise donation first (c). Notification does not depend on the family raising it (d).

24. [CORE] A patient has just died. The family tells the nurse that their faith community has customs for the care of the body. What should the nurse do first?

a. Prepare the body according to the hospital's standard procedure.
b. Call the chaplain to explain the hospital's routines to the family.
c. Tell the family that customs can take place only at the funeral home.
d. Ask the family what they would like done and how the team can help.

Answer: d — Practices after death vary, so the nurse asks the family about their wishes and then works within policy to support them (section 10.5). Using standard procedure first (a) may break an important practice. A chaplain may help, but should not be there to explain routines in place of asking (b). Option c refuses requests that can often be met.

25. [CORE] Which statement about prolonged grief disorder is accurate?

a. In adults, it is diagnosed only when at least 12 months have passed since the death.
b. It is the expected response to the death of a spouse.
c. It is diagnosed when grief includes crying in the first month.
d. It is treated first with medications that target grief.

Answer: a — DSM-5-TR requires at least 12 months since the death for adults (6 months for children and adolescents), with disabling symptoms beyond cultural norms (section 10.6). Typical grief, even after a spouse's death, is not a disorder (b), and crying soon after a loss is normal (c). No medication specifically treats grief symptoms; grief-focused psychotherapy is used (d).

26. [CORE] After three patient deaths in one week, a nurse says she feels guilty and powerless because staffing kept her from being with a dying patient. Which response by the charge nurse is most helpful?

a. "You'll get used to it. Deaths are part of the job."
b. "Try not to think about it at work."
c. "That sounds like moral distress. Let's hold a team debrief, and here is the number for our employee assistance program."
d. "You should consider transferring to a unit with fewer deaths."

Answer: c — Guilt and powerlessness when constraints block what a nurse believes is right describe moral distress, and debriefing and employee assistance are recommended supports (section 10.6). Options a and b dismiss the distress, which, unaddressed, is linked to leaving the profession. A transfer (d) does not address what happened.

27. [RN] Which statement best distinguishes palliative sedation from MAID?

a. Palliative sedation is used only for psychological suffering.
b. Palliative sedation is intended to ease refractory suffering, not to shorten life.
c. Palliative sedation requires a 90-day assessment period.
d. Palliative sedation can be provided only by an NP.

Answer: b — Palliative sedation is the monitored, proportional lowering of consciousness to relieve refractory suffering, while MAID aims to end life at a capable person's request (section 10.5, Going Deeper). Refractory suffering may be physical, psychological or existential, and delirium is the most common reason for sedation (a). The 90-day period is a Track 2 MAID safeguard (c). Palliative sedation is not limited to NPs; the prescriber orders it, and nurses give it and monitor the patient (d).

28. [RN] A patient receiving palliative sedation for refractory delirium is calm and comfortable at a light level of sedation. Which action reflects the principle of proportionality?

a. Increase the infusion to reach deep sedation as soon as possible so that the delirium cannot return.

b. Stop all sedation to assess whether the delirium has resolved.

c. Hold the next dose until the patient is unresponsive.

d. Keep the current level of sedation, and keep monitoring comfort and sedation with a validated tool.

Answer: d — Proportionality means using the lowest level of sedation that gives adequate relief, with ongoing monitoring (section 10.5, Going Deeper). Deepening sedation without need (a) is not proportional. Abruptly stopping sedation (b) risks a return of suffering unless a planned interruption has been agreed on. Waiting for unresponsiveness (c) wrongly treats deep sedation as the goal.

29. [RN] A family member asks, "Will the morphine you're giving her speed up her death?" Which reply is consistent with the evidence?

a. "Studies of opioids used for symptoms at the end of life have not shown that they shorten life."

b. "Yes, it may shorten her life a little, but that is acceptable because it keeps her comfortable."

c. "Only if we give it more often than every 4 hours."

d. "We can stop it if you're worried, even though she is breathless."

Answer: a — Systematic reviews have found no link between opioids used for symptom control and shorter survival (section 10.5, Going Deeper). Option b repeats the myth. Option c invents a rule. Stopping effective symptom relief (d) leaves the patient suffering and does not follow her goals.

30. [RN] Which statement about the principle of double effect in end-of-life care is accurate?

a. It permits a nurse to give medication with the intent of ending the life of a patient who is suffering.

b. It is the legal basis for MAID in Canada.

c. It holds that an act aimed at a good effect may be acceptable even if a harmful effect is foreseen but not intended.

d. It requires the nurse to withhold opioids whenever any harmful effect, such as drowsiness, is possible.

Answer: c — Double effect distinguishes intended good effects from foreseen but unintended harms, and the harm must not be the means to the good (section 10.5, Going Deeper). It never permits intending death (a). MAID rests on the Criminal Code, not on double effect (b). The principle does not require withholding needed opioids (d), and properly titrated opioids have not been shown to hasten death.

References

Act respecting end-of-life care, CQLR, c. S-32.0001. https://www.legisquebec.gouv.qc.ca/en/document/cs/S-32.0001

American Psychiatric Association. (n.d.). *Prolonged grief disorder*. Retrieved October 25, 2026, from https://www.psychiatry.org/patients-families/prolonged-grief-disorder

Ariadne Labs. (2017). *Serious illness conversation guide* [Adapted for use by the BC Centre for Palliative Care; trifold for health care providers]. https://divisionsbc.ca/sites/default/files/54759/SIC-Trifold-for-Health-Care-Providers.pdf

Bourcier, S., Joffre, J., Dubée, V., Preda, G., Baudel, J.-L., Bigé, N., Leblanc, G., Levy, B. I., Guidet, B., Maury, E., & Ait-Oufella, H. (2017). Marked regional endothelial dysfunction in mottled skin area in patients with severe infections. *Critical Care, 21*(1), Article 155. https://doi.org/10.1186/s13054-017-1742-x

Bowers, B., Howard, P., Madden, B., Pollock, K., & Barclay, S. (2023). Is end-of-life anticipatory prescribing always enough? *BMJ, 381*, Article p1106. https://doi.org/10.1136/bmj.p1106

Bowers, B., Ryan, R., Kuhn, I., & Barclay, S. (2019). Anticipatory prescribing of injectable medications for adults at the end of life in the community: A systematic literature review and narrative synthesis. *Palliative Medicine, 33*(2), 160–177. https://doi.org/10.1177/0269216318815796

Campbell, M. L., & Yarandi, H. N. (2013). Death rattle is not associated with patient respiratory distress: Is pharmacologic treatment indicated? *Journal of Palliative Medicine*, *16*(10), 1255–1259. https://doi.org/10.1089/jpm.2013.0122

Canadian Hospice Palliative Care Association. (2013). *A model to guide hospice palliative care: Based on national principles and norms of practice* (Rev. and condensed ed.). https://chpca.ca/wp-content/uploads/2024/07/norms-of-practice-eng-web.pdf

Canadian Hospice Palliative Care Association. (n.d.). *About hospice palliative care*. https://www.chpca.ca/about-hpc/

Canadian Institute for Health Information. (2023). *Access to palliative care in Canada, 2023*. https://secure.cihi.ca/free_products/access-to-palliative-care-in-canada-2023-report-en.pdf

Canadian Partnership Against Cancer. (2022). *Beginning the journey into the spirit world: First Nations, Inuit and Métis approaches to palliative and end-of-life care in Canada*. https://www.partnershipagainstcancer.ca/topics/indigenous-palliative-care-approaches/

Canadian Partnership Against Cancer. (2024). *Did your loved one receive culturally appropriate palliative and end-of-life care?* https://www.partnershipagainstcancer.ca/cancer-strategy/strategic-priorities/priorities-and-indicators/culturally-appropriate-end-of-life-care/

Cancer Care Ontario. (2010). *Symptom management guide-to-practice: Nausea and vomiting*. https://cancercareontario.ca/system/files_force/symptoms/CCONauseaVomitFull.pdf?download=1

Clark, D. (1999). "Total pain," disciplinary power and the body in the work of Cicely Saunders, 1958–1967. *Social Science & Medicine*, *49*(6), 727–736. https://doi.org/10.1016/S0277-9536(99)00098-2

College of Nurses of Ontario. (2025). *Guidance on nurses' roles in medical assistance in dying* (Pub. No. 41056). https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41056-guidance-on-nurses-roles-in-maid.pdf

College of Nurses of Ontario. (n.d.-a). *Can an RN or RPN pronounce death when death has occurred?* Retrieved October 25, 2026, from https://cno.org/standards-learning/ask-practice/can-an-rn-or-rpn-pronounce-death-when-death-has-occurred

College of Nurses of Ontario. (n.d.-b). *Certifying death*. Retrieved October 25, 2026, from https://cno.org/standards-learning/certifying-death

College of Physicians and Surgeons of Ontario. (2023a). *Advice to the profession: End-of-life care*. https://www.cpso.on.ca/physicians/policies-guidance/policies/decision-making-for-end-of-life-care/advice-to-the-profession-end-of-life-care

College of Physicians and Surgeons of Ontario. (2023b). *Decision-making for end-of-life care* [Policy]. https://www.cpso.on.ca/en/physicians/policies-guidance/policies/decision-making-for-end-of-life-care

Criminal Code, R.S.C. 1985, c. C-46. https://laws-lois.justice.gc.ca/eng/acts/c-46/

Dean, M. M., Cellarius, V., Henry, B., Oneschuk, D., & Librach, S. L. (2012). Framework for continuous palliative sedation therapy in Canada. *Journal of Palliative Medicine, 15*(8), 870–879. https://doi.org/10.1089/jpm.2011.0498

Department of Justice Canada. (2026). *Canada's medical assistance in dying (MAID) law*. https://www.justice.gc.ca/eng/cj-jp/ad-am/bk-di.html

Faris, H., Dewar, B., Dyason, C., Dick, D. G., Matthewson, A., Lamb, S., & Shamy, M. C. F. (2021). Goods, causes and intentions: Problems with applying the doctrine of double effect to palliative sedation. *BMC Medical Ethics, 22*(1), Article 141. https://doi.org/10.1186/s12910-021-00709-0

Fearon, K., Strasser, F., Anker, S. D., Bosaeus, I., Bruera, E., Fainsinger, R. L., Jatoi, A., Loprinzi, C., MacDonald, N., Mantovani, G., Davis, M., Muscaritoli, M., Ottery, F., Radbruch, L., Ravasco, P., Walsh, D., Wilcock, A., Kaasa, S., & Baracos, V. E. (2011). Definition and classification of cancer cachexia: An international consensus. *The Lancet Oncology*, *12*(5), 489–495. https://doi.org/10.1016/S1470-2045(10)70218-7

Fernando, S. M., Tran, A., Cheng, W., Rochwerg, B., Taljaard, M., Vaillancourt, C., Rowan, K. M., Harrison, D. A., Nolan, J. P., Kyeremanteng, K., McIsaac, D. I., Guyatt, G. H., & Perry, J. J. (2019). Pre-arrest and intra-arrest prognostic factors associated with survival after in-hospital cardiac arrest: Systematic review and meta-analysis. *BMJ*, *367*, Article l6373. https://doi.org/10.1136/bmj.l6373

Gift of Life Act, R.S.O. 1990, c. H.20. https://www.ontario.ca/laws/statute/90h20

Government of Alberta. (2025). *Personal directive*. https://www.alberta.ca/personal-directive

Government of British Columbia. (2025). *Advance care planning*. https://www2.gov.bc.ca/gov/content/family-social-supports/seniors/health-safety/advance-care-planning

Government of Ontario. (2024). *Medical assistance in dying and end-of-life decisions*. https://www.ontario.ca/page/medical-assistance-dying-and-end-life-decisions

Government of Ontario. (2025). *Make a power of attorney*. https://www.ontario.ca/page/make-power-attorney

Government of Ontario. (2026). *Death investigations*. https://www.ontario.ca/page/death-investigations

Health Canada. (2018). *Framework on palliative care in Canada*. https://www.canada.ca/en/health-canada/services/health-care-system/reports-publications/palliative-care/framework-palliative-care-canada.html

Health Canada. (2019). *Action plan on palliative care*. https://www.canada.ca/en/health-canada/services/health-care-system/reports-publications/palliative-care/action-plan-palliative-care.html

Health Canada. (2023). *Palliative care: What we're doing*. https://www.canada.ca/en/health-canada/services/health-services-benefits/palliative-care/what-we-re-doing.html

Health Canada. (2025). *Sixth annual report on medical assistance in dying in Canada, 2024*. https://www.canada.ca/en/health-canada/services/publications/health-system-services/annual-report-medical-assistance-dying-2024.html

Hospice Palliative Care Ontario. (n.d.). *What are advance care planning, goals of care discussions and health care consent?* (Caregiver Support Education, Topic 7). https://caregiversupport.hpco.ca/ocp/what-are-advance-care-planning-goals-of-care-discussions-and-health-care-consent/

Hui, D., Bohlke, K., Bao, T., Campbell, T. C., Coyne, P. J., Currow, D. C., Gupta, A., Leiser, A. L., Mori, M., Nava, S., Reinke, L. F., Roeland, E. J., Seigel, C., Walsh, D., & Campbell, M. L. (2021). Management of dyspnea in advanced cancer: ASCO guideline. *Journal of Clinical Oncology*, *39*(12), 1389–1411. https://doi.org/10.1200/JCO.20.03465

Hui, D., dos Santos, R., Chisholm, G., Bansal, S., Silva, T. B., Kilgore, K., Crovador, C. S., Yu, X., Swartz, M. D., Perez-Cruz, P. E., Leite, R. de A., Nascimento, M. S. de A., Reddy, S., Seriaco, F., Yennu, S., Paiva, C. E., Dev, R., Hall, S., Fajardo, J., & Bruera, E. (2014). Clinical signs of impending death in cancer patients. *The Oncologist, 19*(6), 681–687. https://doi.org/10.1634/theoncologist.2013-0457

Lam, R. E., & Lam, P. J. (2014). Nutrition in dementia. *CMAJ*, *186*(17), 1319. https://doi.org/10.1503/cmaj.141217

Larkin, P. J., Cherny, N. I., La Carpia, D., Guglielmo, M., Ostgathe, C., Scotté, F., & Ripamonti, C. I. (2018). Diagnosis, assessment and management of constipation in advanced cancer: ESMO clinical practice guidelines. *Annals of Oncology*, *29*(Suppl. 4), iv111–iv125. https://doi.org/10.1093/annonc/mdy148

Larkin, P. J., Sykes, N. P., Centeno, C., Ellershaw, J. E., Elsner, F., Eugene, B., Gootjes, J. R. G., Nabal, M., Noguera, A., Ripamonti, C., Zucco, F., & Zuurmond, W. W. A. (2008). The management of constipation in palliative care: Clinical practice recommendations. *Palliative Medicine*, *22*(7), 796–807. https://doi.org/10.1177/0269216308096908

Lokker, M. E., van Zuylen, L., van der Rijt, C. C. D., & van der Heide, A. (2014). Prevalence, impact, and treatment of death rattle: A systematic review. *Journal of Pain and Symptom Management, 47*(1), 105–122. https://doi.org/10.1016/j.jpainsymman.2013.03.011

Lynn, J., & Adamson, D. M. (2003). *Living well at the end of life: Adapting health care to serious chronic illness in old age* (WP-137). RAND Corporation. https://doi.org/10.7249/WP137

López-Saca, J. M., Guzmán, J. L., & Centeno, C. (2013). A systematic review of the influence of opioids on advanced cancer patient survival. *Current Opinion in Supportive and Palliative Care, 7*(4), 424–430. https://doi.org/10.1097/SPC.0b013e328365763a

Maltoni, M., Scarpi, E., Rosati, M., Derni, S., Fabbri, L., Martini, F., Amadori, D., & Nanni, O. (2012). Palliative sedation in end-of-life care and survival: A systematic review. *Journal of Clinical Oncology, 30*(12), 1378–1383. https://doi.org/10.1200/JCO.2011.37.3795

Moons, L., De Roo, M. L., Deschodt, M., & Oldenburger, E. (2024). Death rattle: Current experiences and non-pharmacological management—A narrative review. *Annals of Palliative Medicine*, *13*(1), 150–161. https://doi.org/10.21037/apm-23-507

Morley, G., Bradbury-Jones, C., & Ives, J. (2020). What is 'moral distress' in nursing? A feminist empirical bioethics study. *Nursing Ethics, 27*(5), 1297–1314. https://doi.org/10.1177/0969733019874492

Murray, S. A., Kendall, M., Boyd, K., & Sheikh, A. (2005). Illness trajectories and palliative care. *BMJ*, *330*(7498), 1007–1011. https://doi.org/10.1136/bmj.330.7498.1007

Noor, A. M., Suryana, D., Kamarudin, E. M. E., Naidu, N. B. M., Kamsani, S. R., . . . Govindasamy, P. (2025). Compassion fatigue in helping professions: A scoping literature review. *BMC Psychology, 13*, Article 349. https://doi.org/10.1186/s40359-024-01869-5

Ontario Health. (n.d.). *Indigenous navigators* [Cancer Care Ontario]. https://cancercareontario.ca/node/33676

Ontario Ministry of the Attorney General, Office of the Public Guardian and Trustee. (2020). *Powers of attorney Q&As* (Original work published 2007). https://www.publications.gov.on.ca/store/20170501121/Free_Download_Files/300629.pdf

Ottawa Hospital Research Institute. (2019, December 4). *How likely are you to survive a hospital cardiac arrest? Newly identified risk factors can help* [News release]. https://ohri.ca/en/newsroom/how-likely-are-you-survive-hospital-cardiac-arrest-newly-identified-risk-factors-can-help

Rana, U. (2026, October 7). *Canada won't expand MAID for mental illness alone, minister says*. Global News. https://globalnews.ca/news/12091165/canada-maid-mental-illness/

Registered Nurses' Association of Ontario. (2011). *End-of-life care during the last days and hours*. https://rnao.ca/media/6023/download

Roeland, E. J., Bohlke, K., Baracos, V. E., Bruera, E., del Fabbro, E., Dixon, S., Fallon, M., Herrstedt, J., Lau, H., Platek, M., Rugo, H. S., Schnipper, H. H., Smith, T. J., Tan, W., & Loprinzi, C. L. (2020). Management of cancer cachexia: ASCO guideline. *Journal of Clinical Oncology*, *38*(21), 2438–2453. https://doi.org/10.1200/JCO.20.00611

Stajduhar, K. I., Mollison, A., Giesbrecht, M., McNeil, R., Pauly, B., Reimer-Kirkham, S., Dosani, N., Wallace, B., Showler, G., Meagher, C., Kvakic, K., Gleave, D., Teal, T., Rose, C., Showler, C., & Rounds, K. (2019). "Just too busy living in the moment and surviving": Barriers to accessing health care for structurally vulnerable populations at end-of-life. *BMC Palliative Care*, *18*(1), Article 11. https://doi.org/10.1186/s12904-019-0396-7

Surges, S. M., Brunsch, H., Jaspers, B., Apostolidis, K., Cardone, A., Centeno, C., Cherny, N., Csikós, Á., Fainsinger, R., Garralda, E., Ling, J., Menten, J., Mercadante, S., Mosoiu, D., Payne, S., Preston, N., Van den Block, L., Hasselaar, J., & Radbruch, L. (2024). Revised European Association for Palliative Care (EAPC) recommended framework on palliative sedation: An international Delphi study. *Palliative Medicine, 38*(2), 213–228. https://doi.org/10.1177/02692163231220225

Trillium Gift of Life Network. (n.d.). *Routine notification for designated hospitals: Frequently asked questions for healthcare professionals*. Ontario Health. https://www.giftoflife.on.ca/resources/pdf/Routine%20Notification.pdf

World Health Organization. (2020, August 5). *Palliative care* [Fact sheet]. https://www.who.int/news-room/fact-sheets/detail/palliative-care

11 Substance Use in Acute Care

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Describe substance use as a continuum, the Canadian picture of alcohol harms and the toxic drug crisis, and the structural causes of substance-related harm.
2. Use language and approaches that reduce stigma when caring for people who use substances.
3. Screen hospital patients for alcohol and other substance use, offer a brief intervention and support referral.
4. Recognize, monitor and respond to alcohol withdrawal and Wernicke encephalopathy, including escalation of severe withdrawal.
5. Recognize opioid toxicity and respond with ventilation and naloxone, and recognize and support the care of opioid withdrawal and opioid agonist treatment in hospital.
6. Describe the nursing care of patients with stimulant toxicity, cannabis-related problems and other substance-related presentations.
7. Apply harm reduction principles and plan safe transitions, including take-home naloxone, follow-up and culturally specific supports.
8. Distinguish RN, RPN and NP roles in substance use care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 3, 4, 5, 6	Clinician; Scholar	Foundations of Practice
2, 7	Advocate; Communicator; Educator	Ethical Practice; Collaborative Practice
5, 8	Professional; Collaborator; Coordinator	Legal Practice; Collaborative Practice

Introduction

Substance use is part of everyday care on medical-surgical units. The Canadian Institute for Health Information (CIHI) reports that about 540 people are hospitalized in Canada every day for harm from alcohol or other drugs, and that alcohol accounts for more than half of these hospital stays (CIHI, 2026). The count is conservative. It includes only stays for conditions wholly caused by substance use, such as poisonings and substance-related mental and behavioural conditions, and medical conditions caused by alcohol. Stays for conditions to which substance use only contributes, such as many cancers, strokes, respiratory diseases and injuries, are not counted, and neither are emergency department visits. Nurses therefore meet people who use alcohol and other drugs on every unit, whatever the reason for admission.

This chapter is the book's home for substance use in hospital. Section 11.1 explains the continuum of use, the Canadian picture, structural causes and the harm done by stigma. Section 11.2 covers screening and brief intervention, and section 11.3 alcohol withdrawal and Wernicke encephalopathy. Section 11.4 turns to opioid toxicity and the naloxone response, opioid withdrawal and opioid agonist treatment (OAT) in hospital; section 11.5 to stimulants, cannabis and other substances; and section 11.6 to harm reduction and safe transitions. Related topics live elsewhere: cultural safety and Indigenous health (Chapter 2), electrolytes (Chapter 3), pain care and opioid safety (Chapter 5), rapid response (Chapter 6), delirium (Chapter 8) and liver disease (Chapter 26).

11.1 Substance Use, Stigma and Health

A Continuum of Use

Substance use is not a single behaviour. It runs along a continuum, from no use, through occasional or lower-risk use, to use that raises the risk of harm, to a substance use disorder. A person can move along this continuum in either direction over a lifetime. Most people who drink alcohol or use other drugs do not have a disorder, yet their use can still matter in hospital, for example through drug interactions, injuries or withdrawal.

A **substance use disorder** is a health condition in which a person keeps using a substance despite significant problems linked to that use. Clinicians diagnose it with the criteria in the *Diagnostic and Statistical Manual of Mental Disorders*, fifth edition, text revision (DSM-5-TR). The Canadian alcohol use disorder guideline summarizes the approach: a problematic pattern of use over 12 months that causes clinically significant impairment or distress, shown by at least 2 of 11 criteria (Wood et al., 2023). The criteria fall into four broad groups:

- **Impaired control:** using more or for longer than intended, failed efforts to cut down, much time spent getting, using or recovering, and craving.
- **Social impairment:** failing at major roles, continuing despite relationship problems, and giving up important activities.
- **Risky use:** use in physically hazardous situations, and continued use despite a physical or psychological problem it is making worse.
- **Pharmacological criteria:** tolerance and withdrawal.

Severity depends on the number of criteria met: 2 or 3 is mild, 4 or 5 is moderate and 6 or more is severe (Wood et al., 2023). Nurses do not make this diagnosis, but knowing its structure helps them recognize cues and describe what they observe.

Tolerance and withdrawal alone do not mean a person has a disorder. When a person takes a medicine such as an opioid only as prescribed and under medical supervision, these two criteria are not counted toward the diagnosis (Centers for Disease Control and Prevention [CDC], 2024). Chapter 5, section 5.4, explains tolerance and physical dependence.

The Canadian Picture

Alcohol is the substance behind most hospital stays for substance-related harm (CIHI, 2026). *Canada's Guidance on Alcohol and Health* (Canadian Centre on Substance Use and Addiction [CCSA], 2023) describes risk as rising steadily with the amount a person drinks each week; section 11.2 explains how nurses use it in screening.

Since 2016, Canada has also lived through a public health crisis of deaths from an **unregulated drug supply**: drugs made and sold outside any legal or quality control, often containing fentanyl and other toxic substances of unknown strength. Public health leaders reported 7,146 opioid-related deaths in 2024, an average of 20 people every day, which was 17% fewer than in 2023 (Public Health Agency of Canada [PHAC], 2025). In 2025, there were 5,608 opioid-related deaths, an average of 15 per day, a further 23% decrease. Leaders called this number unacceptably high and noted that the decrease did not happen everywhere: some jurisdictions and communities were still seeing increases in harm (PHAC, 2026). The Canadian Context box gives more detail.

CANADIAN CONTEXT

The Toxic Drug Crisis in Numbers

- **Total:** 57,509 apparent opioid toxicity deaths were reported in Canada from January 2016 to March 2026 (Substance-related Overdose and Mortality Surveillance Task Group on behalf of the Council of Chief Medical Officers of Health, 2026).
- **Early 2026:** From January to March 2026, there were 1,354 apparent opioid toxicity deaths. Most (96%) were accidental. Fentanyl analogues were involved in 70% of these deaths, fentanyl in 36% and a stimulant in 62%. Males accounted for 70%, and people aged 30 to 39 (25%) and 40 to 49 (26%) made up the largest age groups. British Columbia, Alberta and Ontario together accounted for 78% (Substance-related Overdose and Mortality Surveillance Task Group on behalf of the Council of Chief Medical Officers of Health, 2026). Figures for the latest four quarters are preliminary and could still be revised.
- **A changing supply:** Benzodiazepines contributed to 8% of opioid toxicity deaths in 2018 and 34% in 2024. In 2025, stimulant-related deaths outnumbered opioid-related deaths in seven provinces and territories, including Ontario (PHAC, 2026).

- **Unequal harms:** In British Columbia in 2024, the toxic drug death rate among First Nations people was 6.7 times that of other residents of the province (First Nations Health Authority [FNHA], 2025).

Causes Are Structural

Why a person uses substances, and how much harm follows, depends far more on their circumstances than on willpower. Health Canada explains that people develop addictions for many reasons, among them trauma and chronic stress, their surroundings, their mental well-being, and their genes and biology, and that recovery is possible (Health Canada, 2026c). Poverty, unstable housing, untreated pain and mental illness, and past trauma all raise risk. Stigma and unsafe drug supplies then turn risk into harm.

For some First Nations, Inuit and Métis communities, colonization is a root cause. The Truth and Reconciliation Commission called on governments to acknowledge that the current state of Indigenous health is a direct result of past government policies, including residential schools, and named addictions among the health gaps to be closed (Truth and Reconciliation Commission of Canada [TRC], 2015). A scoping review found that residential school attendance was linked with poorer health, including substance use, among survivors and the generations that followed (Wilk et al., 2017). The response begins from strength. The *First Nations Mental Wellness Continuum Framework* places culture at the foundation of wellness and describes mental wellness as a balance supported by hope, belonging, meaning and purpose (Health Canada & Assembly of First Nations, 2015). First Nations leaders in British Columbia frame the toxic drug response as grounded in culture, self-determination, community and kinship (FNHA, 2025). Chapter 2 explains cultural safety and trauma- and violence-informed care.

Stigma and Language

Stigma is a set of negative attitudes, beliefs and behaviours directed at a group because of their situation, expressed as stereotypes, prejudice and discrimination (Health Canada, 2026c). It works at three levels: in how people see themselves (self-stigma), in how others treat them (social stigma) and in rules and systems (structural stigma).

Stigma harms health. People who expect to be judged avoid or delay care and may hide their use or use alone, which raises the risk of dying (Health Canada, 2026c). In health care, stigma is linked with reduced empathy, lower-quality care and poorer treatment outcomes (PHAC, 2019). In a Vancouver study, people who use drugs who had left hospital against medical advice described emergency care in which they felt stigmatized and neglected and their pain and withdrawal were poorly managed; many became less willing to seek care again (Mayer et al., 2023). Chapter 5, section 5.5, covers pain care and patients who want to leave.

Words are one of the easiest places to start. Federal guidance asks health professionals to use **person-first language**, which names the person before the condition, and to avoid terms that frame substance use as a moral failing or a choice (PHAC, 2020). Table 11.1 gives examples.

Table 11.1 Choosing words that reduce stigma (based on Health Canada, 2026c; PHAC, 2019; and PHAC, 2020; original wording)

Instead of	Say	Why
Addict, user, junkie	Person who uses drugs; person with a substance use disorder	Puts the person first; slang labels carry blame
Alcoholic	Person with an alcohol use disorder	Names a treatable health condition, not an identity
Substance abuse, misuse	Substance use; substance use disorder	"Abuse" and "misuse" express judgment and imply wrongdoing
Clean or dirty (test)	Negative or positive test result	Uses clinical terms; "dirty" suggests the person is soiled
Clean (person)	Not currently using; in recovery	Avoids implying that use makes someone unclean
Relapse	Recurrence of substance use; return to use	Treats a return to use as part of a health condition, not a failure
Drug-seeking	Describe what the person said and did, and the need behind it	The label can lead to needed medicine being withheld; a description keeps the assessment open
Non-compliant	Chose not to receive this care; facing barriers to care	Moves attention to barriers the team can address

11.2 Screening and Brief Intervention in Hospital

Ask Everyone

Canada's alcohol guideline recommends routine screening of every adult and young person for drinking above low-risk levels; its 2026 update lists medical wards and emergency departments among the settings where alcohol problems often go undiagnosed (Wood et al., 2023, 2026). Canadian guidance for older adults names hospital admission as a key time to ask (Butt et al., 2020). Screening only patients who "look like" they drink misses many people and reinforces stereotypes, so the nurse asks every patient, in the same way, at admission.

Asking at admission matters for safety. A patient who drinks heavily every day may begin to withdraw within hours of arriving. A patient who uses benzodiazepines, opioids or other drugs not on the medication list may face dangerous interactions with sedating medicines given in hospital. Knowing what a person uses also helps the team plan pain care and offer treatment.

How the nurse asks shapes the answer. The nurse asks in private, explains why the question is asked of everyone, uses neutral words and accepts the answer without comment. A useful opening is: "I ask everyone about alcohol and other drugs, because it helps us keep you safe while you're here." Patients may worry that the information will be shared with police, employers or child welfare services. The nurse can explain how health information is protected and who on the team will see it (Chapter 1, section 1.5).

Screening Tools

Short tools help the nurse ask in a consistent way.

- **Weekly drinks and drinks per occasion:** In 2026, Canada's guideline replaced its earlier screening approach with simpler questions tied to *Canada's Guidance on Alcohol and Health*. The clinician asks how many standard drinks the person has in an average week and whether they now have more than 2 standard drinks on any one evening or occasion, then compares the answers with the guidance. If use is above low risk, a further question asks about difficulty controlling use or about significant problems at work, in relationships or with physical or mental health (Wood et al., 2026).
- **Single alcohol question:** The 2023 guideline began with a single question: how often in the past year the person has had 5 or more drinks in one day (men) or 4 or more (women) (Smith et al., 2009; Wood et al., 2023). A positive answer led to a longer tool. The 2026 update no longer recommends this two-step approach, but nurses may still see these tools on admission forms.
- **AUDIT-C:** The **AUDIT-C** is a short version of the 10-item Alcohol Use Disorders Identification Test (AUDIT) built from its questions about how often and how much a person drinks. The 2023 guideline grouped AUDIT-C scores of 0 to 4 as low risk, 5 to 7 as moderate risk and 8 or more as high risk (Wood et al., 2023).
- **Single drug question:** The clinician asks how often in the past year the person has used an illegal drug or taken a prescription medicine for non-medical reasons. Any answer of one or more times is positive (Smith et al., 2010).

Canada's Guidance on Alcohol and Health describes a continuum of weekly risk. Not drinking has benefits. People who have 2 standard drinks or fewer per week are likely to avoid alcohol-related harm. From 3 to 6 drinks, the risk of several cancers, including breast and colon cancer, rises. At 7 or more, the risk of heart disease and stroke rises significantly. Each additional drink increases risk further, and anyone who drinks more than 2 drinks a week is advised to have no more than 2 on any day. For a person who is pregnant or trying to become pregnant, no amount of alcohol is known to be safe (CCSA, 2023).

Brief Intervention and Referral

A positive screen leads to a conversation, not a lecture. **Brief intervention** is a short, structured conversation, based on motivational interviewing, that helps a person consider their use and decide on a change. Canada's guideline recommends offering it to everyone who screens positive; it can be delivered by many kinds of health professionals, and even one five-minute session can help (Wood et al., 2023). The nurse shares the result, links it to the person's health concern, asks what they think and supports the step they choose.

When use is above low risk with signs of a problem, the guideline recommends a full diagnostic assessment (Wood et al., 2026). Depending on the setting and employer policy, the nurse can suggest or help arrange:

- an **addiction medicine consult service**, where available, for assessment, withdrawal management and starting treatment;

- a **Rapid Access Addiction Medicine (RAAM) clinic** referral after discharge. Ontario has nearly 100 publicly funded RAAM clinics, supported by the META:PHI (Mentoring, Education, and Clinical Tools for Addiction: Partners in Health Integration) network; most see people without an appointment or referral and offer medication, counselling, harm reduction education and links to other services (META:PHI, n.d.);
- community counselling, withdrawal management and peer support;
- Indigenous-led and culturally specific supports, such as Indigenous patient navigators where available (Chapter 2).

11.3 Alcohol Withdrawal

Why Withdrawal Happens

Alcohol slows the brain. It boosts the effect of gamma-aminobutyric acid (GABA), the main calming messenger, and blocks glutamate, the main excitatory messenger, at N-methyl-D-aspartate (NMDA) receptors. With heavy daily drinking, the brain adapts to keep working: GABA activity falls and glutamate signalling increases. The person now needs alcohol to feel normal.

When the person stops drinking or cuts down sharply, the brakes are gone but the accelerator is still pressed. The nervous system becomes overexcited, which causes the tremor, sweating, fast heart rate, agitation and, in severe cases, seizures and delirium of **alcohol withdrawal** (Gortney et al., 2016). Withdrawal can begin while alcohol is still measurable in the blood, so a patient who arrives intoxicated can be withdrawing by the next shift.

Repeated cycles of heavy drinking and withdrawal leave lasting changes in the brain. Each episode tends to be worse than the last, a process called **kindling**. Kindling has also been linked with more craving and a weaker response to benzodiazepines (American Society of Addiction Medicine [ASAM], 2020). A history of severe or complicated withdrawal is therefore an important warning sign.

Timeline and Severity

Withdrawal ranges from mild discomfort to a life-threatening emergency. How severe it becomes depends on how much the person drinks, how long since the last drink and how many withdrawals they have had before (Gortney et al., 2016). Table 11.2 gives typical timing, although individual patients vary and stages can overlap.

- **Minor withdrawal** starts within hours of the last drink, with tremor, sweating, anxiety, palpitations, headache, nausea, poor appetite and insomnia.
- **Alcoholic hallucinosis** is hallucinations, most often visual but also auditory or tactile, in a person who otherwise remains oriented.
- A **withdrawal seizure** is a generalized tonic-clonic seizure, usually in the first two days.
- **Delirium tremens**, also called alcohol withdrawal delirium, is the most severe form: disorientation, fluctuating attention, hallucinations, agitation and autonomic overactivity such as fever, a fast heart rate and high blood pressure. Its mortality has been reported at 5% to 10% (Gortney et al., 2016).

Some cues look different across skin tones. Flushing and pallor are harder to see on darker skin, so the nurse also feels for warm, damp skin and looks for beads of sweat on the forehead, upper lip and palms. Tremor is best seen with the arms held out and fingers spread. Vital signs give objective evidence on every patient: a rising heart rate, blood pressure and temperature signal worsening withdrawal.

There is no single test for alcohol withdrawal; it is a clinical diagnosis. Blood work usually includes electrolytes, magnesium, glucose, liver tests and a complete blood count, and sometimes a blood alcohol level. ASAM advises that withdrawal treatment should not be delayed while results are pending (ASAM, 2020). The team also looks for other causes of the same signs. A seizure is blamed on withdrawal only when drinking recently stopped or decreased (ASAM, 2020); a fall can cause a head injury, and infection, low blood glucose or other drugs can mimic withdrawal.

Table 11.2 Alcohol withdrawal: timeline, cues and nursing actions (Gortney et al., 2016; ASAM, 2020)

Stage	Typical timing after last drink	Cues	Nursing actions
Minor withdrawal	6 to 12 hours	Tremor, sweating, anxiety, palpitations, headache, nausea, poor appetite, insomnia	Assess with the unit's withdrawal scale; give medicines as ordered; quiet room; fluids and food; reassess per protocol
Alcoholic hallucinosis	12 to 24 hours; usually resolves within 48 hours	Visual, auditory or tactile hallucinations; person usually oriented	Reassure and orient; keep the patient safe; report to the registered nurse (RN) or prescriber; reassess often
Withdrawal seizure	24 to 48 hours; can occur as early as 2 hours	Generalized tonic-clonic seizure	Seizure precautions; protect airway and prevent injury; call for help; report at once; closer monitoring afterward
Delirium tremens	48 to 72 hours; can last up to 5 days	Disorientation, mainly visual hallucinations, agitation, fever, tachycardia, high blood pressure, sweating	Call rapid response or the critical care team per policy; constant observation; safety; fluids and electrolytes as ordered

Predicting and Monitoring

Two different tools serve two different jobs. The **Prediction of Alcohol Withdrawal Severity Scale (PAWSS)** estimates, at admission, whether a patient is likely to develop complicated withdrawal: hallucinosis, seizures or delirium tremens. Its 10 items come from risk factors that research has linked with complicated withdrawal, and it was developed for medically ill patients in hospital (Maldonado et al., 2014). Canada's guideline recommends using the clinical history with PAWSS to choose a withdrawal management plan; a score of 4 or more signals high risk (Wood et al., 2023).

The **Clinical Institute Withdrawal Assessment for Alcohol, revised (CIWA-Ar)** measures how severe withdrawal is right now (Sullivan et al., 1989). The nurse scores 10 areas, some by observation, such as tremor and sweating, and some by asking the patient, such as nausea, anxiety and disturbances in what they see, hear or feel. Higher totals mean more severe withdrawal and guide medication under the unit's protocol (Gortney et al., 2016). In medical and surgical patients, a low score can usually be trusted, but a high score is interpreted with caution (ASAM, 2020).

The CIWA-Ar has important limits (ASAM, 2020):

- It is not a diagnostic tool. Pain, fever, infection, anxiety and other illnesses can raise the score.
- Because much of it depends on what the patient reports, it does not work well for a patient who cannot communicate, including one who is intubated or has a language barrier without an interpreter. Scales that rely more on objective signs are used instead.
- It is not recommended once a patient is delirious. A structured delirium tool is used instead (Chapter 8, section 8.2).

Reassessment follows the protocol. For moderate to severe withdrawal, ASAM (2020) suggests reassessing every 1 to 4 hours, extending the interval once the patient has been stable for a day. The nurse also reassesses after every dose and whenever the patient's condition changes.

Treatment

Canada's guideline is written mainly for primary care, so this section also draws on the ASAM guideline for hospital withdrawal management. **Benzodiazepines** are the first-line medicines for moderate and severe withdrawal, because they calm the overexcited nervous system and prevent seizures and delirium (ASAM, 2020). Longer-acting benzodiazepines are generally preferred because they give a smoother course. For patients with significant liver disease, a benzodiazepine that depends less on the liver is chosen, and older adults need close monitoring because long-acting drugs can build up (ASAM, 2020). Benzodiazepines are used only for the withdrawal period, not as ongoing treatment of alcohol use disorder (Wood et al., 2023).

In hospital, **symptom-triggered treatment** is preferred: medicine is given when the withdrawal score reaches the threshold in the order, rather than on a fixed schedule (ASAM, 2020). This approach usually means less medicine overall. It suits only patients whose symptoms can be assessed reliably, so fixed schedules are used when they cannot, for example right after surgery (Gortney et

al., 2016). Phenobarbital is an alternative only in experienced hands and closely monitored settings (ASAM, 2020). Alcohol itself should never be given to prevent or treat withdrawal (ASAM, 2020).

Supportive nursing care matters as much as medication:

- a quiet, well-lit room, a clock and calendar, and simple, calm explanations;
- fluids, food and help with eating;
- fall precautions and seizure precautions per policy;
- vital signs and sedation checks after each dose;
- monitoring magnesium, potassium and phosphate, which are often low and are replaced as ordered (Chapter 3, sections 3.5 and 3.6).

The nurse escalates promptly. Signs of delirium, a seizure, rising scores despite treatment, oversedation or unstable vital signs are reported at once to the most responsible practitioner (a registered practical nurse [RPN] also consults the RN), and the rapid response team is called per policy (Chapter 6, section 6.2). Severe withdrawal and withdrawal delirium often need critical care and constant one-to-one observation (ASAM, 2020).

Thiamine and Wernicke Encephalopathy

Heavy drinking often reduces how much **thiamine** (vitamin B1) a person takes in and absorbs. Thiamine deficiency can cause **Wernicke encephalopathy**, an acute brain disorder that is a medical emergency. Besides alcohol use disorder, other risk factors include malnutrition, bariatric and other gastrointestinal surgery, prolonged vomiting, cancer and chemotherapy, and malabsorption (Li & Xing, 2025).

The classic triad is confusion, unsteady gait (ataxia) and abnormal eye movements. Only about 10% to 16% of patients show all three, so most cases are missed if the nurse waits for the full picture (Li & Xing, 2025). In a patient at risk, any one of these signs is reported at once. Untreated, Wernicke encephalopathy can lead to coma and death. Many untreated patients develop **Korsakoff syndrome**, a lasting memory disorder in which the person cannot form new memories (Li & Xing, 2025).

Thiamine is given as ordered to everyone at risk. Canada's guideline offers it by mouth before and during withdrawal and by injection when Wernicke encephalopathy is suspected or the person has decompensated liver disease or is at risk of malnutrition (Wood et al., 2023); for inpatients, ASAM prefers the intravenous or intramuscular route, especially with poor nutrition or malabsorption (ASAM, 2020). Thiamine is given before any intravenous glucose, because glucose metabolism uses up the little thiamine that remains and can deepen the deficiency (Gortney et al., 2016; Li & Xing, 2025).

After Withdrawal

Withdrawal management is not treatment of alcohol use disorder. Without further care, many people return to drinking. Canada's guideline recommends naltrexone or acamprosate as first-line medicines for adults with moderate to severe alcohol use disorder (Wood et al., 2023). Naltrexone can support either stopping or reducing drinking; it cannot be used by a person who needs opioids, including for pain or OAT, or who has acute hepatitis. Acamprosate supports abstinence (Wood et al., 2023) and is not used in severe kidney impairment (Mylan Pharmaceuticals ULC, 2011). The guideline advises against antidepressants of the selective serotonin reuptake inhibitor class and antipsychotics as treatment for alcohol use disorder (Wood et al., 2023). An estimated less than 2% of people who could benefit receive evidence-based medicine for alcohol use disorder (BC Centre on Substance Use [BCCSU], n.d.), so hospital is an opportunity to start.

Medication works best alongside psychosocial treatment, such as counselling or family-based therapy (Wood et al., 2023). Before discharge, the nurse helps connect the patient with a RAAM clinic, primary care or community program, and confirms a follow-up plan the patient agrees with.

Patient and family teaching includes:

- Stopping heavy drinking suddenly can be dangerous. Anyone planning to stop or cut down should talk with a health care provider first. People at low risk can often withdraw safely at home with support, while those with a high PAWSS score, past complicated withdrawal or barriers to care in the community may need inpatient care (Wood et al., 2023).

- Warning signs that need urgent care: shaking that gets worse, confusion, seeing or hearing things that are not there, a seizure, or a fast heartbeat with fever.
- Thiamine and other medicines are taken as prescribed, and alcohol is not combined with sedating drugs.
- Any reduction in drinking brings health benefits (CCSA, 2023).

CLINICAL JUDGMENT

Tremor and Hallucinations on Day Two

Roger Thibault, 58, fell at home one evening and fractured his hip. He was admitted that night and had surgery the next morning. On the evening of postoperative day 2, about 3 days after he last drank, the nurse finds him sweating, with a coarse tremor of both hands. His heart rate is 124 beats/min and his blood pressure is higher than at baseline. He points at the window and asks who the people outside are; his room is on the sixth floor.

- **Recognize cues:** Tremor, sweating, tachycardia, high blood pressure and visual hallucinations. His wife now tells the nurse he drinks 8 to 10 beers every day; this was not recorded at admission.
- **Analyze cues:** The timing and signs fit alcohol withdrawal that may be progressing to delirium tremens. Other causes of acute confusion after surgery, such as hypoxia, infection, pain, low blood glucose and medications, must also be considered (Chapter 8, section 8.2).
- **Prioritize hypotheses:** Withdrawal delirium is life-threatening and comes first.
- **Generate solutions:** The nurse checks whether he can attend to questions. If he can communicate reliably, a CIWA-Ar is done per protocol; if he is disoriented, a delirium screen is used instead. Oxygen saturation, temperature and capillary blood glucose are checked.
- **Take action:** The nurse stays with him, keeps the bed low and the room calm, and reports to the most responsible practitioner using SBAR (Situation, Background, Assessment, Recommendation; Chapter 6), calling the rapid response team per the unit's criteria. Thiamine is given before any glucose-containing fluid, and medicines are given as ordered.
- **Evaluate outcomes:** The nurse reassesses after each dose and documents his orientation, vital signs and sedation level.

LIFESPAN CONSIDERATIONS

Older Adults, Alcohol and Benzodiazepines

Alcohol use disorder in older adults is common but under-recognized and under-treated. Its signs, such as falls, poor mobility and memory problems, are easily mistaken for aging (Butt et al., 2020). Every older adult is asked about alcohol at admission, in the same way as younger adults.

Withdrawal may look atypical. Confusion may be the main sign, overlapping with delirium from other causes (Chapter 8, section 8.2), and symptoms may last longer than in younger adults (Gortney et al., 2016). Older adults are more sensitive to benzodiazepines and may clear long-acting drugs more slowly. Benzodiazepines raise the risk of delirium, falls and fractures (Conn et al., 2020), so the nurse checks sedation, orientation and mobility after every dose and puts fall precautions in place.

At discharge, *Canada's Guidance on Alcohol and Health* applies to all adults: less alcohol is better (CCSA, 2023). Older adults who are frail, live with several health conditions or take medicines that interact with alcohol are advised to drink even less or not at all (Butt et al., 2020).

11.4 Opioid Toxicity and Withdrawal

Opioids cause most of the toxic drug deaths described in section 11.1. This section covers the two opioid emergencies nurses meet most often in acute care: opioid toxicity, when too much opioid stops a person from breathing, and opioid withdrawal, when a person who is physically dependent goes without. It ends with starting or continuing OAT in hospital. Opioid pharmacology, respiratory depression from prescribed opioids and OAT during acute pain are covered in Chapter 5 (sections 5.4 and 5.5) and are not repeated here.

The Unregulated Drug Supply

Section 11.1 introduced the unregulated drug supply, also called the toxic drug supply. A person buying from it cannot know what a dose contains or how strong it is. The Council of Chief Medical Officers of Health (2026) describes the drugs in this market as

contaminated and highly toxic, so the risk of overdose is extremely high. Fentanyl and fentanyl analogues, which are chemically related compounds, are involved in most opioid toxicity deaths, and many of these deaths also involve a stimulant (section 11.1).

Non-opioid sedatives are increasingly mixed into the opioid supply. Benzodiazepines contributed to about a third of opioid toxicity deaths in 2024 (section 11.1). Health Canada's Drug Analysis Service identified xylazine, a veterinary sedative not approved for human use in Canada, in sharply rising numbers of seized samples, from 5 in 2018 to 1,350 in 2022, usually together with fentanyl (Health Canada, 2023b). Medetomidine, another veterinary sedative, has since appeared in the supply as well (Council of Chief Medical Officers of Health, 2026; Simcoe Muskoka District Health Unit, 2026).

These mixtures matter at the bedside. Naloxone works on opioids only. It does not reverse sedation from benzodiazepines, alcohol or other non-opioid drugs (Health Canada, 2024a), and an Ontario public health alert states that it does not reverse medetomidine (Simcoe Muskoka District Health Unit, 2026). A person may therefore start breathing again after naloxone yet stay deeply sedated. Ontario public health alerts advise that naloxone is still given whenever opioid exposure is suspected, because medetomidine is almost always found with fentanyl (Simcoe Muskoka District Health Unit, 2026; York Region Public Health, 2026).

Recognizing Opioid Toxicity

Opioid toxicity, often called an opioid overdose or poisoning, is a life-threatening depression of breathing and consciousness caused by opioids. The nurse looks for this cluster of cues (Government of Ontario, 2026; Health Canada, 2024a):

- **Consciousness:** cannot be woken, or does not respond to a loud voice or a firm shake of the shoulders; the body may be limp.
- **Breathing:** slow, shallow or absent, sometimes with snoring or gurgling sounds as the airway obstructs.
- **Pupils:** very small (pinpoint).
- **Skin and colour:** pale, cold or clammy skin; blue, grey or purple lips and nail beds.
- **Other cues:** vomiting; slow or absent pulse.

Cyanosis is a late sign and can be harder to see on darker skin. The nurse checks the lips, gums, nail beds and the inside of the lower eyelids, and does not wait for a colour change before acting (Chapter 12).

Opioid toxicity also happens in hospital. In interviews with 24 people in Toronto and Ottawa who used drugs and were living with human immunodeficiency virus (HIV) or hepatitis C, many said they had used non-prescribed substances while admitted, to cope with withdrawal, untreated pain, boredom or loneliness, and most tried to hide this use (Strike et al., 2020). Hidden use often happens alone, behind a closed bathroom door. A patient who has been in the bathroom for a long time, or who is found with drug equipment and deep sleepiness, needs an immediate check. The aim is safety, not punishment; patients who expect judgment are less likely to tell the nurse what they took.

Responding to Opioid Toxicity

Opioid toxicity is an airway and breathing emergency. In hospital, the nurse follows the code blue or rapid response policy (Chapter 6) and the naloxone order or medical directive. The sequence is:

1. **Check responsiveness:** shout the patient's name and shake the shoulders; check breathing and pulse.

2. **Call for help:** activate the code blue or rapid response team, as policy directs, and ask for the emergency cart and naloxone.

3. **Support breathing:** open the airway and ventilate with a bag-valve-mask and oxygen. In the community, rescue breaths with a barrier are used. If there is no pulse, start cardiopulmonary resuscitation (CPR) (Figure 11.1).

4. **Give naloxone:** by the intramuscular or intranasal route, or intravenously in hospital when the order or medical directive allows. Naloxone can begin to work within about 2 minutes. If there is no response after 2 to 3 minutes, a further dose is given, and doses are repeated as directed while ventilation continues (Health Canada, 2024a; Ontario Ministry of Health, 2026).

5. **Monitor closely:** the duration of action of most opioids is longer than that of naloxone, so sedation and slow breathing can return after the patient wakes (Emergent BioSolutions Canada, 2026). This return is called **recurrent toxicity**. Ontario's naloxone program warns that this is a particular risk with fentanyl and carfentanil (Ontario Ministry of Health, 2026). The nurse watches sedation, breathing and oxygen saturation at the frequency the order or policy sets, and escalates any return of drowsiness at once.

Naloxone can cause sudden **precipitated withdrawal** in a person who is physically dependent on opioids: body aches, vomiting, diarrhea, sweating, fever, a racing heart, high blood pressure, and agitation or aggression (Emergent BioSolutions Canada, 2026). The nurse turns a vomiting patient onto the side, stays calm and explains what happened.

After the event, the patient needs a trauma-informed response (Chapter 2). Many people wake frightened, ashamed or in withdrawal. The nurse speaks without blame, treats withdrawal and pain promptly through the team, and offers an addiction medicine consultation. The nurse documents the time found, the findings, every naloxone dose and route, ventilation, the response and the people notified (Chapter 1).

Figure 11.1 Ventilating with a bag-valve-mask during resuscitation training. In opioid toxicity, supporting breathing comes first while naloxone takes effect.

CLINICAL SAFETY

Responding to Opioid Toxicity on the Unit

- Treat an unresponsive patient with slow or absent breathing as opioid toxicity until proven otherwise, whatever the patient's history.
- Call for help first: activate the code blue or rapid response team by policy.
- Airway and ventilation come first. Bag-valve-mask ventilation with oxygen keeps the patient alive while naloxone takes effect, and it also treats breathing problems that naloxone cannot reverse, such as sedation from benzodiazepines or veterinary sedatives.
- Know where naloxone and the bag-valve-mask are kept on your unit before you need them.
- Give naloxone by the route and dose in the order, medical directive or policy. Repeat as directed if breathing does not improve within 2 to 3 minutes.
- Expect that sedation may return as naloxone wears off. Continue monitoring for as long as the order or policy requires, and never leave a recently reversed patient unobserved.
- After reversal, use a calm, trauma-informed approach. Explain what happened, manage withdrawal symptoms through the team, and avoid blame or threats of discharge.

Table 11.3 Opioid toxicity or opioid withdrawal? Comparing the cues (Emergent BioSolutions Canada, 2026; Government of Ontario, 2026; Health Canada, 2024a; Wesson & Ling, 2003)

Feature	Opioid toxicity	Opioid withdrawal
Level of consciousness	Very drowsy to unrousable; may not respond to voice or a firm shake	Awake and alert; often restless, anxious or irritable
Breathing	Slow, shallow or absent; snoring or gurgling	Normal or fast; yawning is common
Pupils	Very small (pinpoint)	Enlarged
Skin	Pale, cold or clammy; blue, grey or purple lips and nail beds	Sweating, gooseflesh; runny nose and watery eyes
Heart rate and blood pressure	Pulse may be slow or absent; blood pressure may fall	Heart rate often fast; blood pressure may rise
Gastrointestinal	Vomiting with a risk of aspiration	Nausea, cramps, vomiting and diarrhea
Immediate nursing priority	Call for help, support ventilation and give naloxone	Assess with a validated scale, report and treat symptoms as ordered

Opioid Withdrawal

Opioid withdrawal is the set of symptoms that follows stopping or sharply reducing opioids in a person who is physically dependent on them. With short-acting opioids, symptoms begin within hours of the last dose. Early cues include yawning, a runny nose, watery eyes, sweating, anxiety and cravings. As withdrawal progresses, the pupils enlarge, gooseflesh appears, and muscle and joint aches, tremor, cramps, nausea, vomiting and diarrhea follow (Table 11.3).

The **Clinical Opiate Withdrawal Scale (COWS)** is an 11-item scale that a clinician completes to give a consistent rating of withdrawal and to follow it over time (Wesson & Ling, 2003). It combines observed signs, such as resting pulse, pupil size, tremor and restlessness, with what the patient reports, such as aches and stomach upset. The nurse scores only findings caused by withdrawal, not those explained by recent activity, a cold or pre-existing pain. The total places withdrawal in a severity band from mild to severe, which guides medication timing and shows whether treatment is working. Hospitals set how often COWS is repeated.

Opioid withdrawal is intensely uncomfortable. Its main dangers come from what it leads to. Persistent vomiting and diarrhea that go untreated can cause dehydration and a high blood sodium level, and deaths from these complications have been reported (Darke et al., 2017; Chapter 3). Untreated withdrawal is one reason patients leave hospital before treatment is complete (Chapter 5, section 5.5). A person who returns to use after days without opioids has lower tolerance, which raises the risk of overdose (Khan et al., 2024). Withdrawal from medetomidine is a newer concern: an Ontario public health alert describes rapid heart rate, severe hypertension and vomiting that can be life-threatening and need medical treatment (Simcoe Muskoka District Health Unit, 2026). The nurse reports severe or worsening withdrawal promptly.

Starting or Continuing OAT in Hospital

A hospital stay is a chance to start **opioid agonist treatment (OAT)**, a long-acting opioid that prevents withdrawal and reduces cravings (Chapter 5, section 5.5). Canada's 2024 national guideline recommends buprenorphine and methadone as standard first-line options, with slow-release oral morphine as a second-line option. It recommends against offering withdrawal management alone, without ongoing treatment, and states that psychosocial treatment should never be a condition of receiving OAT (Yakovenko et al., 2024).

For a patient already on OAT, the team confirms the current dose and the time of the last dose with the community pharmacy before giving the first hospital dose (Chapter 5, section 5.5).

Buprenorphine is started differently from other opioids. In a **standard induction**, the patient stops other opioids and waits until withdrawal is clearly present, often measured with COWS, before the first dose. Starting too early can cause precipitated withdrawal. With fentanyl in the supply, precipitated withdrawal has been reported even in patients already in moderate to severe withdrawal (Randhawa et al., 2020). **Low-dose buprenorphine initiation**, sometimes called microdosing, is an alternative: very small, gradually increasing doses are started while the patient continues their usual opioid, which is stopped once an effective dose is reached. Early Canadian reports found it well tolerated but called for more research (Randhawa et al., 2020), and British Columbia's provincial guideline includes low-dose initiation as a way to avoid a period of withdrawal before treatment starts (British Columbia Centre on Substance Use [BCCSU], 2023). The Going Deeper box explains why it works.

Buprenorphine is also available as an extended-release injection given under the skin once a month by a health care professional (Indivior UK, 2025). Methadone no longer requires a special federal exemption to prescribe; Health Canada removed this requirement in 2018. Prescribers must still meet provincial or territorial rules and those of their regulatory college (Health Canada, 2018d).

GOING DEEPER

Buprenorphine, Precipitated Withdrawal and Low-Dose Starts

Required for RN students; optional for PN students.

Buprenorphine is a **partial agonist** at the mu-opioid receptor (Indivior UK, 2025). It switches the receptor on, but only part of the way, so its effect levels off as the dose rises. This ceiling is one reason it is safer than full agonists. Buprenorphine also has very high affinity for the mu receptor: it binds more tightly than full agonists such as fentanyl, heroin or hydromorphone (Randhawa et al., 2020).

These two properties explain precipitated withdrawal. If buprenorphine is given while a full agonist still occupies the receptors, it pushes the full agonist off and replaces a strong effect with a weaker one. To the brain, the sudden drop feels like abrupt withdrawal, often more severe than withdrawal that develops gradually. Standard induction avoids this by waiting until enough full agonist has left the receptors that the patient is already in withdrawal. At that point buprenorphine relieves symptoms instead of causing them.

Fentanyl complicates this timing. It is highly fat-soluble and moves into body tissues. With repeated use, it is stored there and released slowly, so it leaves the body more gradually than its short effect would suggest (Randhawa et al., 2020). Fentanyl may still be occupying receptors even when the patient feels withdrawal, and the first buprenorphine dose can then precipitate it.

Low-dose initiation takes another approach. Very small doses of buprenorphine are given while the patient keeps taking the full agonist. Each small dose occupies only a few receptors, too few to displace the full agonist enough to trigger withdrawal. Over several days the buprenorphine doses increase and overlap, gradually taking over the receptors. Once buprenorphine reaches an effective level, the full agonist is stopped (Randhawa et al., 2020). Protocols vary between hospitals; the nurse follows the prescribed schedule exactly, watches for withdrawal and oversedation, and reports both.

MEDICATIONS

Naloxone and Opioid Agonist Treatment in Canada

- **Naloxone nasal spray (NARCAN):** a single-use device delivering 4 mg in 0.1 mL into one nostril. Ontario take-home kits contain two devices (Emergent BioSolutions Canada, 2026; Ontario Ministry of Health, 2026).
- **Injectable naloxone:** Ontario take-home kits hold two 1 mL doses of naloxone 0.4 mg/mL, supplied in ampoules, vials or prefilled syringes, for intramuscular injection (Ontario Ministry of Health, 2026).
- Since Health Canada changed its prescription status in March 2016, naloxone for emergency use in an opioid overdose has been available without a prescription. Participating Ontario pharmacies supply kits free, without a health card (Health Canada, 2024a; Ontario Ministry of Health, 2026; Chapter 5, section 5.4).
- **Buprenorphine-naloxone sublingual tablets:** first-line OAT (Yakovenko et al., 2024), dissolved under the tongue. The naloxone has no effect when taken as directed; it is included to deter injection (Indivior UK, 2021).
- **Buprenorphine extended-release injection (Sublocade):** given under the skin by a health care professional only, never intravenously (Indivior UK, 2025).
- **Methadone oral solution:** first-line OAT, taken by mouth as a liquid (Yakovenko et al., 2024).
- **Slow-release oral morphine (Kadian):** second-line OAT; a once-daily capsule whose pellets are swallowed whole (Alberta Health Services, 2026; Yakovenko et al., 2024).

OAT doses are set by the prescriber and are not given in this book.

11.5 Stimulants, Cannabis and Other Substances

Stimulants and cannabis bring people to hospital in different ways. Stimulant toxicity can be a medical emergency, whereas cannabis more often contributes quietly to other problems, such as persistent vomiting or interactions with anesthesia.

Stimulants

Cocaine and methamphetamine are the stimulants most often seen in Canadian acute care. Stimulants are involved in many toxic drug deaths, often together with opioids, and in 2025 stimulant-related deaths outnumbered opioid-related deaths in several provinces and territories, including Ontario (section 11.1).

Stimulant toxicity is an exaggerated sympathetic ("fight or flight") response to a stimulant. Its cues include agitation, a fast or irregular heartbeat, high blood pressure, rapid breathing, high body temperature, enlarged pupils and psychosis. Seizures, coma, and liver or kidney failure can follow (Health Canada, 2023a). Chest pain needs urgent assessment, because stimulants strain the heart; heart attack, stroke and sudden cardiac death are among their serious harms (Health Canada, 2023a). Hyperthermia is especially dangerous: it can progress quickly to failure of several organs and to cardiac arrest (NSW Health, 2024). Psychosis is also common with methamphetamine; Palis and MacDonald (2023), citing an earlier review, report that up to 40% of people who use it may experience psychosis. A patient with paranoia or hallucinations is frightened, not simply difficult. The nurse keeps a safe distance, speaks simply and watches for delirium (Chapter 8).

Nursing care focuses on safety and early escalation:

- Provide a quiet, low-stimulation space. Speak calmly, explain each step and keep the patient's dignity.
- Check temperature often and start cooling measures as ordered.
- Apply cardiac monitoring and continuous pulse oximetry as ordered, and repeat vital signs often.
- Give benzodiazepines for agitation as ordered; early sedation reduces the heat the body produces (NSW Health, 2024).
- Report chest pain, a temperature that keeps rising, seizures, confusion or a falling level of consciousness at once, using rapid response criteria (Chapter 6).
- Avoid physical restraint wherever possible. Struggling against restraint in severe agitation can precipitate cardiac arrest (NSW Health, 2024). De-escalation and restraint alternatives are covered in Chapter 8.

No medication has been approved in Canada to treat stimulant use disorder (Palis & MacDonald, 2023). Non-drug approaches, such as **contingency management**, which gives small tangible rewards for meeting treatment goals, may be offered, and some clinicians prescribe stimulants as a harm reduction measure (Palis & MacDonald, 2023). Because the stimulant supply may also contain opioids, the nurse teaches patients who use stimulants about naloxone as well.

Cannabis

Non-medical cannabis has been legal in Canada since October 17, 2018, when the **Cannabis Act** took effect (Health Canada, n.d.). Its main psychoactive compound, tetrahydrocannabinol (THC), impairs the skills needed to drive and raises the heart rate. High doses can cause anxiety and short-lived psychotic symptoms (Health Canada, 2018b).

The Lower-Risk Cannabis Use Guidelines, developed in Canada and updated in 2022, give people practical ways to reduce harm (Fischer et al., 2022). In summary, not using is the only sure way to avoid risk. People who choose to use can delay starting until after late adolescence, choose lower-THC products from the legal market, avoid smoking and deep inhalation, avoid daily or near-daily use, and never drive while impaired. People who are planning a pregnancy, pregnant or breastfeeding are advised not to use. The guidelines also advise caution when combining cannabis with alcohol or other psychoactive drugs, and they identify groups at higher risk of harm, including people with a personal or close family history of psychosis, people with a mood or substance use disorder, people with existing heart and blood vessel risks, and older adults (Fischer et al., 2022). This matters in acute care, where many older patients already take sedating medications.

Cannabinoid hyperemesis syndrome (CHS) is repeated episodes of severe nausea, vomiting and abdominal pain in people who have used cannabis heavily, usually daily, for a long time (King & Holmes, 2015). A telling cue is that patients take repeated hot showers or baths because the heat eases their symptoms. Standard antiemetics often fail. The team first rules out dangerous causes such as bowel obstruction, perforation or pancreatitis. The nurse monitors fluid balance, because vomiting can cause dehydration and acute kidney injury (Chapter 3). Lasting remission requires stopping cannabis (King & Holmes, 2015), so the nurse explains the link in a respectful, non-judgmental way.

Health Canada (2018c) estimates that about 1 in 10 people who use cannabis develop an addiction to it (cannabis use disorder), and up to 1 in 2 of those who use it daily or near-daily. People who use cannabis regularly may develop withdrawal once admitted to hospital; it usually starts within 1 or 2 days and can last a few weeks. Its cues include irritability, anxiety, poor sleep, low appetite, restlessness, cravings and low mood (Health Canada, 2018c). The nurse recognizes these as withdrawal, not as a personality problem, and reports them. Asking about cannabis use before surgery is part of the preoperative assessment (Chapter 7).

Other Substances

Benzodiazepine-related drugs and veterinary sedatives found in the unregulated supply (section 11.4) can cause deep, prolonged sedation that naloxone does not reverse (Health Canada, 2024a; Simcoe Muskoka District Health Unit, 2026). A patient may need airway support and close monitoring for hours. The nurse asks every patient who uses drugs what they take, how often and when they last used, because unexpected sedation or withdrawal can follow.

11.6 Harm Reduction and Transitions

Principles of Harm Reduction

Harm reduction is a set of practical, evidence-based approaches that reduce the health and social harms of substance use without requiring a person to stop using. It begins where the person is. The nurse respects the patient's goals, offers choices and keeps the door open to treatment without making care depend on it. Canada's 2024 opioid use disorder guideline makes a strong recommendation that harm reduction be offered across the whole continuum of care, including sterile drug use supplies, overdose prevention education and take-home naloxone (Yakovenko et al., 2024).

Several services make up this continuum:

- **Supervised consumption sites:** places where people use drugs they bring with them, in the presence of trained staff who respond to overdoses. According to Health Canada (2026d), Canadian and international evidence shows that these services save lives and link people to social services and treatment. Because people do not have to hurry or use alone, accidental overdose is also less likely.
- **Naloxone distribution:** free take-home kits and training for people at risk and their families and friends (Ontario Ministry of Health, 2026).
- **Sterile supplies and safe disposal:** sterile needles and other equipment, which help reduce the spread of infections such as HIV (Health Canada, 2026d).
- **Drug checking:** services that test a sample to show what it contains, so a person can decide whether and how to use it (Health Canada, 2026d; Figures 11.3 and 11.4; Figure 11.2).



Figure 11.2 A rapid fentanyl test strip and interpretation guide used in community and hospital harm-reduction drug checking (one red line = positive for fentanyl; two red lines = negative). (credit: "Fentanyl-test-strip" by WikiLinuz/Wikimedia Commons, CC BY-SA 4.0)

Figure 11.3 A harm reduction table at a community event in Portland, Oregon, offering free naloxone and fentanyl test strips. (credit: "Harm Reduction Drug Testing Table" by Sarahmirk/Wikimedia Commons, CC BY-SA 4.0)

Harm reduction services also connect people with health care. Supervised consumption sites may offer wound care, testing for HIV, hepatitis C and sexually transmitted infections, and referral to treatment (Health Canada, 2026d). For a patient admitted with an injection-related infection, these services may be where wound care and testing continue after discharge.

Harm reduction also belongs in hospital. Patients who use drugs in hospital often do so to cope with untreated withdrawal or pain, and staff responses vary widely when policy is unclear (Strike et al., 2020). The nurse treats withdrawal and pain promptly, asks about use without judgment, requests an addiction medicine consultation, and offers naloxone and harm reduction supplies according to hospital policy. Honest conversation keeps patients safer than hidden use, because the nurse can then check on them and act quickly. Chapter 5, section 5.5, covers how to respond when a patient wants to leave early.

Policy in Canada (2026)

Drug policy in Canada changes often and differs between provinces and territories. This book describes it as of October 2026.

Figure 11.4 A public needle disposal box in a parking lot in Denver, Colorado. Safe disposal sites for used needles are part of harm reduction services. (credit: "Needle disposal box" by Jeffrey Beall/Wikimedia Commons, CC BY 4.0)

Federal law: The *Controlled Drugs and Substances Act* prohibits possessing a controlled substance. An organization that wants to operate a supervised consumption site needs an exemption from Health Canada under section 56.1 of this Act. Applications include broad community consultation, and exemptions are generally granted for 1 year (Health Canada, 2018a). Under a separate class exemption, provinces and territories may set up overdose prevention sites to meet urgent public health needs (Health Canada, 2026d).

Ontario: The *Community Care and Recovery Act, 2024*, passed on December 4, 2024, as part of a larger bill, bars anyone from establishing or operating a supervised consumption site less than 200 metres from a school, a licensed child care centre or an EarlyON Child and Family Centre. The prohibition took effect on April 1, 2025, and the Act also requires provincial approval before a municipality or local board applies for a federal supervised consumption exemption (*Community Care and Recovery Act, 2024*). In Toronto, at least five sites had to stop operating at their locations by March 31, 2025 (Toronto Public Health, 2025). Ontario is funding Homelessness and Addiction Recovery Treatment (HART) Hubs. These bring together primary care, addiction services such as RAAM, withdrawal management, supportive housing and social services; several replaced former consumption sites (Ontario Ministry of Health, 2025). Toronto Public Health (2025) notes that the HART Hub model does not include supervised consumption, needle exchange or safer supply services.

British Columbia: From January 31, 2023, a federal exemption allowed adults in British Columbia to possess a small total amount (up to 2.5 g) of certain illegal drugs for personal use without being arrested or charged. In May 2024, possession in public spaces was removed from the exemption (Health Canada, 2024b). The exemption expired on January 31, 2026, and was not renewed (Government of British Columbia, 2026).

Because services open, close and change, the nurse checks which local services exist before teaching a patient about them.

Leaving Hospital Safely

The days after discharge are a period of high risk. During a hospital stay, a person may use less or not at all, or their OAT may be interrupted, so tolerance falls. If they return to their usual amount, an overdose becomes more likely (Khan et al., 2024). A hospital stay can also disconnect people from their usual supply and routines, which may lead to using alone. In a British Columbia study of hospital stays from 2015 to 2019, patients who left before medically advised had a higher rate of overdose in the following 30 days than those discharged on their physician's advice, even after adjustment for other differences (Khan et al., 2024).

The nurse starts discharge planning on admission rather than on the last day, because patients who use drugs sometimes leave suddenly (Chapter 5, section 5.5). Teaching works best when it is hands-on: the nurse opens a kit with the patient, names each item and asks the patient to show the steps back. Discharge planning includes:

- **Take-home naloxone:** a kit and hands-on teaching for the patient and the people they live or use with (Ontario Ministry of Health, 2026).
- **Never using alone:** if the patient does use alone, the **National Overdose Response Service (NORS)** offers a confidential, non-judgmental phone and text line (1-888-688-6677), available 24 hours a day from anywhere in Canada, that supports people while they use and provides overdose response (Health Canada, 2026b; National Overdose Response Service, n.d.).

- **Drug checking**, where it is available locally (Health Canada, 2026d).
- **OAT continuity:** a prescription that bridges to the next appointment, a call or written communication to the community pharmacy and prescriber about the last dose given, and a plan for the first dose after discharge (Chapter 5, section 5.5).
- **Follow-up:** a RAAM clinic, primary care provider or addiction service. In Ontario, many RAAM clinics accept people without an appointment or referral (section 11.2).
- **Housing and income supports:** a social work referral, because housing and income affect recovery and safety.
- **Indigenous and culturally specific supports:** an Indigenous patient navigator or liaison, or community programs, if the patient wishes (Chapter 2). The Hope for Wellness Help Line (1-855-242-3310) offers counselling and crisis support to Indigenous people across Canada, 24 hours a day, in several languages including Cree, Ojibway and Inuktitut (Health Canada, 2026b).

The federal *Good Samaritan Drug Overdose Act* has been law since May 4, 2017. When someone calls 9-1-1 or the local emergency number about an overdose, the Act offers some legal protection to the caller, the person who overdosed and others present when help arrives; the caller is protected whether they stay or leave. It shields them from charges of simple possession of a controlled substance, and from charges for breaking conditions linked to simple possession, such as those of probation, parole or pre-trial release. It does not cover outstanding warrants, drug production or trafficking, or other crimes (Health Canada, 2026a).

SCOPE IN PRACTICE

Naloxone, Withdrawal Monitoring and OAT

CNO's Scope of Practice standard explains nursing roles through authority, competence and context (College of Nurses of Ontario, 2025; Chapter 1, section 1.3).

- **Authority:** In hospital, RNs and RPNs give naloxone under an order or a medical directive, according to policy. Naloxone is also available without a prescription, and the NARCAN product monograph and Health Canada state that a bystander may give the nasal spray in an emergency (Emergent BioSolutions Canada, 2026; Health Canada, 2024a). Nurses give OAT and withdrawal medications as ordered. Physicians and, where provincial or territorial rules allow, nurse practitioners (NPs) prescribe OAT; prescribers must meet provincial or territorial and regulatory college requirements (Health Canada, 2018d).
- **Competence:** The nurse needs the knowledge and skill to recognize opioid toxicity, ventilate with a bag-valve-mask, give naloxone, and monitor withdrawal with a validated tool such as COWS.
- **Context:** Employer policy sets who manages buprenorphine starts and how often scores are repeated. When a patient's condition or needs change, the RPN consults the RN.
- **Every nurse acts:** Any nurse who finds a patient with slow or absent breathing calls for help, ventilates and gives naloxone by policy, whoever is assigned to the patient.

Employer policy and the province or territory matter. CNO's revised Scope of Practice and Medication standards take effect March 1, 2027 (College of Nurses of Ontario, 2026).

PATIENT EDUCATION

Going Home Safer

The nurse teaches the patient, and anyone they live or use with, to:

- Carry a naloxone kit. Participating pharmacies in Ontario give kits free, with no health card or prescription needed.
- Recognize an overdose: cannot be woken, slow or no breathing, snoring or gurgling, tiny pupils, and blue or grey lips or nail beds.
- Respond: shout and shake, call 9-1-1, give naloxone, give rescue breaths or chest compressions, and repeat naloxone after 2 to 3 minutes if there is no change. Stay until help arrives, because the overdose can return.
- Know that the *Good Samaritan Drug Overdose Act* protects people who call for help from charges of simple possession.
- Avoid using alone. If alone, call or text NORS at 1-888-688-6677.
- Remember that tolerance is lower after a hospital stay. Start with a much smaller amount, go slowly, and use drug checking where available.
- Know the OAT plan: the pharmacy, the time of the next dose and the follow-up appointment.
- Keep the numbers for the clinic, the pharmacy and a crisis line.

PRACTICE STORY

"He Came Back"

Names and details are fictional; this is a composite story.

Nurse: Ananya Nadarajah, RPN. Years in practice: 4. Setting: medical unit, community hospital, Ontario.

Mr. Dale Whitford was 36 and on his third day of intravenous (IV) antibiotics for cellulitis of his forearm, at a site where he had injected. He had told the admitting team he used fentanyl, and he had declined to start OAT. That afternoon I noticed his bathroom door had been closed for a long time. I knocked twice and got no answer.

I found him slumped against the wall, grey around the lips, with a few snoring breaths a minute. I shouted his name and shook his shoulders. Nothing. I pulled the bathroom call bell and yelled for help. My RN, Marc, called the rapid response team and brought the emergency cart while I tilted Dale's head back and started ventilating with a bag-valve-mask on oxygen.

Our hospital has a naloxone medical directive. Marc gave the first dose into Dale's thigh while I kept ventilating. After about 3 minutes there was still no change, so Marc gave a second dose. A minute later Dale coughed, pushed the mask away and swore at us. He was sweating and shaking, and he vomited. I rolled him onto his side.

The rapid response team took over. Once Dale was back in bed, he wouldn't look at me. "Go ahead," he said. "Kick me out." I told him nobody was kicking him out, that I was glad he was alive, and that we would stay close for the next few hours because the fentanyl could outlast the naloxone. He was drowsy again 50 minutes later, and the team gave another dose.

The next morning, he asked me what the addiction medicine team could actually do. I paged them. By the end of my shift, he had started a low-dose buprenorphine plan, and he had a naloxone kit in his bag.

Reflect: Which of Priya's actions were within her authority as an RPN, and when did the situation call for the RN and the rapid response team? How did Priya's words after the event affect Dale's choice the next morning?

Chapter 11 Summary

Introduction

- About 540 people are hospitalized in Canada every day for harm from alcohol or other drugs, and alcohol accounts for more than half of these stays (CIHI, 2026).
- Nurses on every unit care for people who use substances; this chapter is the book's home for substance use in hospital.

11.1 Substance Use, Stigma and Health

- Substance use runs along a continuum; a substance use disorder is diagnosed by at least 2 of 11 criteria over 12 months, graded mild, moderate or severe.
- Tolerance and withdrawal alone, from medicines taken as prescribed, do not mean a disorder.
- Canada recorded 7,146 opioid-related deaths in 2024 and 5,608 in 2025 (15 per day); the toxic drug supply keeps changing.
- Trauma, poverty, housing, pain and, for some Indigenous communities, colonization and residential schools drive harm; culture and community are sources of healing.
- Stigma leads to delayed care, poorer care and leaving hospital early; person-first, clinical language is one remedy.

11.2 Screening and Brief Intervention in Hospital

- Every patient is asked about alcohol and other drugs at admission, privately and in the same neutral way.
- Canada's 2026 guideline update screens with weekly and per-occasion drinks compared with *Canada's Guidance on Alcohol and Health*; earlier tools such as the AUDIT-C and single-question screens may still appear on admission forms.
- A positive screen leads to a brief, motivational conversation and referral, such as an addiction medicine consult or a RAAM clinic.

11.3 Alcohol Withdrawal

- Withdrawal reflects an overexcited nervous system after the brain adapts to heavy drinking; repeated withdrawals worsen through kindling.

- Minor symptoms start within 6 to 12 hours; hallucinosis, seizures and delirium tremens follow in typical windows.
- PAWSS predicts risk at admission; the CIWA-Ar measures current severity but needs a patient who can communicate and is not delirious.
- Benzodiazepines, usually symptom-triggered, are first-line, with supportive care, electrolyte replacement and prompt escalation.
- Thiamine is given before glucose to prevent Wernicke encephalopathy, which rarely shows its full triad.
- Naltrexone or acamprosate, psychosocial care and follow-up treat the underlying alcohol use disorder.

11.4 Opioid Toxicity and Withdrawal

- The unregulated drug supply is dominated by fentanyl and fentanyl analogues and increasingly contains non-opioid sedatives, such as benzodiazepine-related drugs and veterinary sedatives, that naloxone does not reverse.
- Opioid toxicity presents as unresponsiveness, slow or absent breathing, pinpoint pupils and cyanosis; cyanosis can be harder to see on darker skin, so the nurse checks the lips, gums, nail beds and inner eyelids.
- The response is to call for help, ventilate, give naloxone per order or medical directive, repeat as directed, and monitor closely, because most opioids outlast naloxone.
- Opioid withdrawal causes yawning, enlarged pupils, gooseflesh, aches and gastrointestinal upset; COWS rates its severity, and untreated withdrawal raises the risk of leaving hospital and of overdose.
- Buprenorphine and methadone are first-line OAT. Buprenorphine starts either with standard induction, after withdrawal begins, or with low-dose initiation.

11.5 Stimulants, Cannabis and Other Substances

- Stimulant toxicity causes agitation, tachycardia, hypertension, hyperthermia, chest pain, seizures and psychosis; the nurse escalates early, cools, gives sedation as ordered and avoids physical restraint.
- No medication is approved in Canada for stimulant use disorder.
- Cannabis has been legal since October 17, 2018; the Lower-Risk Cannabis Use Guidelines describe ways to reduce harm.
- Cannabinoid hyperemesis syndrome causes repeated vomiting with heavy long-term use, is eased by hot showers and resolves only when cannabis stops.
- Cannabis withdrawal usually starts within 1 or 2 days and causes irritability, anxiety, poor sleep and low appetite.

11.6 Harm Reduction and Transitions

- Harm reduction meets people where they are and is recommended across the continuum of care, including in hospital.
- Supervised consumption sites operate under a federal section 56.1 exemption. Ontario's 2024 law bars sites within 200 metres of schools and child care centres, and the province is funding HART Hubs. British Columbia's decriminalization exemption ended on January 31, 2026.
- Overdose risk rises after discharge because tolerance falls during a hospital stay.
- Discharge planning includes take-home naloxone, never using alone or calling NORS, drug checking, OAT continuity, RAAM follow-up, and social and culturally specific supports.
- The Good Samaritan Drug Overdose Act protects people who call for help from charges of simple possession.

Key Terms (35)

alcohol withdrawal: the signs and symptoms of an overexcited nervous system that follow stopping or sharply reducing heavy, prolonged alcohol use.

alcoholic hallucinosis: hallucinations during alcohol withdrawal in a person who otherwise remains oriented.

AUDIT-C: a short alcohol screening tool built from the consumption questions of the Alcohol Use Disorders Identification Test.

brief intervention: a short, structured conversation, based on motivational interviewing, that helps a person consider their substance use and choose a change.

cannabinoid hyperemesis syndrome (CHS): repeated episodes of severe nausea, vomiting and abdominal pain in people with heavy long-term cannabis use, often eased by hot showers and resolved by stopping cannabis.

Cannabis Act: the federal law under which non-medical cannabis has been legal and regulated in Canada since October 17, 2018.

CIWA-Ar: the Clinical Institute Withdrawal Assessment for Alcohol, revised; a 10-area scale that measures the current severity of alcohol withdrawal.

Clinical Opiate Withdrawal Scale (COWS): an 11-item clinician-rated scale that rates the severity of opioid withdrawal and tracks it over time.

contingency management: a non-drug treatment that gives small tangible rewards for meeting treatment goals.

delirium tremens: the most severe form of alcohol withdrawal, with delirium, hallucinations, agitation and autonomic overactivity, usually beginning 48 to 72 hours after the last drink; also called alcohol withdrawal delirium.

drug checking: a service that tests a drug sample to show what it contains.

Good Samaritan Drug Overdose Act: a 2017 federal law that, when someone calls for emergency help with an overdose, protects the caller and others at the scene from charges of simple possession and related breaches of conditions.

harm reduction: practical, evidence-based approaches that reduce the harms of substance use without requiring a person to stop using.

kindling: the tendency for each episode of alcohol withdrawal to be more severe than the last after repeated cycles of heavy drinking and withdrawal.

Korsakoff syndrome: a lasting memory disorder, often following untreated Wernicke encephalopathy, in which the person cannot form new memories.

low-dose buprenorphine initiation: starting buprenorphine with very small, gradually increasing doses while the usual opioid continues until an effective dose is reached; also called microdosing.

naloxone: an opioid antagonist that temporarily reverses opioid toxicity; it does not reverse non-opioid sedatives.

National Overdose Response Service (NORS): a confidential national phone and text line that provides overdose response for people who use drugs alone.

opioid agonist treatment (OAT): treatment of opioid use disorder with a long-acting opioid, such as buprenorphine or methadone, that prevents withdrawal and reduces cravings.

opioid toxicity: a life-threatening depression of breathing and consciousness caused by opioids; often called an opioid overdose or poisoning.

opioid withdrawal: the symptoms that follow stopping or sharply reducing opioids in a person who is physically dependent on them.

partial agonist: a drug that activates a receptor only part of the way, so its effect levels off as the dose rises.

PAWSS: the Prediction of Alcohol Withdrawal Severity Scale; a 10-item tool that estimates a hospitalized patient's risk of complicated alcohol withdrawal.

person-first language: wording that names the person before a condition, such as "person who uses drugs."

precipitated withdrawal: sudden, often severe withdrawal triggered when naloxone or buprenorphine displaces a full opioid agonist from its receptors.

recurrent toxicity: the return of sedation and slow breathing after naloxone wears off, because most opioids act longer than naloxone.

standard induction: starting buprenorphine after other opioids have been stopped and withdrawal is clearly present.

stigma: negative attitudes, beliefs and behaviours directed at a group because of their situation, expressed as stereotypes, prejudice and discrimination at self, social and structural levels.

stimulant toxicity: an exaggerated sympathetic response to a stimulant, with agitation, fast heart rate, high blood pressure, high body temperature and possible seizures or psychosis.

substance use disorder: a health condition in which a person keeps using a substance despite significant problems linked to that use, diagnosed when at least 2 of 11 criteria occur within 12 months and graded mild, moderate or severe.

supervised consumption site: a service where people use drugs they bring with them in the presence of trained staff who can respond to an overdose; it operates under a federal exemption.

symptom-triggered treatment: giving withdrawal medication when a patient's withdrawal score reaches a set threshold, rather than on a fixed schedule.

unregulated drug supply: drugs made and sold outside legal and quality controls, often containing fentanyl and other toxic substances of unknown strength.

Wernicke encephalopathy: an acute, potentially fatal brain disorder caused by thiamine deficiency, classically with confusion, ataxia and abnormal eye movements.

withdrawal seizure: a generalized tonic-clonic seizure caused by alcohol withdrawal, usually within the first two days after the last drink.

Licensure Review & Clinical Judgment Questions (30)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Denise Arsenault (Questions 1–4): Denise Arsenault, 47, is admitted to a medical unit in Belleville, Ontario, with community-acquired pneumonia. At admission she tells the nurse she drinks about a bottle of wine every evening; her last drink was 14 hours ago. Her PAWSS score is 5. A registered practical nurse (RPN) is caring for her, with an RN on the team.

1. [CORE] Six hours later, Ms. Arsenault is restless and sweating, her hands tremble, her heart rate is 112 beats/min and she says she cannot sleep. She is oriented and denies seeing or hearing anything unusual. Which interpretation is most likely?

a. Anxiety about being admitted to hospital

b. Early alcohol withdrawal

c. An allergic reaction to her antibiotic

d. Delirium tremens

Answer: b — About 20 hours after her last drink, tremor, sweating, tachycardia, restlessness and insomnia match minor alcohol withdrawal, and her PAWSS score shows high risk (b) (section 11.3). Anxiety (a) may be present but does not explain the full pattern in a person who drinks daily; labelling it anxiety could delay treatment. An allergic reaction (c) would bring rash, hives, swelling or breathing changes, not tremor. Delirium tremens (d) usually starts 48 to 72 hours after the last drink and involves disorientation and hallucinations, which she does not have.

2. [CORE] The protocol directs the nurse to monitor Ms. Arsenault with the CIWA-Ar. Which statement about this tool is accurate?

a. It predicts, at admission, whether she is likely to go on to develop seizures or delirium tremens.

b. It can be completed from her vital signs alone.

c. A high score confirms that her symptoms are caused by alcohol withdrawal rather than by another illness.

d. It relies on her ability to describe her symptoms, so it becomes unreliable if she is delirious.

Answer: d — Much of the CIWA-Ar depends on what the patient reports, so it is not recommended once a patient is delirious or cannot communicate (d) (section 11.3). Predicting severe withdrawal is the job of PAWSS, not the CIWA-Ar (a). The scale combines observation with the patient's own report, so it cannot be completed from vital signs alone (b). It is not a diagnostic tool: pain, fever, anxiety and infection can also raise the score (c).

3. [CORE] The prescriber orders intravenous thiamine and an infusion of dextrose 5% in water for Ms. Arsenault, who has been eating poorly. Which action by the nurse is best?

a. Give the thiamine before starting the dextrose infusion.

b. Start the dextrose infusion first, then give the thiamine when it is finished.

c. Hold the thiamine until her nutrition laboratory results are back.

d. Give the thiamine only if she develops confusion or an unsteady gait.

Answer: a — Glucose metabolism uses up thiamine, so giving glucose first to a person who is deficient can deepen the deficiency and put her at risk of Wernicke encephalopathy; thiamine goes first (a) (section 11.3). Reversing the order (b) creates that risk. Thiamine is given to everyone at risk without waiting for results (c). Waiting for signs (d) is unsafe, because most patients never show the full triad and the damage may become permanent.

4. [CORE] On her third day, Ms. Arsenault is picking at the air and does not know where she is. Her heart rate is 128 beats/min, her temperature is 38.1 °C and she is sweating heavily. Which action should the RPN take first?

a. Complete a CIWA-Ar right away and give the as-needed benzodiazepine dose that her total score indicates under the protocol.

b. Apply wrist restraints so she cannot pull out her intravenous line.

c. Stay with her, keep her safe, and immediately notify the RN and call for help per the unit's rapid response criteria.

d. Document the findings and reassess her in one hour.

Answer: c — Disorientation, hallucinations, fever and tachycardia on day 3 suggest delirium tremens or another serious cause of delirium, such as worsening infection; this is deterioration that needs immediate escalation while the patient is kept safe (c) (section 11.3; Chapter 1, section 1.3; Chapter 6). The CIWA-Ar is unreliable in delirium, and medicating without escalation delays the team response (a). Restraints increase agitation and injury risk and are not a first action (b; Chapter 8). Waiting an hour (d) could allow life-threatening deterioration.

5. [CORE] Which phrases reflect the non-stigmatizing language recommended in Canadian federal guidance? Select all that apply.

a. "A person who uses drugs"

b. "His urine drug screen was clean."

c. "A recurrence of substance use"

d. "She is an alcoholic."

e. "A person with an alcohol use disorder"

f. "He is drug-seeking again."

Answer: a, c, e — Person-first, clinical terms (a, c, e) describe a person and a health condition without blame (section 11.1, Table 11.1). "Clean" (b) should be replaced by "negative test result." "Alcoholic" (d) defines the person by a condition. "Drug-seeking" (f) is a label that can lead to needed medicine being withheld; the nurse describes what the patient said and did and the need behind it.

6. [CORE] A nurse is completing the admission history for a 39-year-old patient having elective knee surgery. Which approach to alcohol screening best reflects current Canadian guidance?

a. Ask only patients who smell of alcohol, appear intoxicated or have a known history of heavy drinking.

b. Ask about alcohol only if the patient's liver enzymes are abnormal.

c. Ask every patient, privately and neutrally, how many standard drinks they have in an average week.

d. Replace questions about alcohol with a urine drug screen, which gives a more objective measure of recent use.

Answer: c — Canada's guideline recommends routine screening of all adults, now using questions about weekly and per-occasion drinking (c) (section 11.2). Selective screening (a) misses many people who drink heavily and reinforces stereotypes. Liver tests (b) are not a screening tool and can be normal in people who drink heavily. A urine drug screen (d) does not measure drinking patterns, is not a substitute for asking and needs the patient's consent.

7. [CORE] Which statement about Wernicke encephalopathy is accurate?

a. Most patients do not show all three classic signs.

b. It occurs only in people who have an alcohol use disorder.

c. Intravenous glucose should be given before thiamine to provide energy to the brain.

d. The memory loss of Korsakoff syndrome usually resolves fully within a few weeks once thiamine is given.

Answer: a — Only about 10% to 16% of patients show the full triad of confusion, ataxia and abnormal eye movements, so the nurse reports even one sign in a patient at risk (a) (section 11.3). Malnutrition, bariatric surgery, prolonged vomiting and cancer are other causes (b). Thiamine is given before glucose, not after (c). Korsakoff syndrome is a lasting memory disorder; it usually does not resolve (d).

8. [CORE] A patient admitted for cellulitis drank heavily every day until admission. The nurse knows that the risk of delirium tremens is greatest during which period after the last drink?

a. Within the first 6 hours

b. 12 to 24 hours

c. 24 to 48 hours

d. 48 to 72 hours

Answer: d — Delirium tremens typically begins 48 to 72 hours after the last drink and can last up to 5 days (d) (section 11.3, Table 11.2). Minor withdrawal begins in the first hours (a). Hallucinosis usually begins at 12 to 24 hours (b). Withdrawal seizures usually occur at 24 to 48 hours (c). Timing varies, so the nurse keeps monitoring throughout.

9. [CORE] An RPN on an Ontario medical unit is caring for a patient on an alcohol withdrawal protocol. Over three assessments, the patient's scores have risen despite as-needed doses, and the patient now reports seeing insects on the wall. Which action best fits the RPN's scope of practice?

a. Continue giving as-needed doses exactly as the protocol directs and reassess the patient at the next scheduled assessment time.

b. Consult the RN promptly, share the assessment findings, and keep caring for the patient while the plan is reviewed.

c. Hand the patient's care to the RN and stop assessing the patient.

d. Ask the patient's family to stay overnight so that someone is with the patient to watch for any changes.

Answer: b — Under CNO's Scope of Practice standard, the RPN considers authority, competence and context; as a patient's needs change, the RPN consults the RN and continues to provide care within their competence, following employer policy (b) (section 11.3; Chapter 1, section 1.3). Continuing the protocol unchanged (a) ignores signs that treatment is not working and that withdrawal may be progressing. Consultation does not mean abandoning assessment (c). Family presence can comfort but does not replace professional assessment and escalation (d).

Case: Mr. Kevin Lachance (Questions 10–15): Mr. Kevin Lachance, 42, was admitted 3 days ago with an abscess of the right thigh, which was drained in the operating room. He receives IV antibiotics. On admission he said he smokes fentanyl most days, and he declined to start opioid agonist treatment. The unit has a medical directive for naloxone. At 1510, after a visitor leaves, the nurse finds him slumped in his chair. He moans but does not open his eyes to a firm shake of his shoulders. His respiratory rate is 6 and shallow, with gurgling sounds. oxygen saturation (SpO2) is 82% on room air, heart rate 56 and blood pressure 102/60 mm Hg. His pupils are pinpoint and his lips and nail beds look grey. His temperature is 37.2 °C and his capillary blood glucose is 6.1 mmol/L. A piece of foil and a straw lie on his tray table.

10. [CORE] Which of Mr. Lachance's findings require immediate action? Select all that apply.

a. Respiratory rate of 6 and shallow, with gurgling

b. Capillary blood glucose of 6.1 mmol/L

c. No eye opening to a firm shake of the shoulders

d. SpO2 82% on room air

e. Temperature 37.2 °C

f. Grey lips and nail beds

Answer: a, c, d, f — Slow, shallow breathing with gurgling (a), unresponsiveness to a firm shake (c), low oxygen saturation (d) and grey lips and nail beds (f) show that breathing is failing and need immediate action (section 11.4). A glucose of 6.1 mmol/L (b) is within the usual range and makes hypoglycemia an unlikely cause. A temperature of 37.2 °C (e) is normal.

11. [CORE] The nurse analyzes the cues. Which interpretation of Mr. Lachance's findings is most accurate?

a. The grey colour points to a primary heart problem, and the pinpoint pupils are probably a drug side effect.

b. The cluster of cues fits opioid toxicity, though another sedative in the drug supply may also contribute.

c. The cues fit opioid withdrawal, because he has had no prescribed opioids since admission.

d. The cues fit sepsis from the thigh abscess, because sepsis can reduce the level of consciousness.

Answer: b — Unresponsiveness, slow breathing, pinpoint pupils and cyanosis are the cluster of opioid toxicity, and the unregulated supply often contains non-opioid sedatives such as benzodiazepine-related drugs (b) (section 11.4). Grey colour reflects poor oxygenation from slow breathing, not a primary heart problem (a). Withdrawal causes alertness, enlarged pupils and normal or fast breathing (c) (Table 11.3). He has no fever, and pinpoint pupils with a respiratory rate of 6 are not typical of sepsis (d).

12. [CORE] Which problem is the priority for Mr. Lachance?

a. Risk of infection at the drained abscess site

b. Risk of opioid withdrawal after naloxone is given

c. Acute pain from the thigh wound

d. Inadequate breathing caused by opioid toxicity

Answer: d — Inadequate breathing threatens his life within minutes, so it comes first (d) (section 11.4). Wound infection (a) and pain (c) are real but not immediately life-threatening. Precipitated withdrawal (b) may follow naloxone, but it is uncomfortable rather than immediately dangerous and does not outrank restoring breathing.

13. [CORE] Which actions should the nurse plan for Mr. Lachance now? Select all that apply.

a. Call for help through the code blue or rapid response system, as policy directs

b. Leave the room to find his physician and obtain a written order for naloxone

c. Open the airway and ventilate with a bag-valve-mask and oxygen

d. Give naloxone by the route and dose set in the medical directive

e. Search his belongings for drugs before starting treatment

f. Prepare to repeat naloxone if breathing has not improved after 2 to 3 minutes

Answer: a, c, d, f — Calling for help (a), supporting ventilation (c), giving naloxone under the medical directive (d) and preparing to repeat it if there is no response (f) are the core steps of the response (section 11.4). The medical directive already provides authority, and leaving an unresponsive patient to seek an order (b) delays care. Searching belongings (e) delays treatment and is not part of the emergency response.

14. [CORE] Mr. Lachance woke 2 minutes after a second dose of naloxone. At 1600 he was alert, with a respiratory rate of 16. At 1625 the nurse finds him hard to rouse, with a respiratory rate of 8 and SpO2 89% on 2 L/min of oxygen. What should the nurse do first?

a. Stimulate him, support his breathing and call the rapid response team.

b. Increase the oxygen to 6 L/min and recheck him in 15 minutes.

c. Let him sleep, because he did not sleep the night before.

d. Document the findings and report them at the next handover.

Answer: a — Returning sedation and slow breathing signal recurrent toxicity as naloxone wears off, so the nurse acts at once: stimulates him, supports breathing, calls for help and gives naloxone as directed (a) (section 11.4). Raising oxygen and waiting (b) can mask worsening hypoventilation. Assuming he is only tired (c) misses a life-threatening cue. Delaying the report (d) delays rescue.

15. [CORE] By 1900, after a further dose of naloxone and close monitoring, the team reviews Mr. Lachance's care. Which findings show that the plan is working? Select all that apply.

a. He is awake and talking, with a respiratory rate of 16 and SpO2 96% on room air.

b. He has had no further episodes of sedation since the last dose.

c. He says he will leave tonight because he expects to be judged.

d. He agrees to see the addiction medicine team in the morning.

e. He accepts a naloxone kit and can describe how to use it.

f. He has refused all withdrawal assessments since 1700.

Answer: a, b, d, e — Normal breathing and oxygenation (a) and no further sedation (b) show that the immediate danger has passed. Agreeing to an addiction medicine consultation (d) and accepting naloxone with correct teach-back (e) show progress toward safer care (sections 11.4 and 11.6). A plan to leave because he expects judgment (c) and refusing withdrawal assessments (f) show the relationship and the withdrawal plan still need attention.

16. [CORE] A nurse assesses four patients who use opioids. Which finding is most consistent with opioid withdrawal rather than opioid toxicity?

a. Pinpoint pupils and a respiratory rate of 8

b. Snoring respirations and no response to voice

c. Enlarged pupils, yawning and gooseflesh

d. Grey lips and slow, shallow breathing

Answer: c — Enlarged pupils, yawning and gooseflesh are cues of withdrawal (c) (section 11.4, Table 11.3). Pinpoint pupils with slow breathing (a), snoring respirations with unresponsiveness (b) and grey lips with shallow breathing (d) are cues of opioid toxicity.

17. [CORE] The nurse is caring for a patient whose withdrawal is being monitored with the Clinical Opiate Withdrawal Scale (COWS). Which statement about COWS is accurate?

a. It rates observed signs and reported symptoms to track the severity of withdrawal over time.

b. It is a screening questionnaire that the patient completes to identify opioid use disorder.

c. It is used to score how deeply sedated a patient is after receiving an opioid.

d. It counts every elevated pulse, including a pulse raised by walking to the bathroom.

Answer: a — COWS is a clinician-rated scale that combines observed signs and reported symptoms to rate withdrawal and track it over time (a) (section 11.4). It does not diagnose opioid use disorder (b). Sedation is rated with a sedation scale, not COWS (c) (Chapter 5). Only findings caused by withdrawal are scored, so a pulse raised by activity is not counted (d).

18. [CORE] Two minutes after receiving naloxone for opioid toxicity, a patient is awake, sweating, vomiting and shouting. A family member asks whether the naloxone was harmful. Which response by the nurse is best?

a. "This is an allergic reaction to naloxone, so it cannot be given again."

b. "These are signs that the opioid is still working and he needs more naloxone."

c. "These symptoms mean he took a stimulant, not an opioid."

d. "Naloxone blocked the opioid suddenly, which caused withdrawal symptoms."

Answer: d — Naloxone can precipitate sudden withdrawal in a person who is physically dependent on opioids, with vomiting, sweating and agitation (d) (section 11.4). An allergic reaction would cause hives, wheezing or swelling, not this pattern (a). An awake patient is no longer showing opioid toxicity, so more naloxone is not indicated (b). The response to naloxone points to an opioid, not a stimulant (c).

19. [CORE] A patient admitted after using methamphetamine is agitated and pacing. Temperature is 39.4 °C, heart rate 138 and blood pressure 172/98 mm Hg. Which action is the priority?

a. Apply four-point restraints to prevent the patient from leaving.

b. Report the findings at once and begin cooling and sedation as ordered.

c. Encourage the patient to walk in the hallway to calm down.

d. Recheck the temperature in 4 hours to see whether it falls.

Answer: b — A high temperature with severe agitation is dangerous in stimulant toxicity, so the nurse escalates at once and begins cooling and ordered sedation (b) (section 11.5). Physical restraint can precipitate cardiac arrest in severe agitation (a). Activity increases heat production (c). Waiting 4 hours (d) allows hyperthermia to progress.

20. [CORE] A patient has had three admissions this year for severe vomiting. The patient uses cannabis several times a day and says hot showers are the only thing that helps. After serious causes are ruled out, which teaching is most appropriate?

a. "Switching to edible cannabis products should stop the vomiting."

b. "Taking a scheduled antiemetic every day should prevent future episodes."

c. "Stopping cannabis is what makes these episodes go away for good."

d. "Long hot showers are the most effective way to treat the cause."

Answer: c — The pattern suggests cannabinoid hyperemesis syndrome, and lasting remission requires stopping cannabis (c) (section 11.5). The syndrome is linked to heavy long-term use, not only to smoking, so edibles are not a solution (a). Standard antiemetics often fail (b). Hot showers ease symptoms but do not treat the cause (d).

21. [CORE] Which nursing action best reflects the principle of harm reduction?

a. Offering a naloxone kit and teaching to a patient who plans to keep using

b. Telling a patient that treatment is available only after they stop using

c. Removing a patient's access to visitors after drug use is suspected

d. Making a referral to addiction services a condition of pain management

Answer: a — Harm reduction reduces risk without requiring a person to stop using, and take-home naloxone is a core example (a) (section 11.6). Requiring abstinence first (b), punishing suspected use (c) and making pain care conditional (d) work against harm reduction and trust.

22. [CORE] A patient who uses fentanyl is being discharged after 9 days in hospital. Which statement shows that the patient understands overdose risk after discharge?

a. "I can go right back to my usual amount, since I haven't used for a while."

b. "I'm safest if I use alone so that no one gets in trouble."

c. "Overdose only happens to people who inject, and I smoke."

d. "My tolerance is lower now, so the amount I used to take could kill me."

Answer: d — After a hospital stay with little or no use, tolerance falls, so returning to the previous amount can cause an overdose (d) (section 11.6). The usual amount is now riskier, not safer (a). Using alone removes the chance of rescue (b). Overdose can occur with any route, including smoking (c).

23. [CORE] The nurse teaches a patient and a family member how to respond to an opioid overdose with the take-home naloxone kit. Which instructions are accurate? Select all that apply.

a. Call 9-1-1 if the person does not respond to shouting and shaking.

b. Give a second dose if there is no improvement after 2 to 3 minutes.

c. Wait for paramedics before giving naloxone, because it is a prescription drug.

d. Give rescue breaths or chest compressions as part of the response.

e. Stay with the person until help arrives, even after they wake up.

f. Avoid giving naloxone if you are not sure the person took an opioid.

Answer: a, b, d, e — The steps are to shout and shake, call 9-1-1 (a), give naloxone, give rescue breaths or compressions (d), repeat naloxone after 2 to 3 minutes if there is no change (b), and stay because the overdose can return (e) (sections 11.4 and 11.6). Naloxone is available without a prescription and bystanders may give it (c). It is unlikely to cause harm when the cause is not an opioid, so uncertainty is not a reason to withhold it (f).

24. [CORE] A patient being discharged says, "If my friend overdoses, I won't call 9-1-1, because the police will charge me." Which response by the nurse is most accurate?

a. "Calling 9-1-1 protects you from every criminal charge."

b. "A federal law protects you from a charge of simple possession if you call for help."

c. "That law protects only the person who overdosed, not the caller."

d. "That protection applies only if you stay until the ambulance arrives."

Answer: b — When someone calls for help with an overdose, the Good Samaritan Drug Overdose Act protects the people at the scene from charges of simple possession (b) (section 11.6). It does not cover all charges, such as trafficking or outstanding warrants (a). It covers the caller and others at the scene as well as the person who overdosed (c). It applies whether or not the caller stays (d).

25. [CORE] An RPN on a medical unit hears a call bell from a patient assigned to another nurse and finds the patient unresponsive, with a respiratory rate of 4. What should the RPN do first?

a. Find the assigned RN, because the patient is not on the RPN's assignment.

b. Check the patient's medication record for recent opioid doses.

c. Wait at the bedside until the assigned nurse returns from break.

d. Call for help and begin to support the patient's breathing.

Answer: d — Every nurse who finds a patient deteriorating acts at once and escalates, whoever is assigned (d) (section 11.6, Scope in Practice box). Looking for the assigned nurse (a), reviewing records (b) and waiting (c) all delay rescue breathing and naloxone.

26. [CORE] An RPN cares for a patient who started buprenorphine-naloxone yesterday. Today the patient's withdrawal score is rising, and the patient reports new chest tightness. Which action by the RPN is most appropriate?

a. Give an extra buprenorphine-naloxone dose from the patient's own supply.

b. Continue the plan and reassess the withdrawal score at the end of the shift.

c. Consult the RN and report the findings to the prescriber promptly.

d. Change the buprenorphine-naloxone schedule to manage the rising score.

Answer: c — The patient's condition is changing, so the RPN consults the RN and the findings are reported promptly (c) (section 11.6, Scope in Practice box). Nurses give OAT only as ordered and never from a patient's own supply without an order (a). Waiting until the end of the shift (b) delays assessment of chest tightness. Changing the schedule (d) is a prescriber's decision.

27. [RN] A student nurse asks why buprenorphine can cause withdrawal in a patient who has recently used fentanyl. Which explanation by the RN is most accurate?

a. Buprenorphine contains enough naloxone when swallowed to block all opioid receptors.

b. Buprenorphine binds tightly to mu receptors but activates them only partly, displacing fentanyl.

c. Buprenorphine speeds up the liver's breakdown of fentanyl.

d. Buprenorphine is an opioid antagonist with no effect at the mu receptor.

Answer: b — As a high-affinity partial agonist, buprenorphine displaces full agonists such as fentanyl and replaces a strong effect with a weaker one, which feels like abrupt withdrawal (b) (section 11.4, Going Deeper box). The naloxone in sublingual tablets is poorly absorbed when taken as directed and is there to discourage injection (a). Buprenorphine does not speed fentanyl breakdown (c). It is a partial agonist, not an antagonist (d).

28. [RN] A patient who smoked fentanyl 6 hours ago asks for buprenorphine now, under a standard induction plan. The patient has a mild withdrawal score. What is the RN's best response?

a. Explain that the first dose waits until withdrawal is clearer, and notify the prescriber.

b. Give the first dose now, because any withdrawal means the receptors are free.

c. Give naloxone first to clear fentanyl from the receptors before buprenorphine.

d. Tell the patient that buprenorphine cannot be used after fentanyl.

Answer: a — Standard induction waits until withdrawal is clearly present, so that buprenorphine relieves withdrawal instead of precipitating it; the RN explains this and informs the prescriber (a) (section 11.4). Mild withdrawal soon after fentanyl does not mean the receptors are free (b). Naloxone would cause severe withdrawal (c). Buprenorphine can be started after fentanyl, by standard or low-dose induction (d).

29. [RN] Which statement best describes the principle of low-dose buprenorphine initiation?

a. Buprenorphine is started only after all opioids have been stopped for several days.

b. A single large dose of buprenorphine is given to block fentanyl quickly.

c. Methadone is given first, and buprenorphine is added once withdrawal begins.

d. Small, increasing buprenorphine doses overlap with the usual opioid, which stops later.

Answer: d — In low-dose initiation, small doses of buprenorphine gradually occupy receptors while the full agonist continues, and the full agonist stops once buprenorphine reaches an effective level (d) (section 11.4, Going Deeper box). Waiting for several days without opioids (a) is the barrier the approach avoids. A large first dose (b) risks precipitated withdrawal. Starting with methadone (c) is not part of the method.

30. [RN] Why can standard buprenorphine induction be harder for people who use fentanyl?

a. Fentanyl is a partial agonist that competes with buprenorphine at the receptor.

b. Fentanyl is cleared by the kidneys more slowly than other opioids.

c. Fentanyl is stored in fatty tissue and released slowly, so it may still occupy receptors.

d. Fentanyl causes withdrawal that cannot be measured with standard scales.

Answer: c — Fentanyl is highly fat-soluble, accumulates in tissues with repeated use and is released slowly, so it may still occupy receptors when withdrawal is felt (c) (section 11.4, Going Deeper box). Fentanyl is a full agonist, not a partial agonist (a). The issue is tissue storage, not kidney clearance (b). Withdrawal from fentanyl can still be measured with COWS (d).

References

Alberta Health Services. (2026, March 18). *Slow-release oral morphine (Kadian)* [Patient information]. https://www.albertahealthservices.ca/assets/info/amh/if-amh-odp-slow-release-oral-morphine-with-clinic-information.pdf

American Society of Addiction Medicine. (2020). The ASAM clinical practice guideline on alcohol withdrawal management. *Journal of Addiction Medicine, 14*(3S), 1–72. https://doi.org/10.1097/ADM.0000000000000668

BC Centre on Substance Use. (n.d.). *Canadian guideline* [Web page on the Canadian guideline for the clinical management of high-risk drinking and alcohol use disorder]. Retrieved October 25, 2026, from https://www.bccsu.ca/alcohol-use-disorder/canadian/

British Columbia Centre on Substance Use. (2023). *A guideline for the clinical management of opioid use disorder* (2023 update). https://www.bccsu.ca/wp-content/uploads/2025/09/BC-OUD-Treatment-Guideline_2023-Update2.pdf

Butt, P. R., White-Campbell, M., Canham, S., Dowsett Johnston, A., Indome, E. O., Purcell, B., Tung, J., & Van Bussel, L. (2020). Canadian guidelines on alcohol use disorder among older adults. *Canadian Geriatrics Journal, 23*(1), 143–148. https://doi.org/10.5770/cgj.23.425

Canadian Centre on Substance Use and Addiction. (2023). *Canada's guidance on alcohol and health*. https://ccsa.ca/canadas-guidance-alcohol-and-health

Canadian Institute for Health Information. (2026). *Hospital stays for harm caused by substance use* [Indicator]. https://www.cihi.ca/en/indicators/hospital-stays-for-harm-caused-by-substance-use

Centers for Disease Control and Prevention. (2024, April 16). *Opioid use disorder: Diagnosis*. https://www.cdc.gov/overdose-prevention/hcp/clinical-care/opioid-use-disorder-diagnosis.html

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026, October 14). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

Community Care and Recovery Act, 2024, S.O. 2024, c. 27, Sched. 4. https://www.ontario.ca/laws/statute/24c27a

Conn, D. K., Hogan, D. B., Amdam, L., Cassidy, K.-L., Cordell, P., Frank, C., Gardner, D., Goldhar, M., Ho, J. M.-W., Kitamura, C., & Vasil, N. (2020). Canadian guidelines on benzodiazepine receptor agonist use disorder among older adults. *Canadian Geriatrics Journal, 23*(1), 116–122. https://doi.org/10.5770/cgj.23.419

Darke, S., Larney, S., & Farrell, M. (2017). Yes, people can die from opiate withdrawal. *Addiction, 112*(2), 199–200. https://doi.org/10.1111/add.13512

Emergent BioSolutions Canada. (2026). *NARCAN nasal spray (naloxone hydrochloride nasal spray) 2 mg/0.1 mL and 4 mg/0.1 mL* [Product monograph]. https://www.emergentbiosolutions.com/wp-content/uploads/2026/05/Narcan-Spray-Product-Monograph-English-Canada.pdf

First Nations Health Authority. (2025, April 17). *Data shows encouraging impact of harm reduction efforts*. https://fnha.ca/data-shows-encouraging-impact-of-harm-reduction-efforts/

Fischer, B., Robinson, T., Bullen, C., Curran, V., Jutras-Aswad, D., Medina-Mora, M. E., Pacula, R. L., Rehm, J., Room, R., van den Brink, W., & Hall, W. (2022). Lower-Risk Cannabis Use Guidelines (LRCUG) for reducing health harms from non-medical cannabis use: A comprehensive evidence and recommendations update. *International Journal of Drug Policy, 99*, Article 103381. https://doi.org/10.1016/j.drugpo.2021.103381

Gortney, J. S., Raub, J. N., Patel, P., Kokoska, L., Hannawa, M., & Argyris, A. (2016). Alcohol withdrawal syndrome in medical patients. *Cleveland Clinic Journal of Medicine, 83*(1), 67–79. https://doi.org/10.3949/ccjm.83a.14061

Government of British Columbia. (2026). *Decriminalizing people who use drugs in B.C.* https://www2.gov.bc.ca/gov/content/overdose/decriminalization

Government of Ontario. (2026, April 21). *Get a free naloxone kit*. https://www.ontario.ca/page/get-naloxone-kits-free

Health Canada, & Assembly of First Nations. (2015). *First Nations mental wellness continuum framework: Summary report*. https://www.sac-isc.gc.ca/eng/1576093687903/1576093725971

Health Canada. (2018a). *Apply to run a supervised consumption site*. https://www.canada.ca/en/health-canada/services/substance-use/supervised-consumption-sites/apply.html

Health Canada. (2018b). *Information for health care professionals: Cannabis (marihuana, marijuana) and the cannabinoids*. https://www.canada.ca/en/health-canada/services/drugs-medication/cannabis/information-medical-practitioners/information-health-care-professionals-cannabis-cannabinoids.html

Health Canada. (2018c). *Is cannabis addictive?* https://www.canada.ca/en/health-canada/services/publications/drugs-health-products/cannabis-addictive.html

Health Canada. (2018d). *Methadone program*. https://www.canada.ca/en/health-canada/services/health-concerns/controlled-substances-precursor-chemicals/exemptions/methadone-program.html

Health Canada. (2023a). *Methamphetamine*. https://www.canada.ca/en/health-canada/services/substance-use/controlled-illegal-drugs/methamphetamine.html

Health Canada. (2023b). *The emergence of xylazine in Canada*. https://www.canada.ca/en/health-canada/services/publications/healthy-living/emergence-xylazine-canada.html

Health Canada. (2024a). *Frequently asked questions: Access to naloxone in Canada (including NARCAN nasal spray)*. https://www.canada.ca/en/health-canada/services/drugs-health-products/drug-products/announcements/narcan-nasal-spray-frequently-asked-questions.html

Health Canada. (2024b, May 7). *Personal possession of small amounts of certain illegal drugs in British Columbia*. https://www.canada.ca/en/health-canada/news/2024/05/personal-possession-of-small-amounts-of-certain-illegal-drugs-in-british-columbia.html

Health Canada. (2026a). *About the Good Samaritan Drug Overdose Act*. https://www.canada.ca/en/health-canada/services/opioids/about-good-samaritan-drug-overdose-act.html

Health Canada. (2026b). *Get help with substance use*. https://www.canada.ca/en/health-canada/services/substance-use/get-help-with-substance-use.html

Health Canada. (2026c). *Stigma around drug use*. https://www.canada.ca/en/health-canada/services/opioids/stigma.html

Health Canada. (2026d). *Supervised consumption explained: Types of sites and services*. https://www.canada.ca/en/health-canada/services/substance-use/supervised-consumption-sites/explained.html

Health Canada. (n.d.). *Cannabis Act legislative review*. Retrieved October 25, 2026, from https://www.canada.ca/en/health-canada/services/drugs-medication/cannabis/laws-regulations/cannabis-act-legislative-review.html

Indivior UK. (2021). *SUBOXONE (buprenorphine and naloxone) sublingual tablets and soluble film* [Product monograph]. https://pdf.hres.ca/dpd_pm/00063411.PDF

Indivior UK. (2025). *SUBLOCADE (buprenorphine extended-release injection)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00082639.PDF

Khan, M., Hu, X., Crabtree, A., Moe, J., Nasmith, T., Daly-Grafstein, D., Brubacher, J. R., Slaunwhite, A. K., & Staples, J. A. (2024). "Before medically advised" departure from hospital and subsequent drug overdose: A population-based cohort study. *CMAJ, 196*(31), E1066–E1075. https://doi.org/10.1503/cmaj.240364

King, C., & Holmes, A. (2015). Cannabinoid hyperemesis syndrome. *CMAJ, 187*(5), 355. https://doi.org/10.1503/cmaj.140154

Li, S., & Xing, C. (2025). Wernicke encephalopathy: A mini review of the clinical spectrum, atypical manifestations, and diagnostic challenges. *Frontiers in Neurology, 16*, Article 1566366. https://doi.org/10.3389/fneur.2025.1566366

Maldonado, J. R., Sher, Y., Ashouri, J. F., Hills-Evans, K., Swendsen, H., Lolak, S., & Miller, A. C. (2014). The "Prediction of Alcohol Withdrawal Severity Scale" (PAWSS): Systematic literature review and pilot study of a new scale for the prediction of complicated alcohol withdrawal syndrome. *Alcohol, 48*(4), 375–390. https://doi.org/10.1016/j.alcohol.2014.01.004

Mayer, S., Langheimer, V., Nolan, S., Boyd, J., Small, W., & McNeil, R. (2023). Emergency department experiences of people who use drugs who left or were discharged from hospital against medical advice. *PLoS ONE, 18*(2), Article e0282215. https://doi.org/10.1371/journal.pone.0282215

META:PHI. (n.d.). *RAAM clinics*. Retrieved October 25, 2026, from https://www.metaphi.ca/raam-clinics/

Mylan Pharmaceuticals ULC. (2011). *Campral (acamprosate calcium) delayed release tablets 333 mg* [Product monograph]. https://pdf.hres.ca/dpd_pm/00014184.PDF

National Overdose Response Service. (n.d.). *About NORS*. Retrieved October 25, 2026, from https://www.nors.ca/about

NSW Health. (2024). *Pre-hospital guideline: Illicit substance-induced hyperthermia*. https://health.nsw.gov.au/aod/Factsheets/substance-induced-hyperthermia.pdf

Ontario Ministry of Health. (2025). *Homelessness and Addiction Recovery Treatment Hubs (HART Hubs): Reference document, January 2025*. https://www.ontario.ca/page/homelessness-and-addiction-recovery-treatment-hubs-hart-hubs-reference-document-january-2025

Ontario Ministry of Health. (2026, March 19). *Ontario take home naloxone programs*. https://www.ontario.ca/page/ontario-take-home-naloxone-programs

Palis, H., & MacDonald, S. (2023). Incorporating prescription psychostimulants into the continuum of care for people with stimulant use disorder in Canada. *CMAJ, 195*(27), E934–E935. https://doi.org/10.1503/cmaj.230266

Public Health Agency of Canada. (2019). *Addressing stigma: Towards a more inclusive health system. The Chief Public Health Officer's report on the state of public health in Canada 2019*. https://www.canada.ca/en/public-health/corporate/publications/chief-public-health-officer-reports-state-public-health-canada/addressing-stigma-toward-more-inclusive-health-system.html

Public Health Agency of Canada. (2020). *Communicating about substance use in compassionate, safe and non-stigmatizing ways*. https://www.canada.ca/en/public-health/services/publications/healthy-living/communicating-about-substance-use-compassionate-safe-non-stigmatizing-ways-2019.html

Public Health Agency of Canada. (2025, June 25). *Statement from the Council of Chief Medical Officers of Health and the Chief Coroners and Chief Medical Examiners – Latest national data on substance-related harms* [News release]. https://www.canada.ca/en/public-health/news/2025/06/statement-from-the-council-of-chief-medical-officers-of-health-and-the-chief-coroners-and-chief-medical-examiners---latest-national-data-on-substan.html

Public Health Agency of Canada. (2026, June 15). *Statement from the Council of Chief Medical Officers of Health – Latest national data on substance-related harms* [News release]. https://www.canada.ca/en/public-health/news/2026/06/statement-from-the-council-of-chief-medical-officers-of-health-latest-national-data-on-substance-related-harms.html

Randhawa, P. A., Brar, R., & Nolan, S. (2020). Buprenorphine–naloxone "microdosing": An alternative induction approach for the treatment of opioid use disorder in the wake of North America's increasingly potent illicit drug market. *CMAJ, 192*(3), E73. https://doi.org/10.1503/cmaj.74018

Simcoe Muskoka District Health Unit. (2026, January 27). *Medetomidine in the unregulated drug supply* [Public health alert]. https://www.simcoemuskokahealth.org/docs/default-source/jfy-health-care-professionals/jfy-healthfax/20260122-medetomidine-ph-alert-final.pdf

Smith, P. C., Schmidt, S. M., Allensworth-Davies, D., & Saitz, R. (2009). Primary care validation of a single-question alcohol screening test. *Journal of General Internal Medicine, 24*(7), 783–788. https://doi.org/10.1007/s11606-009-0928-6

Smith, P. C., Schmidt, S. M., Allensworth-Davies, D., & Saitz, R. (2010). A single-question screening test for drug use in primary care. *Archives of Internal Medicine, 170*(13), 1155–1160. https://doi.org/10.1001/archinternmed.2010.140

Strike, C., Robinson, S., Guta, A., Tan, D. H., O'Leary, B., Cooper, C., Upshur, R., & Chan Carusone, S. (2020). Illicit drug use while admitted to hospital: Patient and health care provider perspectives. *PLOS ONE, 15*(3), Article e0229713. https://doi.org/10.1371/journal.pone.0229713

Substance-related Overdose and Mortality Surveillance Task Group on behalf of the Council of Chief Medical Officers of Health. (2026, September). *Opioid- and stimulant-related harms in Canada*. Public Health Agency of Canada. https://health-infobase.canada.ca/substance-related-harms/opioids-stimulants/

Sullivan, J. T., Sykora, K., Schneiderman, J., Naranjo, C. A., & Sellers, E. M. (1989). Assessment of alcohol withdrawal: The revised Clinical Institute Withdrawal Assessment for Alcohol scale (CIWA-Ar). *British Journal of Addiction, 84*(11), 1353–1357. https://doi.org/10.1111/j.1360-0443.1989.tb00737.x

Toronto Public Health. (2025, January 7). *Anticipated service impacts for Toronto Public Health and emergency responders due to the closure of supervised consumption sites in Toronto* [Report for action to the Board of Health]. https://www.toronto.ca/legdocs/mmis/2025/hl/bgrd/backgroundfile-251970.pdf

Truth and Reconciliation Commission of Canada. (2015). *Truth and Reconciliation Commission of Canada: Calls to action*. https://nctr.ca/wp-content/uploads/2021/01/Calls_to_Action_English2.pdf

Wesson, D. R., & Ling, W. (2003). The Clinical Opiate Withdrawal Scale (COWS). *Journal of Psychoactive Drugs, 35*(2), 253–259. https://doi.org/10.1080/02791072.2003.10400007

Wilk, P., Maltby, A., & Cooke, M. (2017). Residential schools and the effects on Indigenous health and well-being in Canada: A scoping review. *Public Health Reviews, 38*, Article 8. https://doi.org/10.1186/s40985-017-0055-6

Wood, E., Bright, J., Hsu, K., Goel, N., Ross, J. W. G., Hanson, A., Teed, R., Poulin, G., Denning, B., Corace, K., Chase, C., Halpape, K., Lim, R., Kealey, T., & Rehm, J. (2023). Canadian guideline for the clinical management of high-risk drinking and alcohol use disorder. *CMAJ, 195*(40), E1364–E1379. https://doi.org/10.1503/cmaj.230715

Wood, E., Wong, S. C., Corace, K., Martell, D., Barker, B., de Montigny, C., Hodgins, D. C., Poulin, G., Halpape, K., Le Foll, B., Lim, R., Brosseau, A., Henry, R., Marsh, D. C., Cowan, N., Teed, R., Johnson, C., Brunelle, C., Graham, B., & Rehm, J. (2026). Screening for high-risk drinking and alcohol use disorder: Update of the 2023 national clinical practice guideline. *CMAJ, 198*(17), E655–E665. https://doi.org/10.1503/cmaj.251759

Yakovenko, I., Mukaneza, Y., Germé, K., Belliveau, J., Fraleigh, R., Bach, P., Poulin, G., Selby, P., Goyer, M.-È., Brothers, T. D., Rehm, J., Hodgins, D. C., Stewart, S. H., Wood, E., & Bruneau, J. (2024). Management of opioid use disorder: 2024 update to the national clinical practice guideline. *CMAJ, 196*(38), E1280–E1290. https://doi.org/10.1503/cmaj.241173

York Region Public Health. (2026, January 15). *Drug alert* [Public health alert with Ontario's Drug Checking Community medetomidine fact sheet]. https://www.york.ca/media/128311/download

III Respiratory Nursing Care

UNIT CLINICAL SCOPE & INTEGRATION

Covers comprehensive bedside respiratory assessment, oxygen delivery devices, tracheostomy and chest tube management, lower respiratory tract infections, tuberculosis, lung cancer, chronic obstructive pulmonary disease (COPD), asthma, acute respiratory distress syndrome (ARDS), mechanical ventilation principles, and pulmonary embolism.

Contents of UNIT III

Chapter	Chapter Title	Visual Assets	Page
Chapter 12	Respiratory Assessment and Oxygen Therapy	10 Figs • 4 Tbls	p. 318
Chapter 13	Lower Respiratory Infections and Lung Cancer	7 Figs • 4 Tbls	p. 349
Chapter 14	Obstructive and Restrictive Lung Disease	7 Figs • 4 Tbls	p. 380
Chapter 15	Acute Respiratory Failure and Pulmonary Embolism	6 Figs • 4 Tbls	p. 409

12 Respiratory Assessment and Oxygen Therapy

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Relate ventilation, diffusion, perfusion and oxygen transport to assessment findings.
2. Perform a focused respiratory assessment, describing findings accurately on a range of skin tones.
3. Interpret pulse oximetry and its limits, including reduced accuracy with darker skin pigmentation.
4. Give and monitor oxygen safely to an ordered target range with the right delivery device.
5. Promote airway clearance and prevent pulmonary complications.
6. Care for patients with artificial airways and tracheostomies, including recognizing and responding to airway emergencies.
7. Teach patients and families about home oxygen and tracheostomy care.
8. Distinguish RN and RPN roles in airway care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 5, 6	Clinician; Scholar	Foundations of Practice
3, 7	Advocate; Educator	Foundations of Practice; Ethical Practice
6, 8	Professional; Collaborator	Legal Practice; Collaborative Practice

Introduction

Every cell needs a steady supply of oxygen and a way to get rid of carbon dioxide. When breathing fails, a patient can deteriorate quickly, so nurses check the airway and breathing first in any emergency and reassess them often. A rising respiratory rate or new effort to breathe is often one of the first clues that a patient is getting worse, which is why breathing is part of the early warning scores in Chapter 6. Yet breathing is easy to under-assess: short counts underestimate the respiratory rate (Hill et al., 2018), and a reassuring oximeter reading can distract from a patient who looks unwell.

This chapter is the book's home for respiratory assessment and oxygen therapy. Section 12.1 reviews how the lungs move air and exchange gases, section 12.2 covers the focused respiratory assessment, including colour on a range of skin tones, and section 12.3 explains pulse oximetry, its limits and the oxygen values on an arterial blood gas. Sections 12.4 to 12.6 cover oxygen therapy, airway clearance, and artificial airways and tracheostomy care. Related topics live elsewhere: acid–base balance (Chapter 3, section 3.7), aerosol-generating procedures (Chapter 4), opioid-induced respiratory depression (Chapter 5), recognizing deterioration (Chapter 6), postoperative pulmonary complications (Chapter 7), and respiratory disorders (Chapters 13 to 15).

12.1 Breathing and Gas Exchange: A Brief Review



Figure 12.1 The main structures of the respiratory system, from the nose and mouth to the lungs and diaphragm. (credit: Figure 22.2, "Major Respiratory Structures," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Moving Air

The respiratory system brings oxygen into the blood and removes carbon dioxide (CO_2). Air passes through the upper airway and trachea into bronchi that branch again and again and end in tiny air sacs called **alveoli**, where gas exchange takes place (Figures 12.1 and 12.2). A thin membrane, the **pleura**, covers each lung and lines the chest wall.

Ventilation is the movement of air into and out of the lungs. Breathing in is active: the diaphragm contracts and moves down, and the muscles between the ribs lift the rib cage, drawing air in. Quiet breathing out is mostly passive, as the lungs and chest wall spring back. When more air is needed, accessory muscles in the neck and shoulders help lift the chest.

Two properties decide how hard the breathing muscles must work. **Compliance** is how easily the lungs and chest wall stretch; stiff, scarred or fluid-filled lungs need more effort for each breath. **Airway resistance** is how much the airways oppose airflow; spasm, swelling or secretions raise it. The effort spent on breathing is the **work of breathing** (Sharma & Goodwin, 2006). When it rises, the patient breathes faster and uses accessory muscles; if the effort can't be kept up, breathing can fail (Chapter 15).

Gas Exchange

Oxygen and CO_2 cross the **alveolar–capillary membrane**, the thin barrier between alveolar air and capillary blood, by **diffusion**: each gas moves from higher to lower pressure. Diffusion slows when the area for exchange shrinks, when the membrane thickens with inflammation or scarring, or when blood moves past too quickly. Carbon dioxide dissolves far more readily than oxygen, so a diffusion problem lowers blood oxygen but rarely raises CO_2 (Sarkar et al., 2017).

Perfusion is blood flow through the lung capillaries. When the air reaching part of the lung does not match the blood flowing past it, the result is a **ventilation–perfusion (V/Q) mismatch**. This mismatch causes low blood oxygen more often than any other mechanism (Sarkar et al., 2017). Two extremes help explain it:

- **Shunt:** Blood flows past alveoli that get no air, such as collapsed or fluid-filled alveoli, and returns to the heart without picking up oxygen. Extra oxygen helps little, because it never reaches that blood (Sarkar et al., 2017).
- **Dead space:** Air reaches alveoli with little or no blood flow, so it takes no part in gas exchange (Sarkar et al., 2017). A clot blocking a pulmonary artery is one cause (Chapter 15).

The lung partly protects itself through **hypoxic pulmonary vasoconstriction**: small arteries in poorly ventilated areas narrow and steer blood toward alveoli that are getting air (Sarkar et al., 2017).



Figure 12.2 The respiratory zone: bronchioles end in alveolar ducts and clusters of alveoli, each wrapped in capillaries where gas exchange takes place. (credit: Figure 22.10, “Respiratory Zone,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Hypoxemia is low oxygen in the arterial blood; **hypoxia** is too little oxygen in the tissues. Hemoglobin and cardiac output can protect the tissues of a patient with hypoxemia, and tissue hypoxia can occur with normal blood oxygen when delivery is poor or cells cannot use oxygen, as in cyanide poisoning (Sarkar et al., 2017).

Control of Breathing and Oxygen Transport

Brainstem centres set the rate and depth of breathing in response to chemical sensors. Sensors in the brainstem and in the **carotid bodies**, small clusters of cells beside the carotid arteries in the neck, respond to CO2 mainly through its effect on acidity (pH). This fast feedback is a major way the body keeps arterial CO2 and pH steady from moment to moment. The carotid bodies also sense low arterial oxygen, and acidosis strengthens their response to it (Guyenet & Bayliss, 2015).

Many clinicians were taught that oxygen given to a person with chronic obstructive pulmonary disease (COPD) removes a "hypoxic drive" and stops them breathing. Research has not supported this idea. In people at risk, high oxygen levels raise CO2 mainly by relaxing hypoxic pulmonary vasoconstriction, which worsens V/Q mismatch; a brief fall in breathing effort plays only a small part. Withholding oxygen from patients with hypoxemia because of this myth is unsafe (Abdo & Heunks, 2012); the nurse gives oxygen to the target range the prescriber orders (section 12.4).

Oxygen saturation is the percentage of hemoglobin carrying oxygen: SaO2 when measured on an arterial sample, SpO2 when estimated by a pulse oximeter (section 12.3). The **oxygen–hemoglobin dissociation curve** relates saturation to the partial pressure of oxygen in arterial blood (PaO2). The curve is S-shaped. Above about 90% saturation it is flat, so large changes in PaO2 change saturation very little. Below a PaO2 of about 60 mm Hg it is steep, so a small drop in PaO2 causes a large drop in saturation (Collins et al., 2015). A patient whose saturation is drifting toward 90% therefore has little reserve, so a falling trend needs prompt action.

12.2 Focused Respiratory Assessment

If a patient is in distress, the nurse checks airway, breathing and circulation first, acts and calls for help (Chapter 6); the detailed assessment follows once the patient is safe. A focused respiratory assessment combines history, inspection, palpation, percussion and auscultation with pulse oximetry (section 12.3). Each finding is compared with the patient's baseline and the last assessment.

History

Dyspnea is the patient's own experience of uncomfortable or difficult breathing, so only the patient can report it. The nurse asks:

- **Onset:** Sudden, or over days or weeks?
- **Triggers and relief:** What brings it on (activity, lying flat, allergens) and what eases it?
- **Effect on activity:** What can the patient no longer do? Does it occur at rest or at night?

A rating scale gives a baseline for later comparison. The modified Medical Research Council (mMRC) dyspnea scale grades breathlessness from 0, breathless only with hard exercise, to 4, too breathless to leave the house or breathless while dressing (Canadian Lung Association, n.d.).

The nurse asks how long any cough has lasted and about sputum colour, amount and thickness. Coughing up blood (**hemoptysis**) is always reported. Sharp chest pain that worsens with a deep breath or cough suggests irritation of the pleura. Other questions cover:

- **Smoking and vaping:** Current and past tobacco use, e-cigarettes and cannabis smoking.
- **Exposures:** Dusts and fumes at work, wildfire smoke, and radon at home. Radon is the leading cause of lung cancer in people who don't smoke and the second leading cause overall, and radon and smoking together greatly increase the risk (Health Canada, 2019). The nurse can ask whether the home has been tested.
- **Devices:** Inhalers, home oxygen or a continuous positive airway pressure (CPAP) machine, and the patient's usual oxygen saturation.

Inspection

Inspection begins at the door with the **level of consciousness**: new restlessness, anxiety or confusion can signal low oxygen. New drowsiness in a patient at risk of CO_2 retention is also a warning sign (O'Driscoll et al., 2017b).

Next comes the **respiratory rate**. The nurse counts for a full 60 seconds, ideally while the patient is unaware of it. Shorter counts give systematically lower rates, and awareness of being watched lowers the rate (Hill et al., 2018). The nurse notes rhythm, depth and patterns:

- **Tachypnea:** A rate faster than the normal adult range; a nonspecific early sign of many problems (Chapter 6).
- **Bradypnea:** A rate slower than the normal adult range, as with opioids (Chapter 5).
- **Kussmaul breathing:** Deep, rapid breaths in metabolic acidosis, such as diabetic ketoacidosis, as the body blows off CO_2 (Chapter 3, section 3.7).
- **Cheyne–Stokes breathing:** A repeating cycle in which breathing deepens, fades, then stops for a time; common in heart failure, mostly during sleep (Lorenzi-Filho et al., 2005).

Signs of increased **work of breathing** include use of the neck and shoulder muscles, nostril flaring, pulling in of the skin between the ribs or above the collarbones (retractions), pursed-lip breathing, sitting forward with hands braced on the knees (the tripod position), and speaking only a few words between breaths. A patient working hard to breathe needs help now, even if the oxygen saturation looks acceptable.

Both sides of the chest should rise equally. A curved upper spine can stiffen the chest wall in older adults (Sharma & Goodwin, 2006).

Colour. Cyanosis is a bluish or greyish colour caused by too much hemoglobin that is not carrying oxygen. **Central cyanosis** appears in the tongue, lips and lining of the mouth and signals low arterial oxygen, an emergency. **Peripheral cyanosis** affects only the fingers, toes or nail beds, with a normal tongue, and usually reflects slow blood flow to cold extremities. Judging oxygen by colour is unreliable for everyone and harder still on darker skin. Studies, mostly in newborns, show that visual checks miss low oxygen in darker skin and that the tongue and lips are the most useful places to look (Fair et al., 2025). On darker skin, cyanosis may look grey or whitish around the mouth and in the conjunctivae rather than blue (Pusey-Reid et al., 2023). The nurse therefore:

- looks at the tongue, lips, inside of the mouth and conjunctivae in natural or bright, indirect light, rather than fluorescent light (Pusey-Reid et al., 2023);
- compares with the patient's baseline and asks the patient or family what is normal for them;
- never waits for cyanosis, a late sign, but acts on the respiratory rate, work of breathing, level of consciousness and pulse oximetry.

Pallor can signal anemia or poor blood flow. On brown skin, pallor may look yellow-brown, and on very dark skin, ash-grey; the conjunctivae and the lining of the mouth are easier to judge than the limbs (Pusey-Reid et al., 2023). In a study of adolescents and adults in India, the tongue was the most useful site for detecting severe anemia, ahead of the conjunctivae, palms and nail beds. Observers often disagreed, and the absence of pallor did not rule out milder anemia, so a hemoglobin level is needed when anemia is suspected (Kalantri et al., 2010).

Clubbing is a painless enlargement of the fingertips, with loss of the normal angle where the nail meets the skin. When the backs of matching fingers are placed together, a small diamond-shaped gap normally shows between the nail beds; in clubbing, it disappears. Clubbing is linked to lung cancer and to chronic infective, diffuse lung and heart diseases. COPD itself rarely causes it, so new clubbing in a person with COPD raises concern about lung cancer (Matsuura, 2019; Figure 12.3).

Figure 12.3 Clubbing of the fingers with cyanosis of the nail beds. On darker skin, cyanosis may look grey rather than blue. (credit: modification of "Showing bilateral grade III clubbing with cyanosis of the extremities" by Twayana et al./BMC Research Notes, CC BY 4.0)

Palpation and Percussion

To check **chest expansion**, the nurse places both hands on the lower back of the chest, thumbs near the spine, and asks for a deep breath. The thumbs should move apart equally; a lagging side may hold fluid or collapsed lung. **Tactile fremitus** is the vibration felt through the chest wall when the patient speaks; fluid or air between lung and chest wall dampens it, and an effusion is less likely when fremitus is not reduced (Wong et al., 2009).

The nurse also feels for tenderness and for **subcutaneous emphysema**, air trapped under the skin that crackles under the fingertips. It can appear around a chest injury, chest tube or tracheostomy (section 12.6; Chapter 15); the nurse marks its edges and reports new or spreading crepitus.

Percussion is tapping on the chest to judge what lies beneath. Normal air-filled lung sounds **resonant**; a **dull** note suggests fluid or solid tissue, such as an effusion or consolidation; a **hyperresonant** note suggests extra air, as with a pneumothorax. Dullness is the most accurate bedside sign of pleural effusion, though a chest X-ray is still needed (Wong et al., 2009).

Auscultation

For reliable findings (Figure 12.4), the nurse:

- chooses a quiet setting and has the patient sit up, or turns a patient who can't sit from side to side;
- warms the stethoscope and places the diaphragm on bare skin, never over clothing;
- has the patient take slow, deep breaths with the mouth open;
- starts at the top of the lungs and moves down, comparing the same spot on each side, listening to at least one full breath at each site (Sarkar et al., 2015).

Normal breath sounds vary by location. **Vesicular** sounds over most of the lungs are soft and low-pitched, with breathing in longer than breathing out. **Bronchial** sounds over the upper sternum are loud and high-pitched, with breathing out longer. **Tracheal** sounds are harsh and loud (Sarkar et al., 2015). Quiet or absent sounds over one area suggest less airflow or fluid or air between the lung and the stethoscope.

Adventitious sounds are extra sounds not normally heard. A European Respiratory Society (ERS) task force has worked to standardize their names (Pasterkamp et al., 2016), and its members found that clinicians agree more often when they use simple, broad terms such as crackles and wheezes (Melbye et al., 2016). Table 12.1 summarizes the main sounds.

Figure 12.4 Listening to the lungs from the back, on bare skin, comparing side to side.

- **Crackles:** brief, non-musical pops, usually on breathing in, described as fine or coarse (Sarkar et al., 2015). Crackles predict pneumonia on X-ray better than any single symptom (Melbye et al., 2016).
- **Wheezes:** continuous, musical sounds from narrowed airways, usually on breathing out. A wheeze in one spot suggests a local blockage. In severe asthma, airflow may be too low to make any sound, a "silent chest" (Sarkar et al., 2015).
- **Rhonchi:** low-pitched, continuous, snoring sounds; the term is used interchangeably with "low-pitched wheeze" (Melbye et al., 2016).
- **Stridor:** a loud, high-pitched, musical sound, mostly on breathing in and loudest over the neck, caused by a narrowed upper airway (Sarkar et al., 2015). Stridor is an emergency: the nurse stays with the patient, keeps them upright and calls for immediate help.
- **Pleural friction rub:** a grating sound in both phases of breathing, from inflamed pleural layers rubbing together (Sarkar et al., 2015).

Table 12.1 Normal and adventitious breath sounds (based on Sarkar et al., 2015, and Melbye et al., 2016; original wording)

Sound	What it sounds like	Where and when	What it may suggest	Nursing action
Vesicular (normal)	Soft, low-pitched rustling	Over most of the lungs; breathing in is longer than breathing out	Normal airflow	Record as baseline and compare at each assessment
Bronchial (normal in its usual place)	Loud, hollow, high-pitched	Over the upper sternum; breathing out is longer	Normal over large airways; heard elsewhere may mean consolidation	Compare sides; report bronchial sounds over the outer lung
Fine crackles	Soft, high-pitched, many brief pops	Usually late in breathing in; often at the bases	Interstitial lung disease, early heart failure, resolving pneumonia	Check for other changes; report new crackles
Coarse crackles	Louder, lower-pitched, fewer pops	Breathing in, sometimes breathing out	Secretions or fluid in larger airways	Encourage coughing and deep breathing; report if new or with distress
Wheeze	Continuous, musical, often high-pitched	Usually breathing out; widespread or in one spot	Narrowed airways; a local wheeze may mean a blockage	Assess work of breathing and SpO2; give ordered inhaled medication; report
Rhonchi (low-pitched wheeze)	Continuous, low-pitched, snoring	Breathing in or out	Secretions or narrowing in larger airways	Note any change after coughing; support airway clearance
Stridor	Loud, high-pitched, musical	Mainly breathing in; loudest over the neck	Narrowed upper airway	Emergency: stay with the patient, call for immediate help, keep upright

Sound	What it sounds like	Where and when	What it may suggest	Nursing action
Pleural friction rub	Grating, creaking, leathery	Breathing in and out, often where it hurts	Inflamed pleura	Assess pain; report a new rub

LIFESPAN CONSIDERATIONS

Breathing and Older Adults

Aging changes the lungs and chest in ways that matter for assessment. Changes in the spine and chest wall make the respiratory system less compliant, which raises the work of breathing. The lung tissue loses some of its supporting structure, and the breathing muscles become weaker, which can make coughing less effective at clearing the airways (Sharma & Goodwin, 2006).

Older adults also respond less strongly to low oxygen and high CO2, and they feel breathlessness less. As a result, an older patient may report little dyspnea even when the problem is serious. Reserve is smaller, so illnesses that raise the demand for breathing, such as pneumonia or heart failure, can lead to breathing failure more quickly (Sharma & Goodwin, 2006).

The nurse therefore counts respirations carefully and treats a new rise in rate, new confusion or a change in function as possible signs of respiratory illness. A weak cough and swallowing problems raise the risk of aspiration. Chapter 8 covers delirium, atypical presentations and other priorities for older adults in hospital.

12.3 Pulse Oximetry and Other Measures

How Pulse Oximetry Works

Pulse oximetry estimates arterial oxygen saturation without a needle. A probe on a finger, toe or earlobe (see Figure 6.1) shines red light (about 660 nm) and infrared light (about 940 nm) through the tissue. Hemoglobin carrying oxygen absorbs more infrared light, and hemoglobin without oxygen absorbs more red light. The device looks only at the part of the signal that pulses with each heartbeat, which comes from arterial blood, and filters out skin, bone and venous blood (Miyake et al., 2003). The result is the SpO2. It is usually within about 2% of the SaO2 measured on an arterial blood sample, and it is generally reliable above a saturation of about 88% but less so below it (Collins et al., 2015).

Good technique makes the reading trustworthy:

- Choose a warm site with good blood flow, and keep the patient's hand still and supported.
- Wait for a steady reading, and check the signal-strength indicator or waveform that most devices display (Collins et al., 2015).
- Compare the pulse rate on the oximeter with the patient's heart rate; a mismatch suggests a poor signal.
- Record the SpO2 with the oxygen device and flow, for example "SpO2 93% on nasal cannula at 2 L/min."

A single reading means less than the trend. An independent review in the United Kingdom recommended that people using oximeters at home watch for changes in readings rather than rely on one reading, and that clinicians be taught to follow trends and not to give or withhold treatment on fixed thresholds alone (Department of Health and Social Care [DHSC], 2024).

Pulse oximetry measures oxygen saturation only. It gives no direct information about CO2, pH or ventilation, and a normal SpO2 does not remove the need for a blood gas, especially in a patient receiving oxygen (O'Driscoll et al., 2017b). A patient on oxygen can keep a normal SpO2 while CO2 builds up from slow, shallow breathing; Chapter 5 (section 5.4) explains how capnography detects this.

Accuracy and Skin Pigmentation

Pulse oximeters can overestimate saturation in people with darker skin pigmentation, causing **occult hypoxemia**: a dangerously low arterial saturation hidden behind a reassuring SpO2.

In a widely cited study, Sjoding and colleagues (2020) compared pulse oximetry with arterial blood gases in Black and White patients in the United States. They defined occult hypoxemia as an SaO2 below 88% when the SpO2 read 92% to 96%. Among adult inpatients receiving supplemental oxygen at the University of Michigan, this occurred in 11.7% of such paired readings from Black

patients and 3.6% from White patients. In a cohort from intensive care units at 178 US hospitals, the figures were 17.0% and 6.2%. Race is a poor stand-in for skin pigmentation, and later studies have measured skin colour directly:

- A 2022 systematic review of 32 studies (6,505 participants) found that pulse oximetry probably overestimates saturation in people with high skin pigmentation, by an average of 1.11 percentage points. The average error was small, but individual readings varied around it, and the review could not say how large the problem is outside hospitals (Shi et al., 2022).
- An English study of 903 critically ill adults, in which skin tone was measured with a spectrophotometer, tested five fingertip oximeters used in a home monitoring program. On average, all five read 0.6 to 1.5 percentage points higher when skin tone was darker than when it was lighter. Readings above 94% when the SaO2 was 92% or lower, which falsely looked reassuring, were 2.3 to 7.1 times more common with darker skin, depending on the device (Martin et al., 2026).

Regulators have responded. The UK review, published March 11, 2024, found that oximeters read oxygen levels too high in people with darker skin tones, more so when saturation is low, and that testing on participants with light skin had made their readings the norm. It called for better guidance, labelling and testing (DHSC, 2024). On January 7, 2025, the US Food and Drug Administration (FDA) released draft guidance for manufacturers. It recommends larger clinical studies across skin tones that rate skin tone with both a subjective 10-point scale and an objective measurement, and labelling that states how a device performs across skin tones (FDA, 2025). Canadian action is described in the Canadian Context box.

What the nurse does:

- Looks at the whole patient: respiratory rate, work of breathing, level of consciousness, colour and heart rate.
- Follows trends and is not reassured by a "normal" SpO2 when the patient looks unwell.
- Asks for an arterial blood gas (ABG) when the SpO2 and the patient don't match, and escalates (Chapter 6).
- Reports device concerns according to employer policy.

The nurse never adds or subtracts points from a reading based on a patient's race or skin colour. No validated correction exists, and estimating one invites error and bias (Chapter 2).

Other Limits

Several other factors can make SpO2 readings wrong or impossible to obtain (Table 12.2). Carbon monoxide deserves special attention. Standard oximeters cannot tell hemoglobin carrying carbon monoxide from hemoglobin carrying oxygen, so a person with carbon monoxide poisoning can show a normal SpO2 while their blood carries dangerously little oxygen (Collins et al., 2015; O'Driscoll et al., 2017b). Severe anemia is a similar trap: saturation can read normal although the blood holds little oxygen, because there is little hemoglobin to carry it (O'Driscoll et al., 2017b).

Table 12.2 Factors that affect pulse oximetry readings (Collins et al., 2015; Health Canada, 2022; Miyake et al., 2003; O'Driscoll et al., 2017b; FDA, 2021; original wording)

Factor	Effect on the reading	What the nurse does
Poor perfusion (cold hands, shock, vasoconstriction)	Weak signal; reading may be wrong or absent	Warm the site or try another; check the signal indicator; assess circulation and escalate if shock is suspected
Movement or shivering	False readings and false alarms	Support and steady the limb; wait for a steady waveform before recording
Nail polish or artificial nails	Reading may be inaccurate; some studies found dark colours lowered it	Remove the polish or use another site, per policy
Darker skin pigmentation	Reading may be falsely high, hiding hypoxemia	Assess the whole patient; follow trends; request an ABG when in doubt
Carbon monoxide poisoning	Reading may be falsely normal	Don't trust the SpO2; give high-concentration oxygen as ordered and request an arterial co-oximetry measurement
Severe anemia	SpO2 may be normal even though total oxygen in the blood is low	Check hemoglobin; assess for signs of poor oxygen delivery

Factor	Effect on the reading	What the nurse does
Bright ambient light (for example, fluorescent or procedure lights)	Interference with the light sensor	Shield the probe
Some intravenous dyes (for example, methylene blue)	Temporary false readings	Note the timing of the dye; confirm with an ABG if needed

Other Measures

Capnography measures the CO2 in each exhaled breath. It shows how well a patient is ventilating, which pulse oximetry cannot. Its use with opioids is covered in Chapter 5 (section 5.4) and its use in critical care in Chapter 15.

An **arterial blood gas** is a blood sample taken from an artery, usually the radial artery. It measures pH, PaCO2 and bicarbonate (Chapter 3, section 3.7) along with two oxygen values:

- **PaO2:** the partial pressure of oxygen dissolved in arterial blood. Canadian laboratories report it in millimetres of mercury (mm Hg). Reference ranges vary by laboratory. For example, Alberta Precision Laboratories (2021) lists 70 to 90 mm Hg for adults, while the Medical Council of Canada's list of reference values for its exams gives 83 to 116 mm Hg (Medical Council of Canada, n.d.). British and European guidelines often use kilopascals (kPa); 1 kPa is about 7.5 mm Hg (O'Driscoll et al., 2017b).
- **SaO2:** the percentage of hemoglobin carrying oxygen, measured directly by the blood gas analyzer's co-oximeter. It is the standard against which the SpO2 is judged (Collins et al., 2015).

An ABG is usually requested when a patient is critically ill, when SpO2 falls unexpectedly or more oxygen is needed to reach the target, or when a patient at risk of CO2 retention becomes drowsy or more breathless (O'Driscoll et al., 2017b). A venous blood gas is sometimes used to check pH and CO2, but venous oxygen values do not reliably estimate arterial oxygen, so a venous sample cannot replace an ABG for judging oxygenation (Collins et al., 2015).

CANADIAN CONTEXT

Pulse Oximetry and Equity

Health Canada regulates pulse oximeters as medical devices. Since December 16, 2019, Canadian hospitals have had to report documented medical device incidents to Health Canada within 30 calendar days of first documenting them. A medical device incident is a failure of a device, a decline in how well it works, or a problem with what its label or instructions say, when the problem has led to death or a serious decline in a person's health, or could do so (Health Canada, 2020). The rule covers all hospitals that a province or territory licenses or designates, as well as federal facilities that provide in-patient care. A nurse who suspects that an oximeter gave a falsely reassuring reading reports it through the hospital's safety reporting system. The hospital then decides whether the event meets this standard.

Health Canada's (2022) guidance for health care providers notes reports that oximeter readings can be less accurate in people with dark skin, with a bias toward occult hypoxemia, and that accuracy may also fall as true saturation drops. It advises following trends or taking readings at different sites, considering a blood gas to confirm oxygenation when signs conflict or a reading is in doubt, and, when a blood gas is not possible, assuming the reading is inaccurate and taking a precautionary approach. It also asks providers to check that a device is licensed in Canada and to report device problems (Health Canada, 2022). The main studies described in this section come from the United States and England. Canadian nurses use the same devices and the same safeguards: whole-patient assessment, trends, and an ABG when in doubt.

GOING DEEPER

Oxygenation on the Arterial Blood Gas

Required for RN students; optional for PN students.

Three numbers describe oxygen in arterial blood, and they measure different things:

- **PaO2** is the pressure of oxygen dissolved in the plasma. It reflects how well oxygen moves from the alveoli into the blood.
- **SaO2** is the percentage of hemoglobin carrying oxygen, measured directly by co-oximetry.
- **SpO2** is the pulse oximeter's estimate of SaO2.

The oxygen–hemoglobin dissociation curve links PaO2 to SaO2. Because the top of the curve is flat, PaO2 can fall a long way from a high value before saturation changes much. Below a PaO2 of about 60 mm Hg, the curve is steep, so small changes in

PaO2 bring large changes in saturation. Small increases in oxygen can then produce worthwhile gains in saturation (Collins et al., 2015).

The curve can shift. A **right shift** means hemoglobin holds oxygen less tightly, so it releases oxygen more easily to the tissues. Causes include a higher temperature, more CO2, a lower pH (acidosis) and more 2,3-diphosphoglycerate (2,3-DPG), a red cell compound that rises in chronic hypoxia. A **left shift**, from the opposite changes, means hemoglobin holds oxygen more tightly. This helps it pick up oxygen in the lungs but means it releases less to the tissues. One way to describe the curve's position is the P50, the PaO2 at which hemoglobin is 50% saturated, which is about 26 mm Hg in normal adult blood (Collins et al., 2015).

In practice, a patient who has a fever and acidosis has a curve shifted to the right. At any given PaO2, that patient's saturation is lower, although the tissues can draw oxygen more easily. The registered nurse (RN) reads PaO2, SaO2 and SpO2 together, alongside pH and PaCO2 (Chapter 3, section 3.7). Ratios that combine PaO2 with the inspired oxygen are taught with acute respiratory failure in Chapter 15.

12.4 Oxygen Therapy

Oxygen is one of the most common treatments on medical and surgical units. Too little leaves tissues short of oxygen; too much brings its own harms. This section covers ordering, target ranges, devices used on general units, monitoring and weaning, and safety at home. Measuring oxygenation was covered in section 12.3; respiratory failure and ventilation are covered in Chapter 15.

Oxygen Is a Drug

Medical oxygen is a drug; in Canada its containers carry a Drug Identification Number (DIN) (College of Respiratory Therapists of Ontario [CRTO], 2022). Like any medication, it needs an order or a **medical directive**, an order written in advance for any patient who meets set conditions (College of Nurses of Ontario [CNO], 2025; Chapter 1, section 1.3). Respiratory therapists (RTs) hold their own legal authority for oxygen (CRTO, 2024), and in many hospitals nurses and RTs manage it together.

The order states an **oxygen target range** for SpO2 (section 12.3), and often a starting device and flow. The British Thoracic Society (BTS) guideline advises that every patient admitted to hospital have a target range ordered (O'Driscoll et al., 2017a).

In sudden critical illness, the BTS guideline states that oxygen is started at once and documented afterward; a missing prescription must never stop a patient from receiving oxygen they need (O'Driscoll et al., 2017a). Ontario law allows anyone to give first aid or temporary assistance in an emergency (College of Nurses of Ontario [CNO], 2025), and hospitals may have directives that let nurses start oxygen. The nurse follows policy, calls for help (Chapter 6), documents and obtains an order.

Target Ranges

Hypoxemia starves tissues of oxygen (section 12.1), but **hyperoxia**, more oxygen in the blood than the body needs, also harms. A systematic review known as IOTA pooled 25 randomized trials of more than 16,000 acutely ill adults. Liberal oxygen was associated with more deaths, whether measured in hospital, at 30 days or at the longest follow-up, with no gain in other outcomes that matter to patients; the authors suggested that supplemental oxygen may become unfavourable above an SpO2 of about 94% to 96% (Chu et al., 2018). A high saturation on supplemental oxygen also hides a later fall in SpO2, so deterioration is noticed late (Barnett et al., 2022).

Current guidelines agree on the principle; their ranges differ slightly:

- **Most acutely ill adults:** the BTS guideline recommends 94% to 98% (O'Driscoll et al., 2017a). The Thoracic Society of Australia and New Zealand (TSANZ) recommends 92% to 96% (Barnett et al., 2022). A BMJ Rapid Recommendation panel strongly recommended keeping SpO2 no higher than 96% in acutely ill adult medical patients on oxygen, and judged about 90% to 94% reasonable for most patients (Siemieniuk et al., 2018).
- **Patients at risk of hypercapnic respiratory failure:** all three suggest 88% to 92%. This group includes people with COPD, obesity hypoventilation syndrome or severe obesity, neuromuscular disease, chest wall deformities such as severe kyphoscoliosis, cystic fibrosis and bronchiectasis (Barnett et al., 2022; O'Driscoll et al., 2017a). The BTS guideline suggests this range pending blood gas results (O'Driscoll et al., 2017a).

The nurse works to the range the prescriber orders and asks for one when it is missing. The BMJ panel also recommended not starting oxygen in acute stroke or myocardial infarction when SpO2 on room air is above 92% (Siemieniuk et al., 2018).

Hypercapnia is a raised level of carbon dioxide in arterial blood (partial pressure of carbon dioxide [PaCO2] above 45 mm Hg). In susceptible patients, high oxygen concentrations can raise PaCO2 (Barnett et al., 2022; section 12.3). The answer is careful titration, never withholding oxygen: the BTS guideline warns never to delay or stop oxygen for a seriously ill patient, and that stopping it suddenly can cause life-threatening rebound hypoxemia (O'Driscoll et al., 2017a). An at-risk patient who is breathless, has a falling saturation or becomes drowsy needs a blood gas (O'Driscoll et al., 2017b; Chapter 3, section 3.7).

Figure 12.5 A nasal cannula, the most common low-flow oxygen device. (credit: "Nasal cannula" by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Delivery Devices

Oxygen devices fall into two groups. A **low-flow device** delivers a variable concentration of oxygen that depends on how fast and deeply the patient breathes; nasal cannulas, simple face masks and non-rebreather masks are in this group. A **high-flow device** delivers a fixed fraction of inspired oxygen (FiO2) whatever the patient's breathing pattern; Venturi masks and high-flow nasal cannulas are in this group (CRTO, 2022). Room air has an FiO2 of 0.21 (21%). Table 12.3 compares the devices used on general units.

The **nasal cannula** is the most common device (CRTO, 2022; Figure 12.5), and the BTS guideline prefers it for most patients who need oxygen (O'Driscoll et al., 2017a). The patient can talk and eat while wearing it. A simple face mask (Figure 12.6, a) must run at 5 L/min or more, because lower flows let the patient rebreathe carbon dioxide (Barnett et al., 2022). A **non-rebreather mask** has a reservoir bag and runs at 15 L/min for a seriously ill patient (O'Driscoll et al., 2017a; Figure 6.4).

A **Venturi mask** (air-entrainment mask) mixes oxygen with room air through a colour-coded valve to give a set concentration, often 24% or 28% for patients at risk of hypercapnia. Turning up the flow does not raise the concentration delivered (O'Driscoll et al., 2017a; Figure 12.6, b).

Figure 12.6 (a) A simple face mask. (b) A Venturi mask; the colour-coded valve sets the oxygen concentration. (credit: (a) “Simple face mask” and (b) “Venturi mask” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 12.7 A high-flow nasal cannula system on a pole stand, with an oxygen–air blender, a heated humidifier and heated tubing. Hospital policy decides where it is used. (credit: "High Flow Nasal Cannula Classic" by BreathDriver/Wikimedia Commons, CC BY-SA 4.0)

A **high-flow nasal cannula (HFNC)** delivers heated, humidified, blended air and oxygen through wide-bore nasal prongs at flows of up to 60 L/min (Barnett et al., 2022; CRTO, 2022; Figure 12.7). TSANZ advises considering it in selected patients with severe hypoxemic respiratory failure (Barnett et al., 2022). Hospital policy decides whether it is used on general units, and RTs often set it up.

Humidification adds water vapour to inspired gas. It is not needed for low-flow oxygen by mask or cannula, and it is reasonable for high-flow systems used for more than 24 hours. Bubble bottles, which bubble oxygen through a container of water, should not be used (O'Driscoll et al., 2017a). A tracheostomy bypasses the nose, so these patients need humidification (section 12.6).

Tubing and masks press on the skin. The nurse checks the ears, nares and bridge of the nose at each assessment and pads or repositions devices as policy allows (Chapter 35).

Table 12.3 Oxygen delivery devices on general units (Barnett et al., 2022; CRTO, 2022; O'Driscoll et al., 2017a; original wording)

Device	Flow range	Approximate oxygen delivered	Best used for	Nursing points
Nasal cannula (low flow)	About 1–4 L/min (BTS lists 2–6 L/min for most patients)	FiO2 about 0.24–0.35 at 1–4 L/min	Most patients who need modest oxygen	Comfortable; patient can eat and talk; check ears and nares for pressure; no humidifier needed for low flow
Simple face mask (low flow)	5–10 L/min	FiO2 about 0.35–0.60	Patients who need more oxygen than a cannula gives	Never run below 5 L/min (carbon dioxide rebreathing); remove for eating; watch for rising need

Device	Flow range	Approximate oxygen delivered	Best used for	Nursing points
Non-rebreather (reservoir) mask (low flow)	15 L/min	FiO2 above 0.60	Serious illness while the team assesses and escalates	Bag must stay inflated; a patient who needs it needs urgent medical review
Venturi (air-entrainment) mask (high flow)	Set by the colour-coded valve (for example, 24% at 2–3 L/min; 28% at 4 L/min)	FiO2 about 0.24–0.60, fixed by the valve	Patients at risk of hypercapnia who need a precise concentration	Raising the flow does not raise the concentration; change the valve to change FiO2, per order
High-flow nasal cannula	Up to 60 L/min, depending on the system	FiO2 about 0.21–1.0, set on a blender	Severe hypoxemic respiratory failure, per policy	Heated and humidified; RT usually sets up; rising FiO2 need calls for urgent review

Monitoring and Weaning

After every change of device, flow or FiO2, the nurse reassesses the whole patient: SpO2, respiratory rate, work of breathing, heart rate and level of consciousness. The BTS guideline asks that SpO2 be recorded after 5 minutes on a new oxygen setting, and that blood gases be rechecked after 30 to 60 minutes in a patient with COPD or another risk factor for hypercapnic respiratory failure (O'Driscoll et al., 2017a). The device, flow or FiO2 and SpO2 are documented together (O'Driscoll et al., 2017a). Oxygen treats hypoxemia, not breathlessness (CRTO, 2022); a breathless patient whose SpO2 is in range needs the cause found.

Weaning follows the order or directive. When the patient is stable and SpO2 is above range, oxygen is stepped down, usually to a low flow by cannula, and stopped once SpO2 is in range on two consecutive observations. The nurse watches SpO2 on room air for about 5 minutes and rechecks it an hour later. The target range stays on the order in case of deterioration (O'Driscoll et al., 2017a).

A rising oxygen need is a warning sign. TSANZ advises senior clinician review at an FiO2 of 0.40 or more (or 6 L/min or more by simple face mask) and intensive care review at an FiO2 of 0.50 or more (or 8 L/min or more by simple face mask) (Barnett et al., 2022). The nurse uses the early warning score, the rapid response team and SBAR (Situation, Background, Assessment, Recommendation) communication (Chapter 6).

MEDICATIONS

Oxygen

- **Indication:** hypoxemia, and emergencies in which hypoxemia is likely. Oxygen does not treat breathlessness when SpO2 is in the target range (CRTO, 2022).
- **How it is ordered:** as a target SpO2 range, often with a starting device and flow. The nurse adjusts the flow or device within the order or a medical directive to keep SpO2 in range (O'Driscoll et al., 2017a).
- **Adverse effects:** hyperoxia, which is linked to higher mortality in acutely ill adults (Chu et al., 2018); a rise in PaCO2 in patients at risk of hypercapnia (Barnett et al., 2022); dryness of the nose and mouth; pressure injuries from tubing and masks; and fire, because oxygen makes materials burn faster and hotter.
- **Monitoring:** SpO2, respiratory rate, work of breathing, heart rate and level of consciousness after each change; blood gases as ordered for patients at risk of hypercapnia.
- **Never:** stop oxygen abruptly in a patient at risk of hypercapnia, or delay oxygen in a seriously ill patient (O'Driscoll et al., 2017a).

Oxygen Safety and Home Oxygen

Oxygen does not burn, but it feeds a fire: clothing, bedding, hair and furniture ignite more easily and burn faster and hotter (City of Calgary, n.d.; Office of the Fire Marshal and Emergency Management [OFMEM], n.d.). Ontario's Fire Marshal reports that smoking materials are the most common source of ignition in fires, injuries and deaths involving medical oxygen in the province, and that smoking, including electronic cigarettes, is never safe in the home while oxygen is in use (OFMEM, n.d.). After several burn incidents involving people who used e-cigarettes while on home oxygen, Health Canada warned of the fire risk (Lacasse et al., 2015). Nurses offer smoking cessation support without judgment (Chapter 14). Fire services also advise keeping oxygen away from

flames and stoves, avoiding oily products such as petroleum jelly, and securing cylinders upright, with liquid oxygen at least 10 feet (about 3 m) from heat (City of Calgary, n.d.; OFMEM, n.d.).

In Ontario, home oxygen is funded through the Assistive Devices Program (ADP). A person qualifies by living in Ontario, holding a valid health card and meeting medical criteria, for example, low blood oxygen at rest; income is not considered. ADP pays 75% of the cost and the person pays 25%, but ADP pays the full cost for people aged 65 or older, people in long-term care, people on certain social assistance programs and people receiving services through Ontario Health atHome. A physician or nurse practitioner does the needed tests and completes the application form; an ADP-registered supplier submits it, sets up the system and teaches its use. Home oxygen must be renewed every year (Government of Ontario, 2025). Each other province and territory has its own program and rules.

Before discharge, the nurse helps the patient plan for travel, since carriers have their own rules for medical oxygen, and for power outages, since concentrators need electricity (Figure 12.8).

Figure 12.8 Home oxygen equipment: (a) an oxygen concentrator, which runs on electricity; (b) a portable oxygen cylinder with a regulator. (credit: (a) "Invacare Perfecto 2 Oxygen Concentrator" by BrokenSphere/Wikimedia Commons, CC BY-SA 3.0)

CLINICAL SAFETY

Oxygen and Fire

Oxygen-enriched air turns a small spark into a fast, hot fire, and the face and airway are closest to the source. In hospital and at home, the nurse:

- confirms that no one smokes or vapes near oxygen, including in a bathroom or at a doorway; smoking is never safe while oxygen is in use (OFMEM, n.d.);
- keeps oxygen away from open flames, heaters and stoves, and from sparking devices such as hair dryers and electric razors (City of Calgary, n.d.; OFMEM, n.d.);
- avoids petroleum jelly and oil-based creams on the face while oxygen is in use (OFMEM, n.d.);

- secures cylinders upright (City of Calgary, n.d.) and turns oxygen off at the source when it is not in use;
- knows the hospital fire plan: where the oxygen shut-off valves are and who may close them.

If a patient's tubing or mask catches fire, the nurse removes the device, turns off the oxygen and follows the fire response plan.

PATIENT EDUCATION

Living With Home Oxygen

The nurse teaches the patient and family, using teach-back:

- **Use oxygen as prescribed.** Use the flow rate and the hours of use the prescriber set. Do not change the flow without asking.
- **Never smoke or vape near oxygen.** Ask visitors not to smoke in the home. Put up "No Smoking" and "No Open Flames" signs both inside the home and outside it (City of Calgary, n.d.).
- **Keep it away from heat.** Stay well away from stoves, candles, fireplaces and gas or kerosene heaters. Never cook with the oxygen on (City of Calgary, n.d.).
- **Choose skin products carefully.** Avoid petroleum jelly and oily lotions while oxygen is in use (OFMEM, n.d.).
- **Store cylinders safely.** Keep cylinders secured and upright, and follow the supplier's instructions (City of Calgary, n.d.).
- **Protect the skin.** Check behind the ears and inside the nose for soreness every day.
- **Plan ahead.** Ask the supplier about backup oxygen for a power outage, and check rules with the airline or carrier before travelling.
- **Know when to call.** Increased breathlessness, new confusion or drowsiness, or chest pain needs prompt care; call 9-1-1 for severe breathlessness or chest pain.

12.5 Airway Clearance

Pain, weakness, sedation, immobility and thick secretions all make it harder to clear mucus. Retained secretions block small airways and can cause atelectasis (collapse of alveoli) and infection. This section covers everyday measures and suctioning. Postoperative pulmonary complications are covered in Chapter 7, section 7.6, and pneumonia in Chapter 13.

Helping Patients Clear Secretions

The first steps are simple. The nurse helps the patient sit upright, take slow deep breaths and cough effectively. A **huff cough** (the forced expiratory technique) is a forced breath out through an open mouth and throat, rather than a cough against a closed glottis (Strickland et al., 2013). Some patients find huffing easier than coughing. An American Association for Respiratory Care (AARC) guideline for hospitalized patients advises that teaching effective cough technique may help, and that extra airway clearance treatments are not needed when a patient can clear secretions by coughing (Strickland et al., 2013).

Moving is one of the best airway clearance treatments. The same guideline recommends early mobility and walking after surgery, both to reduce complications and to help clear the airways (Strickland et al., 2013). Pain control matters too. A patient who splints the chest or abdomen because of pain takes shallow breaths and avoids coughing, while too much sedation blunts breathing and cough (Chapter 5). A pillow held firmly over an incision makes coughing easier.

An **incentive spirometer** (Figure 7.1) is a hand-held device that gives visual feedback as the patient breathes in slowly and deeply. The steps below follow the technique in the AARC guideline (Restrepo et al., 2011):

1. The patient sits up and holds the device upright.

2. The patient breathes out normally, then seals the lips tightly around the mouthpiece.

3. The patient breathes in slowly, raising the indicator toward the target set for them, and keeps the lungs inflated for at least 5 seconds.

4. At full inspiration, the patient removes the mouthpiece, holds the breath, then breathes out normally.

5. After a rest, the patient repeats the breaths, then coughs or huffs.

No specific frequency is supported by evidence; studies have used, for example, 10 breaths every 1 to 2 hours while awake. After a return demonstration, the patient is encouraged to use the device independently. The guideline does not recommend incentive spirometry alone as routine care before or after surgery; it recommends using it together with deep breathing, directed coughing, early mobility and good pain control, and suggests that deep breathing exercises give the same benefit. It is not suitable for patients who cannot understand or be supervised in its use, such as those who are delirious or heavily sedated, or for patients who cannot breathe deeply because of pain (Restrepo et al., 2011). Its role after surgery is discussed in Chapter 7, section 7.6.

A **positive expiratory pressure (PEP) device** makes the patient breathe out against resistance, which helps hold airways open; oscillating PEP devices add vibration to loosen mucus. Evidence for routine PEP is limited outside cystic fibrosis, and AARC suggests that airway clearance treatments may be considered for patients with COPD whose secretions are hard to clear, guided by the patient's preference (Strickland et al., 2013). **Chest physiotherapy**, which uses percussion, vibration and postural drainage, is not recommended for routine treatment of uncomplicated pneumonia (Strickland et al., 2013). Physiotherapists and RTs assess for and provide these treatments. Patients with neuromuscular disease and a weak cough may need cough-assist techniques from the RT (Strickland et al., 2013).

Oral and Nasopharyngeal Suctioning

Suctioning is used when a patient cannot clear secretions despite their best cough. The nurse looks for cues: visible secretions, gurgling sounds or coarse crackles, reduced breath sounds, more effort to breathe, a falling SpO2 and restlessness (American Association for Respiratory Care [AARC], 2004). Suctioning is uncomfortable and has risks, so it is done when assessment shows a need, not on a fixed schedule.

Figure 12.9 Oral suctioning with a rigid Yankauer suction tip on a manikin. (credit: “Suctioning with a yankauer” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Oral suctioning clears the mouth and the back of the throat with a rigid suction tip, often called a Yankauer (Figure 12.9). It helps a patient who has a weak cough, cannot swallow secretions or is vomiting. The nurse sweeps the tip along the cheeks and gums and avoids touching the back of the throat, which can trigger gagging.

Nasopharyngeal and nasotracheal suctioning pass a flexible catheter through the nose into the pharynx or the trachea of a patient who has no artificial airway. Suction is applied only while the catheter is withdrawn. When suctioning is needed often, a nasopharyngeal airway protects the nose from repeated trauma (AARC, 2004). The AARC guideline lists epiglottitis and croup as absolute contraindications. Relative contraindications include blocked nasal passages, a nosebleed, an acute injury to the head, face or neck, a bleeding disorder, laryngospasm, an irritable airway and recent tracheal surgery. For adults, it advises suction pressures of about 100 to 150 mm Hg, never more than 150 mm Hg, and suction applied for no more than 15 seconds (AARC, 2004). Complications include hypoxemia, bronchospasm, laryngospasm, nosebleed, slow or irregular heart rhythms and vomiting. The nurse monitors SpO2, heart rate and rhythm, breathing and the patient's response before, during and after the procedure, and documents the amount, colour and thickness of the secretions (AARC, 2004). Passing a catheter beyond where the nasal passages narrow is a controlled act in Ontario (Scope in Practice box, section 12.6).

Suctioning can spread respiratory droplets. The nurse uses Routine Practices and any additional precautions the patient's condition calls for (Chapter 4).

Patients with reduced consciousness, a weak cough or a swallowing problem are at risk of aspiration. The nurse keeps the head of the bed raised unless contraindicated, keeps suction at the bedside, and asks for a speech-language pathologist (SLP) swallowing assessment when the patient coughs or chokes on food or drink.

CLINICAL JUDGMENT

Falling Saturation After Surgery

Names and details are fictional; this is a composite story.

Ms. Gloria Mendes, 58, is on day 1 after an open bowel resection. She has an opioid by patient-controlled analgesia and oxygen at 2 L/min by nasal cannula, ordered to keep SpO2 at 92% to 96%.

- **Recognize cues:** At 0800, SpO2 is 93%. By 1100 it is 89%, then 88%. Her respiratory rate is 24 with shallow breaths. She holds her abdomen and will not cough: "It hurts too much." Breath sounds are diminished at both bases. She answers questions but drifts off between them. Her temperature is 37.9 °C.
- **Analyze cues:** Shallow breathing and a weak cough suggest atelectasis and retained secretions, with pain as a cause. Her drowsiness raises a second concern: opioid-induced respiratory depression (Chapter 5, section 5.4).
- **Prioritize hypotheses:** Her low SpO2 is the most urgent problem; it may be worsened by both splinting and sedation.
- **Generate solutions:** Restore SpO2 within the ordered range, assess sedation with a validated scale, improve pain control without deeper sedation, and clear secretions.
- **Take action:** The nurse sits Ms. Mendes upright and increases the oxygen within the order to reach the target range. She assesses sedation and respiratory rate, and calculates the early warning score (Chapter 6). She calls the surgical resident using SBAR, reporting falling SpO2, rising oxygen need, drowsiness and fever, and asks for a pain review. With a pillow over the incision, she coaches huff coughing and incentive spirometry (Chapter 7, section 7.6).
- **Evaluate outcomes:** An hour later, SpO2 is 94% on 3 L/min, Ms. Mendes is alert, and she coughs up thick sputum. The nurse plans to walk with her that afternoon and to wean the oxygen as SpO2 allows.

12.6 Artificial Airways and Tracheostomy Care

Some patients need help keeping their airway open. This section covers simple airway adjuncts, the endotracheal tube in brief, and care of the patient with a tracheostomy, including the emergencies every nurse must be able to recognize and act on.

Artificial Airways

An **oropharyngeal airway** is a curved plastic device placed in the mouth to hold the tongue away from the back of the throat. It is used for a patient with a markedly reduced level of consciousness; a more alert patient may gag on it. A **nasopharyngeal airway** is a soft tube passed through a nostril into the pharynx. The AARC nasotracheal suctioning guideline recommends one when suctioning is needed often (AARC, 2004). Both devices are sized to the patient, are inserted by trained staff as policy allows, and need regular checks of placement and skin.

An **endotracheal tube** passes through the mouth or nose and the larynx into the trachea. It is placed by a trained provider, usually for mechanical ventilation in critical care (Chapter 15).

Tracheostomy Basics

A **tracheostomy** is a surgical opening into the front of the trachea, held open by a tube. Unless the upper airway itself is blocked, air may still pass between the mouth and nose and the lungs, so in an emergency oxygen is given to both the face and the tracheostomy (National Tracheostomy Safety Project [NTSP], n.d.-b). A **laryngectomy** is different: the larynx is removed and the trachea is brought out to the skin of the neck as an end stoma. A patient after laryngectomy is a **neck breather**, with no connection between the mouth and nose and the lungs, and cannot be given oxygen or ventilated by the mouth or nose (NTSP, n.d.-b). Usually no tube sits in a laryngectomy stoma (NTSP, n.d.-b). Bedside signs that state which airway the patient has are essential.

Tracheostomy tubes vary, but they share common parts (Figure 12.10):

- **Outer cannula:** the main tube that sits in the trachea.
- **Flange:** the flat plate that rests on the neck and holds the ties.
- **Inner cannula:** a removable tube inside the outer cannula. It can be taken out to be cleaned or replaced, or removed at once if secretions block it (Hess & Altobelli, 2014; NTSP, n.d.-a).

- **Cuff:** a balloon near the tip of some tubes. When inflated, it seals the trachea, so air passes through the tube rather than around it. Tubes may be cuffed or uncuffed (Hess & Altobelli, 2014).
- **Fenestration:** an opening in the back wall of some tubes, above the cuff. With the cuff deflated, it lets air pass up through the larynx for speech; a solid inner cannula closes it (Hess & Altobelli, 2014).
- **Obturator:** a smooth, rounded guide placed inside the tube during insertion and taken out as soon as the tube is in position (Hess & Altobelli, 2014). It is kept at the bedside.

The cuff pressure is checked routinely and adjusted as needed (Mitchell et al., 2013). Higher pressures raise the risk of injury to the trachea, and a pressure that is too low makes silent aspiration more likely; one review gives 20 to 30 cm H2O as the range to maintain (Hess & Altobelli, 2014). Who measures it, and the range used, are set by hospital policy; RTs often do this.



Figure 12.10 Tracheostomy equipment, from left: obturator, cuffed tube, uncuffed tube and tracheal dilators. (credit: "Obturator, cuffed tracheostomy tube, non-cuffed tracheostomy tube, tracheal dilators" by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Tracheostomy Care

Tracheostomy care keeps the airway open, the skin healthy and the patient safe. The nurse assesses the stoma at least every shift for redness, swelling, discharge, odour, bleeding and skin breakdown, and cleans the stoma and under the flange as policy directs. The inner cannula is cleaned or replaced regularly in hospital and at home (Mitchell et al., 2013). Ties hold the tube securely; the nurse checks their fit and changes them as policy directs, with a second person holding the tube when policy requires it. An American consensus statement advises using ties unless the patient has had a recent flap reconstruction (Mitchell et al., 2013).

A tracheostomy bypasses the nose, which normally warms and moistens air. Humidification is used after surgery and as needed afterward, for example with thick secretions (Mitchell et al., 2013). A heat and moisture exchanger or a humidified tracheostomy mask is used, as ordered.

The supplies needed to replace the tube must be kept within reach at the bedside (Mitchell et al., 2013). The nurse checks the bedside emergency equipment at the start of every shift. Policy sets the list, which usually includes:

- a spare tube of the same size and one a size smaller, and the obturator;
- working suction with catheters of the right size;
- oxygen, with a tracheostomy mask and a face mask;
- a bag-valve mask;
- spare ties, scissors, gloves and water-based lubricant.

Losing one's voice is frightening. A communication plan starts before a planned tracheostomy, and may include an SLP referral and a speaking valve (Mitchell et al., 2013). Writing boards, picture boards, a call bell within reach, and yes-or-no questions help. A **speaking valve** is a one-way valve that lets air in through the tube and sends exhaled air up through the larynx so the patient can speak. A patient must never use a speaking or swallowing valve while the cuff is inflated (Mitchell et al., 2013); the cuff must be completely deflated first (Hess & Altobelli, 2014), because with the cuff up and the valve on, the patient cannot breathe out. The cuff is deflated and the valve is placed only after the team, often the SLP and RT, has assessed the patient. An SLP often assesses swallowing before the patient eats or drinks. Tracheostomy care follows infection prevention and control (IPAC) practices (Chapter 4).

Suctioning a Tracheostomy

The tube is suctioned when assessment shows a need, such as secretions that can be seen or heard in the airway or changed breath sounds, not on a routine schedule (Blakeman et al., 2022; Mitchell et al., 2013). The AARC artificial airway suctioning guideline recommends the following (Blakeman et al., 2022):

- Give extra oxygen before suctioning (preoxygenation).
- Use shallow suctioning routinely, passing the catheter only to a premeasured depth at about the end of the tube; use deep suctioning only when shallow suctioning does not work.
- Choose a catheter that blocks less than half of the airway's lumen in adults, so air can flow around it.
- Keep suction below 200 mm Hg of negative pressure in adults, and as low as will work.
- Keep suctioning as brief as possible, applying suction for no more than 15 seconds.
- Generally avoid putting normal saline down the tube.
- Use sterile technique for open suctioning when possible, and perform hand hygiene immediately before.

The nurse lets the patient recover between passes, watches SpO2, heart rate and rhythm, and documents the secretions and the patient's tolerance. Closed (in-line) and open systems can both be used safely in adults (Blakeman et al., 2022). The technique taught for home may differ; the team decides it.

Tracheostomy Emergencies

Tracheostomy emergencies include **decannulation** (the tube coming out of the trachea), a blocked tube and bleeding. Bedside staff are the first to recognize and respond to them (NTSP, n.d.-a). Cues include noisy or high-pitched breathing (stridor), no air moving at the tube, a suction catheter that will not pass, a tube that looks longer or sits at an odd angle, air or voice leaking around the tube, distress, agitation and a falling SpO2. Published guidance teaches first responders to call for help, assess the airway, apply oxygen, remove speaking valves and inner tubes, and try to pass a suction catheter: the problems that are easiest to fix come first (McGrath et al., 2012; NTSP, n.d.-a). Table 12.4 summarizes these first actions.

Table 12.4 Tracheostomy emergencies: cues and first actions (based on Mitchell et al., 2013; NTSP, n.d.-a, n.d.-b; original wording)

Emergency	Cues	First nursing actions	Who to call
Blocked tube	Noisy or no airflow at the tube; suction catheter will not pass; distress; falling SpO2	Call for help; give oxygen to the face and the tube; remove the speaking valve, cap or heat and moisture exchanger; remove the inner cannula; try to pass a suction catheter; if it still will not pass, deflate the cuff if trained to do so	Rapid response or code team and the airway team, per policy
Displaced tube or decannulation	Tube partly or fully out, or longer than usual; air or voice escaping around it; distress; falling SpO2	Call for help; give oxygen to the face and the stoma; do not force the tube back; bring the spare tubes and obturator for the responding team, which reinserts the same size or one size smaller	Rapid response or code team, and the team that placed the tube if it is new
Bleeding	Fresh blood from the stoma or in suctioned secretions; coughing blood	Call for help at once; give oxygen to the face and the tracheostomy; suction to keep the tube clear; record the amount	Rapid response or code team and the surgical team
Laryngectomy stoma blocked	Neck breather with noisy or no airflow at the stoma; distress	Call for help; give high-flow oxygen at the stoma, and if unsure whether the patient is a neck breather, give it over the face too; remove any stoma cover and any tube in the stoma; suction through the stoma; do not remove a voice prosthesis (tracheoesophageal puncture prosthesis)	Rapid response or code team and the airway team

If the tube cannot be cleared, an expert removes and replaces it, using a tube of the same size or one size smaller (Mitchell et al., 2013). If the patient stops breathing, the resuscitation team takes over the airway; for a neck breather, ventilation must go through the stoma (NTSP, n.d.-b). After any emergency, the nurse documents the event and the team reviews it.

Going Home With a Tracheostomy

Teaching starts early and involves the patient and family caregivers. Before discharge, caregivers learn to use all the home equipment, to clean the stoma and the tube, and to recognize breathing distress and signs of infection or skin breakdown. They should receive a written home care manual (Mitchell et al., 2013). Each caregiver practises suctioning, inner cannula care, tie changes and the emergency plan with return demonstration. The plan names who to call, where the spare tubes are, and that 9-1-1 is called for an airway emergency. When the patient or family cannot manage care, home nursing should be considered (Mitchell et al., 2013). In Ontario, home and community care is arranged through Ontario Health atHome, and home equipment is arranged by the team and suppliers. The nurse also confirms that the patient has a way to call for help without speaking.

SCOPE IN PRACTICE

Suctioning and Tracheostomy Care

- **Authority:** In Ontario, putting an instrument beyond the point where the nasal passages narrow, beyond the larynx or into an artificial opening into the body is a controlled act, as is administering a substance by inhalation. RNs and RPNs are authorized to perform these acts with an order or directive, or by initiation where the regulation allows it. Nurses cannot initiate controlled acts in public hospitals (CNO, 2025). Tracheostomy suctioning and nasotracheal suctioning therefore need an order or medical directive in a public hospital. The law also allows people to assist a person with routine activities of living that involve some of these acts (CNO, 2025), which matters when family caregivers learn tracheostomy care. RTs hold their own authority to suction beyond the larynx (an order is needed in a public hospital) and, with an order, to change tracheostomy tubes (CRTO, 2024).
- **Competence:** The nurse performs only the care they have the knowledge, skill and judgment to do safely, and seeks education first.
- **Context:** Employer policy decides who changes tracheostomy tubes, who manages cuffs and HFNC, and whether these patients are assigned to RNs, RPNs or both. In an airway emergency, every nurse acts at once and calls for help. The RPN consults the RN as the patient's needs change.
- Other provinces and territories differ. CNO's revised Scope of Practice standard takes effect March 1, 2027.

PRACTICE STORY

The Quiet Alarm

Names and details are fictional; this is a composite story.

Nurse: Sonia Subramanian, RN. Years in practice: 6. Setting: medical unit, community hospital, Ontario.

It was 0320, and Mr. Harold Fitzgerald's oximeter was beeping softly. He was 72 and had come to us from the intensive care unit four days earlier with a cuffed tracheostomy after a long stay with pneumonia. At bedtime his secretions had been thick, and I had suctioned him once.

When I walked in, he was sitting bolt upright, eyes wide, pulling at his gown. His SpO2 read 85%. I held my hand over the tube and felt almost nothing. I pressed the call bell for help, asked my RPN colleague to call the rapid response team, and put the oxygen on his face and over the tube.

Then I went through the steps we had practised in our skills day. I took off the heat and moisture exchanger and pulled out the inner cannula. It was packed with dried mucus. I could hear air rush through the outer tube. I passed a suction catheter, and it slid in easily; I cleared thick, tan secretions. His SpO2 climbed to 90%, then 94%, and he let go of his gown.

The rapid response team arrived to a patient who was breathing comfortably. The RT put in a new inner cannula, checked the cuff and increased the humidification. We reviewed his chart together: his humidifier had been switched to a smaller device during transfer, and nobody had changed it back.

What stays with me is how quiet it was. He could not call out. If I had waited to finish my charting, the outcome could have been very different. Now I check the bedside equipment and humidification at the start of every shift, and I teach new staff where the spare inner cannula is kept.

Reflect: Which cues told Priya the tube was blocked, and why did she start with the inner cannula? Under CNO's Scope of Practice standard, what authority, competence and context would an RPN need to suction this tracheostomy, and when should the RPN involve the RN?

Chapter 12 Summary

Introduction

- A change in breathing is often one of the first signs that a patient is deteriorating; nurses check airway and breathing first and reassess them often.
- This chapter covers the brief respiratory review, focused assessment, pulse oximetry, oxygen therapy, airway clearance and artificial airways.

12.1 Breathing and Gas Exchange: A Brief Review

- Ventilation moves air; compliance and airway resistance determine the work of breathing.
- Oxygen and CO2 cross the alveolar–capillary membrane by diffusion; V/Q mismatch is the most common cause of hypoxemia, and shunt responds poorly to extra oxygen.
- Hypoxemia is low arterial oxygen; hypoxia is too little oxygen in the tissues.
- The "hypoxic drive" explanation is a myth; oxygen is never withheld from a hypoxemic patient, but is given to the ordered target range.
- The oxygen–hemoglobin curve is flat above about 90% saturation and steep below a PaO2 of about 60 mm Hg, so a falling trend needs prompt action.

12.2 Focused Respiratory Assessment

- The history covers dyspnea (with a scale such as the mMRC), cough and sputum, pleuritic pain, smoking and vaping, exposures including radon, and home devices.
- Respirations are counted for a full 60 seconds without the patient's awareness; shorter counts underestimate the rate.
- Increased work of breathing (accessory muscles, retractions, tripod position, short phrases) needs action even when SpO2 looks acceptable.
- Cyanosis and pallor are late, unreliable signs, especially on darker skin; the nurse looks at the tongue, lips and mouth, compares with baseline and asks the patient or family.
- Auscultation is done on bare skin, top to bottom, side to side; crackles, wheezes, rhonchi, stridor and friction rubs each suggest different problems, and stridor is an emergency.

12.3 Pulse Oximetry and Other Measures

- Pulse oximeters estimate SaO2 from red and infrared light; trends and the whole patient matter more than one reading.
- Pulse oximeters can overestimate saturation in darker skin pigmentation, causing occult hypoxemia; race-based correction is never used.
- Poor perfusion, motion, nail polish, ambient light, carbon monoxide and severe anemia also affect readings; carbon monoxide gives falsely normal values.
- SpO2 does not measure CO2 or ventilation; capnography and the ABG fill that gap.
- Canadian laboratories report PaO2 in mm Hg, with reference ranges that vary by laboratory; venous blood gases cannot assess oxygenation.

12.4 Oxygen Therapy

- Oxygen is a drug: it needs an order or medical directive, except that it is started at once in an emergency and documented afterward.
- The order states a target SpO2 range. Guidelines suggest about 92% to 96% (TSANZ) or 94% to 98% (BTS) for most acutely ill adults, no higher than 96% (BMJ), and 88% to 92% for patients at risk of hypercapnia.
- Liberal oxygen is linked to higher mortality and hides deterioration, but oxygen is never delayed or stopped for a seriously ill patient, and it is never stopped suddenly in a patient at risk of hypercapnia.

- Low-flow devices (nasal cannula, simple face mask, non-rebreather) give a variable FiO2; high-flow devices (Venturi mask, HFNC) give a fixed FiO2.
- The nurse reassesses after each change, weans when the patient is stable and above range, and escalates a rising oxygen need.
- Oxygen feeds fire: no smoking or vaping, no flames or oily products, cylinders secured upright. Ontario's ADP funds home oxygen; other provinces and territories have their own programs.

12.5 Airway Clearance

- Upright positioning, deep breathing, huff coughing, early mobility and good pain control are the foundation of airway clearance.
- Incentive spirometry needs a slow, deep breath held for at least 5 seconds; AARC recommends it only alongside deep breathing, coughing, mobility and analgesia, not alone.
- Chest physiotherapy and PEP devices are not routine; physiotherapists and RTs assess for them.
- Suctioning is done when assessment shows a need. Nasotracheal suctioning is avoided with facial, head or neck injury and in other listed conditions, and is limited to 15 seconds per pass.

12.6 Artificial Airways and Tracheostomy Care

- Oropharyngeal airways are for patients with a markedly reduced level of consciousness; a nasopharyngeal airway helps when nasotracheal suctioning is needed often.
- A patient with a tracheostomy may still move air through the upper airway, so oxygen goes to the face and the tracheostomy in an emergency; a neck breather after laryngectomy cannot, so oxygen goes to the stoma.
- Daily care covers the stoma, inner cannula, ties, humidification, communication and bedside emergency equipment, including spare tubes of the same size and one size smaller.
- Tracheostomy suctioning follows AARC guidance: preoxygenate, shallow passes, catheter under half the lumen, adult pressure below 200 mm Hg, no more than 15 seconds, no routine saline.
- In a blocked or displaced tube, the nurse calls for help, gives oxygen to the face and stoma, removes the speaking valve and inner cannula, and tries a suction catheter.

Key Terms (60)

airway resistance: how much the airways oppose airflow; narrowing from spasm, swelling or secretions raises it.

alveolar–capillary membrane: the thin barrier between alveolar air and capillary blood across which oxygen and carbon dioxide diffuse.

alveoli: the tiny air sacs at the ends of the smallest airways, where gas exchange takes place.

arterial blood gas (ABG): analysis of an arterial blood sample for pH, PaCO2, bicarbonate, PaO2 and SaO2.

capnography: continuous measurement of carbon dioxide in each exhaled breath, used to monitor ventilation.

carotid bodies: small clusters of sensing cells beside the carotid arteries that respond to low arterial oxygen and to acidity.

central cyanosis: a bluish or greyish colour of the tongue, lips and oral lining that signals low arterial oxygen.

chest physiotherapy: External chest wall techniques (percussion, vibration and postural drainage) used to help move secretions.

Cheyne–Stokes breathing: a repeating cycle of breaths that deepen, then fade, followed by a pause in breathing.

clubbing: painless enlargement of the fingertips with loss of the normal angle at the nail bed, linked to lung cancer and chronic lung and heart disease.

compliance: how easily the lungs and chest wall stretch; low compliance makes each breath take more effort.

crackles: brief, non-musical, discontinuous popping sounds, usually heard when breathing in; described as fine or coarse.

cuff: A balloon near the tip of some tracheostomy and endotracheal tubes that seals the trachea when inflated.

dead space: air that reaches alveoli with little or no blood flow and so takes no part in gas exchange.

decannulation: Removal of a tracheostomy tube from the trachea, planned or accidental.

diffusion: the movement of a gas from an area of higher partial pressure to one of lower partial pressure, as across the alveolar–capillary membrane.

dyspnea: the patient's own experience of uncomfortable or difficult breathing.

endotracheal tube: A tube passed through the mouth or nose and the larynx into the trachea, usually for mechanical ventilation.

hemoptysis: coughing up blood.

high-flow device: An oxygen device that delivers a fixed FiO2 whatever the patient's breathing pattern, such as a Venturi mask or high-flow nasal cannula.

high-flow nasal cannula (HFNC): A system that delivers heated, humidified, blended air and oxygen through wide-bore nasal prongs at high flows and a set FiO2.

huff cough: A forced breath out through an open mouth and throat (the forced expiratory technique), used to move secretions.

humidification: Adding water vapour to inspired gas to prevent drying of the airway.

hypercapnia: A raised level of carbon dioxide in arterial blood (PaCO2 above 45 mm Hg).

hyperoxia: More oxygen in the blood than the body needs; in acutely ill adults, liberal oxygen use is linked to higher mortality.

hypoxemia: a low level of oxygen in the arterial blood.

hypoxia: too little oxygen in the body's tissues.

hypoxic pulmonary vasoconstriction: narrowing of small pulmonary arteries in poorly ventilated lung, which steers blood toward better-ventilated alveoli.

incentive spirometer: A hand-held device that gives visual feedback to encourage slow, deep breaths held at full inspiration.

inner cannula: A removable tube inside a tracheostomy tube that can be cleaned or replaced, or removed at once if secretions block it.

Kussmaul breathing: deep, rapid breathing seen in metabolic acidosis.

laryngectomy: Surgical removal of the larynx, after which the trachea opens to the neck as an end stoma.

low-flow device: An oxygen device whose delivered concentration varies with the patient's breathing pattern, such as a nasal cannula, simple face mask or non-rebreather mask.

medical directive: An order written in advance by an authorized prescriber that applies to any patient who meets set conditions.

nasal cannula: Two short prongs in the nostrils that deliver low-flow oxygen; the most common oxygen device.

nasopharyngeal airway: A soft tube passed through a nostril into the pharynx to keep the upper airway open.

neck breather: A person who breathes only through a neck stoma after laryngectomy and cannot be oxygenated or ventilated through the mouth or nose.

non-rebreather mask: A face mask with a reservoir bag, run at 15 L/min, that delivers a high oxygen concentration to a seriously ill patient.

obturator: A rounded guide placed inside a tracheostomy tube during insertion; kept at the bedside.

occult hypoxemia: low arterial oxygen saturation hidden by a pulse oximetry reading that looks acceptable.

oropharyngeal airway: A curved device placed in the mouth to hold the tongue off the back of the throat in a patient with a markedly reduced level of consciousness.

oxygen target range: The SpO2 range the prescriber orders, within which the nurse adjusts oxygen.

oxygen–hemoglobin dissociation curve: the S-shaped curve relating PaO2 to hemoglobin saturation; flat above about 90% saturation and steep below a PaO2 of about 60 mm Hg.

perfusion: blood flow through the capillaries of the lungs.

peripheral cyanosis: a bluish colour limited to the fingers, toes or nail beds, usually from slow peripheral blood flow.

pleural friction rub: a grating or creaking sound in both phases of breathing, caused by inflamed pleural layers rubbing together.

positive expiratory pressure (PEP) device: A device that makes the patient breathe out against resistance to help hold airways open; oscillating versions add vibration.

pulse oximetry: a non-invasive method that estimates arterial oxygen saturation (SpO2) from the absorption of red and infrared light by pulsing arterial blood.

rhonchi: low-pitched, continuous, snoring sounds; used interchangeably with "low-pitched wheeze."

shunt: blood flow past alveoli that receive no air, so the blood returns to the heart without gaining oxygen.

speaking valve: A one-way valve on a tracheostomy tube that lets air in and directs exhaled air up through the larynx for speech; used only with the cuff deflated.

stridor: a loud, high-pitched, musical sound, mainly on breathing in, that signals a narrowed upper airway and is an emergency.

subcutaneous emphysema: air trapped under the skin, felt as crackling under the fingertips.

tactile fremitus: the vibration felt through the chest wall when a patient speaks.

tracheostomy: A surgical opening into the front of the trachea, held open by a tube.

ventilation: the movement of air into and out of the lungs.

ventilation–perfusion (V/Q) mismatch: an imbalance between the air reaching parts of the lung and the blood flowing past them; it causes hypoxemia more often than any other mechanism.

Venturi mask: An air-entrainment mask that mixes oxygen with room air through a valve to give a fixed oxygen concentration.

wheeze: a continuous, musical sound produced by narrowed airways, usually heard when breathing out.

work of breathing: the effort the breathing muscles spend to move air; signs of increased work include accessory muscle use, retractions and speaking in short phrases.

Licensure Review & Clinical Judgment Questions (35)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Florence Mensah (Questions 1–4): Florence Mensah, 81, was admitted to a medical unit in Kingston, Ontario, two days ago with cellulitis of the left leg. Tonight she says she "can't catch her breath." A registered practical nurse (RPN) is caring for her, with an RN on the team. Mrs. Mensah has dark skin.

1. [CORE] Which finding best shows that Mrs. Mensah's work of breathing has increased?

a. She sits forward, hands on her knees, speaking a few words per breath.

b. Her respiratory rate, counted over one full minute, is 18 breaths/min.

c. Her chest rises equally on both sides each time she breathes in.

d. She says she slept poorly last night because of noise on the unit.

Answer: a — The tripod position and speaking only a few words between breaths are signs of increased work of breathing (a) (section 12.2). A rate of 18 breaths/min counted over a full minute (b) and equal chest rise (c) are reassuring findings. Poor sleep from noise (d) does not reflect her breathing effort.

2. [CORE] The RPN wants to check Mrs. Mensah for central cyanosis. Which approach is best?

a. Press on a fingernail and time how long the colour takes to return to normal.

b. Compare the skin on her forearms with the skin on her chest under the room light.

c. Inspect her tongue, lips and mouth in good light; ask family about her usual colour.

d. Rely on the pulse oximeter alone, because cyanosis cannot be seen on dark skin.

Answer: c — Central cyanosis appears in the tongue, lips and lining of the mouth. Good light and a comparison with the patient's usual colour, which the patient or family can describe, improve assessment on every skin tone (c) (section 12.2). Nail bed refill (a) tests peripheral circulation, not central oxygenation. Skin on the arms and chest (b) is a poor place to judge oxygen, especially on darker skin. Pulse oximetry is useful, but it may overestimate saturation in darker skin pigmentation, and the nurse still looks at the patient (d) (section 12.3).

3. [CORE] On auscultation, the RPN hears soft, high-pitched popping sounds at both lung bases late in each breath in. These sounds do not clear when Mrs. Mensah coughs. How should the RPN interpret this finding?

a. Stridor, which suggests narrowing of the upper airway

b. A pleural friction rub, which suggests inflamed pleura

c. Wheezes, which suggest narrowing of the small airways

d. Fine crackles, which may suggest fluid in the small airways

Answer: d — Brief, soft, high-pitched popping sounds late in inspiration are fine crackles. They can occur in early heart failure and interstitial lung disease, among other causes (d) (section 12.2, Table 12.1). Stridor (a) is a loud, musical sound heard mainly over the neck. A friction rub (b) is a grating sound heard in both phases. Wheezes (c) are continuous and musical, not popping.

4. [CORE] Mrs. Mensah's SpO2 reads 95% on room air. Her respiratory rate is 28 breaths/min, she is newly restless, and she looks unwell to the RPN. What should the RPN do next?

a. Record the SpO2 as normal and reassess her at the next scheduled set of vital signs.

b. Promptly report all of her findings, not just the SpO2, to the RN and escalate per policy.

c. Move the probe from finger to finger until the reading rises to above 97%.

d. Subtract 3% from the reading to correct for her skin colour, and act on that value.

Answer: b — A rising respiratory rate and new restlessness are warning signs. Pulse oximeters can overestimate saturation in people with darker skin pigmentation, so the nurse acts on the whole patient and escalates; the team may request an ABG (b) (section 12.3; Chapter 6). Reassuring herself with the SpO2 (a) delays care. Moving the probe in search of a higher number (c) is a misuse of the device. No validated correction exists, and race- or colour-based adjustments are never used (d).

5. [CORE] A nurse is assessing a patient's respiratory rate. Which technique gives the most accurate count?

a. Count the breaths for 15 seconds, then multiply the result by 4.

b. Ask the patient to breathe normally, then count for 30 seconds and double it.

c. Use the rate recorded at the last vital signs if the patient looks comfortable.

d. Count for a full 60 seconds while the patient is unaware of the count.

Answer: d — Counting for a full minute, without the patient knowing, avoids the underestimation seen with shorter counts and the slowing that happens when people know they are being watched (d) (section 12.2). A 15-second count (a) and a 30-second count (b) both give systematically lower rates, and telling the patient (b) can change their breathing. Copying an old value (c) misses change, which is the point of reassessment.

6. [CORE] A patient who had surgery on the neck the previous day develops a loud, high-pitched, musical sound heard mainly when breathing in, louder over the neck than the chest. What is the nurse's priority?

a. Encourage the patient to cough and use the incentive spirometer.

b. Document the finding as a wheeze and reassess in an hour.

c. Stay with the patient, keep them upright and call for immediate help.

d. Give the as-needed inhaled bronchodilator that is ordered and recheck in 20 minutes.

Answer: c — The sound is stridor, which means the upper airway is narrowed and can close; it is an emergency (c) (section 12.2). Coughing and deep breathing (a) do not treat upper airway narrowing. Calling it a wheeze and waiting (b) delays urgent care. A bronchodilator (d) acts on the lower airways and would delay calling for help.

7. [CORE] A nurse auscultates a patient's chest. Which finding is normal?

a. Soft, low-pitched rustling sounds over most of the lung fields, with breathing in longer than breathing out

b. Loud, high-pitched sounds over the outer lung fields, with breathing out longer than breathing in

c. Continuous musical sounds heard on breathing out over both lungs

d. Grating, creaking sounds heard on breathing in and out over the lower right chest

Answer: a — Vesicular sounds are soft and low-pitched over most of the lungs, with inspiration longer than expiration (a) (section 12.2). Bronchial sounds are normal over the upper sternum, but heard over the outer lung (b) they may signal consolidation. Continuous musical sounds (c) are wheezes from narrowed airways. Grating sounds in both phases (d) suggest a pleural friction rub.

8. [CORE] Which findings suggest central cyanosis rather than peripheral cyanosis?

a. Bluish fingertips on cold hands, with a pink tongue

b. Bluish or greyish colour of the tongue and the inside of the lips

c. Bluish toes in a patient with known poor circulation in the legs

d. Pale nail beds that turn pink when the hands are warmed

Answer: b — Central cyanosis appears in the tongue, lips and oral lining and signals low arterial oxygen (b) (section 12.2). Blue fingertips with a pink tongue (a) and blue toes with poor circulation (c) are peripheral cyanosis from slow blood flow. Nail beds that pink up with warming (d) reflect peripheral circulation and cold, not central oxygenation.

9. [CORE] A nurse is assessing for pallor in patients with a range of skin tones. Which statement reflects the evidence?

a. The palms are the most reliable site for detecting anemia in people with darker skin.

b. Pallor is easy to see on all skin tones, so laboratory testing is rarely needed.

c. If no pallor is seen at any site, the patient's anemia can be safely ruled out.

d. The tongue is a useful site, but a hemoglobin level is still needed if anemia is suspected.

Answer: d — In a hospital study of adolescents and adults in India, the tongue was the most useful site for detecting severe anemia, but observers often disagreed and a hemoglobin level is still needed (d) (section 12.2). The palms (a) were less accurate than the tongue. Pallor is not easy to judge (b). The absence of pallor does not rule out milder anemia (c).

10. [CORE] A patient is brought to the emergency department after running a gas generator inside a closed garage. The patient has a headache and is confused. The SpO2 reads 99%. Which interpretation is correct?

a. Oxygenation is normal, so the confusion must have another cause, such as a stroke.

b. A reading this high happens with carbon monoxide only in people with darker skin.

c. The SpO2 may be falsely normal, because the oximeter reads carbon monoxide as oxygen.

d. The patient is breathing fast, and the hyperventilation has raised the SpO2 to 99%.

Answer: c — In carbon monoxide poisoning, standard two-wavelength oximeters count carbon monoxide-bound hemoglobin as oxygen-bound hemoglobin, so SpO2 can look normal while oxygen delivery is dangerously low (c) (section 12.3, Table 12.2). Assuming normal oxygenation (a) is the trap this question tests. Carbon monoxide affects readings on all skin tones (b). Hyperventilation (d) cannot raise saturation far on the flat top of the curve, and it does not explain the history.

11. [CORE] Which factors can make a pulse oximetry reading inaccurate? Select all that apply.

a. Dark nail polish on the finger under the probe

b. Cold hands with poor circulation

c. The patient's age

d. Shivering or other movement of the hand

e. Darker skin pigmentation

f. Bright procedure lights shining on the probe

Answer: a, b, d, e, f — Dark nail polish (a), poor perfusion (b), movement (d), darker skin pigmentation (e) and bright ambient light (f) can all make readings wrong or unreliable (section 12.3, Table 12.2). Age itself (c) is not a factor that affects how the device reads, although older adults may have cold hands or poor circulation.

12. [CORE] A patient on 4 L/min oxygen by nasal cannula after receiving an opioid has an SpO2 of 97%. The patient is hard to rouse, with slow, shallow breathing. Which statement explains why the nurse must not be reassured by the SpO2?

a. Pulse oximetry does not measure CO2, so CO2 can rise while SpO2 stays normal.

b. Pulse oximeters become inaccurate whenever a patient is receiving extra oxygen.

c. An SpO2 of 97% shows hyperoxia, which is what is causing the patient's drowsiness.

d. Nasal cannulas interfere with the light signal sent and received by a finger probe.

Answer: a — Pulse oximetry gives no information about CO2 or ventilation; extra oxygen can keep SpO2 normal while CO2 builds up from hypoventilation (a) (section 12.3; Chapter 5, section 5.4). Oximeters remain accurate on oxygen (b); the problem is what they don't measure. An SpO2 of 97% is not evidence of harmful hyperoxia (c), and the drowsiness fits opioid-related hypoventilation. Nasal cannulas do not affect finger probes (d).

13. [CORE] A student nurse asks why oxygen should not be withheld from a patient with COPD who has low oxygen levels. Which response by the nurse is accurate?

a. "People with COPD breathe only because of low oxygen, so we give oxygen only if they stop breathing."

b. "Oxygen is safe for them in any amount, so we always start with the highest flow the device allows."

c. "Withholding it is unsafe; we give oxygen to the ordered target range and watch for rising CO2."

d. "Oxygen has no effect on CO2 in people with COPD, so they need no extra monitoring once it starts."

Answer: c — Research has not supported the hypoxic drive theory, and withholding oxygen from a hypoxemic patient is unsafe. Oxygen is titrated to the ordered target, with monitoring for CO2 retention (c) (section 12.1). The idea that these patients breathe only because of low oxygen (a) is the myth itself. Too much oxygen can raise CO2 in people at risk, so maximal flow (b) is not appropriate. Oxygen can affect CO2, mainly through worsening V/Q mismatch, so monitoring is needed (d).

14. [RN] A patient with sepsis has a temperature of 39.4 °C and an arterial pH of 7.28. How will these conditions affect oxygen transport?

a. The curve shifts left, so hemoglobin releases oxygen more easily to the tissues.

b. The curve shifts right, so hemoglobin releases oxygen more easily to the tissues.

c. The curve does not shift, because only the level of 2,3-DPG can move the curve.

d. The curve shifts right, so hemoglobin picks up oxygen more easily in the lungs.

Answer: b — A higher temperature and a lower pH shift the oxygen–hemoglobin dissociation curve to the right. Hemoglobin's hold on oxygen loosens, so it releases oxygen more readily to the tissues, and saturation is lower at any given PaO2 (b) (section 12.3, Going Deeper box). A left shift (a) has the opposite effect and is not caused by fever or acidosis. Temperature, CO2 and pH all shift the curve, as does 2,3-DPG (c). A right shift makes it harder, not easier, for hemoglobin to pick up oxygen in the lungs (d).

15. [RN] An RN reviews an ABG for a patient with pneumonia: PaO2 58 mm Hg; SaO2 89%. The pulse oximeter read 94% when the sample was drawn. Which interpretation is most accurate?

a. The patient is on the steep part of the curve, and the SpO2–SaO2 gap should be reported.

b. The pulse oximeter is more accurate than the ABG, so the ABG result should be repeated.

c. A PaO2 of 58 mm Hg is within normal limits for an adult, so no further action is needed.

d. SaO2 and SpO2 cannot be compared, because the two values measure different things.

Answer: a — Below a PaO2 of about 60 mm Hg, the curve is steep, so this patient has little reserve. The SaO2 is the standard against which the SpO2 is judged, so a 5-point gap is significant and should be reported (a) (section 12.3, Going Deeper box). The co-oximetry SaO2, not the oximeter, is the reference measure, so repeating the ABG to match the oximeter is not the answer (b). A PaO2 of 58 mm Hg is below the reference ranges reported by Canadian laboratories (c). SpO2 is an estimate of SaO2, so the two are directly compared (d).

Case: Mr. Alan Kowalczyk (Questions 16–21): Mr. Alan Kowalczyk, 66, is on a surgical unit 9 days after a surgical tracheostomy for airway swelling after surgery to drain a deep neck abscess. His secretions have been thick. He has a cuffed tracheostomy tube with an inner cannula, and he breathes humidified oxygen at an FiO2 of 0.35 by tracheostomy mask, ordered to keep SpO2 at 92% to 96%. The cuff is deflated during the day per the care plan and inflated at night. At 0215, the nurse answers his call bell. He is sitting up, agitated and pointing at his neck. His respiratory rate is 32, heart rate 118 and SpO2 84%. Breath sounds are faint on both sides. The nurse cannot feel air moving at the tube, and there is no misting in the mask.

16. [CORE] Which finding is most important for the nurse to recognize as a cue that Mr. Kowalczyk's airway is in danger?

a. Heart rate of 118

b. No air felt moving at the tracheostomy tube

c. Agitation and pointing at his neck

d. FiO2 of 0.35 by tracheostomy mask

Answer: b — Absent airflow at the tube is a direct sign that the tracheostomy is not working and is the cue that defines the emergency (section 12.6). A fast heart rate is a non-specific stress response that can have many causes. Agitation matters, but it does not point to the airway by itself. The FiO2 is the treatment he was already on, not a finding of deterioration.

17. [CORE] The nurse analyzes the cues. Which explanation fits them best?

a. Secretions are blocking the tracheostomy tube.

b. He is having a panic attack after waking.

c. His oxygen tubing has come off the wall outlet.

d. He has developed pneumonia overnight.

Answer: a — No airflow at the tube, no misting, faint breath sounds and a falling SpO2 in a patient with thick secretions point to a blocked tube (section 12.6, Table 12.4). A panic attack does not stop airflow through the tube. A disconnected oxygen supply would lower SpO2 more slowly and would not stop air moving at the tube. Pneumonia develops over hours to days and would not abolish airflow.

18. [CORE] What should the nurse do first?

a. Remove the tracheostomy ties so the tube can be changed.
b. Instill normal saline into the tube to loosen secretions.
c. Call for help and give oxygen to his face and the tracheostomy.
d. Leave the room to get the spare tracheostomy tubes.

Answer: c — First responders call for help, assess the airway and apply oxygen to both the face and the tracheostomy, because a tracheostomy patient may still move air through the upper airway (section 12.6; NTSP, n.d.-a). Cutting ties risks displacing the tube before expert help arrives. Saline instillation is not recommended. The spare tubes should already be at the bedside, and leaving the patient alone in an airway emergency is unsafe.

19. [CORE] Help is on the way and oxygen is applied. Which action should the nurse take next?

a. Inflate the cuff with more air to improve the seal.
b. Place a speaking valve so he can describe his symptoms.
c. Raise the oxygen flow to the tracheostomy mask.
d. Remove the inner cannula and check for airflow.

Answer: d — Removing the inner cannula is a quick, low-risk step that often clears a blockage, because secretions collect inside it (section 12.6; Table 12.4). Adding air to the cuff does nothing for a blocked lumen and makes it harder to breathe around the tube. A speaking valve with the cuff inflated would stop him breathing out and must never be used. More oxygen cannot pass a blocked tube.

20. [CORE] The nurse removes the inner cannula, which is clear. A suction catheter will not pass beyond a few centimetres, and his SpO2 is now 80%. The rapid response team is arriving. Which action is most appropriate while the team takes over?

a. Push the suction catheter harder to break up the plug.
b. Deflate the cuff, if trained to do so, and bring the spare tubes and obturator.
c. Reinsert the inner cannula and wait for the SpO2 to improve before doing more.
d. Give the ordered oxygen by nasal cannula instead of the mask.

Answer: b — When a catheter will not pass, the tube itself is blocked or misplaced. Deflating the cuff may let air move around the tube through the upper airway, and the responding team will need the spare tubes to replace it (section 12.6; Table 12.4). Forcing the catheter can injure the trachea. Reinserting the inner cannula and waiting wastes critical time. Switching to a nasal cannula alone does not deal with the blocked tube.

21. [CORE] The team replaces the tracheostomy tube. Which finding best shows that the intervention has worked?

a. His chest rises equally, a suction catheter passes easily and SpO2 is 94%.
b. He is calmer and has stopped calling for the nurse.
c. His heart rate has dropped from 118 to 100.
d. The cuff holds its pressure after inflation.

Answer: a — Equal chest rise, easy catheter passage and an SpO2 back in the ordered range together show a patent, working airway (section 12.6). Being calmer and quieter could also mean exhaustion or falling consciousness. A lower heart rate is encouraging but is not specific to the airway. A cuff holding pressure does not show that the tube is in the trachea or open.

22. [CORE] A nurse is teaching a patient going home with oxygen and his family about fire safety. Which statements by the family show understanding? Select all that apply.

a. "He can vape inside if he turns the oxygen down first."
b. "We'll put 'No Smoking' signs inside and outside the house."
c. "He should stay well away from the gas stove and not cook while using oxygen."
d. "Petroleum jelly is the best thing for his dry lips while he wears the cannula."
e. "We'll keep the cylinders secured and standing upright."
f. "Oxygen itself is explosive, so we'll keep it in the garage."

Answer: b, c, e — Posting signs, keeping away from stoves and not cooking, and securing cylinders upright are all recommended by fire services (section 12.4). Smoking or vaping is never safe while oxygen is in use, whatever the flow. Petroleum jelly and oily products should be avoided while oxygen is in use. Oxygen itself does not burn, but it feeds a fire, and cylinders are kept secured and upright where the supplier directs.

23. [CORE] A patient with COPD is admitted with an acute exacerbation. The prescriber has not yet written an oxygen target. Which target range would the nurse expect for this patient, based on current guidelines?

a. 94% to 98%
b. 92% to 96%
c. 88% to 92%
d. 85% to 88%

Answer: c — For patients at risk of hypercapnic respiratory failure, such as those with COPD, the BTS, TSANZ and BMJ guidance all suggest 88% to 92% (section 12.4). The ranges of 94% to 98% and 92% to 96% are for most other acutely ill adults. A range of 85% to 88% is lower than recommended for COPD. The nurse still obtains a written order.

24. [CORE] A patient has a 28% Venturi mask. SpO2 has fallen from 90% to 86%, below the ordered range of 88% to 92%. Which statement about adjusting this device is accurate?

a. Turning up the flow will deliver a higher oxygen concentration.
b. A different valve is needed to change the oxygen concentration.
c. The mask must run at 15 L/min to work correctly.
d. Venturi masks deliver an oxygen concentration that varies with each breath.

Answer: b — The colour-coded valve sets the concentration in a Venturi mask, so the valve is changed, per order or directive, to increase FiO2 (section 12.4). Increasing the flow does not raise the concentration delivered. Fifteen litres per minute is the flow for a non-rebreather mask, not a 28% Venturi. A Venturi mask is a high-flow device that delivers a fixed concentration, not a variable one.

25. [CORE] A nurse watches a patient use an incentive spirometer on day 1 after surgery. Which action shows that the patient needs more teaching?

a. Holding the device upright while sitting up
b. Breathing out normally, then sealing the lips around the mouthpiece
c. Breathing in quickly and forcefully to make the indicator jump
d. Keeping the lungs inflated for at least 5 seconds at full inspiration

Answer: c — The patient should breathe in slowly and steadily toward the target, not quickly and forcefully (section 12.5). Holding the device upright, breathing out normally before sealing the lips, and keeping the lungs inflated for at least 5 seconds at full inspiration are all correct technique.

26. [CORE] A nurse is preparing to suction a patient's tracheostomy. Which action follows current suctioning guidance?

a. Instilling 5 mL of normal saline to thin secretions
b. Applying suction for up to 30 seconds per pass
c. Suctioning every 2 hours whether or not secretions are present
d. Giving extra oxygen before suctioning

Answer: d — The AARC guideline recommends preoxygenation before suctioning (section 12.6). Routine saline instillation should generally be avoided. Suction should be applied for no more than 15 seconds. Suctioning is done when assessment shows a need, not on a fixed schedule.

27. [CORE] In an Ontario public hospital, an RPN caring for a patient with a stable, long-standing tracheostomy hears coarse secretions in the tube. Which statement about the RPN's authority is accurate?

a. The RPN may suction the tracheostomy if there is an order or medical directive and the RPN is competent to do so.
b. The RPN may initiate suctioning independently because it is routine care.
c. Only an RN or an RT may suction a tracheostomy in Ontario.
d. The RPN needs a physician to delegate the act before each suctioning episode on the unit.

Answer: a — Putting an instrument into an artificial opening or beyond the larynx is a controlled act that RPNs are authorized to perform with an order or directive; competence and employer policy also apply (section 12.6, Scope in Practice box). Nurses cannot initiate controlled acts in public hospitals. RPNs are not excluded by law. Delegation is not needed because the act is already authorized to nurses; an order or directive is the authorizing mechanism.

28. [CORE] A patient has an oxygen order for nasal cannula at 1 to 4 L/min to keep SpO2 at 92% to 96%. The patient is on 4 L/min, is comfortable, and has an SpO2 of 99%. What should the nurse do?

a. Leave the flow at 4 L/min because a higher saturation is safer.
b. Lower the flow within the order and recheck SpO2 after about 5 minutes.
c. Stop the oxygen completely and recheck the next day.
d. Change to a simple face mask at 4 L/min for more comfort.

Answer: b — SpO2 is above the ordered range, so the nurse turns the flow down within the order and reassesses after about 5 minutes on the new setting (section 12.4). Liberal oxygen is linked to higher mortality and hides deterioration. Stopping oxygen abruptly without stepwise weaning and monitoring is unsafe. A simple face mask must not run below 5 L/min because of carbon dioxide rebreathing.

29. [CORE] A patient after abdominal surgery has crackles at the bases and a weak cough because of incisional pain. Which nursing action best supports airway clearance?

a. Asking for chest physiotherapy every 4 hours
b. Keeping the patient on bed rest until the crackles clear
c. Teaching huff coughing with a pillow over the incision, after pain is controlled
d. Suctioning the patient's nose and throat every 2 hours to keep the airway clear

Answer: c — Effective pain control and huff coughing with splinting help the patient clear secretions with less pain (section 12.5). Chest physiotherapy is not routine postoperative care. Early mobility, not bed rest, is recommended after surgery. Suctioning is used only when the patient cannot clear secretions despite their best cough, not on a schedule.

30. [CORE] Nasotracheal suctioning is being considered for a patient who cannot clear secretions. Which finding would make the nurse question the order?

a. Gurgling sounds on breathing
b. A facial fracture from a fall the day before
c. An SpO2 of 91% on room air
d. A weak cough after a stroke

Answer: b — Acute head, facial or neck injury is a contraindication to nasotracheal suctioning (section 12.5). Gurgling breath sounds and a weak cough are indications for suctioning, not reasons to avoid it. A modest SpO2 drop is a reason to give oxygen and monitor closely, not a contraindication.

31. [CORE] A patient who had a total laryngectomy 2 weeks ago becomes distressed, and the SpO2 is falling. How should the nurse give oxygen?

a. By non-rebreather mask over the mouth and nose
b. By nasal cannula at 4 L/min
c. By bag-valve mask over the mouth and nose
d. Directly to the neck stoma

Answer: d — After a laryngectomy, the patient is a neck breather, with no connection between the upper airway and the lungs, so oxygen and any ventilation must be given at the stoma (section 12.6). Masks, cannulas and bag-valve ventilation over the mouth and nose cannot reach the lungs.

32. [CORE] Which statement best explains why a target SpO2 range, rather than "as much oxygen as possible", is ordered for acutely ill adults?

a. Too little oxygen and too much oxygen can both harm patients.
b. Higher SpO2 values are always more accurate on a pulse oximeter.
c. Oxygen is expensive, so hospitals limit its use.
d. A target range is needed only for patients with COPD.

Answer: a — Hypoxemia harms tissues, and liberal oxygen in acutely ill adults has been linked to higher mortality and can hide deterioration (section 12.4). Oximeter accuracy does not improve at higher values. Cost is not the reason for target ranges. Target ranges are recommended for all patients, with a lower range for those at risk of hypercapnia.

33. [RN] A patient with pneumonia is on a high-flow nasal cannula at 50 L/min. Over 2 hours, the FiO2 needed to keep SpO2 in range has risen from 0.40 to 0.60. What is the priority?

a. Document the change and continue to titrate within the order.

b. Switch to a simple face mask to give the patient a break.

c. Turn off the heated humidifier to reduce the work of breathing.

d. Escalate for urgent medical and critical care review.

Answer: d — A rising oxygen requirement, especially an FiO2 of 0.50 or more, calls for urgent senior and intensive care review (section 12.4; Barnett et al., 2022). Titrating without escalating misses deterioration. A simple face mask delivers an FiO2 of about 0.60 at most and would reduce support. Turning off the humidifier removes a key feature of HFNC and does not reduce work of breathing.

34. [RN] A patient with a cuffed tracheostomy is ready to try a speaking valve after assessment by the SLP and RT. What must the nurse confirm before placing the valve?

a. The cuff is fully deflated.

b. The cuff is inflated to its usual pressure.

c. The inner cannula has been removed and discarded.

d. Oxygen has been turned off.

Answer: a — A speaking valve lets air in but not out through the tube, so exhaled air must pass around the tube and up through the larynx. The cuff must be completely deflated first; with the cuff inflated, the patient cannot breathe out (section 12.6; Hess & Altobelli, 2014; Mitchell et al., 2013). The inner cannula is managed according to the tube type and product instructions. Oxygen can be given with a speaking valve if the patient needs it.

35. [RN] A patient with COPD has an order for oxygen titrated to SpO2 88% to 92% under a unit directive. On 3 L/min by nasal cannula, SpO2 is 97%, and the patient is newly drowsy and hard to rouse. What should the nurse do?

a. Stop the oxygen immediately and recheck SpO2 and level of consciousness in 1 hour.

b. Increase the oxygen to raise SpO2 to 98%.

c. Reduce the oxygen to reach the target range, call for urgent medical review and anticipate a blood gas.

d. Encourage sleep and reassess at the next routine vital signs.

Answer: c — A high SpO2 and new drowsiness in a patient at risk of hypercapnia suggest oxygen-related carbon dioxide retention. The nurse titrates down to the target range, escalates and anticipates a blood gas (section 12.4). Stopping oxygen abruptly can cause life-threatening rebound hypoxemia. More oxygen would worsen the problem. Waiting until routine vital signs delays care for a deteriorating patient.

References

Abdo, W. F., & Heunks, L. M. A. (2012). Oxygen-induced hypercapnia in COPD: Myths and facts. *Critical Care, 16*(5), Article 323. https://doi.org/10.1186/cc11475

Alberta Precision Laboratories. (2021, July 12). *Changes to blood gas reference intervals and critical values* [Lab bulletin]. https://www.albertahealthservices.ca/assets/wf/lab/if-lab-hp-lab-bulletin-changes-to-blood-gas-reference-intervals-and-critical-values.pdf

American Association for Respiratory Care. (2004). AARC clinical practice guideline: Nasotracheal suctioning—2004 revision & update. *Respiratory Care, 49*(9), 1080–1084. https://www.aarc.org/wp-content/uploads/2014/08/09.04.1080.pdf

Barnett, A., Beasley, R., Buchan, C., Chien, J., Farah, C. S., King, G., McDonald, C. F., Miller, B., Munsif, M., Psirides, A., Reid, L., Roberts, M., Smallwood, N., & Smith, S. (2022). Thoracic Society of Australia and New Zealand position statement on acute oxygen use in adults: "Swimming between the flags". *Respirology, 27*(4), 262–276. https://doi.org/10.1111/resp.14218

Blakeman, T. C., Scott, J. B., Yoder, M. A., Capellari, E., & Strickland, S. L. (2022). AARC clinical practice guidelines: Artificial airway suctioning. *Respiratory Care, 67*(2), 258–271. https://doi.org/10.4187/respcare.09548

Canadian Lung Association. (n.d.). *Shortness of breath scale* [BREATHE Better, Stay STRONG, Module 8: Advance planning and self-management]. https://www.lung.ca/sites/default/files/2023-02/VPR-Module-8-Shortness-of-Breathe-Scale.pdf

Chu, D. K., Kim, L. H.-Y., Young, P. J., Zamiri, N., Almenawer, S. A., Jaeschke, R., Szczeklik, W., Schünemann, H. J., Neary, J. D., & Alhazzani, W. (2018). Mortality and morbidity in acutely ill adults treated with liberal versus conservative oxygen therapy (IOTA): A systematic review and meta-analysis. *The Lancet, 391*(10131), 1693–1705. https://doi.org/10.1016/S0140-6736(18)30479-3

City of Calgary. (n.d.). *Portable oxygen safety*. Retrieved October 25, 2026, from https://www.calgary.ca/safety/portable-oxygen.html

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Respiratory Therapists of Ontario. (2022). *Oxygen therapy clinical best practice guideline*. https://oxygen.crto.on.ca/oxygen-therapy/

College of Respiratory Therapists of Ontario. (2024). *Orders for medical care* [Professional practice guideline]. https://orders.crto.on.ca/wp-content/uploads/sites/13/2024/10/Orders-for-Medical-Care-PPG-2024-09-13.pdf

Collins, J.-A., Rudenski, A., Gibson, J., Howard, L., & O'Driscoll, R. (2015). Relating oxygen partial pressure, saturation and content: The haemoglobin–oxygen dissociation curve. *Breathe, 11*(3), 194–201. https://doi.org/10.1183/20734735.001415

Department of Health and Social Care. (2024, March 11). *Equity in medical devices: Independent review – Final report*. https://www.gov.uk/government/publications/equity-in-medical-devices-independent-review-final-report

Fair, F. J., Furness, A., Higginbottom, G., Oddie, S. J., & Soltani, H. (2025). Systematic review of Apgar scores & cyanosis in Black, Asian, and ethnic minority infants. *Pediatric Research, 97*(3), 939–952. https://doi.org/10.1038/s41390-024-03543-3

Government of Ontario. (2025, July 10). *Home oxygen therapy*. https://www.ontario.ca/page/home-oxygen-therapy

Guyenet, P. G., & Bayliss, D. A. (2015). Neural control of breathing and CO2 homeostasis. *Neuron, 87*(5), 946–961. https://doi.org/10.1016/j.neuron.2015.08.001

Health Canada. (2019). *Radon: Is it in your home? Information for health professionals*. https://www.canada.ca/en/health-canada/services/environmental-workplace-health/reports-publications/radiation/radon-is-it-in-you-home-information-health-professionals.html

Health Canada. (2020). *Module 1: Overview of Vanessa's Law and mandatory hospital reporting requirements*. https://www.canada.ca/en/health-canada/services/drugs-health-products/medeffect-canada/adverse-reaction-reporting/mandatory-hospital-reporting/education/module-1.html

Health Canada. (2022). *Pulse oximeters: For health care providers*. https://www.canada.ca/en/health-canada/services/drugs-medical-devices/pulse-oximeters/health-care-providers.html

Hess, D. R., & Altobelli, N. P. (2014). Tracheostomy tubes. *Respiratory Care, 59*(6), 956–973. https://doi.org/10.4187/respcare.02920

Hill, A., Kelly, E., Horswill, M. S., & Watson, M. O. (2018). The effects of awareness and count duration on adult respiratory rate measurements: An experimental study. *Journal of Clinical Nursing, 27*(3–4), 546–554. https://doi.org/10.1111/jocn.13861

Kalantri, A., Karambelkar, M., Joshi, R., Kalantri, S., & Jajoo, U. (2010). Accuracy and reliability of pallor for detecting anaemia: A hospital-based diagnostic accuracy study. *PLOS ONE, 5*(1), Article e8545. https://doi.org/10.1371/journal.pone.0008545

Lacasse, Y., Légaré, M., & Maltais, F. (2015). E-cigarette use in patients receiving home oxygen therapy. *Canadian Respiratory Journal, 22*(2), 83–85. https://doi.org/10.1155/2015/215932

Lorenzi-Filho, G., Genta, P. R., Figueiredo, A. C., & Inoue, D. (2005). Cheyne-Stokes respiration in patients with congestive heart failure: Causes and consequences. *Clinics, 60*(4), 333–344. https://doi.org/10.1590/S1807-59322005000400012

Martin, D. S., Doidge, J. C., Gould, D., Shahid, T., Cowden, A., Charles, W. N., Francis Johnson, A., Garrett, R., Mbema, C., Olusanya, O., Healy, E., Rowan, K., Mouncey, P., & Harrison, D. A. (2026). The impact of skin tone on performance of pulse oximeters used by NHS England COVID Oximetry @home scheme: Measurement and diagnostic accuracy study. *BMJ, 392*, Article e085535. https://doi.org/10.1136/bmj-2025-085535

Matsuura, N. (2019). Schamroth sign. *CMAJ, 191*(45), E1251. https://doi.org/10.1503/cmaj.190515

McGrath, B. A., Bates, L., Atkinson, D., & Moore, J. A. (2012). Multidisciplinary guidelines for the management of tracheostomy and laryngectomy airway emergencies. *Anaesthesia, 67*(9), 1025–1041. https://doi.org/10.1111/j.1365-2044.2012.07217.x

Medical Council of Canada. (n.d.). *List of normal lab values*. Retrieved October 25, 2026, from https://mcc.ca/examinations-assessments/resources-to-help-with-exam-prep/normal-lab-values/

Melbye, H., Garcia-Marcos, L., Brand, P., Everard, M., Priftis, K., & Pasterkamp, H. (2016). Wheezes, crackles and rhonchi: Simplifying description of lung sounds increases the agreement on their classification: A study of 12 physicians' classification of lung sounds from video recordings. *BMJ Open Respiratory Research, 3*(1), Article e000136. https://doi.org/10.1136/bmjresp-2016-000136

Mitchell, R. B., Hussey, H. M., Setzen, G., Jacobs, I. N., Nussenbaum, B., Dawson, C., Brown, C. A., III, Brandt, C., Deakins, K., Hartnick, C., & Merati, A. (2013). Clinical consensus statement: Tracheostomy care. *Otolaryngology–Head and Neck Surgery, 148*(1), 6–20. https://doi.org/10.1177/0194599812460376

Miyake, M. H., Diccini, S., & Bettencourt, A. R. C. (2003). Interferência da coloração de esmaltes de unha e do tempo na oximetria de pulso em voluntários sadios [Interference of nail polish colours and time on pulse oximetry in healthy volunteers]. *Jornal de Pneumologia, 29*(6), 386–390. https://doi.org/10.1590/S0102-35862003000600011

National Tracheostomy Safety Project. (n.d.-a). *Emergency care (adults)* [Web pages: First responder; Emergency algorithm – tracheostomy]. Retrieved October 25, 2026, from https://www.tracheostomy.org.uk/healthcare-staff/emergency-care

National Tracheostomy Safety Project. (n.d.-b). *Emergency laryngectomy management* [Algorithm]. Retrieved October 25, 2026, from https://rightdecisions.scot.nhs.uk/media/f0oj0iv3/ntsp_red_laryngectomy_algorithm.pdf

O'Driscoll, B. R., Howard, L. S., Earis, J., & Mak, V. (2017a). British Thoracic Society guideline for oxygen use in adults in healthcare and emergency settings. *BMJ Open Respiratory Research, 4*(1), Article e000170. https://doi.org/10.1136/bmjresp-2016-000170

O'Driscoll, B. R., Howard, L. S., Earis, J., & Mak, V. (2017b). BTS guideline for oxygen use in adults in healthcare and emergency settings. *Thorax, 72*(Suppl. 1), ii1–ii90. https://doi.org/10.1136/thoraxjnl-2016-209729

Office of the Fire Marshal and Emergency Management. (n.d.). *Medical oxygen fire safety* [Information sheet]. Retrieved October 25, 2026, from https://www7.mississauga.ca/documents/fire/2018/Medical_Oxygen_Info_Sheet.pdf

Pasterkamp, H., Brand, P. L. P., Everard, M., Garcia-Marcos, L., Melbye, H., & Priftis, K. N. (2016). Towards the standardisation of lung sound nomenclature. *European Respiratory Journal, 47*(3), 724–732. https://doi.org/10.1183/13993003.01132-2015

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Restrepo, R. D., Wettstein, R., Wittnebel, L., & Tracy, M. (2011). AARC clinical practice guideline: Incentive spirometry: 2011. *Respiratory Care, 56*(10), 1600–1604. https://doi.org/10.4187/respcare.01471

Sarkar, M., Madabhavi, I., Niranjan, N., & Dogra, M. (2015). Auscultation of the respiratory system. *Annals of Thoracic Medicine, 10*(3), 158–168. https://doi.org/10.4103/1817-1737.160831

Sarkar, M., Niranjan, N., & Banyal, P. K. (2017). Mechanisms of hypoxemia. *Lung India, 34*(1), 47–60. https://doi.org/10.4103/0970-2113.197116

Sharma, G., & Goodwin, J. (2006). Effect of aging on respiratory system physiology and immunology. *Clinical Interventions in Aging, 1*(3), 253–260. https://doi.org/10.2147/ciia.2006.1.3.253

Shi, C., Goodall, M., Dumville, J., Hill, J., Norman, G., Hamer, O., Clegg, A., Watkins, C. L., Georgiou, G., Hodkinson, A., Lightbody, C. E., Dark, P., & Cullum, N. (2022). The accuracy of pulse oximetry in measuring oxygen saturation by levels of skin pigmentation: A systematic review and meta-analysis. *BMC Medicine, 20*(1), Article 267. https://doi.org/10.1186/s12916-022-02452-8

Siemieniuk, R. A. C., Chu, D. K., Kim, L. H.-Y., Güell-Rous, M.-R., Alhazzani, W., Soccal, P. M., Karanicolas, P. J., Farhoumand, P. D., Siemieniuk, J. L. K., Satia, I., Irusen, E. M., Refaat, M. M., Mikita, J. S., Smith, M., Cohen, D. N., Vandvik, P. O., Agoritsas, T., Lytvyn, L., & Guyatt, G. H. (2018). Oxygen therapy for acutely ill medical patients: A clinical practice guideline. *BMJ, 363*, Article k4169. https://doi.org/10.1136/bmj.k4169

Sjoding, M. W., Dickson, R. P., Iwashyna, T. J., Gay, S. E., & Valley, T. S. (2020). Racial bias in pulse oximetry measurement. *New England Journal of Medicine, 383*(25), 2477–2478. https://doi.org/10.1056/NEJMc2029240

Strickland, S. L., Rubin, B. K., Drescher, G. S., Haas, C. F., O'Malley, C. A., Volsko, T. A., Branson, R. D., & Hess, D. R. (2013). AARC clinical practice guideline: Effectiveness of nonpharmacologic airway clearance therapies in hospitalized patients. *Respiratory Care, 58*(12), 2187–2193. https://doi.org/10.4187/respcare.02925

U.S. Food and Drug Administration. (2021, February 19). *FDA in brief: FDA warns about limitations and accuracy of pulse oximeters*. https://www.fda.gov/news-events/fda-brief/fda-brief-fda-warns-about-limitations-and-accuracy-pulse-oximeters

U.S. Food and Drug Administration. (2025). *Pulse oximeters for medical purposes – Non-clinical and clinical performance testing, labeling, and premarket submission recommendations: Draft guidance for industry and Food and Drug Administration staff*. https://www.fda.gov/media/184896/download

Wong, C. L., Holroyd-Leduc, J., & Straus, S. E. (2009). Does this patient have a pleural effusion? *JAMA, 301*(3), 309–317. https://doi.org/10.1001/jama.2008.937

13 Lower Respiratory Infections and Lung Cancer

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain how pneumonia, influenza, COVID-19, RSV, tuberculosis, lung cancer and pleural effusion develop, and link each to its manifestations.
2. Recognize pneumonia in adults and older adults, including atypical presentations, and escalate signs of sepsis and respiratory failure.
3. Use diagnostic findings (chest imaging, cultures, rapid tests, TB tests and laboratory values in SI units) in nursing care.
4. Apply infection prevention and control, including airborne precautions for TB and precautions for respiratory viruses.
5. Support safe antimicrobial, antiviral and TB treatment, including adherence and adverse effects.
6. Care for patients with lung cancer through diagnosis, surgery, radiation and systemic therapy.
7. Teach prevention: vaccination, smoking cessation and radon testing.
8. Describe TB in Canada with a distinctions-based, strengths-based lens, including Inuit Nunangat.
9. Distinguish RN and RPN roles in these settings using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 6	Clinician; Scholar	Foundations of Practice
4, 5, 7	Educator; Advocate; Collaborator	Foundations of Practice; Collaborative Practice
8, 9	Advocate; Professional	Ethical Practice; Legal Practice

Introduction

Lower respiratory infections fill medical units every winter, and they also develop in patients admitted for other reasons. In 2023–2024, pneumonia was the fourth most common reason for a hospital stay in Canada. It accounted for 66,128 hospitalizations, or 2.2% of all stays, with an average acute stay of 6.9 days. Only giving birth, chronic obstructive pulmonary disease (COPD) and bronchitis, and heart failure ranked higher (Canadian Institute for Health Information [CIHI], 2025). Influenza and pneumonia together are among the 10 leading causes of death in Canada (National Advisory Committee on Immunization [NACI], 2025).

This chapter is the book's home for lower respiratory infections and lung cancer. Section 13.1 covers community-acquired pneumonia, section 13.2 hospital-acquired and aspiration pneumonia, and section 13.3 influenza, COVID-19 and respiratory syncytial virus (RSV) in adults. Section 13.4 covers tuberculosis, section 13.5 lung cancer, and section 13.6 pleural effusion and empyema. Related topics live in other chapters:

- infection prevention and control (IPAC), sepsis and antimicrobial stewardship (Chapter 4);
- early warning scores and rapid response (Chapter 6);
- older adults and delirium (Chapter 8);
- cancer care in general (Chapter 9);
- respiratory assessment, oxygen therapy and airway clearance (Chapter 12);
- asthma, COPD and smoking cessation (Chapter 14);
- acute respiratory failure, mechanical ventilation and chest tubes (Chapter 15).

13.1 Community-Acquired Pneumonia

How Pneumonia Develops

Pneumonia is an acute infection of the lung tissue, the alveoli and smallest airways, that sets off inflammation there. **Community-acquired pneumonia (CAP)** starts outside hospital. The 2019 guideline from the American Thoracic Society and the Infectious Diseases Society of America (ATS/IDSA) dropped the label "health care-associated pneumonia"; local data now guide the judgment of resistance risk (Metlay et al., 2019). The most recent national Canadian CAP guideline, from the Canadian Infectious Disease Society and the Canadian Thoracic Society, dates from 2000 (Mandell et al., 2000). Canadian hospital stewardship guidance, such as Sinai Health's in Toronto, cites the ATS/IDSA guideline (Sinai Health, n.d.), and this chapter follows it.

Often no cause is found: in a large United States study of adults admitted with CAP, testing identified one in only 38% of patients. Viruses were found more often than bacteria, and the most common single causes were human rhinovirus, influenza virus and *Streptococcus pneumoniae* (Jain et al., 2015). In Canadian adults, pneumonia caused by *S. pneumoniae* (pneumococcus), with bacteria in the bloodstream, is the most common form of invasive pneumococcal disease (NACI, 2024a). Other causes include:

- influenza virus, the virus that causes COVID-19, and RSV (section 13.3);
- **atypical bacteria**, such as *Legionella*, which need special tests to detect (Metlay et al., 2019). In Ontario, the risk of *Legionella* is highest from June to November (Sinai Health, n.d.);
- less often, *Staphylococcus aureus*, including methicillin-resistant *S. aureus* (MRSA), and *Pseudomonas aeruginosa* (Metlay et al., 2019).

Organisms usually reach the alveoli by inhalation or by aspiration of small amounts of throat secretions. When they overcome the lung's defences, the inflammatory response (Chapter 4, section 4.1) fills the air spaces with fluid, white blood cells and fibrin. The lung becomes solid, a change called **consolidation**. Blood flowing past these airless alveoli picks up no oxygen, and hypoxemia follows (Chapter 12, section 12.1). Inflamed pleura cause **pleuritic chest pain**, a sharp pain that worsens with deep breaths or coughing (effusion: section 13.6).

Who Is at Risk

Risk climbs steeply with age. In the United States study, the yearly rate of CAP needing hospital care was 24.8 per 10,000 adults overall, 63.0 per 10,000 at ages 65 to 79 and 164.3 per 10,000 at 80 and older (Jain et al., 2015). Working-age adults are not spared: in Canada, pneumonia hospitalizations among adults aged 18 to 64 rose from 14,937 in 2022–2023 to 17,447 in 2023–2024, nearly 17% (CIHI, 2025).

Chronic heart, lung, liver or kidney disease, diabetes, alcohol use disorder, cancer and asplenia are comorbidities that change antibiotic choice (Metlay et al., 2019). NACI adds these groups at higher risk of invasive pneumococcal disease (NACI, 2024a):

- people with weakened immune systems, including people living with human immunodeficiency virus (HIV);
- people who smoke, especially after age 50;
- people who misuse alcohol, use cocaine or inject drugs;
- residents of long-term care and other residential care;
- people who are unhoused.

In surveillance in Toronto and Peel Region from 2014 to 2023 (excluding 2020 and 2021), the overall rate of invasive pneumococcal disease in adults aged 18 to 49 was 2.5 per 100,000, but among unhoused adults of the same ages it was 66 per 100,000 (NACI, 2024a). NACI also notes a higher risk of severe pneumococcal disease among First Nations, Inuit and Métis people, arising from intersecting factors (NACI, 2024a). These factors are structural, such as crowded housing and distance from care, not Indigenous identity (Chapter 2). Anything that raises aspiration risk also raises pneumonia risk (section 13.2).

Recognizing Pneumonia

The classic picture is new cough, sputum, fever or chills, shortness of breath and pleuritic pain, with a rising respiratory and heart rate. Over consolidated lung, the nurse may hear crackles or bronchial breath sounds (Chapter 12, section 12.2). Oxygen saturation

measured by pulse oximetry (SpO2) often falls. A careful full-minute count of the respiratory rate matters, because a rising rate is an early warning sign (Chapter 6).

Older adults often lack these signs; new confusion, a fall or loss of function may be the first clue (Chapter 4, section 4.2; Lifespan Considerations box). On darker skin, pallor and cyanosis are harder to see, so the nurse checks the lips, oral mucosa, conjunctivae and nail beds, and remembers that pulse oximetry can overestimate saturation on darker skin (Chapter 12, sections 12.2 and 12.3).

Pneumonia can lead to sepsis. A rising respiratory rate, new confusion, falling blood pressure, a racing pulse, mottled skin or falling urine output calls for sepsis screening and escalation (Chapter 4, section 4.6; Chapter 6).

Diagnostics

The diagnosis rests on clinical findings plus a new infiltrate on chest imaging (Metlay et al., 2019; Figure 13.1). The ATS/IDSA guideline does not recommend routine cultures for patients treated at home. In hospital, it advises pretreatment sputum and blood cultures for patients with the following (a strong recommendation for the first two groups, a conditional one for the last two):

- severe CAP;
- planned empirical treatment for MRSA or *P. aeruginosa*;
- previous infection with either organism;
- a hospital stay with intravenous (IV) antibiotics in the past 90 days (Metlay et al., 2019).

The nurse collects ordered cultures before the first antibiotic dose whenever this causes no delay (Chapter 4, section 4.5).

- **Urine antigen tests:** pneumococcal and *Legionella* tests are suggested for severe CAP, and the *Legionella* test also for an outbreak or recent travel (Metlay et al., 2019).
- **Viral testing:** when influenza is circulating, the guideline recommends a rapid molecular influenza test (Metlay et al., 2019).
- **Blood work:** the white blood cell (WBC) count, in $\times 10^9$/L, and C-reactive protein (CRP) are trended (Chapter 4, section 4.2); reference ranges vary by laboratory. A procalcitonin result does not decide whether to start antibiotics in confirmed CAP (Metlay et al., 2019).
- **Sepsis work-up:** lactate, creatinine and urea are added when sepsis is suspected (Chapter 4, section 4.6).
- **Oxygenation:** SpO2 is trended; an arterial blood gas is drawn for severe hypoxemia or suspected carbon dioxide retention (Chapter 12, section 12.3).



Figure 13.1 Chest X-ray of lobar pneumonia. Consolidation fills the right middle lobe, the white area beside the right heart border (on the viewer's left).

Nursing Care

Nursing care follows the clinical judgment model (Chapter 1, section 1.4).

- **Recognize and analyze cues.** The nurse trends vital signs, SpO2, oxygen need, mental status, intake and urine output, and calculates the early warning score (Chapter 6). A rising oxygen need is a cue even when the SpO2 looks acceptable.
- **Prioritize hypotheses.** Worsening hypoxemia and sepsis come first; dehydration, delirium and falls follow.
- **Give oxygen to a target.** The nurse titrates oxygen to the prescribed SpO2 range and asks for a range when none is ordered (Chapter 12, section 12.4).
- **Give the first antibiotic dose promptly.** No guideline sets one deadline for every patient with CAP, but for septic shock or probable or definite sepsis, antimicrobials are given immediately, ideally within 1 hour of recognition (Prescott et al., 2026;

Chapter 4, section 4.6).

- **Support fluids and nutrition.** Fever and fast breathing increase fluid losses. The nurse gives IV fluids as ordered, watches for overload in heart or kidney disease (Chapter 3) and offers small, frequent meals.
- **Clear the airway and mobilize.** Sitting upright, deep breathing, coughing and early mobility help clear secretions (Chapter 12, section 12.5). Analgesia for pleuritic pain makes deep breathing possible (Chapter 5).
- **Promote comfort.** Antipyretics as ordered, mouth care and rest periods help.
- **Prevent spread.** Droplet and contact precautions are added while a respiratory virus is suspected (section 13.3; Chapter 4, section 4.3).
- **Evaluate outcomes.** Clinical stability supports the switch to oral therapy and discharge. An IDSA clinical pathway defines it as at least five of the following, or a return to baseline (Infectious Diseases Society of America [IDSA], n.d.):
- temperature 38 °C or lower;
- heart rate 100 beats/min or lower;
- respiratory rate 24 breaths/min or lower;
- SpO2 of 90% or higher;
- baseline mental status;
- systolic blood pressure of 90 mm Hg or higher.

The patient must also tolerate oral medications. The nurse who sees these signs prompts a review (Chapter 4, section 4.5).

Before discharge, the nurse teaches the patient to take the antibiotic as prescribed and to return for worsening breathlessness, new confusion or returning fever, and checks follow-up and vaccine status. A routine follow-up chest X-ray is not recommended; lung cancer screening is offered when clinically indicated (Metlay et al., 2019; Chapter 9).

Antimicrobials

Antibiotic choice depends on the care setting, severity, comorbidities and local resistance. The ATS/IDSA guideline recommends these approaches (Metlay et al., 2019):

- **Outpatients without comorbidities:** amoxicillin, or doxycycline. A macrolide such as azithromycin is used alone only where pneumococcal resistance to macrolides is low.
- **Outpatients with comorbidities:** amoxicillin–clavulanate or a cephalosporin, combined with a macrolide or doxycycline. Another option is a **respiratory fluoroquinolone** (levofloxacin or moxifloxacin) alone.
- **Inpatients with non-severe CAP:** a beta-lactam such as ceftriaxone plus a macrolide, or a respiratory fluoroquinolone alone.
- **Severe CAP:** a beta-lactam plus either a macrolide or a respiratory fluoroquinolone.
- **MRSA or *P. aeruginosa* coverage:** added only when locally validated risk factors are present.

Hospitals adapt these options: one Toronto stewardship program uses amoxicillin or ampicillin for lower-risk patients, and amoxicillin–clavulanate or ceftriaxone, with azithromycin considered, for higher-risk patients (Sinai Health, n.d.).

Before the first dose, the nurse asks what happened with any reported drug allergy and records the reaction exactly; most penicillin allergy labels do not hold up when assessed (Ontario Medical Association [OMA], 2025; Chapter 4, section 4.5). Stewardship continues:

- therapy is narrowed when cultures exclude resistant organisms (Metlay et al., 2019);
- courses are short: the Toronto program stops after 3 days if the patient is afebrile and stable by day 3, and extends to 5 or 7 days for slower responses (Sinai Health, n.d.);
- the nurse asks for the planned stop date (Chapter 4, section 4.5).

Prevention

- **Vaccination:** pneumococcal, influenza, COVID-19 and RSV vaccines protect adults' lungs (section 13.3, Patient Education box).
- **Smoking cessation:** smoking raises pneumococcal risk (NACI, 2024a; Chapter 14).

- **Oral health:** poor oral hygiene and gum disease are linked to aspiration pneumonia (Son et al., 2017).
- **Everyday measures:** hand hygiene, covering coughs and staying home when sick limit the spread of respiratory viruses (Public Health Agency of Canada [PHAC], 2026a).

LIFESPAN CONSIDERATIONS

Pneumonia in Older Adults

- **Older adults:** pneumonia needing hospital care is far more common after 65, and more common again after 80 (Jain et al., 2015). It often shows up as confusion, a fall, poor appetite or a sudden loss of function rather than fever and cough. The nurse treats any new change in thinking or function as a possible sign of infection and checks for delirium (Chapter 8, section 8.2). Dysphagia, frailty and sedating drugs raise the risk of aspiration. Bed rest quickly costs strength, so mobilizing early with help protects function and lowers the risk of hospital-associated disability (Chapter 8, section 8.1). Older adults lose fluid easily with fever, yet many also have heart or kidney disease, so fluid balance needs careful watching. A medication review matters too: some antimicrobials and antivirals interact with common drugs (section 13.3).
- **Younger adults:** risk rises with smoking, alcohol or drug use, unstable housing and chronic disease (NACI, 2024a). Pregnant people with influenza or COVID-19 are a higher-risk group for severe illness (NACI, 2025, 2026a).

CLINICAL JUDGMENT

From Pneumonia to Sepsis

Names and details are fictional; this is a composite story.

Mr. Harold Pelletier, 74, was admitted to a medical unit today with community-acquired pneumonia and received his first IV antibiotic dose at 1600. At 2000: temperature 38.2 °C, heart rate 96 beats/min, respiratory rate 20 breaths/min, blood pressure 128/74 mm Hg, SpO2 94% on 2 L/min oxygen; alert and chatting with his daughter.

- **Recognize cues:** at 0100 his respiratory rate is 30 breaths/min, heart rate 118 beats/min, blood pressure 92/54 mm Hg, temperature 39.1 °C and SpO2 89% on 2 L/min. He is trying to climb out of bed and does not know where he is. His urinal holds 40 mL since 2000.
- **Analyze cues:** fast breathing, low blood pressure and new confusion together suggest organ dysfunction.
- **Prioritize hypotheses:** the most urgent explanation is sepsis from pneumonia, with worsening hypoxemia. Delirium is a sign of it.
- **Generate solutions:** support oxygenation, escalate at once, prepare for a sepsis assessment and keep him safe.
- **Take action:** the nurse stays with Mr. Pelletier, raises the head of the bed and increases oxygen within the ordered range. The nurse calculates the early warning score, which meets the hospital's trigger for the rapid response team, and calls using SBAR (Situation, Background, Assessment, Recommendation; Chapter 6, section 6.2). The nurse asks whether a lactate and repeat cultures are needed, reports when the next antibiotic dose is due, prepares for IV fluids and keeps the bed low. A registered practical nurse (RPN) would take the same immediate actions and notify the registered nurse (RN) and the team under the same employer policy.
- **Evaluate outcomes:** the nurse rechecks vital signs, SpO2, mental status and urine output as often as the team orders, and reports any further fall in blood pressure (Chapter 4, section 4.6).

GOING DEEPER

Pneumonia Severity Scores

Required for RN students; optional for PN students.

Severity scores help the team decide where a patient with CAP should be treated: at home, on a ward or in critical care. Two are widely used.

CURB-65 was built from three hospital cohorts in the United Kingdom, New Zealand and the Netherlands (Lim et al., 2003). Its name lists its five criteria, each worth one point:

- **C**onfusion;
- **U**rea above 7 mmol/L;
- **R**espiratory rate of 30 breaths/min or more;
- **B**lood pressure low: systolic under 90 mm Hg, or diastolic of 60 mm Hg or lower;
- age **65** years or older.

In the original study, death within 30 days was uncommon at scores of 0 to 2 (from under 1% to about 3%). It rose to 17% at a score of 3 and to over 40% at scores of 4 and 5. The authors proposed using the score to sort patients into management groups (Lim et al., 2003).

The **Pneumonia Severity Index (PSI)** was derived from more than 14,000 inpatients. It sorts patients into five risk classes using age, coexisting diseases, and vital signs and laboratory results that are abnormal when the patient first presents (Fine et al., 1997). Very few patients in the three lowest classes died, which helped identify people who could safely be treated at home. PSI needs more data than CURB-65, so it is usually calculated with an electronic tool.

The ATS/IDSA guideline recommends using a validated rule together with clinical judgment. It prefers PSI over CURB-65 (Metlay et al., 2019). Neither score sees everything. A patient with a low score may still need admission for hypoxemia, inability to take oral drugs, delirium or no safe place to recover. CURB-65 does not include oxygenation at all. Scores support the team's decision; they never replace assessment and reassessment.

13.2 Hospital-Acquired and Aspiration Pneumonia

Hospital-Acquired Pneumonia

Hospital-acquired pneumonia (HAP) is pneumonia that was not incubating at admission and appears 48 hours or more after admission. **Ventilator-associated pneumonia (VAP)** is pneumonia that develops more than 48 hours after endotracheal intubation (Kalil et al., 2016). VAP belongs to critical care and is covered in Chapter 15. Pneumonia in patients who are not on a ventilator gets less attention than VAP. A systematic review notes that it occurs more often, costs more and is just as dangerous (Mitchell et al., 2019), and it roughly doubles the time to discharge (Klompas et al., 2022).

Many hospital routines raise the risk of HAP:

- bed rest and immobility;
- sedating drugs and reduced consciousness;
- dysphagia, tube feeding and poor oral hygiene (Son et al., 2017);
- surgery, especially of the chest or abdomen (Chapter 7, section 7.6).

The likely organisms differ from those in CAP. Empirical treatment often covers *S. aureus*, *P. aeruginosa* and other gram-negative bacilli, some of them resistant. In the guideline's analysis, IV antibiotics in the previous 90 days was the one risk factor for resistant organisms in HAP that stood out (Kalil et al., 2016). Each hospital produces a local antibiogram, a summary of how its own bacteria respond to antibiotics, and empirical choices follow it. Therapy is narrowed once cultures return, and about 7 days of treatment is recommended for most patients (Kalil et al., 2016). Antibiotic-resistant organisms are covered in Chapter 4, section 4.4. Table 13.1 compares CAP and HAP.

Table 13.1 Community-acquired and hospital-acquired pneumonia compared (Kalil et al., 2016; Metlay et al., 2019; Mitchell et al., 2019; NACI, 2024a; original wording)

Feature	Community-acquired	Hospital-acquired
Definition and timing	Starts outside hospital, including in long-term care	Not incubating at admission; starts 48 hours or more after admission
Setting	Treated at home, on a ward or in critical care, depending on severity	Develops on a hospital unit; pneumonia after more than 48 hours on a ventilator is VAP (Chapter 15)
Likely organisms	Respiratory viruses, S. pneumoniae and atypical bacteria; often no cause found	S. aureus (including MRSA), P. aeruginosa and other gram-negative bacilli, more often resistant
Main risk factors	Older age, smoking, chronic heart, lung, liver or kidney disease, diabetes, weakened immunity, alcohol or drug use, unstable housing	Immobility, sedation or reduced consciousness, dysphagia, tube feeding, poor oral hygiene, recent surgery; IV antibiotics in the past 90 days raise the risk of resistant organisms
First-line approach	Narrower agents chosen by severity and comorbidities; MRSA or Pseudomonas coverage only with local risk factors	Broader coverage guided by the local antibiogram, then narrowed; about 7 days for most patients

Feature	Community-acquired	Hospital-acquired
Prevention focus	Vaccination, smoking cessation, oral health, hand hygiene	Oral care, swallowing screens, early mobility, sitting upright, lighter sedation, hand hygiene and stopping viral spread on the unit

Prevention on the Unit

HAP prevention is largely nursing work, and the evidence keeps growing. A systematic review of 15 studies found that most programs focused on oral care, and that most oral care studies reported less HAP. Programs that screened swallowing after stroke, or that got patients moving early, also reported fewer cases. The studies varied widely in quality, however, and the authors called for well-designed, nurse-led trials (Mitchell et al., 2019). Nurses can act on this evidence now:

- **Oral care:** brush the teeth, gums and tongue, and clean dentures, on the regular schedule set by unit policy, with help for patients who cannot do it themselves. In ventilated patients, toothbrushing without chlorhexidine is recommended, and routine chlorhexidine oral care is not (Klompas et al., 2022).
- **Swallowing screens:** screen patients at risk, such as those with a stroke, before giving the first food, fluid or oral medication. Refer to speech-language pathology as policy directs (Mitchell et al., 2019; Chapter 31).
- **Early mobility:** sit patients up and walk them as soon as it is safe (Mitchell et al., 2019).
- **Position upright:** sit patients up for meals and keep the head of the bed raised during tube feeding to reduce reflux and aspiration (Son et al., 2017).
- **Minimize sedation:** use the lightest effective sedation and watch closely after sedating drugs (Son et al., 2017).
- **Deep breathing:** encourage deep breathing and coughing. Incentive spirometry is used together with these measures and early mobility, not alone (Chapter 12, section 12.5).
- **Hand hygiene and viral prevention:** clean hands before and after patient contact, and use droplet and contact precautions for respiratory viruses (section 13.3).

Aspiration Pneumonia and Pneumonitis

Aspiration is the passage of material from the mouth, throat or stomach into the airways. It can cause two different problems (Son et al., 2017).

- **Aspiration pneumonitis** is a chemical injury caused by inhaling a large volume of stomach contents, which are usually sterile. It typically follows vomiting in a person with reduced consciousness, for example after sedation, poisoning or trauma. The event may be witnessed, and hypoxemia comes on within hours. The injury may settle within about 48 hours. Care is supportive, and antibiotics are not routinely required unless infection follows.
- **Aspiration pneumonia** is an infection that develops after a person breathes in mouth and throat secretions carrying bacteria. It usually occurs in a person with dysphagia, often an older adult, and the aspiration is usually not witnessed.

Risk factors include dysphagia after stroke (Chapter 31) or with dementia or Parkinson disease, reduced consciousness, tube feeding, reflux and poor oral health (Son et al., 2017). On imaging, aspiration tends to affect the parts of the lung that are lowest at the time it happens. In a patient lying flat, that means the back of the lungs (Son et al., 2017).

The nurse watches for coughing or choking with meals or medications, a change in voice after swallowing, food left in the mouth, and new fever, crackles or hypoxemia. When aspiration is witnessed, the nurse:

- stops any feeding;
- positions the patient upright or on the side;
- suctions the mouth and throat as needed (Chapter 12, section 12.5);
- gives oxygen to target and escalates.

The ATS/IDSA guideline suggests not adding routine anaerobic antibiotic coverage for suspected aspiration pneumonia unless a lung abscess or empyema is suspected (Metlay et al., 2019; section 13.6). Prevention rests on the measures listed above, together with the diet textures the speech-language pathologist recommends.

13.3 Influenza, COVID-19 and RSV

How They Spread and How to Protect Others

Influenza, **COVID-19** and infection with **respiratory syncytial virus (RSV)** are acute viral respiratory illnesses (Figure 13.2). COVID-19 is caused by severe acute respiratory syndrome coronavirus 2 (SARS-CoV-2). All three spread through respiratory particles and through contact with secretions on hands and surfaces.

- **Influenza:** adults can spread it from about 1 day before symptoms start to about 5 days after (NACI, 2025).
- **RSV:** people are infectious for about 8 days on average, and sometimes for up to 3 weeks (PHAC, 2026a).
- **COVID-19:** people who have no symptoms yet, or who never develop them, can spread the virus (Public Health Ontario [PHO], 2023).

Ontario guidance places patients with influenza, RSV or COVID-19 on droplet and contact precautions in a single room. Staff wear a gown, gloves, a mask and eye protection (Provincial Infectious Diseases Advisory Committee [PIDAC], n.d.). Precautions start when the illness is suspected, not when the test result returns. Before each interaction, the nurse's point-of-care risk assessment guides any added protection, such as a fit-tested N95 respirator for aerosol-generating medical procedures. Respirator rules for COVID-19 have changed over time and still vary between hospitals, so the nurse follows current policy and the sign on the door. Personal protective equipment is taught in full in Chapter 4, section 4.3.

Nurses also protect patients by staying home when ill and by keeping their own vaccines up to date. NACI names health care workers among the groups for which it particularly recommends influenza and COVID-19 vaccines; for influenza, one reason is that they can pass the infection to patients at high risk (NACI, 2025, 2026a).



Figure 13.2 Influenza A (H1N1) virus particles, coloured blue, seen with a transmission electron microscope.

Recognizing Illness and Complications

Influenza classically begins suddenly with fever, cough and muscle aches. Headache, chills, loss of appetite, fatigue and sore throat are also common, and most people recover in about 7 to 10 days (NACI, 2025). RSV causes a runny nose, cough, sneezing, fever and wheezing. In severe cases, it causes pneumonia or other lower respiratory tract disease (PHAC, 2026a). COVID-19 shares many of these symptoms. Because the three look alike at the bedside, testing is needed to tell them apart.

Complications are what bring adults into hospital:

- respiratory failure;
- viral pneumonia, or a bacterial pneumonia that follows the viral illness;
- delirium;
- worsening of chronic conditions (NACI, 2025).

The risk of heart attack and stroke also rises significantly in the first 15 days after influenza (NACI, 2025). Older adults carry most of the burden. In 2023–2024, adults 65 and older accounted for 45% of the hospitalizations and 71% of the deaths associated with influenza in Canada (NACI, 2025). In pooled Canadian surveillance of adults admitted to hospital with respiratory illness, RSV hospitalization rates climbed from 43.7 per 100,000 at ages 60 to 69 to 282.5 per 100,000 at age 80 and older. About 10% of older

adults admitted with RSV needed intensive care. In a Canadian study of adults 50 and older admitted with RSV over the 2012–2015 seasons, 98.1% had at least one chronic condition (NACI, 2024b).

Other groups at higher risk include adults with chronic heart, lung, kidney or metabolic disease, people with weakened immunity, pregnant people, residents of long-term care, and First Nations, Inuit and Métis people. For Indigenous Peoples, this risk reflects intersecting structural and social determinants of health, such as crowded housing and access to care, not biology (NACI, 2025, 2026a, 2026b; Chapter 2).

Testing and Treatment

Testing uses molecular tests, such as polymerase chain reaction (PCR), or rapid tests. When influenza is circulating, the ATS/IDSA guideline recommends a rapid molecular test for patients with pneumonia (Metlay et al., 2019). For COVID-19, a PCR, rapid molecular or rapid antigen test can confirm infection (Ontario Health, 2024).

An **antiviral** is a drug that stops a virus from multiplying. Antivirals for influenza and COVID-19 work best when started early, so the nurse gives the first dose without delay once it is ordered. Table 13.2 summarizes the three viruses.

- **Influenza:** Ontario Health (2025) recommends oseltamivir as first-line treatment for severe or worsening influenza, no matter how long the patient has had symptoms or whether risk factors are present. For milder illness, treatment may be considered when risk factors are present, ideally within 48 hours after symptoms begin. Treatment does not wait for a test result when influenza is circulating. For milder illness, inhaled zanamivir is an alternative, and baloxavir is generally reserved for patients who cannot take oseltamivir or zanamivir. Oseltamivir doses are adjusted for kidney function. Its most common side effects are nausea and vomiting (Ontario Health, 2025).
- **COVID-19: nirmatrelvir–ritonavir** is used to treat adults who have mild to moderate COVID-19 and are at high risk of severe disease. It is not started in patients who already need hospital care for severe or critical COVID-19. It must begin within 5 days of symptom onset (Pfizer Canada ULC, 2026). Ontario Health (2024) recommends it for adults 65 and older and for immunocompromised adults, and suggests considering it for other higher-risk adults. Remdesivir, started within 7 days of onset, is the alternative when nirmatrelvir–ritonavir cannot be used (Ontario Health, 2024).
- **RSV:** no antiviral drug specifically treats RSV. Care is supportive, and severe cases may need admission for oxygen (PHAC, 2026a).

Ritonavir is a strong inhibitor of the liver enzyme CYP3A4, so it can raise other drugs to dangerous levels (Ontario Health, 2024). The product monograph carries a serious warning about drug interactions. It lists drugs that must not be combined with nirmatrelvir–ritonavir, including some antiarrhythmics, some statins and some anticoagulants. Strong enzyme inducers, such as some anticonvulsants, rifampin and St. John's wort, make the antiviral less effective (Pfizer Canada ULC, 2026). Before the first dose, the nurse makes sure the prescriber or pharmacist has a complete list of the patient's medications, including prescription, over-the-counter, recreational and natural health products. Ritonavir can also make combined hormonal contraceptives less effective, so the patient is taught to use another effective method or an added barrier method (Pfizer Canada ULC, 2026).

Supportive care is the same for all three viruses:

- oxygen to target;
- fluids;
- fever and symptom control;
- rest, then early mobility;
- monitoring for bacterial pneumonia and for worsening of chronic disease.

Older adults need the same watchfulness as in pneumonia. Delirium is a recognized complication of influenza (NACI, 2025), and a rising respiratory rate, a rising oxygen need or new confusion calls for the escalation steps in section 13.1. Teaching for nirmatrelvir–ritonavir covers its most common side effects, a changed sense of taste and diarrhea. If a patient is admitted to hospital after starting treatment, the full 5-day course may be completed at the health care team's discretion. Patients are taught to report a rash or other signs of an allergic reaction at once, because the drug is stopped for a significant hypersensitivity reaction (Pfizer Canada ULC, 2026).

Some people have lasting symptoms after COVID-19. The World Health Organization (WHO) defines **post-COVID-19 condition** (long COVID) as symptoms that continue more than 3 months after confirmed or probable infection with SARS-CoV-2, last at least 2 months and have no other explanation. Fatigue, shortness of breath, sleep problems, palpitations, anxiety and depression are common (Quinn et al., 2023). The nurse takes these symptoms seriously and helps the patient connect with primary care.

Table 13.2 Influenza, COVID-19 and RSV in adults at a glance (NACI, 2025, 2026a, 2026b; Ontario Health, 2024, 2025; PHAC, 2026a; PHO, 2023; PIDAC, n.d.; original wording)

Feature	Influenza	COVID-19	RSV
Usual spread	Respiratory particles and contact with secretions; adults contagious from about 1 day before to 5 days after symptoms begin	Respiratory particles and contact; people without symptoms can spread it	Respiratory particles and contaminated surfaces; infectious for about 8 days on average
Precautions in hospital (Ontario; may vary by province and policy)	Droplet and contact, single room	Droplet and contact, single room; respirator rules set by hospital policy	Droplet and contact, single room
Who is at higher risk	Adults 65 and older, chronic conditions, pregnancy, long-term care residents, First Nations, Inuit and Métis communities	Adults 65 and older, chronic conditions, weakened immunity, pregnancy, long-term care residents	Adults 75 and older, chronic heart and lung disease, weakened immunity, long-term care residents
Antiviral treatment in Canada	Oseltamivir first-line for severe illness; inhaled zanamivir or baloxavir in selected cases	Nirmatrelvir–ritonavir within 5 days for high-risk adults; remdesivir as the alternative	No specific antiviral; supportive care
Adult vaccine (NACI)	Every year for everyone 6 months and older	Yearly for adults at higher risk, with a second yearly dose for some; other adults may receive it	One dose for adults 75 and older and for some younger adults at high risk

PATIENT EDUCATION

Vaccines That Protect Adults' Lungs

- **Influenza:** NACI recommends a flu vaccine every year for everyone 6 months and older, unless a contraindication applies (NACI, 2025). In Ontario, it is publicly funded. For the 2026–2027 season, pharmacies offer it to the general public aged 2 and older from October 26, 2026, with high-dose and adjuvanted vaccines for people 65 and older (Ontario Ministry of Health, 2026a).
- **COVID-19:** starting in fall 2026, NACI strongly recommends a yearly dose for adults 65 and older and for other higher-risk groups. A second yearly dose is recommended for people 80 and older, residents of long-term care and some others (NACI, 2026b).
- **Pneumococcal:** NACI recommends one dose of Pneu-C-20 or Pneu-C-21 for all adults 65 and older and for adults under 65 at increased risk, whatever vaccines they had before (NACI, 2024a). Ontario funds Pneu-C-21 at 65 and older and Pneu-C-20 for high-risk adults aged 18 to 64 (Ontario Ministry of Health, 2026b).
- **RSV:** NACI recommends one dose for all adults 75 and older and for some higher-risk younger adults (NACI, 2026a). Ontario funds it for all adults 75 and older and for adults aged 60 to 74 in certain high-risk groups (Ontario Ministry of Health, 2026c).

Programs differ in other provinces and territories, and they change from season to season. The nurse checks current local eligibility and encourages patients to keep a record of their vaccines.

13.4 Tuberculosis

Tuberculosis is curable and preventable, yet it still causes illness and death in Canada, and its burden falls unequally for social and historical reasons. Pneumonia and viral respiratory infections were covered in sections 13.1 to 13.3.

How TB Develops

Tuberculosis (TB) is an infection caused by the bacterium *Mycobacterium tuberculosis* (Figure 13.3). It spreads through the air. When a person with TB in the lungs or larynx coughs or sneezes, they release droplet nuclei, particles about 1 to 5 microns across that stay in the air and travel on air currents and through ducts. Almost all spread happens indoors (Long et al., 2022).



Figure 13.3 Mycobacterium tuberculosis bacteria seen with a scanning electron microscope, magnified about 15,500 times.

After someone breathes in the bacteria, the immune system usually contains them. The bacteria stay alive but inactive. The Canadian Tuberculosis Standards call this state **TB infection**; older sources and some chapters of the Standards still say *latent TB infection* (LTBI) (Alvarez et al., 2022; Campbell et al., 2022). In Nunavut, it is sometimes called "sleeping TB" (Government of Nunavut, 2026). A person with TB infection has no symptoms and cannot spread TB.

TB disease (active TB) develops when the bacteria multiply and cause illness. About 90% to 95% of people with TB infection never develop disease (Long et al., 2022). The risk is highest in the first 2 to 3 years after infection (Campbell et al., 2022). The Standards rank risk factors for progression:

- **Very high:** HIV (Chapter 21), recent contact with infectious TB, and silicosis.
- **High:** stage 4 or 5 chronic kidney disease (Chapter 27); transplant; immunosuppressing drugs such as tumour necrosis factor (TNF) inhibitors or corticosteroids; some cancers; and fibronodular scarring on chest X-ray.
- **Moderate:** diabetes (Chapter 22), heavy alcohol use and heavy smoking (Campbell et al., 2022).

Young children are also at high risk (Long et al., 2022). Table 13.3 compares the two states.

Table 13.3 TB infection and TB disease compared (Canadian Tuberculosis Standards, 8th edition; original wording)

Feature	TB infection	TB disease
What the bacteria are doing	Alive but held in check by the immune system	Multiplying and damaging tissue, most often the lungs
How the person feels	Well; no symptoms	Usually unwell: cough, fever, night sweats, weight loss, fatigue
Can the person spread TB?	No	Yes, when TB is in the lungs or larynx, especially with cough, cavities or a positive smear
Skin test or blood test	Usually positive	Usually positive, but a negative result does not rule out disease
Chest X-ray	Usually normal, or old scarring only	Often abnormal; X-ray alone cannot confirm TB
Sputum smear and culture	Negative, or not needed	Culture grows M. tuberculosis; smear may be positive
Treatment	Preventive treatment with one or two drugs for months	Several drugs together for at least 6 months
Public health	Reporting rules vary by province or territory	Reportable in every Canadian jurisdiction; contacts are traced

TB in Canada

In 2023, Canada reported 2,217 cases of TB disease, a rate of 5.5 per 100,000 population, up from 4.6 per 100,000 in 2014; men aged 65 and older had the highest rate of any age and sex group, at 8.2 per 100,000 (PHAC, 2025). Surveillance data for 2024 show the same sharp gaps. People born outside Canada accounted for 82.9% of people with TB disease, and incidence was 186.9 per 100,000 among Inuit, 13.5 among First Nations, 1.3 among Métis and 0.4 among non-Indigenous people born in Canada (PHAC, 2026b). First Nations data belong to First Nations under the principles of OCAP® (First Nations Information Governance Centre, n.d.; Chapter 2).

These gaps have structural causes, not biological ones. Crowded housing raises the risk both of becoming infected and of progressing to disease (Mounchili et al., 2022). Inuit leaders and the federal government have named poverty, food insecurity and inadequate housing as drivers of TB in Inuit Nunangat (Inuit Tapiriit Kanatami [ITK], 2019), and ITK has said that limits on staffing, accommodation and space for non-local health workers stretch northern resources beyond capacity (ITK, 2025). These conditions grew out of colonial policies; Chapter 2 discusses this history and culturally safe care.

CANADIAN CONTEXT

TB and Inuit-Led Elimination

In December 2018, Inuit Tapiriit Kanatami (ITK), the national organization representing Inuit, released the Inuit Tuberculosis Elimination Framework. It builds on a joint commitment made by Inuit and the Government of Canada in March 2018: to end TB among Inuit across Inuit Nunangat by 2030 and, as an interim step, to cut the reported active TB rate by 50% or more by 2025 (Indigenous Services Canada, 2018).

- **Inuit-led priorities:** the Framework's six areas include reducing poverty and improving social conditions, mobilizing communities and developing Inuit-specific solutions. Each of the four Inuit regions wrote its own action plan, with community-wide screening, regional TB committees and education (ITK, 2019).
- **Where things stand:** in March 2025, ITK reported that TB incidence among Inuit in Inuit Nunangat had climbed from 182.9 (2016) to 268.6 (2023) per 100,000 people, and that the rate among Inuit living in Inuit Nunangat is 300 times the rate among non-Indigenous people born in Canada. ITK said the 2025 milestone would not be met, noted that pandemic priorities had pulled attention away from TB work, and asked Canada and the federal parties seeking to form government to identify the funding needed to reach the 2030 goal (ITK, 2025). These ITK figures describe Inuit in Inuit Nunangat; the PHAC rate in section 13.4 (186.9 per 100,000 in 2024) describes Inuit across Canada.
- **Signs of progress:** in March 2026, the Government of Nunavut and Nunavut Tunngavik Inc. (NTI) reaffirmed their shared aim of a Nunavut free of TB by 2030. They reported that fewer people in Nunavut have had active TB in recent years, partly because more people are being screened and treated for TB infection ("sleeping TB"). NTI has funded hamlets to lead local responses to outbreaks, and both partners named housing, food security and health care access as part of the work (Government of Nunavut, 2026).

Recognizing TB

TB disease in the lungs usually develops slowly. Common symptoms are a cough that lasts for weeks (public health guidance uses three weeks or more), sputum, coughing up blood (**hemoptysis**), fever, night sweats, loss of appetite, weight loss, fatigue and chest pain (Windsor-Essex County Health Unit, 2024). Some people have few respiratory symptoms (B. L. Johnston et al., 2022).

The Standards advise considering TB in anyone with subacute or chronic respiratory symptoms, even if a different cause seems more probable (B. L. Johnston et al., 2022). The nurse asks about birth in or travel to places where TB is common; contact with TB; past TB or TB treatment; shelters or crowded housing; the risk factors above; and the date the cough began, which public health uses to set the infectious period (Rea et al., 2022). A weeks-long cough plus one of these factors is a cue to mask the patient and start airborne precautions while TB is ruled out.

Testing

Two tests show whether a person has been infected:

- **Tuberculin skin test (TST):** purified protein derivative is injected into the skin of the inner forearm. A trained nurse measures the induration (firm swelling) 48 to 72 hours later in millimetres. Bacille Calmette-Guérin (BCG) vaccine can cause a false-positive result (Campbell et al., 2022).

- **Interferon-gamma release assay (IGRA):** a blood test that measures interferon-gamma released by T cells exposed to proteins specific to *M. tuberculosis*. BCG does not affect it. It is preferred for people who had BCG after infancy or are unlikely to return for a TST reading (Campbell et al., 2022).

A positive result on either test does not show whether the person has TB infection or TB disease (Campbell et al., 2022). A positive result is followed by a symptom review and a chest X-ray (Windsor-Essex County Health Unit, 2024).

Figure 13.4 A room pressure monitor beside a negative-pressure isolation room. The green "normal" display shows that air is flowing into the room; the nurse checks it as policy directs and reports an alarm. (credit: “Joondalup Hospital negative pressure room” by Orderinchaos/Wikimedia Commons, CC BY-SA 4.0)

Diagnosing TB disease relies on sputum. At least three specimens are collected; the Standards recommend collecting them on one day, spaced at least 1 hour apart (Behr et al., 2022). Each is tested by:

- **Smear microscopy:** a stain looks for acid-fast bacilli. It is fast but misses many cases, and other mycobacteria also stain positive.
- **Culture:** the reference standard; results take 2 to 8 weeks. Drug susceptibility testing is done on the first positive culture.
- **Nucleic acid amplification test (NAAT):** detects the genetic material of *M. tuberculosis* much faster than culture, and some NAATs can flag rifampin resistance. A negative NAAT alone does not rule out TB (Behr et al., 2022).

A chest X-ray is part of every work-up, but it cannot confirm TB on its own (Behr et al., 2022).

The nurse teaches the patient to cough deeply and bring up sputum from the lungs, not saliva. When a patient cannot, sputum may be induced with nebulized 3% hypertonic saline (Behr et al., 2022). Induction creates infectious aerosols, so it is done in an airborne infection isolation room or a sputum booth that meets the same ventilation standard (B. L. Johnston et al., 2022), following employer policy.

Airborne Precautions

Airborne precautions are taught in full in Chapter 4. For TB, the Standards call for:

- an **airborne infection isolation room (AIIR)**, a single room under negative pressure so that air flows in from the hallway and is exhausted outdoors or filtered, with at least 12 air changes per hour; airflow is checked daily while the room is in use (Figure 13.4);
- a Health Canada-approved, fit-tested **N95 respirator** (or equivalent) for every health care worker who provides care to, transports or is in direct contact with the patient;
- a medical mask on the patient whenever they leave the AIIR (B. L. Johnston et al., 2022).

For suspected TB, precautions can stop after three consecutive negative sputum smears and another diagnosis that explains the illness. Confirmed TB that is not rifampin resistant needs clinical improvement and at least 2 weeks of effective treatment, plus three consecutive negative smears if the smear was positive. Rifampin-resistant TB needs at least 4 weeks of effective treatment, clinical improvement and further criteria, including susceptibility results and negative smears (B. L. Johnston et al., 2022).

CLINICAL SAFETY

Airborne Isolation and N95 Fit

- **Mask the patient first.** A patient with a weeks-long cough and TB risk factors wears a medical mask from triage onward and is moved to an AIIR as soon as possible (B. L. Johnston et al., 2022).
- **Wear the respirator you were fitted for.** Fit testing matches a person to a specific make, model and size of N95. A different model may not seal (B. L. Johnston et al., 2022) (Figure 13.5).
- **Seal check every time.** The nurse performs a user seal check each time the respirator goes on (B. L. Johnston et al., 2022).
- **Keep the room working.** The door stays closed and the airflow indicator is checked per policy. If the room is not under negative pressure, the nurse reports it at once (Chapter 4).
- **Plan transport.** The receiving department is told in advance, the patient wears a medical mask and staff wear N95s (B. L. Johnston et al., 2022).

Treatment and Adherence

TB infection. Treating TB infection prevents disease. The Standards recommend either 4 months of daily rifampin or 12 once-weekly doses of isoniazid with rifapentine; 9 months, or if needed 6 months, of daily isoniazid is the alternative when rifamycins cannot be used (Alvarez et al., 2022). Health Canada has not approved rifapentine (Alvarez et al., 2022). Instead, it appears on Health Canada's List of Drugs for an Urgent Public Health Need for treating TB infection, together with isoniazid, in people at high risk of progression. The Public Health Agency of Canada notified Health Canada on November 28, 2025, for use in all jurisdictions; this kind of notification lets a listed drug be brought into Canada and sold in the notifying jurisdiction for 1 year (Health Canada, 2026). The weekly regimen is generally given as directly observed therapy (Alvarez et al., 2022).



Figure 13.5 Three things an N95 respirator needs to protect the wearer: it is put on and worn correctly, it seals snugly against the face, and its filter captures more than 95% of particles. (credit: "Three Key Factors Required for a Respirator to be Effective" by Centers for Disease Control and Prevention/NIOSH, public domain)

Drug-susceptible TB disease. Standard treatment has two phases. In the first 2 months, the patient takes isoniazid, rifampin, pyrazinamide and ethambutol daily; ethambutol can stop once tests show the strain is fully susceptible. For the next 4 months, the patient takes isoniazid and rifampin. Some people need a longer continuation phase (J. C. Johnston et al., 2022). Sputum is tested regularly until it turns negative.

Supporting adherence. Missed or erratic doses can lead to treatment failure and drug resistance (Brode et al., 2022). In **directly observed therapy (DOT)**, a trained person watches the patient take each dose. The Standards recommend DOT for intermittent regimens and higher-risk groups, decided with the patient, and favour DOT in the community; video-observed therapy may be an option. Care is patient-centred: professional interpreters, non-stigmatizing language and practical supports such as reminders, home visits, blister packs and transportation (J. C. Johnston et al., 2022). In Ontario, TB drugs are free to the patient (Ontario Ministry of Health, 2025). Baseline and monthly monitoring includes liver tests, blood counts, weight and, with ethambutol, vision (J. C. Johnston et al., 2022).

Drug-resistant TB. Multidrug-resistant TB (MDR-TB) is resistant to at least isoniazid and rifampin. Resistance can be acquired through inadequate treatment or missed doses, or a person can be infected with a resistant strain (Brode et al., 2022). In 2023, 1.6% of tested samples in Canada were MDR-TB (PHAC, 2025). Treatment uses several second-line drugs for many months under an experienced team, with DOT (Brode et al., 2022).

Reporting and contact tracing. TB disease is reportable in every Canadian jurisdiction (Rea et al., 2022). In Ontario, nurses, physicians, pharmacists and others have a duty to report under the *Health Protection and Promotion Act*. Within 24 hours of being notified, the board of health contacts the person with suspected or confirmed respiratory TB, directs respiratory isolation, identifies

high-priority contacts within 48 hours and provides DOT (Ontario Ministry of Health, 2025). Contacts are tested in widening circles, starting with the household (Rea et al., 2022). The nurse reassures patients that public health protects their privacy (Chapter 1).

MEDICATIONS

Drugs for TB

Drugs are always given in combination for TB disease; never as a single drug.

- **Isoniazid:** can injure the liver and cause peripheral neuropathy. Pyridoxine (vitamin B6) is added for people at risk, such as those with diabetes, kidney disease, HIV, malnutrition or substance use, and during pregnancy (J. C. Johnston et al., 2022).
- **Rifampin:** can turn urine, saliva, sweat, tears and other body fluids red or orange and can permanently stain soft contact lenses (Valeant Canada, 2019). It speeds the breakdown of many drugs, such as warfarin, methadone and phenytoin. The Standards advise monitoring these interactions early (within 1 to 2 weeks of starting rifampin) and again after it stops, because the effect wears off over about 2 weeks (J. C. Johnston et al., 2022). It can make estrogen-containing hormonal contraceptives less effective (Valeant Canada, 2019).
- **Pyrazinamide:** a common cause of liver injury (J. C. Johnston et al., 2022).
- **Ethambutol:** can damage the optic nerve. Vision and colour vision are tested at baseline and monthly (J. C. Johnston et al., 2022).
- **Rifapentine with isoniazid (weekly):** may cause a flu-like reaction (Alvarez et al., 2022).

Teach: report yellow skin or eyes, dark urine, nausea, abdominal pain, rash, numbness or tingling, or any change in vision; ask before taking any new drug; do not stop early.

13.5 Lung Cancer

Lung cancer is the leading cause of cancer death in Canada. This section covers its causes, main types, recognition and treatment, and the nursing care that helps people live as well as possible through it. Cancer biology, staging, screening and cancer treatments in general are in Chapter 9; palliative care is in Chapter 10.

Lung Cancer in Canada

An estimated 32,900 people in Canada will be diagnosed with lung cancer in 2026, and 19,300 will die of it. It is the most commonly diagnosed cancer (excluding non-melanoma skin cancer) and accounts for about 22% of all cancer deaths, more than any other cancer in men or women. Incidence has fallen in men since the early 1990s and in women since 2016, and death rates are now falling in both sexes; differences between men and women in these trends likely reflect past patterns of tobacco use (Brenner et al., 2026; Canadian Cancer Society, 2026).

Smoking is the leading cause of lung cancer (Health Canada, 2024). Other risk factors include second-hand smoke; work exposures such as asbestos, arsenic, chromium, beryllium and nickel; radiation to the chest; air pollution; a family history of lung cancer; HIV infection; and increasing age (PDQ Adult Treatment Editorial Board, 2025a).

Radon is a radioactive gas, with no colour or smell, released when uranium in soil and rock breaks down (Figure 13.6). It can build up in homes (Health Canada, 2018). Radon is the second leading cause of lung cancer in Canada after smoking and the leading cause in people who don't smoke; it accounts for an estimated 16% of lung cancer deaths. At Health Canada's guideline level, the estimated lifetime risk of lung cancer from radon is about 2% for people who don't smoke but about 17% for people who smoke (Health Canada, 2024). Health Canada recommends a long-term radon test of at least 3 months, ideally in fall or winter, and action to lower levels above the Canadian guideline of 200 becquerels per cubic metre as soon as possible (Health Canada, 2018). Nurses can include radon testing in patient teaching.

Lung cancer also occurs in people who have never smoked; the gene changes that guide targeted therapy (see the Going Deeper box) are more common in this group (PDQ Adult Treatment Editorial Board, 2025a). Every patient deserves care free of blame. Data on lung cancer among First Nations, Inuit and Métis Peoples are best drawn from Indigenous-governed sources, and First Nations data are used under OCAP® (Chapter 2).

Types and Spread

Lung cancers are grouped by how the cells look under the microscope:

- **Non-small cell lung cancer (NSCLC):** any lung cancer other than small cell. Adenocarcinoma (about 40% of lung cancers) is now the most common type and usually starts in the outer lung. Squamous cell carcinoma (about 25%) usually arises in the large central airways and is strongly linked with smoking. Large cell carcinoma makes up about 10% (PDQ Adult Treatment Editorial Board, 2025a).
- **Small cell lung cancer (SCLC):** about 15% of lung cancers. It grows quickly and has usually spread by the time it is found; only about 30% of people have limited-stage disease at diagnosis (PDQ Adult Treatment Editorial Board, 2025b).

Figure 13.6 Radon detectors from a home test kit. Because radon has no colour or smell, testing is the only way to know a home's level.

Lung cancer spreads to lymph nodes in the chest and to the brain, bones, liver and adrenal glands. Stage drives treatment; staging is explained in Chapter 9, as is lung cancer screening, including the Ontario Lung Screening Program.

Recognizing and Diagnosing

Early lung cancer often causes no symptoms. When symptoms appear, they include a new or worsening cough, hemoptysis, shortness of breath (dyspnea), chest pain, weight loss and fatigue. Pneumonia that does not resolve, a pleural effusion (section 13.6) or a collapsed lobe may be the first sign. A tumour pressing on nearby structures can cause hoarseness, difficulty swallowing, or swelling of the face and distended neck veins from compression of the superior vena cava. Spread to the brain can cause neurological changes, and spread to bone causes pain (PDQ Adult Treatment Editorial Board, 2025a). Swelling of the face and neck is an oncologic emergency (Chapter 9).

A **paraneoplastic syndrome** is a group of signs caused by substances a tumour releases, not by the tumour's physical presence. NSCLC can release a hormone-like protein (parathyroid hormone–related protein) that raises calcium (hypercalcemia), and it can cause finger clubbing (PDQ Adult Treatment Editorial Board, 2025a). Small cell cancer can cause the syndrome of inappropriate antidiuretic hormone (SIADH) with low sodium, cortisol excess (Cushing syndrome) and nerve and muscle syndromes such as Lambert-Eaton myasthenic syndrome (PDQ Adult Treatment Editorial Board, 2025b). Hypercalcemia and SIADH are explained in Chapters 9 and 23; sodium and calcium imbalances in Chapter 3. New confusion in a patient with lung cancer may be a metabolic cause and needs prompt assessment, not an assumption of delirium (Chapter 8).

Diagnosis begins with a chest X-ray and a computed tomography (CT) scan of the chest with contrast. A positron emission tomography (PET) scan helps show spread. Tissue is needed to confirm the type, through bronchoscopy, a needle biopsy guided by imaging, or sampling of chest lymph nodes (PDQ Adult Treatment Editorial Board, 2025a). Tumour tissue is also tested for biomarkers (see the Going Deeper box). The nurse prepares the patient for each procedure (Chapter 1 for consent), watches for bleeding and pneumothorax afterward (Chapter 15), and supports the patient through a frightening wait for results.

Treatment and Nursing Care

Treatment depends on the type, stage, biomarkers, the person's health and their goals (Table 13.4). Many patients receive more than one treatment.

Surgery offers the best chance of cure for early NSCLC (PDQ Adult Treatment Editorial Board, 2025a). A **lobectomy** removes one lobe; a segmentectomy removes a smaller portion; a pneumonectomy removes a whole lung. The enhanced recovery guideline for lung surgery recommends video-assisted thoracoscopic surgery (VATS), done through small incisions, for early-stage cancer. It also recommends quitting smoking 4 or more weeks before surgery; multimodal pain control including regional anesthesia to reduce

opioid use; getting out of bed within 24 hours; early eating and drinking; and both drug and mechanical prophylaxis against venous thromboembolism (Batchelor et al., 2019).

After lung surgery, the nurse:

- keeps pain controlled so the patient can breathe deeply and cough (Chapter 5);
- coaches deep breathing, coughing and incentive spirometry (Chapter 12) and helps the patient walk early;
- monitors the chest drain for air leak, drainage and function (Chapter 15);
- watches for pneumonia, atelectasis and respiratory failure, and for new atrial fibrillation, which occurs in about 12% of patients after lung resection (Batchelor et al., 2019);
- recognizes and escalates deterioration using early warning scores and SBAR (Chapter 6; postoperative complications in Chapter 7, section 7.6).

Radiation to the chest can inflame the esophagus. Painful or difficult swallowing often lasts several weeks after treatment; care focuses on pain relief and keeping up nutrition and fluids. **Radiation pneumonitis**, inflammation of the lung, usually appears in the first weeks to months after radiation begins, with cough, dyspnea and fever. Severe cases can be fatal (Billiet et al., 2014). Patients are taught to report new or worse breathing symptoms even after treatment ends.

Systemic therapy includes chemotherapy, targeted therapy and immunotherapy (Chapter 9). **Immunotherapy** with immune checkpoint inhibitors releases a brake on T cells so they attack the cancer. These T cells can also attack healthy organs, causing immune-related adverse effects: pneumonitis, colitis, hepatitis, kidney inflammation, skin reactions and hormone disorders such as thyroid and adrenal problems or type 1 diabetes. These effects can appear even after the last dose (Merck Canada, 2019). A patient on immunotherapy who reports new cough, dyspnea or diarrhea needs prompt assessment and a call to the oncology team.

Symptom care. Dyspnea, cough, pain and fatigue are common. The nurse assesses each symptom, gives ordered treatments, positions the patient upright, teaches energy conservation and pacing, and involves the interprofessional team. Coughing up a large amount of blood is an emergency: the nurse stays with the patient, calls for help at once and follows Chapter 6. Palliative care can start at diagnosis, alongside treatment aimed at the cancer (Chapter 10).

Teaching and transitions. Before discharge, the nurse confirms that the patient knows which symptoms to report after radiation or immunotherapy, even weeks later. Patients taking an oral targeted drug at home, such as osimertinib, learn to take it at the same time each day, to swallow tablets whole and to care for their skin and nails (Cancer Care Ontario, 2023). Smoking cessation support continues after surgery (Chapter 14), and the family can be encouraged to test their home for radon. Older adults face a higher risk of atrial fibrillation after lung resection (Batchelor et al., 2019), so the nurse checks pulse rhythm and teaches what palpitations or new dizziness may mean.

Table 13.4 Lung cancer treatments and nursing focus (Batchelor et al., 2019; Billiet et al., 2014; Cancer Care Ontario, 2023; Merck Canada, 2019; original wording)

Treatment	What it involves	Main risks	Nursing focus
Surgery	Removing a segment, lobe or whole lung, often by VATS	Pneumonia, atelectasis, air leak, atrial fibrillation, venous thromboembolism	Pain control, breathing exercises, walking within 24 hours, chest drain checks, early escalation
Radiation	High-energy beams aimed at the tumour over several weeks	Esophagitis with painful swallowing; pneumonitis weeks to months later; fatigue	Swallowing and nutrition, pain relief, teaching to report new cough or dyspnea
Chemotherapy	Drugs that kill dividing cells, often given with radiation or immunotherapy	Low blood counts and infection, nausea, fatigue (Chapter 9)	Infection prevention, symptom control, safe handling of hazardous drugs
Targeted therapy	Oral drugs aimed at a specific gene change in the tumour	Rash, diarrhea, nail and skin changes; rarely lung inflammation or heart effects	Skin care teaching, hydration, reporting new breathlessness, adherence at home

Treatment	What it involves	Main risks	Nursing focus
Immunotherapy	Checkpoint inhibitors that help T cells attack the cancer	Immune attack on lungs, bowel, liver, skin or glands, even after treatment ends	Teaching early reporting, baseline and follow-up assessment, prompt referral

GOING DEEPER

Biomarkers and Targeted Therapy in Lung Cancer

Required for RN students; optional for PN students.

Many NSCLCs, especially adenocarcinomas, carry gene changes that drive their growth. Tumour tissue is tested for these **biomarkers** before treatment is chosen. Changes in the epidermal growth factor receptor (EGFR) gene and rearrangements of the anaplastic lymphoma kinase (ALK) gene are more common in adenocarcinomas of people who never smoked. Other targetable genes include ROS1, BRAF, KRAS, MET, RET, NTRK and HER2 (PDQ Adult Treatment Editorial Board, 2025a). Tumours are also tested for programmed death-ligand 1 (PD-L1), a protein that helps predict benefit from immunotherapy.

Targeted therapy. Osimertinib is an oral EGFR inhibitor used in Ontario for NSCLC with a confirmed EGFR mutation. Common effects are diarrhea, rash, dry skin and nail changes; serious effects include interstitial lung disease (about 4% of patients, median onset about 3 months), QT prolongation, heart muscle weakness and eye inflammation (keratitis). Monitoring includes blood counts, liver and kidney function, electrolytes, an electrocardiogram (ECG) at baseline and heart function (Cancer Care Ontario, 2023).

Immune checkpoint inhibitors. Pembrolizumab, marketed in Canada, blocks the programmed cell death protein 1 (PD-1) receptor on T cells. In its 2026 Canadian monograph, single-drug first-line use covers adults with metastatic NSCLC, or stage III disease when surgery or chemoradiation is not an option, whose tumours express PD-L1 (tumour proportion score of 1% or more) and have no EGFR or ALK change. Suspected immune-related pneumonitis needs imaging and corticosteroids are used for moderate or worse cases (Merck Canada, 2019). Moderate (grade 2) pneumonitis means holding the drug, and severe or recurrent moderate pneumonitis means stopping it for good (Merck Canada, 2026).

Nursing focus. The RN reviews baseline findings and teaches the patient which symptoms to report and how fast. At every contact, the RN asks about new cough, dyspnea, diarrhea, rash, fatigue and eye symptoms, and grades any effect so the oncology team can act. The RN also remembers that oral cancer drugs taken at home are hazardous drugs (Chapter 9).

13.6 Pleural Effusion and Empyema

The pleural space normally holds only a thin film of fluid. This section explains why fluid collects, how thoracentesis removes it and the nursing care around the procedure. Chest tubes and chest drainage are taught in Chapter 15.

Fluid Around the Lung

A **pleural effusion** is an abnormal collection of fluid in the pleural space. Effusions fall into two groups. A **transudate** is thin fluid pushed out by pressure or low protein in the blood; heart failure (Chapter 18) is a common cause, as are cirrhosis and nephrotic syndrome. An **exudate** is protein-rich fluid caused by inflammation or disease of the pleura itself, most often infection or cancer. The laboratory compares protein and lactate dehydrogenase (LDH) in the fluid and the blood to tell them apart (Roberts et al., 2023).

A **parapneumonic effusion** forms next to a pneumonia (sections 13.1 and 13.2). When the fluid becomes infected or frankly purulent, it is called **empyema**. A low fluid pH signals an infection that needs drainage (Roberts et al., 2023). A **malignant pleural effusion** is caused by cancer that involves the pleura, and it often returns after drainage (Roberts et al., 2023).

A large effusion compresses the lung. The patient may report dyspnea, cough or chest discomfort. On assessment, the nurse finds dullness to percussion, reduced or absent breath sounds and reduced chest expansion on the affected side (Chapter 12). Fever, chills and a pneumonia that is not improving suggest empyema. Ultrasound and chest imaging confirm the effusion.

Thoracentesis

Thoracentesis (pleural aspiration) is the removal of pleural fluid with a needle or small catheter (Figure 13.7). A diagnostic tap sends fluid for chemistry, cell counts, cytology and culture; a therapeutic tap relieves dyspnea. Thoracic ultrasound guidance is

mandatory except in an emergency, because it reduces the risk of pneumothorax and organ puncture (Asciak et al., 2023; Roberts et al., 2023).

Before. The nurse confirms that informed consent has been obtained by the practitioner doing the procedure (Chapter 1). The nurse records baseline vital signs, SpO2 and breath sounds, and checks for anticoagulants and antiplatelet drugs; for elective procedures, some are held for a set time beforehand, following policy and the practitioner's orders (Asciak et al., 2023). The patient usually sits upright, leaning forward over a padded bedside table.

During. The nurse helps the patient keep still, gives reassurance and watches the patient's face, breathing and SpO2. Fluid is drained slowly by syringe or gravity, not by wall suction or vacuum bottles. In general, no more than 1.5 L is removed at one time. Drainage stops early, even below that volume, if the patient reports chest tightness or pain, keeps coughing or becomes more breathless (Asciak et al., 2023). The patient may feel faint from a vasovagal response; the nurse watches for pallor, sweating and a falling heart rate or blood pressure.

After. The nurse checks vital signs, SpO2, breath sounds and the puncture site, and labels and sends specimens. A chest X-ray is not routine after an uncomplicated tap, but it is done if symptoms persist, the procedure was complicated or several attempts were needed (Asciak et al., 2023). The nurse acts at once on:

Figure 13.7 A packaged thoracentesis kit: a drainage bag and tubing, syringes, and the needle and catheter used to drain pleural fluid. (credit: "ThoracentesisEquip" by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

- sudden dyspnea, chest pain or falling SpO2, which suggest **pneumothorax**, the most common complication (Asciak et al., 2023; Chapter 15);
- cough, frothy sputum, crackles and hypoxemia, which suggest **re-expansion pulmonary edema**, a rare but potentially fatal complication that usually appears within the first hour (Asciak et al., 2023);
- bleeding, which is uncommon but can be life-threatening (Asciak et al., 2023).

When a Chest Tube or Other Procedure Is Needed

Pleural infection with a pH of 7.2 or less, or frank pus, needs a chest tube; a small-bore tube is used first. If drainage stops while infected fluid remains, medicines to break down clots and thick debris may be instilled into the pleural space, and some patients need surgery, preferably by VATS (Roberts et al., 2023). Antibiotics are given throughout (sections 13.1 and 13.2).

For a malignant effusion that keeps returning, patients without a trapped lung are offered a choice between an **indwelling pleural catheter**, a tunnelled tube that the patient or a family member drains at home, and **pleurodesis**, in which talc is placed in the pleural space to seal it shut. The choice rests with the patient (Roberts et al., 2023). Chest drainage care is in Chapter 15; home and community nursing support is part of planning the transition home.

SCOPE IN PRACTICE

Directly Observed Therapy, Thoracentesis and Reporting

Roles depend on **authority, competence and context** (Chapter 1, section 1.3). Employer policy and the province or territory also shape practice.

- **Thoracentesis:** performed by a physician, or by a nurse practitioner (NP) with the competence to do it where employer policy permits; CNO's practice standard lists performing a procedure below the dermis or a mucous membrane among the controlled

acts NPs are authorized to perform (College of Nurses of Ontario [CNO], 2026). RNs and practical nurses assist, monitor and recognize complications. RNs and RPNs cannot initiate controlled acts in Ontario's public hospitals (Chapter 1).

- **DOT:** in Ontario, the board of health keeps a system for DOT (Ontario Ministry of Health, 2025). Who observes the doses depends on the local program and employer policy.
- **Reporting:** TB is a disease of public health significance in Ontario (Windsor-Essex County Health Unit, 2024), and the duty to report it under the *Health Protection and Promotion Act* applies to nurses as well as physicians, pharmacists and others (Ontario Ministry of Health, 2025). The nurse follows the employer's reporting process, which often involves infection prevention and control.
- **Assignment:** an RPN may care for a patient in airborne isolation or after thoracentesis when the RPN has the competence and the context supports it. Assigning stable patients to RPNs is a common employer practice, not a CNO rule.
- **Deterioration:** every nurse who notices worsening acts at once and escalates (Chapter 6). The RPN consults the RN as the patient's needs change.

PRACTICE STORY

Stopping at the Right Moment

Names and details are fictional; this is a composite story.

Nurse: Mireille Gagnon, RPN. Years in practice: 6. Setting: medical unit, eastern Ontario.

Madame Lucie Thibodeau, 74, has lung adenocarcinoma that has spread to the pleura. She speaks mostly French, and I am one of the few francophone nurses on our unit, so I often take her assignment. That morning she told me, "Je n'arrive plus à respirer quand je marche." Her right side was dull to percussion with almost no breath sounds at the base.

The respirologist came to do a therapeutic thoracentesis with ultrasound at the bedside. My RN colleague, Kofi, was the resource nurse for the procedure and checked that her apixaban had been held as ordered. I explained each step in French, helped her lean over the padded table and stayed in front of her where she could see me.

At about 1.2 L she started to cough, and kept coughing. She squeezed my hand and said her chest felt tight. I said, "Doctor, she has a persistent cough and chest tightness." He stopped the drainage right away.

Afterward I sat her up and checked her every 15 minutes. Her SpO2 was 95% before the procedure. Forty minutes later it was 89%, her respiratory rate was 28 and I heard new fine crackles on the right. She was coughing up thin, pink-tinged sputum. I did not wait to see if it would settle. I called Kofi to the room, and we called the physician together while Kofi started oxygen under the existing order. The team treated her for suspected re-expansion pulmonary edema, and by morning she was back on room air.

Before I left, Madame Thibodeau asked whether she would need "the needle" every week. I told her honestly that I didn't know, and I asked the team to talk with her about an indwelling catheter or pleurodesis, in French, with her daughter present.

Reflect:

1. Which cues told Mireille that this was not simple post-procedure coughing, and why did timing matter?

2. Using authority, competence and context, explain why Mireille consulted the RN and called the physician rather than managing the change alone.

Chapter 13 Summary

Introduction

- Pneumonia was the fourth most common reason for a hospital stay in Canada in 2023–2024, with 66,128 hospitalizations.
- This chapter covers lower respiratory infections, tuberculosis, lung cancer and pleural disease; assessment and oxygen therapy are in Chapter 12.

13.1 Community-Acquired Pneumonia

- Pneumonia fills alveoli with exudate (consolidation), causing hypoxemia; viruses and S. pneumoniae are common causes, and often none is found.
- Risk rises steeply with age and with chronic disease, smoking, substance use, unstable housing and other structural conditions.
- Older adults may present with confusion, falls or loss of function rather than fever; sepsis cues call for immediate escalation.

- Cultures are collected before the first antibiotic dose when this causes no delay; antimicrobial choice follows severity, comorbidities and local resistance.
- Clinical stability guides the IV-to-oral switch and discharge; short courses and allergy assessment are part of stewardship.
- Severity scores such as CURB-65 and PSI support, but do not replace, clinical judgment.

13.2 Hospital-Acquired and Aspiration Pneumonia

- HAP appears 48 hours or more after admission; VAP is covered in Chapter 15.
- HAP organisms are more often resistant, and treatment follows the local antibiogram.
- Oral care, swallowing screens, early mobility, upright positioning and lighter sedation are core nursing prevention measures.
- Aspiration pneumonitis is a chemical injury from stomach contents; aspiration pneumonia is an infection, usually in a person with dysphagia.

13.3 Influenza, COVID-19 and RSV

- All three spread by respiratory particles and contact; in Ontario, they need droplet and contact precautions from the time illness is suspected.
- Complications include viral and bacterial pneumonia, delirium, worsening chronic disease and, after influenza, heart attack and stroke.
- Oseltamivir is first-line for severe influenza regardless of timing; nirmatrelvir–ritonavir is for high-risk adults with mild to moderate COVID-19 within 5 days and has serious drug interactions.
- RSV has no specific antiviral; care is supportive.
- NACI recommends influenza, COVID-19, pneumococcal and RSV vaccines for many adults; eligibility for public funding varies by province.

13.4 Tuberculosis

- TB spreads through airborne droplet nuclei, mostly indoors. TB infection causes no symptoms and is not contagious; TB disease causes illness and can spread.
- In 2023, Canada reported 2,217 TB cases (5.5 per 100,000). In 2024, rates were highest among Inuit, and 82.9% of people with TB disease were born outside Canada. Crowded housing, food insecurity, poverty and colonial history drive these gaps; Inuit-led elimination work targets 2030.
- TST and IGRA detect TB infection but not disease; sputum smear, culture and NAAT, with chest X-ray, diagnose TB disease.
- Suspected pulmonary TB needs an AIIR, fit-tested N95 respirators for staff and a medical mask for the patient outside the room.
- TB infection is treated with 4 months of rifampin or 12 weekly doses of isoniazid and rifapentine; drug-susceptible disease is treated with four drugs for 2 months, then isoniazid and rifampin for 4 months, supported by DOT and patient-centred care.
- TB disease is reportable in every jurisdiction; public health leads contact tracing.

13.5 Lung Cancer

- Lung cancer is the leading cause of cancer death in Canada; an estimated 32,900 people will be diagnosed and 19,300 will die of it in 2026.
- Smoking is the leading cause; radon is the second leading cause and the leading cause in people who never smoked. Health Canada recommends a long-term home radon test.
- NSCLC (mainly adenocarcinoma and squamous cell) is far more common than SCLC, which spreads early and causes paraneoplastic syndromes such as SIADH.
- Surgery, often by VATS, is the main curative option for early NSCLC; nursing care centres on pain control, early mobility, breathing exercises and early detection of complications.
- Radiation, chemotherapy, targeted therapy and immunotherapy each carry distinct risks, including radiation pneumonitis and immune-related pneumonitis, which may appear after treatment ends.

13.6 Pleural Effusion and Empyema

- Transudates usually come from pressure or low protein, as in heart failure; exudates from inflammation, infection or cancer. Empyema is infected pleural fluid.
- Thoracentesis is done under ultrasound guidance; no more than 1.5 L is removed at one time, and drainage stops if chest tightness, pain, persistent cough or worse breathlessness develop.
- After thoracentesis, the nurse watches for pneumothorax, re-expansion pulmonary edema and bleeding.
- Pleural infection with low pH or pus needs a chest tube; recurrent malignant effusion is managed with an indwelling pleural catheter or pleurodesis, by patient choice.

Key Terms (42)

airborne infection isolation room (AIIR): A single room under negative pressure, with air exhausted outdoors or filtered, used for patients with diseases spread by the airborne route.

antimicrobial stewardship: coordinated efforts to use antimicrobials only when needed, with the right drug, dose, route and duration.

antiviral: a drug that stops a virus from multiplying, such as oseltamivir for influenza or nirmatrelvir–ritonavir for COVID-19.

aspiration: the passage of material from the mouth, throat or stomach into the airways.

aspiration pneumonia: a lung infection that follows the breathing in of mouth and throat secretions that carry bacteria, usually in a person with dysphagia.

aspiration pneumonitis: a chemical lung injury caused by breathing in a large volume of stomach contents, usually in a person with reduced consciousness.

atypical bacteria: bacteria such as Legionella that cause pneumonia but need special tests, such as urine antigen tests or selective cultures, to detect.

blood culture: a blood sample placed in culture bottles to detect and identify bacteria or fungi in the bloodstream, collected before the first antibiotic dose when possible.

community-acquired pneumonia (CAP): pneumonia that begins outside hospital, including in long-term care.

consolidation: the filling of alveoli with fluid, cells and debris so that part of the lung becomes solid and airless.

COVID-19: the respiratory illness caused by the SARS-CoV-2 virus.

CURB-65: a five-item pneumonia severity score (confusion, urea, respiratory rate, blood pressure, age 65 or older) that helps decide where a patient should be treated.

directly observed therapy (DOT): A method in which a trained person watches a patient take each dose of medication, used to support completion of TB treatment.

drug-resistant TB: TB caused by bacteria resistant to one or more TB drugs; multidrug-resistant TB is resistant to at least isoniazid and rifampin.

empyema: Infected fluid or pus in the pleural space.

exudate: Protein-rich pleural fluid caused by inflammation or disease of the pleura, such as infection or cancer.

hospital-acquired pneumonia (HAP): pneumonia that was not incubating at admission and appears 48 hours or more after admission.

immunotherapy: Cancer treatment, such as immune checkpoint inhibitors, that helps the immune system attack cancer cells.

influenza: an acute respiratory illness caused by influenza viruses, classically with sudden fever, cough and muscle aches.

interferon-gamma release assay (IGRA): A blood test that detects TB infection by measuring interferon-gamma released by T cells exposed to M. tuberculosis proteins; not affected by BCG vaccine.

lobectomy: Surgical removal of one lobe of a lung.

N95 respirator: A fit-tested respirator that filters small airborne particles, worn by health care workers caring for patients with airborne infections such as TB.

non-small cell lung cancer (NSCLC): The group of lung cancers other than small cell, including adenocarcinoma, squamous cell carcinoma and large cell carcinoma.

nucleic acid amplification test (NAAT): A rapid laboratory test that detects the genetic material of M. tuberculosis in a specimen and can identify rifampin resistance.

paraneoplastic syndrome: Signs and symptoms caused by substances a tumour releases, such as hormones, rather than by the tumour's direct spread.

pleural effusion: An abnormal collection of fluid in the pleural space.

pleuritic chest pain: sharp chest pain that worsens with deep breathing or coughing, caused by inflammation of the pleura.

pneumonia: an acute infection of the lung tissue (alveoli and smallest airways) that causes inflammation and fills air spaces with fluid and cells.

Pneumonia Severity Index (PSI): a pneumonia prediction rule that sorts patients into five risk classes using age, coexisting diseases, vital signs and laboratory values.

post-COVID-19 condition: in the WHO definition, symptoms that continue more than 3 months after SARS-CoV-2 infection, last at least 2 months and have no other explanation.

radon: A colourless, odourless radioactive gas from the breakdown of uranium in soil and rock; the second leading cause of lung cancer in Canada.

re-expansion pulmonary edema: A rare, potentially fatal fluid build-up in a lung that re-expands quickly after removal of pleural fluid or air.

respiratory fluoroquinolone: a fluoroquinolone antibiotic, such as levofloxacin or moxifloxacin, that is active against the common bacterial causes of pneumonia.

respiratory syncytial virus (RSV): a common respiratory virus that can cause severe lower respiratory tract disease in older adults and people with chronic conditions.

small cell lung cancer (SCLC): A fast-growing lung cancer, about 15% of cases, that has usually spread by the time it is diagnosed.

TB disease: Active illness from M. tuberculosis multiplying in the body; TB disease in the lungs or larynx can spread to others.

TB infection: A state in which M. tuberculosis is alive but held in check by the immune system; the person has no symptoms and cannot spread TB (formerly called latent TB infection).

thoracentesis: Removal of fluid from the pleural space with a needle or small catheter, for diagnosis or relief of symptoms.

transudate: Low-protein pleural fluid caused by pressure or low blood protein, as in heart failure.

tuberculin skin test (TST): A test in which purified protein derivative is injected into the skin and the induration is measured 48 to 72 hours later to detect TB infection.

tuberculosis (TB): An infection caused by Mycobacterium tuberculosis that spreads through the air and most often affects the lungs.

ventilator-associated pneumonia (VAP): pneumonia that develops more than 48 hours after endotracheal intubation.

Licensure Review & Clinical Judgment Questions (35)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Lucille Arsenault (Questions 1–4): Lucille Arsenault, 82, lives alone in a seniors' apartment in Belleville, Ontario. Her son brought her to the emergency department because she fell twice yesterday and "isn't herself." A chest X-ray shows a new right lower lobe infiltrate, and she is admitted to a medical unit with community-acquired pneumonia. Her temperature is 37.4 °C, heart rate 104 beats/min, respiratory rate 26 breaths/min, blood pressure 118/70 mm Hg and SpO2 91% on room air. An RPN is caring for her, with an RN on the team.

1. [CORE] Mrs. Arsenault's son says, "It can't be pneumonia. She doesn't even have a fever." Which response by the nurse is most accurate?

a. "In older adults, pneumonia often shows up as confusion or falls, and the temperature may be only slightly raised."

b. "A temperature of 37.4 °C means the infection is viral rather than bacterial, so she will not need any antibiotics."

c. "The X-ray result is probably an error, because pneumonia in any adult always causes a high fever."

d. "Her temperature will go up once the antibiotic starts to work."

Answer: a — Older adults often present with confusion, falls or loss of function, and fever may be mild or absent (a) (section 13.1, Lifespan Considerations box). Temperature does not tell a viral cause from a bacterial one (b). Pneumonia does not always cause a high fever, and the infiltrate on imaging supports the diagnosis (c). Antibiotics treat the infection; they do not raise the temperature (d).

2. [CORE] The prescriber orders two sets of blood cultures and a first dose of IV ceftriaxone for Mrs. Arsenault. The antibiotic has arrived on the unit, and the person who draws the cultures can come in 10 minutes. What should the nurse do?

a. Give the antibiotic now and have the cultures drawn on the morning blood rounds

b. Ask the prescriber to cancel the cultures, since the antibiotic is ready

c. Have the cultures drawn in the next few minutes, then give the antibiotic right away

d. Hold the antibiotic until a sputum specimen is also obtained, however long that takes

Answer: c — Cultures are collected before the first dose when this can be done quickly, because antibiotics can sterilize specimens (c) (section 13.1; Chapter 4, section 4.5). Drawing cultures the next morning, after the antibiotic, lowers their yield (a). Cancelling ordered cultures is not the nurse's decision, and it gives up useful information (b). The dose is not delayed indefinitely for a sputum specimen that may be hard to obtain (d).

3. [CORE] At 0300 on day 2, Mrs. Arsenault's respiratory rate is 30 breaths/min, blood pressure 94/58 mm Hg and SpO2 88% on 2 L/min oxygen. She no longer follows simple commands. Which action should the RPN take first?

a. Recheck her vital signs in 1 hour so the trend can be confirmed before anyone is called

b. Give the as-needed sedative that is ordered for agitation so that she can rest

c. Record the findings in detail and report them to the RN and prescriber at morning rounds

d. Stay with her, raise the oxygen within the ordered range and escalate now

Answer: d — Rapid breathing, falling blood pressure, hypoxemia and new confusion suggest sepsis and worsening respiratory status. Any nurse acts at once and escalates, and the RPN involves the RN and the rapid response pathway as policy directs (d) (section 13.1, Clinical Judgment box; Chapter 6). Waiting an hour (a) or until rounds (c) delays care. A sedative could mask confusion and depress breathing (b).

4. [CORE] Mrs. Arsenault is ready for discharge. Which statement shows that she understands the teaching?

a. "I will stop my antibiotic as soon as I feel better."

b. "I will ask my pharmacist which pneumonia and RSV vaccines I am due for."

c. "I will need a chest X-ray every month for the next year to check my lungs."

d. "I should stay in bed for two weeks to let my lungs rest."

Answer: b — At 82, she is in the age groups for which NACI recommends pneumococcal and RSV vaccines, so checking her vaccine status is appropriate (b) (section 13.3, Patient Education box). The course is taken as prescribed (a). A routine follow-up chest X-ray is not recommended after recovery (c). Bed rest causes deconditioning; gradual activity is encouraged (d).

5. [CORE] Why does a patient with lobar pneumonia develop hypoxemia?

a. Inflammation narrows the trachea and blocks the flow of air to both lungs.

b. Blood flows past alveoli filled with fluid and cells, so it does not pick up oxygen.

c. Fever lowers the amount of hemoglobin available to carry oxygen in the blood.

d. The infection stops the respiratory centre in the brainstem from triggering breaths.

Answer: b — In consolidation, alveoli fill with exudate, so blood passing them leaves the lung without picking up oxygen (b) (section 13.1; Chapter 12, section 12.1). Pneumonia affects the lung tissue, not the trachea (a). Fever does not lower hemoglobin (c). The drive to breathe usually increases, which is why the respiratory rate rises (d).

6. [CORE] Before the first dose of amoxicillin, a patient with community-acquired pneumonia says, "I'm allergic to penicillin. It gave me an upset stomach once." What should the nurse do?

a. Give the amoxicillin as ordered, because an upset stomach is a side effect rather than a true allergy

b. Remove the penicillin allergy from the health record, since the reaction was not an allergy

c. Hold all antibiotics until an allergist can see the patient and test for penicillin allergy

d. Record the exact reaction and discuss it with the prescriber or pharmacist before the dose

Answer: d — The nurse documents what actually happened and shares it, so the prescriber or pharmacist can assess the label (d) (section 13.1; Chapter 4, section 4.5). Stomach upset is usually a side effect rather than an allergy, but the nurse does not give a drug against a recorded allergy without that review (a), and does not remove a label alone (b). Waiting for an allergist would delay treatment that the team can usually arrange safely (c).

7. [CORE] Which nursing actions help prevent hospital-acquired pneumonia in a patient on a medical unit who is not on a ventilator? Select all that apply.

a. Brushing the patient's teeth and gums on a regular schedule

b. Keeping the patient lying flat in bed to conserve energy

c. Screening swallowing before the first oral intake after a stroke

d. Helping the patient sit up and walk as soon as it is safe

e. Using a chlorhexidine mouth rinse for every patient on the unit

f. Keeping the head of the bed raised during tube feeding

Answer: a, c, d, f — Oral care (a), swallowing screens (c), early mobility (d) and an upright position during tube feeding (f) are prevention measures supported by studies (section 13.2). Lying flat (b) increases the risk of aspiration and deconditioning. Routine chlorhexidine oral care is not recommended even for ventilated patients; toothbrushing is the recommended practice (e).

8. [CORE] Which patient's pneumonia is classified as hospital-acquired?

a. A patient admitted for a hip fracture who develops pneumonia on day 4 of the stay

b. A long-term care resident admitted with pneumonia that began 2 days before transfer

c. A patient admitted with fever and cough that started at home the day before

d. A patient who develops pneumonia on day 3 of mechanical ventilation in critical care

Answer: a — HAP was not incubating at admission and appears 48 hours or more after admission (a) (section 13.2). Pneumonia that starts in long-term care is managed as community-acquired (b). Symptoms that began at home before admission point to CAP (c). Pneumonia that starts more than 48 hours after intubation is ventilator-associated pneumonia (d).

9. [CORE] A drowsy patient vomits while lying flat after receiving a sedative. Within 2 hours, the patient's SpO2 falls and crackles are heard. Which statement about this problem is accurate?

a. It is caused by bacteria from the mouth and always needs antibiotics that cover anaerobic organisms.

b. It occurs only in patients with dysphagia from a stroke.

c. It is most likely a chemical injury from stomach contents, which may settle within about 48 hours.

d. It can be ruled out because the event was witnessed.

Answer: c — A witnessed episode of vomiting in a person with reduced consciousness, followed by rapid hypoxemia, suggests aspiration pneumonitis. This is a chemical injury that may settle within about 48 hours with supportive care (c) (section 13.2). The cause is chemical, not bacterial, and the ATS/IDSA guideline suggests not adding routine anaerobic coverage unless abscess or empyema is suspected (a). Reduced consciousness, not only stroke, is a risk factor (b). Pneumonitis is often witnessed (d).

10. [CORE] A patient admitted to an Ontario hospital with a cough and fever is suspected of having influenza. Which precautions should the nurse use while the test result is pending?

a. Airborne precautions in a negative-pressure room, with an N95 respirator only

b. Droplet and contact precautions in a single room, with gown, gloves, mask and eye protection

c. Routine practices only, until a positive laboratory test result confirms that the patient has influenza

d. Contact precautions only, with gown and gloves

Answer: b — Ontario guidance lists influenza, RSV and COVID-19 under droplet and contact precautions, which start when infection is suspected (b) (section 13.3; Chapter 4, section 4.3). Airborne precautions (a) are for infections such as tuberculosis and measles. Waiting for the test (c) allows spread. Contact precautions alone (d) do not protect against droplets.

11. [CORE] An adult who takes several heart medications is prescribed nirmatrelvir–ritonavir for COVID-19. What is the nurse's most important action before the first dose?

a. Make sure the prescriber or pharmacist has reviewed a full medication list, including natural health products

b. Give the first dose right away, because drug interactions only begin after several days of combined treatment

c. Tell the patient to stop taking all heart medications for the 5 days of antiviral treatment

d. Ask the patient to take the heart medications 2 hours apart from the antiviral to avoid interactions

Answer: a — Ritonavir strongly inhibits CYP3A4, and the monograph warns of serious interactions, including with some antiarrhythmics, statins and anticoagulants. A full medication review comes first (a) (section 13.3). Interactions can occur from the first dose (b). Stopping drugs without an order is unsafe and outside the nurse's authority (c). Spacing doses a few hours apart does not prevent this kind of interaction, which happens in the liver while ritonavir is in the body (d).

12. [CORE] An adult is admitted with severe influenza 4 days after symptoms began, and the test result is pending. Oseltamivir is ordered. Which statement reflects Ontario Health guidance?

a. Oseltamivir offers no benefit once 48 hours have passed since symptoms began, so the nurse should question the order.

b. The dose should wait until the influenza test is positive.

c. Oseltamivir is used only for patients who have no chronic conditions.

d. Oseltamivir is recommended for severe influenza no matter how long symptoms have been present.

Answer: d — For severe or worsening influenza, oseltamivir is first-line regardless of time since symptom onset (d) (section 13.3). The 48-hour window applies to milder illness (a). Treatment does not wait for test results when influenza is circulating (b). Chronic conditions increase, rather than rule out, the need for treatment (c).

13. [CORE] A 78-year-old with no chronic health conditions asks which vaccines are recommended. Which statement is accurate according to NACI?

a. Influenza vaccine is recommended only for people with lung disease.

b. RSV vaccine is recommended only for residents of long-term care homes.

c. One dose of an RSV vaccine is recommended for all adults 75 and older.

d. Pneumococcal vaccine is not recommended after age 75.

Answer: c — NACI recommends that all adults 75 and older receive one dose of an RSV vaccine (c) (section 13.3, Patient Education box). Influenza vaccine is recommended every year for everyone 6 months and older (a). RSV vaccine is not limited to long-term care residents (b). Pneumococcal vaccine is recommended for all adults 65 and older, with no upper age limit (d).

14. [CORE] An RPN is caring for a patient with pneumonia whose condition has been stable. The patient now has a rising oxygen need and new confusion. Which action best reflects scope of practice?

a. Continue caring for the patient without involving others, since the patient was assigned to the RPN

b. Meet immediate safety needs, consult the RN and escalate as hospital policy directs

c. Hand the patient's care over to the RN and leave the bedside to care for other patients

d. Wait for the prescriber's morning rounds before sharing the new findings with anyone

Answer: b — Any nurse who notices deterioration acts at once and escalates. As the patient's needs change, the RPN consults the RN, based on authority, competence and the practice context, including employer policy, which can differ by province or territory (b) (section 13.1; Chapter 1, section 1.3). Continuing alone ignores the change in the patient's needs (a). Stepping away abandons a deteriorating patient (c). Waiting for rounds delays care (d).

15. [CORE] A patient had COVID-19 four months ago and still has fatigue and shortness of breath. Testing has found no other cause. Which statement fits the definition of post-COVID-19 condition?

a. The diagnosis requires a positive COVID-19 test within the past week to confirm active infection.

b. Any symptoms that last up to 4 weeks after infection and then resolve fully fit the definition.

c. The condition affects only people whose COVID-19 was severe enough to need hospital care.

d. Symptoms continue more than 3 months after infection, last 2 months or more and have no other explanation.

Answer: d — The WHO definition requires symptoms more than 3 months after infection, lasting at least 2 months and not explained by another diagnosis (d) (section 13.3). A current positive test is not required (a). Symptoms that resolve within 4 weeks do not fit the definition (b). The condition is not limited to people who were admitted to hospital (c).

16. [RN] A 70-year-old with community-acquired pneumonia is newly confused. Results show urea 8.4 mmol/L, respiratory rate 24 breaths/min and blood pressure 104/66 mm Hg. What is the patient's CURB-65 score, and what does it suggest?

a. 2; a low-risk group, so the patient is suitable for treatment at home without admission

b. 4; a very high-risk group in which death is expected

c. 3; a higher-risk group in which 30-day mortality rose sharply in the original study

d. 1; the patient's age is the only CURB-65 criterion that is met

Answer: c — The patient scores 1 point each for confusion, urea above 7 mmol/L and age 65 or older, for a total of 3. In the derivation study, 30-day mortality rose to 17% at a score of 3 (c) (section 13.1, Going Deeper box). The respiratory rate (under 30) and blood pressure (systolic 90 or higher, diastolic over 60) do not score, so 4 is wrong (b), and the low scores in a and d leave out criteria that are met. No score predicts death for an individual.

17. [RN] Which statement about pneumonia severity scores is accurate?

a. The ATS/IDSA guideline prefers the Pneumonia Severity Index and uses it together with clinical judgment.

b. A CURB-65 score of 0 means the patient can always be safely treated at home, whatever else is found.

c. CURB-65 includes the SpO2, so it fully captures how hypoxemic the patient is.

d. Once a severity score has been calculated, it replaces the nurse's ongoing reassessment of the patient.

Answer: a — The guideline recommends a validated rule alongside clinical judgment and prefers PSI over CURB-65 (a) (section 13.1, Going Deeper box). A patient with a score of 0 may still need admission for hypoxemia, inability to take oral drugs or no safe place to recover (b). CURB-65 does not include oxygenation (c). Scores support decisions but do not replace reassessment (d).

Case: Mr. Teodoro Reyes (Questions 18–23): Mr. Teodoro Reyes, 58, moved to Belleville from the Philippines 3 years ago and works as a cook. He has type 2 diabetes. He comes to the emergency department with a cough for 5 weeks, now producing sputum with streaks of blood, night sweats, and a 6 kg weight loss. His temperature is 38.1 °C, heart rate 98, respiratory rate 22 and SpO2 95% on room air. He lives with his wife, two adult children and a grandchild aged 3. A chest X-ray shows a cavity in the right upper lobe. He is admitted to a medical unit.

18. [CORE] The nurse reviews Mr. Reyes's history and assessment. Which group of findings most strongly suggests active pulmonary TB?

a. Fever of 38.1 °C, heart rate 98 and type 2 diabetes

b. Cough for 5 weeks, blood-streaked sputum, night sweats and weight loss

c. Respiratory rate 22, SpO2 95% and work as a cook

d. Recent arrival in Canada, a large household and work in a busy kitchen

Answer: b — A weeks-long cough with hemoptysis, night sweats and weight loss is the classic pattern of pulmonary TB disease (section 13.4, Recognizing TB). Option a lists a nonspecific fever and tachycardia plus a risk factor, not symptoms of TB. Option c includes mild abnormalities that many lung conditions share, and his job is not a TB risk. Option d lists background and risk information, not symptoms; birth in a country where TB is common raises suspicion, and household size matters for contact tracing, but neither shows that he is ill with TB.

19. [CORE] Which finding suggests that Mr. Reyes is likely to be highly infectious?

a. His type 2 diabetes, which raises his TB risk

b. His temperature of 38.1 °C

c. His SpO2 of 95%

d. The cavity in his right upper lobe

Answer: d — Cavities and upper-lobe disease, along with frequent cough and a positive smear, make a person more infectious (section 13.4, How TB Develops). Diabetes (option a) raises his risk of developing TB disease but does not change how infectious he is. Fever (option b) reflects illness, not the number of bacteria he releases. An SpO2 of 95% (option c) describes his oxygenation, not his infectiousness.

20. [CORE] Mr. Reyes arrives on the unit. What is the nurse's priority?

a. Place him in an airborne infection isolation room with the door closed.

b. Collect a first sputum specimen at the nursing station.

c. Ask his family to wear medical masks while visiting in a shared room.

d. Start droplet precautions in a shared room until the first sputum smear result is known.

Answer: a — TB spreads through droplet nuclei that stay in the air, so a patient with suspected pulmonary TB needs an AIIR under negative pressure at once (section 13.4, Airborne Precautions). Collecting sputum at the station (option b) exposes others. A shared room with masked visitors (option c) does not stop airborne spread. Droplet precautions in a shared room (option d) are the wrong category for TB; the particles are small enough to travel on air currents.

21. [CORE] The physician orders sputum for acid-fast bacilli smear, culture and nucleic acid amplification testing. Which plan best fits the Canadian Tuberculosis Standards?

a. Collect one specimen now; if the smear is negative, TB is ruled out.

b. Collect three specimens, each at least 24 hours apart, from saliva if needed.

c. Collect three or more specimens; same-day collection 1 hour apart is acceptable.

d. Collect one specimen by sputum induction at the bedside, with the room door left open for airflow.

Answer: c — The Standards call for at least three specimens and recommend collecting them on one day, spaced at least 1 hour apart (section 13.4, Testing). A single negative smear (option a) cannot rule out TB, because smear microscopy misses many cases. Saliva (option b) is not a useful specimen; the patient must bring up sputum from the lungs. Sputum induction (option d) creates aerosols and must be done in an AIIR or a booth that meets the same standard, never with the door open.

22. [CORE] Before entering Mr. Reyes's room, which action by the nurse is correct?

a. Put on a medical mask and eye protection.

b. Put on the N95 respirator model for which the nurse was fit-tested and do a seal check.

c. Put on any available N95 respirator; fit testing is needed only for aerosol-generating procedures.

d. Enter without a respirator, because he is wearing a medical mask.

Answer: b — Every health care worker caring for a patient with suspected respiratory TB wears a fit-tested N95 (or equivalent) and performs a user seal check each time it goes on (section 13.4, Clinical Safety box). A medical mask (option a) does not filter droplet nuclei. An unfitted model (option c) may not seal; the rule covers all care, not only procedures. The patient wears a medical mask only when outside the AIIR (option d); inside, staff still need respirators.

23. [CORE] Mr. Reyes is diagnosed with drug-susceptible TB and will finish treatment at home with public health support. Which statement shows that he understands his teaching?

a. "Once I feel better and stop coughing, I can stop the pills."

b. "If my urine turns orange, I should stop the rifampin and call the clinic."

c. "I can take the pills whenever I remember, as long as I take most of them."

d. "I need to take all my pills for at least 6 months, even when I feel well."

Answer: d — Drug-susceptible TB needs about 6 months of treatment, and missed or erratic doses can cause treatment failure and drug resistance (section 13.4, Treatment and Adherence). Stopping when symptoms ease (option a) risks relapse. Orange body fluids (option b) are an expected effect of rifampin, not a reason to stop. Erratic dosing (option c) is a known cause of acquired resistance.

24. [CORE] A patient is starting isoniazid, rifampin, pyrazinamide and ethambutol. Which findings should the nurse teach the patient to report promptly? Select all that apply.

a. Yellowing of the skin or eyes

b. Orange-red urine

c. Blurred vision or trouble telling red from green

d. Numbness or tingling in the hands or feet

e. Mild tiredness in the first week

f. A new skin rash

Answer: a, c, d, f — Jaundice (a) can signal liver injury from isoniazid, pyrazinamide or rifampin. Changes in visual acuity or colour vision (c) can signal optic nerve damage from ethambutol. Numbness or tingling (d) suggests isoniazid neuropathy. Rash (f) can occur with all four drugs (section 13.4, Medications box). Orange-red urine (b) is an expected, harmless effect of rifampin; the patient is warned about it but does not need to report it. Mild tiredness early in treatment (e) is common with TB itself and is not a specific drug warning sign, though the nurse still assesses it at follow-up.

25. [CORE] An adult who received the bacille Calmette-Guérin (BCG) vaccine at age 12 needs testing after contact with a person who has TB. The nurse expects which test?

a. A tuberculin skin test read at 24 hours

b. A chest X-ray alone, because BCG makes all TB tests invalid

c. An interferon-gamma release assay

d. A sputum culture, because it detects TB infection

Answer: c — IGRA is not affected by BCG and is preferred for people who received BCG after infancy (section 13.4, Testing). A TST (option a) is read at 48 to 72 hours, and BCG can cause a false-positive result. BCG does not invalidate the IGRA, and a chest X-ray alone (option b) cannot detect TB infection. Sputum culture (option d) detects TB disease, not TB infection, and a person with TB infection usually has no sputum to test.

26. [CORE] A patient who has never smoked asks how she could have lung cancer. Which response by the nurse is accurate?

a. "Radon gas in homes is the leading cause in people who don't smoke."

b. "Lung cancer in people who never smoked is almost always inherited."

c. "Radon testing takes a few hours, so your family can find out quickly."

d. "Air pollution is the leading cause of lung cancer in Canada."

Answer: a — Health Canada identifies radon as the leading cause of lung cancer in people who don't smoke and the second leading cause overall, after smoking (section 13.5, Lung Cancer in Canada). Family history is one risk factor, but option b overstates it. Health Canada recommends a long-term test of at least 3 months (option c). Smoking, not air pollution (option d), is the leading cause.

27. [CORE] A patient is on the surgical unit the morning after a right lower lobectomy by video-assisted thoracoscopic surgery. Which nursing action best supports recovery?

a. Keep the patient on bed rest until the chest tube is removed to protect the incision.

b. Hold pain medication so the patient can cough more forcefully.

c. Restrict oral fluids until bowel sounds return on day 3.

d. Help the patient walk, with pain controlled enough to allow deep breathing.

Answer: d — The enhanced recovery guideline recommends getting out of bed within 24 hours and multimodal pain control, which allows deep breathing and coughing (section 13.5, Treatment and Nursing Care). Bed rest until tube removal (option a) increases the risk of pneumonia, atelectasis and venous thromboembolism. Uncontrolled pain (option b) makes patients breathe shallowly and avoid coughing. The guideline supports early eating and drinking (option c).

28. [CORE] Thirty minutes after an uncomplicated thoracentesis, which finding should the nurse report immediately?

a. A small dry dressing at the puncture site

b. Sudden dyspnea, sharp chest pain and SpO2 falling from 95% to 88%

c. Mild soreness at the puncture site

d. Breath sounds slightly louder on the treated side than before the procedure

Answer: b — Sudden dyspnea, chest pain and falling SpO2 suggest pneumothorax, the most common complication of thoracentesis, and need urgent escalation (section 13.6, Thoracentesis). A dry dressing (option a) and mild soreness (option c) are expected. Breath sounds often improve after fluid is removed (option d), a sign that the lung has re-expanded.

29. [CORE] In an Ontario hospital, a registered practical nurse (RPN) is caring for a patient after thoracentesis. The patient begins coughing frothy sputum, and the SpO2 is falling. What is the RPN's best action?

a. Document the findings and recheck in 1 hour.

b. Wait for the physician's next rounds, since the RPN did not perform the procedure.

c. Stay with the patient, call for help at once and consult the RN.

d. Transfer the assignment to the RN and leave to care for other patients.

Answer: c — Every nurse who notices deterioration acts at once and escalates, and the RPN consults the RN as the patient's needs change (section 13.6, Scope in Practice box). Waiting an hour (option a) or until rounds (option b) delays care for possible re-expansion pulmonary edema. Handing over and leaving (option d) abandons a deteriorating patient; the RPN stays and works with the RN.

30. [CORE] A patient with suspected pulmonary TB must go to the imaging department. Which action is correct?

a. The patient wears a medical mask, and the transporting staff wear fit-tested N95 respirators.

b. The patient wears an N95 respirator, and staff wear no respiratory protection.

c. The patient goes without a mask, because the corridor is well ventilated and the trip is short.

d. The test is cancelled until the sputum culture result returns in several weeks.

Answer: a — Outside the AIIR, the patient wears a medical mask, and staff who transport or care for the patient wear fit-tested N95s (section 13.4, Airborne Precautions). An N95 on the patient (option b) is not the standard, and staff still need protection. Corridor ventilation (option c) does not protect others. Needed tests are not cancelled (option d); they are planned with precautions, and culture can take 2 to 8 weeks.

31. [CORE] A patient with small cell lung cancer has new confusion and a serum sodium of 121 mmol/L. The nurse recognizes this as most consistent with which condition?

a. Radiation pneumonitis

b. Superior vena cava syndrome

c. Hypercalcemia caused by the cancer's spread to bone tissue

d. Syndrome of inappropriate antidiuretic hormone (SIADH)

Answer: d — SIADH is a paraneoplastic syndrome linked to small cell lung cancer; it causes water retention and low sodium, which can lead to confusion (section 13.5, Recognizing and Diagnosing). Radiation pneumonitis (option a) causes cough, dyspnea and fever, not low sodium. Superior vena cava syndrome (option b) causes swelling of the face and neck. Hypercalcemia (option c) can cause confusion, but the laboratory finding here is low sodium, not high calcium.

32. [CORE] Which assessment finding is most consistent with a large right pleural effusion?

a. Hyperresonance to percussion and loud breath sounds over the right side

b. Dullness to percussion and reduced breath sounds at the right base

c. Coarse crackles that clear with coughing

d. A barking cough with inspiratory stridor

Answer: b — Fluid in the pleural space muffles sound, so percussion is dull and breath sounds are reduced or absent over it (section 13.6, Fluid Around the Lung). Hyperresonance (option a) suggests air, as in pneumothorax. Crackles that clear with coughing (option c) reflect secretions in the airways. Stridor and a barking cough (option d) point to upper airway narrowing.

33. [RN] A patient with metastatic NSCLC finished pembrolizumab 6 weeks ago. He calls the clinic with a new dry cough and breathlessness when climbing stairs. What is the RN's best response?

a. Tell him that immune-related effects stop once treatment ends, so this is likely a cold.

b. Advise him to try an over-the-counter cough suppressant and call back in a week if no better.

c. Arrange same-day assessment, because immune-related pneumonitis can follow the last dose.

d. Tell him to restart his next scheduled infusion early to control the cancer.

Answer: c — Immune-related adverse effects, including pneumonitis, can appear after the last dose of a checkpoint inhibitor; suspected pneumonitis needs prompt imaging and may need corticosteroids (section 13.5, Going Deeper box). Option a is incorrect, because these effects can appear after treatment ends. Option b delays assessment of a potentially serious condition. More immunotherapy (option d) could worsen pneumonitis; moderate pneumonitis means holding the drug.

34. [RN] During ultrasound-guided thoracentesis, about 1.3 L has been removed. The patient develops a persistent cough and says, "My chest feels tight." What should the RN do first?

a. Ask the practitioner to stop the drainage.

b. Encourage the patient to cough, because coughing helps the lung expand.

c. Increase the suction to finish draining the remaining fluid quickly.

d. Give a cough suppressant and continue the procedure.

Answer: a — The British Thoracic Society (BTS) Clinical Statement advises stopping drainage when the patient develops chest tightness, chest pain, a persistent cough or increasing breathlessness, even below 1.5 L, to reduce the risk of re-expansion pulmonary edema (section 13.6, Thoracentesis). Encouraging coughing and continuing (options b and d) ignores warning signs. Suction or vacuum drainage (option c) is not used, and faster drainage raises the risk.

35. [RN] A patient who takes warfarin for atrial fibrillation is starting rifampin for TB infection. What should the RN anticipate?

a. Rifampin will raise the INR, so the warfarin dose will likely be cut in half at once.

b. No change is needed, because rifampin does not interact with warfarin or other anticoagulants.

c. The warfarin should be stopped while rifampin is taken.

d. Rifampin will speed warfarin breakdown, so the INR may fall and needs closer monitoring.

Answer: d — Rifampin strongly induces the liver enzymes that break down warfarin, so the INR tends to fall and the warfarin dose often needs adjustment; the Standards advise monitoring early (within 1 to 2 weeks of starting) and again after rifampin stops (section 13.4, Medications box). Option a reverses the effect. Option b is false; rifampin has many drug interactions. Stopping warfarin (option c) would leave the patient unprotected from stroke and is not the standard approach.

References

Alvarez, G. G., Pease, C., & Menzies, D. (2022). Chapter 6: Tuberculosis preventive treatment in adults. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 6*(sup1), 77–86. https://doi.org/10.1080/24745332.2022.2039498

Asciak, R., Bedawi, E. O., Bhatnagar, R., Clive, A. O., Hassan, M., Lloyd, H., Reddy, R., Roberts, H., & Rahman, N. M. (2023). British Thoracic Society Clinical Statement on pleural procedures. *Thorax, 78*(Suppl 3), s43–s68. https://doi.org/10.1136/thorax-2022-219371

Batchelor, T. J. P., Rasburn, N. J., Abdelnour-Berchtold, E., Brunelli, A., Cerfolio, R. J., Gonzalez, M., Ljungqvist, O., Petersen, R. H., Popescu, W. M., Slinger, P. D., & Naidu, B. (2019). Guidelines for enhanced recovery after lung surgery: Recommendations of the Enhanced Recovery After Surgery (ERAS®) Society and the European Society of Thoracic Surgeons (ESTS). *European Journal of Cardio-Thoracic Surgery, 55*(1), 91–115. https://doi.org/10.1093/ejcts/ezy301

Behr, M. A., Grandjean Lapierre, S., Kunimoto, D. Y., Lee, R. S., Long, R., Sekirov, I., Soualhine, H., & Turenne, C. Y. (2022). Chapter 3: Diagnosis of tuberculosis disease and drug-resistant tuberculosis. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 6*(sup1), 33–48. https://doi.org/10.1080/24745332.2022.2035638

Billiet, C., Peeters, S., & De Ruysscher, D. (2014). Focus on treatment complications and optimal management: Radiation oncology. *Translational Lung Cancer Research, 3*(3), 187–191. https://doi.org/10.3978/j.issn.2218-6751.2014.06.08

Brenner, D. R., Gillis, J., Demers, A. A., Ellison, L. F., Ng, C., Zhang, S. X., Finley, C., Fitzgerald, N., Saint-Jacques, N., Shack, L., Turner, D., Urquhart, R., & Woods, R. R. (2026). Projected estimates of cancer in Canada in 2026. *Canadian Medical Association Journal, 198*(14), E526–E534. https://doi.org/10.1503/cmaj.252152

Brode, S. K., Dwilow, R., Kunimoto, D., Menzies, D., & Khan, F. A. (2022). Chapter 8: Drug-resistant tuberculosis. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 6*(sup1), 109–128. https://doi.org/10.1080/24745332.2022.2039499

Campbell, J. R., Pease, C., Daley, P., Pai, M., & Menzies, D. (2022). Chapter 4: Diagnosis of tuberculosis infection. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 6*(sup1), 49–65. https://doi.org/10.1080/24745332.2022.2036503

Canadian Cancer Society. (2026). *Lung and bronchus cancer statistics*. https://cancer.ca/en/cancer-information/cancer-types/lung/statistics

Canadian Institute for Health Information. (2025, February 20). *Hospitalizations in Canada remained stable in 2023–2024* [News release]. https://www.cihi.ca/en/news/hospitalizations-in-canada-remained-stable-in-2023-2024

Cancer Care Ontario. (2023). *Drug monograph: Osimertinib*. Ontario Health. https://www.cancercareontario.ca/system/files_force/osimertinib.pdf?download=1

College of Nurses of Ontario. (2026). *Nurse practitioner* [Practice standard]. https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41038_strdrnec.pdf

Fine, M. J., Auble, T. E., Yealy, D. M., Hanusa, B. H., Weissfeld, L. A., Singer, D. E., Coley, C. M., Marrie, T. J., & Kapoor, W. N. (1997). A prediction rule to identify low-risk patients with community-acquired pneumonia. *New England Journal of Medicine*, *336*(4), 243–250. https://doi.org/10.1056/NEJM199701233360402

First Nations Information Governance Centre. (n.d.). *The First Nations principles of OCAP®*. Retrieved October 24, 2026, from https://fnigc.ca/ocap-training/

Government of Nunavut. (2026, March 24). *Working together for a TB free Nunavut: GN and NTI reaffirm 2030 goal* [News release]. https://www.premier.gov.nu.ca/en/working-together-tb-free-nunavut-gn-and-nti-reaffirm-2030-goal

Health Canada. (2018). *Radon: Is it in your home? Information for health professionals*. https://www.canada.ca/content/dam/hc-sc/documents/services/health/publications/radon/Radon-Is-It-in-Your-Home-PROF-EN.pdf

Health Canada. (2024). *Justifications and policy rationales for radon action*. https://www.canada.ca/en/health-canada/services/health-risks-safety/radiation/radon/action-guides/justification-policy-rationales.html

Health Canada. (2026). *List of drugs for an urgent public health need*. https://www.canada.ca/en/health-canada/services/drugs-health-products/access-drugs-exceptional-circumstances/list-drugs-urgent-public-health-need.html

Indigenous Services Canada. (2018, December 10). *Inuit tuberculosis elimination framework released* [News release]. https://www.canada.ca/en/indigenous-services-canada/news/2018/12/inuit-tuberculosis-elimination-framework-released.html

Infectious Diseases Society of America. (n.d.). *CAP clinical pathway*. https://www.idsociety.org/globalassets/idsa/practice-guidelines/community-acquired-pneumonia-in-adults/cap-clinical-pathway-final-online.pdf

Inuit Tapiriit Kanatami. (2019, March 24). *Progress update on TB elimination*. https://itk.ca/progress-update-on-tb-elimination/

Inuit Tapiriit Kanatami. (2025, March 24). *ITK calls for renewed focus on TB elimination in Inuit Nunangat*. https://itk.ca/itk-calls-for-renewed-focus-on-tb-elimination-in-inuit-nunangat/

Jain, S., Self, W. H., Wunderink, R. G., Fakhran, S., Balk, R., Bramley, A. M., Reed, C., Grijalva, C. G., Anderson, E. J., Courtney, D. M., Chappell, J. D., Qi, C., Hart, E. M., Carroll, F., Trabue, C., Donnelly, H. K., Williams, D. J., Zhu, Y., Arnold, S. R., … Finelli, L. (2015). Community-acquired pneumonia requiring hospitalization among U.S. adults. *New England Journal of Medicine*, *373*(5), 415–427. https://doi.org/10.1056/NEJMoa1500245

Johnston, B. L., Ogunremi, T., Defalco, K., Savard, N., & Smith, S. W. (2022). Chapter 14: Prevention and control of tuberculosis transmission in healthcare settings. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 6*(sup1), 205–228. https://doi.org/10.1080/24745332.2022.2043677

Johnston, J. C., Cooper, R., & Menzies, D. (2022). Chapter 5: Treatment of tuberculosis disease. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 6*(sup1), 66–76. https://doi.org/10.1080/24745332.2022.2036504

Kalil, A. C., Metersky, M. L., Klompas, M., Muscedere, J., Sweeney, D. A., Palmer, L. B., Napolitano, L. M., O'Grady, N. P., Bartlett, J. G., Carratalà, J., El Solh, A. A., Ewig, S., Fey, P. D., File, T. M., Jr., Restrepo, M. I., Roberts, J. A., Waterer, G. W., Cruse, P., Knight, S. L., & Brozek, J. L. (2016). Management of adults with hospital-acquired and ventilator-associated pneumonia: 2016 clinical practice guidelines by the Infectious Diseases Society of America and the American Thoracic Society. *Clinical Infectious Diseases*, *63*(5), e61–e111. https://doi.org/10.1093/cid/ciw353

Klompas, M., Branson, R., Cawcutt, K., Crist, M., Eichenwald, E. C., Greene, L. R., Lee, G., Maragakis, L. L., Powell, K., Priebe, G. P., Speck, K., Yokoe, D. S., & Berenholtz, S. M. (2022). Strategies to prevent ventilator-associated pneumonia, ventilator-associated events, and nonventilator hospital-acquired pneumonia in acute-care hospitals: 2022 update. *Infection Control & Hospital Epidemiology*, *43*(6), 687–713. https://doi.org/10.1017/ice.2022.88

Lim, W. S., van der Eerden, M. M., Laing, R., Boersma, W. G., Karalus, N., Town, G. I., Lewis, S. A., & Macfarlane, J. T. (2003). Defining community acquired pneumonia severity on presentation to hospital: An international derivation and validation study. *Thorax*, *58*(5), 377–382. https://doi.org/10.1136/thorax.58.5.377

Long, R., Divangahi, M., & Schwartzman, K. (2022). Chapter 2: Transmission and pathogenesis of tuberculosis. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 6*(sup1), 22–32. https://doi.org/10.1080/24745332.2022.2035540

Mandell, L. A., Marrie, T. J., Grossman, R. F., Chow, A. W., Hyland, R. H., & the Canadian CAP Working Group. (2000). Summary of Canadian guidelines for the initial management of community-acquired pneumonia: An evidence-based update by the Canadian Infectious Disease Society and the Canadian Thoracic Society. *Canadian Journal of Infectious Diseases*, *11*(5), 237–248. https://doi.org/10.1155/2000/457147

Merck Canada. (2019). *Keytruda (pembrolizumab) product monograph*. https://pdf.hres.ca/dpd_pm/00052759.PDF

Merck Canada. (2026). *Keytruda (pembrolizumab) product monograph*. https://www.merck.ca/en/wp-content/uploads/sites/20/2021/04/KEYTRUDA-PM_E.pdf

Metlay, J. P., Waterer, G. W., Long, A. C., Anzueto, A., Brozek, J., Crothers, K., Cooley, L. A., Dean, N. C., Fine, M. J., Flanders, S. A., Griffin, M. R., Metersky, M. L., Musher, D. M., Restrepo, M. I., & Whitney, C. G. (2019). Diagnosis and treatment of adults with community-acquired pneumonia: An official clinical practice guideline of the American Thoracic Society and Infectious Diseases Society of America. *American Journal of Respiratory and Critical Care Medicine*, *200*(7), e45–e67. https://doi.org/10.1164/rccm.201908-1581ST

Mitchell, B. G., Russo, P. L., Cheng, A. C., Stewardson, A. J., Rosebrock, H., Curtis, S. J., Robinson, S., & Kiernan, M. (2019). Strategies to reduce non-ventilator-associated hospital-acquired pneumonia: A systematic review. *Infection, Disease & Health*, *24*(4), 229–239. https://doi.org/10.1016/j.idh.2019.06.002

Mounchili, A., Perera, R., Lee, R. S., Njoo, H., & Brooks, J. (2022). Chapter 1: Epidemiology of tuberculosis in Canada. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 6*(sup1), 8–21. https://doi.org/10.1080/24745332.2022.2033062

National Advisory Committee on Immunization. (2024a). *Recommendations on the use of pneumococcal vaccines in adults, including PNEU-C-21*. Public Health Agency of Canada. https://www.canada.ca/en/public-health/services/publications/vaccines-immunization/national-advisory-committee-immunization-statement-recommendations-use-pneumococcal-vaccines-adults-pneu-c-21.html

National Advisory Committee on Immunization. (2024b). *Statement on the prevention of respiratory syncytial virus disease in older adults*. Public Health Agency of Canada. https://www.canada.ca/en/public-health/services/publications/vaccines-immunization/national-advisory-committee-immunization-statement-prevention-rsv-disease-older-adults.html

National Advisory Committee on Immunization. (2025). *Statement on seasonal influenza vaccines for 2025–2026*. Public Health Agency of Canada. https://www.canada.ca/en/public-health/services/publications/vaccines-immunization/national-advisory-committee-immunization-statement-seasonal-influenza-vaccines-2025-2026.html

National Advisory Committee on Immunization. (2026a). *Summary of NACI statement of April 10, 2026: Updated guidance on respiratory syncytial virus vaccines for older adults and adults at high risk of severe RSV disease*. Public Health Agency of Canada. https://www.canada.ca/en/public-health/services/publications/vaccines-immunization/national-advisory-committee-immunization-summary-updated-guidance-respiratory-syncytial-virus-vaccines-older-adults-high-risk-severe-rsv-disease.html

National Advisory Committee on Immunization. (2026b). *Summary of NACI statement of June 2026: Guidance on the use of COVID-19 vaccines starting fall 2026*. Public Health Agency of Canada. https://www.canada.ca/en/public-health/services/publications/vaccines-immunization/national-advisory-committee-immunization-summary-guidance-covid-19-vaccines-starting-fall-2026.html

Ontario Health. (2024). *Recommendations for antiviral therapy for adults with mild to moderate COVID-19*. https://ontariohealth.ca/content/dam/ontariohealth/documents/recommendations-for-antiviral-therapy-for-adults-with-mild-to-moderate-covid-19.pdf

Ontario Health. (2025). *Recommendations for antiviral therapy of seasonal influenza*. https://ontariohealth.ca/content/dam/ontariohealth/documents/recommendations-antiviral-therapy-seasonal-influenza.pdf

Ontario Medical Association. (2025). *Pathways to appropriate penicillin allergy (de)labelling: Support tool for primary care physicians* (Version 2). https://www.oma.org/siteassets/oma/media/pagetree/pps/running/news/pathways-to-appropriate-penicillin-allergy-delabelling.pdf

Ontario Ministry of Health. (2025). *Tuberculosis prevention and control protocol, 2025*. https://www.ontario.ca/files/2025-01/moh-tuberculosis-prevention-control-protocol-en-2025-01-06.pdf

Ontario Ministry of Health. (2026a). *Executive officer notice: Administration of publicly funded influenza and COVID-19 vaccines in Ontario pharmacies*. https://www.ontario.ca/files/2026-09/moh-executive-officer-notice-en-2026-09-25.pdf

Ontario Ministry of Health. (2026b). *Health care provider fact sheet: Pneumococcal conjugate vaccines for adults aged 18 years and older*. https://www.ontario.ca/files/2026-07/moh-hcp-fact-sheet-pneumococcal-vaccine-18-and-older-en-2026-07-31.pdf

Ontario Ministry of Health. (2026c). *Respiratory syncytial virus*. Retrieved October 25, 2026, from https://www.ontario.ca/page/respiratory-syncytial-virus

PDQ Adult Treatment Editorial Board. (2025a). *Non-small cell lung cancer treatment (PDQ®): Health professional version*. National Cancer Institute. https://www.cancer.gov/types/lung/hp/non-small-cell-lung-treatment-pdq

PDQ Adult Treatment Editorial Board. (2025b). *Small cell lung cancer treatment (PDQ®): Health professional version*. National Cancer Institute. https://www.cancer.gov/types/lung/hp/small-cell-lung-treatment-pdq

Pfizer Canada ULC. (2026). *PAXLOVID (nirmatrelvir tablets; ritonavir tablets), co-packaged* [Product monograph]. https://pdf.hres.ca/dpd_pm/00085971.PDF

Prescott, H. C., Antonelli, M., Alhazzani, W., Møller, M. H., Alshamsi, F., Azevedo, L. C. P., Belley-Cote, E., De Waele, J., Derde, L., Dionne, J. C., Evans, L., Gershengorn, H. B., Hodgson, C. L., Honarmand, K., Kesecioglu, J., McIntyre, L., Mer, M., Nunnally, M. E., Oczkowski, S. J. W., … Coopersmith, C. M. (2026). Surviving Sepsis Campaign: International guidelines for management of sepsis and septic shock 2026. *Intensive Care Medicine*, *52*(5), 863–936. https://doi.org/10.1007/s00134-026-08361-1

Provincial Infectious Diseases Advisory Committee. (n.d.). *Clinical syndromes/conditions with required level of precautions* [Appendix N excerpt]. Public Health Ontario. https://www.publichealthontario.ca/-/media/Documents/R/2012/rpap-clinical-syndromes.pdf

Public Health Agency of Canada. (2025). *Tuberculosis disease in Canada, 2023* [Infographic]. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/tuberculosis-disease-2023-infographic.html

Public Health Agency of Canada. (2026a). *Respiratory syncytial virus (RSV): For health professionals*. https://www.canada.ca/en/public-health/services/diseases/respiratory-syncytial-virus-rsv/health-professionals.html

Public Health Agency of Canada. (2026b). *Tuberculosis disease surveillance: TB trends* [Data dashboard]. Health Infobase. https://health-infobase.canada.ca/tuberculosis/epidemiology-report.html

Public Health Ontario. (2023). *Interim infection prevention and control measures based on respiratory virus transmission risk in health care settings* (1st rev.). Ontario Agency for Health Protection and Promotion. https://www.publichealthgreybruce.on.ca/Portals/0/Topics/IPAC/Interim%20Infection%20Prevention%20and%20Control%20Measures%20Based%20on%20Respiratory%20Virus.pdf

Quinn, K. L., Razak, F., & Cheung, A. M. (2023). Diagnosing post-COVID-19 condition (long COVID) in adults. *CMAJ*, *195*(2), E78–E79. https://doi.org/10.1503/cmaj.220818

Rea, E., Huard, J., & Lee, R. (2022). Chapter 11: Tuberculosis contact investigation and outbreak management. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 6*(sup1), 167–183. https://doi.org/10.1080/24745332.2022.2037909

Roberts, M. E., Rahman, N. M., Maskell, N. A., Bibby, A. C., Blyth, K. G., Corcoran, J. P., Edey, A., Evison, M., de Fonseka, D., Hallifax, R., Harden, S., Lawrie, I., Lim, E., McCracken, D., Mercer, R., Mishra, E. K., Nicholson, A. G., Noorzad, F., Opstad, K. S., … Walker, S. (2023). British Thoracic Society Guideline for pleural disease. *Thorax, 78*(11), 1143–1156. https://doi.org/10.1136/thorax-2023-220304

Sinai Health. (n.d.). *Community-acquired pneumonia* [Antimicrobial stewardship clinical summary]. Retrieved October 25, 2026, from https://www.sinaihealth.ca/areas-of-care/antimicrobial-stewardship/clinical-summaries/community-acquired-pneumonia

Son, Y. G., Shin, J., & Ryu, H. G. (2017). Pneumonitis and pneumonia after aspiration. *Journal of Dental Anesthesia and Pain Medicine*, *17*(1), 1–12. https://doi.org/10.17245/jdapm.2017.17.1.1

Valeant Canada. (2019). *Rofact (rifampin capsules): Consumer information*. Health Canada Drug and Health Product Portal. https://dhpp.hpfb-dgpsa.ca/dhpp/resource/2863/consumer-information

Windsor-Essex County Health Unit. (2024). *Guide to tuberculosis screening and management: Health care providers*. https://wechu.org/sites/default/files/HCP_TB_Guide.pdf

14 Obstructive and Restrictive Lung Disease

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Distinguish obstructive from restrictive lung disease and interpret basic spirometry results.
2. Explain the pathophysiology of asthma, COPD, bronchiectasis, interstitial lung disease and obstructive sleep apnea, and link it to manifestations.
3. Recognize and respond to asthma and COPD exacerbations, including signs of life-threatening deterioration.
4. Give inhaled medications safely and teach inhaler technique for each device type.
5. Support long-term self-management: action plans, pulmonary rehabilitation, vaccination and home oxygen.
6. Provide evidence-based smoking and vaping cessation support in hospital and the community.
7. Address equity in chronic lung disease, including Indigenous, rural and occupational exposures and wildfire smoke.
8. Distinguish RN and RPN roles in respiratory care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4	Clinician; Scholar	Foundations of Practice
5, 6, 7	Educator; Advocate; Collaborator	Foundations of Practice; Collaborative Practice; Ethical Practice
8	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

Asthma and chronic obstructive pulmonary disease (COPD) are long-term lung diseases that nurses meet in almost every setting. National surveillance data from the Canadian Chronic Disease Surveillance System (CCDSS) counted about 3.8 million Canadians aged 1 year and older living with diagnosed asthma in 2011–2012, and about 2.0 million Canadians aged 35 and older living with COPD (Public Health Agency of Canada [PHAC], 2018). In hospital, COPD and bronchitis were the second most common reason for a stay in Canada in 2023–2024, after giving birth. They accounted for 76,968 hospitalizations, with an average acute stay of 7.1 days (Canadian Institute for Health Information [CIHI], 2025).

This chapter is the book's home for diseases that block airflow or limit lung expansion. Section 14.1 compares obstructive and restrictive patterns and explains spirometry. Section 14.2 covers asthma, and section 14.3 covers inhaled medications and devices. Section 14.4 covers COPD, section 14.5 smoking and vaping cessation, and section 14.6 bronchiectasis, interstitial lung disease and sleep apnea. Related topics live in other chapters:

- acid–base balance and blood gases (Chapter 3, section 3.7);
- the palliative approach and dyspnea management (Chapter 10);
- respiratory assessment, pulse oximetry and oxygen therapy (Chapter 12);
- pneumonia, respiratory viruses and lung cancer (Chapter 13);
- acute respiratory failure and ventilation (Chapter 15).

14.1 Obstructive and Restrictive Patterns

Two Ways Breathing Gets Harder

Chronic lung diseases usually make breathing harder in one of two ways. In **obstructive lung disease**, the airways are narrowed by inflammation, tightened airway muscle, mucus or loss of the elastic tissue that holds small airways open. Air gets in but has trouble getting out, so breathing out takes longer and some air stays trapped with each breath. The trapped air over-inflates the chest and makes breathing more work. Asthma, COPD and bronchiectasis are obstructive diseases.

In **restrictive lung disease**, the lungs cannot expand fully, so lung volumes are small. The lung tissue itself may be stiff and scarred, as in interstitial lung disease (section 14.6), or the cause may lie outside the lungs, in a stiff chest wall or weak breathing muscles. Breaths tend to be shallow and fast. A person can have both patterns at once. Table 14.1 compares them.

Table 14.1 Obstructive and restrictive patterns compared (Stanojevic et al., 2022; Yang et al., 2021; original wording)

Feature	Obstructive	Restrictive
Main problem	Narrowed airways slow the flow of air out of the lungs; air is trapped	Stiff lungs or a limited chest wall keep the lungs from filling; volumes are small
Examples	Asthma, COPD, bronchiectasis	Interstitial lung disease, including idiopathic pulmonary fibrosis; chest wall or breathing muscle problems
FEV1/FVC ratio	Reduced (below the lower limit of normal)	Normal or high
FVC and lung volumes	FVC normal or reduced; trapped air can raise total lung volume	FVC reduced; total lung capacity below normal confirms restriction
Typical findings	Long, slow breath out; wheeze; over-inflated chest	Rapid, shallow breathing; reduced chest expansion; crackles in some diseases
Main treatments in general	Bronchodilators, inhaled anti-inflammatory medicines, avoiding triggers, smoking cessation, pulmonary rehabilitation	Treating the cause where possible, oxygen when needed, pulmonary rehabilitation (section 14.6)

Spirometry Basics

Spirometry measures how much air a person can blow out after filling the lungs completely, and how quickly (Figure 14.1). The patient takes the deepest possible breath, then blows out as hard and fast as possible and keeps going until no more air comes out. Three results matter most:

- **Forced vital capacity (FVC):** the total volume of air blown out in that forced breath.
- **Forced expiratory volume in 1 second (FEV1):** the volume blown out in the first second.
- **FEV1/FVC ratio:** the share of the FVC that leaves in the first second.

Results are compared with predicted values for the person's age, sex and height, so height is measured accurately (Coates et al., 2013). The international standard discourages fixed race-based adjustments (Stanojevic et al., 2022).

Healthy lungs empty most of their air in the first second. A reduced FEV1/FVC ratio means the air leaves slowly, which is the mark of airflow obstruction. The European Respiratory Society and American Thoracic Society (ERS/ATS) standard defines obstruction as a ratio below the **lower limit of normal (LLN)**, the value below which only 5% of healthy people fall; some COPD guidance uses a fixed cut-off of 0.70 instead (Stanojevic et al., 2022; section 14.4). In restriction, FEV1 and FVC both fall, so the ratio stays normal or rises. A low FVC on its own does not prove restriction, though. Confirming it requires measuring **lung volumes**, especially total lung capacity (Stanojevic et al., 2022).

Spirometry is often repeated after an inhaled bronchodilator. In the Canadian Thoracic Society (CTS) asthma guideline, an increase in FEV1 of at least 12% and at least 200 mL after a bronchodilator, or after a course of controller medication, shows **reversibility** and supports a diagnosis of asthma in people aged 6 and older (Yang et al., 2021; Coates et al., 2013). Section 14.4 explains how

post-bronchodilator results confirm COPD. A **diffusing capacity** test uses a tiny amount of carbon monoxide to estimate how well gas crosses from the alveoli into the blood; it is low in emphysema and interstitial lung disease (Stanojevic et al., 2022).

Results depend on the patient's effort and cooperation. The nurse explains the test, encourages full effort and asks about recent medication use. Bronchodilators are held beforehand only as the laboratory or prescriber instructs; they may be continued when the test is meant to show how well current treatment works (Coates et al., 2013). Canadian guidance advises no smoking for 1 hour, no large meal for 2 hours and no heavy exercise for 30 minutes before testing, and loose clothing. The nurse reports recent eye, chest or abdominal surgery, a recent heart attack, coughing up blood or confusion, which can make testing unsafe or unreliable (Coates et al., 2013).

Figure 14.1 The mouthpiece and flow sensor of a hospital pulmonary function testing system, used for spirometry and related breathing tests. (credit: “Device for Spirometry or Body Plethysmography 02” by Joe Mabel/Wikimedia Commons, CC BY-SA 3.0)

Figure 14.2 A peak flow meter. The patient blows into it in a short, sharp blow, and a marker moves along the scale to show the peak expiratory flow.

Peak expiratory flow (PEF) is the fastest speed of air in a short, sharp blow into a hand-held meter (Figure 14.2). It is less precise than spirometry but useful for tracking asthma at home against the person's own best value, and for judging the severity of an exacerbation (section 14.2). Readings should be compared on the same meter (Yang et al., 2021).

14.2 Asthma

What Happens in Asthma

Asthma is a chronic airway disease, usually driven by ongoing inflammation, in which wheeze, breathlessness, chest tightness and cough come and go and change in intensity over time (Global Initiative for Asthma [GINA], 2026). During a flare, three changes narrow the airways: the smooth muscle around them tightens (**bronchoconstriction**), the inflamed walls swell and thicken, and mucus builds up. The airways are also overly sensitive. **Airway hyperresponsiveness** means they narrow quickly and strongly in response to stimuli that barely affect other people. Because the narrowing rises and falls, airflow limitation is variable, and lung function may be normal between episodes. After many years of asthma, some narrowing can become permanent (GINA, 2026).

Triggers differ from person to person. Common ones include (GINA, 2026; Yang et al., 2021):

- viral respiratory infections;
- allergens, such as house dust mites, animals, pollens and cockroaches;

- tobacco smoke, vaping (including cannabis) and air pollution;
- exercise, cold air, strong emotion and laughter;
- irritants or allergens at work;
- medicines: beta-blockers, and in some people acetylsalicylic acid (ASA) and other nonsteroidal anti-inflammatory drugs (NSAIDs).

Wildfire smoke is a growing seasonal trigger in Canada (Figure 14.3). Its fine particles (PM2.5) are its main health risk, and asthma attacks are among its more serious effects (Health Canada, 2026b). The CTS estimates that about 36% of asthma that starts in adulthood is probably or possibly related to work, so every adult with asthma needs an occupational history (Yang et al., 2021). Smoking and vaping raise the risk of exacerbations; section 14.5 covers cessation.

Who Has Asthma in Canada

In CCDSS data, the age-standardized prevalence of diagnosed asthma among Canadians aged 1 and older rose from 6.5% in 2000–2001 to 10.8% in 2011–2012. Over the same years, the age-standardized rate of new diagnoses fell by 44.8% (PHAC, 2018). In childhood, prevalence was higher in males; from the 25–29 age group onward, it was higher in females (PHAC, 2018).

Risk is not shared equally. People in rural and remote areas, outdoor workers, and people with lower incomes or insecure housing are more exposed to wildfire smoke or less able to limit their exposure (Health Canada, 2026b). Major psychological or socioeconomic problems also raise a person's risk of exacerbations (GINA, 2026). These are structural causes, rooted in housing, work and income, not personal failings (Chapter 2).



Figure 14.3 Smoke from the June 2023 wildfires in Quebec over New York City. Wildfire smoke can travel far from the fires and trigger asthma attacks. (credit: “Wildfire Smoke” by Marc A. Hermann/Metropolitan Transportation Authority, CC BY 2.0)

Recognizing and Diagnosing Asthma

Typical symptoms are wheeze, cough, chest tightness and breathlessness that vary over time and often follow a trigger. Night-time symptoms on 1 night a week or more mean that asthma is not well controlled (Yang et al., 2021). On examination between flares, the chest may sound normal.

Symptoms alone are not enough for a diagnosis. The CTS requires a compatible history plus objective proof of variable or reversible airflow obstruction (Yang et al., 2021). Spirometry is the preferred test: a reduced FEV1/FVC ratio together with the FEV1 rise described in section 14.1. When spirometry does not settle the question, other tests can (Yang et al., 2021):

- **PEF variability:** a rise in PEF of at least 20% (and at least 60 L/min) after a bronchodilator or controller, or a large difference between readings over the day.
- **Methacholine challenge:** the patient inhales increasing amounts of methacholine, a substance that narrows sensitive airways. Airways that react at a low concentration confirm hyperresponsiveness.
- **Exercise challenge:** a fall in FEV1 after exercise.

Normal spirometry on one day does not rule out asthma (Yang et al., 2021). A confirmed diagnosis matters because treatment is long term.

Asthma Control and Long-Term Treatment

Asthma control describes how well treatment keeps symptoms and flare-ups away. The CTS considers asthma well controlled only when all these are true (Yang et al., 2021):

- symptoms during the day on 2 days a week or fewer, and at night less than once a week and mild;

- normal physical activity, with no time lost from work or school;
- only mild, infrequent exacerbations;
- reliever needed 2 times a week or fewer;
- FEV1 or PEF at 90% or more of the person's best, with little day-to-day PEF variation.

For adolescents and adults, the CTS 2021 guideline builds treatment on inhaled corticosteroids (ICS), the main anti-inflammatory controller (Yang et al., 2021):

- **Mild asthma that is poorly controlled on an as-needed short-acting beta2-agonist (SABA):** start a daily ICS with an as-needed SABA. For people aged 12 and older whose adherence to a daily ICS is poor, as-needed budesonide–formoterol is recommended instead.
- **Mild asthma that is well controlled on an as-needed SABA:** people at higher risk of exacerbations move to a daily ICS or as-needed budesonide–formoterol. People at lower risk may continue the SABA alone, or choose either option for better control.
- **After any severe exacerbation** (one needing systemic corticosteroids, an emergency visit or a hospital stay) in a person using a SABA alone, a controller is started.
- **Asthma not controlled on a low-dose ICS despite good adherence:** a combined ICS and long-acting beta2-agonist (ICS–LABA) inhaler is first choice. A LABA is never used alone in asthma.
- **Poor control on an ICS–LABA:** switching to budesonide–formoterol as **maintenance and reliever therapy (MART)** is an option. The same inhaler is taken daily and also for symptoms.
- **Still not controlled:** adding a leukotriene receptor antagonist (LTRA), such as montelukast, or the long-acting muscarinic antagonist tiotropium is considered. GINA notes that montelukast has been linked to a risk of serious mental health effects (GINA, 2026).

The CTS is clear that a SABA relieves symptoms but does not treat the disease. Using a reliever more than twice a week signals poor control, and using more than two SABA inhalers a year should prompt reassessment (Yang et al., 2021). The GINA 2026 strategy goes further: asthma should not be treated with a SABA alone, because SABA-only treatment is linked to more exacerbations and a higher risk of death (GINA, 2026). In practice, the nurse asks every patient how often they use their reliever and reports rising use.

People whose asthma stays uncontrolled on a medium-dose ICS plus a second controller are referred to a specialist for assessment of **severe asthma** (Yang et al., 2021). In September 2026, the CTS released a guideline on managing severe asthma in children, adolescents and adults (Canadian Thoracic Society [CTS], 2026). Specialist treatment may include **biologics**: injected antibodies that block specific steps in allergic or eosinophilic inflammation, such as immunoglobulin E (IgE) or interleukin-5 (GINA, 2026). Before treatment is stepped up at any level, the clinician confirms adherence and inhaler technique and checks that the inhaler is not empty (Yang et al., 2021; section 14.3).

Every person with asthma should have a **written action plan**, because plans reduce exacerbations. A plan may be based on symptoms or on PEF readings (Yang et al., 2021). It tells the person how to recognize worsening asthma, how to step up treatment, and when to seek urgent care.

MEDICATIONS

Bronchodilators and Inhaled Corticosteroids

- **Short-acting beta2-agonist (SABA):** salbutamol (Ventolin HFA) relaxes airway muscle within minutes. Watch for tremor, fast heart rate and palpitations. Low blood potassium is rare, but during repeated treatments in hospital the nurse follows potassium results as ordered (GlaxoSmithKline, 2025).
- **Long-acting beta2-agonist (LABA):** formoterol, given with budesonide in one inhaler (Symbicort Turbuhaler). In asthma, a LABA is always paired with an ICS (Yang et al., 2021).
- **Inhaled corticosteroid (ICS):** fluticasone propionate (Flovent HFA) and budesonide reduce airway inflammation over days to weeks. They can cause thrush in the mouth and hoarseness. The patient rinses the mouth with water and spits after each use; denture wearers also clean their dentures (AstraZeneca Canada, 2021).
- **Muscarinic antagonists:** short-acting ipratropium and long-acting tiotropium (Spiriva Respimat) block the nerve signals that tighten airway muscle. They can cause dry mouth and trouble passing urine. The mist must be kept out of the eyes, because it

> can worsen narrow-angle glaucoma; eye pain, blurred vision or halos need prompt care (Boehringer Ingelheim, 2019; JAMP Pharma, 2023).
> - Tremor or a racing heart after a reliever is common; chest tightness or wheeze that worsens right after a dose may be paradoxical bronchospasm and needs immediate care (GlaxoSmithKline, 2025).

Asthma Exacerbations in Hospital

An **asthma exacerbation** is a flare in which symptoms and lung function worsen beyond the person's usual day-to-day variation. The CTS has no current guideline on hospital management of adult exacerbations, so this section draws on GINA and the British guideline.

The nurse judges severity from how the patient looks and talks and from objective measures. GINA advises assessing breathlessness, accessory muscle use, pulse, oxygen saturation (SpO2) and PEF while treatment is started (GINA, 2026). The British guideline describes two levels that need urgent action (British Thoracic Society [BTS] & Scottish Intercollegiate Guidelines Network [SIGN], 2019):

- **Acute severe asthma:** any one of these: cannot finish sentences in one breath; respiratory rate 25 breaths/min or more; heart rate 110 beats/min or more; PEF 33% to 50% of best or predicted.
- **Life-threatening asthma:** any one of these: PEF below 33%; SpO2 below 92%; a **silent chest**, in which so little air moves that wheeze can no longer be heard; cyanosis (a blue or grey tinge of the lips, tongue and nail beds that can be harder to see on darker skin; Chapter 12); poor respiratory effort; an abnormal heart rhythm or low blood pressure; exhaustion or a change in level of consciousness.

GINA advises transfer to intensive care if the patient is drowsy, confused or has a silent chest (GINA, 2026). Patients with severe asthma may not look distressed (BTS & SIGN, 2019). Early in an attack, fast breathing blows off carbon dioxide, so the partial pressure of carbon dioxide in arterial blood (PaCO2) is usually low. A "normal" PaCO2 (about 35 to 45 mm Hg) in a breathless patient with asthma is a life-threatening sign, because it means the patient is tiring; a rising PaCO2 signals near-fatal asthma (BTS & SIGN, 2019; Chapter 3, section 3.7). Pulse oximetry may overestimate saturation in people with darker skin (GINA, 2026; Chapter 12).

Nursing care follows the orders and the unit's protocol:

- Sit the patient upright, stay close, and give oxygen to the target range ordered. GINA suggests a target of 92% to 95% in acute asthma (GINA, 2026), while the British guideline uses 94% to 98% (BTS & SIGN, 2019); Chapter 12 explains target ranges.
- Give the inhaled SABA, repeated at short intervals, by metered-dose inhaler with a spacer or by nebulizer. Ipratropium is added for moderate or severe exacerbations, or when the first SABA doses do not help enough (GINA, 2026; BTS & SIGN, 2019).
- Give systemic corticosteroids early, as ordered (GINA, 2026).
- For life-threatening features or asthma that responds poorly, intravenous magnesium sulfate may be ordered (BTS & SIGN, 2019). A single infusion reduced hospital admissions in adults who had not responded well to oxygen, nebulized SABA and corticosteroids (Kew et al., 2014). The nurse watches for flushing and low blood pressure.
- Avoid sedatives of any kind (BTS & SIGN, 2019).

Response is reassessed often: respiratory rate, heart rate, SpO2, accessory muscle use, air entry, ability to speak and PEF. Guidance suggests repeating PEF 15 to 30 minutes after treatment starts and reviewing response within an hour (BTS & SIGN, 2019; GINA, 2026). Worsening or life-threatening features call for an immediate rapid response or critical care call (Chapter 6). Patients who tire, become drowsy or show rising PaCO2 need intensive care; ventilation is covered in Chapter 15.

Before discharge, the patient starts or steps up an ICS-containing controller (GINA, 2026). The nurse checks inhaler technique with the patient's own device and reviews the written action plan. Early follow-up matters: GINA advises a review within 1 week after an exacerbation (GINA, 2026), and the British guideline advises primary care follow-up within 2 working days of discharge (BTS & SIGN, 2019).

CLINICAL JUDGMENT

The Quiet Chest

Daniel Okafor, 24, came to the emergency department with an asthma exacerbation after a cold. He was admitted to a medical unit after several bronchodilator treatments. At 0200, the nurse notes that his loud wheeze has faded and he is lying back with his eyes closed. A family member says, "He's finally settling down."

- **Recognize cues:** Daniel answers in single words and is hard to rouse. His respiratory rate has dropped from 32 to 20 breaths/min, his SpO2 is 89% on the ordered oxygen, and air entry is faint on both sides. He has not received any sedative.
- **Analyze cues:** A quieter chest with faint air entry means less air is moving, not that the airways have opened. A slower rate and drowsiness in a patient who was working hard suggest exhaustion and rising carbon dioxide.
- **Prioritize hypotheses:** Life-threatening asthma with fatigue and impending respiratory failure ranks first. Improvement does not fit falling SpO2 and drowsiness.
- **Generate solutions:** Get help at once, do not leave Daniel alone or lie him flat, keep him upright, keep giving oxygen to target, have bronchodilator treatment continued as ordered, and prepare for blood gases and transfer.
- **Take action:** The nurse stays with Daniel, presses the call bell, calls the rapid response team and gives an SBAR (Situation, Background, Assessment, Recommendation) report (Chapter 6).
- **Evaluate outcomes:** The nurse reassesses responsiveness, respiratory effort and SpO2 every few minutes until the team arrives. A blood gas shows a rising PaCO2, which confirms fatigue. The team transfers Daniel to the intensive care unit, where his breathing can be supported (Chapter 15).

14.3 Inhaled Medications and Devices

Relievers and Controllers

Inhaled medicines go straight to the airways, so they work quickly with small doses and fewer whole-body effects. Patients find it easier to manage their treatment when they understand two plain-language groups. A **reliever** opens narrowed airways within minutes and is used when symptoms appear. A **controller** is used every day to calm airway inflammation or keep airways open for many hours, which prevents symptoms and flare-ups. One medicine can do both jobs: in an **ICS–formoterol reliever**, each dose of budesonide–formoterol both relieves symptoms and treats inflammation (Yang et al., 2021).

The main classes, with Canadian examples, are:

- **Short-acting beta2-agonist (SABA):** salbutamol (Ventolin HFA), the usual reliever.
- **Short-acting muscarinic antagonist (SAMA):** ipratropium, added to a SABA in more severe exacerbations and used in COPD.
- **Long-acting beta2-agonist (LABA):** formoterol and others; in asthma, always combined with an ICS.
- **Long-acting muscarinic antagonist (LAMA):** tiotropium (Spiriva Respimat), mainly used in COPD (section 14.4) and as an add-on in asthma.
- **Inhaled corticosteroid (ICS):** fluticasone propionate (Flovent HFA) and budesonide (Pulmicort Turbuhaler), the main controllers in asthma.
- **Combination inhalers:** an ICS–LABA such as budesonide–formoterol (Symbicort Turbuhaler); LAMA–LABA and triple combinations are used in COPD (section 14.4).

A medicine works only if it reaches the lungs. The CTS reports that up to 70% of patients use their inhaler incorrectly, and that poor technique is linked to poor control (Yang et al., 2021).

Devices and Technique

A **pressurized metered-dose inhaler (pMDI)** releases a measured puff of medicine in a propellant spray. The patient must press the canister just after starting a slow, deep breath, which many people find hard to coordinate. A new pMDI, or one unused for several days, is first primed by spraying into the air as the leaflet directs (GlaxoSmithKline, 2025). A **spacer**, or valved holding chamber, is a tube that attaches to the pMDI and holds the puff so the patient can breathe it in without precise timing; it also cuts down the

medicine left in the mouth and throat. The CTS recommends a valved holding chamber for people of all ages who are prescribed a pMDI (Yang et al., 2021), and a spacer can also increase the amount of medicine delivered (Gupta et al., 2023).

A **dry powder inhaler (DPI)** holds the medicine as a fine powder. There is no propellant: the patient's own fast, deep, forceful breath pulls the powder out, so the patient must never breathe out into the device. The dose is small, so the patient may not taste or feel the powder; this is expected (AstraZeneca Canada, 2021). The Turbuhaler is one example (Figure 14.4). A **soft mist inhaler**, such as the Respimat, releases a slow-moving mist when a button is pressed during a slow, deep breath (Boehringer Ingelheim, 2019). A **nebulizer** turns liquid medicine into a mist that the patient breathes in through a mouthpiece or mask, which helps when a patient is too breathless to use a hand-held device.

Figure 14.4 Three dry powder inhalers: a Turbuhaler, an Accuhaler (sold in Canada as Diskus) and an Ellipta. Each is loaded differently, so the nurse checks technique with the patient's own device. (credit: "Dry powder inhalers" by Brett Montgomery/Wikimedia Commons, CC BY-SA 4.0)

Common errors include not breathing out before the dose, poor timing with a pMDI, breathing in too fast through a pMDI or too gently through a DPI, breathing out into a DPI, and skipping the breath-hold (Table 14.2). Using an empty inhaler is another hidden error. Some pMDIs, including Ventolin HFA, have no dose counter, so the patient must keep count; shaking or floating the canister is not a reliable test (GlaxoSmithKline, 2025). The Respimat has a dose indicator and locks when empty (Boehringer Ingelheim, 2019). A pMDI's plastic casing is rinsed weekly with warm water, never the metal canister, and spacers are cleaned as the manufacturer directs (GlaxoSmithKline, 2025).

The device must fit the person. A DPI needs enough inspiratory flow. The CTS notes that low inspiratory flow is likely a concern for only a small minority (under 5%) of people with chronic lung disease, but breathing-in strength is lower at the extremes of age, and severe disease or an exacerbation can reduce it further; a pMDI with a spacer may then work better (Gupta et al., 2023). Coordination, hand strength, cognition and vision also matter. The CTS recommends choosing inhalers through shared decision-making that weighs technique, preference, cost, side effects and environmental impact. Propellants in pMDIs are potent greenhouse gases, and DPIs and soft mist inhalers have roughly one-tenth of their carbon footprint. However, switching should not be automatic for a patient who prefers a pMDI and uses it well, and used inhalers should be returned to a pharmacy for disposal (Gupta et al., 2023).

Table 14.2 Inhaler devices and key technique points (GlaxoSmithKline, 2025; AstraZeneca Canada, 2021; Boehringer Ingelheim, 2019; Yang et al., 2021; original wording)

Device	How the patient breathes in	Key steps	Common errors
pMDI alone	Slowly and deeply, starting just before pressing the canister	Shake; breathe out away from the mouthpiece; seal lips; press once while breathing in; hold breath; wait about 30 seconds between puffs	Pressing too early or late; breathing in fast; not shaking; no breath-hold; not tracking doses on a device without a counter
pMDI with spacer	Slowly and deeply through the spacer mouthpiece	Shake; attach to spacer; breathe out; seal lips on spacer; one puff into the spacer, then breathe in; hold breath; repeat for each puff	Several puffs into the spacer at once; delay between puff and breath; dirty or cracked spacer
Dry powder inhaler	Fast, deep and forceful from the start	Load the dose as the device directs; breathe out away from the mouthpiece; seal lips; breathe in hard; hold breath; close the device	Breathing out into the device; breathing in too gently; not loading the dose; shaking or tilting some devices after loading

Device	How the patient breathes in	Key steps	Common errors
Soft mist inhaler	Slowly and deeply while pressing the button	Turn the base until it clicks; open the cap; breathe out; seal lips without covering the air vents; press while breathing in; hold the breath for about 10 seconds	Not turning the base fully; covering the air vents; spraying mist into the eyes

Teaching and Checking Technique

Checking technique is part of every encounter, not a one-time lesson. GINA advises asking the patient to show how they use the inhaler, comparing each step with a device-specific checklist, demonstrating the steps that went wrong, and checking again up to 2 or 3 times (GINA, 2026). Technique should be rechecked whenever the device or treatment changes. Faulty technique is linked to more symptoms, more urgent care visits and a greater environmental burden (GINA, 2026). The nurse also checks whether the inhaler is empty, a simple and often missed cause of poor control (Yang et al., 2021). The nurse uses teach-back and an observed demonstration, not just a question such as "Do you know how to use this?"

Admission and discharge are key moments. A patient may use a different device in hospital from the one at home, so the nurse checks technique with the patient's own device before discharge. Written instructions with pictures support verbal teaching. Plain language helps, and a professional interpreter is used when the patient prefers another language (Chapter 2). Cost and coverage affect whether patients fill prescriptions and keep using them. The nurse asks about drug coverage, such as provincial or territorial drug programs and the Non-Insured Health Benefits program for eligible First Nations and Inuit patients, and involves the pharmacist or social worker when cost is a barrier (Chapter 2).

PATIENT EDUCATION

Using Your Inhaler

Using a puffer with a spacer

- Take the cap off, check the mouthpiece, and shake the puffer.
- Put the puffer into the end of the spacer.
- Breathe out gently, away from the spacer.
- Close your lips around the spacer mouthpiece.
- Press the puffer once, then breathe in slowly and deeply.
- Hold your breath as long as is comfortable, then breathe out.
- Wait about 30 seconds before the next puff.

After a steroid inhaler: rinse your mouth with water and spit it out. This helps prevent thrush and a hoarse voice.

Your reliever: use it when you have symptoms, as your action plan says. Carry it with you every day. If you need it more than twice a week, tell your health care provider, because your asthma may not be well controlled.

Get help right away if your reliever does not help, the relief lasts less than 3 hours, or you need it more often than usual. Call 9-1-1 if you cannot speak in full sentences, your lips or nail beds turn grey or blue, or you feel drowsy or confused.

LIFESPAN CONSIDERATIONS

Inhalers and Older Adults

- **Hands:** arthritis or a weak grip can make it hard to press a canister, twist a Turbuhaler or turn the base of a soft mist inhaler. Ask the pharmacist about aids or another device.
- **Coordination and memory:** pressing and breathing at the same time is hard for many older adults. A spacer removes the need for precise timing. Cognitive impairment can make multi-step devices unreliable (Chapter 8).
- **Breath strength:** some older adults cannot breathe in hard enough for a dry powder inhaler, especially during an exacerbation (Gupta et al., 2023).
- **Vision and hearing:** small dose counters and printed steps can be hard to read. Use large print, good light, and teaching that suits the person's hearing.
- **Caregivers:** when a family member or care worker helps, teach that person too and watch them do it.
- **Cost:** ask whether cost leads the person to skip or stretch doses, and involve the pharmacist (Chapter 2).

- **Reassess often:** check technique at every visit, after any decline in health and whenever the device changes.

14.4 Chronic Obstructive Pulmonary Disease

This section follows the person with chronic obstructive pulmonary disease from diagnosis through long-term care to an exacerbation in hospital and the return home. Spirometry is introduced in section 14.1, and inhalers in section 14.3.

What Happens in COPD

Chronic obstructive pulmonary disease (COPD) is a long-term lung condition in which damaged airways, damaged alveoli or both cause airflow obstruction that does not fully reverse and often worsens over time. People with COPD have ongoing breathlessness, cough, sputum and flare-ups (Global Initiative for Chronic Obstructive Lung Disease [GOLD], 2025). Two kinds of damage contribute, and most patients have some of each.

- **Chronic bronchitis:** long-standing inflammation of the airways. The airway walls thicken, mucus-producing cells multiply and the small airways narrow and plug with mucus. The person coughs and brings up sputum on most days.
- **Emphysema:** destruction of the walls of the alveoli. Small air sacs merge into larger, floppy spaces with less surface for gas exchange. The lung also loses its elastic recoil, the spring that normally pushes air out and holds small airways open (Figure 14.5).

Both changes trap air. During exhalation, narrowed or unsupported small airways close before the lungs have emptied, so some air stays behind with each breath. This **air trapping** builds up, especially when the person breathes faster during exercise or illness. The result is **hyperinflation**: the lungs sit at a larger volume than normal, the diaphragm is pushed down and flattened, and the breathing muscles work at a mechanical disadvantage (GOLD, 2025). Each breath starts from an already full chest, so people with COPD feel they cannot get a satisfying breath and tire quickly. The mismatch between ventilation and blood flow in damaged lung units lowers oxygen levels and, in some patients, lets carbon dioxide (CO_2) build up (Chapter 12).

Figure 14.5 A cut slice of lung with centrilobular emphysema, the pattern typical of smoking: many small spaces where alveolar walls have been destroyed, lined with black carbon deposits. The specimen number on the ruler is pixelated. (credit: modification of "Centrilobular emphysema 865 lores" by Edwin P. Ewing, Jr./Centers for Disease Control and Prevention, public domain)

People with COPD often live with other conditions that affect their health and prognosis (GOLD, 2025). In Canada, people who have diabetes, high blood pressure, a mood or anxiety disorder or asthma are more likely to have COPD than people without these conditions (PHAC, 2018).

COPD in Canada

COPD mainly affects adults aged 35 and older. In 2011–2012, the most recent year in the national report, surveillance counted about 2.0 million Canadians in this age group living with diagnosed COPD (PHAC, 2018). The burden on hospitals is heavy. In 2023–2024, COPD and bronchitis were the second most common reason for hospital stays in Canada, after giving birth: 76,968 hospitalizations, 2.5% of the total, with an average acute stay of 7.1 days (CIHI, 2025). The CTS notes that, in Canada, COPD exacerbations lead all chronic conditions as a cause of acute hospital stays among adults (Bourbeau et al., 2023).

Smoking tobacco, including exposure to second-hand smoke, is the main cause (PHAC, 2018). Other risk factors include the following (GOLD, 2025):

- **Work exposures:** organic and inorganic dusts, chemicals and fumes.

- **Burning biomass fuels:** wood, crop waste or coal burned for cooking or heat in open fires or poor stoves.
- **Air pollution:** outdoor pollution, which also raises the risk of exacerbations, admissions and death. Health Canada lists people with lung conditions and adults aged 65 and older among those at higher risk from wildfire smoke (Health Canada, 2026b).
- **Genetics: alpha-1 antitrypsin deficiency**, an inherited lack of a protein that protects the lung from damage.
- **Early-life factors:** disadvantages in childhood that limit lung growth.

COPD is often missed. Many people with COPD have symptoms and poor health yet no diagnosis (Bourbeau et al., 2023), and GOLD reports that about 81% of people whose spirometry shows COPD have never been diagnosed (GOLD, 2025).

Risk is shaped by social conditions. In the 2012 Aboriginal Peoples Survey, which did not include people living on reserve, 6.8% of First Nations, Métis and Inuit respondents aged 35 and older self-reported COPD (Métis 7.9%, First Nations 6.6%, Inuit 3.2%); daily smoking, the lowest income level and unmet health care needs were each linked to higher odds (Bird et al., 2017). The diagnoses were self-reported, not confirmed by spirometry, and the authors suggest that the lower figure among Inuit may reflect underdiagnosis or limited access to a regular doctor (Bird et al., 2017). First Nations data belong to First Nations under the principles of OCAP® (First Nations Information Governance Centre, n.d.). Chapter 2 discusses the colonial roots of these gaps.

CANADIAN CONTEXT

COPD in Canada

- **A leading reason for hospital care:** in 2023–2024, COPD and bronchitis accounted for 76,968 hospitalizations, second only to giving birth; patients stayed an average of 7.1 days in acute care (CIHI, 2025).
- **Many Canadians affected:** in 2011–2012, diagnosed COPD was recorded in about 2.0 million people in Canada aged 35 and older (PHAC, 2018).
- **Rehabilitation gaps:** pulmonary rehabilitation eases breathlessness and improves exercise capacity, yet it is underused. Barriers include too few programs, too little capacity, low referral rates and gaps in rural access. The American Thoracic Society (ATS) guideline recommends offering a choice of centre-based or virtual (tele-) rehabilitation, an option for people who live far from a program (Rochester et al., 2023).
- **Wildfire smoke:** Health Canada lists people with lung conditions and adults aged 65 and older among those at higher risk, and advises checking the Air Quality Health Index (Health Canada, 2026b).
- **Indigenous health:** in a national Statistics Canada survey, First Nations, Métis and Inuit adults who could not get care when they needed it had higher odds of COPD (Bird et al., 2017). Community-led tobacco programs that keep tobacco sacred while reducing commercial tobacco use (First Nations Health Authority [FNHA], n.d.) and culturally safe access to diagnosis and rehabilitation build on community strengths (section 14.5; Chapter 2).

Recognizing and Diagnosing COPD

The typical person is an adult aged 35 or older with a history of smoking or other exposure who reports breathlessness, cough, sputum and flare-ups (GOLD, 2025; PHAC, 2018). Because breathlessness creeps up slowly, the nurse asks what the person can no longer do, not only whether they feel short of breath.

Spirometry confirms the diagnosis. A ratio of forced expiratory volume in 1 second to forced vital capacity (FEV1/FVC) below 0.70 after a bronchodilator confirms COPD (Bourbeau et al., 2023; section 14.1). Spirometry alone does not describe how sick a person is (Bourbeau et al., 2023), so the CTS guideline adds two other measures:

- **Symptom burden:** the modified Medical Research Council (mMRC) dyspnea scale (Chapter 12) and the **COPD Assessment Test (CAT)**, a short questionnaire about the effect of COPD on daily life. An mMRC score of 2 or more or a CAT score of 10 or more means moderate to severe symptoms or impaired health (Bourbeau et al., 2023).
- **Exacerbation risk:** a person is at high risk if, in the past year, they had two or more moderate exacerbations (treated with antibiotics, oral corticosteroids or both) or one or more severe exacerbations (needing an emergency department visit or hospital stay) (Bourbeau et al., 2023).

The nurse records the person's usual breathlessness, activity level, SpO2 and sputum when they are well. This baseline makes it easier to see when they are not.

Long-Term Care

The CTS 2023 guideline states that every person with symptoms and spirometry-confirmed COPD should receive maintenance treatment with a long-acting bronchodilator (Bourbeau et al., 2023). Its main recommendations are summarized here:

- **Mild symptoms, low exacerbation risk and only mildly reduced lung function:** start one long-acting bronchodilator, either a LAMA or a LABA.
- **Moderate to high symptoms and low exacerbation risk:** start LAMA/LABA dual therapy.
- **High exacerbation risk with moderate to high symptoms:** use LAMA/LABA/ICS **triple therapy**. For this group, the CTS also recommends triple therapy over dual therapy to lower the risk of death.
- **Ongoing exacerbations despite triple therapy:** consider adding a long-term macrolide antibiotic, after weighing the risks of antimicrobial resistance, hearing loss and prolongation of the QT interval on the electrocardiogram. For people with a chronic bronchitis pattern, the CTS suggests one of two other oral add-on medications.
- **Not recommended:** an ICS on its own, theophylline and maintenance oral corticosteroids such as prednisone.
- **For everyone:** a short-acting bronchodilator as needed (Bourbeau et al., 2023).

ICS-containing therapy raises the risk of pneumonia, especially in severe disease (Bourbeau et al., 2023), so the nurse teaches patients on an ICS to report fever or a change in sputum early. The CTS calls proper inhaler technique one of the most important parts of COPD care (Bourbeau et al., 2023); the nurse checks it at every opportunity (section 14.3).

The CTS also lists smoking cessation counselling, vaccination, self-management education, pulmonary rehabilitation and a written action plan for exacerbations as core treatments (Bourbeau et al., 2023):

- **Smoking cessation:** counselling and medication for everyone who smokes (section 14.5).
- **Vaccination:** influenza, pneumococcal, COVID-19 and respiratory syncytial virus (RSV) vaccines as recommended (Chapter 13).
- **Pulmonary rehabilitation:** a supervised, tailored program of exercise training, education and behaviour change. For people with stable COPD, it improves exercise capacity, breathlessness and quality of life. Started within 3 weeks of discharge after a hospitalized exacerbation, it reduces readmissions (Rochester et al., 2023).
- **Self-management and a written action plan:** the plan tells the person how to recognize a flare-up, which medications to start or increase and when to call for help.
- **Long-term oxygen:** for people with low blood oxygen at rest once their condition is stable and treatment optimized. In Ontario, the criteria are a partial pressure of oxygen in arterial blood (PaO2) of 55 mm Hg or less, or an arterial oxygen saturation (SaO2) of 88% or less, on room air at rest (College of Respiratory Therapists of Ontario [CRTO], 2022). Home oxygen and fire safety are covered in Chapter 12.
- **A palliative approach:** COPD is a life-limiting illness. Managing breathlessness and planning care early belong alongside active treatment (Chapter 10).

Acute Exacerbations in Hospital

The CTS 2023 guideline grades exacerbations by the treatment they need but does not define the acute event in detail, so this book uses the definition in the GOLD 2026 report. An **acute exacerbation of COPD** is a sudden flare-up in which symptoms get worse over a period of days, 14 days at most (GOLD, 2025). The CTS describes a change in at least one major symptom: breathlessness, sputum volume or sputum purulence (Bourbeau et al., 2023). Infections (viral or bacterial) and environmental pollutants are the most frequent triggers (GOLD, 2025). The team also looks for other causes of breathlessness, such as pneumonia (Chapter 13), heart failure (Chapter 18), pneumothorax or pulmonary embolism (Chapter 15).

Recognizing and escalating. The nurse assesses respiratory rate, work of breathing, ability to speak, SpO2, heart rate, temperature, sputum and level of consciousness, and scores them with the hospital's early warning tool (Chapter 6). Table 14.3 links common cues to their meaning and the nurse's response. New drowsiness or confusion, a rising respiratory rate with tiring, or failure to improve with bronchodilators calls for rapid escalation.

Oxygen and blood gases. The nurse gives oxygen to the target range on the order. For people at risk of hypercapnic respiratory failure, including those with COPD, guidelines suggest 88% to 92% (Barnett et al., 2022; O'Driscoll et al., 2017; Chapter 12). Oxygen is never withheld from a hypoxemic patient. **Hypercapnia**, a raised level of CO2 in arterial blood, can develop in some patients when too much oxygen is given (Abdo & Heunks, 2012). An arterial blood gas (ABG) is needed when an at-risk patient is breathless, has a falling SpO2 or becomes drowsy, and blood gases are rechecked 30 to 60 minutes after an oxygen change (O'Driscoll et al., 2017).

Medications. The CTS 2023 guideline covers stable COPD, so for acute treatment this book follows GOLD. Short-acting beta2-agonists, with or without a short-acting muscarinic antagonist, are the first bronchodilators (GOLD, 2025), given by inhaler and spacer or by nebulizer as ordered (section 14.3). For moderate or severe exacerbations, GOLD advises a systemic corticosteroid course of no more than 5 days. It advises a 5-day antibiotic course for patients with purulent sputum or other indications, such as a history of lung infections (GOLD, 2025). The nurse monitors blood glucose in patients on corticosteroids, especially those with diabetes (Chapter 22).

Ventilatory support. If blood gases show rising CO2 with acidemia despite treatment, the team may start non-invasive ventilation (NIV) (Rochwerg et al., 2017). Indications and care are in Chapter 15.

Comfort and function. Many patients find breathing easier sitting upright and leaning forward with the arms supported. The CTS dyspnea guideline supports pursed-lip breathing and walking aids for breathlessness in advanced COPD (Marciniuk et al., 2011). A calm voice and staying with the patient ease the anxiety that feeds breathlessness (Chapter 10). The nurse paces care to save energy, offers small frequent meals, mobilizes the patient early and gives venous thromboembolism (VTE) prophylaxis as ordered (Chapter 7).

Transitions home. GOLD advises starting long-acting maintenance therapy as soon as possible, and recovery can take up to 4 to 6 weeks (GOLD, 2025). Before discharge, the nurse:

- checks inhaler technique with the patient's own devices (section 14.3);
- reviews or writes the action plan with the patient and family;
- confirms a referral to pulmonary rehabilitation (Rochester et al., 2023);
- arranges follow-up with primary care or the respiratory clinic;
- offers cessation support (section 14.5) and reviews vaccines (Chapter 13).

Table 14.3 COPD exacerbation: cues and nursing actions (Barnett et al., 2022; GOLD, 2025; O'Driscoll et al., 2017; original wording)

Cue	What it may mean	Nursing action
More breathlessness than usual; more sputum or a change to yellow or green	An exacerbation, often triggered by infection	Assess vital signs, SpO2 and work of breathing; give ordered short-acting bronchodilators; send sputum if ordered; report
SpO2 below the ordered target (for example below 88%)	Worsening hypoxemia	Raise oxygen within the order to reach the target; reassess after 5 minutes; report if the target is not reached; expect an ABG
SpO2 above the target (for example above 92%) in a patient at risk of hypercapnia	More oxygen than needed; CO2 may rise	Lower oxygen within the order to bring SpO2 into range; never stop it abruptly; watch level of consciousness; report
New drowsiness, confusion or difficulty waking	Rising CO2 or worsening hypoxemia	Check airway, breathing and level of consciousness; call the rapid response team; prepare for an ABG; hold sedating drugs and report
Accessory muscle use, fast breathing, speaks only a few words	Severe exacerbation; breathing muscles tiring	Sit upright; stay with the patient; escalate at once; prepare for an ABG and possible NIV (Chapter 15)
Fever	Infection, possibly pneumonia	Report; obtain cultures and chest X-ray as ordered; give antibiotics as ordered (Chapter 13)

Cue	What it may mean	Nursing action
Little or no relief from bronchodilators	Severe exacerbation or another cause, such as pneumothorax, pulmonary embolism or heart failure	Check that the drug was delivered; escalate for urgent review (Chapters 15 and 18)

GOING DEEPER

Blood Gases in Chronic CO2 Retention

Required for RN students; optional for PN students.

Some people with advanced COPD retain CO2 even when stable. Chapter 3 (section 3.7) explains how to read an ABG; this box applies those steps to chronic CO2 retention. Chapter 12's Going Deeper box covers oxygenation.

Chronic respiratory acidosis. When PaCO2 rises slowly over weeks to months, the kidneys keep more bicarbonate (HCO3−). As a rough guide, HCO3− rises about 4 mmol/L for every 10 mm Hg rise in PaCO2 in chronic respiratory acidosis, compared with only about 1 mmol/L in acute respiratory acidosis (Farley & Licari, 2019). The pH therefore stays near normal. Illustrative values (not from a patient): pH 7.35, PaCO2 60 mm Hg, HCO3− 32 mmol/L. The PaCO2 and HCO3− are both high, and the pH is at the low end of normal: a compensated respiratory acidosis.

Acute-on-chronic. During an exacerbation, PaCO2 can climb faster than the kidneys can respond. Illustrative values: pH 7.25, PaCO2 80 mm Hg, HCO3− 34 mmol/L. The high HCO3− shows the old, chronic retention; the falling pH shows a new, acute rise in CO2 on top of it. This pattern, with drowsiness or tiring, needs urgent escalation, and the team may consider NIV (Chapter 15). The patient's own baseline values, if known from earlier stable blood gases, are the best comparison.

Why the oxygen target is lower. In people at risk, high oxygen concentrations can raise PaCO2, mainly by worsening the match between ventilation and blood flow, not by switching off a "hypoxic drive" (Abdo & Heunks, 2012). A target of 88% to 92% supplies enough oxygen while limiting this effect (O'Driscoll et al., 2017). Withholding oxygen from a hypoxemic patient is never the answer.

14.5 Smoking and Vaping Cessation

No other cause of illness and death in Canada is as preventable as smoking tobacco (Thombs et al., 2025). A hospital stay is a good time to stop: the patient cannot smoke on the unit and is surrounded by people who can help. Chapters 12 and 13 point here for cessation.

Tobacco and Vaping in Canada

In the 2022 Canadian Tobacco and Nicotine Survey, 10.9% of Canadians aged 15 and older, about 3.5 million people, currently smoked cigarettes. Among people who smoked daily, 31.4% had made at least one quit attempt lasting 24 hours in the past year (Health Canada, 2023). Vaping in the past 30 days was reported by 5.8% of people aged 15 and older, 13.6% of youth aged 15 to 19 and 19.7% of young adults aged 20 to 24. Among people who vaped, 18.8% gave quitting smoking as their reason (Health Canada, 2023).

Health Canada states that vaping nicotine can cause dependence, is not harmless, may damage the lungs through harmful chemicals and has long-term risks that are still being studied. It also states that, for a person who smokes, replacing cigarettes completely with vaping carries less harm than smoking (Health Canada, 2026a). The Canadian Task Force on Preventive Health Care suggests against using e-cigarettes to quit except in certain circumstances, citing the lack of long-term safety data (Thombs et al., 2025).

Helping in Hospital

The **Ottawa Model for Smoking Cessation** is a hospital-based program. Staff identify and document every patient's smoking status, trained staff give a standard bedside consultation, cessation medications are ordered through preprinted order forms, and patients who agree are enrolled in automated telephone follow-up after discharge, with calls from cessation nurse specialists for those who relapse or lose confidence (Mullen et al., 2017). In a study at 14 Ontario hospitals, patients who received the program had fewer readmissions than usual-care controls at 30 days (7.1% vs 13.3%), 1 year and 2 years, and lower death rates at 1 and 2 years (Mullen et al., 2017).

The Registered Nurses' Association of Ontario (RNAO) best practice guideline asks nurses to use brief interventions to screen all patients for all forms of tobacco use, build a person-centred plan with them, provide or refer for counselling and medication, and follow up until the person's goals are met (RNAO, 2017). The Task Force likewise advises clinicians to ask patients whether they smoke and to advise those who do to quit (Thombs et al., 2025). In hospital, the nurse can put this into three steps:

- **Ask** every patient, on admission, about smoking, vaping and other tobacco use, and document it.
- **Advise** clearly and kindly to stop, linking the advice to the reason for admission.
- **Offer help** with medication to manage withdrawal now and referral for support after discharge.



Figure 14.6 A nicotine patch on the upper arm. It gives a steady dose of nicotine through the skin; a short-acting form such as gum or a lozenge can be added for cravings. (credit: “Nicoderm” by RegBarc/Wikimedia Commons, CC BY 2.5)

A patient who cannot smoke in hospital may go into nicotine withdrawal and feel restless, irritable or anxious. Offering **nicotine replacement therapy (NRT)** early, under an order or medical directive, eases withdrawal; in the Ottawa Model, cessation medications are ordered through preprinted order forms (Mullen et al., 2017). Language matters: "a person who smokes," not "a smoker," and no blame (Chapter 11). Many people try to quit several times, and a patient who relapses is invited to plan another attempt (Thombs et al., 2025).

At discharge, the nurse connects the patient to follow-up: the provincial or territorial quit service listed by Health Canada (Health Canada, 2024) or, for First Nations, Inuit, Métis and urban Indigenous people, **Talk Tobacco**, a Canadian Cancer Society service that offers free, confidential, culturally tailored support to quit smoking, vaping or commercial tobacco (1-833-998-8255) (Canadian Cancer Society, n.d.; FNHA, n.d.).

Cessation Medications

Canada's Task Force strongly recommends four medications to help adults stop smoking: NRT, varenicline, bupropion and cytisine. It also recommends combining medication with behavioural support (Thombs et al., 2025). Table 14.4 summarizes them. NRT comes as a long-acting patch (Figure 14.6) and short-acting forms such as gum and lozenges. Alberta's adult inpatient algorithm, for example, pairs a patch with a short-acting form for breakthrough cravings (Alberta Health Services [AHS], 2025). **Varenicline** is a prescription tablet that partly stimulates the brain's nicotine receptors (Auro Pharma, 2025). Bupropion for smoking cessation is sold as Zyban (Bausch Health, 2023). Cytisine is approved in Canada as a natural health product; the Task Force notes that, unlike NRT, it lacks coverage (Thombs et al., 2025).

Table 14.4 Smoking cessation medications in Canada (AHS, 2025; Auro Pharma, 2025; Bausch Health, 2023; Thombs et al., 2025; original wording)

Medication	How it helps	Key cautions	Nursing points
Nicotine patch (NRT)	Gives a steady dose of nicotine through the skin to ease withdrawal	May slightly increase palpitations or chest pain; few other harms	Offer early in the stay under an order or directive; ask about cravings each shift; pair with a short-acting form if ordered
Short-acting NRT (such as gum or lozenge)	Delivers nicotine quickly to relieve sudden cravings	As for the patch	Teach the patient to use it when cravings strike; combined with a patch when ordered

Medication	How it helps	Key cautions	Nursing points
Varenicline	Partly stimulates nicotine receptors, easing craving and withdrawal	Serious neuropsychiatric symptoms reported after marketing; caution with heart disease and with a history of seizures; alcohol may raise the risk of psychiatric effects; lower dose in severe kidney impairment	Nausea is the most common adverse effect; started 1 to 2 weeks before a set quit date, or with a flexible quit date; caution with driving until the person knows how it affects them; use with counselling
Bupropion (Zyban)	Non-nicotine tablet used with behavioural support	Contraindicated with seizures or a seizure history, current or past bulimia or anorexia nervosa, monoamine oxidase (MAO) inhibitors, other bupropion products, or abrupt withdrawal from alcohol or sedatives; seizure risk rises with dose; risk of self-harm and suicidal thinking	Start while the person is still smoking; dry mouth and insomnia are common; ask about seizures, eating disorders and other bupropion products such as Wellbutrin
Cytisine	Recommended cessation aid in Canadian guidance	Approved as a natural health product; check the licensed product information for cautions	Not covered, unlike NRT; the nurse includes it in the list of options the patient can discuss with the prescriber or pharmacist

Commercial and Traditional Tobacco

For many First Nations, tobacco is a sacred medicine. It is burned in ceremony, used in smudging and pipe ceremonies, placed as an offering and given as a gift to Elders and Knowledge Keepers. This **traditional tobacco** is different from **commercial tobacco**: cigarettes, chew and snuff with added chemicals that make them more addictive; commercial tobacco is linked to lung disease, heart disease and several cancers (FNHA, n.d.). The First Nations Health Authority in British Columbia describes its goal as keeping tobacco sacred while reducing commercial tobacco use (FNHA, n.d.).

Practices differ among First Nations, Inuit and Métis communities and individuals, so the nurse asks rather than assumes. Cessation advice addresses commercial tobacco, never ceremony. A patient who wishes to have a smudge or other ceremony in hospital is supported through the hospital's Indigenous health team and policy (Chapter 2).

14.6 Bronchiectasis, Interstitial Lung Disease and Sleep Apnea

The three conditions in this section are less common than COPD, but nurses meet them on every medical unit. Bronchiectasis is an airway disease, interstitial lung disease scars the lung itself, and obstructive sleep apnea is a disorder of breathing during sleep.

Bronchiectasis

Bronchiectasis is permanent widening of the bronchi, seen on chest computed tomography (CT), together with typical symptoms (Chalmers et al., 2025). Damaged airways clear mucus poorly. Mucus pools, bacteria grow, inflammation damages the airways further and the cycle continues. Bronchiectasis has many causes, infectious and immune among them. Daily symptoms and exacerbations, when cough, sputum and breathlessness worsen, matter most to patients (Chalmers et al., 2025).

The European Respiratory Society (ERS) 2025 guideline recommends airway clearance techniques for most patients and pulmonary rehabilitation for those with reduced exercise capacity. It recommends long-term macrolide treatment for people at high risk of exacerbations, and long-term inhaled antibiotics for people with chronic *Pseudomonas aeruginosa* infection who are at high risk. It suggests against routine ICS (Chalmers et al., 2025). The nurse supports daily airway clearance with the physiotherapist or respiratory therapist (Chapter 12), sends sputum cultures as ordered, and teaches the patient to report a change in sputum early. People who cough up sputum every day know their own baseline well, so the nurse asks what is usual for them and reports more sputum, thicker or darker sputum, fever or new breathlessness. The Thoracic Society of Australia and New Zealand (TSANZ) includes bronchiectasis among the conditions for which an oxygen target of 88% to 92% is recommended (Barnett et al., 2022; Chapter 12).

Interstitial Lung Disease

Interstitial lung disease (ILD) is a group of disorders that inflame or scar the lung tissue between the alveoli and blood vessels. Scarring makes the lungs stiff and small and thickens the barrier oxygen must cross: a restrictive pattern (section 14.1). Some ILDs occur with connective tissue diseases such as systemic sclerosis (Boehringer Ingelheim, 2024; Chapter 34); others have other identifiable causes, and some have no known cause.

Idiopathic pulmonary fibrosis (IPF), a scarring ILD of unknown cause, is the most familiar. Patients typically describe slowly worsening breathlessness on exertion and a dry cough. On auscultation, fine crackles that sound like Velcro being pulled apart may be heard at the lung bases (Chapter 12), and some patients have clubbing. Diagnosis rests on high-resolution CT and discussion among specialists (Raghu et al., 2018).

Antifibrotic drugs slow the loss of lung function but do not reverse scarring:

- **Nintedanib** (Ofev) is approved for IPF and for other progressive fibrosing ILDs. Diarrhea is the most common adverse effect. It raises bleeding risk, needs liver tests before and during treatment, is taken with food and must not be used in pregnancy (Boehringer Ingelheim, 2024).
- **Pirfenidone** is approved for IPF. Nausea and rash are common. Patients avoid sun exposure and use a high-protection sunscreen, take it with food and have regular liver tests. Smoking lowers the drug's level, so patients stop smoking before starting it (Sandoz Canada, 2024).

SpO2 can fall during activity even when it is acceptable at rest, so the nurse checks it while the patient walks or receives care, titrates oxygen within the order, paces activity and reports a rising oxygen need, which can signal progression or a new problem such as infection. Care also includes oxygen when needed (Chapter 12) and pulmonary rehabilitation, which improves exercise capacity in ILD (Rochester et al., 2023). Because IPF shortens life, an early palliative approach that addresses breathlessness, cough and planning is part of good care (Chapter 10).

Figure 14.7 A home CPAP machine with its tubing and mask. People who use CPAP at home are encouraged to bring their machine to hospital and use it whenever they sleep. (credit: “ResMed CPAP machine and mask” by Infrogmation/Wikimedia Commons, CC BY-SA 4.0)

Obstructive Sleep Apnea

In **obstructive sleep apnea (OSA)**, the upper airway collapses again and again during sleep. Each collapse stops or reduces airflow until the brain briefly wakes the person to reopen it. Sleep is broken and of poor quality, so people feel sleepy and less alert by day (Ayas et al., 2014). OSA is common: Ayas et al. (2014) report it in about 24% of middle-aged men and 9% of middle-aged women.

The **STOP-Bang** questionnaire is a quick screening tool. It asks about loud snoring, daytime tiredness, observed pauses in breathing and high blood pressure, then adds a body mass index over 35 kg/m², age over 50, a neck circumference over 40 cm and male sex. Each "yes" scores a point: 0 to 2 points suggests low risk, 3 to 4 moderate risk and 5 to 8 high risk (Chung et al., 2016). Screening only flags risk. Diagnosis needs a sleep study, done in a sleep laboratory or at home.

The usual treatment is **continuous positive airway pressure (CPAP)**: a machine blows air through a mask at a set pressure that holds the airway open (Figure 14.7). Many people find the mask hard to get used to. Nurses help with mask fit, dry mouth and claustrophobia and encourage nightly use.

On admission, the nurse asks about snoring, daytime sleepiness and home CPAP, uses STOP-Bang if the hospital does, and reports a high score before surgery or sedation.

People who use CPAP at home are encouraged to bring their machine to hospital, as policy allows, and to use it whenever they sleep, including naps. The nurse records the settings and mask type, follows policy for checking the equipment and involves the respiratory therapist. OSA raises the risk of breathing problems around surgery (Memtsoudis et al., 2018; Chapter 7). Untreated OSA raises the risk of motor vehicle crashes, and people who use CPAP consistently have a crash risk similar to others their age. Each province decides on driving restrictions through its licensing authority, and clinicians use the visit to teach about drowsy driving (Ayas et al., 2014).

CLINICAL SAFETY

Sleep Apnea, Opioids and Sedation

People with OSA may be at greater risk of breathing complications from opioids and from propofol used for procedural sedation, and intravenous benzodiazepine sedation calls for caution (Memtsoudis et al., 2018). Their airway tends to collapse during sleep, and these drugs deepen sedation and blunt the body's response to low oxygen and high CO2. For any patient with known or suspected OSA (a high STOP-Bang score), the nurse:

- monitors sedation level and respiratory rate before each opioid dose and at the peak of its effect, using the hospital's sedation scale (Chapter 5, section 5.4);
- watches for snoring followed by silent pauses, which signal obstruction;
- places CPAP on the patient whenever they sleep, as ordered;
- uses continuous SpO2 or capnography monitoring as ordered or as policy requires;
- reviews every sedating drug on the medication record, including sleeping pills, and asks the prescriber about combinations;
- holds the dose and escalates at once if the patient is hard to rouse or breathing slows.

SCOPE IN PRACTICE

Inhalers, Nebulizers, Oxygen and Cessation Support

- **Authority:** In Ontario, administering a substance by inhalation is a controlled act. RNs and RPNs may perform it, including giving inhalers, nebulized drugs and oxygen, with an order or a medical directive. Nurses cannot initiate controlled acts in public hospitals (College of Nurses of Ontario [CNO], 2025). Titrating oxygen to a target range follows the order or directive (CRTO, 2022). Respiratory therapists are authorized to administer substances by inhalation and may start, titrate and stop oxygen without an order (CRTO, 2024); they often lead this care. In hospital, cessation medications such as NRT are given under an order or directive (Mullen et al., 2017).
- **Competence:** The nurse needs the knowledge, skill and judgment to do the activity safely (CNO, 2025). That means knowing the device, the drug, the oxygen target and what to watch for. Nebulizers generate aerosols, so the nurse follows infection prevention and control (IPAC) precautions (Chapter 4). Brief cessation counselling is part of every nurse's practice (RNAO, 2017).
- **Context:** The setting, resources and patient's needs shape who does what (CNO, 2025). Employer policy may limit, but never expand, scope, and rules differ by province or territory.
- **Deterioration:** Every nurse who sees a patient deteriorate acts at once and escalates (Chapter 6). The RPN consults the RN as the patient's needs change, for example when oxygen needs rise or drowsiness appears.

PRACTICE STORY

Second Time This Month

Names and details are fictional; this is a composite story.

Nurse: Ngozi Eze, RN. Years in practice: 6. Setting: medical unit, community hospital, Ontario.

I recognized Mr. Leblanc the moment I saw his name on the board. He had gone home from our unit 19 days earlier after a COPD flare-up, and now he was back, sitting on the edge of the stretcher, leaning on his elbows, talking in short phrases. His SpO2 was 86% on room air.

I started oxygen by nasal cannula under our directive and titrated to his ordered target of 88% to 92%. Once he settled, I asked him to show me how he used his inhalers. He shook the dry powder inhaler, breathed out into the mouthpiece and then took a slow, gentle breath in. Much of each dose had probably never reached his lungs. No one had watched him use it at discharge; we had only asked whether he knew how.

That evening he was restless and irritable, and he admitted he had been smoking about ten cigarettes a day again. I said nothing about blame. I asked how he was managing the cravings, and he laughed and said, "I'm not." Under our hospital's Ottawa Model directive, I offered a nicotine patch, and the physician added nicotine gum for breakthrough cravings. He agreed to the follow-up calls.

Before discharge, the RPN on my team, Daniel, and I went through his action plan with him and his daughter. Daniel had him demonstrate his inhaler technique twice more. I made sure the physician's referral went to the pulmonary rehabilitation program and called them myself to book his intake for the next week, within the 3-week window after discharge. His daughter asked why no one had mentioned rehabilitation before. I did not have a good answer.

Six weeks later, Mr. Leblanc's daughter left a card at the desk. He had been to eight rehabilitation classes and was walking to the corner store again.

Reflect: Which actions in this story could Daniel, the RPN, carry out on his own, and when should he consult the RN? What changes on your unit would make sure every patient's inhaler technique is watched, not just asked about, before discharge?

Chapter 14 Summary

Introduction

- Asthma and COPD are common long-term lung diseases in Canada; CCDSS data counted about 3.8 million people aged 1 and older with asthma and 2.0 million aged 35 and older with COPD in 2011–2012.
- COPD and bronchitis were the second most common reason for a hospital stay in Canada in 2023–2024.
- This chapter covers obstructive and restrictive disease, asthma, inhalers, COPD, cessation, bronchiectasis, interstitial lung disease and sleep apnea.

14.1 Obstructive and Restrictive Patterns

- Obstruction narrows airways and traps air; restriction keeps the lungs from filling.
- Spirometry measures FVC, FEV1 and their ratio; a reduced FEV1/FVC ratio shows obstruction.
- Restriction is suggested by a low FVC with a normal or high ratio and confirmed by lung volume testing.
- An FEV1 rise of at least 12% and 200 mL after a bronchodilator shows reversibility that supports asthma.
- The nurse prepares the patient, holds bronchodilators only as instructed, and coaches full effort.

14.2 Asthma

- Asthma involves airway inflammation, hyperresponsiveness, variable narrowing and mucus; triggers include viruses, allergens, smoke (including wildfire smoke), work exposures and some medicines.
- Diagnosis needs a compatible history plus objective proof of variable airflow obstruction.
- CTS treatment builds on inhaled corticosteroids; as-needed budesonide–formoterol and MART are key options, and frequent SABA use signals poor control.
- Every person with asthma needs a written action plan.
- In an exacerbation, drowsiness, a silent chest, SpO2 below 92% and a normal or rising PaCO2 are life-threatening signs that need immediate escalation.

14.3 Inhaled Medications and Devices

- Relievers open airways within minutes; controllers prevent symptoms and flare-ups.
- A pMDI needs a slow, deep breath, ideally through a spacer; a dry powder inhaler needs a fast, forceful breath.
- The device must fit the person's inspiratory flow, coordination, hands, cognition and vision.
- The nurse checks technique at every opportunity with observed demonstration and teach-back.

14.4 Chronic Obstructive Pulmonary Disease

- COPD causes airflow obstruction that does not fully reverse; chronic bronchitis and emphysema both lead to air trapping and hyperinflation.
- COPD and bronchitis were the second most common reason for hospital stays in Canada in 2023–2024; smoking is the main cause, and many people are never diagnosed.
- A post-bronchodilator FEV1/FVC below 0.70 confirms COPD; the CTS adds symptom burden (mMRC, CAT) and exacerbation risk to guide treatment.
- The CTS 2023 guideline calls for long-acting bronchodilators for all symptomatic patients, LAMA/LABA for most, and triple therapy for those at high exacerbation risk, with cessation, vaccination, rehabilitation and an action plan.
- In an exacerbation, the nurse gives oxygen to 88% to 92%, short-acting bronchodilators, a short steroid course and antibiotics for purulent sputum as ordered, and escalates new drowsiness at once.
- Discharge includes a technique check, an action plan, pulmonary rehabilitation referral and follow-up.

14.5 Smoking and Vaping Cessation

- In 2022, 10.9% of Canadians aged 15 and older smoked cigarettes, and vaping was most common among young adults.
- The Ottawa Model identifies every patient who smokes, offers counselling and medication in hospital and follows up after discharge; it lowered readmissions and deaths in Ontario hospitals.
- NRT, varenicline, bupropion and cytisine are recommended in Canada, ideally with behavioural support; bupropion is contraindicated with seizures.
- Cessation support addresses commercial tobacco and respects traditional tobacco used in ceremony.

14.6 Bronchiectasis, Interstitial Lung Disease and Sleep Apnea

- Bronchiectasis is permanent widening of the bronchi; daily airway clearance is recommended for most patients.
- IPF causes exertional breathlessness, dry cough and fine basal crackles; nintedanib and pirfenidone slow decline, and an early palliative approach is part of care.
- STOP-Bang screens for OSA, a sleep study confirms it, and CPAP treats it; patients use their CPAP whenever they sleep in hospital.
- People with OSA are more sensitive to opioids and sedatives, so the nurse monitors sedation and breathing closely.
- RNs and RPNs give inhaled drugs and titrate oxygen under orders or directives; every nurse escalates deterioration at once.

Key Terms (57)

acute exacerbation of COPD: A sudden flare-up in which symptoms such as breathlessness, sputum volume or sputum purulence get worse over a period of days, 14 days at most.

air trapping: Air left behind in the lungs at the end of each breath because narrowed or unsupported small airways close early during exhalation.

airway hyperresponsiveness: A tendency of the airways to narrow quickly and strongly in response to stimuli that barely affect other people.

alpha-1 antitrypsin deficiency: An inherited lack of a protein that protects the lungs from damage; a genetic risk factor for COPD.

antifibrotic: A drug, such as nintedanib or pirfenidone, that slows the loss of lung function in pulmonary fibrosis without reversing scarring.

asthma: A chronic, usually inflammatory airway disease with variable symptoms and variable airflow limitation.

asthma control: How well treatment keeps asthma symptoms and exacerbations away, judged against set criteria.

asthma exacerbation: A flare in which asthma symptoms and lung function worsen beyond the person's usual variation.

biologic: An injected antibody medicine that blocks a specific step in airway inflammation, used for some people with severe asthma.

bronchiectasis: Permanent widening of the bronchi, seen on CT, with chronic symptoms and recurrent exacerbations.

bronchoconstriction: Tightening of the smooth muscle around the airways, which narrows them.

chronic bronchitis: Long-standing airway inflammation with thickened airway walls, excess mucus and a cough that brings up sputum on most days.

chronic obstructive pulmonary disease (COPD): A long-term lung condition in which damaged airways, damaged alveoli or both cause airflow obstruction that does not fully reverse and often worsens over time.

commercial tobacco: Manufactured tobacco products, such as cigarettes, chew and snuff, that contain added chemicals and cause addiction and disease.

compensated respiratory acidosis: A high PaCO2 balanced by a rise in bicarbonate retained by the kidneys, so the pH is near normal.

continuous positive airway pressure (CPAP): A machine that delivers air through a mask at a set pressure to hold the upper airway open during sleep.

controller: An inhaled medicine used regularly to reduce airway inflammation or keep airways open, preventing symptoms and flare-ups.

COPD Assessment Test (CAT): A short questionnaire that measures the effect of COPD on daily life; a score of 10 or more shows a moderate to high symptom burden.

diffusing capacity: A test of how well gas crosses from the alveoli into the blood, measured with a small amount of carbon monoxide.

dry powder inhaler (DPI): A device that holds medicine as a powder released by the patient's own fast, forceful breath.

emphysema: Destruction of alveolar walls that reduces the surface for gas exchange and the lung's elastic recoil.

FEV1/FVC ratio: The share of the forced vital capacity blown out in the first second; a reduced ratio shows airflow obstruction.

forced expiratory volume in 1 second (FEV1): The volume of air blown out in the first second of a forced breath.

forced vital capacity (FVC): The total volume of air blown out in one full, forced breath.

hypercapnia: A raised level of carbon dioxide in arterial blood.

hyperinflation: An abnormally large lung volume caused by air trapping, which flattens the diaphragm and makes breathing less efficient.

ICS–formoterol reliever: Budesonide–formoterol used as needed for symptoms, so each reliever dose also treats inflammation.

idiopathic pulmonary fibrosis (IPF): A scarring interstitial lung disease of unknown cause.

inhaled corticosteroid (ICS): An inhaled anti-inflammatory controller, such as fluticasone or budesonide.

interstitial lung disease (ILD): A group of disorders that inflame or scar the lung tissue between the alveoli and blood vessels, causing a restrictive pattern.

long-acting beta2-agonist (LABA): A bronchodilator that keeps airways open for many hours; in asthma it is always combined with an inhaled corticosteroid.

long-acting muscarinic antagonist (LAMA): A long-acting bronchodilator, such as tiotropium, used mainly in COPD and as an add-on in asthma.

lower limit of normal (LLN): The value below which only 5% of healthy people fall; used to judge whether a lung function result is abnormal.

maintenance and reliever therapy (MART): Use of one budesonide–formoterol inhaler both as the daily controller and as the reliever for symptoms.

nebulizer: A device that turns liquid medicine into a mist breathed in through a mouthpiece or mask.

nicotine replacement therapy (NRT): Medication that supplies nicotine without tobacco smoke, as a patch or short-acting forms such as gum and lozenges, to ease withdrawal and cravings.

obstructive lung disease: Lung disease in which narrowed airways slow the flow of air out of the lungs and trap air, as in asthma and COPD.

obstructive sleep apnea (OSA): Repeated collapse of the upper airway during sleep, causing broken sleep and daytime sleepiness.

Ottawa Model for Smoking Cessation: A hospital program that identifies every patient who smokes, provides bedside counselling and medication, and follows patients after discharge.

peak expiratory flow (PEF): The fastest speed of air during a short, sharp blow into a hand-held meter.

pressurized metered-dose inhaler (pMDI): A device that releases a measured puff of medicine in a propellant spray.

pulmonary rehabilitation: A supervised, tailored program of exercise training, education and behaviour change for people with chronic lung disease.

reliever: An inhaled medicine that opens narrowed airways within minutes and is used for symptoms.

restrictive lung disease: Lung disease in which stiff lungs or a limited chest wall keep the lungs from filling, so lung volumes are small.

reversibility: A meaningful improvement in airflow after a bronchodilator or a course of controller treatment; in the CTS asthma guideline, an FEV1 rise of at least 12% and 200 mL.

severe asthma: Asthma that stays uncontrolled despite high-level inhaled treatment, needing specialist assessment.

short-acting beta2-agonist (SABA): A reliever, such as salbutamol, that relaxes airway smooth muscle within minutes.

short-acting muscarinic antagonist (SAMA): A short-acting bronchodilator, such as ipratropium, that blocks the nerve signals that tighten airway muscle.

silent chest: A life-threatening sign in asthma in which so little air moves that wheeze can no longer be heard.

soft mist inhaler: A device that releases a slow-moving mist of liquid medicine during a slow, deep breath.

spacer: A tube, often with a valve (valved holding chamber), that attaches to a pMDI and holds the puff so it can be breathed in without precise timing.

spirometry: A breathing test that measures how much air a person can blow out after a full breath in, and how fast.

STOP-Bang: An eight-item screening questionnaire for obstructive sleep apnea that scores snoring, tiredness, observed apnea, blood pressure, BMI, age, neck circumference and sex.

traditional tobacco: Tobacco used by many First Nations as a sacred medicine in ceremony, offerings and gifts; distinct from commercial tobacco.

triple therapy: Maintenance treatment with a LAMA, a LABA and an ICS, usually in one inhaler, for people with COPD at high risk of exacerbations.

varenicline: A prescription cessation medication that partly stimulates nicotine receptors, easing cravings and withdrawal.

written action plan: A personal written guide that tells a person with asthma how to recognize worsening, step up treatment and seek help.

Licensure Review & Clinical Judgment Questions (35)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Marisol Vega (Questions 1–4): Marisol Vega, 41, is admitted to a medical unit in Kingston, Ontario, with an asthma exacerbation that began after a cold. She uses a salbutamol inhaler "almost every day" and stopped her steroid inhaler months ago because of the cost. On arrival she is sitting upright, speaking in short phrases and using her neck muscles to breathe. Her respiratory rate is 28 breaths/min, heart rate 112 beats/min and SpO2 92% on room air. An RPN and an RN share her care.

1. [CORE] Which finding in Ms. Vega's admission assessment is a feature of acute severe asthma?

a. Sitting upright to breathe
b. A respiratory rate of 28 breaths/min
c. Daily use of salbutamol before admission
d. The recent cold that preceded the exacerbation

Answer: b — A respiratory rate of 25 breaths/min or more is a feature of acute severe asthma, as are being unable to finish sentences in one breath and a heart rate of 110 beats/min or more, which Ms. Vega also shows (section 14.2). Sitting upright is a common position of comfort and does not grade severity on its own. Daily salbutamol use shows poor control before admission, not the severity of today's flare. A viral infection is a trigger, not a severity finding.

2. [CORE] Salbutamol by metered-dose inhaler with a spacer and oxygen to the ordered target are prescribed. What should the nurse do first?

a. Teach her how to use her inhaler correctly
b. Obtain a peak flow reading to confirm the diagnosis
c. Give the salbutamol as ordered while staying with her
d. Ask the pharmacist about coverage for her steroid inhaler

Answer: c — Treating airway narrowing comes first; the nurse gives the ordered bronchodilator and stays to watch her response (section 14.2). Teaching technique matters, but not while she is breathless. Peak flow helps judge severity and response, but it should not delay treatment, and her asthma diagnosis is not in question. Coverage is an important barrier to address before discharge, not a first action.

3. [CORE] One hour after treatment, which finding shows that Ms. Vega is responding?

a. She speaks in full sentences and her respiratory rate is 20 breaths/min
b. Her wheeze is quieter and she is more drowsy than before
c. Her heart rate has risen to 120 beats/min with a fine tremor
d. She asks to lie flat and her SpO2 is 89% on oxygen

Answer: a — Full sentences and a slower respiratory rate show improved airflow and less work of breathing (section 14.2). A quieter chest with drowsiness may mean less air is moving and the patient is tiring, which is a life-threatening sign. Faster heart rate and tremor are expected salbutamol effects and do not show improvement. Falling SpO2 on oxygen is a sign of worsening, not response.

4. [CORE] Ms. Vega is ready for discharge with a budesonide–formoterol inhaler. Which statement shows she needs more teaching?

a. "I'll rinse my mouth and spit after I use it."
b. "I'll bring my action plan to my follow-up visit this week."
c. "If I need my reliever more than twice a week, I'll call my provider."
d. "Once I feel better, I can stop it and just use salbutamol."

Answer: d — Stopping her controller and relying on a SABA alone repeats the pattern that led to this admission; a SABA relieves symptoms but does not treat inflammation, the CTS advises a controller after a severe exacerbation in a person using a SABA alone, and GINA links SABA-only treatment to more exacerbations (sections 14.2 and 14.3). Rinsing and spitting after an ICS-containing inhaler prevents thrush. Early follow-up with her action plan is recommended. Needing a reliever more than twice a week signals poor control and should be reported.

5. [CORE] A patient's spirometry report shows a reduced FEV1/FVC ratio. What does this finding mean?

a. Air leaves the lungs slowly because the airways are narrowed
b. The lungs are stiff and cannot fill to a normal volume
c. Gas moves poorly from the alveoli into the blood
d. The patient did not give full effort during the test

Answer: a — A reduced FEV1/FVC ratio means a smaller share of air leaves in the first second, the mark of airflow obstruction (section 14.1). In restriction, FEV1 and FVC fall together, so the ratio is normal or high. Gas transfer is measured by diffusing capacity, not this ratio. Poor effort makes results unreliable but is judged by test quality criteria, not by a low ratio.

6. [CORE] The nurse watches a patient use a pressurized metered-dose inhaler without a spacer. Which actions are errors that the nurse should correct? Select all that apply.

a. Breathing in quickly and forcefully as the canister is pressed
b. Shaking the inhaler before the dose
c. Pressing the canister after the breath in is finished
d. Breathing out away from the mouthpiece before the dose
e. Breathing out right after the puff without holding the breath
f. Waiting about 30 seconds before the second puff

Answer: a, c, e — A pMDI needs a slow, deep breath started just before the canister is pressed, followed by a breath-hold (section 14.3, Table 14.2). Breathing in fast, pressing after the breath is over and skipping the breath-hold all reduce the dose reaching the lungs. Shaking the inhaler, breathing out first and waiting about 30 seconds between puffs are correct steps.

7. [CORE] A patient starting fluticasone propionate by inhaler asks why the nurse recommends rinsing after each dose. Which response is accurate?

a. "Rinsing makes the medicine work faster in your lungs."
b. "Rinsing prevents the shakiness this medicine can cause."
c. "Rinsing removes the propellant that can harm your teeth."
d. "Rinsing and spitting helps prevent thrush and a hoarse voice."

Answer: d — Inhaled corticosteroid left in the mouth and throat can cause thrush and hoarseness; rinsing with water and spitting reduces this (section 14.2, Medications box). Rinsing does not change how fast the medicine acts in the lungs. Tremor is a beta2-agonist effect, not an ICS effect. Protecting teeth from propellant is not the reason for rinsing.

8. [CORE] A patient with asthma says, "I only use my blue puffer, and I go through about four of them a year." What is the nurse's best interpretation?

a. Her asthma is well controlled because she avoids daily medicine
b. Her reliever use suggests poor control and a higher risk of exacerbations
c. She needs a stronger short-acting reliever to reduce the number of inhalers
d. Her use is normal for someone with mild asthma

Answer: b — Using more than two SABA inhalers a year should prompt reassessment, and treating asthma with a SABA alone is linked to more exacerbations and a higher risk of death (section 14.2). Avoiding a controller is not a sign of good control. A stronger short-acting reliever does not treat airway inflammation. This level of use is not normal for well-controlled mild asthma.

9. [CORE] Why does the nurse encourage a patient who uses an inhaled corticosteroid by metered-dose inhaler to use a valved holding chamber (spacer)?

a. It allows two puffs to be sprayed into the chamber at once
b. It removes the need to shake the inhaler before each puff
c. It holds the puff so precise timing with the breath matters less
d. It lets the patient breathe in quickly and forcefully through it

Answer: c — A spacer holds the puff so the patient can breathe it in without precise timing, and it reduces medicine left in the mouth; the CTS recommends one for all ages prescribed a pMDI (section 14.3). Puffs go into the spacer one at a time. The inhaler still needs shaking. A slow, deep breath is needed with a spacer; a fast, forceful breath is for dry powder inhalers.

10. [CORE] During a summer of wildfires in northern Ontario, a patient with asthma asks how the smoke affects her. Which response is accurate?

a. "Fine particles in the smoke can trigger asthma attacks, even when you can't see smoke."
b. "Smoke affects only people who work outdoors near the fire."
c. "If you can't smell smoke, the air is safe for your lungs."
d. "Wildfire smoke irritates the eyes but does not affect asthma."

Answer: a — Fine particles (PM2.5) are the main health risk in wildfire smoke, they cannot be seen, and asthma attacks are among the more serious effects (section 14.2). Outdoor workers face more exposure, but anyone breathing the smoke can be affected, especially people with lung conditions. Air quality can be poor without any visible or smelled smoke. The smoke affects the airways as well as the eyes.

11. [CORE] An RPN on a medical unit is caring for a patient admitted with asthma. The patient becomes drowsy, the wheeze becomes faint and SpO2 falls despite oxygen. What should the RPN do?

a. Document the findings and reassess in 1 hour
b. Give an extra dose of salbutamol without an order
c. Ask the patient's family to keep the patient awake
d. Stay with the patient, call for immediate help and notify the RN

Answer: d — Drowsiness, a quiet chest and falling SpO2 are life-threatening signs; every nurse who recognizes deterioration acts at once and escalates, through the rapid response team where the employer has one, and the RPN consults the RN as the patient's needs change (section 14.2; Chapter 1, section 1.3). Waiting an hour delays urgent care. Giving medication without an order or directive is outside the nurse's authority. Family cannot replace urgent clinical assessment.

12. [CORE] A patient is booked for spirometry to help diagnose asthma. Which instruction should the nurse give?

a. "Take an extra puff of your reliever just before the test so you can blow harder."
b. "Follow the lab's instructions about holding your inhalers, and don't smoke for an hour before."
c. "Eat a large meal shortly before the test so you have enough energy to blow."
d. "Wear a snug belt to support your abdomen while you blow out during the test."

Answer: b — For diagnostic testing, bronchodilators are held only as the laboratory or prescriber instructs, and smoking is avoided for 1 hour beforehand (section 14.1). A dose just before the test could hide reversible obstruction. Large meals within 2 hours and tight clothing interfere with full breaths.

13. [CORE] Which spirometry pattern suggests a restrictive lung disease such as pulmonary fibrosis?

a. Reduced FEV1/FVC ratio with a large rise in FEV1 after a bronchodilator
b. Reduced FEV1/FVC ratio with no change after a bronchodilator
c. Reduced FVC with a normal or high FEV1/FVC ratio
d. Normal FVC with a reduced FEV1

Answer: c — In restriction, the lungs cannot fill fully, so FVC and FEV1 fall together and the ratio stays normal or high; lung volume testing confirms it (section 14.1). A reduced ratio with a large bronchodilator response suggests asthma. A reduced ratio without reversibility suggests fixed obstruction such as COPD. A normal FVC with a low FEV1 lowers the ratio, which is an obstructive pattern.

14. [CORE] A patient with a dry powder inhaler asks how to breathe in. Which instruction is correct?

a. "Breathe in fast, deep and hard from the start."
b. "Breathe in slowly over 5 seconds, as with your puffer."
c. "Breathe out into the mouthpiece first to warm it."
d. "Take several small breaths through the device."

Answer: a — A dry powder inhaler has no propellant, so the patient's own fast, forceful, deep breath releases the powder (section 14.3). A slow breath suits a pMDI or soft mist inhaler. Breathing out into a DPI can blow the powder out and dampen it. Small breaths may not draw out the full dose.

15. [CORE] Which finding is consistent with the CTS criteria for well-controlled asthma?

a. Waking at night with cough two nights a week
b. Missing one day of work a month because of asthma
c. Using the reliever five times a week
d. Using the reliever once a week, with normal activity

Answer: d — The CTS criteria include reliever use 2 times a week or fewer and normal physical activity (section 14.2). Night symptoms should occur less than once a week. Any time lost from work because of asthma means it is not well controlled. Reliever use five times a week exceeds the limit.

16. [RN] A patient with severe asthma has been breathing at 34 breaths/min for several hours. An arterial blood gas now shows a PaCO2 of 42 mm Hg. How should the RN interpret this result?

a. Reassuring, because the value lies within the normal range
b. A warning sign that the patient is tiring and may be developing respiratory failure
c. Evidence that the bronchodilator treatment has been effective
d. Expected in asthma, because carbon dioxide is retained in all exacerbations

Answer: b — Early in an attack, fast breathing lowers PaCO2; a "normal" value in a patient who has been breathing fast for hours suggests fatigue and is a life-threatening sign, and a rising value signals near-fatal asthma (section 14.2; Chapter 3, section 3.7). A normal number is not reassuring in this context. It reflects ventilation, not proof of bronchodilator effect. Carbon dioxide is usually low, not retained, in early exacerbations.

17. [RN] An 82-year-old patient with asthma is being discharged after a severe exacerbation. She is weak and short of breath, and her prescriber is choosing a new ICS-containing inhaler. Which device is the best fit for now?

a. A dry powder inhaler, because it has no propellant
b. A soft mist inhaler without teaching, because it needs no coordination
c. A pressurized metered-dose inhaler with a valved holding chamber
d. A dry powder inhaler with instructions to breathe in more forcefully

Answer: c — Older age and a recent exacerbation make low inspiratory flow more likely; a pMDI with a valved holding chamber needs only a slow breath and no precise timing (section 14.3). A DPI depends on a forceful breath she may not manage, and telling her to try harder does not fix weak inspiratory flow. Every device needs teaching and observed practice; a soft mist inhaler still requires pressing the button during a slow breath.

Case: Mrs. Agnes Kowalczyk (Questions 18–23): Mrs. Agnes Kowalczyk, 76, lives alone in Belleville, Ontario, and has COPD treated with a LAMA/LABA inhaler and a salbutamol inhaler as needed. She smokes about 10 cigarettes a day. She comes to the emergency department after 3 days of worsening breathlessness and a cough now producing thick yellow-green sputum. Her respiratory rate is 30 breaths/min, heart rate 108 beats/min, blood pressure 148/86 mm Hg, temperature 37.9 °C and SpO2 85% on room air. She is sitting forward with her hands on her knees, using her neck muscles to breathe, and speaks in short phrases. She is admitted to a medical unit.

18. [CORE] The nurse reviews Mrs. Kowalczyk's assessment. Which findings need the nurse's immediate attention?

a. Temperature 37.9 °C and blood pressure 148/86 mm Hg
b. Daily smoking and living alone
c. SpO2 85%, respiratory rate 30 breaths/min and use of neck muscles to breathe
d. Thick yellow-green sputum and a 3-day history of symptoms

Answer: c — Low oxygen saturation, fast breathing and accessory muscle use show hypoxemia and increased work of breathing, which threaten her now (section 14.4, Acute Exacerbations in Hospital; Table 14.3). A mild fever and a modest rise in blood pressure (a) need follow-up but are not immediately dangerous. Smoking and living alone (b) matter for discharge planning and cessation support, not for immediate safety. Sputum change and the time course (d) help explain the cause but are not the most urgent cues.

19. [CORE] Which explanation best fits the change in Mrs. Kowalczyk's sputum together with her worsening breathlessness?

a. An acute exacerbation of COPD, probably triggered by a respiratory infection
b. Expected day-to-day variation in stable COPD
c. A side effect of her LAMA/LABA inhaler
d. Heart failure causing pink, frothy sputum

Answer: a — An exacerbation is an acute worsening of breathlessness, cough and sputum over a few days, and infections are among the most frequent triggers (section 14.4; GOLD, 2025); purulent sputum supports infection. Her change is outside her usual pattern, so it is not normal variation (b). Long-acting bronchodilators do not cause purulent sputum (c). Heart failure can cause breathlessness, but its classic sputum is pink and frothy, not yellow-green (d), although the team still considers it.

20. [CORE] Mrs. Kowalczyk is placed on oxygen at 4 L/min by nasal cannula. Two hours later her SpO2 is 97%, and she is hard to rouse and mumbling. Which problem is the nurse's highest priority?

a. Anxiety related to breathlessness

b. Rising carbon dioxide from more oxygen than her target allows

c. Dehydration from fast breathing

d. Pain from coughing

Answer: b — In a patient at risk of hypercapnia, SpO2 above the 88% to 92% target with new drowsiness points to rising CO2, a life-threatening problem (section 14.4, Going Deeper; Table 14.3). Anxiety (a) does not cause someone to become hard to rouse. Dehydration (c) and pain (d) may need attention but do not explain sudden drowsiness and are less urgent.

21. [CORE] Which set of orders would the nurse expect for Mrs. Kowalczyk's exacerbation, based on current guidance?

a. An inhaled corticosteroid on its own, oral theophylline, and oxygen titrated to SpO2 94% to 98%

b. Oral prednisone for 14 days, no antibiotic until an X-ray confirms pneumonia, and oxygen titrated to SpO2 100%

c. An antibiotic only, with all bronchodilators held until the sputum culture and sensitivity results return

d. Short-acting bronchodilators, up to 5 days of a systemic corticosteroid, an antibiotic, and oxygen to SpO2 88% to 92%

Answer: d — GOLD advises short-acting bronchodilators first, a systemic corticosteroid course of no more than 5 days and, for patients with purulent sputum such as hers, a 5-day antibiotic course; guidelines suggest 88% to 92% for patients at risk of hypercapnia (section 14.4). An ICS alone and theophylline (a) are not recommended in COPD, and 94% to 98% is too high a target for her. A 14-day steroid course and a target of 100% (b) exceed guidance and risk harm. Bronchodilators are never held while awaiting cultures (c).

22. [CORE] The nurse finds Mrs. Kowalczyk drowsy with SpO2 97% on 4 L/min. Her order is for oxygen titrated to SpO2 88% to 92%. What should the nurse do first?

a. Remove the oxygen completely and wait for her to wake up before reassessing her breathing.

b. Increase the oxygen flow, because new drowsiness in COPD usually means worsening hypoxemia.

c. Lower the oxygen within the order to reach the target range, assess her, and call for urgent help.

d. Document the finding, notify her family and recheck her level of consciousness in 1 hour.

Answer: c — The nurse lowers oxygen within the order to the target range, assesses her and escalates at once, expecting an ABG (section 14.4; Table 14.3; Chapter 6). Stopping oxygen abruptly (a) can cause dangerous rebound hypoxemia. Her SpO2 is already above target, so more oxygen (b) would worsen CO2 retention. Documenting and waiting an hour (d) delays care for a deteriorating patient.

23. [CORE] On day 4, Mrs. Kowalczyk is preparing for discharge. Which finding best shows that the plan is working?

a. She correctly demonstrates her inhaler technique and describes when to use her action plan.

b. She asks for her oxygen to be turned up "to be safe."

c. She says she will start pulmonary rehabilitation "if things get worse again."

d. She plans to cut down to five cigarettes a day and decline follow-up calls.

Answer: a — Correct technique and understanding of the action plan are key outcomes before going home (section 14.4, Transitions home; section 14.3). Wanting more oxygen (b) suggests a misunderstanding of her target. Pulmonary rehabilitation (c) is recommended soon after a hospitalized exacerbation, not only if she worsens. Cutting down without support (d) shows the cessation plan is not yet working; the nurse continues to offer support.

24. [CORE] A nurse is supporting a hospitalized patient who smokes. Which actions reflect evidence-based cessation support? Select all that apply.

a. Asking about smoking, vaping and other tobacco use on admission and documenting the answer

b. Offering nicotine replacement therapy under an order or medical directive to manage withdrawal

c. Telling the patient that repeated relapse shows they are not ready to quit

d. Arranging follow-up support after discharge, such as a quit service or follow-up calls

e. Referring to the patient as "a smoker" in the chart to make the risk clear

f. Including the patient's preferences when choosing among medications

Answer: a, b, d, f — Screening and documenting all tobacco use (a), treating withdrawal with NRT (b), linking to follow-up (d) and shared decision-making (f) are part of the Ottawa Model, the RNAO guideline and the Task Force recommendations (section 14.5). Relapse is common and many people need several attempts, so blaming the patient (c) is wrong. Stigma-free, person-first language such as "a person who smokes" is used instead of "a smoker" (e) (Chapter 11).

25. [CORE] A patient with COPD and no oxygen target written is admitted with an exacerbation. The nurse calls the prescriber for an order. Which target range does the nurse expect?

a. 94% to 98%

b. 88% to 92%

c. 92% to 96%

d. 80% to 85%

Answer: b — For patients at risk of hypercapnic respiratory failure, including those with COPD, guidelines suggest 88% to 92% (section 14.4; Chapter 12). The ranges of 94% to 98% (a, British guideline) and 92% to 96% (c, Australian and New Zealand position statement) are for most other acutely ill adults. A range of 80% to 85% (d) is too low and risks hypoxemia.

26. [CORE] A patient with COPD is being discharged after a hospital stay for an exacerbation. Which statement about pulmonary rehabilitation should the nurse include in teaching?

a. "Rehabilitation programs are meant only for people who already need oxygen at home."

b. "It is safest to wait at least 3 months after this flare-up before you start a program."

c. "Starting a program soon after you leave hospital can lower your chance of coming back."

d. "Rehabilitation works mainly by adjusting the doses of your inhalers to suit your activity."

Answer: c — Pulmonary rehabilitation started within 3 weeks of discharge reduces readmissions, and it is strongly recommended after a hospitalized exacerbation (section 14.4; Rochester et al., 2023). It is not limited to people on oxygen (a). Waiting months (b) misses the recommended window. Rehabilitation is exercise training, education and behaviour change, not inhaler dose changes (d).

27. [CORE] A patient wearing a nicotine patch ordered under a medical directive tells the nurse, "I still get strong cravings every couple of hours." What is the nurse's best response?

a. Remove the patch, because ongoing cravings show that nicotine replacement is not working for this patient.

b. Suggest switching to vaping, because e-cigarettes relieve cravings faster than any form of NRT.

c. Advise the patient to step outside for one cigarette whenever a strong craving occurs.

d. Check the directive or ask the prescriber about adding a short-acting NRT form for cravings.

Answer: d — Inpatient algorithms, such as Alberta's, pair a patch with a short-acting form of NRT to relieve sudden cravings (section 14.5; Table 14.4). Removing the patch (a) would worsen withdrawal. The Task Force suggests against e-cigarettes for cessation except in certain circumstances, and the guidance cited in this chapter does not compare how fast vaping and NRT relieve cravings (b). Smoking (c) undermines the quit attempt.

28. [CORE] A patient with known obstructive sleep apnea is on the surgical unit after a hip replacement and is receiving an opioid for pain. Which action is most important?

a. Use CPAP whenever the patient sleeps, and monitor sedation and breathing around each opioid dose.

b. Store the CPAP machine until discharge so that it does not interfere with postoperative care.

c. Give opioid doses while the patient is asleep so that rest is not interrupted by pain assessments.

d. Rely on continuous SpO2 alone, because a normal reading rules out slow or shallow breathing.

Answer: a — People with OSA are at greater risk of breathing complications from opioids, so they use CPAP during sleep and are monitored for sedation and slow breathing (section 14.6, Clinical Safety box; Chapter 5, section 5.4). Storing the CPAP (b) raises the risk of obstruction during sleep. Giving opioids to a sleeping patient (c) bypasses sedation assessment. A patient on oxygen can have a normal SpO2 while CO2 rises, so SpO2 alone is not enough (d).

29. [CORE] A patient with idiopathic pulmonary fibrosis starts pirfenidone. Which teaching point should the nurse include?

a. Take it on an empty stomach for better absorption.

b. Avoid sun exposure and use a high-protection sunscreen.

c. The drug will reverse the scarring in the lungs within months.

d. Smoking will not affect the drug.

Answer: b — Pirfenidone commonly causes rash and photosensitivity, so patients avoid the sun and use sunscreen (section 14.6). It is taken with food to reduce nausea and dizziness (a). Antifibrotics slow the decline in lung function; they do not reverse scarring (c). Smoking lowers pirfenidone levels, and patients are asked to stop before starting it (d).

30. [CORE] An RPN on a medical unit cares for a patient with COPD who has an order for oxygen titrated to SpO2 88% to 92%. The patient's oxygen needs have risen from 1 L/min to 4 L/min over the shift, and the patient now seems more confused. What should the RPN do?

a. Keep increasing the oxygen within the order as needed and reassess the patient at the end of the shift.

b. Note the trend and wait for the respiratory therapist's next scheduled visit to review the oxygen.

c. Act at once to assess and escalate, and consult the RN about the patient's changing needs.

d. Stop the oxygen for a short trial to see whether the patient's confusion improves on room air.

Answer: c — Every nurse who notices deterioration acts at once and escalates, and the RPN consults the RN as the patient's needs change (section 14.6, Scope in Practice box; Chapter 6). Continuing to titrate without escalating (a) ignores a deteriorating trend. Waiting for a scheduled visit (b) delays care. Stopping oxygen, even briefly (d), can cause dangerous rebound hypoxemia.

31. [CORE] A patient with bronchiectasis asks why the physiotherapist wants her to do airway clearance every day, even when she feels well. Which response by the nurse is most accurate?

a. "Airway clearance is needed only during a chest infection, when there is extra mucus to remove."

b. "Doing it every day means you will not need antibiotics if you have a flare-up later."

c. "Airway clearance is mainly a way to measure how well your lungs are working at home."

d. "Damaged airways clear mucus poorly; daily clearance helps break the cycle of infection and damage."

Answer: d — In bronchiectasis, damaged airways clear mucus poorly, which leads to infection, inflammation and further damage; airway clearance is recommended for most patients (section 14.6; Chalmers et al., 2025). It is routine, not only during infection (a). It does not replace antibiotics during exacerbations (b). It is a treatment, not a measurement (c).

32. [CORE] A First Nations patient with COPD is offered cessation support and says, "I use tobacco in ceremony. I don't want to give that up." What is the nurse's best response?

a. "All tobacco harms the lungs, so ceremonial use will need to stop as well."

b. "If you want to keep using tobacco, you may not be ready for cessation support yet."

c. "You will need to decide between your ceremonies and your lung health."

d. "This support is about cigarettes and other commercial tobacco. Tell me about your smoking."

Answer: d — Traditional tobacco used in ceremony is different from commercial tobacco, and cessation support addresses commercial tobacco while respecting ceremony (section 14.5). Options a and c dismiss a sacred practice and are not culturally safe. Option b wrongly closes the door on support the patient may want.

33. [RN] A patient with severe COPD who is known to retain CO2 has these ABG results during an exacerbation: pH 7.25, PaCO2 82 mm Hg, HCO3− 35 mmol/L. How should the nurse interpret them?

a. Compensated respiratory acidosis at the patient's usual baseline

b. Metabolic alkalosis with respiratory compensation

c. Acute respiratory acidosis on top of chronic CO2 retention

d. Metabolic acidosis

Answer: c — The high HCO3− reflects long-standing kidney compensation for chronic CO2 retention, while the low pH shows a new, acute rise in CO2 that the kidneys have not matched: acute-on-chronic respiratory acidosis needing urgent escalation (section 14.4, Going Deeper). A compensated state (a) would have a near-normal pH. Metabolic alkalosis (b) needs a high pH. Metabolic acidosis (d) would show a low HCO3−.

34. [RN] A patient asks about bupropion (Zyban) to help quit smoking. Which history should the nurse report to the prescriber before it is started?

a. A history of seizures

b. Mild seasonal allergies

c. Use of a salbutamol inhaler as needed

d. A previous attempt to quit with NRT

Answer: a — The Canadian monograph lists seizures, whether current or in the past, as a contraindication, and the seizure risk rises with dose (section 14.5; Table 14.4). Seasonal allergies (b) and as-needed salbutamol (c) are not contraindications. A previous NRT attempt (d) is common and does not prevent use of bupropion.

35. [RN] According to the CTS 2023 guideline, which patient with stable COPD is the best candidate for LAMA/LABA/ICS triple therapy?

a. A patient with a CAT score of 6 and no exacerbations in the past year

b. A patient with a CAT score of 18, an FEV1 of 55% predicted and one hospital admission for an exacerbation in the past year

c. A patient with mild symptoms who wants an ICS on its own

d. A patient with a CAT score of 12 and one exacerbation treated at home with oral prednisone in the past year

Answer: b — The CTS recommends triple therapy for people at high exacerbation risk (two or more moderate or at least one severe exacerbation in the past year) with moderate to high symptoms and impaired lung function; one hospitalization counts as severe (section 14.4). A patient with low symptoms and no exacerbations (a) is at low risk and would usually start one long-acting bronchodilator. ICS on its own (c) is not recommended. One moderate exacerbation (d) is low risk, so LAMA/LABA dual therapy is the starting choice.

References

Abdo, W. F., & Heunks, L. M. A. (2012). Oxygen-induced hypercapnia in COPD: Myths and facts. *Critical Care, 16*(5), Article 323. https://doi.org/10.1186/cc11475

Alberta Health Services. (2025). *Tobacco and vaping assessment toolkit: AHS pharmacotherapy algorithm – adult inpatient*. https://www.albertahealthservices.ca/assets/info/trp/if-trp-tct-ahs-pharmacotherapy-algorithm.pdf

AstraZeneca Canada. (2021). *Symbicort Turbuhaler (budesonide/formoterol fumarate dihydrate) product monograph*. https://pdf.hres.ca/dpd_pm/00061466.PDF

Auro Pharma. (2025). *Auro-Varenicline (varenicline tartrate tablets) product monograph*. https://pdf.hres.ca/dpd_pm/00078269.PDF

Ayas, N., Skomro, R., Blackman, A., Curren, K., Fitzpatrick, M., Fleetham, J., George, C., Hakemi, T., Hanly, P., Li, C., Morrison, D., & Series, F. (2014). Obstructive sleep apnea and driving: A Canadian Thoracic Society and Canadian Sleep Society position paper. *Canadian Respiratory Journal, 21*(2), 114–123. https://cts-sct.ca/wp-content/uploads/2018/02/1-CTS_CSS_Position_Paper_OSA_Driving_2014.pdf

Barnett, A., Beasley, R., Buchan, C., Chien, J., Farah, C. S., King, G., McDonald, C. F., Miller, B., Munsif, M., Psirides, A., Reid, L., Roberts, M., Smallwood, N., & Smith, S. (2022). Thoracic Society of Australia and New Zealand position statement on acute oxygen use in adults: "Swimming between the flags". *Respirology, 27*(4), 262–276. https://doi.org/10.1111/resp.14218

Bausch Health. (2023). *Zyban (bupropion hydrochloride) extended-release tablets product monograph*. https://pdf.hres.ca/dpd_pm/00073768.PDF

Bird, Y., Moraros, J., Mahmood, R., Esmaeelzadeh, S., & Kyaw Soe, N. M. (2017). Prevalence and associated factors of COPD among Aboriginal peoples in Canada: A cross-sectional study. *International Journal of Chronic Obstructive Pulmonary Disease, 12*, 1915–1922. https://doi.org/10.2147/COPD.S138304

Boehringer Ingelheim. (2019). *Spiriva Respimat (tiotropium bromide monohydrate) product monograph*. https://pdf.hres.ca/dpd_pm/00051030.PDF

Boehringer Ingelheim. (2024). *Ofev (nintedanib) capsules product monograph*. https://pdf.hres.ca/dpd_pm/00077134.PDF

Bourbeau, J., Bhutani, M., Hernandez, P., Aaron, S. D., Beauchesne, M.-F., Kermelly, S. B., D'Urzo, A., Lal, A., Maltais, F., Marciniuk, J. D., Mulpuru, S., Penz, E., Sin, D. D., Van Dam, A., Wald, J., Walker, B. L., & Marciniuk, D. D. (2023). 2023 Canadian Thoracic Society guideline on pharmacotherapy in patients with stable COPD. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 7*(4), 173–191. https://doi.org/10.1080/24745332.2023.2231451

British Thoracic Society & Scottish Intercollegiate Guidelines Network. (2019). *British guideline on the management of asthma (SIGN 158): Management of acute asthma in adults in hospital*. https://rightdecisions.scot.nhs.uk/asthma-pathway-bts-nice-sign-sign-244/managing-acute-asthma/management-of-acute-asthma-in-adults/asthma-management-algorithms-for-adults/management-of-acute-asthma-in-adults-in-hospital

Canadian Cancer Society. (n.d.). *About Talk Tobacco*. Retrieved October 25, 2026, from https://ccsshouat.cancer.ca/talktobacco/about/about-tt

Canadian Institute for Health Information. (2025, February 20). *Hospitalizations in Canada remained stable in 2023–2024* [News release]. https://www.cihi.ca/en/news/hospitalizations-in-canada-remained-stable-in-2023-2024

Canadian Thoracic Society. (2026, September). *CTS guideline for the management of severe asthma in children, adolescents and adults* [Guideline library listing]. https://cts-sct.ca/guideline-library/

Chalmers, J. D., Haworth, C. S., Flume, P., Long, M. B., Burgel, P. R., Dimakou, K., Blasi, F., Herrero-Cortina, B., Dhar, R., Chotirmall, S. H., Ringshausen, F. C., Altenburg, J., Morgan, L., Nigro, M., Crichton, M. L., Van Meel, C., Sibila, O., Timothy, A., Kompatsiari, E., … Aliberti, S. (2025). European Respiratory Society clinical practice guideline for the management of adult bronchiectasis. *European Respiratory Journal, 66*(6), Article 2501126. https://doi.org/10.1183/13993003.01126-2025

Chung, F., Abdullah, H. R., & Liao, P. (2016). STOP-Bang questionnaire: A practical approach to screen for obstructive sleep apnea. *Chest, 149*(3), 631–638. https://doi.org/10.1016/j.chest.2015.08.012

Coates, A. L., Graham, B. L., McFadden, R. G., McParland, C., Moosa, D., Provencher, S., & Road, J. (2013). Spirometry in primary care. *Canadian Respiratory Journal, 20*(1), 13–22. https://cts-sct.ca/wp-content/uploads/2018/01/Spirometry-in-Primary-Care_CRJ-Jan-Feb-2013.pdf

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Respiratory Therapists of Ontario. (2022). *Oxygen therapy clinical best practice guideline*. https://oxygen.crto.on.ca/oxygen-therapy/

College of Respiratory Therapists of Ontario. (2024). *Orders for medical care* [Professional practice guideline]. https://orders.crto.on.ca/wp-content/uploads/sites/13/2024/10/Orders-for-Medical-Care-PPG-2024-09-13.pdf

Farley, K. J., & Licari, E. (2019). A structured approach to acid–base interpretation. *Medical Journal of Australia, 211*(7), 308–311.e1. https://doi.org/10.5694/mja2.50344

First Nations Health Authority. (n.d.). *Respecting tobacco* [Brochure]. https://www.fnha.ca/Documents/FNHA-Respecting-Tobacco-Brochure.pdf

First Nations Information Governance Centre. (n.d.). *The First Nations principles of OCAP®*. Retrieved October 24, 2026, from https://fnigc.ca/ocap-training/

GlaxoSmithKline. (2025). *Ventolin HFA (salbutamol) patient medication information*. https://ca.gsk.com/media/6435/ventolin-hfa-part-iii.pdf

Global Initiative for Asthma. (2026). *Summary guide for asthma management and prevention, for adults, adolescents and children 6–11 years*. https://ginasthma.org/wp-content/uploads/2026/07/GINA-Summary-Guide-2026-WEB-WMS.pdf

Global Initiative for Chronic Obstructive Lung Disease. (2025). *Global strategy for prevention, diagnosis and management of COPD: 2026 report*. https://goldcopd.org/wp-content/uploads/2026/01/GOLD-REPORT-2026-v1.3-8Dec2025_WMV2.pdf

Gupta, S., Couillard, S., Digby, G., Tse, S. M., Green, S., Aceron, R., Carlsten, C., Hubick, J., & Penz, E. (2023). Canadian Thoracic Society position statement on climate change and choice of inhalers for patients with respiratory disease. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 7*(5), 232–239. https://doi.org/10.1080/24745332.2023.2254283

Health Canada. (2023). *Canadian Tobacco and Nicotine Survey (CTNS): Summary of results for 2022*. https://www.canada.ca/en/health-canada/services/canadian-tobacco-nicotine-survey/2022-summary.html

Health Canada. (2024). *Quit with confidence: Deciding to quit*. https://www.canada.ca/en/health-canada/services/smoking-tobacco/quit-smoking.html

Health Canada. (2026a). *Risks of vaping*. https://www.canada.ca/en/health-canada/services/smoking-tobacco/vaping/risks.html

Health Canada. (2026b). *Wildfire smoke and your health*. https://www.canada.ca/en/health-canada/services/publications/healthy-living/wildfire-smoke-health.html

JAMP Pharma. (2023). *JAMP Ipratropium HFA (ipratropium bromide) product monograph*. https://pdf.hres.ca/dpd_pm/00073101.PDF

Kew, K. M., Kirtchuk, L., & Michell, C. I. (2014). Intravenous magnesium sulfate for treating adults with acute asthma in the emergency department. *Cochrane Database of Systematic Reviews, 2014*(5), Article CD010909. https://doi.org/10.1002/14651858.CD010909.pub2

Marciniuk, D. D., Goodridge, D., Hernandez, P., Rocker, G., Balter, M., Bailey, P., Ford, G., Bourbeau, J., O'Donnell, D. E., Maltais, F., Mularski, R. A., Cave, A. J., Mayers, I., Kennedy, V., Oliver, T. K., Brown, C., & Canadian Thoracic Society COPD Committee Dyspnea Expert Working Group. (2011). Managing dyspnea in patients with advanced chronic obstructive pulmonary disease: A Canadian Thoracic Society clinical practice guideline. *Canadian Respiratory Journal, 18*(2), 69–78. https://doi.org/10.1155/2011/745047

Memtsoudis, S. G., Cozowicz, C., Nagappa, M., Wong, J., Joshi, G. P., Wong, D. T., Doufas, A. G., Yilmaz, M., Stein, M. H., Krajewski, M. L., Singh, M., Pichler, L., Ramachandran, S. K., & Chung, F. (2018). Society of Anesthesia and Sleep Medicine guideline on intraoperative management of adult patients with obstructive sleep apnea. *Anesthesia & Analgesia, 127*(4), 967–987. https://doi.org/10.1213/ANE.0000000000003434

Mullen, K. A., Manuel, D. G., Hawken, S. J., Pipe, A. L., Coyle, D., Hobler, L. A., Younger, J., Wells, G. A., & Reid, R. D. (2017). Effectiveness of a hospital-initiated smoking cessation programme: 2-year health and healthcare outcomes. *Tobacco Control, 26*(3), 293–299. https://doi.org/10.1136/tobaccocontrol-2015-052728

O'Driscoll, B. R., Howard, L. S., Earis, J., & Mak, V. (2017). British Thoracic Society guideline for oxygen use in adults in healthcare and emergency settings. *BMJ Open Respiratory Research, 4*(1), Article e000170. https://doi.org/10.1136/bmjresp-2016-000170

Public Health Agency of Canada. (2018). *Asthma and chronic obstructive pulmonary disease (COPD) in Canada, 2018*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/asthma-chronic-obstructive-pulmonary-disease-canada-2018.html

Raghu, G., Remy-Jardin, M., Myers, J. L., Richeldi, L., Ryerson, C. J., Lederer, D. J., Behr, J., Cottin, V., Danoff, S. K., Morell, F., Flaherty, K. R., Wells, A., Martinez, F. J., Azuma, A., Bice, T. J., Bouros, D., Brown, K. K., Collard, H. R., Duggal, A., … Wilson, K. C. (2018). Diagnosis of idiopathic pulmonary fibrosis: An official ATS/ERS/JRS/ALAT clinical practice guideline. *American Journal of Respiratory and Critical Care Medicine, 198*(5), e44–e68. https://doi.org/10.1164/rccm.201807-1255ST

Registered Nurses' Association of Ontario. (2017). *Integrating tobacco interventions into daily practice* (3rd ed.). https://rnao.ca/bpg/guidelines/integrating-tobacco-interventions-daily-practice

Rochester, C. L., Alison, J. A., Carlin, B., Jenkins, A. R., Cox, N. S., Bauldoff, G., Bhatt, S. P., Bourbeau, J., Burtin, C., Camp, P. G., Cascino, T. M., Dorney Koppel, G. A., Garvey, C., Goldstein, R., Harris, D., Houchen-Wolloff, L., Limberg, T., Lindenauer, P. K., Moy, M. L., … Holland, A. E. (2023). Pulmonary rehabilitation for adults with chronic respiratory disease: An official American Thoracic Society clinical practice guideline. *American Journal of Respiratory and Critical Care Medicine, 208*(4), e7–e26. https://doi.org/10.1164/rccm.202306-1066ST

Rochwerg, B., Brochard, L., Elliott, M. W., Hess, D., Hill, N. S., Nava, S., Navalesi, P., Antonelli, M., Brozek, J., Conti, G., Ferrer, M., Guntupalli, K., Jaber, S., Keenan, S., Mancebo, J., Mehta, S., & Raoof, S. (2017). Official ERS/ATS clinical practice guidelines: Noninvasive ventilation for acute respiratory failure. *European Respiratory Journal, 50*(2), Article 1602426. https://doi.org/10.1183/13993003.02426-2016

Sandoz Canada. (2024). *Sandoz Pirfenidone (pirfenidone) capsules and tablets product monograph*. https://pdf.hres.ca/dpd_pm/00076662.PDF

Stanojevic, S., Kaminsky, D. A., Miller, M. R., Thompson, B., Aliverti, A., Barjaktarevic, I., Cooper, B. G., Culver, B., Derom, E., Hall, G. L., Hallstrand, T. S., Leuppi, J. D., MacIntyre, N., McCormack, M., Rosenfeld, M., & Swenson, E. R. (2022). ERS/ATS technical standard on interpretive strategies for routine lung function tests. *European Respiratory Journal, 60*(1), Article 2101499. https://doi.org/10.1183/13993003.01499-2021

Thombs, B. D., Traversy, G., Reynolds, D. L., Lang, E., Groulx, S., & Wilson, B. J. (2025). Recommendations on interventions for tobacco smoking cessation in adults in Canada. *CMAJ, 197*(28), E846–E861. https://doi.org/10.1503/cmaj.241584

Yang, C. L., Hicks, E. A., Mitchell, P., Reisman, J., Podgers, D., Hayward, K. M., Waite, M., & Ramsey, C. D. (2021). Canadian Thoracic Society 2021 guideline update: Diagnosis and management of asthma in preschoolers, children and adults. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 5*(6), 348–361. https://doi.org/10.1080/24745332.2021.1945887

15 Acute Respiratory Failure and Pulmonary Embolism

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Distinguish hypoxemic from hypercapnic respiratory failure, link causes to findings, and recognize impending failure early.
2. Explain acute respiratory distress syndrome (ARDS) and the nursing care that supports lung-protective treatment, including prone positioning.
3. Care safely for patients on non-invasive ventilation and invasive mechanical ventilation, including preventing ventilator-associated complications.
4. Recognize pneumothorax, including tension pneumothorax, and respond as an emergency.
5. Assess and maintain chest drainage systems and respond to problems.
6. Recognize, help diagnose and care for patients with pulmonary embolism.
7. Teach patients and families during recovery from critical respiratory illness and after a pulmonary embolism.
8. Distinguish RN and RPN roles in these settings using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 4, 6	Clinician; Scholar	Foundations of Practice
3, 5	Clinician; Collaborator; Coordinator	Foundations of Practice; Collaborative Practice
7, 8	Educator; Professional	Collaborative Practice; Legal Practice

Introduction

Acute respiratory failure happens when the lungs can no longer keep the oxygen and carbon dioxide in the blood within safe limits. It can follow almost any serious illness, from pneumonia or a flare of chronic obstructive pulmonary disease (COPD) to an opioid overdose or major surgery. Nurses on medical-surgical units are often the first to see it develop, and many of these patients need critical care. In 2013–2014, time in an intensive care unit (ICU) was part of 11% of hospital stays by adults in Canada (excluding Quebec), and invasive ventilation was used for 33% of ICU patients (Canadian Institute for Health Information [CIHI], 2016). A pulmonary embolism (PE), a clot blocking blood flow in the lungs, can strike a patient who seemed to be recovering.

Sections 15.1 to 15.6 cover acute respiratory failure, acute respiratory distress syndrome, non-invasive and mechanical ventilation, pneumothorax and chest injury, chest tubes and chest drainage, and PE. Related topics live elsewhere:

- acid–base balance and blood gases (Chapter 3, section 3.7);
- sepsis and infection prevention and control (IPAC) (Chapter 4);
- early warning scores, rapid response and shock (Chapter 6);
- preventing venous thromboembolism (VTE) after surgery (Chapter 7);
- respiratory assessment and oxygen therapy (Chapter 12);
- pneumonia (Chapter 13), and asthma and COPD (Chapter 14);
- deep vein thrombosis and anticoagulation (Chapter 19).

15.1 Acute Respiratory Failure

Two Kinds of Failure

The lungs have two jobs: to move oxygen into the blood and to move carbon dioxide (CO_2) out. Respiratory failure is classed by which job fails. Many patients have elements of both.

In **hypoxemic respiratory failure (type 1)**, oxygenation fails. The British Thoracic Society (BTS) defines it as an arterial partial pressure of oxygen (PaO_2) below 60 mm Hg (8 kPa), roughly equal to an arterial oxygen saturation of 90%, with a normal or low arterial partial pressure of carbon dioxide ($PaCO_2$) (O'Driscoll et al., 2017). Breathing still clears CO_2, but blood leaves the lungs short of oxygen. Chapter 12 (section 12.1) explains the mechanisms:

- **Ventilation–perfusion (V/Q) mismatch:** some areas of lung get blood but too little air. It is the most common cause of low blood oxygen, and extra oxygen usually corrects it (Sarkar et al., 2017).
- **Shunt:** blood flows past alveoli that are collapsed or filled with fluid or pus, so it picks up no oxygen at all. Because the extra oxygen never reaches that blood, hypoxemia from shunt responds poorly to oxygen therapy (Sarkar et al., 2017).
- **Diffusion limitation:** a thickened or damaged alveolar membrane slows the passage of oxygen.

Pneumonia (Chapter 13), acute respiratory distress syndrome (ARDS; section 15.2), pulmonary edema (Chapter 18) and PE (section 15.6) are common causes.

In **hypercapnic respiratory failure (type 2)**, ventilation fails: not enough air moves in and out to clear CO_2, and $PaCO_2$ rises (O'Driscoll et al., 2017). The BTS counts a $PaCO_2$ above the normal range as hypercapnia (its guideline gives about 34–46 mm Hg; Chapter 3 uses 35–45 mm Hg, and ranges vary by laboratory), and a patient with a high $PaCO_2$ has type 2 failure even when the oxygen saturation measured by pulse oximetry (SpO_2) is normal (O'Driscoll et al., 2017). CO_2 forms acid in the blood, so a sudden rise lowers the pH. Oxygen often falls as well. Causes fall into four groups:

- **Reduced drive to breathe:** opioids, sedatives and other central nervous system depressants (Chapter 5, section 5.4; Chapter 11).
- **Weak breathing muscles or nerves:** neuromuscular diseases such as Guillain–Barré syndrome and myasthenia gravis (Chapter 32).
- **Chest wall problems:** chest wall deformity and severe obesity (O'Driscoll et al., 2017; Davidson et al., 2016).
- **Airway disease:** COPD and severe asthma, where narrowed airways trap air and the breathing muscles tire (Chapter 14).

Timing matters as much as type. **Acute** failure develops over minutes to days, so the body has no time to adapt. **Chronic** respiratory failure develops over months or years, as in some people with advanced COPD; the kidneys keep extra bicarbonate, which brings the pH close to normal despite a high $PaCO_2$. **Acute-on-chronic** failure is a sudden worsening on top of a chronic problem, so the pH falls even though bicarbonate is high (Rochwerg et al., 2017). Chapter 14 shows these patterns on arterial blood gases (ABGs). Table 15.1 compares the two types.

Table 15.1 Hypoxemic and hypercapnic respiratory failure compared (Davidson et al., 2016; O'Driscoll et al., 2017; Rochwerg et al., 2017; Sarkar et al., 2017; original wording)

Feature	Hypoxemic (type 1)	Hypercapnic (type 2)
Main problem	Oxygen does not get into the blood well enough	Too little air moves in and out, so CO_2 builds up
ABG pattern	PaO_2 below about 60 mm Hg; $PaCO_2$ normal or low	$PaCO_2$ above the normal range; pH low if the rise is acute or acute-on-chronic; PaO_2 often low too
Common causes	Pneumonia, ARDS, pulmonary edema, PE, collapsed lung tissue	Opioids and sedatives, neuromuscular disease, chest wall disease, severe obesity, COPD or asthma exacerbation
Key early cues	Fast breathing, fast heart rate, restlessness, rising oxygen needs	Fast shallow breathing and hard work, or slow breathing after opioids; drowsiness, confusion

Feature	Hypoxemic (type 1)	Hypercapnic (type 2)
Main supports	Oxygen to the target range; high-flow nasal cannula; positive pressure; treating the cause	Controlled oxygen to the target range; treating the cause; bilevel non-invasive ventilation; reversing drug effects as ordered
Cautions	Shunt responds poorly to more oxygen; a rising oxygen need is a warning sign	A normal SpO2 does not rule it out; too much oxygen can raise PaCO2 in at-risk patients

Recognizing Failure Early

Respiratory failure rarely arrives without warning. The early cues show a body working hard to compensate:

- a rising respiratory rate and heart rate, which are more common in hypoxemia than cyanosis (O'Driscoll et al., 2017);
- more work of breathing: use of neck and shoulder muscles, flaring nostrils, speaking in short phrases, sitting forward to breathe;
- restlessness, anxiety or new confusion, which can be the first sign of low oxygen or high CO2 (O'Driscoll et al., 2017);
- needing more oxygen to stay in the target range (Chapter 12, section 12.4).

Late cues show that compensation is failing. The patient tires: breathing slows or becomes irregular, and the patient becomes drowsy, confused or hard to rouse. A rising CO2 causes drowsiness and, when severe, coma (O'Driscoll et al., 2017). The SpO2 falls even as oxygen is increased. In a patient with severe asthma, a quiet chest with faint air entry means that little air is moving (Chapter 14). **Central cyanosis**, a bluish or greyish colour of the tongue, lips and lining of the mouth, is a late and unreliable sign. On darker skin it may look grey or whitish rather than blue, so the nurse checks the tongue and oral mucosa in good light and never waits for colour change to act (Chapter 12, section 12.2).

Two traps deserve attention. First, pulse oximetry measures oxygen, not CO2. A patient on supplemental oxygen can show a normal SpO2 while the PaCO2 climbs (O'Driscoll et al., 2017). This is why a sleepy patient on opioids with a slow respiratory rate needs a full assessment, not just a glance at the oximeter (Chapter 5, section 5.4). Second, a patient who stops struggling is not necessarily improving.

Early warning scores combine these vital signs and help the nurse decide when to call for help; escalation and the rapid response team are covered in Chapter 6 (section 6.2). An ABG confirms the type of failure: a low PaO2 with a normal or low PaCO2 points to type 1, and a high PaCO2 with a low pH points to acute type 2. Chapter 3 (section 3.7) explains how to read a blood gas.

Nursing Care

The nurse uses the Clinical Judgment Measurement Model (CJMM) (Chapter 1, section 1.4).

Recognize and analyze cues. The nurse counts the respiratory rate for a full minute and looks at the patient's work of breathing, colour, level of consciousness and SpO2, then compares the findings with earlier ones. Trends matter more than a single value.

Prioritize hypotheses. The nurse asks three questions. Is this mainly a problem of oxygen, of CO2, or both? What is the likely cause, such as pneumonia, fluid overload, an opioid or a COPD flare? How fast is the patient getting worse?

Generate solutions and take action. Actions depend on the cause, the orders, and the nurse's role and setting:

- **Stay with the patient and call for help** when cues are worsening; use the escalation process in Chapter 6.
- **Position the patient upright,** if tolerated, to help the lungs expand (Chapter 12).
- **Give oxygen to the ordered target range.** Patients at risk of hypercapnic failure, such as those with COPD, usually have a target of 88–92% until blood gases are known (O'Driscoll et al., 2017). Oxygen is never withheld from a patient who is hypoxemic; it is adjusted to the target (Abdo & Heunks, 2012).
- **Report a rising oxygen need at once.** It may lead to high-flow nasal cannula (Chapter 12), non-invasive ventilation (section 15.3) or intubation.
- **Support airway clearance:** coughing, deep breathing and suctioning when needed (Chapter 12, section 12.5).
- **Treat the cause as ordered,** for example bronchodilators for a COPD flare (Chapter 14), antimicrobials for pneumonia (Chapter 13) or diuretics for heart failure (Chapter 18).

- **Reverse drug effects when ordered.** For opioid-induced respiratory depression, the nurse stops the opioid, stimulates the patient, supports breathing and gives naloxone according to the order, medical directive and policy (Chapter 5, section 5.4; Chapter 11).
- **Monitor closely:** continuous pulse oximetry, frequent respiratory rate and level of consciousness, and blood gases as ordered.
- **Communicate clearly.** The nurse reports findings to the most responsible provider or rapid response team using SBAR (Situation, Background, Assessment, Recommendation) (Chapter 6, section 6.2).

Goals of care. Before a crisis, the team needs to know what the patient wants. Would the patient want intubation and ICU care, or a trial of non-invasive ventilation only? The BTS advises agreeing on and documenting what will happen if non-invasive ventilation fails before it is started, involving the patient wherever possible (Davidson et al., 2016). The nurse prompts this conversation early and supports the patient and family through it (Chapter 10, section 10.2).

Evaluate outcomes. The nurse reassesses after every intervention. A falling respiratory rate with better alertness and a steady SpO2 suggests improvement. A falling respiratory rate with drowsiness suggests exhaustion or rising CO2.

CLINICAL JUDGMENT

Tiring on Non-invasive Ventilation

Names and details are fictional; this is a composite story.

Mr. Albert Nakamura, 70, has COPD and was admitted to a step-down unit with an exacerbation. Bilevel non-invasive ventilation (NIV), often called BiPAP, was started 2 hours ago. His first blood gas showed pH 7.30 and PaCO2 68 mm Hg. His written plan says he wants a trial of intubation if needed.

- **Recognize cues:** He is harder to rouse than an hour ago and is not following commands. His respiratory rate is 34 breaths/min, his SpO2 is 90% and air is leaking around the mask. The repeat ABG shows pH 7.24 and PaCO2 82 mm Hg.
- **Analyze cues:** His acidosis is worsening and his CO2 is rising despite NIV. A rising PaCO2 explains the drowsiness. Worsening pH and respiratory rate signal that NIV is failing (Davidson et al., 2016).
- **Prioritize hypotheses:** The main concern is hypercapnic failure that NIV is not reversing. A poor mask seal may add to it. A drowsy patient also risks aspiration.
- **Generate solutions:** call the physician and respiratory therapist now; check the mask fit; prepare for intubation and ICU transfer, in line with his stated wishes.
- **Take action:** The nurse stays with Mr. Nakamura, raises the head of the bed, refits the mask with the respiratory therapist and gives an SBAR report: "Mr. Nakamura is on BiPAP with a worsening ABG, rising respiratory rate and drowsiness. I recommend urgent bedside review for intubation." The nurse brings suction and the bag-valve mask to the bedside and updates his daughter.
- **Evaluate outcomes:** The physician confirms Mr. Nakamura's wishes with his daughter, and he is intubated and moved to the ICU within the hour.

15.2 Acute Respiratory Distress Syndrome

What ARDS Is

Acute respiratory distress syndrome (ARDS) is a sudden, widespread injury to both lungs that causes hypoxemic respiratory failure. It is not caused mainly by heart failure. In 2024, an international group of experts published a new global definition that builds on the earlier Berlin definition from 2012 (Matthay et al., 2024). The 2024 definition has four parts:

- **Risk factor and cause:** ARDS follows an acute trigger, such as pneumonia, infection outside the lungs, trauma, transfusion, aspiration or shock. The lung swelling is not mainly due to heart failure or fluid overload.
- **Timing:** hypoxemic respiratory failure begins or worsens within 1 week of the trigger or of new or worsening breathing symptoms.
- **Imaging:** opacities in both lungs on chest X-ray or computed tomography (CT), or matching findings on ultrasound, not fully explained by fluid around the lungs, collapse or masses.

- **Hypoxemia:** a ratio of PaO2 to the fraction of inspired oxygen (FiO2) of 300 mm Hg or less. Alternatively, a ratio of SpO2 to FiO2 of 315 or less can be used, but only when the SpO2 is 97% or lower.

The 2024 definition differs from Berlin in important ways (Matthay et al., 2024). It includes patients who are not intubated but are receiving high-flow nasal oxygen at 30 L/min or more, or non-invasive ventilation or continuous positive airway pressure (CPAP) of at least 5 cm H2O. It also allows pulse oximetry and ultrasound, so that ARDS can be recognized where blood gases and X-rays are not available. ARDS in intubated patients is graded mild, moderate or severe by the oxygen ratio (see the Going Deeper box in section 15.3), and patients may move between categories as the illness changes (Matthay et al., 2024).

In ARDS, inflammation damages the thin barrier between the alveoli and the capillaries. Fluid leaks into the air spaces even though the heart is working normally; this is **noncardiogenic pulmonary edema**. Flooded and collapsed alveoli receive blood but no air, creating a large shunt. That is why patients with ARDS stay hypoxemic despite high levels of oxygen (Sarkar et al., 2017). The injured lungs also become stiff and small, so each breath takes more pressure to deliver.

Causes include pneumonia (Chapter 13), sepsis (Chapter 4, section 4.6), aspiration of stomach contents (Chapter 13), major trauma, transfusion (Chapter 20) and shock (Chapter 6) (Matthay et al., 2024).

Supporting the Lungs

No drug cures ARDS. Care treats the cause and supports the lungs while they heal, without causing further injury.

Lung-protective ventilation means using small breaths and limited pressures to avoid overstretching the injured lung. A 2017 guideline from the American Thoracic Society (ATS), the European Society of Intensive Care Medicine and the Society of Critical Care Medicine strongly recommends small tidal volumes and limits on inspiratory pressure for all patients with ARDS (Fan et al., 2017). The 2024 ATS update suggests higher positive end-expiratory pressure (PEEP), without lung recruitment manoeuvres, for moderate to severe ARDS. It recommends against prolonged lung recruitment manoeuvres. It also makes conditional recommendations for corticosteroids, for neuromuscular blockers in early severe ARDS, and for extracorporeal membrane oxygenation (ECMO) for some carefully chosen patients whose ARDS is severe (Qadir et al., 2024). The Going Deeper box in section 15.3 gives the numbers.

Prone positioning means turning the ventilated patient onto the abdomen for long periods. In the prone position, more of the lung takes part in gas exchange. In the PROSEVA trial of 466 patients with severe ARDS, prone sessions of at least 16 hours a day lowered death at 28 days from 32.8% to 16.0% (Guérin et al., 2013). The 2017 guideline strongly recommends prone positioning for more than 12 hours a day in severe ARDS (Fan et al., 2017).

Proning is a planned team procedure:

- Before the turn, the team uses a safety checklist, secures the endotracheal tube, lines and drains, and has suction ready (González-Seguel et al., 2021).
- During the turn, one person at the head of the bed controls the airway and directs the move (González-Seguel et al., 2021).
- After the turn, the nurse confirms tube position and ventilation, and watches for drops in SpO2, low blood pressure and dysrhythmias, which are common adverse events (González-Seguel et al., 2021).
- While the patient is prone, the nurse protects the face, eyes, chest, knees and other pressure points. Pressure injuries and facial swelling are among the most frequent complications. Rotating the head and arms and repositioning about every 2 hours are commonly used strategies (González-Seguel et al., 2021). Chapter 35 covers pressure injury prevention.

Fluid management. In a large trial in acute lung injury, a conservative fluid strategy did not significantly change the death rate at 60 days. It did increase the number of days alive and off the ventilator, without causing more shock or failure of other organs (National Heart, Lung, and Blood Institute ARDS Clinical Trials Network, 2006). The nurse supports it with accurate intake and output and daily weights.

Recovery

Post-intensive care syndrome (PICS) is new or worse problems with physical, cognitive or mental health that begin after critical illness and last beyond the hospital stay (Needham et al., 2012). Survivors may face weakness, trouble with memory and

concentration, anxiety or low mood for months or years.

Families are affected too. In **post-intensive care syndrome–family (PICS-F)**, family members experience anxiety, acute stress, posttraumatic stress, depression or complicated grief, sometimes for more than four years (Davidson et al., 2012). How the team communicates with families and includes them in care and decisions may shape these outcomes (Davidson et al., 2012).

Nurses help prevent PICS from the first ICU day. They aim for light sedation, regular delirium screening and early mobility (Devlin et al., 2018), and they keep the family informed and involved. At discharge, the nurse explains that slow recovery is common and links the patient and family with follow-up visits, support groups or ICU follow-up clinics where they exist (Davidson et al., 2012).

15.3 Non-invasive and Mechanical Ventilation

Non-invasive Ventilation

Non-invasive ventilation (NIV) delivers breathing support through a tight-fitting mask rather than a tube in the airway (Figure 15.1). There are two main forms:

- **Continuous positive airway pressure (CPAP)** gives one steady pressure throughout the breath. It holds small airways and alveoli open and improves oxygenation.
- **Bilevel positive airway pressure** gives a higher pressure when the patient breathes in and a lower pressure when the patient breathes out. The extra push rests tired muscles and helps clear CO2; it is often called BiPAP, a brand name.

The evidence is strongest for two groups (Rochwerg et al., 2017):

- **COPD exacerbation with respiratory acidosis.** The European Respiratory Society (ERS) and ATS strongly recommend bilevel NIV when an exacerbation causes respiratory acidosis (pH 7.35 or lower), whether acute or acute-on-chronic. They suggest not using NIV for patients whose CO2 is high but whose pH is normal. The BTS advises starting NIV when a pH below 7.35 and a PaCO2 above 6.5 kPa (about 49 mm Hg) persist despite optimal medical treatment (Davidson et al., 2016).
- **Cardiogenic pulmonary edema.** The ERS and ATS strongly recommend either bilevel NIV or CPAP (Rochwerg et al., 2017; Chapter 18).

Figure 15.1 Non-invasive ventilation through a full face mask that covers the nose and mouth, connected to a ventilator. This is a posed demonstration; the person's eyes are pixelated. (credit: modification of "BIPAP" by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

NIV is safest when the patient can cooperate and keep the airway protected (Rochwerg et al., 2017). Caution is needed when the patient has a reduced level of consciousness, severe hypoxemia or severe acidemia (Klompas et al., 2022). NIV must never delay intubation when intubation is the better choice; delay is a main risk of NIV (Davidson et al., 2016; Rochwerg et al., 2017).

Nursing care of the patient on NIV. NIV belongs where enhanced nursing care and monitoring are available (Davidson et al., 2016). The nurse:

- **fits the mask** with the respiratory therapist (RT). A full face mask is usually tried first, and overtightening is avoided (Davidson et al., 2016);
- **protects the skin.** Ulcers over the bridge of the nose are the most common problem, affecting 5–10% of patients (Davidson et al., 2016). The nurse checks the skin often, uses protective dressings per policy and offers mask breaks when safe (Chapter 35);

- **reduces aspiration risk.** The nurse keeps the head of the bed raised, watches for nausea and drowsiness, and reports a patient who cannot protect the airway;
- **supports communication:** keeps the call bell in reach and agrees on simple signals;
- **monitors closely:** continuous SpO2 (usually 88–92% in hypercapnic failure), respiratory rate, heart rate, level of consciousness, comfort and mask leak (Davidson et al., 2016). Blood gases are checked before and after NIV starts, then as ordered (Davidson et al., 2016).

Is NIV working? A falling respiratory rate and an improving pH within the first hours predict success (Rochwerg et al., 2017; Davidson et al., 2016). A worsening pH and respiratory rate mean the plan must change (Davidson et al., 2016). Rising drowsiness, exhaustion or no improvement within the first hours are warning signs to escalate at once.

Infection control. NIV can spread respiratory particles, so the nurse follows local IPAC policy (Chapter 4, section 4.3). For pandemic viral illness, the ERS/ATS guideline made no recommendation; it noted that NIV in a protected environment, such as a negative-pressure room, may be reasonable (Rochwerg et al., 2017).

Intubation

Intubation means placing an endotracheal tube through the mouth into the trachea for ventilation (Figure 15.2). Common reasons include a patient who cannot protect the airway, failing NIV and severe or worsening hypoxemia or acidosis. Repeated intubation attempts can cause hypoxemia (Law et al., 2021a), so the team prepares carefully.



Figure 15.2 An endotracheal tube in a teaching model of the airway. The tube passes through the mouth into the trachea, and its inflated cuff seals the trachea around it. (credit: “Endotracheal tube” by John Campbell/Flickr, public domain)

Following policy and the team leader, the nurse helps prepare by:

- checking that suction, oxygen, a bag-valve mask, monitoring and intravenous (IV) access are ready and working;
- preparing the medications ordered, such as sedatives and neuromuscular blockers, as the team directs;
- taking part in the team briefing, in which the airway leader explains the plan (Law et al., 2021b);
- explaining what is happening to the patient and family.

After the tube is placed, **end-tidal carbon dioxide (ETCO2)** monitoring by waveform capnography is the main way to confirm it. With the tube in the trachea, CO2 shows in every exhaled breath; with the tube in the esophagus, the trace is flat or fades. When sustained exhaled CO2 cannot be detected, the default response is to remove the tube (Chrimes et al., 2022). Team members say aloud what the capnography shows, and the nurse speaks up if the trace is absent. A chest X-ray is often ordered afterward to help check the tube's position; it does not replace capnography. The nurse records the tube size and centimetre mark at the lips or teeth, and helps secure the tube per policy.

Caring for the Ventilated Patient

Mechanical ventilation uses a machine to move air into the lungs through an endotracheal or tracheostomy tube.

Safety checks. Each shift and after any transfer, the nurse checks:

- a bag-valve mask connected to oxygen and suction set up and working at the bedside (Chapter 12, section 12.5);
- the tube's centimetre mark and how it is secured;
- that alarms are on and audible.

Alarms. A high-pressure alarm usually means the ventilator meets resistance, as with secretions, coughing, biting on the tube or a kinked circuit. A low-pressure or low-volume alarm usually means air is escaping, as with a disconnection or a leak. The nurse looks at the patient first, then traces the circuit to the ventilator, and never silences an alarm and walks away. If the patient is in distress and the cause is not obvious at once, the nurse calls for help and, following policy, ventilates by bag-valve mask until the RT or physician arrives.

Preventing ventilator-associated pneumonia. Ventilator-associated pneumonia (VAP) is a pneumonia that develops in a patient on a ventilator (Chapter 13). Up to 1 in 10 patients on invasive ventilation develops hospital-acquired pneumonia (Klompas et al., 2022). Table 15.2 lists prevention practices. Endotracheal tubes that drain secretions from above the cuff are an added option for patients expected to need ventilation for more than 48–72 hours. Oral care with chlorhexidine is no longer recommended (Klompas et al., 2022).

Table 15.2 Practices that help prevent ventilator-associated pneumonia (Klompas et al., 2022; original wording)

Practice	What the nurse does	Why it helps
Avoid intubation when safe	Supports high-flow oxygen or NIV for suitable patients, and escalates if they fail	No tube means no tube-related pneumonia
Minimize sedation	Uses the lightest sedation that keeps the patient safe; takes part in daily sedation interruptions	Linked to shorter ICU stays
Daily spontaneous breathing trial	Checks readiness with the team each day and monitors the patient during the trial	Patients come off the ventilator about a day sooner on average
Raise the head of the bed	Keeps the head of the bed at 30–45 degrees unless contraindicated	Linked to lower VAP rates; simple, cheap and low risk
Oral care with toothbrushing	Brushes teeth, gums and tongue regularly, without chlorhexidine	Linked to lower VAP rates and shorter ventilation and ICU stays
Early mobility	Works with physiotherapy to sit, stand and walk the patient when safe	May shorten ventilation and ICU stays

Sedation and delirium. The Society of Critical Care Medicine suggests light rather than deep sedation for ventilated adults. It also suggests non-benzodiazepine sedatives over benzodiazepines (Devlin et al., 2018). The 10-level **Richmond Agitation–Sedation Scale (RASS)** runs from +4 (combative) through 0 (alert and calm) to −5 (unarousable) (Sessler et al., 2002). The same guideline advises that critically ill adults be assessed for delirium regularly with a valid tool (Devlin et al., 2018). The **Confusion Assessment Method for the ICU (CAM-ICU)** looks at four features: an acute change or fluctuation in mental status, inattention, an altered level of consciousness and disorganized thinking. Delirium is present when the first two features are present along with either of the last two (Island Health, 2018; Chapter 8, section 8.2).

Communication. A patient with an endotracheal tube cannot speak. The nurse asks yes-or-no questions, offers letter boards or writing materials, and makes sure the patient has glasses and hearing aids, which also helps prevent delirium (Devlin et al., 2018).

Weaning. Weaning is the process of reducing ventilator support, and the team checks readiness every day. In a **spontaneous awakening trial**, sedation is paused so the patient becomes alert. In a **spontaneous breathing trial**, the patient breathes with little or no ventilator help (Klompas et al., 2022). The nurse monitors the patient closely during the trial and after extubation, and reports distress, a rising respiratory rate or a falling SpO2.

GOING DEEPER

Ventilator Modes and Settings in Plain Terms

Required for RN students; optional for PN students.

A ventilator gives each breath in one of two basic ways. In **volume-controlled** modes, the clinician sets the size of each breath, and the pressure needed to deliver it varies with how stiff the lungs are. In **pressure-controlled** modes, the clinician sets the pressure, and the size of each breath varies. The RT and physician choose and adjust the mode.

- **Tidal volume:** the volume of each breath. In ARDS, guidelines strongly recommend 4–8 mL per kg of **predicted body weight** (Fan et al., 2017). Predicted body weight is calculated from height and sex, not from actual weight.
- **Respiratory rate:** the number of breaths the ventilator guarantees each minute. Changing it changes how much CO2 is cleared.
- **FiO2:** the fraction of inspired oxygen, from 0.21 (room air) to 1.0.
- **Positive end-expiratory pressure (PEEP):** pressure kept in the lungs at the end of each breath to stop alveoli from collapsing. Higher PEEP is suggested for moderate to severe ARDS (Qadir et al., 2024).
- **Plateau pressure:** the pressure in the alveoli when air is held briefly at the end of a breath in. In ARDS, it is kept below 30 cm H2O (Fan et al., 2017).

The **PaO2/FiO2 (P/F) ratio** shows how well the lungs oxygenate for the oxygen given. For example, a PaO2 of 75 mm Hg on an FiO2 of 0.5 gives a ratio of 150. In intubated patients receiving a PEEP of at least 5 cm H2O, the 2024 definition grades ARDS as mild (P/F more than 200 and up to 300), moderate (more than 100 and up to 200) or severe (100 or less) (Matthay et al., 2024).

The nurse watches for:

- rising airway pressures;
- a falling tidal volume in pressure modes;
- falling SpO2 or ETCO2 changes;
- patient–ventilator distress, such as the patient breathing against the machine.

The nurse reports these at once. Any FiO2 or PEEP change is followed by reassessment.

LIFESPAN CONSIDERATIONS

Older Adults and Critical Respiratory Illness

Many patients with respiratory failure are older adults, and CIHI expects the aging population to place more demands on Canadian ICUs in the coming decades (CIHI, 2016). Frailty, meaning low reserve across body systems, raises the risk of complications and slow recovery (Chapter 8, section 8.1). Older adults are at high risk of delirium, which often shows as quiet withdrawal rather than agitation. Regular screening, light sedation, glasses and hearing aids, sleep and early mobility all help (Devlin et al., 2018; Chapter 8, section 8.2). Bed rest quickly weakens muscles, so the nurse supports mobility as soon as it is safe. Many older survivors live with the physical, cognitive or mental effects of PICS (Needham et al., 2012). Before a crisis, the nurse helps make sure the team knows the patient's values and wishes about intubation, NIV and ICU care, and involves the substitute decision-maker when needed (Chapter 10, section 10.2). At discharge, the nurse prepares the patient and family for a slow recovery and links them with follow-up supports (Davidson et al., 2012).

CANADIAN CONTEXT

Critical Care Far From the City

Many people in rural, remote and northern Canada live hours from an ICU. A patient in respiratory failure may need stabilization in a small hospital or nursing station, then transfer by air or land (Figure 15.3). In Ontario, Ornge provides air ambulance and critical care land transport from 14 bases. It carries out about 20,000 patient-related transports a year across more than one million square kilometres (Ornge, n.d.). Other provinces and territories run their own transport services.

For First Nations people and Inuit who are eligible, the Non-Insured Health Benefits (NIHB) program helps pay for medical travel that provincial and territorial programs do not cover. A physician or registered nurse escort may be approved when the patient needs monitoring or stabilization during travel. A non-medical escort may be approved when the patient cannot travel alone, for example because of language or decision-making needs (Indigenous Services Canada [ISC], 2022). Critical illness can still mean long separation from family, community and language. The nurse asks early about escorts, interpreters and the patient's supports, and helps the family stay in contact (Chapter 2).

Figure 15.3 A BC Emergency Health Services critical care helicopter on the rooftop helipad of Vancouver General Hospital. (credit: "BCEHSHeli2017" by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

15.4 Pneumothorax and Chest Injury

Air in the Pleural Space

A **pneumothorax** is air in the pleural space, the thin gap between the pleura covering the lung and the pleura lining the chest wall. Normally this space holds only a film of fluid at a pressure below atmospheric pressure, which keeps the elastic lung stretched against the chest wall. Once air enters, that pull is lost and the lung recoils and collapses. The BTS guideline groups pneumothorax by cause (M. E. Roberts et al., 2023):

- **Primary spontaneous pneumothorax:** occurs with no known lung disease, although CT often shows small emphysema-like changes.
- **Secondary spontaneous pneumothorax:** occurs with established lung disease, such as COPD (Chapter 14). The BTS also counts people over 50 with a smoking history in this group. With less reserve, even a small pneumothorax can cause respiratory failure (section 15.1).
- **Traumatic pneumothorax:** follows blunt or penetrating chest injury.
- **Iatrogenic pneumothorax:** results from care, for example thoracentesis, where it is the most common complication (Asciak et al., 2023; Chapter 13), a lung biopsy or pacemaker insertion (M. E. Roberts et al., 2023), or positive-pressure ventilation (section 15.3).

The collapsed lung still receives blood but no air, so that blood returns to the heart without picking up oxygen (section 15.1). Pain adds to the problem by keeping breaths shallow.

Recognizing Pneumothorax

The typical story is sudden, sharp, one-sided chest pain that worsens with breathing (**pleuritic pain**), with shortness of breath. On the affected side, the nurse may find reduced chest movement, reduced or absent breath sounds and a hyperresonant percussion note (Chapter 12). Heart and respiratory rates rise, and SpO2 may fall. Cyanosis is late and harder to see on darker skin, so the nurse checks the lips, oral mucosa and nail beds and does not wait for colour change (Chapter 12). Air escaping into the tissues causes **subcutaneous emphysema**, felt as crackling under the fingers. It is common and usually minor after chest drain insertion, but a spreading area can mean a blocked drain or a large air leak (Asciak et al., 2023).

A chest X-ray is commonly used to confirm the diagnosis (Figure 15.4), and the BTS advises a follow-up X-ray 2 to 4 weeks later for patients managed by observation or needle aspiration (M. E. Roberts et al., 2023). Bedside ultrasound is more sensitive in injured patients: in a Cochrane review, among 100 patients of whom 30 had a pneumothorax, ultrasound would miss about 3 and a chest X-ray taken lying flat about 16 (Chan et al., 2020). CT, the reference test in that review, gives the most definitive answer (Chan et al., 2020).

The BTS states that size alone is no longer a reason for invasive treatment, although it affects which procedures are safe (M. E. Roberts et al., 2023). Options, chosen with the patient, include observation for a primary pneumothorax with few symptoms, needle aspiration, a chest drain (section 15.5) and an ambulatory device: a small drain with a one-way valve that lets suitable patients go home with close follow-up. Surgery or pleurodesis (sealing the pleural layers together) is considered to prevent recurrence. Before discharge, patients learn to return at once if breathless and to stop smoking. The BTS advises no commercial flights until an X-ray shows full resolution (then waiting 7 days) and discourages scuba diving for life unless definitive surgery has been done (M. E. Roberts et al., 2023).



Figure 15.4 Chest X-ray of a large left pneumothorax, labelled: no lung markings in the air-filled space, the collapsed left lung, and the mediastinum shifted to the right. A shift like this, with signs of shock, points to tension pneumothorax, which is treated at once without waiting for an X-ray. (credit: "X-ray of pneumothorax signs" by Karthik Easvur/Wikimedia Commons, CC BY-SA 3.0)

Tension Pneumothorax

In a **tension pneumothorax**, air enters the pleural space with each breath but cannot leave. Pressure climbs, the lung collapses fully and the heart and great vessels are pushed aside. Venous return and cardiac output fall, causing obstructive shock (Chapter 6). Death can follow within minutes.

Early signs are chest pain, respiratory distress, tachycardia, low SpO2 and reduced air entry on one side. A Canadian emergency guideline notes that low blood pressure appears in fewer than a quarter of cases and that tracheal deviation and distended neck veins are uncommon or hard to detect (Shared Health, 2025). Patients on a ventilator are more likely to have hypoxemia, hypotension and cardiac arrest, and these often appear within minutes (D. J. Roberts et al., 2015).

Decompression must be done the moment the condition is suspected, to prevent collapse of breathing and circulation (Shared Health, 2025). The nurse stays with the patient, calls the rapid response team or a code as policy directs (Chapter 6), gives high-flow oxygen, attaches a monitor and checks any existing chest drain for clamps, kinks or blockage. The nurse brings equipment for immediate decompression by a provider authorized and trained to do it: a long catheter-over-needle through the chest wall, or a **finger thoracostomy**, in which the provider opens the pleura through a small incision. Needle decompression fails in about 40% of cases, and finger thoracostomy succeeds more often (Shared Health, 2025).

Other Chest Injuries in Brief

A **hemothorax** is blood in the pleural space from injured chest wall vessels, lung or great vessels, or after surgery. Signs resemble pneumothorax, but percussion is dull and the patient may show hypovolemic shock (Chapter 6). A hemothorax in an unstable patient may need a large-bore drain (Asciak et al., 2023).

Rib fractures hurt, so patients breathe shallowly and avoid coughing, which can lead to pneumonia and respiratory failure. One trauma review reports a death rate of at least 20% in older adults with rib fractures (Brasel et al., 2017). A **flail chest** is three or more ribs each broken in two or more places; the loose segment may move inward on inspiration, but bruised lung and pain cause most of the breathing problem. Pain control comes first: acetaminophen, nonsteroidal anti-inflammatory drugs (NSAIDs) and, for severe pain, early epidural or paravertebral analgesia (Brasel et al., 2017; Chapter 5). The nurse coaches deep breathing, coughing and walking, and watches for a pneumothorax or hemothorax that can appear later (Brasel et al., 2017). Major trauma is covered in Chapter 33.

15.5 Chest Tubes and Chest Drainage

A chest tube lets air, blood or fluid leave the pleural space while stopping air from being drawn back in. The principles are the same across products, but designs differ, so the nurse follows the manufacturer's instructions and hospital policy for the system in use.

Why and How Chest Tubes Are Placed

A **chest tube** (intercostal chest drain) is a flexible tube placed between the ribs into the pleural space. Common reasons include pneumothorax that has not settled with simpler treatment, hemothorax, pleural infection or empyema, large effusions, pleurodesis and recovery from thoracic surgery such as lobectomy (Chapter 13) (Asciak et al., 2023).

Tube size is measured in French (Fr) units. Small-bore drains (14 Fr or smaller), usually inserted over a guidewire, suit most purposes, including pleural infection. Large-bore drains (often larger than 20 Fr, mostly inserted by blunt dissection) may be needed after thoracic surgery, for hemothorax in an unstable patient or for a pneumothorax with a large air leak (Asciak et al., 2023).

At insertion, the nurse:

- confirms that the provider has obtained informed consent (Chapter 1, section 1.5); complications follow 8% to 20% of insertions (Asciak et al., 2023);
- checks for anticoagulant use and bleeding risk as policy directs, gives prescribed analgesia and sets up the drainage unit;
- positions and supports the patient as the operator directs;
- monitors SpO2, heart rate, blood pressure, pain and signs of a vasovagal reaction;
- keeps the field sterile as policy directs.

The drain is sutured in place and dressed, and a chest X-ray within a few hours confirms its position (Asciak et al., 2023).



Figure 15.5 A chest drainage unit with its parts labelled. (credit: "Chest tube drainage system with labelled parts" by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

How Drainage Systems Work

Most chest drainage units combine up to three functions in one plastic box (Figure 15.5).

- **Collection chamber:** drainage collects here in a marked chamber so it can be measured.
- **Water seal:** air from the patient bubbles out through a short column of water, but the water stops air from flowing back toward the chest. The **water seal** therefore acts as a one-way valve, and the tube end must stay under the right depth of water (Asciak et al., 2023).
- **Suction control:** routine suction is not recommended, because its benefit is unproven; it is avoided right after insertion, and when used the pressure is prescribed (Asciak et al., 2023). In **wet suction** units, the height of a water column limits suction, and gentle continuous bubbling in that chamber is expected. In **dry suction** units, an adjustable control on the unit, rather than a water column, sets the suction level (Getinge, n.d.).

A one-way **flutter valve** (sometimes called a Heimlich valve) lets air out without a water seal, so the patient can walk around or go home with a drain (M. E. Roberts et al., 2023). **Digital chest drainage** systems provide suction electronically and measure air leak continuously, which can help guide removal (Asciak et al., 2023; Figure 15.6).

Figure 15.6 A portable digital chest drainage unit at the bedside. It applies suction electronically and measures air leak continuously. (credit: "P4053296 logo" by TKiefer/Wikimedia Commons, CC BY-SA 4.0)

Two rules apply to every system. The unit stays upright and below the chest, so fluid cannot flow back into the pleural space (Asciak et al., 2023; da Silva et al., 2024). The tubing lies without kinks or dependent loops, because fluid trapped in a loop resists drainage (da Silva et al., 2024).

Assessing the Patient and the System

The nurse assesses the patient first: respiratory rate and effort, SpO2, breath sounds on both sides, chest movement, heart rate, blood pressure, pain, the insertion site and any subcutaneous emphysema. Pain control matters, because a patient in pain will not breathe deeply or cough. Walking, deep breathing and coughing are encouraged (da Silva et al., 2024).

The nurse then traces the system from the chest to the unit, checking:

- secure connections and tubing free of kinks and loops;
- the water seal level;
- **tidalling**, the rise and fall of fluid in the water seal or tubing with breathing, which shows the drain is open to the pleural space;
- bubbling in the water seal, which shows an **air leak** from the lung or a loose connection;
- drainage amount, colour and consistency, marked and timed as policy directs;
- the suction source and setting, if ordered.

After surgery, one review recommends recording drainage every 30 to 60 minutes for the first 3 to 4 hours (da Silva et al., 2024). Bubbling when the patient coughs or breathes out is expected while a pneumothorax resolves or after lung surgery. Tidalling can stop when the lung has fully re-expanded, but it usually means the tube is blocked (Asciak et al., 2023). The nurse reports at once a sudden rise in bloody drainage (one review cites more than 100 mL in an hour after the first 3 postoperative hours; units set their own limits), new continuous bubbling, tidalling that stops while the patient becomes more breathless, spreading subcutaneous emphysema or any sign of tension pneumothorax (da Silva et al., 2024; Asciak et al., 2023). When a large effusion is draining, coughing, chest tightness or pain can signal **re-expansion pulmonary edema**, a rare but life-threatening complication; drainage is stopped as ordered and the patient assessed (Asciak et al., 2023). Table 15.3 brings these checks together.

Table 15.3 Chest drainage: what to check and what to do (Asciak et al., 2023; da Silva et al., 2024; original wording)

Finding	What it may mean	Nursing action

Finding	What it may mean	Nursing action
Fluid in the water seal rises and falls with breathing	The drain is open to the pleural space	Record it; keep checking as policy directs
Tidalling stops and the patient is comfortable, with clear breath sounds	The lung may have re-expanded	Check tubing for kinks or loops; report and expect a chest X-ray
Tidalling stops and the patient is more breathless	The tube may be blocked or kinked; air or fluid may be building up	Check the whole system, stay with the patient and get help at once
Bubbling in the water seal when the patient coughs or breathes out	Expected air leak from the lung	Record it and watch for change
New continuous bubbling in the water seal	Large air leak from the lung or a leak in the system	Check connections from the chest to the unit; report at once
Sudden increase in bright red drainage	Possible bleeding	Assess vital signs and the patient; report at once
Crackling under the skin that is spreading	Air escaping into tissues; possible blocked drain or large leak	Assess breathing, check the drain and report

Troubleshooting

Disconnection or a broken unit. Air can enter the chest through an open tube, so the nurse acts at once as policy directs to restore the closed system: usually by reconnecting the tubing, or by attaching a new unit with aseptic technique if the ends are contaminated (Asciak et al., 2023). One review allows clamping by hand for less than a minute while this is done (da Silva et al., 2024). The nurse then assesses breathing and SpO2 and reports the event. If the unit tips over, the nurse sets it upright, checks the water seal and replaces the unit if the chambers have mixed, following the manufacturer's instructions.

Accidental removal. A dislodged drain is never pushed back in, because of infection risk; a new drain may be needed at a new site (Asciak et al., 2023). The nurse covers the site at once with a dressing and pressure as policy directs, calls for help and watches for a growing or tension pneumothorax (da Silva et al., 2024).

Clamping. Clamping a bubbling drain can trap air and cause a tension pneumothorax (Asciak et al., 2023). Drains are not clamped for transport; the unit is kept below the chest instead. Brief clamping, for example while changing a unit, happens only as policy allows and for the shortest possible time (da Silva et al., 2024). Clamping as part of a prescribed plan, such as controlled drainage of a large effusion, follows the written order (Asciak et al., 2023).

Milking and stripping. Squeezing or stripping the tubing to move clots is not routine care: the evidence is weak, and correct positioning may be enough to keep the drain open (da Silva et al., 2024). Clots are cleared only as ordered or as policy allows, and small-bore drains may have prescribed saline flushes (Asciak et al., 2023).

Transport and mobility. The unit travels upright, below the chest and unclamped. The nurse asks whether ordered suction may be paused or must continue on a portable device.

Removal

A drain comes out when it has done its job: typically, the air leak has stopped, drainage is low and the X-ray shows a re-expanded lung. A physician, a nurse practitioner (NP) or another suitably trained person removes it, according to policy (Asciak et al., 2023).

The nurse gives prescribed analgesia beforehand, often at least 30 minutes ahead (da Silva et al., 2024), explains each step and positions the patient as directed. The patient takes a breath and bears down (the Valsalva manoeuvre) as the tube is pulled; the BTS reports that timing removal to the end of a breath in or out does not seem to change the risk of a large pneumothorax remaining, as long as the Valsalva manoeuvre is done (Asciak et al., 2023). The tube comes out in one steady pull and the site is covered quickly (Asciak et al., 2023), and an occlusive dressing is applied (da Silva et al., 2024). Afterward, the nurse monitors breathing, SpO2, breath sounds, pain, the dressing and any subcutaneous emphysema, and a chest X-ray is done as ordered (Asciak et al., 2023).

CLINICAL SAFETY

Chest Tube Safety

- Keep the drainage unit upright and below chest level at all times, including during transport and walks.
- Do not clamp a drain that is bubbling. Clamping can cause a tension pneumothorax. Clamp only briefly when policy allows, or when a written order sets out a plan.
- Keep tubing free of kinks and dependent loops, and keep connections secure.
- Assess the patient before the equipment. New breathlessness, falling SpO2, reduced breath sounds or a dropping blood pressure need action now, not after the next check.
- If the tubing disconnects or the drain falls out, act at once as policy directs: reconnect, or cover the site, then stay, assess and call for help.
- Never push a dislodged drain back in.
- Keep the bedside supplies that hospital policy requires, and check them at the start of each shift.
- Follow the manufacturer's instructions for the specific system.

(Asciak et al., 2023; da Silva et al., 2024)

15.6 Pulmonary Embolism

Pulmonary embolism ranges from a small clot found by chance to sudden cardiac arrest. It can develop in patients already in hospital, where nurses are often the first to notice it. This section builds on venous thromboembolism prevention (Chapter 7, section 7.6); deep vein thrombosis and anticoagulants are taught in full in Chapter 19.

How PE Develops

A **pulmonary embolism (PE)** is a blockage of the pulmonary artery or one of its branches, usually by a clot that has broken off from a **deep vein thrombosis (DVT)** in the leg or pelvis and travelled through the right heart into the lungs. Together, DVT and PE are called **venous thromboembolism (VTE)**. Clots form when parts of **Virchow's triad** are present: slow or still blood flow (stasis), injury to the vessel wall and blood that clots more readily than normal (hypercoagulability). Surgery combines all three.

Lung units beyond the clot still receive air but no blood, so ventilation and perfusion no longer match and blood oxygen falls. The blocked arteries also raise the pressure the right ventricle must pump against. The right ventricle can dilate and fail, starving the left ventricle of blood and lowering cardiac output; in a large PE this causes obstructive shock (Chapter 6).

The European Society of Cardiology (ESC) guideline groups risk factors by strength (Konstantinides et al., 2020):

- **Strong:** hip or knee replacement, lower-limb fracture, major trauma, spinal cord injury, a previous VTE, a recent heart attack and recent hospital care for heart failure or atrial fibrillation.
- **Moderate:** cancer and chemotherapy (Chapter 9), estrogen-containing contraceptives and hormone replacement therapy, the postpartum period, infection, inflammatory bowel disease and inherited or acquired clotting disorders (**thrombophilia**).
- **Weaker:** bed rest for more than 3 days, obesity, pregnancy, older age and long periods of sitting during travel.

About 40% of people with PE have no identifiable risk factor (Konstantinides et al., 2020).

Recognizing PE

The signs of PE are nonspecific. It is usually suspected in a patient with shortness of breath (often sudden), chest pain (often pleuritic), fainting or near-fainting, or coughing up blood (**hemoptysis**) (Konstantinides et al., 2020). Other cues include a fast heart rate and breathing rate, low SpO2, anxiety and signs of DVT, such as one swollen, painful or warm leg. Redness is harder to see on darker skin, so the nurse compares leg size, warmth and tenderness with the other side. Some patients have few signs, and some PEs are found by chance on CT (Konstantinides et al., 2020). A large PE presents with shock: low blood pressure, cool skin, confusion and, at worst, cardiac arrest.

Older adults may have vague symptoms: breathlessness may be blamed on heart or lung disease, and a faint on a fall (Chapter 8). The nurse keeps PE in mind whenever an older patient's breathing or heart rate changes without a clear reason.

Diagnosis

Testing is stepwise, so that low-risk people are not exposed to radiation and contrast dye. The details below follow the ESC guideline (Konstantinides et al., 2020) and the 2026 American Heart Association and American College of Cardiology (AHA/ACC) guideline (Creager et al., 2026), whose stepwise approach matches Choosing Wisely Canada's advice for Canadian emergency departments (Choosing Wisely Canada, 2024).

Step 1: Pretest probability. The provider judges how likely PE is, often with a structured rule. The **Wells rule** gives points for features such as signs of DVT, a fast heart rate, recent surgery or immobility, a past VTE, hemoptysis, cancer and whether PE is more likely than another diagnosis (Creager et al., 2026). The **YEARS** approach uses three items: signs of DVT, hemoptysis and PE as the most likely diagnosis (Konstantinides et al., 2020). For patients already judged low risk, the **pulmonary embolism rule-out criteria (PERC)** are eight simple clinical checks; a patient who meets all eight needs no testing. PERC is not used where PE is common (Konstantinides et al., 2020). The rules are not validated in some groups, such as pregnant patients and people with clotting disorders, so clinical judgment guides care (Choosing Wisely Canada, 2024).

Step 2: D-dimer. D-dimer is a fragment released when fibrin breaks down. A normal result makes PE unlikely when pretest probability is not high. The test gives more false-positive results with age, so for patients over 50 an **age-adjusted D-dimer cut-off** of age × 10 mcg/L reduces false positives. Under YEARS, PE is excluded when no item is present and the D-dimer is below 1,000 mcg/L, or when items are present and it is below 500 mcg/L (Konstantinides et al., 2020). Units and cut-offs vary by laboratory. Choosing Wisely Canada advises against ordering a CT pulmonary angiogram or a lung scan until a decision rule has been used and, where needed, a D-dimer result is back (Choosing Wisely Canada, 2024).

Step 3: Imaging. CT pulmonary angiography (CTPA) uses IV contrast to show clots in the pulmonary arteries. It is the test of choice, and a negative result rules out PE in patients with low or intermediate probability. A **ventilation–perfusion (V/Q) scan** compares where air and blood reach the lungs. It may be preferred in pregnancy, in young patients (especially women), after a severe reaction to contrast and in severe kidney failure (Konstantinides et al., 2020; Chapter 27). A DVT close to the trunk on leg ultrasound justifies treatment without further imaging (Konstantinides et al., 2020).

Step 4: Severity. Once PE is confirmed, the team looks for right ventricular strain: a dilated right ventricle on echocardiography or CT, a raised **troponin** (a marker of heart muscle injury) or natriuretic peptide (a marker of heart strain), and a clinical score, the simplified Pulmonary Embolism Severity Index (sPESI) (Konstantinides et al., 2020).

In rural and remote communities, CTPA may not be available locally, and transfer for imaging can mean time away from family and community (Chapter 2).

Risk Levels and Treatment

The ESC sorts PE into high, intermediate and low risk (Konstantinides et al., 2020), and Canadian protocols, such as Manitoba's provincial guideline, use the same levels (Shared Health, 2024) (Table 15.4). The 2026 AHA/ACC guideline introduced a five-category system (A to E) that readers may meet in practice (Creager et al., 2026).

High-risk PE, often called **massive pulmonary embolism**, means the circulation is unstable, with persistent hypotension (systolic pressure below 90 mm Hg, or a drop of 40 mm Hg or more lasting over 15 minutes with no other cause), obstructive shock or cardiac arrest (Konstantinides et al., 2020). For PE with hemodynamic compromise, the American Society of Hematology (ASH) recommends **thrombolysis**, treatment with a drug that dissolves the clot, followed by anticoagulation (Ortel et al., 2020). Canadian protocols, such as Manitoba's, use **alteplase**, and Manitoba's guideline tells clinicians not to delay it while awaiting specialist advice if there are no contraindications (Shared Health, 2024). Contraindications centre on bleeding risk: active internal bleeding, a past stroke, recent brain or spinal surgery or head injury, a brain tumour or vascular malformation, a bleeding disorder and severe uncontrolled hypertension (Hoffmann-La Roche, 2024; Southern Health–Santé Sud, 2024). Other options are catheter-directed treatment, mechanical clot removal and surgical **embolectomy**, often chosen by a **PE response team (PERT)** (Creager et al., 2026; Shared Health, 2024).

Intermediate-risk PE means stable blood pressure with a higher clinical score, right ventricular strain or a raised troponin. ASH suggests anticoagulation alone rather than routine thrombolysis (Ortel et al., 2020). The patient is monitored closely, and reperfusion is considered if early circulatory failure appears (Creager et al., 2026).

Low-risk PE means a stable patient with no heart strain and a low clinical score. ASH suggests home treatment when the patient has support, can get the medication and has no other reason to stay (Ortel et al., 2020).

Anticoagulation is the treatment at every level, and the ESC recommends starting it when clinical probability is high or intermediate, while tests are under way (Konstantinides et al., 2020). Anticoagulants do not dissolve the clot; they stop it from growing while the body breaks it down. When an injected drug is needed first, low-molecular-weight heparin (LMWH) is recommended over unfractionated heparin (Creager et al., 2026). In high- and intermediate-risk PE, one provincial guideline advises avoiding direct oral anticoagulants (DOACs) until the patient is stable, and any heparin infusion is stopped before alteplase (Shared Health, 2024). For ongoing treatment, a DOAC is suggested over warfarin for most patients (Ortel et al., 2020). Treatment lasts at least 3 to 6 months, and longer for some (Creager et al., 2026; Chapter 19).

Table 15.4 Pulmonary embolism risk levels and usual treatment (Konstantinides et al., 2020; Ortel et al., 2020; Creager et al., 2026; original wording)

Risk level	Typical findings	Usual treatment	Nursing focus
High (massive)	Shock, persistent low blood pressure or cardiac arrest	Thrombolysis followed by anticoagulation; catheter or surgical clot removal if thrombolysis is unsafe or fails; specialist team	Call for help at once; oxygen, monitoring and IV access; watch for bleeding and neurologic change during and after thrombolysis
Intermediate	Stable blood pressure, but a higher clinical score, right ventricular strain on imaging or a raised troponin	Anticoagulation in hospital with close monitoring; reperfusion considered if the patient worsens	Frequent vital signs and SpO2; recognize early shock and escalate; bleeding precautions
Low	Stable, no heart strain, low clinical score	Anticoagulation, often at home or with early discharge	Teaching about the anticoagulant, bleeding signs and when to seek help; arrange follow-up

Nursing Care

Using the CJMM (Chapter 1, section 1.4), the nurse treats sudden breathlessness, tachycardia, low SpO2 or chest pain after surgery as cues to analyze at once; hypoxemia and early shock are the priority problems.

- **Oxygen and monitoring:** Give oxygen to the target range (Chapter 12), monitor vital signs and SpO2 (with cardiac monitoring as ordered), sit the patient up if blood pressure allows and secure IV access.
- **Recognizing deterioration:** Rising heart rate, falling blood pressure, new confusion, cool skin or falling urine output signal shock; escalate through the rapid response system using SBAR (Chapter 6).
- **Bleeding precautions:** During and after thrombolysis, the patient needs continuous cardiac and SpO2 monitoring, frequent blood pressure and neurologic checks, close watch for bleeding and as few needle punctures and intramuscular injections as possible (Southern Health–Santé Sud, 2024). A severe headache, new confusion or weakness can mean bleeding in the brain: stop the infusion as the protocol directs and report at once. Swelling of the lips or tongue can signal angioedema (Hoffmann-La Roche, 2024). Patients over 75 bleed more easily (Southern Health–Santé Sud, 2024), and falls add to the risk for older adults on anticoagulants (Chapter 8).
- **Mobility:** Once anticoagulation is under way and the patient is stable, walking is encouraged as ordered; in a meta-analysis of patients with DVT, early walking on anticoagulants did not raise the rate of new PE (Liu et al., 2015).
- **Anxiety:** Stay with the patient, explain each step and involve the family.
- **Teaching and transition:** Teach about the anticoagulant, bleeding and follow-up. The care team should ask about breathlessness and exercise tolerance at every visit for at least a year to detect chronic thromboembolic pulmonary disease (Creager et al., 2026).

MEDICATIONS

Thrombolytics and Anticoagulants for PE

Alteplase, heparin, enoxaparin, apixaban, rivaroxaban and warfarin are marketed in Canada (Drug Shortages Canada, n.d.; Health Canada, 2026). Doses and full teaching are in Chapter 19.

- **Alteplase:** a thrombolytic that activates the body's clot-dissolving system. Bleeding is the main risk. Monitor all puncture sites, avoid intramuscular injections and do neurologic checks. Stop the infusion and report at once if signs of serious bleeding appear. Its Canadian product monograph lists heart attack and stroke; use for PE follows guidelines and hospital protocols (Hoffmann-La Roche, 2024).
- **Heparin (unfractionated):** an IV anticoagulant that boosts antithrombin. It acts and wears off quickly. An infusion is stopped before thrombolysis (Shared Health, 2024), and its effect can be reversed with protamine (Hoffmann-La Roche, 2024).
- **Low-molecular-weight heparins (such as enoxaparin):** injected under the skin; often the first anticoagulant.
- **Direct oral anticoagulants (such as apixaban and rivaroxaban):** block a single clotting factor; suggested over warfarin for most patients (Ortel et al., 2020).
- **Warfarin:** blocks vitamin K–dependent clotting factors and needs international normalized ratio (INR) monitoring.

For every anticoagulant, the nurse watches for bleeding, checks kidney function and platelet counts as ordered, and confirms the reversal plan with the pharmacist.

PATIENT EDUCATION

After a Pulmonary Embolism

- Take your anticoagulant exactly as prescribed. Do not skip doses or stop it unless your prescriber tells you to. Tell every health care provider, dentist and pharmacist that you take it.
- Check with your pharmacist before starting any new medicine, herbal product or supplement.
- Watch for bleeding: nosebleeds or bleeding gums that will not stop, blood in urine, black or bloody stools, unusual bruising, or coughing or vomiting blood. Call your prescriber about minor bleeding.
- Call 9-1-1 for sudden shortness of breath, chest pain, fainting, coughing up blood, a severe headache, weakness on one side or bleeding that will not stop.
- Report a new swollen, painful leg.
- Keep follow-up appointments. Tell your care team if your breathing or exercise tolerance has not returned to normal; lasting symptoms need checking.
- Stay active as you are able, and build up slowly.
- Ask your care team before long trips. Walk and stretch your legs during long periods of sitting.

SCOPE IN PRACTICE

Non-invasive Ventilation, Ventilated Patients and Chest Drains

Who cares for a patient on NIV, a ventilated patient or a patient with a chest drain depends on authority, competence and context, as the College of Nurses of Ontario (CNO) sets out in its Scope of Practice standard (CNO, 2025; Chapter 1, section 1.3). Employer policy and the province or territory also matter. Some employers assign ventilated patients only to registered nurses (RNs), while others employ registered practical nurses (RPNs) in critical care roles. These are employer decisions, not CNO rules. An employer can limit a nurse's practice but cannot expand it beyond what the law and the standards allow (CNO, 2025).

Respiratory therapists (RTs) manage ventilators and airways. In Ontario they are authorized to intubate, suction beyond the larynx and give substances by inhalation, and they work from orders and medical directives (College of Respiratory Therapists of Ontario [CRTO], 2024).

Chest drains are inserted by physicians and, where they are competent and employer policy allows, by NPs, who are authorized to perform procedures below the dermis and must be competent to do so (CNO, 2026). On surgical units, both RNs and RPNs assess and maintain chest drains, as policy directs and when they are competent.

Every nurse who notices deterioration acts at once. Examples include signs of tension pneumothorax, a disconnected drain or a patient struggling on NIV. The nurse stays with the patient, calls for help and escalates (Chapter 6). The RPN consults the RN as the patient's needs change.

PRACTICE STORY

The Bubbles That Would Not Stop

Names and details are fictional; this is a composite story.

Nurse: Nadia Benali, RPN. Years in practice: 4. Setting: thoracic surgery unit, community hospital, Ontario.

Mr. Ivan Petrenko was 71 and one day out from a right upper lobectomy. At my 0800 check his chest drain was tidalling nicely, and the water seal bubbled only when he coughed, which the surgeon had told us to expect. He was sitting up, SpO2 94% on 2 L by nasal cannula, and pleased he had walked to the door.

At 1015 his call bell went. He said his chest felt "tight, like a belt." His breathing rate was 28, and his SpO2 had dropped to 89%. In the water seal, the bubbling no longer came and went; it was steady and fast. I started from his chest and worked toward the unit. The dressing was dry. Then I found it: the connector between the drain and the tubing had separated by about a centimetre where the tape had peeled when he turned.

I reconnected it right away and taped it as our policy shows. The continuous bubbling slowed to the old pattern within a minute. I raised the head of his bed, increased his oxygen as ordered and stayed with him. I pressed the bell for my RN partner, Daniel. I gave him SBAR: what I had found, what I had done and his current numbers. Daniel assessed him with me and paged the surgical resident, who ordered a chest X-ray. By 1100 Mr. Petrenko's SpO2 was back to 93%, and the film showed only a small pocket of air.

Afterward, Daniel thanked me for checking the system from the patient outward instead of assuming that more bubbling just meant more leak from the lung. I filed an incident report, and our educator added "check connections at every turn" to our mobility teaching.

Reflect: Mr. Petrenko's condition changed from stable to uncertain. Which actions belonged to Grace, and at what point did she need to consult the RN? What might have happened if the connector had been clamped instead of reconnected?

Chapter 15 Summary

Introduction

- Acute respiratory failure and pulmonary embolism are common emergencies that nurses on medical-surgical units are often the first to recognize.
- In 2013–2014, ICU time was part of 11% of hospital stays by adults in Canada (excluding Quebec), and invasive ventilation was used for 33% of ICU patients.

15.1 Acute Respiratory Failure

- Hypoxemic (type 1) failure is a failure of oxygenation (PaO2 below about 60 mm Hg). Hypercapnic (type 2) failure is a failure of ventilation, with a high PaCO2.
- Causes of type 2 failure include opioids and sedatives, neuromuscular disease, chest wall disease and severe obesity, and COPD or asthma.
- Early cues include a rising respiratory and heart rate, more work of breathing, restlessness and a rising oxygen need. Late cues include slowing breathing, drowsiness and a falling SpO2 despite oxygen.
- A normal SpO2 on oxygen does not rule out rising CO2.
- The nurse positions the patient upright, gives oxygen to target, treats the cause as ordered, escalates with SBAR and makes sure goals of care are known.

15.2 Acute Respiratory Distress Syndrome

- The 2024 global definition requires a trigger, onset within 1 week, bilateral opacities not mainly from heart failure, and a PaO2/FiO2 ratio of 300 or less (or SpO2/FiO2 of 315 or less when the SpO2 is 97% or lower). It includes patients on high-flow nasal oxygen or NIV.
- Leaky capillaries flood and collapse alveoli, causing a shunt that responds poorly to oxygen.
- Care relies on lung-protective ventilation, prone positioning for severe ARDS and a conservative fluid strategy.

- Nurses coordinate safe prone turns and prevent pressure injuries.
- Survivors and families are at risk of post-intensive care syndrome.

15.3 Non-invasive and Mechanical Ventilation

- Bilevel NIV is strongly recommended for COPD exacerbations with respiratory acidosis, and bilevel NIV or CPAP for cardiogenic pulmonary edema.
- NIV must not delay intubation. A worsening pH and respiratory rate signal failure.
- A capnography waveform showing CO2 in every exhaled breath is the mainstay for confirming that an endotracheal tube is in the trachea.
- Safety checks, assessing the patient first when an alarm sounds, and VAP prevention practices are core nursing care.
- Light sedation, RASS and CAM-ICU screening, communication supports and daily breathing trials help patients leave the ventilator sooner.

15.4 Pneumothorax and Chest Injury

- A pneumothorax is air in the pleural space. It may be primary spontaneous (no known lung disease), secondary spontaneous (established lung disease or, under BTS guidance, age over 50 with a smoking history), traumatic or iatrogenic.
- Typical cues are sudden pleuritic chest pain, dyspnea, reduced breath sounds and hyperresonance on one side, tachycardia and falling SpO2. Chest X-ray, bedside ultrasound or CT confirm it.
- Under the BTS 2023 guideline, treatment depends on symptoms, safety and patient choice rather than size alone. Options range from observation to aspiration, chest drains and ambulatory devices.
- Tension pneumothorax causes obstructive shock and can kill within minutes. Hypotension, tracheal deviation and distended neck veins are late or unreliable signs. The nurse calls for help, gives oxygen and prepares for immediate decompression by a qualified provider.
- Hemothorax, rib fractures and flail chest impair breathing; pain control and pulmonary care prevent pneumonia and respiratory failure, especially in older adults.

15.5 Chest Tubes and Chest Drainage

- Chest tubes drain air, blood or fluid. Small-bore drains suit most uses; large-bore drains may be needed after thoracic surgery, for hemothorax in an unstable patient or for a large air leak.
- The water seal acts as a one-way valve. Suction, wet or dry, is used only when prescribed. Flutter valves and digital systems are alternatives to a standard water-seal unit.
- The nurse assesses the patient first, then the system: tidalling, bubbling, drainage, connections and suction setting. A sudden rise in bloody drainage, new continuous bubbling or loss of tidalling with distress must be reported at once.
- Keep the unit upright and below the chest. Do not clamp for transport or clamp a bubbling drain. Avoid dependent loops and do not milk or strip the tubing routinely.
- For removal, the nurse gives analgesia, coaches the Valsalva manoeuvre, applies an occlusive dressing and monitors the patient afterward.

15.6 Pulmonary Embolism

- PE is usually a clot from a DVT that blocks pulmonary arteries. It causes V/Q mismatch, hypoxemia and right ventricular strain, and a massive PE causes obstructive shock.
- Risk factors include surgery, fractures, immobility, prior VTE, cancer, estrogen-containing hormones, pregnancy and thrombophilia. Signs are nonspecific, so the nurse acts on sudden dyspnea, tachycardia and low SpO2.
- Diagnosis follows pretest probability (Wells, YEARS, PERC), then D-dimer (age-adjusted over 50), then CTPA or a V/Q scan. Choosing Wisely Canada advises against imaging before these steps.
- High-risk PE is treated with thrombolysis (alteplase) and anticoagulation. Intermediate-risk PE is treated with anticoagulation and close monitoring, and low-risk PE often at home.

- Nursing care centres on oxygen, monitoring, early escalation, bleeding and neurologic checks during thrombolysis, early mobility once anticoagulated, and teaching.

Key Terms (64)

acute respiratory distress syndrome: A sudden, widespread inflammatory injury to both lungs that causes noncardiogenic pulmonary edema and hypoxemic respiratory failure within 1 week of a trigger.

acute respiratory failure: Failure of the lungs to keep blood oxygen and carbon dioxide within safe limits, developing over minutes to days.

age-adjusted D-dimer cut-off: A D-dimer threshold for patients over 50, calculated as age × 10 mcg/L, that reduces false-positive results in older adults.

air leak: Air entering a chest drainage system from the lung or through a loose connection, seen as bubbling in the water seal chamber.

bilevel positive airway pressure: A form of NIV that gives a higher pressure on inspiration and a lower pressure on expiration, resting the breathing muscles and helping clear CO2.

central cyanosis: A bluish or greyish colour of the tongue, lips and lining of the mouth; a late, unreliable sign of low blood oxygen.

chest tube: A flexible tube placed between the ribs into the pleural space to drain air, blood or fluid and let the lung re-expand; also called an intercostal chest drain.

Confusion Assessment Method for the ICU: A delirium screening tool for critically ill patients, including those who cannot speak, based on four features.

continuous positive airway pressure: A form of NIV that delivers one steady pressure throughout the breath to keep airways and alveoli open.

CT pulmonary angiography (CTPA): A CT scan with IV contrast that shows clots in the pulmonary arteries; the usual imaging test for pulmonary embolism.

D-dimer: A fragment released when fibrin breaks down; a normal level makes pulmonary embolism unlikely when pretest probability is not high.

deep vein thrombosis (DVT): A blood clot in a deep vein, usually of the leg or pelvis, and the usual source of a pulmonary embolism.

digital chest drainage: A chest drainage system that provides suction electronically and measures air leak continuously.

dry suction: A chest drainage design in which an adjustable control on the unit, rather than a column of water, sets the level of suction.

embolectomy: Surgical removal of a clot from the pulmonary arteries.

end-tidal carbon dioxide: The level of CO2 at the end of each exhaled breath; a sustained waveform confirms that an endotracheal tube is in the trachea.

finger thoracostomy: An emergency procedure in which a provider makes a small incision in the chest wall and opens the pleura with a finger to release trapped air.

flail chest: Three or more ribs each broken in two or more places, leaving a loose segment of chest wall that can move inward on inspiration.

flutter valve: A one-way valve attached to a chest drain that lets air out of the pleural space without a water seal; sometimes called a Heimlich valve.

hemoptysis: Coughing up blood.

hemothorax: Blood in the pleural space.

hypercapnic respiratory failure: Type 2 respiratory failure; ventilation fails, so the PaCO2 rises above the normal range, often with a low pH.

hypoxemic respiratory failure: Type 1 respiratory failure; oxygenation fails, with a PaO2 below about 60 mm Hg and a normal or low PaCO2.

intubation: Placement of an endotracheal tube through the mouth into the trachea.

lung-protective ventilation: Ventilation with small tidal volumes and limited pressures to avoid further injury to the lungs.

massive pulmonary embolism: High-risk pulmonary embolism, in which the circulation is unstable (persistent hypotension, obstructive shock or cardiac arrest).

mechanical ventilation: Use of a machine to move air into the lungs through an endotracheal or tracheostomy tube.

non-invasive ventilation: Breathing support delivered through a tight-fitting mask rather than a tube in the airway.

noncardiogenic pulmonary edema: Fluid in the alveoli caused by leaky lung capillaries rather than by heart failure or fluid overload.

P/F ratio: The ratio of arterial oxygen pressure (PaO2) to the fraction of inspired oxygen (FiO2), used to grade the severity of hypoxemia and ARDS.

PE response team (PERT): A group of specialists who advise on treatment choices when pulmonary embolism is intermediate or high risk.

plateau pressure: The pressure in the alveoli measured during a brief pause at the end of inspiration.

pleuritic pain: Sharp chest pain that worsens with breathing in.

pneumothorax: Air in the pleural space, which causes part or all of the lung to collapse.

positive end-expiratory pressure: Pressure kept in the lungs at the end of each breath to stop alveoli from collapsing.

post-intensive care syndrome: New or worse physical, cognitive or mental health problems that begin after critical illness and last beyond the hospital stay.

post-intensive care syndrome–family: Anxiety, acute or posttraumatic stress, depression or complicated grief in family members of a critically ill patient.

predicted body weight: A weight calculated from height and sex and used to set tidal volume.

primary spontaneous pneumothorax: A pneumothorax in a person with no known lung disease.

prone positioning: Placing a ventilated patient face down for long periods to improve gas exchange in severe ARDS.

pulmonary embolism (PE): Blockage of the pulmonary artery or one of its branches, usually by a clot from a deep vein thrombosis.

pulmonary embolism rule-out criteria (PERC): Eight clinical checks used for patients already judged at low risk; a patient who meets all eight needs no further testing for pulmonary embolism.

re-expansion pulmonary edema: Rare, life-threatening fluid in the lung that can follow rapid drainage of air or fluid from the pleural space.

Richmond Agitation–Sedation Scale: A 10-level scale from +4 (combative) to −5 (unarousable), with 0 meaning alert and calm, used to measure sedation and agitation.

secondary spontaneous pneumothorax: A pneumothorax in a person with established lung disease, or, under BTS guidance, a person over 50 with a smoking history.

shunt: Blood flow past alveoli that receive no air, so the blood picks up no oxygen; hypoxemia from shunt responds poorly to extra oxygen.

spontaneous awakening trial: A planned daily pause in sedation to let the patient wake.

spontaneous breathing trial: A daily test in which the ventilated patient breathes with little or no ventilator support to judge readiness for extubation.

subcutaneous emphysema: Air trapped in the tissues under the skin, felt as crackling on palpation.

tension pneumothorax: A pneumothorax in which air enters the pleural space but cannot leave, so pressure rises, compresses the heart and great vessels and causes obstructive shock.

thrombolysis: Treatment with a drug that dissolves a blood clot, such as alteplase.

thrombophilia: An inherited or acquired tendency for blood to clot more readily than normal.

tidal volume: The volume of air delivered with each breath.

tidalling: The rise and fall of fluid in the water seal or tubing with breathing, which shows that a chest drain is open to the pleural space.

troponin: A blood marker of heart muscle injury; a raised level in pulmonary embolism suggests right ventricular strain.

venous thromboembolism (VTE): The combined term for deep vein thrombosis and pulmonary embolism.

ventilation–perfusion (V/Q) scan: A nuclear medicine scan that compares where air and blood reach the lungs; preferred when contrast or radiation is a concern.

ventilator-associated pneumonia: Pneumonia that develops in a patient receiving invasive mechanical ventilation.

Virchow's triad: The three conditions that promote clotting: stasis of blood, injury to the vessel wall and hypercoagulability.

water seal: The chamber of a chest drainage unit in which a column of water lets air leave the chest but stops it from flowing back, acting as a one-way valve.

weaning: The process of reducing ventilator support until the patient breathes without it.

Wells rule: A structured clinical rule that estimates the pretest probability of pulmonary embolism from findings such as signs of DVT, heart rate, recent surgery or immobility, and past VTE.

wet suction: A chest drainage design in which the height of a water column limits the level of suction.

YEARS: A diagnostic approach for suspected pulmonary embolism that combines three clinical items with a D-dimer threshold that depends on whether any item is present.

Licensure Review & Clinical Judgment Questions (35)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

1. [CORE] A patient admitted with pneumonia has been on nasal cannula oxygen for 6 hours. Which finding is a late sign that respiratory failure is progressing?

a. Respiratory rate rising from 18 to 26 breaths/min over the past several hours

b. New restlessness and anxiety

c. Respiratory rate slowing from 32 to 14 breaths/min with new drowsiness

d. Needing more oxygen than before to keep the SpO2 within the ordered target range

Answer: c — A slowing rate with drowsiness in a patient who was breathing fast suggests exhaustion and rising CO2, a late and dangerous sign (c) (section 15.1). A rising respiratory rate (a), new restlessness or anxiety (b) and a rising oxygen need (d) are early cues of compensation. They also need prompt reporting, but they show a body that is still compensating.

2. [CORE] A postoperative patient receiving IV opioids is on 2 L/min oxygen by nasal cannula. The SpO2 is 95%, the respiratory rate is 7 breaths/min and the patient is hard to rouse. What is the nurse's priority?

a. Increase the oxygen flow rate and recheck, since the SpO2 is still acceptable

b. Stop the opioid, rouse the patient, call for help and give naloxone as ordered

c. Document the findings and recheck in 30 minutes

d. Obtain a pain score and sedation score before deciding on the next opioid dose

Answer: b — Slow breathing and sedation after opioids suggest hypercapnic respiratory failure from reduced drive. Supplemental oxygen can keep the SpO2 normal while CO2 rises, so the nurse acts on the respiratory rate and level of consciousness (b) (section 15.1; Chapter 5, section 5.4). More oxygen (a) does not treat hypoventilation. Waiting (c) delays urgent care. Scoring pain and sedation before the next dose (d) delays action for a patient who cannot be roused.

3. [CORE] Which ABG result best fits acute hypercapnic (type 2) respiratory failure?

a. pH 7.26, PaCO2 70 mm Hg, PaO2 58 mm Hg

b. pH 7.47, PaCO2 32 mm Hg, PaO2 55 mm Hg

c. pH 7.40, PaCO2 40 mm Hg, PaO2 92 mm Hg

d. pH 7.38, PaCO2 52 mm Hg, HCO3− 31 mmol/L, PaO2 65 mm Hg

Answer: a — A high PaCO2 with a low pH shows an acute rise in CO2 (a) (section 15.1). Option b, with low oxygen and low CO2, fits hypoxemic (type 1) failure in a patient breathing fast. Option c is normal. Option d shows a high PaCO2 with a near-normal pH and raised bicarbonate, the pattern of chronic, compensated CO2 retention (Chapter 14).

4. [CORE] A patient with ARDS remains hypoxemic despite a high FiO2. Which explanation is most accurate?

a. The patient's drive to breathe is suppressed by the oxygen

b. Heart failure is pushing fluid back into the lungs from the left ventricle

c. The oxygen is too dry to cross the alveolar membrane

d. Blood flows past flooded and collapsed alveoli without picking up oxygen

Answer: d — In ARDS, fluid-filled and collapsed alveoli receive blood but no air, creating a shunt that responds poorly to extra oxygen (d) (sections 15.1 and 15.2). Suppressed drive (a) affects CO2 clearance, not shunt. ARDS is noncardiogenic; the edema is not mainly from heart failure (b). Humidity (c) does not explain refractory hypoxemia.

5. [CORE] A patient with pneumonia has bilateral opacities on chest X-ray, developed 3 days after admission, and is receiving high-flow nasal oxygen at 40 L/min. The PaO2/FiO2 ratio is 180 mm Hg, and heart failure has been ruled out. How does the 2024 global definition apply?

a. ARDS cannot be diagnosed until the patient is intubated

b. The patient meets the criteria for ARDS

c. ARDS is ruled out because the onset was after 24 hours

d. ARDS is ruled out because pneumonia explains the opacities

Answer: b — The 2024 definition includes non-intubated patients on high-flow nasal oxygen of at least 30 L/min with a PaO2/FiO2 ratio of 300 mm Hg or less, onset within 1 week of the trigger, and bilateral opacities not explained by heart failure (b) (section 15.2). Intubation is no longer required (a). The time window is 1 week, not 24 hours (c). Pneumonia is a common trigger for ARDS, not an exclusion (d).

6. [CORE] A ventilated patient with severe ARDS has been placed in the prone position. Which nursing action is most important during the prone period?

a. Keep the head turned to the same side throughout to protect the endotracheal tube

b. Stop enteral feeding for the whole prone session

c. Check pressure points often and reposition the head and arms per protocol

d. Return the patient to the supine position as soon as the SpO2 rises above 92%

Answer: c — Pressure injuries and facial swelling are among the most frequent complications of prone positioning. Regular checks and repositioning of the head and arms are common protective strategies (c) (section 15.2). Leaving the head in one position (a) raises the risk of facial pressure injury. Feeding decisions (b) follow the team's protocol, not a fixed rule. Prone sessions are planned for long periods, and an improved SpO2 is not a reason to turn back early (d).

7. [CORE] The daughter of a patient discharged from the ICU after ARDS says, "I can't sleep, and I keep reliving that week." Which response by the nurse is best?

a. "Many families have lasting stress after an ICU stay. Can we talk about supports for you?"

b. "Those feelings are normal, and they will pass on their own once your father is settled at home."

c. "Your father is the patient right now, so his recovery is what we all need to focus on."

d. "You should ask your father's physician to prescribe something for sleep."

Answer: a — Post-intensive care syndrome–family includes anxiety, acute and posttraumatic stress, depression and complicated grief, which can last for years. The nurse acknowledges this and links the family member with support (a) (section 15.2). Promising that it will pass (b) is false reassurance. Dismissing the family member's needs (c) ignores PICS-F. Directing her to her father's physician (d) is not appropriate; she needs her own care and support.

8. [CORE] A patient on bilevel NIV for a COPD exacerbation becomes nauseated and is harder to rouse. What should the nurse do first?

a. Tighten the mask straps to reduce the air leak and improve the delivered pressure

b. Give oral fluids to settle the nausea

c. Lower the head of the bed so the patient can rest more comfortably on the mask

d. Stay, keep the head of the bed raised and call the physician and RT urgently

Answer: d — A drowsy, nauseated patient on a tight mask is at risk of aspiration and may not be able to protect the airway; drowsiness may also mean rising CO2. The nurse stays, keeps the head up and escalates (d) (section 15.3). Tightening the mask (a) adds skin injury risk and does not address the danger. Oral fluids (b) raise aspiration risk. Lowering the head of the bed (c) also raises aspiration risk.

9. [CORE] A patient has been on bilevel NIV for 2 hours for acute hypercapnic respiratory failure. Which finding most strongly suggests NIV is failing?

a. pH fell from 7.29 to 7.23 and respiratory rate rose to 36 breaths/min

b. The respiratory rate has fallen from 30 to 22 breaths/min since NIV was started

c. The patient asks for a short mask break to take a drink of water and rest the face

d. SpO2 is 90% on the ordered oxygen

Answer: a — A worsening pH with a rising respiratory rate means NIV is not reversing hypercapnic failure, and the plan must change (a) (section 15.3). A falling respiratory rate (b) suggests success. A request for a break (c) is common and is managed safely. An SpO2 of 90% (d) is within the usual 88–92% target for hypercapnic failure.

10. [CORE] A patient has just been intubated. Which finding best confirms that the tube is in the trachea?

a. Mist inside the tube during exhalation

b. Breath sounds heard on the right side of the chest

c. A sustained CO2 waveform on capnography with each breath

d. An SpO2 that stays above 92% for the first minute after the tube is placed

Answer: c — A capnography waveform showing CO2 in every exhaled breath is the mainstay for confirming that the tube is in the trachea (c) (section 15.3). Misting (a) and breath sounds (b) can occur even with an esophageal tube and are unreliable. Oxygen saturation (d) may stay high for minutes after an esophageal intubation in a well-oxygenated patient, so it does not confirm placement.

11. [CORE] The high-pressure alarm sounds on a ventilated patient's ventilator. What should the nurse do first?

a. Silence the alarm and call the RT

b. Look at the patient for coughing, biting, secretions or distress

c. Raise the high-pressure alarm limit so that the alarm stops sounding

d. Increase the FiO2

Answer: b — The nurse looks at the patient first; a high-pressure alarm often means coughing, biting, secretions or a kink (b) (section 15.3). Silencing the alarm without assessing (a) is unsafe. Changing alarm limits (c) hides the problem and is outside the nurse's role unless policy allows it. Raising the FiO2 (d) does not address the cause.

12. [CORE] A nurse is planning care for a patient on invasive mechanical ventilation. Which actions help prevent ventilator-associated pneumonia? Select all that apply.

a. Keep the head of the bed at 30–45 degrees unless contraindicated

b. Brush the patient's teeth as part of regular oral care

c. Use chlorhexidine mouth rinse for routine oral care

d. Take part in daily sedation interruption and spontaneous breathing trials

e. Keep the patient sedated deeply to reduce oxygen use

f. Help the patient get out of bed early when safe

Answer: a, b, d, f — Elevating the head of the bed (a), toothbrushing (b), daily sedation interruption and breathing trials (d) and early mobility (f) are essential VAP prevention practices (section 15.3, Table 15.2). Chlorhexidine oral care (c) is no longer recommended because it has no clear effect on VAP rates and may cause harm. Deep sedation (e) prolongs ventilation; light sedation is preferred.

13. [CORE] A ventilated patient has a RASS score of −2. Over the past few hours, the patient's mental status has changed from earlier in the day. On the CAM-ICU letters attention test, the patient makes 5 errors. What does the nurse conclude?

a. Delirium cannot be assessed because the patient is sedated

b. Delirium is absent because the patient follows some commands

c. More testing for disorganized thinking is needed before delirium can be identified

d. The patient screens positive for delirium

Answer: d — The CAM-ICU is positive when an acute change or fluctuation and inattention are both present, plus either an altered level of consciousness or disorganized thinking. A RASS other than 0 means an altered level of consciousness, so all required features are present (d) (section 15.3). The patient responded well enough to complete the letters test, so delirium can be assessed (a). Following some commands does not rule out delirium (b). Disorganized thinking need not be tested because feature 3 is present (c).

14. [CORE] A registered practical nurse (RPN) on a step-down unit in Ontario is asked to care for a patient on bilevel NIV. How should the RPN decide whether to accept the assignment?

a. Weigh authority, competence and context, including employer policy and support

b. Accept, because CNO allows RPNs to care for any patient admitted to a step-down unit

c. Decline, because CNO limits RPNs to caring for stable patients with predictable outcomes

d. Accept, because the RT is solely responsible for patients on NIV

Answer: a — The College of Nurses of Ontario (CNO) Scope of Practice standard asks nurses to consider authority, competence and context (CNO, 2025). Context includes employer policy, the setting and available resources, such as an RN and an RT to consult (a) (section 15.3; Chapter 1, section 1.3). No blanket rule allows every assignment (b). "Stable and predictable" is a common employer practice, not a CNO rule (c). The nurse remains accountable for nursing assessment and care even when an RT manages the device (d).

15. [CORE] Which patient is the best candidate for a trial of bilevel NIV, according to current guidelines?

a. A patient with a COPD exacerbation whose PaCO2 is 52 mm Hg and whose pH is 7.40

b. A patient who is vomiting repeatedly and cannot protect the airway on their own

c. A patient with a COPD flare, pH 7.28 and PaCO2 72 mm Hg despite treatment

d. A patient in respiratory arrest

Answer: c — Bilevel NIV is strongly recommended for COPD exacerbations with respiratory acidosis, and the BTS advises starting it when acidosis persists despite treatment (c) (section 15.3). During an exacerbation, NIV is not suggested for high CO2 without acidosis (a). A patient who cannot protect the airway (b) or who has stopped breathing (d) needs intubation, not NIV.

16. [RN] An intubated patient with ARDS on a PEEP of 10 cm H2O has a PaO2 of 72 mm Hg on an FiO2 of 0.6. How is this patient's ARDS classified under the 2024 global definition?

a. Mild
b. Moderate
c. Severe
d. Not ARDS, because the PaO2 is above 60 mm Hg

Answer: b — The P/F ratio is 72 ÷ 0.6 = 120, which falls in the moderate range (more than 100 and up to 200) for intubated patients on a PEEP of at least 5 cm H2O (b) (Going Deeper box, section 15.3). Mild (a) is more than 200 and up to 300. Severe (c) is 100 or less. The definition uses the ratio, not the PaO2 alone (d).

17. [RN] A ventilated patient with ARDS is 175 cm tall and weighs 110 kg. The ordered tidal volume is based on actual body weight. Which action by the nurse is best?

a. Accept the order, since a larger patient needs larger breaths to meet oxygen demand
b. Increase the respiratory rate to make up for the larger breaths
c. Check the plateau pressure only if the patient's SpO2 begins to fall below target
d. Question the order, because lung-protective ventilation uses predicted body weight

Answer: d — Lung-protective ventilation for ARDS uses 4–8 mL/kg of predicted body weight, which is based on height and sex. Basing it on actual weight in a patient with obesity would overstretch the lungs, so the nurse questions the order with the physician and RT (d) (Going Deeper box, section 15.3). Lung size does not grow with body weight (a). A higher rate (b) does not correct oversized breaths. Plateau pressure is monitored routinely, not only when the SpO2 falls (c).

Case: Harjit Sandhu (Questions 18–27): Harjit Sandhu, 58, is on a surgical unit on day 1 after a right lower lobectomy. He has a right chest drain connected to a drainage unit with wet suction as ordered. His vital signs are stable, and he rates his pain 3 out of 10.

18. [CORE] Which finding shows the nurse that Mr. Sandhu's chest drain is open to the pleural space?

a. Continuous, vigorous bubbling in the water seal chamber during every breath
b. Fluid in the water seal rising and falling with each breath
c. No fluid in the collection chamber over the past 2 hours
d. Absence of bubbling in the wet suction control chamber

Answer: b — Tidalling (b) shows that pressure changes in the pleural space are reaching the water seal, so the drain is open (section 15.5). Continuous bubbling in the water seal (a) means a large air leak or a system leak and must be investigated. No drainage (c) may mean the drain is blocked or that drainage has stopped; it does not show that the drain is open. Gentle continuous bubbling in a wet suction chamber is expected, so its absence (d) suggests the suction is not working as set.

19. [CORE] At 1500, the nurse finds 250 mL of bright red drainage in the collection chamber over the past hour. In the previous hours, drainage was 30 to 50 mL per hour of pink fluid. What should the nurse do first?

a. Milk the tubing firmly from the chest toward the unit to keep clots from blocking the drain
b. Lower the drainage unit further below the chest
c. Assess him and his vital signs, then report to the surgeon at once
d. Record the amount and recheck the drainage in 4 hours

Answer: c — A sudden rise in bright red drainage suggests bleeding, which needs prompt assessment and reporting (c) (section 15.5; Table 15.3). Milking (a) is not routine care and does nothing for bleeding. The unit is already below the chest; moving it lower (b) does not address the problem. Waiting 4 hours (d) delays care for possible hemorrhage.

20. [CORE] Mr. Sandhu is going to the imaging department for a chest X-ray. Which action by the nurse is correct?

a. Keep the unit upright, below his chest and unclamped
b. Clamp the chest tube near the insertion site until he returns to the unit
c. Place the drainage unit on the stretcher beside his pillow so it stays in view
d. Empty the collection chamber into a graduated container before transport so the drainage does not spill

Answer: a — Drains are not clamped for transport; the unit stays upright and below the chest (a) (section 15.5). Clamping (b) can trap air and cause a tension pneumothorax. A unit placed at pillow level (c) is above the chest, so fluid could flow back into the pleural space. The collection chamber of a closed system is not emptied (d); drainage is measured and marked, and the unit is changed only as policy directs.

21. [CORE] While Mr. Sandhu is walking, his chest tube is pulled out of his chest. What is the nurse's priority action?

a. Reinsert the tube gently along the same track, then secure it with tape and notify the surgeon
b. Clamp the tubing and return Mr. Sandhu to bed
c. Ask him to cough forcefully to expel any trapped air
d. Cover the site at once as policy directs and call for help

Answer: d — The nurse covers the site at once with a dressing as policy directs, gets help and watches for a growing or tension pneumothorax (d) (section 15.5). A dislodged drain is never pushed back in (a); a new drain may be needed at a new site. Clamping the tubing (b) does nothing once the tube is out of the chest. Coughing (c) does not remove air from the pleural space and delays care.

22. [CORE] Recognize cues: Which group of findings is most significant?

a. Temperature 37.1 °C, her recent knee surgery, her anxiety and her statement that something is wrong

b. Blood pressure 128/76 mm Hg and alertness

c. Pain in her operated knee and difficulty sleeping

d. Sudden dyspnea, heart rate 118, SpO2 88% and a swollen, tender calf

Answer: d — Sudden breathlessness, tachycardia, hypoxemia and signs of DVT together are the key cues (d) (section 15.6). A normal temperature (a) is not a concerning cue, although recent surgery is a risk factor. Her stable blood pressure and alertness (b) are reassuring, not concerning. Knee pain and poor sleep (c) are expected after surgery and do not explain her sudden symptoms.

23. [CORE] Analyze cues: Which condition best explains Ms. Beaulieu's findings?

a. Opioid-induced respiratory depression

b. Pulmonary embolism

c. Postoperative pneumonia

d. Anxiety attack

Answer: b — Sudden dyspnea, pleuritic chest pain, tachycardia, hypoxemia and a swollen calf after joint replacement point to PE (b) (section 15.6). Opioid-induced respiratory depression (a) causes slow, shallow breathing and drowsiness, not tachypnea (Chapter 5). Pneumonia (c) usually develops over hours to days with fever and cough. An anxiety attack (d) does not cause hypoxemia or a swollen calf, and assuming anxiety could miss a life-threatening condition.

24. [CORE] Prioritize hypotheses: Which problem is the nurse's priority?

a. Impaired gas exchange

b. Fear related to sudden illness

c. Acute pain in the operated knee

d. Risk for falls related to anticoagulant therapy and reduced mobility after knee surgery

Answer: a — Hypoxemia from PE threatens life and comes first (a) (section 15.6). Fear (b) is real and is addressed while care proceeds, but it is not the most urgent problem. Knee pain (c) is not the immediate threat. Fall risk with anticoagulant therapy (d) matters, but it is not an immediate threat to life.

25. [CORE] Generate solutions and take action: What should the nurse do first?

a. Give the prescribed as-needed analgesic for her chest pain, document the findings and reassess her in 30 minutes

b. Encourage her to walk to help her breathing

c. Give oxygen, stay with her and call the rapid response team

d. Massage her calf to relieve the swelling

Answer: c — The nurse treats hypoxemia, stays with the patient and escalates at once (c) (section 15.6; Chapter 6). An analgesic (a) may ease pain but delays escalation for a possible PE. Walking (b) increases oxygen demand in an unstable patient. Massaging a calf with a suspected DVT (d) is avoided and does not treat the problem.

26. [CORE] Take action: The physician orders LMWH to start now and a CT pulmonary angiogram. Ms. Beaulieu asks why she is getting a "blood thinner" before the scan confirms anything. Which response by the nurse is best?

a. "The medication dissolves the clot, so it helps the scan show the problem more clearly."

b. "When a clot is likely, starting treatment during testing keeps it from getting worse."

c. "It is a routine order for everyone after knee surgery, so it is not related to your symptoms."

d. "The scan is risky, and the medication protects your kidneys from the contrast dye."

Answer: b — Guidelines recommend starting anticoagulation when PE is likely, while testing continues (b) (section 15.6). Anticoagulants stop clots from growing; they do not dissolve them, and they do not change how the scan looks (a). Prophylaxis is routine after joint replacement, but this order is for suspected PE, so (c) is misleading. LMWH does not protect the kidneys from contrast (d).

27. [CORE] Evaluate outcomes: CTPA confirmed a PE. Which finding 24 hours later best shows that Ms. Beaulieu is improving?

a. Heart rate 124, new confusion and restlessness

b. Blood pressure 88/50 mm Hg with cool hands

c. Several small bruises at her LMWH injection sites on the abdomen

d. SpO2 94% on 2 L, heart rate 92, less dyspnea

Answer: d — Better oxygen saturation, a slower heart rate and less dyspnea show improvement (d) (section 15.6). A rising heart rate with confusion (a) and low blood pressure with cool hands (b) suggest worsening and possible shock, which need urgent escalation. Small bruises at injection sites (c) are common with LMWH and do not show whether the PE is improving.

28. [CORE] Which findings should the nurse recognize as possible signs of a tension pneumothorax? Select all that apply.

a. Severe, worsening shortness of breath

b. Heart rate 132

c. Falling blood pressure

d. Bradycardia that improves with oxygen

e. Reduced breath sounds on one side

f. Productive cough with fever developing over 3 days

g. Falling SpO2

Answer: a, b, c, e, g — Respiratory distress (a), tachycardia (b), reduced air entry on one side (e) and hypoxemia (g) are early signs. Falling blood pressure (c) is a later sign of obstructive shock (section 15.4). Tension pneumothorax causes a fast heart rate, not bradycardia that improves with oxygen (d). A productive cough with fever over several days (f) suggests infection, not tension pneumothorax.

29. [CORE] A patient's chest drain tubing separates from the drainage unit while the patient is turning in bed. What is the nurse's most appropriate action?

a. Reconnect the tubing at once as policy directs, then assess the patient

b. Leave the tubing open to air until the surgeon arrives to check it

c. Clamp the chest tube close to the dressing and leave it clamped until the next chest X-ray confirms that the lung is expanded

d. Remove the chest tube and cover the site with gauze

Answer: a — The nurse restores the closed system right away as policy directs, using a new sterile unit if the ends are contaminated, and then assesses the patient (a) (section 15.5). An open tube (b) lets air into the chest. Leaving a drain clamped (c) can cause a tension pneumothorax. Removing the drain (d) is outside routine nursing action and is not indicated.

30. [CORE] Which patient has the strongest risk factor for pulmonary embolism?

a. A 30-year-old who sat through a 3-hour bus ride

b. A 45-year-old with mild obesity who walks daily and takes no medications

c. A 70-year-old admitted 2 days ago with a hip fracture who is on bed rest

d. A 25-year-old who is 10 weeks pregnant

Answer: c — Lower-limb fracture is a strong risk factor, and this patient is also older and less mobile (c) (section 15.6). A short bus ride (a) carries little risk; prolonged sitting during long travel is only a weak factor. Obesity (b) is a weak factor, and daily walking lowers stasis. Pregnancy (d) raises risk, but less than a fracture of the leg.

31. [CORE] A patient is receiving alteplase for a high-risk pulmonary embolism. Which finding requires the nurse to stop the infusion as the protocol directs and report at once?

a. Mild oozing at the IV site that stops with light pressure

b. A new severe headache and confusion

c. Heart rate decreasing from 118 to 100

d. SpO2 rising from 88% to 93%

Answer: b — A new severe headache with confusion may signal bleeding in the brain, a critical bleed that calls for stopping the infusion and reporting at once (b) (section 15.6). Minor oozing that stops with pressure (a) is watched and reported, but it is not a critical bleed. A slowing heart rate (c) and rising SpO2 (d) suggest improvement.

32. [CORE] An RPN on a surgical unit is caring for a patient with a chest drain. The patient was stable this morning but is now very short of breath, with SpO2 86% and absent breath sounds on the drain side. What should the RPN do?

a. Stay, call the rapid response team, give oxygen and inform the RN

b. Finish giving medications to her other patients, then report the change to the RN at the next scheduled huddle

c. Ask the RN to take over the patient and return to other assignments

d. Clamp the chest drain to stop air from leaking out

Answer: a — Every nurse who notices deterioration acts at once and escalates, and the RPN consults the RN as the patient's needs change (a) (Scope in Practice box; section 15.4). Delaying (b) risks death from a possible tension pneumothorax. Handing over and leaving (c) abandons an unstable patient. Clamping a drain (d) can make a tension pneumothorax worse.

33. [RN] A 72-year-old patient in the emergency department has suspected PE, and the provider has judged her clinical probability to be low. Her D-dimer result is 620 mcg/L, and the laboratory's standard cut-off is 500 mcg/L. Using an age-adjusted cut-off, how should the nurse interpret this result?

a. The result is above the laboratory's standard cut-off, so CTPA is required to rule out PE

b. The result cannot be used because she is over 50

c. It is below her age-adjusted cut-off of 720 mcg/L, so PE can be excluded without imaging

d. The result means a V/Q scan should replace CTPA

Answer: c — For patients over 50, the age-adjusted cut-off is age × 10 mcg/L, which is 720 mcg/L for this patient. Her result of 620 mcg/L is negative, and with low probability PE is excluded (c) (section 15.6). Against the age-adjusted cut-off the result is not positive (a). Age-adjusted D-dimer was designed for patients over 50, so (b) is wrong. A D-dimer result does not decide between CTPA and V/Q scanning (d).

34. [RN] For which patient with suspected PE would the nurse expect a V/Q scan rather than CTPA?

a. A patient with a past anaphylactic reaction to iodinated contrast

b. A patient with mild asthma and a normal chest X-ray who is not pregnant

c. A patient with a history of hip replacement

d. A patient who is hypotensive and too unstable to leave the emergency department

Answer: a — A V/Q scan is preferred when contrast is a concern, such as after a previous anaphylactic reaction to contrast (a) (section 15.6). Mild asthma with a normal X-ray (b) and a past hip replacement (c) are not reasons to avoid CTPA. An unstable patient (d) needs immediate bedside assessment and treatment, and a V/Q scan is not a bedside test.

35. [RN] A patient with confirmed PE has a blood pressure of 124/78 mm Hg, a raised troponin and a dilated right ventricle on CT. Which plan does the nurse anticipate?

a. Immediate systemic thrombolysis, because a raised troponin shows the right ventricle is failing

b. Discharge home today with an oral anticoagulant

c. No anticoagulation until an echocardiogram is repeated

d. Anticoagulation in hospital with close monitoring

Answer: d — A stable blood pressure with right ventricular strain and a raised troponin means intermediate-risk PE. Treatment is anticoagulation with close monitoring, and reperfusion is considered if the patient worsens (d) (section 15.6; Table 15.4). Routine thrombolysis (a) is not suggested for patients without hemodynamic compromise. Signs of heart strain make home treatment (b) unsuitable. Anticoagulation should not be delayed (c).

References

Abdo, W. F., & Heunks, L. M. A. (2012). Oxygen-induced hypercapnia in COPD: Myths and facts. *Critical Care, 16*(5), Article 323. https://doi.org/10.1186/cc11475

Asciak, R., Bedawi, E. O., Bhatnagar, R., Clive, A. O., Hassan, M., Lloyd, H., Reddy, R., Roberts, H., & Rahman, N. M. (2023). British Thoracic Society clinical statement on pleural procedures. *Thorax, 78*(Suppl 3), s43–s68. https://doi.org/10.1136/thorax-2022-219371

Brasel, K. J., Moore, E. E., Albrecht, R. A., deMoya, M., Schreiber, M., Karmy-Jones, R., Rowell, S., Namias, N., Cohen, M., Shatz, D. V., & Biffl, W. L. (2017). Western Trauma Association critical decisions in trauma: Management of rib fractures. *Journal of Trauma and Acute Care Surgery, 82*(1), 200–203. https://doi.org/10.1097/TA.0000000000001301

Canadian Institute for Health Information. (2016). *Care in Canadian ICUs*. https://www.cihi.ca/sites/default/files/document/care-canadian-icu-report-en.pdf

Chan, K. K., Joo, D. A., McRae, A. D., Takwoingi, Y., Premji, Z. A., Lang, E., & Wakai, A. (2020). Chest ultrasonography versus supine chest radiography for diagnosis of pneumothorax in trauma patients in the emergency department. *Cochrane Database of Systematic Reviews, 2020*(7), Article CD013031. https://doi.org/10.1002/14651858.CD013031.pub2

Choosing Wisely Canada. (2024). *Ten tests and treatments to question in emergency medicine* [Canadian Association of Emergency Physicians list]. https://choosingwiselycanada.org/recommendation/emergency-medicine/

Chrimes, N., Higgs, A., Hagberg, C. A., Baker, P. A., Cooper, R. M., Greif, R., Kovacs, G., Law, J. A., Marshall, S. D., Myatra, S. N., O'Sullivan, E. P., Rosenblatt, W. H., Ross, C. H., Sakles, J. C., Sorbello, M., & Cook, T. M. (2022). Preventing unrecognised oesophageal intubation: A consensus guideline from the Project for Universal Management of Airways and international airway societies. *Anaesthesia, 77*(12), 1395–1415. https://doi.org/10.1111/anae.15817

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026). *Nurse practitioner* [Practice standard]. https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41038_strdrnec.pdf

College of Respiratory Therapists of Ontario. (2024). *Orders for medical care* [Professional practice guideline]. https://orders.crto.on.ca/wp-content/uploads/sites/13/2024/10/Orders-for-Medical-Care-PPG-2024-09-13.pdf

Creager, M. A., Barnes, G. D., Giri, J., Mukherjee, D., Jones, W. S., Burnett, A. E., Carman, T., Casanegra, A. I., Castellucci, L. A., Clark, S. M., Cushman, M., de Wit, K., Eaves, J. M., Fang, M. C., Goldberg, J. B., Henkin, S., Johnston-Cox, H., Kadavath, S., Kadian-Dodov, D., . . . Young, M. N. (2026). 2026 AHA/ACC/ACCP/ACEP/CHEST/SCAI/SHM/SIR/SVM/SVN guideline for the evaluation and management of acute pulmonary embolism in adults: A report of the American College of Cardiology/American Heart Association Joint Committee on Clinical Practice Guidelines. *Circulation, 153*(12). https://doi.org/10.1161/CIR.0000000000001415

da Silva, E. G., Araujo, B. R., Borges, R. D. M., Vieira, T. W., de Paula, C. C., & Caregnato, R. C. A. (2024). Nursing care for adult patients with chest drainage: A scoping review. *Revista da Escola de Enfermagem da USP, 58*, Article e20240017. https://doi.org/10.1590/1980-220X-REEUSP-2024-0017en

Davidson, A. C., Banham, S., Elliott, M., Kennedy, D., Gelder, C., Glossop, A., Church, A. C., Creagh-Brown, B., Dodd, J. W., Felton, T., Foëx, B., Mansfield, L., McDonnell, L., Parker, R., Patterson, C. M., Sovani, M., & Thomas, L. (2016). BTS/ICS guideline for the ventilatory management of acute hypercapnic respiratory failure in adults. *Thorax, 71*(Suppl. 2), ii1–ii35. https://doi.org/10.1136/thoraxjnl-2015-208209

Davidson, J. E., Jones, C., & Bienvenu, O. J. (2012). Family response to critical illness: Postintensive care syndrome–family. *Critical Care Medicine, 40*(2), 618–624. https://doi.org/10.1097/CCM.0b013e318236ebf9

Devlin, J. W., Skrobik, Y., Gélinas, C., Needham, D. M., Slooter, A. J. C., Pandharipande, P. P., Watson, P. L., Weinhouse, G. L., Nunnally, M. E., Rochwerg, B., Balas, M. C., van den Boogaard, M., Bosma, K. J., Brummel, N. E., Chanques, G., Denehy, L., Drouot, X., Fraser, G. L., Harris, J. E., … Alhazzani, W. (2018). Clinical practice guidelines for the prevention and management of pain, agitation/sedation, delirium, immobility, and sleep disruption in adult patients in the ICU. *Critical Care Medicine, 46*(9), e825–e873. https://doi.org/10.1097/CCM.0000000000003299

Drug Shortages Canada. (n.d.). *Drug shortage reports* [Reports for heparin sodium injection (Fresenius Kabi, DIN 02392453) and APO-WARFARIN (Apotex, DIN 02242924), market status "Marketed"; accessed October 25, 2026]. https://www.healthproductshortages.ca/

Fan, E., Del Sorbo, L., Goligher, E. C., Hodgson, C. L., Munshi, L., Walkey, A. J., Adhikari, N. K. J., Amato, M. B. P., Branson, R., Brower, R. G., Ferguson, N. D., Gajic, O., Gattinoni, L., Hess, D., Mancebo, J., Meade, M. O., McAuley, D. F., Pesenti, A., Ranieri, V. M., … Brochard, L. J. (2017). An official American Thoracic Society/European Society of Intensive Care Medicine/Society of Critical Care Medicine clinical practice guideline: Mechanical ventilation in adult patients with acute respiratory distress syndrome. *American Journal of Respiratory and Critical Care Medicine, 195*(9), 1253–1263. https://doi.org/10.1164/rccm.201703-0548ST

Getinge. (n.d.). *Atrium Oasis dry suction water seal chest drain* [Product information]. https://getinge.com/us/products/oasis-dry-suction-water-seal-chest-drain

González-Seguel, F., Pinto-Concha, J. J., Aranis, N., & Leppe, J. (2021). Adverse events of prone positioning in mechanically ventilated adults with ARDS. *Respiratory Care, 66*(12), 1898–1911. https://doi.org/10.4187/respcare.09194

Guérin, C., Reignier, J., Richard, J.-C., Beuret, P., Gacouin, A., Boulain, T., Mercier, E., Badet, M., Mercat, A., Baudin, O., Clavel, M., Chatellier, D., Jaber, S., Rosselli, S., Mancebo, J., Sirodot, M., Hilbert, G., Bengler, C., Richecoeur, J., … Ayzac, L. (2013). Prone positioning in severe acute respiratory distress syndrome. *New England Journal of Medicine, 368*(23), 2159–2168. https://doi.org/10.1056/NEJMoa1214103

Health Canada. (2026). *Drug Product Database* [Database entries for apixaban, rivaroxaban (Xarelto), enoxaparin (Lovenox) and alteplase (Activase rt-PA); accessed October 25, 2026]. https://health-products.canada.ca/dpd-bdpp/

Hoffmann-La Roche. (2024). *Activase rt-PA (alteplase for injection)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00076099.PDF

Indigenous Services Canada. (2022). *Non-Insured Health Benefits (NIHB) program for First Nations and Inuit: Medical transportation policy framework (interim)*. https://www.sac-isc.gc.ca/eng/1579891130443/1579891286837

Island Health. (2018). *CAM-ICU worksheet*. https://www.islandhealth.ca/sites/default/files/2018-05/cam-icu-worksheet.pdf

Klompas, M., Branson, R., Cawcutt, K., Crist, M., Eichenwald, E. C., Greene, L. R., Lee, G., Maragakis, L. L., Powell, K., Priebe, G. P., Speck, K., Yokoe, D. S., & Berenholtz, S. M. (2022). Strategies to prevent ventilator-associated pneumonia, ventilator-associated events, and nonventilator hospital-acquired pneumonia in acute-care hospitals: 2022 update. *Infection Control & Hospital Epidemiology, 43*(6), 687–713. https://doi.org/10.1017/ice.2022.88

Konstantinides, S. V., Meyer, G., Becattini, C., Bueno, H., Geersing, G.-J., Harjola, V.-P., Huisman, M. V., Humbert, M., Jennings, C. S., Jiménez, D., Kucher, N., Lang, I. M., Lankeit, M., Lorusso, R., Mazzolai, L., Meneveau, N., Ní Áinle, F., Prandoni, P., Pruszczyk, P., . . . ESC Scientific Document Group. (2020). 2019 ESC guidelines for the diagnosis and management of acute pulmonary embolism developed in collaboration with the European Respiratory Society (ERS). *European Heart Journal, 41*(4), 543–603. https://doi.org/10.1093/eurheartj/ehz405

Law, J. A., Duggan, L. V., Asselin, M., Baker, P., Crosby, E., Downey, A., Hung, O. R., Jones, P. M., Lemay, F., Noppens, R., Parotto, M., Preston, R., Sowers, N., Sparrow, K., Turkstra, T. P., Wong, D. T., & Kovacs, G. (2021a). Canadian Airway Focus Group updated consensus-based recommendations for management of the difficult airway: Part 1. Difficult airway management encountered in an unconscious patient. *Canadian Journal of Anesthesia, 68*(9), 1373–1404. https://doi.org/10.1007/s12630-021-02007-0

Law, J. A., Duggan, L. V., Asselin, M., Baker, P., Crosby, E., Downey, A., Hung, O. R., Kovacs, G., Lemay, F., Noppens, R., Parotto, M., Preston, R., Sowers, N., Sparrow, K., Turkstra, T. P., Wong, D. T., & Jones, P. M. (2021b). Canadian Airway Focus Group updated consensus-based recommendations for management of the difficult airway: Part 2. Planning and implementing safe management of the patient with an anticipated difficult airway. *Canadian Journal of Anesthesia, 68*(9), 1405–1436. https://doi.org/10.1007/s12630-021-02008-z

Liu, Z., Tao, X., Chen, Y., Fan, Z., & Li, Y. (2015). Bed rest versus early ambulation with standard anticoagulation in the management of deep vein thrombosis: A meta-analysis. *PLOS ONE, 10*(4), Article e0121388. https://doi.org/10.1371/journal.pone.0121388

Matthay, M. A., Arabi, Y., Arroliga, A. C., Bernard, G., Bersten, A. D., Brochard, L. J., Calfee, C. S., Combes, A., Daniel, B. M., Ferguson, N. D., Gong, M. N., Gotts, J. E., Herridge, M. S., Laffey, J. G., Liu, K. D., Machado, F. R., Martin, T. R., McAuley, D. F., Mercat, A., … Wick, K. D. (2024). A new global definition of acute respiratory distress syndrome. *American Journal of Respiratory and Critical Care Medicine, 209*(1), 37–47. https://doi.org/10.1164/rccm.202303-0558WS

National Heart, Lung, and Blood Institute Acute Respiratory Distress Syndrome (ARDS) Clinical Trials Network. (2006). Comparison of two fluid-management strategies in acute lung injury. *New England Journal of Medicine, 354*(24), 2564–2575. https://doi.org/10.1056/NEJMoa062200

Needham, D. M., Davidson, J., Cohen, H., Hopkins, R. O., Weinert, C., Wunsch, H., Zawistowski, C., Bemis-Dougherty, A., Berney, S. C., Bienvenu, O. J., Brady, S. L., Brodsky, M. B., Denehy, L., Elliott, D., Flatley, C., Harabin, A. L., Jones, C., Louis, D., Meltzer, W., … Harvey, M. A. (2012). Improving long-term outcomes after discharge from intensive care unit: Report from a stakeholders' conference. *Critical Care Medicine, 40*(2), 502–509. https://doi.org/10.1097/CCM.0b013e318232da75

O'Driscoll, B. R., Howard, L. S., Earis, J., & Mak, V. (2017). BTS guideline for oxygen use in adults in healthcare and emergency settings. *Thorax, 72*(Suppl. 1), ii1–ii90. https://doi.org/10.1136/thoraxjnl-2016-209729

Ornge. (n.d.). *About*. Retrieved October 25, 2026, from https://www.ornge.ca/about

Ortel, T. L., Neumann, I., Ageno, W., Beyth, R., Clark, N. P., Cuker, A., Hutten, B. A., Jaff, M. R., Manja, V., Schulman, S., Thurston, C., Vedantham, S., Verhamme, P., Witt, D. M., Florez, I. D., Izcovich, A., Nieuwlaat, R., Ross, S., Schünemann, H. J., . . . Zhang, Y. (2020). American Society of Hematology 2020 guidelines for management of venous thromboembolism: Treatment of deep vein thrombosis and pulmonary embolism. *Blood Advances, 4*(19), 4693–4738. https://doi.org/10.1182/bloodadvances.2020001830

Qadir, N., Sahetya, S., Munshi, L., Summers, C., Abrams, D., Beitler, J., Bellani, G., Brower, R. G., Burry, L., Chen, J.-T., Hodgson, C., Hough, C. L., Lamontagne, F., Law, A., Papazian, L., Pham, T., Rubin, E., Siuba, M., Telias, I., … Fan, E. (2024). An update on management of adult patients with acute respiratory distress syndrome: An official American Thoracic Society clinical practice guideline. *American Journal of Respiratory and Critical Care Medicine, 209*(1), 24–36. https://doi.org/10.1164/rccm.202311-2011ST

Roberts, D. J., Leigh-Smith, S., Faris, P. D., Blackmore, C., Ball, C. G., Robertson, H. L., Dixon, E., James, M. T., Kirkpatrick, A. W., Kortbeek, J. B., & Stelfox, H. T. (2015). Clinical presentation of patients with tension pneumothorax: A systematic review. *Annals of Surgery, 261*(6), 1068–1078. https://doi.org/10.1097/SLA.0000000000001073

Roberts, M. E., Rahman, N. M., Maskell, N. A., Bibby, A. C., Blyth, K. G., Corcoran, J. P., Edey, A., Evison, M., de Fonseka, D., Hallifax, R., Harden, S., Lawrie, I., Lim, E., McCracken, D. J., Mercer, R., Mishra, E. K., Nicholson, A. G., Noorzad, F., Opstad, K., . . . Walker, S. (2023). British Thoracic Society guideline for pleural disease. *Thorax, 78*(Suppl 3), s1–s42. https://doi.org/10.1136/thorax-2022-219784

Rochwerg, B., Brochard, L., Elliott, M. W., Hess, D., Hill, N. S., Nava, S., Navalesi, P., Antonelli, M., Brozek, J., Conti, G., Ferrer, M., Guntupalli, K., Jaber, S., Keenan, S., Mancebo, J., Mehta, S., & Raoof, S. (2017). Official ERS/ATS clinical practice guidelines: Noninvasive ventilation for acute respiratory failure. *European Respiratory Journal, 50*(2), Article 1602426. https://doi.org/10.1183/13993003.02426-2016

Sarkar, M., Niranjan, N., & Banyal, P. K. (2017). Mechanisms of hypoxemia. *Lung India, 34*(1), 47–60. https://doi.org/10.4103/0970-2113.197116

Sessler, C. N., Gosnell, M. S., Grap, M. J., Brophy, G. M., O'Neal, P. V., Keane, K. A., Tesoro, E. P., & Elswick, R. K. (2002). The Richmond Agitation–Sedation Scale: Validity and reliability in adult intensive care unit patients. *American Journal of Respiratory and Critical Care Medicine, 166*(10), 1338–1344. https://doi.org/10.1164/rccm.2107138

Shared Health. (2024). *Treatment and referral guidelines for high-risk and intermediate-risk pulmonary embolism in adult patients: Highlights*. https://healthproviders.sharedhealthmb.ca/files/pert-highlights.pdf

Shared Health. (2025). *H05 – Tension pneumothorax* [Emergency treatment guideline]. https://healthproviders.sharedhealthmb.ca/download/572/h-reference/28286/h05-tension-pneumothorax.pdf

Southern Health–Santé Sud. (2024). *Regional adult parenteral drug monograph: Alteplase (pulmonary embolism)*. https://staffnet.southernhealth.ca/download/1065/a-b/30969/alteplase-pulmonary-embolism.pdf

IV Cardiovascular & Vascular Nursing Care

UNIT CLINICAL SCOPE & INTEGRATION

Integrates Canadian Cardiovascular Society (CCS) and Hypertension Canada guidelines across cardiac assessment, 12-lead ECG and bedside dysrhythmia interpretation, pacemaker and ICD care, coronary artery disease, acute coronary syndromes (STEMI/NSTEMI), heart failure, valvular and inflammatory heart disease, hypertension, aortic aneurysms, peripheral arterial disease, and venous thromboembolism.

Contents of UNIT IV

Chapter	Chapter Title	Visual Assets	Page
Chapter 16	Cardiac Assessment and Dysrhythmias	22 Figs • 4 Tbls	p. 439
Chapter 17	Coronary Artery Disease and Acute Coronary Syndromes	5 Figs • 4 Tbls	p. 476
Chapter 18	Heart Failure, Valvular and Inflammatory Heart Disease	10 Figs • 4 Tbls	p. 504
Chapter 19	Hypertension and Vascular Disorders	8 Figs • 4 Tbls	p. 538

16 Cardiac Assessment and Dysrhythmias

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Relate the heart's structure, conduction system and cardiac output to assessment findings.
2. Perform a focused cardiovascular assessment, describing findings accurately on a range of skin tones.
3. Interpret common cardiac tests and laboratory values in SI units (troponin, natriuretic peptides, electrolytes) and prepare patients for them.
4. Apply cardiac monitoring safely: lead placement, alarm management and when monitoring is indicated.
5. Analyze a rhythm strip systematically and recognize common dysrhythmias.
6. Respond to dysrhythmias by stability, including the emergency response to pulseless rhythms.
7. Care for patients with atrial fibrillation, heart blocks, pacemakers, implantable cardioverter-defibrillators, cardioversion and defibrillation.
8. Distinguish RN and RPN roles in cardiac monitoring and dysrhythmia response using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 5	Clinician; Scholar	Foundations of Practice
4, 6, 7	Clinician; Collaborator; Educator	Foundations of Practice; Collaborative Practice
8	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

Heart disease is one of the main causes of death in Canada. In preliminary data for 2024, diseases of the heart caused 17.7% of all deaths, second only to cancer (Statistics Canada, 2026). Heart problems are not confined to cardiac units. A patient recovering from hip surgery may develop a fast, irregular pulse. A patient admitted with pneumonia may wake at night with pressure in the chest. On any unit, the nurse is often the first person to notice the change, and what the nurse does in the next few minutes matters.

This chapter builds the skills that the later cardiac chapters rely on. Section 16.1 reviews how the heart pumps and how its electrical system works. Section 16.2 covers the focused cardiovascular assessment, and section 16.3 the tests used to find heart disease. Section 16.4 explains cardiac monitoring and a step-by-step way to read a rhythm strip. Sections 16.5 to 16.7 apply that method to common dysrhythmias, to atrial fibrillation and flutter, and to heart blocks, pacemakers and implantable devices.

Chapters 16 to 20 form the book's cardiovascular unit:

- Chapter 17: coronary artery disease and acute coronary syndromes;
- Chapter 18: heart failure and valvular and inflammatory heart disease;
- Chapter 19: hypertension, vascular disorders, venous thromboembolism (VTE) and anticoagulation;
- Chapter 20: blood disorders and transfusion.

16.1 The Heart and Its Rhythm: A Brief Review

Structure and Blood Flow

The heart is a muscular pump with four chambers (Figure 16.1). The upper chambers, the right and left atria, receive blood; the lower chambers, the right and left ventricles, pump it out. Four valves keep blood moving in one direction. The **atrioventricular valves** (tricuspid on the right, mitral on the left) sit between each atrium and its ventricle. The **semilunar valves** (pulmonic and aortic) guard the exits from the ventricles. The closing of these valves makes the normal heart sounds (section 16.2) (Warriner et al., 2019). The heart sits inside a protective sac, the pericardium; inflammation of this sac is covered in Chapter 18.

The heart works as two pumps side by side. The right side sends oxygen-poor blood from the body through the lungs, where it picks up oxygen and gives off carbon dioxide (the pulmonary circuit). The left side pumps oxygen-rich blood from the lungs through the aorta to the body (the systemic circuit).



Figure 16.1 The inside of the heart, front view: the four chambers, the four valves and the great vessels. (credit: Figure 19.9, "Internal Structures of the Heart," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)



Figure 16.2 The coronary arteries and cardiac veins on the surface of the heart, front view (top) and back view (bottom). (credit: Figure 19.15, "Coronary Circulation," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

The heart muscle gets its own blood supply from the coronary arteries, which branch off the aorta and run over the surface of the heart (Figure 16.2). When the left ventricle contracts in **systole**, the muscle squeezes the vessels inside its own wall. At rest, blood does not move forward through the large surface coronary arteries of the left ventricle while the ventricle contracts (Sniderman et al., 2025). The left ventricle therefore fills its coronary arteries mainly during **diastole**, the relaxation phase between beats. A very fast heart rate shortens diastole, leaving less time for the heart muscle to receive blood just when it needs more (Chapter 17).

The Conduction System

Each heartbeat starts as an electrical impulse (Figure 16.3). The **sinoatrial (SA) node**, a cluster of specialized cells high in the right atrium near the superior vena cava, is the heart's normal pacemaker because its cells fire faster than any others (Sampson & McGrath, 2015). A rhythm that starts in the SA node is called a sinus rhythm.

The impulse spreads across both atria, which contract and push blood into the ventricles. It then reaches the **atrioventricular (AV) node**, low in the right atrium. In a normal heart, the AV node and the bundle of His are the only route from the atria to the ventricles. The AV node conducts about ten times more slowly than the surrounding muscle. This built-in delay lets the atria finish emptying before the ventricles contract. It also limits how many impulses reach the ventricles when the atria fire very fast, as in atrial fibrillation (section 16.6) (Sampson & McGrath, 2015).

From the AV node, the impulse travels down the bundle of His, which divides into the right and left bundle branches. These end in the Purkinje fibres, which spread the impulse through the ventricles almost at once, so the ventricles contract together (Sampson & McGrath, 2015).

Every part of the system can produce impulses, but lower sites fire more slowly. Typical intrinsic rates are 60 to 100 beats per minute (bpm) for the SA node, 40 to 60 bpm for the AV node and 20 to 40 bpm for the His–Purkinje system (Sampson & McGrath, 2015). If the SA node fails, a lower site can take over as a backup. These backup pacemakers are slower, and those below the AV junction are less reliable (Sampson, 2016). Section 16.7 shows why this matters in heart block.

Electrical activation of heart muscle cells is called **depolarization**; it triggers contraction. The return of the cells to their resting electrical state is **repolarization**. On the electrocardiogram (ECG), the **P wave** shows atrial depolarization, the **QRS complex** shows ventricular depolarization, and the **T wave** shows ventricular repolarization (Sampson & McGrath, 2015). The ECG records electrical activity only. It does not show whether the heart is pumping blood, which is why the nurse always checks the patient (section 16.4) (Figure 16.4).



Figure 16.3 The conduction system of the heart, from the sinoatrial (SA) node through the atrioventricular (AV) node and bundle of His to the bundle branches and Purkinje fibres. (credit: Figure 19.18, "Conduction System of the Heart," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)



Figure 16.4 A normal ECG cycle with its waves, intervals and segments labelled. (credit: Figure 19.23, "Electrocardiogram," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Cardiac Output

Cardiac output is the amount of blood the heart pumps each minute. It equals the heart rate multiplied by the **stroke volume**, the amount the left ventricle ejects with each beat (Vincent, 2008). Three factors shape stroke volume:

- **Preload:** how much the ventricle fills, and so how much its muscle is stretched, before it contracts (Vincent, 2008). Bleeding and dehydration lower it; fluid overload raises it.
- **Afterload:** the force the ventricle must work against to eject blood (Vincent, 2008). High blood pressure or a narrowed aortic valve raises it.
- **Contractility:** the strength of the muscle's squeeze, apart from how much it was stretched. Damaged heart muscle contracts less well.

The autonomic nervous system adjusts these factors. Sympathetic nerves act like an accelerator: they speed the heart rate and conduction and strengthen contraction during exercise or stress. Parasympathetic fibres in the vagus nerve act like a brake, slowing the heart at rest (Sampson & McGrath, 2015).

A heart rate that is too slow, as in a severe bradycardia, can lower cardiac output because too few beats occur each minute. A rate that is too fast can also lower it. Acute supraventricular or ventricular tachycardia can lower cardiac output enough to cause cardiogenic shock (Vincent, 2008), partly because a fast rate shortens diastole and leaves the ventricles too little time to fill. The nurse looks for the effects: dizziness, low blood pressure, confusion, chest pain or breathlessness (sections 16.2 and 16.5).

16.2 Focused Cardiovascular Assessment

History

The nurse asks open questions and records the patient's own words. For chest pain or discomfort, the nurse explores:

- **Onset:** when and how it started, and what the patient was doing;
- **Location and radiation:** where it is felt and whether it spreads to the neck, jaw, shoulders, arms or back;
- **Character:** the patient's words, such as pressure, squeezing, fullness, burning or heaviness (Heart and Stroke Foundation of Canada, n.d.-d);
- **Severity and duration:** a pain score (Chapter 5) and how long it lasts;
- **Triggers and relief:** exertion, emotion, meals, breathing, position, rest or medication.

Some patients deny "pain" but describe tightness, pressure or discomfort; such differences in wording are one reason heart attacks in women are missed (Mulvagh et al., 2024).

Associated symptoms matter as much as the pain. The nurse asks about **dyspnea** (shortness of breath), diaphoresis (sweating), nausea, light-headedness, unusual fatigue, palpitations (an awareness of the heartbeat), **syncope** (fainting), swelling of the legs, and **orthopnea**, breathlessness when lying flat (Chapter 18).

Chest pain or discomfort is the most common sign of a heart attack in both women and men (Heart and Stroke Foundation of Canada, n.d.-d; Mehta et al., 2016). Yet many people have none. In a large United States registry of patients with myocardial infarction, 42.0% of women and 30.7% of men presented without chest pain (Canto et al., 2012). Women more often report dyspnea, fatigue or weakness (Mehta et al., 2016). They may also feel pressure in the upper abdomen or upper back, dizziness or extreme fatigue (Heart and Stroke Foundation of Canada, n.d.-d). The nurse never rules out a cardiac cause because the symptoms do not fit the classic picture.

The rest of the history covers:

- **Risk factors:** smoking, high blood pressure, diabetes, high cholesterol, family history and others (Chapter 17);
- **Medications:** prescribed, over-the-counter and natural health products, recent changes, missed doses, and anticoagulants or antiplatelets (section 16.3);
- **Substance use:** tobacco, alcohol, cannabis and stimulants such as cocaine or methamphetamine, asked about without judgment (Chapter 11).

Physical Assessment

Vital signs. The nurse counts an irregular pulse for a full minute. Oxygen saturation (SpO2) is checked with its limits in mind, including reduced accuracy on darker skin (Chapter 12). A **pulse deficit** is the difference between the apical rate, counted with a stethoscope over the apex of the heart, and the radial rate. Two nurses count at the same time for 1 minute, one at the apex and one at the wrist (Abbas et al., 2024). A deficit means some beats heard at the apex are not felt at the wrist; an ECG identifies the rhythm more accurately than the deficit does (Abbas et al., 2024). Orthostatic blood pressure, measured lying and then standing, helps when a patient reports dizziness or fainting (Chapter 8).

Inspection. The **jugular venous pressure (JVP)** estimates the pressure in the right side of the heart. With the patient reclining, the head of the bed is raised to the angle that brings the top of the pulsation in the right internal jugular vein into view, often between 30 and 60 degrees. The vertical height of the top of the pulsation is measured above the sternal angle; a height of more than about 3 cm is above normal. Unlike the carotid pulse, the venous pulse cannot be felt, has two peaks with each beat, and fades with gentle pressure just above the clavicle. A raised JVP most often reflects high filling pressures from heart failure (Chua Chiaco et al., 2013; Chapter 18).

Palpation. The nurse compares the radial, brachial, femoral, popliteal, dorsalis pedis and posterior tibial pulses on both sides. Each carotid pulse is checked one at a time. Each pulse is described as absent, weak, normal or bounding on the agency's scale, and skin temperature and capillary refill are compared with earlier findings.

Edema. Firm pressure over the shin, ankle or top of the foot can leave a pit. A common scale grades pitting from 0 (none) to 4 (a very deep pit of about 8 mm in a grossly swollen limb), but it is subjective, and examiners often disagree. Ankle circumference measured with a tape is more reliable for tracking change (Brodovicz et al., 2009). On darker skin, swelling may show as a larger, shiny area or marked indentation along the sock line (Mukwende et al., 2020).

Auscultation. The first heart sound (**S1**) is the closing of the atrioventricular valves at the start of systole. The second (**S2**) is the closing of the semilunar valves at the start of diastole. The nurse listens with the diaphragm in four areas (Figure 16.5): aortic (second intercostal space, right sternal edge), pulmonic (second intercostal space, left sternal edge), tricuspid (lower left sternal edge) and mitral (fifth intercostal space, midclavicular line). The bell picks up low-pitched sounds (Warriner et al., 2019). Extra sounds include:

- **S3:** a sound in early diastole, just after S2, from rapid ventricular filling. It can be normal in young people and athletes (Warriner et al., 2019); a new S3 in an older adult is reported (Chapter 18).
- **S4:** a sound in late diastole, just before S1. It is always abnormal and is linked to cardiomyopathies or increased afterload (Warriner et al., 2019).
- **Murmur:** a sound made when smooth blood flow becomes turbulent. Murmurs are described by timing (systole or diastole), location, loudness and quality (Warriner et al., 2019). A new murmur is reported (Chapter 18).



Figure 16.5 Where to listen to the heart: the aortic, pulmonic, tricuspid and mitral areas. (credit: "2030 Stethoscope Placement" by OpenStax College/Wikimedia Commons, CC BY 3.0)

Perfusion on a range of skin tones. Pallor and cyanosis are harder to see on darker skin, and visual assessment alone is unreliable (Pusey-Reid et al., 2023). The nurse looks where the skin is thin and blood vessels are close to the surface: the lips, tongue and inside of the mouth, the conjunctivae, the nail beds, palms and soles (Mukwende et al., 2020; Pusey-Reid et al., 2023). On dark skin, cyanosis may make the lips and tongue look grey or whitish, and pallor may make the skin look ashen grey; the conjunctivae look pale pink or white with pallor on any skin tone (Mukwende et al., 2020; Pusey-Reid et al., 2023). Natural light works best, and the nurse compares with an unaffected area (Pusey-Reid et al., 2023). Chapter 12 covers cyanosis and oximetry, and Chapter 6 covers mottling and other signs of shock.

Recognizing Deterioration

Low cardiac output shows up as poor perfusion: a rising heart rate, falling blood pressure, new restlessness or confusion, cool clammy skin, weak pulses, falling urine output and breathlessness. Together, these cues suggest cardiogenic shock (Chapter 6). Every nurse who notices deterioration stays with the patient, calls for help as the agency's rapid response criteria direct, and reports using SBAR (Situation, Background, Assessment, Recommendation; Chapter 6). The RPN consults the RN as the patient's needs change.

New chest pain, or symptoms that could stand in for it, are treated as an emergency until proven otherwise. The nurse stays with the patient, checks vital signs, obtains a 12-lead ECG as ordered or as agency policy directs (section 16.3), and notifies the prescriber or rapid response team (Chapter 6; acute coronary syndromes are covered in Chapter 17). Outside hospital, people with heart attack signs should call 9-1-1 at once (Heart and Stroke Foundation of Canada, n.d.-d).

LIFESPAN CONSIDERATIONS

Chest Pain and Heart Symptoms in Older Adults and Women

- **Older adults:** Heart disease is very common late in life. In 2012/13, diagnosed ischemic heart disease was recorded for 38.5% of women and 47.9% of men aged 85 and older in Canada (Public Health Agency of Canada [PHAC], 2017). Illness often shows up differently in older adults (Chapter 8), so the nurse treats new breathlessness, fatigue, confusion or a fall as a possible cardiac cue.
- **Age and sex together:** In one large registry, heart attacks without chest pain were more common in women than in men. The gap was widest in younger adults and had nearly closed in those aged 75 and older (Canto et al., 2012).
- **Women:** After a heart attack, women's risk of dying is on average 30% higher than men's. Subtler symptoms, more coexisting illnesses and delays in care help explain this gap (PHAC, 2017). Women with ST-elevation myocardial infarction (STEMI) are also slower to recognize their symptoms and to seek care (Mulvagh et al., 2024).
- **Nursing focus:** Ask about every symptom, use the patient's words, and never dismiss "indigestion", jaw pain or exhaustion without assessment.

16.3 Cardiac Tests

The 12-Lead ECG

The 12-lead ECG records the heart's electrical activity from 10 electrodes as 12 views, or leads: six limb leads (I, II, III, aVR, aVL and aVF) and six precordial (chest) leads, V1 to V6 (Kligfield et al., 2007; Figure 16.6). It shows the rhythm, conduction problems, ischemia or infarction (Chapter 17) and some electrolyte and drug effects (Chapter 3).



Figure 16.6 A 12-lead ECG in normal sinus rhythm. Each row shows four leads; the long strip along the bottom is lead II. (credit: "Normal sinus rhythm" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Misplaced electrodes change the tracing, so placement must be exact (Figure 16.7) (Kligfield et al., 2007; Society for Cardiological Science and Technology [SCST], 2014):

- **Limb electrodes:** on the arms and legs, usually just above the wrists and ankles; for a diagnostic 12-lead, never on the torso;
- **V1:** right sternal border, fourth intercostal space;
- **V2:** left sternal border, fourth intercostal space;

- **V3:** midway between V2 and V4;
- **V4:** midclavicular line, fifth intercostal space;
- **V5:** anterior axillary line, level with V4;
- **V6:** midaxillary line, level with V4 and V5.

To find the fourth intercostal space, the nurse locates the sternal angle, moves to the second intercostal space beside it, and counts down. V1 and V2 are often placed too high, and V4 to V6 too low. When breast tissue covers the sites, V4 to V6 usually go under the breast, which the nurse lifts gently with the back of the hand (Kligfield et al., 2007; SCST, 2014).

The skin should be clean and dry. Mild soap, an alcohol wipe or very light abrasion helps, and chest hair is clipped only when needed and with the patient's agreement. The patient reclines at about 45 degrees with relaxed, supported limbs to limit muscle interference. The standard recording speed is 25 mm per second (Kligfield et al., 2007; SCST, 2014).



Figure 16.7 Placement of the six chest (precordial) electrodes, V1 to V6, for a 12-lead ECG. The dotted line marks the left midclavicular line. (credit: "ECG lead positioning" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

For acute chest pain, the 2021 American chest pain guideline from the American Heart Association, the American College of Cardiology and partner societies calls for an ECG to be recorded and read within 10 minutes of the patient's arrival, in any care setting (Gulati et al., 2021). The nurse obtains the ECG as ordered or as a medical directive allows, labels it with the time and the patient's symptoms, and shows it to the prescriber at once (Chapter 1, section 1.3).

Blood Tests

Troponins are heart muscle proteins that enter the blood when the cells are damaged. **High-sensitivity cardiac troponin** (hs-troponin) tests measure very low levels precisely (Reichlin et al., 2015). Myocardial injury is present when troponin is above the 99th percentile upper reference limit (the value below which 99% of healthy people fall), and a rise or fall on repeat samples shows that the injury is acute. Results are reported in nanograms per litre (ng/L) (Thygesen et al., 2018). Rapid pathways repeat the test after a short interval; one validated algorithm compares a sample at arrival with one taken 1 hour later (Reichlin et al., 2015), so the nurse draws each sample on time and records the exact time. Troponin can also rise without a heart attack, for example with tachydysrhythmias, myocarditis or pulmonary embolism (Reichlin et al., 2015).

Natriuretic peptides, B-type natriuretic peptide (BNP) and N-terminal pro-BNP (NT-proBNP), are released by heart muscle mainly when wall stress increases. A low level makes heart failure an unlikely cause of acute breathlessness. Levels rise with age and kidney impairment and differ between assays (Felker et al., 2006; Chapter 18).

Potassium, magnesium and calcium affect how heart cells fire (Chapter 3). Reference ranges vary by laboratory (Table 16.1).

Table 16.1 Cardiac biomarkers and other key laboratory tests (Felker et al., 2006; Reichlin et al., 2015; Thygesen et al., 2018; original wording)

Test	What it shows	Notes for the nurse
High-sensitivity cardiac troponin	Injury to heart muscle cells; a rise or fall on repeat samples suggests acute injury	Reported in ng/L; draw repeat samples exactly on time per protocol; can rise without a heart attack; ranges vary by laboratory and assay
BNP or NT-proBNP	Wall stress in the heart; helps judge whether heart failure explains breathlessness	Higher with older age and kidney impairment, lower with obesity; assays are not interchangeable; see Chapter 18

Test	What it shows	Notes for the nurse
Potassium	Electrolyte that strongly affects heart cell excitability	High or low levels can cause dysrhythmias; avoid hemolysis when drawing; ranges vary by laboratory; see Chapter 3
Magnesium	Electrolyte linked to stable heart rhythm	Low levels can cause dysrhythmias and often occur with low potassium; ranges vary by laboratory; see Chapter 3
Calcium	Electrolyte needed for heart muscle contraction and conduction	Abnormal levels can change the ECG; ranges vary by laboratory; see Chapter 3
Complete blood count	Hemoglobin and other blood cells	Anemia reduces oxygen delivery to the heart; also checked before invasive tests; ranges vary by laboratory; see Chapter 20

Imaging and Invasive Tests

Echocardiography uses ultrasound to show the heart's structure and movement (Heart and Stroke Foundation of Canada, n.d.-e), usually with a probe on the chest. For a **transesophageal echocardiogram (TEE)**, often used to look for clots in the heart, a probe passes into the esophagus. The patient fasts for 4 to 6 hours, may receive a mild sedative, has the throat numbed with an anesthetic, and needs someone to drive them home (Heart and Stroke Foundation of Canada, n.d.-f). The nurse monitors sedation as policy directs and follows the agency's protocol on when eating can resume, because a numbed throat raises the risk of choking.

An **exercise stress test** records the heart's response as the patient walks on a treadmill or pedals, until the heart reaches the fastest safe rate or chest pain develops. Patients usually avoid food and smoking for at least 2 hours beforehand (Heart and Stroke Foundation of Canada, n.d.-b).

Cardiac catheterization threads a thin tube through a vessel in the groin or arm into the heart. In angiography, dye injected through it shows the coronary arteries on X-ray (Heart and Stroke Foundation of Canada, n.d.-a). Before the test, the nurse confirms consent and fasting, reviews anticoagulants, antiplatelets and the diabetes plan (Heart and Stroke Foundation of Canada, n.d.-a), asks about past reactions to contrast, and checks kidney function. Canadian radiology guidance states that kidney injury after contrast is a risk mainly for people with an estimated glomerular filtration rate (eGFR) of 30 mL/min/1.73 m² or less or with existing acute kidney injury. Needed contrast should not be withheld, and metformin is held only for those patients (Macdonald et al., 2022). Afterward, the nurse checks the access site for bleeding or swelling and the limb below it for pulse, colour, warmth and sensation (Chapter 17).

Holter monitors record the rhythm continuously for 24 hours or longer while the patient keeps a symptom diary. **Event monitors** record only when the patient triggers them during symptoms (Heart and Stroke Foundation of Canada, n.d.-c).

CANADIAN CONTEXT

Heart Disease Across Canada

- **Burden:** In 2024, diseases of the heart caused 17.7% of deaths in Canada, second to cancer (Statistics Canada, 2026). In 2012/13, about 2.4 million adults aged 20 and older (8.5%) were living with diagnosed ischemic heart disease (PHAC, 2017).
- **Women:** Heart and Stroke's 2018 report found that two-thirds of clinical research on heart disease still focused on men. It also reported that 78% of women had warning signs that went unrecognized before their heart attack, and that the exercise treadmill (stress) test is far less sensitive in women than in men (Heart and Stroke Foundation of Canada, 2018).
- **Indigenous women:** The same report described a 53% higher death rate from coronary heart disease among Indigenous women than non-Indigenous women. It also noted a lack of cardiac care in the remote and rural hospitals that serve women living on reserve (Heart and Stroke Foundation of Canada, 2018). This pan-Indigenous figure is not distinctions-based. The gap reflects colonialism, racism and unequal access to care, not biology (Chapter 2). OCAP® principles apply whenever First Nations data are used.
- **Rural access:** Distance from cardiac services shapes how fast patients reach an ECG, a catheterization laboratory or rehabilitation.

GOING DEEPER

Reading the 12-Lead ECG

Required for RN students; optional for PN students.

- **Leads as views:** Each lead looks at the heart's electrical activity from a different angle. The limb leads come from the arm and leg electrodes; the precordial leads, V1 to V6, cross the front and left side of the chest (Kligfield et al., 2007).
- **Contiguous leads:** Leads that look at neighbouring areas of the heart are read as groups: I and aVL; V1 to V6; and II, III and aVF, often called the inferior leads (Thygesen et al., 2018). ST-segment changes are judged significant when they appear in at least two contiguous leads.
- **Axis:** The axis is the overall direction of the ventricles' electrical activity, viewed by the limb leads. The ECG machine reports it in degrees; in adults, a normal axis lies between −30° and +90° (Surawicz et al., 2009). A value outside this range is called left or right axis deviation and can accompany conduction blocks or changes in the ventricles; a qualified clinician interprets it.
- **ST and T changes:** New ST elevation, measured at the J point, in two contiguous leads, new horizontal or downsloping ST depression, and new T-wave inversion can signal myocardial ischemia or injury. The thresholds vary with the lead, sex and age (Thygesen et al., 2018); Chapter 17 explains them.
- **QTc:** The QT interval spans the start of the QRS through the end of the T wave. Because it shortens as the heart speeds up, it is corrected for rate (QTc). The common Bazett formula (QT ÷ √R–R, with R–R in seconds) overestimates the QTc at fast rates. A QTc above 450 ms in males or 460 ms in females is prolonged. Above 500 ms, the risk of torsades de pointes, a dangerous ventricular tachycardia, rises; the prescriber is notified at once, and a drug causing the prolongation is generally stopped. Measure in the lead with the longest T wave, and do not compare monitor values with 12-lead values (Sandau et al., 2017).

16.4 Cardiac Monitoring and Reading a Rhythm Strip

Who Needs Monitoring

The American Heart Association's practice standards list common indications, with suggested durations (Sandau et al., 2017):

- intermediate- or high-risk acute coronary syndrome (at least 24 to 48 hours, or until it is ruled out), and at least 12 to 24 hours after a blocked coronary artery is reopened;
- fainting that may have a cardiac cause (at least 24 hours, and until the cause and treatment are identified);
- new or recurrent atrial fibrillation, until a treatment plan is set;
- symptomatic bradycardia, symptomatic second- or third-degree AV block, and some second- or third-degree blocks even without symptoms (section 16.7);
- moderate to severe potassium or magnesium imbalance, until corrected;
- drug overdose, until the drug's effects have resolved;
- the first 12 to 24 hours after a pacemaker is placed in a patient who depends on it.

A stable patient with long-standing atrial fibrillation admitted for an unrelated reason does not need monitoring. The need for monitoring should be reviewed no less often than every 24 to 48 hours (Sandau et al., 2017), and stopping it when it is no longer needed reduces alarms.

Telemetry sends the ECG from a small wireless transmitter to a central station, so patients can move about. Bedside monitors, common in critical care, display the rhythm in the room. A patient with a strong indication who leaves the unit is monitored with a portable monitor-defibrillator, accompanied by a provider skilled in its use and in reading the ECG (Sandau et al., 2017).

Lead Placement and Signal Quality

For monitoring, the limb electrodes are placed on the torso so patients can move freely with less artifact (Sandau et al., 2017). In a common 3-electrode system, the right arm electrode sits below the right clavicle, the left arm electrode below the left clavicle, and the left leg electrode on the lower left rib cage. A 5-electrode system adds a right leg electrode on the lower right rib cage and a chest electrode, usually in the V1 position (Sampson, 2018). V1 is often chosen because it helps tell ventricular tachycardia from other wide rhythms (Sandau et al., 2017). Colour codes differ between standards, so the nurse follows the labels on the lead wires. Because torso placement changes the waveforms, a monitor strip is never a substitute for a 12-lead ECG (Sampson, 2018).

The skin must be dry and free of oil, loose flakes and excess hair. The nurse washes with soap and water or uses an alcohol wipe, exfoliates gently with dry gauze, and clips hair if needed (Sampson, 2018). In a before-and-after study on one 36-bed adult cardiac telemetry unit, daily electrode changes were followed by a 74% drop in telemetry alarms (McGuffin & Ortiz, 2019).

An **artifact** is a signal on the monitor that does not come from the heart. Loose electrodes, dried gel, movement, shivering and tremor are common causes. Low-amplitude complexes can make the monitor miss beats, and artifact can mimic ventricular tachycardia (Drew et al., 2014).

Alarm Safety

Most monitor alarms need no action. In one study of intensive care units, audible alarms averaged 187 per bed per day, and 88.8% of the arrhythmia alarms reviewed were false (Drew et al., 2014). Other studies found 89% to 99% of ECG monitor alarms to be false or clinically insignificant (American Association of Critical-Care Nurses [AACN], 2018).

Alarm fatigue is the desensitization that follows: clinicians exposed to too many alarms respond more slowly or miss alarms, and deaths have been linked to it (AACN, 2018). Safer practice includes:

- monitoring only patients with an indication (Sandau et al., 2017);
- setting alarm limits to the patient's baseline and the purpose of monitoring, within agency policy (Sandau et al., 2017);
- preparing the skin and changing electrodes as policy directs (McGuffin & Ortiz, 2019);
- never permanently silencing alarms (Sampson, 2018) and always assessing the patient.

A Systematic Strip Analysis

ECG paper is a grid of small 1-mm boxes, with a heavier line every five boxes. At the standard speed of 25 mm per second (Kligfield et al., 2007; SCST, 2014), each small box equals 0.04 seconds (1 mm ÷ 25 mm per second) and each large box 0.20 seconds. Thirty large boxes equal 6 seconds. Two quick rate methods follow:

- **6-second method:** count the QRS complexes in a 6-second strip and multiply by 10. It works for regular and irregular rhythms.
- **Large-box method:** for a regular rhythm only, divide 300 by the number of large boxes between two R waves.

The nurse then works through the same steps every time (Table 16.2).

Normal sinus rhythm meets all of these criteria: a regular rhythm at 60 to 100 bpm; an upright P wave before every QRS; a PR interval of 0.12 to 0.20 seconds (3 to 5 small boxes); and a QRS narrower than 0.12 seconds (fewer than 3 small boxes) (Sampson, 2016; Sampson & McGrath, 2015). In adults, a QRS of 0.12 seconds or more is wide, as in complete bundle branch block (Surawicz et al., 2009). The 60 to 100 bpm range is the traditional one. The 2018 American College of Cardiology, American Heart Association and Heart Rhythm Society (ACC/AHA/HRS) bradycardia guideline defines sinus bradycardia as a sinus rate below 50 bpm (Kusumoto et al., 2019), so by that definition a sinus rate of 50 to 59 bpm is not called bradycardia (section 16.5).

The strip never replaces the patient. A chaotic tracing in a patient who is chatting and brushing their teeth is almost certainly artifact. A flat line in a patient who is awake points to a loose lead. An organized rhythm in a patient with no pulse is a cardiac arrest (section 16.5). The nurse looks at the patient, checks responsiveness and pulse, and only then interprets the screen.

Table 16.2 Steps of rhythm strip analysis (Kusumoto et al., 2019; Sampson, 2016; Sampson & McGrath, 2015; Sandau et al., 2017; Surawicz et al., 2009; original wording)

Step	What to look at	Normal finding	What an abnormal finding may mean
Rate	Count QRS complexes (6-second method) or use 300 divided by large boxes between R waves	60 to 100 bpm for a sinus rhythm (traditional range; one guideline defines sinus bradycardia as under 50 bpm)	Slower suggests bradycardia; faster suggests tachycardia (section 16.5)
Regularity	Measure the R–R intervals across the strip with calipers or paper	R–R intervals about equal	Irregular spacing suggests early beats, atrial fibrillation or some heart blocks
P waves	Look for one upright, similar P wave before each QRS	One P wave before every QRS	Missing, extra, inverted or chaotic P waves suggest a rhythm starting outside the SA node or a block
PR interval	Measure from the start of the P wave to the start of the QRS	0.12 to 0.20 seconds (3 to 5 small boxes), the same each beat	Longer, lengthening or varying PR intervals suggest AV block (section 16.7)

Step	What to look at	Normal finding	What an abnormal finding may mean
QRS duration	Measure from the start to the end of the QRS	Less than 0.12 seconds (fewer than 3 small boxes)	A QRS of 0.12 seconds or more suggests a bundle branch block or a beat that starts in the ventricles
QT and QTc	Measure from QRS onset through the end of the T wave, in the lead with the longest T wave; correct for rate	QTc 450 ms or less in males and 460 ms or less in females	A prolonged QTc raises the risk of torsades de pointes; over 500 ms is high risk

CLINICAL SAFETY

Monitor Alarms

- Go to the patient for every alarm. Look, check responsiveness and breathing, and feel for a pulse before deciding the alarm is false.
- Never turn alarms off or permanently silence them. If a pause is needed during care, use the agency's temporary pause and stay with the patient.
- Set alarm limits to the patient's own baseline, following policy and the prescriber's orders, and review them at every handover.
- Prepare the skin, place electrodes correctly, and change them as policy directs. Most false alarms come from poor signal, not from the heart.
- Ask each day whether the patient still needs monitoring. Unneeded monitoring adds alarms and burden.
- Report repeated false alarms and device problems through the agency's safety reporting system.
- Remember why this matters: in one study, most arrhythmia alarms were false, yet the true alarms still included ventricular tachycardia (Drew et al., 2014).

16.5 Common Dysrhythmias and How to Respond

A **dysrhythmia** is any rhythm other than normal sinus rhythm: one that is too fast, too slow, irregular or started from the wrong place. Section 16.4 set out a step-by-step way to read a rhythm strip. This section applies that method to common rhythms and to what the nurse does next. Table 16.3 brings the key points together.

Responding by Stability

The response to a new rhythm begins with the patient, not the monitor. An alarm or an odd-looking strip sends the nurse to the bedside to check responsiveness, breathing and a pulse, and to rule out artifact from movement or loose electrodes (section 16.4). The same rhythm can be harmless in one person and dangerous in another, so the deciding question is whether the rhythm is causing poor perfusion.

The Heart and Stroke Foundation of Canada, a member of the International Liaison Committee on Resuscitation (ILCOR), publishes a Canadian edition of the highlights of the 2025 American Heart Association (AHA) resuscitation guidelines, adapted to Canadian systems, practices and drugs (Heart and Stroke Foundation of Canada, 2025). Because Canadian guidance follows this science, this chapter cites the AHA guidelines where the Canadian edition follows them. That guidance treats a fast rhythm as unstable when it comes with **hypotension**, a sudden change in mental status, signs of shock, chest pain or acute heart failure (Wigginton et al., 2025). A slow rhythm is judged the same way: dizziness, confusion, chest discomfort, fainting, low blood pressure or new heart failure signs show that the slow rate is harming perfusion. Pallor and cyanosis can be harder to see on darker skin, so the nurse also checks the lips, oral mucosa, nail beds and conjunctivae (Chapter 12).

When the patient is unstable, the nurse stays at the bedside and calls for help at once through the rapid response or code system (Chapter 6). While help comes, the nurse supports airway and breathing, gives oxygen if saturation is below the target (Chapter 12), keeps the patient on the monitor, confirms intravenous (IV) access and, if the patient's condition allows, records a 12-lead ECG, which shows the rhythm in more detail than a monitor strip. In a stable patient there is time to look for causes. Many dysrhythmias have a correctable trigger: low or high potassium or low magnesium (Chapter 3, sections 3.5–3.6), hypoxemia (Chapter 12), drugs

that slow or speed the heart, stimulant use (Chapter 11), pain, fever, low blood volume and myocardial ischemia (Chapter 17). The AHA notes that a slow rhythm may not resolve until its cause is treated (Wigginton et al., 2025).

Sinus Rhythms

In **sinus bradycardia**, the sinus node fires in the normal way but slowly (Figure 16.8). The 2018 American College of Cardiology (ACC), AHA and Heart Rhythm Society (HRS) guideline defines it as a sinus rate below 50 per minute, lower than the 60 per minute used in the past (Kusumoto et al., 2019; Wigginton et al., 2025). A slow rate is normal for many fit adults and during sleep. Causes include high vagal tone, rate-slowing drugs, hypothyroidism, hypothermia, hypoxemia and ischemia (Kusumoto et al., 2019). The rhythm matters when it causes symptoms. For bradycardia with poor perfusion, the guidance supports atropine; if atropine does not work, an infusion of an adrenergic drug such as epinephrine or dopamine, or transcutaneous pacing, may be used while transvenous pacing is arranged (Wigginton et al., 2025; section 16.7).



Figure 16.8 A 12-lead ECG showing sinus bradycardia: a P wave before every QRS complex, at a slow rate. (credit: “Sinus bradycardia” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Sinus tachycardia is a sinus rhythm faster than 100 per minute (Page et al., 2016; Figure 16.9). It is usually the body's response to something else: fever, pain, anxiety, bleeding or low blood volume, anemia, hypoxemia, sepsis (Chapter 4), stimulants or pulmonary embolism (Chapter 15). The fast rate is often keeping cardiac output up, so the goal is to treat the cause, not to slow the heart with a drug. The nurse checks temperature, pain, fluid balance, signs of bleeding, oxygen saturation and any new breathlessness or chest pain, and reports the likely cause.



Figure 16.9 A 12-lead ECG showing sinus tachycardia at about 150 per minute. At fast rates the P waves can merge into the T waves before them. (credit: "Sinus tachycardia" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Supraventricular Tachycardia

In this chapter, **supraventricular tachycardia (SVT)** means a regular, narrow-complex tachycardia that starts above the ventricles, often from a short-circuit loop that runs through the AV node. The rate is fast and steady, and P waves are hard to see because they are hidden in or just after each QRS complex. Patients often describe a sudden racing or pounding heartbeat, light-headedness or chest discomfort.

For a stable adult with a regular narrow-complex tachycardia, the AHA recommends **vagal manoeuvres** first and adenosine next (Wigginton et al., 2025). A standard Valsalva manoeuvre, in which the patient strains against a closed airway, ends about 20% to 30% of episodes. Modified methods raise success to about half: for example, the patient strains while semi-reclined and is then laid flat with the legs raised right away, or strains by blowing into a syringe connected to a pressure gauge. Carotid sinus massage carries a risk of stroke in people with carotid artery disease (Wigginton et al., 2025).

Adenosine briefly blocks conduction through the AV node. Its Canadian monograph states that it must be given only with cardiac monitoring and with resuscitation equipment at hand, because short or longer pauses, including asystole, can occur (Fresenius Kabi Canada, 2016). Before the dose, the nurse warns the patient that flushing, shortness of breath or chest pressure may start right away and usually passes in under a minute. Caffeine and theophylline can block its effect, it is avoided in asthma and chronic obstructive pulmonary disease, and it does not convert atrial fibrillation, atrial flutter or ventricular tachycardia (Fresenius Kabi Canada, 2016). An unstable patient with SVT needs synchronized cardioversion, which is also used when vagal manoeuvres and drugs fail (Wigginton et al., 2025; section 16.7).

Premature Beats

A **premature atrial contraction (PAC)** is an early beat from a site in the atria. The strip shows an early P wave, often shaped differently, followed by a normal narrow QRS. A **premature ventricular contraction (PVC)** is an early beat that starts in the ventricles: a wide, oddly shaped QRS with no P wave before it, usually followed by a pause. Nearly everyone has some PVCs, and in a person with a normal heart and few PVCs they usually need no treatment beyond avoiding triggers such as caffeine, stimulants and stress (Cantillon, 2013; Figure 16.10).



Figure 16.10 A 12-lead ECG showing ventricular bigeminy: a wide, early premature ventricular contraction (PVC) after every normal beat. (credit: "ECG Premature Ventricular Complex (PVC) Bigeminy" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

PVCs need closer attention in four situations:

- **Frequent PVCs:** a high share of PVCs among all beats, or short runs of ventricular tachycardia, can weaken the left ventricle over time (Cantillon, 2013).
- **Heart disease or ischemia:** PVCs in a person with structural heart disease warrant cardiology assessment, and new frequent PVCs in a patient with chest pain call for a 12-lead ECG and escalation (Cantillon, 2013; Chapter 17).
- **Electrolytes and drugs:** low potassium or magnesium (Chapter 3) and digoxin toxicity, in which PVCs, often in a pattern of every second or third beat, are the most common rhythm problem (Pharmascience, 2022).
- **Early timing:** a PVC that falls on the T wave of the beat before it (the "R-on-T" pattern) is reported promptly, especially in a patient with ischemia, low potassium or magnesium, or a long QT interval.

Ventricular Tachycardia, Ventricular Fibrillation, Asystole and PEA

Ventricular tachycardia (VT) is a fast rhythm from the ventricles with wide QRS complexes (Figure 16.11). In monomorphic VT the complexes look alike; in polymorphic VT their shape keeps changing. VT may or may not produce a pulse, so the nurse checks the patient. A stable patient in VT with a pulse needs urgent help, a 12-lead ECG and expert care; IV amiodarone or procainamide, or synchronized cardioversion, may follow. An unstable patient with a pulse needs urgent synchronized cardioversion. Polymorphic VT cannot be reliably synchronized and is treated with an unsynchronized shock (Wigginton et al., 2025). VT without a pulse is cardiac arrest.



Figure 16.11 Rhythm strip of monomorphic ventricular tachycardia: a fast, regular rhythm of wide QRS complexes that look alike. (credit: "Monomorphic ventricular tachycardia" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Ventricular fibrillation (VF) is chaotic electrical activity in the ventricles, with no organized QRS complexes and no cardiac output (Figure 16.12). The patient collapses and is unresponsive, without normal breathing or a pulse. The emergency response follows Heart and Stroke Foundation of Canada guidance (Heart and Stroke Foundation of Canada, 2025; Wigginton et al., 2025):

- **Recognize:** the patient is unresponsive, not breathing normally and pulseless.
- **Call:** activate the code system and bring the defibrillator.
- **Compress:** start high-quality cardiopulmonary resuscitation (CPR) at once.
- **Shock:** defibrillate VF and pulseless VT as soon as the defibrillator is ready, one shock at a time, then resume CPR for about 2 minutes before the next rhythm check.
- **Drugs:** for these shockable rhythms, epinephrine is given after the first shocks have failed and repeated during the arrest; amiodarone or lidocaine may be considered when VF or pulseless VT continues despite shocks.

Figure 16.12 Rhythm strip of ventricular fibrillation: chaotic, irregular waves with no identifiable P waves, QRS complexes or T waves. (credit: "VF rhythm strip" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Asystole is the absence of electrical activity in the ventricles (Figure 16.13), seen as a flat line once the nurse has confirmed that the electrodes are attached and the patient has no pulse. **Pulseless electrical activity (PEA)** is an organized rhythm on the monitor without a palpable pulse. Neither is shockable. The team gives CPR and epinephrine as soon as feasible, and pacing is not used during an established arrest (Wigginton et al., 2025). The team also hunts for reversible causes, listed in the AHA algorithm as the Hs (hypovolemia, hypoxia, hydrogen ion or acidosis, low or high potassium, hypothermia) and the Ts (tension pneumothorax, cardiac tamponade, toxins, pulmonary thrombosis and coronary thrombosis) (American Heart Association, 2025). The nurse helps by reporting recent laboratory values, medications and events before the arrest.



Figure 16.13 Rhythm strip in which a slow rhythm ends in a flat line (asystole). The nurse confirms that the electrodes are attached and that the patient has no pulse. (credit: Figure 12.18 in Medical-Surgical Nursing by OpenStax, CC BY-NC-SA 4.0)

When a pulse returns, post-arrest care begins. Canadian guidance includes keeping the mean arterial pressure at 65 mm Hg or higher, keeping oxygen saturation between 90% and 98%, recording an early 12-lead ECG and controlling temperature (between 32 °C and 37.5 °C) for at least 36 hours in patients who do not follow commands, and coronary angiography before discharge for survivors when a cardiac cause is suspected (Heart and Stroke Foundation of Canada, 2025). The family needs updates and support throughout.

Table 16.3 Common dysrhythmias: recognition, causes and first nursing actions (Kusumoto et al., 2019; Andrade et al., 2020; Wigginton et al., 2025)

Rhythm	Key features on the strip	Common causes	First nursing actions
Sinus bradycardia	Regular; a P wave before every QRS; sinus rate below 50 per minute	High vagal tone, sleep, fitness, rate-slowing drugs, hypothyroidism, hypothermia, hypoxemia, ischemia	Assess perfusion and symptoms; review drugs; report; if unstable, call for help and prepare for atropine and pacing as ordered
Sinus tachycardia	Regular; normal P waves; rate above 100 per minute	Fever, pain, anxiety, bleeding, low volume, hypoxemia, sepsis, pulmonary embolism, stimulants	Find and treat the cause: temperature, pain, fluid balance, bleeding, oxygen saturation; report
Supraventricular tachycardia	Fast, regular, narrow QRS; P waves hard to see	Re-entry loop involving the AV node; triggers such as stimulants	Assess stability; 12-lead ECG; coach a vagal manoeuvre as ordered; prepare adenosine with monitoring; if unstable, call for help for synchronized cardioversion
Premature ventricular contractions	Early, wide, oddly shaped QRS with no P wave before it, then a pause	Stimulants, ischemia, low potassium or magnesium, digoxin toxicity, structural heart disease	Assess the patient; count frequency; check electrolytes and drug levels as ordered; report new or frequent PVCs, especially with chest pain
Atrial fibrillation	Irregularly irregular; no clear P waves; wavy baseline; QRS usually narrow	Age, hypertension, heart failure, valve disease, thyroid disease, sleep apnea, alcohol, surgery, acute illness	Check stability and apical-radial pulses; 12-lead ECG; report; ask about onset time and anticoagulation (section 16.6)
Ventricular tachycardia	Fast, wide QRS complexes; regular if monomorphic	Ischemia or scarred myocardium, heart failure, electrolyte imbalance, drug effects	Check for a pulse; if pulseless, start the cardiac arrest response; if a pulse is present, call for urgent help and a 12-lead ECG
Ventricular fibrillation	Chaotic baseline with no recognizable QRS complexes	Ischemia, cardiomyopathy, electrolyte imbalance, untreated VT	Call a code; start CPR; defibrillate as soon as possible
Asystole	Flat line once leads and gain are checked	End stage of untreated arrest; reversible causes (Hs and Ts)	Call a code; start CPR; no shock; epinephrine as soon as feasible as ordered; search for reversible causes
Pulseless electrical activity	Organized rhythm on the monitor but no pulse	Hypovolemia, hypoxia, tamponade, tension pneumothorax, pulmonary embolism and other Hs and Ts	Call a code; start CPR; no shock; search for and correct reversible causes

PRACTICE STORY

The Artifact That Wasn't

Names and details are fictional; this is a composite story.

Nurse: Samuel Boateng, RN. Years in practice: 6. Setting: telemetry unit, community hospital, Ontario.

It was just after 0700 and I was halfway through report when the central station alarmed for Mr. Kovac in room 12. He was 74, admitted two days earlier with heart failure, and his potassium had been low the evening before. The strip showed a run of wide, fast complexes. My colleague at the desk glanced at it and said, "He's brushing his teeth; it's probably artifact. He did that yesterday too."

She might have been right. Movement can make a strip look terrible. But in nursing school I learned that the screen is a clue, not an answer, so I walked to his room. Mr. Kovac was sitting on the edge of the bed, grey, sweaty and confused, with the toothbrush still in his hand. His radial pulse was fast and thready. The monitor beside him showed the same wide-complex rhythm, and it was not changing with his movement.

I pressed the call bell for help, laid him down and asked the RPN who came in to call the rapid response team. His blood pressure was 78/50 mm Hg. The team arrived within minutes. Just as the physician confirmed ventricular tachycardia and the team prepared for synchronized cardioversion, he became unresponsive and lost his pulse. We started CPR, and he was defibrillated within a minute of losing his pulse. He had a pulse again after the first shock.

Later his potassium came back low again, and his medications were reviewed. He went home a week later with a cardiology appointment booked to discuss whether he needed an ICD.

I still think about how easy it would have been to silence that alarm. Since then, our unit has changed its practice: any wide-complex alarm gets a bedside check, every time, before anyone calls it artifact.

Reflect: What cues at the bedside helped Daniel tell a real rhythm from artifact? If the RPN had reached the room first, what actions would fall within the RPN's authority, competence and context, and how should the RPN and RN share the response?

16.6 Atrial Fibrillation and Flutter

What Happens

In **atrial fibrillation (AF)**, many disorganized electrical wavelets activate the atria instead of the sinus node, so the atria quiver rather than contract. The AV node receives far more impulses than it can conduct and lets them through at random. The strip shows an **irregularly irregular** rhythm with no clear P waves, a wavy baseline and usually narrow QRS complexes (section 16.4; Figure 16.14). **Atrial flutter** comes from a single, organized loop of electrical activity in the atrium. It produces regular **flutter waves** with a sawtooth look (Figure 16.15), and the ventricular rhythm is often regular because the AV node passes a fixed share of the flutter waves.



Figure 16.14 A 12-lead ECG showing atrial fibrillation with a rapid ventricular response: an irregularly irregular rhythm with no clear P waves. (credit: "AF with rapid ventricular response" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)



Figure 16.15 A 12-lead ECG showing atrial flutter with 4:1 block: sawtooth flutter waves, with one QRS complex for every four flutter waves. (credit: "Atrial flutter with 4:1 block" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

AF harms the patient in three ways. First, losing the **atrial kick**, the atrial contraction that tops up ventricular filling, lowers stroke volume. Second, a **rapid ventricular response (RVR)**, a ventricular rate above 100 per minute in AF, shortens filling time even further and can cause hypotension, heart failure or ischemia; a fast rate that lasts for weeks can weaken the ventricle (tachycardia-mediated cardiomyopathy) (Andrade et al., 2020). Third, blood pools in the quivering atria, especially in the left atrial appendage,

where clots can form and travel to the brain. AF-related strokes tend to be the most severe (Canadian Cardiovascular Society [CCS], n.d.). Weak beats may not reach the wrist, so the radial pulse can be lower than the apical pulse (section 16.2).

AF in Canada

The 2020 Canadian Cardiovascular Society and Canadian Heart Rhythm Society (CCS/CHRS) guidelines describe AF as the most common sustained dysrhythmia. They estimate that 1% to 2% of the general population has AF, rising to about 4% at age 65 and about 12% at age 80 or older. When people with paroxysmal and silent AF are counted, the estimated number of Canadians with AF rises from 500,000 to nearly 1 million. In 2007–2008, AF accounted for 76,964 emergency department visits and 64,214 acute care admissions in Canada (Andrade et al., 2020).

Established risk factors include older age, male sex, hypertension, heart failure with reduced ejection fraction, valve disease, overt thyroid disease, obstructive sleep apnea, obesity, heavy alcohol use and congenital heart disease. Emerging risk factors include diabetes, chronic kidney disease, coronary artery disease and tobacco use (Andrade et al., 2020). Many can be changed, so AF care includes managing them.

Stroke Prevention

The CCS uses a decision tool, the **CHADS-65** algorithm (the "CCS algorithm"), to decide who needs an anticoagulant (Andrade et al., 2020):

- **Step 1:** If the person is 65 years or older, oral anticoagulation (OAC) is recommended.
- **Step 2:** If the person is younger than 65 but has at least one CHADS2 risk factor (congestive heart failure, hypertension, diabetes, or a previous stroke or transient ischemic attack), OAC is recommended.
- **Step 3:** If the person is younger than 65, has no CHADS2 risk factor but has coronary or peripheral arterial disease, a single antiplatelet drug such as acetylsalicylic acid (ASA) is suggested instead of OAC.
- **Step 4:** If none of these applies, no routine antithrombotic drug is suggested.

For most patients with AF who need OAC, the CCS recommends a direct oral anticoagulant (DOAC), such as apixaban, dabigatran, edoxaban or rivaroxaban, over warfarin. Warfarin remains the drug for people with a mechanical heart valve or moderate to severe mitral stenosis (Andrade et al., 2020). Bleeding risk, drug interactions, adherence and kidney function are reassessed regularly, and bleeding risks are reduced by controlling blood pressure, avoiding nonsteroidal anti-inflammatory drugs (NSAIDs) and preventing falls (Andrade et al., 2020). Chapter 19 covers anticoagulants in full.

Rate and Rhythm Control

Rate control slows the ventricular response. When the left ventricular ejection fraction (LVEF) is above 40%, the CCS lists beta-blockers or the nondihydropyridine calcium channel blockers diltiazem and verapamil as first-line choices. When the LVEF is 40% or less, beta-blockers such as bisoprolol, carvedilol or metoprolol come first, and IV calcium channel blockers are used with caution because they can worsen heart failure. Digoxin or amiodarone may be used when heart failure is decompensated or blood pressure is low; digoxin can also be added to other drugs or used alone in older or less active people with permanent AF. The long-term target is a resting heart rate under 100 per minute (Andrade et al., 2020).

Rhythm control aims to restore and keep sinus rhythm. The CCS suggests it for most stable patients whose AF began recently and suggests considering it, rather than rate control, for newly diagnosed AF. Sinus rhythm can be restored by electrical cardioversion under procedural sedation, which works in about 90% of cases, or with drugs, most often IV procainamide in Canadian emergency departments. Antiarrhythmic drugs help keep sinus rhythm, and **catheter ablation**, which isolates the areas that trigger AF, is used after drugs fail or as a first choice in selected patients with symptoms (Andrade et al., 2020).

Because cardioversion can dislodge a clot, the CCS sets anticoagulation rules. If AF has lasted more than 48 hours, most stable patients should receive at least 3 weeks of therapeutic anticoagulation before a planned cardioversion, unless a transesophageal echocardiogram rules out a clot. Cardioversion without that preparation is reserved for AF with a clear onset within 12 hours and no recent stroke or transient ischemic attack, or for AF of 12 to 48 hours in a patient with a CHADS2 score of 0 or 1. Anticoagulation is started as early as possible, ideally before the procedure, and continued for at least 4 weeks afterward; after that, the CHADS-65 algorithm decides (Andrade et al., 2020).

In the emergency department, AF that directly causes hypotension, acute coronary syndrome or pulmonary edema needs immediate electrical cardioversion, while AF triggered by another illness, such as sepsis, is managed by treating that illness. Most patients go home, with follow-up ideally within a week (Andrade et al., 2020). New AF can also follow surgery (Chapter 7; Clinical Judgment box).

Nursing Care and Teaching

The nurse counts the apical and radial pulses for a full minute and records any pulse deficit (section 16.2), and asks about palpitations, fatigue, breathlessness, dizziness and chest pain. Heart rate and blood pressure are checked before rate-control drugs, and values outside the ordered limits are reported. For patients on anticoagulants, the nurse watches for bleeding, assesses fall risk (Chapter 8), checks for drug interactions and follows kidney function. The nurse teaches stroke warning signs using Heart and Stroke's FAST message (Chapter 31) and the need to call 9-1-1 at once. Patients learn what to do about a missed dose and never to stop an anticoagulant without talking to the prescriber. AF is most common in older adults, who are also more likely to have reduced kidney function, several medications and falls, so their medication lists need close review.

CLINICAL JUDGMENT

New Atrial Fibrillation After Surgery

Names and details are fictional; this is a composite story.

Rosa Medeiros, 72, is on day 2 after a total hip replacement. At 0300 she calls the nurse, saying her heart is "fluttering." Her pulse is irregular at about 140 per minute, and her blood pressure has fallen from 132/78 mm Hg at midnight to 96/60 mm Hg. She is alert but anxious.

- **Recognize cues:** new palpitations; irregular rapid pulse; falling blood pressure; recent major surgery. The nurse also checks oxygen saturation, respiratory rate, temperature, pain, urine output, the wound and dressing, and her skin colour, looking at lips and nail beds as well as skin.
- **Analyze cues:** the pattern suggests new AF with rapid ventricular response. Possible triggers after surgery include pain, low blood volume or bleeding, low potassium or magnesium, hypoxemia, infection and pulmonary embolism (Chapter 15).
- **Prioritize hypotheses:** the first concern is falling cardiac output from the fast rate; bleeding as a cause or a contributor must be ruled out.
- **Generate solutions:** call the physician or rapid response team now using SBAR (Chapter 6); place her on a cardiac monitor; obtain a 12-lead ECG; anticipate electrolytes, a complete blood count and other tests; prepare IV access.
- **Take action:** stay with Ms. Medeiros, keep her in bed, give oxygen if saturation is below target, treat pain as ordered and give rate-control drugs as ordered with blood pressure checks.
- **Evaluate outcomes:** heart rate, blood pressure, rhythm, mental status and urine output. If she becomes hypotensive with confusion or chest pain, she needs urgent cardioversion. The team will weigh her stroke risk against her bleeding risk after surgery before choosing anticoagulation.

MEDICATIONS

Drugs for Rate and Rhythm

These drugs are named here without doses; always check the order, the Canadian product monograph and employer policy.

- **Beta-blockers (metoprolol, bisoprolol):** slow the heart rate in AF and other tachycardias. Check heart rate and blood pressure before each dose; watch for bradycardia, hypotension, dizziness and worsening heart failure.
- **Nondihydropyridine calcium channel blockers (diltiazem, verapamil):** slow AV node conduction. Watch for hypotension and bradycardia; used with caution when the ejection fraction is low (Andrade et al., 2020).
- **Digoxin:** slows AV node conduction. Watch for toxicity: poor appetite, nausea, vomiting, blurred or yellow vision, confusion, a slow pulse and new PVCs. Low potassium or magnesium, high calcium, kidney impairment and older age raise the risk (Pharmascience, 2022).
- **Amiodarone:** an antiarrhythmic with a long half-life. Monitoring includes thyroid function, liver enzymes, chest X-ray and lung function, eye symptoms and the QTc. It raises digoxin levels and increases the effect of warfarin (JAMP Pharma Corporation, 2022).
- **Adenosine:** ends many SVTs; given only with cardiac monitoring and resuscitation equipment available. Warn the patient about brief flushing, breathlessness and chest pressure (Fresenius Kabi Canada, 2016).

- **Atropine:** raises the heart rate in symptomatic bradycardia (Wigginton et al., 2025).

16.7 Heart Blocks, Pacemakers and Implantable Devices

Atrioventricular Blocks

In an **AV block**, impulses from the atria are delayed or stopped on their way to the ventricles. The 2018 ACC/AHA/HRS guideline describes four main patterns (Kusumoto et al., 2019):

- **First-degree AV block:** every P wave is conducted, but the PR interval is longer than 0.20 seconds (200 milliseconds). Because no beat is actually blocked, the guideline notes that "AV delay" is the more accurate term (Figure 16.16).
- **Second-degree AV block, Mobitz I (Wenckebach):** the PR interval grows longer from beat to beat until one P wave is not conducted and a QRS is dropped; then the cycle starts again (Figure 16.17).
- **Second-degree AV block, Mobitz II:** the PR interval stays the same, but now and then a P wave is suddenly not followed by a QRS. When every second P wave is blocked (2:1 block), the type cannot be told from the strip (Figure 16.18).
- **Third-degree (complete) AV block:** no impulses reach the ventricles. P waves and QRS complexes each keep their own rhythm with no relationship between them (AV dissociation), and a slow escape rhythm keeps the ventricles beating (Figure 16.19).

Figure 16.16 Rhythm strip showing first-degree AV block: every P wave is followed by a QRS complex, but the PR interval (marked) is longer than 0.20 seconds. (credit: “Rhythm strip: PR interval prolonged, first-degree AV block” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)



Figure 16.17 A 12-lead ECG showing second-degree AV block, Mobitz I (Wenckebach): the PR interval lengthens from beat to beat until a P wave is not conducted and a QRS complex is dropped. (credit: "Mobitz I AV block" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)



Figure 16.18 Rhythm strip showing second-degree AV block, Mobitz II: the PR interval stays the same, and the arrows mark P waves that are suddenly not conducted. (credit: "Mobitz II AV block" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)



Figure 16.19 Rhythm strip showing complete (third-degree) AV block: P waves (small arrows) at about 100 per minute, unrelated to wide QRS complexes (R) at about 40 per minute. (credit: "Complete heart block" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Causes include rate-slowing drugs such as beta-blockers, nondihydropyridine calcium channel blockers, digoxin and amiodarone; ischemia or myocardial infarction (Chapter 17); hyperkalemia (Chapter 3); and cardiac surgery (Kusumoto et al., 2019). Gradual,

age-related wear of the conduction system is another cause. First-degree block usually needs only monitoring and a drug review. Mobitz II and third-degree block are more serious because the ventricular rate can fall suddenly. When acquired Mobitz II, high-grade or third-degree block is not due to a reversible cause, the guideline recommends a permanent pacemaker whether or not the patient has symptoms (Kusumoto et al., 2019). A patient who is unstable from a slow rate needs help at once, with atropine, an adrenergic infusion or pacing as described in section 16.5; the AHA notes that immediate pacing may be considered for unstable high-degree AV block when IV access is not available (Wigginton et al., 2025).

Pacing

Transcutaneous pacing sends electrical impulses through large adhesive pads on the chest from an external pacemaker or defibrillator. It is an emergency bridge to a transvenous wire or permanent pacemaker. It is often painful, so the nurse gives analgesia or sedation as ordered (Wigginton et al., 2025). The nurse confirms that each pacing spike produces a QRS and a pulse that matches the paced rate. **Temporary transvenous pacing** uses a wire passed through a vein into the heart. After cardiac surgery, thin pacing wires attached to the outer surface of the heart may exit through the chest wall so that an external pacemaker can be connected if needed.

A **permanent pacemaker** has a small pulse generator placed under the skin of the upper chest, usually with one or more leads in the heart (Figure 16.20). It senses the heart's own activity and paces only when the rate falls too low or a beat is missed. On the strip, a paced beat starts with a **pacing spike**, a sharp vertical line just before the P wave or QRS it triggers; paced QRS complexes are wide. Two problems are important to recognize:

- **Failure to capture:** a spike appears, but no P wave or QRS follows, so the heart does not beat. The rate may drop and the patient may become dizzy or faint.
- **Sensing problems:** in **undersensing** (failure to sense), the pacemaker misses the heart's own beats and fires anyway, so spikes appear at the wrong times. In **oversensing**, it mistakes other electrical signals for heartbeats and holds back pacing, causing pauses.

The nurse assesses the patient, records a strip and a 12-lead ECG, reports promptly and arranges a device check. Lead movement is a known early risk after implantation (Guerra et al., 2024).

Implantable Cardioverter-Defibrillators

An **implantable cardioverter-defibrillator (ICD)** is a device placed under the skin that watches the heart rhythm and treats VT or VF with rapid pacing or a shock; it can also pace for bradycardia. ICDs are used for **secondary prevention** in people who have survived a cardiac arrest or sustained VT, and for **primary prevention** in people at high risk who have not yet had such an event (Guerra et al., 2024). Patients describe a shock as a sudden, uncomfortable thump in the chest. A Canadian patient guide advises a person who receives one shock to sit or lie down and contact the device clinic; to go to the emergency department right away after more than one shock, or after one shock outside clinic hours if feeling unwell; never to drive themselves; and to call 9-1-1 for fainting, dizziness or a racing heart (Nova Scotia Health, 2025). A **wearable cardioverter-defibrillator** is worn on the body for a limited time. It warns with vibration, sound and lights before a shock, which a conscious patient can cancel. It may bridge a period when risk may fall, such as soon after a heart attack, or while an ICD is removed for infection; it cannot pace (Piccini et al., 2016).

Caring for a Patient After Device Implantation

After implantation, the nurse checks the site for bleeding and hematoma, monitors the rhythm and teaches the signs of infection: warmth, redness or swelling that is getting worse, pain that is severe or growing, a temperature over 38 °C, chills, or any drainage (Nova Scotia Health, 2025). One Canadian guide tells ICD patients not to raise the arm on the device side above the head, and to avoid sudden, jerky movements that pull the arm away from the body, for 6 weeks; nurses follow their own site's instructions for pacemakers and ICDs. Patients receive a temporary device identification card, are encouraged to wear a medical alert bracelet and have regular device checks in clinic or through a home remote monitor (Nova Scotia Health, 2025). Remote monitoring can spare people in rural and remote communities long trips.

Driving rules depend on the device, its purpose and whether the person drives privately or commercially. The CCS 2023 fitness-to-drive guidelines, for example, restrict private driving for 1 week after an ICD implanted for primary prevention and for 3 months

after an ICD implanted for secondary prevention, and prohibit driving for 3 months after an appropriate ICD shock. After a pacemaker is implanted, private driving is restricted for a short period set by the CCS guideline; the team gives the exact time (Guerra et al., 2024). People should also not drive for 24 hours after sedation (Nova Scotia Health, 2025).

Many newer systems are **MR-conditional**: magnetic resonance imaging (MRI) is possible only under specific conditions. HRS consensus calls for device checks and reprogramming before and after the scan, ICD shock detection turned off, continuous ECG and oxygen saturation monitoring, and staff trained in advanced life support present (Indik et al., 2017). The nurse makes sure every device is flagged on MRI screening. A magnet over an ICD usually suspends shock therapy while it stays there, though pacing continues (Lampert et al., 2010), so magnets are used only by trained clinicians following protocol. Microwave ovens and everyday appliances are safe. Patients keep mobile phones at least 15 cm (6 inches) from the device, walk through security gates normally while showing their card, ask for a hand search instead of a wand and avoid leaning over a running engine (Nova Scotia Health, 2025).



Figure 16.20 Chest X-ray of a single-chamber permanent pacemaker: the pulse generator under the skin of the upper chest and one lead in the heart. A label in the corner is pixelated. (credit: modification of "VVI Schrittmacher THWZ" by Th. Zimmermann/Wikimedia Commons, CC BY-SA 3.0 DE)



Figure 16.21 Anterolateral pad placement: one pad below the right clavicle and one on the left side of the chest, so the current passes through the heart. (credit: "Defib electrode placement" by Owain Davies/Wikimedia Commons, CC BY 3.0)

Cardioversion, Defibrillation and AEDs

Synchronized cardioversion times the shock to the QRS complex, which lowers the risk of setting off VF (Wigginton et al., 2025). It is used for unstable tachycardias with a pulse and for planned cardioversion of AF or flutter. **Defibrillation** is an unsynchronized shock delivered the moment the button is pressed; it treats VF, pulseless VT and polymorphic VT, which cannot be synchronized reliably (Wigginton et al., 2025). Table 16.4 compares them. Planned cardioversion is done under procedural sedation (Andrade et al., 2020), and the nurse monitors airway, breathing, oxygen saturation and blood pressure until recovery. Pads are placed so the current passes through the heart (Wigginton et al., 2025; Figure 16.21). Before any shock, the operator announces it loudly and confirms that no one is touching the patient or bed.

An **automated external defibrillator (AED)** analyzes the heart rhythm, decides whether a shock is needed and guides the rescuer with voice or screen prompts. AEDs are now found in arenas, recreation centres and other public places (Figure 16.22), and CPR courses teach their use (Health Canada, 2016). In Canada, defibrillators must be licensed

by Health Canada before sale (Heart and Stroke Foundation of Canada, 2025).

When a person with an ICD nears the end of life, shocks can add to the suffering of the patient and family. A person with decision-making capacity, or a substitute decision-maker, may ask for shock therapy to be turned off. HRS consensus states that these conversations begin before implantation, return as goals change and that deactivation is done by people with device expertise wherever possible (Lampert et al., 2010). Chapter 10 discusses these conversations in full.

Figure 16.22 A public-access AED in a wall cabinet. (credit: modification of Figure 19.26, "Defibrillators," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0; panel (a) only)

Table 16.4 Synchronized cardioversion and defibrillation compared (Andrade et al., 2020; Wigginton et al., 2025)

Feature	Synchronized cardioversion	Defibrillation
Timing of the shock	Timed to the QRS complex; the device waits for the next QRS	Delivered as soon as the operator presses the shock button
Main uses	Unstable tachycardia with a pulse (SVT, atrial fibrillation or flutter, monomorphic VT); planned cardioversion of atrial fibrillation or flutter	Ventricular fibrillation, pulseless VT and polymorphic VT
State of the patient	Has a pulse; often awake	Usually pulseless and unresponsive
Sedation and analgesia	Procedural sedation for planned cardioversion; sedation when time allows in an emergency	Not given before the shock; CPR comes first
Before the shock	Turn on sync mode and confirm a sync marker on each QRS; for planned AF cardioversion, confirm the anticoagulation plan	Start CPR; apply pads; shock as soon as the defibrillator is ready
After the shock	Check rhythm, pulse, blood pressure, airway and recovery from sedation	Resume CPR right away for about 2 minutes before the next rhythm check

SCOPE IN PRACTICE

Monitoring, Rhythm Interpretation and Medical Directives

Who watches monitors varies by site. Some hospitals use telemetry technicians to watch central monitors and alert nurses, but the bedside nurse remains accountable for assessing the patient. RNs and RPNs analyze rhythm strips when they have the competence and employer policy supports it (authority, competence and context; Chapter 1, section 1.3; CNO, 2025b).

- **Acting on deterioration:** every nurse who sees a dangerous rhythm acts at once: checks the patient, starts CPR if there is no pulse and calls for help. The RPN consults the RN as the patient's needs change.
- **Directives:** medical directives, orders that apply to a group of patients, let nurses record a 12-lead ECG or start a response without an individual order (College of Nurses of Ontario [CNO], 2025b).
- **Shocks:** in Ontario, applying electricity for cardioversion, defibrillation, cardiac pacemaker therapy or transcutaneous cardiac pacing is a controlled act (a prescribed form of energy) that is not authorized to RNs or RPNs, and using an AED falls under the controlled act of defibrillation (CNO, 2025a). A nurse may defibrillate, including with an AED, under the exception for first aid or temporary assistance in an emergency, or through delegation with an order or directive in place, and only with the knowledge, skill and judgment to do it safely (CNO, 2025a). Where emergencies are likely, such as in hospitals, CNO expects a standardized process with education, ongoing competence assessment and written criteria (CNO, 2025b).

- **Employer and province:** employers can limit but not expand scope, and rules differ by province or territory.

PATIENT EDUCATION

Living With a Pacemaker or ICD

- **Your wound:** Keep the dressing on and the site dry as instructed, and check it daily. Call your provider for growing swelling, redness, warmth, worsening pain, fever above 38 °C, chills or drainage.
- **Your arm:** Follow your team's limits on raising the arm on the device side and on sudden pulling movements, often for several weeks.
- **Your card:** Carry your device card, and consider a medical alert bracelet. Show the card at airport security and ask for a hand search.
- **Your checks:** Keep every device clinic appointment and keep any home monitor plugged in.
- **Your phone:** Keep mobile phones at least 15 cm (6 inches) from the device and not in a shirt pocket over it. Microwave ovens and most household appliances are safe.
- **Your tests:** Tell every provider, including dentists, about your device, especially before an MRI.
- **Driving:** Ask how long you must wait before driving. The answer depends on your device and why you have it.
- **If you have an ICD:** After one shock, sit or lie down and call the device clinic. After more than one shock, or if you feel unwell, go to the emergency department and do not drive yourself. Call 9-1-1 if you faint or feel your heart racing.

Chapter 16 Summary

Introduction

- Diseases of the heart caused 17.7% of deaths in Canada in 2024, second only to cancer.
- Nurses on every unit are often first to notice cardiac problems; this chapter builds the assessment and rhythm skills used in Chapters 17 to 20.

16.1 The Heart and Its Rhythm: A Brief Review

- Four chambers and four valves keep blood moving one way through the pulmonary and systemic circuits.
- The left ventricle receives most of its coronary blood flow in diastole, so very fast rates can starve the heart muscle.
- The SA node normally paces the heart; the AV node delays the impulse; the His–Purkinje system spreads it through the ventricles. Lower pacemakers are slower and less reliable.
- The P wave shows atrial depolarization, the QRS ventricular depolarization, and the T wave ventricular repolarization.
- Cardiac output equals heart rate times stroke volume; preload, afterload and contractility shape stroke volume, and rates that are too slow or too fast can lower output.

16.2 Focused Cardiovascular Assessment

- A chest pain history covers onset, location, radiation, character, severity, duration, triggers and associated symptoms, in the patient's own words.
- Many people, especially women, have heart attacks without chest pain; the nurse never rules out a cardiac cause because symptoms seem atypical.
- The assessment includes an apical-radial pulse deficit when the pulse is irregular, JVP, pulses, edema (ankle circumference is more reliable than pitting scales) and heart sounds.
- On darker skin, the nurse checks the lips, tongue, oral mucosa, conjunctivae and nail beds for cyanosis and pallor.
- Signs of low cardiac output and new chest pain need immediate action and escalation.

16.3 Cardiac Tests

- Correct electrode placement and skin preparation are essential for an accurate 12-lead ECG; a 2021 American chest pain guideline calls for an ECG within 10 minutes of arrival.
- High-sensitivity troponin is reported in ng/L; a rise or fall on timed repeat samples suggests acute injury.
- BNP and NT-proBNP reflect wall stress and help assess breathlessness (Chapter 18); electrolytes affect rhythm (Chapter 3).
- Nursing care for TEE, stress tests and catheterization includes consent, fasting, medication review, kidney function and post-procedure monitoring.

16.4 Cardiac Monitoring and Reading a Rhythm Strip

- Monitor only patients with an indication, and review the need every 24 to 48 hours or sooner.
- Good skin preparation, correct electrode placement and electrode changes reduce artifact and false alarms.
- Most monitor alarms are false or non-actionable; alarm fatigue can lead to missed events, so the nurse assesses the patient for every alarm.
- Analyze every strip in the same order: rate, regularity, P waves, PR interval, QRS duration, then QT and QTc.

16.5 Common Dysrhythmias and How to Respond

- The response to any new rhythm starts with the patient: check responsiveness, breathing, pulse and perfusion, and rule out artifact.
- Hypotension, sudden change in mental status, chest pain, signs of shock and acute heart failure mean a rhythm is unstable; the nurse calls for help at once.
- Sinus tachycardia is treated by treating its cause; symptomatic bradycardia may need atropine, an adrenergic infusion or pacing.
- Stable SVT is treated with vagal manoeuvres and then adenosine with cardiac monitoring; unstable SVT needs synchronized cardioversion.
- VF and pulseless VT need CPR and early defibrillation; asystole and PEA need CPR, epinephrine as soon as feasible and a search for reversible causes, with no shock.

16.6 Atrial Fibrillation and Flutter

- AF produces an irregularly irregular rhythm with no clear P waves; flutter produces regular sawtooth waves.
- AF lowers cardiac output through lost atrial kick and rapid ventricular response, and raises stroke risk through clots in the left atrial appendage.
- The CCS CHADS-65 algorithm recommends oral anticoagulation, usually a DOAC, for people 65 or older or with any CHADS2 risk factor.
- Rate control uses beta-blockers, diltiazem, verapamil or digoxin; rhythm control uses cardioversion, antiarrhythmic drugs or ablation, with anticoagulation rules around cardioversion.
- Nursing care includes apical-radial pulse checks, monitoring for instability and bleeding, teaching stroke warning signs and supporting adherence.

16.7 Heart Blocks, Pacemakers and Implantable Devices

- First-degree block is a long PR interval; Mobitz I shows a lengthening PR before a dropped beat; Mobitz II drops beats with a constant PR; third-degree block shows unrelated P waves and QRS complexes.
- Unstable bradycardia from AV block may need transcutaneous pacing as a bridge; acquired Mobitz II and third-degree block usually lead to a permanent pacemaker.
- Nurses recognize pacing spikes, failure to capture and sensing problems (undersensing and oversensing), and escalate promptly.
- After device implantation, teaching covers wound care, arm limits, ID cards, remote checks, driving rules, MRI and electromagnetic interference.

- Synchronized cardioversion is timed to the QRS for rhythms with a pulse; defibrillation is immediate and unsynchronized for pulseless VT and VF; AEDs guide any rescuer.

Key Terms (52)

afterload: The force the ventricle must work against to eject blood; raised by high blood pressure or a narrowed aortic valve.

alarm fatigue: Desensitization of clinicians exposed to many false or non-actionable alarms, leading to slower or missed responses.

artifact: A signal on an ECG or monitor that does not come from the heart's electrical activity, such as interference from movement or loose electrodes.

asystole: The absence of electrical activity in the ventricles, seen as a flat line; a non-shockable arrest rhythm.

atrial fibrillation (AF): A dysrhythmia in which disorganized atrial activity produces an irregularly irregular ventricular rhythm with no clear P waves.

atrial flutter: A dysrhythmia caused by an organized loop of atrial activity that produces regular sawtooth flutter waves.

atrioventricular (AV) node: Conduction tissue low in the right atrium that delays the impulse before it reaches the ventricles; with the bundle of His, the normal route from atria to ventricles.

automated external defibrillator (AED): A portable device that analyzes the heart rhythm, decides whether a shock is needed and guides the rescuer with prompts.

cardiac output: The volume of blood the heart pumps each minute; heart rate multiplied by stroke volume.

CHADS-65: The Canadian Cardiovascular Society algorithm that recommends oral anticoagulation for people with AF who are 65 or older or who have any CHADS2 risk factor.

contractility: The strength of the heart muscle's contraction, apart from how much it was stretched by filling.

defibrillation: An unsynchronized shock delivered immediately to treat ventricular fibrillation, pulseless VT or polymorphic VT.

depolarization: Electrical activation of heart muscle cells, which triggers contraction.

dysrhythmia: Any heart rhythm other than normal sinus rhythm, whether too fast, too slow, irregular or started from an abnormal site.

echocardiography: Ultrasound imaging of the heart's structure and movement, done through the chest wall (transthoracic) or from the esophagus (transesophageal).

failure to capture: A pacemaker problem in which a pacing spike is not followed by a P wave or QRS.

first-degree AV block: Delayed AV conduction in which every P wave is conducted but the PR interval is longer than 0.20 seconds.

high-sensitivity troponin: A blood test that measures very low levels of cardiac troponin, a protein released from injured heart muscle; reported in ng/L.

implantable cardioverter-defibrillator (ICD): An implanted device that detects VT or VF and treats it with rapid pacing or a shock.

jugular venous pressure (JVP): The vertical height of the internal jugular venous pulsation above the sternal angle; an estimate of right-sided filling pressure.

Mobitz I: Second-degree AV block in which the PR interval lengthens progressively until a P wave is not conducted (also called Wenckebach).

Mobitz II: Second-degree AV block in which the PR interval stays constant but some P waves are suddenly not conducted.

murmur: A heart sound made by turbulent blood flow, described by its timing, location, loudness and quality.

natriuretic peptide: A hormone (BNP or NT-proBNP) released by heart muscle under increased wall stress; used in assessing heart failure.

normal sinus rhythm: A regular rhythm from the SA node at 60 to 100 bpm, with an upright P wave before each QRS, a PR interval of 0.12 to 0.20 seconds and a QRS under 0.12 seconds.

P wave: The ECG wave produced by atrial depolarization.

permanent pacemaker: An implanted device with a pulse generator and leads that senses the heart's activity and paces when the rate is too slow.

PR interval: The time from the start of the P wave to the start of the QRS complex; normally 0.12 to 0.20 seconds.

preload: The filling of the ventricle, and the stretch of its muscle, just before it contracts.

premature ventricular contraction (PVC): An early beat that starts in the ventricles, seen as a wide, oddly shaped QRS with no P wave before it.

pulse deficit: The apical rate minus the radial rate, counted at the same time by two nurses; a sign that some beats do not reach the periphery.

pulseless electrical activity (PEA): An organized rhythm on the monitor without a palpable pulse; a non-shockable arrest rhythm.

QRS complex: The ECG complex produced by ventricular depolarization; normally under 0.12 seconds wide.

QT interval: The time from the start of the QRS complex to the end of the T wave; corrected for heart rate as the QTc.

rapid ventricular response (RVR): A ventricular rate above 100 per minute in atrial fibrillation or flutter.

rate control: An AF treatment strategy that slows the ventricular rate, usually with beta-blockers, nondihydropyridine calcium channel blockers or digoxin.

repolarization: The return of heart muscle cells to their resting electrical state after depolarization.

rhythm control: An AF treatment strategy that restores and maintains sinus rhythm with cardioversion, antiarrhythmic drugs or catheter ablation.

S3: An extra heart sound in early diastole, just after S2, from rapid ventricular filling.

S4: An extra heart sound in late diastole, just before S1; always abnormal.

sinoatrial (SA) node: The heart's normal pacemaker, in the high right atrium; its cells fire faster than any others.

sinus bradycardia: A sinus rhythm slower than normal; the 2018 ACC/AHA/HRS guideline defines it as a sinus rate below 50 per minute.

sinus tachycardia: A sinus rhythm faster than 100 per minute, usually a response to another problem such as fever, pain or low blood volume.

stroke volume: The volume of blood the left ventricle ejects with each beat.

supraventricular tachycardia (SVT): A regular, narrow-complex tachycardia that starts above the ventricles, often from a loop involving the AV node.

synchronized cardioversion: A shock timed to the QRS complex, used for tachycardias with a pulse.

telemetry: Continuous ECG monitoring that sends the signal from a wireless transmitter to a central station.

third-degree AV block: Complete AV block in which no atrial impulses reach the ventricles, so P waves and QRS complexes are unrelated.

transcutaneous pacing: Emergency pacing through adhesive pads on the chest, used as a bridge to transvenous or permanent pacing.

vagal manoeuvre: An action that increases vagal tone to slow AV node conduction, such as a Valsalva manoeuvre, used first for stable regular narrow-complex tachycardia.

ventricular fibrillation (VF): Chaotic electrical activity in the ventricles with no organized QRS complexes and no cardiac output.

ventricular tachycardia (VT): A fast rhythm from the ventricles with wide QRS complexes that may or may not produce a pulse.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Gloria Benoit (Questions 1–4): Gloria Benoit, 74, was admitted to a medical unit in Belleville, Ontario, after fainting at home. She is on telemetry because a cardiac cause of her syncope is suspected. Her electrodes were placed 2 days ago. An RPN is caring for her, with an RN and a central monitor technician on the team.

1. [CORE] The monitor technician reports repeated "leads off" and "irregular rhythm" alarms for Mrs. Benoit. The nurse finds her sitting up, talking and in no distress, with a radial pulse that is regular. Which finding most likely explains the alarms?

a. Her rhythm has changed to atrial fibrillation with a fast ventricular response

b. The chest electrode has been placed in the V1 position on her chest

c. The electrodes are 2 days old, with dry gel and lifting edges

d. Her heart rate is 84 bpm

Answer: c — Old electrodes with dried gel and poor contact are a leading cause of artifact and false alarms, and daily electrode changes with skin preparation reduce nuisance alarms (c) (section 16.4). A regular radial pulse in a comfortable patient makes atrial fibrillation unlikely (a), although an ECG would confirm the rhythm. V1 is a standard and useful monitoring position (b). A heart rate of 84 bpm is normal and would not trigger these alarms (d).

2. [CORE] After the electrodes are replaced, the strip shows a regular rhythm with 4 large boxes between consecutive R waves. What is Mrs. Benoit's heart rate?

a. 60 bpm

b. 75 bpm

c. 100 bpm

d. 150 bpm

Answer: b — For a regular rhythm, the rate is 300 divided by the number of large boxes between R waves: 300 ÷ 4 = 75 bpm (b) (section 16.4). Option a would need 5 large boxes, c would need 3, and d would need 2.

3. [CORE] Later, the central monitor shows a flat line in Mrs. Benoit's monitoring lead. What does the nurse do first?

a. Go to the patient and check responsiveness, breathing and pulse

b. Ask the technician to print the strip for the chart

c. Increase the size (gain) of the tracing on the monitor

d. Replace all electrodes before assessing further

Answer: a — The nurse assesses the patient before interpreting the screen. A flat line may be a loose lead or a cardiac arrest, and only the patient can tell which (a) (section 16.4). Printing the strip (b), changing the display (c) or replacing electrodes (d) first could delay resuscitation if she has no pulse.

4. [CORE] The next morning, Mrs. Benoit says she feels dizzy. Her heart rate is 38 bpm, her blood pressure is 82/50 mm Hg, and she is pale and clammy. What is the RPN's most appropriate action?

a. Recheck the vital signs in 30 minutes, since she is awake and talking

b. Ask her to stand slowly at the bedside so that orthostatic blood pressure changes can be measured

c. Document the findings and report them at the end of the shift

d. Stay with her, call for help as the rapid response criteria direct, and notify the RN

Answer: d — A slow heart rate with low blood pressure and signs of poor perfusion suggests low cardiac output. Every nurse who notices deterioration acts at once and escalates; the RPN consults the RN as the patient's needs change (d) (sections 16.1 and 16.2; Chapter 6). Waiting (a) or delaying the report (c) puts her at risk. Standing (b) could cause her to faint and fall.

5. [CORE] A nurse is teaching a community group about heart attack signs. Which symptoms may signal a heart attack, especially in women? Select all that apply.

- **a.** Shortness of breath
- **b.** Extreme fatigue
- **c.** Pressure in the upper back
- **d.** Fever with chills
- **e.** A rash on the chest
- **f.** Dizziness or light-headedness

Answer: a, b, c, f — Heart and Stroke lists shortness of breath (a), extreme fatigue (b), upper back pressure (c), and dizziness or light-headedness (f) among heart attack signs that women may have, sometimes without chest pressure; pain or pressure in the upper abdomen is another (section 16.2). Fever with chills (d) points to infection, and a rash (e) is not a sign of a heart attack.

6. [CORE] A patient has long-standing high blood pressure. Which part of cardiac output does high blood pressure most directly increase?

- **a.** Afterload
- **b.** Preload
- **c.** Heart rate
- **d.** Contractility

Answer: a — Afterload is the force the ventricle must work against to eject blood, and high blood pressure raises it (a) (section 16.1). Preload is the filling and stretch of the ventricle before it contracts (b). High blood pressure does not directly set the heart rate (c). Contractility is the strength of the muscle's contraction (d).

7. [CORE] Two nurses count a patient's pulse at the same time for 1 minute. The apical rate is 112 bpm and the radial rate is 88 bpm. Which interpretation is correct?

- **a.** The radial pulse is the more accurate measure of heart rate, so it should be documented
- **b.** A difference this size is normal when counting at two sites
- **c.** There is a pulse deficit of 24, and some beats are not reaching the wrist
- **d.** The apical count is too high because heart sounds were counted twice

Answer: c — The pulse deficit is the apical rate minus the radial rate (112 − 88 = 24). It shows that some beats heard at the apex are not felt at the wrist, often with an irregular rhythm, and an ECG should identify the rhythm (c) (section 16.2). The apical count reflects every beat the heart makes, so the radial count underestimates the rate (a). A deficit is not a normal finding (b). With two nurses counting together, double-counting is not the explanation (d).

8. [CORE] A patient with chest pain has a high-sensitivity troponin drawn at arrival. Which statement about this test is accurate?

- **a.** A single normal result at arrival rules out heart muscle injury, so no repeat test is needed
- **b.** Results are reported in micromoles per litre
- **c.** Troponin rises only when a coronary artery is blocked
- **d.** A rise or fall between repeat samples suggests acute injury

Answer: d — Acute myocardial injury is shown by troponin above the 99th percentile with a rising or falling pattern on repeat samples, so timed repeat samples matter (d) (section 16.3). One early sample is not enough on its own (a). Results are reported in ng/L (b). Troponin can also rise with tachydysrhythmias, myocarditis, pulmonary embolism or heart failure (c).

9. [CORE] Where does the nurse place the V1 electrode for a 12-lead ECG?

- **a.** Fifth intercostal space, left midclavicular line
- **b.** Fourth intercostal space, right sternal border
- **c.** Second intercostal space, right sternal border
- **d.** Fourth intercostal space, left sternal border

Answer: b — V1 sits at the right sternal border in the fourth intercostal space (b) (section 16.3). The fifth intercostal space at the left midclavicular line is V4 (a). The second intercostal space is too high, a common error (c). The left sternal border at the fourth intercostal space is V2 (d).

10. [CORE] A telemetry unit wants to reduce nuisance monitor alarms. Which practice is supported by evidence?

- **a.** Change electrodes daily after preparing the skin
- **b.** Turn down the alarm volume at the central station
- **c.** Use the same default alarm limits for every patient
- **d.** Silence arrhythmia alarms for patients who often have artifact

Answer: a — Daily electrode changes with skin preparation reduced nuisance alarms on an adult telemetry unit (a) (section 16.4). Lowering the volume (b) and silencing alarms (d) risk missing true events. Limits should be set to each patient's baseline and the purpose of monitoring, within policy, rather than one default for all (c).

11. [CORE] On a regular rhythm strip, the nurse measures 6 small boxes from the start of the P wave to the start of the QRS complex. Which interpretation is correct?

- **a.** The PR interval is 0.12 seconds, which is normal
- **b.** The PR interval is 0.30 seconds, which is prolonged
- **c.** The PR interval is 0.24 seconds, which is prolonged
- **d.** The PR interval is 0.18 seconds, which is normal

Answer: c — Each small box equals 0.04 seconds at 25 mm per second, so 6 boxes equal 0.24 seconds. This is longer than the normal 0.12 to 0.20 seconds (c) (section 16.4). Option a would be 3 boxes, b would be 7.5 boxes, and d would be 4.5 boxes.

12. [CORE] A nurse is assessing a patient with very dark skin for central cyanosis. Where should the nurse look?

- **a.** The skin of the forearms
- **b.** The skin of the cheeks
- **c.** The palms only, in fluorescent light
- **d.** The lips, tongue and inside of the mouth

Answer: d — Cyanosis is best seen where the skin is thin and the blood supply is rich, such as the lips, tongue and oral mucosa, with the conjunctivae and nail beds also checked; on dark skin these may look grey or whitish (d) (section 16.2). Forearm (a) and cheek (b) skin hide colour changes on darker skin. Fluorescent light gives a bluish tint, and the palms alone are not enough (c).

13. [CORE] An RPN on a medical unit in Ontario notices that a patient on telemetry has a new irregular rhythm. The patient reports palpitations, and the vital signs are within the patient's usual range. Which action best reflects CNO's scope of practice standard?

a. Wait for the RN to review the central monitor at the next scheduled check

b. Assess the patient, notify the RN and prescriber, and obtain a 12-lead ECG if agency policy authorizes it

c. Ask the charge nurse to reassign the patient to an RN because any change in rhythm means the patient is no longer stable

d. Give an antidysrhythmic drug from the unit stock to control the rate

Answer: b — CNO's Scope of Practice standard asks nurses to consider authority, competence and context (College of Nurses of Ontario, 2025b). The RPN assesses the patient, consults the RN as the patient's needs change, and obtains an ECG where policy and orders allow (b) (section 16.3; Chapter 1, section 1.3). Waiting delays care (a). A change in rhythm does not by itself require reassignment (c). Giving a drug without an order is outside the RPN's authority (d).

14. [CORE] A nurse is assessing jugular venous pressure. Which technique is correct?

a. Measure the vertical height of the top of the venous pulsation above the sternal angle

b. Palpate the internal jugular vein to find the highest point of pulsation

c. Lay the patient flat and measure from the earlobe to the pulsation

d. Use the carotid pulsation as the reference point

Answer: a — The JVP is the vertical height of the top of the venous pulsation above the sternal angle, which has an upper limit of normal of about 3 cm (a) (section 16.2). The venous pulse cannot be felt (b). The bed is raised to the angle that brings the pulsation into view, and the sternal angle, not the earlobe, is the reference (c). The carotid pulse is arterial and is not the JVP (d).

15. [CORE] While auscultating, the nurse hears an extra heart sound just after S2. How is this sound described?

a. S1, from the atrioventricular valves closing

b. S4, in late diastole

c. A systolic murmur

d. S3, in early diastole

Answer: d — S3 occurs in early diastole, just after S2, from rapid filling of the ventricle (d) (section 16.2). S1 marks the start of systole (a). S4 occurs in late diastole, just before S1 (b). A murmur is a longer sound from turbulent flow, and this sound falls in diastole, not systole (c).

16. [CORE] A patient with type 2 diabetes is scheduled for coronary angiography. The patient takes metformin and has an estimated glomerular filtration rate (eGFR) of 58 mL/min/1.73 m². Based on Canadian radiology guidance, what does the nurse expect?

a. The angiogram will be cancelled to protect the kidneys

b. Metformin will be stopped for 1 week before the test and restarted only after repeat kidney tests

c. Metformin does not routinely need to be stopped for this test

d. Contrast dye cannot be used in people with diabetes

Answer: c — The Canadian Association of Radiologists does not recommend stopping metformin before contrast, except for patients with an eGFR of 30 or less or acute kidney injury (c) (section 16.3). Fear of kidney injury is not a reason to withhold needed contrast, and diabetes alone does not rule contrast out (a, d). Routine stopping of metformin is not recommended at this eGFR (b).

17. [RN] A patient's 12-lead ECG shows new ST elevation. In which group of leads would elevation be considered to be in contiguous leads?

a. aVR and V6

b. II, III and aVF

c. I and III

d. V1 and aVF

Answer: b — Leads II, III and aVF form a contiguous group that views the inferior heart (b) (section 16.3, Going Deeper). The other contiguous groups are I and aVL, and V1 to V6. aVR and V6 (a), I and III (c), and V1 and aVF (d) do not look at neighbouring areas.

18. [RN] A patient started a class III antidysrhythmic drug 2 days ago. The baseline QTc was 440 ms; today's 12-lead ECG shows a QTc of 520 ms. The patient's potassium is low. What is the nurse's priority?

a. Recheck the QTc on the bedside monitor and compare it with the 12-lead value

b. Document the finding, as some QT prolongation is expected with this drug

c. Give the next dose and repeat the ECG tomorrow

d. Hold the next dose and notify the prescriber at once

Answer: d — A QTc over 500 ms raises the risk of torsades de pointes, and the causative drug is generally stopped; low potassium adds to the risk (d) (section 16.3, Going Deeper). Monitor-derived QTc values should not be compared with 12-lead values (a). This degree of prolongation is not an acceptable expected effect (b). Giving the dose (c) increases the danger.

Case: Farah Haddad (Questions 19–24): Farah Haddad, 69, comes to the emergency department in Hamilton, Ontario, saying her heart has been "racing" since she woke 6 hours ago. She has hypertension and type 2 diabetes. She is alert. Heart rate 148 per minute and irregular, blood pressure 118/72 mm Hg, respiratory rate 20 per minute, oxygen saturation 96% on room air. The monitor shows narrow QRS complexes at irregular intervals with a wavy baseline and no clear P waves.

19. [CORE] Which finding from the monitor is most consistent with atrial fibrillation?

a. Regular sawtooth waves between the QRS complexes

b. Irregularly irregular narrow QRS complexes with no clear P waves

c. A PR interval that lengthens until one QRS is dropped

d. Wide, regular QRS complexes at 148 per minute

Answer: b — An irregularly irregular rhythm without clear P waves and with a wavy baseline is the pattern of atrial fibrillation (section 16.6). Regular sawtooth waves (a) suggest atrial flutter. A lengthening PR interval with a dropped QRS (c) is second-degree AV block, Mobitz I (section 16.7). Wide, regular complexes at this rate (d) suggest ventricular tachycardia (section 16.5).

20. [CORE] Ms. Haddad says she gets short of breath walking to the washroom. Which explanation best links this symptom to her rhythm?

a. The irregular rhythm causes her lungs to retain carbon dioxide during exertion.

b. Atrial fibrillation directly lowers her hemoglobin level.

c. Anxiety about the diagnosis is the main cause of the breathlessness.

d. A fast rate and the lost atrial kick reduce her stroke volume.

Answer: d — In AF with rapid ventricular response, the loss of atrial contraction and the short filling time reduce stroke volume and cardiac output, which can cause breathlessness on exertion (section 16.6). AF does not cause carbon dioxide retention (a) or lower hemoglobin (b). Anxiety (c) may add to symptoms, but assuming it is the main cause would miss a physiological explanation.

21. [CORE] Which concern should the nurse monitor most closely over the next hour?

a. Signs of reduced perfusion, such as hypotension or confusion

b. Bleeding from a long-term anticoagulant she has not yet started

c. Long-term weakening of the ventricle from months of fast rates

d. Her knowledge of the Heart and Stroke FAST message

Answer: a — With a heart rate of 148 per minute, the most immediate risk is hemodynamic instability: hypotension, altered mental status, chest pain, shock or acute heart failure (sections 16.5 and 16.6). Bleeding (b) is not yet a risk from a drug not yet started. Tachycardia-mediated cardiomyopathy (c) develops over weeks. Stroke teaching (d) matters but comes after stability is assured.

22. [CORE] The physician orders an IV beta-blocker to slow Ms. Haddad's heart rate. Which nursing action belongs in the plan of care?

a. Teach her to perform a Valsalva manoeuvre before each dose so the drug works faster

b. Restrict all oral fluids until her rhythm converts

c. Monitor her rhythm continuously and check heart rate and blood pressure around each dose

d. Place defibrillator pads on her chest in case the drug causes ventricular fibrillation

Answer: c — Rate-control drugs can cause hypotension and bradycardia, so continuous monitoring and blood pressure and heart rate checks before and after each dose are needed (section 16.6; Medications box). Vagal manoeuvres (a) are used for regular narrow-complex SVT, not for AF. Fluid restriction (b) has no basis here. Applying pads routinely (d) is not indicated for a stable patient receiving rate control.

23. [CORE] Thirty minutes later, Ms. Haddad's blood pressure is 80/48 mm Hg, she is confused and she reports chest pressure. Her rhythm is unchanged. What should the nurse do first?

a. Give a second dose of the beta-blocker to slow the rate further

b. Call for urgent help through the rapid response or code system and stay with her

c. Teach her slow, deep breathing to reduce anxiety

d. Reposition her and recheck her blood pressure in 15 minutes

Answer: b — Hypotension, confusion and chest pressure are signs of instability; AF that directly causes these needs urgent help and likely immediate synchronized cardioversion (sections 16.5 and 16.6). Another dose of a beta-blocker (a) could worsen hypotension. Breathing coaching (c) and waiting 15 minutes (d) delay care for an unstable patient.

24. [CORE] After synchronized cardioversion, which finding shows the treatment has had the intended effect?

a. Her heart rate is 128 per minute and irregular with no clear P waves, and her blood pressure is 90/56 mm Hg.

b. She is drowsy and difficult to rouse 2 hours after the procedure, although her rhythm is regular.

c. The monitor shows sync markers on each QRS complex.

d. She is alert, with a P wave before each QRS at 78 per minute and blood pressure 122/74 mm Hg.

Answer: d — A regular sinus rhythm with normal blood pressure and normal mental status shows restored rhythm and perfusion (section 16.7). A fast irregular rate with low blood pressure (a) shows AF has continued. Being hard to rouse 2 hours later (b) is a concern that needs reporting. Sync markers (c) are checked before the shock and show the device setting, not the outcome.

25. [CORE] The nurse is caring for patients with new tachycardias. Which findings indicate that a patient's rhythm is unstable? Select all that apply.

a. Blood pressure 82/50 mm Hg

b. New confusion

c. Palpitations at rest with blood pressure 134/82 mm Hg and normal mental status

d. Chest pain

e. New crackles in both lungs with acute shortness of breath

f. Heart rate 112 per minute with warm, dry skin and normal mental status

Answer: a, b, d, e — Heart and Stroke Foundation of Canada and AHA guidance list hypotension (a), a sudden change in mental status (b), chest pain (d) and acute heart failure (e) as signs of instability, along with signs of shock (section 16.5). Palpitations with normal blood pressure and mentation (c) and a moderate tachycardia with good perfusion (f) are not signs of instability, although both still need assessment and reporting.

26. [CORE] A patient on a medical unit is found unresponsive, not breathing normally and pulseless. The monitor shows a chaotic baseline with no recognizable QRS complexes. After calling for help, what is the nurse's priority?

a. Obtain a 12-lead ECG to confirm the rhythm before any treatment

b. Prepare for synchronized cardioversion timed to the next QRS complex

c. Start high-quality CPR and defibrillate as soon as the defibrillator is ready

d. Give epinephrine before the first shock to improve the chance of success

Answer: c — This is ventricular fibrillation, a shockable rhythm; the response is immediate high-quality CPR and defibrillation as soon as possible (section 16.5). A 12-lead ECG (a) delays care. Synchronized cardioversion (b) is for rhythms with a pulse and cannot sync to VF. In shockable rhythms, epinephrine (d) is given after the first shocks have failed.

27. [CORE] During a code, the monitor shows a flat line. The nurse has confirmed that the electrodes are attached, and the patient has no pulse. Which action should the team take?

a. Continue CPR, give epinephrine as soon as feasible and look for reversible causes

b. Deliver an unsynchronized shock at once

c. Start transcutaneous pacing

d. Pause CPR every 30 seconds to check for a pulse

Answer: a — Asystole is not shockable; care is CPR, epinephrine as soon as feasible and a search for reversible causes (the Hs and Ts) (section 16.5). A shock (b) does not help asystole. Pacing (c) is not recommended during an established cardiac arrest. Frequent pauses (d) interrupt compressions; rhythm checks occur about every 2 minutes.

28. [CORE] A stable adult has a regular, narrow-complex tachycardia at 190 per minute. A vagal manoeuvre has not worked, and the physician orders adenosine. What should the nurse tell the patient before the dose?

a. "This medicine is given slowly over an hour, so you can rest while it drips in."

b. "You will not need the heart monitor once the medicine is in."

c. "You will need to stop eating and drinking for 12 hours afterward."

d. "You may feel flushing or chest pressure right away, but it passes quickly."

Answer: d — Flushing, breathlessness and chest pressure are common and short-lived with adenosine, and warning the patient reduces fear (section 16.5). Adenosine acts within seconds rather than over an hour (a). Cardiac monitoring is required (b) because pauses, including asystole, can occur. No fasting (c) is needed afterward.

29. [CORE] Which patient's premature ventricular contractions (PVCs) are of greatest concern to the nurse?

a. A 24-year-old with occasional PVCs after drinking coffee and a normal echocardiogram

b. A 68-year-old with chest pain, new frequent PVCs and a potassium level of 3.1 mmol/L

c. A 40-year-old who notices a skipped beat once a day and has no heart disease

d. A 55-year-old whose PVCs disappeared after quitting an energy drink

Answer: b — New frequent PVCs with chest pain and low potassium suggest ischemia and electrolyte imbalance, both of which raise the risk of dangerous ventricular rhythms; this needs a 12-lead ECG and escalation (section 16.5). Occasional PVCs in a structurally normal heart (a, c) are usually benign, and PVCs that resolve when a trigger is removed (d) are reassuring.

30. [CORE] A patient's rhythm strip shows a constant PR interval of 0.18 seconds, but now and then a P wave is not followed by a QRS. How should the nurse interpret this?

a. First-degree AV block, which usually needs only monitoring

b. Second-degree AV block, Mobitz I, because the PR interval stays the same

c. Second-degree AV block, Mobitz II, which can progress to complete heart block

d. Third-degree AV block, because some P waves are not conducted

Answer: c — A constant PR interval with sudden dropped QRS complexes is Mobitz II, which is more dangerous than Mobitz I and often leads to a permanent pacemaker (section 16.7). First-degree block (a) has no dropped beats. Mobitz I (b) shows a PR interval that lengthens before the dropped beat. In third-degree block (d), no P waves are conducted and P waves and QRS complexes are unrelated.

31. [CORE] A patient's strip shows regular P waves at 80 per minute and regular wide QRS complexes at 34 per minute, with no relationship between them. The patient is dizzy and has a blood pressure of 84/50 mm Hg. What should the nurse do first?

a. Call for urgent help and prepare for transcutaneous pacing and other ordered treatment

b. Give the patient's scheduled metoprolol to control the wide QRS complexes

c. Coach the patient through a Valsalva manoeuvre

d. Recheck the vital signs in 1 hour, because the rhythm is regular

Answer: a — This is third-degree AV block with signs of poor perfusion; the patient needs urgent help, with atropine, an adrenergic infusion or pacing as ordered (sections 16.5 and 16.7). Metoprolol (b) would slow the heart further. A Valsalva manoeuvre (c) increases vagal tone and could worsen bradycardia. Waiting an hour (d) delays care for an unstable patient.

32. [CORE] The nurse is teaching a patient going home after a new permanent pacemaker. Which statement shows the patient understands the teaching?

a. "I'll keep my mobile phone in my shirt pocket so I can hear it ring."

b. "I need to stop using my microwave oven."

c. "I can leave my device card at home because the clinic has my records."

d. "I won't raise my arm on the pacemaker side above my head until my team says it's safe."

Answer: d — Limiting arm movement on the device side for the period the team advises helps the incision heal and the leads stay in place (section 16.7). Phones should be kept at least 15 cm from the device, not in a pocket over it (a). Microwave ovens are safe (b). Patients should carry the device card (c), for example to show at security screening.

33. [CORE] The nurse is helping with a planned synchronized cardioversion for atrial fibrillation. Which action is essential before the shock?

a. Switch the defibrillator to unsynchronized mode to save time
b. Confirm that a sync marker appears on each QRS complex
c. Withhold the ordered procedural sedation so the patient can report pain
d. Ask the patient to hold the bed rails during the shock

Answer: b — The shock must be timed to the QRS to lower the risk of causing ventricular fibrillation, so the nurse confirms a sync marker on each QRS (section 16.7). Unsynchronized mode (a) is for defibrillation. Planned cardioversion is done under procedural sedation (c). No one, including the patient, should touch the bed or rails during a shock (d).

34. [CORE] A visitor collapses in a hospital lobby. The nurse finds the person unresponsive and not breathing normally, and a colleague brings an AED. What should the nurse do?

a. Wait for the code team to arrive before using the AED
b. Use the AED only if the person's heart rhythm can first be read on a monitor
c. Continue CPR, turn on the AED and follow its prompts, keeping everyone clear during analysis
d. Give two minutes of rescue breaths before applying the pads

Answer: c — An AED analyzes the rhythm and guides the rescuer with prompts; CPR continues until it is ready, and no one touches the person during analysis or a shock (sections 16.5 and 16.7). Waiting (a) delays defibrillation. An AED does its own rhythm analysis (b). Delaying pads for rescue breaths (d) delays a possible shock.

35. [CORE] An RPN on a medical unit sees that a patient's rhythm has changed to a fast, wide-complex rhythm. The patient is pale and responsive, with a blood pressure of 80/50 mm Hg. The RN is in another room. What should the RPN do?

a. Stay with the patient, call the rapid response team and inform the RN
b. Wait for the RN to return and interpret the rhythm before taking any action
c. Record the strip and recheck the patient in 15 minutes
d. Tell the patient to rest because only the RN can respond to rhythm changes

Answer: a — Every nurse who sees deterioration acts at once and escalates; the RPN consults the RN as the patient's needs change (Scope in Practice box; Chapter 1, section 1.3). Waiting for the RN (b), delaying reassessment (c) or believing only the RN can respond (d) all delay care for an unstable patient.

36. [CORE] On the first day after bowel surgery, a patient has sinus tachycardia at 122 per minute, a temperature of 38.6 °C and pain rated 8 out of 10. What is the nurse's best action?

a. Ask the physician for a rate-control drug to bring the heart rate below 100 per minute
b. Encourage the patient to perform a Valsalva manoeuvre
c. Prepare the patient for synchronized cardioversion
d. Assess for causes such as pain, fever, bleeding and low fluid volume, and report the findings

Answer: d — Sinus tachycardia is usually a response to another problem, so the nurse looks for and treats the cause (section 16.5). Slowing the rate with a drug (a) could reduce cardiac output if the tachycardia is compensating. Vagal manoeuvres (b) are for SVT. Cardioversion (c) does not treat sinus tachycardia.

37. [RN] A 58-year-old with newly diagnosed atrial fibrillation has hypertension and no other conditions. According to the CCS CHADS-65 algorithm, what is the recommended antithrombotic approach?

a. No antithrombotic drug, because the patient is younger than 65
b. Acetylsalicylic acid (ASA) alone
c. Oral anticoagulation, preferably a direct oral anticoagulant
d. Oral anticoagulation only once the patient reaches 75

Answer: c — Under the CCS algorithm, a person younger than 65 with at least one CHADS2 risk factor (here hypertension) should receive oral anticoagulation, and a DOAC is preferred over warfarin for most patients (section 16.6). No therapy (a) applies only when there are no CHADS2 risk factors and no arterial disease. ASA alone (b) is for people under 65 with no CHADS2 risk factors but with coronary or arterial disease. The algorithm's age threshold is 65, not 75 (d).

38. [RN] A patient with a permanent pacemaker reports dizziness. The strip shows pacing spikes at regular intervals, but several spikes are not followed by a QRS, and the heart rate is 38 per minute. How should the nurse interpret this?

a. Failure to capture
b. Failure to sense
c. Normal demand pacing
d. Third-degree AV block with normal pacemaker function

Answer: a — A spike without a following P wave or QRS means the impulse did not stimulate the heart: failure to capture (section 16.7). Failure to sense (b), or undersensing, shows spikes at the wrong times that compete with the patient's own beats; oversensing causes pauses with no spikes at all. Normal pacing (c) has a QRS after each ventricular spike. A normally functioning pacemaker (d) would capture and prevent such a slow rate.

39. [RN] A patient who has taken amiodarone for 8 months reports a new dry cough and increasing shortness of breath. What should the nurse do?

a. Reassure the patient that a cough is an expected, harmless effect
b. Report the symptoms promptly, because they may signal pulmonary toxicity
c. Advise the patient to take a double dose to control the rhythm better
d. Tell the patient to stop amiodarone right away without contacting the prescriber

Answer: b — Pulmonary toxicity is the most important potentially fatal adverse effect of amiodarone, and new respiratory symptoms call for prompt reassessment (Medications box). The cough is not harmless (a). Doubling the dose (c) is unsafe. Stopping the drug without the prescriber (d) is unsafe, and its long half-life means effects persist for months anyway.

40. [RN] A stable patient has had atrial fibrillation for at least 3 weeks and is booked for a planned electrical cardioversion. According to CCS guidance, what is the usual anticoagulation plan?

a. No anticoagulation is needed, provided the cardioversion restores sinus rhythm.

b. Anticoagulation is needed only if the patient's CHADS2 score is 2 or higher.

c. A single dose of anticoagulant on the morning of the procedure is enough to prevent clots.

d. At least 3 weeks of therapeutic anticoagulation before, or a transesophageal echocardiogram to rule out clot, and at least 4 weeks after

Answer: d — For AF lasting more than 48 hours, the CCS recommends at least 3 weeks of therapeutic anticoagulation before planned cardioversion (or a transesophageal echocardiogram), and at least 4 weeks afterward, then long-term therapy by the CHADS-65 algorithm (section 16.6). Clots can form or travel after a successful cardioversion (a). The CHADS2 rule (b) applies only to AF of 12 to 48 hours. A single dose (c) is not adequate.

References

Abbas, N., Rehman, H. Y., Siddique, F. A., Sharif, A., Rehman, A., & Ahmad, F. (2024). Diagnostic accuracy of apex-pulse deficit for detecting atrial fibrillation. *Pakistan Armed Forces Medical Journal, 74*(4), 1129–1132. https://doi.org/10.51253/pafmj.v74i4.11531

American Association of Critical-Care Nurses. (2018, April 3). *Managing alarms in acute care across the life span: Electrocardiography and pulse oximetry* [Practice alert]. https://www.aacn.org/clinical-resources/practice-alerts/alarm-management

American Heart Association. (2025). *Adult cardiac arrest algorithm* [Accessible long description]. https://cpr.heart.org/-/media/CPR-Files/CPR-Guidelines-Files/2025-Accessible/Algorithm-ACLS-CA-Circular-LngDscrp-250725-Ed.pdf

Andrade, J. G., Aguilar, M., Atzema, C., Bell, A., Cairns, J. A., Cheung, C. C., Cox, J. L., Dorian, P., Gladstone, D. J., Healey, J. S., Khairy, P., Leblanc, K., McMurtry, M. S., Mitchell, L. B., Nair, G. M., Nattel, S., Parkash, R., Pilote, L., Sandhu, R. K., … Macle, L. (2020). The 2020 Canadian Cardiovascular Society/Canadian Heart Rhythm Society comprehensive guidelines for the management of atrial fibrillation. *Canadian Journal of Cardiology, 36*(12), 1847–1948. https://doi.org/10.1016/j.cjca.2020.09.001

Brodovicz, K. G., McNaughton, K., Uemura, N., Meininger, G., Girman, C. J., & Yale, S. H. (2009). Reliability and feasibility of methods to quantitatively assess peripheral edema. *Clinical Medicine & Research, 7*(1–2), 21–31. https://doi.org/10.3121/cmr.2009.819

Canadian Cardiovascular Society. (n.d.). *Top 10 takeaways: 2020 atrial fibrillation guidelines*. https://ccs.ca/news/top-10-takeaways/

Cantillon, D. J. (2013). Evaluation and management of premature ventricular complexes. *Cleveland Clinic Journal of Medicine, 80*(6), 377–387. https://doi.org/10.3949/ccjm.80a.12168

Canto, J. G., Rogers, W. J., Goldberg, R. J., Peterson, E. D., Wenger, N. K., Vaccarino, V., Kiefe, C. I., Frederick, P. D., Sopko, G., Zheng, Z.-J., & NRMI Investigators. (2012). Association of age and sex with myocardial infarction symptom presentation and in-hospital mortality. *JAMA, 307*(8), 813–822. https://doi.org/10.1001/jama.2012.199

Chua Chiaco, J. M. S., Parikh, N. I., & Fergusson, D. J. (2013). The jugular venous pressure revisited. *Cleveland Clinic Journal of Medicine, 80*(10), 638–644. https://doi.org/10.3949/ccjm.80a.13039

College of Nurses of Ontario. (2025a). *Forms of energy*. https://cno.org/standards-learning/educational-tools/forms-of-energy

College of Nurses of Ontario. (2025b). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

Drew, B. J., Harris, P., Zègre-Hemsey, J. K., Mammone, T., Schindler, D., Salas-Boni, R., Bai, Y., Tinoco, A., Ding, Q., & Hu, X. (2014). Insights into the problem of alarm fatigue with physiologic monitor devices: A comprehensive observational study of consecutive intensive care unit patients. *PLoS ONE, 9*(10), Article e110274. https://doi.org/10.1371/journal.pone.0110274

Felker, G. M., Petersen, J. W., & Mark, D. B. (2006). Natriuretic peptides in the diagnosis and management of heart failure. *CMAJ, 175*(6), 611–617. https://doi.org/10.1503/cmaj.060236

Fresenius Kabi Canada. (2016). *Adenosine injection, USP: Product monograph*. https://www.fresenius-kabi.com/en-ca/documents/Adenosine-PM-ENG-v6.1.pdf

Guerra, P. G., Simpson, C. S., Van Spall, H. G. C., Asgar, A. W., Billia, P., Cadrin-Tourigny, J., Chakrabarti, S., Cheung, C. C., Dore, A., Fordyce, C. B., Gouda, P., Hassan, A., Krahn, A., Luc, J. G. Y., Mak, S., McMurtry, S., Norris, C., Philippon, F., Sapp, J., … Wood, D. A. (2024). Canadian Cardiovascular Society 2023 guidelines on the fitness to drive. *Canadian Journal of Cardiology, 40*(4), 500–523. https://doi.org/10.1016/j.cjca.2023.09.033

Gulati, M., Levy, P. D., Mukherjee, D., Amsterdam, E., Bhatt, D. L., Birtcher, K. K., Blankstein, R., Boyd, J., Bullock-Palmer, R. P., Conejo, T., Diercks, D. B., Gentile, F., Greenwood, J. P., Hess, E. P., Hollenberg, S. M., Jaber, W. A., Jneid, H., Joglar, J. A., Morrow, D. A., … Shaw, L. J. (2021). 2021 AHA/ACC/ASE/CHEST/SAEM/SCCT/SCMR guideline for the evaluation and diagnosis of chest pain: A report of the American College of Cardiology/American Heart Association Joint Committee on Clinical Practice Guidelines. *Circulation, 144*(22), e368–e454. https://doi.org/10.1161/CIR.0000000000001029

Health Canada. (2016). *Automated external defibrillators (AEDs)*. https://www.canada.ca/en/health-canada/services/drugs-medical-devices/automated-external-defibrillators-aeds.html

Heart and Stroke Foundation of Canada. (2018, February 1). *Women's heart health is another glass ceiling we need to smash* [News release]. https://www.heartandstroke.ca/what-we-do/media-centre/news-releases/2018-heart-report-news-release

Heart and Stroke Foundation of Canada. (2025). *Highlights of the 2025 American Heart Association guidelines for cardiopulmonary resuscitation and emergency cardiovascular care: Heart and Stroke Foundation of Canada edition*. https://cpr.heartandstroke.ca/resource/GuidelinesHighlightsEN2025

Heart and Stroke Foundation of Canada. (n.d.-a). *Cardiac catheterization*. Retrieved October 25, 2026, from https://www.heartandstroke.ca/heart-disease/tests/cardiac-catheterization

Heart and Stroke Foundation of Canada. (n.d.-b). *Exercise electrocardiogram*. Retrieved October 25, 2026, from https://www.heartandstroke.ca/heart-disease/tests/exercise-electrocardiogram

Heart and Stroke Foundation of Canada. (n.d.-c). *Holter or event monitoring*. Retrieved October 25, 2026, from https://www.heartandstroke.ca/heart-disease/tests/holter-or-event-monitoring

Heart and Stroke Foundation of Canada. (n.d.-d). *Signs of a heart attack*. Retrieved October 25, 2026, from https://www.heartandstroke.ca/heart-disease/emergency-signs

Heart and Stroke Foundation of Canada. (n.d.-e). *Tests*. Retrieved October 25, 2026, from https://www.heartandstroke.ca/heart-disease/tests

Heart and Stroke Foundation of Canada. (n.d.-f). *Transesophageal echocardiogram (TEE)*. Retrieved October 25, 2026, from https://www.heartandstroke.ca/heart-disease/tests/transesophageal-echocardiogram-tee

Indik, J. H., Gimbel, J. R., Abe, H., Alkmim-Teixeira, R., Birgersdotter-Green, U., Clarke, G. D., Dickfeld, T. M. L., Froelich, J. W., Grant, J., Hayes, D. L., Heidbuchel, H., Idriss, S. F., Kanal, E., Lampert, R., Machado, C. E., Mandrola, J. M., Nazarian, S., Patton, K. K., Rozner, M. A., … Woodard, P. K. (2017). 2017 HRS expert consensus statement on magnetic resonance imaging and radiation exposure in patients with cardiovascular implantable electronic devices. *Heart Rhythm, 14*(7), e97–e153. https://doi.org/10.1016/j.hrthm.2017.04.025

JAMP Pharma Corporation. (2022). *JAMP Amiodarone (amiodarone hydrochloride tablets): Product monograph*. https://pdf.hres.ca/dpd_pm/00067870.PDF

Kligfield, P., Gettes, L. S., Bailey, J. J., Childers, R., Deal, B. J., Hancock, E. W., van Herpen, G., Kors, J. A., Macfarlane, P., Mirvis, D. M., Pahlm, O., Rautaharju, P., & Wagner, G. S. (2007). Recommendations for the standardization and interpretation of the electrocardiogram: Part I: The electrocardiogram and its technology. *Circulation, 115*(10), 1306–1324. https://doi.org/10.1161/CIRCULATIONAHA.106.180200

Kusumoto, F. M., Schoenfeld, M. H., Barrett, C., Edgerton, J. R., Ellenbogen, K. A., Gold, M. R., Goldschlager, N. F., Hamilton, R. M., Joglar, J. A., Kim, R. J., Lee, R., Marine, J. E., McLeod, C. J., Oken, K. R., Patton, K. K., Pellegrini, C. N., Selzman, K. A., Thompson, A., & Varosy, P. D. (2019). 2018 ACC/AHA/HRS guideline on the evaluation and management of patients with bradycardia and cardiac conduction delay: A report of the American College of Cardiology/American Heart Association Task Force on Clinical Practice Guidelines and the Heart Rhythm Society. *Circulation, 140*(8), e382–e482. https://doi.org/10.1161/CIR.0000000000000628

Lampert, R., Hayes, D. L., Annas, G. J., Farley, M. A., Goldstein, N. E., Hamilton, R. M., Kay, G. N., Kramer, D. B., Mueller, P. S., Padeletti, L., Pozuelo, L., Schoenfeld, M. H., Vardas, P. E., Wiegand, D. L., & Zellner, R. (2010). HRS expert consensus statement on the management of cardiovascular implantable electronic devices (CIEDs) in patients nearing end of life or requesting withdrawal of therapy. *Heart Rhythm, 7*(7), 1008–1026. https://doi.org/10.1016/j.hrthm.2010.04.033

Macdonald, D. B., Hurrell, C. D., Costa, A. F., McInnes, M. D. F., O'Malley, M., Barrett, B. J., Brown, P. A., Clark, E. G., Hadjivassiliou, A., Kirkpatrick, I. D. C., Rempel, J., Jeon, P., & Hiremath, S. (2022). Canadian Association of Radiologists guidance on contrast-associated acute kidney injury. *Canadian Journal of Kidney Health and Disease, 9*, Article 20543581221097455. https://doi.org/10.1177/20543581221097455

McGuffin, K. S., & Ortiz, S. (2019). Daily electrocardiogram electrode change and the effect on frequency of nuisance alarms. *Dimensions of Critical Care Nursing, 38*(4), 187–191. https://doi.org/10.1097/DCC.0000000000000362

Mehta, L. S., Beckie, T. M., DeVon, H. A., Grines, C. L., Krumholz, H. M., Johnson, M. N., Lindley, K. J., Vaccarino, V., Wang, T. Y., Watson, K. E., & Wenger, N. K. (2016). Acute myocardial infarction in women: A scientific statement from the American Heart Association. *Circulation, 133*(9), 916–947. https://doi.org/10.1161/CIR.0000000000000351

Mukwende, M., Tamony, P., & Turner, M. (2020). *Mind the gap: A handbook of clinical signs in Black and Brown skin*. St George's, University of London. https://iiif.wellcomecollection.org/file/b32878382_0001.pdf

Mulvagh, S. L., Colella, T. J. F., Gulati, M., Crosier, R., Allana, S., Randhawa, V. K., Bruneau, J., Pacheco, C., Jaffer, S., Cotie, L., Mensour, E., Clavel, M.-A., Hill, B., Kirkham, A. A., Foulds, H., Liblik, K., Van Damme, A., Grace, S. L., Bouchard, K., … Norris, C. M. (2024). The Canadian Women's Heart Health Alliance ATLAS on the epidemiology, diagnosis, and management of cardiovascular disease in women: Chapter 9: Summary of current status, challenges, opportunities, and recommendations. *CJC Open, 6*(2 Part B), 258–278. https://doi.org/10.1016/j.cjco.2023.12.001

Nova Scotia Health. (2025). *Living with your implantable cardioverter defibrillator (ICD)* [Patient pamphlet 0241]. https://www.nshealth.ca/sites/default/files/documents/0241-2026.03.25.pdf

Page, R. L., Joglar, J. A., Caldwell, M. A., Calkins, H., Conti, J. B., Deal, B. J., Estes, N. A. M., III, Field, M. E., Goldberger, Z. D., Hammill, S. C., Indik, J. H., Lindsay, B. D., Olshansky, B., Russo, A. M., Shen, W.-K., Tracy, C. M., & Al-Khatib, S. M. (2016). 2015 ACC/AHA/HRS guideline for the management of adult patients with supraventricular tachycardia: A report of the American College of Cardiology/American Heart Association Task Force on Clinical Practice Guidelines and the Heart Rhythm Society. *Heart Rhythm, 13*(4), e136–e221. https://doi.org/10.1016/j.hrthm.2015.09.019

Pharmascience. (2022). *pms-DIGOXIN (digoxin) tablets and oral solution: Product monograph*. https://pdf.hres.ca/dpd_pm/00069390.PDF

Piccini, J. P., Allen, L. A., Kudenchuk, P. J., Page, R. L., Patel, M. R., & Turakhia, M. P. (2016). Wearable cardioverter-defibrillator therapy for the prevention of sudden cardiac death: A science advisory from the American Heart Association. *Circulation, 133*(17), 1715–1727. https://doi.org/10.1161/CIR.0000000000000394

Public Health Agency of Canada. (2017). *Heart disease in Canada: Highlights from the Canadian Chronic Disease Surveillance System*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/heart-disease-canada-fact-sheet.html

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Reichlin, T., Twerenbold, R., Wildi, K., Rubini Gimenez, M., Bergsma, N., Haaf, P., Druey, S., Puelacher, C., Moehring, B., Freese, M., Stelzig, C., Krivoshei, L., Hillinger, P., Jäger, C., Herrmann, T., Kreutzinger, P., Radosavac, M., Moreno Weidmann, Z., Pershyna, K., … Mueller, C. (2015). Prospective validation of a 1-hour algorithm to rule-out and rule-in acute myocardial infarction using a high-sensitivity cardiac troponin T assay. *CMAJ, 187*(8), E243–E252. https://doi.org/10.1503/cmaj.141349

Sampson, M. (2016). Understanding the ECG. Part 4: Conduction blocks. *British Journal of Cardiac Nursing, 11*(2), 71–79. https://doi.org/10.12968/bjca.2016.11.2.71

Sampson, M. (2018). Continuous ECG monitoring in hospital: Part 2, practical issues. *British Journal of Cardiac Nursing, 13*(3), 128–134. https://doi.org/10.12968/bjca.2018.13.3.128

Sampson, M., & McGrath, A. (2015). Understanding the ECG. Part 1: Anatomy and physiology. *British Journal of Cardiac Nursing, 10*(11), 548–554. https://doi.org/10.12968/bjca.2015.10.11.548

Sandau, K. E., Funk, M., Auerbach, A., Barsness, G. W., Blum, K., Cvach, M., Lampert, R., May, J. L., McDaniel, G. M., Perez, M. V., Sendelbach, S., Sommargren, C. E., & Wang, P. J. (2017). Update to practice standards for electrocardiographic monitoring in hospital settings: A scientific statement from the American Heart Association. *Circulation, 136*(19), e273–e344. https://doi.org/10.1161/CIR.0000000000000527

Sniderman, A. D., Lachapelle, K. J., & Thanassoulis, G. (2025). Myocardial compression and recoil as determinants of coronary blood flow. *European Heart Journal, 46*(39), 3844–3850. https://doi.org/10.1093/eurheartj/ehaf518

Society for Cardiological Science and Technology. (2014). *Clinical guidelines by consensus: Recording a standard 12-lead electrocardiogram. An approved methodology* (Version 2.0). https://www.bmj.com/sites/default/files/response_attachments/2016/09/CAC_SCST_Recording_a_12-lead_ECG_final_version_2014_CS2v2.0.pdf

Statistics Canada. (2026, January 13). Deaths, 2024. *The Daily*. https://www150.statcan.gc.ca/n1/daily-quotidien/260113/dq260113b-eng.htm

Surawicz, B., Childers, R., Deal, B. J., & Gettes, L. S. (2009). AHA/ACCF/HRS recommendations for the standardization and interpretation of the electrocardiogram: Part III: Intraventricular conduction disturbances: A scientific statement from the American Heart Association Electrocardiography and Arrhythmias Committee, Council on Clinical Cardiology; the American College of Cardiology Foundation; and the Heart Rhythm Society. *Circulation, 119*(10), e235–e240. https://doi.org/10.1161/CIRCULATIONAHA.108.191095

Thygesen, K., Alpert, J. S., Jaffe, A. S., Chaitman, B. R., Bax, J. J., Morrow, D. A., White, H. D., & Executive Group on behalf of the Joint European Society of Cardiology (ESC)/American College of Cardiology (ACC)/American Heart Association (AHA)/World Heart Federation (WHF) Task Force for the Universal Definition of Myocardial Infarction. (2018). Fourth universal definition of myocardial infarction (2018). *Circulation, 138*(20), e618–e651. https://doi.org/10.1161/CIR.0000000000000617

Vincent, J.-L. (2008). Understanding cardiac output. *Critical Care, 12*(4), Article 174. https://doi.org/10.1186/cc6975

Warriner, D., Michaels, J., & Morris, P. D. (2019). Cardiac auscultation: Normal and abnormal. *British Journal of Hospital Medicine, 80*(2), C28–C31. https://doi.org/10.12968/hmed.2019.80.2.C28

Wigginton, J. G., Agarwal, S., Bartos, J. A., Coute, R. A., Drennan, I. R., Haamid, A., Kudenchuk, P. J., Link, M. S., Panchal, A. R., Pelter, M. M., Del Rios, M., Rodriguez, A. J., Perman, S. M., Sanko, S., Kotini-Shah, P., & Kurz, M. C. (2025). Part 9: Adult advanced life support: 2025 American Heart Association guidelines for cardiopulmonary resuscitation and emergency cardiovascular care. *Circulation, 152*(16 Suppl. 2), S538–S577. https://doi.org/10.1161/CIR.0000000000001376

17 Coronary Artery Disease and Acute Coronary Syndromes

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain how atherosclerosis develops and relate it to stable angina and the acute coronary syndromes.
2. Identify cardiovascular risk factors using Canadian data, and interpret lipid test results in mmol/L against CCS thresholds.
3. Teach patients with stable angina about their medications, including sublingual nitroglycerin and when to call 9-1-1.
4. Recognize acute coronary syndromes, including presentations common in women and older adults, and take the immediate actions in order.
5. Describe reperfusion for STEMI and the early medications for ACS, and monitor for bleeding and other complications.
6. Provide nursing care before and after PCI and after CABG, including access-site checks and sternal precautions.
7. Support cardiac rehabilitation and secondary prevention, naming the structural barriers to referral and completion.
8. Distinguish RN and RPN roles in ACS care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 4, 5	Clinician; Scholar	Foundations of Practice
3, 6, 7	Clinician; Educator; Advocate; Collaborator	Foundations of Practice; Collaborative Practice
8	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

Coronary artery disease (CAD) is the narrowing of the coronary arteries by atherosclerotic plaque, which limits blood flow to the heart muscle. Canadian Chronic Disease Surveillance System data for 2023 to 2024 show that 8.2% of Canadian adults had diagnosed **ischemic heart disease** (about 10% among males and 7% among females aged 20 years and older) (Public Health Agency of Canada [PHAC], 2026). In preliminary data for 2024, diseases of the heart ranked second among causes of death in Canada, behind cancer, and accounted for 17.7% of all deaths (Statistics Canada, 2026).

Every nurse, on every unit, may be the first to notice an **acute coronary syndrome (ACS)**: a patient admitted for pneumonia can develop chest pressure in the night. Heart muscle starts to die soon after a coronary artery closes, so fast recognition and escalation save lives.

This chapter covers atherosclerosis and cardiovascular risk (section 17.1), stable angina and chronic coronary disease (17.2), recognizing acute coronary syndromes (17.3), early treatment and complications of ACS (17.4), care around percutaneous coronary intervention (PCI) and coronary artery bypass grafting (CABG) (17.5), and cardiac rehabilitation and living with coronary disease (17.6). It builds on Chapter 16 (cardiac assessment and the 12-lead electrocardiogram [ECG]) and links to Chapters 14 (smoking), 18 (heart failure), 19 (hypertension) and 22 (diabetes).

17.1 Atherosclerosis and Cardiovascular Risk

How Plaque Forms

Atherosclerosis is a chronic inflammatory disease of the artery wall in which lipids, immune cells and fibrous tissue collect beneath the inner lining. It develops silently over many years.

The process begins with **endothelial dysfunction**. A healthy endothelium keeps the vessel relaxed, smooth and resistant to clotting. High blood lipids, hypertension, smoking and diabetes increase oxidative stress and reduce nitric oxide, so the lining becomes leaky, sticky and prone to spasm. Damage tends to start where blood flow is disturbed, such as at branch points (Jebari-Benslaiman et al., 2022).

Next, **low-density lipoprotein (LDL)** particles cross the damaged lining and become trapped in the intima, the innermost layer of the wall. There they are chemically altered, mainly by oxidation. Oxidized LDL acts as an alarm signal: endothelial cells display adhesion molecules and release chemical attractants that pull monocytes into the wall. The monocytes mature into macrophages and engulf altered LDL until they are swollen with fat. These **foam cells** form the **fatty streak**, the earliest visible lesion. Smooth muscle cells can also take up lipid and become foam cells (Jebari-Benslaiman et al., 2022).

As the lesion grows, smooth muscle cells move in from the middle layer of the wall, multiply and lay down collagen. This builds a **fibrous cap** that keeps the lesion's contents away from the bloodstream. Under the cap, macrophages that die and are not cleared away form a soft **necrotic core**, rich in lipid and in tissue factor, a strong trigger of clotting.

A **stable plaque** has a thick cap and little inflammation. It may narrow the lumen enough to limit flow during exertion, causing angina. A **vulnerable plaque** has a large necrotic core, a thin cap and active inflammation, and enzymes released by inflammatory cells weaken the cap further (Jebari-Benslaiman et al., 2022). When the cap tears, called **plaque rupture**, blood meets the core. Platelets stick and activate, the clotting cascade makes thrombin and fibrin, and a thrombus forms that can partly or fully block the artery. Loss of the lining over a plaque without a tear, called erosion, can also start a thrombus. Plaque rupture or erosion with thrombosis is the mechanism of most heart attacks, classed as type 1 myocardial infarction (Thygesen et al., 2018).

Risk Factors

In the INTERHEART case-control study, which compared 15,152 people with a first myocardial infarction with 14,820 controls in 52 countries, nine potentially modifiable factors together accounted for 90% of the population attributable risk in men and 94% in women (Yusuf et al., 2004). Smoking, an unfavourable balance of blood apolipoproteins, hypertension, diabetes, abdominal obesity and psychosocial stress were strongly linked to heart attack, while fruit and vegetable intake and regular physical activity were protective.

Modifiable risk factors include:

- **Smoking and vaping:** cessation support is covered in Chapter 14.
- **Hypertension:** see Chapter 19.
- **Dyslipidemia:** high LDL cholesterol or other atherogenic lipoproteins (described below).
- **Diabetes:** see Chapter 22; most adults with diabetes have a condition for which the Canadian Cardiovascular Society (CCS) recommends a statin (Pearson et al., 2021).
- **Abdominal obesity, physical inactivity and an unhealthy diet:** for example, low intake of vegetables, fruit and fibre.
- **Psychosocial stress.**
- **Chronic kidney disease:** another statin-indicated condition (Chapter 27).

Nonmodifiable factors include older age, male sex and inherited lipid disorders such as familial hypercholesterolemia and a high lipoprotein(a) level. A 2017 PHAC surveillance report found that a first heart attack was about twice as likely in men as in women (PHAC, 2017).

Some risk factors are specific to women. Preeclampsia and gestational hypertension raise the chance of hypertension later in life, and gestational diabetes raises the chance of type 2 diabetes. After menopause, LDL cholesterol, triglycerides, blood pressure and weight

tend to rise (Heart and Stroke Foundation of Canada, n.d.-c). The CCS recommends a full lipid panel late in the postpartum period for women who had a pregnancy complication such as a hypertensive disorder of pregnancy, along with counselling about their higher lifetime risk (Pearson et al., 2021).

Risk is also shaped by structural conditions such as income, housing, food access and distance from care, not by race as biology (Chapter 2). The CCS suggests considering earlier lipid screening for South Asian and Indigenous people at higher risk, and it notes that high lipoprotein(a) carries a particularly high population burden among South Asian and Latin American people (Pearson et al., 2021). When First Nations data are used, the First Nations principles of OCAP® (ownership, control, access and possession) apply.

Assessing Risk and Lipid Tests

The CCS recommends lipid screening for adults over age 40, and at any age when certain risk conditions are present (Pearson et al., 2021). Screening uses a **lipid panel**: total cholesterol, LDL cholesterol (LDL-C), high-density lipoprotein cholesterol (HDL-C), triglycerides and **non-HDL cholesterol (non-HDL-C)**, which is total cholesterol minus HDL-C. A nonfasting sample is recommended, except for people with known triglycerides above 4.5 mmol/L. When triglycerides are above 1.5 mmol/L, the CCS prefers non-HDL-C or **apolipoprotein B (ApoB)** to LDL-C. **Lipoprotein(a) [Lp(a)]** should be measured a single time in life, at the first lipid screen (Pearson et al., 2021). Reference ranges vary by laboratory.

Some people need a statin whatever their calculated risk. The CCS lists these **statin-indicated conditions** (Pearson et al., 2021):

- clinical atherosclerotic cardiovascular disease (ASCVD), such as previous myocardial infarction or angina;
- abdominal aortic aneurysm larger than 3.0 cm, or previous aneurysm surgery;
- most people with diabetes (aged 40 or older; aged 30 or older with diabetes for 15 years or more; or with microvascular complications);
- chronic kidney disease, not on dialysis, with an estimated glomerular filtration rate below 60 mL/min/1.73 m^2 or albuminuria (urine albumin-to-creatinine ratio of 3 mg/mmol or more) for at least 3 months;
- LDL-C of 5.0 mmol/L or more, or familial hypercholesterolemia.

For everyone else aged 40 to 75, the CCS recommends estimating 10-year cardiovascular risk every 5 years with the Framingham Risk Score or the Cardiovascular Life Expectancy Model. A 10-year risk of 20% or more is high, 10% to 19.9% is intermediate, and below 10% is low (Pearson et al., 2021). Table 17.1 summarizes the lipid tests.

Table 17.1 Lipid tests and when CCS suggests intensifying treatment (Pearson et al., 2021; original wording)

Test	What it measures	Threshold for intensifying therapy (ASCVD on the highest tolerated statin dose)	Notes
LDL-C	Cholesterol carried in low-density lipoprotein particles, the main target of treatment	In a person with ASCVD on the highest tolerated statin dose: LDL-C 1.8 mmol/L or more	Less reliable when triglycerides are above 1.5 mmol/L
Non-HDL-C	All cholesterol in atherogenic particles (total cholesterol minus HDL-C)	Non-HDL-C 2.4 mmol/L or more	Preferred over LDL-C when triglycerides are above 1.5 mmol/L; nonfasting sample is fine
ApoB	The number of atherogenic particles (each carries one ApoB molecule)	ApoB 0.7 g/L or more	Alternative to non-HDL-C; reported in g/L
Lp(a)	An inherited lipoprotein particle that adds risk	Not a treatment target; 50 mg/dL (100 nmol/L) or more calls for earlier, more intensive risk-factor management in primary prevention	Measure once in a lifetime at the first lipid screen

Lowering Risk

Health behaviours are the base of prevention. The CCS recommends a Mediterranean dietary pattern first and also names the Portfolio, DASH (Dietary Approaches to Stop Hypertension), low-glycemic-index and plant-based patterns, along with nuts,

legumes, olive oil, vegetables and fruit, fibre and whole grains. It recommends 150 minutes or more each week of moderate- to vigorous-intensity aerobic activity, plus muscle- and bone-strengthening activity on at least 2 days a week (Pearson et al., 2021).

Statins are the first lipid-lowering drugs for people with ASCVD or another statin-indicated condition, at the highest dose the person tolerates (Pearson et al., 2021). Atorvastatin and rosuvastatin are common examples. When a person with ASCVD stays at or above the thresholds in Table 17.1, the CCS recommends intensifying treatment with **ezetimibe**, a **proprotein convertase subtilisin/kexin type 9 (PCSK9) inhibitor** such as evolocumab or alirocumab, or both. If ezetimibe is added first and LDL-C stays at 1.8 mmol/L or more, a PCSK9 inhibitor is recommended next. **Icosapent ethyl** is recommended for people with ASCVD, or with diabetes and at least one other cardiovascular risk factor, whose fasting triglycerides stay between 1.5 and 5.6 mmol/L on the highest tolerated statin dose (Pearson et al., 2021).

The main adverse effects of statins involve muscle. Muscle aches (myalgia) can occur, true myopathy is less common, and rhabdomyolysis, which can cause acute kidney injury, is rare. Risk is higher with age over 65, hypothyroidism, kidney impairment and some interacting drugs. The Canadian atorvastatin monograph tells patients to report, without delay, muscle pain, tenderness or weakness that has no clear cause, particularly if they also have a fever or feel generally unwell, and it advises liver tests before treatment starts (Apotex Inc., 2024). The nurse asks about muscle symptoms, reports them, and encourages the patient not to stop a statin without talking to the prescriber, because a lower or different statin dose often works (Pearson et al., 2021).

CANADIAN CONTEXT

Coronary Disease and Equity

- **Women:** The Heart and Stroke Foundation's 2018 report named heart disease as the top cause of early death among women in Canada. It noted that women were less likely than men to receive bypass surgery, stents, statins and anticlotting therapy, and only half as likely to take part in or complete cardiac rehabilitation (Heart and Stroke Foundation of Canada, 2018). Women with ST-elevation myocardial infarction (STEMI) are slower to recognize their symptoms and to seek help, and they wait longer for an ECG and for reperfusion (Mulvagh et al., 2024).
- **First Nations, Inuit and Métis Peoples:** The same report described a death rate from coronary heart disease that was 53% higher among Indigenous women than among non-Indigenous women, and too few cardiac care resources in the remote and rural hospitals serving women who live on reserve (Heart and Stroke Foundation of Canada, 2018). Many sources do not report data by distinct Nation or People; the causes are structural, rooted in colonization and access to care (Chapter 2).
- **Rural and remote communities:** Canada's geography makes timely reperfusion hard, which is why the CCS calls for regional STEMI networks with set transport and treatment pathways (Wong et al., 2019).

17.2 Stable Angina and Chronic Coronary Disease

What Stable Angina Is

Angina pectoris is discomfort caused by **myocardial ischemia**, a shortfall of oxygen to heart muscle. In **stable angina**, a fixed plaque narrows a coronary artery. At rest, enough blood gets through. When exertion or emotional stress raises the heart rate, blood pressure and force of contraction, the muscle's oxygen demand outstrips the limited supply, and ischemia follows.

The classic picture is discomfort behind the breastbone that is brought on by exertion or emotional stress and eased by rest or nitroglycerin (Vrints et al., 2024). Patients often describe pressure, squeezing, tightness or heaviness rather than pain, and it may spread to the neck, jaw, shoulders, arms or back. What makes the angina "stable" is its predictable pattern: a similar trigger, a similar feeling and a similar response to rest or nitroglycerin each time.

Some people never feel chest discomfort. An **anginal equivalent** is a symptom other than chest pain that reflects ischemia, such as breathlessness or unusual fatigue on exertion. Breathlessness on exertion can be the main symptom for some people, and women may describe breathlessness and fatigue (Vrints et al., 2024). The European Society of Cardiology (ESC) recommends avoiding the word "atypical" for these symptoms, because it can lead clinicians to dismiss them (Byrne et al., 2023).

Stable angina is one form of **chronic coronary disease**, the long-term phase of CAD that also includes people living with CAD after an ACS or a revascularization procedure. Diagnosis rests on the history, a resting 12-lead ECG, blood tests including a lipid profile,

and functional or anatomical tests such as stress testing, coronary computed tomography angiography or invasive angiography (Vrints et al., 2024; Figure 17.1). Stress testing and cardiac catheterization are described in Chapter 16, section 16.3.

At each contact, the nurse asks about the pattern: how often episodes occur, what brings them on, how long they last and how many nitroglycerin doses the patient uses. A change in pattern, such as angina at rest or with much less effort than usual, may mean unstable angina and needs urgent assessment (section 17.3).



Figure 17.1 Three-dimensional images of the heart built from a coronary computed tomography angiography scan, showing the coronary arteries on its surface. (credit: “Coronary CT Angiography Scan” by Goleisureintl/Wikimedia Commons, CC BY 4.0)

Treatment

Treatment has two goals: to relieve symptoms and to prevent heart attack and death. The drug guidance in this subsection comes from the United Kingdom's National Institute for Health and Care Excellence (NICE) and the 2024 ESC guideline, which are not Canadian guidelines; local protocols may differ. All patients need risk-factor management as described in section 17.1, including a statin, since clinical ASCVD is a statin-indicated condition (Pearson et al., 2021). Low-dose acetylsalicylic acid (ASA) is commonly used as an antiplatelet drug, weighed against the person's bleeding risk (NICE, 2011). NICE also suggests considering an angiotensin-converting enzyme (ACE) inhibitor for people who have both stable angina and diabetes.

For symptoms, NICE names a **beta-blocker** as one first-line anti-anginal choice and a **calcium channel blocker** as the other (NICE, 2011). Both lower the heart's oxygen demand. When these cannot be used or do not control symptoms, a long-acting nitrate or another agent may be added, and a combination is often needed (NICE, 2011; Vrints et al., 2024). Every patient also has a short-acting nitrate for relief, described below.

Revascularization, by PCI or CABG, is considered when symptoms persist despite medical treatment or when testing shows high-risk coronary anatomy (Vrints et al., 2024). Section 17.5 covers nursing care around these procedures.

The nurse checks heart rate and blood pressure before giving rate-lowering drugs as ordered, asks about dizziness and fatigue, and helps the patient keep a simple record of angina episodes to bring to appointments.

Teaching About Nitroglycerin

Nitroglycerin is a fast-acting nitrate taken under the tongue as a spray or tablet (Figure 17.2). It is used to relieve an episode of angina, and it can also be taken just before an activity that usually brings on angina (NICE, 2011). Heart and Stroke Foundation of Canada advice is clear on one point: when heart attack signs appear, the person calls 9-1-1 first, and a person who has nitroglycerin then takes their usual dose (Heart and Stroke Foundation of Canada, n.d.-d).

Canadian patient guidance from British Columbia health authorities gives a simple rule. The person sits down and takes one dose; the pain should ease within 5 minutes, and if it has not, the person calls 9-1-1. If the pain comes back, another dose may be taken after 5 minutes, with no more than 3 doses in 15 minutes (Fraser Health et al., 2023). The Canadian spray monograph allows the dose to be repeated twice at 5- to 10-minute intervals and tells people to seek emergency help if the pain persists (sanofi-aventis Canada, 2021). The nurse teaches the plan the prescriber has chosen and makes sure the patient knows when to call 9-1-1.

Headache is the most common side effect and can be severe. Dizziness and flushing are also common, so the person sits before each dose (Fraser Health et al., 2023; sanofi-aventis Canada, 2021). Nitroglycerin must never be combined with a phosphodiesterase-5 (PDE5) inhibitor, a drug class used for erectile dysfunction, because the combination can cause a dangerous fall in blood pressure (sanofi-aventis Canada, 2021). The Canadian tadalafil monograph states that at least 48 hours should pass after the last tadalafil dose before a nitrate is given in a life-threatening situation, under close medical supervision (Teva Canada, 2020). The vardenafil

Figure 17.2 Three forms of nitroglycerin: an intravenous solution (used in hospital), a sublingual spray and a transdermal patch. (credit: "Nitro" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

monograph sets an interval of at least 24 hours, again only for a life-threatening situation (Angita Pharma, 2022), and the sildenafil monograph states that it is not known when a nitrate can be given safely (Upjohn Canada, 2020).

PATIENT EDUCATION

Using Nitroglycerin and Calling 9-1-1

- **Carry it always.** Keep your nitroglycerin with you. Store the spray at room temperature, 15 °C to 30 °C (sanofi-aventis Canada, 2021). Keep extra tablets or spray in a dry place, not in a bathroom or car (Fraser Health et al., 2023).
- **Stop and sit down** at the first sign of angina.
- **Take one dose** under your tongue as your prescriber has taught you. Do not inhale the spray.
- **Call 9-1-1 if the pain has not eased 5 minutes after you use your nitroglycerin**, or if it feels different or worse than your usual angina. If the pain comes back, you may take another dose after 5 minutes, but no more than 3 doses in 15 minutes (Fraser Health et al., 2023).
- **If you think you are having a heart attack,** call 9-1-1 right away, then take your usual nitroglycerin dose. Chew and swallow ASA if you are not allergic or intolerant (Heart and Stroke Foundation of Canada, n.d.-d).
- **Expect a headache, flushing or light-headedness.** Get up slowly afterward.
- **Never combine nitroglycerin with erectile dysfunction drugs** such as sildenafil or tadalafil. Tell emergency staff if you have taken one.
- **Keep a record** of when angina happens and how many doses you needed, and report any change in your usual pattern.

17.3 Recognizing Acute Coronary Syndromes

The ACS Spectrum

An **acute coronary syndrome** is a sudden fall in blood flow to the heart muscle, most often caused by plaque rupture or erosion with thrombus. Unstable angina, non-ST-elevation myocardial infarction and ST-elevation myocardial infarction are grouped together as ACS (Thygesen et al., 2018). They share a cause and differ in how much heart muscle is injured and in what the ECG shows (Table 17.2).

A **myocardial infarction (MI)** is death of heart muscle cells caused by ischemia. Under the Fourth Universal Definition of Myocardial Infarction, acute MI is diagnosed when cardiac troponin (cTn) rises and/or falls with at least one value above the 99th percentile upper reference limit, together with clinical evidence of ischemia, such as symptoms, new ischemic ECG changes or

imaging showing newly lost heart muscle (Thygesen et al., 2018). A single troponin value cannot show a rise or fall, which is why samples are repeated. High-sensitivity troponin testing and rapid pathways are explained in Chapter 16, section 16.3.

The three ACS types are:

- **Unstable angina:** myocardial ischemia at rest or on minimal exertion without acute injury or death of heart muscle cells (Byrne et al., 2023). Troponin does not show an MI pattern. A previously stable pattern that changes, with angina at rest or with much less effort, fits this picture.
- **Non-ST-elevation myocardial infarction (NSTEMI):** an MI, confirmed by a troponin rise and/or fall, without persistent ST elevation. The ECG may show ST depression or T-wave inversion, or it may look normal.
- **ST-elevation myocardial infarction (STEMI):** an MI with new ST elevation in at least two contiguous leads. New, convex ST elevation, especially with reciprocal ST depression, usually reflects acute occlusion of a coronary artery (Thygesen et al., 2018).

The definition also separates MI by cause. **Type 1 MI** results from atherothrombosis: plaque rupture or erosion with a clot. **Type 2 MI** results from an imbalance between the heart's oxygen supply and its demand, without acute plaque disruption (Thygesen et al., 2018). Causes include severe anemia, hypoxemia, hypotension or shock, a fast or very slow heart rhythm, severe hypertension and coronary spasm. Type 2 MI can develop in hospitalized patients, for example during severe bleeding or shock. Treatment targets the cause, such as restoring blood volume or oxygenation, rather than opening an artery.

Table 17.2 Stable angina and the acute coronary syndromes compared (Byrne et al., 2023; Thygesen et al., 2018; Vrints et al., 2024; original wording)

Feature	Stable angina	Unstable angina	NSTEMI	STEMI
Pattern of pain	Predictable; brought on by exertion or emotional stress and eased by rest or nitroglycerin	New, at rest or on minimal exertion, or a change from the usual pattern	Ischemic symptoms, often at rest; may occur without chest pain	Ischemic symptoms, often at rest; may occur without chest pain
ECG	No new acute changes at rest	May show ST depression or T-wave inversion, or be normal	May show ST depression or T-wave inversion, or be normal	New ST elevation in at least 2 contiguous leads, or an equivalent pattern
Troponin	No rise and fall pattern	No rise and fall pattern above the 99th percentile	Rises and/or falls with at least one value above the 99th percentile	Rises and/or falls; the ECG identifies STEMI before results return
Usual urgency	Planned outpatient follow-up	Urgent assessment in hospital	Urgent assessment and treatment in hospital	Emergency; reperfusion as fast as possible
Main treatment	Risk reduction, anti-anginal drugs, revascularization if symptoms persist	Antithrombotic therapy and risk-based angiography (section 17.4)	Antithrombotic therapy and risk-based angiography (section 17.4)	Primary PCI, or fibrinolysis when PCI would be delayed

Presentation

Ischemic discomfort in ACS is often felt as pressure, squeezing, fullness, burning or heaviness in the chest. It may spread to the neck, jaw, shoulders, arms or back and may come with sweating, nausea, shortness of breath or light-headedness (Heart and Stroke Foundation of Canada, n.d.-d). Unlike stable angina, it often comes at rest or with little effort and is not reliably eased by rest.

Chest discomfort is the most common symptom in both women and men, but many people with MI have none. In a large United States registry, 42.0% of women and 30.7% of men with MI presented without chest pain, and the gap between the sexes narrowed with age (Canto et al., 2012). Women more often report breathlessness, fatigue or weakness with or without chest discomfort (Mehta et al., 2016), and they may feel pressure or pain in the lower chest, upper abdomen or upper back, dizziness, fainting or extreme fatigue (Heart and Stroke Foundation of Canada, n.d.-d). The ESC lists breathlessness, epigastric pain, and pain in either arm or in the neck or jaw as chest pain equivalents (Byrne et al., 2023). The chest pain history and presentations in older adults are covered in Chapter 16, section 16.2, and Chapter 8.

Physical findings may include anxiety, sweating, cool skin, pallor, a fast or slow heart rate, and high or low blood pressure. Colour changes are harder to see on darker skin. On very dark skin, pallor may look ash-grey and on brown skin yellow-brown, so the nurse

checks the conjunctivae and the lining of the mouth and compares with the patient's usual colour (Pusey-Reid et al., 2023). Cyanosis on darker skin may look grey or whitish around the mouth (Chapter 12, section 12.2). Findings of shock, such as confusion or low urine output, need immediate escalation (Chapter 6).

Immediate Actions

The nurse treats new chest discomfort, or a symptom that could stand in for it, as ACS until proven otherwise, and works through the Clinical Judgment Measurement Model (Chapter 1, section 1.4) quickly. To **recognize cues**, the nurse notes the patient's description of the discomfort, its onset and any associated symptoms, along with vital signs, oxygen saturation (SpO2), heart rhythm, colour and level of consciousness. To **analyze cues and prioritize hypotheses**, the nurse puts ischemia first but also looks for other causes, such as bleeding, low SpO2 or a fast rhythm, that can cause a type 2 MI. To **generate solutions and take action**, the nurse:

- stays with the patient, stops all activity and helps the patient into a comfortable position, then calls for help as agency policy directs, such as the prescriber or the rapid response team (Chapter 6);
- obtains a 12-lead ECG within 10 minutes of first medical contact and shows it to a physician or nurse practitioner (NP) at once (Byrne et al., 2023; Chapter 16, section 16.3);
- starts continuous cardiac monitoring, keeps the defibrillator close by (Chapter 16) and establishes intravenous access;
- sends blood for troponin and other tests, then repeats troponin at the times the pathway sets (Chapter 16);
- gives ASA, to be chewed and swallowed, under an order or medical directive, if the patient has no allergy or intolerance; for the public, Heart and Stroke advises one 325 mg tablet or two 81 mg tablets (Heart and Stroke Foundation of Canada, n.d.-d);
- gives oxygen only if SpO2 is low: a guideline panel recommended not starting oxygen in suspected MI when SpO2 on room air is above 92%, and suggested not starting it at 90% to 92% (Siemieniuk et al., 2018), and the nurse follows the ordered target range (Chapter 12);
- gives nitroglycerin as ordered unless the patient has hypotension, a suspected right ventricular infarction or recent PDE5 inhibitor use (see the Clinical Safety box);
- gives analgesia as ordered if discomfort continues (Chapter 5);
- explains each step calmly and supports and informs the family.

To **evaluate outcomes**, the nurse reassesses discomfort, vital signs, rhythm and SpO2 after each intervention and repeats the ECG, as ordered, if symptoms change or return.

Every nurse who notices these signs acts and escalates at once. A registered practical nurse (RPN), or a practical nurse (PN) elsewhere (licensed practical nurse [LPN] in many provinces), starts these first steps and consults the registered nurse (RN) as the patient's needs change. Actions such as giving ASA or nitroglycerin need an order or medical directive, and what each nurse may do depends on authority, competence and context, employer policy and the province or territory (Chapter 1, section 1.3).

CLINICAL SAFETY

Nitroglycerin Cautions

Before each dose of nitroglycerin, the nurse checks blood pressure and heart rate and holds the dose and reports when:

- **Blood pressure is low.** The Canadian monograph lists acute circulatory failure, including severe hypotension, as a contraindication (sanofi-aventis Canada, 2021). The order or directive sets the blood pressure limit.
- **Right ventricular infarction is suspected.** The monograph warns of serious reflex effects, including fatal dysrhythmias, mainly in acute inferior MI with right ventricular involvement (sanofi-aventis Canada, 2021). With an inferior STEMI, right-sided leads are recorded early, as ordered (Thygesen et al., 2018).
- **A PDE5 inhibitor has been taken.** Ask every patient, of every sex, in private and without judgment. Sildenafil, tadalafil and vardenafil are absolutely contraindicated with nitroglycerin (sanofi-aventis Canada, 2021).
- **Certain structural heart conditions are known.** The monograph's contraindications include heart failure caused by hypertrophic obstructive cardiomyopathy, constrictive pericarditis, or aortic or mitral stenosis (sanofi-aventis Canada, 2021).

The patient sits or lies down for each dose, and the nurse watches for headache, dizziness and falling blood pressure.

STEMI and Reperfusion

A STEMI is a race against time. When the ECG shows ST elevation that meets the criteria in the Going Deeper box, the nurse makes sure a physician or NP sees it immediately and activates the agency's STEMI process. **Reperfusion**, restoring blood flow through the blocked artery, is the cornerstone of STEMI care (Wong et al., 2019).

Primary PCI is emergency coronary angiography with balloon and stent opening of the blocked artery, without fibrinolytic drugs given first. It is preferred when it can be done quickly. **Fibrinolysis** is an intravenous drug that dissolves the fibrin in a clot. Canadian guidance from Emergency Care BC advises considering fibrinolysis when primary PCI cannot be done within 120 minutes of first medical contact, with a target of 30 minutes or less from first medical contact to the drug. After successful fibrinolysis, the patient should have angiography within 24 hours, and a patient whose ST elevation does not settle by more than 50%, or who has ongoing pain or instability, needs urgent rescue PCI (Emergency Care BC, 2020). Emergency Care BC prefers a fibrin-specific drug such as tenecteplase. The ESC uses the same 120-minute threshold for choosing fibrinolysis (Byrne et al., 2023). The 2019 CCS guideline could not be read for this edition, so these time targets are given as Emergency Care BC and the ESC state them. Nursing care during and after fibrinolysis is covered in section 17.4.

Canada's distances shape these choices. The CCS and the Canadian Association of Interventional Cardiology call for regional STEMI networks with set pathways for identification, transport and reperfusion, whether the patient is first seen in the field, at a hospital without PCI or at a PCI centre (Wong et al., 2019). In eastern Ontario, the regional paramedic program advises that paramedics aim to record a 12-lead ECG within 10 minutes and that a STEMI-positive ECG is required before they take a patient directly to a PCI centre, under provincial standards and local agreements (Regional Paramedic Program for Eastern Ontario, 2023). In rural and remote hospitals, the nurse may care for a patient receiving fibrinolysis while transfer to a PCI centre is arranged.

GOING DEEPER

STEMI on the 12-Lead ECG

Required for RN students; optional for PN students.

Chapter 16 introduced contiguous leads and ST changes. The Fourth Universal Definition sets these STEMI criteria (Thygesen et al., 2018):

- **ST elevation:** new elevation at the J point in at least 2 contiguous leads, of 1 mm or more in all leads other than V2 and V3. In V2 and V3, the cut-off is 2 mm or more in men aged 40 and older, 2.5 mm or more in men under 40, and 1.5 mm or more in women of any age.
- **Lead groups:** as in Chapter 16, the contiguous groups are I and aVL; V1 to V6; and II, III and aVF, the inferior leads (Figures 17.3 and 17.4). ST elevation in the anterior precordial leads is linked to significant occlusion of the left anterior descending artery.
- **Reciprocal changes:** ST depression in leads facing the opposite wall. Convex ST elevation with reciprocal depression usually means acute occlusion, and reciprocal changes help tell STEMI apart from pericarditis or early repolarization.
- **Right ventricular infarction:** with an inferior STEMI, right-sided leads V3R and V4R are recorded early. ST elevation of 0.5 mm or more (1 mm or more in men under 30) supports the diagnosis, but normal right-sided leads do not rule it out. Lead aVR or V1 may also show ST elevation.
- **Posterior (inferobasal) ischemia:** ST depression in V1 to V3, especially with an upright terminal T wave, may reflect blockage of the circumflex artery. Posterior leads V7 to V9 (left posterior axillary line, midscapular line and paraspinal border) are then recorded; elevation of 0.5 mm or more is significant (1 mm or more in men under 40).
- **Left bundle branch block (LBBB):** ST elevation of 1 mm or more in the same direction as the QRS in any lead may signal acute ischemia.
- **Lead aVR:** ST elevation of more than 1 mm can be seen with anterior or inferior STEMI and is linked to higher 30-day mortality.

The nurse who sees possible STEMI changes escalates immediately; the physician or NP confirms the diagnosis.



Figure 17.3 A 12-lead ECG showing an acute extensive anterior STEMI: ST elevation across the chest leads and in I and aVL, with reciprocal ST depression in the inferior leads. (credit: "Extensive Anterior STEMI (acute)" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)



Figure 17.4 A 12-lead ECG showing an inferior STEMI: ST elevation in leads II, III and aVF, with reciprocal ST depression in aVL. (credit: "Inferior STEMI" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

17.4 Early Treatment and Complications of ACS

Medications in the First Days

Once the first actions described in section 17.3 are under way, treatment has four aims: keep the culprit artery open, stop new clots from forming, protect the heart muscle and lower the chance of another event. The nurse gives these drugs as ordered, watches for their adverse effects and starts teaching early, because many of them continue for months or for life (Medications box).

Dual antiplatelet therapy (DAPT) is the combination of ASA with a **P2Y12 inhibitor**, a drug that blocks the P2Y12 receptor on platelets so they are less able to stick together and form a clot. Three P2Y12 inhibitors are marketed in Canada: clopidogrel, ticagrelor and prasugrel. The CCS and Canadian Association of Interventional Cardiology (CAIC) updated their antiplatelet guidance in 2023, and it puts bleeding risk at the centre of the decision. For a patient at high bleeding risk after PCI, it supports DAPT for only 1 to 3 months, followed by a single antiplatelet drug, when no clotting or bleeding event occurs in the first month. It also allows a switch from ticagrelor or prasugrel to clopidogrel in selected patients with ACS treated with PCI who have had at least

a month of the stronger drug without a new clotting event (Bainey et al., 2024). Where Canadian guidance does not address a point, Canadian teams follow international guidelines, and this chapter uses the 2025 American College of Cardiology/American Heart Association (ACC/AHA) ACS guideline for those points. That guideline recommends adding an oral P2Y12 inhibitor to ASA for patients with ACS. For patients treated with PCI, it prefers ticagrelor or prasugrel over clopidogrel. It names at least 12 months of DAPT as the default for patients who are not at high risk of bleeding (Rao et al., 2025). The cardiology team sets the plan and its length. The nurse makes sure the patient knows the plan and leaves with it in writing.

During the acute phase, many patients also receive a parenteral anticoagulant such as heparin, enoxaparin or fondaparinux. The team chooses the drug based on the treatment plan, kidney function and bleeding risk. Chapter 19 covers anticoagulants in full.

Other drugs protect the heart over the long term. The 2025 guideline recommends a high-intensity statin for every patient with ACS (Rao et al., 2025); section 17.1 explains statins and lipid targets. Many patients also start a beta-blocker and an ACE inhibitor or an angiotensin II receptor blocker (ARB). The choice depends on heart function, blood pressure, heart rate, kidney function and other conditions. For patients at risk of bleeding from the stomach or bowel, the guideline recommends a proton pump inhibitor (Rao et al., 2025).

Every one of these antithrombotic drugs raises the risk of bleeding, and the risk adds up when they are combined and when an artery has just been punctured. Prasugrel is contraindicated after a stroke or transient ischemic attack (TIA). Its Canadian monograph also advises against it for people aged 75 or older or weighing less than 60 kg (JAMP Pharma Corporation, 2020). Ticagrelor causes shortness of breath in some patients. This is usually mild to moderate and often settles while the patient keeps taking the drug (AstraZeneca Canada, 2026). Patients are taught to report it and not to stop the drug on their own.

MEDICATIONS

Antiplatelets, Anticoagulants and Other ACS Drugs

All drugs named here are marketed in Canada. Doses are not listed.

- **ASA plus a P2Y12 inhibitor (clopidogrel, ticagrelor, prasugrel):** watch for bleeding from gums, nose, urine, stool and puncture sites. Ticagrelor can cause shortness of breath; it is usually mild and often settles, but the patient reports it. Ticagrelor is used with caution in patients at higher risk of slow heart rhythms. Its monograph warns that stopping it early raises the risk of cardiac events (AstraZeneca Canada, 2026).
- **Prasugrel:** contraindicated after a stroke or TIA and with active bleeding. It is not recommended for people aged 75 or older or weighing less than 60 kg (JAMP Pharma Corporation, 2020).
- **Heparin, enoxaparin, fondaparinux:** watch for bleeding and check kidney function and blood counts as ordered (Chapter 19).
- **High-intensity statin (for example, atorvastatin):** ask about new muscle pain or weakness and report it (section 17.1).
- **Beta-blocker (for example, metoprolol):** check apical pulse and blood pressure before giving it; report a slow heart rate, dizziness or new breathlessness.
- **ACE inhibitor (for example, ramipril) or ARB:** watch blood pressure, potassium and creatinine; a dry cough is a common reason patients stop an ACE inhibitor, so they are asked to report it rather than stop.
- **Teaching:** no antiplatelet drug is stopped without the cardiology team's advice.

Monitoring and Nursing Care

In the first days, the patient has continuous cardiac monitoring because dangerous rhythms are most likely early (Chapter 16, sections 16.4 and 16.5). Any new or returning chest pain is treated as possible new ischemia. The nurse stops the activity, assesses the pain, records a 12-lead ECG under the order or directive in place and reports at once (section 17.3). A patient who has had a stent may be having stent thrombosis (section 17.5), described in section 17.5.

The nurse trends vital signs, oxygen saturation, urine output and mental status. Oxygen is given only when saturation falls below the threshold in section 17.3 (Chapter 12). The nurse listens for crackles and looks for new breathlessness, rising heart rate, falling blood pressure, cool or clammy skin and confusion. These are cues of heart failure or cardiogenic shock (Chapter 6, section on shock; Chapter 18). Early warning scores and rapid response are described in Chapter 6.

Activity increases step by step as ordered once the patient is stable. The nurse watches the patient's response and stops the activity if chest pain, marked breathlessness, dizziness or a sharp change in heart rate occurs. Fear is common after a heart attack. The nurse

explains what each monitor and test is for, protects sleep by grouping night-time care, and includes the family in teaching when the patient agrees. An interpreter is used whenever needed (Chapter 2).

Bleeding precautions apply to every patient on these drugs. The nurse checks puncture sites, intravenous sites, urine and stool, and trends hemoglobin and platelets as ordered (Chapter 20). The nurse also prevents falls (Chapter 8) and offers a soft toothbrush and an electric razor. Patients are taught to report black or bloody stools, blood in the urine, vomit that looks like coffee grounds, a severe headache or bleeding that will not stop.

CLINICAL JUDGMENT

Fatigue and Nausea in a Woman Aged 68

Names and details are fictional; this is a composite story.

Margaret Chen, 68, is on a surgical unit 2 days after a hip replacement. She has type 2 diabetes and hypertension. At 1400 she tells the RPN she feels "washed out" and queasy and does not want to walk. She denies chest pain.

- **Recognize cues:** new fatigue and nausea; she looks pale and is sweating; heart rate 108 per minute (was 84), blood pressure 104/62 mm Hg (was 138/76), respiratory rate 22 per minute, oxygen saturation 93% on room air. She has diabetes and is an older woman, so her ACS symptoms may not be typical (Chapter 16, section 16.2).
- **Analyze cues:** possible causes include ACS, bleeding, pulmonary embolism (Chapter 15), infection, hypoglycemia and drug effects. Surgery, anemia and pain all strain the heart.
- **Prioritize hypotheses:** ACS is the most time-critical, along with bleeding and pulmonary embolism.
- **Generate solutions:** stay with her; record a 12-lead ECG within 10 minutes under the directive in place (section 17.3); check capillary glucose; call the RN and the rapid response team (Chapter 6); check the wound and drain.
- **Take action:** the ECG shows new ST depression. The team assesses her. ASA is weighed against her bleeding risk after surgery, and nitroglycerin against her low blood pressure. Oxygen is not started at a saturation of 93% (section 17.3; Chapter 12). Troponin is drawn.
- **Evaluate outcomes:** the nurse repeats vital signs, asks about her symptoms, and follows the repeat ECG and the troponin trend. Her family is told what is happening. She is transferred for cardiology care, and the nurse gives a full handover.

Complications

Dysrhythmias are the most immediate threat. Ventricular fibrillation can cause sudden death, and ischemia can damage the conduction system and cause atrioventricular (AV) block (Chapter 16, sections 16.5 and 16.7). Atrial fibrillation (AF) may also appear and brings its own stroke risk (Chapter 16, section 16.6).

Heart failure and **cardiogenic shock** develop when a large area of muscle stops pumping well. The cues listed above under Monitoring and Nursing Care call for immediate escalation (Chapter 6; Chapter 18).

Mechanical complications are tears in heart structures weakened by the infarct. They include **papillary muscle rupture**, which causes sudden, severe leakage through the mitral valve; **ventricular septal rupture**, a hole in the wall between the ventricles; and **free wall rupture**, a tear in the outer wall that can cause sudden death. They are rare. A 2021 AHA scientific statement notes that they mainly threaten patients with large infarcts or delayed reperfusion, and that each carries a substantial risk of death. Care depends on a multidisciplinary team that recognizes the problem quickly, confirms it with imaging, supports the circulation and decides on definitive treatment, often surgery, or on palliative care (Damluji et al., 2021). The nurse's role is to notice when a patient who was improving suddenly becomes breathless, hypotensive or collapses, and to escalate at once.

Inflammation of the pericardium (pericarditis) can follow MI and is covered in Chapter 18. New chest pain after MI is always assessed and reported, never assumed to be pericarditis.

Depression is common after ACS. An AHA scientific statement concluded that the weight of evidence supports treating depression after ACS as a risk factor for a poor prognosis. The outcomes linked to it included death from any cause, cardiac death, and composite outcomes that combine death with nonfatal events (Lichtman et al., 2014). The nurse asks about mood, sleep and hopelessness, uses the screening tool the unit uses and reports positive results (section 17.6).

LIFESPAN CONSIDERATIONS

Older Adults With ACS

- **Presentation:** older adults more often have ACS without classic chest pain. Fatigue, breathlessness, nausea, confusion or a fall may be the only signs (Chapter 16, section 16.2).
- **Bleeding:** age raises bleeding risk with antithrombotic drugs. Prasugrel is not recommended at age 75 or older (JAMP Pharma Corporation, 2020). Kidney function guides drug choices and contrast decisions (Chapter 16, section 16.3).
- **Frailty and polypharmacy:** frailty affects recovery and how much invasive treatment a person can tolerate. Adding several cardiac drugs to an existing list raises the risk of falls, low blood pressure and drug interactions (Chapter 8).
- **Delirium:** new confusion may be the first cue of ACS or of a complication. Delirium needs its own assessment (Chapter 8).
- **Shared decisions:** treatment choices, including whether to have angiography or PCI, should fit the person's goals, values and quality of life. The nurse makes sure the patient and family have the information to take part, and that any advance care plan is known (Chapter 10).

17.5 Care Around PCI and CABG

Before Catheterization or PCI

Percutaneous coronary intervention (PCI) opens a narrowed or blocked coronary artery through a catheter, usually with a balloon and a **stent**: a small mesh tube left in the artery to hold it open (Figure 17.5). The catheter enters through an artery in the wrist (**radial access**) or the groin (**femoral access**). Heart and Stroke Foundation of Canada (n.d.-a) explains to patients that the catheter is removed with a clamp and pressure.

Before the procedure, the nurse confirms that informed consent has been obtained by the physician performing it (Chapter 1, section 1.5). The nurse asks about allergies and any past reaction to contrast dye, and reviews kidney function. Canadian radiology guidance states that kidney injury after contrast is a concern mainly for people with an estimated glomerular filtration rate (eGFR) of 30 mL/min/1.73 m^2 or less, or with existing acute kidney injury. Under that guidance, metformin is held only for those patients (Macdonald et al., 2022; Chapter 16, section 16.3). Anticoagulants and diabetes drugs are held or adjusted only as ordered (Chapter 22). Fasting follows local policy. The nurse records baseline vital signs and checks pulses, colour, warmth and sensation in both arms and both legs, so later checks can be compared. The nurse also explains what to expect. Local anesthetic and mild to moderate sedation, with a warm room, reduce anxiety, discomfort and spasm of the radial artery (Mason et al., 2018). After a groin approach, the patient will need several hours of bed rest (Heart and Stroke Foundation of Canada, n.d.-a). Knowing this ahead of time eases fear and helps the patient keep still.



Figure 17.5 An expanded coronary stent holding a narrowed artery open (enlarged view). (credit: “Cobalt Chromium Coronary Stent in Heart” by ETTon/Wikimedia Commons, CC BY-SA 4.0)

After PCI

After PCI, the nurse checks the access site and the limb beyond it often, as the unit protocol directs (Table 17.3). Limb checks compare the two sides for pulses, warmth, capillary refill, movement and sensation. Colour changes are easy to miss on darker skin.

Pallor may show as an ashen or greyish tone, so the nurse also looks at nail beds and palms and relies on warmth, capillary refill and the patient's report of numbness or tingling.

After radial access, a compression band holds pressure on the wrist. Air is released in steps on a schedule set by protocol. An AHA scientific statement names **radial artery occlusion** as a common complication. It calls keeping some blood flowing through the artery during compression (patent hemostasis) critical to prevention, and lists checks of distal pulses, skin temperature and colour as nursing best practices (Mason et al., 2018). A **hematoma** (a collection of blood under the skin) at the wrist or a swelling, tight and painful forearm is reported at once.

After femoral access, the patient lies flat or nearly flat with the leg straight for the time set by protocol. Heart and Stroke Foundation of Canada (n.d.-a) tells patients to expect 4 to 6 hours of bed rest. **Retroperitoneal bleeding**, bleeding into the space behind the abdominal organs, may show no blood at the groin at all. The cues are back, flank or lower abdominal pain, a rising heart rate, falling blood pressure, restlessness and a falling hemoglobin. These need urgent escalation.

Contrast-associated acute kidney injury is a decline in kidney function after contrast dye. The nurse follows the ordered fluid plan, records urine output and checks creatinine as ordered, especially in patients with low eGFR (Chapter 27).

New chest pain after PCI may mean **stent thrombosis**: a clot forming inside the stent and suddenly blocking the artery. It presents like a new MI. The nurse records a 12-lead ECG at once and calls for urgent help (section 17.3).

Why radial first? The RIVAL trial randomly assigned 7,021 patients with ACS at 158 hospitals in 32 countries. The combined rate of death, MI, stroke or major bleeding not related to CABG at 30 days was similar: 3.7% with radial and 4.0% with femoral access. Large hematomas and pseudoaneurysms needing closure were less common with radial access (Jolly et al., 2011). The MATRIX trial randomized 8,404 patients with ACS. Net adverse clinical events at 30 days were 9.8% with radial and 11.7% with femoral access. The difference came mainly from less major bleeding (1.6% vs 2.3%) and lower death from any cause (1.6% vs 2.2%) (Valgimigli et al., 2015). The 2025 guideline prefers the radial approach for PCI in ACS to reduce bleeding (Rao et al., 2025).

Before discharge, the nurse teaches why DAPT matters. Stopping a P2Y12 inhibitor early leaves the new stent unprotected. The ticagrelor monograph states that patients who stop it are at higher risk of cardiac events (AstraZeneca Canada, 2026). The patient learns not to stop or skip a dose without speaking to the cardiology team, to tell every dentist and surgeon about the stent, and to refill before running out. The nurse also asks whether the patient can afford the drugs and connects them with help if needed (Chapter 2).

Table 17.3 Caring for the access site after catheterization: radial and femoral compared (Heart and Stroke Foundation of Canada, n.d.-a; Mason et al., 2018; Jolly et al., 2011; original wording)

Feature	Radial access	Femoral access
Closure and compression	Compression band on the wrist; air released in steps per protocol; aim is to stop bleeding while keeping some flow in the artery	Manual pressure, a closure device or a compression device per protocol
Positioning and mobility	Patient can usually sit up and walk sooner; the wrist is kept still and the arm is not used for lifting while the band is on	Bed rest with the leg straight for the time set by protocol (patients are told to expect 4 to 6 hours); head of bed raised only as allowed
What to check	Site; hand colour, warmth, capillary refill, movement and sensation; radial and ulnar pulses compared with the other side	Site; foot colour, warmth, capillary refill, movement and sensation; pedal pulses compared with the other side and with baseline
Bleeding cues	Oozing at the band; swelling, firmness or pain in the wrist or forearm	Bleeding or swelling at the groin; back, flank or lower abdominal pain, rising heart rate and falling blood pressure (possible retroperitoneal bleeding)
Other complications	Radial artery occlusion; radial artery spasm; forearm hematoma	Hematoma; pseudoaneurysm (a pulsing lump); limb ischemia
Teaching	Avoid heavy use of that hand and wrist for the time advised; report numbness, coldness or swelling	Avoid heavy lifting and straining for the time advised; report groin swelling, a pulsing lump or bleeding; apply pressure and call 9-1-1 for bleeding that will not stop

SCOPE IN PRACTICE

Directives, Access Sites and Nitroglycerin

Care around ACS and PCI uses the three ideas in the College of Nurses of Ontario's (CNO's) Scope of Practice standard: authority, competence and context (Chapter 1, section 1.3). Employer policy and the province or territory also matter.

- **Directives:** a medical directive is an order written by an authorized provider that applies to a group of patients when stated conditions are met (CNO, 2025b). Many hospitals use directives that let RNs and RPNs record a 12-lead ECG and give ASA and sublingual nitroglycerin for suspected ACS. The CNO Medication standard requires the nurse to accept only clear, complete and appropriate orders, and to act only within their own competence (CNO, 2025a). CNO's revised Scope of Practice and Medication standards take effect March 1, 2027 (CNO, 2026).
- **Access sites:** sheath removal, manual compression and compression band release are done by nurses whom the employer authorizes and who have the education and competence for them.
- **Infusions:** titrated cardiac infusions are usually managed by RNs in critical care or step-down settings, according to employer policy; this is RN-level depth.
- **Deterioration:** every nurse who notices bleeding, new chest pain or a cool, pulseless limb acts at once and escalates. The RPN consults the RN as the patient's needs change.

After CABG on the Ward

Coronary artery bypass grafting (CABG) is surgery that carries blood around blocked coronary arteries using grafts. The grafts are arteries, such as one from inside the chest wall or from the forearm, or veins taken from the leg. Most patients have the surgery through a sternotomy, an incision through the breastbone. They spend the first day or so in intensive care and then move to a cardiac surgery ward. The ward nurse receives a report on drains (Chapter 15), temporary pacing wires (Chapter 16, section 16.7), pain control (Chapter 5) and the activity plan. On arrival, the ward nurse completes a full assessment and compares it with the report: vital signs and rhythm, oxygen saturation, breath sounds, pain, incisions, drain and urine output, glucose and mental status. Transfers are a common point for lost information, so the nurse clarifies anything unclear, including which drugs were stopped, started or held.

Sternal precautions are limits on arm and upper-body use that protect the healing breastbone. Under traditional precautions, patients limit how they use their arms for as long as 12 weeks after sternotomy (Park et al., 2021). A newer approach, "Keep Your Move in the Tube," replaces fixed weight and time limits. Patients use their arms for everyday activities, moving mindfully and guided by pain, and keep their movements close to the body ("in the tube") (Gach et al., 2021; Park et al., 2021). In a Canadian quasi-experimental study of 100 patients per group, return to function was slower over time with traditional precautions, but the gap narrowed by 12 weeks. After adjustment, the two approaches did not differ (Park et al., 2021). In a before-and-after study of 1,104 patients at one large hospital, those taught the newer approach had about three times the odds of going home rather than to a rehabilitation or nursing facility. Sternal wound complications and 30-day readmissions did not differ significantly (Gach et al., 2021). The nurse teaches the approach the program uses and reinforces it every time the patient moves.

The nurse checks the sternal incision and the arm or leg donor site for redness, drainage, separation and swelling. The leg is raised when the patient sits, and the patient learns to report fever or a wound that opens or drains. Other postoperative priorities are covered elsewhere: pain (Chapter 5), chest drains (Chapter 15) and new AF after surgery (Chapter 16, section 16.6). Delirium (Chapter 8), glucose control, including in patients without known diabetes (Chapter 22), and early walking with deep breathing and coughing (Chapter 12) also need attention. Canadian guidance favours DAPT over a single antiplatelet drug after CABG, whether or not the surgery followed ACS (Bainey et al., 2024). Mood often dips after surgery. The nurse screens for depression as for any patient after ACS (section 17.4).

PRACTICE STORY

The Ache in His Back

Names and details are fictional; this is a composite story.

Nurse: Aisha Rahman, RPN. Years in practice: 4. Setting: cardiac step-down unit, regional hospital, Ontario.

Mr. Doucet was 72 and had come back from the catheterization lab at noon after PCI through his right groin. His radial arteries were small, so the femoral route had been used. At 1400 his groin dressing was dry, his foot was warm and his pedal pulses matched the baseline I had marked that morning. He was chatting about his grandson's hockey game.

At 1500 he said, "My back's killing me. Must be lying flat on this mattress." He wanted something for the pain and to sit up. It would have been easy to agree. Lying flat for hours is uncomfortable, and his groin still looked clean. But his heart rate had gone from 72 to 96 and his blood pressure from 134/80 to 108/68. He was restless, and his face looked greyer than an hour before.

I remembered that bleeding after a femoral puncture can track backward, where you can't see it. I kept him flat, checked the site and his foot again, and asked my RN colleague, Tom, to come. Tom agreed this could be retroperitoneal bleeding and called the interventional cardiologist while I repeated his vital signs. His blood pressure was now 96/60 mm Hg. I documented each set with the time.

The team ordered a stat hemoglobin and a computed tomography (CT) scan, and gave fluids. His hemoglobin had dropped from 138 to 104 g/L. The CT confirmed a retroperitoneal hematoma. He did not need surgery, but he did need a transfusion and a night in the coronary care unit.

Later, Mr. Doucet's daughter thanked me for "not just giving him a pill." I think about how ordinary his words sounded. The numbers told the story his back was starting to tell.

Reflect: What cues, together, made back pain after a femoral PCI a warning sign? Which parts of this patient's care were within the RPN's scope, and at what point was consulting the RN required?

17.6 Cardiac Rehabilitation and Living With Coronary Disease

Cardiac Rehabilitation

Cardiac rehabilitation is a structured program that combines exercise, education and counselling to help people recover after a heart attack, heart surgery or other heart conditions (Heart and Stroke Foundation of Canada, n.d.-b). It is a core part of **secondary prevention**: care that lowers the risk of another event in someone who already has coronary disease. Programs differ but usually include a medical assessment, supervised physical activity, education on nutrition and other risk factors, and psychosocial support for depression, anxiety and return to work (Table 17.4). The team may include physicians, nurses, exercise physiologists, dietitians, physiotherapists, occupational therapists, psychologists and social workers (Heart and Stroke Foundation of Canada, n.d.-b).

The benefits are well studied. A 2021 Cochrane review pooled 85 trials with 23,430 people with coronary heart disease. Over 6 to 12 months, exercise-based rehabilitation reduced MI (risk ratio 0.72) and hospital admission for any cause (risk ratio 0.58). It probably caused a slight reduction in death from any cause and improved health-related quality of life. Over longer follow-up, it may also lower cardiovascular death (Dibben et al., 2021).

Referral is where many patients are lost. A Canadian review names lack of referral and lack of a physician's recommendation among the main barriers. It also notes a national policy position calling for systematic referral of eligible inpatients (Grace et al., 2014). When referral is automatic, part of the standard discharge order set, it no longer depends on someone remembering. The 2025 guideline recommends referral to cardiac rehabilitation and includes home-based programs as an option (Rao et al., 2025). Home-based and virtual programs can reach people who cannot travel to a hospital program. For people with no program nearby, Heart and Stroke Foundation of Canada (n.d.-b) offers a self-guided recovery plan to use with their provider's approval.

Table 17.4 Components of cardiac rehabilitation (Heart and Stroke Foundation of Canada, n.d.-b; Grace et al., 2014; original wording)

Component	What it includes	The nurse's role
Assessment	Review of physical abilities, limits, symptoms and risk factors at entry	Share the discharge summary, drug list and procedure details; make sure the referral is sent before discharge
Exercise training	Supervised aerobic and strength activity, progressed over weeks	Teach warning signs to stop exercise; explain why activity is safe and helps recovery
Risk factor management	Blood pressure, lipids, glucose, weight, smoking and vaping, alcohol	Reinforce targets (section 17.1); refer for smoking cessation support (Chapter 14)
Education	Heart disease, drugs, nutrition, symptoms and when to call 9-1-1	Start teaching in hospital; use plain language and an interpreter when needed; include family
Psychosocial support	Screening and help for depression, anxiety and stress; return to work and daily roles	Screen for low mood; listen to fears; link to counselling and peer support

Who Gets Left Out

In Canada, rehabilitation works when people attend, but many do not. A Canadian review reported that only 34% of eligible patients take part. It added that ways of widening access for groups that are under-represented, for example women and members of ethnic minority groups, were not yet in wide use (Grace et al., 2014). Heart and Stroke Foundation of Canada (n.d.-b) reports that women are only half as likely as men to attend and follow a program, in part because physicians refer them less often and because work or family demands lead some to stop. In a study of cardiac inpatients from 11 Ontario hospitals, patients of lower socioeconomic status were less likely to be referred, to enrol and to participate. Rural patients, defined as living more than a 30-minute drive from hospital, attended fewer sessions. Both groups reported more barriers, especially distance, cost and transportation (Shanmugasegaram et al., 2013).

Many of these barriers are structural rather than personal: where programs are located, when sessions run, transportation, lost wages, language and past experiences of racism in health care (Chapter 2). First Nations, Inuit and Métis patients in rural, remote or northern communities may be far from any program. The nurse can help close these gaps:

- Make sure every eligible patient leaves with a referral, not only those who ask.
- Explain in plain language what rehabilitation is and why it helps, and that women and older adults benefit too.
- Ask about transportation, cost, work, caregiving and language, and involve the social worker or discharge planner.
- Offer home-based or virtual options where they exist, and connect patients with community, Indigenous health or culturally specific services when the patient wants this.

Living Well After ACS

Living well starts with the drugs. The nurse reviews each drug's purpose, explains that DAPT and statins work quietly even when the patient feels well, and helps set up reminders and refills (section 17.5). Risk factor control continues for life: lipids and physical activity (section 17.1), smoking and vaping cessation (Chapter 14), blood pressure (Chapter 19) and diabetes (Chapter 22).

Mood needs regular attention because depression after ACS is linked to worse outcomes (Lichtman et al., 2014). The nurse asks about mood at each contact and makes sure the follow-up plan includes screening.

Many patients want to ask about sex but wait to be asked. An AHA scientific statement considers it reasonable to resume sex 1 week or more after an uncomplicated MI, provided mild to moderate exertion causes no heart symptoms. Sex may resume several days after PCI if the access site has no complications, and 6 to 8 weeks after standard CABG once the sternotomy has healed. The statement adds that anxiety and depression about sexual activity should be assessed, and that counselling the patient and partner helps (Levine et al., 2012). Cardiac rehabilitation and regular exercise can also lower the risk of complications during sexual activity (Levine et al., 2012). Drugs for erectile dysfunction must not be combined with nitrates (section 17.2).

Return to work depends on the person's recovery, the type of work and the treatment received, and cardiac rehabilitation programs can help plan it (Heart and Stroke Foundation of Canada, n.d.-b). The nurse encourages the patient to talk with the employer about a gradual return or lighter duties where possible, and to include family in planning. Driving is also individual. After ACS, PCI or CABG, the CCS 2023 fitness-to-drive guideline restricts driving for a period set by the guideline; the team gives the exact time. Its recommendations are stricter for commercial drivers, and in some provinces, clinicians are required to report a driver they judge to be unsafe (Guerra et al., 2024). The nurse tells patients not to drive until their cardiologist confirms it is safe.

Every patient leaves knowing what to do if symptoms return, including how to use nitroglycerin and when to call 9-1-1 (section 17.2, Patient Education box).

Chapter 17 Summary

Introduction

- In 2023 to 2024, 8.2% of Canadian adults had diagnosed ischemic heart disease; diseases of the heart ranked second among causes of death in 2024.
- Any nurse may be the first to recognize an acute coronary syndrome, so every nurse needs to know its signs and first actions.

17.1 Atherosclerosis and Cardiovascular Risk

- Atherosclerosis begins with endothelial dysfunction and LDL retention, leading to foam cells, a fibrous cap and a necrotic core; thin-capped, inflamed plaques can rupture and cause thrombosis.
- Smoking, hypertension, dyslipidemia, diabetes, abdominal obesity, inactivity, diet and stress are modifiable; pregnancy complications and menopause add risk for women.
- CCS recommends nonfasting lipid screening from age 40, Lp(a) once in a lifetime, and statins for statin-indicated conditions.
- In ASCVD on the highest tolerated statin, CCS suggests intensifying therapy when LDL-C is 1.8 mmol/L or more, non-HDL-C 2.4 mmol/L or more, or ApoB 0.7 g/L or more.
- Patients report unexplained muscle pain, tenderness or weakness on a statin promptly.

17.2 Stable Angina and Chronic Coronary Disease

- Stable angina is predictable ischemic discomfort from a fixed narrowing, brought on by exertion or stress and eased by rest or nitroglycerin; breathlessness and fatigue can be anginal equivalents.
- Treatment combines risk reduction, antiplatelet therapy and a statin with beta-blockers or calcium channel blockers (NICE and ESC guidance); revascularization is considered for persistent symptoms or high-risk anatomy.
- Patients sit, take one nitroglycerin dose, and call 9-1-1 if the pain has not eased within 5 minutes; nitroglycerin is never combined with PDE5 inhibitors.

17.3 Recognizing Acute Coronary Syndromes

- ACS includes unstable angina, NSTEMI and STEMI; MI requires a troponin rise and/or fall with at least one value above the 99th percentile plus evidence of ischemia.
- Type 1 MI comes from plaque disruption and thrombus; type 2 MI from a supply–demand mismatch.
- Many people, especially women, have MI without chest pain.
- First actions: stay, call for help, 12-lead ECG within 10 minutes, monitoring, IV access, troponin, chewed ASA, oxygen only for low SpO2, nitroglycerin unless contraindicated.
- STEMI needs immediate reperfusion by primary PCI, or fibrinolysis when PCI cannot happen within 120 minutes of first medical contact.

17.4 Early Treatment and Complications of ACS

- DAPT combines ASA with a P2Y12 inhibitor (clopidogrel, ticagrelor or prasugrel). The 2025 ACC/AHA guideline names at least 12 months as the default, and Canadian guidance shortens it for people at high bleeding risk.
- Parenteral anticoagulants, high-intensity statins, beta-blockers, ACE inhibitors or ARBs and, when bleeding risk is high, a proton pump inhibitor complete early treatment.
- Bleeding is the main hazard. Prasugrel is contraindicated after stroke or TIA, and ticagrelor can cause mild shortness of breath.
- The nurse monitors rhythm, chest pain, perfusion and bleeding, and escalates any cue of heart failure or shock.
- Complications include dysrhythmias, heart failure, cardiogenic shock, rare but deadly mechanical ruptures and depression.

17.5 Care Around PCI and CABG

- Before PCI, the nurse confirms consent, allergies, kidney function, drug holds as ordered and baseline limb checks.
- After PCI, the nurse checks the access site and limb often and watches for hematoma, radial artery occlusion and hidden retroperitoneal bleeding.
- New chest pain after PCI may be stent thrombosis and needs an immediate ECG and urgent help.
- Radial access lowers bleeding and vascular complications (RIVAL, MATRIX), and DAPT must never be stopped early.
- After CABG, care covers sternal protection, incisions, pain, drains, AF, delirium, glucose, mobility and mood.

17.6 Cardiac Rehabilitation and Living With Coronary Disease

- Cardiac rehabilitation combines assessment, exercise, risk factor management, education and psychosocial support, and reduces MI and hospital admission.
- Only about one in three eligible Canadians take part. Women, people of lower socioeconomic status and rural residents face extra barriers.
- Automatic referral before discharge, plus home-based or virtual options, helps close these gaps.
- Living well includes drug adherence, risk factor control, depression screening and frank talk about sex, work and driving.

Key Terms (37)

acute coronary syndrome (ACS): a sudden fall in blood flow to the heart muscle, usually from plaque rupture or erosion with thrombus; includes unstable angina, NSTEMI and STEMI.

anginal equivalent: a symptom other than chest pain, such as breathlessness or unusual fatigue on exertion, that reflects myocardial ischemia.

apolipoprotein B (ApoB): the protein on each atherogenic lipoprotein particle; its level, in g/L, reflects the number of particles that can enter the artery wall.

atherosclerosis: a chronic inflammatory disease of the artery wall in which lipids, immune cells and fibrous tissue build up beneath the lining to form plaque.

cardiac rehabilitation: A structured program of assessment, exercise, education and psychosocial support after a heart event or heart surgery.

contrast-associated acute kidney injury: A decline in kidney function after contrast dye, a concern mainly when eGFR is 30 mL/min/1.73 m² or less or acute kidney injury is already present.

coronary artery bypass grafting (CABG): Surgery that carries blood around blocked coronary arteries using arterial or venous grafts.

dual antiplatelet therapy (DAPT): Treatment with ASA plus a P2Y12 inhibitor to prevent clots after ACS or stent placement.

femoral access: Entry to the arterial system through the femoral artery in the groin for catheterization or PCI.

fibrinolysis: reperfusion with an intravenous drug that dissolves the fibrin in a coronary clot, used when primary PCI would be delayed.

hematoma: A collection of blood under the skin or in tissue, seen as a firm, tender swelling.

LDL cholesterol (LDL-C): cholesterol carried in low-density lipoprotein particles, reported in mmol/L; the main target of lipid-lowering treatment.

lipoprotein(a) [Lp(a)]: an inherited lipoprotein particle that adds cardiovascular risk; measured once in a lifetime.

mechanical complications of MI: Rare tears in heart structures weakened by infarction, including papillary muscle rupture, ventricular septal rupture and free wall rupture.

myocardial infarction (MI): death of heart muscle cells from ischemia, shown by a rise and/or fall in cardiac troponin with at least one value above the 99th percentile plus clinical evidence of ischemia.

non-HDL cholesterol (non-HDL-C): total cholesterol minus HDL cholesterol; the cholesterol in all atherogenic particles.

NSTEMI (non-ST-elevation myocardial infarction): an MI confirmed by troponin without persistent ST elevation on the ECG.

P2Y12 inhibitor: A drug that blocks the P2Y12 receptor on platelets so they are less able to clump; clopidogrel, ticagrelor and prasugrel are examples.

papillary muscle rupture: A tear in a muscle that anchors the mitral valve, causing sudden severe mitral leakage after MI.

percutaneous coronary intervention (PCI): A catheter procedure that opens a narrowed or blocked coronary artery, usually with a balloon and a stent.

plaque rupture: a tear in the fibrous cap of a plaque that exposes its core to blood and triggers thrombus formation.

primary PCI: emergency coronary angiography with balloon and stent opening of a blocked artery, without fibrinolysis first.

radial access: Entry to the arterial system through the radial artery at the wrist for catheterization or PCI.

radial artery occlusion: Blockage of the radial artery after radial access, a common complication that patent hemostasis helps prevent.

reciprocal changes: ST depression in leads facing the wall opposite an area of ST elevation, supporting acute coronary occlusion.

reperfusion: restoring blood flow through a blocked coronary artery by primary PCI or fibrinolysis.

retroperitoneal bleeding: Bleeding into the space behind the abdominal organs, a hidden complication of femoral access shown by back or flank pain, rising heart rate and falling blood pressure.

right ventricular infarction: MI involving the right ventricle, often with inferior STEMI; nitroglycerin is used with great caution or avoided.

secondary prevention: Care that lowers the risk of another event in a person who already has coronary disease.

stable angina: predictable chest discomfort brought on by exertion or emotional stress and eased by rest or nitroglycerin, caused by a fixed coronary narrowing.

statin: a lipid-lowering drug that is the first-line treatment for people with ASCVD or another statin-indicated condition.

STEMI (ST-elevation myocardial infarction): an MI with new ST elevation in at least two contiguous leads, usually from acute occlusion of a coronary artery.

stent: A small mesh tube left in a coronary artery to hold it open after PCI.

stent thrombosis: A clot that forms inside a stent and suddenly blocks the artery; it presents like a new MI.

sternal precautions: Limits on arm and upper-body movement that protect the breastbone while it heals after sternotomy.

type 2 myocardial infarction: MI caused by an imbalance between the heart's oxygen supply and demand, such as severe anemia or hypotension, without acute plaque disruption.

unstable angina: myocardial ischemia at rest or on minimal exertion without heart muscle cell death.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mr. Daniel Okafor (Questions 1–4): Mr. Daniel Okafor, 64, is on a medical unit for cellulitis of the left leg. He has hypertension and type 2 diabetes. At 0215 h he calls the nurse, pale and sweating, and says his chest feels "heavy, like someone is sitting on it." Pulse 104 beats/min, blood pressure 142/86 mm Hg, SpO2 95% on room air.

1. [CORE] What is the nurse's first action?

a. Go to the medication room to get nitroglycerin under the medical directive

b. Stay with Mr. Okafor, have him stop all activity, and call for help

c. Document the episode and reassess in 30 minutes

d. Apply oxygen by nasal cannula at 4 L/min

Answer: b — New chest heaviness with pallor and sweating is treated as ACS; the nurse stays with the patient, stops activity and calls for help so that other actions can happen at once (b) (section 17.3). Leaving to get nitroglycerin (a) leaves an unstable patient alone; it is given only after a blood pressure check and with help on the way. Waiting 30 minutes (c) delays ECG, ASA and possible reperfusion. Oxygen (d) is not indicated with SpO2 95% on room air; a guideline panel recommends not starting oxygen in suspected MI when SpO2 is above 92% (section 17.3; Chapter 12).

2. [CORE] The rapid response team is on its way. Within what time should Mr. Okafor's 12-lead ECG be recorded and shown to a physician or nurse practitioner?

a. Within 60 minutes of the first troponin result

b. Within 30 minutes, after the first troponin is drawn

c. Within 20 minutes of his report of chest discomfort

d. Within 10 minutes of first medical contact

Answer: d — A 12-lead ECG within 10 minutes of first medical contact identifies STEMI, which needs immediate reperfusion (d) (section 17.3; Chapter 16). The ECG does not wait for troponin (a, b); STEMI is identified from the ECG before results return. Twenty minutes (c) is longer than the recommended target.

3. [CORE] The ECG shows no ST elevation. The physician orders sublingual nitroglycerin. Mr. Okafor quietly mentions he took tadalafil the previous evening. What should the nurse do?

a. Hold the nitroglycerin and report the tadalafil use to the physician at once

b. Give the nitroglycerin with the patient lying flat

c. Give half the usual nitroglycerin dose and recheck blood pressure in 5 minutes

d. Give the nitroglycerin, because his blood pressure is 142/86 mm Hg

Answer: a — Nitroglycerin is contraindicated with PDE5 inhibitors such as tadalafil because the combination can cause a dangerous fall in blood pressure; the Canadian tadalafil monograph allows a nitrate only in a life-threatening situation, at least 48 hours after the last dose and under close medical supervision (a) (section 17.2 and Clinical Safety box). Positioning (b) does not remove the risk. A nurse does not change an ordered dose (c), and a reduced dose is still contraindicated. A normal blood pressure now (d) does not protect against the interaction.

4. [CORE] A repeat ECG 15 minutes later shows new ST elevation in leads II, III and aVF. The registered practical nurse (RPN) caring for Mr. Okafor sees the printout first. What is the RPN's best action?

a. Wait for the next troponin result to confirm the change before reporting

b. Mount the ECG in the chart so the cardiology team can review it on morning rounds

c. Report the ECG to the RN and the responding team immediately

d. Give a second dose of ASA, then reassess

Answer: c — New ST elevation in contiguous leads suggests STEMI; every nurse who notices it escalates at once, and the RPN consults the RN as the patient's needs change, so reperfusion can begin (c) (section 17.3; Chapter 1, section 1.3). Waiting for troponin (a) or the morning team (b) wastes heart muscle; STEMI is identified from the ECG. A second ASA dose (d) is not ordered and does not replace escalation.

5. [CORE] Which risk factors for coronary artery disease can be modified? Select all that apply.

a. Smoking

b. Older age

c. Hypertension

d. Abdominal obesity

e. Familial hypercholesterolemia

f. Physical inactivity

Answer: a, c, d, f — Smoking (a), hypertension (c), abdominal obesity (d) and physical inactivity (f) are among the potentially modifiable factors that together accounted for about 90% of attributable heart attack risk in INTERHEART (section 17.1). Older age (b) cannot be changed. Familial hypercholesterolemia (e) is an inherited disorder; its LDL level can be treated, but the condition itself is not modifiable.

6. [CORE] A patient who had a myocardial infarction asks what "LDL-C 2.6" on his report means. He takes the highest statin dose he tolerates. Which response by the nurse is accurate?

a. "It is your total cholesterol, measured in milligrams per decilitre, and a value of 2.6 is well within the healthy range."

b. "It is your protective HDL cholesterol, measured in grams per litre, so a higher number like yours is better for your heart."

c. "It is cholesterol carried in LDL particles, in mmol/L; with heart disease, extra treatment is suggested at 1.8 or more."

d. "It measures lipoprotein(a), which is checked once in a lifetime."

Answer: c — LDL-C is reported in mmol/L in Canada; in a person with ASCVD on the highest tolerated statin dose, CCS suggests intensifying therapy when LDL-C is 1.8 mmol/L or more (c) (section 17.1, Table 17.1). It is not total cholesterol, and Canadian labs do not use mg/dL for LDL-C (a). HDL-C is the protective lipoprotein, and g/L is used for ApoB, not LDL-C (b). Lp(a) is a separate test (d).

7. [CORE] A patient taking atorvastatin tells the nurse she has new, unexplained aching and weakness in both thighs and feels feverish. What should the nurse do?

a. Report the symptoms to the prescriber promptly

b. Advise her to stop the statin permanently

c. Reassure her that statins do not affect muscles

d. Suggest she increase her exercise to stretch the muscles

Answer: a — The Canadian monograph tells patients to report unexplained muscle pain, tenderness or weakness promptly, especially with fever or malaise, because it can signal myopathy or, rarely, rhabdomyolysis (a) (section 17.1). Stopping permanently (b) is a prescriber decision, and a lower or different statin dose often works. Statins can affect muscle (c). More exercise (d) delays assessment and excessive exercise is itself a risk factor for myopathy.

8. [CORE] Which description best distinguishes unstable angina from stable angina?

a. Unstable angina is always relieved by one dose of nitroglycerin.

b. Unstable angina causes troponin to rise and fall with at least one value above the 99th percentile.

c. Unstable angina occurs only during heavy exertion.

d. Unstable angina occurs at rest or with minimal exertion.

Answer: d — Unstable angina is ischemia at rest or on minimal exertion without heart muscle death, often a change from a previously stable pattern (d) (section 17.3). Predictable relief by rest or nitroglycerin describes stable angina (a). A troponin rise and fall above the 99th percentile defines MI, not unstable angina (b). Angina with predictable exertion describes stable angina (c).

9. [CORE] Which statement shows that a patient understands teaching about sublingual nitroglycerin?

a. "I will lie flat in bed before I take it, and then walk around to see if it worked."

b. "I'll sit down, take one dose, and call 9-1-1 if the pain isn't better in 5 minutes."

c. "I can keep taking doses every few minutes for as long as I need until the pain goes away completely."

d. "If I get a headache, it means the medicine has stopped working."

Answer: b — The person sits, takes one dose, and calls 9-1-1 if the pain has not eased within 5 minutes; if the pain comes back, a dose may be repeated after 5 minutes, to no more than 3 doses in 15 minutes (b) (section 17.2). Walking afterward (a) increases demand and risks a fall from low blood pressure. Doses are limited, and waiting for relief delays emergency care (c). Headache is the most common side effect and does not mean the drug has failed (d).

10. [CORE] A woman with suspected ACS has an SpO2 of 96% on room air and no shortness of breath. The family asks why the nurse has not started oxygen. Which reply is accurate?

a. "Oxygen is given to every patient with chest pain because extra oxygen protects the heart muscle from damage."

b. "Oxygen is only used after the troponin results come back."

c. "Oxygen helps only when the oxygen level is low, and hers is normal."

d. "Oxygen would make the ECG hard to read."

Answer: c — Oxygen is given in ACS only for low SpO2; a guideline panel recommends against starting it in suspected MI when SpO2 is above 92% on room air (c) (section 17.3; Chapter 12). Routine oxygen (a) is no longer recommended. Troponin results (b) do not decide oxygen use. Oxygen does not affect the ECG (d).

11. [CORE] A 58-year-old woman on a surgical unit reports sudden extreme fatigue, shortness of breath and pressure in her upper back, but no chest pain. What is the nurse's best interpretation?

a. These can be heart attack signs in women and need an ECG and escalation now.

b. Without chest pain or pressure, a cardiac cause is unlikely, so the nurse can monitor her overnight.

c. The symptoms are expected after surgery and need rest.

d. These symptoms point to anxiety and need reassurance.

Answer: a — Women may have MI without chest pressure, presenting instead with breathlessness, upper back pressure or extreme fatigue, so the nurse obtains an ECG and escalates (a) (section 17.3). Many people with MI, especially women, have no chest pain (b). Attributing the symptoms to surgery (c) or anxiety (d) delays diagnosis; under-recognition in women is a documented equity gap (section 17.1, Canadian Context box).

12. [CORE] A patient with chest discomfort that began 40 minutes ago has a first high-sensitivity troponin within the reference range and a nondiagnostic ECG. What does the nurse anticipate?

a. Discharge home, because a normal first troponin has ruled out myocardial infarction

b. Fibrinolytic therapy

c. No further troponin testing unless pain returns

d. A repeat troponin at the time the chest pain pathway sets

Answer: d — MI is diagnosed by a rise and/or fall in troponin, so one value cannot show the pattern; the nurse anticipates a repeat sample as the pathway directs (d) (section 17.3; Chapter 16). One normal value early after onset does not rule out MI (a, c). Fibrinolysis (b) is a STEMI treatment, and this ECG does not show STEMI.

13. [CORE] A patient on a medical unit has suspected ACS. The agency's medical directive allows the nurse to give ASA. Which action is correct?

a. Give an enteric-coated ASA tablet with water, to be swallowed whole to protect the stomach

b. Check for ASA allergy or intolerance, then have the patient chew it

c. Hold ASA until troponin confirms MI

d. Give ASA only if the ECG shows ST elevation

Answer: b — ASA is chewed and swallowed for suspected ACS if the person has no allergy or intolerance (b) (section 17.3). Swallowing a coated tablet whole (a) defeats the purpose of chewing. ASA is given for suspected ACS, so it does not wait for troponin (c) or for STEMI changes (d).

14. [CORE] On a medical unit in Ontario, an RPN finds a patient with new chest pressure. Which action reflects the RPN's scope and accountability?

a. Wait for the RN to assess before taking any action

b. Interpret the 12-lead ECG independently and decide whether the patient needs reperfusion

c. Ask the family to watch the patient while the RPN finishes medications

d. Stay with the patient, call for help and consult the RN right away

Answer: d — Every nurse who notices deterioration acts at once; the RPN starts the first steps and consults the RN as the patient's needs change (d) (section 17.3; Chapter 1, section 1.3). Waiting (a) delays care. Diagnosing STEMI and choosing reperfusion (b) belong to the physician or NP. A family member cannot take over the nurse's monitoring (c).

15. [CORE] Which statement about lipid testing reflects the 2021 CCS dyslipidemia guideline?

a. A nonfasting sample is acceptable for most people, and lipoprotein(a) is measured once in a lifetime.

b. Patients must fast for 12 hours, and lipoprotein(a) is checked every year.

c. Lipid screening should begin at age 65 for everyone, and earlier only when heart symptoms appear.

d. LDL-C is preferred over non-HDL-C when triglycerides are high.

Answer: a — CCS recommends nonfasting testing except when triglycerides are known to be above 4.5 mmol/L, and Lp(a) once in a lifetime (a) (section 17.1). Fasting is not routinely needed and Lp(a) is not repeated yearly (b). Screening starts after age 40, or earlier with risk conditions (c). When triglycerides exceed 1.5 mmol/L, the CCS prefers non-HDL-C or ApoB to LDL-C (d).

16. [CORE] A patient with a bleeding duodenal ulcer has a hemoglobin of 68 g/L and a rising troponin, with no new ST elevation. The physician documents "type 2 MI." What does this mean?

a. A coronary plaque has ruptured and a new clot is now blocking one of the coronary arteries.

b. Oxygen supply could not meet demand, here because of severe anemia.

c. The patient has stable angina.

d. The troponin rise is a laboratory error.

Answer: b — Type 2 MI results from a supply–demand mismatch without acute plaque disruption; severe anemia reduces oxygen delivery (b) (section 17.3). Plaque rupture with thrombus is type 1 MI (a). Stable angina (c) does not raise troponin in an MI pattern. The rising troponin reflects real injury (d), and treatment targets the cause, such as stopping the bleeding and replacing blood.

17. [RN] A patient's ECG shows ST elevation in II, III and aVF. Blood pressure is 88/56 mm Hg and the lungs are clear. Which nursing action is the priority?

a. Give sublingual nitroglycerin now to relieve the pain and reduce myocardial oxygen demand

b. Repeat the standard 12-lead ECG in 1 hour

c. Record V3R and V4R as ordered, hold nitroglycerin and report the hypotension

d. Sit the patient upright with legs dependent to ease breathing and pain

Answer: c — Inferior STEMI with hypotension raises concern for right ventricular infarction; right-sided leads are recorded early, and nitroglycerin is held because severe hypotension is a contraindication and the monograph warns of serious effects in inferior MI with right ventricular involvement (c) (section 17.3, Going Deeper and Clinical Safety boxes). Giving nitroglycerin (a) could worsen hypotension. Waiting an hour (b) delays diagnosis. Sitting upright with legs down (d) reduces venous return and could lower blood pressure further; it does not treat the cause.

18. [RN] A 12-lead ECG shows ST elevation in V1 to V4 with ST depression in II, III and aVF. How should the nurse interpret the ST depression?

a. As a separate inferior STEMI

b. As a sign that the anterior ST elevation is caused by pericarditis rather than ischemia

c. As early repolarization, a normal variant

d. As reciprocal change, which supports an acute anterior STEMI

Answer: d — ST depression in leads facing the opposite wall is a reciprocal change; with convex ST elevation it usually means acute occlusion and helps tell STEMI apart from pericarditis or early repolarization (d) (section 17.3, Going Deeper box). Inferior STEMI (a) would show ST elevation, not depression, in II, III and aVF. Reciprocal changes argue against pericarditis (b) and early repolarization (c).

Case: Lucien Bergeron (Questions 19–24): Lucien Bergeron, 61, had PCI with a stent through his right femoral artery this morning for a non-ST-elevation MI at a hospital in Kingston, Ontario. He takes ASA and ticagrelor and received heparin during the procedure. He has type 2 diabetes, and his eGFR this morning was 52 mL/min/1.73 m². He returned to the cardiac step-down unit 2 hours ago on bed rest with his right leg straight, per protocol. Baseline pedal pulses were strong and equal.

19. [CORE] At the 2-hour check, which finding should the nurse follow up first?

a. A dry dressing with a small, unchanged mark from the procedure

b. Heart rate 76 per minute and blood pressure 130/78 mm Hg

c. A new, firm, tender swelling beside the dressing

d. The patient's request for something to drink

Answer: c — A new, firm, tender swelling at a femoral puncture site suggests bleeding under the skin and needs follow-up first (section 17.5, Table 17.3). An unchanged mark on a dry dressing (a) is expected. The vital signs (b) are within normal limits and unchanged. Thirst (d) matters, but he can drink if allowed, and it does not threaten the limb or circulation.

20. [CORE] Which explanation best fits the new groin swelling?

a. A hematoma from blood leaking out of the arterial puncture

b. An allergic reaction to the contrast dye

c. A blood clot forming in a deep leg vein

d. Stent thrombosis in the coronary artery that was treated this morning

Answer: a — A firm, tender swelling at the puncture site after femoral access is most consistent with a hematoma, a collection of blood from the arterial puncture; antiplatelets and heparin add to the risk (sections 17.4 and 17.5). A contrast reaction (b) causes hives, itching or breathing problems, not a local lump. A deep vein clot (c) causes calf or leg swelling and pain, not a firm lump at the groin. Stent thrombosis (d) causes chest pain and ECG changes, not groin swelling.

21. [CORE] Thirty minutes later, Mr. Bergeron's right foot is cooler than the left and his right pedal pulses are weaker than at baseline. The groin swelling is unchanged. Which problem is the priority?

a. Discomfort from lying flat

b. Reduced blood flow to the right leg

c. Anxiety about the procedure

d. Risk of urinary retention from bed rest

Answer: b — A cooler foot with weaker pulses than baseline suggests reduced arterial flow to the limb. This threatens the limb and needs urgent escalation (section 17.5). Discomfort (a), anxiety (c) and urinary retention (d) all need attention, but none is as time-critical as possible limb ischemia.

22. [CORE] Which plan is most appropriate for the RPN caring for Mr. Bergeron?

a. Raise the head of the bed so he is more comfortable, then reassess the site and foot in 1 hour

b. Remove the dressing, apply a warm compress to the swelling and document its size in the chart

c. Encourage him to walk to the bathroom to improve circulation in the leg

d. Keep the leg straight, apply pressure per protocol, consult the RN and call the physician

Answer: d — The plan keeps him safe and gets the right people involved quickly. He stays still with the leg straight, pressure is applied as the protocol directs, the RPN consults the RN because his needs are changing, and the physician is notified urgently (section 17.5; Scope in Practice box). Raising the head of the bed and waiting an hour (a) delays care and may worsen bleeding. Warm compresses (b) are not appropriate for a new arterial bleed. Walking (c) breaks bed rest and may increase bleeding.

23. [CORE] That evening, Mr. Bergeron reports new chest pressure rated 7 out of 10. What should the nurse do first?

a. Record a 12-lead ECG under the directive and call for urgent help

b. Give his evening dose of ticagrelor early

c. Ask him to rest quietly and reassess the pain in 30 minutes to see if it settles

d. Reassure him that chest discomfort is expected after PCI

Answer: a — New chest pain after PCI may mean stent thrombosis, which acts like a new MI. A 12-lead ECG and urgent help come first (sections 17.3 and 17.5). Changing drug timing (b) is not the nurse's decision and does not treat a blocked stent. Waiting 30 minutes (c) delays reperfusion. Chest pain is not an expected finding after PCI (d).

24. [CORE] The next morning, which finding best shows that Mr. Bergeron's access-site care has been effective?

a. He says he slept well

b. The groin swelling has not grown past its marked edges, and his right foot is warm with pedal pulses equal to baseline

c. His urine output was 400 mL overnight

d. His heart rate is 58 per minute after his beta-blocker

Answer: b — A stable hematoma inside its marked edges, a warm foot and pulses back to baseline show that bleeding is controlled and blood flow to the limb is restored (section 17.5, Table 17.3). Sleep (a) is good but does not show site or limb safety. Urine output (c) relates to kidney function after contrast. A slow heart rate after a beta-blocker (d) relates to the drug, not the access site.

25. [CORE] A patient had PCI through the femoral artery 4 hours ago. Which findings may indicate retroperitoneal bleeding? Select all that apply.

a. New lower back or flank pain
b. Heart rate rising from 70 to 104 per minute
c. Blood pressure falling from 132/78 to 96/58 mm Hg
d. New restlessness
e. Hemoglobin falling from 136 to 108 g/L
f. Warm foot with strong pedal pulses
g. Mild itch at the dressing edge

Answer: a, b, c, d, e — Bleeding behind the abdominal organs may show no blood at the groin. Back, flank or lower abdominal pain (a), a rising heart rate (b), falling blood pressure (c), restlessness (d) and a falling hemoglobin (e) are its cues and need urgent escalation (section 17.5). A warm foot with strong pulses (f) shows good limb perfusion and does not rule out retroperitoneal bleeding. A mild itch at the dressing (g) is usually from the adhesive.

26. [CORE] Two weeks after PCI with a stent, a patient calls the cardiac clinic. He says he plans to stop his ticagrelor because he bruises easily, and he will keep taking ASA. What is the nurse's best response?

a. "Bruising is a sign of a serious reaction, so stop both drugs now."
b. "That's a reasonable plan as long as you keep taking ASA every day without missing doses."
c. "Please don't stop it. Let's have the cardiology team review the bruising first."
d. "Take it every second day to reduce the bruising."

Answer: c — Stopping a P2Y12 inhibitor early leaves a new stent at risk of stent thrombosis, so the nurse asks him not to stop it. The ticagrelor monograph states that patients who stop it are at higher risk of cardiac events, so the team should review the bruising before any change (section 17.5). Stopping both drugs (a) is dangerous and is not justified by mild bruising. ASA alone (b) is not the prescribed plan. Taking it every second day (d) is an unsafe dose change the nurse cannot make.

27. [CORE] A patient has a compression band on the right wrist after radial catheterization. Forty-five minutes later, the patient reports tingling fingers, and the hand is cooler and paler than the left. What should the nurse do?

a. Assess the hand fully and act on the band per protocol, then notify the physician if perfusion does not improve
b. Tighten the band to make sure the site does not bleed
c. Raise the arm above the head and recheck in 2 hours
d. Remove the band completely and apply a gauze dressing

Answer: a — Tingling, coolness and pallor suggest reduced hand perfusion. The nurse assesses the hand fully and follows the protocol for the band, which aims to stop bleeding while keeping some flow in the artery, and escalates if perfusion does not improve (section 17.5; Mason et al., 2018). Tightening the band (b) would reduce flow further. Waiting 2 hours (c) delays care. Removing the band completely (d) outside protocol risks bleeding.

28. [CORE] A patient on the second day after CABG is being taught the "Keep Your Move in the Tube" approach. Which statement shows correct understanding?

a. "I can't lift my arms above my waist for 12 weeks."
b. "I can use my arms for everyday tasks if I keep my movements close to my body."
c. "I should push up from a chair with my arms spread wide."
d. "I don't need to protect my breastbone once the drains are out."

Answer: b — The approach lets patients use their arms for everyday activities, guided by pain, with movements kept close to the body (section 17.5). Strict limits on arm use for 12 weeks (a) describe traditional precautions. Spreading the arms wide to push up (c) is the movement the approach avoids. The breastbone still needs protection after drain removal (d).

29. [CORE] On the second day after CABG, a patient's monitor shows a new irregularly irregular rhythm at 136 per minute. Blood pressure is 102/64 mm Hg (was 124/72). What is the nurse's first action?

a. Encourage the patient to walk in the hallway to see whether the rhythm settles on its own
b. Document the rhythm in the chart and recheck it at the next scheduled assessment in 4 hours
c. Remove the temporary pacing wires
d. Assess the patient, get an ECG as directed and notify the team promptly

Answer: d — New AF is common after heart surgery and can lower blood pressure. The nurse assesses the patient, documents the rhythm and notifies the team promptly (section 17.5; Chapter 16, section 16.6). Walking (a) could worsen hypotension. Waiting for the next scheduled assessment (b) delays care. Pacing wires (c) are removed only by order and procedure, and removing them does not treat AF.

30. [CORE] Which nursing action is most likely to increase a patient's participation in cardiac rehabilitation after MI?

a. Telling the patient to ask their family doctor about rehabilitation at a future visit
b. Waiting until the patient raises the topic of exercise programs before discussing it
c. Advising the patient to start exercising alone at a gym as soon as they get home from hospital
d. Making sure a referral is sent before discharge and explaining what the program offers

Answer: d — Lack of referral and physician recommendation are main barriers, and a national position calls for systematic inpatient referral (Grace et al., 2014). A referral sent before discharge, with an explanation, is the strongest step (section 17.6). Leaving it to the patient (a, b) means many patients will never be referred. Unsupervised exercise (c) does not replace rehabilitation and may not be safe without assessment.

31. [CORE] Three days after an MI, a patient says, "I don't see the point of any of this anymore," and reports sleeping poorly. What is the most appropriate nursing response?

a. Explore the feelings, screen with the unit's tool and report the results

b. Tell the patient that everyone feels this way after a heart attack and it will pass

c. Ask the family to cheer the patient up

d. Document "patient tired" and continue care

Answer: a — Depression after ACS is linked to poorer outcomes, so these cues need screening and reporting, including asking about safety (Lichtman et al., 2014; section 17.4). Dismissing the feelings (b), handing the problem to family (c) or labelling it as tiredness (d) leaves possible depression unrecognized.

32. [CORE] A patient who drives a delivery truck for a living asks when he can drive again after his MI and PCI. What is the nurse's best response?

a. "You can drive as soon as you feel well."

b. "Drivers are never allowed to return to commercial driving after a heart attack."

c. "The waiting period depends on your situation, and commercial drivers have stricter rules. Please check with your cardiologist first."

d. "You can drive your own car but not the truck, so there is no need to ask."

Answer: c — The CCS 2023 guideline restricts driving for a set period after these events, with stricter recommendations for commercial drivers; the cardiology team gives the exact time (Guerra et al., 2024; section 17.6). Feeling well (a) is not the standard. A lifetime ban (b) is incorrect. Option d gives a rule the nurse cannot confirm and discourages him from getting advice.

33. [CORE] A patient is going home on ASA and clopidogrel. Which teaching about bleeding is correct?

a. "Use a stiff toothbrush to keep your gums healthy."

b. "Use a soft toothbrush and report black stools or blood in your urine."

c. "Take ibuprofen for any aches and pains so that you can avoid needing stronger drugs."

d. "Small nosebleeds mean the dose is too high, so skip a day."

Answer: b — A soft toothbrush reduces minor bleeding, and black stools or blood in the urine can signal serious bleeding (section 17.4). A stiff toothbrush (a) increases gum bleeding. Nonsteroidal anti-inflammatory drugs such as ibuprofen (c) add to bleeding risk and should not be taken without advice. Skipping doses (d) raises the risk of stent thrombosis.

34. [CORE] A patient admitted 4 days ago with a large MI, who arrived many hours after symptoms began and did not have early reperfusion, had been improving. He suddenly becomes very short of breath with crackles throughout both lungs, and his blood pressure falls to 84/50 mm Hg. What should the nurse suspect and do?

a. Anxiety; coach slow breathing and recheck in 30 minutes

b. Pericarditis; position him upright and give his usual analgesic

c. A possible mechanical complication of MI; call for urgent help and stay with him

d. Constipation from bed rest; give a laxative as ordered

Answer: c — Sudden breathlessness and hypotension in a patient with a large, late-treated MI may signal a mechanical complication such as papillary muscle rupture. These complications are rare but carry a substantial risk of death and need rapid team assessment with imaging and, often, surgery (Damluji et al., 2021; section 17.4). Anxiety (a) and constipation (d) do not explain crackles and shock. Pericarditis (b) does not usually cause sudden pulmonary edema and hypotension, and assuming it would delay care.

35. [CORE] An RPN on a cardiac step-down unit is asked to remove a femoral sheath for the first time. The RPN has not completed the hospital's sheath-removal education. What should the RPN do?

a. Remove the sheath, because RPNs may perform any task an RN performs

b. Ask a family member to hold pressure while the RPN removes the sheath

c. Remove the sheath under the physician's verbal order, because the order gives the RPN the authority and competence needed

d. Decline the task, explain the reason, and ask the RN or charge nurse to arrange care by an authorized, competent nurse

Answer: d — Under CNO's Scope of Practice standard, a nurse needs authority, competence and a supportive context. Employers can limit practice through policy, and a nurse who lacks the competence declines and makes sure care is still provided (Chapter 1, section 1.3; Scope in Practice box). RN and RPN roles are not identical (a). Family members (b) cannot take on clinical procedures. An order (c) does not give the RPN competence.

36. [CORE] A patient asks when it is safe to resume sexual activity after an uncomplicated MI. Based on the AHA scientific statement, which response is accurate?

a. "Usually from about 1 week after an uncomplicated MI, if mild to moderate activity causes you no heart symptoms."

b. "You will need to wait at least 6 months."

c. "It is safe right away, whatever your symptoms."

d. "You can resume only after you finish cardiac rehabilitation."

Answer: a — The AHA statement considers sex reasonable from 1 week or more after an uncomplicated MI when mild to moderate exertion causes no heart symptoms (Levine et al., 2012; section 17.6). A 6-month wait (b) is not supported. Ignoring symptoms (c) is unsafe. Finishing rehabilitation (d) is not required, although rehabilitation can help.

37. [RN] A patient with NSTEMI is going for PCI. She is 78, weighs 56 kg and had a TIA 2 years ago. The draft order set lists prasugrel as the P2Y12 inhibitor. What should the RN do?

a. Give prasugrel, because it is preferred over clopidogrel for patients with ACS who are having PCI

b. Hold all antiplatelet drugs until after PCI

c. Give prasugrel at the usual time and monitor for bleeding

d. Question the order, because of her TIA, age and weight

Answer: d — Prasugrel is contraindicated after a stroke or TIA and is not recommended for people aged 75 or older or weighing less than 60 kg (JAMP Pharma Corporation, 2020; Rao et al., 2025; section 17.4). The general preference for potent P2Y12 inhibitors (a) does not override a contraindication. Holding all antiplatelets (b) is not the plan for ACS. Giving it with bleeding monitoring (c) ignores the contraindication.

38. [RN] On day 2 after a large anterior MI, which group of findings most strongly suggests cardiogenic shock?

a. Blood pressure 142/88 mm Hg, warm skin, urine output 60 mL/h

b. Blood pressure 84/56 mm Hg, cool clammy skin, new confusion, urine output 15 mL/h

c. Heart rate 58 per minute after a beta-blocker, alert, warm skin

d. Temperature 37.9 °C, mild chest discomfort when breathing deeply, stable blood pressure

Answer: b — Low blood pressure with signs of poor perfusion (cool clammy skin, confusion, low urine output) suggests cardiogenic shock, which needs immediate escalation (section 17.4; Chapter 6). Option a shows adequate perfusion. Option c is an expected beta-blocker effect with good perfusion. Option d may suggest pericarditis (Chapter 18) but not shock.

39. [RN] Based on Canadian radiology guidance, which patient scheduled for coronary angiography is at greatest risk of contrast-associated acute kidney injury?

a. A 54-year-old with eGFR 26 mL/min/1.73 m²

b. A 70-year-old with eGFR 64 mL/min/1.73 m²

c. A 48-year-old with type 2 diabetes and eGFR 88 mL/min/1.73 m²

d. A 61-year-old with a past rash after contrast and eGFR 75 mL/min/1.73 m²

Answer: a — Canadian guidance identifies an eGFR of 30 mL/min/1.73 m² or less, or existing acute kidney injury, as the main risk for contrast-associated kidney injury (Macdonald et al., 2022; section 17.5). Age alone with eGFR 64 (b) and diabetes with normal kidney function (c) are lower risk. A past contrast rash (d) raises concern about an allergic-type reaction, not kidney injury.

40. [RN] A student asks why the unit uses a radial-first approach for PCI in ACS. Which statement accurately reflects the trial evidence?

a. In RIVAL, radial access cut the combined rate of death, MI, stroke or major bleeding at 30 days by about half

b. Both trials found that femoral access caused fewer hematomas and other vascular complications

c. In MATRIX, radial access reduced net adverse clinical events, mainly through less major bleeding and lower death from any cause

d. Both trials found no differences of any kind between radial and femoral access

Answer: c — In MATRIX, radial access reduced net adverse clinical events (9.8% vs 11.7%), mainly through less major bleeding and lower all-cause death (Valgimigli et al., 2015; section 17.5). In RIVAL the combined outcome was similar (3.7% vs 4.0%), so it was not halved (a). RIVAL found fewer large hematomas and pseudoaneurysms with radial access, not with femoral access (b). Option d ignores these differences.

References

Angita Pharma Inc. (2022). *AG-Vardenafil (vardenafil hydrochloride tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00066919.PDF

Apotex Inc. (2024). *APO-ATORVASTATIN (atorvastatin calcium tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00075568.PDF

AstraZeneca Canada. (2026). *Brilinta (ticagrelor tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00083390.PDF

Bainey, K. R., Marquis-Gravel, G., Belley-Côté, E., Turgeon, R. D., Ackman, M. L., Babadagli, H. E., Bewick, D., Boivin-Proulx, L.-A., Cantor, W. J., Fremes, S. E., Graham, M. M., Lordkipanidzé, M., Madan, M., Mansour, S., Mehta, S. R., Potter, B. J., Shavadia, J., So, D. F., Tanguay, J.-F., … Wong, G. C. (2024). Canadian Cardiovascular Society/Canadian Association of Interventional Cardiology 2023 focused update of the guidelines for the use of antiplatelet therapy. *Canadian Journal of Cardiology, 40*(2), 160–181. https://doi.org/10.1016/j.cjca.2023.10.013

Byrne, R. A., Rossello, X., Coughlan, J. J., Barbato, E., Berry, C., Chieffo, A., Claeys, M. J., Dan, G.-A., Dweck, M. R., Galbraith, M., Gilard, M., Hinterbuchner, L., Jankowska, E. A., Jüni, P., Kimura, T., Kunadian, V., Leosdottir, M., Lorusso, R., Pedretti, R. F. E., … ESC Scientific Document Group. (2023). 2023 ESC guidelines for the management of acute coronary syndromes. *European Heart Journal, 44*(38), 3720–3826. https://doi.org/10.1093/eurheartj/ehad191

Canto, J. G., Rogers, W. J., Goldberg, R. J., Peterson, E. D., Wenger, N. K., Vaccarino, V., Kiefe, C. I., Frederick, P. D., Sopko, G., Zheng, Z.-J., & NRMI Investigators. (2012). Association of age and sex with myocardial infarction symptom presentation and in-hospital mortality. *JAMA, 307*(8), 813–822. https://doi.org/10.1001/jama.2012.199

College of Nurses of Ontario. (2025a). *Medication* [Practice standard]. https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41007_medication.pdf

College of Nurses of Ontario. (2025b). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

Damluji, A. A., van Diepen, S., Katz, J. N., Menon, V., Tamis-Holland, J. E., Bakitas, M., Cohen, M. G., Balsam, L. B., & Chikwe, J. (2021). Mechanical complications of acute myocardial infarction: A scientific statement from the American Heart Association. *Circulation, 144*(2), e16–e35. https://doi.org/10.1161/CIR.0000000000000985

Dibben, G., Faulkner, J., Oldridge, N., Rees, K., Thompson, D. R., Zwisler, A.-D., & Taylor, R. S. (2021). Exercise-based cardiac rehabilitation for coronary heart disease. *Cochrane Database of Systematic Reviews, 2021*(11), Article CD001800. https://doi.org/10.1002/14651858.CD001800.pub4

Emergency Care BC. (2020). *Fibrinolytic therapy for STEMI* [Clinical summary]. https://emergencycarebc.ca/clinical_resource/clinical-summary/fibrinolytic-therapy-for-stemi

Fraser Health, Providence Health Care, Provincial Health Services Authority, & Vancouver Coastal Health. (2023). *Nitrates* [Patient education, FH #262765]. https://patienteduc.fraserhealth.ca/file/nitrates-6366.pdf

Gach, R., Triano, S., Ogola, G. O., da Graca, B., Shannon, J., El-Ansary, D., Bilbrey, T., Cortelli, M., & Adams, J. (2021). "Keep Your Move in the Tube" safely increases discharge home following cardiac surgery. *PM&R, 13*(12), 1321–1330. https://doi.org/10.1002/pmrj.12562

Grace, S. L., Bennett, S., Ardern, C. I., & Clark, A. M. (2014). Cardiac rehabilitation series: Canada. *Progress in Cardiovascular Diseases, 56*(5), 530–535. https://doi.org/10.1016/j.pcad.2013.09.010

Guerra, P. G., Simpson, C. S., Van Spall, H. G. C., Asgar, A. W., Billia, P., Cadrin-Tourigny, J., Chakrabarti, S., Cheung, C. C., Dore, A., Fordyce, C. B., Gouda, P., Hassan, A., Krahn, A., Luc, J. G. Y., Mak, S., McMurtry, S., Norris, C., Philippon, F., Sapp, J., … Wood, D. A. (2024). Canadian Cardiovascular Society 2023 guidelines on the fitness to drive. *Canadian Journal of Cardiology, 40*(4), 500–523. https://doi.org/10.1016/j.cjca.2023.09.033

Heart and Stroke Foundation of Canada. (2018, February 1). *Women's heart health is another glass ceiling we need to smash* [News release]. https://www.heartandstroke.ca/what-we-do/media-centre/news-releases/2018-heart-report-news-release

Heart and Stroke Foundation of Canada. (n.d.-a). *Cardiac catheterization*. Retrieved October 25, 2026, from https://www.heartandstroke.ca/heart-disease/tests/cardiac-catheterization

Heart and Stroke Foundation of Canada. (n.d.-b). *Cardiac rehabilitation*. Retrieved October 26, 2026, from https://www.heartandstroke.ca/heart-disease/recovery-and-support/cardiac-rehabilitation

Heart and Stroke Foundation of Canada. (n.d.-c). *Pregnancy to menopause: The heart and brain health connection*. Retrieved October 26, 2026, from https://www.heartandstroke.ca/articles/pregnancy-to-menopause-the-heart-and-brain-health-connection

Heart and Stroke Foundation of Canada. (n.d.-d). *Signs of a heart attack*. Retrieved October 26, 2026, from https://www.heartandstroke.ca/heart-disease/emergency-signs

JAMP Pharma Corporation. (2020). *JAMP Prasugrel (prasugrel hydrochloride tablets)* [Product monograph; in French]. https://pdf.hres.ca/dpd_pm/00057293.PDF

Jebari-Benslaiman, S., Galicia-García, U., Larrea-Sebal, A., Olaetxea, J. R., Alloza, I., Vandenbroeck, K., Benito-Vicente, A., & Martín, C. (2022). Pathophysiology of atherosclerosis. *International Journal of Molecular Sciences, 23*(6), Article 3346. https://doi.org/10.3390/ijms23063346

Jolly, S. S., Yusuf, S., Cairns, J., Niemelä, K., Xavier, D., Widimsky, P., Budaj, A., Niemelä, M., Valentin, V., Lewis, B. S., Avezum, A., Steg, P. G., Rao, S. V., Gao, P., Afzal, R., Joyner, C. D., Chrolavicius, S., & Mehta, S. R. (2011). Radial versus femoral access for coronary angiography and intervention in patients with acute coronary syndromes (RIVAL): A randomised, parallel group, multicentre trial. *The Lancet, 377*(9775), 1409–1420. https://doi.org/10.1016/S0140-6736(11)60404-2

Levine, G. N., Steinke, E. E., Bakaeen, F. G., Bozkurt, B., Cheitlin, M. D., Conti, J. B., Foster, E., Jaarsma, T., Kloner, R. A., Lange, R. A., Lindau, S. T., Maron, B. J., Moser, D. K., Ohman, E. M., Seftel, A. D., & Stewart, W. J. (2012). Sexual activity and cardiovascular disease: A scientific statement from the American Heart Association. *Circulation, 125*(8), 1058–1072. https://doi.org/10.1161/CIR.0b013e3182447787

Lichtman, J. H., Froelicher, E. S., Blumenthal, J. A., Carney, R. M., Doering, L. V., Frasure-Smith, N., Freedland, K. E., Jaffe, A. S., Leifheit-Limson, E. C., Sheps, D. S., Vaccarino, V., & Wulsin, L. (2014). Depression as a risk factor for poor prognosis among patients with acute coronary syndrome: Systematic review and recommendations: A scientific statement from the American Heart Association. *Circulation, 129*(12), 1350–1369. https://doi.org/10.1161/CIR.0000000000000019

Macdonald, D. B., Hurrell, C. D., Costa, A. F., McInnes, M. D. F., O'Malley, M., Barrett, B. J., Brown, P. A., Clark, E. G., Hadjivassiliou, A., Kirkpatrick, I. D. C., Rempel, J., Jeon, P., & Hiremath, S. (2022). Canadian Association of Radiologists guidance on contrast-associated acute kidney injury. *Canadian Journal of Kidney Health and Disease, 9*, Article 20543581221097455. https://doi.org/10.1177/20543581221097455

Mason, P. J., Shah, B., Tamis-Holland, J. E., Bittl, J. A., Cohen, M. G., Safirstein, J., Drachman, D. E., Valle, J. A., Rhodes, D., & Gilchrist, I. C. (2018). An update on radial artery access and best practices for transradial coronary angiography and intervention in acute coronary syndrome: A scientific statement from the American Heart Association. *Circulation: Cardiovascular Interventions, 11*(9), Article e000035. https://doi.org/10.1161/HCV.0000000000000035

Mehta, L. S., Beckie, T. M., DeVon, H. A., Grines, C. L., Krumholz, H. M., Johnson, M. N., Lindley, K. J., Vaccarino, V., Wang, T. Y., Watson, K. E., & Wenger, N. K. (2016). Acute myocardial infarction in women: A scientific statement from the American Heart Association. *Circulation, 133*(9), 916–947. https://doi.org/10.1161/CIR.0000000000000351

Mulvagh, S. L., Colella, T. J. F., Gulati, M., Crosier, R., Allana, S., Randhawa, V. K., Bruneau, J., Pacheco, C., Jaffer, S., Cotie, L., Mensour, E., Clavel, M.-A., Hill, B., Kirkham, A. A., Foulds, H., Liblik, K., Van Damme, A., Grace, S. L., Bouchard, K., … Norris, C. M. (2024). The Canadian Women's Heart Health Alliance ATLAS on the epidemiology, diagnosis, and management of cardiovascular disease in women: Chapter 9: Summary of current status, challenges, opportunities, and recommendations. *CJC Open, 6*(2 Part B), 258–278. https://doi.org/10.1016/j.cjco.2023.12.001

National Institute for Health and Care Excellence. (2011). *Stable angina: Management* (Clinical guideline CG126). https://www.nice.org.uk/guidance/cg126

Park, L., Coltman, C., Agren, H., Colwell, S., & King-Shier, K. M. (2021). "In the tube" following sternotomy: A quasi-experimental study. *European Journal of Cardiovascular Nursing, 20*(2), 160–166. https://doi.org/10.1177/1474515120951981

Pearson, G. J., Thanassoulis, G., Anderson, T. J., Barry, A. R., Couture, P., Dayan, N., Francis, G. A., Genest, J., Grégoire, J., Grover, S. A., Gupta, M., Hegele, R. A., Lau, D., Leiter, L. A., Leung, A. A., Lonn, E., Mancini, G. B. J., Manjoo, P., McPherson, R., … Wray, W. (2021). 2021 Canadian Cardiovascular Society guidelines for the management of dyslipidemia for the prevention of cardiovascular disease in adults. *Canadian Journal of Cardiology, 37*(8), 1129–1150. https://doi.org/10.1016/j.cjca.2021.03.016

Public Health Agency of Canada. (2017). *Heart disease in Canada: Highlights from the Canadian Chronic Disease Surveillance System*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/heart-disease-canada-fact-sheet.html

Public Health Agency of Canada. (2026). *Heart disease: Monitoring*. https://www.canada.ca/en/public-health/services/chronic-diseases/cardiovascular-disease/hypertension-facts-figures.html

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Rao, S. V., O'Donoghue, M. L., Ruel, M., Rab, T., Tamis-Holland, J. E., Alexander, J. H., Baber, U., Baker, H., Cohen, M. G., Cruz-Ruiz, M., Davis, L. L., de Lemos, J. A., DeWald, T. A., Elgendy, I. Y., Feldman, D. N., Goyal, A., Isiadinso, I., Menon, V., Morrow, D. A., … Williams, M. S. (2025). 2025 ACC/AHA/ACEP/NAEMSP/SCAI guideline for the management of patients with acute coronary syndromes: A report of the American College of Cardiology/American Heart Association Joint Committee on Clinical Practice Guidelines. *Journal of the American College of Cardiology, 85*(22), 2135–2237. https://doi.org/10.1016/j.jacc.2024.11.009

Regional Paramedic Program for Eastern Ontario. (2023, January 25). *STEMI and transport to PCI timeline* [MedicAsk answer]. https://www.rppeo.ca/paramedic-practice/medicask-about/medicask-answers-list/359-professionalism/291-paramedic-practice/1638-stemi-and-transport-to-pci-timeline

sanofi-aventis Canada Inc. (2021). *Nitrolingual Pumpspray (nitroglycerin sublingual spray)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00061931.PDF

Shanmugasegaram, S., Oh, P., Reid, R. D., McCumber, T., & Grace, S. L. (2013). Cardiac rehabilitation barriers by rurality and socioeconomic status: A cross-sectional study. *International Journal for Equity in Health, 12*, Article 72. https://doi.org/10.1186/1475-9276-12-72

Siemieniuk, R. A. C., Chu, D. K., Kim, L. H.-Y., Güell-Rous, M.-R., Alhazzani, W., Soccal, P. M., Karanicolas, P. J., Farhoumand, P. D., Siemieniuk, J. L. K., Satia, I., Irusen, E. M., Refaat, M. M., Mikita, J. S., Smith, M., Cohen, D. N., Vandvik, P. O., Agoritsas, T., Lytvyn, L., & Guyatt, G. H. (2018). Oxygen therapy for acutely ill medical patients: A clinical practice guideline. *BMJ, 363*, Article k4169. https://doi.org/10.1136/bmj.k4169

Statistics Canada. (2026, January 13). Deaths, 2024. *The Daily*. https://www150.statcan.gc.ca/n1/daily-quotidien/260113/dq260113b-eng.htm

Teva Canada Limited. (2020). *Tadalafil tablets* [Product monograph]. https://pdf.hres.ca/dpd_pm/00059296.PDF

Thygesen, K., Alpert, J. S., Jaffe, A. S., Chaitman, B. R., Bax, J. J., Morrow, D. A., White, H. D., & Executive Group on behalf of the Joint European Society of Cardiology (ESC)/American College of Cardiology (ACC)/American Heart Association (AHA)/World Heart Federation (WHF) Task Force for the Universal Definition of Myocardial Infarction. (2018). Fourth universal definition of myocardial infarction (2018). *Circulation, 138*(20), e618–e651. https://doi.org/10.1161/CIR.0000000000000617

Upjohn Canada ULC. (2020). *Viagra (sildenafil citrate tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00056254.PDF

Valgimigli, M., Gagnor, A., Calabró, P., Frigoli, E., Leonardi, S., Zaro, T., Rubartelli, P., Briguori, C., Andò, G., Repetto, A., Limbruno, U., Cortese, B., Sganzerla, P., Lupi, A., Galli, M., Colangelo, S., Ierna, S., Ausiello, A., Presbitero, P., … Jüni, P. (2015). Radial versus femoral access in patients with acute coronary syndromes undergoing invasive management: A randomised multicentre trial. *The Lancet, 385*(9986), 2465–2476. https://doi.org/10.1016/S0140-6736(15)60292-6

Vrints, C., Andreotti, F., Koskinas, K. C., Rossello, X., Adamo, M., Ainslie, J., Banning, A. P., Budaj, A., Buechel, R. R., Chiariello, G. A., Chieffo, A., Christodorescu, R. M., Deaton, C., Doenst, T., Jones, H. W., Kunadian, V., Mehilli, J., Milojevic, M., Piek, J. J., … ESC Scientific Document Group. (2024). 2024 ESC guidelines for the management of chronic coronary syndromes. *European Heart Journal, 45*(36), 3415–3537. https://doi.org/10.1093/eurheartj/ehae177

Wong, G. C., Welsford, M., Ainsworth, C., Abuzeid, W., Fordyce, C. B., Greene, J., Huynh, T., Lambert, L., Le May, M., Lutchmedial, S., Mehta, S. R., Natarajan, M., Norris, C. M., Overgaard, C. B., Perry Arnesen, M., Quraishi, A., Tanguay, J.-F., Traboulsi, M., van Diepen, S., … So, D. (2019). 2019 Canadian Cardiovascular Society/Canadian Association of Interventional Cardiology guidelines on the acute management of ST-elevation myocardial infarction: Focused update on regionalization and reperfusion. *Canadian Journal of Cardiology, 35*(2), 107–132. https://doi.org/10.1016/j.cjca.2018.11.031

Yusuf, S., Hawken, S., Ôunpuu, S., Dans, T., Avezum, A., Lanas, F., McQueen, M., Budaj, A., Pais, P., Varigos, J., Lisheng, L., & INTERHEART Study Investigators. (2004). Effect of potentially modifiable risk factors associated with myocardial infarction in 52 countries (the INTERHEART study): Case-control study. *The Lancet, 364*(9438), 937–952. https://doi.org/10.1016/S0140-6736(04)17018-9

18 Heart Failure, Valvular and Inflammatory Heart Disease

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain how heart failure develops, and classify it by ejection fraction and NYHA class.
2. Recognize worsening and acute heart failure on a range of skin tones, interpret key tests in SI units, and escalate.
3. Provide nursing care for acute decompensated heart failure using the CJMM.
4. Monitor and teach patients taking the main heart failure drug classes.
5. Teach self-management (daily weights, an action plan, sodium and fluid guidance) and plan safe transitions home, with attention to older adults and rural and Indigenous communities.
6. Care for patients with valvular heart disease and after valve replacement, including anticoagulation safety.
7. Recognize and respond to infective endocarditis, pericarditis, cardiac tamponade, myocarditis and the cardiomyopathies.
8. Distinguish RN and RPN roles in heart failure and valve care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 6, 7	Clinician; Scholar	Foundations of Practice
4, 5	Clinician; Educator; Advocate	Foundations of Practice; Collaborative Practice
8	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

Heart failure (HF) is a clinical syndrome in which a structural or functional problem of the heart causes symptoms and signs, supported by raised natriuretic peptide levels or objective evidence of congestion in the lungs or body (Bozkurt et al., 2021). Put simply, the heart can no longer fill or pump well enough to meet the body's needs without abnormally high pressures inside it. **Valvular heart disease** is narrowing or leaking of one or more heart valves. **Inflammatory heart disease** includes infection or inflammation of the heart's inner lining and valves (endocarditis), its outer sac (pericarditis) and its muscle (myocarditis).

These conditions fill medical units. Heart failure is one of the top reasons people in Canada are admitted to hospital, and about 1 in 5 patients with heart failure is readmitted within a month of discharge (Heart and Stroke Foundation of Canada, 2022). Many patients are older adults living with several other illnesses, so nurses on general medical, surgical, rehabilitation and long-term care units, not only cardiac units, care for them every day.

This chapter explains how heart failure develops (section 18.1), how to recognize and manage worsening heart failure (18.2), the medications and devices that treat it (18.3), and self-management and transitions home (18.4). It then covers valvular heart disease and care after valve replacement (18.5), infective endocarditis (18.6), and pericarditis, myocarditis and the cardiomyopathies (18.7). The chapter builds on cardiac assessment and tests in Chapter 16 and on coronary artery disease in Chapter 17. It links to recognizing deterioration and shock (Chapter 6), non-invasive ventilation (Chapter 15), and hypertension and anticoagulation (Chapter 19).

18.1 Heart Failure: How It Develops

What Goes Wrong

Cardiac output depends on heart rate and stroke volume, and stroke volume depends on preload, afterload and contractility (section 16.1). Heart failure develops when injury or strain to the heart muscle upsets this balance.

Two main problems can occur, and many patients have both. In **systolic dysfunction**, the left ventricle cannot contract forcefully, so it ejects a smaller share of its blood with each beat; the chamber often enlarges. In **diastolic dysfunction**, the ventricle squeezes adequately but is stiff and does not relax and fill normally. Higher pressure is needed to fill it, and that pressure backs up into the lungs. A stiff ventricle relies heavily on the atria to top up its filling, which is one reason atrial fibrillation (AF) can tip a stable patient into failure (section 16.6).

Which side of the heart fails determines where congestion appears. In **left-sided heart failure**, pressure rises in the left atrium and the pulmonary veins. Fluid moves out of the pulmonary capillaries into lung tissue and, when severe, into the alveoli, causing breathlessness and crackles. In **right-sided heart failure**, the right ventricle cannot move blood forward into the lungs, so pressure rises in the systemic veins. The result is a raised jugular venous pressure (JVP) (Figure 18.1), swelling of the legs and abdomen, and congestion of the liver and gut.

Left-sided failure is the usual reason the right side fails. Chronically high pressure in the pulmonary circulation forces the right ventricle to pump against a heavy load until it, too, weakens. Right-sided failure can also arise on its own from chronic lung disease or pulmonary embolism (Chapters 14 and 15).

Many conditions damage or overload the heart:

- **Coronary artery disease:** loss of muscle after a myocardial infarction (MI) is named by Canadian surveillance as the most common cause of heart failure (Public Health Agency of Canada [PHAC], 2018; Chapter 17).
- **Hypertension:** years of high afterload thicken and stiffen the ventricle (Chapter 19).
- **Valve disease:** narrowed or leaking valves overload the chambers (section 18.5).
- **Cardiomyopathies and myocarditis:** diseases of the muscle itself, some of them inherited (section 18.7).
- **Dysrhythmias:** a persistently fast or irregular rhythm reduces filling and output (section 16.6).
- **Toxins:** heavy alcohol use (section 18.7) and some cancer treatments. Damage from anthracycline chemotherapy is related to the total lifetime dose and is largely irreversible, whereas heart dysfunction linked to trastuzumab in early breast cancer is mostly reversible (Virani et al., 2016; Chapter 9).

Figure 18.1 A markedly raised jugular venous pressure: the distended external jugular vein (arrow) runs up the side of the neck. The face was masked by the photographer, and the Commons page records the person's consent. (credit: “Elevated JVP1” by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Compensation and Remodelling

When output falls, the body responds much as it would to blood loss: it tries to raise blood pressure and hold on to fluid. Two systems lead this response (Hartupee & Mann, 2017):

- The **sympathetic nervous system** speeds the heart, strengthens contraction and narrows blood vessels.
- The kidneys sense reduced flow and activate the **renin–angiotensin–aldosterone system (RAAS)**. Angiotensin II constricts arterioles, and aldosterone makes the kidneys keep sodium, with water following it.

A third system pushes the other way. Stretched heart muscle releases **natriuretic peptides**, hormones that promote sodium and water excretion and relax blood vessels (Ezekowitz et al., 2017). In established heart failure, however, their effect is outweighed.

In the short term, these responses keep blood pressure and organ flow steady. Kept up for months, they cause harm (Hartupee & Mann, 2017). Retained sodium and water raise preload until the lungs and tissues become congested. Narrowed arterioles raise afterload, so a weak ventricle must push against more resistance. A faster heart rate raises the heart's own oxygen demand. Angiotensin II, aldosterone and the stress hormones also act directly on the heart: muscle cells enlarge or die, and scar tissue builds up between them. This process, called **remodelling**, changes the ventricle's size, shape and function. In systolic failure, the chamber typically becomes larger, rounder and weaker, which lowers output further and keeps the cycle turning.

This cycle explains the treatment in section 18.3. The drugs that help people with a reduced ejection fraction live longer interrupt these systems: beta-blockers blunt sympathetic activity, RAAS blockers and mineralocorticoid receptor antagonists block angiotensin II and aldosterone, and neprilysin inhibition boosts the body's own natriuretic peptides (Hartupee & Mann, 2017; McDonald et al., 2021).

Classifying Heart Failure

Ejection fraction (EF) is the percentage of the blood in the left ventricle that is pumped out with each beat, usually measured by echocardiography (section 16.3). Canadian guidelines group patients by EF because the groups respond differently to drugs (Table 18.1).

Heart failure with reduced ejection fraction (HFrEF) means an EF of 40% or less (Bozkurt et al., 2021). When the EF of a person with HFrEF later rises above 40%, the condition is called **heart failure with improved ejection fraction (HFimpEF)**. The international definition requires a rise of at least 10 percentage points from baseline and a second measurement above 40% (Bozkurt et al., 2021). The person still has heart failure.

International documents divide an EF above 40% into **heart failure with mildly reduced ejection fraction (HFmrEF)**, 41% to 49%, and **heart failure with preserved ejection fraction (HFpEF)**, 50% or more (Bozkurt et al., 2021). The 2025 update from the Canadian Cardiovascular Society (CCS) and the Canadian Heart Failure Society (CHFS) joins these into one group, **heart failure with nonreduced ejection fraction (HFnrEF)**: heart failure symptoms and signs with an EF above 40%. The panel noted that patients across this range have similar clinical outcomes (Virani et al., 2025). This book uses the Canadian terms.

The **New York Heart Association (NYHA) functional class** describes how much symptoms limit daily activity (Guidelines and Protocols Advisory Committee [GPAC], 2023):

- **Class I:** no symptoms with ordinary activity.
- **Class II:** slight limitation; ordinary activity brings on symptoms such as breathlessness or fatigue.
- **Class III:** marked limitation; less than ordinary activity brings on symptoms, but the person is comfortable at rest.
- **Class IV:** symptoms at rest; any activity brings on symptoms.

A person's NYHA class can change from week to week as congestion comes and goes, whereas the EF category describes the underlying heart.

Table 18.1 Heart failure categories by ejection fraction and what they mean for treatment (Bozkurt et al., 2021; McDonald et al., 2021; Virani et al., 2025)

Category	Ejection fraction	What it means	Treatment focus
HF with reduced EF (HFrEF)	40% or less	The ventricle contracts weakly and is often enlarged	Four drug classes started early and adjusted by the prescriber: ARNI (or ACE inhibitor or ARB), beta-blocker, MRA and SGLT2 inhibitor; loop diuretic for congestion; devices for selected patients

Category	Ejection fraction	What it means	Treatment focus
HF with improved EF (HFimpEF)	Was 40% or less; now above 40% after a rise of at least 10 points	Pumping has partly recovered with treatment; heart failure is still present	Ongoing treatment and follow-up planned by the heart failure team; the 2025 Canadian update does not address this group specifically
HF with nonreduced EF (HFnrEF)	Above 40% (includes HFmrEF, 41% to 49%, and HFpEF, 50% or more)	The ventricle contracts but is often stiff and fills poorly; other conditions often drive symptoms	SGLT2 inhibitor and MRA; ARNI or glucagon-like peptide-1 (GLP-1) receptor agonist for selected patients; loop diuretic for congestion; control of blood pressure, AF and other conditions; beta-blockers are not indicated for HF itself in this group

Heart Failure in Canada

The Canadian Chronic Disease Surveillance System (CCDSS) tracks diagnosed heart failure among adults aged 40 and older. In 2012–2013, 669,600 adults in this age group were living with diagnosed heart failure (PHAC, 2018). From 2000–2001 to 2012–2013, the age-standardized rate of new diagnoses fell by 35%, from 8.1 to 5.3 per 1,000, while prevalence stayed close to 3.5%. In a given year, adults with heart failure were about six times as likely to die of any cause as adults without it. Prevalence was higher among men than women, rose with age in both, and the gap between the sexes narrowed with age (PHAC, 2018). More recently, Heart and Stroke Foundation of Canada (2022) reported that 750,000 people in Canada live with heart failure and that more than 100,000 are diagnosed each year.

Heart failure is also costly in hospital days: about 1 in 5 patients is readmitted within a month of discharge (Heart and Stroke Foundation of Canada, 2022). Many eligible patients in Canada do not take all the recommended medications, and fewer still reach target doses (Canadian Cardiovascular Society [CCS], 2022). Closing that gap is shared work, and nurses play a large part in it (section 18.4).

CANADIAN CONTEXT

Heart Failure Across Canada

Heart failure is not spread evenly across Canada. Among Métis citizens in Ontario, a population-based study of 2006 to 2011 data, commissioned by the Métis Nation of Ontario (MNO), found an adjusted heart failure prevalence of 5.1%, compared with 3.9% in the general Ontario population. Métis people with heart failure were hospitalized more often and had twice as many heart failure–related emergency department visits in the year after diagnosis (Atzema et al., 2015). The study was carried out under a data-sharing agreement with the MNO, and three of the authors worked for the MNO. When First Nations data are used, the First Nations principles of ownership, control, access and possession (OCAP®) apply (Chapter 2).

Differences like these come from structural causes, not from the people affected: colonial policies, unequal access to primary care, distance from specialist services, and higher rates of diabetes and hypertension driven by those same conditions (Chapter 2). Specialized heart function clinics are concentrated in larger centres. Provinces have tried to bridge the distance. In British Columbia, for example, primary care clinicians can phone a specialist for advice through the Rapid Access to Consultative Expertise (RACE) line and refer to heart function clinics (GPAC, 2023). Nurses in rural, remote and northern settings often carry much of the monitoring and teaching between visits (section 18.4).

18.2 Recognizing and Managing Worsening Heart Failure

Signs of Congestion and Low Output

Worsening heart failure shows up in two ways: too much fluid in the wrong places (congestion) and too little blood flow to the organs (low output) (Table 18.2). A large European registry used a simple bedside version of this idea. Congestion was present with any of these: crackles, edema of both legs, a JVP above 6 cm, an enlarged liver or a positive hepatojugular reflux. Low perfusion was marked by cold extremities, low urine output or confusion (Chioncel et al., 2019).

Breathlessness is usually the first symptom. It starts with exertion and, as congestion builds, comes on with less activity. **Orthopnea** is breathlessness when lying flat that eases on sitting up, because lying down returns more blood to an overloaded heart. The nurse asks how many pillows the patient sleeps on and whether this has changed. **Paroxysmal nocturnal dyspnea (PND)** is waking from sleep suddenly short of breath and needing to sit up or go to a window for air. A dry cough at night can be an early sign.

On examination, the nurse listens for crackles, which start at the lung bases and climb as congestion worsens (Chapter 12). The nurse also listens for a third heart sound (S3) and measures the JVP (section 16.2). Edema (Figure 3.1) collects where gravity pulls it: the ankles and shins when the patient is up, and the sacrum and back of the thighs when the patient is in bed. Weight gain from retained fluid often comes before visible edema, which is why daily weights matter. Right-sided congestion can cause a full, tender abdomen, ascites, nausea and poor appetite.

Low output is quieter and easier to miss: fatigue, weakness, cool hands and feet, slow capillary refill, new confusion, and less urine. Blood pressure may fall or stay normal while the heart rate climbs.

Colour changes look different on different skin tones. On darker skin, cyanosis may show as grey or whitish lips and tongue, with a bluish tinge in the conjunctivae, palms, soles and nail beds; pallor can make very dark skin look ashen grey (Pusey-Reid et al., 2023). The nurse inspects mucous membranes and conjunctivae in good natural or halogen light, compares with an unaffected area, and never relies on sight alone. Skin temperature, capillary refill and oxygen saturation complete the picture (Chapter 12; section 16.2). Edema is assessed by pressing and feeling for pitting, as described in section 16.2, rather than by colour.

Table 18.2 Signs of left-sided congestion, right-sided congestion and low output (Chioncel et al., 2019; Ezekowitz et al., 2017)

Problem	What the nurse sees or hears	Why it happens
Left-sided congestion	Breathlessness with exertion, then at rest; orthopnea; paroxysmal nocturnal dyspnea; cough; crackles; falling oxygen saturation; S3	High pressure in the left atrium and pulmonary veins pushes fluid into lung tissue and alveoli; lying flat returns more blood to the heart
Right-sided congestion	Raised JVP; edema of the legs, or of the sacrum in bed; weight gain; full, tender liver; ascites; bloating, nausea and poor appetite	High pressure in the systemic veins pushes fluid into tissues and congests the liver and gut
Low output	Fatigue and weakness; cool, pale or mottled skin; slow capillary refill; confusion; low urine output; rising heart rate; low or falling blood pressure	Too little blood reaches the brain, kidneys and skin; the body narrows vessels to protect the heart and brain

Tests

Natriuretic peptides, B-type natriuretic peptide (BNP) and N-terminal pro-BNP (NT-proBNP), help confirm or rule out heart failure when the cause of breathlessness is unclear (Ezekowitz et al., 2017; section 16.3). Results are reported in ng/L, which is numerically the same as pg/mL. In an acute setting, a BNP below 100 ng/L or an NT-proBNP below 300 ng/L makes heart failure unlikely, and a BNP above 400 ng/L makes it very likely. The NT-proBNP level that makes heart failure likely rises with age. In an outpatient setting, even a mildly raised result (BNP above 50 ng/L or NT-proBNP above 125 ng/L) calls for further investigation (GPAC, 2023).

Several factors change the result (Ezekowitz et al., 2017):

- **Higher levels:** older age, kidney dysfunction, anemia, lung disease, sepsis, and other heart conditions such as valve disease or ischemia.
- **Lower levels:** obesity, so a modest value in a person with obesity does not exclude heart failure as confidently.
- **Sacubitril/valsartan:** BNP is broken down by neprilysin, so it rises when neprilysin is blocked; NT-proBNP is not affected in the same way and is the peptide to follow in patients taking this drug (Ezekowitz et al., 2017; Novartis Pharmaceuticals Canada, 2026).

A raised peptide never replaces imaging (GPAC, 2023). **Echocardiography** confirms the diagnosis, measures EF and shows valve problems and wall motion, but treatment should not wait for it when heart failure is likely (GPAC, 2023). A 12-lead electrocardiogram (ECG) looks for AF, ischemia, old infarction and conduction problems (section 16.3). A chest X-ray is part of the initial work-up (GPAC, 2023); it can show congestion (Figure 18.2) and other causes of breathlessness, such as pneumonia.

Initial blood tests include a complete blood count, sodium, potassium, creatinine and estimated glomerular filtration rate (eGFR), thyroid-stimulating hormone, hemoglobin A1C and ferritin (GPAC, 2023). In acute heart failure, high-sensitivity troponin is measured on admission to look for an acute coronary syndrome (Ezekowitz et al., 2017; Chapter 17). Results use SI units: potassium

and sodium in mmol/L, creatinine in µmol/L, eGFR in mL/min/1.73 m² and hemoglobin in g/L; reference ranges vary by laboratory (Chapter 3).

Acute Decompensated Heart Failure and Pulmonary Edema

Acute heart failure is a new or worsening change in heart failure symptoms and signs, whether sudden or gradual, that calls for urgent treatment (Ezekowitz et al., 2017). Most hospital patients have **acute decompensated heart failure (ADHF)**, a worsening of known heart failure. Other presentations are acute pulmonary edema, isolated right ventricular failure and cardiogenic shock (McDonagh et al., 2021).



Figure 18.2 Chest X-ray in heart failure, labelled: an enlarged heart, upper-lobe vessels that are more prominent than usual, Kerley B lines from fluid in the lung tissue, and a small pleural effusion.

A trigger can often be found. In a large US registry, about 6 in 10 admissions had at least one; pneumonia or another respiratory illness, ischemia and dysrhythmias were the most frequent. Uncontrolled hypertension, worsening kidney function and not following the medication or diet plan also played a part (Fonarow et al., 2008). Nonsteroidal anti-inflammatory drugs (NSAIDs) blunt diuretics and can harm the kidneys (GPAC, 2023). Finding and treating the trigger is part of the plan.

Acute pulmonary edema is an emergency in which fluid floods the alveoli. The patient is severely breathless, sits bolt upright, is often anxious and sweaty, and has crackles throughout the chest and a falling oxygen saturation. The nurse:

- stays with the patient and calls for help (rapid response; Chapter 6);
- sits the patient upright;
- gives oxygen if saturation is below the target range, titrated to that target (Chapter 12);
- secures intravenous (IV) access and gives an IV loop diuretic as ordered;
- prepares for non-invasive ventilation if the team orders it (Chapter 15).

Opioids are not given routinely (McDonagh et al., 2021).

After the emergency, care follows the clinical judgment model (CJMM; Chapter 1, section 1.4):

- **Daily weight:** same scale, same time (usually morning, after voiding and before breakfast), similar clothing. The trend is the most practical bedside measure of fluid change.
- **Intake and output:** urine volume after each IV diuretic dose shows whether the drug is working.
- **Laboratory values:** diuretics waste potassium and magnesium, and low levels raise the risk of dysrhythmias (Chapter 3). The nurse also trends sodium and creatinine and reports changes.
- **Blood pressure and falls:** brisk diuresis can cause dizziness on standing. The nurse checks for orthostatic changes, keeps a commode or urinal close and helps the patient to the toilet promptly (Chapter 8).
- **Skin:** stretched, edematous skin tears and breaks down easily, so the nurse repositions the patient and protects the heels and sacrum (Chapter 35).
- **Fluid restriction:** applied only if ordered.

Before discharge, oral heart failure drugs are started or resumed and congestion is carefully cleared, with follow-up within 1 to 2 weeks (McDonagh et al., 2021). Patients who leave hospital still congested have higher mortality at 1 year (Chioncel et al., 2019; section 18.4).

Every nurse who sees deterioration acts and escalates at once; the registered practical nurse (RPN) consults the registered nurse (RN) as the patient's needs change (Chapter 1, section 1.3). Cues of **cardiogenic shock** include a falling blood pressure, rising heart rate, cool and clammy or mottled skin, new confusion, falling urine output and a rising lactate (Chapter 6). Signs of poor perfusion matter even before blood pressure falls (Chioncel et al., 2019). Rising respiratory rate, falling saturation despite oxygen and exhaustion signal respiratory failure (Chapter 15).

CLINICAL JUDGMENT

Breathless at 0300

Names and details are fictional; this is a composite story.

Mrs. Lucille Arsenault, 84, has HFrEF (EF 30%) and was admitted two days ago with a urinary tract infection. IV normal saline has run at 100 mL/h since admission because she was eating little.

- **Recognize cues:** At 0300 she is sitting on the edge of the bed, unable to lie down. Respiratory rate 28 breaths/min, heart rate 114 beats/min and irregular, blood pressure 156/92 mm Hg, SpO2 88% on room air (95% at 2300), temperature 37.1 °C. Crackles reach the mid-lung fields on both sides. Her weight is 2.1 kg above admission. Evening potassium was 3.4 mmol/L.
- **Analyze cues:** Orthopnea, crackles, hypoxemia and weight gain point to fluid overload. Continuous IV fluid is a likely trigger; the irregular rhythm suggests AF.
- **Prioritize hypotheses:** Acute pulmonary edema from decompensated heart failure comes first; pneumonia and pulmonary embolism remain possible.
- **Generate solutions:** Restore oxygenation, get help, stop the fluid load, start decongestion, identify the rhythm.
- **Take action:** The nurse stays, sits her upright, starts oxygen to target (Chapter 12) and calls the rapid response team. The SBAR (Situation, Background, Assessment, Recommendation) report (Chapter 6) names the infusion and asks for an immediate review. The team orders IV furosemide, a 12-lead ECG, potassium and magnesium.
- **Evaluate outcomes:** One hour later, SpO2 is 93% on 2 L/min, respiratory rate 22 breaths/min, and she has passed 650 mL of urine. The nurse plans a repeat potassium and an assisted walk to the commode.

GOING DEEPER

Warm or Cold, Wet or Dry

Required for RN students; optional for PN students.

A quick bedside profile sorts patients with acute heart failure by two questions. Is there congestion ("wet" or "dry")? Is perfusion adequate ("warm" or "cold")? Congestion was judged from crackles, edema of both legs, a raised JVP, an enlarged liver or hepatojugular reflux. Poor perfusion was judged from cold extremities, low urine output or confusion. In a European registry of 7,865 patients, 69.9% were warm and wet, 19.8% cold and wet, 9.9% warm and dry, and 0.4% cold and dry. In-hospital mortality rose from 2.0% (warm and dry) and 3.8% (warm and wet) to 9.1% (cold and dry) and 12.1% (cold and wet) (Chioncel et al., 2019).

- **Warm and wet:** the most common profile. The main need is decongestion, usually with IV loop diuretics; vasodilators are among the options the guideline describes.
- **Cold and wet:** congestion plus poor perfusion. These patients may be heading toward cardiogenic shock and need critical care assessment (Chapter 6).
- **Inotropes:** these drugs strengthen contraction. They are not used routinely when cardiogenic shock is absent (McDonagh et al., 2021).
- **Warm and dry:** compensated; the focus is optimizing oral therapy.

The profile also matters at discharge. In the same registry, 30.9% of survivors still had congestion when they left hospital, and they had higher 1-year mortality (Chioncel et al., 2019).

18.3 Medications and Devices

Drugs That Change the Course of HFrEF

The 2021 CCS/CHFS update defined a new standard of care for HFrEF. Four drug classes are recommended for most patients (McDonald et al., 2021):

- an **angiotensin receptor–neprilysin inhibitor (ARNI)**, sacubitril/valsartan, or an angiotensin-converting enzyme (ACE) inhibitor or angiotensin II receptor blocker (ARB) if an ARNI is not used;
- an evidence-based **beta-blocker**;
- a **mineralocorticoid receptor antagonist (MRA)**;
- a **sodium–glucose cotransporter 2 (SGLT2) inhibitor**.

The four classes are started early and adjusted in parallel rather than one after another (GPAC, 2023). The prescriber raises each dose step by step toward a target the patient tolerates. Many patients in Canada never reach full therapy (CCS, 2022), so the nurse's monitoring, reporting and teaching help each step happen safely.

What each class does:

- **ARNI:** sacubitril blocks neprilysin, the enzyme that breaks down natriuretic peptides, so their beneficial effects last longer; valsartan blocks angiotensin II (Novartis Pharmaceuticals Canada, 2026). ACE inhibitors and ARBs block angiotensin II's formation or action.
- **Beta-blockers:** slow the heart and shield it from the long-term effects of sympathetic stimulation.
- **MRAs:** block aldosterone, limiting sodium retention and scarring of heart muscle.
- **SGLT2 inhibitors:** make the kidneys excrete glucose and sodium. In adults with heart failure, they lower the risk of cardiovascular death and heart failure hospitalization (AstraZeneca Canada, 2025).

Relieving Congestion

Loop diuretics such as furosemide remove excess sodium and water. The CCS recommends them to control congestion and edema (Virani et al., 2025). They are not among the four classes that change the course of HFrEF. They relieve breathlessness and swelling, and the prescriber adjusts the dose to the patient's weight and symptoms.

HF With Nonreduced Ejection Fraction

The 2025 CCS/CHFS update gives these recommendations for symptomatic heart failure with an EF above 40% (Virani et al., 2025):

- an SGLT2 inhibitor, to reduce heart failure hospitalization (strong recommendation);
- an MRA, including the newer nonsteroidal MRA finerenone, to reduce hospitalization (strong recommendation);
- sacubitril/valsartan as a suggestion for patients at low risk of symptomatic low blood pressure (weak recommendation). The Canadian product monograph lists HFrEF as its indication (Novartis Pharmaceuticals Canada, 2026);
- an evidence-based glucagon-like peptide-1 (GLP-1) receptor agonist as a suggestion for patients with an EF of 45% or more and a body mass index of 30 kg/m² or more, to reduce hospitalization and improve quality of life (weak recommendation).

The update also carries forward earlier recommendations: candesartan may be considered (it is the preferred renin–angiotensin system blocker when an ARNI cannot be used), blood pressure is controlled (Chapter 19) and loop diuretics are used for congestion (Virani et al., 2025). Treating AF (section 16.6), obesity, diabetes (Chapter 22) and kidney disease (Chapter 27) is central, because these conditions often drive symptoms.

What the Nurse Monitors

Before giving heart failure drugs, the nurse checks blood pressure, heart rate, dizziness on standing and the most recent potassium, creatinine and eGFR. These are compared with the ordered parameters. When a value falls outside them, the nurse holds the dose only as ordered or per policy and reports it promptly, so the prescriber can adjust therapy rather than lose it.

- **ARNI, ACE inhibitor or ARB:** watch for low blood pressure, rising potassium and creatinine. **Angioedema** is swelling of the lips, tongue, face or throat. If it occurs, sacubitril/valsartan is stopped at once and never restarted, and the airway is an emergency. Sacubitril/valsartan must not be given until at least 36 hours after the last ACE inhibitor dose. It has not been studied in patients starting with a systolic pressure below 100 mm Hg, and low volume or sodium is corrected before the first dose (Novartis Pharmaceuticals Canada, 2026). A rise in creatinine of up to 30% is not unexpected after starting an ACE inhibitor or ARB; the nurse still reports it so the prescriber can judge whether it settles (GPAC, 2023).

- **MRA:** the main risk is **hyperkalemia** (Chapter 3). The 2025 CCS/CHFS update advises that spironolactone or eplerenone is not started when eGFR is below 30 mL/min/1.73 m² (finerenone, below 25), and that no MRA is started when potassium is above 5.0 mmol/L. Potassium and creatinine are checked within a week after an MRA is started or its dose is changed. Monitoring is closer during illnesses that dehydrate, such as vomiting or diarrhea (Virani et al., 2025).
- **Beta-blocker:** watch for slow heart rate, low blood pressure and fatigue, especially after a dose increase.
- **SGLT2 inhibitor:** teach that genital yeast infections are more likely and that genital itching or discharge or urinary symptoms should be reported (AstraZeneca Canada, 2025). These drugs also raise the risk of urinary tract infection, and a rare but dangerous infection of the perineum (Fournier's gangrene) requires urgent surgery, so pain, swelling or redness in the genital area with fever is reported at once. They are not recommended when the patient is volume depleted, which matters when loop diuretics are also working hard. A small early drop in eGFR is expected (GPAC, 2023). Ketoacidosis can occur even when blood glucose is not high. A temporary pause is considered on sick days with poor intake or fluid loss, and the drug is stopped at least 3 days ahead of major surgery when feasible (AstraZeneca Canada, 2025).
- **Loop diuretic:** trend weight, intake and output, potassium, magnesium, sodium and creatinine.
- **NSAIDs:** patients avoid them. They reduce the diuretic effect, can worsen kidney function and add to hyperkalemia with an MRA (GPAC, 2023).

The CCS names other drugs for patients with specific characteristics (McDonald et al., 2021). Ivabradine slows the heart rate in sinus rhythm. Hydralazine combined with isosorbide dinitrate dilates arteries and veins. Digoxin has a narrow safety margin: nausea, visual changes, a slow pulse and dysrhythmias signal toxicity, and low potassium or magnesium or kidney impairment raises the risk. Patients taking digoxin learn to check their pulse and to contact their provider if it is below 60 beats/min (Pharmascience, 2022).

MEDICATIONS

Heart Failure Drug Classes

- **ARNI:** sacubitril/valsartan. Check blood pressure, potassium and creatinine; at least 36 hours after the last ACE inhibitor dose; stop and get help for angioedema.
- **ACE inhibitors and ARBs:** for example ramipril and candesartan. Check blood pressure, potassium and creatinine; watch for angioedema and dizziness.
- **Beta-blockers:** bisoprolol and carvedilol. Check heart rate and blood pressure; fatigue may increase for a short time after a dose increase.
- **MRAs:** spironolactone and eplerenone (finerenone in HFnrEF). Check potassium and creatinine within a week after a start or dose change; avoid NSAIDs.
- **SGLT2 inhibitors:** dapagliflozin and empagliflozin. Teach about genital infections, sick-day pauses and signs of ketoacidosis; expect a small early drop in eGFR.
- **Loop diuretics:** furosemide. Daily weight, intake and output, potassium, magnesium, orthostatic blood pressure and fall precautions.
- **Other agents for selected patients:** ivabradine, hydralazine with isosorbide dinitrate, and digoxin. Before digoxin, check the apical pulse and potassium and watch for toxicity.

Sources: McDonald et al. (2021); Virani et al. (2025); Canadian product monographs.



Figure 18.3 Chest X-ray of a cardiac resynchronization pacemaker: the generator in the upper chest and three leads, one in the right atrium and one in each ventricle. (credit: "CRT-P-THWZ" by Th. Zimmermann/Wikimedia Commons, CC BY-SA 3.0 DE)



Figure 18.4 A left ventricular assist device: the pump draws blood from the left ventricle and returns it to the aorta; a driveline through the skin connects it to an external controller and batteries. (credit: "Ventricular assist device" by Madhero88/Wikimedia Commons, CC BY-SA 3.0)

Devices and Advanced Heart Failure

For selected patients with HFrEF, an implantable cardioverter-defibrillator (ICD) protects against sudden death from ventricular dysrhythmias. **Cardiac resynchronization therapy (CRT)** (Figure 18.3) paces both ventricles so they contract together, which can improve symptoms and EF (section 16.7).

When heart failure advances despite full therapy, a **left ventricular assist device (LVAD)** may be considered (Figure 18.4). This implanted pump moves blood from the left ventricle into the aorta, either as a bridge to heart transplant or as long-term support. Transplant is offered to a small number of carefully selected patients at specialized centres. Throughout, a palliative approach to care can run alongside active treatment, with advance care planning and symptom relief from early in the illness (Chapter 10).

18.4 Self-Management and Transitions

Most HF care happens at home. A person admitted with worsening HF usually goes home within days, and the following weeks carry a high risk of readmission. In HF, **self-care** means three linked activities: keeping the condition stable, watching for change, and responding when change appears. The nurse's teaching builds these skills from the first day of admission.

Daily Weights and an Action Plan

Fluid builds up before swelling or breathlessness is obvious, so a rising weight over a day or two is often the earliest cue of the congestion described in section 18.2. The nurse teaches the patient to weigh every morning after emptying the bladder and before breakfast, on the same scale, in about the same clothing, and to write the result down and compare it with the day before (Heart and Stroke Foundation of Canada [Heart & Stroke], n.d.). Heart & Stroke's patient guide tells people to call their health care provider if

their weight rises by more than 2 kg over 2 consecutive days or by more than 2.5 kg within a week. Some HF clinics set a different limit for an individual patient; the nurse teaches the limit written in that patient's plan.

An **action plan** is a written, personalized guide that tells the patient what to watch for and what to do. Heart & Stroke's guide organizes it in three colour zones (Heart & Stroke, n.d.):

- **Green (stable):** weight within the set limits; breathing, swelling and energy at the person's usual level.
- **Yellow (call the HF clinic or health care provider):** weight gain beyond the limit; more breathlessness than usual or needing extra pillows to sleep; more swelling of the feet, legs or abdomen; a dry cough; new dizziness; more fatigue; or vomiting or diarrhea that goes on for more than 2 days.
- **Red (call 9-1-1):** breathlessness at rest that does not settle, chest pain that rest or medicine does not relieve, a fast heartbeat that does not slow at rest, new confusion or fainting.

The nurse confirms that the patient owns a working scale, checks reading level, vision and preferred language (including French-language services), uses teach-back and includes a family caregiver. On a follow-up call, the nurse applies the Clinical Judgment Measurement Model (CJMM; section 1.4): recognizing a 2 kg rise plus new orthopnea as cues of early congestion and arranging prompt assessment.

Sodium, Fluids and Activity

Patients with HF were long told to follow a strict low-sodium diet, but the evidence for very strict limits is weak. The SODIUM-HF trial, an international randomized trial, assigned 806 adults with chronic HF to dietitian support aiming for less than 1,500 mg of sodium a day or to usual care (Ezekowitz et al., 2022). At 12 months, the combined rate of death, cardiovascular hospitalization and cardiovascular emergency visits did not differ significantly (about 15% versus 17%). The nurse therefore teaches an individualized plan: limiting high-sodium processed and restaurant foods, reading labels and working with a dietitian.

A fluid limit is not needed for everyone. The British Columbia HF guideline suggests one for people with symptoms or signs of fluid overload or who take diuretics, usually 1.5 to 2 L of total fluid a day (GPAC, 2023). The nurse teaches the limit in the patient's own plan and helps the patient count soups, ice and jelly as fluid.

Regular physical activity, balanced with rest, improves stamina and quality of life. Cardiac rehabilitation includes people with HF (Chapter 17). The patient stops and reports activity that brings on chest pain, marked breathlessness or dizziness.

Infections such as influenza can tip a stable patient into decompensation. The National Advisory Committee on Immunization (NACI) recommends yearly influenza vaccine for everyone 6 months of age and older without a contraindication, and lists adults with chronic health conditions among those at high risk (NACI, 2025). The nurse also checks that other vaccines recommended for the person's age and conditions, such as COVID-19 and pneumococcal vaccines, are up to date.

NSAIDs such as ibuprofen and naproxen blunt the effect of diuretics and can worsen kidney function (GPAC, 2023; section 18.3). The patient asks a pharmacist before buying any over-the-counter pain, cold or herbal product.

Leaving Hospital

Before the patient leaves, the nurse:

- completes medication reconciliation, comparing the home list, hospital orders and discharge prescriptions so the patient knows which drugs are new, changed or stopped;
- records the discharge weight as the patient's starting point for daily weights;
- gives a written action plan and confirms understanding with teach-back;
- confirms that a follow-up appointment within 1 to 2 weeks (section 18.2) and blood work for potassium and creatinine (section 18.3) are booked.

In an Ontario study of 34,519 adults discharged from emergency departments with HF between 2007 and 2014, only 47.1% saw a physician within 7 days; those seen within 7 days had lower 1-year mortality and fewer later hospital admissions than those first seen between days 8 and 30 (Atzema et al., 2018). Home care nursing, HF clinics and, in some regions, telemonitoring of weight, blood pressure and symptoms bridge this period.

Access is not equal. People in rural, remote and northern communities may live hours from an HF clinic or laboratory, which delays drug titration and potassium checks, and fresh, lower-sodium food costs more there. First Nations, Inuit and Métis patients may face long medical travel away from family and racism in health care, structural barriers described in Chapter 2. Nursing stations, virtual HF clinics, Indigenous patient navigators and culturally safe discharge planning help close these gaps.

A Palliative Approach

HF usually follows an unpredictable course: stable periods broken by sudden worsening, with a gradual overall decline. A **palliative approach** brings symptom relief, emotional support and planning into care early, alongside HF medicines and devices rather than in place of them (Chapter 10). The nurse assesses and treats breathlessness, fatigue, edema, pain, low mood and poor sleep, and supports caregivers.

Advance care planning helps the patient name a substitute decision-maker and discuss values and goals before a crisis (Chapter 1, section 1.5; Chapter 10). For a patient with an implantable cardioverter-defibrillator (ICD; section 16.7), planning includes whether to turn off the shock function near the end of life, when shocks can cause distress without changing the outcome. The nurse raises the topic, documents the patient's wishes and involves the cardiology and palliative care teams.

PATIENT EDUCATION

Daily Weights and Your Action Plan

- Weigh yourself every morning after you empty your bladder and before you eat breakfast.
- Use the same scale each day and wear about the same clothing.
- Write your weight on your chart or in an app and compare it with yesterday's.
- Call your heart failure clinic or health care provider if your weight goes up by more than 2 kg over 2 days in a row or by more than 2.5 kg within a week, or by the amount on your own plan.
- Also call if you are more short of breath, need more pillows to sleep, have more swelling, a new dry cough, new dizziness, or vomiting or diarrhea for more than 2 days.
- Call 9-1-1 if you cannot catch your breath at rest, have chest pain that does not go away, feel your heart racing at rest, become confused or faint.
- Bring your weight record and all your pill bottles to every appointment.
- Ask your pharmacist before taking any pain, cold or flu medicine, or any herbal product.

LIFESPAN CONSIDERATIONS

Older Adults With Heart Failure

- **Frailty:** many older adults with HF are frail; small changes in fluid or medicines can lead to falls, delirium or loss of independence (Chapter 8).
- **Atypical presentation:** worsening HF may appear as new confusion, a fall, poor appetite or reduced function rather than obvious breathlessness.
- **Polypharmacy:** older adults often take many drugs. The nurse reviews the full list, including over-the-counter products, at every transition.
- **Orthostatic hypotension and falls:** diuretics and other HF drugs can lower blood pressure on standing. The nurse checks lying and standing blood pressure, teaches the patient to rise slowly, and plans safe toileting when diuretics start working.
- **Hyponatremia and kidney function:** older adults are more prone to low sodium and changes in creatinine with diuretics; the nurse watches laboratory results and reports changes (Chapter 3).
- **Cognitive impairment:** memory problems make daily weights and complex regimens harder. Blister packs, simple written plans and caregiver involvement help.
- **Caregiver support:** caregivers need teaching, respite and a clear contact for questions.

18.5 Valvular Heart Disease

The four heart valves keep blood moving forward. When a valve is diseased, the heart must work harder, and over time this extra load can lead to HF, AF and sudden symptoms. In older adults, valve disease is common and easy to miss, because breathlessness and fatigue are often blamed on age.

Stenosis and Regurgitation

A valve can fail in two ways. In **stenosis**, the valve opening narrows and stiffens, so the chamber behind it must generate higher pressure to push blood through. This pressure load makes the muscle wall thicken. In **regurgitation** (also called insufficiency), the valve does not close fully and blood leaks backward. The chamber receiving the leak has to handle extra volume with every beat, so it gradually enlarges. A valve can have both problems at once.

Either disorder usually produces a murmur, heard with the stethoscope as described in section 16.2. Echocardiography confirms the diagnosis, measures severity and shows how the heart is coping (section 16.3). Decisions about repair or replacement are made by a **Heart Team** of cardiologists, cardiac surgeons, imaging specialists and nurses, together with the patient (Otto et al., 2021; Praz et al., 2025). Table 18.3 summarizes the common valve disorders.

Aortic Stenosis

Aortic stenosis is narrowing of the aortic valve that obstructs outflow from the left ventricle. In older adults the usual cause is gradual calcification of a valve that was once normal. A valve born with two leaflets instead of three (a bicuspid valve) tends to narrow at a younger age, and rheumatic heart disease is another cause.

Aortic stenosis may progress for years without symptoms while the left ventricle thickens to compensate. Once symptoms begin, they follow from a heart that cannot raise its output on demand:

- chest pain (angina), because the thickened muscle needs more oxygen than the coronary arteries can supply;
- fainting or near-fainting (syncope), often with exertion;
- breathlessness and other signs of HF.

New symptoms in a person with severe aortic stenosis are a signal to refer for valve replacement. No drug relieves the obstruction. The two options are **surgical aortic valve replacement (SAVR)**, an open-heart operation, and **transcatheter aortic valve implantation (TAVI)**, in which a collapsible valve is guided through an artery, usually the femoral artery, and expanded inside the diseased valve. The 2020 American College of Cardiology/American Heart Association (ACC/AHA) guideline favours SAVR for people younger than 65 with a long life expectancy, allows either approach between 65 and 80, and favours TAVI for people older than 80 (Otto et al., 2021). The 2025 European Society of Cardiology/European Association for Cardio-Thoracic Surgery (ESC/EACTS) guideline extends TAVI to anatomically suitable patients aged 70 or older with a three-leaflet valve, whatever their surgical risk, and keeps surgery as a key option for younger, lower-risk patients and for many with bicuspid valves (Praz et al., 2025). Both guidelines stress shared decision-making. For a patient with a very short life expectancy, the conversation includes palliative care. In Canada, TAVI is offered in larger cardiac centres, so rural and northern patients often travel for assessment and the procedure.

Nursing care of a patient with severe aortic stenosis centres on preload. Because the ventricle must push blood through a fixed narrow opening, it depends on adequate filling. Dehydration, bleeding, aggressive diuresis or drugs that dilate blood vessels (such as nitrates) can cause a sudden fall in blood pressure and syncope; the ACC/AHA guideline warns against abruptly lowering blood pressure in people with a narrowed valve (Otto et al., 2021). The nurse helps the patient change position slowly, monitors blood pressure closely after any new vasodilator or diuretic, and reports chest pain, syncope or new breathlessness at once.

Mitral Valve Disease

In **mitral regurgitation**, blood leaks back from the left ventricle into the left atrium with each contraction. It has two broad forms:

- **Primary (degenerative)** mitral regurgitation comes from disease of the valve itself, such as a floppy, prolapsing leaflet or a torn chord.

- **Secondary (functional)** mitral regurgitation occurs when the leaflets are normal but the left ventricle or atrium has enlarged, pulling the leaflets apart. It is common in HFrEF.

Sudden severe regurgitation, for example after rupture of a papillary muscle in myocardial infarction or destruction of a leaflet by endocarditis, causes abrupt pulmonary edema and shock, and needs urgent escalation (Chapter 6). For severe primary regurgitation, surgical repair is preferred; the 2025 ESC/EACTS guideline now recommends early repair even for some patients without symptoms, and supports **transcatheter edge-to-edge repair (TEER)**, a catheter-delivered clip that brings the leaflets together, for selected high-risk patients (Praz et al., 2025). For secondary regurgitation, HF medicines come first (section 18.3); TEER is then recommended for selected patients who remain symptomatic, to reduce HF hospitalizations and improve quality of life.

Mitral stenosis is narrowing of the mitral valve, and most often results from **rheumatic heart disease**: lasting valve damage after acute rheumatic fever, an immune reaction to a group A streptococcal throat infection. Blood backs up into the left atrium and lungs, causing breathlessness that worsens with exertion, fast heart rates or pregnancy. The enlarged left atrium favours AF, and AF with mitral stenosis carries a high risk of stroke (section 16.6).

Rheumatic heart disease is a disease of poverty and crowding. Worldwide, the World Health Organization (WHO) estimates that it affects about 55 million people and causes about 360,000 deaths a year, most of them in low- and middle-income countries; Indigenous and other marginalized communities are also affected (WHO, 2025). These are global figures; published national Canadian data are limited. In Canada, nurses most often meet rheumatic valve disease in adults who grew up where the disease is common. Prevention depends on prompt treatment of strep throat, adequate housing and, for people who have had rheumatic fever, long-term secondary prevention with long-acting penicillin injections every 3 to 4 weeks for many years (WHO, 2025). Barriers such as cost, distance and language can interrupt that prevention.

After Valve Replacement

Replacement valves are either mechanical or tissue. A **mechanical valve** is made of durable synthetic materials and can last a lifetime, but blood clots form on it unless the person takes an anticoagulant for life (Figure 18.5). A **bioprosthetic valve** (tissue valve) is made from animal tissue; it does not need lifelong anticoagulation but wears out over time and may later need a repeat procedure. The choice weighs age, bleeding risk, plans for pregnancy and the patient's preferences.



Figure 18.5 A mechanical heart valve shown in place in the heart (illustration). Clots can form on its surfaces, so lifelong anticoagulation is needed. (credit: "3D Medical Animation still shot Artificial Heart Valve" by Scientific Animations/Wikimedia Commons, CC BY-SA 4.0)

People with mechanical valves take warfarin, a vitamin K antagonist, adjusted to the **international normalized ratio (INR)**, a blood test that measures how long blood takes to clot. The ACC/AHA guideline sets a target INR of 2.5 for a current-generation mechanical aortic valve without added clotting risk factors, and 3.0 for a mechanical mitral valve or a mechanical aortic valve with risk factors or an older valve design (Otto et al., 2021). The cardiologist states each patient's target. Direct oral anticoagulants (DOACs), including dabigatran and the factor Xa inhibitors, are contraindicated with mechanical valves (Otto et al., 2021). After a bioprosthetic valve, the guideline supports low-dose ASA and, after surgical replacement, sometimes a few months of warfarin.

Care after SAVR follows the perioperative principles in Chapter 7 and the sternal care in Chapter 17. After TAVI, the nurse checks the femoral access site and distal pulses, as after percutaneous coronary intervention (Chapter 17), and watches the cardiac rhythm for new conduction problems (section 16.7). Every patient with a replacement valve has a lifelong higher risk of infective endocarditis, so daily oral hygiene and regular dental care are part of discharge teaching (section 18.6).

Table 18.3 Common valve disorders: causes, findings and treatment (Otto et al., 2021; Praz et al., 2025; WHO, 2025)

Disorder	Common causes	Key findings	Treatment
Aortic stenosis	Age-related calcification; bicuspid valve; rheumatic disease	Systolic murmur; angina, syncope with exertion, breathlessness; thick left ventricle on echocardiography	Valve replacement once severe and symptomatic (SAVR or TAVI, chosen with the Heart Team); careful volume and blood pressure management meanwhile
Aortic regurgitation	Bicuspid valve; enlarged aortic root; endocarditis; rheumatic disease	Diastolic murmur; gradual breathlessness; enlarged left ventricle	Monitoring with echocardiography; surgery when severe with symptoms or a weakening ventricle; urgent surgery if sudden
Primary mitral regurgitation	Prolapsing leaflet; torn chord; endocarditis; rheumatic disease	Systolic murmur; breathlessness; AF; sudden pulmonary edema if acute	Surgical repair preferred; TEER for selected high-risk patients
Secondary mitral regurgitation	Enlarged left ventricle or atrium, often with HFrEF	Murmur that may be soft; HF symptoms	HF medicines first; TEER for selected patients with persistent symptoms

Disorder	Common causes	Key findings	Treatment
Mitral stenosis	Rheumatic heart disease	Diastolic murmur; breathlessness worse with exertion or fast heart rate; AF; stroke risk	Rate control and anticoagulation for AF; balloon or surgical procedures when severe

CLINICAL SAFETY

Mechanical Valves and Anticoagulation

- Warfarin is lifelong with a mechanical valve. Missing doses raises the risk of valve thrombosis and stroke.
- INR checks are done on a regular schedule and more often when another medicine is started, stopped or changed, during illness, and after diet changes.
- Many drugs interact with warfarin, including some antibiotics, antifungals, amiodarone, NSAIDs and herbal products. The nurse checks every new order with the pharmacist.
- Sudden large changes in foods rich in vitamin K, such as leafy green vegetables, alter the INR. The goal is a steady intake, not avoidance.
- The nurse teaches the patient to report bleeding gums, nosebleeds, blood in the urine or stool, black stools, unusual bruising, severe headache or a fall with a head strike.
- A patient with a mechanical valve is never switched to a DOAC, even if a DOAC seems simpler; DOACs are contraindicated with mechanical valves (Otto et al., 2021). Any such order is questioned at once.
- Bridging and procedure planning, reversal and INR management in depth are covered in Chapter 19.

18.6 Infective Endocarditis

Infective endocarditis (IE) is infection of the inner lining of the heart, most often a heart valve or implanted material. It is uncommon but serious, and it needs weeks of treatment, a team approach and careful attention to the person's life outside hospital.

How It Develops and Who Is at Risk

Endocarditis starts where the endocardium is damaged or covered by foreign material. Platelets and fibrin collect on the rough surface, and bacteria in the bloodstream lodge there and multiply. The result is a **vegetation**, a mass of clot, bacteria and inflammatory cells. Vegetations destroy valve leaflets, causing regurgitation; spread into nearby tissue to form abscesses; and break off as infected emboli that travel to the brain, kidneys, spleen, limbs or, from right-sided valves, the lungs.

The 2023 Duke-International Society for Cardiovascular Infectious Diseases (Duke-ISCVID) criteria list the main predisposing conditions (Fowler et al., 2023):

- previous endocarditis;
- a prosthetic valve or previous valve repair;
- congenital heart disease;
- a valve that leaks or is narrowed more than mildly;
- an implanted cardiac device such as a pacemaker or ICD;
- hypertrophic obstructive cardiomyopathy;
- injection drug use.

Frequent access to the bloodstream, as with hemodialysis catheters and other central lines, also allows bacteria to enter.

In Ontario, a population-based study of 2006 to 2015 found that hospital admissions for endocarditis among people who inject drugs rose from a mean of 13.4 per quarter before late 2011 to 35.1 per quarter afterward, a rise that paralleled growth in hydromorphone prescribing (Weir et al., 2019). Structural factors shape this risk: an unpredictable drug supply, limited access to sterile equipment, unstable housing, criminalization and stigma that delays care. Harm reduction (Chapter 11) is part of endocarditis care.

Recognizing Endocarditis

The presentation ranges from a slow illness over weeks to a sudden, septic one. Cues include:

- fever (above 38.0 °C), chills, night sweats, fatigue, poor appetite and weight loss;
- a new murmur or a change in a known murmur;
- signs of HF from a newly leaking valve;
- embolic events: stroke symptoms, a cold painful limb, flank or left upper abdominal pain, or, with right-sided infection, cough, chest pain and breathlessness from septic lung emboli.

Figure 18.6 Janeway lesions on the palm of a man with staphylococcal endocarditis: small, flat, painless red spots. On darker skin they look purple to dark brown. (credit: "Janeway lesion" by Warfieldian/Wikimedia Commons, CC BY-SA 4.0)

Small signs in the skin, nails and eyes support the diagnosis, and the nurse looks for them in good light on every patient:

- **Splinter hemorrhages:** thin red-brown to dark lines under the nails. They are easier to see on pale nail beds; on darker skin the nurse checks every nail and compares with the person's usual nail colour.
- **Conjunctival hemorrhages or petechiae:** tiny red spots inside the lower eyelid. The conjunctiva is a useful site to inspect on all skin tones.
- **Janeway lesions:** painless, flat spots on the palms or soles that look red on lighter skin and purple to dark brown on darker skin (Figure 18.6).
- **Osler nodes:** small, painful, tender bumps on the pads of the fingers or toes, found by touch and by asking about pain.
- **Roth spots:** small retinal hemorrhages seen on eye examination.

Endocarditis can cause sepsis (Chapter 4). A falling blood pressure, rising respiratory rate, new confusion or sudden neurologic change means the nurse escalates at once (Chapter 6).

Diagnosis and Treatment



Figure 18.7 Echocardiogram showing a vegetation (arrow) on the tricuspid valve in infective endocarditis. (credit: "Endocarditis ultrasound" by Daisuke Koya, Kazuyuki Shibuya, Ryuichi Kikkawa and Masakazu Haneda; derivative work by Materialscientist/Wikimedia Commons, CC BY 2.0)

Blood cultures come first. Several separate sets are drawn before the first antibiotic dose, because cultures taken after antibiotics may not grow the organism (Otto et al., 2021). Growth of a typical organism in two or more separate sets is a major diagnostic criterion (Fowler et al., 2023). Transthoracic echocardiography is the first imaging test (Figure 18.7); transesophageal echocardiography (TEE) follows when the first study is negative but suspicion stays high, when a prosthetic valve or device leads are present, and before a switch from intravenous to oral antibiotics (Delgado et al., 2023; Otto et al., 2021). The **Duke-ISCVID criteria** combine microbiology, imaging and clinical findings to classify endocarditis as definite, possible or rejected (see the Going Deeper box in section 18.7).

Treatment is a long course of antibiotics chosen with infectious diseases specialists: commonly 2 to 6 weeks for a native valve and at least 6 weeks for a prosthetic valve. After about 2 weeks of inpatient intravenous therapy,

selected stable patients may finish treatment with oral antibiotics or with **outpatient parenteral antibiotic therapy (OPAT)**, once TEE shows no local spread (Delgado et al., 2023). Surgery is needed for HF caused by valve damage, infection that cannot be controlled, such as an abscess, or a large vegetation with a high risk of emboli.

For a person who uses drugs, admission is also a chance to treat substance use as a health condition. The 2023 ESC guideline recommends addiction treatment after endocarditis in people who inject drugs and a recovery plan developed with the patient (Delgado et al., 2023). The nurse uses person-first language, assesses and treats withdrawal and pain promptly, and advocates for an addiction medicine consultation and for starting or continuing opioid agonist treatment (Chapter 11). Whether a person finishes treatment with a peripherally inserted central catheter (PICC; Figure 18.8) and OPAT, or with oral step-down, is decided with the patient and the endocarditis team, taking housing and supports into account. Untreated withdrawal, pain and feeling judged are common reasons people leave before treatment ends. Preventing patient-directed discharge, and planning safely if it happens, is covered in Chapter 11.



Figure 18.8 A peripherally inserted central catheter (PICC) after removal at the end of two months of treatment, with its hub and securement dressing. (credit: "Peripherally inserted central catheter (PICC or PIC line) after use in a patient for two months 2018 The Netherlands" by Hansmuller/Wikimedia Commons, CC BY-SA 4.0)

Prevention

Daily oral hygiene and regular dental care reduce the bacteria entering the blood every day. Antibiotic prophylaxis before dental procedures is recommended only for people at high risk: those with previous endocarditis, a surgical or transcatheter prosthetic valve or valve repair with prosthetic material, certain congenital heart disease and ventricular assist devices (Delgado et al., 2023). The nurse teaches these patients to tell every dentist about their heart condition. For people who inject drugs, sterile supplies and safer-injection teaching help lower the risk of a first or repeat infection (Chapter 11).

PATIENT EDUCATION

Protecting Your Heart Valves

- Brush your teeth twice a day, floss, and see a dentist regularly.
- Tell every dentist and health care provider that you have a heart valve problem or a replacement valve.
- If your care team says you need antibiotics before dental work, take them exactly as directed.
- Look after your skin: clean cuts well and get help early for redness, swelling or pus.
- If you inject drugs, use new sterile equipment every time, clean the skin first, never share equipment, and ask about local harm reduction services.
- Call your health care provider if you have a fever, chills, night sweats or unusual tiredness that lasts more than a few days.
- Call 9-1-1 if you have sudden weakness, trouble speaking, or chest pain.

PRACTICE STORY

Six Weeks Is a Long Time

Names and details are fictional; this is a composite story.

Nurse: Chantal Pelletier, RN. Years in practice: 9. Setting: medical unit, Ontario.

Tyler was 24 and had been admitted with fever and a new murmur. His blood cultures grew *Staphylococcus aureus*, and the TEE showed a vegetation on his tricuspid valve. The plan was six weeks of intravenous antibiotics. When I came in on his second day, he had his coat on.

I sat down instead of standing at the door. I asked what was making it hard to stay. He said he was "dope sick," his last nurse had looked at him "like garbage," and he was sure we would kick him out the moment we found out he'd used. I told him that withdrawal and pain were things we treat, not punishments, and that I would get the team to see him that morning.

I called the hospitalist and asked for an addiction medicine consult. By noon, Tyler had started buprenorphine–naloxone with a plan for his pain. I paged the social worker about his housing and his dog, which was being looked after by a friend for only a week.

I worked with Sana, the RPN on our team. Tyler's condition had settled, and our unit assigns RPNs to patients like him once they are stable. Sana knew him from a previous admission and was skilled in caring for patients on long IV antibiotic courses. We agreed she would call me right away for any fever spike, new breathlessness or neurologic change, since septic emboli were a real risk.

At rounds I asked whether OPAT or an oral step-down could be options later if his housing came together, and the team agreed to look at it after his next echo. We also set aside a daily time for Tyler to call his friend and step outside with a staff member. Two weeks later he was still with us, asking about a clinic near home that could continue his buprenorphine–naloxone.

Reflect: What cues suggested Tyler might leave before treatment ended, and how did each response address them? Using authority, competence and context, what parts of Tyler's care could the RPN provide, and when should she consult the RN?

18.7 Pericarditis, Myocarditis and Cardiomyopathies

The heart's muscle and its surrounding sac can be inflamed or structurally abnormal. The 2025 ESC guideline groups pericarditis and myocarditis under one umbrella term, **inflammatory myopericardial syndrome**, because they share causes and often overlap (Schulz-Menger et al., 2025).

Acute Pericarditis

The pericardium is a two-layered sac around the heart with a small amount of lubricating fluid between the layers. In **pericarditis**, those layers become inflamed. Common causes include viral infection, unknown (idiopathic) causes, injury after myocardial infarction or cardiac surgery, autoimmune disease, kidney failure and cancer.

The typical symptom is sharp chest pain that worsens with a deep breath, coughing or lying flat, and eases when the person sits up and leans forward. A **pericardial friction rub**, a high-pitched scratching or grating sound heard best with the stethoscope diaphragm at the left lower sternal border while the patient leans forward, is a classic finding. The 2025 ESC guideline diagnoses pericarditis when typical chest pain is accompanied by at least one more finding: a friction rub, compatible ECG changes, a raised C-reactive protein (CRP), a pericardial effusion, or compatible findings on cardiac magnetic resonance imaging (MRI) (Schulz-Menger et al., 2025). ECG changes may include ST elevation across many leads (Figure 18.9); the guideline notes that ST elevation suggests some involvement of the heart muscle but does not change management. Because pericarditis can mimic acute coronary syndrome, the patient with chest pain is assessed for both (Chapter 17).



Figure 18.9 A 12-lead ECG in acute pericarditis, with ST elevation in many leads. Because pericarditis can mimic acute coronary syndrome, the patient with chest pain is assessed for both. (credit: "ECG Pericarditis" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

First-line treatment is ASA or an NSAID combined with colchicine (Schulz-Menger et al., 2025). Colchicine continues for months (at least 3 to 6) and is the last drug stopped once symptoms have settled. Corticosteroids are kept for people who do not respond to first-line treatment. Physical activity is restricted for an initial month and then adjusted to the individual. Pericarditis comes back in 15% to 30% of people, so teaching covers taking colchicine for the full course, reporting stomach upset or bleeding with NSAIDs, and returning if pain recurs.

Pericardial Effusion and Cardiac Tamponade

A **pericardial effusion** is extra fluid in the pericardial sac. Fluid that collects slowly can reach a large volume before it causes problems, because the sac stretches. Fluid that collects quickly, as with bleeding after cardiac surgery, trauma or a procedure, can be dangerous in small amounts.

Cardiac tamponade occurs when pressure in the sac squeezes the heart so that the ventricles cannot fill. Stroke volume and cardiac output fall, and the patient develops obstructive shock (Chapter 6). Cues include:

- breathlessness and tachycardia;
- low blood pressure;
- distended neck veins;
- muffled heart sounds;
- **pulsus paradoxus**, an exaggerated drop in systolic blood pressure during inspiration (see the Going Deeper box).

Low blood pressure, distended neck veins and muffled heart sounds together form **Beck's triad**, but all three may be absent, especially when tamponade develops from a medical cause (Roy et al., 2007). Tamponade is an emergency. The nurse who suspects it calls the rapid response team at once, stays with the patient, monitors vital signs continuously and prepares for urgent bedside echocardiography and drainage of the fluid by needle (**pericardiocentesis**) or surgery. Because the heart depends on filling, the nurse questions any order that would reduce preload, such as a diuretic or nitrate, until the team reassesses.

Myocarditis

Myocarditis is inflammation of the heart muscle. Viral infection is a common cause; others include immune and autoimmune disease, toxins and some medicines, including the immune checkpoint inhibitors used in cancer care (Chapter 9). Presentations vary widely: chest pain that resembles a heart attack, new HF, palpitations and dysrhythmias, or, rarely, fulminant illness with cardiogenic shock or sudden death. A recent flu-like illness is a common clue.

The 2025 ESC guideline recommends inflammatory markers, troponin, BNP or NT-proBNP and echocardiography for every patient with suspected myocarditis, and cardiac MRI to confirm the diagnosis (Schulz-Menger et al., 2025). Endomyocardial biopsy is reserved for high-risk presentations, such as acute HF or cardiogenic shock. The guideline advises hospital admission for all patients with myocarditis. Care is supportive: continuous cardiac monitoring, HF medicines when the ventricle is weak (section 18.3), treatment of dysrhythmias, and a period without strenuous exercise set by the cardiologist. Corticosteroids are not a routine first treatment.

Rare cases of myocarditis or pericarditis have followed mRNA COVID-19 vaccines, more often in males aged 12 to 29 years, after a second dose and usually within a week. Most people recover quickly with conservative treatment, and the risk with updated vaccine formulations is considerably lower (PHAC, 2026).

Cardiomyopathies

A **cardiomyopathy** is a disease of the heart muscle itself, not explained by coronary disease, hypertension or valve disease alone.



Figure 18.10 A normal heart compared with hypertrophic cardiomyopathy (thickened muscle) and dilated cardiomyopathy (enlarged chamber with thin, stretched muscle). (credit: "Illustration of an enlarged heart (Cardiomegaly)" by myUpchar/Wikimedia Commons, CC BY-SA 4.0)

- **Dilated cardiomyopathy:** the left ventricle enlarges and contracts weakly. Causes include inherited gene variants, alcohol, some cancer drugs, previous myocarditis and pregnancy. It presents as HFrEF and is treated as described in section 18.3, with devices as needed (section 16.7) (Figure 18.10).
- **Hypertrophic cardiomyopathy:** the ventricular wall thickens abnormally. It is a common inherited heart disease, often passed on in an autosomal dominant pattern through variants in sarcomere genes, although a family history is not always present (Ommen et al., 2024). In some people, the thick wall blocks outflow from the left ventricle (obstructive hypertrophic cardiomyopathy). That obstruction changes with heart rate, blood pressure, fluid status, activity, food, alcohol and medicines, so health advice includes staying well hydrated. Symptoms include breathlessness, chest pain, palpitations and fainting with exertion. Assessing the risk of sudden cardiac death is central to care and guides decisions about an ICD. First-degree relatives are offered screening with an ECG, echocardiography and, where available, genetic testing. A blanket ban on exercise is not recommended; activity is planned through shared decision-making (Ommen et al., 2024).
- **Restrictive cardiomyopathy:** stiff ventricles fill poorly, causing HF with a nonreduced ejection fraction. A key cause is **cardiac amyloidosis**, in which misfolded proteins, often transthyretin, deposit in the heart. Transthyretin amyloidosis may be inherited or may develop with age, so it should be considered in older adults with HF and thick ventricular walls. Tafamidis, a drug that stabilizes transthyretin, is authorized in Canada for adults with transthyretin amyloid cardiomyopathy, wild-type or inherited, to reduce cardiovascular death and cardiovascular hospitalization (Health Canada, n.d.).
- **Takotsubo (stress) cardiomyopathy:** sudden, temporary weakness of the left ventricle, set off in most cases by an emotional or physical stress. At first it can look exactly like a myocardial infarction, both in symptoms and in ECG and troponin changes (Ghadri et al., 2018).

Table 18.4 compares these conditions.

Table 18.4 Pericarditis, tamponade, myocarditis and the cardiomyopathies compared (Ommen et al., 2024; Roy et al., 2007; Schulz-Menger et al., 2025)

Condition	What happens	Key findings	Main treatment	Nursing focus

Condition	What happens	Key findings	Main treatment	Nursing focus
Acute pericarditis	Inflamed pericardial layers	Sharp chest pain eased by sitting forward; friction rub; ECG changes; raised CRP	ASA or NSAID plus colchicine; activity restriction	Pain and rub assessment; rule out acute coronary syndrome; teach full colchicine course; recurrence
Cardiac tamponade	Fluid under pressure stops ventricles filling	Hypotension; distended neck veins; muffled heart sounds; tachycardia; pulsus paradoxus	Urgent drainage by pericardiocentesis or surgery	Recognize early; call rapid response; continuous monitoring; avoid lowering preload
Myocarditis	Inflamed heart muscle	Chest pain; raised troponin; HF or dysrhythmias; MRI changes	Supportive care; HF medicines; dysrhythmia treatment	Cardiac monitoring; watch for HF and shock; activity limits
Dilated cardiomyopathy	Enlarged, weak left ventricle	HFrEF signs; low ejection fraction	HF medicines and devices	HF self-care teaching; device care
Hypertrophic cardiomyopathy	Abnormally thick ventricular wall, sometimes blocking outflow	Breathlessness; exertional fainting; family history; murmur	Beta-blocker or nondihydropyridine calcium channel blocker for obstruction symptoms; ICD when indicated	Hydration; family screening; sudden death risk
Cardiac amyloidosis (restrictive)	Protein deposits stiffen ventricles	HF with nonreduced ejection fraction; thick walls in an older adult	HF symptom care; tafamidis for transthyretin type	Fluid balance; gentle diuresis; falls and orthostatic hypotension
Takotsubo cardiomyopathy	Sudden stress-triggered left ventricular weakness	Mimics acute coronary syndrome	Supportive care; HF medicines while recovering	Monitoring; emotional support

GOING DEEPER

Tamponade, Pulsus Paradoxus and the Duke Criteria

Required for RN students; optional for PN students.

Systolic blood pressure normally falls slightly on inspiration. In tamponade, the right ventricle fills more on inspiration and, inside a tight sac, pushes the septum toward the left ventricle, so left-sided output drops further. To measure pulsus paradoxus, the nurse uses a manual cuff while the patient breathes normally, deflates slowly from above systolic pressure, and notes the pressure at which Korotkoff sounds are first heard, only during expiration. Deflation continues until sounds are heard with every beat; the difference between the two pressures is the pulsus paradoxus. When an effusion is present, a pulsus paradoxus above 10 mm Hg raises the likelihood of tamponade, although echocardiography is needed to confirm it (Roy et al., 2007).

The 2023 Duke-ISCVID criteria (Fowler et al., 2023) classify endocarditis using major and minor criteria:

- **Major:** a typical organism grown from two or more separate blood culture sets (three or more for organisms that rarely cause endocarditis), or certain molecular tests; imaging showing a vegetation, new valve leak or prosthetic valve separation; or endocarditis seen at surgery.
- **Minor:** a predisposing condition; temperature above 38.0 °C; embolic signs (such as arterial emboli, conjunctival hemorrhages, Janeway lesions); immune signs (Osler nodes, Roth spots, glomerulonephritis); or microbiology short of a major criterion.
- **Definite** endocarditis: two major, one major and three minor, or five minor criteria. **Possible:** one major and one minor, or three minor.

SCOPE IN PRACTICE

IV Diuretics, Telemetry and PICC Lines

the College of Nurses of Ontario's (CNO's) Scope of Practice standard asks every nurse to consider authority, competence and context (Chapter 1, section 1.3). Employer policy and province or territory matter.

- **Authority:** RNs and RPNs both have authority to give an ordered IV diuretic and to care for a PICC. Where a specific activity is restricted, the employer's policy sets the limit.

- **Competence:** interpreting telemetry rhythms, giving IV push medicines and managing OPAT infusions require education and practice. A nurse who lacks the competence seeks it or hands the task to a colleague who has it.
- **Context:** the patient's condition and the supports available matter. Many employers assign patients whose condition is stable and expected to remain so to RPNs; this is an employer practice, not a CNO rule. When a patient with HF or endocarditis needs more frequent assessment, rapid changes in treatment or complex decision-making, the RPN consults the RN, and care may be shared or transferred.
- **Deterioration:** any nurse who notices increasing breathlessness, a falling blood pressure, new confusion, a new rhythm on the monitor or signs of tamponade acts at once and escalates through rapid response (Chapter 6).
- **OPAT and PICC lines at home:** home care nurses teach patients and families line care and infusion, and follow the agency's policies and the prescriber's orders.

Chapter 18 Summary

Introduction

- Heart failure is a syndrome in which a heart problem causes symptoms and signs, supported by raised natriuretic peptides or evidence of congestion.
- Heart failure is one of the top reasons for hospital admission in Canada, and about 1 in 5 patients is readmitted within a month.
- The chapter also covers valvular heart disease, endocarditis, pericarditis, myocarditis and the cardiomyopathies.

18.1 Heart Failure: How It Develops

- Systolic dysfunction is weak contraction; diastolic dysfunction is poor filling of a stiff ventricle.
- Left-sided failure congests the lungs; right-sided failure congests the systemic veins; left-sided failure is the usual cause of right-sided failure.
- Sympathetic and RAAS activation support output at first but cause sodium and water retention, higher afterload and remodelling over time.
- Canadian guidelines use HFrEF (EF 40% or less), HF with improved EF and HF with nonreduced EF (above 40%); NYHA class describes symptom limits.
- About 670,000 Canadians aged 40 or older had diagnosed heart failure in 2012–2013; Métis people in Ontario had higher prevalence and hospitalization.

18.2 Recognizing and Managing Worsening Heart Failure

- Congestion shows as breathlessness, orthopnea, PND, crackles, a raised JVP, edema and weight gain; low output as fatigue, cool skin, confusion and low urine output.
- Cyanosis and pallor look different on darker skin; the nurse checks mucous membranes, temperature and capillary refill.
- In an acute setting, BNP below 100 ng/L or NT-proBNP below 300 ng/L makes heart failure unlikely; age, kidney function, obesity and sacubitril/valsartan affect results.
- Acute pulmonary edema is an emergency: stay, sit the patient up, give oxygen to target, call for help and give IV diuretics as ordered.
- Daily weights, intake and output, electrolytes, fall prevention and skin care guide ongoing care; cues of cardiogenic shock are escalated at once.

18.3 Medications and Devices

- Four drug classes change the course of HFrEF: ARNI (or ACE inhibitor or ARB), beta-blocker, MRA and SGLT2 inhibitor, started early and adjusted in parallel.
- Loop diuretics relieve congestion; in HFnrEF, SGLT2 inhibitors and MRAs are strongly recommended.
- The nurse checks blood pressure, heart rate, potassium and creatinine; watches for angioedema; and allows 36 hours between an ACE inhibitor and sacubitril/valsartan.

- MRAs need potassium and creatinine checks within 1 week; SGLT2 inhibitors need sick-day and genital hygiene teaching; NSAIDs are avoided.
- ICDs, CRT, LVADs and transplant help selected patients, with a palliative approach alongside.

18.4 Self-Management and Transitions

- Self-care in HF means keeping the condition stable, watching for change and acting on it; teaching starts on admission.
- Patients weigh daily after voiding and before breakfast and follow a written action plan; Heart & Stroke advises calling for a rise of more than 2 kg in 2 days or more than 2.5 kg in a week, or as the patient's plan states.
- Sodium teaching is individualized: the SODIUM-HF trial found that very strict restriction did not reduce clinical events. Fluid limits (often 1.5 to 2 L a day) are for selected patients.
- Annual influenza vaccine, other recommended vaccines, activity and cardiac rehabilitation, and avoiding NSAIDs support stability.
- Safe discharge includes medication reconciliation, an action plan and early follow-up; rural, remote and Indigenous patients face structural barriers to access.
- A palliative approach runs alongside HF treatment and includes advance care planning and discussion of ICD deactivation.

18.5 Valvular Heart Disease

- Stenosis obstructs forward flow and causes a pressure load; regurgitation causes backward leakage and a volume load.
- Aortic stenosis causes angina, syncope and HF; symptomatic severe disease is treated with SAVR or TAVI, chosen by the Heart Team with the patient.
- Patients with severe aortic stenosis depend on adequate preload; dehydration and vasodilators can cause sudden hypotension.
- Mitral regurgitation is primary or secondary; mitral stenosis usually results from rheumatic heart disease, a disease of poverty and crowding.
- Mechanical valves need lifelong warfarin with INR monitoring; DOACs are contraindicated with mechanical valves.

18.6 Infective Endocarditis

- Vegetations form on damaged or prosthetic valves and cause valve destruction, abscesses and emboli.
- Risk factors include previous endocarditis, prosthetic valves, congenital heart disease, cardiac devices and injection drug use; Ontario admissions for drug use–associated endocarditis have risen.
- Cues include fever, a new murmur, HF and embolic signs; skin, nail and eye signs are assessed carefully on every skin tone.
- Blood cultures are drawn before antibiotics; echocardiography and the 2023 Duke-ISCVID criteria guide diagnosis; treatment lasts weeks.
- Care for people who inject drugs is non-stigmatizing and harm-reduction-based, with treatment of withdrawal and opioid agonist treatment.
- Dental prophylaxis is limited to the highest-risk patients; oral hygiene matters for everyone.

18.7 Pericarditis, Myocarditis and Cardiomyopathies

- Acute pericarditis causes sharp chest pain eased by sitting forward and may cause a friction rub; first-line treatment is ASA or an NSAID with colchicine.
- Cardiac tamponade causes hypotension, distended neck veins, muffled heart sounds, tachycardia and pulsus paradoxus; the nurse escalates at once.
- Myocarditis ranges from chest pain to HF and shock; troponin, echocardiography and cardiac MRI support diagnosis.
- Hypertrophic cardiomyopathy is often inherited; care includes hydration, family screening and sudden death risk assessment.
- Cardiac amyloidosis and takotsubo cardiomyopathy are causes of HF that nurses should recognize.

Key Terms (60)

action plan: A written, personalized guide that tells a person with heart failure which signs to watch for and what to do, often organized in green, yellow and red zones.

acute decompensated heart failure (ADHF): Worsening of known heart failure that needs urgent treatment, usually in hospital.

acute heart failure: A sudden or gradual change in heart failure symptoms and signs that calls for urgent treatment.

acute pulmonary edema: An emergency in which fluid floods the alveoli, causing severe breathlessness and hypoxemia.

angioedema: Swelling of the lips, tongue, face or throat; an emergency that can follow ACE inhibitors, ARBs or an ARNI.

angiotensin receptor–neprilysin inhibitor (ARNI): A drug combining neprilysin inhibition with angiotensin II receptor blockade; sacubitril/valsartan.

aortic stenosis: Narrowing of the aortic valve that obstructs blood flow out of the left ventricle.

Beck's triad: Low blood pressure, distended neck veins and muffled heart sounds, a classic but often incomplete sign of cardiac tamponade.

bioprosthetic valve: A replacement heart valve made from animal tissue; it does not need lifelong anticoagulation but wears out over time.

cardiac amyloidosis: A restrictive cardiomyopathy in which misfolded proteins, often transthyretin, deposit in the heart muscle and stiffen it.

cardiac resynchronization therapy (CRT): Pacing of both ventricles so they contract together.

cardiac tamponade: Compression of the heart by fluid under pressure in the pericardial sac, preventing ventricular filling and causing obstructive shock.

cardiomyopathy: A disease of the heart muscle itself that is not explained by coronary disease, hypertension or valve disease alone.

diastolic dysfunction: A stiff ventricle that does not relax and fill normally, raising pressure behind it.

dilated cardiomyopathy: A cardiomyopathy in which the left ventricle enlarges and contracts weakly.

Duke-ISCVID criteria: The 2023 Duke-International Society for Cardiovascular Infectious Diseases criteria, which classify infective endocarditis as definite, possible or rejected using major and minor criteria.

ejection fraction (EF): The percentage of blood in the left ventricle pumped out with each beat, usually measured by echocardiography.

heart failure (HF): A clinical syndrome in which a structural or functional problem of the heart causes symptoms and signs, supported by raised natriuretic peptides or evidence of congestion.

heart failure with improved ejection fraction (HFimpEF): Heart failure in which a previously reduced ejection fraction has risen above 40% by at least 10 percentage points.

heart failure with mildly reduced ejection fraction (HFmrEF): An international term for heart failure with an ejection fraction of 41% to 49%.

heart failure with nonreduced ejection fraction (HFnrEF): The Canadian term for heart failure with an ejection fraction above 40%, combining HFmrEF and HFpEF.

heart failure with preserved ejection fraction (HFpEF): An international term for heart failure with an ejection fraction of 50% or more.

heart failure with reduced ejection fraction (HFrEF): Heart failure with an ejection fraction of 40% or less.

Heart Team: A multidisciplinary group, including cardiologists, cardiac surgeons, imaging specialists and nurses, that plans valve treatment with the patient.

hypertrophic cardiomyopathy: An often inherited cardiomyopathy in which the ventricular wall thickens abnormally and may block outflow from the left ventricle.

infective endocarditis (IE): Infection of the inner lining of the heart, usually a valve or implanted material.

inflammatory myopericardial syndrome: The 2025 ESC umbrella term for pericarditis and myocarditis, which share causes and often overlap.

international normalized ratio (INR): A standardized blood test of clotting time used to adjust warfarin.

left ventricular assist device (LVAD): An implanted pump that moves blood from the left ventricle into the aorta in advanced heart failure.

left-sided heart failure: Failure of the left ventricle, raising pressure in the pulmonary veins and causing lung congestion.

mechanical valve: A durable replacement heart valve made of synthetic materials that requires lifelong anticoagulation with warfarin.

mineralocorticoid receptor antagonist (MRA): A drug that blocks aldosterone, such as spironolactone or eplerenone; its main risk is hyperkalemia.

mitral regurgitation: Backward leakage of blood from the left ventricle into the left atrium through a mitral valve that does not close fully; primary when the valve itself is diseased and secondary when chamber enlargement pulls the leaflets apart.

mitral stenosis: Narrowing of the mitral valve, most often caused by rheumatic heart disease.

myocarditis: Inflammation of the heart muscle.

natriuretic peptides: Hormones (BNP and NT-proBNP) released by stretched heart muscle that promote sodium and water excretion; measured to help diagnose heart failure.

NYHA functional class: A four-level scale describing how much heart failure symptoms limit activity.

orthopnea: Breathlessness when lying flat that eases on sitting up.

outpatient parenteral antibiotic therapy (OPAT): Intravenous antibiotic treatment given outside hospital, at home or in a clinic.

palliative approach: Care that brings symptom relief, emotional support and advance care planning into the course of a chronic illness, alongside disease-directed treatment.

paroxysmal nocturnal dyspnea (PND): Waking from sleep suddenly short of breath and needing to sit up.

pericardial effusion: An abnormal collection of fluid in the pericardial sac.

pericardial friction rub: A scratching or grating sound produced by inflamed pericardial layers rubbing together.

pericardiocentesis: Removal of fluid from the pericardial sac with a needle.

pericarditis: Inflammation of the pericardium.

pulsus paradoxus: An exaggerated fall in systolic blood pressure during inspiration; when an effusion is present, a fall of more than 10 mm Hg suggests tamponade.

regurgitation: Backward leakage of blood through a valve that does not close fully.

remodelling: Changes in the size, shape and function of the heart caused by neurohormonal activation, cell loss and scarring.

renin–angiotensin–aldosterone system (RAAS): A hormone system activated by low kidney blood flow that constricts vessels and retains sodium and water.

rheumatic heart disease: Lasting heart valve damage after acute rheumatic fever, an immune reaction to group A streptococcal throat infection.

right-sided heart failure: Failure of the right ventricle, raising pressure in the systemic veins and causing edema, a raised JVP and organ congestion.

self-care: In heart failure, the daily activities of keeping the condition stable, watching for change and responding to it.

sodium–glucose cotransporter 2 (SGLT2) inhibitor: A drug that makes the kidneys excrete glucose and sodium; reduces heart failure hospitalization across ejection fraction categories.

stenosis: Narrowing and stiffening of a valve opening that obstructs forward blood flow.

surgical aortic valve replacement (SAVR): Open-heart surgery to replace the aortic valve.

systolic dysfunction: Weak contraction of the ventricle, so a smaller share of its blood is ejected with each beat.

takotsubo cardiomyopathy: Sudden, temporary weakness of the left ventricle, usually triggered by emotional or physical stress, that can mimic a myocardial infarction; also called stress cardiomyopathy.

transcatheter aortic valve implantation (TAVI): Placement of a replacement aortic valve through a catheter, usually inserted in the femoral artery.

transcatheter edge-to-edge repair (TEER): A catheter-delivered clip that joins the mitral valve leaflets to reduce regurgitation.

vegetation: A mass of clot, bacteria and inflammatory cells attached to a heart valve or other endocardial surface in infective endocarditis.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mr. Henri Tremblay (Questions 1–6): Mr. Henri Tremblay, 76, has HFrEF (EF 30%) and is on a medical unit after 3 days of increasing breathlessness. At 0600 the nurse finds him sitting upright, saying he slept in a chair. Respiratory rate 26 breaths/min, heart rate 108 beats/min, blood pressure 148/88 mm Hg, SpO2 89% on room air. Crackles reach the mid-lung fields. His weight is 2.4 kg higher than at his clinic visit 5 days ago, and both ankles have pitting edema.

1. [CORE] Which finding is the strongest cue that Mr. Tremblay's left-sided congestion is worsening?

a. Resting heart rate of 108 beats/min, up from 84 yesterday
b. Pitting edema of both ankles extending up to the mid-shins
c. Crackles to the mid-lung fields with SpO2 89%
d. Blood pressure of 148/88 mm Hg

Answer: c — Crackles climbing to the mid-lung fields with low oxygen saturation show fluid in the lungs from high left-sided pressure (c) (section 18.2, Table 18.2). A rising heart rate (a) is nonspecific; it can come from anxiety, fever, AF or low output. Ankle and shin edema (b) reflects right-sided or systemic venous congestion, not the lungs. A blood pressure of 148/88 mm Hg (d) is a possible trigger to note but is not itself a sign of lung congestion.

2. [CORE] Which explanation best fits Mr. Tremblay's need to sleep in a chair?

a. Lying flat sends more blood to an overloaded heart, raising lung pressure.
b. Sitting up slows his heart rate and lowers the oxygen demand of the heart muscle.
c. A chair relieves the ankle edema that builds up when he lies flat in bed.
d. Lying flat presses the congested liver up against the diaphragm and compresses the lungs.

Answer: a — Orthopnea occurs because lying flat returns more venous blood to a heart that cannot handle it, raising pulmonary venous pressure (a) (section 18.2). Sitting up does not reliably slow the heart (b). Sitting in a chair lets edema collect in the legs rather than relieving it (c). Liver congestion (d) causes abdominal fullness, not orthopnea.

3. [CORE] The nurse considers several possible problems. Which should be addressed first?

a. Risk of falls related to nocturia and new diuretic therapy
b. Knowledge gap about the sodium plan and daily weights at home
c. Risk of pressure injury from ankle edema
d. Impaired gas exchange from pulmonary congestion

Answer: d — Hypoxemia from fluid in the lungs threatens oxygen delivery now and comes first (d) (section 18.2; Chapter 1, section 1.4). Fall risk (a) and skin risk (c) are real but less urgent than the airway and breathing. Teaching (b) waits until he is stable (section 18.4).

4. [CORE] What is the nurse's first action?

a. Restrict his fluids to 1 L for the day and explain the reason to him

b. Stay, keep him upright, give oxygen to target and call for help

c. Weigh him on the bed scale to confirm the size of the fluid gain

d. Give his regular morning dose of oral furosemide 2 hours early

Answer: b — The nurse stays, positions him upright, gives oxygen titrated to the target because SpO2 is below range, and escalates (b) (section 18.2; Chapters 6 and 12). Fluid restriction (a) is applied only when ordered and does not treat hypoxemia. A weight (c) is useful later but does not change the urgent plan. Changing the timing or route of a drug (d) needs an order; decongestion in this setting is usually IV, as ordered by the team.

5. [CORE] The physician orders IV furosemide. Thirty minutes after the dose, a registered practical nurse (RPN) caring for Mr. Tremblay finds him confused and clammy, with blood pressure 86/52 mm Hg. What should the RPN do?

a. Lower the head of the bed and recheck the blood pressure in 1 hour

b. Document the findings and report them at the end of the shift

c. Stay with him, call for immediate help and inform the RN

d. Give a 500 mL normal saline bolus to raise his blood pressure

Answer: c — New confusion, clammy skin and hypotension are cues of low output or cardiogenic shock; every nurse who notices deterioration escalates at once, and the RPN consults the RN as needs change (c) (section 18.2; Chapter 1, section 1.3; Chapter 6). Lying him flat and waiting an hour (a) worsens breathing and delays care. Reporting at shift end (b) is unsafe. A fluid bolus (d) needs an order and could worsen pulmonary congestion.

6. [CORE] After a rapid response assessment, Mr. Tremblay stabilizes. Which finding 6 hours later best shows that treatment of his congestion is working?

a. Urine output 1,400 mL, SpO2 94% on 2 L/min, crackles only at bases

b. Heart rate unchanged at 108 beats/min with blood pressure 140/84 mm Hg

c. Potassium 3.2 mmol/L after the second dose of IV furosemide

d. Ankle edema unchanged, but he says he feels a little less tired than at 0600

Answer: a — Good urine output after the diuretic, better oxygenation on less support and receding crackles show decongestion (a) (section 18.2). An unchanged fast heart rate (b) suggests the problem persists. Low potassium (c) is a diuretic adverse effect to report, not a sign of benefit. Edema in the legs (d) often clears more slowly and does not show improvement.

7. [CORE] A 79-year-old woman arrives at the emergency department breathless. Her NT-proBNP is 180 ng/L. How should the nurse interpret this result?

a. Heart failure is very likely and treatment should begin

b. Heart failure is an unlikely cause; another cause should be sought

c. The result cannot be interpreted, because age-specific cut-offs apply over age 75

d. She has HF with nonreduced ejection fraction

Answer: b — In the acute setting, an NT-proBNP below 300 ng/L makes heart failure unlikely, so another cause is sought (b) (section 18.2). A "very likely" result (a) requires a much higher, age-adjusted level. Age raises levels and changes the rule-in cut-offs, but the test is still useful (c). The peptide does not tell the EF category; echocardiography does (d).

8. [CORE] Which instruction about daily weights is correct for a patient with heart failure in hospital?

a. Weigh after breakfast and morning medications so the result reflects a normal day

b. Use whichever scale is closest on the unit, as long as it is calibrated each year

c. Weigh only on days when new edema is visible in the ankles or sacrum

d. Weigh each morning on the same scale after voiding, in similar clothing

Answer: d — Weighing at the same time, on the same scale, after voiding and in similar clothing makes the trend reliable (d) (section 18.2). Weighing after a meal (a) or on different scales (b) adds error. Weight gain from fluid often comes before visible edema, so waiting for edema (c) delays detection.

9. [CORE] A patient with HFrEF is starting spironolactone. Which result should the nurse report before the first dose is given?

a. Potassium 5.4 mmol/L

b. Sodium 138 mmol/L

c. Hemoglobin 128 g/L

d. eGFR 62 mL/min/1.73 m^2

Answer: a — An MRA is not started when potassium is above 5.0 mmol/L, because hyperkalemia is its main risk (a) (section 18.3). The sodium (b) and hemoglobin (c) values do not affect starting an MRA. Spironolactone is not started when eGFR is below 30 mL/min/1.73 m^2; 62 (d) does not prevent it.

10. [CORE] A patient with heart failure is going home on empagliflozin. Which statement shows the teaching was understood?

a. "I'll take an extra tablet on days when my ankles look more swollen than usual."

b. "I need to stop eating fruit because this pill raises my potassium."

c. "If I'm vomiting and can't keep fluids down, I'll pause it and call my clinic."

d. "Itching or discharge in the genital area is expected, so I won't mention it."

Answer: c — A pause of the SGLT2 inhibitor is considered on sick days with poor intake or fluid loss, and the patient contacts the clinic or prescriber (c) (section 18.3). Patients never change doses on their own (a). Raised potassium is the concern with MRAs and RAAS blockers, not SGLT2 inhibitors (b). Genital itching or discharge suggests a mycotic infection and should be reported (d).

11. [CORE] Which finding suggests right-sided rather than left-sided heart failure?

a. Paroxysmal nocturnal dyspnea that wakes the patient

b. Raised jugular venous pressure with ascites

c. Fine crackles heard at both lung bases

d. Breathlessness when lying flat in bed at night

Answer: b — A raised JVP and ascites come from high pressure in the systemic veins, the hallmark of right-sided failure (b) (section 18.1; Table 18.2). Paroxysmal nocturnal dyspnea (a), crackles (c) and orthopnea (d) all reflect fluid in the lungs from left-sided failure.

12. [CORE] An RPN on a medical unit is caring for a patient with heart failure who has been stable. At 1400, the patient's SpO2 has fallen from 95% to 89% on room air and new crackles are heard. What should the RPN do?

a. Recheck the SpO2 at the next scheduled vital signs
b. Ask the patient to walk in the hallway to clear the lungs
c. Wait for the RN to complete medication rounds before reporting
d. Stay with the patient, act within the RPN's competence and inform the RN promptly

Answer: d — Any nurse who notices deterioration acts and escalates at once; the RPN consults the RN as the patient's needs change, and employer policy guides the details (d) (section 18.2; Chapter 1, section 1.3). Waiting for scheduled checks (a) or until rounds end (c) delays care. Walking (b) increases oxygen demand in a hypoxemic patient.

13. [CORE] A patient says, "I wake up about two hours after falling asleep, gasping, and have to sit at the edge of the bed." How should the nurse document this?

a. Paroxysmal nocturnal dyspnea
b. Orthopnea
c. Obstructive sleep apnea with snoring
d. Exertional dyspnea

Answer: a — Waking suddenly from sleep short of breath and needing to sit up is paroxysmal nocturnal dyspnea (a) (section 18.2). Orthopnea (b) is breathlessness on lying flat that eases on sitting up, without waking from sleep. Obstructive sleep apnea (c) involves pauses in breathing, often with snoring, that a partner notices. Exertional dyspnea (d) occurs with activity.

14. [CORE] A patient has heart failure with an ejection fraction of 52%. Which term do the current Canadian guidelines use for this patient?

a. Heart failure with reduced ejection fraction
b. Heart failure with improved ejection fraction
c. Heart failure with nonreduced ejection fraction
d. Heart failure with mildly reduced ejection fraction

Answer: c — The 2025 CCS/CHFS update uses heart failure with nonreduced ejection fraction for heart failure with an EF above 40% (c) (section 18.1). Reduced EF (a) is 40% or less. Improved EF (b) applies only when a previously reduced EF has risen above 40%. Mildly reduced EF (d) is an international term for 41% to 49%; Canadian guidelines include it within HFnrEF.

15. [CORE] A patient taking ramipril is to switch to sacubitril/valsartan. The last ramipril dose was at 0800 today. When is the earliest the first dose of sacubitril/valsartan can be given?

a. At 2000 today
b. At 2000 tomorrow
c. At 0800 tomorrow
d. Immediately, because both drugs treat HFrEF

Answer: b — Sacubitril/valsartan must not be given until at least 36 hours after the last ACE inhibitor dose, because of the risk of angioedema; 0800 plus 36 hours is 2000 the next day (b) (section 18.3). Twelve hours (a), 24 hours (c) and no gap (d) are all too soon.

16. [CORE] Which findings suggest low cardiac output in a patient with heart failure? Select all that apply.

a. New confusion
b. Ascites
c. Cool hands and feet
d. Urine output falling over several hours
e. Weight gain of 2 kg in two days
f. Slow capillary refill

Answer: a, c, d, f — Confusion (a), cool extremities (c), falling urine output (d) and slow capillary refill (f) show too little blood reaching the brain, skin and kidneys (section 18.2, Table 18.2). Ascites (b) and rapid weight gain (e) are signs of congestion from fluid retention, not of low output.

17. [CORE] A patient with heart failure asks what to take for knee pain. Which response is best?

a. "Ibuprofen is fine as long as you take it with food."
b. "Naproxen is safer than ibuprofen for your heart."
c. "Any pain reliever you can buy without a prescription is safe to take alongside your heart medicines."
d. "Avoid anti-inflammatory pain relievers such as ibuprofen; ask your prescriber or pharmacist."

Answer: d — NSAIDs blunt diuretics, can worsen kidney function and add to hyperkalemia with an MRA, so patients avoid them and seek advice on alternatives (d) (section 18.3). Taking an NSAID with food (a) protects the stomach, not the heart or kidneys. Naproxen (b) is also an NSAID. Many nonprescription products contain NSAIDs (c).

18. [RN] A patient with acute heart failure has crackles, edema of both legs, cold hands and feet, new confusion and low urine output. Which profile does this describe?

a. Warm and wet
b. Warm and dry
c. Cold and wet
d. Cold and dry

Answer: c — Crackles and edema show congestion ("wet"); cold extremities, confusion and low urine output show poor perfusion ("cold") (c) (section 18.2, Going Deeper). Warm and wet (a) has congestion with adequate perfusion. Warm and dry (b) is compensated. Cold and dry (d) has poor perfusion without congestion.

19. [RN] For the patient in the previous question, which statement about inotropes is consistent with current guidance?

a. They are not used routinely unless cardiogenic shock is present.
b. They are first-line treatment for every patient admitted with acute decompensated heart failure.
c. They replace IV loop diuretics in patients who are warm and wet, because they work faster.
d. They are started on general medical units before discharge to help prevent readmission.

Answer: a — Inotropes are not recommended routinely in the absence of cardiogenic shock; a cold and wet patient needs critical care assessment, where they may be considered (a) (section 18.2, Going Deeper; Chapter 6). They are not first-line for all patients (b). Warm and wet patients need decongestion, usually with IV loop diuretics (c). Inotropes need critical care monitoring and do not prevent readmission (d).

20. [RN] A patient taking sacubitril/valsartan for 3 months has a rising BNP. The prescriber orders an NT-proBNP instead. What is the reason?

a. NT-proBNP is cheaper and faster to run in most Canadian hospital laboratories.

b. Neprilysin breaks down BNP, so sacubitril raises it; NT-proBNP is not affected.

c. BNP cannot be measured in patients with HFrEF.

d. Valsartan lowers NT-proBNP to normal, which confirms the drug is working.

Answer: b — BNP is a substrate of neprilysin, so blocking neprilysin raises BNP independent of heart failure status; NT-proBNP is the peptide to follow (b) (section 18.2). Cost and speed (a) are not the reason; the issue is the drug's effect on BNP. BNP can be measured in HFrEF (c). A normal NT-proBNP is not the treatment goal, and valsartan does not normalize it (d).

Case: Jordan (Questions 21–24): Jordan, 31, who injects opioids, is admitted to a medical unit with 5 days of fever, chills and fatigue. Temperature is 38.9 °C, heart rate 112 beats/min, blood pressure 108/64 mm Hg. A new murmur is heard. The admission orders include blood cultures and intravenous antibiotics.

21. [CORE] Which action should the nurse take first?

a. Give the first dose of the intravenous antibiotic, then draw the cultures.

b. Arrange transthoracic echocardiography.

c. Teach Jordan about dental hygiene.

d. Draw the ordered blood culture sets before the antibiotic.

Answer: d — Blood cultures are drawn before the first antibiotic dose because antibiotics can prevent the organism from growing (section 18.6). Giving the antibiotic first (a) risks a negative culture; it follows promptly after cultures. Echocardiography (b) is needed but does not come before cultures. Dental teaching (c) is important later, not first.

22. [CORE] While assessing Jordan's hands, the nurse notes thin dark red-brown lines under two fingernails. How should the nurse interpret this finding?

a. Expected trauma from manual work

b. Splinter hemorrhages, which support possible endocarditis

c. A sign of iron deficiency that needs a dietary referral

d. A normal variation in nail pigment that needs no follow-up

Answer: b — Thin red-brown to dark lines under the nails are splinter hemorrhages, a sign that supports endocarditis (section 18.6). Trauma (a) and normal pigment variation (d) should not be assumed in a febrile patient with a new murmur; the nurse compares with the person's usual nail colour. Iron deficiency (c) causes other nail changes, such as spoon-shaped nails.

23. [CORE] Jordan tells the nurse, "I'm getting sick from withdrawal and I'm going to leave." Which response by the nurse is most appropriate?

a. "Withdrawal is something we treat. I'll ask the team to see you now about medicine for it."

b. "If you leave, you will not be allowed to come back to this hospital."

c. "You should have thought about withdrawal before you used."

d. "I can't do anything about withdrawal until your infection has been fully treated."

Answer: a — Untreated withdrawal is a common reason people leave before treatment ends; prompt assessment, treatment and an addiction medicine consultation, including opioid agonist treatment, support staying (section 18.6; Chapter 11). Threats (b) and blame (c) are stigmatizing and increase the risk of patient-directed discharge. Withdrawal can be treated now (d), alongside the infection.

24. [CORE] On day 6, Jordan develops sudden weakness of the right arm and slurred speech. What should the nurse do first?

a. Document the findings and reassess in 1 hour.

b. Give acetaminophen and recheck the temperature.

c. Activate the stroke or rapid response protocol and stay with Jordan.

d. Ask Jordan whether he used any drugs on the unit before calling anyone.

Answer: c — Sudden focal neurologic signs in a person with endocarditis suggest an embolic stroke, an emergency that requires immediate escalation (section 18.6; Chapter 6). Waiting (a) delays time-sensitive treatment. Acetaminophen (b) does not address the cause. Questioning drug use (d) is not the priority and delays care.

25. [CORE] A patient with HF reports by phone that her weight has risen from 72.0 kg to 74.5 kg over the past 2 days and that she needed an extra pillow last night. What is the nurse's best action?

a. Arrange for the patient to be assessed by the HF team today.

b. Tell her to recheck her weight in 1 week.

c. Advise her to stop drinking fluids until her weight returns to normal.

d. Tell her to double her diuretic dose without consulting the prescriber.

Answer: a — A gain of more than 2 kg over two days plus new orthopnea are yellow-zone cues that call for prompt assessment by the HF team (section 18.4). Waiting a week (b) risks decompensation. Stopping all fluids (c) is unsafe and not part of the plan. Changing the dose without an order or a written plan (d) is unsafe.

26. [CORE] Which instruction about daily weights is correct?

a. Weigh yourself at any time of day as long as you do it daily.

b. Weigh yourself in the morning after you empty your bladder and before breakfast.

c. Weigh yourself after breakfast, wearing your shoes.

d. Weigh yourself once a week, using a different scale each time to compare readings.

Answer: b — Weighing each morning after voiding and before breakfast, on the same scale and in similar clothing, makes day-to-day changes meaningful (section 18.4). Varying the time (a), weighing after a meal in shoes (c) or weekly on different scales (d) adds error and misses early change.

27. [CORE] A patient with HF asks whether he must keep his sodium intake as low as possible. Which response reflects current evidence?

a. "You need to eat no sodium at all."

b. "Sodium doesn't matter in heart failure anymore."

c. "Very strict limits haven't been shown to prevent hospital stays, so we'll set a realistic goal with your dietitian."

d. "Sodium matters only if you also have high blood pressure, so we'll check that before setting any limit."

Answer: c — The SODIUM-HF trial found that targeting less than 1,500 mg a day did not significantly reduce death or cardiovascular hospital and emergency visits, so teaching is individualized (section 18.4). Zero sodium (a) is neither possible nor recommended. Sodium still matters (b, d), especially high-sodium processed foods.

28. [CORE] Which over-the-counter product should the nurse teach a patient with HF to avoid unless a prescriber approves it?

a. Acetaminophen

b. A saline nasal spray

c. A calcium supplement

d. Ibuprofen

Answer: d — NSAIDs such as ibuprofen blunt the effect of diuretics and can worsen kidney function, so people with HF avoid them (section 18.4). Acetaminophen (a), used as directed, does not have these effects. Saline spray (b) and calcium (c) are not linked to HF worsening in the same way, although the patient should still check with a pharmacist.

29. [CORE] An 84-year-old with HF is started on a loop diuretic. Which finding is the priority for the nurse to report?

a. A drop in systolic blood pressure from 128 to 98 mm Hg on standing, with dizziness

b. Increased urine output in the first few hours

c. A 0.5 kg weight loss the next morning

d. Mild thirst

Answer: a — Orthostatic hypotension with dizziness puts an older adult at high risk of falls and needs prompt reporting and a safety plan (section 18.4, Lifespan Considerations box). Increased urine output (b) and modest weight loss (c) are expected effects. Mild thirst (d) is common and less urgent.

30. [CORE] A patient with severe aortic stenosis is waiting for TAVI. Which new order should the nurse clarify with the prescriber before acting on it?

a. Daily weights before breakfast

b. Sublingual nitroglycerin as needed for chest pain

c. Continuous telemetry monitoring

d. A heart-healthy diet that is low in saturated fat and sodium

Answer: b — In severe aortic stenosis, the ventricle depends on adequate filling. Nitrates dilate blood vessels and can cause a sudden fall in blood pressure and syncope, and the ACC/AHA guideline warns against abruptly lowering blood pressure with a narrowed valve, so the nurse clarifies the order (section 18.5). Daily weights (a), telemetry (c) and a heart-healthy diet (d) do not pose this risk.

31. [CORE] A patient with a mechanical mitral valve asks to change from warfarin to "one of the new blood thinners that don't need blood tests." What is the nurse's best response?

a. "That's a good idea; I'll ask your provider to switch you."

b. "You can switch once your INR has stayed in your target range for a few months."

c. "Those drugs are not safe with a mechanical valve, so warfarin is still needed."

d. "You can take both drugs together for extra protection."

Answer: c — DOACs, including dabigatran and factor Xa inhibitors, are contraindicated with mechanical valves; warfarin with INR monitoring is required (section 18.5, Clinical Safety box). Options a and b would expose the patient to valve thrombosis. Combining anticoagulants (d) greatly increases bleeding risk without benefit.

32. [CORE] Which statement by a patient taking warfarin for a mechanical aortic valve shows correct understanding?

a. "I'll keep the amount of leafy greens I eat about the same each week."

b. "I'll stop eating all green vegetables."

c. "I'll take ibuprofen for my back pain."

d. "If I miss a dose, I'll take three tablets the next day to make up for it."

Answer: a — A steady intake of vitamin K–rich foods keeps the INR stable (section 18.5, Clinical Safety box). Avoiding all greens (b) is unnecessary and can make the INR unstable when intake changes. NSAIDs (c) increase bleeding risk. Tripling a dose (d) can cause a dangerously high INR; missed doses are managed as the prescriber directs.

33. [CORE] Two days after cardiac surgery, a patient becomes restless. Blood pressure has fallen from 118/70 to 84/66 mm Hg, heart rate is 128 beats/min, neck veins are distended and heart sounds are muffled. What should the nurse do first?

a. Give the scheduled furosemide.

b. Reposition the patient flat and recheck vital signs in 30 minutes.

c. Encourage deep breathing and coughing.

d. Call the rapid response team and stay with the patient.

Answer: d — Hypotension, distended neck veins, muffled heart sounds and tachycardia suggest cardiac tamponade, an emergency needing immediate escalation and drainage (section 18.7). A diuretic (a) lowers preload and could worsen shock. Waiting (b) delays care. Breathing exercises (c) do not address the cause.

34. [CORE] A patient with acute pericarditis is discharged on an NSAID and colchicine. Which teaching point is correct?

a. Stop taking the colchicine as soon as the chest pain has gone away completely, to avoid side effects.

b. Avoid strenuous activity for now; your team will tell you when to increase it.

c. Lying flat will relieve the pain.

d. Take the NSAID only if the pain becomes severe.

Answer: b — The 2025 ESC guideline restricts physical activity for an initial period, then individualizes it (section 18.7). Colchicine continues for months and is the last drug stopped (a), which helps prevent recurrence. Pain typically eases when sitting forward, not lying flat (c). The NSAID is given on a schedule as prescribed (d).

35. [CORE] An RPN caring for a stable patient receiving IV antibiotics for endocarditis notes a new fever of 39.2 °C, a respiratory rate of 26 breaths/min and new confusion. What should the RPN do?

a. Give acetaminophen and reassess at the end of the shift.

b. Wait for the RN to make rounds.

c. Document the findings for the next day's team.

d. Act at once to escalate, including rapid response, and inform the RN.

Answer: d — Every nurse who notices deterioration acts at once and escalates; the RPN also consults the RN as the patient's needs change (section 18.7, Scope in Practice box; Chapter 6). Treating the fever and waiting (a), waiting for rounds (b) or documenting only (c) delay care for possible sepsis.

36. [CORE] A nurse on a medical unit is asked to interpret a new telemetry rhythm but has not completed the unit's rhythm interpretation education. According to CNO's Scope of Practice standard, what should the nurse do?

a. Seek help from a colleague who has the competence and arrange the education.

b. Interpret the rhythm anyway, because nurses have authority to monitor patients.

c. Ignore the alarm until a physician arrives.

d. Refuse to care for any patient on telemetry.

Answer: a — Competence is one of the three considerations, with authority and context; a nurse who lacks it seeks help and gains it (section 18.7, Scope in Practice box). Authority alone (b) is not enough. Ignoring the alarm (c) is unsafe. Refusing all telemetry patients (d) does not address the immediate need.

37. [CORE] Which statements about hypertrophic cardiomyopathy should the nurse include when teaching a young adult who has just been diagnosed? Select all that apply.

a. "Your parents, siblings and children may be offered heart screening."

b. "It's important to stay well hydrated."

c. "Report any fainting, especially during exercise."

d. "You will never be able to exercise again."

e. "This condition is caused by a past viral infection."

f. "Your team will assess your risk of a dangerous heart rhythm."

Answer: a, b, c, f — First-degree relatives are offered screening (a); fluid status affects outflow obstruction, so hydration matters (b); exertional fainting is a warning sign (c); and sudden cardiac death risk assessment guides decisions about an ICD (f) (section 18.7). A blanket ban on exercise is not recommended (d); activity is planned through shared decision-making. The condition is usually inherited, not viral (e).

38. [RN] A nurse measures pulsus paradoxus in a patient with a known pericardial effusion. Korotkoff sounds are first heard during expiration only at 124 mm Hg and are heard with every beat at 108 mm Hg. How should the nurse interpret this?

a. Normal respiratory variation

b. A pulsus paradoxus of 16 mm Hg, supporting possible tamponade

c. A pulsus paradoxus of 8 mm Hg, ruling out tamponade

d. A measurement error, because the sounds should first appear at the same pressure throughout breathing

Answer: b — The difference between 124 and 108 mm Hg is 16 mm Hg; a value above 10 mm Hg when an effusion is present raises the likelihood of tamponade, and echocardiography confirms it (section 18.7, Going Deeper box). It is not normal variation (a). The calculation in (c) is wrong. Sounds normally appear at slightly different pressures during the breathing cycle (d).

39. [RN] Using the 2023 Duke-ISCVID criteria, which combination classifies a patient as having definite endocarditis?

a. One major criterion only

b. Three minor criteria

c. One major and one minor criterion

d. Two major criteria

Answer: d — Definite endocarditis requires two major, one major plus three minor, or five minor criteria (section 18.7, Going Deeper box). One major alone (a) is insufficient. Three minor (b) and one major plus one minor (c) classify endocarditis as possible.

40. [RN] Which finding counts as a major criterion in the 2023 Duke-ISCVID criteria?

a. Temperature of 38.6 °C

b. Osler nodes on the finger pads

c. Staphylococcus aureus grown from two separate blood culture sets

d. A history of injection drug use

Answer: c — A typical organism grown from two or more separate blood culture sets is a major microbiologic criterion (section 18.7, Going Deeper box). Fever above 38.0 °C (a), immunologic signs such as Osler nodes (b) and predisposing conditions such as injection drug use (d) are minor criteria.

References

AstraZeneca Canada. (2025). *Forxiga (dapagliflozin) tablets: Product monograph*. https://pdf.hres.ca/dpd_pm/00078565.PDF

Atzema, C. L., Austin, P. C., Yu, B., Schull, M. J., Jackevicius, C. A., Ivers, N. M., Rochon, P. A., & Lee, D. S. (2018). Effect of early physician follow-up on mortality and subsequent hospital admissions after emergency care for heart failure: A retrospective cohort study. *Canadian Medical Association Journal, 190*(50), E1468–E1477. https://doi.org/10.1503/cmaj.180786

Atzema, C. L., Khan, S., Lu, H., Allard, Y. E., Russell, S. J., Gravelle, M. R., Klein-Geltink, J., & Austin, P. C. (2015). Cardiovascular disease rates, outcomes, and quality of care in Ontario Métis: A population-based cohort study. *PLOS ONE, 10*(3), Article e0121779. https://doi.org/10.1371/journal.pone.0121779

Bozkurt, B., Coats, A. J. S., Tsutsui, H., Abdelhamid, M., Adamopoulos, S., Albert, N., Anker, S. D., Atherton, J., Böhm, M., Butler, J., Drazner, M. H., Felker, G. M., Filippatos, G., Fiuzat, M., Fonarow, G. C., Gomez-Mesa, J.-E., Heidenreich, P., Imamura, T., Jankowska, E. A., … Zieroth, S. (2021). Universal definition and classification of heart failure: A report of the Heart Failure Society of America, Heart Failure Association of the European Society of Cardiology, Japanese Heart Failure Society and Writing Committee of the Universal Definition of Heart Failure. *European Journal of Heart Failure, 23*(3), 352–380. https://doi.org/10.1002/ejhf.2115

Canadian Cardiovascular Society. (2022). *Heart failure* [Information sheet]. https://ccs.ca/wp-content/uploads/2022/08/CCS_Info_HF_Eng_v7.pdf

Chioncel, O., Mebazaa, A., Maggioni, A. P., Harjola, V.-P., Rosano, G., Laroche, C., Piepoli, M. F., Crespo-Leiro, M. G., Lainscak, M., Ponikowski, P., Filippatos, G., Ruschitzka, F., Seferovic, P., Coats, A. J. S., & Lund, L. H. (2019). Acute heart failure congestion and perfusion status: Impact of the clinical classification on in-hospital and long-term outcomes; insights from the ESC-EORP-HFA Heart Failure Long-Term Registry. *European Journal of Heart Failure, 21*(11), 1338–1352. https://doi.org/10.1002/ejhf.1492

Delgado, V., Ajmone Marsan, N., de Waha, S., Bonaros, N., Brida, M., Burri, H., Caselli, S., Doenst, T., Ederhy, S., Erba, P. A., Foldager, D., Fosbøl, E. L., Kovac, J., Mestres, C. A., Miller, O. I., Miro, J. M., Pazdernik, M., Pizzi, M. N., Quintana, E., … ESC Scientific Document Group. (2023). 2023 ESC Guidelines for the management of endocarditis. *European Heart Journal, 44*(39), 3948–4042. https://doi.org/10.1093/eurheartj/ehad193

Ezekowitz, J. A., Colin-Ramirez, E., Ross, H., Escobedo, J., Macdonald, P., Troughton, R., Saldarriaga, C., Alemayehu, W., McAlister, F. A., Arcand, J., Atherton, J., Doughty, R., Gupta, M., Howlett, J., Jaffer, S., Lavoie, A., Lund, M., Marwick, T., McKelvie, R., … Zieroth, S. (2022). Reduction of dietary sodium to less than 100 mmol in heart failure (SODIUM-HF): An international, open-label, randomised, controlled trial. *The Lancet, 399*(10333), 1391–1400. https://doi.org/10.1016/S0140-6736(22)00369-5

Ezekowitz, J. A., O'Meara, E., McDonald, M. A., Abrams, H., Chan, M., Ducharme, A., Giannetti, N., Grzeslo, A., Hamilton, P. G., Heckman, G. A., Howlett, J. G., Koshman, S. L., Lepage, S., McKelvie, R. S., Moe, G. W., Rajda, M., Swiggum, E., Virani, S. A., Zieroth, S., … Sussex, B. (2017). 2017 comprehensive update of the Canadian Cardiovascular Society guidelines for the management of heart failure. *Canadian Journal of Cardiology, 33*(11), 1342–1433. https://doi.org/10.1016/j.cjca.2017.08.022

Fonarow, G. C., Abraham, W. T., Albert, N. M., Stough, W. G., Gheorghiade, M., Greenberg, B. H., O'Connor, C. M., Pieper, K., Sun, J. L., Yancy, C. W., & Young, J. B. (2008). Factors identified as precipitating hospital admissions for heart failure and clinical outcomes: Findings from OPTIMIZE-HF. *Archives of Internal Medicine, 168*(8), 847–854. https://doi.org/10.1001/archinte.168.8.847

Fowler, V. G., Jr., Durack, D. T., Selton-Suty, C., Athan, E., Bayer, A. S., Chamis, A. L., Dahl, A., DiBernardo, L., Durante-Mangoni, E., Duval, X., Fortes, C. Q., Fosbøl, E., Hannan, M. M., Hasse, B., Hoen, B., Karchmer, A. W., Mestres, C. A., Petti, C. A., Pizzi, M. N., … Miro, J. M. (2023). The 2023 Duke-International Society for Cardiovascular Infectious Diseases criteria for infective endocarditis: Updating the modified Duke criteria. *Clinical Infectious Diseases, 77*(4), 518–526. https://doi.org/10.1093/cid/ciad271

Ghadri, J.-R., Wittstein, I. S., Prasad, A., Sharkey, S., Dote, K., Akashi, Y. J., Cammann, V. L., Crea, F., Galiuto, L., Desmet, W., Yoshida, T., Manfredini, R., Eitel, I., Kosuge, M., Nef, H. M., Deshmukh, A., Lerman, A., Bossone, E., Citro, R., … Templin, C. (2018). International expert consensus document on takotsubo syndrome (Part I): Clinical characteristics, diagnostic criteria, and pathophysiology. *European Heart Journal, 39*(22), 2032–2046. https://doi.org/10.1093/eurheartj/ehy076

Guidelines and Protocols Advisory Committee. (2023). *Heart failure – diagnosis and management*. BC Guidelines. https://www2.gov.bc.ca/assets/gov/health/practitioner-pro/bc-guidelines/hf_guideline_complete_2024.pdf

Hartupee, J., & Mann, D. L. (2017). Neurohormonal activation in heart failure with reduced ejection fraction. *Nature Reviews Cardiology, 14*(1), 30–38. https://doi.org/10.1038/nrcardio.2016.163

Health Canada. (n.d.). *Regulatory decision summary for Vyndaqel*. Drug and Health Product Portal. https://dhpp.hpfb-dgpsa.ca/review-documents/resource/RDS00663

Heart and Stroke Foundation of Canada. (2022). *Falling short: How Canada is failing people with heart failure – and how we can change that* [2022 Spotlight on heart failure]. https://heartandstroke.ca/-/media/pdf-files/canada/2022-heart-month/hs-heart-failure-report-2022-final.pdf

Heart and Stroke Foundation of Canada. (n.d.). *Managing heart failure* [Living with heart failure series]. https://publications.saskatchewan.ca/api/v1/products/129459/formats/155990/download

McDonagh, T. A., Metra, M., Adamo, M., Gardner, R. S., Baumbach, A., Böhm, M., Burri, H., Butler, J., Čelutkienė, J., Chioncel, O., Cleland, J. G. F., Coats, A. J. S., Crespo-Leiro, M. G., Farmakis, D., Gilard, M., Heymans, S., Hoes, A. W., Jaarsma, T., Jankowska, E. A., … ESC Scientific Document Group. (2021). 2021 ESC guidelines for the diagnosis and treatment of acute and chronic heart failure. *European Heart Journal, 42*(36), 3599–3726. https://doi.org/10.1093/eurheartj/ehab368

McDonald, M., Virani, S., Chan, M., Ducharme, A., Ezekowitz, J. A., Giannetti, N., Heckman, G. A., Howlett, J. G., Koshman, S. L., Lepage, S., Mielniczuk, L., Moe, G. W., O'Meara, E., Swiggum, E., Toma, M., Zieroth, S., Anderson, K., Bray, S. A., Clarke, B., … Yip, A. M. C. (2021). CCS/CHFS heart failure guidelines update: Defining a new pharmacologic standard of care for heart failure with reduced ejection fraction. *Canadian Journal of Cardiology, 37*(4), 531–546. https://doi.org/10.1016/j.cjca.2021.01.017

National Advisory Committee on Immunization. (2025). *Summary: Statement on seasonal influenza vaccines for 2025–2026*. Public Health Agency of Canada. https://www.canada.ca/en/public-health/services/publications/vaccines-immunization/national-advisory-committee-immunization-summary-seasonal-influenza-vaccines-2025-2026.html

Novartis Pharmaceuticals Canada. (2026). *Entresto (sacubitril/valsartan) film-coated tablets: Product monograph*. https://www.novartis.com/ca-fr/sites/novartis_ca/files/entresto_pm_20260226_en.pdf

Ommen, S. R., Ho, C. Y., Asif, I. M., Balaji, S., Burke, M. A., Day, S. M., Dearani, J. A., Epps, K. C., Evanovich, L., Ferrari, V. A., Joglar, J. A., Khan, S. S., Kim, J. J., Kittleson, M. M., Krittanawong, C., Martinez, M. W., Mital, S., Naidu, S. S., Saberi, S., … Waldman, C. B. (2024). 2024 AHA/ACC/AMSSM/HRS/PACES/SCMR guideline for the management of hypertrophic cardiomyopathy: A report of the American Heart Association/American College of Cardiology Joint Committee on Clinical Practice Guidelines. *Circulation, 149*(23), e1239–e1311. https://doi.org/10.1161/CIR.0000000000001250

Otto, C. M., Nishimura, R. A., Bonow, R. O., Carabello, B. A., Erwin, J. P., III, Gentile, F., Jneid, H., Krieger, E. V., Mack, M., McLeod, C., O'Gara, P. T., Rigolin, V. H., Sundt, T. M., III, Thompson, A., & Toly, C. (2021). 2020 ACC/AHA guideline for the management of patients with valvular heart disease: A report of the American College of Cardiology/American Heart Association Joint Committee on Clinical Practice Guidelines. *Circulation, 143*(5), e72–e227. https://doi.org/10.1161/CIR.0000000000000923

Pharmascience. (2022). *pms-DIGOXIN (digoxin) tablets and oral solution: Product monograph*. https://pdf.hres.ca/dpd_pm/00069390.PDF

Praz, F., Borger, M. A., Lanz, J., Marin-Cuartas, M., Abreu, A., Adamo, M., Ajmone Marsan, N., Barili, F., Bonaros, N., Cosyns, B., De Paulis, R., Gamra, H., Jahangiri, M., Jeppsson, A., Klautz, R. J. M., Mores, B., Pérez-David, E., Pöss, J., Prendergast, B. D., … ESC/EACTS Scientific Document Group. (2025). 2025 ESC/EACTS Guidelines for the management of valvular heart disease. *European Heart Journal, 46*(44), 4635–4736. https://doi.org/10.1093/eurheartj/ehaf194

Public Health Agency of Canada. (2018). *Report from the Canadian Chronic Disease Surveillance System: Heart disease in Canada, 2018*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/report-heart-disease-Canada-2018.html

Public Health Agency of Canada. (2026). *COVID-19 vaccines: Canadian Immunization Guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-4-active-vaccines/page-26-covid-19-vaccine.html

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Roy, C. L., Minor, M. A., Brookhart, M. A., & Choudhry, N. K. (2007). Does this patient with a pericardial effusion have cardiac tamponade? *JAMA, 297*(16), 1810–1818. https://doi.org/10.1001/jama.297.16.1810

Schulz-Menger, J., Collini, V., Gröschel, J., Adler, Y., Brucato, A., Christian, V., Ferreira, V. M., Gandjbakhch, E., Heidecker, B., Kerneis, M., Klein, A. L., Klingel, K., Lazaros, G., Lorusso, R., Nesukay, E. G., Rahimi, K., Ristić, A. D., Rucinski, M., Sade, L. E., … ESC Scientific Document Group. (2025). 2025 ESC Guidelines for the management of myocarditis and pericarditis. *European Heart Journal, 46*(40), 3952–4041. https://doi.org/10.1093/eurheartj/ehaf192

Virani, S. A., Dent, S., Brezden-Masley, C., Clarke, B., Davis, M. K., Jassal, D. S., Johnson, C., Lemieux, J., Paterson, I., Sebag, I. A., Simmons, C., Sulpher, J., Thain, K., Thavendiranathan, P., Wentzell, J. R., Wurtele, N., Côté, M.-A., Fine, N. M., Haddad, H., … Straatman, L. (2016). Canadian Cardiovascular Society guidelines for evaluation and management of cardiovascular complications of cancer therapy. *Canadian Journal of Cardiology, 32*(7), 831–841. https://doi.org/10.1016/j.cjca.2016.02.078

Virani, S. A., Zieroth, S., Aleksova, N., Anderson, K., Clarke, B., Ducharme, A., Ezekowitz, J. A., Foroutan, F., Giannetti, N., Jain, R., Lee, D., Lepage, S., Lyons, K., McDonald, M., McGuinty, C., Mielniczuk, L., O'Meara, E., Poon, S., Siatecki, K., … Yip, A. M. C. (2025). Canadian Cardiovascular Society/Canadian Heart Failure Society 2025 guideline update for pharmacologic management of heart failure with nonreduced ejection fraction (LVEF > 40%). *Canadian Journal of Cardiology, 41*(10), 1857–1874. https://doi.org/10.1016/j.cjca.2025.07.027

Weir, M. A., Slater, J., Jandoc, R., Koivu, S., Garg, A. X., & Silverman, M. (2019). The risk of infective endocarditis among people who inject drugs: A retrospective, population-based time series analysis. *Canadian Medical Association Journal, 191*(4), E93–E99. https://doi.org/10.1503/cmaj.180694

World Health Organization. (2025, January 24). *Rheumatic heart disease* [Fact sheet]. https://www.who.int/news-room/fact-sheets/detail/rheumatic-heart-disease

19 Hypertension and Vascular Disorders

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Measure blood pressure accurately in clinic, hospital and home settings, and classify it using Hypertension Canada's 2025 thresholds.
2. Explain the causes and risk factors of hypertension using Canadian data, naming structural causes.
3. Support treatment of hypertension (lifestyle, drug classes, adherence and teaching), with attention to older adults.
4. Recognize a hypertensive emergency and an acute aortic syndrome, and escalate.
5. Assess and care for patients with peripheral arterial disease and acute limb ischemia, describing findings on a range of skin tones.
6. Recognize, prevent and help manage venous thromboembolism and chronic venous disease.
7. Give and monitor anticoagulants safely (heparins, warfarin and DOACs), including teaching, bleeding recognition and reversal.
8. Distinguish RN and RPN roles in vascular care and anticoagulation using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 4, 5, 6	Clinician; Scholar	Foundations of Practice
3, 7	Clinician; Educator; Advocate	Foundations of Practice; Collaborative Practice
8	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

High blood pressure is one of the most common long-term conditions nurses meet in adults. It rarely causes symptoms, yet over years it damages the arteries, heart, brain, kidneys and eyes. Nurses measure blood pressure in every setting, teach people to measure it at home, give the drugs that lower it and notice when it climbs high enough to harm organs within hours. Doing this well depends on accurate measurement and on knowing what Canada's current guideline says.

This chapter begins with hypertension: how blood pressure is regulated, how hypertension is defined and measured, and its causes and risk factors (section 19.1). It then covers lifestyle and drug treatment and care in hospital (19.2), followed by severe hypertension, hypertensive emergencies and acute aortic syndromes (19.3). The second half turns to the vessels themselves: peripheral arterial disease and acute limb ischemia (19.4), abdominal aortic aneurysm (19.5), and venous disease and venous thromboembolism (19.6). The chapter ends with anticoagulation (19.7). This chapter is the book's home for anticoagulant drugs, their monitoring, bleeding, reversal and patient teaching, so other chapters point here.

The chapter builds on cardiac output (section 16.1), focused cardiovascular assessment, including pulses (16.2), atherosclerosis and its risk factors (Chapter 17), and heart failure (Chapter 18). Venous thromboembolism prevention around surgery is taught in Chapter 7, and pulmonary embolism in Chapter 15. Recognizing deterioration and calling for help, which every section here relies on, is covered in Chapter 6.

19.1 Hypertension: Measurement and Risk

How Blood Pressure Is Regulated

Blood pressure is the force that blood exerts on artery walls. It depends on two things: cardiac output, which is the volume of blood the heart pumps each minute (section 16.1), and **systemic vascular resistance**, the resistance that small arteries and arterioles offer to that flow. A rise in either raises blood pressure.

Several systems adjust these two factors from moment to moment and over the long term:

- **Sympathetic nervous system:** baroreceptors in the carotid arteries and aortic arch sense stretch. When pressure falls, sympathetic activity rises, the heart beats faster and harder, and arterioles constrict. This fast response explains why pain, fear and a full bladder raise readings.
- **Renin–angiotensin–aldosterone system (RAAS):** when blood flow to the kidneys falls, the kidneys release renin. This leads to the formation of angiotensin II, which constricts arterioles and prompts the adrenal glands to release aldosterone. Aldosterone makes the kidneys hold sodium and water, which expands blood volume.
- **The kidneys and sodium:** over days and weeks, the kidneys set blood pressure by controlling how much sodium and water the body keeps. A diet high in sodium, or kidneys that cannot excrete it, keeps volume and pressure high.

In sustained hypertension, these controls reset at a higher level. Arterioles thicken and stiffen, which raises resistance further. Several drug classes in section 19.2 work by blocking one of these systems.

Defining Hypertension

Hypertension is a blood pressure persistently above the level at which the risk of heart attack, stroke, heart failure and kidney disease clearly rises. Hypertension Canada's 2025 guideline for adults in primary care defines hypertension as a blood pressure of 130/80 mm Hg or higher, taken with a validated device and standardized technique (Goupil et al., 2025). The guideline uses this single threshold for every measurement method; it does not give separate cut-offs for office, home or ambulatory readings (Table 19.1).

This is lower than Hypertension Canada's earlier advice. The 2020 guidelines used thresholds that differed by method, for example 135/85 mm Hg for automated office and home readings and 140/90 mm Hg for other office readings (Rabi et al., 2020). The 2025 authors note that more people will now be labelled as having hypertension (Goupil et al., 2025). Nurses will meet both sets of numbers in older charts and resources and should use the current one.

Table 19.1 Blood pressure thresholds by measurement method (Hypertension Canada, 2025; original wording)

Method	How it is done	Threshold for hypertension	Notes
Automated office blood pressure (AOBP)	A validated automated upper-arm device takes several readings at set intervals and averages them, with the patient seated and rested	130/80 mm Hg or higher	Validated automated devices are preferred to manual ones
Standardized office reading by other methods, including manual (auscultatory)	A trained person measures with a validated device or a manual sphygmomanometer and stethoscope, using standard technique	130/80 mm Hg or higher	Manual measurement is preferred when an arrhythmia makes automated readings unreliable
Home blood pressure monitoring (HBPM)	The person measures at home with a validated device, two readings each morning and evening for 1 week	130/80 mm Hg or higher	Confirms the diagnosis; detects white-coat and masked hypertension
Ambulatory blood pressure monitoring (ABPM)	A worn device records blood pressure every 20 to 30 minutes over a day and night	130/80 mm Hg or higher	Confirms the diagnosis; the 2025 guideline gives no separate daytime, night or 24-hour cut-offs

Measuring Blood Pressure Well

A diagnosis and every treatment decision rest on accurate readings. Hypertension Canada recommends a validated automated device and a standardized method (Goupil et al., 2025).

Automated office blood pressure (AOBP) uses a validated automated upper-arm device that takes several readings in a row and averages them. Hypertension Canada describes a seated rest of 1 to 5 minutes, if feasible, then 3 readings 1 minute apart that are averaged (Goupil et al., 2025). The patient sits with the back and feet supported, legs uncrossed, and the bare arm supported at heart level. The lower edge of a correctly sized cuff sits about 3 cm above the elbow crease. Caffeine, tobacco and exercise are avoided for 30 minutes beforehand.

Figure 19.1 An aneroid sphygmomanometer: an adult cuff with its size label and range marks, a dial gauge and an inflation bulb. The range marks show whether the cuff fits the arm.

When an office reading is raised, the guideline recommends confirming it out of the office before making the diagnosis (Goupil et al., 2025). **Home blood pressure monitoring (HBPM)** means the person measures at home with a validated device; the standard protocol is two readings, twice a day, for 1 week. Hypertension Canada keeps a list of recommended home devices (Hypertension Canada, n.d.). **Ambulatory blood pressure monitoring (ABPM)** uses a device worn for a day and night that inflates every 20 to 30 minutes. If neither is possible, standardized office readings are repeated at a separate visit (Goupil et al., 2025).

Nurses still use the manual (auscultatory) method (Figure 19.1), and the guideline prefers it when a persistent or frequent arrhythmia makes automated devices inaccurate (Goupil et al., 2025). The technique below follows a British Columbia guideline appendix based on earlier Hypertension Canada (Canadian Hypertension Education Program) recommendations (Guidelines and Protocols Advisory Committee, n.d.):

- **Prepare:** the patient rests quietly, seated, for about 5 minutes, with the back supported, feet flat and legs uncrossed. Neither the patient nor the nurse talks.
- **Size the cuff:** the bladder width is about 40% of the arm's circumference and its length covers 80% to 100% of it. The nurse measures the mid-upper arm rather than guessing (Figure 19.2).
- **Place the cuff:** on the bare arm, with the bladder centred over the brachial artery and the lower edge about 3 cm above the elbow crease. The arm is supported so the elbow crease is level with the heart.
- **Estimate the systolic pressure:** the nurse feels the radial pulse, inflates until it disappears, then inflates about 30 mm Hg higher. This avoids missing an auscultatory gap, a silent interval that can lead to a falsely low systolic reading.
- **Deflate slowly:** about 2 mm Hg per heartbeat. The first clear tapping sound is the systolic pressure; the point where sounds disappear is the diastolic pressure.
- **Repeat and record:** wait at least 1 minute between readings. Record the values, the arm used, the position and the pulse. Measure both arms at least once and use the arm that reads higher from then on.

An arm that hangs below heart level gives falsely high systolic and diastolic readings. A cuff of the wrong size, an unsupported back, crossed legs and talking also make readings unreliable, so each is avoided. Deflating too fast makes the exact systolic and diastolic points easy to miss. Leaving the cuff partly inflated too long fills the veins of the arm and makes the sounds hard to hear (Guidelines and Protocols Advisory Committee, n.d.).

Measuring outside the office reveals two patterns. **White-coat hypertension** is raised office blood pressure with normal out-of-office readings. **Masked hypertension** is the reverse: normal office readings with raised readings at home or on ambulatory monitoring (Rabi et al., 2020). Both are common. Hypertension Canada's 2020 guidelines put the prevalence of white-coat

Figure 19.2 Blood pressure cuffs come in many sizes, from neonatal to large adult and thigh cuffs. A cuff of the wrong size makes readings unreliable, so the arm is measured to choose the size. (credit: "Sizes of blood pressure cuffs" by Chippewa Valley Technical College, CC BY 4.0)

hypertension at between 9% and 30%, and suggested that masked hypertension may affect about 20% of untreated adults. Masked hypertension is more likely in people with high-normal office readings, diabetes, obesity, smoking or heavy alcohol use (Rabi et al., 2020). People with white-coat hypertension may be treated unnecessarily, while masked hypertension is missed unless someone checks. This is one reason the nurse encourages home readings rather than relying on a single clinic visit.

Causes and Risk Factors

Most adults have **primary hypertension**, which develops over time from a mix of genetic, ageing and lifestyle influences, with no single cause. **Secondary hypertension** has an identifiable cause that may be treatable. Causes include chronic kidney disease (Chapter 27), narrowing of a renal artery, **primary aldosteronism** (overproduction of aldosterone by the adrenal glands), sleep apnea and some drugs. Drugs that can raise blood pressure include nonsteroidal anti-inflammatory drugs (NSAIDs), corticosteroids, sympathomimetics such as some decongestants, stimulants such as amphetamines and cocaine, calcineurin inhibitors, erythropoietin and licorice (Rabi et al., 2020). Hypertension Canada advises screening for secondary causes when hypertension is resistant to treatment and checking aldosterone and renin for primary aldosteronism. Specialist referral is advised for unexplained, sudden worsening of blood pressure, low potassium or an adrenal nodule (Goupil et al., 2025).

In Canadian Health Measures Survey data, risk rose with age, overweight or obesity, low physical activity and eating fruit and vegetables fewer than five times a day; diabetes was the strongest predictor, and chronic kidney disease was a risk factor for women (Statistics Canada, 2019). In the Canadian Health Measures Survey (CHMS) for 2016 to 2019, 23% of adults aged 20 to 79 had what the survey called stage 2 hypertension: a measured reading of 140/90 mm Hg or higher, a diagnosis by a health care professional, or use of blood pressure medication in the past month. That included 51% of adults aged 60 to 79. About 29% of this group did not know they had it, and about 51% were treated with medication and controlled below 140/90 mm Hg (Statistics Canada, 2021). These figures predate the 130/80 mm Hg threshold, so they understate the share now defined as hypertensive.

Blood pressure is also shaped by where and how people live. Hypertension Canada notes that in a typical Western diet, more than 70% of sodium comes from processed foods rather than the salt shaker (Goupil et al., 2025), so food environments, food costs and time to cook matter as much as personal choice. Low income, racism, unstable housing and distance from primary care all make diagnosis, regular follow-up and medications harder to reach. The nurse names these causes rather than blaming the person, and looks for local supports (Chapter 2).

CANADIAN CONTEXT

Blood Pressure Across Canada

- About one in four adults aged 20 to 79 in the 2016 to 2019 CHMS had hypertension by the older 140/90 mm Hg definition. Among those aged 60 to 79, the figure was about half (Statistics Canada, 2021).
- Close to 3 in 10 people in that group were unaware of their hypertension. Of those with readings of 130 to 139 systolic or 80 to 89 diastolic, nearly three-quarters were unaware (Statistics Canada, 2021).
- In a 2017 health survey of 1,177 Inuit adults in Nunavik, 23% had hypertension (140/90 mm Hg or higher, or taking medication for it): 29% of men and 18% of women. About a third (34%) of those with hypertension were taking medication (Allaire et al., 2024). Remote location, travel for care and the cost and supply of fresh food affect both prevention and treatment in northern communities.
- Under the First Nations principles of OCAP® (ownership, control, access and possession), First Nations control how data about their communities are collected, used and shared (Chapter 2). The nurse uses distinctions-based data as each Nation or

organization publishes it.

- Under the 2025 threshold, more Canadians will meet the definition of hypertension, which increases demand for accurate measurement and follow-up in primary care (Goupil et al., 2025).

PATIENT EDUCATION

Measuring Your Blood Pressure at Home

- Buy a monitor that is validated and on Hypertension Canada's recommended list. An upper-arm cuff that fits your arm is best; ask the nurse or pharmacist to check the size.
- Measure in the morning and evening for 7 days before your next appointment or after your medication is changed.
- For 30 minutes before, do not smoke, drink coffee or other caffeine, or exercise. Empty your bladder first.
- Place the cuff directly on your skin, not over a sleeve. Sit quietly for 5 minutes with your back supported, feet flat on the floor and legs uncrossed. Rest your arm on a table so the cuff is level with your heart.
- Do not talk or look at your phone while the cuff inflates.
- Take two readings, 1 minute apart, each time.
- Write down every reading with the date and time, or use a monitor that stores them, and bring the record to your appointment.
- Tell your health care provider if your readings are often higher than usual. Call 9-1-1 right away for signs of a heart attack, such as chest discomfort or shortness of breath, or for signs of a stroke, whatever your reading.

(Goupil et al., 2025; Heart and Stroke Foundation of Canada, n.d.-a, n.d.-b; Hypertension Canada, n.d.)

19.2 Treating Hypertension

Lifestyle

Lifestyle change is recommended for every adult with hypertension, whether or not drugs are started (Goupil et al., 2025). The 2025 guideline cites these targets, several of them from the World Health Organization:

- **Sodium:** less than 2 g of sodium a day. Because most sodium comes from processed and restaurant food, teaching focuses on reading labels and cooking more meals from whole ingredients.
- **Potassium:** more than 3.5 g a day, mainly from vegetables and fruit. People with chronic kidney disease or taking an angiotensin-converting enzyme (ACE) inhibitor, an angiotensin receptor blocker (ARB) or a mineralocorticoid receptor antagonist need their potassium monitored, because their levels can rise too high (Chapter 3).
- **Physical activity:** 150 to 300 minutes of moderate aerobic activity each week.
- **Weight:** weight loss lowers blood pressure in people living with obesity. Glucagon-like peptide-1 (GLP-1) receptor agonists used for weight loss also lower blood pressure.
- **Alcohol:** cutting back lowers blood pressure in a dose-dependent way, with clear benefit in people who drink 3 or more drinks a day.
- **Smoking:** everyone with hypertension is counselled to quit (Chapter 14).

Teaching works best when it is practical. The nurse shows the person how to find sodium on a Nutrition Facts table, suggests swapping one high-sodium convenience food at a time, and explains that vegetables, fruit, beans and lentils supply potassium. Because high potassium is dangerous for some people, the nurse checks kidney function and the medication list before encouraging potassium-rich foods or salt substitutes made with potassium chloride. The nurse starts with what matters to the person and chooses one or two changes at a time. Cost, food access, shift work, disability and safe places to walk all shape what is realistic, so the nurse plans with the person rather than handing over a list.

Drug Treatment

Hypertension Canada recommends starting medication when blood pressure is 140/90 mm Hg or higher. When systolic pressure is 130 to 139 mm Hg, drugs are started only for people at high cardiovascular risk: those with established cardiovascular disease, diabetes, chronic kidney disease (estimated glomerular filtration rate below 60 mL/min/1.73 m² or albuminuria of 3 mg/mmol or

more), a 10-year Framingham risk score of 20% or more, or age 75 or older. Others focus on lifestyle and are reassessed in 3 to 6 months (Goupil et al., 2025).

The treatment target is a systolic pressure below 130 mm Hg, as long as treatment is well tolerated; the guideline sets no diastolic target. Exceptions include frailty, a high risk of falls, orthostatic hypotension and the person's goals of care. For these patients, the aim is the lowest systolic pressure that can reasonably be reached, decided case by case (Goupil et al., 2025).

The guideline names three first-line classes (Goupil et al., 2025):

- ACE inhibitors or ARBs, which block the RAAS;
- thiazide or thiazide-like diuretics, which increase sodium and water loss in the kidney;
- long-acting dihydropyridine calcium channel blockers, which relax arterial smooth muscle.

Treatment usually starts with low doses of two of these classes, ideally combined in one tablet. A **single-pill combination** contains two or more drugs in one tablet. It simplifies the routine, which helps adherence, and in Canada it usually costs less than the separate drugs. The guideline's preferred first pill combines irbesartan and hydrochlorothiazide; the panel chose it for reasons that included cost, drug-plan coverage and supply, and says the choice may be revisited. If the target is not reached, the third class is added. If blood pressure stays high on all three, spironolactone may be added, with potassium checked 2 to 4 weeks after it is started or the dose changes. An ACE inhibitor and an ARB are never combined. When a person is at high risk of symptomatic low blood pressure, starting with one drug is reasonable (Goupil et al., 2025).

Beta-blockers are not first-line for hypertension alone. They are used when there is another reason for them, such as heart failure, angina, a past myocardial infarction or heart rate control (Goupil et al., 2025). ACE inhibitors and ARBs must be avoided in pregnancy and stopped in people trying to become pregnant, so the nurse makes sure people who could become pregnant know this (Chapter 29).

Hypertension that stays above target despite three first-line drugs is usually called resistant hypertension. Before more drugs are added, the team checks that the person is taking the medications, that readings are accurate and that no other drug is raising the pressure. Hypertension Canada advises screening people with resistant hypertension for secondary causes, including primary aldosteronism, ideally before spironolactone is started (Goupil et al., 2025).

After an ACE inhibitor, ARB, diuretic or spironolactone is started or its dose changes, blood work for potassium, sodium and creatinine is commonly ordered; the nurse makes sure it is done and reports abnormal values (Chapter 3). Home readings brought to follow-up visits show whether the regimen is working. Hypertension Canada advises follow-up every 1 to 3 months until the target is reached, then every 6 to 12 months (Goupil et al., 2025). Many people stop their drugs because they feel well, have side effects or cannot afford them. The nurse asks about missed doses without judgment, checks whether a drug plan covers the medication, explains that the drugs work only while they are taken, and asks the prescriber or pharmacist about simpler or lower-cost options. Pill organizers, pharmacy blister packs, linking doses to a daily routine and home readings that show progress can all help people keep taking their medications.

MEDICATIONS

Antihypertensive Classes

Examples are generic names marketed in Canada. Doses follow the order and the Canadian product monograph.

- **ACE inhibitors** (for example, ramipril, perindopril): block the formation of angiotensin II. Check potassium and creatinine after starting. A dry cough can occur. Swelling of the lips, tongue or throat (angioedema) is an emergency.
- **ARBs** (for example, candesartan, irbesartan, telmisartan): block angiotensin II receptors. Check potassium and creatinine; cough is less common than with ACE inhibitors. Never given with an ACE inhibitor.
- **Thiazide and thiazide-like diuretics** (for example, hydrochlorothiazide, chlorthalidone, indapamide): increase sodium and water loss. Check sodium and potassium; watch for dizziness and dehydration, especially in heat or with vomiting or diarrhea.
- **Long-acting dihydropyridine calcium channel blockers** (for example, amlodipine): relax arterial smooth muscle. Ankle swelling, flushing and headache can occur.
- **Beta-blockers** (for example, bisoprolol, metoprolol): slow the heart and lower its force. Check apical pulse and blood pressure; teach not to stop suddenly. Not first-line for hypertension alone.

- **Spironolactone** (fourth drug for resistant hypertension): blocks aldosterone. Check potassium 2 to 4 weeks after starting or a dose change; counsel about possible breast enlargement (gynecomastia).
- **ACE inhibitors and ARBs in pregnancy:** must be avoided; teach people who could become pregnant.

(Goupil et al., 2025)

In Hospital

In hospital, the nurse checks blood pressure and heart rate before giving an antihypertensive and follows the hold parameters written in the order. If the order has none and the reading seems low for the patient, the nurse holds the dose and contacts the prescriber rather than guessing. Every hold is documented and reported. Patients who are acutely ill, vomiting, not eating or newly dehydrated may need their usual antihypertensives adjusted, so the nurse reports these changes rather than giving every home drug automatically. Whether to give antihypertensives on the morning of surgery is decided by the surgical and anesthesia teams (Chapter 7).

Patients newly started on antihypertensives, given diuretics or receiving several blood-pressure-lowering drugs need **orthostatic vital signs**. The nurse measures blood pressure and pulse after the patient has been lying down, then again after standing for up to 3 minutes. **Orthostatic hypotension** is a sustained fall of at least 20 mm Hg systolic or 10 mm Hg diastolic within 3 minutes of standing (Freeman et al., 2011). Dizziness on standing is a falls warning: the nurse has the patient sit on the edge of the bed first, stands with them and reports the finding (Chapter 8).

A single high reading in a patient who is in pain, anxious, short of breath or needing to void is usually a response to that stress. The nurse treats the cause, rechecks the reading with good technique after a rest and looks for symptoms, rather than calling for an extra antihypertensive dose straight away. A very high reading with symptoms such as headache, chest pain, shortness of breath, confusion or weakness is different and is escalated at once (section 19.3).

Admission and discharge are high-risk points for medication errors. The nurse compares the home list with what is ordered, including combination pills, over-the-counter drugs (such as NSAIDs and decongestants) and natural health products, and makes sure the patient leaves knowing which drugs to continue. If the patient owns a home monitor, the nurse can check the cuff size and the patient's technique before discharge.

LIFESPAN CONSIDERATIONS

Older Adults, Targets and Falls

- **Older adults:** hypertension is most common in later life. Age 75 or older counts as high cardiovascular risk in the 2025 guideline, so drug treatment is considered from a systolic pressure of 130 mm Hg (Goupil et al., 2025).
- The systolic target of under 130 mm Hg applies only when treatment is well tolerated. For a person living with frailty, a high falls risk or orthostatic hypotension, or whose goals of care point elsewhere, the target is set individually at the lowest level reasonably achievable (Goupil et al., 2025).
- Orthostatic hypotension, dehydration, several blood-pressure-lowering drugs and drugs taken for other conditions (such as for the prostate or for mood) can combine to cause falls. The nurse checks lying and standing readings and reviews the full medication list (Chapter 8).
- A fall, new confusion or dizziness after a dose change is reported, because the regimen may need to be simplified.
- **Younger adults:** in earlier CHMS data, about 65% of adults aged 20 to 39 with hypertension knew they had it, compared with 90% of those aged 70 to 79 (Statistics Canada, 2019). ACE inhibitors and ARBs need pregnancy counselling (Chapter 29).

19.3 Hypertensive Emergencies and Acute Aortic Syndromes

Urgency and Emergency

Very high blood pressure is not always an emergency. What matters is whether organs are being damaged now. Under Hypertension Canada's 2020 guidelines, an office reading with a systolic pressure of 180 mm Hg or higher or a diastolic pressure of 110 mm Hg or higher was enough on its own to diagnose hypertension (Rabi et al., 2020), and the 2024 European guideline recommends assessing anyone with a reading of 180/110 mm Hg or higher for a hypertensive emergency (McEvoy et al., 2024).

A **hypertensive emergency** is severe hypertension with new or worsening **target-organ damage**: acute injury to the brain, eyes, heart, kidneys or large arteries caused by the high pressure (van den Born et al., 2019). Examples are hypertensive encephalopathy, stroke, acute coronary syndrome, acute heart failure with pulmonary edema, acute kidney injury, retinal hemorrhage and aortic dissection. **Hypertensive urgency** is a common term for severe hypertension without acute organ damage. Some European experts discourage the term and describe it as a diagnosis reached only once organ damage is excluded; these patients can usually be treated with oral drugs and do not need rapid lowering (van den Born et al., 2019) (Table 19.2). The same document advises watching such patients for at least 2 hours after an oral dose before they leave. The nurse looks for a reason, such as missed or stopped home medications, pain or a drug that raises blood pressure, and makes sure follow-up is arranged.

In most hypertensive emergencies, blood pressure is lowered in a controlled way rather than to normal at once. The brain, heart and kidneys have adapted to the high pressure, and a sudden fall can starve them of blood. A European position document advises lowering mean arterial pressure by about 20% to 25% over several hours in malignant hypertension and warns that large falls have been linked with ischemic stroke and death (van den Born et al., 2019). The main exception is aortic dissection, where pressure and heart rate are lowered quickly. Stroke has its own targets (Chapter 31), as does severe hypertension in pregnancy (Chapter 29).

The nurse's role is recognition and escalation. The nurse repeats the measurement with correct technique, checks both arms, and assesses neurologic status, vision, chest pain, breathing, oxygen saturation and urine output. A neurologic check includes level of consciousness, orientation, speech, pupils and limb strength. The nurse asks about missed doses, pain and recent use of substances such as cocaine or amphetamines, which can raise blood pressure (Rabi et al., 2020). Readings in both arms and in a leg help reveal aortic disease, and an electrocardiogram (ECG) is recorded to look for ischemia (van den Born et al., 2019). Any sign of organ injury is reported immediately using the unit's escalation process (Chapter 6). Patients with a hypertensive emergency are moved to a monitored setting for IV treatment.

Table 19.2 Hypertensive urgency and emergency compared (van den Born et al., 2019; Rabi et al., 2020; McEvoy et al., 2024; original wording)

Feature	Urgency (severe hypertension without new organ damage)	Emergency (with acute organ damage)
Blood pressure	Severe, often 180/110 mm Hg or higher	Severe, often 180/110 mm Hg or higher; the level alone does not decide
Organ injury	None found after assessment	New or worsening injury to brain, eyes, heart, kidneys or aorta
Typical findings	May have mild headache or none; often missed or stopped medications	Severe headache, confusion, seizures, vision loss, chest pain, dyspnea, low urine output, new weakness
Setting	Usually outpatient or ward care with follow-up	Monitored unit such as emergency department resuscitation area or intensive care
Treatment	Oral drugs; restart or adjust usual regimen; gradual lowering	IV drugs titrated to targets; controlled lowering over hours except for aortic dissection
Nursing priority	Confirm readings, look for causes such as pain or missed doses, arrange follow-up	Escalate at once, frequent neurologic and vital sign checks, prepare for transfer

Acute Aortic Syndromes

Acute aortic syndromes are life-threatening injuries to the aortic wall. The best known is **aortic dissection**, in which a tear in the inner lining lets blood track between the layers of the wall. The dissection can extend along the aorta, block its branches or rupture. In an international registry of patients who had surgery for acute dissection of the ascending aorta, a history of hypertension was the most common predisposing condition (Berretta et al., 2016).

The 2022 American College of Cardiology and American Heart Association aortic guideline lists high-risk features (Isselbacher et al., 2022):

- pain that starts suddenly, is severe and feels ripping or tearing, in the chest, back or abdomen;
- a pulse deficit or a difference in systolic pressure of more than 20 mm Hg between limbs;

- new neurologic signs with the pain, such as stroke symptoms or paralysis of the legs.

Dissection is an emergency. The nurse stays with the patient, calls for help immediately and checks pulses and blood pressure in both arms (section 16.2). Treatment starts with IV beta-blockers to bring heart rate to 60 to 80 beats/min and systolic pressure below 120 mm Hg, or the lowest pressure that keeps organs perfused, plus pain relief; IV vasodilators are added if pressure is not controlled. A computed tomography (CT) scan usually confirms the diagnosis, and a dissection involving the ascending aorta needs emergency surgery (Isselbacher et al., 2022). Dissection can look like a heart attack or stroke. If it is mistaken for one and anticoagulants or thrombolytics are given, serious or fatal bleeding can follow (Zschaler et al., 2018). The nurse who notices tearing pain or unequal arm pressures says so before such drugs are given.

While help arrives, the nurse keeps the patient on bed rest, ensures IV access and continuous monitoring, gives pain relief as ordered and prepares the patient for urgent imaging. New limb pain or coldness, stroke signs, abdominal pain or falling urine output can mean the dissection is blocking branch arteries, and is reported at once. Abdominal aortic aneurysm is covered in section 19.5.

CLINICAL JUDGMENT

Headache and 220/130 on the Ward

Mrs. Leila Haddad, 66, was admitted 2 days ago with pneumonia. At 2300 she reports a severe headache and blurry vision. Her automated reading is 220/130 mm Hg.

- **Recognize cues:** the nurse rechecks manually with the correct cuff after she rests: 218/128 mm Hg in the right arm, 214/126 mm Hg in the left. Heart rate 92 beats/min, SpO2 95% on room air. She is slow to answer and unsure of the date, which is new. Her usual antihypertensive was not ordered on admission.
- **Analyze cues:** severe hypertension plus headache, vision change and new confusion suggests brain injury from the pressure, not a reaction to pain or anxiety. Similar pressures in both arms and no tearing pain make dissection less likely.
- **Prioritize hypotheses:** hypertensive emergency with possible encephalopathy or stroke comes first.
- **Generate solutions:** urgent assessment by the prescriber or rapid response team; controlled, not sudden, lowering in a monitored setting; neurologic checks.
- **Take action:** the nurse stays, raises the head of the bed, does a neurologic check including a stroke screen, and calls the rapid response team using SBAR (Situation, Background, Assessment, Recommendation; Chapter 6). The nurse reports the missed home medication. No extra oral dose is given without an order.
- **Evaluate outcomes:** she transfers to the intensive care unit. Two hours later her pressure is 176/104 mm Hg and she knows the date.

GOING DEEPER

Titrated IV Antihypertensives and Arterial Lines

Required for RN students; optional for PN students.

Hypertensive emergencies are treated with short-acting IV drugs whose effect can be adjusted minute by minute. IV agents marketed in Canada include labetalol, esmolol, hydralazine and sodium nitroprusside (Health Canada, 2026). A European position document suggests labetalol as one of two drugs that can treat most hypertensive emergencies (the other, IV nicardipine, has no IV product listed in the Drug Product Database). For aortic dissection, an IV beta-blocker such as esmolol is given first, and a vasodilator such as nitroprusside is added if pressure stays above target (van den Born et al., 2019; Isselbacher et al., 2022).

Principles of titration:

- The prescriber sets the target and the time frame, such as a percentage fall in mean arterial pressure over the first hours, or a heart rate and systolic target for dissection.
- The nurse uses an infusion pump, increases or decreases the rate only within the ordered range, and checks blood pressure often enough to see each change take effect.
- Falling too far or too fast is as dangerous as staying too high. The nurse watches for new confusion, chest pain, low urine output and dizziness as pressure falls.

An **arterial line** gives continuous beat-to-beat pressure readings and is recommended in acute aortic syndromes (Isselbacher et al., 2022). The nurse keeps the transducer levelled and zeroed per unit policy, checks the waveform, compares it with a cuff reading when values seem wrong, and assesses circulation in the limb beyond the catheter.

19.4 Peripheral Arterial Disease

What Happens and Who Is at Risk

Peripheral arterial disease (PAD) is narrowing or blockage of the arteries that supply the limbs, most often the legs. The usual cause is atherosclerosis (Chapter 17). A narrowed artery may supply enough blood at rest but not during exercise; as narrowing worsens, the foot becomes short of blood even at rest.

The Canadian Cardiovascular Society (CCS) 2022 guideline describes PAD as often silent and as underdiagnosed, under-recognized and undertreated; lower-extremity PAD is common from age 50 (Abramson et al., 2022). Smoking, diabetes, chronic kidney disease, high blood pressure, abnormal lipids and older age raise the risk. Compared with people who have PAD alone, those who also have diabetes have about three to four times the mortality and about five times the amputation rate, the guideline reports.

Amputation is not shared equally in Canada. In an Ontario study of adults with diabetes from 1995/96 to 2014/15, First Nations people had revascularization rates similar to those of other Ontarians but three to five times their rate of lower-extremity amputation, and more than six times the rate at age 44 or younger (Shah et al., 2019). Risk rose with rurality in both groups and was highest in remote communities. The authors suggested that PAD may be underdiagnosed or undertreated in First Nations people. The study was designed with the Chiefs of Ontario and approved by its Data Governance Committee (First Nations data governance and OCAP®: Chapter 2). A second Ontario study of major (above-ankle) amputations linked to diabetes or PAD from 2007 to 2017 found regional rates that differed more than fourfold (de Mestral et al., 2020). The highest-rate regions had a larger share of patients who lived rurally or in the lowest income quintile, and rates were lower where more patients had seen a vascular surgeon or had revascularization. These gaps point to structural causes, such as distance from specialist care, poverty and health services shaped by colonial policy, rather than to biology (Chapter 2).

Recognizing PAD

The classic symptom is **intermittent claudication**: cramping or aching pain, usually in the calf, that comes on with walking at about the same distance each time and eases within about 10 minutes of rest (Abramson et al., 2022).

Chronic limb-threatening ischemia (CLTI) is the advanced stage: ischemic pain at rest, ulcers or gangrene (Abramson et al., 2022). Rest pain in the foot is often worse lying flat at night and eases when the leg hangs down. Arterial ulcers (Figure 19.3) form on the toes or below the ankle and look punched out, often with pale or dry, black tissue (Evans et al., 2025).

The nurse compares both legs (section 16.2):

- **Pulses:** weak or absent; a handheld Doppler can find pulses that cannot be felt.
- **Capillary refill and temperature:** slower refill and a cooler foot on the affected side.
- **Skin, hair and nails:** thin, shiny, dry, hairless skin, thickened nails and slow-healing cuts.
- **Colour with position: elevation pallor**, in which the foot blanches when raised, and **dependent rubor**, a dusky red colour when the leg hangs down.

Colour changes are harder to see on darker skin. Pallor may look ash-grey or yellow-brown and shows best in the conjunctiva and mucous membranes (Pusey-Reid et al., 2023). The nurse uses natural light, compares the limbs and relies on temperature, refill, pulses and symptoms, not colour alone.

Figure 19.3 A foot with peripheral arterial disease: a dry ulcer at the tip of the big toe and thickened nails. (credit: “Peripheral artery disease” by Milorad Dimić (Intermedichbo)/Wikimedia Commons, CC BY-SA 4.0)

The **ankle-brachial index (ABI)** compares ankle and arm systolic pressures. With the patient lying flat, systolic pressures are measured with a Doppler probe in both arms and at each ankle

(dorsalis pedis and posterior tibial arteries). For each leg, the higher ankle pressure is divided by the higher arm pressure (Abramson et al., 2022). The CCS states that an ABI below 0.9 suggests PAD. Calcified arteries, common in diabetes, kidney disease and older age, can give a falsely normal ABI or one above 1.4; a toe-brachial index or other tests are then used.

Treatment and Nursing Care

Treatment aims to prevent heart attack, stroke and death, and to save the limb. The CCS recommends (Abramson et al., 2022):

- **Smoking cessation** with counselling and medication (Chapter 14).
- **Supervised exercise** as first-line treatment for claudication, with walking preferred, at least twice a week for 30 minutes or more over at least 12 weeks; a structured home or community program is the alternative.
- **A statin** for every patient with PAD (Chapter 17).
- **Antithrombotic therapy for symptomatic PAD:** for most patients with low bleeding risk, low-dose (vascular-dose) rivaroxaban plus low-dose acetylsalicylic acid (ASA), especially with diabetes, heart failure, kidney impairment, disease in other arterial beds or a high-risk limb; a single antiplatelet drug for those at high bleeding risk. Routine antithrombotic therapy is not recommended when PAD causes no symptoms.

Because the vascular dose of rivaroxaban is much lower than the clot-treatment dose, the nurse checks that the dose matches the indication. Blood pressure (section 19.2), diabetes control and daily foot care (Chapter 22) also protect the limb.

When claudication stays disabling or CLTI threatens the limb, flow may be restored by **endovascular revascularization** (a balloon or stent passed through a catheter) or **bypass surgery** with a vein or synthetic graft. Afterward, the nurse:

- checks pulses, colour, warmth, capillary refill, sensation and movement against the pre-procedure baseline, and reports a lost pulse at once;
- inspects the access site or incision for bleeding or hematoma;
- reports rising pain, tense swelling or new numbness at once, because compartment syndrome can develop or worsen after revascularization (National Confidential Enquiry into Patient Outcome and Death [NCEPOD], 2025; Chapter 33).

In arterial disease, gravity helps blood reach the foot, so the legs stay level or slightly lower than the heart rather than raised; arterial pain worsens with elevation (Evans et al., 2025).

Acute Limb Ischemia

Acute limb ischemia is a sudden loss of blood flow to a limb, usually from an embolus (often from the heart in atrial fibrillation, section 16.6) or a clot in a diseased artery or graft. Its signs are remembered as the "six Ps": pain, pallor, pulselessness, paresthesia, paralysis and poikilothermia (a very cold limb); not all need be present (NCEPOD, 2025).

New numbness or weakness in a painful limb marks a limb in danger. A national review in the United Kingdom described a limb with sensory loss beyond the toes and some weakness as salvageable if revascularized promptly, ideally within 6 hours for full function; untreated, it progresses to irreversible nerve and muscle damage (NCEPOD, 2025). Every nurse who notices these signs escalates at once (Chapter 6), records when symptoms began, keeps the limb level and protected, and prepares for anticoagulation, imaging and transfer to the vascular team.

19.5 Abdominal Aortic Aneurysm

An **abdominal aortic aneurysm (AAA)** (Figure 19.4) is a weak area in the wall of the abdominal aorta that balloons outward as blood pressure pushes on it (Canadian Task Force on Preventive Health Care [CTFPHC], 2017). About 20,000 Canadians are diagnosed each year, and AAA caused about 1,244 deaths a year from 2009 to 2013. The strongest risk factors are male sex, smoking, older age and a family history of AAA; coronary artery disease, atherosclerosis, high cholesterol and hypertension are weaker ones, and AAA appears to be less common in people with diabetes. Among people aged 65 to 80, AAA is four to six times less common in women than in men, but women appear more likely to die after repair. Smoking promotes aneurysm formation,

growth and rupture, and current smoking roughly doubles the risk of rupture; even so, the Task Force made no separate recommendation for people who smoke.

An AAA usually causes no symptoms until it ruptures, so it is often found by chance on imaging or by screening. The CTFPHC (2017) recommends:

- one-time ultrasound screening for men aged 65 to 80 (weak recommendation, moderate-quality evidence);
- no screening for men older than 80 (weak recommendation, low-quality evidence);
- no screening for women (strong recommendation, very low-quality evidence).

Guidance outside Canada differs; the 2022 American College of Cardiology and American Heart Association guideline, for example, includes some women aged 65 or older who have ever smoked (Isselbacher et al., 2022). The nurse explains the Canadian recommendation and that the decision is shared with the primary care provider.

Figure 19.4 Contrast-enhanced CT of an abdominal aortic aneurysm measuring about 4.8 by 3.8 cm (green measurement lines). (credit: "Contrast-enhanced CT scan demonstrating abdominal aortic aneurysm" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

A small aneurysm is watched with repeat imaging; the 2022 guideline advises a scan every 3 years for one measuring 3.0 to 3.9 cm, and more often as it grows. Repair is generally offered once it reaches a size threshold, which the 2022 guideline sets at 5.5 cm for men and 5.0 cm for women, or when it causes symptoms (Isselbacher et al., 2022). Meanwhile the nurse supports smoking cessation, blood pressure control (section 19.2) and statin therapy when atherosclerosis is present.

Rupture

Rupture causes bleeding inside the abdomen that can cause death (CTFPHC, 2017). Warning signs include sudden, severe abdominal, back or flank pain; signs of shock, such as hypotension, a fast pulse, cool clammy skin and fainting; and sometimes a pulsating abdominal mass. A patient with a known AAA and new abdominal or back pain is treated as an emergency until proven otherwise. The nurse calls the rapid response team or 9-1-1 at once (Chapter 6), keeps the patient still, starts or prepares for large-bore intravenous (IV) access and blood work, and readies the patient for imaging and surgery. Section 19.3 covers aortic dissection, which can produce similar pain.

Care After Repair

Repair is done by **endovascular aneurysm repair (EVAR)**, in which a stent graft is passed through the femoral arteries to line the aneurysm from inside, or by open surgery through an abdominal incision. Perioperative care follows Chapter 7. After repair, the nurse also checks:

- **Limb perfusion:** pulses, colour, warmth, sensation and movement in both legs, because clot or debris can travel downstream.
- **Access sites:** groin wounds after EVAR for bleeding, swelling or hematoma.
- **Kidney function:** urine output and creatinine, because contrast dye and aortic clamping can injure the kidneys (Chapter 27).
- **The bowel after open repair:** pain, distension or bloody diarrhea, which can signal reduced blood flow to the colon.

After EVAR, the patient needs follow-up imaging on the schedule the vascular team sets. The nurse explains why missed scans matter and confirms that follow-up is booked.

19.6 Venous Disease and VTE

How Clots Form in Veins

Venous thromboembolism (VTE) includes **deep vein thrombosis (DVT)**, a clot in a deep vein, most often in the leg or pelvis, and **pulmonary embolism (PE)**, in which a clot travels to the lungs (Chapter 15). **Virchow's triad** names the three conditions that favour venous clotting: slow or stagnant blood flow (stasis), injury to the vein wall, and blood that clots more easily than usual (hypercoagulability).

Common risk factors map onto the triad:

- **Stasis:** surgery, bed rest, reduced mobility in hospital, a leg in a cast, paralysis and long travel.
- **Vein wall injury:** surgery or trauma to the leg or pelvis, and central venous catheters.
- **Hypercoagulability:** active cancer and some cancer treatments, estrogen-containing contraceptives and hormone therapy, pregnancy and the weeks after birth, and inherited clotting disorders.
- **Previous VTE**, which raises the risk of another.

Prevention in hospital, including risk assessment, early mobilization and prophylactic anticoagulants, is taught in Chapter 7.

Recognizing and Diagnosing DVT

A DVT typically causes swelling of one calf or the whole leg (Figure 19.5), pain or tenderness along the deep veins, warmth, and dilated superficial veins. Redness or a bluish colour is easy to see on light skin; on darker skin the change may look darker, purplish or be hard to see at all, so the nurse compares the two legs, feels for warmth and measures both calves at the same marked level. Many clots cause few or no signs, especially in patients in hospital, and these signs are also found in other conditions such as cellulitis or a ruptured cyst behind the knee. Examination alone therefore cannot confirm or rule out DVT.

Clinicians first estimate the **pretest probability**: how likely DVT is before any test. A validated clinical prediction rule, such as the Wells score, weighs features that make DVT more likely, such as active cancer, recent surgery or immobilization, a previous DVT and swelling or tenderness of the leg, against whether another diagnosis is as likely (Lim et al., 2018). The result places the patient in a lower or higher probability group, which sets the testing path.

- **Lower probability:** a **D-dimer** test comes first. D-dimer is a fragment released when cross-linked fibrin breaks down. A negative result rules out DVT without imaging; a positive result leads to ultrasound (Lim et al., 2018).
- **Higher probability: compression ultrasound** comes first. The sonographer presses on the vein with the probe; a vein that will not collapse contains clot. If the first scan is negative and no other cause is found, the scan is repeated, because one negative scan does not rule out DVT in this group.

D-dimer is less useful in patients in hospital, after surgery and in pregnancy, because levels are often raised without a clot (Lim et al., 2018). Levels also rise with age; for outpatients older than 50, the American Society of Hematology (ASH) reports that a cut-off adjusted for age is as safe as the standard cut-off (Lim et al., 2018). The nurse reports a suspected DVT promptly, does not massage the leg, and watches for sudden shortness of breath, chest pain or a fast heart rate, which may signal PE and call for immediate escalation (Chapter 15).

Treatment

Anticoagulation is the treatment for DVT (section 19.7). For most patients, ASH suggests a direct oral anticoagulant over warfarin, with exceptions such as severe kidney impairment, moderate to severe liver disease and antiphospholipid syndrome (Ortel et al., 2020). For uncomplicated DVT, ASH suggests that home treatment be offered in preference to hospital treatment (conditional recommendation); hospital care may benefit patients with a limb-threatening clot or a high risk of bleeding (Ortel et al., 2020).

Strict bed rest is no longer routine. In a meta-analysis of 13 studies with 3,269 patients receiving standard anticoagulation, walking early was not linked to more new PEs, clot extension or DVT-related deaths, and leg pain eased sooner in those with moderate or severe pain (Liu et al., 2015). The nurse encourages walking once anticoagulation has started, unless the prescriber orders otherwise.

Some patients go on to develop **post-thrombotic syndrome (PTS)**: lasting pain, swelling, heaviness and skin changes in the leg after a DVT. A Canadian-led trial randomly assigned 806 patients after a first proximal DVT to active or placebo compression stockings for 2 years; PTS developed in 14.2% and 12.7%, respectively (Kahn et al., 2014). The American College of Chest Physicians (CHEST) advises against routine compression stockings for preventing PTS (Stevens et al., 2021).

Superficial Thrombophlebitis and Chronic Venous Disease

Superficial vein thrombosis (SVT), also called superficial thrombophlebitis, is a clot with inflammation in a vein near the skin surface. It causes a tender, warm, firm cord along the vein, with redness on lighter skin or darker discoloration on darker skin. A leg SVT can extend, so the prescriber may order an ultrasound to look for clot progression or DVT. For SVT of the leg at increased risk of progression, CHEST suggests 45 days of anticoagulation, with fondaparinux preferred and rivaroxaban as an alternative for patients who cannot use injections (Stevens et al., 2021).

Varicose veins are swollen, twisted, bluish surface veins, common on the calf and inner leg (Evans et al., 2025; Figure 19.6). **Chronic venous insufficiency (CVI)** develops when vein valves fail or veins stay blocked after a DVT, so pressure in the leg veins stays high. Risk factors include older age, previous DVT, obesity, long periods of standing or sitting, several pregnancies, a weak calf-muscle pump and a family history. Findings include:

Figure 19.5 Deep vein thrombosis of the right leg (arrow): the leg is swollen and redder than the other. On darker skin, the change may look darker or purplish, or be hard to see. (credit: "Deep vein thrombosis of the right leg" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 19.6 Varicose veins: raised, twisted surface veins over the lower leg and ankle.

- ankle edema that worsens when the leg hangs down and improves with elevation;
- **hemosiderin staining**, a grey-brown discoloration around the lower calf and ankle from iron pigment left by broken-down red blood cells; on darker skin it may appear as darker brown or black patches that blend with the person's skin tone, so the nurse compares legs and asks about change;
- hard, tight skin above the ankle, itchy scaling (stasis dermatitis) and, eventually, venous ulcers around the ankle (Chapter 35; Figure 19.7).

Care centres on **compression** and **elevation** (Figure 19.8). Compression lowers venous pressure, but only after an arterial assessment, because compression can harm a leg with poor arterial flow; Wounds Canada advises against compression when the ABI is below 0.5 and reserves high compression for an ABI of 0.9 or higher (Evans et al., 2025). After a venous ulcer heals, compression is generally continued for life to prevent it from returning. Raising the legs above heart level (for example, for 30 minutes three times a day), walking and ankle exercises that work the calf-muscle pump also help. This is the opposite of arterial

disease, in which the legs are not elevated (Table 19.3). A patient with both arterial and venous disease needs a full vascular assessment before compression is used.

Figure 19.7 Chronic venous insufficiency on darker skin: dark hyperpigmentation and thickened skin above the ankle, with an open venous ulcer. (credit: "Chronic venous insufficiency & Venous ulcer" by Ahmed Shawky Mohammedin, MD (Ashashyou)/Wikimedia Commons, CC BY-SA 4.0)

Figure 19.8 Medical compression stockings come in different lengths, strengths and colours; the type is prescribed after an arterial assessment. (credit: "Medizinische Kompressionsstrümpfe" by Enter/Wikimedia Commons, CC BY-SA 3.0)

Table 19.3 Arterial and venous disease compared at the bedside (Abramson et al., 2022; Evans et al., 2025; original wording)

Feature	Arterial disease	Venous disease
Main problem	Too little blood reaching the tissues	Blood pooling in the leg veins
Typical pain	Cramping with walking; rest pain in the foot, worse when the leg is raised	Aching or heaviness, worse at the end of the day, eased by raising the leg
Pulses	Weak or absent	Usually present
Skin and hair	Thin, shiny, dry, hairless; cool	Brownish staining, thickened skin, scaling; warm
Colour with position	Pale when raised; dusky when hanging down	Swelling and darker colour when hanging down

Feature	Arterial disease	Venous disease
Edema	Usually little	Common, around the ankle
Ulcers	Toes or below the ankle; punched out, often pale or dry, black tissue	Around the ankle; shallow, irregular, with moderate to heavy drainage
Positioning	Legs level or slightly lower than the heart	Legs raised above heart level
Compression	Avoided until arterial flow is assessed	Main treatment once arterial flow is confirmed

19.7 Anticoagulation

How Anticoagulants Work

Anticoagulants slow clot formation. They stop existing clots from growing and new clots from forming while the body's own fibrinolytic system gradually breaks the clot down; they do not dissolve clots themselves (thrombolytics are covered in Chapter 15). All of them increase the risk of bleeding.

- **Unfractionated heparin (UFH)** boosts antithrombin, which inactivates thrombin and factor Xa. It is given IV by continuous infusion or subcutaneously, acts quickly and wears off within hours, which makes it useful when a procedure may be needed or kidney function is poor.
- **Low-molecular-weight heparins (LMWHs)**, such as enoxaparin, dalteparin and tinzaparin, act mainly against factor Xa. They are injected subcutaneously at weight-based doses, have a predictable effect and are cleared by the kidneys.
- **Fondaparinux** is a synthetic injectable that blocks factor Xa through antithrombin. It is not recommended for treating DVT or PE when creatinine clearance (CrCl) is 30 mL/min or less (Aspen Pharmacare Canada, 2019).
- **Warfarin**, a vitamin K antagonist, lowers the liver's production of the vitamin K–dependent clotting factors. Its full effect takes several days, so a heparin is often given alongside it at first.
- **Direct oral anticoagulants (DOACs)** act directly on one clotting factor: apixaban, rivaroxaban and edoxaban block factor Xa, and dabigatran blocks thrombin. They work within hours, are taken at fixed doses and do not need routine blood tests of their effect.

Monitoring

- **International normalized ratio (INR):** the standardized measure of warfarin's effect. For most indications, including VTE and atrial fibrillation, the target is 2.5 within a range of 2.0 to 3.0 (Guidelines and Protocols Advisory Committee [GPAC], 2023); mechanical heart valves need different targets (section 18.5). The INR is checked every 2 to 4 days when warfarin is started or its dose is changed, at longer intervals once stable, and more often with illness, new medications or supplements, or a major change in diet.
- **Activated partial thromboplastin time (aPTT) or anti-Xa level:** used to adjust a heparin infusion according to the hospital's protocol (Table 19.4).
- **Platelet count:** watched in patients on heparin for heparin-induced thrombocytopenia (HIT; see the Going Deeper box).
- **Kidney function:** For apixaban, CrCl is estimated with the Cockcroft-Gault formula before the drug starts and checked at least once a year, and more often with dehydration, worsening heart failure or more diuretic use (Pfizer Canada & Bristol-Myers Squibb Canada, 2025). The other DOACs, LMWHs and fondaparinux also depend on the kidneys.
- **Hemoglobin:** a falling value in grams per litre (g/L) can be the first clue to hidden bleeding.

The INR does not measure the effect of apixaban (Pfizer Canada & Bristol-Myers Squibb Canada, 2025), so a normal INR does not mean a patient on a DOAC is not anticoagulated.

Table 19.4 Anticoagulants compared: monitoring, key cautions and reversal (sources in text; original wording)

Drug or class	How it is given	Monitoring	Key cautions	Reversal

Drug or class	How it is given	Monitoring	Key cautions	Reversal
Unfractionated heparin	IV infusion or subcutaneous	aPTT or anti-Xa per protocol; platelets; hemoglobin	High-alert drug; infusion errors; HIT	Protamine
LMWHs (enoxaparin, dalteparin, tinzaparin)	Subcutaneous	Platelets; creatinine; hemoglobin	Builds up when the kidneys fail; spinal or epidural hematoma with neuraxial procedures	Per hospital protocol, with expert advice
Fondaparinux	Subcutaneous	Creatinine; hemoglobin	Not recommended for treatment with CrCl 30 mL/min or less	No specific reversal agent
Warfarin	Oral	INR	Many drug, supplement and food interactions; slow onset and offset; generally avoided in pregnancy	Vitamin K; prothrombin complex concentrate for life-threatening bleeding
Apixaban, rivaroxaban, edoxaban	Oral	Creatinine; hemoglobin; INR is not a guide	Missed doses; interacting drugs; kidney function	Prothrombin complex concentrate (off-label; usual Canadian care)
Dabigatran	Oral	Creatinine; hemoglobin	Strongly dependent on the kidneys	Idarucizumab

Bleeding and Reversal

Some bleeding is obvious: nosebleeds, bleeding gums, blood in the urine, heavy menstrual periods, large bruises, or vomit that is bloody or looks like coffee grounds. Other bleeding is hidden and must be suspected:

- black, tarry stools from bleeding in the gut;
- headache, drowsiness, confusion or vomiting after a fall or head knock, which may signal bleeding inside the skull, even when the patient first seems well (Chapter 8);
- back, flank or groin pain, especially after a femoral procedure, which may signal bleeding behind the abdomen;
- dizziness, fainting, a rising pulse, falling blood pressure or a falling hemoglobin.

When bleeding is suspected, the nurse first stops a running anticoagulant infusion or holds the next dose as policy directs, applies pressure to any visible bleeding site and assesses airway, breathing, circulation and level of consciousness. The nurse then escalates using SBAR (Situation, Background, Assessment, Recommendation; Chapter 6), reporting the drug, dose and time of the last dose, because these determine which reversal agent is used. Blood work is sent as ordered, and blood products are given according to Chapter 20.

Reversal depends on the drug:

- **Warfarin:** vitamin K, given orally for a high INR and IV in emergencies, plus **prothrombin complex concentrate (PCC)**, a concentrate of vitamin K–dependent clotting factors, for life-threatening bleeding (GPAC, 2023).
- **Heparin:** protamine neutralizes heparin within minutes of IV administration; given too fast, it can cause severe hypotension and anaphylactoid reactions (Fresenius Kabi Canada, 2016).
- **Dabigatran:** idarucizumab, an antibody fragment that binds only dabigatran and reverses no other anticoagulant (Boehringer Ingelheim Canada, 2019).
- **Factor Xa inhibitors (apixaban, rivaroxaban, edoxaban):** in Canada, usual care for major bleeding is PCC, used off-label, together with stopping the drug, resuscitation, local measures and blood products (Canadian Agency for Drugs and Technologies in Health [CADTH], 2024). Andexanet alfa, a specific reversal agent for apixaban and rivaroxaban, received conditional Health Canada authorization in 2023 and is listed as marketed, but CADTH recommended against public reimbursement and Canadian Blood Services decided not to list it (Canadian Blood Services, 2024). Experts consulted for the CADTH review noted that PCC and blood products are not available in every clinical setting (CADTH, 2024), which matters for patients far from a hospital.

CLINICAL SAFETY

Anticoagulants as High-Alert Medications

The Institute for Safe Medication Practices Canada (ISMP Canada) lists anticoagulants among **high-alert medications**: drugs that are not necessarily involved in more errors, but that carry a greater risk of serious harm when an error happens (ISMP Canada, 2016). ISMP Canada has reported a patient death after a home LMWH was continued on admission while a heparin infusion was also started; the duplication was not caught before both were given. System safeguards work better than vigilance alone:

- Reconcile medications on admission and transfer, and look for duplicate anticoagulants, including a home LMWH or DOAC alongside a hospital heparin.
- Use standard concentrations and pre-mixed bags, and programmed infusion pumps with dose limits.
- Check heparin vials and bags carefully, because products with very different strengths can look alike.
- Complete an independent double check before starting an infusion or changing its rate when policy requires it; the second nurse checks the order, product, concentration, pump settings and patient on their own, not by reading out the first nurse's work.
- Document the product, concentration, rate, laboratory result and time of each change.
- Act on aPTT or anti-Xa results promptly and adjust the infusion only as the protocol directs.

MEDICATIONS

Anticoagulants and Their Reversal

- **UFH:** IV or subcutaneous; aPTT or anti-Xa monitoring per protocol; reversed by protamine.
- **LMWHs (enoxaparin, dalteparin, tinzaparin):** subcutaneous; check platelets and creatinine; follow the product's injection instructions.
- **Fondaparinux:** subcutaneous; avoid for treatment when CrCl is 30 mL/min or less.
- **Warfarin:** oral; INR guides dosing; many interactions; reversed with vitamin K and PCC.
- **Apixaban, rivaroxaban, edoxaban:** oral factor Xa inhibitors; kidney function checked; PCC is the usual reversal approach in Canada.
- **Dabigatran:** oral thrombin inhibitor; strongly kidney-dependent; reversed with idarucizumab.
- **All:** watch for bleeding, ask about falls, and check for spinal or epidural hematoma (leg numbness or weakness, bowel or bladder changes) after neuraxial anesthesia or lumbar puncture (Pfizer Canada & Bristol-Myers Squibb Canada, 2025).

Teaching and Transitions

Anticoagulants are safe only when taken as directed. Stopping early raises the risk of clots (Pfizer Canada & Bristol-Myers Squibb Canada, 2025), so the nurse explains why the drug is needed and for how long, and checks that the patient can get and afford the next supply. Teaching covers:

- **Missed doses:** instructions differ by drug and by once- or twice-daily schedule. For apixaban, the patient takes the missed dose as soon as remembered and continues the usual twice-daily schedule, without doubling a dose (Pfizer Canada & Bristol-Myers Squibb Canada, 2019). For other drugs, the nurse uses that product's patient information or asks the pharmacist.
- **Interactions:** other anticoagulants and antiplatelet drugs, ASA, NSAIDs such as ibuprofen, and some antidepressants increase bleeding. Some antifungals and human immunodeficiency virus (HIV) drugs raise apixaban levels, and rifampin, some seizure medications and St. John's wort lower them (Pfizer Canada & Bristol-Myers Squibb Canada, 2025). Warfarin interacts with many antibiotics, acetaminophen in higher doses, alcohol binges and supplements such as fish oil, garlic and ginseng (GPAC, 2023).
- **Vitamin K and warfarin:** no food is forbidden. The patient keeps vitamin K intake steady from week to week rather than avoiding green vegetables, and reports large diet changes or nutritional supplement drinks (GPAC, 2023).
- **Falls and injuries:** removing fall hazards (Chapter 8), and seeking same-day assessment after any head injury.
- **Procedures:** telling dentists, surgeons and pharmacists about the anticoagulant before any procedure (Chapter 7).
- **Identification and pregnancy:** wearing medical alert identification; warfarin is generally avoided in pregnancy, so people who could become pregnant discuss contraception and plans (GPAC, 2023).

Older adults need extra attention. Kidney function falls with age and with dehydration or acute illness, many older adults take several interacting drugs, and falls are common, so the nurse reviews creatinine, the medication list and fall risk at every transition (Pfizer Canada & Bristol-Myers Squibb Canada, 2025; Chapter 8).

Cost is a real barrier. Drug coverage differs by province or territory and by private plan, and DOACs cost more than warfarin. The nurse asks directly about cost, involves the pharmacist or social worker, and checks that patients in rural, remote and northern communities can reach INR testing or pharmacy services (Chapter 2).

PATIENT EDUCATION

Living Safely With an Anticoagulant

- Take your anticoagulant at the same time every day. Use a pill organizer or phone reminder.
- If you miss a dose, follow the instructions for your medicine. Never take two doses to catch up. Ask your pharmacist if you are unsure.
- Do not stop taking it unless your health care provider tells you to.
- Check with your pharmacist before taking any new medicine, pain reliever, vitamin or herbal product. Avoid ibuprofen and naproxen unless your provider approves them.
- If you take warfarin, keep your diet steady from week to week, and go for every INR test.
- Use a soft toothbrush and an electric razor.
- Get medical help the same day if you hit your head, even if you feel fine.
- Call 9-1-1 if you have a sudden severe headache, vomit blood, have black stools or bleeding that will not stop.
- Tell every dentist, surgeon and pharmacist that you take an anticoagulant.
- Wear medical alert identification.

GOING DEEPER

Heparin-Induced Thrombocytopenia and Anti-Xa Monitoring

Required for RN students; optional for PN students.

Heparin-induced thrombocytopenia (HIT) is an immune reaction in which antibodies form against heparin bound to a platelet protein. The antibodies activate platelets, so the platelet count falls while the risk of clotting rises sharply. ASH describes HIT as a profoundly hypercoagulable state in which one-third to one-half of patients develop venous, arterial or small-vessel thrombosis (Cuker et al., 2018). A platelet fall of more than 50% that begins 5 to 10 days after heparin is started points most strongly to HIT.

Clinicians estimate the probability of HIT with the **4Ts** score, which considers how far the platelets have fallen, when the fall began in relation to heparin exposure, whether new thrombosis is present, and whether another cause of a low platelet count is more likely. A low score makes HIT unlikely, and laboratory testing is not recommended. With an intermediate or high score, all heparin is stopped and a non-heparin anticoagulant such as argatroban, fondaparinux or a DOAC is started. Routine platelet transfusion is avoided, and warfarin is not started until the platelet count recovers.

UFH infusions are adjusted using either the aPTT, a clotting time affected by many factors, or an anti-Xa level, which measures heparin's activity directly. Each hospital chooses one method and a protocol with set targets; the nurse follows that protocol.

SCOPE IN PRACTICE

Heparin Infusions, Injections and Doppler Checks

Whether a nurse performs a task depends on **authority, competence and context** (Chapter 1, section 1.3); employer policy and the province or territory also matter.

- **Subcutaneous LMWH:** registered nurses (RNs) and registered practical nurses (RPNs) commonly give it and teach self-injection once they have the authority (an order) and competence.
- **IV heparin infusions:** many hospitals assign titrated heparin infusions to RNs, or require added education before RPNs manage them. The rule comes from employer policy, not from any College of Nurses of Ontario (CNO) classification of patients.
- **Doppler pulse checks and ABI:** handheld Doppler pulse checks are within both RN and RPN practice when the nurse is competent and the employer supports it. ABI is often done by vascular laboratory staff or nurses with added training.

- **Escalation:** every nurse who notices bleeding, a pulseless limb or signs of PE acts at once and escalates. The RPN consults the RN as the patient's needs change, for example when a stable patient on an LMWH develops melena or a falling hemoglobin.

PRACTICE STORY

A Sunday Morning Visit

Names and details are fictional; this is a composite story.

Nurse: Maya Nwosu, RPN. Years in practice: 6. Setting: home and community care, Ontario.

Mrs. Rose Thibault is 84 and lives alone in a small town. She takes apixaban for atrial fibrillation, and I visit twice a week to manage her leg wound. On Sunday her daughter, Claire, met me at the door. "Mom tripped on the bath mat last night. She bumped her head on the sink, but she says she's fine."

Mrs. Thibault was in her chair doing the crossword. She knew the day and the date, her speech was clear and her grips were equal. There was a small swelling above her right eyebrow. Her blood pressure was 148/82 mm Hg and her pulse was 78 and irregular, her usual rhythm. She had no headache and no nausea.

It would have been easy to feel reassured. But I knew her anticoagulant meant she could be bleeding inside her skull without any signs yet, and that a bleed can show up hours after a fall. Her normal assessment did not rule that out.

I explained to Mrs. Thibault and Claire that she needed to be seen in the emergency department that morning. Mrs. Thibault said she didn't want to "make a fuss." I told her plainly why the visit mattered, and she agreed. Claire drove her to the hospital, and I made sure the apixaban bottle and medication list went with her.

I called the emergency department and gave a short report: anticoagulant, time of her last dose, time of the fall and my findings. I then called the on-call RN for our agency and left a message for the care coordinator, so her visits and wound care could be adjusted. I documented my assessment, advice and calls.

Claire phoned that evening. The scan showed no bleeding, and her mother was home. The next week we talked about removing the bath mat and adding grab bars.

Reflect: Which cues told the nurse that a normal assessment was not enough? Which actions were within the RPN's scope, and when should the RPN involve the RN?

Chapter 19 Summary

Introduction

- Hypertension is one of the most common chronic conditions in adults; it is usually silent but damages arteries and organs over time.
- This chapter covers hypertension, acute aortic syndromes, arterial and venous disease, venous thromboembolism and anticoagulation, the book's main section on anticoagulants.

19.1 Hypertension: Measurement and Risk

- Blood pressure depends on cardiac output and systemic vascular resistance, regulated by the sympathetic nervous system, the RAAS and the kidneys' handling of sodium.
- Hypertension Canada's 2025 guideline defines hypertension as 130/80 mm Hg or higher by any validated method; the 2020 guidelines used higher, method-specific thresholds.
- AOBP and out-of-office readings (home or ambulatory) are preferred; manual technique is used when arrhythmias make automated readings unreliable.
- Cuff size, arm position, rest, silence and slow deflation all affect accuracy; white-coat and masked hypertension are found only by measuring outside the office.
- Secondary causes include kidney disease, primary aldosteronism, sleep apnea and drugs such as NSAIDs and decongestants; food environments, income and access to care make diagnosis and control harder for some people.

19.2 Treating Hypertension

- Lifestyle targets include sodium under 2 g a day, potassium over 3.5 g a day from food, 150 to 300 minutes of moderate activity a week, less alcohol and quitting smoking.
- Drugs start at 140/90 mm Hg, or at a systolic of 130 to 139 mm Hg in high-risk people; the systolic target is below 130 mm Hg if tolerated.
- First-line treatment is two of three classes (ACE inhibitor or ARB, thiazide-type diuretic, long-acting dihydropyridine calcium channel blocker), ideally as a single-pill combination.
- In hospital, the nurse follows hold parameters, checks orthostatic vital signs, treats pain or anxiety before reacting to a single high reading, and reconciles home medications.
- For older adults with frailty, falls or orthostatic hypotension, targets are individualized.

19.3 Hypertensive Emergencies and Acute Aortic Syndromes

- A hypertensive emergency is severe hypertension with acute damage to the brain, eyes, heart, kidneys or aorta; without organ damage, oral drugs and gradual lowering are used.
- In most emergencies, pressure is lowered in a controlled way over hours, because a sudden fall can cause ischemia.
- The nurse rechecks readings, assesses neurologic status, chest pain, breathing and urine output, and escalates at once.
- Aortic dissection causes sudden tearing pain and unequal pulses or arm pressures; heart rate and systolic pressure are lowered quickly, and anticoagulants or thrombolytics given in error can cause fatal bleeding.

19.4 Peripheral Arterial Disease

- PAD is usually atherosclerosis of the leg arteries; smoking, diabetes, kidney disease and age raise the risk, and it signals high cardiovascular risk.
- In Ontario, First Nations people with diabetes had three to five times the amputation rate of other Ontarians, and amputation rates were highest in rural, remote and lower-income regions, reflecting structural barriers to care.
- Claudication, rest pain, ulcers, weak pulses, elevation pallor and dependent rubor are key findings; colour changes are assessed with care on darker skin.
- The CCS states that an ABI below 0.9 suggests PAD; calcified arteries can give falsely normal or high values.
- Care includes smoking cessation, supervised exercise, a statin, antithrombotic therapy, foot care, checks after revascularization, and keeping the legs level or slightly lowered.
- Acute limb ischemia, especially with new sensory or motor loss, is an emergency; the nurse escalates at once.

19.5 Abdominal Aortic Aneurysm

- An AAA is usually silent until it ruptures; male sex, smoking, age and family history are the strongest risk factors.
- The CTFPHC recommends one-time ultrasound screening for men aged 65 to 80, not for older men or for women.
- Sudden abdominal, back or flank pain with signs of shock in a patient with an AAA is treated as rupture and escalated immediately.
- After repair, the nurse checks limb perfusion, access sites, kidney function and the bowel; EVAR needs imaging follow-up as the vascular team directs.

19.6 Venous Disease and VTE

- Virchow's triad of stasis, vein wall injury and hypercoagulability explains VTE risk factors.
- DVT signs are unreliable; pretest probability guides testing, with D-dimer first when probability is lower and compression ultrasound first when it is higher.
- Most patients start anticoagulation, often at home, and walk early; routine compression stockings are not recommended to prevent post-thrombotic syndrome.

- Chronic venous insufficiency causes edema, staining and ulcers; compression after arterial assessment and leg elevation are central, unlike in arterial disease.

19.7 Anticoagulation

- UFH, LMWHs, fondaparinux, warfarin and DOACs act at different points in clotting and differ in route, monitoring and reversal.
- The INR target for most warfarin indications is 2.0 to 3.0; heparin infusions follow aPTT or anti-Xa protocols; kidney function and hemoglobin are checked for all.
- The nurse recognizes hidden bleeding, holds the drug, assesses and escalates; reversal agents include vitamin K and PCC for warfarin, protamine for heparin and idarucizumab for dabigatran, with PCC as usual Canadian care for factor Xa inhibitors.
- Anticoagulants are high-alert medications that need system safeguards, and teaching covers adherence, missed doses, interactions, vitamin K consistency, falls, procedures, identification and cost.

Key Terms (44)

abdominal aortic aneurysm (AAA): a weak area in the wall of the abdominal aorta that balloons outward.

acute aortic syndrome: A life-threatening injury to the wall of the aorta, such as aortic dissection, that causes sudden severe pain.

acute limb ischemia: sudden loss of blood flow to a limb that threatens its survival and needs emergency treatment.

ambulatory blood pressure monitoring (ABPM): Blood pressure measured automatically every 20 to 30 minutes over a day and night by a device the person wears.

ankle-brachial index (ABI): the ratio of ankle to arm systolic pressure; the CCS states that a value below 0.9 suggests PAD.

anticoagulant: a drug that slows clot formation and stops existing clots from growing.

aortic dissection: A tear in the inner lining of the aorta that lets blood track between the layers of its wall.

automated office blood pressure (AOBP): Several readings taken and averaged by a validated automated upper-arm device in a health care setting.

chronic limb-threatening ischemia (CLTI): advanced PAD with ischemic rest pain, ulcers or gangrene.

chronic venous insufficiency (CVI): persistently high pressure in the leg veins from failed valves or blocked veins, causing edema, skin changes and ulcers.

compression ultrasound: ultrasound in which a vein that will not collapse under probe pressure shows a clot.

D-dimer: a fragment released when cross-linked fibrin breaks down; a negative result helps rule out DVT when pretest probability is low.

deep vein thrombosis (DVT): a clot in a deep vein, most often in the leg or pelvis.

dependent rubor: dusky red colour of the foot when the leg hangs down, a sign of advanced arterial disease.

direct oral anticoagulant (DOAC): an oral drug that directly blocks factor Xa (apixaban, rivaroxaban, edoxaban) or thrombin (dabigatran).

elevation pallor: blanching of the foot when the leg is raised, a sign of arterial disease.

endovascular aneurysm repair (EVAR): repair of an aneurysm with a stent graft placed through the femoral arteries.

hemosiderin staining: grey-brown or dark discoloration of the lower leg from iron pigment left by broken-down red blood cells.

heparin-induced thrombocytopenia (HIT): an immune reaction to heparin that lowers the platelet count and greatly increases the risk of clotting.

high-alert medication: a drug that carries a high risk of serious harm when an error occurs.

home blood pressure monitoring (HBPM): Readings taken by the person at home with a validated device, using a set schedule such as two readings morning and evening for 1 week.

hypertension: Blood pressure persistently at or above 130/80 mm Hg, taken with a validated device and standardized technique (Goupil et al., 2025).

hypertensive emergency: Severe hypertension with new or worsening damage to the brain, eyes, heart, kidneys or large arteries.

hypertensive urgency: Severe hypertension without acute target-organ damage; treated with oral drugs and gradual lowering.

intermittent claudication: cramping or aching leg pain that comes on with walking at a predictable distance and eases with rest.

international normalized ratio (INR): the standardized test of warfarin's effect; the usual target range is 2.0 to 3.0.

low-molecular-weight heparin (LMWH): a subcutaneous heparin, such as enoxaparin, dalteparin or tinzaparin, that acts mainly against factor Xa.

masked hypertension: Normal blood pressure in the office with raised readings at home or on ambulatory monitoring.

orthostatic hypotension: A sustained fall of at least 20 mm Hg systolic or 10 mm Hg diastolic within 3 minutes of standing.

peripheral arterial disease (PAD): narrowing or blockage of the arteries that supply the limbs, usually from atherosclerosis.

post-thrombotic syndrome (PTS): lasting pain, swelling, heaviness and skin changes in a leg after DVT.

pretest probability: the estimated likelihood of a disease before testing, used to choose the testing path.

primary aldosteronism: Excess aldosterone production by the adrenal glands, a cause of secondary hypertension.

primary hypertension: Hypertension without a single identifiable cause.

prothrombin complex concentrate (PCC): a concentrate of vitamin K–dependent clotting factors used to reverse warfarin and, in Canadian practice, for major bleeding on factor Xa inhibitors.

secondary hypertension: Hypertension caused by an identifiable condition or drug.

single-pill combination: A tablet that contains two or more blood-pressure-lowering drugs.

superficial vein thrombosis (SVT): a clot with inflammation in a vein near the skin surface.

systemic vascular resistance: The resistance that small arteries and arterioles offer to blood flow.

target-organ damage: Injury to the brain, eyes, heart, kidneys or large arteries caused by high blood pressure.

unfractionated heparin (UFH): an anticoagulant given IV or subcutaneously that boosts antithrombin; monitored by aPTT or anti-Xa level.

venous thromboembolism (VTE): deep vein thrombosis, pulmonary embolism or both.

Virchow's triad: stasis of blood flow, vein wall injury and hypercoagulability, the three conditions that favour venous clotting.

white-coat hypertension: Raised blood pressure in the office with normal readings at home or on ambulatory monitoring.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mr. Samuel Mensah (Questions 1–6): Mr. Samuel Mensah, 58, is on a medical unit with cellulitis of the left leg. He has a history of hypertension and ran out of his home medication 5 days ago. At 2200 he reports a severe headache, nausea and blurred vision. Repeat readings with a correctly sized cuff are 224/132 mm Hg in the right arm and 220/130 mm Hg in the left. Heart rate 96 beats/min, respiratory rate 20 breaths/min, SpO2 96% on room air, temperature 37.4 °C. He is unsure of the date. Serum creatinine is 171 µmol/L today; it was 94 µmol/L on admission. He has passed 90 mL of urine in the past 4 hours.

1. [CORE] Which findings suggest acute target-organ damage in Mr. Mensah? Select all that apply.

- **a.** Severe headache with blurred vision
- **b.** New uncertainty about the date
- **c.** Creatinine rise from 94 to 171 µmol/L
- **d.** Heart rate of 96 beats/min
- **e.** Running out of medication 5 days ago
- **f.** SpO2 of 96% on room air

Answer: a, b, c — Headache with vision change (a) and new confusion (b) point to the brain and eyes, and a rapid rise in creatinine with low urine output (c) points to kidney injury (section 19.3). A heart rate of 96 beats/min (d) is mildly raised and not specific. Missed medication (e) explains why the pressure rose but is not organ damage. SpO2 of 96% (f) is within the expected range.

2. [CORE] Which interpretation best fits Mr. Mensah's findings?

- **a.** Hypertensive emergency with signs of brain and kidney injury
- **b.** Hypertensive urgency caused by pain and stress from the cellulitis
- **c.** White-coat hypertension triggered by the hospital setting
- **d.** Expected rebound that will settle once he sleeps

Answer: a — Severe hypertension with new neurologic signs and acute kidney injury meets the definition of a hypertensive emergency (a) (section 19.3, Table 19.2). Urgency (b) means no acute organ damage, which is not the case here. White-coat hypertension (c) is a diagnosis made by comparing office and home readings, not an explanation for symptoms. Waiting for him to sleep (d) would delay care for an emergency.

3. [CORE] Which concern has the highest priority for Mr. Mensah right now?

- **a.** Risk of falls from nausea and blurred vision
- **b.** Worsening infection in the left leg
- **c.** Knowledge gap about refilling his prescriptions
- **d.** Injury to the brain from severely raised pressure

Answer: d — New confusion with severe hypertension signals possible encephalopathy or stroke, which can progress quickly (d) (section 19.3). Falls (a) are a real risk, but they follow from the neurologic problem. The cellulitis (b) is being treated and is not the immediate threat. Teaching about refills (c) matters before discharge but not during an emergency.

4. [CORE] The nurse anticipates the team's plan. Which approach to lowering Mr. Mensah's blood pressure is expected?

- **a.** An extra dose of his usual oral antihypertensive now, with a recheck of the pressure in the morning
- **b.** Controlled lowering with IV medication in a monitored setting over hours
- **c.** Rapid lowering to below 120/80 mm Hg within the first 30 minutes
- **d.** No treatment until a CT scan of the head is completed

Answer: b — Most hypertensive emergencies are treated with titrated IV drugs in a monitored area, lowering pressure gradually because a sudden fall can cause ischemia (b) (section 19.3). An oral dose with a morning recheck (a) fits urgency, not emergency. Rapid lowering to normal (c) risks stroke and other ischemic injury; fast lowering is reserved for aortic dissection. Imaging may be part of the work-up, but treatment of a hypertensive emergency is not simply withheld until it is done (d).

5. [CORE] Mr. Mensah's nurse is a registered practical nurse (RPN). What should the RPN do first?

a. Stay with him and call the rapid response team or the most responsible provider

b. Give the PRN acetaminophen ordered for headache and recheck the blood pressure in 1 hour

c. Ask the RN on the next unit to come and assess him before calling anyone else

d. Document the readings and report them to the night supervisor at the end of the shift

Answer: a — Every nurse who notices deterioration acts at once and escalates, using the unit's process (a) (section 19.3; Chapter 6; Chapter 1, section 1.3). Treating the headache alone (b) delays care for a hypertensive emergency. Waiting for another nurse to assess (c) wastes time; the RPN can call directly and involve the RN as the patient's needs change. Reporting at the end of the shift (d) is unsafe.

6. [CORE] Mr. Mensah is transferred to the intensive care unit and IV treatment is started. Which finding 2 hours later best shows that care is working safely?

a. Blood pressure 118/74 mm Hg with new drowsiness

b. Blood pressure 210/126 mm Hg with the headache unchanged since the infusion began

c. Blood pressure 120/80 mm Hg and urine output 10 mL/h

d. Blood pressure 178/106 mm Hg and he now states the date correctly

Answer: d — A gradual fall with improving orientation shows the brain is being protected (d) (section 19.3). A fall to 118/74 mm Hg with new drowsiness (a) suggests the pressure dropped too far, too fast. Unchanged pressure and symptoms (b) show treatment is not yet effective. A normal pressure with very low urine output (c) may mean the kidneys are underperfused.

7. [CORE] The nurse measures the mid-upper arm of a patient as 40 cm. Which cuff bladder width is closest to correct for a manual reading?

a. 10 cm

b. 16 cm

c. 24 cm

d. 32 cm

Answer: b — The bladder width should be about 40% of arm circumference, so about 16 cm for a 40 cm arm (b) (section 19.1). A 10 cm bladder (a) is too narrow for this arm, so the reading would be inaccurate. Widths of 24 cm (c) and 32 cm (d) are far too wide; 32 cm is closer to the bladder length needed, which covers 80% to 100% of the arm.

8. [CORE] A student takes a manual blood pressure while the patient sits with the arm hanging at the side, below heart level. What effect does the nurse expect this error to have?

a. The reading will underestimate the true pressure.

b. There is no effect as long as the cuff is the right size.

c. Only the diastolic value will be affected.

d. The reading will overestimate the true pressure.

Answer: d — An arm below heart level gives falsely high systolic and diastolic readings (d) (section 19.1). It does not lower the reading (a). A correctly sized cuff does not make up for poor arm position (b). Both the systolic and the diastolic values are affected, not only the diastolic (c).

9. [CORE] A patient is learning home blood pressure monitoring. Which statement shows the teaching has been understood?

a. "I'll take two readings 1 minute apart each morning and evening for a week."

b. "I'll check my pressure right after my morning walk, when I feel most awake."

c. "I'll take one reading a day, whenever I remember, for the next month."

d. "I'll keep my sweater on so the cuff fits snugly over the sleeve."

Answer: a — Hypertension Canada advises two readings, 1 minute apart, morning and evening for 7 days (a) (section 19.1). Exercise in the 30 minutes before (b) raises readings. Single random readings (c) do not follow the protocol. The cuff goes on the bare arm (d).

10. [CORE] A patient's home readings over 1 week average 134/82 mm Hg. According to Hypertension Canada's 2025 guideline, how should the nurse interpret this average?

a. Normal, because home readings use a threshold of 135/85 mm Hg

b. Normal, because hypertension starts at 140/90 mm Hg

c. In the hypertensive range, because the threshold is 130/80 mm Hg for all methods

d. Not interpretable, because only readings taken in an office can be used to diagnose hypertension

Answer: c — The 2025 guideline uses 130/80 mm Hg for every validated method, so this average is in the hypertensive range (c) (section 19.1, Table 19.1). The 135/85 mm Hg home threshold (a) comes from the older 2020 guidelines. A threshold of 140/90 mm Hg (b) is the level at which drug treatment is generally started, not the definition. Home readings are recommended to confirm the diagnosis (d).

11. [CORE] Lying, a patient's blood pressure is 142/84 mm Hg. Which standing reading at 3 minutes meets the definition of orthostatic hypotension?

a. 134/80 mm Hg

b. 120/80 mm Hg

c. 138/78 mm Hg

d. 130/76 mm Hg

Answer: b — Orthostatic hypotension is a fall of at least 20 mm Hg systolic or 10 mm Hg diastolic within 3 minutes of standing; 142 to 120 is a 22 mm Hg systolic fall (b) (section 19.2). The falls in (a) (8 systolic, 4 diastolic), (c) (4 and 6) and (d) (12 and 8) are all below those amounts.

12. [CORE] Which teaching statement about sodium matches Hypertension Canada's 2025 guideline?

a. "Using less salt at the table is the main way to cut the sodium you eat."

b. "Sea salt is a low-sodium choice you can use freely."

c. "Aim for under 2 grams of sodium a day; most comes from processed foods."

d. "Sodium matters only if you also have kidney disease."

Answer: c — The guideline sets a target of under 2 g of sodium a day and notes that in a typical Western diet more than 70% of sodium comes from processed foods (c) (section 19.2). Table salt (a) is a smaller source than processed food. Sea salt (b) is still sodium. Sodium reduction is advised for all adults with hypertension (d).

13. [CORE] Which patient's blood pressure is most likely to reflect white-coat hypertension?

a. Office readings of 148/92 mm Hg with home readings averaging 122/76 mm Hg

b. Office readings of 124/78 mm Hg with home readings averaging 142/88 mm Hg

c. Office and home readings both averaging 150/94 mm Hg

d. Office readings of 118/74 mm Hg with home readings averaging 116/72 mm Hg

Answer: a — White-coat hypertension is raised office pressure with normal out-of-office readings (a) (section 19.1). Option (b) shows masked hypertension. Option (c) shows sustained hypertension. Option (d) is normal in both settings.

14. [CORE] An RPN is about to give amlodipine at 0900. The order says, "Hold if systolic BP below 100 mm Hg." The patient's systolic pressure is 92 mm Hg, and he says he feels light-headed. What should the RPN do?

a. Give the dose because amlodipine works slowly and will not lower the pressure today

b. Give half the tablet and recheck the pressure in 1 hour

c. Ask the patient whether he wants to take the dose

d. Hold the dose, keep him safe from falls, and report and document the finding

Answer: d — The order gives a hold parameter, and the patient is symptomatic, so the RPN holds the dose, protects him from falls and reports to the prescriber, documenting the action (d) (section 19.2; Chapter 1, section 1.3). Giving the full dose (a) ignores the order. Splitting a tablet (b) changes the dose without an order. A patient may refuse a medication, but asking him to decide (c) does not replace the nurse's duty to follow the hold order and report.

15. [CORE] A patient admitted for a knee replacement has a blood pressure of 176/98 mm Hg on the first postoperative evening. He rates his pain as 8 out of 10 and is grimacing. He has no headache, chest pain or neurologic change. What is the nurse's best first action?

a. Call the prescriber at once to request an IV antihypertensive for the reading

b. Treat his pain as ordered, then recheck the pressure after he rests

c. Give his usual morning antihypertensive dose now

d. Activate the rapid response team for a hypertensive emergency

Answer: b — A high reading in a patient in severe pain, without signs of organ damage, is usually a stress response; the nurse treats the cause and rechecks (b) (section 19.2). An IV antihypertensive (a) is not indicated without organ damage. Giving a scheduled dose early (c) needs an order. There are no features of a hypertensive emergency (d), although the nurse escalates if symptoms appear or the pressure stays high.

16. [CORE] A patient with long-standing hypertension suddenly reports severe chest pain "like something ripping" that moves to his back. Which finding most strongly supports the nurse's concern about aortic dissection?

a. Right arm 168/94 mm Hg; left arm 136/80 mm Hg

b. Pain that eases when he leans forward

c. Pain that is worse with deep breathing and coughing

d. A heart rate of 88 beats/min that is regular

Answer: a — A systolic difference of more than 20 mm Hg between arms, with tearing pain, is a high-risk feature of acute aortic syndrome (a) (section 19.3). Pain eased by leaning forward (b) suggests pericarditis (Chapter 18). Pain worse with breathing (c) suggests a pleural cause. A regular heart rate of 88 (d) is not specific.

17. [CORE] The nurse suspects aortic dissection in the patient above. The emergency physician has not yet seen him, and a colleague suggests starting the heparin order set for a possible heart attack. What should the nurse do?

a. Start the heparin order set, because early anticoagulation improves outcomes in a heart attack

b. Give ASA from the chest pain order set now and start heparin once the ECG is done

c. Tell the physician about the tearing pain and unequal arm pressures before any anticoagulant

d. Wait for the physician to arrive and complete the assessment before reporting findings

Answer: c — Dissection can resemble a heart attack, and anticoagulants or thrombolytics given in error to a patient with dissection can cause serious or fatal bleeding; the nurse reports the features of dissection before any such drug is given (c) (section 19.3). Starting heparin (a) or giving ASA (b) without that information is unsafe. Waiting to report (d) delays emergency care.

18. [RN] A patient in a hypertensive emergency has a blood pressure of 220/130 mm Hg. The order is to lower the mean arterial pressure (MAP) by no more than 25% in the first hour. What is the lowest MAP the nurse should accept at 1 hour?

a. 98 mm Hg

b. 160 mm Hg

c. 120 mm Hg

d. 140 mm Hg

Answer: c — MAP is about (systolic + 2 × diastolic) ÷ 3, so (220 + 260) ÷ 3 = 160 mm Hg; a 25% fall gives 120 mm Hg (c) (section 19.3, Going Deeper). A MAP of 98 mm Hg (a) is a fall of nearly 40%, which risks ischemia. A MAP of 160 mm Hg (b) is the starting value. A MAP of 140 mm Hg (d) is within the limit but is not the lowest acceptable value.

19. [RN] A patient with aortic dissection is receiving IV esmolol. The prescriber plans to add sodium nitroprusside. Which statement about the order of these drugs is correct?

a. Esmolol is started first so that nitroprusside can share its IV line.

b. Once esmolol is running, an arterial line is no longer needed.

c. Esmolol is expected to bring systolic pressure to target within 5 minutes.

d. Heart rate is controlled first; a vasodilator is added if needed.

Answer: d — The 2022 ACC/AHA guideline recommends an IV beta-blocker as initial management, aiming for a heart rate of 60 to 80 beats/min, with an IV vasodilator added if blood pressure is not controlled (d) (section 19.3, Going Deeper). The order of drugs has nothing to do with sharing an IV line (a). Continuous arterial pressure monitoring is still recommended (b). The aim is controlled lowering to the ordered targets, not a set number of minutes (c).

20. [RN] A patient receiving a titrated IV antihypertensive has an arterial line reading 88/50 mm Hg. Twenty minutes ago it read 150/90 mm Hg. The patient is alert and talking, and a cuff reading on the other arm is 148/88 mm Hg. What should the nurse do first?

a. Stop the infusion and call the rapid response team for hypotension

b. Check the arterial line set-up, including transducer level, zero and waveform

c. Increase the infusion rate, because the cuff reading is still above target

d. Remove the arterial line, because it is clearly malfunctioning

Answer: b — An alert patient with a cuff reading that matches the earlier trend suggests a technical problem; the nurse checks the transducer level, zero and waveform first (b) (section 19.3, Going Deeper). Stopping the infusion (a) based on a suspect reading could cause a rebound rise. Increasing the rate (c) before resolving the discrepancy is unsafe. Removing the line (d) needs an order and is not the first step.

Case: Gordon (Questions 21–24): Gordon, 71, is admitted to a medical unit with a left-leg DVT. He has started apixaban. He also takes ASA for a past heart attack and ibuprofen for knee pain, and he lives alone in a rural community.

21. [CORE] Which finding should the nurse report first?

a. Mild bruising at a former IV site

b. A black, tarry stool this morning

c. Persistent swelling of the left calf

d. A blood pressure of 136/84 mm Hg

Answer: b — Black, tarry stool suggests gastrointestinal bleeding, a serious hidden bleed in a patient on an anticoagulant plus ASA and an NSAID (section 19.7). Minor bruising is expected and less urgent. Calf swelling persists for days after DVT treatment begins. The blood pressure is acceptable and not a sign of bleeding.

22. [CORE] Gordon asks whether he will need regular blood tests to check that apixaban is working, as his brother does with warfarin. What is the nurse's best response?

a. "You will need an INR test every 2 to 4 days at first."

b. "Apixaban needs an aPTT test before each dose."

c. "The INR will tell us if the dose is right for you."

d. "Its effect is not checked routinely, but your kidney function will be."

Answer: d — DOACs are given at fixed doses without routine tests of their effect, but kidney function is checked before starting and at least yearly (section 19.7). INR testing every 2 to 4 days applies to warfarin. aPTT is used for heparin infusions. The INR does not measure apixaban's effect.

23. [CORE] Which statement by Gordon shows that teaching about pain relief has been effective?

a. "I'll take ibuprofen only when my knee is very sore."

b. "I'll ask the pharmacist before I take any pain medicine."

c. "I'll switch from ibuprofen to naproxen instead."

d. "I can take extra ASA for my knee because it is only a mild pain reliever."

Answer: b — NSAIDs and extra ASA increase bleeding with an anticoagulant, so checking with the pharmacist before taking any pain reliever shows understanding (section 19.7). Occasional ibuprofen still adds risk. Naproxen is also an NSAID. Extra ASA increases bleeding risk.

24. [CORE] Before discharge, which action best addresses Gordon's risk of not continuing apixaban at home?

a. Confirming that he can afford and obtain the medication locally

b. Giving him a printed list of foods high in vitamin K

c. Booking weekly INR tests at the laboratory closest to his home community

d. Teaching him to take two tablets if he misses a dose

Answer: a — Cost, coverage and access to a pharmacy are real barriers, especially in rural communities, and stopping early raises clot risk (section 19.7). Vitamin K lists apply to warfarin, and even then consistency matters, not avoidance. INR testing does not guide apixaban. Doubling a dose is unsafe.

25. [CORE] A patient with intermittent claudication asks how to position the legs in bed. What should the nurse advise?

a. Raise both legs on two pillows so they rest above the level of the heart.

b. Keep the legs level or slightly lower than the heart.

c. Alternate raising each leg every 2 hours.

d. Elevate the foot of the bed at night.

Answer: b — In arterial disease, gravity helps blood reach the foot, so the legs stay level or slightly dependent (section 19.4). Raising the legs reduces arterial flow and can worsen ischemic pain; elevation is used for venous disease. Alternating elevation and raising the foot of the bed still elevate the legs.

26. [CORE] A patient's ankle-brachial index is 0.7 in the right leg. How should the nurse interpret this result?

a. It suggests PAD in the right leg.

b. It is within the normal range.

c. It suggests stiff, calcified arteries.

d. It confirms a DVT in the right leg.

Answer: a — The CCS states that an ABI below 0.9 suggests PAD (section 19.4). A value of 0.7 is not normal. Calcified arteries give falsely normal values or values above 1.4. The ABI assesses arterial flow, not venous clots.

27. [CORE] Which finding in a patient with acute limb ischemia shows that the limb is becoming threatened and needs the most urgent treatment?

a. A cool foot with a weak pulse
b. Pain in the calf at rest
c. Pallor of the foot when it is raised and a dusky colour when it is lowered
d. New numbness above the toes and weak foot movement

Answer: d — New sensory loss beyond the toes and motor weakness mark an immediately threatened limb that is salvageable only with prompt revascularization (section 19.4). Coolness, a weak pulse, rest pain and elevation pallor are ischemic signs, but none shows the nerve and muscle threat that sensory and motor loss do.

28. [CORE] A 74-year-old man with a known AAA reports sudden severe back pain. His blood pressure is 86/50 mm Hg and his pulse is 124. What should the nurse do first?

a. Give the ordered analgesic and reassess in 30 minutes.
b. Call the rapid response team.
c. Help him walk to the bathroom.
d. Palpate the abdomen firmly for a mass.

Answer: b — Sudden back pain with hypotension and tachycardia in a patient with an AAA suggests rupture, an emergency that needs immediate escalation (section 19.5). Treating pain alone delays care. Walking increases risk. Firm palpation delays help and is not needed to act.

29. [CORE] Which patient meets the Canadian Task Force on Preventive Health Care recommendation for AAA screening?

a. A 70-year-old man who has never been screened
b. A 68-year-old woman who smoked for 30 years
c. An 84-year-old man with high blood pressure
d. A 55-year-old man with a family history of AAA

Answer: a — The Task Force recommends one-time ultrasound screening for men aged 65 to 80 (section 19.5). It recommends against screening women and men over 80. A 55-year-old is below the recommended age range.

30. [CORE] A patient in hospital 4 days after hip surgery has new swelling and warmth of one calf. What is the nurse's best action?

a. Massage the calf gently to ease the discomfort.
b. Wait for the next scheduled assessment.
c. Apply a compression stocking to the affected leg.
d. Report the findings promptly to the prescriber.

Answer: d — One-sided calf swelling and warmth after surgery suggest DVT, which needs prompt reporting and diagnostic testing (section 19.6). Massage is avoided. Compression does not treat a DVT and is not a substitute for assessment. Waiting delays diagnosis.

31. [CORE] A patient with a suspected DVT is in the lower-probability group. Which test is usually done first?

a. Compression ultrasound of both legs
b. International normalized ratio
c. D-dimer
d. Ankle-brachial index

Answer: c — In the lower-probability group, a negative D-dimer rules out DVT without imaging (section 19.6). Compression ultrasound comes first when probability is higher. The INR measures warfarin's effect. The ABI assesses arterial disease.

32. [CORE] A patient taking warfarin for VTE asks about diet. Which response is accurate?

a. "Avoid all green vegetables while you take warfarin."
b. "Eat as many green vegetables as you like each day."
c. "Keep the amount of vitamin K you eat about the same from week to week."
d. "Vitamin K in food has no effect on warfarin."

Answer: c — Consistent vitamin K intake keeps the INR stable; no food is forbidden (section 19.7). Avoiding greens is unnecessary. Large swings in intake change warfarin's effect, so unlimited variation is unsafe and vitamin K does matter.

33. [CORE] A patient taking warfarin for a DVT has an INR of 2.4. How should the nurse interpret this result?

a. Within the usual target range of 2.0 to 3.0
b. Too low for VTE treatment, so the weekly dose should be increased
c. Too high for VTE treatment, so the next dose should be held and the prescriber called
d. The target for a mechanical valve

Answer: a — For most indications, including VTE, the target INR is 2.5 within a range of 2.0 to 3.0 (section 19.7). The value is neither low nor high. Mechanical valves have different targets (section 18.5).

34. [CORE] A patient who takes apixaban twice daily realizes at noon that the morning dose was missed. What should the nurse advise?

a. Take two tablets with the evening dose.
b. Skip the missed dose and wait until tomorrow.
c. Take the missed dose now, then continue the usual schedule.
d. Stop apixaban for the rest of the day and call the prescriber in the morning.

Answer: c — The Canadian patient information for apixaban says to take the missed dose as soon as remembered and continue twice daily without doubling (section 19.7). Doubling raises bleeding risk. Skipping leaves the patient unprotected. Stopping raises clot risk.

35. [CORE] An 80-year-old resident of a long-term care home who takes rivaroxaban slipped and hit her head. She is alert and has no headache. Which action should the nurse take?

a. Apply ice and recheck her tomorrow.
b. Hold rivaroxaban for one week.
c. Arrange urgent medical assessment.
d. Document the fall and continue routine care.

Answer: c — A head injury in a person on an anticoagulant can cause bleeding inside the skull that appears hours later, so urgent assessment is needed even without symptoms (section 19.7; Chapter 8). Waiting until the next day delays diagnosis. Holding the anticoagulant is a prescriber decision and does not replace assessment. Routine care misses the risk.

36. [CORE] On a medical unit, an RPN is caring for a patient receiving enoxaparin for DVT. The patient's hemoglobin has fallen from 128 g/L to 101 g/L, and the patient feels dizzy on standing. What should the RPN do?

a. Give the next dose and recheck the hemoglobin tomorrow.

b. Encourage oral fluids, help the patient back to bed and continue to monitor the vital signs.

c. Ask the patient to stay in bed until morning.

d. Hold the next dose and consult the RN and prescriber now.

Answer: d — A falling hemoglobin with dizziness suggests bleeding; every nurse acts at once, holds the next dose per policy and escalates, and the RPN consults the RN as the patient's needs change (section 19.7). Giving the dose risks more bleeding. Fluids and bed rest do not address the cause.

37. [CORE] Which statement about scope for heparin therapy reflects how role differences are explained in Ontario?

a. CNO rules state that only RNs may care for any patient receiving an anticoagulant.

b. CNO classifies patients on heparin as unstable, so RPNs may not care for them.

c. Whether a nurse manages a heparin infusion depends on authority, competence, context and employer policy.

d. RPNs may manage heparin infusions without an order if they are competent.

Answer: c — Role differences are explained by authority, competence and context, and employer policy shapes who manages titrated infusions (section 19.7, Scope in Practice box). CNO has no rule limiting all anticoagulant care to RNs and does not classify patients this way. An order is part of authority.

38. [RN] A patient receiving IV unfractionated heparin for 7 days has a platelet count that has fallen from 240 × 10^9/L to 95 × 10^9/L, and the left arm is newly swollen. Which action should the nurse anticipate?

a. Stop all heparin and start a non-heparin anticoagulant.

b. Switch from the heparin infusion to a subcutaneous LMWH such as enoxaparin.

c. Give a platelet transfusion before any other treatment.

d. Start warfarin today to prevent further clots.

Answer: a — A fall of about 60% beginning within days 5 to 10, with new thrombosis, points strongly to HIT; all heparin stops and a non-heparin anticoagulant starts (Going Deeper box). Switching to an LMWH still exposes the patient to heparin. Routine platelet transfusion is not recommended. Warfarin waits until the platelet count recovers.

39. [RN] Which features does the 4Ts score consider when estimating the probability of HIT? Select all that apply.

a. How far the platelet count has fallen

b. When the fall began in relation to heparin exposure

c. Whether new thrombosis has occurred

d. Whether another cause of a low platelet count is likely

e. The patient's hemoglobin level

f. The heparin infusion rate

Answer: a, b, c, d — The 4Ts score weighs the size of the platelet fall, its timing, new thrombosis and other possible causes (Going Deeper box). Hemoglobin and the infusion rate are not part of the score.

40. [RN] A hospital adjusts heparin infusions using anti-Xa levels instead of the aPTT. What best explains the difference?

a. Anti-Xa measures the effect of warfarin, whereas the aPTT measures the effect of heparin.

b. Anti-Xa measures heparin's activity directly; the aPTT is affected by many factors.

c. The aPTT is used only for LMWH.

d. Anti-Xa monitoring removes the need for a protocol.

Answer: b — The anti-Xa level measures heparin activity directly, whereas the aPTT is a clotting time influenced by many factors; each hospital chooses one with a protocol (Going Deeper box). Warfarin is monitored with the INR. The aPTT is used for UFH. A protocol is always needed.

References

Abramson, B. L., Al-Omran, M., Anand, S. S., Albalawi, Z., Coutinho, T., de Mestral, C., Dubois, L., Gill, H. L., Greco, E., Guzman, R., Herman, C., Hussain, M. A., Huckell, V. F., Jetty, P., Kaplovitch, E., Karlstedt, E., Kayssi, A., Lindsay, T., Mancini, G. B. J., … Virani, S. (2022). Canadian Cardiovascular Society 2022 guidelines for peripheral arterial disease. *Canadian Journal of Cardiology, 38*(5), 560–587. https://doi.org/10.1016/j.cjca.2022.02.029

Allaire, J., Lévesque, B., Poirier, P., Gagnon, C., Auclair, G., Lemire, M., & Ayotte, P. (2024). Prevalence and determinants of hypertension in the adult Inuit population of Nunavik (northern Quebec, Canada). *Canadian Journal of Public Health, 115*(Suppl. 1), 168–179. https://doi.org/10.17269/s41997-023-00774-5

Aspen Pharmacare Canada. (2019). *Arixtra (fondaparinux sodium injection): Product monograph*. https://pdf.hres.ca/dpd_pm/00052315.PDF

Berretta, P., Patel, H. J., Gleason, T. G., Sundt, T. M., Myrmel, T., Desai, N., Korach, A., Panza, A., Bavaria, J., Khoynezhad, A., Woznicki, E., Montgomery, D., Isselbacher, E. M., Di Bartolomeo, R., Fattori, R., Nienaber, C. A., Eagle, K. A., Trimarchi, S., & Di Eusanio, M. (2016). IRAD experience on surgical type A acute dissection patients: Results and predictors of mortality. *Annals of Cardiothoracic Surgery, 5*(4), 346–351. https://doi.org/10.21037/acs.2016.05.10

Boehringer Ingelheim Canada. (2019). *Praxbind (idarucizumab): Monographie de produit* [Product monograph]. https://pdf.hres.ca/dpd_pm/00051046.PDF

Canadian Agency for Drugs and Technologies in Health. (2024). *Andexanet alfa (Ondexxya): CADTH reimbursement review* (Report No. ST0772). https://www.ncbi.nlm.nih.gov/books/NBK602903/

Canadian Blood Services. (2024, March 20). *Formulary listing recommendation report: Ondexxya (andexanet alfa)*. https://www.blood.ca/sites/default/files/CBS_Formulary_Listing_Recommendation_Report_Ondexxya-EN.pdf

Canadian Task Force on Preventive Health Care. (2017). Recommendations on screening for abdominal aortic aneurysm in primary care. *CMAJ, 189*(36), E1137–E1145. https://doi.org/10.1503/cmaj.170118

Cuker, A., Arepally, G. M., Chong, B. H., Cines, D. B., Greinacher, A., Gruel, Y., Linkins, L. A., Rodner, S. B., Selleng, S., Warkentin, T. E., Wex, A., Mustafa, R. A., Morgan, R. L., & Santesso, N. (2018). American Society of Hematology 2018 guidelines for management of venous thromboembolism: Heparin-induced thrombocytopenia. *Blood Advances, 2*(22), 3360–3392. https://doi.org/10.1182/bloodadvances.2018024489

de Mestral, C., Hussain, M. A., Austin, P. C., Forbes, T. L., Sivaswamy, A., Kayssi, A., Salata, K., Wijeysundera, H. C., Verma, S., & Al-Omran, M. (2020). Regional health care services and rates of lower extremity amputation related to diabetes and peripheral artery disease: An ecological study. *CMAJ Open, 8*(4), E659–E666. https://doi.org/10.9778/cmajo.20200048

Evans, R., Kuhnke, J. L., Burrows, C., Kayssi, A., O'Sullivan-Drombolis, D., Mitchell-McDonald, B., Labrecque, C., & Houghton, P. (2025). Best practice recommendations for the prevention and management of venous leg ulcers. In J. L. Kuhnke, C. A. Burrows, R. M. Evans, H. L. Orsted, & S. Rosenthal (Eds.), *Best practice recommendations for skin health and wound management 2025*. Wounds Canada. https://doi.org/10.56885/LORP2958

Freeman, R., Wieling, W., Axelrod, F. B., Benditt, D. G., Benarroch, E., Biaggioni, I., Cheshire, W. P., Chelimsky, T., Cortelli, P., Gibbons, C. H., Goldstein, D. S., Hainsworth, R., Hilz, M. J., Jacob, G., Kaufmann, H., Jordan, J., Lipsitz, L. A., Levine, B. D., Low, P. A., … van Dijk, J. G. (2011). Consensus statement on the definition of orthostatic hypotension, neurally mediated syncope and the postural tachycardia syndrome. *Clinical Autonomic Research, 21*(2), 69–72. https://doi.org/10.1007/s10286-011-0119-5

Fresenius Kabi Canada. (2016). *Protamine sulfate injection USP: Product monograph*. https://fresenius-kabi.com/content/dam/fresenius-kabi/ca/products/product-documents/iv-drugs/protamine-sulfate-injection-usp_/Product%20Monograph.pdf

Goupil, R., Tsuyuki, R. T., Santesso, N., Terenzi, K. A., Habert, J., Cheng, G., Gysel, S. C., Bruneau, J., Leung, A. A., Campbell, N. R. C., Schiffrin, E. L., & Hundemer, G. L. (2025). Hypertension Canada guideline for the diagnosis and treatment of hypertension in adults in primary care. *Canadian Medical Association Journal, 197*(20), E549–E564. https://doi.org/10.1503/cmaj.241770

Guidelines and Protocols Advisory Committee. (2023). *Warfarin therapy management*. British Columbia Ministry of Health. https://www2.gov.bc.ca/assets/gov/health/practitioner-pro/bc-guidelines/doctorsbc-warfarin-guideline_v5.pdf

Guidelines and Protocols Advisory Committee. (n.d.). *Hypertension – detection, diagnosis and management: Appendix A*. British Columbia Ministry of Health. https://www2.gov.bc.ca/assets/gov/health/about-bc-s-health-care-system/bc-guidelines/hypertension_appendix_a.pdf

Health Canada. (2026). *Drug Product Database*. Government of Canada. https://health-products.canada.ca/dpd-bdpp/

Heart and Stroke Foundation of Canada. (n.d.-a). *Signs of a heart attack*. https://www.heartandstroke.ca/heart-disease/emergency-signs

Heart and Stroke Foundation of Canada. (n.d.-b). *Signs of stroke*. https://www.heartandstroke.ca/stroke/signs-of-stroke

Hypertension Canada. (n.d.). *How do I monitor my BP?* https://hypertension.ca/how-do-i-monitor-my-bp/

ISMP Canada. (2016). High-alert medications need multiple safeguards. *Ontario Critical Incident Learning*, (15). https://www.ismp-canada.org/download/ocil/ISMPCONCIL2016-15_highalertmedications.pdf

Isselbacher, E. M., Preventza, O., Black, J. H., III, Augoustides, J. G., Beck, A. W., Bolen, M. A., Braverman, A. C., Bray, B. E., Brown-Zimmerman, M. M., Chen, E. P., Collins, T. J., DeAnda, A., Jr., Fanola, C. L., Girardi, L. N., Hicks, C. W., Hui, D. S., Jones, W. S., Kalahasti, V., Kim, K. M., … Volgman, A. S. (2022). 2022 ACC/AHA guideline for the diagnosis and management of aortic disease: A report of the American Heart Association/American College of Cardiology Joint Committee on Clinical Practice Guidelines. *Circulation, 146*(24), e334–e482. https://doi.org/10.1161/CIR.0000000000001106

Kahn, S. R., Shapiro, S., Wells, P. S., Rodger, M. A., Kovacs, M. J., Anderson, D. R., Tagalakis, V., Houweling, A. H., Ducruet, T., & Holcroft, C. (2014). Compression stockings to prevent post-thrombotic syndrome: A randomised placebo-controlled trial. *The Lancet, 383*(9920), 880–888. https://doi.org/10.1016/S0140-6736(13)61902-9

Lim, W., Le Gal, G., Bates, S. M., Righini, M., Haramati, L. B., Lang, E., Kline, J. A., Chasteen, S., Snyder, M., Patel, P., Bhatt, M., Patel, P., Braun, C., Begum, H., Wiercioch, W., Schünemann, H. J., & Mustafa, R. A. (2018). American Society of Hematology 2018 guidelines for management of venous thromboembolism: Diagnosis of venous thromboembolism. *Blood Advances, 2*(22), 3226–3256. https://doi.org/10.1182/bloodadvances.2018024828

Liu, Z., Tao, X., Chen, Y., Fan, Z., & Li, Y. (2015). Bed rest versus early ambulation with standard anticoagulation in the management of deep vein thrombosis: A meta-analysis. *PLOS ONE, 10*(4), Article e0121388. https://doi.org/10.1371/journal.pone.0121388

McEvoy, J. W., McCarthy, C. P., Bruno, R. M., Brouwers, S., Canavan, M. D., Ceconi, C., Christodorescu, R. M., Daskalopoulou, S. S., Ferro, C. J., Gerdts, E., Hanssen, H., Harris, J., Lauder, L., McManus, R. J., Molloy, G. J., Rahimi, K., Regitz-Zagrosek, V., Rossi, G. P., Sandset, E. C., … Touyz, R. M. (2024). 2024 ESC guidelines for the management of elevated blood pressure and hypertension. *European Heart Journal, 45*(38), 3912–4018. https://doi.org/10.1093/eurheartj/ehae178

National Confidential Enquiry into Patient Outcome and Death. (2025). *Risking life and limb: A review of the quality of the care provided to adults with acute limb ischaemia*. https://www.ncepod.org.uk/2025ali/Risking%20Life%20and%20Limb_Extended%20report.pdf

Ortel, T. L., Neumann, I., Ageno, W., Beyth, R., Clark, N. P., Cuker, A., Hutten, B. A., Jaff, M. R., Manja, V., Schulman, S., Thurston, C., Vedantham, S., Verhamme, P., Witt, D. M., Florez, I. D., Izcovich, A., Nieuwlaat, R., Ross, S., Schünemann, H. J., … Zhang, Y. (2020). American Society of Hematology 2020 guidelines for management of venous thromboembolism: Treatment of deep vein thrombosis and pulmonary embolism. *Blood Advances, 4*(19), 4693–4738. https://doi.org/10.1182/bloodadvances.2020001830

Pfizer Canada & Bristol-Myers Squibb Canada. (2019). *Eliquis (apixaban): Consumer information*. https://webfiles.pfizer.com/file/fa16c5d5-1a3b-49d2-b16f-11176b4e1ecd

Pfizer Canada & Bristol-Myers Squibb Canada. (2025). *Eliquis (apixaban): Monographie de produit* [Product monograph]. https://pdf.hres.ca/dpd_pm/00078566.PDF

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Rabi, D. M., McBrien, K. A., Sapir-Pichhadze, R., Nakhla, M., Ahmed, S. B., Dumanski, S. M., Butalia, S., Leung, A. A., Harris, K. C., Cloutier, L., Zarnke, K. B., Ruzicka, M., Hiremath, S., Feldman, R. D., Tobe, S. W., Campbell, T. S., Bacon, S. L., Nerenberg, K. A., Dresser, G. K., … Daskalopoulou, S. S. (2020). Hypertension Canada's 2020 comprehensive guidelines for the prevention, diagnosis, risk assessment, and treatment of hypertension in adults and children. *Canadian Journal of Cardiology, 36*(5), 596–624. https://doi.org/10.1016/j.cjca.2020.02.086

Shah, B. R., Frymire, E., Jacklin, K., Jones, C. R., Khan, S., Slater, M., Walker, J. D., & Green, M. E. (2019). Peripheral arterial disease in Ontario First Nations people with diabetes: A longitudinal population-based cohort study. *CMAJ Open, 7*(4), E700–E705. https://doi.org/10.9778/cmajo.20190162

Statistics Canada. (2019, February 20). *Health Reports: Blood pressure, hypertension and leading risk factors* (The Daily). https://www150.statcan.gc.ca/n1/daily-quotidien/190220/dq190220a-eng.htm

Statistics Canada. (2021, March 23). *Blood pressure of adults, 2016–2019* (Health Fact Sheets, Catalogue No. 82-625-X). https://www150.statcan.gc.ca/n1/pub/82-625-x/2021001/article/00001-eng.htm

Stevens, S. M., Woller, S. C., Baumann Kreuziger, L., Bounameaux, H., Doerschug, K., Geersing, G.-J., Huisman, M. V., Kearon, C., King, C. S., Knighton, A. J., Lake, E., Murin, S., Vintch, J. R. E., Wells, P. S., & Moores, L. K. (2021). Antithrombotic therapy for VTE disease: Second update of the CHEST guideline and expert panel report. *Chest, 160*(6), e545–e608. https://doi.org/10.1016/j.chest.2021.07.055

van den Born, B.-J. H., Lip, G. Y. H., Brguljan-Hitij, J., Cremer, A., Segura, J., Morales, E., Mahfoud, F., Amraoui, F., Persu, A., Kahan, T., Agabiti Rosei, E., de Simone, G., Gosse, P., & Williams, B. (2019). ESC Council on hypertension position document on the management of hypertensive emergencies. *European Heart Journal – Cardiovascular Pharmacotherapy, 5*(1), 37–46. https://doi.org/10.1093/ehjcvp/pvy032

Zschaler, S., Schmidt, G., Kukucka, M., Syrmas, G., Zaschke, L., & Kurz, S. D. (2018). How to prevent inadvertent emergency anticoagulation in acute type A aortic dissection: When in doubt, don't. *Cardiovascular Diagnosis and Therapy, 8*(6), 805–810. https://doi.org/10.21037/cdt.2018.10.13

V Hematologic, Immunologic & Endocrine Care

UNIT CLINICAL SCOPE & INTEGRATION

Explores hematologic assessment, anemias, sickle cell vaso-occlusive crisis, Canadian Blood Services transfusion safety, hematologic malignancies, immune deficiency, HIV care, anaphylaxis, Diabetes Canada clinical practice guidelines (DKA, HHS, inpatient glycemic targets), and thyroid, parathyroid, adrenal, and pituitary disorders.

Contents of UNIT V

Chapter	Chapter Title	Visual Assets	Page
Chapter 20	Hematologic Disorders and Transfusion	8 Figs • 4 Tbls	p. 569
Chapter 21	Immunity, Allergy and HIV	7 Figs • 4 Tbls	p. 601
Chapter 22	Diabetes	6 Figs • 4 Tbls	p. 635
Chapter 23	Thyroid, Parathyroid, Adrenal and Pituitary Disorders	5 Figs • 3 Tbls	p. 665

20 Hematologic Disorders and Transfusion

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain how blood cells are made, and interpret the complete blood count, iron studies and basic clotting tests in SI units, recognizing that reference ranges vary by laboratory.
2. Recognize and care for adults with iron deficiency, vitamin B12 and folate deficiency and other anemias, describing findings on a range of skin tones and in older adults.
3. Provide safe, equitable care for people with sickle cell disease and thalassemia, including timely pain management in a vaso-occlusive crisis and early recognition of complications.
4. Recognize and respond to bleeding and clotting disorders (thrombocytopenia, immune thrombocytopenia, hemophilia, von Willebrand disease and DIC), and teach bleeding precautions.
5. Describe leukemia, lymphoma and multiple myeloma, and manage the infection, bleeding and anemia risks common to blood cancers.
6. Give blood components safely: pre-transfusion checks, bedside identification, monitoring, and recognition of and first actions for transfusion reactions, using the CJMM.
7. Distinguish RN and RPN roles in transfusion and hematologic care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 5	Clinician; Scholar	Foundations of Practice
3, 6	Clinician; Advocate; Educator	Foundations of Practice; Ethical Practice
7	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

Blood problems show up on every unit. A low hemoglobin can explain why an older adult is short of breath after a few steps, why a patient feels faint when standing after surgery, or why chest pain appears in someone with narrowed coronary arteries. Disorders of bleeding and clotting shape decisions about procedures and medications. Blood products are given on medical, surgical, oncology and critical care units every day. Whatever the setting, the nurse reads results, follows trends, links numbers to what is seen at the bedside, and acts when a value or a patient changes.

This chapter starts with how blood cells are made and how to read the complete blood count, iron studies and basic clotting tests in SI units (section 20.1). It then covers the anemias (20.2) and two inherited hemoglobin disorders, sickle cell disease and thalassemia (20.3). The second half turns to bleeding and clotting disorders (20.4); leukemia, lymphoma and multiple myeloma (20.5); and blood components and transfusion, including consent, bedside checks and transfusion reactions (20.6).

The chapter builds on earlier ones. Scope of practice, the Clinical Judgment Measurement Model (CJMM) and consent are taught in Chapter 1. Pain assessment and opioid principles are in Chapter 5, and recognizing deterioration in Chapter 6. Cancer treatment, including febrile neutropenia, is covered in Chapter 9. Anticoagulants and the monitoring that goes with them are taught in Chapter 19, and the anemia of chronic kidney disease in Chapter 27.

20.1 Blood and Its Tests

How Blood Cells Are Made

Hematopoiesis is the production of blood cells. In adults it takes place in the bone marrow, the soft tissue inside bones. All blood cells come from a small pool of stem cells that can both renew themselves and mature into each cell line. One branch produces red blood cells, platelets and most white blood cells. The other produces lymphocytes, the cells of specific immunity. Because all the lines share this origin, diseases of the marrow, such as aplastic anemia or leukemia, often lower more than one cell count at once (sections 20.2 and 20.5) (Figure 20.1).

Red blood cell production responds to oxygen delivery. When the kidneys sense that tissues are receiving too little oxygen, they release the hormone erythropoietin, which signals the marrow to make more red cells. This is why chronic kidney disease so often causes anemia (Chapter 27). Building a red cell needs iron to make hemoglobin, and vitamin B12 and folate to copy DNA as precursor cells divide. A shortage of any of these produces one of the anemias in section 20.2.

Young red cells leave the marrow as **reticulocytes**, which mature in the bloodstream. A mature red cell normally survives about 120 days (Phillips & Henderson, 2018). Old cells are removed mainly in the spleen, and their iron is recycled. Platelets are fragments of large marrow cells called megakaryocytes; they start clot formation at sites of vessel injury. White cells defend against infection: neutrophils respond first to bacteria, lymphocytes direct immune responses, monocytes become tissue macrophages, and eosinophils and basophils take part in allergic and parasitic responses (Chapter 21).



Figure 20.1 Hematopoiesis: one stem cell population in the bone marrow gives rise to two lines. The myeloid line makes red cells, platelets and most white cells; the lymphoid line makes lymphocytes. (credit: Figure 18.4, "Hematopoietic System of Bone Marrow," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

The Complete Blood Count

The **complete blood count (CBC)** is the most common blood test in hospital. It reports:

- **Hemoglobin:** the oxygen-carrying protein in red cells, reported in grams per litre (g/L). It is the main value used to define anemia.
- **Hematocrit:** the fraction of blood volume made up of red cells, reported in litres per litre (L/L), for example 0.40.
- **Red blood cell count:** reported as $\times 10^{12}$/L.
- **White blood cell count and differential:** the total count and the count of each type, reported as $\times 10^{9}$/L.
- **Platelet count:** reported as $\times 10^{9}$/L.

The nurse looks at the absolute count of each white cell type, not only the total. A patient with a normal total white count can still have too few neutrophils, the cells most needed to fight bacterial infection.

The CBC also reports **red cell indices**, which describe the cells themselves. The **mean corpuscular volume (MCV)** is the average size of red cells in femtolitres (fL). The mean corpuscular hemoglobin (MCH) is the average amount of hemoglobin in each cell, and the mean corpuscular hemoglobin concentration (MCHC) is how concentrated that hemoglobin is. The red cell distribution width (RDW) shows how much cell size varies. Together these help sort anemias into small-cell, normal-cell and large-cell patterns (Going Deeper box). A reticulocyte count shows whether the marrow is responding to anemia.

Iron studies answer a different question: how much iron the body has stored. **Ferritin** is the storage form of iron, and serum ferritin is the screening test laboratories prefer when iron deficiency is suspected (Alberta Precision Laboratories [APL] & DynaLIFE Medical Labs, 2021). Serum iron alone cannot show iron stores. Ferritin also rises with inflammation and acute illness, so a normal ferritin in a sick patient does not rule out iron deficiency. Vitamin B12 and folate levels are ordered when red cells are large or nerve symptoms suggest deficiency.

Reference ranges vary by laboratory, by the patient's age and sex, and sometimes by the instrument used. Nurses always read results against the range printed on the patient's own report. Table 20.1 gives example adult ranges from Alberta's provincial laboratory system to show typical units and size of values. Laboratories also set **critical values** that are phoned to the care team at once. In the same Alberta system, for example, a hemoglobin below 70 g/L and a platelet count below 10×10^9/L in an inpatient are critical (Alberta Health Services, 2023). The nurse who receives a critical value repeats it back, assesses the patient, notifies the prescriber promptly and documents according to employer policy.

Table 20.1 The complete blood count, ferritin and vitamin B12 in SI units, and what changes may mean (Alberta Health Services, 2023; APL, 2020; APL & DynaLIFE Medical Labs, 2021; Phillips & Henderson, 2018; Weiss et al., 2019)

Test	Unit	Example adult range (varies by laboratory)	Low may mean	High may mean
Hemoglobin	g/L	Female 120–160; male 135–175	Anemia from blood loss, low production or red cell destruction	Dehydration (concentration) or too many red cells
Hematocrit	L/L	Female 0.36–0.48; male 0.40–0.52	Same as for low hemoglobin	Same as for high hemoglobin
Red blood cell count	$\times 10^{12}$/L	Female 3.80–5.20; male 4.30–6.00	Anemia	Too many red cells, or many small cells as in thalassemia trait
White blood cell count	$\times 10^9$/L	4.0–11.0	Marrow suppression (for example after chemotherapy) or marrow failure; higher infection risk	Infection, inflammation, physiological stress, some leukemias
Neutrophils	$\times 10^9$/L	1.8–7.5	Neutropenia; high risk of serious infection	Bacterial infection, inflammation, corticosteroids
Lymphocytes	$\times 10^9$/L	0.5–4.5	Some infections, immune suppression	Viral infection, some leukemias and lymphomas
Platelets	$\times 10^9$/L	140–400	Thrombocytopenia; bleeding risk rises as the count falls (section 20.4)	Reactive rise with inflammation, iron deficiency or bleeding; marrow disorders
Mean corpuscular volume (MCV)	fL	80–100	Small cells: iron deficiency, thalassemia trait	Large cells: vitamin B12 or folate deficiency, high reticulocyte count
Mean corpuscular hemoglobin concentration (MCHC)	g/L	310–360	Pale cells, as in iron deficiency	Some inherited red cell membrane disorders
Red cell distribution width (RDW)	%	Below 16.0	Not usually significant	Mixed cell sizes, as in early iron deficiency or a recent response to treatment
Ferritin	µg/L	Female 20–300; male 30–500	Depleted iron stores; values below about 30–45 are linked to iron deficiency	Inflammation, acute illness, liver disease, iron overload
Vitamin B12	pmol/L	160 or higher	Possible deficiency; confirm with clinical picture and further testing	Not usually a concern

Clotting Tests

Clotting tests measure how long plasma takes to form a clot, or the amount of key clotting proteins.

- **International normalized ratio (INR):** a standardized form of the prothrombin time. It rises with warfarin, liver disease and vitamin K deficiency; warfarin monitoring is taught in Chapter 19.
- **Activated partial thromboplastin time (aPTT):** a clotting time in seconds that rises with heparin, some factor deficiencies such as hemophilia (section 20.4) and some inhibitors. Its range depends on the reagent: when one Alberta laboratory changed reagent lots, its range moved from 26.0–36.0 to 28.0–38.0 seconds (APL, 2019).
- **Fibrinogen:** the protein that becomes the fibrin mesh of a clot. It falls when clotting factors are used up, as in disseminated intravascular coagulation and massive bleeding (sections 20.4 and 20.6).
- **D-dimer:** a fragment released when a fibrin clot breaks down. It rises with venous thromboembolism but also after surgery, with infection and in many other states, so a raised value is not specific (Chapter 19).

The platelet count belongs with these tests. A low count raises the risk of bleeding, and the link between platelet levels, bleeding and platelet transfusion is discussed in sections 20.4 and 20.6.

GOING DEEPER

Reading Red Cell Indices

Required for RN students; optional for PN students.

The MCV sorts anemia into three patterns that narrow the search for a cause.

- **Microcytic (MCV below the reference range):** most often iron deficiency. Thalassemia trait also causes small cells, often with a normal or high red cell count and a normal ferritin. Anemia of inflammation is usually normocytic but can become microcytic.
- **Normocytic:** acute blood loss, anemia of inflammation, chronic kidney disease, hemolysis and marrow failure (Phillips & Henderson, 2018; Weiss et al., 2019).
- **Macrocytic (MCV above the range):** vitamin B12 or folate deficiency, a high reticulocyte count (reticulocytes are larger than mature cells) and some drugs; hydroxyurea, for example, causes macrocytosis (Eugia Pharma, 2024).

The RDW adds detail. A high RDW means cells of mixed sizes, as when new small iron-deficient cells mix with older normal ones.

The reticulocyte count shows whether the marrow is keeping up. A low count in an anemic patient points to a production problem: missing iron, B12 or folate, low erythropoietin, or marrow failure. A high count points to loss or destruction of red cells, as in bleeding or hemolysis (Phillips & Henderson, 2018). After treatment of a deficiency starts, the reticulocyte count rises first. The cyanocobalamin monograph, for example, advises checking reticulocytes before treatment and again around days 5 to 7 (Eugia Pharma, 2023).

20.2 Anemias

Anemia is a hemoglobin below the lower limit of the reference range for the person's age and sex. It is a sign with a cause, not a diagnosis on its own. Anemia results from one of three processes: blood loss, too little red cell production, or early red cell destruction. Table 20.2 compares the main types.

Recognizing Anemia

With less hemoglobin, each litre of blood carries less oxygen. The body compensates by raising heart rate and cardiac output and by breathing faster. Symptoms depend on how low the hemoglobin is, how fast it fell and how much reserve the heart and lungs have. A person whose hemoglobin drifted down over months may adapt surprisingly well. A sudden fall from bleeding causes hypovolemia as well as anemia and can lead to shock (Chapter 6).

Common findings are fatigue, weakness, reduced exercise tolerance, dyspnea on exertion, tachycardia and, in more severe cases, low blood pressure (Phillips & Henderson, 2018). Patients may report dizziness when standing, palpitations or headaches. In a person with coronary artery disease, anemia can trigger angina; in a person with heart failure, it can worsen breathlessness and fluid retention (Chapters 17 and 18).

Assessing pallor on a range of skin tones: pallor is easy to see in the face and skin of people with light skin and much harder to see in medium and dark skin. The nurse looks where pigment does not hide colour: the inner lower eyelid (conjunctiva), the lips and inside of the mouth, the nail beds and the palms. Comparing with the patient's usual colour, or asking the patient or family whether

they look different, also helps. Even so, no single site is accurate enough on its own; a pooled review of studies in children found that palm, conjunctival and nail bed pallor were each only moderately useful for detecting anemia (Chalco et al., 2005). Pallor prompts a hemoglobin level, and a normal-looking patient can still be anemic. Pulse oximetry measures the saturation of the hemoglobin that is present, not the amount, so oxygen saturation can be normal in severe anemia; its reduced accuracy on darker skin is discussed in Chapter 12.

When to escalate: the nurse reports at once a critical hemoglobin value, a fall from the patient's baseline, chest pain, syncope, new confusion, rising heart rate with falling blood pressure, or signs of bleeding such as black or bloody stools or vomiting blood. These findings are communicated with a structured tool such as Situation, Background, Assessment, Recommendation (SBAR) (Chapter 6).



Figure 20.2 A blood smear in severe iron deficiency anemia: the red cells are small (microcytic) and pale (hypochromic), with wide pale centres. (credit: “Iron-deficiency Anemia, Peripheral Blood Smear” by Ed Uthman/Wikimedia Commons, CC BY 2.0)

Iron Deficiency Anemia

Iron deficiency anemia develops in stages. Iron stores, measured by ferritin, fall first. Next, the marrow runs short of iron for new red cells. Finally, the hemoglobin falls and the red cells become small and pale (Cooper et al., 2012; Figure 20.2). Long-standing iron deficiency can also make the nails thin and spoon-shaped, a change called koilonychia (Figure 20.3).

Figure 20.3 Koilonychia: thin nails that curve up at the edges into a spoon shape, a sign of long-standing iron deficiency. Nail and skin changes are useful cues on every skin tone. (credit: “Koilonychia iron deficiency anemia” by CHeitz/Wikimedia Commons, CC BY 2.0)

Iron is lost mainly through bleeding. Common causes are heavy menstrual bleeding, slow bleeding from the gastrointestinal tract (for example from ulcers, polyps, cancer or anti-inflammatory drugs), the extra demands of pregnancy, poor absorption after gastric surgery or with celiac disease or inflammatory bowel disease, and diets low in absorbable iron (Ko et al., 2020). Iron from plant foods is harder to absorb than iron from meat, poultry and fish (Health Canada, 2025).

Canadian data: using Canadian Health Measures Survey data from 2012 to 2019, Health Canada (2025) reports that low iron affects about 1 in 4 women (ages 14 to 50) and that the chance of low iron is twice as high among people new to Canada; the infographic does not name the comparison group. In the 2009 to 2011 survey cycle, about 3% of Canadians aged 3 to 79 had anemia; people in the lowest household income quartile had a slightly lower mean hemoglobin than those in the highest (140 versus 143 g/L) (Cooper et al., 2012). That survey did not include people living on First Nations reserves or Crown lands, people in institutions or people in certain remote regions, so it cannot describe iron status in those communities.

Finding the cause: a diagnosis of iron deficiency always raises the question of where the iron went. In a person with anemia, a ferritin below 45 µg/L (equal to 45 ng/mL) supports iron deficiency; ferritin is less reliable with chronic inflammation or chronic kidney disease (Ko et al., 2020). The American Gastroenterological Association recommends upper endoscopy and colonoscopy for men and postmenopausal women with iron deficiency anemia, because a bleeding lesion, including cancer, may be the cause. It also

recommends blood testing for celiac disease (Ko et al., 2020). In older adults especially, starting iron without looking for the source can let a cancer progress.

Nursing care using the CJMM: the nurse *recognizes cues* such as fatigue, exertional dyspnea, pallor, tachycardia and dark stools, and *analyzes* them against the CBC and ferritin. The *priority hypotheses* are usually reduced activity tolerance, risk of falls and the possibility of ongoing bleeding. The nurse *generates solutions and takes action*: pacing activity, helping with mobility, checking stools, teaching about iron, and reporting signs of active bleeding. To *evaluate outcomes*, the nurse follows symptoms, the reticulocyte count and hemoglobin. Hemoglobin should rise after about a month of oral iron; if it does not, poor adherence, poor absorption or ongoing blood loss is considered (Ko et al., 2020).

Oral and intravenous iron: oral iron is inexpensive and easy to take, but nausea and constipation are common (Black et al., 2024). Teaching focuses on timing and absorption (Patient Education box). Intravenous (IV) iron is used when oral iron is not tolerated or not working, when absorption is poor, as after gastric surgery or with inflammatory bowel disease or chronic kidney disease (Ko et al., 2020; Health Canada, 2024).

Hypersensitivity, including anaphylaxis, is a known risk with every IV iron product. The risk is higher in people with known allergies, severe asthma or eczema, and a reaction can occur even after earlier doses were uneventful (Health Canada, 2024). The nurse takes baseline vital signs, keeps emergency equipment and medications at hand, watches closely during the infusion and repeats vital signs afterward. One Alberta order set asks for observation for 30 minutes after the infusion and describes milder reactions to free iron (flushing, chest tightness, joint aches) that are managed by pausing the infusion and calling the prescriber (Black et al., 2024). Local policy sets the exact monitoring. With ferric carboxymaltose, low blood phosphate has been reported, sometimes with serious outcomes such as softened bones and fractures (Health Canada, 2024).

PATIENT EDUCATION

Taking Iron by Mouth

- Take your iron exactly as your prescriber or pharmacist told you. More is not better.
- Ask your pharmacist the best time of day to take it. If it upsets your stomach, ask whether you can take it with a little food.
- Foods and drinks with vitamin C, such as fruits and vegetables, help your body absorb iron.
- Tea, coffee and high amounts of calcium lower how much iron you absorb. Have tea or coffee, or take calcium or antacids, 1 to 2 hours after eating rather than with the meal (Health Canada, 2025).
- Nausea and constipation are common (Black et al., 2024). Drink fluids, stay active and tell your provider if they bother you; another form or schedule may help.
- Tell your provider right away if your stools are black and sticky like tar, or if you vomit blood or feel faint, because these can be signs of bleeding.
- Keep iron locked away from children. An overdose can be very dangerous for a child.
- Keep your follow-up blood tests. They show whether the iron is working.

Vitamin B12 and Folate Deficiency

Vitamin B12 and folate are needed to copy DNA when red cell precursors divide. When either is missing, the precursors grow but divide poorly, so the red cells that reach the blood are large: a **macrocytic** or megaloblastic anemia.

Absorbing B12 from food depends on intrinsic factor, a protein made in the stomach (Eugia Pharma, 2023). **Pernicious anemia** is an autoimmune disease in which antibodies damage the stomach lining and intrinsic factor, so B12 cannot be absorbed. Other causes of B12 deficiency include gastric surgery or removal of the stomach, disease of the last part of the small bowel (such as Crohn disease), long-term metformin, proton pump inhibitors, low dietary intake and older age (Patel & McGuirk, 2025). Low folate usually reflects low intake or higher needs.

Vitamin B12, unlike folate, is also needed for healthy nerves. Deficiency can cause fatigue, "brain fog", depression, peripheral neuropathy (numbness and tingling in the hands and feet) and ataxia, an unsteady gait (Patel & McGuirk, 2025). If deficiency goes untreated for more than about three months, spinal cord damage can become permanent (Eugia Pharma, 2023). For this reason, both B12 and folate are checked before treatment. Folic acid given alone can improve the anemia while nerve damage from B12 deficiency continues.

The nurse assesses sensation, balance, gait and cognition, and asks about metformin and acid-suppressing drugs. Vitamin B12 can be replaced by injection or by mouth. Injection is the traditional route for pernicious anemia, and the Canadian monograph states that people with pernicious anemia need it for life (Eugia Pharma, 2023). A recent review notes that high-dose oral B12 works as well as injection for most people, with injection preferred when deficiency is severe or there are neurologic signs (Patel & McGuirk, 2025). The prescriber chooses the route. As red cell production restarts, potassium can fall sharply, so potassium is monitored closely in the first 48 hours of treatment for severe deficiency (Eugia Pharma, 2023). People taking metformin long term may need periodic B12 checks (Patel & McGuirk, 2025).

Other Anemias in Brief

- **Anemia of inflammation:** the anemia seen most often in people who are hospitalized or chronically ill. During infection, autoimmune disease or cancer, inflammatory signals raise the hormone hepcidin, which blocks iron absorption and traps iron inside storage cells. The marrow cannot use the iron the body has. Serum iron is low but ferritin is normal or high. Treatment targets the underlying disease (Weiss et al., 2019).
- **Anemia of chronic kidney disease:** damaged kidneys make too little erythropoietin. This anemia and its treatment are covered in Chapter 27.
- **Hemolytic anemia:** red cells are destroyed before their normal lifespan ends. Causes include inherited disorders (sickle cell disease, thalassemia, glucose-6-phosphate dehydrogenase deficiency, hereditary spherocytosis) and acquired ones (autoimmune hemolysis, some drugs, transfusion reactions and red cell fragmentation in disseminated intravascular coagulation) (Phillips & Henderson, 2018). Hemoglobin released from destroyed cells is broken down to bilirubin, which causes **jaundice**. Jaundice is easiest to see in the sclera on every skin tone; on darker skin the nurse also checks the hard palate and the palms. Urine may be dark from bilirubin or hemoglobin. Laboratory signs include a high reticulocyte count, raised lactate dehydrogenase and unconjugated bilirubin, and low haptoglobin (Phillips & Henderson, 2018).
- **Aplastic anemia:** the marrow fails to make enough of all three cell lines. Patients have anemia, infections from low neutrophils and bleeding from low platelets. Treatment, in specialized centres, includes immune-suppressing therapy and stem cell transplant (Young, 2018). Nursing care resembles care for any patient with very low blood counts (Chapter 9).

Table 20.2 Types of anemia compared (Ko et al., 2020; Patel & McGuirk, 2025; Phillips & Henderson, 2018; Weiss et al., 2019; Young, 2018)

Type	Common causes	Typical red cell pattern	Key findings	Treatment focus
Iron deficiency	Blood loss (menstrual, gastrointestinal), pregnancy, poor absorption, low intake	Small, pale cells; RDW often high	Low ferritin; fatigue, exertional dyspnea, pallor	Find and treat the source; oral or IV iron
Vitamin B12 deficiency	Pernicious anemia, gastric or ileal surgery or disease, metformin, proton pump inhibitors, low intake	Large cells	Low B12; numbness, tingling, unsteady gait, cognitive change	B12 by injection or by mouth; monitor potassium early
Folate deficiency	Low intake, higher needs	Large cells	Low folate; no nerve damage from folate lack alone	Folic acid after B12 deficiency is ruled out
Anemia of inflammation	Chronic infection, autoimmune disease, cancer	Usually normal size; sometimes small	Low serum iron with normal or high ferritin	Treat the underlying disease
Anemia of chronic kidney disease	Too little erythropoietin	Normal size	Reduced kidney function	See Chapter 27
Hemolytic	Inherited red cell disorders, autoimmune, drugs, transfusion reaction	Usually normal or large size	Jaundice, dark urine, high reticulocytes, raised lactate dehydrogenase and bilirubin, low haptoglobin	Treat or remove the cause

Type	Common causes	Typical red cell pattern	Key findings	Treatment focus
Aplastic	Marrow failure, often immune	Normal or large size	Low red cells, white cells and platelets; infections, bleeding	Specialist care: immune suppression, stem cell transplant

MEDICATIONS

Iron, Vitamin B12 and Hydroxyurea

- **Oral iron** (iron salts taken by mouth; the prescriber or pharmacist recommends the product): first-line for most iron deficiency. Check the timing of other drugs and of tea, coffee, calcium and antacids; ask about constipation and nausea.
- **IV iron** (iron sucrose; ferric carboxymaltose): for intolerance, failure or poor absorption of oral iron. Check for previous reactions and allergies, take baseline vital signs, have emergency drugs and equipment ready, monitor during and after the infusion as policy states, and know that anaphylaxis can occur with any IV iron (Health Canada, 2024).
- **Vitamin B12 (cyanocobalamin):** by injection or by mouth. Ask about cobalt or B12 allergy; monitor potassium closely early in treatment of severe deficiency; teach that pernicious anemia needs lifelong treatment (Eugia Pharma, 2023).
- **Folic acid:** for confirmed folate deficiency, after B12 deficiency has been ruled out.
- **Hydroxyurea:** a disease-modifying oral drug used in sickle cell disease (section 20.3). The Canadian product monograph lists only cancer indications; use in sickle cell disease follows hematology guidance (CanHaem, 2014). It suppresses the marrow, so blood counts are monitored. Because it can harm a fetus, the monograph advises reliable birth control while it is taken and afterward: at least 6 months after the last dose for women and at least 1 year for men. It is handled as a hazardous drug: gloves for anyone handling capsules, hand washing, and no opening of capsules without precautions (Eugia Pharma, 2024; Chapter 9).

LIFESPAN CONSIDERATIONS

Anemia in Older Adults

- **Older adults:** anemia is common in older people living in the community, but it is not harmless. Studies link it to higher death rates, more hospital admissions, loss of physical function and frailty, and to worse outcomes in heart failure (Patel & Guralnik, 2009). A low hemoglobin is a finding to explain, not something to accept as part of aging.
- In Canada, anemia among people aged 65 to 79 rose between the 1970s and 2009 to 2011, and the authors suggested that causes other than iron deficiency, including B12 deficiency, may play a part (Cooper et al., 2012).
- In older adults, anemia may first show as fatigue, a fall, worsening angina or heart failure, or confusion. The nurse treats dizziness and weakness as fall risks (Chapter 8).
- New iron deficiency in an older adult calls for a search for gastrointestinal bleeding, including cancer (Ko et al., 2020).
- Medications matter: anti-inflammatory drugs and anticoagulants can cause bleeding, and metformin and proton pump inhibitors can lower B12. A medication review is part of the work-up (Chapter 8).
- **Younger adults:** heavy menstrual bleeding and pregnancy are common causes of iron deficiency in people who menstruate.

20.3 Sickle Cell Disease and Thalassemia

What Happens in Sickle Cell Disease

Sickle cell disease is a group of inherited disorders caused by an abnormal hemoglobin called hemoglobin S. When hemoglobin S gives up its oxygen, its molecules link into long, stiff chains. The red cell becomes rigid and distorts into a crescent or sickle shape that can be trapped in small vessels (Alberta Health Services, 2019; Figure 20.4). Two problems follow:

- **Hemolysis:** sickled cells are fragile and break down early, which causes chronic anemia, jaundice and, over time, gallstones.
- **Vaso-occlusion:** rigid cells block small blood vessels. The tissue downstream becomes ischemic, causing sudden severe pain and, over years, organ damage.

Sickle cell disease is inherited when a person receives a hemoglobin S gene from each parent, or hemoglobin S from one parent and another hemoglobin variant, such as hemoglobin C or beta thalassemia, from the other (Canadian Haemoglobinopathy Association

[CanHaem], 2014). A person who inherits only one hemoglobin S gene has **sickle cell trait**. People with the trait are carriers and generally do not have the disease, but they can pass the gene to their children.

Newborn screening finds the disease before symptoms start, so that infection prevention and family teaching begin early. Programs differ by province and territory (Canadian Context box). Screening also identifies infants with the trait, and families need clear, respectful counselling about what that means (Canadian Institute of Child Health, n.d.).

Figure 20.4 Red blood cells seen with a scanning electron microscope: normal round, dimpled discs and one rigid, crescent-shaped sickle cell. (credit: Janice Haney Carr/Centers for Disease Control and Prevention, public domain)

Complications

- **Vaso-occlusive crisis:** an episode of acute pain from blocked blood flow, often in the back, chest, arms or legs. It is the most common reason people with sickle cell disease come to an emergency department or are admitted (Ontario Health, 2023).
- **Acute chest syndrome:** a new infiltrate on chest X-ray plus one or more of fever, chest pain, rapid breathing, wheezing or cough (Pastore et al., 2017). Infection, fat emboli from damaged marrow and sickled cells trapped in the lungs contribute. It is an emergency that can develop during a pain crisis and progress to respiratory failure. Management includes admission, close monitoring, oxygen to keep saturation at or above 95%, careful fluid balance, urgent hematology input and sometimes transfusion (CanHaem, 2014; Pastore et al., 2017).
- **Infection and functional asplenia:** repeated sickling damages the spleen so that it no longer filters bacteria well. This **functional asplenia** brings a lifelong risk of overwhelming bloodstream infection from encapsulated bacteria. The *Canadian Immunization Guide* recommends all routine vaccines including yearly influenza vaccine, plus pneumococcal, meningococcal and *Haemophilus influenzae* type b vaccines, and hepatitis B vaccine for people who need repeated transfusions (Public Health Agency of Canada [PHAC], 2026). Fever is treated as an emergency: CanHaem (2014) advises giving antibiotics by injection or infusion within 30 minutes of arrival, without waiting for blood cultures.
- **Stroke:** sudden weakness or trouble speaking needs emergency care (Ontario Health, 2023; Chapter 31). Children at high risk are screened and may receive regular transfusions to prevent stroke (CanHaem, 2014).
- **Splenic sequestration:** sickled cells pool in the spleen, which enlarges and becomes painful while the hemoglobin drops quickly (CanHaem, 2014).
- **Priapism:** a sustained, often painful erection lasting 4 hours or more is an emergency (Ontario Health, 2023).
- **Acute anemia:** a hemoglobin that drops 20 g/L or more below the patient's usual (baseline) level (Ontario Health, 2023).
- **Chronic organ damage:** over years, many organs can be affected, and life expectancy is shorter than in people without the disease (Ontario Health, 2023).

Care During a Pain Crisis

Ontario Health's (2023) quality standard sets clear expectations for a vaso-occlusive crisis. Pain is assessed promptly with an age-appropriate pain tool. The patient is triaged at Canadian Triage and Acuity Scale (CTAS) level 2 or a more urgent level. Treatment starts **within 30 minutes of triage or within 60 minutes of arrival**. CanHaem's (2014) consensus statement likewise calls for management to start ideally within 30 minutes. Opioid principles and pain assessment are covered in Chapter 5.

Care during the crisis includes:

- **Following the individualized care plan:** many patients have a written plan from their sickle cell centre; the nurse asks for it and uses it (Ontario Health, 2023).
- **Reassessing often:** pain, sedation, respiratory rate and oxygen saturation are rechecked frequently so that doses are adjusted promptly and opioid-related hypoventilation is caught early (CanHaem, 2014).
- **Hydration:** by mouth if tolerated. Overhydration is avoided because it can cause pulmonary edema (CanHaem, 2014).
- **Oxygen only when needed:** oxygen has no proven benefit in an uncomplicated pain crisis. It is given when saturation is low or respiratory symptoms appear (CanHaem, 2014).
- **Incentive spirometry:** advised once a patient is admitted, and particularly with chest or back pain, to help prevent acute chest syndrome (CanHaem, 2014).
- **Comfort measures:** heat and massage may help alongside medication (Ontario Health, 2023).
- **Watching for acute chest syndrome:** new chest pain, fever, cough, faster breathing or falling saturation are reported immediately.
- **Planning for home:** before discharge, the patient helps write a plan for pain at home, whom to call and follow-up (Ontario Health, 2023).

Stigma and racism: in Canada, sickle cell disease mostly affects racialized people, particularly Black people (Ontario Health, 2023). Patients describe racism and anti-Black racism in health care, long waits, lack of respect and being falsely accused of "drug-seeking", and many delay or avoid emergency care as a result (Ontario Health, 2023). An Ontario study of emergency visits for sickle cell pain crises from 2006 to 2018 found that adults waited on average about 90 minutes to be seen by a physician, longer than the guideline target of a first analgesic dose within 60 minutes of arrival, and that adults and people from lower-income neighbourhoods received poorer-quality care (Chan et al., 2020). Labels such as "frequent flyer" or "drug-seeking" are not assessments. The nurse believes the patient's report of pain, gives analgesia on time, documents objectively and challenges biased comments from colleagues (Chapter 2).

Long-Term Care and Thalassemia

Hydroxyurea is the main disease-modifying drug for sickle cell disease. It raises the level of fetal hemoglobin, which does not sickle, and so reduces sickling. CanHaem (2014) advises that adults with the most severe forms of the disease who have three or more pain crises a year be strongly encouraged to start it, and that it be considered after even one episode of acute chest syndrome. Blood counts are monitored regularly (Medications box). Regular transfusion is used to prevent stroke in high-risk children and for some patients in whom hydroxyurea has not worked (CanHaem, 2014). Each unit of red cells adds about 200 to 250 mg of iron, and the body loses only about 1 mg a day, so repeated transfusion leads to **iron overload** (CanHaem, 2014). Stem cell transplant can cure sickle cell disease in selected patients. Section 20.6 covers transfusion.

The move from pediatric to adult care is a vulnerable time. Ontario Health (2023) recommends that young people aged 15 to 24 have a designated provider who coordinates care until the transition is complete.

Thalassemia is a group of inherited disorders in which the body makes too little of one of the protein chains of hemoglobin. Beta thalassemia is the most common form, and it is classed as major, intermedia or minor (trait). In Canada it mainly affects people of South Asian, Mediterranean or North African descent (Canadian Agency for Drugs and Technologies in Health [CADTH], 2016). People with **thalassemia trait** have small red cells and mild or no anemia. People with transfusion-dependent thalassemia need regular transfusions for life, starting in early childhood (CADTH, 2016); others, with non-transfusion-dependent thalassemia, need transfusion only occasionally.

For transfusion-dependent patients, iron overload is unavoidable: iron comes from transfusions and from increased absorption. Excess iron damages the heart, liver and endocrine glands, causing heart failure, dysrhythmias, cirrhosis, diabetes and hypothyroidism (CADTH, 2016). Iron chelation drugs bind iron so that it can be excreted. A Canadian drug review describes three: deferoxamine, given by slow subcutaneous infusion, usually overnight on most nights of the week, and deferasirox and deferiprone, taken by mouth (CADTH, 2016). Deferiprone can cause a severe drop in neutrophils, so blood counts are monitored and patients

report fever or sore throat at once (CADTH, 2016). Thalassemia major can also cause functional asplenia, so the same vaccine recommendations apply (PHAC, 2026).

CANADIAN CONTEXT

Sickle Cell Disease in Canada

- **How many people:** about 6,500 people in Canada live with sickle cell disease, about 3,500 of them in Ontario, and numbers are expected to grow (Ontario Health, 2023).
- **Who is affected:** the disease is most common in people whose families come from parts of Africa, India, the Middle East and the Mediterranean (Ontario Health, 2023). In Canada it mostly affects racialized people, especially Black people. Sickle cell trait occurs in all racial and ethnic groups, so ancestry alone should never be used to rule it in or out.
- **Newborn screening:** programs vary by province and territory. Ontario and British Columbia screen all newborns, and Alberta added sickle cell disease to its newborn panel in 2019 (Alberta Health Services, 2019; Canadian Institute of Child Health, n.d.).
- **Access to care:** Ontario's quality standard calls for a yearly assessment by an interprofessional team at a dedicated sickle cell centre, with a care plan shared with the patient's circle of care (Ontario Health, 2023). People in smaller or remote communities may live far from such centres.
- **Racism:** the first statement of Ontario's standard is care free from racism, anti-Black racism, discrimination and stigma (Ontario Health, 2023).
- **Advocacy:** patient organizations such as the Sickle Cell Awareness Group of Ontario (SCAGO) support patients and families and advocate for better care.

CLINICAL JUDGMENT

A Vaso-occlusive Crisis in the Emergency Department

Names and details are fictional; this is a composite story.

Daniel Boateng, 24, has sickle cell disease (hemoglobin SS). He arrives at 0140 with severe pain in his lower back and both thighs, rated 9 out of 10, that began 5 hours ago. His home medications have not helped. Heart rate 112 beats/min, blood pressure 128/76 mm Hg, respiratory rate 22 breaths/min, temperature 37.6 °C, SpO2 96% on room air. Hemoglobin is 76 g/L; his baseline in his care plan is 88 g/L.

- **Recognize cues:** severe pain typical of his crises, tachycardia, a hemoglobin 12 g/L below baseline, normal oxygen saturation.
- **Analyze cues:** this fits a vaso-occlusive crisis. Nothing yet suggests acute chest syndrome, but he is at risk.
- **Prioritize hypotheses:** uncontrolled pain is the immediate priority; acute chest syndrome and opioid-related hypoventilation are the main risks.
- **Generate solutions:** analgesia from his individualized plan within 30 minutes of triage; frequent reassessment; oral fluids; incentive spirometry once admitted.
- **Take action:** the nurse gives the first dose 20 minutes after triage and reassesses pain, sedation and breathing often. Six hours later he reports new left-sided chest pain. Temperature is 38.4 °C, respiratory rate 28 breaths/min and SpO2 90%. The nurse applies oxygen, places him upright and calls the physician at once using SBAR, stating a concern for acute chest syndrome.
- **Evaluate outcomes:** a chest X-ray shows a new infiltrate. He is admitted to a monitored bed with hematology involved.

20.4 Bleeding and Clotting Disorders

Hemostasis needs working platelets, clotting factors and a balance between forming and breaking down clots (section 20.1).

Thrombocytopenia

Thrombocytopenia is a platelet count below the laboratory's reference range (section 20.1). Canadian Blood Services explains that it results from decreased production of platelets or from their increased destruction, consumption or sequestration (Lafrance et al., 2025). Low production follows marrow failure, such as aplastic anemia (section 20.2) or leukemia (section 20.5), and chemotherapy (Chapter 9). Consumption occurs in disseminated intravascular coagulation (described below), and in liver disease an enlarged

spleen from portal hypertension can lower the count (Poon et al., 2022). Drugs can also lower the count, including heparin (heparin-induced thrombocytopenia [HIT], Chapter 19).

Immune thrombocytopenia (ITP) is an acquired autoimmune disorder in which the platelet count is low (Neunert et al., 2019). Most people have bruising and petechiae; more severe cases cause nosebleeds, gastrointestinal bleeding or heavy menstrual bleeding (American Society of Hematology [ASH], 2019). Hematology directs treatment. For adults with newly diagnosed ITP and a count below 30×10^9/L, the ASH guideline suggests a short course of corticosteroids (Neunert et al., 2019). Intravenous immunoglobulin (IVIG), a plasma protein product, is also licensed for ITP in Canada (Rutledge Harding et al., 2024). Platelet transfusion is generally reserved for critical bleeding in ITP (Lafrance et al., 2025).

Symptoms often appear only when the count is very low (Canadian Cancer Society, n.d.-b). The nurse looks for:

- **Petechiae:** tiny, flat, red or purple pinpoint spots caused by bleeding under the skin (Figure 20.5).
- **Purpura:** larger patches of bleeding under the skin; **ecchymoses** are bruises.
- **Mucosal bleeding:** bleeding gums, nosebleeds, or oozing that will not stop.
- **Hidden bleeding:** pink, red or brown urine; black or bloody stool; vomit that looks like coffee grounds (Canadian Cancer Society, n.d.-b).

On darker skin, a bruise may look darker than the skin around it rather than blue or purple, and palpation may find tenderness or swelling (Pusey-Reid et al., 2023). Pusey-Reid et al. (2023) advise natural or other indirect light, because fluorescent light casts a bluish tint, and comparing the area with an unaffected site. Petechiae can also be hard to see on darker skin, so the nurse inspects areas with less pigment as well, such as the inside of the mouth, the gums and palate, and the conjunctiva.

Figure 20.5 Petechiae on the lower leg of a person with immune thrombocytopenia and a very low platelet count. On darker skin, petechiae may look darker than the surrounding skin rather than red, and are easier to find in good light. (credit: "Petechia lower leg" by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

Using the Clinical Judgment Measurement Model (CJMM; Chapter 1, section 1.4), the nurse treats a falling count as a cue. Bleeding precautions protect the patient: an extra-soft toothbrush, an electric razor, no rectal thermometers, suppositories or enemas, a check with the prescriber before any intramuscular injection, and no straining at stool (Canadian Cancer Society, n.d.-b). The nurse holds firm pressure on puncture sites, prevents falls (Chapter 8) and checks with the prescriber or pharmacist before giving drugs that weaken platelets, such as acetylsalicylic acid (ASA).

For inpatients with low production caused by therapy, Canadian Blood Services suggests one dose of platelets when the count is below 10×10^9/L, with higher thresholds before procedures and during significant bleeding (Lafrance et al., 2025). Choosing Wisely Canada advises against routine platelet transfusion for chemotherapy-induced thrombocytopenia, noting that a count of 10×10^9/L or more usually allows adequate hemostasis (Canadian Society for Transfusion Medicine [CSTM], 2026). A new headache, blurred vision or a change in level of consciousness can signal bleeding in the brain (Canadian Cancer Society, n.d.-b). The nurse escalates at once (Chapter 6; Chapter 31).

PATIENT EDUCATION

Living With a Low Platelet Count

The nurse teaches the patient and family how to lower the chance of bleeding at home and when to call for help (Canadian Cancer Society, n.d.-b):

- Brush with an extra-soft toothbrush and floss very gently, if at all, as the care team advises.
- Shave with an electric razor, not a blade.

- Do not use rectal thermometers, suppositories or enemas. Ask about a stool softener to avoid straining.
- Check with the pharmacist or prescriber before taking any over-the-counter pain or cold medicine, because some contain ASA or other drugs that weaken platelets.
- Avoid alcohol, contact sports and activities that could cause a fall or injury.
- Use pads rather than tampons during menstruation.
- Ask before any injection into a muscle.
- Call the care team if bleeding cannot be controlled after 10 minutes of pressure or keeps getting worse.
- Call 9-1-1 for a sudden severe headache, blurred vision, confusion or unusual drowsiness, or for vomiting blood or material that looks like coffee grounds.

Hemophilia and Von Willebrand Disease

Hemophilia is an inherited lack of a clotting factor. Hemophilia A is a lack of factor VIII and makes up 80% to 85% of cases; hemophilia B is a lack of factor IX (Poon et al., 2022). Bleeding Disorders Canada, the national patient organization for people with bleeding disorders, estimates that hemophilia A affects about 3,900 people in Canada and hemophilia B about 800 (Bleeding Disorders Canada, 2024).

The gene changes sit on the X chromosome, so hemophilia usually affects males who inherit an affected X chromosome from their mother. Females who have one affected X chromosome are called carriers, and some carriers bleed, for example with heavy or prolonged menstrual periods (Srivastava et al., 2020). Severity follows the factor level: below 1 IU/dL is severe, above 5 IU/dL is mild, and levels in between are moderate (Poon et al., 2022). Severe hemophilia causes bleeding with little or no injury, especially into joints, muscles and soft tissues (Srivastava et al., 2020). A patient may first feel tingling or tightness in a joint; a joint bleed then shows increasing swelling, warmth or pain, or a growing loss of movement. Factor is ideally given as soon as a bleed is suspected (Srivastava et al., 2020). A head injury is treated as a possible bleed in the brain, and bleeding in the throat or neck is an emergency because it can block the airway; treatment is not delayed while waiting for symptoms or a full assessment (Srivastava et al., 2020). Bleeding into deep muscles such as the iliopsoas can also cause large blood loss (Poon et al., 2022; Srivastava et al., 2020).

Treatment replaces the missing factor with factor VIII or factor IX concentrates, including extended half-life products (Poon et al., 2022). Regular prophylaxis is standard care for severe hemophilia. Emicizumab, a non-factor product given to prevent bleeds in hemophilia A, is supplied through Canadian Blood Services and Héma-Québec (Poon et al., 2022). Desmopressin can treat minor bleeds in mild hemophilia A (Poon et al., 2022). Practically all people with hemophilia in Canada are registered with one of 25 hemophilia or bleeding disorder programs, where a team provides comprehensive care (Poon et al., 2022). Patients carry a FactorFirst card that names the diagnosis, the first emergency treatment and the clinic's contact (Poon et al., 2022). The nurse reads the card, believes the patient's report of a bleed and helps start factor without delay.

Von Willebrand disease (VWD) is a lack or defect of von Willebrand factor (VWF), a protein needed to stop bleeding from mucous membranes in the first stage of clotting (Poon et al., 2022). It is the most common inherited bleeding disorder, with a prevalence of about 1 in 1,000 people (Poon et al., 2022). Common signs are frequent nosebleeds, large bruises, heavy menstrual periods, and long bleeding after dental work, surgery, injury or childbirth (Centers for Disease Control and Prevention [CDC], 2024). Treatment depends on the type: desmopressin for people who respond (not type 2B) and concentrates that contain both factor VIII and VWF (Poon et al., 2022). Antifibrinolytic drugs such as tranexamic acid help control mucosal bleeding, and hormonal therapy can help heavy menstrual bleeding (CDC, 2024; Poon et al., 2022). Cryoprecipitate is not recommended for hemophilia A or VWD (Rotin & Mack, 2025).

Disseminated Intravascular Coagulation

Disseminated intravascular coagulation (DIC) is uncontrolled activation of clotting throughout the circulation. Clots form in small vessels and use up clotting factors and platelets; at the same time, the body breaks clots down and releases fibrin degradation products. Depending on that balance, the patient may bleed, clot, or both (Poon et al., 2022). Triggers include severe infection and sepsis (Chapter 4), trauma and massive tissue injury, obstetric complications and cancer (Poon et al., 2022; Popescu et al., 2022).

Because platelets and clotting factors are being used up while clots are broken down, results typically show a falling platelet count and fibrinogen, a rising D-dimer (a fibrin-related marker) and a prolonged prothrombin time (PT); the International Society on

Thrombosis and Haemostasis (ISTH) overt DIC score combines these tests (Poon et al., 2022; Popescu et al., 2022). Removing the trigger is the most important treatment (Poon et al., 2022). A bleeding patient may receive plasma, fibrinogen concentrate, cryoprecipitate or platelets (section 20.6), but replacement does not stop the process, and prothrombin complex concentrate (PCC) is contraindicated because it promotes clotting in DIC (Poon et al., 2022).

The nurse watches for new oozing from IV sites, drains, wounds and gums, and for blood in urine or stool. Cool, mottled or dusky fingers and toes, falling urine output and new confusion can signal clotting in small vessels. Bleeding with a falling blood pressure or rising heart rate needs rapid response (Chapter 6).

GOING DEEPER

Reading DIC Labs

Required for RN students; optional for PN students.

DIC laboratory pattern. No single test diagnoses DIC. The ISTH overt DIC score adds points from four widely available tests: platelet count, PT, fibrinogen and a fibrin-related marker such as D-dimer (Popescu et al., 2022). The maximum is 8 points, and a total of at least 5 is consistent with overt DIC (Poon et al., 2022). Because DIC changes quickly, trends over hours matter more than one result: a platelet count that halves, a fibrinogen that keeps falling and a D-dimer that keeps rising all point the same way. Fibrinogen and factor VIII tend to rise in uncomplicated liver disease, so low levels of both in a patient with liver disease suggest that consumption or DIC has been added (Poon et al., 2022).

20.5 Leukemia, Lymphoma and Myeloma

Blood cancers start in the marrow or the lymphatic system. Cancer biology, chemotherapy and immunotherapy are taught in Chapter 9; this section focuses on what is specific to blood cancers and what the nurse sees at the bedside.



Figure 20.6 A myeloblast with an Auer rod, a thin rod in the cell's cytoplasm. Auer rods are a feature of acute myeloid leukemia, and blasts on a smear are often the first clue to leukemia. (credit: "Myeloblast with Auer Rod smear 2009-11-23" by Paulo Henrique Orlandi Mourao/Wikimedia Commons, CC BY-SA 3.0)

Leukemias

Leukemia is a blood cancer that arises from the blood-forming stem cells of the bone marrow (Canadian Cancer Society, 2022). Immature cells, called blasts, fail to mature and gradually crowd out normal blood cells. Leukemias are grouped in two ways. Acute leukemias start suddenly and develop over days or weeks; chronic leukemias develop over months or years. Myeloid leukemias come from myeloid stem cells, and lymphocytic (lymphoblastic) leukemias from lymphoid stem cells. The four main types are acute myeloid leukemia (AML), acute lymphoblastic leukemia (ALL), chronic myeloid leukemia (CML) and chronic lymphocytic leukemia (CLL) (Canadian Cancer Society, 2022).

For 2026, the Canadian Cancer Statistics Advisory Committee projected 6,500 new diagnoses of leukemia and 3,200 deaths from it in Canada (Brenner et al., 2026; Canadian Cancer Society, 2026b).

When blasts fill the marrow, the patient shows signs of marrow failure:

- **Anemia:** fatigue, weakness, breathlessness and pallor (section 20.2).
- **Infection:** fever and repeated infections, because the white cells present do not work normally.
- **Bleeding:** petechiae, bruising, nosebleeds and gum bleeding from thrombocytopenia (section 20.4).

Diagnosis begins with a CBC and a blood smear (section 20.1), which may show blasts and low counts (Figure 20.6). A bone marrow aspiration and biopsy (Figure 20.7) removes marrow cells for laboratory testing, which shows whether leukemia cells are present and, if so, the type (Canadian Cancer Society, n.d.-a). After the procedure, the nurse checks the site for bleeding, especially when the platelet count is low. Treatment ranges from monitoring in some chronic leukemias to chemotherapy, targeted drugs and stem cell transplant (Chapter 9). Acute promyelocytic leukemia, a form of AML, carries a high risk of serious bleeding and clotting early in treatment. For these patients, Canadian Blood Services lists a higher platelet transfusion threshold (below 30 to 50 × 10^9/L) and notes that it is the only situation in which fibrinogen is routinely replaced as prevention (Lafrance et al., 2025; Rotin & Mack, 2025).



Figure 20.7 Sites that can be used for bone marrow aspiration and biopsy: the sternum, the tibia, and the posterior and anterior iliac crests. (credit: "Site for procedure of Bone Marrow" by Scientific Animations (scientificanimations.com)/Wikimedia Commons, CC BY-SA 4.0)

Lymphomas

Lymphoma is a cancer of lymphocytes that usually grows in lymph nodes or other lymphatic tissue. The two main groups are Hodgkin lymphoma and non-Hodgkin lymphoma; the second is far more common. For 2026, the Canadian Cancer Statistics Advisory Committee projected 12,100 new diagnoses of non-Hodgkin lymphoma and 3,200 deaths from it in Canada, compared with 1,250 new diagnoses of Hodgkin lymphoma and 120 deaths (Brenner et al., 2026; Canadian Cancer Society, 2026a, 2026d).

The most common sign of non-Hodgkin lymphoma is enlarged, usually painless lymph nodes in the neck, groin or armpit (Canadian Cancer Society, n.d.-d). Patients may also have itching, fatigue or **B symptoms**, a set of three general symptoms used in staging and prognosis (North American Association of Central Cancer Registries [NAACCR], 2025):

- unexplained fever above 38 °C;
- drenching night sweats, enough to need a change of bedclothes;
- unexplained loss of more than 10% of usual weight over the 6 months before diagnosis.

Diagnosis needs a biopsy of an affected node. The nurse asks about these symptoms, weighs the patient on the same scale each time and records temperatures and night sweats accurately.

Multiple Myeloma

Multiple myeloma is a cancer of plasma cells, the marrow cells that make antibodies. Abnormal plasma cells multiply in the bone marrow, and the disease can weaken bone, lower blood counts and damage the kidneys (Canadian Cancer Society, n.d.-c). For 2026, the Canadian Cancer Statistics Advisory Committee projected 4,400 new diagnoses of multiple myeloma and 1,800 deaths from it in Canada (Brenner et al., 2026; Canadian Cancer Society, 2026c).

The main features are often remembered as CRAB (Canadian Cancer Society, n.d.-c):

- **High calcium:** thirst, frequent urination, dehydration, constipation, nausea, vomiting, weakness, drowsiness and confusion.
- **Kidney problems:** up to kidney failure (Chapter 27).
- **Anemia:** fatigue and breathlessness.
- **Bone disease:** pain and fractures, often in the back, ribs, hips or skull.

Patients are also prone to infection and may have low platelets, thick blood (hyperviscosity) or nerve problems. New back pain with leg weakness, numbness or trouble passing urine can signal spinal cord compression, a cancer emergency (Canadian Cancer Society, n.d.-c; Chapter 9).

Hypercalcemia is taught in Chapter 3 and hypercalcemia of malignancy in Chapter 9. The nurse recognizes new confusion, drowsiness or constipation in a patient with myeloma as possible cues of a rising calcium, checks the result and reports it promptly. Fragile bones make safe movement central. The nurse assesses pain before activity and treats it (Chapter 5), helps the patient move without twisting or lifting, uses a mobility aid and the bed's lowest position, and puts fall prevention in place (Chapter 8). Gentle activity as tolerated is encouraged, because bed rest weakens bone and muscle further.

Nursing Care Across Blood Cancers

Blood cancers and their treatments often leave patients with low white cells, low platelets and anemia at the same time.

- **Infection prevention:** Neutropenia means a low neutrophil count. The nurse uses careful hand hygiene and infection prevention and control (IPAC) practices (Chapter 4), teaches the patient to report fever and treats fever in neutropenia as an emergency (Chapter 9).
- **Bleeding:** The nurse uses the bleeding precautions in section 20.4 and the transfusion practices in section 20.6.
- **Fatigue:** The nurse plans rest between activities and links fatigue to the hemoglobin trend.
- **Tumour lysis syndrome:** Rapid cell death at the start of treatment can upset electrolytes and harm the kidneys (Chapter 9).

A **stem cell transplant** replaces blood-forming stem cells. Autologous transplants use the patient's own stem cells, and allogeneic transplants use stem cells from a donor; both are used for some leukemias, lymphomas and myeloma (Canadian Cancer Society, n.d.-e). **Graft-versus-host disease**, listed among the possible side effects of transplant (Canadian Cancer Society, n.d.-e), occurs after allogeneic transplant when the donor's immune cells react against the recipient's tissues (Chapter 9).

Diagnosis brings fear, financial strain and decisions about work and family. Treatment can affect fertility, so the nurse makes sure that patients of reproductive age have had the chance to discuss fertility before treatment starts (Chapter 9). Specialized treatment is concentrated in large centres, so many rural, remote and northern patients must stay far from home for weeks. Inuit from remote communities often travel thousands of kilometres to southern cities for cancer care. In one Canadian study, Inuit patients and their medical escorts described feeling directed with little support and lacking explanations of the decisions they faced (Jull et al., 2021). The nurse explains each step, arranges an Inuktitut interpreter when wanted, includes the escort and family, and connects the patient with Indigenous patient navigators and culturally safe supports (Chapter 2).

20.6 Blood Components and Transfusion

Transfusion can save lives, but each unit carries risks and comes from a volunteer donor. In Canada, Canadian Blood Services supplies blood outside Quebec and Héma-Québec supplies Quebec; Health Canada regulates blood under the *Food and Drugs Act*

and the *Blood Regulations*, and the Canadian Standards Association (CSA) blood standard covers facilities that collect, process, test, store and use blood components for transfusion (Gabarin & Yan, 2024).

Components and Plasma Products

A **blood component** is a part of donated blood, separated after collection (Table 20.3):

- **Red blood cell concentrate:** red cells with most plasma and white cells removed. In a non-bleeding adult weighing about 70 kg, one unit usually raises hemoglobin by about 10 g/L (Rotin & Mack, 2025).
- **Platelets:** pooled from several donors or collected from one donor by apheresis, and stored at room temperature (20 °C to 24 °C) with gentle agitation (Rotin & Mack, 2025).
- **Frozen plasma:** plasma that contains all the clotting factors.
- **Cryoprecipitate:** a small volume made from frozen plasma that is rich in fibrinogen. Fibrinogen concentrate is increasingly preferred in Canada (Rotin & Mack, 2025).

Plasma protein products are drugs made by pharmaceutical companies from pooled donor plasma, or made by recombinant technology, and distributed to hospitals by the blood operators (Gabarin & Yan, 2024). They include albumin, IVIG, PCC, fibrinogen concentrate and factor concentrates (CSTM, 2026; Poon et al., 2022; Rutledge Harding et al., 2024).

Compatibility starts with the ABO and RhD groups. In an emergency, before the patient's group is known, uncrossmatched group O red cells are given. Group O RhD-negative red cells are reserved for females of child-bearing age, children and patients known or suspected to have anti-D antibodies; in discussing emergency supply, Canadian Blood Services refers to females 45 years and younger (Trudeau et al., 2021). Outside emergencies, RhD-negative girls, and RhD-negative women who could become pregnant, are not routinely given RhD-positive components, because antibodies to RhD could harm a future fetus (Duncan, 2020). Group O RhD-negative red cells and group AB plasma are in short supply; Choosing Wisely Canada advises keeping O-negative red cells for O-negative patients, noting that O-positive red cells are acceptable for males and for females who cannot become pregnant, and keeping AB plasma for group AB patients and emergencies in which the group is unknown (CSTM, 2026). Some patients need specially processed components, such as irradiated or washed products; the prescriber and the transfusion service decide.

Table 20.3 Blood components and plasma products: what each is, why it is given, and nursing points (Rotin & Mack, 2025; Gabarin & Yan, 2024; Rutledge Harding et al., 2024; CSTM, 2026; original wording)

Product	What it contains	Main uses	Nursing points
Red blood cell concentrate	Red cells in a preserving solution; leukoreduced	Symptomatic anemia; acute blood loss	Give one unit, then reassess in stable patients; not for volume replacement; refrigerated until issued
Platelets	Pooled or single-donor platelets, often pathogen-reduced	Bleeding with low or poorly working platelets; prevention when the count is very low	Stored at room temperature, never refrigerated; generally avoided in ITP, HIT and thrombotic thrombocytopenic purpura (TTP)
Frozen plasma	Plasma with all clotting factors	Bleeding with clotting factor deficiency when no specific product exists; massive hemorrhage; plasma exchange	Must be ABO compatible; thawed before use; not for volume or a mildly raised INR
Cryoprecipitate	Concentrated fibrinogen and other factors from plasma	Bleeding with low fibrinogen	Thawed before use; not used to treat hemophilia A or VWD
Albumin	Protein from pooled plasma	Selected uses such as therapeutic plasma exchange	A plasma protein product; routine 5% albumin is not recommended outside plasma exchange
IVIG	Antibodies from many donors	Immune deficiency, ITP and some neurologic disorders	Start slowly and raise the rate as tolerated; watch for headache and chills, and for thrombosis during or up to 8 days after the infusion

Product	What it contains	Main uses	Nursing points
PCC and fibrinogen concentrate	Concentrated clotting factors or fibrinogen	Urgent warfarin reversal (PCC); low fibrinogen with bleeding	Dosed like drugs; PCC is contraindicated in DIC

Before a Transfusion

Red cells are given for symptomatic anemia or bleeding, not because of one number. Canadian Blood Services describes the restrictive thresholds generally considered: hemoglobin below 70 g/L for most hospitalized patients, including those in intensive care and oncology, below 75 g/L after cardiac surgery, and below 80 g/L for patients with cardiac ischemia or undergoing orthopedic surgery. The decision is individualized (Rotin & Mack, 2025). Choosing Wisely Canada advises against transfusion when another therapy, such as iron for stable iron deficiency, would work as well, and advises that stable, non-bleeding patients receive a single red cell unit, with the patient and hemoglobin reassessed before any further unit (CSTM, 2026). Standard thresholds such as 70 g/L do not apply in sickle cell disease, and hematology or transfusion medicine specialists should be involved in those decisions (CSTM, 2026; section 20.3).

Informed consent is required before transfusion. Facility policy sets out what is discussed: the product, its benefits and risks, including serious ones, and the alternatives; the discussion is documented (O'Reilly, 2020). Consent and capacity are taught in Chapter 1, section 1.5. A capable patient may refuse blood or some blood products. Before a refusal is accepted, the team explains what could happen without the transfusion and records that conversation (O'Reilly, 2020). The nurse does not assume the reason. The nurse asks which products and procedures the patient will and will not accept, checks for an advance directive or wishes expressed while capable, and makes sure the team has discussed alternatives, such as early treatment of iron deficiency. The nurse respects the decision and continues care without pressure.

Before blood is issued, the laboratory does a **group and screen** (also called type and screen): ABO and RhD typing and a screen for antibodies against red cells (Duncan, 2020). A **crossmatch**, done serologically or electronically, confirms that donor red cells are compatible with the patient's plasma. The nurse labels the sample at the bedside, in the patient's presence, at the time it is drawn. If the patient has been transfused or pregnant in the past 3 months, the sample must be drawn within 96 hours before the transfusion (Duncan, 2020).

The patient needs a dedicated IV line; medications are not infused with blood components (a separate lumen of a multi-lumen central line may be used). Canadian Blood Services suggests a 20- to 22-gauge catheter for routine adult transfusion and 16 to 18 gauge for rapid transfusion, with a standard blood set that has a 170- to 260-micron filter (O'Reilly, 2020). The line is primed with the component or a compatible solution, such as sterile 0.9% sodium chloride, and flushed afterwards with 0.9% sodium chloride (O'Reilly, 2020). The nurse collects the component from the transfusion service only when the patient, line and paperwork are ready (Figure 20.8).

Giving Blood Safely

Canadian Blood Services calls for positive identification at every step, from labelling the sample at the bedside with at least two unique identifiers to giving the component, using the patient's identification band. Whenever possible, the patient confirms the band by spelling their name and stating their date of birth (O'Reilly, 2020). At the bedside, in the patient's presence, the component label is checked against the band and the order. Facility policy sets whether a second person performs an independent double check.

Canadian Blood Services describes the following monitoring (O'Reilly, 2020); hospital policy governs local practice:

- An assessment and baseline vital signs, documented no more than 30 minutes before the transfusion starts.
- A slow start: the guide gives 50 mL/h as the adult starting rate for red cells, platelets, plasma and cryoprecipitate.
- The nurse stays with the patient, or close enough to observe closely, for the first 5 to 15 minutes of each unit.
- After 15 minutes, the nurse reassesses the patient and repeats vital signs, then increases the rate if there is no reaction; further checks follow policy.
- Each component is transfused within 4 hours of issue. An interrupted transfusion is stopped once 4 hours have passed, even if it is not finished.

Blood warmers are used during rapid transfusion to prevent hypothermia, and pressure devices must not exceed 300 mm Hg (O'Reilly, 2020). The nurse documents the product and unit number, start and finish times, volume, vital signs, staff involved and any reaction. Any change in the patient's condition within 6 hours after a transfusion is treated as a possible reaction and reported to the transfusion service. Outpatients go home with written information on signs to report (O'Reilly, 2020).

Figure 20.8 A unit of red blood cell concentrate connected to a blood administration set with an in-line filter. The nurse checks the unit tag against the patient and the order at the bedside before starting. (credit: "Red blood cells and blood IV tubing" by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

CLINICAL SAFETY

The Bedside Transfusion Check

The final check happens in the patient's presence, using the identification band, immediately before the component is given. Canadian Blood Services calls it the last opportunity to prevent an identification error (O'Reilly, 2020).

- Ask the patient to say and spell their full name and give their date of birth, and match both to the identification band. If the patient cannot answer, use the band and the facility's process for patients who cannot confirm their identity.
- Match the band to the component's tag or label and to the transfusion order: name, identification number, ABO and RhD group, unit number and product type.
- Confirm that consent is documented and that any special requirement, such as irradiated product, has been met.
- Check the bag's expiry, appearance and integrity; do not use a bag that is leaking, clumped or discoloured.
- Use only 0.9% sodium chloride or another solution the facility lists as compatible, and no medications, in the line.
- Perform an independent double check when policy requires it.
- If anything does not match, do not start. Return the unit to the transfusion service and call it.

SCOPE IN PRACTICE

Who Checks and Gives Blood

Whether a nurse may check, hang or monitor a transfusion depends on authority, competence and context (Chapter 1, section 1.3). Authority comes from legislation and a valid order. Competence includes knowing the components, the bedside check and the signs of a reaction, often confirmed by an employer's education and skills check. Context includes the patient's condition and the supports nearby.

Employer policy decides who may perform each step. Some hospitals limit which nurses may hang blood or act as the second checker, or assign transfusion to registered nurses (RNs). These limits are employer practices, not College of Nurses of Ontario

(CNO) rules, and policies differ between employers and between provinces and territories. A practical nurse (PN), called a licensed practical nurse (LPN) in some provinces and a registered practical nurse (RPN) in Ontario, follows their own employer's policy.

Some duties never depend on role. Every nurse who notices signs of a possible reaction stops the transfusion, stays with the patient, keeps the line open with 0.9% sodium chloride and calls for help, including a rapid response if the patient is unstable (Chapter 6). As the patient's needs change, the RPN consults the RN and the team.

Transfusion Reactions

A **transfusion reaction** is any harmful response to a blood component or product. Canadian national surveillance for 2018 to 2019 reported a risk of about 1 reaction for every 2,600 units of blood components transfused (Laureano et al., 2022). Manitoba's provincial guidance notes that most reactions begin between 1 and 30 minutes after the transfusion starts (Shared Health, 2024). Table 20.4 summarizes the main types (Laureano et al., 2022):

- **Acute hemolytic transfusion reaction:** rapid destruction of transfused red cells, most often from ABO incompatibility caused by an identification error. It is rare but can be fatal.
- **Febrile non-hemolytic transfusion reaction:** fever and chills without hemolysis, more common with platelets.
- **Allergic and anaphylactic reactions:** from hives and itching to a rare, life-threatening anaphylaxis.
- **Transfusion-associated circulatory overload (TACO):** fluid overload that causes breathlessness and pulmonary edema.
- **Transfusion-related acute lung injury (TRALI):** sudden lung injury that floods the lungs with fluid, not from heart failure, and can cause respiratory failure.
- **Septic reaction:** from a component contaminated with bacteria, more often platelets.
- **Delayed hemolytic transfusion reaction:** hemolysis more than 24 hours later, often 1 to 2 weeks after transfusion.

Because signs overlap at first, the first actions are the same for any suspected reaction, as provincial guidance describes (Shared Health, 2024; Laureano et al., 2022):

- **Stop** the transfusion. Disconnect the component but do not discard it.
- **Keep the vein open** with 0.9% sodium chloride through new IV tubing.
- **Stay** with the patient and check vital signs at least every 15 minutes until the patient is stable.
- **Check** the patient's identity and the component label again, ideally with a second person.
- **Notify** the prescriber and the transfusion service. The prescriber decides whether the transfusion may continue.
- **Send** the samples policy requires and return the bag with the tubing attached, clamped and capped.
- **Document** the event and complete the facility's reaction report.

Severe signs, such as low blood pressure, breathing difficulty, chest or back pain or dark urine, need immediate rapid response (Chapter 6). Anaphylaxis is treated with epinephrine and airway support (Laureano et al., 2022; Chapter 21). For a minor reaction such as hives alone, the prescriber may allow the transfusion to restart, but only within 4 hours of the original start, with close observation for the next 15 minutes (Shared Health, 2024).

Hemovigilance is the surveillance of transfusions and their outcomes. The hospital transfusion service reports reactions to the provincial office, which forwards reports to the Public Health Agency of Canada, and reports some events to Health Canada and Canadian Blood Services (Yan, 2020). When in doubt, the guidance is to report.

Table 20.4 Transfusion reactions: timing, signs and first actions (Laureano et al., 2022; Shared Health, 2024; original wording)

Reaction	Usual timing	Key signs	First actions
Acute hemolytic	During the transfusion, often early	Fever, chills, pain (such as back or flank pain), breathlessness, low blood pressure, dark urine, low urine output, oozing	Stop; keep line open with new saline tubing; rapid response; recheck identity and label; notify transfusion service
Febrile non-hemolytic	During or up to 4 hours after	Temperature rise of more than 1 °C and/or above 38 °C; chills or rigors	Stop; assess for more serious causes; notify; treat fever as ordered

Reaction	Usual timing	Key signs	First actions
Allergic (minor)	During transfusion	Hives, itching, flushing	Stop; notify; antihistamine as ordered; restart only if the prescriber allows
Anaphylactic	During the transfusion, often early	Wheeze, throat swelling, low blood pressure	Stop; call for help; epinephrine and airway support
TACO	During or up to 12 hours after	Breathlessness, signs of volume overload such as crackles and edema; blood pressure may rise	Stop; sit upright; oxygen; notify; diuretic as ordered
TRALI	During or within 6 hours after	Breathlessness and low oxygen from non-cardiogenic pulmonary edema; blood pressure may fall; fever possible	Stop; oxygen and respiratory support; rapid response; notify
Septic	During or after	Fever, fast heart rate, low blood pressure	Stop; rapid response; blood cultures from patient and bag; notify
Delayed hemolytic	More than 24 hours, often 1 to 2 weeks	Falling hemoglobin, jaundice, low-grade fever	Report to the prescriber and transfusion service

GOING DEEPER

Telling TACO From TRALI

Required for RN students; optional for PN students.

Both cause sudden breathlessness and low oxygen saturation during or after a transfusion. Canadian Blood Services lists features that help tell them apart (Laureano et al., 2022):

- **Timing:** TACO appears up to 12 hours after transfusion; TRALI appears within 6 hours of the transfusion ending.
- **Blood pressure:** may be raised in TACO; may be low in TRALI.
- **Fever:** usually absent in TACO, though it can occur; may be present in TRALI.
- **Fluid overload and diuretics:** TACO shows volume overload and improves with diuretics; in TRALI, both are inconsistent.
- **Brain natriuretic peptide (BNP):** raised in TACO; inconsistent in TRALI.

Suspected TRALI is also reported to Canadian Blood Services, with its TRALI patient data form, in addition to any provincial form (Yan, 2020).

Massive Hemorrhage in Brief

Older definitions of massive hemorrhage, such as 10 or more red cell units in 24 hours, can only be applied looking back. A more practical marker at the bedside is the critical administration threshold: needing 3 or more red cell units within 1 hour (Trudeau et al., 2021). A **massive hemorrhage protocol** is a hospital plan that, once activated, speeds the delivery of components to the bedside and coordinates the team while the bleeding is controlled. Protocols supply red cells, plasma and platelets in ratios that approximate whole blood, and replace fibrinogen early (Trudeau et al., 2021). Uncrossmatched group O red cells are used until the patient's group is confirmed. For trauma, most protocols include early tranexamic acid, an antifibrinolytic; in the large trial behind this practice, the benefit was seen when it was given within 3 hours of injury (Trudeau et al., 2021).

The nurse keeps components flowing and the patient warm and monitored. Transfused blood is run through an approved blood warmer; temperature is checked continuously or at least hourly, because a temperature below 35 °C impairs clotting. The citrate in blood products lowers ionized calcium, so calcium is monitored and replaced (Trudeau et al., 2021). Blood work, including ionized calcium, is repeated at least every hour (Trudeau et al., 2021). Shock is taught in Chapter 6 and surgical blood management in Chapter 7.

PRACTICE STORY

One Unit at a Time

Names and details are fictional; this is a composite story.

Nurse: Mariam Haddad, RN. Years in practice: 7. Setting: medical unit, Ontario.

Mr. Lucien Thibodeau was 86, with heart failure and anemia from a slow gastrointestinal bleed that had since stopped. His hemoglobin that morning was 64 g/L, and two units of red cells were ordered. The first unit went in over 3 hours without a problem. He said he felt "a bit less wobbly."

I started the second unit just after supper. His blood pressure was 138/74 mm Hg, his heart rate 82 and his oxygen saturation 95% on room air. About an hour in, he pressed his call bell. He was sitting forward, breathing fast and coughing. His blood pressure had climbed to 172/90 mm Hg, his heart rate was 108 and his saturation had dropped to 88%. I heard crackles at both lung bases that had not been there at noon.

I stopped the transfusion and kept the line open with saline on new tubing. I sat him upright with his legs down, started oxygen under our protocol and called for help. My charge nurse came in, and I called the physician on duty with an SBAR (Situation, Background, Assessment, Recommendation) report, saying I suspected circulatory overload. He ordered a diuretic and a chest X-ray. I stayed with Mr. Thibodeau, checked his vital signs every 15 minutes and watched his urine output. Within an hour his breathing had eased and his saturation was back to 93%. I returned the bag and tubing to the transfusion service and completed the reaction report.

Later I looked at his chart again. After the first unit, nobody had checked his hemoglobin or asked whether he still needed a second. For a frail man with a weak heart, the volume of two units in one day was too much. Now, when I see an order for more than one unit in a stable patient, I ask whether we can give one, reassess, and then decide.

Reflect: What cues suggested circulatory overload rather than an allergic reaction? If an RPN had been caring for Mr. Thibodeau and noticed his breathlessness, what should the RPN have done first, and when should the RPN have involved the RN?

Chapter 20 Summary

Introduction

- Blood disorders and transfusion affect patients on every unit, and nurses read results, follow trends and act on changes.
- The chapter covers blood tests, anemias, inherited hemoglobin disorders, bleeding and clotting disorders, blood cancers and transfusion.

20.1 Blood and Its Tests

- Blood cells are made in the bone marrow from stem cells; erythropoietin from the kidneys drives red cell production, which needs iron, vitamin B12 and folate.
- The CBC reports hemoglobin (g/L), hematocrit (L/L), red cell indices, white cells with a differential and platelets ($\times 10^9$/L); ranges vary by laboratory.
- Laboratories prefer serum ferritin to screen for iron deficiency, but inflammation can raise it.
- Critical values are phoned to the team; the nurse assesses the patient, notifies the prescriber and documents.
- INR, aPTT, fibrinogen and D-dimer each answer a different clotting question; reagent and laboratory affect their ranges.

20.2 Anemias

- Anemia results from blood loss, low production or early destruction of red cells, and is always a sign with a cause.
- Pallor is assessed in the conjunctiva, mouth, nail beds and palms on every skin tone, and confirmed with a hemoglobin level.
- Iron deficiency anemia needs a search for the source of loss, including gastrointestinal investigation in men and postmenopausal women.
- Oral iron is first-line; IV iron needs monitoring for hypersensitivity, which can occur with any product.
- Vitamin B12 deficiency causes large red cells and nerve damage that can become permanent; potassium is monitored early in treatment.
- In older adults, anemia is linked with poorer outcomes and should be investigated, not accepted as aging.

20.3 Sickle Cell Disease and Thalassemia

- Hemoglobin S causes sickling, hemolysis and blocked blood vessels; sickle cell trait is a carrier state.
- Acute chest syndrome, fever with functional asplenia, stroke, splenic sequestration and priapism are emergencies.

- Ontario's quality standard expects treatment of a pain crisis to start within 30 minutes of triage or within 60 minutes of arrival, with frequent reassessment and an individualized plan.
- Stigma and anti-Black racism affect sickle cell care in Canada; nurses believe the patient's report of pain and challenge biased labels.
- Hydroxyurea, transfusion and iron chelation are the mainstays of long-term care; transfusion-dependent thalassemia leads to iron overload.

20.4 Bleeding and Clotting Disorders

- Thrombocytopenia comes from low production or from increased destruction, consumption or sequestration of platelets; ITP is immune, and platelet transfusion is reserved for critical bleeding.
- On darker skin, bruises may look darker than the surrounding skin and petechiae can be hard to see, so the nurse uses natural or indirect light, compares with an unaffected site and checks the mouth and conjunctiva.
- Bleeding precautions include an extra-soft toothbrush, an electric razor, no rectal routes and a check before intramuscular injections; neurologic change is escalated at once.
- Hemophilia A (factor VIII) and B (factor IX) are X-linked; joint and muscle bleeds need prompt factor replacement guided by the FactorFirst card and a bleeding disorder program.
- VWD is the most common inherited bleeding disorder and often causes heavy menstrual bleeding; desmopressin, factor VIII/VWF concentrates and tranexamic acid are used.
- DIC consumes platelets and factors, causing bleeding and clotting; treating the cause comes first, and new oozing with hypotension needs rapid response.

20.5 Leukemia, Lymphoma and Myeloma

- Leukemias are acute or chronic and myeloid or lymphocytic; blasts crowd out normal cells and cause anemia, infection and bleeding.
- Lymphoma most often shows painless swollen lymph nodes and may cause B symptoms: fever, drenching night sweats and weight loss.
- Multiple myeloma causes high calcium, kidney problems, anemia and bone disease; new confusion or constipation may signal hypercalcemia, and fall prevention protects fragile bones.
- Nursing care across blood cancers covers infection prevention in neutropenia, bleeding, fatigue and tumour lysis, with stem cell transplant as autologous or allogeneic.
- Patients from rural, remote and northern communities, including Inuit, often travel far for care and need clear explanations, interpreters and culturally safe support.

20.6 Blood Components and Transfusion

- Components include red cells, platelets, frozen plasma and cryoprecipitate; plasma protein products such as albumin, IVIG, PCC and fibrinogen concentrate are distributed by Canadian Blood Services and Héma-Québec.
- Restrictive thresholds guide red cell transfusion (generally below 70 g/L in most hospitalized patients, individualized), and stable, non-bleeding patients receive one unit at a time, then reassessment.
- Consent covers benefits, risks and alternatives; a capable patient may refuse, and the nurse explores what the patient will accept without assumptions.
- Safe administration requires positive identification in the patient's presence, a dedicated line with no medications, baseline and 15-minute vital signs, a slow start with close observation and completion within 4 hours of issue.
- For any suspected reaction, the nurse stops the transfusion, keeps the vein open with saline through new tubing, stays, rechecks identity and label, notifies and escalates; reactions are reported through hemovigilance systems.
- Massive hemorrhage protocols deliver components quickly in balanced ratios, with early tranexamic acid in trauma, blood warming and calcium monitoring.

Key Terms (53)

acute chest syndrome: a new lung infiltrate with fever or respiratory symptoms in a person with sickle cell disease; an emergency

acute hemolytic transfusion reaction: rapid destruction of transfused red cells, most often from ABO incompatibility, causing fever, pain, hypotension and dark urine.

anemia: a hemoglobin below the reference range for the person's age and sex; a sign with an underlying cause

anemia of inflammation: anemia caused by inflammatory signals that block iron absorption and trap iron in storage cells

aplastic anemia: failure of the bone marrow to produce enough red cells, white cells and platelets

B symptoms: unexplained fever above 38 °C, drenching night sweats and unexplained loss of more than 10% of body weight in the 6 months before diagnosis.

blood component: a part of donated blood separated after collection, such as red cells, platelets, plasma or cryoprecipitate.

complete blood count (CBC): a blood test that reports hemoglobin, hematocrit, red cell count and indices, white cell count and differential, and platelet count

critical value: a laboratory result far enough outside the reference range that the laboratory reports it to the care team at once

crossmatch: a test, serologic or electronic, that confirms donor red cells are compatible with the patient's plasma.

cryoprecipitate: a small-volume plasma component rich in fibrinogen.

disseminated intravascular coagulation (DIC): uncontrolled activation of clotting throughout the circulation that consumes platelets and clotting factors and can cause both bleeding and clotting.

ecchymosis: a bruise; bleeding under the skin that may look darker than the surrounding skin on darker skin tones.

febrile non-hemolytic transfusion reaction: fever and chills during or up to 4 hours after a transfusion without destruction of red cells.

ferritin: the storage form of iron; serum ferritin is the screening test laboratories prefer when iron deficiency is suspected

frozen plasma: plasma that contains all the clotting factors, frozen after collection and thawed before use.

functional asplenia: loss of the spleen's ability to filter bacteria even though the spleen is present, as in sickle cell disease

graft-versus-host disease: a complication of allogeneic transplant in which the donor's immune cells react against the recipient's tissues.

group and screen: laboratory ABO and RhD typing with a screen for antibodies against red cells; also called type and screen.

hematocrit: the fraction of blood volume made up of red blood cells; reported in L/L

hematopoiesis: the production of blood cells, which in adults takes place in the bone marrow

hemoglobin: the iron-containing protein in red blood cells that carries oxygen; reported in g/L

hemolysis: destruction of red blood cells before the end of their normal lifespan

hemophilia: an inherited lack of clotting factor VIII (hemophilia A) or factor IX (hemophilia B), usually affecting males.

hemovigilance: the surveillance of transfusions and their outcomes to improve safety.

hydroxyurea: an oral drug that raises fetal hemoglobin and reduces sickling; handled as a hazardous drug

immune thrombocytopenia (ITP): an acquired autoimmune disorder with a low platelet count, causing bruising, petechiae and sometimes mucosal bleeding.

iron chelation: drug treatment that binds excess iron so that it can be excreted

iron deficiency anemia: anemia caused by too little iron for hemoglobin production, with small, pale red cells and low ferritin

iron overload: excess body iron, usually from repeated transfusion, that damages the heart, liver and endocrine glands

jaundice: yellow colour of the sclera, mucous membranes and skin caused by raised bilirubin

leukemia: a cancer that starts in the blood-forming stem cells of the bone marrow, in which immature cells crowd out normal blood cells.

lymphoma: a cancer of lymphocytes that usually grows in lymph nodes or other lymphatic tissue; the two main groups are Hodgkin and non-Hodgkin lymphoma.

macrocytic anemia: anemia with large red cells, typically from vitamin B12 or folate deficiency

massive hemorrhage protocol: a hospital plan that speeds delivery of blood components and coordinates the team during life-threatening bleeding.

mean corpuscular volume (MCV): the average size of red blood cells, in femtolitres, used to sort anemias into small-cell, normal-cell and large-cell patterns

multiple myeloma: a cancer of plasma cells in the bone marrow that can cause high calcium, kidney problems, anemia and bone disease.

pernicious anemia: an autoimmune disease in which loss of intrinsic factor prevents absorption of vitamin B12

petechiae: tiny, flat, red or purple pinpoint spots caused by bleeding under the skin.

plasma protein product: a drug made from pooled donor plasma or by recombinant technology, such as albumin, IVIG, PCC or a factor concentrate.

purpura: patches of bleeding under the skin that are larger than petechiae.

red blood cell concentrate: a unit of donated red cells with most plasma and white cells removed.

reticulocyte: a young red blood cell recently released from the marrow; the count shows whether the marrow is responding to anemia

sickle cell disease: inherited disorders in which hemoglobin S makes red cells rigid and sickle-shaped, causing hemolysis and blocked blood vessels

sickle cell trait: carrying one hemoglobin S gene; carriers generally do not have the disease but can pass the gene on

stem cell transplant: replacement of blood-forming stem cells with the patient's own (autologous) or a donor's (allogeneic) stem cells.

thalassemia: inherited disorders in which too little of one hemoglobin protein chain is made

thrombocytopenia: a platelet count below the laboratory's reference range, from decreased production or from increased destruction, consumption or sequestration of platelets.

transfusion reaction: any harmful response to a blood component or product.

transfusion-associated circulatory overload (TACO): fluid overload from transfusion, during or up to 12 hours after it, that causes breathlessness and signs of volume overload such as pulmonary edema.

transfusion-related acute lung injury (TRALI): sudden lung injury, with fluid in the lungs that is not caused by heart failure, during a transfusion or within 6 hours after it.

vaso-occlusive crisis: an episode of acute pain caused by sickled cells blocking blood flow

von Willebrand disease (VWD): the most common inherited bleeding disorder, caused by a lack or defect of von Willebrand factor; it often causes nosebleeds, bruising and heavy menstrual bleeding.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Ms. Abena Owusu (Questions 1–4): Ms. Abena Owusu, 27, has sickle cell disease (hemoglobin SS) and arrives at a community hospital emergency department at 0215. She reports pain in her lower back and both thighs, 9 out of 10, that began 6 hours ago and did not improve with her home medication. Heart rate 108 beats/min, blood pressure 124/78 mm Hg, respiratory rate 20 breaths/min, temperature 37.3 °C, SpO2 97% on room air. She carries a written care plan from her sickle cell clinic. As the nurse takes her to a stretcher, a staff member says, "She's in here every month looking for opioids."

1. [CORE] Which action by the nurse is most important in the first 30 minutes after triage?

a. Obtaining a urine drug screen before giving any analgesic medication

b. Starting analgesia as directed by her individualized care plan

c. Applying oxygen by nasal prongs to reduce sickling

d. Starting IV fluids at a high rate to reverse the crisis

Answer: b — Ontario's quality standard expects treatment of a vaso-occlusive crisis to start within 30 minutes of triage or within 60 minutes of arrival, and the individualized plan names what works for her (b) (section 20.3). A drug screen (a) delays care and reflects bias rather than a clinical need. Oxygen (c) has no proven benefit in an uncomplicated crisis when saturation is normal. Overhydration (d) is avoided because it can cause pulmonary edema.

2. [CORE] How should the nurse respond to the staff member's comment?

a. Agree, and ask the physician to choose non-opioid analgesics only

b. Say nothing, to avoid conflict in front of the patient

c. Document the comment in Ms. Owusu's health record as a behavioural concern about opioid use

d. Say that her frequent visits reflect her disease, and treat her pain promptly

Answer: d — Labels such as "drug-seeking" are not assessments, and Ontario's standard calls for care free from racism and stigma; challenging the comment respectfully protects the patient (d) (section 20.3). Agreeing (a) lets bias change her treatment. Silence (b) allows stigma to continue. Recording the comment as a behavioural concern (c) carries the bias into her record.

3. [CORE] Four hours after admission to the medical unit, which finding requires the nurse to notify the physician immediately?

a. New chest pain, temperature 38.5 °C and SpO2 falling to 91%

b. Pain decreasing from 9 to 5 out of 10 after the latest dose

c. Urine output of 40 mL/h

d. Mild nausea after drinking juice

Answer: a — New chest pain with fever and falling saturation suggests acute chest syndrome, an emergency that can progress to respiratory failure (a) (section 20.3). Falling pain scores (b) show a response to treatment. A urine output of 40 mL/h (c) is adequate. Mild nausea (d) needs attention but is not urgent.

4. [CORE] The nurse teaches Ms. Owusu to use an incentive spirometer. Which statement shows she understands its purpose?

a. "It will lower my pain without more medication."

b. "It tells me when my oxygen level is low."

c. "Deep breaths with it keep my lungs open and help prevent a chest problem."

d. "I only need to use it if I start coughing up sputum or feel short of breath."

Answer: c — Deep breathing with an incentive spirometer helps prevent acute chest syndrome in admitted patients, particularly those with chest or back pain (c) (section 20.3). It does not treat pain (a) or measure oxygen (b). It is used to prevent complications, not only once cough or breathlessness appears (d).

5. [CORE] A 46-year-old woman's results are hemoglobin 94 g/L, MCV 71 fL, RDW 18.5% and ferritin 6 µg/L. Which interpretation fits these results best?

a. Vitamin B12 deficiency
b. Anemia of inflammation
c. Iron deficiency anemia
d. Hemolytic anemia

Answer: c — Low hemoglobin with small cells, mixed cell sizes and very low ferritin is the pattern of iron deficiency anemia (c) (section 20.1, Table 20.1). B12 deficiency (a) causes large cells. Anemia of inflammation (b) has a normal or high ferritin. Hemolysis (d) usually gives normal or large cells with a high reticulocyte count, not a low ferritin.

6. [CORE] The nurse is assessing a patient with dark brown skin for anemia. Which approach is most appropriate?

a. Inspect the inner lower eyelids, mouth, nail beds and palms
b. Compare the colour of the patient's face with that of the nurse's own face
c. Rely on the pulse oximeter, because a normal saturation rules out anemia
d. Assume pallor cannot be assessed and skip this part of the examination

Answer: a — Pallor is easier to see where pigment does not hide colour, such as the conjunctiva, mouth, nail beds and palms (a) (section 20.2). Comparing with another person's face (b) is unreliable. Oxygen saturation (c) can be normal in severe anemia. Pallor can still be assessed (d), although no sign replaces a hemoglobin level.

7. [CORE] Which statement by a patient starting oral iron shows that teaching was effective?

a. "I'll take my iron with my morning coffee so I don't forget it."
b. "I'll take an extra tablet on days when I feel more tired than usual."
c. "I'll take my iron together with my calcium tablet."
d. "I'll take it with orange juice and wait before having tea."

Answer: d — Vitamin C helps iron absorption, and tea and coffee reduce it, so waiting 1 to 2 hours is advised (d) (section 20.2, Patient Education box). Coffee (a) and calcium (c) reduce absorption. Iron is taken exactly as prescribed; extra doses (b) add side effects and risk without faster benefit.

8. [CORE] A 72-year-old man with pernicious anemia has not received treatment for several months. Which findings does the nurse expect?

a. Spoon-shaped nails and a craving for ice
b. Numbness and tingling in the feet and an unsteady gait
c. Dark urine and yellow sclera
d. Bleeding gums and bruising

Answer: b — Vitamin B12 deficiency damages nerves, causing peripheral neuropathy and ataxia (b) (section 20.2). The findings in (a) are linked with iron deficiency, not B12 deficiency. Dark urine and jaundice (c) suggest hemolysis. Bleeding and bruising (d) suggest low platelets or a clotting problem.

9. [CORE] At 0300 the laboratory phones a hemoglobin of 66 g/L for a patient whose value was 92 g/L yesterday. The patient reports feeling light-headed. What should the nurse do first?

a. Assess the patient, including vital signs, and notify the prescriber at once
b. Record the value and report it at morning rounds
c. Ask the laboratory to repeat the test before telling anyone
d. Encourage oral fluids, document the value and recheck the hemoglobin in 6 hours

Answer: a — This is a critical value with a sharp fall and new symptoms, so the nurse assesses for bleeding and instability and notifies the prescriber promptly (a) (sections 20.1 and 20.2). Waiting for rounds (b), delaying for a repeat test (c) or waiting 6 hours (d) could allow ongoing bleeding to cause shock.

10. [CORE] An RPN is caring for a patient on a medical unit who has iron deficiency anemia and has been stable. The patient now has a heart rate of 124 beats/min, new chest discomfort and a black, sticky stool. Which action is most appropriate for the RPN?

a. Continue the care plan and document the findings for the next shift
b. Give the next scheduled dose of oral iron and recheck in an hour
c. Stay with the patient, check vital signs and consult the RN at once
d. Transfer care of the patient to an RN before doing any assessment

Answer: c — Every nurse who notices deterioration acts and escalates; the RPN consults the RN as the patient's needs change, under the authority, competence and context framework and employer policy (c) (Chapter 1, section 1.3; section 20.2). Documenting only (a) and giving iron (b) ignore signs of bleeding and cardiac strain. Handing off before assessing (d) delays care.

11. [CORE] A 68-year-old woman is newly diagnosed with iron deficiency anemia. She has no obvious source of bleeding. Which next step does the nurse expect the team to plan?

a. Oral iron only, with no further testing
b. A blood transfusion to bring her hemoglobin back into the normal range
c. A diet higher in red meat as the main treatment
d. Upper endoscopy and colonoscopy

Answer: d — In postmenopausal women and men, iron deficiency anemia calls for a search for gastrointestinal bleeding, including cancer (d) (section 20.2). Treating with iron alone (a) or diet (c) could let a cancer progress. A stable patient does not need transfusion to normal levels (b) (section 20.6).

12. [CORE] During an IV iron infusion, a patient develops facial flushing and chest tightness. Blood pressure is 128/80 mm Hg and SpO2 97%. What is the nurse's first action?

a. Increase the rate to finish the infusion quickly
b. Stop the infusion, stay with the patient, monitor closely and call the prescriber
c. Reassure the patient that this is expected and continue
d. Give an oral antihistamine and continue at the same rate

Answer: b — Any reaction during IV iron is treated as possible hypersensitivity; the nurse stops the infusion, monitors for progression to anaphylaxis and calls the prescriber (b) (section 20.2). Speeding up (a) or continuing (c) increases exposure. Giving a drug and continuing (d) needs a prescriber's order and ignores possible progression.

13. [CORE] Which factors increase a person's risk of vitamin B12 deficiency? Select all that apply.

a. Long-term metformin therapy
b. Heavy menstrual bleeding
c. Previous gastric surgery
d. A diet that includes red meat several times a week
e. Long-term use of a proton pump inhibitor
f. Regular use of an anti-inflammatory drug

Answer: a, c, e — Metformin (a), gastric surgery (c) and proton pump inhibitors (e) are linked with B12 deficiency (section 20.2). Heavy menstrual bleeding (b) and anti-inflammatory drugs (f), through gastrointestinal bleeding, cause iron loss. Red meat (d) is a source of B12.

14. [CORE] A patient with sickle cell disease is admitted with a pain crisis. Which finding most strongly suggests acute chest syndrome?

a. New cough and fever with an infiltrate on chest X-ray
b. Pain in both thighs rated 8 out of 10
c. Yellow sclera that the patient says are usual for him
d. Hemoglobin of 84 g/L, the same as his baseline

Answer: a — Acute chest syndrome is defined by a new infiltrate on chest X-ray with symptoms such as fever, cough or chest pain (a) (section 20.3). Limb pain (b) is typical of a vaso-occlusive crisis. Chronic jaundice (c) reflects ongoing hemolysis. A hemoglobin at baseline (d) is not a sign of acute chest syndrome.

15. [CORE] An adult with sickle cell disease calls the clinic to say he has a temperature of 38.7 °C. What should the nurse advise?

a. Take an antipyretic and call back if the fever lasts 3 days
b. Increase fluids and rest at home
c. Book the next available routine clinic appointment
d. Go to the emergency department now, because fever can mean a serious infection

Answer: d — Functional asplenia puts people with sickle cell disease at risk of overwhelming bloodstream infection; fever needs urgent assessment and antibiotics within 30 minutes of arrival (d) (section 20.3). Waiting (a, b, c) risks sepsis.

16. [CORE] A new parent asks what it means that their baby's newborn screen shows sickle cell trait. Which response is accurate?

a. "Your baby has a mild form of sickle cell disease and will need hydroxyurea."
b. "The trait will turn into the disease during adolescence."
c. "Your baby carries one sickle gene, generally does not have the disease and could pass the gene on later in life."
d. "Sickle cell trait occurs only in families of African ancestry."

Answer: c — Sickle cell trait means one hemoglobin S gene; carriers generally do not have the disease but can pass the gene on (c) (section 20.3). The trait is not a mild disease (a) and does not progress to disease (b). The trait occurs in all racial and ethnic groups (d).

17. [CORE] A patient with sickle cell disease is starting hydroxyurea. Which teaching point is correct?

a. Blood tests are needed only if symptoms of infection appear
b. Use reliable contraception; anyone handling the capsules wears gloves
c. Open the capsules and sprinkle the powder on food to make them easier to take
d. Stop the drug during each pain crisis

Answer: b — Hydroxyurea can harm a fetus and is handled as a hazardous drug (b) (section 20.2, Medications box). It suppresses the marrow, so regular blood counts are needed (a). Opening capsules (c) exposes people to the powder. Stopping during crises (d) is not advised; changes are made by the prescriber.

18. [RN] A patient has hemoglobin 98 g/L, MCV 114 fL and a low reticulocyte count. Which cause is most consistent with these findings?

a. Acute gastrointestinal bleeding
b. Iron deficiency
c. Hemolysis
d. Vitamin B12 or folate deficiency

Answer: d — Large cells with a low reticulocyte count point to impaired production from B12 or folate deficiency (d) (Going Deeper box). Acute bleeding (a) is normocytic with a reticulocyte rise once the marrow responds. Iron deficiency (b) causes small cells. Hemolysis (c) causes a high reticulocyte count.

19. [RN] A 30-year-old man has hemoglobin 122 g/L, MCV 64 fL, red blood cell count 6.1 × 10^{12}/L and ferritin 110 µg/L. What is the most appropriate interpretation?

a. Thalassemia trait is likely; iron is not indicated without proven deficiency
b. The pattern confirms iron deficiency, and the nurse expects oral iron to be ordered
c. The pattern suggests vitamin B12 deficiency
d. The pattern is normal, and no follow-up is needed

Answer: a — Very small cells with a high red cell count and normal ferritin suggest thalassemia trait (a) (Going Deeper box; section 20.3). The normal ferritin argues against iron deficiency (b), and giving iron without deficiency adds to iron load. B12 deficiency (c) causes large cells. An MCV of 64 fL is well below the reference range (d).

20. [RN] A patient with severe pernicious anemia starts cyanocobalamin injections. Which change in laboratory results does the nurse expect, and monitor for, in the first week?

a. A fall in the reticulocyte count and a rise in serum potassium
b. A rise in ferritin to above the reference range
c. A rise in the reticulocyte count within about 5 to 7 days, with a risk of low potassium
d. An immediate return of the MCV to normal

Answer: c — As red cell production restarts, reticulocytes rise within days and potassium can fall sharply, so it is monitored closely in the first 48 hours (c) (section 20.2; Going Deeper box). Reticulocytes rise rather than fall, and potassium falls rather than rises (a). B12 does not raise ferritin (b). The MCV normalizes gradually as new cells replace old ones (d).

Case: Diane Martel (Questions 21–26): Diane Martel, 62, is on a medical oncology unit with acute myeloid leukemia. Her hemoglobin is 66 g/L, and one unit of red cells is ordered. Ten minutes after the unit is started, she has chills and says, "My lower back really hurts." Her temperature has risen from 37.1 °C to 38.8 °C, her heart rate from 88 to 122, and her blood pressure has fallen from 128/76 to 92/54 mm Hg.

21. [CORE] Which findings are the most important cues that Diane may be having a serious transfusion reaction?

a. Her hemoglobin of 66 g/L, which was measured before the transfusion began

b. Her diagnosis of acute myeloid leukemia

c. Back pain with a falling blood pressure and rising heart rate

d. The order for a single unit of red cells rather than two units

Answer: c — New back pain, hypotension and tachycardia soon after a red cell unit starts point to a serious reaction, such as acute hemolysis or sepsis (section 20.6). The low hemoglobin was the reason for transfusion, not a reaction cue. Leukemia explains her anemia but not the sudden change. Ordering one unit is good practice and is not a cue.

22. [CORE] The nurse analyzes the cues. Which reaction best fits the combination of fever, back pain and hypotension within minutes of starting red cells?

a. Acute hemolytic transfusion reaction

b. Minor allergic reaction

c. Delayed hemolytic transfusion reaction

d. Febrile non-hemolytic reaction

Answer: a — Fever, chills, pain and hypotension early in a red cell transfusion fit an acute hemolytic reaction, usually from ABO incompatibility (section 20.6, Table 20.4). A minor allergic reaction causes hives and itching without hypotension. Delayed hemolysis occurs days to weeks later. A febrile non-hemolytic reaction causes fever and chills but not hypotension or back pain, so it cannot be assumed when serious signs are present.

23. [CORE] Which concern does the nurse place first?

a. Diane may become anxious about receiving any transfusions in the future.

b. Diane may have a life-threatening reaction that is affecting her circulation.

c. Diane's hemoglobin will not reach the target the prescriber set for today.

d. Diane's back pain may come from lying in bed.

Answer: b — Hypotension and tachycardia show that circulation is threatened, which comes first (section 20.6; Chapter 6). Anxiety matters but is not the priority. Reaching a hemoglobin target is less urgent than her safety. Back pain from positioning would not explain fever and hypotension.

24. [CORE] The nurse plans care. Which plan best addresses Diane's situation?

a. Slow the transfusion, give acetaminophen as ordered and recheck her vital signs in 1 hour

b. Finish the unit quickly so that the bag can be returned to the transfusion service with all of its tubing

c. Stop the transfusion, keep the vein open with 0.9% sodium chloride on new tubing and call for urgent help

d. Flush the existing line with dextrose 5% in water and then restart the same unit at a slower rate

Answer: c — Any suspected serious reaction requires stopping the transfusion, keeping IV access with saline through new tubing and calling for urgent help; the transfusion service is then notified (section 20.6). Slowing the unit continues the exposure. Finishing the unit gives more of a possibly incompatible product. Dextrose is never used with blood, and the unit must not be restarted.

25. [CORE] After stopping the transfusion and calling for help, what should the nurse do next?

a. Discard the bag and tubing in a biohazard container so that no one else is exposed to them.

b. Recheck Diane's band against the unit label, and keep the bag and tubing for the transfusion service.

c. Remove the IV catheter so that no more of the component can enter the vein.

d. Wait for the physician to arrive before taking another set of vital signs.

Answer: b — A clerical check of the patient and label can find an identification error, and the bag and tubing are returned for investigation (section 20.6). Discarding the bag destroys evidence. IV access must be kept for treatment. Vital signs are checked at least every 15 minutes without waiting.

26. [CORE] An hour later, Diane's first urine since the reaction is dark red-brown. How should the nurse interpret this finding?

a. It suggests ongoing hemolysis and must be reported now.

b. It shows that the reaction has resolved.

c. It is an expected finding after any red cell transfusion.

d. It means she needs more oral fluid only.

Answer: a — Dark urine after a suspected hemolytic reaction suggests hemoglobin in the urine and possible kidney injury, so it is reported at once (section 20.6, Table 20.4). It does not show resolution. It is not an expected finding after transfusion. Fluids may be part of treatment, but the finding needs urgent reporting, not only fluids.

27. [CORE] A patient has a platelet count of 18 × 10^9/L after chemotherapy. Which actions should the nurse include in the plan of care? Select all that apply.

a. Provide an extra-soft toothbrush.

b. Take the temperature rectally for accuracy.

c. Offer an electric razor for shaving.

d. Check with the prescriber before giving an intramuscular injection.

e. Encourage the patient to avoid straining at stool.

f. Give acetylsalicylic acid for a headache.

Answer: a, c, d, e — An extra-soft toothbrush, an electric razor, checking before intramuscular injections and avoiding straining all reduce bleeding (section 20.4). Rectal thermometers can injure the mucosa and are avoided. ASA weakens platelets, and a new headache in a patient with a low platelet count should be assessed and reported, not just treated.

28. [CORE] The nurse is assessing a patient with dark skin and a low platelet count for petechiae. Which approach is best?

a. Look for blue or purple bruising on the abdomen under the room's fluorescent light.

b. Rely on the trend in the platelet count instead of a full skin assessment.

c. Ask the patient whether the skin looks redder than usual.

d. Inspect the oral mucosa and conjunctiva in natural or indirect light.

Answer: d — Petechiae can be easier to see where there is less pigment, such as the mouth and conjunctiva, and natural or indirect light is preferred to fluorescent light (section 20.4). Bruises on darker skin may look darker rather than blue, and fluorescent light adds a bluish tint. The count does not show where the patient is bleeding. Redness can be hard to see on darker skin, and asking alone is not an assessment.

29. [CORE] A man with severe hemophilia A arrives with a warm, swollen, painful knee and a FactorFirst card. What is the nurse's priority?

a. Apply a heating pad to the knee to ease the pain and stiffness before anything else is done.

b. Help the patient move the knee through its full range several times to prevent stiffness.

c. Follow the card and notify the prescriber so factor VIII replacement starts without delay.

d. Give an intramuscular injection of an analgesic.

Answer: c — A joint bleed needs factor replacement as soon as it is suspected, and the FactorFirst card states the first emergency treatment (section 20.4). Heat is not part of first care for a joint bleed, which pairs prompt factor with rest, short periods of ice, compression and elevation. Moving a bleeding joint through its full range can worsen the bleed. An intramuscular injection risks a bleed into the muscle and does not treat the joint bleed.

30. [CORE] A patient with multiple myeloma has new confusion, constipation and extreme thirst. What should the nurse do first?

a. Encourage more dietary calcium to protect the bones.

b. Check the latest calcium result and report the findings promptly.

c. Reorient the patient and recheck in the morning.

d. Give a laxative for the constipation now and reassess the patient in 24 hours.

Answer: b — Confusion, constipation and thirst in myeloma are cues of hypercalcemia, which needs prompt reporting (section 20.5; Chapter 3). Extra calcium would worsen it. Reorienting alone delays care. A laxative treats only one symptom and misses the cause.

31. [CORE] A patient receiving treatment for leukemia has a low neutrophil count. Which action best protects the patient?

a. Teach the patient to report a fever right away and practise careful hand hygiene.

b. Encourage visits from family members who have colds, for emotional support.

c. Take the temperature only once a day to avoid disturbing rest.

d. Wait for a second high temperature before reporting the fever to the prescriber or team.

Answer: a — In neutropenia, infection can progress quickly, so fever is reported at once and hand hygiene is essential (section 20.5; Chapter 9). Visitors with colds expose the patient to infection. Once-daily temperatures may miss a fever. Waiting for a second fever delays emergency treatment.

32. [CORE] During the bedside check before a red cell transfusion, which action is correct?

a. Confirm the patient's identity using the room number, the bed number and the chart.

b. Complete the check with a second nurse at the nursing station to save time.

c. Read the patient's name aloud and accept a nod as confirmation.

d. Have the patient spell their name and give their birth date, and match these to the band and label.

Answer: d — Identifiers given by the patient where possible and matched to the band and label in the patient's presence prevent wrong-patient transfusion (section 20.6). Room and bed numbers are not identifiers. A check away from the bedside misses errors. A nod to a name read aloud can confirm the wrong person.

33. [CORE] Which solution may be infused through the same line as red blood cells?

a. Dextrose 5% in water

b. 0.9% sodium chloride

c. Ringer's lactate

d. An IV antibiotic

Answer: b — Sterile 0.9% sodium chloride is the compatible solution used to prime and flush a blood line (section 20.6). Dextrose 5% in water and Ringer's lactate are not used with red cells. Medications are not infused with blood components.

34. [CORE] A capable adult declines a red cell transfusion recommended for a hemoglobin of 68 g/L. Which response by the nurse is best?

a. "Can you tell me what you will and will not accept, so the team can talk with you about other options?"

b. "If you were family, you would want the blood."

c. "Your religion must be the reason, so I'll call your faith leader."

d. "You do not have a choice about this when your hemoglobin is this low."

Answer: a — A capable patient may refuse blood; the nurse explores what the patient will accept and supports a discussion of risks and alternatives, which is documented (section 20.6; Chapter 1, section 1.5). Option b pressures the patient. Option c assumes a reason. Option d is false and disrespects the patient's right to refuse.

35. [CORE] An RPN is caring for a patient whose red cell transfusion was started by an RN 20 minutes ago. The patient now has hives and is wheezing, and the throat feels tight. What should the RPN do first?

a. Slow the transfusion and wait for the RN to return from break.

b. Document the hives and recheck in 15 minutes.

c. Stop the transfusion, stay with the patient and call for urgent help.

d. Give the next medication due and then report.

Answer: c — Wheeze and throat tightness suggest anaphylaxis. Every nurse who notices a possible reaction stops the transfusion, stays with the patient and escalates, whoever started the unit (section 20.6, Scope in Practice box; Chapter 6). Slowing the unit and waiting delays care. Documenting alone ignores airway risk. Other tasks can wait.

36. [CORE] A patient with sepsis has new oozing from all IV sites, a falling platelet count and a blood pressure of 86/50 mm Hg. Which action should the nurse take first?

a. Apply pressure dressings to the IV sites and reassess at the end of the shift.

b. Ask the patient to stay in bed and avoid brushing the teeth.

c. Remove all IV catheters to stop the oozing and apply pressure to each site.

d. Activate the rapid response team, giving an SBAR report.

Answer: d — Bleeding from several sites with hypotension in sepsis suggests DIC and shock, which need urgent escalation (section 20.4; Chapter 6). Waiting until the end of the shift is unsafe. Bleeding precautions help but do not address shock. Removing IV access would prevent treatment.

37. [CORE] A stable, non-bleeding patient has a hemoglobin of 66 g/L, and two units of red cells are ordered. Which action reflects Canadian guidance?

a. Give both units back to back so the patient has fewer interruptions overnight.

b. Hold both units until the hemoglobin falls below 60 g/L on a repeat test.

c. Ask the prescriber whether one unit can be given and the patient reassessed before the second.

d. Give the second unit only if the first causes a reaction.

Answer: c — Choosing Wisely Canada advises a single red cell unit for stable, non-bleeding patients, with the patient and hemoglobin reassessed before any further unit (section 20.6). Giving both without reassessment increases the risk of overload. There is no rule to wait for 60 g/L; thresholds are individualized. A reaction is a reason to stop, not to give more.

38. [RN] A patient with septic shock has these results over 6 hours: platelets 140 × 10⁹/L, then 62 × 10⁹/L; fibrinogen 2.8 g/L, then 1.1 g/L; D-dimer rising; PT prolonged. How should the nurse interpret this pattern?

a. It suggests heparin-induced thrombocytopenia.

b. It suggests consumption of platelets and clotting factors consistent with DIC.

c. It is expected with fluid resuscitation alone.

d. It suggests immune thrombocytopenia.

Answer: b — Falling platelets and fibrinogen with a rising D-dimer and prolonged PT show consumption and fibrinolysis, the pattern of DIC (Going Deeper box, section 20.6). HIT lowers platelets after heparin exposure but does not consume fibrinogen. Dilution does not explain a rising D-dimer. ITP lowers platelets without this clotting pattern.

39. [RN] Which statement about the ISTH overt DIC score is accurate?

a. It is based on one test, the D-dimer, measured at a single point in time.

b. It replaces the need to find and treat the cause of DIC.

c. It is used to choose the dose of prothrombin complex concentrate for a bleeding patient.

d. It combines four common tests, and a total of 5 or more is consistent with overt DIC.

Answer: d — The score adds points for the platelet count, PT, fibrinogen and a fibrin-related marker, and a total of at least 5 is consistent with overt DIC (Going Deeper box, section 20.6). No single test diagnoses DIC. Treating the cause remains the most important step. PCC is contraindicated in DIC.

40. [RN] Two hours into a transfusion, a patient becomes short of breath with crackles. Which finding most supports TACO rather than TRALI?

a. Blood pressure 178/96 mm Hg and an elevated BNP

b. Temperature 38.6 °C and low blood pressure

c. No improvement after a diuretic

d. A normal BNP with a blood pressure of 84/50 mm Hg

Answer: a — A raised blood pressure and a raised BNP favour TACO (Going Deeper box, section 20.6). In TRALI, fever may be present, blood pressure may fall, and the response to diuretics and the BNP are inconsistent, so fever with hypotension (b), no improvement after a diuretic (c), and hypotension with a normal BNP (d) all point more toward TRALI.

References

Alberta Health Services. (2019, June 19). *Newborn screening now tests for sickle cell disease* [News release]. https://www.albertahealthservices.ca/news/Page15119.aspx

Alberta Health Services. (2023). *CBC and differential provincial reference intervals and critical values – Epic* (Form HE02-100, Rev. 3.00). https://www.albertahealthservices.ca/assets/wf/lab/if-lab-cbc-and-differential-provincial-reference-intervals-and-critical-values-epic.pdf

Alberta Precision Laboratories & DynaLIFE Medical Labs. (2021, March 22). *Provincial standardization of reference intervals, comments and available tests: Creatine kinase, ferritin, urine osmolality, total testosterone and the iron and TIBC panel* [Laboratory bulletin]. https://www.albertahealthservices.ca/assets/wf/lab/if-lab-hp-bulletin-provincial-standardization-of-reference-intervals-comments-and-available-tests-creatine-kinase-ferritin-urine-osmalality-total-testosterone-and-the-irone-and-tibc-panel.pdf

Alberta Precision Laboratories. (2019, July 2). *Activated partial thromboplastin time (PTT) reference interval adjustment* [Laboratory bulletin]. https://www.albertahealthservices.ca/assets/wf/lab/wf-lab-bulletin-activated-partial-thromboplastin-tim-ptt-reference-interval-adjustment.pdf

Alberta Precision Laboratories. (2020, June 15). *Changes to reference intervals of alanine aminotransferase, vitamin B12, ferritin, gamma glutamyl transferase, magnesium and urea* [Laboratory bulletin]. https://www.albertahealthservices.ca/assets/wf/lab/wf-apl-lab-bulletin-changes-reference-intervals-of-alanine-aminotransferase-vit-b12-ferritin-gamma-glutamyl-transferase-magnesium-urea.pdf

American Society of Hematology. (2019, December 10). *New clinical practice guidelines on immune thrombocytopenia released* [News release]. https://www.hematology.org/newsroom/press-releases/2019/new-clinical-practice-guidelines-on-immune-thrombocytopenia-released

Black, C., Brownlee, T., & Pasay, D. (2024). Describing and comparing patient factors associated with use of parenteral iron before and after implementation of an order set for parenteral iron (DECODE IRON). *Canadian Journal of Hospital Pharmacy, 77*(1), Article e3500. https://doi.org/10.4212/cjhp.3500

Bleeding Disorders Canada. (2024). *Hemophilia A and B*. https://bleedingdisorderscanada.ca/hemophilia-a-and-b/

Brenner, D. R., Gillis, J., Demers, A. A., Ellison, L. F., Ng, C., Zhang, S. X., Finley, C., Fitzgerald, N., Saint-Jacques, N., Shack, L., Turner, D., Urquhart, R., & Woods, R. R. (2026). Projected estimates of cancer in Canada in 2026. *CMAJ, 198*(14), E526–E534. https://doi.org/10.1503/cmaj.252152

Canadian Agency for Drugs and Technologies in Health. (2016). *CDR clinical review report: Deferiprone (Ferriprox)*. https://www.cda-amc.ca/sites/default/files/cdr/clinical/SR0448_Ferriprox_CL_Report.pdf

Canadian Cancer Society. (2022). *What is leukemia?* https://cancer.ca/en/cancer-information/cancer-types/leukemia/what-is-leukemia

Canadian Cancer Society. (2026a). *Hodgkin lymphoma statistics*. https://cancer.ca/en/cancer-information/cancer-types/hodgkin-lymphoma/statistics

Canadian Cancer Society. (2026b). *Leukemia statistics*. https://cancer.ca/en/cancer-information/cancer-types/leukemia/statistics

Canadian Cancer Society. (2026c). *Multiple myeloma statistics*. https://cancer.ca/en/cancer-information/cancer-types/multiple-myeloma/statistics

Canadian Cancer Society. (2026d). *Non-Hodgkin lymphoma statistics*. https://cancer.ca/en/cancer-information/cancer-types/non-hodgkin-lymphoma/statistics

Canadian Cancer Society. (n.d.-a). *Diagnosis of leukemia*. https://cancer.ca/en/cancer-information/cancer-types/leukemia/diagnosis

Canadian Cancer Society. (n.d.-b). *Low platelet count (thrombocytopenia)*. https://cancer.ca/en/treatments/side-effects/low-platelet-count

Canadian Cancer Society. (n.d.-c). *Signs and symptoms of multiple myeloma*. https://cancer.ca/en/cancer-information/cancer-types/multiple-myeloma/signs-and-symptoms

Canadian Cancer Society. (n.d.-d). *Signs and symptoms of non-Hodgkin lymphoma*. https://cancer.ca/en/cancer-information/cancer-types/non-hodgkin-lymphoma/signs-and-symptoms

Canadian Cancer Society. (n.d.-e). *Stem cell transplant*. https://cancer.ca/en/treatments/treatment-types/stem-cell-transplant

Canadian Haemoglobinopathy Association. (2014). *Consensus statement on the care of patients with sickle cell disease in Canada* [Draft] (M. Verhovsek & E. Simpson, Eds.). https://emergencymedicinecases.com/wp-content/uploads/filebase/pdf/Canadian%20Sickle%20Cell%20Guidelines%202014.pdf

Canadian Institute of Child Health. (n.d.). Specific conditions: Newborn screening for sickle cell disease. In *The health of Canada's children and youth: A CICH profile*. https://cichprofile.ca/module/2/section/4/page/specific-conditions-newborn-screening-for-sickle-cell-disease/

Canadian Society for Transfusion Medicine. (2026). *Twelve tests and treatments to question in transfusion medicine*. Choosing Wisely Canada. https://choosingwiselycanada.org/recommendation/transfusion-medicine/

Centers for Disease Control and Prevention. (2024). *About von Willebrand disease*. https://www.cdc.gov/von-willebrand/about/index.html

Chalco, J. P., Huicho, L., Alamo, C., Carreazo, N. Y., & Bada, C. A. (2005). Accuracy of clinical pallor in the diagnosis of anaemia in children: A meta-analysis. *BMC Pediatrics, 5*, Article 46. https://doi.org/10.1186/1471-2431-5-46

Chan, D., Kouyoumdjian, F., Athale, U., Pendergrast, J., & Verhovsek, M. (2020). Emergency department quality of care for sickle cell disease in Ontario, Canada: A population-based matched cohort study [Abstract]. *Blood, 136*(Suppl. 1), 38–39. https://doi.org/10.1182/blood-2020-143472

Cooper, M., Greene-Finestone, L., Lowell, H., Levesque, J., & Robinson, S. (2012). Iron sufficiency of Canadians. *Health Reports, 23*(4). Statistics Canada. https://www150.statcan.gc.ca/pub/82-003-x/2012004/article/11742-eng.htm

Duncan, J. (2020). Pre-transfusion testing. In G. Clarke & S. Chargé (Eds.), *Clinical guide to transfusion* (Chapter 8). Canadian Blood Services. https://profedu.blood.ca/en/transfusion/clinical-guide/pre-transfusion-testing

Eugia Pharma Inc. (2023). *Cyanocobalamin injection USP: Product monograph*. https://pdf.hres.ca/dpd_pm/00070787.PDF

Eugia Pharma Inc. (2024). *Eugia-Hydroxyurea (hydroxyurea capsules): Product monograph*. https://pdf.hres.ca/dpd_pm/00077491.PDF

Gabarin, N., & Yan, M. (2024). Vein to vein: A summary of the blood system in Canada. In A. Khandelwal & T. Abe (Eds.), *Clinical guide to transfusion* (Chapter 1). Canadian Blood Services. https://profedu.blood.ca/en/transfusion/clinical-guide/vein-vein-summary-blood-system-canada

Health Canada. (2024). *Summary basis of decision: Ferinject*. https://dhpp.hpfb-dgpsa.ca/review-documents/resource/SBD1725979957573

Health Canada. (2025). *Iron: A powerhouse nutrient for your health* [Infographic]. https://www.canada.ca/content/dam/hc-sc/documents/services/publications/food-nutrition/iron-powerhouse-nutrient-health/iron-infographic-eng.pdf

Jull, J., Sheppard, A. J., Hizaka, A., Inuit Medical Interpreter Team, Barton, G., Doering, P., Dorschner, D., Edgecombe, N., Ellis, M., Graham, I. D., Habash, M., Jodouin, G., Kilabuk, L., Koonoo, T., Roberts, C., & Mamisarvik Healing Centre Team. (2021). Experiences of Inuit in Canada who travel from remote settings for cancer care and impacts on decision making. *BMC Health Services Research, 21*, Article 328. https://doi.org/10.1186/s12913-021-06303-9

Ko, C. W., Siddique, S. M., Patel, A., Harris, A., Sultan, S., Altayar, O., & Falck-Ytter, Y. (2020). AGA clinical practice guidelines on the gastrointestinal evaluation of iron deficiency anemia. *Gastroenterology, 159*(3), 1085–1094. https://doi.org/10.1053/j.gastro.2020.06.046

Lafrance, C., Malcolmson, C., Ning, S., Seftel, M., Gupta, A., & Anani, W. (2025). Platelet transfusion, alloimmunization and management of platelet refractoriness. In A. Khandelwal & K. Brooks (Eds.), *Clinical guide to transfusion* (Chapter 18). Canadian Blood Services. https://profedu.blood.ca/en/transfusion/clinical-guide/platelet-transfusion-alloimmunization-and-management-platelet

Laureano, M., Khandelwal, A., & Yan, M. (2022). Transfusion reactions. In A. Khandelwal & T. Abe (Eds.), *Clinical guide to transfusion* (Chapter 10). Canadian Blood Services. https://profedu.blood.ca/en/transfusion/clinical-guide/transfusion-reactions

Neunert, C., Terrell, D. R., Arnold, D. M., Buchanan, G., Cines, D. B., Cooper, N., Cuker, A., Despotovic, J. M., George, J. N., Grace, R. F., Kühne, T., Kuter, D. J., Lim, W., McCrae, K. R., Pruitt, B., Shimanek, H., & Vesely, S. K. (2019). American Society of Hematology 2019 guidelines for immune thrombocytopenia. *Blood Advances, 3*(23), 3829–3866. https://doi.org/10.1182/bloodadvances.2019000966

North American Association of Central Cancer Registries. (2025). *SSDI manual: B symptoms* (Version 3.3). https://apps.naaccr.org/ssdi/input/lymphoma/b_symptoms/

O'Reilly, C. (2020). Blood administration. In G. Clarke & S. Chargé (Eds.), *Clinical guide to transfusion* (Chapter 9). Canadian Blood Services. https://profedu.blood.ca/en/transfusion/clinical-guide/blood-administration

Ontario Health. (2023). *Sickle cell disease: Care for people of all ages* [Quality standard]. https://ontariohealth.ca/content/dam/ontariohealth/documents/filter-list/qs/qs-sickle-cell-disease-quality-standard-en.pdf

Pastore, Y. D., Robitaille, N., & Naessens, V. (2017). A 15-year-old boy with sickle cell disease, chest pain and respiratory distress. *CMAJ, 189*(49), E1529–E1530. https://doi.org/10.1503/cmaj.170526

Patel, H., & McGuirk, R. (2025). Vitamin B12 deficiency: Common questions and answers. *American Family Physician, 112*(3), 294–300. https://www.aafp.org/pubs/afp/issues/2025/0900/vitamin-b12-deficiency.html

Patel, K. V., & Guralnik, J. M. (2009). Prognostic implications of anemia in older adults. *Haematologica, 94*(1), 1–2. https://doi.org/10.3324/haematol.2008.001289

Phillips, J., & Henderson, A. C. (2018). Hemolytic anemia: Evaluation and differential diagnosis. *American Family Physician, 98*(6), 354–361. https://www.aafp.org/pubs/afp/issues/2018/0915/p354.html

Poon, M. C., Goodyear, M. D., Rydz, N., & Lee, A. (2022). Hemostatic disorders and hereditary angioedema. In *Clinical guide to transfusion* (Chapter 17). Canadian Blood Services. https://profedu.blood.ca/en/transfusion/clinical-guide/hemostatic-disorders-and-hereditary-angioedema

Popescu, N. I., Lupu, C., & Lupu, F. (2022). Disseminated intravascular coagulation and its immune mechanisms. *Blood, 139*(13), 1973–1986. https://doi.org/10.1182/blood.2020007208

Public Health Agency of Canada. (2026). Immunization of persons with chronic diseases. In *Canadian immunization guide* (Part 3). https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-3-vaccination-specific-populations/page-7-immunization-persons-with-chronic-diseases.html

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Rotin, L., & Mack, J. (2025). Blood components. In A. Khandelwal & T. Abe (Eds.), *Clinical guide to transfusion* (Chapter 2). Canadian Blood Services. https://profedu.blood.ca/en/transfusion/clinical-guide/blood-components

Rutledge Harding, S., Cowan, J., & Jennings, S. (2024). Immunoglobulin products. In A. Khandelwal & T. Abe (Eds.), *Clinical guide to transfusion* (Chapter 4). Canadian Blood Services. https://profedu.blood.ca/en/transfusion/clinical-guide/immunoglobulin-products

Shared Health. (2024). *Guideline 7: Transfusion reaction: Identification, management and reporting*. In *Manitoba transfusion best practice resource manual 2024*. https://healthproviders.sharedhealthmb.ca/files/mtbprm-guideline-7.pdf

Srivastava, A., Santagostino, E., Dougall, A., Kitchen, S., Sutherland, M., Pipe, S. W., Carcao, M., Mahlangu, J., Ragni, M. V., Windyga, J., Llinás, A., Goddard, N. J., Mohan, R., Poonnoose, P. M., Feldman, B. M., Lewis, S. Z., van den Berg, H. M., Pierce, G. F., & WFH Guidelines for the Management of Hemophilia panelists and co-authors. (2020). WFH guidelines for the management of hemophilia, 3rd edition. *Haemophilia, 26*(Suppl. 6), 1–158. https://doi.org/10.1111/hae.14046

Trudeau, J. D., Dawe, P., & Shih, A. W. (2021). Massive hemorrhage and emergency transfusion. In G. Clarke & S. Chargé (Eds.), *Clinical guide to transfusion* (Chapter 11). Canadian Blood Services. https://profedu.blood.ca/en/transfusion/clinical-guide/massive-hemorrhage-and-emergency-transfusion

Weiss, G., Ganz, T., & Goodnough, L. T. (2019). Anemia of inflammation. *Blood, 133*(1), 40–50. https://doi.org/10.1182/blood-2018-06-856500

Yan, M. (2020). *A guide to reporting adverse transfusion reactions*. Canadian Blood Services. https://profedu.blood.ca/en/node/484

Young, N. S. (2018). Aplastic anemia. *New England Journal of Medicine, 379*(17), 1643–1656. https://doi.org/10.1056/NEJMra1413485

21 Immunity, Allergy and HIV

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain innate and adaptive immunity, and interpret immune-related tests (white cell differential, CD4 count, HIV viral load).
2. Distinguish the four types of hypersensitivity, and take and document an accurate allergy history, including penicillin allergy labels.
3. Recognize severe drug and allergic reactions on a range of skin tones, and escalate them.
4. Care for immunocompromised adults, including atypical signs of infection and cautions with live vaccines.
5. Explain HIV transmission, testing, PrEP, PEP and U=U, and offer testing in a non-stigmatizing way.
6. Support people living with HIV through antiretroviral therapy, adherence, monitoring and prevention of opportunistic infections, with a distinctions-based, strengths-based lens.
7. Describe autoimmunity, and give adult vaccines safely under the Canadian Immunization Guide: screening, consent, hesitancy conversations and reporting adverse events following immunization.
8. Distinguish RN and RPN roles in immunization and HIV care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 6	Clinician; Scholar	Foundations of Practice
5, 6, 7	Educator; Advocate	Foundations of Practice; Ethical Practice
8	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

Every adult unit cares for people whose immune systems shape the plan of care. An allergy entry sits at the top of almost every medication record. A wrong or vague entry can do as much harm as a missing one: it can steer a patient away from the best antibiotic or fail to warn the next prescriber about a reaction that must never recur. Many patients also take drugs that weaken immunity, such as corticosteroids, transplant medicines, biologic therapies and chemotherapy. In these patients, infection can start quietly and progress quickly, so the nurse watches for small changes. People living with human immunodeficiency virus (HIV) who take effective antiretroviral therapy (ART) come to hospital for the same reasons as anyone else, and they deserve care that is skilled and free of stigma (section 21.5). Adults also need vaccines throughout life, and screening for, giving and documenting them is nursing work.

This chapter begins with a focused review of the immune system, the immune tests nurses see most often and the way immunity changes with age (section 21.1). Section 21.2 explains the four types of hypersensitivity and the everyday skills that prevent allergic harm: taking and documenting an allergy history, understanding penicillin allergy labels, caring for people with latex allergy, recognizing angioedema and severe skin reactions, and preventing anaphylaxis. Section 21.3 covers immunodeficiency and the care of adults whose defences are weakened. The rest of the chapter turns to HIV, from testing and prevention to living well on treatment (sections 21.4 and 21.5), and then to autoimmunity and adult immunization (section 21.6).

The chapter builds on earlier ones. Inflammation, infection prevention and control (IPAC) and sepsis are taught in Chapter 4. The recognition and emergency treatment of anaphylaxis, including the epinephrine dose, are taught in Chapter 6, section 6.5. Cancer treatment and neutropenia are covered in Chapter 9, respiratory vaccines in Chapter 13, and blood products and immune globulin in Chapter 20.

21.1 The Immune System: A Focused Review

Innate and Adaptive Immunity

The **immune system** protects the body from microbes, toxins and abnormal cells. It works in two connected layers that share information.

Innate immunity is the defence a person is born with. It acts within minutes to hours and responds in the same way every time it meets a threat, because it has no memory (Marshall et al., 2018). Its parts include:

- **Barriers:** intact skin and mucous membranes, along with body temperature, acidity and chemical substances that make tissues hostile to microbes.
- **Phagocytes:** cells that engulf and destroy microbes. Neutrophils arrive first and live only briefly. Macrophages can persist in tissues for months or years and show fragments of what they have eaten to T cells.
- **Complement:** a chain of blood proteins that coats microbes so phagocytes can take them up, and that can kill some microbes and infected cells directly (Marshall et al., 2018).

Inflammation, the innate response to injury and infection, is taught in Chapter 4, section 4.1.

Adaptive immunity is slower to start but precise. It responds to an **antigen**, any molecule the immune system can recognize as a target, and each response is aimed at one antigen. It needs time to reach full strength the first time, and it remembers what it has met. Its main cells are two kinds of lymphocyte: B cells and T cells (Marshall et al., 2018; Figure 21.1).

When a B cell is activated, it matures into a plasma cell that secretes **antibodies** (immunoglobulins), proteins that bind one antigen. There are five classes (Marshall et al., 2018):

- **IgG:** the main antibody when the body meets an antigen for the second time; the only class that crosses the placenta; it neutralizes toxins and viruses and helps phagocytes and complement.
- **IgM:** the first antibody produced when the body meets a new antigen.
- **IgA:** the guard of mucous membranes, such as those of the airway and gut, where it blocks microbes and toxins.
- **IgE:** the antibody of allergic reactions, which also takes part in defence against parasites.
- **IgD:** an antibody whose role is still not well understood.

T cells do not make antibodies. **CD4 T cells**, also called helper T cells, direct the immune response by releasing signalling proteins called cytokines that switch on other cells, including B cells and macrophages. **CD8 T cells**, or cytotoxic T cells, kill cells infected with viruses and some tumour cells (Marshall et al., 2018). HIV infects and depletes CD4 T cells, which is why their number is followed closely in people living with HIV (section 21.5).



Figure 21.1 The lymphatic system. Lymphocytes are made in the bone marrow, T cells mature in the thymus, and both gather in the lymph nodes, spleen and tonsils, where they meet antigens carried in lymph and blood. (credit: Figure 21.2, "Anatomy of the Lymphatic System," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

The defining feature of adaptive immunity is memory. After an infection clears, most of the responding cells die, but a small number of memory B and T cells remain. If the same antigen returns, these cells produce a faster and more effective response (Marshall et al., 2018). Vaccines use this principle: they create memory without the illness.

A person can gain immunity in two ways:

- **Active immunity:** the body makes its own antibodies and memory cells. It is natural after an infection and artificial after a vaccine. It takes time to develop but can last.
- **Passive immunity:** ready-made antibodies come from someone else. It is natural when a pregnant person's IgG crosses the placenta and artificial when immune globulin is injected or infused, as with intravenous immune globulin (IVIG) (Chapter 20). It works at once, which helps when there is no time to wait for a vaccine response, but it is temporary because no memory cells are made (Marshall et al., 2018).

Immune Tests the Nurse Sees

Several tests reflect immune function. Reference ranges vary by laboratory, so the nurse reads each result against the range on the patient's own report.



Figure 21.2 Skin prick testing on the forearms. Each pen mark labels one allergen, and a raised, red wheal at a site suggests sensitization to that allergen; redness is harder to judge on darker skin. A positive test is interpreted with the history.

- **White blood cell count and differential:** the first look at immune cells. Ranges and the meaning of high and low counts are taught in section 20.1. The differential includes the absolute lymphocyte count, which the nurse reads alongside the patient's diagnosis, medications and trend.
- **Serum immunoglobulin levels:** IgG, IgA and IgM are measured when an antibody deficiency is suspected, for example in an adult with repeated sinus infections and pneumonias (McCusker et al., 2018).
- **CD4 count:** the number of CD4 T cells in the blood, the key measure of immune health in HIV (section 21.5). Treatment guidelines and this chapter give it in cells per microlitre (cells/µL). Some laboratories print the SI equivalent in × 10^9/L instead; the two express the same quantity, so 200 cells/µL equals 0.2 × 10^9/L.
- **HIV viral load:** the amount of HIV genetic material in the blood, reported in copies per millilitre (copies/mL) (section 21.5).
- **Allergy tests:** allergists confirm an allergy suspected from the history with skin prick testing (Figure 21.2), in which a tiny amount of allergen is introduced through a light prick and the skin is watched for a raised wheal, or with a blood test for allergen-specific IgE. Skin testing needs a skilled tester, carries some risk, and can be affected by factors that include skin colour. The blood test is a safe alternative that can screen many allergens at once (Ellis et al., 2024). A positive test shows only that IgE is present, so results are always read together with the history.

The Aging Immune System

Immunosenescence is the natural, gradual decline in immune function that comes with age (National Advisory Committee on Immunization [NACI], 2018). It has three practical effects for nurses.

First, older adults are more likely to develop some infections. Shingles is the clearest example. After chickenpox, the varicella-zoster virus (VZV) stays in the body in an inactive state. As cell-mediated immunity weakens with age or immune suppression, the virus can reactivate as **herpes zoster** (shingles) (NACI, 2018; Figure 21.3). Shingles is more common in older adults and in people who are immunocompromised, and its estimated lifetime risk in the general Canadian population reaches up to 30% (Krishnan et al., 2026).

Second, infection may not look the way students expect. Fever can be low or absent, and the first sign may be new confusion, a fall or a loss of appetite. This atypical presentation is taught in Chapter 4, and its link with delirium in Chapter 8.

Third, some vaccines work less well as people age, which is why certain vaccines are designed with older adults in mind. NACI found that the effectiveness of the older live zoster vaccine falls with age and is significantly lower in adults over 70 than in those aged 50 to 59. The non-live **recombinant zoster vaccine (RZV)** stays more effective across all age groups (NACI, 2018). NACI recommends RZV for adults aged 50 and older without contraindications (NACI, 2018) and two doses for adults aged 18 and older who are, or will be, immunocompromised (Krishnan et al., 2026). Some influenza vaccines are also designed for older adults (Chapter 13).

Figure 21.3 Herpes zoster (shingles): clustered red papules and vesicles in a band that follows one or two dermatomes on one side of the trunk. (credit: CDC/K.L. Herrmann, Public Health Image Library, public domain)

GOING DEEPER

Inside a Type I Reaction

Required for RN students; optional for PN students.

A type I (immediate) reaction needs two meetings with the allergen. At the first, called **sensitization**, helper T cells of a type that favours allergy steer B cells to make IgE against the allergen. The IgE attaches to receptors on mast cells in tissues and on basophils in the blood. The person has no symptoms, but these cells are now primed (Marshall et al., 2018).

At the next exposure, the allergen binds neighbouring IgE molecules on the cell surface and links them (cross-linking). Within minutes the cell releases histamine, leukotrienes and prostaglandins (Marshall et al., 2018), which widen blood vessels, make capillaries leak, tighten airway muscle and cause itch. Symptoms can also return after the first episode has fully settled. When they come back within 48 hours, the reaction is called biphasic anaphylaxis; in a meta-analysis of 2,890 adults, a median of 6.5% had it (Golden et al., 2024).

Mast cells also release the enzyme **tryptase**. A 2023 practice parameter suggests drawing an acute serum tryptase as early as possible, ideally within 2 hours after symptoms begin, and a later baseline level for comparison. A rise of at least 20% plus 2 µg/L (2 ng/mL) above baseline supports systemic mast cell activation (Golden et al., 2024), but a normal result does not rule out anaphylaxis (Warrington et al., 2018). The nurse records when symptoms began and when the sample was drawn.

21.2 Hypersensitivity and Allergy

Hypersensitivity is an excessive or misdirected immune response that damages the body's own tissues. An **allergy** is hypersensitivity to a substance harmless to most people, such as a food, pollen or drug. Drug allergy is unpredictable and occurs at ordinary doses (Warrington et al., 2018).

Four Types of Hypersensitivity

Hypersensitivity reactions are grouped into four types by mechanism (Table 21.1) (Marshall et al., 2018):

- **Type I (immediate):** IgE on mast cells and basophils triggers a reaction within minutes, as in hives, allergic rhinitis and anaphylaxis.
- **Type II:** IgG or IgM binds the person's own cells, and complement destroys them, as in a hemolytic transfusion reaction (section 20.6).
- **Type III:** antibody–antigen clumps called immune complexes settle in tissues and inflame them over days to weeks, as in serum sickness and lupus (Chapter 34).
- **Type IV (delayed):** T cells and macrophages, not antibodies, cause inflammation 2 or more days after exposure, as in contact dermatitis and the tuberculin skin test reaction (Chapter 13). Many delayed drug rashes, including the severe reactions later in this section, are T cell-mediated (Warrington et al., 2018).

Table 21.1 The four types of hypersensitivity reaction (Marshall et al., 2018; Warrington et al., 2018)

Type	What happens	Usual timing	Examples	Nursing focus
Type I: immediate, IgE-mediated	IgE on mast cells and basophils binds the allergen; the cells release histamine and other mediators	Minutes, sometimes up to a few hours	Anaphylaxis, hives, allergic rhinitis, food, insect sting and some drug allergies	Check allergies before every drug and food; recognize anaphylaxis early and act (Chapter 6)
Type II: antibody against cells	IgG or IgM binds the person's own cells; complement destroys them	Hours	Hemolytic transfusion reaction, autoimmune hemolytic anemia, immune thrombocytopenia	Follow transfusion checks; stop the transfusion and report a reaction (section 20.6); watch blood counts
Type III: immune complex	Antibody-antigen clumps deposit in tissues and trigger inflammation	Days to weeks	Serum sickness, systemic lupus erythematosus	Assess joints, skin and kidney function; report new rash, fever or joint pain
Type IV: delayed, T cell-mediated	T cells and macrophages cause inflammation without antibodies	2 days or more; severe drug reactions can take weeks	Contact dermatitis, tuberculin skin test reaction, delayed drug rashes, including the severe reactions described later in this section	Ask about recent new drugs; inspect skin and mucous membranes; report promptly

Taking and Documenting an Allergy History

An accurate allergy history starts with three distinctions:

- **Allergy:** an immune-mediated reaction, such as hives, swelling, wheeze or anaphylaxis.
- **Drug intolerance:** an unwanted drug effect at a low, sometimes below-therapeutic, dose that is not immune-mediated (Warrington et al., 2018).
- **Side effect:** a known effect of a drug at usual doses. Nausea, diarrhea, stomach pain and headache with an antibiotic are common side effects, not allergic reactions (Ontario Medical Association [OMA] Section on Allergy, 2025).

The nurse asks open questions and records the substance by generic name (and brand, if known) without abbreviations; what happened, in detail; its timing in relation to the dose; its severity and treatment; and when it occurred and whether the drug has been taken since (Institute for Safe Medication Practices Canada [ISMP Canada], 2016; Warrington et al., 2018).

ISMP Canada counts death or serious harm from giving a drug to which a patient's allergy was already known, or from failing to ask about allergies, as a "never event." In the incidents it reviewed, the earlier reaction was already on file but was not flagged or was lost between paper and electronic records. It recommends confirming the allergy record whenever a history is taken and at every transition in care (ISMP Canada, 2016). The nurse also checks allergy status before any new drug, applies an allergy band where employer policy requires one and documents according to the Documentation standard (Chapter 1).

CLINICAL SAFETY

The Allergy Label

An allergy label can harm a patient in two directions. A missing or vague entry, such as "antibiotics" or "sulfa?", leaves the next nurse unable to protect the patient. An entry that records a side effect as an allergy can deny the patient the safest and most effective drug for years (Saravanabavan et al., 2023).

A useful entry names the exact drug, describes the reaction, states when it happened and how long after the dose, records its severity and treatment, and notes any later doses that were tolerated (ISMP Canada, 2016; Warrington et al., 2018). For example: "Amoxicillin, 2019: itchy raised rash on trunk 2 hours after first dose, treated with an oral antihistamine; no breathing problems." That entry tells the team far more than "penicillin allergy."

The nurse checks the allergy record at every handover, at every transfer between units or facilities, and before every first dose of a drug. If a patient's story does not match the record, the nurse reports the difference to the prescriber or pharmacist. The nurse never removes or changes a label alone, but follows the employer's process, so that the reason for the change stays visible to every clinician (ISMP Canada, 2016).

Penicillin Allergy Labels

Penicillin is the most frequently reported drug allergy, affecting about 10% of patients, yet more than 80% of people who report it have a negative skin test, and about 90% of adult inpatients tolerate penicillin after evaluation (Warrington et al., 2018). In five Vancouver hospitals, delabelling programs removed the label from 697 of 711 patients (98.0%) (Saravanabavan et al., 2023).

A false label has real costs: less effective antibiotic choices, surgical site infections and infections with resistant organisms (Saravanabavan et al., 2023). In a large UK primary care cohort, adults with a documented penicillin allergy had a 69% higher risk of methicillin-resistant *Staphylococcus aureus* (MRSA) and a 26% higher risk of *Clostridioides difficile* infection than matched adults, partly because they received more alternative antibiotics (Blumenthal et al., 2018; see Chapter 4 on stewardship).

Delabelling is the removal of an inaccurate allergy label after the history is reviewed and, when needed, testing is done. A short scoring tool, PEN-FAST, sorts histories by risk; a score below 3 means low risk (Trubiano et al., 2020). Some histories, such as common side effects alone, need no testing. Some patients go directly to an oral challenge (a test dose given while a clinician observes), while others need skin testing first, and people with severe past reactions see an allergist (OMA Section on Allergy, 2025).

Testing and challenge are prescriber or allergist decisions. The nurse takes the precise history that makes delabelling possible, monitors the patient during a challenge as ordered, documents the outcome and teaches the patient that the label is gone and why.

Latex Allergy

Latex allergy is an allergic reaction to natural rubber latex, found in some gloves and other products. People at higher risk include health care and laboratory workers, people who have had many surgeries (such as 10 or more), and people allergic to certain foods, including banana, avocado, kiwi, passion fruit and chestnut (Canadian Centre for Occupational Health and Safety [CCOHS], 2023). Reactions range from dry, itchy, irritated skin, which is not an allergy, to a delayed contact rash (type IV) and immediate hives, wheeze, swelling or anaphylaxis (type I) (CCOHS, 2023; Marshall et al., 2018). The nurse asks about latex on admission and before every procedure, uses non-latex products, informs the perioperative team (Chapter 7) and follows the employer's latex-safe care policy.

Angioedema

Angioedema is swelling of the deeper layers of the skin or the lining of the mouth, throat or gut. It has two main mechanisms (Kanani et al., 2018):

- **Histamine-mediated angioedema** is often allergic and often comes with hives (urticaria): itchy, raised wheals with pale centres, each of which usually fades within about 24 hours (Figure 6.2).
- **Bradykinin-mediated angioedema** is driven by the peptide bradykinin, and hives are typically absent. It may be acquired, caused by a drug or inherited: **hereditary angioedema** is a rare inherited deficiency or dysfunction of the C1 inhibitor protein.

ACE inhibitor angioedema occurs in about 0.1% to 6% of people taking angiotensin-converting enzyme (ACE) inhibitors (Chapters 18 and 19). Most cases appear in the first week, but up to one-third appear months to years after the drug was started. The

drug is stopped in anyone who develops angioedema, and swelling can recur for about a month afterward (Kanani et al., 2018). Histamine is not directly involved in hereditary and acquired angioedema, so those forms do not respond to antihistamines or corticosteroids (Kanani et al., 2018). ACE inhibitor angioedema is also bradykinin-driven, and it is suspected in anyone taking an ACE inhibitor who develops angioedema without hives (Kanani et al., 2018). An emergency medicine practice statement found that epinephrine, antihistamines and corticosteroids have not been shown to help in ACE inhibitor angioedema, although they may be tried (Rosenbaum et al., 2020), so the nurse cannot count on the usual allergy drugs to reverse it.

Swelling of the larynx can quickly cause fatal asphyxiation (Kanani et al., 2018). A swollen tongue or lips, a changed voice, trouble swallowing, drooling or noisy breathing is an emergency: the nurse stays with the patient, calls the rapid response team at once (Chapter 6) and later documents the reaction.

On darker skin, the redness of hives can be hard to see because melanin masks it (Akinbisehin et al., 2026). The nurse looks for raised wheals in good light, feels for warmth, asks about itch and asks whether the face or lips look different from usual.

Severe Cutaneous Adverse Reactions

Severe cutaneous adverse reactions (SCARs) are rare but deadly delayed drug reactions.

Stevens-Johnson syndrome (SJS) and **toxic epidermal necrolysis (TEN)** are one disease at different extents: the epidermis dies and separates from the layer beneath. Detachment of less than 10% of the body surface is SJS, more than 30% is TEN, and the range between is an overlap. The reaction usually begins within 4 weeks of starting the drug (Akinbisehin et al., 2026). Fever, sore throat, fatigue and sore, red eyes come early; a rash then spreads and may blister, and the mouth, eyes and other mucous membranes ulcerate (Warrington et al., 2018). The eyes are involved in up to 75% of patients; mortality reaches 30%. High-risk drugs include allopurinol, carbamazepine, lamotrigine, nevirapine and sulfonamide antibiotics (Akinbisehin et al., 2026).

Drug reaction with eosinophilia and systemic symptoms (DRESS) usually develops 2 to 6 weeks after a drug is started. It brings a widespread rash, fever, swollen lymph nodes, facial and ear swelling, a high eosinophil count and involvement of organs such as the liver, kidneys and lungs; mortality reaches 10% (Akinbisehin et al., 2026). Anticonvulsants, sulfonamides and allopurinol are common causes, and symptoms can persist for weeks after the drug is stopped (Warrington et al., 2018).

On darker skin, early SJS/TEN lesions may look darker and less distinct rather than red, and mouth or eye involvement may be the first clear sign. A DRESS rash may look violet or darker than the surrounding skin (Akinbisehin et al., 2026). The nurse inspects the mouth, eyes and skin in good light and does not wait for redness.

Stopping the culprit drug is the most effective treatment (Warrington et al., 2018), but that decision belongs to the prescriber. The nurse reports a new rash with fever or mucosal sores at once, holds the next dose under employer policy until the prescriber assesses the patient, and escalates if the prescriber cannot be reached. A UK national guideline advises that adults who have lost epidermis over more than 10% of the body surface be moved promptly to a burn centre or an intensive care unit (ICU) experienced in caring for SJS/TEN (Creamer et al., 2016). The reaction is documented in detail as an allergy, and the patient is referred to an allergist (Warrington et al., 2018).

CLINICAL JUDGMENT

A New Rash on Day 9

Names and details are fictional; this is a composite story.

Mr. Daniel Osei, 61, is on a medical unit after a stroke. Carbamazepine was started 9 days ago for new seizures. At 0700 he tells the registered practical nurse (RPN) his mouth is too sore to eat and his eyes feel "full of sand." He has dark brown skin.

- **Recognize cues:** Temperature 38.7 °C, heart rate 112 beats/min, blood pressure 116/70 mm Hg, respiratory rate 20 breaths/min, oxygen saturation (SpO2) 96% on room air. Crusted lips, ulcers inside both cheeks, watery red eyes. Dusky, grey-purple patches on his chest and back, two with thin blisters. He says the skin "burns."
- **Analyze cues:** A new drug started 9 days ago, fever, mucosal ulcers, eye involvement and blistering skin fit a severe cutaneous adverse reaction. Blisters mean the epidermis is separating.
- **Prioritize hypotheses:** SJS/TEN is the most urgent possibility; infection and sepsis must also be considered. Skin loss threatens fluid balance, infection and his eyes.

- **Generate solutions:** Hold the 0800 carbamazepine dose under hospital policy and report immediately; protect the skin; keep him drinking if he can; prepare for urgent assessment and possible transfer.
- **Take action:** The RPN notifies the registered nurse (RN); they assess him together, and the RN calls the physician using SBAR (Situation, Background, Assessment, Recommendation; Chapter 6). The physician stops carbamazepine, orders bloodwork and consults dermatology and ophthalmology. The RPN documents findings, times and the held dose, and adds a detailed allergy entry.
- **Evaluate outcomes:** The nurses reassess skin, mouth, eyes, vital signs, intake and output at least hourly, measure any spread of blisters and report changes at once. By evening he is transferred to a specialized unit.

Preventing Anaphylaxis

The recognition and emergency treatment of anaphylaxis, including the adult epinephrine dose, are taught in Chapter 6, section 6.5; this section covers prevention.

The most frequent triggers are drugs, foods and insect venom; others seen in hospital include antiseptics, latex and contrast media (Cardona et al., 2020). The nurse checks the allergy record before every drug, blood product, contrast study and meal tray, asks the patient again when anything is new, and follows employer policy on observation after first doses and after vaccines (section 21.6).

Only about half of people who have had anaphylaxis are referred to an allergist, although referral identifies the cause and teaches self-management (Cardona et al., 2020), so the nurse advocates for it. The Canadian EpiPen monograph states that patients are prescribed two autoinjectors (Figure 6.3 shows how to hold one), should carry them at all times and should wear medical identification (Mylan Specialty, 2024). A written anaphylaxis emergency plan lists symptoms, the steps to take and where the device is kept (Association des allergologues et immunologues du Québec [AAIQ], 2020). As of October 2026, EpiPen autoinjectors and an epinephrine nasal spray (neffy) are marketed in Canada; Allerject and Emerade are no longer marketed (Health Canada, n.d.-b).

PATIENT EDUCATION

Carrying and Using an Epinephrine Autoinjector

The nurse teaches the patient, and family if the patient wishes, with a trainer device and the instructions for the patient's own product:

- **Know the signs.** Hives or swelling of the face, lips or tongue; a cough, wheeze, hoarse voice, throat tightness or trouble breathing or swallowing; vomiting or cramps; or feeling faint, dizzy or a sense that something terrible is happening (AAIQ, 2020).
- **Use it first.** Give the epinephrine as soon as a known or suspected reaction begins, then call 9-1-1 and say it is a life-threatening allergic reaction (AAIQ, 2020).
- **Where.** Inject into the outer thigh, through clothing if needed. For EpiPen, hold it firmly in place for 3 seconds. Never inject into the buttock (Mylan Specialty, 2024).
- **Second dose.** If symptoms do not improve, a second dose may be given once 5 to 15 minutes have passed (Mylan Specialty, 2024).
- **Go to hospital,** ideally by ambulance, even if you feel better, because symptoms can return (AAIQ, 2020).
- **Storage.** Keep it at room temperature, protected from light; do not refrigerate or freeze it. Check that the liquid is clear and replace the device before its expiry date (Mylan Specialty, 2024).
- **Carry it always.** Carry both devices everywhere and wear medical identification (Mylan Specialty, 2024).

The adult dose is taught in Chapter 6.

21.3 Immunodeficiency and the Immunocompromised Patient

Primary and Secondary Immunodeficiency

Immunodeficiency is a state in which the immune system cannot defend the body adequately. A person who is **immunocompromised** has defences weakened by a disease or its treatment.

Primary immunodeficiencies are built into the immune system, usually because of inherited changes. They are rare, and many are found in childhood, but more than half of people with antibody deficiencies are diagnosed as adults. **Common variable immunodeficiency (CVID)**, the most important example in adults, usually begins after age 10. It causes repeated sinus and lung infections and is linked with autoimmune disease, digestive problems and a higher risk of cancer. It is treated with immunoglobulin replacement (Chapter 20), which many patients need for life (McCusker et al., 2018). Warning signs in adults include two or more new sinus infections in a year without allergy, a pneumonia every year for more than one year, repeated need for intravenous antibiotics, persistent thrush and chronic diarrhea with weight loss (McCusker et al., 2018). In the most severe primary immunodeficiencies, live vaccines can cause severe, spreading and even fatal infection, while non-live vaccines are safe but may protect less well (McCusker et al., 2018).

Secondary immunodeficiency is acquired. It results from another disease, from malnutrition or from treatment with drugs that suppress immunity (McCusker et al., 2018). Common causes in adult care are:

- **Drugs:** corticosteroids; transplant drugs, such as calcineurin inhibitors and antimetabolites; biologic therapies, such as tumour necrosis factor (TNF) inhibitors (for example, adalimumab); and chemotherapy (Chapter 9).
- **Infections:** HIV above all (section 21.4).
- **Chronic diseases:** diabetes (Chapter 22), advanced chronic kidney disease (Chapter 27) and cancers of the blood cells (Chapter 20).
- **Other causes:** malnutrition, removal or loss of function of the spleen (Chapter 20) and aging (section 21.1).

Table 21.2 summarizes what these causes mean for nursing care. The Canadian Tuberculosis Standards illustrate the effect: people living with HIV have a very high risk that tuberculosis (TB) infection will progress to disease; transplant recipients, people with stage 4 or 5 kidney disease and people taking TNF inhibitors or corticosteroids have a high risk; and people with diabetes have a moderate risk (Campbell et al., 2022).

Table 21.2 Common causes of secondary immunodeficiency and what they mean for nursing care (AbbVie Corporation, 2022; Campbell et al., 2022; McCusker et al., 2018; NACI, 2018; Public Health Agency of Canada, 2026e)

Cause	Effect on immunity	Nursing points
Corticosteroids	Suppress inflammation and immune responses; raise the risk that TB infection progresses to disease	Signs of infection, including fever, may be muted; do not stop long-term therapy without an order (Chapter 23); check vaccine plans with the prescriber
Transplant immunosuppressants	Suppress the immune response to prevent rejection; raise the risk of TB disease	Give on time, every time; report signs of infection early; avoid live vaccines; strict hand hygiene
Biologics, such as TNF inhibitors	Block specific immune signals; raise the risk of serious infection, TB and hepatitis B reactivation	Confirm TB and hepatitis B screening was done before the first dose; assess for infection before each dose and report it; no live vaccines during therapy
Chemotherapy	Suppresses the bone marrow, which can cause neutropenia (Chapter 9)	Treat fever as an emergency (Chapter 9); check the neutrophil count before procedures
HIV	Depletes CD4 T cells; very high risk that TB infection progresses to disease; opportunistic infections (section 21.5)	Support ART adherence; follow CD4 count and viral load (section 21.5); non-stigmatizing care
Diabetes and chronic kidney disease	Raise the risk of infection, including progression of TB infection (moderate risk with diabetes, high with stage 4 or 5 kidney disease)	Inspect feet, skin and wounds; keep glucose in target (Chapter 22); report infection early
Older age	Immunosenescence weakens T cell responses and vaccine responses	Expect atypical signs such as confusion or falls (Chapter 8); keep vaccines up to date

Recognizing Infection When Immunity Is Low

When immunity is weak, the body may not mount the fever, redness, swelling or pus that usually signal infection. An immunocompromised adult may have a serious infection with a normal or only slightly raised temperature. The nurse therefore

watches trends and subtle changes: new confusion or fatigue, a rising respiratory or heart rate, a falling blood pressure, reduced urine output or a vague report of "not feeling right." These early warning signs and the escalation steps for sepsis are taught in Chapters 4 and 6. Fever in a patient with neutropenia is a medical emergency, covered in Chapter 9. Because TB infection is more likely to progress to disease in many of these patients (Campbell et al., 2022), the nurse also reports symptoms that could suggest TB (Chapter 13).

Screening before treatment is part of prevention. The Canadian product monograph for adalimumab, a TNF inhibitor, directs that patients be checked for both active and inactive TB before starting, that TB infection be treated before therapy begins, and that people at risk be checked for previous hepatitis B infection. It also states that therapy should not be started during an active infection and should be stopped if a serious infection or sepsis develops (AbbVie Corporation, 2022). Before giving a dose of a biologic, the nurse confirms that screening results are on the record, asks about fever and new symptoms, and reports any sign of infection to the prescriber before proceeding.

Nursing Care and Teaching

Care for an immunocompromised adult combines protection, early detection and teaching:

- **Infection prevention:** routine practices and hand hygiene by everyone who enters the room, visitors included (Chapter 4).
- **Devices:** avoid unnecessary invasive devices, such as urinary catheters and intravenous lines, and ask daily whether each one is still needed (Chapter 4).
- **Food safety:** reinforce safe food handling, because foodborne infections can be more serious when immunity is weak, and follow any food advice from the care team.
- **Vaccines:** The Canadian Immunization Guide (CIG) advises immunizing before planned immunosuppression whenever possible and vaccinating family members and other close contacts, with annual influenza vaccine encouraged. People who are severely immunocompromised should not receive a **live vaccine**, one that contains a weakened living microbe. Non-live vaccines are given at least 2 weeks before immunosuppressive therapy begins in people with blood cancers, and live vaccines at least 4 weeks before an organ transplant. Vaccine responses are often weaker and shorter in immunocompromised people, and live vaccines wait at least 6 months after treatment with an antibody that targets B cells (Public Health Agency of Canada [PHAC], 2026e). People taking adalimumab may receive other vaccines but not live ones (AbbVie Corporation, 2022). NACI recommends two doses of the non-live recombinant zoster vaccine for adults aged 18 and older who are or will be immunocompromised; before immunosuppressive therapy, the second dose can be given as early as 4 weeks after the first (Krishnan et al., 2026). Immunization is covered in section 21.6.
- **When to call:** teach the patient to report a fever, chills, a new cough, burning on urination, a red or draining wound, or simply feeling unwell, the same day.
- **Medication safety:** teach patients never to stop or skip a transplant drug or biologic without talking to the prescriber, and to tell every health care provider which immunosuppressing drugs they take.

All nurses monitor these patients and act on change. An RPN who notices subtle signs of infection reports them at once and consults the RN as the patient's needs change, as described in Chapter 1, section 1.3.

LIFESPAN CONSIDERATIONS

Immunosenescence, Vaccines and HIV After 50

- **Older adults first.** Immunosenescence means infection may appear as confusion, a fall or loss of appetite rather than fever (Chapters 4 and 8). The nurse compares today's behaviour and function with the person's usual baseline, asking family when the patient cannot say.
- **Vaccine priorities.** NACI recommends the recombinant zoster vaccine for adults aged 50 and older without contraindications, because shingles becomes more common with age and the older live vaccine works less well in older adults (NACI, 2018). Influenza and pneumococcal vaccines, also priorities for older adults, are covered in Chapter 13. The nurse checks immunization status on admission and at discharge.

- **HIV after 50.** With effective ART, people living with HIV are growing older (section 21.5), and some will meet age-related conditions, such as heart and kidney disease, alongside HIV. Older adults also have sexual health needs. Age alone is never a reason to skip a sexual health history or the offer of an HIV test (section 21.4).

21.4 HIV: Infection, Testing and Prevention



Figure 21.4 The structure of HIV: an outer envelope with docking proteins that attach to the CD4 receptor on a host cell, and a capsid holding the viral RNA and the enzymes reverse transcriptase and integrase. (credit: National Institute of Allergy and Infectious Diseases, public domain)

Human immunodeficiency virus (HIV) can now be prevented, found early and treated well. Nurses help close the remaining gaps: people never offered a test, people unaware of prevention medicines, and people who avoid care for fear of how they will be treated. Section 21.5 covers treatment.

How HIV Causes Disease

HIV is a retrovirus (Figure 21.4). Its genes are carried as RNA, and it brings its own enzymes into the cells it infects: reverse transcriptase copies the viral RNA into DNA, integrase splices that DNA into the host cell's chromosomes, and protease cuts new viral proteins into working parts. Each enzyme is a target of antiretroviral drugs (section 21.5; Figure 21.5). Because viral DNA stays in infected cells for their lifetime, treatment controls HIV but does not cure it.

HIV mainly infects CD4 T helper cells, which coordinate both antibody and cell-mediated responses (section 21.1). Untreated, the virus destroys them faster than the body replaces them, and over years the falling CD4 count leaves the person open to infections and cancers a healthy immune system controls.

HIV passes from person to person through a small set of body fluids: blood, semen and pre-seminal fluid, vaginal fluid, rectal fluid and human milk. The main routes are anal or vaginal sex without a condom or other prevention, sharing needles or other drug-use equipment, and transmission during pregnancy, birth or breastfeeding or chestfeeding (Chapter 29). HIV is not passed on through healthy, unbroken skin or through casual contact such as kissing, hugging, shaking hands, sharing food or toilet seats, and mosquitoes do not spread it (Public Health Agency of Canada [PHAC], 2025b). A person whose viral load stays suppressed on treatment does not transmit HIV through sex (PHAC, 2023b).



Figure 21.5 The HIV replication cycle. Antiretroviral drug classes act at different steps: entry, reverse transcription, integration and maturation by protease (section 21.5). (credit: "HI-Virus Replication Cycle" by NIAID/Wikimedia Commons, CC BY 2.0)

Untreated HIV moves through three broad stages:

- **Acute HIV infection:** the first weeks after the virus enters the body. The virus multiplies quickly, the viral load is very high and the person is highly infectious. At least half of people have a mild flu-like illness 2 to 4 weeks after infection, with fever, sore throat, rash or swollen lymph nodes, among other symptoms; others notice nothing (PHAC, 2025c). Antibody tests may still be negative (see the window period, below).
- **Chronic HIV infection:** the immune system partly controls the virus, and the person may feel well for years while CD4 cells are slowly lost.
- **Advanced HIV disease:** in the United States surveillance case definition, **acquired immunodeficiency syndrome (AIDS)**, or stage 3 HIV, is a CD4 count below 200 cells/µL (0.2×10^9/L), a CD4 percentage below 14%, or the diagnosis of an AIDS-defining opportunistic illness (Selik et al., 2014). With treatment, most people never reach this stage, but people diagnosed late may arrive in hospital with an opportunistic infection as the first sign of HIV.

HIV in Canada

PHAC (2024a) estimated that 65,270 people were living with HIV in Canada at the end of 2022. About 1 in 10 of them did not know they had HIV. Canada committed to the global **95-95-95 targets** for 2025: 95% of people living with HIV diagnosed, 95% of those diagnosed on treatment, and 95% of those on treatment with a suppressed viral load. In 2022, the estimates were 89%, 85% and 95%, so only the third target was met. PHAC estimated 1,848 new infections in 2022, about 15% more than its 2020 estimate, and noted that the COVID-19 pandemic disrupted services (PHAC, 2024a).

Surveillance counts first-time diagnoses, not new infections. In 2024, 2,288 people received a first HIV diagnosis in Canada (5.5 per 100,000 population), fewer than in 2023 but more than before the pandemic (PHAC, 2026c). Manitoba (19.5 per 100,000) and Saskatchewan (18.6 per 100,000) had the highest rates in 2024, and the Atlantic region had the lowest (1.7 per 100,000). Among males diagnosed in 2024, male-to-male sexual contact was the most common exposure category (49.9%); among females, heterosexual contact was the most common (58.1%); and injection drug use accounted for 16.9% of all first-time diagnoses (PHAC, 2026c).

Race and ethnicity were reported for only 38.1% of 2024 diagnoses, so PHAC (2026c) cautions that the figures may not represent everyone diagnosed. Among the 871 diagnoses with these data, 31.6% were among Black people, 25.4% among white people and 7.1% among Indigenous people (6.1% First Nations, 0.3% Inuit and 0.7% Métis). Data about First Nations communities are

governed by the First Nations principles of OCAP® (ownership, control, access and possession), so the nurse uses published aggregate figures and respects community control over local data.

These patterns reflect structures, not personal failings. The federal STBBI (sexually transmitted and blood-borne infections) action plan names gay, bisexual and other men who have sex with men, people who inject drugs, Indigenous Peoples, Black communities, people who experience incarceration, and trans and non-binary people as key populations. It points to stigma, including in health care, anti-Black racism, anti-Indigenous racism rooted in colonial policies, the criminalization of HIV non-disclosure, and unequal access to income, housing, food and mental health support (PHAC, 2024b). Chapter 2 teaches cultural safety and anti-racist care.

CANADIAN CONTEXT

HIV in Canada

- **Two figures to know:** an estimated 65,270 people were living with HIV in Canada at the end of 2022, and about 1 in 10 of them had not been diagnosed (PHAC, 2024a).
- **Where diagnoses are highest:** in 2024, Manitoba and Saskatchewan had first-diagnosis rates more than three times the national rate of 5.5 per 100,000 (PHAC, 2026c).
- **Communities leading the response:** community organizations, including Indigenous-led and Black-led organizations, offer testing, harm reduction, peer support and help finding care. The federal action plan commits to funding community-led projects and to peer-based approaches such as peer navigation, in which a person with lived experience helps someone move through testing and care (PHAC, 2024b).
- **Finding local testing:** in Ontario, Sexual Health Infoline Ontario (1-800-668-2437) helps people find sexual health services, and the province lists anonymous testing sites (Government of Ontario, 2025). Local public health units and community health centres offer testing across Canada.
- **For the nurse:** the most useful thing a nurse can do is offer HIV testing routinely, in a matter-of-fact way, to every adult in their care who has not been tested recently.

Testing

PHAC's HIV screening guidance asks clinicians to make HIV testing a routine part of care and to offer it whether or not the person asks (PHAC, 2013, 2020). Testing should be offered to anyone who asks; anyone with signs of HIV or of immune-related illness; sexually active people who have never been tested; people who are pregnant or planning a pregnancy; people who have shared drug-use equipment or had condomless sex with a partner whose HIV status is positive or unknown; and survivors of sexual assault. People with ongoing risk should be tested at least yearly, and some more often (PHAC, 2013). That guide is under review, so the nurse watches for updates; PHAC's current STBBI guidance also supports offering screening during routine care (PHAC, 2025d).

HIV testing is voluntary; verbal consent is enough, and the person may decline (PHAC, 2020). Before the test, the nurse explains the window period, how results are kept private and the limits of that privacy (positive results are reported to public health), and the right to refuse (PHAC, 2013). A negative result opens a talk about prevention. A positive result is given in person, with time for questions, a rapid link to HIV care and support for partner notification (PHAC, 2013, 2020). Consent is taught in Chapter 1, section 1.5.

Three kinds of tests are used (PHAC, 2020):

- **Laboratory screening test:** a fourth-generation test on a blood sample detects both HIV antibodies and the p24 antigen, a viral protein that appears before antibodies. It can be reactive 15 to 20 days after exposure. A reactive screen is followed by confirmatory testing in the laboratory.
- **Point-of-care (rapid) test:** a finger-prick test that gives a result within minutes. It detects antibodies only, so it becomes reactive later, about 20 to 30 days after exposure. A reactive rapid result is preliminary and must be confirmed with a standard laboratory test.
- **Self-test:** Health Canada approved the first home-based HIV self-test in Canada in 2020 (Health Canada, n.d.-a). As of September 2026, two self-test kits are approved: one uses a finger prick and the other an oral swab (PHAC, 2026a). A reactive self-test must be confirmed with a standard laboratory test (PHAC, 2020).

The **window period** is the time between infection and the point when a test can reliably detect it; a person can test negative but be highly infectious during it. PHAC (2020) states that it can last up to 12 weeks, so after a negative test within 12 weeks of a possible exposure, the nurse offers repeat testing.

In Ontario, people can choose standard (name-based) testing or anonymous testing, in which results are given using a code known only to the person and no name or Ontario Health Insurance Plan (OHIP) number is needed (Government of Ontario, 2025). Every province and territory requires positive HIV results, AIDS diagnoses or both to be reported to public health (PHAC, 2013). In Ontario, the laboratory reports a positive name-based test with the person's name and contact information, and a confirmed positive anonymous test without them. Public health units require that sexual and drug-use partners be told of a possible exposure, by the person, their health care provider or public health (Community Legal Education Ontario [CLEO], 2022). The nurse explains these rules before testing so that consent is informed.

Prevention Options

The nurse helps each person choose the options that fit their life (Table 21.3).

Condoms, external or internal, prevent HIV and also protect against other sexually transmitted infections and pregnancy, which antiretroviral prevention does not (PHAC, 2023b).

Pre-exposure prophylaxis (PrEP) is the use of antiretroviral medication by an HIV-negative person to prevent HIV. The 2025 Canadian guideline states that PrEP is appropriate for adults and adolescents who ask for it, and that clinicians should ask about HIV risk at routine visits and actively offer PrEP when they identify risk, even if the person has not raised it (Tan et al., 2025). Daily oral tenofovir disoproxil fumarate/emtricitabine is recommended for every HIV-negative person for whom PrEP is suitable and is available in Canada as generic products. For cisgender men and transgender women whose risk comes from sex with cisgender men, the same drug can also be taken "on demand", before and after sex; on-demand dosing is not recommended for cisgender women or people who inject drugs. For cisgender men and transgender women whose risk comes from sex, the guideline also lists daily oral emtricitabine/tenofovir alafenamide (an option that may be considered) and long-acting injectable cabotegravir, which Health Canada approved for PrEP in 2024 (Tan et al., 2025). Follow-up includes (Tan et al., 2025):

- HIV testing before the first dose and again at 30 days, then on a schedule that depends on the form of PrEP: every 3 months for daily tablets and every 2 months for the injection;
- kidney function (serum creatinine) at baseline and then every 3 to 12 months, depending on the drug and the person's kidney risk;
- screening for gonorrhea, chlamydia and syphilis at baseline and every 3 to 4 months;
- hepatitis B and hepatitis C testing at baseline, repeated yearly for people who remain susceptible, and pregnancy testing as appropriate.

Post-exposure prophylaxis (PEP) is a 28-day course of antiretroviral drugs taken after a possible exposure. It is an emergency: the Canadian guideline says to start it as soon as possible and no later than 72 hours after the exposure (Tan et al., 2025). The preferred regimens are bictegravir/emtricitabine/tenofovir alafenamide, or dolutegravir with tenofovir disoproxil fumarate/emtricitabine. Follow-up HIV testing is done 4 to 6 weeks after the exposure, with a final test at 12 weeks (Tan et al., 2025). PEP is not started after sex with a partner who has an undetectable viral load, because that exposure carries no risk of sexual transmission (Tan et al., 2025). After a work exposure, such as a needlestick, the nurse gives first aid, reports it at once under employer policy and is assessed urgently for PEP (Chapter 4).

Undetectable = untransmittable (U=U) describes the scientific consensus that HIV cannot be passed on through sex when someone living with HIV takes ART as prescribed and keeps a viral load below 200 copies/mL, measured every 4 to 6 months (PHAC, 2023b). PHAC (2023b) notes limits: U=U does not prevent other sexually transmitted infections or pregnancy; the evidence behind it comes from sexual transmission, so it does not apply to shared drug-use equipment or to transmission during pregnancy, breastfeeding or chestfeeding; it depends on continuing treatment and regular viral load tests; and suppression is not a cure. Talking about U=U helps reduce fear and shame.

Harm reduction prevents HIV among people who use drugs: new sterile needles, syringes and other equipment for every use, supervised consumption services and treatment for opioid use disorder (Chapter 11).

Table 21.3 HIV prevention options at a glance (Tan et al., 2025; PHAC, 2023b)

Option	Who it is for	Timing	Nursing points
Condoms (external or internal)	Anyone who has anal or vaginal sex	Every time, from start to finish of sex	Also protect against other sexually transmitted infections and pregnancy; teach correct use and offer free supplies
Pre-exposure prophylaxis (PrEP)	HIV-negative people who ask for it or are at increased risk through sex or drug use	Daily oral, on demand (selected groups only) or long-acting injection	Rule out HIV first; HIV test 30 days after starting, then every 2 to 3 months; check kidney function and screen for sexually transmitted infections
Post-exposure prophylaxis (PEP), non-occupational	A person with a possible exposure, such as condomless sex or a shared needle	Start as soon as possible, no later than 72 hours after exposure; take for 28 days	Treat as an emergency; refer to the emergency department or a sexual health clinic; HIV tests at 4 to 6 weeks and 12 weeks
Occupational exposure	A health care worker with a needlestick or a splash of blood or other body fluid	First aid and reporting at once; PEP assessment urgently	Follow employer policy and Chapter 4; occupational health arranges follow-up testing
Treatment as prevention (U=U)	People living with HIV and their partners	Viral load below 200 copies/mL, checked every 4 to 6 months	Prevents sexual transmission only; support adherence; condoms still protect against other infections
Harm reduction supplies	People who use drugs	New sterile equipment for every use	Offer supplies without judgment; link to supervised consumption and treatment (Chapter 11)

21.5 Living With HIV: Treatment and Nursing Care

A person who starts treatment early and keeps taking it can expect to stay well and will not pass HIV on through sex. In hospital, the main threats to that outcome are missed doses, drug interactions and stigma.

Antiretroviral Therapy

Antiretroviral therapy (ART) is a combination of drugs from different classes that stops HIV from multiplying. The adult antiretroviral guidelines of the United States Department of Health and Human Services (DHHS) recommend ART for everyone with HIV, to prevent illness and death and to prevent transmission, and advise starting it right away, or as soon as possible after diagnosis, on the day of diagnosis when possible (Panel on Antiretroviral Guidelines for Adults and Adolescents, 2025). The goal is a viral load that stays below the level the laboratory test can detect.

Most regimens combine two or three drugs from these classes:

- **Nucleoside reverse transcriptase inhibitors (NRTIs):** the "backbone" of most regimens (for example, emtricitabine, lamivudine, tenofovir alafenamide and abacavir).
- **Non-nucleoside reverse transcriptase inhibitors (NNRTIs):** for example, rilpivirine.
- **Integrase strand transfer inhibitors (INSTIs):** the anchor of most first regimens (for example, bictegravir, dolutegravir and cabotegravir).
- **Protease inhibitors:** for example, darunavir, given with a "booster" (cobicistat or ritonavir) that slows the drug's breakdown.

Many people take a single tablet once a day. Examples marketed in Canada include bictegravir/emtricitabine/tenofovir alafenamide (Gilead Sciences Canada, 2025), dolutegravir/lamivudine (ViiV Healthcare ULC, 2025a) and dolutegravir/abacavir/lamivudine (ViiV Healthcare ULC, 2023). For people whose virus is already suppressed, long-acting cabotegravir and rilpivirine can replace daily pills with injections into the gluteal muscle, given by a health care professional monthly or every 2 months (ViiV Healthcare ULC, 2025b).

Adherence, Interactions and Resistance

HIV copies itself with many errors. When missed doses let drug levels fall, the virus multiplies again and copies that resist the drugs are selected, which can make a regimen fail and narrow future choices. Poor adherence, side effects and drug interactions that lower antiretroviral levels are leading causes of treatment failure (Panel on Antiretroviral Guidelines for Adults and Adolescents, 2025). The nurse asks about missed doses without judgment and helps remove barriers: pill organizers, reminders, a regular pharmacist, peer navigators, and help with cost, housing, mental health or substance use.

Every new drug, supplement and over-the-counter product is checked with the pharmacist. Key interactions from Canadian product monographs:

- **Integrase inhibitors and polyvalent cations:** antacids and laxatives containing aluminum or magnesium, and calcium or iron supplements, reduce absorption. Bictegravir/emtricitabine/tenofovir alafenamide is taken at least 2 hours before or after these products, or together with food, but not at the same time on an empty stomach (Gilead Sciences Canada, 2025). Dolutegravir products are taken 2 hours before or 6 hours after cation-containing medicines; calcium or iron supplements may be taken at the same time only with food (ViiV Healthcare ULC, 2023, 2025a).
- **Boosted regimens:** cobicistat strongly inhibits CYP3A, the liver enzyme that clears many drugs, so regimens boosted with cobicistat must not be given with drugs that depend heavily on CYP3A for clearance (Janssen Inc., 2023b).
- **Rilpivirine and acid suppression:** proton pump inhibitors are contraindicated; H2-receptor antagonists must be given at least 12 hours before or 4 hours after rilpivirine, and antacids at least 2 hours before or 4 hours after; rilpivirine is taken with a meal (Janssen Inc., 2023a).
- **Rifampin:** this tuberculosis drug is contraindicated with bictegravir because it lowers bictegravir levels (Gilead Sciences Canada, 2025); Chapter 13 covers tuberculosis.

In hospital, the nurse never stops or interrupts ART without a prescriber's order and gives each dose on time. If a patient cannot take anything by mouth, the nurse contacts the prescriber and pharmacist before a dose is missed. Stopping a regimen that contains emtricitabine, lamivudine or tenofovir can cause a severe flare of hepatitis B in a person who also has hepatitis B (Gilead Sciences Canada, 2025).

Monitoring

The **viral load** (HIV RNA) is the amount of virus in the blood, and it shows whether treatment is working. The **CD4 count** shows the state of the immune system (section 21.1). After ART starts, the viral load is checked every 4 to 8 weeks until it is undetectable, then every 3 to 4 months, and in some stable, adherent people every 6 months. CD4 counts are repeated every 3 to 4 months in the first 1 to 2 years if the count is below 300 cells/µL; once the count is 300 cells/µL or more with a suppressed viral load, CD4 monitoring becomes optional unless there is a clinical reason (Panel on Antiretroviral Guidelines for Adults and Adolescents, n.d.). Kidney and liver function, lipids and glucose are also checked periodically.

GOING DEEPER

Viral Load, CD4 Count and Resistance Testing

Required for RN students; optional for PN students.

- **Undetectable:** a viral load below the lower limit of detection of the assay used, which varies by test. For example, the Canadian monograph for long-acting cabotegravir/rilpivirine describes suppression as HIV RNA below 50 copies/mL (ViiV Healthcare ULC, 2025b). For U=U, PHAC (2023b) uses a threshold of under 200 copies/mL, checked every 4 to 6 months.
- **Blip versus failure:** a viral blip is a single, isolated detectable result after suppression that returns to undetectable on the next test. Virologic failure is the inability to reach or keep a viral load below 200 copies/mL; virologic rebound is a confirmed result of 200 copies/mL or more after suppression (Panel on Antiretroviral Guidelines for Adults and Adolescents, 2025).
- **Resistance testing:** a genotypic resistance test reads the virus's genes for mutations that reduce drug activity. Blood for this test is drawn at diagnosis, without delaying ART, and again at treatment failure, ideally while the person is still taking the failing regimen (Panel on Antiretroviral Guidelines for Adults and Adolescents, 2025).
- **CD4 recovery lags:** viral suppression usually comes within weeks, but CD4 counts rise slowly, often about 50 to 150 cells/µL in the first year (Panel on Antiretroviral Guidelines for Adults and Adolescents, n.d.). Until the count recovers, prophylaxis against opportunistic infections may still be needed.

- **For the nurse:** a rising viral load is a cue to explore adherence, new interacting drugs and vomiting or diarrhea before assuming resistance.

MEDICATIONS

Antiretroviral Classes

- **NRTIs (nucleoside reverse transcriptase inhibitors):** block reverse transcriptase so viral RNA cannot be copied into DNA. Examples: emtricitabine, lamivudine, tenofovir alafenamide, tenofovir disoproxil fumarate, abacavir. Abacavir: the HLA-B*5701 gene is tested before starting; a hypersensitivity reaction (fever, rash, gastrointestinal or respiratory symptoms) means abacavir is never restarted (ViiV Healthcare ULC, 2023). Stopping emtricitabine, lamivudine or tenofovir can trigger a hepatitis B flare.
- **NNRTIs (non-nucleoside reverse transcriptase inhibitors):** bind reverse transcriptase directly. Example: rilpivirine. Taken with a meal; proton pump inhibitors are contraindicated (Janssen Inc., 2023a).
- **INSTIs (integrase strand transfer inhibitors):** stop viral DNA from entering the cell's DNA. Examples: bictegravir, dolutegravir, cabotegravir. Separate from antacids, laxatives, and calcium or iron products exactly as the monograph states (Gilead Sciences Canada, 2025; ViiV Healthcare ULC, 2025a).
- **Protease inhibitors with boosters:** stop viral proteins from being cut into working parts. Example: darunavir with cobicistat. The booster inhibits CYP3A, so many drug combinations are contraindicated (Janssen Inc., 2023b).
- **Long-acting injectables:** cabotegravir with rilpivirine, injected into the gluteal muscle by a health care professional monthly or every 2 months; observe the person for about 10 minutes afterward and keep every appointment (ViiV Healthcare ULC, 2025b).
- **Single-tablet regimens:** bictegravir/emtricitabine/tenofovir alafenamide; dolutegravir/lamivudine; dolutegravir/abacavir/lamivudine.

Opportunistic Infections

An **opportunistic infection** takes advantage of a weakened immune system. Most occur when the CD4 count is below 200 cells/µL, and ART is the best protection.



Figure 21.6 Oral candidiasis (thrush): creamy white patches on red, inflamed mucosa. Unlike food debris, the patches do not rinse away. (credit: Centers for Disease Control and Prevention, Public Health Image Library, public domain)

- **Pneumocystis pneumonia (PJP):** caused by the fungus *Pneumocystis jirovecii*. It begins gradually over days to weeks with worsening breathlessness, fever, a dry (non-productive) cough and chest discomfort. With exertion the person breathes fast and the heart rate climbs, and low blood oxygen is the most typical laboratory finding. Oxygen saturation often falls with exercise, although this finding is not specific to PJP. Diagnosis needs induced sputum or bronchoscopy; ordinary coughed-up sputum has low sensitivity and is not used (Panel on Opportunistic Infections in Adults and Adolescents With HIV, 2026).
- **Candidiasis:** a fungal infection. Oral thrush appears as white patches on the tongue, palate or inside the cheeks (Figure 21.6), and pain on swallowing may mean the infection has reached the esophagus; the nurse reports both.
- **Toxoplasmosis:** a parasite that can reactivate in the brain, mainly when the CD4 count is below 50 cells/µL, causing headache, new focal weakness, sometimes fever, and seizures; these are urgent neurologic cues (Panel on Opportunistic Infections in Adults and Adolescents With HIV, 2025b; Chapter 30).
- **Tuberculosis:** more likely and more serious in people living with HIV; Chapter 13 covers screening, airborne precautions and treatment.
- **Cytomegalovirus (CMV):** can infect the retina, typically when the CD4 count is below 50 cells/µL; new floaters, blind spots or changes in vision need urgent referral to an eye specialist (Panel on Opportunistic Infections in Adults and Adolescents With

HIV, 2025a).

- **Kaposi sarcoma:** a cancer linked to human herpesvirus 8 that causes flat or raised patches or nodules on the skin or in the mouth (Figure 21.7). The lesions are classically violet, but their colour varies with skin tone and they can be harder to see on darker skin, so the nurse inspects the whole skin and the mouth in good light.

Figure 21.7 Kaposi sarcoma on the skin of a person with advanced HIV: raised, red-purple patches and nodules. On darker skin the lesions may look brown or black. (credit: unknown author/Wikimedia Commons, public domain)

Prophylaxis prevents PJP. The DHHS opportunistic infection guideline (updated May 27, 2026) recommends trimethoprim-sulfamethoxazole for adults with a CD4 count below 200 cells/µL who are not on ART or are starting it. For people already on ART, prophylaxis is started if the CD4 count falls below 100 cells/µL, whatever the viral load, or falls to 100 to 200 cells/µL while the viral load keeps rising. Prophylaxis can be stopped once ART has raised the CD4 count to 200 cells/µL or more for at least 3 months (Panel on Opportunistic Infections in Adults and Adolescents With HIV, 2026). **Immune reconstitution inflammatory syndrome (IRIS)** is an inflammatory worsening of an infection's signs, usually in the first weeks to months after ART starts, as the recovering immune system reacts to organisms already present; CMV eye disease is one example (Panel on Opportunistic Infections in Adults and Adolescents With HIV, 2025a). The nurse reports any new fever or worsening symptoms after ART begins.

Care in Hospital and Aging With HIV

HIV calls for routine practices only (Chapter 4). No extra gloves, signs, separate dishes or private rooms are needed because of HIV; additional precautions are used only when another condition, such as suspected tuberculosis, calls for them. HIV status is personal health information, shared only with team members who need it and never in hallways or on whiteboards (Chapter 1). Language matters: the nurse says "person living with HIV" rather than "HIV-infected" or "AIDS victim", and documents facts, not judgments.

Because treatment works, many people living with HIV are now older adults. A Quebec study of 3,905 people on ART found that cardiovascular, bone and kidney conditions were more common in people living with HIV than in matched controls and appeared at younger ages, and that polypharmacy was more frequent (Baribeau et al., 2022). The nurse watches for fracture risk, falls and kidney changes, asks about memory and mood, and asks the pharmacist to review every new drug against the antiretroviral regimen. Chapter 8 covers care of older adults.

Stigma, Disclosure and the Law

People living with HIV still meet stigma in health care. A Quebec research team summarized studies from Western countries in which 45% to 83% of people living with HIV reported stigma from health care professionals, including inappropriate questions, unnecessary infection control measures, breaches of confidentiality and refused care; nurses were described as showing more stigmatizing behaviour than other professionals (Pelletier et al., 2022). Stigma leads people to avoid care, take medicines less consistently and test less often (Pelletier et al., 2022). The nurse examines their own assumptions, uses routine practices for everyone and speaks up when colleagues treat a patient differently.

Disclosure of HIV status is the person's own decision. The nurse does not tell family members, visitors or other patients without the person's consent. Notifying sexual or drug-use partners is handled through the public health process described in section 21.4.

Nurses give information about the criminal law, never legal advice. In *R v Mabior* (2012), the Supreme Court of Canada held that a person living with HIV must disclose their status before sex when there is a "realistic possibility of transmission"; the Court found that a low viral load combined with condom use negates that possibility (Department of Justice Canada, 2022). A federal directive

that took effect on December 8, 2018, tells federal prosecutors, who handle these cases in the three territories, not to prosecute when the person has maintained a suppressed viral load (below 200 copies/mL), and generally not to prosecute when condoms were used, only oral sex took place or the person was taking treatment as prescribed (Department of Justice Canada, 2018). Provinces prosecute within their own borders, and Ontario, British Columbia and Quebec have issued their own prosecutorial guidance (Department of Justice Canada, 2022). The federal government consulted on possible reform in 2022, so nurses check current sources before giving patients information about the law.

21.6 Autoimmunity and Adult Immunization

The immune system must attack invaders while leaving the body's own tissues alone. This section introduces what happens when that balance fails and then turns to immunization, one of the most effective ways nurses protect adults.

Autoimmunity

Autoimmunity is an immune response directed against the body's own tissues. Normally, T and B cells that react strongly to self are removed or silenced as they mature, and regulatory T cells hold back those that escape. This is called self-tolerance. In autoimmune disease, tolerance breaks down, and autoantibodies or self-reactive T cells damage tissue. Most autoimmune diseases appear to arise from inherited susceptibility combined with triggers such as infections, certain drugs or other environmental exposures.

Autoimmune disease is common, and it is more common in women. In a United Kingdom study of about 22 million people, 19 common autoimmune disorders together affected 10.2% of people at some point during the study: 13.1% of women and 7.4% of men (Conrad et al., 2023). The same study found that having one autoimmune disease made having another more likely. Examples covered elsewhere in this book include:

- type 1 diabetes (Chapter 22);
- Hashimoto thyroiditis and Graves disease (Chapter 23);
- celiac disease and inflammatory bowel disease (Chapter 25);
- multiple sclerosis (Chapter 32);
- rheumatoid arthritis and systemic lupus erythematosus (Chapter 34);
- immune thrombocytopenia (section 20.4).

Treatment often relies on drugs that suppress the immune system, such as corticosteroids, disease-modifying drugs and biologic agents. A person taking them is immunocompromised, so the care in section 21.3 applies: atypical signs of infection, early reporting of fever, and caution with live vaccines. Vaccines are ideally brought up to date before immunosuppression starts (section 21.3).

Adult Vaccines

Immunization is not only for children. The CIG asks clinicians to counsel every adult about their immunization status and to review immunization records during routine encounters (PHAC, 2026d). Its main recommendations for adults, other than respiratory vaccines (Chapter 13), are summarized here and in Table 21.4 (PHAC, 2026d):

- **Tetanus and diphtheria:** a booster every 10 years, plus one dose of tetanus-diphtheria-acellular pertussis vaccine (Tdap) for adults who have not had Tdap as adults. Tdap is given in every pregnancy, ideally at 27 to 32 weeks (Chapter 29).
- **Measles, mumps and rubella (MMR):** for adults born in 1970 or later who are susceptible. Adults born before 1970 are generally presumed immune, but some, such as health care workers, students, travellers and military personnel, may still need vaccine.
- **Varicella:** for susceptible adults aged 18 to 49 years.
- **Herpes zoster (shingles):** two doses of recombinant zoster vaccine for adults aged 50 years and older, and for adults aged 18 and older who are or will be immunocompromised.
- **Human papillomavirus (HPV):** for people up to and including age 26; older adults at ongoing risk may receive it after shared decision-making.

- **Hepatitis B:** for adults at increased risk, including people with chronic liver or kidney disease, people who inject drugs, men who have sex with men, people with more than one sexual partner in the past 6 months, people living with HIV, and workers exposed to blood (PHAC, 2026b).
- **Hepatitis A:** an inactivated vaccine for adults at increased risk, such as travellers to countries where hepatitis A is common, people with chronic liver disease, people who use drugs in a problematic way and men who have sex with men (PHAC, 2023a).

Vaccines are either live or non-live. A **live attenuated vaccine** contains a weakened virus or bacterium that can still replicate, such as MMR and varicella vaccines; these are generally avoided in pregnancy and in people with significant immunosuppression (section 21.3). An **inactivated vaccine** cannot replicate. Non-live products include toxoid, subunit and recombinant vaccines such as Td, Tdap, HPV, hepatitis A and B vaccines and recombinant zoster vaccine (Krishnan et al., 2026; PHAC, 2023a, 2026b).

Ontario is the worked example. Its schedule funds Tdap once in adulthood and in every pregnancy, Td every 10 years, and a 2-dose shingles series between ages 65 and 70 (Government of Ontario, 2026), completed before the 71st birthday; HPV vaccine for males up to age 26 who have sex with men; and hepatitis A and B vaccines for listed high-risk groups (North Bay Parry Sound District Health Unit, 2025; Ontario Ministry of Health, 2022). Eligibility changes often, so the nurse checks the current provincial schedule.

Table 21.4 Adult vaccines at a glance; Ontario funding is shown as of each source's date (2022 to 2026), and eligibility changes often, so check the current Canadian Immunization Guide and provincial schedule (PHAC, 2023a, 2026b, 2026d; Government of Ontario, 2026; Ontario Ministry of Health, 2022; North Bay Parry Sound District Health Unit, 2025)

Vaccine	Live or inactivated	Adults who should receive it (summary)	Ontario publicly funded? (as of the source date)
Td and Tdap	Inactivated (toxoid)	All adults: Td every 10 years; one adult Tdap dose; Tdap in every pregnancy	Yes: one adult Tdap, Td every 10 years, Tdap in every pregnancy (2026)
MMR	Live	Susceptible adults born in 1970 or later; higher-risk groups such as health care workers and travellers	Yes: eligible from age 1 year; a second adult dose for groups such as health care workers, post-secondary students and travellers (2022)
Varicella	Live	Susceptible adults aged 18 to 49	Limited: adults born before 2000 only through high-risk criteria (2022)
Recombinant zoster	Non-live (recombinant)	Adults 50 and older; adults 18 and older who are or will be immunocompromised	Yes, ages 65 to 70 (2026)
HPV	Non-live (recombinant)	People up to and including 26; older adults at ongoing risk after shared decision-making	Adults only for high-risk males up to age 26 who have sex with men (2025)
Hepatitis B	Non-live (recombinant)	Adults with a higher risk of exposure or of complications	Yes, for listed high-risk groups (2022)
Hepatitis A	Inactivated	Adults at increased risk, such as people with chronic liver disease	Yes, for listed high-risk groups (2022)

Giving Vaccines Safely

Before every vaccine, the nurse screens for contraindications and precautions. The CIG checklist asks whether the vaccine is due, whether the person has had a serious reaction to a vaccine or is allergic to any component (including latex), and whether they are or may be pregnant. For live vaccines it also asks about immunosuppression, other live vaccines in the past 4 weeks and blood products in the past year (PHAC, 2026g). Informed consent follows Chapter 1, section 1.5.

Vaccines must stay within the **cold chain**, the system that keeps them at the right temperature from manufacturer to patient. Refrigerated vaccines are stored between +2 °C and +8 °C in their original packaging. If the temperature goes out of range, the nurse labels the vaccines "do not use", keeps them refrigerated and calls public health or the supplier for advice (PHAC, 2026f).

For most adults, the deltoid is the preferred intramuscular site. The CIG bases needle length on body weight and sex, with 2.5 cm (1 inch) suitable for many adults, 1.6 to 2.5 cm (5/8 to 1 inch) for those under 60 kg and 3.8 cm (1.5 inch) for larger adults. The needle enters at 90 degrees, and aspiration is not recommended (PHAC, 2026g). The person stays under observation for at least 15 minutes,

or 30 minutes when there is a specific concern about a reaction (PHAC, 2026g). The nurse is ready to manage anaphylaxis (Chapter 6, section 6.5). Each vaccine is recorded in the patient's record and, where one exists, the provincial registry.

An **adverse event following immunization (AEFI)** is any unwanted or unexpected health effect that follows a vaccine, whether or not the vaccine caused it. In Ontario, health professionals must report AEFIs to the local public health unit, using the provincial AEFI reporting form (Public Health Ontario, 2026). People who have a reaction can contact their health care provider or public health unit.

Talking About Vaccines

Vaccine hesitancy is a delay in or refusal of vaccination because of concerns about vaccines (PHAC, 2025a). The CIG advises providers to find out where a person's concern comes from and to listen in a calm, non-judgmental way. The nurse asks why the person holds a particular belief and answers in plain words, without jargon. Some people want data and others want stories from experience, so the nurse adapts. Motivational interviewing, a guiding style that helps people find their own reasons for change, can help. The person stays part of the decision, and patience and openness build trust; some people will still decline, and the conversation can continue at the next visit (PHAC, 2025a). Mistrust may be rooted in past harms in health care, especially for Indigenous and Black communities, so the nurse practises cultural safety (Chapter 2).

SCOPE IN PRACTICE

Who Gives Vaccines, and on Whose Authority

CNO's Scope of Practice standard asks every nurse to have the **authority**, the **competence** and a supportive **context** for each activity (Chapter 1, section 1.3).

- **Authority:** in Ontario, giving a vaccine by injection is the controlled act of administering a substance by injection. RNs and RPNs may carry it out when an authorized health care professional has given an order (College of Nurses of Ontario [CNO], 2025, n.d.-a). The order may be a direct order or a directive: an order from a physician or nurse practitioner that a nurse may carry out for a number of patients when specific conditions are met, with employer policy naming who may implement it (CNO, 2025). RNs who are authorized to prescribe may prescribe "any vaccines for prevention of bacterial and viral disease," which is one category on CNO's RN prescribing list (CNO, n.d.-b). RN prescribing is not an entry-level competency, requires additional education, and does not apply in public hospitals.
- **Competence:** the nurse needs current knowledge of the vaccine, screening, technique, cold chain handling, and recognition and emergency treatment of anaphylaxis (Chapter 6). CNO asks whether the nurse has the knowledge, skill and judgment to carry out the activity and manage any adverse outcome (CNO, n.d.-a).
- **Context:** employer policy may limit which nurses immunize and in which settings. An anaphylaxis kit with epinephrine must be at hand, and someone must be available to help in an emergency.
- **Working together:** an RPN who finds a contraindication, an unclear history or a reaction consults the RN or the prescriber before going ahead.
- **Elsewhere in Canada:** rules for nurse-led immunization vary by province and territory, so nurses check their own regulator's standards and employer policy.

PRACTICE STORY

The Sign on the Door

Names and details are fictional; this is a composite story.

Nurse: Amira Mansour, RPN. Years in practice: 4. Setting: medical unit, Ontario.

I came on shift and saw a sheet of paper taped to the door of room 12. Someone had written "Blood and body fluid precautions – HIV" in marker. Inside was Mr. Gauthier, a 58-year-old retired bus driver admitted with pneumonia. His chart showed he had lived with HIV for 20 years and his viral load was undetectable.

Ten minutes later I watched my colleague Kevin put on two pairs of gloves to carry in a breakfast tray. He set it down at the end of the bed and left quickly. Mr. Gauthier looked at the tray, then at the door, and said nothing.

I went to our charge nurse, Lisa, an RN, and told her what I had seen. She came with me, and we took the sign down together. She checked the chart: there was no order for additional precautions, and his chest x-ray and history did not suggest tuberculosis. Routine practices were all he needed, the same as every other patient on the unit. Lisa said she would find out who had posted the sign and remind the whole team at huddle that a diagnosis never goes on a door.

> Later I asked Kevin if we could talk in the medication room. I didn't want to embarrass him. He told me he had heard that "you can't be too careful" with HIV. I explained that gloves are for contact with blood or body fluids, not for meal trays, and that a person with an undetectable viral load does not transmit HIV through sex. He was quiet, then said he hadn't thought about how it looked from the bed.
>
> When I brought Mr. Gauthier his pills, I apologized for the sign. He said, "That's the third hospital that's done that." I thought about how many people stay home rather than face that, and about how a piece of paper had told every visitor and cleaner something that belonged only to him.
>
> Reflect: How did the sign breach Mr. Gauthier's privacy, and what would you document? If the sign reappeared or a colleague refused care, when would you involve the RN, the charge nurse or the manager, and why?

Chapter 21 Summary

Introduction

- Allergy labels, immunocompromised patients, people living with HIV and adult vaccines are part of everyday nursing on adult units.
- An allergy entry that is wrong or vague can harm a patient as much as one that is missing.

21.1 The Immune System: A Focused Review

- Innate immunity (barriers, phagocytes, complement) acts fast and has no memory; adaptive immunity (B cells, antibodies, CD4 and CD8 T cells) is specific and builds memory.
- The five antibody classes have different roles; IgE drives type I allergy and IgG crosses the placenta.
- Vaccines give active immunity with memory; immune globulin gives passive, temporary protection.
- Common immune tests include the white cell differential, immunoglobulin levels, CD4 count, HIV viral load and allergy tests; read results against the patient's own laboratory ranges.
- Immunosenescence raises the risk of infections such as shingles, blunts fever and weakens some vaccine responses; NACI recommends recombinant zoster vaccine from age 50.

21.2 Hypersensitivity and Allergy

- Hypersensitivity has four types: I (IgE, immediate), II (antibody against cells), III (immune complexes) and IV (delayed, T cell-mediated).
- An accurate allergy history separates allergy from intolerance and side effects and records the drug, reaction, timing, severity, treatment and date.
- Most penicillin labels are inaccurate, and false labels are linked to resistant infections and C. difficile; delabelling is a prescriber or allergist decision supported by the nurse's history and teaching.
- ACE inhibitor angioedema can appear after years on the drug, usually without hives, and airway swelling is an emergency.
- SJS/TEN and DRESS are delayed, life-threatening drug reactions; on darker skin they may look dusky, violet or darker rather than red; the nurse reports at once and holds the next dose per policy.
- Anaphylaxis prevention includes checking allergies before every drug and meal, allergist referral, two autoinjectors, medical identification and an action plan.

21.3 Immunodeficiency and the Immunocompromised Patient

- Primary immunodeficiencies are rare and inherited, though many antibody deficiencies, such as CVID, are diagnosed in adults; secondary causes include drugs, HIV, chronic disease, malnutrition and aging.
- Infection may cause little or no fever in immunocompromised adults; subtle changes are escalated early.
- TB and hepatitis B screening precede TNF inhibitor therapy, and doses are not given during active infection without the prescriber's review.

- The Canadian Immunization Guide advises vaccinating before immunosuppression, avoiding live vaccines in severe immunosuppression and vaccinating close contacts.

21.4 HIV: Infection, Testing and Prevention

- HIV is a retrovirus that destroys CD4 T helper cells; untreated, it moves from acute infection through chronic infection to advanced HIV disease (AIDS).
- HIV spreads through blood, semen, vaginal and rectal fluids and human milk, not through casual contact.
- In 2022, about 65,270 people in Canada were living with HIV and about 1 in 10 were undiagnosed; first-diagnosis rates in 2024 were highest in Manitoba and Saskatchewan, and the patterns reflect stigma, racism, colonialism, criminalization and unequal access to care.
- Nurses offer HIV testing routinely with verbal consent, explain the window period (up to 12 weeks) and, in Ontario, the options of nominal or anonymous testing and public health reporting.
- Prevention combines condoms, PrEP, PEP (started within 72 hours and taken for 28 days), U=U and harm reduction.

21.5 Living With HIV: Treatment and Nursing Care

- ART is recommended for everyone with HIV, started as soon as possible after diagnosis, with the goal of an undetectable viral load.
- Missed doses and drug interactions lead to resistance; in hospital, ART is never interrupted without a prescriber's order, and every new drug is checked with the pharmacist.
- Viral load shows whether treatment works; the CD4 count shows immune status and recovers slowly.
- Pneumocystis pneumonia, candidiasis, toxoplasmosis, tuberculosis, cytomegalovirus and Kaposi sarcoma are key opportunistic illnesses; trimethoprim-sulfamethoxazole prophylaxis starts below a CD4 count of 200 cells/µL in people not yet on ART or starting it.
- HIV needs routine practices only; nurses protect privacy, counter stigma, leave disclosure to the person, and know the criminal law only in outline.

21.6 Autoimmunity and Adult Immunization

- Autoimmunity results from a breakdown of self-tolerance; it is common and more common in women, and its treatment often makes people immunocompromised.
- The Canadian Immunization Guide recommends adult Td boosters, one adult Tdap dose, MMR and varicella for susceptible adults, recombinant zoster vaccine from age 50, HPV and hepatitis vaccines for eligible adults; Ontario funds some of these.
- Safe immunization includes screening, consent, cold chain storage at +2 °C to +8 °C, correct technique, at least 15 minutes of observation, documentation and AEFI reporting to the local public health unit in Ontario.
- Nurses address vaccine hesitancy by listening, clarifying concerns and respecting the person's decision.

Key Terms (40)

acquired immunodeficiency syndrome (AIDS) / advanced HIV disease: the most advanced stage of HIV infection, defined for surveillance as a CD4 count below 200 cells/µL, a CD4 percentage below 14%, or an AIDS-defining opportunistic illness.

acute HIV infection: the first weeks after HIV enters the body, when the viral load is very high, the person is highly infectious and a flu-like illness may occur.

adaptive immunity: the slower, antigen-specific part of the immune system, carried out by B cells and T cells, that develops memory after exposure.

adverse event following immunization (AEFI): any unwanted or unexpected health effect that follows a vaccine, whether or not the vaccine caused it.

allergy: a hypersensitivity reaction to a substance that is harmless to most people, such as a food, pollen or drug.

anaphylaxis: a severe, potentially life-threatening allergic reaction involving more than one body system; its recognition and emergency treatment are taught in Chapter 6.

angioedema: swelling of the deeper layers of the skin or of the lining of the mouth, throat or gut, caused by histamine or by bradykinin.

antibody: a protein (immunoglobulin) made by plasma cells that binds one specific antigen.

antigen: any molecule that the immune system can recognize as a target and respond to.

antiretroviral therapy (ART): a combination of drugs from different classes that stops HIV from multiplying.

autoimmunity: an immune response against the body's own tissues that results from a breakdown of self-tolerance.

CD4 T cell: a helper T cell that directs the immune response by releasing cytokines; the cell HIV infects and depletes.

cold chain: the system that keeps vaccines at the correct temperature, usually +2 °C to +8 °C, from manufacturer to patient.

delabelling: removing an inaccurate allergy label after the history is reviewed and, when needed, testing or a supervised challenge is done.

DRESS: drug reaction with eosinophilia and systemic symptoms; a delayed, severe drug reaction with rash, fever, swollen lymph nodes, facial swelling, eosinophilia and organ involvement, usually 2 to 6 weeks after a drug is started.

drug intolerance: an unwanted, non-immune effect of a drug that occurs at a low or below-therapeutic dose.

HIV non-disclosure: not telling a sexual partner about one's HIV status; a criminal matter in Canada only when there is a realistic possibility of transmission.

human immunodeficiency virus (HIV): a retrovirus that infects CD4 T helper cells and, without treatment, gradually destroys the immune system.

hypersensitivity: an excessive or misdirected immune response that damages the body's own tissues; grouped into types I to IV.

IgE: the antibody class that binds mast cells and basophils and drives type I allergic reactions.

immune reconstitution inflammatory syndrome (IRIS): an inflammatory worsening of an infection's signs, usually in the first weeks to months after ART starts, caused by the recovering immune system reacting to organisms already present.

immunocompromised: having immune defences weakened by a disease or its treatment.

immunodeficiency: a state in which the immune system cannot defend the body adequately; primary when built into the immune system, secondary when acquired.

immunosenescence: the natural, gradual decline in immune function that comes with age.

inactivated vaccine: a vaccine containing an organism or its parts that cannot replicate; non-live vaccines also include toxoid, subunit and recombinant vaccines.

innate immunity: the inborn, rapid first line of defence, including barriers, phagocytes and complement, which responds the same way each time and has no memory.

Kaposi sarcoma: a cancer linked to human herpesvirus 8 that causes patches or nodules on the skin or in the mouth; classically violet, with colour that varies by skin tone.

latex allergy: an allergic reaction to natural rubber latex, either delayed (type IV contact dermatitis) or immediate (type I, including anaphylaxis).

live attenuated vaccine: a vaccine containing a weakened organism that can still replicate, such as MMR or varicella vaccine.

live vaccine: a vaccine containing a weakened form of a living microbe; generally avoided in people who are severely immunocompromised.

opportunistic infection: an infection that takes advantage of a weakened immune system.

Pneumocystis pneumonia (PJP): a fungal lung infection that causes gradually worsening breathlessness, fever, dry cough and hypoxemia in people with low CD4 counts.

post-exposure prophylaxis (PEP): a 28-day course of antiretroviral drugs started as soon as possible, and within 72 hours, after a possible exposure to HIV.

pre-exposure prophylaxis (PrEP): antiretroviral medication taken by an HIV-negative person before possible exposure to prevent HIV.

Stevens-Johnson syndrome: a severe, usually drug-induced reaction in which the epidermis dies and separates over less than 10% of the body surface, with mucosal ulcers.

toxic epidermal necrolysis: the most extensive form of the same reaction as Stevens-Johnson syndrome, with detachment of more than 30% of the body surface.

undetectable = untransmittable (U=U): the scientific consensus that a person living with HIV who takes treatment and keeps a viral load below 200 copies/mL does not transmit HIV through sex.

vaccine hesitancy: a delay in or refusal of vaccination because of concerns about vaccines.

viral load: the amount of HIV RNA in the blood, used to judge whether antiretroviral therapy is working.

window period: the time between HIV infection and the point when a test can reliably detect it; up to 12 weeks.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mr. Thomas Leblanc (Questions 1–4): Mr. Thomas Leblanc, 58, is admitted to a medical unit with pneumonia. His electronic record lists "penicillin allergy." When the nurse asks about it, he says that at age 16 he had loose stools for two days while taking amoxicillin for an ear infection, and that he has "avoided penicillin ever since." He is treated with a non-penicillin antibiotic and improves. On day 4, he mentions that his family physician started him on a new anticonvulsant 4 weeks ago for nerve pain in his face. That evening his temperature is 38.9 °C, his face and ears are swollen, a widespread rash covers his trunk and arms, and the nurse feels enlarged lymph nodes in his neck. Results from the afternoon show an eosinophil count of 1.6 × 10^9/L and a rise in his liver enzymes.

1. [CORE] Based on Mr. Leblanc's description of what happened when he took amoxicillin, how should the nurse interpret his penicillin label?

a. The reaction suggests a type I allergy, because diarrhea is a common early feature of IgE-mediated drug reactions in teenagers and young adults

b. The reaction he describes is a common side effect, and the label may be inaccurate and worth reviewing with the prescriber

c. The label must be confirmed as a true allergy because any reaction to an antibiotic is recorded as an allergy for life

d. The reaction proves he has a delayed type IV allergy to all beta-lactam antibiotics, including cephalosporins

Answer: b — Diarrhea and other stomach upset with an antibiotic are common side effects, not allergic reactions, so the label may be wrong and can be reviewed for delabelling (b) (section 21.2, Taking and Documenting an Allergy History; Penicillin Allergy Labels). Diarrhea alone is not a feature of a type I reaction (a). Not every reaction is an allergy; recording side effects as allergies causes harm (c). Nothing in his history suggests a type IV reaction, and the history does not justify avoiding a whole drug group (d).

2. [CORE] Which entry should the nurse make in Mr. Leblanc's record about his amoxicillin history?

a. "Penicillin allergy, patient avoids all penicillins; reaction unknown; do not give any antibiotic in this family"

b. "PCN intolerance; mild; please clarify with family physician at discharge and update record when possible"

c. "No known drug allergies; patient's reported penicillin reaction was diarrhea and is therefore not significant"

d. "Amoxicillin, age 16: loose stools for 2 days; no rash, swelling or breathing problems; no treatment"

Answer: d — A useful entry names the drug, describes the reaction, gives its timing and severity, and states what treatment was needed, without abbreviations (d) (section 21.2, Clinical Safety box). Entry (a) keeps a vague label and adds an instruction the history does not support. Entry (b) uses an abbreviation and gives no detail. Entry (c) removes the label on the nurse's own authority; any change to an allergy entry follows the employer's process with the prescriber and patient.

3. [CORE] Which finding in Mr. Leblanc's evening assessment most strongly suggests a severe drug reaction rather than a simple rash?

a. Fever, facial swelling, enlarged lymph nodes, a high eosinophil count and rising liver enzymes 4 weeks after a new drug

b. A rash on the trunk and arms that appeared in the evening, after he had been in bed for most of the afternoon

c. A history of loose stools with amoxicillin as a teenager, which suggests that he reacts to many types of medication

d. Improvement of his pneumonia on a non-penicillin antibiotic, which suggests that his immune system is overactive

Answer: a — A widespread rash with fever, facial swelling, swollen lymph nodes, eosinophilia and liver involvement 2 to 6 weeks after starting a drug fits drug reaction with eosinophilia and systemic symptoms (DRESS), and anticonvulsants are common causes (a) (section 21.2, Severe Cutaneous Adverse Reactions). The timing of the rash in the day (b) is not a warning sign. His amoxicillin history was a side effect and does not predict other reactions (c). Recovery from pneumonia (d) is expected and is not a sign of hypersensitivity.

4. [CORE] What is the nurse's priority action for Mr. Leblanc this evening?

a. Give an oral antihistamine from the as-needed orders and reassess the rash at the next scheduled vital signs

b. Apply a cool compress to the face, document the rash, and report it to the day team at morning handover

c. Report to the prescriber now, hold the next anticonvulsant dose per policy, and escalate if needed

d. Remove the anticonvulsant from his medication list and tell him he must never take it again

Answer: c — A suspected severe drug reaction is reported immediately, the next dose is held according to employer policy pending the prescriber's assessment, and the nurse escalates if the prescriber cannot be reached (c) (section 21.2, Severe Cutaneous Adverse Reactions). An antihistamine (a) does not treat DRESS and delays assessment. Waiting until morning (b) risks organ damage. Stopping a drug permanently and changing the medication list is a prescriber's decision (d); the nurse documents the reaction and reports it.

5. [CORE] A patient asks why a vaccine protects for years but an injection of immune globulin protects only for a while. Which response by the nurse is accurate?

a. "Immune globulin contains live microbes that the body slowly clears, so its effect fades once they are gone."

b. "A vaccine gives you antibodies that were made by other people, and these last much longer than the antibodies your own body makes."

c. "A vaccine trains your own immune system to form memory cells; immune globulin gives borrowed antibodies that wear off."

d. "Immune globulin works only on the innate immune system, which has no memory, so it must be repeated often."

Answer: c — Vaccines create active immunity: the person's own B and T cells respond and leave memory cells. Immune globulin gives passive immunity: ready-made antibodies that act at once but are temporary because no memory cells form (c) (section 21.1). Immune globulin contains antibodies, not microbes (a). Option (b) describes passive immunity, not vaccination. Antibodies are part of adaptive immunity, and the reason for repeat doses is the lack of memory cells, not an effect on innate immunity (d).

6. [CORE] Which antibody class is responsible for type I allergic reactions?

a. IgE

b. IgA

c. IgM

d. IgG

Answer: a — IgE binds to mast cells and basophils and drives type I reactions (a) (section 21.1). IgA protects mucous membranes (b). IgM is the first antibody made in a new response (c). IgG is the main antibody in a repeat response and the only class that crosses the placenta (d).

7. [CORE] An 82-year-old resident of a long-term care home is admitted with new confusion. Her temperature is 37.4 °C. Her daughter says, "She can't have an infection; she doesn't have a fever." Which response by the nurse is best?

a. "You are right that infection is unlikely without a fever, so the team will look first for a medication, stroke or other cause."

b. "A temperature of 37.4 °C is a fever in anyone over 80, so she clearly has an infection."

c. "Confusion in older adults is part of normal aging and does not usually need investigation."

d. "Older adults often have a weaker fever response, so infection can show up first as confusion; we will look for it."

Answer: d — Immunosenescence can blunt fever, and infection in older adults often presents atypically, for example as new confusion, so infection must still be considered (d) (section 21.1, The Aging Immune System). Ruling out infection because of a normal temperature (a) is unsafe. The nurse should not label a single temperature as proof of infection (b). New confusion is never normal aging and needs assessment (c) (Chapter 8).

8. [CORE] Which statement about penicillin allergy labels is accurate?

a. Most people with a penicillin label are truly allergic, so testing is rarely worthwhile in hospital

b. Most people with a penicillin label tolerate penicillin when evaluated, and false labels are linked to harm

c. A penicillin label has no effect on care, because many other antibiotics work equally well for all infections

d. A penicillin label can be removed by the nurse once the patient says the reaction was mild

Answer: b — More than 80% of people reporting penicillin allergy have negative skin tests and about 90% of adult inpatients tolerate penicillin after evaluation; false labels are linked to less effective antibiotics, resistant organisms and C. difficile (b) (section 21.2, Penicillin Allergy Labels). Option (a) is the reverse of the evidence. Alternative antibiotics are not equivalent and add risk (c). Removing a label is a prescriber or allergist decision made through the employer's process (d).

9. [CORE] A patient who has taken an angiotensin-converting enzyme (ACE) inhibitor for 6 years reports that her lower lip and tongue have been swelling over the last hour. She has no hives or itch. What should the nurse conclude?

a. ACE inhibitor angioedema is possible even after years on the drug, and tongue swelling is an airway emergency

b. The swelling cannot be related to her ACE inhibitor, because drug angioedema occurs only in the first week

c. Without hives, the swelling is not an allergic or drug reaction, so it can be reassessed at the next round

d. The swelling is most likely a type IV contact reaction to toothpaste and will settle without treatment

Answer: a — Up to one-third of ACE inhibitor angioedema cases appear months to years after starting the drug, hives are typically absent in bradykinin-mediated angioedema, and tongue swelling can progress to airway obstruction, so the nurse stays with the patient and calls for help at once (a) (section 21.2, Angioedema). Option (b) ignores late cases. The absence of hives does not make swelling harmless (c). A contact reaction is delayed and does not cause tongue swelling over an hour (d).

10. [CORE] Which patient has the highest risk of latex allergy?

a. A 45-year-old office worker with seasonal allergic rhinitis and no surgical history

b. A 30-year-old with a peanut allergy who has never worn gloves at work

c. A 52-year-old operating room nurse with an allergy to avocado and kiwi

d. A 70-year-old who had cataract surgery once and reacts to adhesive tape

Answer: c — Health care workers and people allergic to foods such as banana, avocado, kiwi, passion fruit and chestnut have a higher risk of latex allergy (c) (section 21.2, Latex Allergy). Seasonal rhinitis (a) and peanut allergy (b) are not among the risk factors described in this section, and neither person has a higher-risk occupation. One surgery is not "many surgeries," and a reaction to tape adhesive is not a latex allergy (d).

11. [CORE] On day 12 of a sulfonamide antibiotic, a patient with deeply pigmented skin reports a sore mouth and gritty eyes. The nurse sees no obvious redness of the skin. What should the nurse do next?

a. Reassure the patient that a serious drug reaction is unlikely because the skin shows no redness or swelling

b. Ask the patient to rinse with salt water and recheck the mouth at the end of the shift

c. Document the findings and wait until the course is finished before reporting them

d. Look closely in good light for dusky or darker patches, blisters or ulcers, and report promptly

Answer: d — On darker skin, early SJS/TEN lesions may look darker and less distinct than red, and mouth or eye involvement may be the first clear sign, so the nurse inspects carefully and reports promptly (d) (section 21.2, Severe Cutaneous Adverse Reactions). Absence of redness does not rule out a reaction (a). Delays (b, c) allow a life-threatening reaction to progress.

12. [CORE] An RPN on a medical unit notices that a patient started on carbamazepine 10 days ago now has a fever of 38.8 °C and new blisters on the chest. The patient's next dose is due. Which action is appropriate?

a. Give the dose, because only the physician can decide to stop a drug, and report the findings afterward

b. Hold the dose according to employer policy, notify the RN and prescriber immediately, and document

c. Give half the dose to reduce the risk of reaction while waiting to hear from the prescriber

d. Discontinue the order in the electronic record and add carbamazepine to the allergy list

Answer: b — Fever with blistering after a new high-risk drug suggests SJS/TEN. Every nurse who notices a possible severe reaction acts at once: the RPN holds the dose under employer policy, reports to the RN and prescriber, and documents (b) (section 21.2, Severe Cutaneous Adverse Reactions; Chapter 1, section 1.3). Giving the dose (a) could worsen the reaction. Changing the dose (c) is not within the nurse's authority. Discontinuing an order (d) is the prescriber's decision, although the nurse documents the reaction.

13. [CORE] A patient with a history of anaphylaxis to bee stings is being discharged with an epinephrine autoinjector. Which actions should the nurse include in teaching? Select all that apply.

a. Carry two autoinjectors at all times and wear medical identification

b. Inject into the outer thigh, through clothing if necessary

c. Take an antihistamine first and use the autoinjector only if symptoms worsen

d. Call 9-1-1 after using the autoinjector, even if symptoms improve

e. Store the autoinjector in the refrigerator to protect the medicine

f. Check that the liquid is clear and replace the device before its expiry date

Answer: a, b, d, f — The EpiPen monograph advises carrying two devices and wearing medical identification (a), injecting into the outer thigh, through clothing if needed (b), and checking the liquid and expiry date (f). Patients call 9-1-1 and go to hospital after use, even if they feel better (d) (section 21.2, Patient Education box). Epinephrine is used first at the first sign of a reaction; an antihistamine must never delay it (c). The device is kept at room temperature and must not be refrigerated (e).

14. [CORE] A 34-year-old has had four sinus infections and two pneumonias in the past 18 months, each treated with antibiotics. Which test would the nurse expect the prescriber to order to look for an antibody deficiency?

a. Serum immunoglobulin levels (IgG, IgA and IgM)

b. Serum tryptase drawn within 2 hours of symptoms

c. Skin prick testing to common airborne allergens

d. Patch testing for contact allergens on the back

Answer: a — Repeated sinus and lung infections are warning signs of an antibody deficiency such as common variable immunodeficiency, and serum immunoglobulin levels are measured (a) (sections 21.1 and 21.3). Tryptase helps confirm mast cell activation in suspected anaphylaxis (b). Skin prick testing looks for IgE-mediated allergy (c). Patch testing looks for type IV contact allergy (d).

15. [CORE] A patient receiving a TNF inhibitor every 2 weeks arrives for the next dose. Which finding should the nurse report to the prescriber before giving it?

a. Mild redness at the previous injection site that faded within 2 days

b. A blood pressure of 128/78 mm Hg, unchanged from the last visit

c. A new cough with a temperature of 37.9 °C that began 3 days ago

d. Fatigue after a long work week that has improved with rest

Answer: c — TNF inhibitors raise the risk of serious infections, including TB, and should not be given during an active infection, so a new cough with a raised temperature must be reported before the dose (c) (section 21.3, Recognizing Infection When Immunity Is Low). A resolved local reaction (a), a stable blood pressure (b) and fatigue that improved with rest (d) do not need to delay the dose, although the nurse documents them.

16. [CORE] A man who is about to start a TNF inhibitor asks whether his wife and teenage children should be vaccinated. Which response is consistent with the Canadian Immunization Guide?

a. "Your family should avoid all vaccines while you are on treatment, so they cannot pass anything to you."

b. "Only you need vaccines; your family's immunization status does not affect your risk of infection."

c. "Your family should delay their vaccines until your treatment ends, then catch up all at once."

d. "Your family should keep their vaccines up to date, including a yearly flu shot, to help protect you."

Answer: d — The Canadian Immunization Guide advises vaccinating family members and other close contacts of immunocompromised people and strongly encourages annual influenza vaccination (d) (section 21.3, Nursing Care and Teaching). Avoiding (a) or delaying (c) family vaccines removes a layer of protection. Close contacts' immunity does affect the patient's exposure (b).

17. [CORE] A 68-year-old patient asks whether she is "too old" for the shingles vaccine. Which response by the nurse is accurate?

a. "The shingles vaccine works only before age 60, because the virus is no longer active after that."

b. "NACI recommends the recombinant zoster vaccine for adults aged 50 and older, and it stays effective across older age groups."

c. "Older adults should receive the live zoster vaccine instead, because it works better than the non-live vaccine in people over 70."

d. "Shingles is uncommon after 65, so most older adults do not need to be vaccinated against it."

Answer: b — NACI recommends the recombinant zoster vaccine for adults 50 and older without contraindications, and its effectiveness remains higher across age groups than the live vaccine's (b) (section 21.1, The Aging Immune System). The virus can reactivate at any age, and risk rises with age (a, d). The live vaccine is less effective in adults over 70 (c).

18. [RN] A patient with suspected anaphylaxis to an intravenous antibiotic has received emergency treatment and is now stable. The physician orders a serum tryptase. Which nursing action best supports interpretation of the result?

a. Wait 24 hours so that the tryptase level has time to peak, then draw the sample with morning bloodwork

b. Draw the sample only if the patient's blood pressure falls again, because tryptase rises only with hypotension

c. Ask the laboratory to cancel the test, because a normal tryptase would rule out anaphylaxis and change nothing

d. Draw the sample as soon as possible and record both the time symptoms began and the time the sample was taken

Answer: d — An acute tryptase is drawn as early as possible, ideally within 2 hours after symptoms begin, and compared with a later baseline level, so recording both times is essential (d) (section 21.1, Going Deeper box). A level drawn 24 hours later serves as the baseline, not the acute sample (a). Tryptase is not limited to hypotensive reactions (b). A normal level does not rule out anaphylaxis, but an elevated one supports the diagnosis (c).

19. [RN] **A patient with seasonal allergies asks why her first bee sting caused no reaction but the second caused hives and wheezing. Which explanation is most accurate?**

a. "The first sting led your body to make IgE that coated mast cells; the second sting linked that IgE and the cells released histamine."

b. "The first sting used up your body's histamine, so the second sting caused an overload when your stores were refilled."

c. "Your T cells attacked your own skin cells after the second sting, which takes about two days to cause symptoms."

d. "The second sting contained more venom than the first, so the reaction was simply a larger toxic effect of the venom."

Answer: a — Type I reactions need sensitization: the first exposure leads to IgE that binds mast cells and basophils, and on re-exposure the allergen cross-links IgE and the cells release histamine and other mediators within minutes (a) (section 21.1, Going Deeper box). Histamine depletion (b) is not the mechanism. A T cell-mediated delayed reaction (c) describes type IV. A dose-related toxic effect (d) is not an allergy.

20. [RN] **A patient on an ACE inhibitor has rapidly increasing tongue swelling without hives. The team has given an antihistamine and a corticosteroid, but the swelling is worsening and the patient's voice is now muffled. What is the RN's priority?**

a. Give a second dose of the antihistamine now, because the first dose may not yet have been fully absorbed from the gut

b. Reassure the patient that the corticosteroid will take effect within the next few hours

c. Call for urgent airway support from the rapid response or anesthesia team and prepare for airway management

d. Hold the next ACE inhibitor dose and reassess the swelling at the next scheduled vital signs

Answer: c — ACE inhibitor angioedema is driven by bradykinin, not histamine, so antihistamines and corticosteroids cannot be relied on, and a muffled voice signals airway involvement that can quickly become fatal (c) (section 21.2, Angioedema; Chapter 6). Repeating the antihistamine (a) or waiting for the corticosteroid (b) delays airway care. The ACE inhibitor must be stopped, but waiting until the next vital signs (d) ignores an airway emergency.

Case: Martin Leclerc (Questions 21–26): Martin Leclerc, 44, comes to the emergency department in Kingston, Ontario, with 3 weeks of dry cough, breathlessness that is worse on stairs, evening fevers and a 6-kg weight loss. He has no known medical conditions and has never had an HIV test. At rest: temperature 38.4 °C, heart rate 106, respiratory rate 26, blood pressure 118/72 mm Hg, SpO2 93% on room air. After walking 30 m, his SpO2 falls to 85%. White plaques cover his tongue and the inside of his cheeks. A chest x-ray shows diffuse haziness in both lungs.

21. [CORE] **The nurse reviews Martin's assessment. Which findings are cues that need follow-up? Select all that apply.**

a. SpO2 falling from 93% to 85% after walking 30 m

b. Respiratory rate of 26 breaths per minute at rest

c. White plaques on the tongue and inside the cheeks

d. Blood pressure of 118/72 mm Hg

e. Weight loss of 6 kg over 3 weeks

f. No known medical conditions

Answer: a, b, c, e — A sharp drop in SpO2 with exertion (a) and a fast respiratory rate at rest (b) show impaired gas exchange, a typical pattern in Pneumocystis pneumonia (section 21.5). White plaques suggest oral candidiasis (c), and unexplained weight loss (e) is a sign of a serious underlying illness; both raise the possibility of a weakened immune system (sections 21.4 and 21.5). His blood pressure (d) is within normal limits. Having no known medical conditions (f) is history, not a finding that needs follow-up, although it is consistent with undiagnosed HIV.

22. [RN] **Martin's arterial blood gas on room air shows pH 7.48, PaCO2 30 mm Hg, $HCO3^-$ 23 mmol/L and PaO2 58 mm Hg. How should the nurse interpret these results?**

a. Metabolic alkalosis with partial respiratory compensation, and adequate oxygenation for his age

b. Respiratory acidosis caused by hypoventilation, with hypoxemia that needs oxygen therapy

c. Respiratory alkalosis from rapid breathing, with hypoxemia that needs oxygen therapy

d. Metabolic acidosis with full respiratory compensation, with mild hypoxemia on room air

Answer: c — The pH is high and the PaCO2 is low, so the alkalosis is respiratory: Martin is breathing fast because he is hypoxemic, and the bicarbonate is normal, so the kidneys have not compensated (c). A PaO2 of 58 mm Hg is hypoxemia. Option a is wrong because the bicarbonate is normal, not raised, and oxygenation is not adequate. Option b is wrong because a low PaCO2 reflects hyperventilation, not hypoventilation. Option d is wrong because the pH is alkalotic, not acidotic, and the bicarbonate is normal (section 21.5; Chapter 3 covers acid–base balance).

23. [CORE] Considering all of Martin's findings, which hypothesis should the nurse rank highest?

a. Pneumocystis pneumonia linked to an immune deficiency that has not yet been diagnosed, such as HIV

b. Heart failure with fluid in both lungs, causing breathlessness when he climbs stairs

c. An asthma exacerbation set off by a viral cold, causing a cough and low oxygen levels

d. A pulmonary embolism from reduced mobility, causing sudden chest pain and breathlessness on exertion

Answer: a — A subacute dry cough, fever, weight loss, oxygen saturation that drops with exertion, diffuse changes in both lungs and oral thrush together point to Pneumocystis pneumonia in a person with an undiagnosed immune deficiency, most often HIV (a; sections 21.4 and 21.5). Heart failure (b) does not explain the fever, thrush and weight loss. Asthma (c) usually causes wheeze and does not explain the thrush or weight loss. A pulmonary embolism (d) usually begins suddenly, and Martin's illness developed over 3 weeks with no reported immobility.

24. [CORE] Martin agrees to HIV testing, and the fourth-generation test is reactive; confirmatory testing is under way. His CD4 count is 80 cells/µL, and induced sputum confirms Pneumocystis pneumonia. Intravenous trimethoprim-sulfamethoxazole and oxygen are ordered. Which actions should the nurse include in the plan of care? Select all that apply.

a. Give oxygen as ordered and titrate it to the ordered SpO2 target

b. Wear double gloves and a gown for all contact because he is living with HIV

c. Before the first dose, ask about any sulfonamide allergy and confirm the order with the pharmacist

d. Cluster care and pace activities to limit drops in oxygen saturation with exertion

e. Tell his sister about the HIV result when she visits so that she can support him

f. Offer a private space for his questions and connect him with the HIV care team and peer support

Answer: a, c, d, f — Oxygen titrated to the ordered target (a) and pacing activity (d) address impaired gas exchange (section 21.5). Trimethoprim-sulfamethoxazole is a sulfonamide, so checking allergies and confirming the order before the first dose is safe practice (c; section 21.2 covers allergy histories). Privacy, time for questions and early links to HIV care and peer support are part of good care after a new diagnosis (f; sections 21.4 and 21.5). Routine practices are all that HIV requires; double gloves and a gown for all contact are unnecessary and stigmatizing (b). Disclosure is Martin's decision, and telling his sister without consent breaches his privacy (e; section 21.5; Chapter 1).

25. [CORE] On the evening of day 2, Martin's respiratory rate is 34, his SpO2 is 86% on 4 L/min by nasal prongs, he is using his neck muscles to breathe, and he is newly confused. What should the nurse do first?

a. Let him rest for 30 minutes and recheck his vital signs before making any calls about the change

b. Increase oxygen within the ordered range and escalate at once by calling the rapid response team

c. Hold the next dose of trimethoprim-sulfamethoxazole, since the drug may be causing the breathlessness

d. Give the as-needed lorazepam that is ordered for anxiety, since he is restless and confused tonight

Answer: b — Rising respiratory rate, falling SpO2, accessory muscle use and new confusion are signs of respiratory failure. The nurse acts within the order to improve oxygenation and escalates immediately, using the rapid response team or the facility's escalation process (b; Chapter 6). Waiting to recheck (a) delays care for a deteriorating patient. Holding the antimicrobial (c) withholds treatment for the cause of his illness without an order. A sedative (d) can depress breathing and mask worsening hypoxemia, which is likely causing the confusion.

26. [CORE] Martin is treated in the intensive care unit and returns to the medical unit. Which finding on day 9 best shows that his treatment is working?

a. His CD4 count has risen to 350 cells/µL since admission

b. He says he is less worried about his diagnosis than before

c. A repeat HIV test is still reactive and his viral load is high

d. His SpO2 stays at 95% on room air while he walks the hallway

Answer: d — The main problem in Pneumocystis pneumonia is hypoxemia, especially with exertion, so a normal SpO2 on room air while walking shows that gas exchange has improved (d; section 21.5). CD4 counts recover slowly after ART starts, often by about 50 to 150 cells/µL in the first year, so a rise to 350 cells/µL within days (a) is not expected and does not measure the pneumonia. Reduced worry (b) is welcome but does not show that the infection is resolving. A reactive HIV test and high viral load (c) are expected before ART takes effect and do not reflect the pneumonia.

27. [CORE] The nurse is teaching the partner of a man who is living with HIV. Which statement by the partner shows correct understanding of how HIV is transmitted?

a. "I should use a separate bathroom from him at home to keep myself safe from HIV."

b. "We can hug and share food, because HIV is not spread by everyday contact."

c. "I could get HIV from kissing him, so I should avoid kissing him on the mouth."

d. "Mosquitoes could carry HIV from him to me during the summer when we're outside."

Answer: b — HIV spreads through blood, semen, vaginal and rectal fluids and human milk, not through casual contact such as hugging or sharing food (b; section 21.4). Toilet seats (a) do not transmit HIV, so a separate bathroom is not needed. Kissing (c) is casual contact that does not transmit HIV. Mosquitoes (d) do not transmit HIV.

28. [CORE] A woman had condomless sex with a new partner 10 days ago. A fourth-generation HIV test today is non-reactive. Which response by the nurse is correct?

a. "This result rules out HIV, so you do not need any further testing for this exposure."

b. "A fourth-generation test only detects older infections, so we should also do a rapid test today."

c. "You should start post-exposure prophylaxis today, because it works best after 10 days."

d. "The test may not detect a very recent infection yet, so we'll repeat it later on."

Answer: d — The window period can last up to 12 weeks, so a non-reactive test 10 days after an exposure needs to be repeated (d; section 21.4). A single early negative test does not rule out HIV (a). Fourth-generation tests detect infection earlier than rapid antibody tests, not later (b). Post-exposure prophylaxis must start within 72 hours of the exposure, so at 10 days it is too late (c).

29. [CORE] A man calls the clinic 30 hours after condomless anal sex with a partner whose HIV status is unknown. What is the nurse's best response?

a. "Please come in now. Medication to prevent HIV can still be started, and it should begin as soon as possible."

b. "It is too late for preventive medication. Please come in for an HIV test 12 weeks after the exposure."

c. "Ask your partner to get tested first. If their result is positive, we can start medication at that point."

d. "Book your next routine visit, and we can talk then about daily pre-exposure prophylaxis to prevent HIV."

Answer: a — Post-exposure prophylaxis can be started up to 72 hours after an exposure and works best when started as soon as possible, so 30 hours is still within the window (a; section 21.4). Telling him it is too late (b) is incorrect. Waiting for the partner's result (c) or for a routine visit (d) could push him past the 72-hour limit, although PrEP may be discussed later.

30. [CORE] A patient who has lived with HIV for 8 years asks whether he can pass HIV to his partner through sex. His viral load has been below 200 copies/mL on every test for 3 years. What should the nurse explain?

a. "HIV can still pass on through sex, so your partner will need to take pre-exposure prophylaxis daily."

b. "Your risk is low but not zero, so you should only have sex after your next viral load test."

c. "You will not pass HIV on through sex while you take treatment and your viral load stays suppressed."

d. "Your treatment has cured the HIV, so you no longer need to have your viral load tested every year."

Answer: c — PHAC describes U=U as the scientific consensus that a person who takes ART as prescribed does not pass HIV on through sex while keeping a viral load below 200 copies/mL, checked every 4 to 6 months (c; section 21.4). The partner does not need PrEP to prevent sexual transmission (a). Timing sex around tests (b) is not needed, because protection depends on ongoing suppression. A suppressed viral load is not a cure, and regular testing continues (d).

31. [CORE] A patient is starting daily oral pre-exposure prophylaxis. Which follow-up tests does the Canadian guideline call for? Select all that apply.

a. HIV test 30 days after starting and then every 3 months

b. Serum creatinine to monitor kidney function

c. Screening for gonorrhea, chlamydia and syphilis

d. CD4 count every 3 months

e. Hepatitis B testing at baseline and yearly if susceptible

f. Chest x-ray every 6 months

Answer: a, b, c, e — The 2025 Canadian guideline calls for HIV testing at baseline, at 30 days and then every 3 months on oral PrEP (a), creatinine monitoring (b), screening for sexually transmitted infections every 3 to 4 months (c) and hepatitis B testing at baseline and yearly for people who remain susceptible (e) (section 21.4). CD4 counts (d) monitor the immune system in people living with HIV, not in people taking PrEP. Routine chest x-rays (f) are not part of PrEP monitoring.

32. [CORE] An RPN is caring for a patient living with HIV who will have nothing by mouth before surgery tomorrow. The patient's once-daily ART is due at 0800. What should the RPN do?

a. Skip the 0800 dose, since a single missed dose of ART is harmless, and give it after surgery when he eats

b. Ask the RN and the prescriber, with the pharmacist, how to give the dose before 0800 rather than omit it

c. Give the ART dose with a full glass of water and a snack, since the medication must be taken with food

d. Tell the patient to bring his own supply from home and decide himself when to take it after surgery

Answer: b — ART is never stopped or interrupted without a prescriber's order, and doses are given on time; the RPN consults the RN and prescriber and involves the pharmacist when a patient cannot take anything by mouth (b; section 21.5). Missed doses can lead to resistance, so skipping (a) is unsafe. Giving food (c) breaks the order to have nothing by mouth. Leaving the decision to the patient (d) does not address the order or medication safety.

33. [CORE] An RPN working in a community clinic in Ontario is asked to give a Tdap vaccine to an adult. What does the RPN need before giving it?

a. Nothing further, because Tdap is a routine vaccine that any nurse may give on their own judgment

b. Nothing, because RPNs are not authorized to give vaccines, and the RN must give every injection

c. A prescription written by an authorized RN prescriber, because only RN prescribers can order a vaccine

d. An order from an authorized professional, the competence to give it safely and employer support

Answer: d — In Ontario, giving a vaccine by injection is a controlled act; RNs and RPNs may carry it out with an order (a direct order or a directive) from an authorized health care professional, when they are competent, including in managing anaphylaxis, and the setting supports it (d; Scope in Practice box, section 21.6). A nurse cannot give it on their own judgment without an order (a). RPNs are authorized with an order (b). Physicians, nurse practitioners and other authorized prescribers can order vaccines, not only RN prescribers (c).

34. [CORE] The clinic's vaccine refrigerator reads 11 °C when the nurse arrives in the morning. What should the nurse do?

a. Give the vaccines today before they lose any more potency, and then call to have the refrigerator repaired

b. Move the vaccines to the freezer to bring them back down to the right temperature more quickly

c. Label the vaccines "do not use", keep them refrigerated and contact public health or the supplier

d. Throw out all the vaccines right away and order a new supply from the local public health unit

Answer: c — Refrigerated vaccines must stay between +2 °C and +8 °C. After a cold chain break, the nurse sets the vaccines apart, labels them "do not use", keeps them cold and asks public health or the supplier whether they can be used (c; section 21.6). Giving them (a) risks giving ineffective vaccine. Freezing (b) can damage vaccines. Throwing them out (d) may waste usable vaccine before their integrity has been assessed.

35. [CORE] A 62-year-old patient with rheumatoid arthritis is about to start a biologic drug that suppresses the immune system. She asks whether she can get the shingles vaccine. What should the nurse tell her?

a. "The recombinant zoster vaccine is non-live and is recommended for adults who are or will be immunocompromised."

b. "All shingles vaccines are live vaccines, so you will never be able to have one while you take your arthritis drug."

c. "You only need a shingles vaccine if you have had shingles before, so ask your family to check your history."

d. "You will need to wait until after your 65th birthday, because the vaccine is not recommended before that age."

Answer: a — The Canadian Immunization Guide recommends two doses of recombinant zoster vaccine for adults aged 50 and older and for adults 18 and older who are or will be immunocompromised; it is non-live and ideally given before immunosuppression starts (a; sections 21.3 and 21.6). The recombinant vaccine is not live (b). A past episode of shingles is not a requirement (c). Ontario funds the vaccine at ages 65 to 70, but the recommendation begins at age 50, and earlier for immunocompromised adults (d).

36. [CORE] A nurse hears a colleague at the nursing station tell a visitor, "Be careful in room 8, he has AIDS." What should the nurse do first?

a. Put a sign on the door of room 8 so that all visitors know to take extra precautions

b. Tell the visitor that HIV is not easily spread, and leave the matter there to avoid conflict with the colleague

c. Write an incident report and avoid speaking with the colleague directly about what was said

d. Ask the colleague to talk privately, and address the breach of privacy and the stigmatizing words

Answer: d — The colleague disclosed personal health information and used stigmatizing language. The nurse addresses it promptly and privately, and involves the charge nurse or manager under policy if needed (d; section 21.5; Chapter 1). A sign (a) adds a further breach and implies precautions that HIV does not need. Reassuring the visitor (b) does not stop the breach from happening again. An incident report may be needed under policy, but avoiding the colleague (c) misses the chance to stop the behaviour.

37. [CORE] A patient says, "I'm not sure about vaccines. I read that they cause more problems than they prevent." Which response by the nurse best follows the Canadian Immunization Guide's advice?

a. "That's misinformation. The science is settled, so you should get your vaccines today."

b. "Can you tell me more about what you read and what worries you most about vaccines?"

c. "If you don't get vaccinated, I'll need to note in your chart that you refused my advice."

d. "Many people feel that way at first, so let's skip vaccines for now and not talk about it."

Answer: b — The guide advises finding the source of a person's hesitancy, listening without judgment and clarifying why a belief is held before offering clear information (b; section 21.6). Dismissing the concern (a) or using pressure (c) damages trust. Dropping the subject (d) misses the chance to give accurate information, although the person's final decision is respected.

38. [RN] A patient has taken ART for 2 years with an undetectable viral load. Today's viral load is 640 copies/mL, and a repeat test 4 weeks later is 710 copies/mL. Which interpretation and next step are correct?

a. This is a viral blip, so the nurse reassures the patient and plans the next routine viral load test in 6 months

b. This shows the regimen is working, because any viral load below 1,000 copies/mL counts as suppressed

c. This is virologic rebound, so the nurse explores adherence and interactions and expects resistance testing

d. This is immune reconstitution inflammatory syndrome, so the nurse expects the prescriber to stop ART

Answer: c — A confirmed viral load of 200 copies/mL or more after suppression is virologic rebound, a form of virologic failure. The nurse explores missed doses and new interacting drugs, and resistance testing is done, ideally while the person is still on the regimen (c; section 21.5, Going Deeper box). A blip (a) is a single detectable result that returns to undetectable. Suppression is defined well below 1,000 copies/mL (b). IRIS (d) is an inflammatory reaction soon after ART starts, and ART is not stopped without a prescriber's order.

39. [RN] Which patient living with HIV meets the current DHHS indication for primary Pneumocystis pneumonia prophylaxis with trimethoprim-sulfamethoxazole?

a. A newly diagnosed adult with a CD4 count of 150 cells/µL who is starting ART this week

b. An adult on ART for 2 years with a CD4 count of 260 cells/µL and a suppressed viral load

c. An adult on ART for 5 years whose CD4 count has stayed above 350 cells/µL for 3 years

d. A newly diagnosed adult with a CD4 count of 420 cells/µL who is starting ART this month

Answer: a — The DHHS guideline recommends prophylaxis for adults with a CD4 count below 200 cells/µL who are not on ART or are starting it (a; section 21.5). People on ART whose CD4 count is 200 cells/µL or more (b, c) do not need prophylaxis; for people on ART, prophylaxis is started if the count falls below 100 cells/µL, or to 100 to 200 cells/µL with a rising viral load. A CD4 count of 420 cells/µL (d) is above the threshold.

40. [RN] A patient who takes rilpivirine as part of their ART is admitted with gastrointestinal bleeding. An order for intravenous pantoprazole is written. What should the nurse do?

a. Give the pantoprazole now and give the rilpivirine 4 hours later, so that the two doses are separated in time

b. Hold the pantoprazole and call the prescriber and pharmacist, because it is contraindicated with rilpivirine

c. Give the pantoprazole and hold the rilpivirine until discharge, since ART can be paused safely in hospital

d. Give the pantoprazole as ordered, since an intravenous drug cannot interact with an oral antiretroviral regimen

Answer: b — The rilpivirine monograph lists proton pump inhibitors as contraindicated because raising gastric pH lowers rilpivirine levels and risks treatment failure and resistance; the nurse holds the dose and contacts the prescriber and pharmacist so a safe alternative can be chosen (b; section 21.5). Spacing the doses (a) is the advice for antacids and H2-receptor antagonists, not proton pump inhibitors. ART is never paused without a prescriber's order (c). The interaction depends on gastric acid suppression, not on the route of the acid suppressant (d).

References

AbbVie Corporation. (2022). *Humira (adalimumab injection)* [Product monograph]. https://www.abbvie.ca/content/dam/abbvie-dotcom/ca/en/documents/products/HUMIRA_PM_EN.pdf

Akinbisehin, R., Ufodiama, C., & Sommerlad, M. (2026). Dermatology emergencies in skin of colour patients. *British Journal of Hospital Medicine, 87*(3), Article 52245. https://doi.org/10.31083/BJHM52245

Association des allergologues et immunologues du Québec. (2020). *Anaphylaxis emergency plan* [Form]. Canadian Society of Allergy and Clinical Immunology. https://csaci.ca/wp-content/uploads/2020/08/Anaphylaxis_Emergency_Plan_with_EpiPen_and_ALLERJECT_instructions_May-2020_a.pdf

Baribeau, V., Kim, C. J., Lorgeoux, R.-P., Brisebois, J., Tossonian, H., & Lachaine, J. (2022). Healthcare resource utilization and costs associated with renal, bone and cardiovascular comorbidities among persons living with HIV compared to the general population in Quebec, Canada. *PLoS ONE, 17*(7), Article e0262645. https://doi.org/10.1371/journal.pone.0262645

Blumenthal, K. G., Lu, N., Zhang, Y., Li, Y., Walensky, R. P., & Choi, H. K. (2018). Risk of meticillin resistant *Staphylococcus aureus* and *Clostridium difficile* in patients with a documented penicillin allergy: Population based matched cohort study. *BMJ, 361*, Article k2400. https://doi.org/10.1136/bmj.k2400

Campbell, J. R., Pease, C., Daley, P., Pai, M., & Menzies, D. (2022). Chapter 4: Diagnosis of tuberculosis infection. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 6*(sup1), 49–65. https://doi.org/10.1080/24745332.2022.2036503

Canadian Centre for Occupational Health and Safety. (2023). *Latex allergy*. https://www.ccohs.ca/oshanswers/diseases/latex.html

Cardona, V., Ansotegui, I. J., Ebisawa, M., El-Gamal, Y., Fernandez Rivas, M., Fineman, S., Geller, M., Gonzalez-Estrada, A., Greenberger, P. A., Sanchez Borges, M., Senna, G., Sheikh, A., Tanno, L. K., Thong, B. Y., Turner, P. J., & Worm, M. (2020). World Allergy Organization anaphylaxis guidance 2020. *World Allergy Organization Journal, 13*(10), Article 100472. https://doi.org/10.1016/j.waojou.2020.100472

College of Nurses of Ontario. (2025). *Directives* [Practice guideline]. https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41019_medicaldirectives.pdf

College of Nurses of Ontario. (n.d.-a). *Administering Botox*. https://www.cno.org/standards-learning/practice-support/practice-support-faqs/administering-botox

College of Nurses of Ontario. (n.d.-b). *RN prescribing drug list*. https://www.cno.org/standards-learning/rn-prescribing/rn-prescribing-drug-list

Community Legal Education Ontario. (2022). *HIV testing and reporting to Public Health in Ontario*. https://www.cleo.on.ca/en/publications/hivtest/all

Conrad, N., Misra, S., Verbakel, J. Y., Verbeke, G., Molenberghs, G., Taylor, P. N., Mason, J., Sattar, N., McMurray, J. J. V., McInnes, I. B., Khunti, K., & Cambridge, G. (2023). Incidence, prevalence, and co-occurrence of autoimmune disorders over time and by age, sex, and socioeconomic status: A population-based cohort study of 22 million individuals in the UK. *The Lancet, 401*(10391), 1878–1890. https://doi.org/10.1016/S0140-6736(23)00457-9

Creamer, D., Walsh, S. A., Dziewulski, P., Exton, L. S., Lee, H. Y., Dart, J. K. G., Setterfield, J., Bunker, C. B., Ardern-Jones, M. R., Watson, K. M. T., Wong, G. A. E., Philippidou, M., Vercueil, A., Martin, R. V., Williams, G., Shah, M., Brown, D., Williams, P., Mohd Mustapa, M. F., … Brain, A. G. (2016). U.K. guidelines for the management of Stevens–Johnson syndrome/toxic epidermal necrolysis in adults 2016. *British Journal of Dermatology, 174*(6), 1194–1227. https://doi.org/10.1111/bjd.14530

Department of Justice Canada. (2018, December 1). *Attorney General of Canada to issue directive regarding prosecutions of HIV non-disclosure cases* [News release]. https://www.canada.ca/en/department-justice/news/2018/12/attorney-general-of-canada-to-issue-directive-regarding-prosecutions-of-hiv-non-disclosure-cases.html

Department of Justice Canada. (2022). *HIV non-disclosure*. https://justice.gc.ca/eng/cons/hiv-vih/nd.html

Ellis, A. K., Cook, V., Keith, P. K., Mace, S. R., Moote, W., O'Keefe, A., Quirt, J., Rosenfield, L., Small, P., & Watson, W. (2024). Focused allergic rhinitis practice parameter for Canada. *Allergy, Asthma & Clinical Immunology, 20*(1), Article 45. https://doi.org/10.1186/s13223-024-00899-3

Gilead Sciences Canada. (2025). *Biktarvy (bictegravir/emtricitabine/tenofovir alafenamide) tablets* [Product monograph]. https://pdf.hres.ca/dpd_pm/00078536.PDF

Golden, D. B. K., Wang, J., Waserman, S., Akin, C., Campbell, R. L., Ellis, A. K., Greenhawt, M., Lang, D. M., Ledford, D. K., Lieberman, J., Oppenheimer, J., Shaker, M. S., Wallace, D. V., Abrams, E. M., Bernstein, J. A., Chu, D. K., Horner, C. C., Rank, M. A., & Stukus, D. R. (2024). Anaphylaxis: A 2023 practice parameter update. *Annals of Allergy, Asthma & Immunology, 132*(2), 124–176. https://doi.org/10.1016/j.anai.2023.09.015

Government of Ontario. (2025, June 27). *HIV and AIDS in Ontario*. https://www.ontario.ca/page/hiv-and-aids-ontario

Government of Ontario. (2026, August 4). *Ontario's routine immunization schedule*. https://www.ontario.ca/page/ontarios-routine-immunization-schedule

Health Canada. (n.d.-a). *Drug and medical device highlights 2020: Medical devices*. https://www.canada.ca/en/health-canada/services/publications/drugs-health-products/drug-medical-device-highlights-2020/medical-devices.html

Health Canada. (n.d.-b). *Drug Product Database online query*. Retrieved October 26, 2026, from https://health-products.canada.ca/dpd-bdpp/

Institute for Safe Medication Practices Canada. (2016). Allergy never events. *ISMP Canada Safety Bulletin, 16*(10). https://ismpcanada.ca/wp-content/uploads/ISMPCSB2016-10-AllergyNeverEvents.pdf

Janssen Inc. (2023a). *Edurant (rilpivirine) tablets* [Product monograph]. https://pdf.hres.ca/dpd_pm/00069229.PDF

Janssen Inc. (2023b). *Prezcobix (darunavir/cobicistat) tablets* [Product monograph]. https://pdf.hres.ca/dpd_pm/00069794.PDF

Kanani, A., Betschel, S. D., & Warrington, R. (2018). Urticaria and angioedema. *Allergy, Asthma & Clinical Immunology, 14*(Suppl 2), Article 59. https://doi.org/10.1186/s13223-018-0288-z

Krishnan, R., Baclic, O., Howarth, A., Tuite, A. R., & Andrew, M. K. (2026). Summary of the National Advisory Committee on Immunization (NACI) statement: Updated recommendations on herpes zoster vaccination for adults who are immunocompromised. *Canada Communicable Disease Report, 52*(1/2), 1–7. https://doi.org/10.14745/ccdr.v52i0102a01

Marshall, J. S., Warrington, R., Watson, W., & Kim, H. L. (2018). An introduction to immunology and immunopathology. *Allergy, Asthma & Clinical Immunology, 14*(Suppl 2), Article 49. https://doi.org/10.1186/s13223-018-0278-1

McCusker, C., Upton, J., & Warrington, R. (2018). Primary immunodeficiency. *Allergy, Asthma & Clinical Immunology, 14*(Suppl 2), Article 61. https://doi.org/10.1186/s13223-018-0290-5

Mylan Specialty. (2024). *EpiPen and EpiPen Jr (epinephrine injection USP) auto-injectors* [Product monograph]. https://pdf.hres.ca/dpd_pm/00075941.PDF

National Advisory Committee on Immunization. (2018). *Updated recommendations on the use of herpes zoster vaccines*. Public Health Agency of Canada. https://www.canada.ca/en/services/health/publications/healthy-living/updated-recommendations-use-herpes-zoster-vaccines.html

North Bay Parry Sound District Health Unit. (2025). *Routine publicly funded immunization schedule for Ontario – Spring 2025*. https://www.myhealthunit.ca/en/health-professionals-and-partners/resources/Health-Care-Professionals/Publicly-Funded-Immunization-Schedule-for-Ontario---Spring-2025.pdf

Ontario Medical Association Section on Allergy. (2025). *Pathways to appropriate penicillin allergy (de)labelling: Support tool for primary care physicians* (Version 2). https://www.oma.org/siteassets/oma/media/pagetree/pps/running/news/pathways-to-appropriate-penicillin-allergy-delabelling.pdf

Ontario Ministry of Health. (2022). *Publicly funded immunization schedules for Ontario – June 2022*. https://www.ontario.ca/files/2024-01/moh-publicly-funded-immunization-schedule-en-2024-01-23.pdf

Panel on Antiretroviral Guidelines for Adults and Adolescents. (2025). *Guidelines for the use of antiretroviral agents in adults and adolescents with HIV*. U.S. Department of Health and Human Services. https://clinicalinfo.hiv.gov/en/guidelines/hiv-clinical-guidelines-adult-and-adolescent-arv

Panel on Antiretroviral Guidelines for Adults and Adolescents. (n.d.). Plasma HIV-1 RNA (viral load) and CD4 count monitoring. In *Guidelines for the use of antiretroviral agents in adults and adolescents with HIV*. U.S. Department of Health and Human Services. https://clinicalinfo.hiv.gov/en/node/9252

Panel on Opportunistic Infections in Adults and Adolescents With HIV. (2025a). Cytomegalovirus disease. In *Guidelines for the prevention and treatment of opportunistic infections in adults and adolescents with HIV*. U.S. Department of Health and Human Services. https://clinicalinfo.hiv.gov/en/guidelines/hiv-clinical-guidelines-adult-and-adolescent-opportunistic-infections/cytomegalovirus

Panel on Opportunistic Infections in Adults and Adolescents With HIV. (2025b). Toxoplasma gondii encephalitis. In *Guidelines for the prevention and treatment of opportunistic infections in adults and adolescents with HIV*. U.S. Department of Health and Human Services. https://clinicalinfo.hiv.gov/en/guidelines/hiv-clinical-guidelines-adult-and-adolescent-opportunistic-infections/toxoplasma-gondii

Panel on Opportunistic Infections in Adults and Adolescents With HIV. (2026). Pneumocystis pneumonia. In *Guidelines for the prevention and treatment of opportunistic infections in adults and adolescents with HIV*. U.S. Department of Health and Human Services. https://clinicalinfo.hiv.gov/en/guidelines/hiv-clinical-guidelines-adult-and-adolescent-opportunistic-infections/pneumocystis

Pelletier, J., Bergeron, D., Rouleau, G., & Guillaumie, L. (2022). Nurses' clinical practices reducing the impact of HIV-related stigmatisation in non-HIV-specialised healthcare settings: A protocol for a realist synthesis. *BMJ Open, 12*(11), Article e062569. https://doi.org/10.1136/bmjopen-2022-062569

Public Health Agency of Canada. (2013). *Human immunodeficiency virus: HIV screening and testing guide*. https://www.canada.ca/en/public-health/services/hiv-aids/hiv-screening-testing-guide.html

Public Health Agency of Canada. (2020). *Approach to HIV screening*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/hiv-factsheet-types-screening-tests.html

Public Health Agency of Canada. (2023a). *Hepatitis A vaccines: Canadian Immunization Guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-4-active-vaccines/page-6-hepatitis-a-vaccine.html

Public Health Agency of Canada. (2023b). *Preventing HIV transmission: Undetectable = Untransmittable (U=U) for health professionals*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/preventing-hiv-transmission-undetectable-equals-untransmittable-health-professionals-fact-sheet.html

Public Health Agency of Canada. (2024a). *Canada's progress towards ending the HIV epidemic*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/canada-progress-towards-ending-hiv-epidemic.html

Public Health Agency of Canada. (2024b). *Government of Canada's sexually transmitted and blood-borne infections (STBBI) action plan 2024–2030*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/sexually-transmitted-blood-borne-infections-action-plan-2024-2030.html

Public Health Agency of Canada. (2025a). *Communicating effectively about immunization: Canadian Immunization Guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-1-key-immunization-information/page-5-communicating-effectively-immunization.html

Public Health Agency of Canada. (2025b). *HIV and AIDS: Prevention and risks*. https://www.canada.ca/en/public-health/services/diseases/hiv-aids/prevention-risks.html

Public Health Agency of Canada. (2025c). *HIV and AIDS: Symptoms and treatment*. https://www.canada.ca/en/public-health/services/diseases/hiv-aids.html

Public Health Agency of Canada. (2025d). *STBBI prevention guide: Screening and diagnostic testing*. https://www.canada.ca/en/public-health/services/infectious-diseases/sexual-health-sexually-transmitted-infections/canadian-guidelines/stbbi-prevention-guide/screening-diagnostic-testing.html

Public Health Agency of Canada. (2026a, September 10). *Government of Canada expands access to HIV self-testing and peer support services* [News release]. https://www.canada.ca/en/public-health/news/2026/09/government-of-canada-expands-access-to-hiv-self-testing-and-peer-support-services.html

Public Health Agency of Canada. (2026b). *Hepatitis B vaccines: Canadian Immunization Guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-4-active-vaccines/page-7-hepatitis-b-vaccine.html

Public Health Agency of Canada. (2026c). *HIV in Canada, surveillance report to December 31, 2024: Executive summary*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/hiv-canada-surveillance-report-december-31-2024-executive-summary.html

Public Health Agency of Canada. (2026d). *Immunization of adults: Canadian Immunization Guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-3-vaccination-specific-populations/page-2-immunization-of-adults.html

Public Health Agency of Canada. (2026e). *Immunization of immunocompromised persons: Canadian Immunization Guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-3-vaccination-specific-populations/page-8-immunization-immunocompromised-persons.html

Public Health Agency of Canada. (2026f). *Storage and handling of immunizing agents: Canadian Immunization Guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-1-key-immunization-information/page-9-storage-handling-immunizing-agents.html

Public Health Agency of Canada. (2026g). *Vaccine administration practices: Canadian Immunization Guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-1-key-immunization-information/page-8-vaccine-administration-practices.html

Public Health Ontario. (2026). *Vaccine safety*. https://www.publichealthontario.ca/en/Health-Topics/Immunization/Vaccine-Safety

Rosenbaum, S. B., Wilkerson, R. G., & Winters, M. (2020). *Clinical practice statement: What is the emergency department management of patients with angioedema secondary to an ACE-inhibitor?* American Academy of Emergency Medicine. https://www.aaem.org/wp-content/uploads/2023/05/111920FAngiofrPost.pdf

Saravanabavan, S., Aulakh, A., Douglas, J., Elwood, C., Erdle, S., Grant, J., Kang, K. T., Kwan, N., Lacaria, K., Lau, T. T. Y., Lee, C., Leung, V., Lin, Y. C., Mah, A., Nguyen, A., Paquette, V., Roberts, A., Watt, M., Van Schalkwyk, J., … Wong, T. (2023). Penicillin de-labelling in Vancouver, British Columbia, Canada: Comparison of approaches, outcomes and future directions. *Allergy, Asthma & Clinical Immunology, 19*(1), Article 30. https://doi.org/10.1186/s13223-023-00777-4

Selik, R. M., Mokotoff, E. D., Branson, B., Owen, S. M., Whitmore, S., & Hall, H. I. (2014). Revised surveillance case definition for HIV infection—United States, 2014. *MMWR Recommendations and Reports, 63*(RR-03), 1–10. https://www.cdc.gov/mmwr/preview/mmwrhtml/rr6303a1.htm

Tan, D. H. S., Hull, M. W., Onyegbule, S. O., Ajiboye, W., Arkell, C., Baril, J.-G., Cox, J., Harris, M., Kelly, D., Kwag, M., Lambert, G., O'Byrne, P., O'Donnell, S., Shukalek, C. B., Singh, A., Sotindjo, T., Swidrovich, J., Tremblay, C., & Yoong, D. (2025). Canadian guideline on HIV pre- and postexposure prophylaxis: 2025 update. *CMAJ, 197*(41), E1374–E1391. https://doi.org/10.1503/cmaj.250511

Trubiano, J. A., Vogrin, S., Chua, K. Y. L., Bourke, J., Yun, J., Douglas, A., Stone, C. A., Yu, R., Groenendijk, L., Holmes, N. E., & Phillips, E. J. (2020). Development and validation of a penicillin allergy clinical decision rule. *JAMA Internal Medicine, 180*(5), 745–752. https://doi.org/10.1001/jamainternmed.2020.0403

ViiV Healthcare ULC. (2023). *Triumeq (dolutegravir, abacavir and lamivudine) tablets* [Product monograph]. https://pdf.hres.ca/dpd_pm/00071492.PDF

ViiV Healthcare ULC. (2025a). *Dovato (dolutegravir and lamivudine) tablets* [Product monograph]. https://pdf.hres.ca/dpd_pm/00082174.PDF

ViiV Healthcare ULC. (2025b). *Vocabria (cabotegravir tablets) and Cabenuva (cabotegravir and rilpivirine extended-release injectable suspensions)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00080951.PDF

Warrington, R., Silviu-Dan, F., & Wong, T. (2018). Drug allergy. *Allergy, Asthma & Clinical Immunology, 14*(Suppl 2), Article 60. https://doi.org/10.1186/s13223-018-0289-y

22 Diabetes

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain how the body regulates glucose and how type 1, type 2 and other types of diabetes develop, and apply Canadian diagnostic criteria in SI units.
2. Monitor glucose with meters, continuous glucose monitoring, A1C and ketone testing, and interpret results against individualized targets.
3. Give insulin and non-insulin medications safely, treating insulin as a high-alert medication and teaching self-administration.
4. Recognize and treat hypoglycemia promptly, including in older adults and people with impaired awareness.
5. Recognize DKA and HHS, and provide nursing care and escalation using the CJMM.
6. Manage glucose in hospital, prevent and detect chronic complications, and teach foot care and sick-day guidance.
7. Support self-management with attention to access, cost and food security, with a distinctions-based, strengths-based lens for First Nations, Inuit and Métis communities.
8. Distinguish RN and RPN roles in insulin administration and adjustment using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 4, 5, 6	Clinician; Scholar	Foundations of Practice
3, 6, 7	Educator; Advocate	Foundations of Practice; Ethical Practice
8	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

Nurses meet diabetes on every unit. A patient admitted with pneumonia, a hip fracture or a heart attack may also live with diabetes, and the illness, the hospital routine and new medications can all push glucose too high or too low. In Canada, about 3.9 million people aged 1 year and older (9.7%) were living with diagnosed diabetes in 2023–2024, and about 260,000 people were newly diagnosed that year (Public Health Agency of Canada [PHAC], 2025). Nurses check glucose at the bedside, give insulin and other glucose-lowering drugs, recognize emergencies early and teach people to manage a lifelong condition at home.

This chapter is the book's home for diabetes in adults. Section 22.1 explains how the body controls glucose, how the main types of diabetes develop, who is at risk in Canada and how diabetes is diagnosed. Section 22.2 covers glucose meters, continuous glucose monitoring, the A1C test and ketone testing. Section 22.3 describes insulin and the non-insulin medications and how to give insulin safely. The second half of the chapter turns to hypoglycemia (22.4), the hyperglycemic emergencies diabetic ketoacidosis and hyperglycemic hyperosmolar state (22.5), and glucose management in hospital, chronic complications, foot care and self-management (22.6).

The chapter builds on earlier ones. Scope of practice, the Clinical Judgment Measurement Model (CJMM) and consent are taught in Chapter 1 (sections 1.3 to 1.5), and cultural safety, Indigenous health and food insecurity in Chapter 2. Acid–base balance, the anion gap and potassium are explained in Chapter 3, sepsis in Chapter 4, and recognizing deterioration in Chapter 6. Perioperative care, including when to hold some diabetes drugs before procedures, is in Chapter 7, and older adults and deprescribing are in Chapter 8. Heart, kidney, eye and wound complications are taught in the chapters for those systems.

22.1 Glucose Regulation and Types of Diabetes

How the Body Regulates Glucose

Glucose is a key fuel, especially for the brain, so the body keeps blood glucose within a narrow band through day and night. Two hormones from the islets of the pancreas do most of this work, pulling in opposite directions (Röder et al., 2016).

Insulin, made by the beta cells, is released when glucose rises after a meal. It lets muscle and fat cells take up glucose, tells the liver to stop releasing glucose and to store the extra as glycogen, and promotes the storage of fat and protein. Insulin also holds back the breakdown of fat. This last effect matters at the bedside: when insulin is missing and glucagon is high, fat breaks down without restraint and the liver turns the released fatty acids into **ketones**, acids that can build up in the blood (Goguen & Gilbert, 2018; section 22.5).

Glucagon, made by the alpha cells, rises between meals and overnight. It tells the liver to break down glycogen and to make new glucose from other sources, keeping glucose up while a person is not eating (Röder et al., 2016). Acute illness also pushes glucose up: stress hormones (catecholamines) can suppress insulin release, and infection, heart attack and stroke are common triggers of hyperglycemic emergencies (Goguen & Gilbert, 2018). Corticosteroid drugs raise glucose as well (Malcolm et al., 2018; section 22.6).

The gut takes part as well. After a meal, intestinal hormones called **incretins**, mainly glucagon-like peptide-1 (GLP-1) and glucose-dependent insulinotropic polypeptide (GIP), boost insulin release when glucose is high. GLP-1 also lowers glucagon and slows stomach emptying (Röder et al., 2016). Several diabetes medications act on this system (section 22.3).

Types of Diabetes

Diabetes is a group of metabolic disorders that share hyperglycemia caused by too little insulin secretion, poor insulin action, or both. Over time, high glucose damages the eyes, kidneys and nerves and raises cardiovascular risk (Punthakee et al., 2018).

- **Type 1 diabetes:** the beta cells are destroyed, usually by an autoimmune process (section 21.6), leaving the person with little or no insulin. People with type 1 diabetes are prone to ketoacidosis and need insulin for life (Punthakee et al., 2018). About 3 in 4 people with type 1 diabetes were diagnosed before age 20 (PHAC, 2025). Diabetes Canada also places latent autoimmune diabetes in adults (LADA), an autoimmune diabetes that begins in adulthood, within type 1 (Punthakee et al., 2018).
- **Type 2 diabetes:** the main problems are **insulin resistance**, in which cells respond poorly to insulin, and a beta-cell defect that leaves insulin output too low for the body's needs. The balance between the two varies from person to person, and ketoacidosis is less common (Punthakee et al., 2018). Beta-cell function tends to decline over the years, so many people need more medications, including insulin, as time passes. Type 2 is usually diagnosed after age 40; more than 80% of people with type 2 diabetes were diagnosed after that age (PHAC, 2025).
- **Prediabetes:** glucose or A1C values above normal but below the diabetes range. It marks a high risk of developing diabetes, although not everyone with prediabetes goes on to develop it (Punthakee et al., 2018).
- **Gestational diabetes:** glucose intolerance first recognized during pregnancy (Chapter 29).
- **Other specific types:** diabetes caused by diseases of the exocrine pancreas, such as pancreatitis or cystic fibrosis; by drugs, such as glucocorticoids; or by rare single-gene (monogenic) defects in beta-cell function (Punthakee et al., 2018).

Who Is at Risk in Canada

The 3.9 million Canadians with diagnosed diabetes combine type 1 and type 2 and exclude gestational diabetes (PHAC, 2025). Others have diabetes but do not know it: in national data for adults aged 20 to 79, collected from 2007 to 2019, an estimated 1.9% had undiagnosed diabetes and 6.3% had prediabetes (PHAC, 2025).

Diabetes Canada lists these risk factors for type 2 diabetes (Ekoé et al., 2018):

- age 40 years or older, or a first-degree relative with type 2 diabetes;
- membership in a population at high risk, which the guideline gives as Indigenous peoples; people of African, Arab, Asian, Hispanic or South Asian descent; and people with low socioeconomic status;

- a history of prediabetes, of gestational diabetes or of giving birth to a large baby;
- signs of end-organ damage, such as retinopathy, neuropathy, kidney disease or cardiovascular disease;
- vascular risk factors: low high-density lipoprotein (HDL) cholesterol, high triglycerides, hypertension, overweight, abdominal obesity and smoking;
- associated conditions, including pancreatitis, polycystic ovary syndrome, acanthosis nigricans, gout, fatty liver disease, some mental illnesses, HIV infection, obstructive sleep apnea and cystic fibrosis;
- drugs such as glucocorticoids, atypical antipsychotics, statins, antiretroviral therapy and anti-rejection drugs.

The population groups in this list describe risk, not biology. Higher rates in these communities follow from conditions that people live with, including poverty, food insecurity, racism and unequal access to care. For Indigenous peoples, Diabetes Canada, citing the World Health Organization, recognizes colonization, including residential schools, forced relocation and the banning of ceremonies, as "the most significant social determinant of health" (Crowshoe et al., 2018; Chapter 2).

Diabetes Canada recommends that everyone's risk be reviewed each year, and that people aged 40 and older, or at high risk on a risk calculator, be screened with a fasting glucose and/or A1C every 3 years. Earlier or more frequent testing (every 6 to 12 months) is considered for people at very high risk or with additional risk factors. The Canadian Diabetes Risk Assessment Questionnaire (CANRISK) estimates risk in Canada's multi-ethnic population (Ekoé et al., 2018). A hospital stay is also a chance to find risk: the nurse asks about family history, reviews medications such as corticosteroids and antipsychotics, notes raised glucose results and makes sure follow-up testing is arranged.

Diagnosis

When glucose rises above what the kidneys can reabsorb, glucose spills into the urine and pulls water and electrolytes with it. The person passes large amounts of urine, becomes thirsty and may feel weak (Goguen & Gilbert, 2018). Type 1 diabetes often develops over days to weeks, and some people are first diagnosed when they arrive with ketoacidosis (section 22.5). Type 2 diabetes develops slowly. Many people have no symptoms at all and are diagnosed through screening, during an admission for another illness, or only after a complication has appeared.

Diabetes Canada's criteria use plasma glucose and A1C in SI units (Table 22.1). One result in the diabetes range is enough when the person has symptoms of hyperglycemia. Without symptoms, the result is confirmed by a repeat test on another day. When type 1 diabetes is suspected, treatment is never delayed for a confirmatory test, especially if ketones are present (Punthakee et al., 2018).

Table 22.1 Diagnosing diabetes and prediabetes in adults (Punthakee et al., 2018)

Test	Prediabetes	Diabetes	Notes
Fasting plasma glucose	6.1–6.9 mmol/L (impaired fasting glucose)	7.0 mmol/L or higher	Fasting means no food or caloric drinks for at least 8 hours
A1C	6.0–6.4%	6.5% or higher	Adults only, with a standardized laboratory test; not used when type 1 diabetes is suspected; can mislead with hemoglobin variants, some anemias and severe kidney or liver disease
2-hour plasma glucose in a 75 g oral glucose tolerance test	7.8–11.0 mmol/L (impaired glucose tolerance)	11.1 mmol/L or higher	Blood drawn 2 hours after a standard glucose drink
Random plasma glucose	Not used	11.1 mmol/L or higher	Any time of day, whatever the timing of the last meal
Confirming the diagnosis	Not applicable	One result is enough with symptoms; otherwise repeat on another day	The same test is preferred for the repeat, but a random value without symptoms is confirmed with a different test

Acanthosis nigricans is a skin sign of insulin resistance and a listed risk factor (Ekoé et al., 2018). The nurse looks for thick, velvety patches in skin folds such as the back and sides of the neck, the armpits and the groin. The colour change can be subtle, especially on

brown and black skin, where the patches may differ little from the surrounding skin. Because visual assessment alone is unreliable, the nurse uses good lighting, compares the area with nearby unaffected skin and feels for the velvety texture (Pusey-Reid et al., 2023). The nurse never mistakes it for poor hygiene, since washing does not remove it.

CANADIAN CONTEXT

Diabetes in First Nations, Inuit and Métis Communities

Diabetes Canada describes Indigenous peoples in Canada as among the populations at highest risk of diabetes and its complications, and recommends earlier and more frequent screening (Crowshoe et al., 2018). The guideline places the cause in history and living conditions: colonization, residential schools, forced relocation, poverty, food insecurity and racism in health care.

Rates differ across First Nations, Inuit and Métis peoples, so data are reported by distinct group. In the First Nations Regional Health Survey (RHS) Phase 3 (2015–2016), 19.2% of First Nations adults living on reserve and in northern First Nations communities had diabetes (age-standardized), a steady trend compared with 20.7% in Phase 2 (2008–2010) and 20.1% in Phase 1 (2002–2003) (First Nations Information Governance Centre [FNIGC], 2018). The RHS is owned and governed by First Nations under the principles of ownership, control, access and possession (OCAP®) (Rosella et al., 2020). In the 2009–2010 Canadian Community Health Survey, the age-standardized prevalence among Métis was 7.3%, compared with 5.0% among non-Indigenous people. Among Inuit aged 15 and older, self-reported prevalence in the 2006 Aboriginal Peoples Survey was about 4%, double the 2001 figure, and PHAC described the age-adjusted rate as comparable to that of the general population (PHAC, 2011). These Métis and Inuit figures are now more than 15 years old.

Communities lead much of the response. The Kahnawake Schools Diabetes Prevention Project, run since 1994 under a community advisory board in Kahnawà:ke, combines Kanien'kehá:ka knowledge with research to promote healthy eating and activity in schools and families (McComber & Macaulay, 2016). Nurses support such programs and offer culturally safe care (Chapter 2).

22.2 Monitoring Glucose

Meters and Point-of-Care Testing

A glucose meter measures glucose in a drop of capillary blood (Figure 22.1). In hospital this is **point-of-care glucose testing**: testing at the bedside with a meter that the laboratory approves and checks for quality. Employer policy sets who may test, how often the meter is checked, how results are documented and which values must be reported at once.



Figure 22.1 A point-of-care glucose meter with lancets, test strips and cotton balls. The meter must be one the laboratory approves, and the nurse follows the unit's quality-control routine. (credit: “A blood glucose monitoring machine with cotton balls, lancets, and reagent strips” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Technique affects the result. In one study, sugar left on the fingers after touching fruit produced a falsely high first-drop reading in most participants, and squeezing the finger also distorted results. The nurse therefore has the patient wash and dry their hands, uses the first drop, and avoids hard squeezing (Hortensius et al., 2011). The fingertip is preferred when glucose may be changing quickly, such as after a meal, after exercise or during suspected hypoglycemia, because forearm or thigh samples lag behind (Berard et al., 2018).

Meters are less exact than laboratory tests. Diabetes Canada accepts a difference of less than 15% between a meter and a simultaneous fasting laboratory glucose at values above 4.2 mmol/L (Berard et al., 2018). Its 2021 update advises comparing meter results with a simultaneous laboratory glucose when readings seem inaccurate or do not match the A1C (Cheng et al., 2021). When a reading does not fit how the patient looks, the nurse acts on the

patient, repeats the test and sends a laboratory sample as policy directs. People on insulin more than once a day are advised to check at least three times daily, including before and after meals (Berard et al., 2018; Cheng et al., 2021).

Continuous Glucose Monitoring

Continuous glucose monitoring (CGM) uses a small sensor inserted under the skin that measures glucose in the interstitial fluid every few minutes. Real-time systems send readings to a reader or phone automatically and can sound alarms for high or low values. Intermittently scanned ("flash") systems display readings when the sensor is scanned (Figure 22.2). Diabetes Canada recommends CGM for people with type 1 diabetes who use insulin injections or a pump (Halperin et al., 2025), and its 2021 update states that, for people with type 2 diabetes on basal-bolus insulin, real-time or flash CGM may be used to cut the time spent in hypoglycemia (Cheng et al., 2021). Costs and provincial coverage are discussed in section 22.6.

Figure 22.2 An intermittently scanned (flash) glucose sensor on the upper arm. Holding the reader or a phone near the sensor shows the current glucose and its trend. (credit: “FreeStyle libre am Oberarm und Auslesegerät-4” by Thirunavukkarasye-Raveendran/Wikimedia Commons, CC BY 4.0)

Interstitial glucose trails blood glucose. In fasting healthy adults the delay was about 5 to 6 minutes (Basu et al., 2013), and the gap between sensor and fingerstick values is largest when glucose is rising or falling quickly. If a sensor reading does not match symptoms, the nurse checks capillary glucose.

In hospital, patients may keep using their own CGM if hospital protocol allows. A current guideline advises confirming sensor values with point-of-care tests before insulin doses are adjusted. Some medications can distort readings, as can extensive skin infection, poor perfusion and vasopressor drugs, and sensors may need to be replaced after magnetic resonance imaging (MRI) and some other imaging (Korytkowski et al., 2022). The nurse follows employer policy and documents which value guided each decision.

CGM reports summarize glucose as **time in range**, the percentage of readings between 3.9 and 10.0 mmol/L. A time in range of 70% corresponds to an A1C of about 7.0% (Cheng et al., 2021), and each 5% gain in time in range brings clinically meaningful benefit (Halperin et al., 2025). The Going Deeper box explains the full report.

A1C and Targets

A1C (glycated hemoglobin) is the percentage of hemoglobin that has glucose attached. Because red cells live for months, A1C reflects average glucose across roughly the past 8 to 12 weeks, with the last 30 days contributing about half (Berard et al., 2018). It is checked at least every 3 months while targets are not being met, and every 6 months may be enough once targets are met consistently. Conditions that change red cell lifespan or hemoglobin structure, such as some anemias and hemoglobin variants, can make A1C misleading; meter or CGM data then carry more weight.

Diabetes Canada states that glycemic targets should be individualized. For most adults with type 1 or type 2 diabetes, the A1C target is 7.0% or less, with a fasting or before-meal glucose of 4.0 to 7.0 mmol/L and a glucose 2 hours after meals of 5.0 to 10.0 mmol/L. An A1C of 6.5% or less may be targeted in some people with type 2 diabetes at low risk of hypoglycemia. Higher targets protect people for whom hypoglycemia is the greater danger: 7.1% to 8.0% for people who are functionally dependent, and 7.1% to 8.5% for those with recurrent severe hypoglycemia, limited life expectancy, or frailty or dementia (Imran et al., 2018). Targets for older adults are covered in the Lifespan Considerations box in section 22.6.

Ketone Testing

Ketones form when the body burns fat because insulin is lacking. Blood ketone meters measure beta-hydroxybutyrate, the main ketone in ketoacidosis, and Diabetes Canada states that blood testing may be preferred to urine strips because it detects ketosis earlier (Berard et al., 2018). People with type 1 diabetes are advised to check ketones during acute illness with high glucose, when

glucose before meals stays above 14.0 mmol/L, or when symptoms of diabetic ketoacidosis appear, such as nausea, vomiting or abdominal pain (Berard et al., 2018). Diabetes Canada's type 1 guideline also asks people with type 1 diabetes who take a sodium-glucose cotransporter-2 (SGLT2) inhibitor to have a blood ketone meter and a written plan for ketone levels above 1.0 mmol/L (Halperin et al., 2025). In hospital, the nurse checks ketones as ordered or under a medical directive and reports rising values promptly (section 22.5).

GOING DEEPER

Reading a CGM Report

Required for RN students; optional for PN students.

An international consensus, which Diabetes Canada uses for its sensor targets, set out the core measures of a CGM report (Battelino et al., 2019; Cheng et al., 2021; Halperin et al., 2025). The standard one-page report, the ambulatory glucose profile, overlays 14 days of readings as if they were one day, so patterns by time of day stand out. Data are trusted when the sensor was worn for at least 70% of those 14 days.

Targets for most adults with type 1 or type 2 diabetes:

- **Time in range (3.9–10.0 mmol/L):** more than 70%, about 16 hours 48 minutes a day.
- **Time below range:** under 4% below 3.9 mmol/L, and under 1% below 3.0 mmol/L.
- **Time above range:** under 25% above 10.0 mmol/L, and under 5% above 13.9 mmol/L.
- **Glycemic variability:** a coefficient of variation of 36% or less.

For older or high-risk adults, the consensus relaxes the targets: time in range above 50% and time below 3.9 mmol/L under 1%.

The **glucose management indicator (GMI)** estimates A1C from the sensor's mean glucose. It may differ from a laboratory A1C, which can itself be thrown off by conditions such as some anemias (Punthakee et al., 2018).

The nurse reads hypoglycemia first, because lows are the immediate danger. A cluster of lows at 0300, for example, points to the evening basal or bedtime dose, not the lunch dose.

22.3 Insulin and Non-Insulin Medications

Insulin Types

Everyone with type 1 diabetes needs insulin. In type 2 diabetes, insulin is started at once when glucose is very high with symptoms or the person is metabolically unstable, and later when targets are not met despite other drugs (Butalia et al., 2024). It may also be used for a time during illness, surgery or other stress (Lipscombe et al., 2018).

Insulin regimens copy the body's normal pattern.

- **Basal insulin** provides a steady background level that controls glucose between meals and overnight.
- **Bolus (prandial) insulin** is given with meals to cover the rise in glucose from food.
- **Correction insulin** is an extra amount of rapid- or short-acting insulin, added to the scheduled dose when glucose is above target.

In type 2 diabetes, insulin often starts as one daily injection of basal insulin added to other drugs (Lipscombe et al., 2018). Diabetes Canada suggests long-acting analogues rather than NPH to lower the risk of hypoglycemia. It also advises stopping sulfonylureas and meglitinides once bolus insulin is added (Shah et al., 2024).

Insulins are grouped by how fast they start, when they peak and how long they last (Table 22.2). These times are averages: they vary between people and with the dose, injection site and activity (Diabetes Canada, n.d.-a). Rapid-acting, short-acting and long-acting insulins are clear; intermediate-acting (NPH) and premixed insulins are cloudy.

Biosimilars are insulins highly similar to an original brand, such as Basaglar and Semglee for glargine, and Admelog, Trurapi and Kirsty for lispro and aspart. They cost less than the original products (Butalia et al., 2024; Halperin et al., 2025). Concentrated insulins hold more units in each millilitre (U-200, U-300 and U-500). The dose is still ordered and dialled in units, never in

millilitres. A once-weekly basal insulin, icodec (Awiqli), has been authorized in Canada (Health Canada, n.d.-b); Diabetes Canada's 2024 update made no recommendation about it (Butalia et al., 2024).

Table 22.2 Insulin types and what the nurse watches for (aspart times from the NovoRapid product monograph, Novo Nordisk Canada, 2026; all other times from Diabetes Canada, n.d.-a)

Type	Canadian examples	Onset, peak and duration (as stated)	Nursing points
Rapid-acting analogue (bolus; clear)	Aspart (NovoRapid; biosimilars Trurapi, Kirsty); lispro (Humalog U-100 and U-200; biosimilar Admelog)	Aspart: onset within 10–20 min, maximum effect 1–3 h, duration 3–5 h (monograph). Lispro: onset 10–15 min, peak 1–2 h, duration 3–4.75 h	Aspart is given immediately before a meal, no more than 5–10 min ahead, or right after the meal when necessary; confirm food is present and the patient can eat
Faster-acting analogue (bolus; clear)	Faster-acting aspart (Fiasp)	Onset 4 min, peak 0.5–1.5 h, duration 3–5 h	Fastest onset of all; the same meal checks apply
Short-acting (bolus; clear)	Regular insulin (Humulin R, Novolin ge Toronto)	Onset 30 min, peak 2–3 h, duration 6.5 h	Slower to start than analogues, so it is timed further ahead of meals as ordered; IV use only by order and protocol
Intermediate-acting (basal; cloudy)	NPH (Humulin N, Novolin ge NPH)	Onset 1–3 h, peak 5–8 h, duration up to 18 h	Its peak can cause hypoglycemia many hours after a dose; check the label, since Humulin N and Humulin R have been mixed up
Long-acting analogue (basal; clear)	Glargine U-100 (Lantus; biosimilars Basaglar, Semglee); glargine U-300 (Toujeo); degludec U-100 and U-200 (Tresiba)	Onset 90 min; no peak; duration 24 h (glargine U-100), more than 30 h (glargine U-300), 42 h (degludec)	Usually continued when the patient is not eating, at the ordered dose (section 22.6); clear like rapid-acting insulin, so check the name every time
Premixed (cloudy)	Humulin 30/70, Novolin ge 30/70; NovoMix 30; Humalog Mix25	Fixed proportions of a rapid- or short-acting insulin with an intermediate-acting insulin; action reflects both parts	Given with meals; a missed or late meal raises the risk of hypoglycemia
Concentrated	Lispro U-200; glargine U-300; degludec U-200; regular U-500 (Entuzity)	Regular U-500: onset 15 min, peak 4–8 h, duration 17–24 h	Dose in units from the pen as ordered; never withdraw insulin from a pen or cartridge with a syringe

Giving Insulin Safely

Insulin is a **high-alert medication**: a drug with a heightened risk of serious harm when used in error. ISMP Canada has identified insulin as high-alert in the community, and it is repeatedly linked to harmful incidents in hospitals (Canadian Society of Hospital Pharmacists Ontario Branch & ISMP Canada, 2014; Kasprzak & Ho, 2016). Common errors include choosing the wrong product, such as one look-alike name for another; reading a dose in millilitres instead of units; and using an old order after the regimen has changed. An excessive dose can cause life-threatening seizures and coma (Kasprzak & Ho, 2016).

The nurse applies the usual medication checks with extra care:

- **Right product and strength:** read the full name, the type and the concentration on every vial or pen. Colour coding on caps is not a safe check.
- **Units only:** orders and records say "units", written in full; "U" can be misread as a zero.
- **One pen, one patient:** a pen carries a patient-specific label on the barrel, not the cap, and is never used for another patient, even with a new needle. Using one pen for several patients can spread bloodborne infections. Insulin is never drawn from a pen or cartridge with a syringe (Canadian Society of Hospital Pharmacists Ontario Branch & ISMP Canada, 2014).
- **Needles:** a new pen needle is used for each injection. A 4 mm pen needle, held at 90 degrees to the skin, reaches the subcutaneous tissue in adults of any body size (Bari et al., 2020) (Figure 22.3).

Lipohypertrophy is a lump of thickened fatty tissue that forms under skin injected repeatedly at the same spot. Insulin is absorbed poorly and unpredictably from these lumps, raising the risk of both high glucose and hypoglycemia. In one Canadian study, 37% of people who noticed lumps still injected into them (Bari et al., 2020). The nurse looks at and feels injection areas, injects only into healthy tissue and teaches rotation across as large an area as possible.

Figure 22.3 An insulin pen with a pen needle and its outer cap. A new needle is attached for every injection, and the pen is labelled for one patient only. The round device on the left is an injection port, which some people use to reduce skin punctures. (credit: "I-Port Advance and insulin pen (Novorapid), with needle cover" by Marius Vassnes/Wikimedia Commons, CC BY-SA 4.0)

Timing with meals is a common source of harm. Before giving bolus insulin, the nurse confirms the meal tray is present, the patient can eat and no test or procedure will interrupt the meal. When a patient is not eating or is fasting for a procedure, the nurse follows the order or policy and consults the prescriber rather than guessing (sections 22.4 and 22.6). Correction insulin and the problems with sliding-scale insulin alone are discussed in section 22.6.

Employer policy decides which insulin doses need an independent double check by a second nurse. A provincial roundtable judged double checks valuable but not feasible for every subcutaneous dose (Canadian Society of Hospital Pharmacists Ontario Branch & ISMP Canada, 2014). The nurse gives insulin intravenously only when an order, the product monograph and hospital protocol allow it (section 22.5). Patients may keep wearing their own insulin pump or CGM in hospital, or give their own insulin through a self-administration program, only as hospital policy allows. Hospital policies should also say how insulin pumps are managed during MRI and computed tomography (CT) (Korytkowski et al., 2022). The Scope in Practice box in section 22.6 explains who may give and adjust insulin.

Teaching People to Use Insulin

Starting insulin is a big change, and many people worry about needles, low glucose or what insulin says about their illness. The nurse first learns what the person can see, read and do: vision, hand strength and dexterity, memory, language and literacy, and who helps at home. Teaching is short, practical and repeated. The person handles the actual pen or syringe they will use at home, gives a return demonstration and explains the steps back in their own words. An interpreter is used when needed (Chapter 2).

Before discharge the person should be able to give a dose, rotate sites and check for lumps, check glucose, and recognize and treat a low (section 22.4). The person also needs to know what to do on sick days (section 22.6) and whom to call with questions. A hospital self-administration program, where policy allows, lets people practise under supervision. The cost of insulin and supplies can decide whether a plan works, so the nurse asks about coverage and links people to help (section 22.6). Older adults may need simpler regimens and support from family or home care (Chapter 8).

CLINICAL SAFETY

Insulin Is a High-Alert Medication

Most insulin errors follow a few patterns. Each has a simple defence.

- **Look-alike names:** Humulin N and Humulin R, or two clear basal insulins, have been confused (Kasprzak & Ho, 2016). The nurse reads the full product name and type aloud at the bedside and compares it with the order.
- **Units and volume:** an order written as "4 mL" when 4 units was meant is a hundredfold error. The nurse never gives insulin from an order in millilitres or one using "U", and clarifies with the prescriber.
- **Shared or unlabelled devices:** a pen or syringe without the patient's label is not used. Syringes are filled at the bedside, never drawn up ahead and carried unlabelled (Canadian Society of Hospital Pharmacists Ontario Branch & ISMP Canada, 2014).

- **Concentrated products:** U-200, U-300 and U-500 insulins are dialled in units with the pen made for them; insulin is never drawn from a pen or cartridge with a syringe (Canadian Society of Hospital Pharmacists Ontario Branch & ISMP Canada, 2014).
- **Timing:** bolus insulin is given when the meal is in front of the patient, not when the tray is expected.
- **Changes in the plan:** after a new order, the nurse checks that old doses have been stopped in the medication record.

When an error or near miss happens, the nurse checks the patient's glucose, monitors for hypoglycemia, tells the prescriber, and reports the event through the employer's incident system.

Non-Insulin Medications

Most people with type 2 diabetes start with non-insulin drugs. Diabetes Canada recommends metformin as the first glucose-lowering drug. It also recommends specific GLP-1 receptor agonists and SGLT2 inhibitors for heart and kidney protection, whatever the A1C. The guideline's 2024 update advises a GLP-1 receptor agonist or an SGLT2 inhibitor with proven benefit for people at high cardiovascular risk. For people with heart failure or chronic kidney disease, it advises an SGLT2 inhibitor with proven benefit (Shah et al., 2024). Proven benefit belongs to particular drugs. Liraglutide, dulaglutide and injectable semaglutide reduced major cardiovascular events, and canagliflozin, dapagliflozin and empagliflozin protected the kidneys. At the time of the 2024 update, oral semaglutide had not been shown to affect cardiorenal outcomes (Shah et al., 2024; Butalia et al., 2024). Heart failure use is taught in Chapter 18 and kidney disease in Chapter 27.

The nurse needs to know which drugs can cause hypoglycemia. Insulin and the **insulin secretagogues**, drugs that make the pancreas release insulin whatever the glucose level (sulfonylureas and meglitinides), carry the highest risk. Metformin, dipeptidyl peptidase-4 (DPP-4) inhibitors, GLP-1 receptor agonists, SGLT2 inhibitors and thiazolidinediones rarely cause hypoglycemia on their own, but they add to the risk when combined with insulin or a secretagogue (Shah et al., 2024). Weight effects also matter to patients. Insulin, sulfonylureas and thiazolidinediones cause the most weight gain, and GLP-1-based drugs and SGLT2 inhibitors cause weight loss (Shah et al., 2024).

Using the CJMM (Chapter 1, section 1.4), the nurse links each drug to the cues it can produce: a secretagogue with sweating before lunch, an SGLT2 inhibitor with vomiting and fast breathing, a GLP-1 receptor agonist with nausea and poor intake. Several drugs need specific nursing attention:

- **Metformin:** stomach upset is common when it is started. Canadian monographs advise stopping it at the time of or before a procedure with iodinated contrast, holding it for 48 hours afterward, and restarting only once kidney function has been rechecked and found normal. Vitamin B12 is checked at least every 1 to 2 years during long-term use (sanofi-aventis Canada, 2018).
- **SGLT2 inhibitors:** these drugs make the kidneys excrete glucose, so genital yeast infections and urinary tract infections are more common, and fluid loss can lower blood pressure (Lipscombe et al., 2018). They carry a rare but serious risk of **euglycemic diabetic ketoacidosis**: ketoacidosis with glucose that is only mildly raised or even normal. They are held during acute illness with a risk of dehydration, during fasting, and before major surgery (Butalia et al., 2024). Perioperative holds are in Chapter 7, sick-day guidance is in section 22.6 and ketoacidosis is in section 22.5.
- **GLP-1 receptor agonists and tirzepatide:** nausea, vomiting and diarrhea are common, especially as doses rise, so doses are increased slowly (Butalia et al., 2024). Because these drugs slow stomach emptying (Röder et al., 2016), aspiration risk before anesthesia is a concern; planning for procedures is in Chapter 7. Tirzepatide acts on both the GIP and GLP-1 receptors (Butalia et al., 2024).

MEDICATIONS

Non-Insulin Drug Classes

Canadian generic examples, with one key nursing point for each class (Lipscombe et al., 2018; Shah et al., 2024; Butalia et al., 2024). Doses follow the prescriber's order and the Canadian monograph.

- **Biguanide (metformin):** the first-line drug. Stomach upset is common, especially at the start. Held around iodinated contrast as ordered, and the nurse watches for low vitamin B12.
- **SGLT2 inhibitors (canagliflozin, dapagliflozin, empagliflozin):** protect heart and kidneys. The nurse teaches genital hygiene, watches for dehydration and reports nausea, vomiting, abdominal pain or unusual tiredness, which may signal ketoacidosis even when glucose is near normal.

- **GLP-1 receptor agonists (liraglutide, semaglutide; oral semaglutide):** most are given by injection, some once weekly. Nausea is common at the start. They are not combined with DPP-4 inhibitors and are avoided in people with a personal or family history of medullary thyroid cancer.
- **GIP/GLP-1 receptor agonist (tirzepatide):** a once-weekly injection with similar stomach effects. Diabetes Canada's 2024 user's guide noted no data yet showing cardiovascular benefit.
- **DPP-4 inhibitors (alogliptin, linagliptin, saxagliptin, sitagliptin):** taken by mouth, weight-neutral and low in hypoglycemia risk; pancreatitis is rare.
- **Sulfonylureas (gliclazide, glimepiride, glyburide):** insulin secretagogues that cause hypoglycemia, especially with missed meals. Gliclazide is preferred over glyburide.
- **Meglitinide (repaglinide):** a short-acting secretagogue taken with meals; like sulfonylureas it can cause hypoglycemia, so the nurse confirms the patient is eating.
- **Thiazolidinedione (pioglitazone):** the nurse watches for edema and weight gain, which may signal heart failure.

22.4 Hypoglycemia

Definition and Causes

Hypoglycemia is a blood glucose level low enough to cause symptoms or put a person at risk of harm. Insulin and the insulin secretagogues (sulfonylureas and meglitinides; section 22.3) can both cause it, so prevention, quick recognition and prompt treatment all matter (Lega et al., 2023).

Diabetes Canada's 2023 update uses an alert value below 3.9 mmol/L to classify hypoglycemia and grades its severity in three levels (Lega et al., 2023):

- **Level 1:** glucose below normal, often 3.0 to 3.9 mmol/L, with autonomic symptoms.
- **Level 2:** glucose below normal, often below 3.0 mmol/L, with neuroglycopenic symptoms.
- **Level 3 (severe):** any glucose reading with a marked change in mental or physical status, so that the person needs someone else's help to treat it.

Level 3 is defined by the need for help, not by a number.

In hospital, lows usually come from a mismatch between glucose-lowering drugs and glucose supply:

- **Meals:** a tray that is missed, late or only partly eaten after mealtime insulin is given (see the Practice Story in section 22.6).
- **Nothing by mouth (NPO):** fasting for a test or surgery while insulin or a secretagogue continues (Chapter 7); these patients need ready access to oral or IV glucose (Malcolm et al., 2018).
- **Interrupted feeds:** when enteral or parenteral nutrition is stopped, the patient may need IV dextrose so that glucose does not fall (Malcolm et al., 2018).
- **Kidney function:** falling kidney function reduces the clearance of sulfonylureas, and chronic kidney disease raises the risk of severe hypoglycemia (Diabetes Canada, n.d.-b; Lega et al., 2023).
- **Corticosteroid changes:** insulin increased for steroid-induced hyperglycemia must come down when the steroid is tapered or stopped (Malcolm et al., 2018).

Diabetes Canada also lists risk factors for severe hypoglycemia: earlier severe episodes, impaired awareness, long duration of diabetes or of insulin use, autonomic neuropathy, chronic kidney disease, advanced age and frailty, cognitive impairment, low health literacy, food insecurity and a low A1C (Lega et al., 2023). Food insecurity is a structural cause: a person who cannot count on regular meals cannot safely match insulin to food (Chapter 2).

Recognizing Hypoglycemia

Symptoms fall into two groups (Lega et al., 2023):

- **Autonomic (adrenergic):** trembling, palpitations, sweating, anxiety, hunger, nausea and tingling.

- **Neuroglycopenic:** from the brain's shortage of glucose: difficulty concentrating, confusion, weakness, drowsiness, vision changes, slurred speech, headache and dizziness.

Sweating is felt as well as seen: on every skin tone the skin is cool, damp and clammy to touch. Pallor is harder to see on darker skin, where it may appear ash grey or yellow-brown rather than pale, so the nurse inspects the conjunctiva, lips and oral mucosa and compares them with the patient's usual colour (Pusey-Reid et al., 2023).

Impaired awareness of hypoglycemia means the early warning symptoms are blunted or missing, so a person may first show confusion or even lose consciousness (Lega et al., 2023). Diabetes Canada recommends screening people at risk of severe hypoglycemia for impaired awareness at each visit, by history or a questionnaire such as the Gold or Clarke score. Everyone treated with insulin or a secretagogue is also screened for fear of hypoglycemia, which may affect up to about 30% of them. Fear can lead people to aim for higher glucose levels, take less insulin, limit exercise or overeat (Lega et al., 2023).

Some patients need extra vigilance:

- **Older adults:** frail older adults treated with insulin or secretagogues are at particular risk (Lega et al., 2023). Because confusion and drowsiness are neuroglycopenic symptoms, the nurse checks glucose whenever an older adult with diabetes becomes confused, sleepy or unsteady, before the change is put down to delirium (Chapter 8).
- **Beta-blockers:** Canadian monographs warn that beta-blockers may mask early signs of hypoglycemia, such as a fast heart rate, and delay recovery (Sivem Pharmaceuticals, 2021), so other cues matter more.
- **Sleeping patients:** lows can go unnoticed; continuous glucose monitoring (CGM; section 22.2) or more frequent checks, including overnight, help find them (Lega et al., 2023).

Treatment

The nurse treats first and investigates after, following the hospital's hypoglycemia protocol; Diabetes Canada recommends protocols with nurse-initiated treatment (Malcolm et al., 2018). Treatment depends on whether the person can swallow safely (Lega et al., 2023):

- **Level 1 or 2:** give 15 g of fast-acting carbohydrate, preferably glucose or sucrose tablets or solution. Recheck glucose after 15 minutes and give another 15 g if it is still below 3.9 mmol/L.
- **Level 3, conscious and able to swallow:** give 20 g of oral carbohydrate, preferably glucose tablets. Recheck in 15 minutes and give another 15 g of glucose if it is still below 3.9 mmol/L. Glucagon is an alternative.
- **Unable to swallow or unconscious:** give nothing by mouth. Without IV access, give glucagon 1 mg subcutaneously or intramuscularly, or 3 mg intranasally, and call for help (in hospital, the rapid response team, Chapter 6; in the community, 9-1-1). With IV access, IV dextrose is given as ordered or by protocol.

Once glucose is corrected, the person eats the next scheduled meal or snack. If the meal is more than an hour away, they have a snack with 15 g of carbohydrate and a protein source (Lega et al., 2023). Overtreatment is avoided because it causes rebound hyperglycemia.

Nasal glucagon (Baqsimi) is marketed in Canada (Health Canada, n.d.-a). The recommended dose is 3 mg into the nose for adults, and the person does not have to breathe in for it to work (Amphastar Pharmaceuticals, 2024). An unconscious person is turned on their side and given oral carbohydrate once able to swallow safely. The two injectable glucagon products once sold in Canada were discontinued in 2023 and 2024. Health Canada has let a company import a US glucagon injection since May 2023, an arrangement that runs until December 31, 2026, and in June 2026 it authorized a new Canadian glucagon for injection whose launch date had not been announced (Health Canada, 2026). Glucagon works less well after more than two standard drinks of alcohol, prolonged fasting or advanced liver disease (Lega et al., 2023).

Afterward, the nurse documents values, treatment, times and response, reports the episode to the prescriber, and looks for the cause so the order can be reviewed.

Prevention and Teaching

People at risk of severe hypoglycemia should have glucagon prescribed, and support persons should learn to give it; for people at high risk, Diabetes Canada recommends CGM together with a structured education program (Lega et al., 2023). The nurse teaches the person to carry fast-acting glucose, know their own early symptoms, report lows and wear diabetes identification, such as a medical alert bracelet (Lega et al., 2023).

Diabetes Canada's driving chapter advises people taking insulin or secretagogues to consider checking glucose just before driving and at least every 4 hours while driving, and not to drive with glucose below 4.0 mmol/L (Houlden et al., 2018). After treating a low, they wait until glucose is at least 5.0 mmol/L and 40 minutes have passed. Fast-acting carbohydrate stays within reach in the vehicle; if a low starts while driving, they stop safely, remove the keys and treat it.

CLINICAL JUDGMENT

Sweaty and Confused at 0400

Names and details are fictional; this is a composite story.

Mr. Samuel Mensah, 71, has type 2 diabetes and is on day 3 of treatment for pneumonia on a medical unit. He takes evening basal insulin and gliclazide. He ate little at supper. At 0400 the nurse finds him awake, picking at his sheets and unsure where he is.

- **Recognize cues:** His dark-brown skin is cool and damp to touch, and his lips and oral mucosa look ash grey rather than their usual colour. His heart rate is 104. His creatinine rose yesterday. The point-of-care glucose is 2.6 mmol/L.
- **Analyze cues:** Poor intake, a sulfonylurea, basal insulin and falling kidney function all point to hypoglycemia. New confusion could also be delirium or worsening infection, but the glucose explains it and can be treated at once.
- **Prioritize hypotheses:** Severe (level 3) hypoglycemia is the priority, because he needs help to treat it and his brain is short of glucose now.
- **Generate solutions:** He is drowsy but sits up and swallows water safely, so oral glucose is possible. If he could not swallow, glucagon or IV dextrose by protocol would be needed.
- **Take action:** Following the hypoglycemia protocol, the nurse gives 20 g of glucose tablets, stays with him and rechecks in 15 minutes: 4.6 mmol/L. Because breakfast is more than an hour away, she gives a snack with 15 g of carbohydrate and some protein. She informs the most responsible provider using SBAR (Chapter 6), noting the gliclazide and the rising creatinine.
- **Evaluate outcomes:** At 0445 he is oriented and his glucose is 6.1 mmol/L. The nurse documents the event, increases glucose checks as ordered, and confirms with the prescriber how the gliclazide and insulin will be changed before the next doses.

22.5 Hyperglycemic Emergencies: DKA and HHS

How DKA and HHS Develop

Diabetic ketoacidosis (DKA) and **hyperglycemic hyperosmolar state (HHS)** are the two hyperglycemic emergencies of diabetes. Both begin when insulin action falls far short of the body's needs. High glucose spills into the urine and carries water and electrolytes with it, so the person becomes dehydrated (Goguen & Gilbert, 2018).

In DKA, insulin deficiency and high glucagon levels drive the breakdown of fat. The liver turns fatty acids into ketones, mainly beta-hydroxybutyrate and acetoacetate, which are acids. As ketones build up, a metabolic acidosis with a high anion gap develops (Chapter 3). Potassium shifts out of cells, so the serum potassium may be normal or even high at first, although the body as a whole has lost potassium. Diabetes Canada gives typical potassium deficits of 2 to 5 mmol/kg in DKA and 4 to 6 mmol/kg in HHS (Goguen & Gilbert, 2018).

In HHS, a longer period of relative insulin insufficiency, together with too little fluid intake, pushes glucose higher than in DKA. The main features are severe fluid loss and high plasma osmolality, with little or no acidosis. HHS occurs far less often than DKA, and in up to 20% of cases the person had no known diabetes (Goguen & Gilbert, 2018).

DKA is more common in type 1 diabetes, with a reported incidence of 4.6 to 8.0 per 1,000 patient-years, than in type 2 diabetes, where estimates range from 0.32 to 2.0 per 1,000 patient-years (Goguen & Gilbert, 2018). Common triggers include:

- a new diagnosis of diabetes;

- missed insulin doses;
- infection (Chapter 4), heart attack, stroke, an abdominal crisis or trauma;
- thyrotoxicosis, cocaine use and some drugs, such as glucocorticoids and atypical antipsychotics;
- possibly problems with an insulin pump.

HHS shares these triggers and can also follow cardiac surgery or the use of diuretics or lithium. Infection is present in about 40% to 60% of HHS cases (Goguen & Gilbert, 2018).

Euglycemic diabetic ketoacidosis is DKA with a normal or only mildly raised glucose. SGLT2 inhibitors (section 22.3) lower the threshold for DKA, although it was uncommon in trials (no more than 0.1% of treated people). Usual triggers are reducing or omitting insulin, surgery, alcohol, strenuous exercise and eating little carbohydrate (Goguen & Gilbert, 2018). Because the glucose may not look alarming, Diabetes Canada recommends assessing for DKA in anyone taking an SGLT2 inhibitor who has symptoms, even if glucose is not high. Holding these drugs before procedures is covered in Chapter 7.

Recognizing DKA and HHS

Diabetes Canada lists these symptoms and signs of DKA (Goguen & Gilbert, 2018):

- increased urination and thirst, and weakness;
- air hunger, nausea, vomiting and abdominal pain;
- **Kussmaul respirations**, deep and rapid breathing that removes carbon dioxide to offset the acidosis (Chapter 3), and an acetone odour on the breath;
- an altered level of consciousness.

In HHS, fluid loss is usually more severe and consciousness more depressed; seizures or a stroke-like picture can occur. Because HHS develops over a longer period, the nurse asks about a gradual build-up of thirst, urination and drowsiness.

Signs of fluid loss include dry mucous membranes, a fast heart rate, low blood pressure that may drop on standing, and low urine output. On darker skin, changes in colour are less reliable, so the nurse checks the mucous membranes and conjunctiva (which may look ash grey), capillary refill, vital signs and urine output, and compares with the patient's baseline (Pusey-Reid et al., 2023).

Diabetes Canada's diagnostic criteria are summarized in Table 22.3 (Goguen & Gilbert, 2018). DKA is typically defined by an arterial pH of 7.3 or less, a serum bicarbonate of 15 mmol/L or less, an anion gap above 12 mmol/L, and positive serum or urine ketones. Plasma glucose is usually 14.0 mmol/L or higher but may be lower, especially with SGLT2 inhibitors. HHS is typically defined by a plasma glucose of 34.0 mmol/L or higher, a plasma osmolality above 320 mmol/kg, marked fluid loss and minimal acidosis.

Several testing points matter to the nurse. A venous blood gas is usually adequate. A point-of-care capillary beta-hydroxybutyrate test is sensitive and specific for DKA; negative urine ketones do not rule it out. Capillary glucose readings are unreliable in severe acidosis, so laboratory glucose guides treatment (Goguen & Gilbert, 2018).

Table 22.3 DKA and HHS compared at the bedside (Goguen & Gilbert, 2018; original wording)

Feature	DKA	HHS
Who	Much more common in type 1 diabetes; also occurs in type 2 diabetes and with SGLT2 inhibitors	Much less common; up to 20% have no known diabetes
Onset	Usually develops faster than HHS	Develops over a longer period of relative insulin shortage and poor fluid intake
Glucose	Usually 14.0 mmol/L or higher; can be near normal (euglycemic DKA)	Typically 34.0 mmol/L or higher
Ketones	Positive in serum or urine; capillary beta-hydroxybutyrate is a sensitive test	Minimal

Feature	DKA	HHS
Acid–base	pH 7.3 or less, bicarbonate 15 mmol/L or less, anion gap above 12 mmol/L	Minimal or no acidosis
Osmolality	May be raised	Above 320 mmol/kg
Dehydration	Present	Usually more severe
Mental status	Alert to drowsy; may be altered	More often depressed; seizures or stroke-like signs possible
Key treatment points	Fluids, potassium, IV insulin until the anion gap closes; dextrose added as glucose falls	Fluids individualized; potassium; insulin; slow fall in osmolality

Treatment Priorities and Nursing Care

DKA and HHS are treated with a written protocol, ideally in an intensive care unit (ICU) or step-down unit with specialist input. Diabetes Canada's protocol elements are fluid resuscitation, avoiding low potassium, insulin, avoiding a rapid fall in osmolality, and finding the trigger (Goguen & Gilbert, 2018). The nurse carries out each element by order and watches for the problems each one can cause:

- **Fluids first:** IV 0.9% sodium chloride restores circulating volume. The nurse tracks blood pressure, heart rate, urine output and lung sounds, watching for fluid overload in older adults and people with heart or kidney disease.
- **Potassium:** potassium is added to the IV fluid once urine output is established and the serum potassium is below about 5.0 to 5.5 mmol/L. If potassium is below 3.3 mmol/L, insulin is withheld until potassium reaches at least 3.3 mmol/L (Goguen & Gilbert, 2018). The nurse checks the latest potassium before the infusion starts and reports values outside the protocol's limits at once.
- **IV insulin:** a short-acting insulin infusion runs by protocol and continues until the anion gap returns to normal. Once glucose falls to about 14.0 mmol/L, dextrose is added to the IV fluid to hold glucose at 12.0 to 14.0 mmol/L while insulin continues (Goguen & Gilbert, 2018). Insulin infusions are high-alert medications (section 22.3).
- **Monitoring:** vital signs, fluid status, neurologic status, electrolytes, anion gap, osmolality and glucose are checked as often as every 2 hours at first (Goguen & Gilbert, 2018), and bedside glucose every 1 to 2 hours during IV insulin (Malcolm et al., 2018). The protocol sets the exact schedule.
- **Neurologic checks:** osmolality should fall no faster than about 3 mmol/kg per hour. Life-threatening cerebral edema is mainly a risk in children and adolescents; in adults, rapid fluid replacement was linked to it in one study but not another (Goguen & Gilbert, 2018). New headache, vomiting that returns, or a falling level of consciousness is reported at once.
- **Finding the trigger:** the team looks for infection, a cardiac event or another cause. The nurse asks without judgment why insulin was missed; cost, supply problems, fear of hypoglycemia or diabetes distress may lie behind it (section 22.6).

When the anion gap has closed and the person can eat, the team changes to subcutaneous insulin. The first subcutaneous dose overlaps the infusion so that the patient is never left without insulin. Diabetes Canada's in-hospital chapter describes giving short- or rapid-acting insulin 1 to 2 hours, or intermediate- or long-acting insulin 2 to 3 hours, before IV insulin is stopped (Malcolm et al., 2018); the hospital's protocol sets the exact timing.

Deaths from DKA and HHS still occur; about half happen in the first 48 to 72 hours, from the triggering illness, electrolyte problems (especially potassium) or cerebral edema (Goguen & Gilbert, 2018). Any nurse who sees falling consciousness, low blood pressure, falling urine output, chest pain or a potassium outside the protocol's limits calls the rapid response team and reports using SBAR (Chapter 6). Insulin infusions are often assigned to RNs by employer policy; an RPN caring for a patient who develops DKA acts at once and consults the RN as the patient's needs change (Chapter 1, section 1.3). Before discharge, the nurse reviews sick-day guidance (section 22.6).

> GOING DEEPER
>
> **Closing the Gap — Potassium and the Anion Gap in DKA**
>
> *Required for RN students; optional for PN students.*

Insulin moves potassium from the blood into cells. In DKA, the serum potassium often looks normal at first because acidosis and insulin deficiency have shifted potassium out of cells, while urine losses have emptied the body's stores (Goguen & Gilbert, 2018). Once fluids dilute the blood and the insulin infusion starts, potassium moves back into cells and the serum level can fall quickly. Starting insulin when potassium is already below 3.3 mmol/L risks dangerous hypokalemia, which can cause dysrhythmias; this is why insulin waits until potassium reaches at least 3.3 mmol/L (Chapter 3 explains potassium shifts).

Glucose falls faster than ketones clear. If the infusion were stopped when glucose reached a normal value, ketone production would restart. Diabetes Canada therefore uses the anion gap, not the glucose, as the endpoint: IV insulin continues until the anion gap returns to normal, and dextrose is added once glucose reaches about 14.0 mmol/L so that insulin can keep running without causing hypoglycemia (Goguen & Gilbert, 2018). The anion gap is calculated as sodium minus the sum of chloride and bicarbonate (Chapter 3). A gap that falls from 26 to 11 mmol/L shows that ketoacids are clearing, even if glucose has been near target for hours. Capillary beta-hydroxybutyrate may also be used to adjust the insulin.

22.6 Diabetes in Hospital, Complications and Living Well

Glucose Management in Hospital

Illness, stress, steroids, changes in eating and bed rest all disturb glucose control. Diabetes Canada recommends these targets for most adults in hospital, as long as they can be reached safely (Malcolm et al., 2018):

- **Not critically ill:** glucose of 5.0 to 8.0 mmol/L before meals and below 10.0 mmol/L at random times.
- **Critically ill:** glucose kept between 6.0 and 10.0 mmol/L, usually with an IV insulin infusion.

Bedside glucose checks are individualized: before meals and at bedtime for people who are eating, every 4 to 6 hours for people who are NPO or on continuous tube feeds, and every 1 to 2 hours during IV insulin or critical illness. An A1C is measured on admission if none was done in the previous 3 months (Malcolm et al., 2018).

Diabetes Canada recommends a proactive **basal-bolus insulin** plan with correction: basal insulin covers the body's background needs, bolus (mealtime) insulin covers food, and correction insulin treats a high reading before a meal. Basal insulin is not withheld when a person is eating poorly, even if the bolus dose is reduced. **Sliding-scale insulin**, a correction-only approach that gives insulin only after glucose is already high, is discouraged as the sole way to treat high glucose (Malcolm et al., 2018). It supplies no background insulin and reacts after the fact. For a person with type 1 diabetes, a correction-only order leaves them without basal insulin, the setting for DKA (section 22.5). The nurse who sees such an order questions it with the prescriber.

Other situations need planning:

- **Procedures and NPO:** Chapter 7 covers fasting plans and holding drugs before surgery.
- **Corticosteroids:** glucose monitoring may be considered for 48 hours after a steroid is started. A basal-bolus-correction plan works better and more safely than correction-only insulin. Insulin may need changing when the steroid dose changes, including at discharge (Malcolm et al., 2018).
- **Tube feeding:** when feeds are interrupted, IV dextrose may be ordered to keep glucose from falling.
- **Self-management in hospital:** a person who is mentally competent and able to inject insulin and check glucose may manage their own diabetes under hospital policy, with the team's agreement. People using insulin pumps (Figure 22.4) are encouraged to continue them when it is safe and feasible (Malcolm et al., 2018).

Discharge planning starts early. Diabetes Canada recommends written and spoken instructions on how often to check glucose, how to manage hypoglycemia, a reconciled medication list and whom to call, along with communication with the primary care provider, especially when steroids or insulin have changed (Malcolm et al., 2018).

Chronic Complications

Long-term high glucose damages large and small blood vessels and nerves. Coronary disease is covered in Chapter 17, hypertension and peripheral arterial disease in Chapter 19, kidney disease in Chapter 27 and retinopathy in Chapter 36.

Peripheral neuropathy is nerve damage from prolonged high glucose, most often in the feet and legs. High glucose, high triglycerides, a higher body mass index, smoking and hypertension raise its risk (Bril et al., 2018). People notice numbness, tingling and lost sensation in the toes and feet, or sharp, shooting or burning pain. Loss of protective sensation means a stone in a shoe or a burn from hot water can go unnoticed, which is why neuropathy raises the risk of foot ulcers and amputation. Diabetes Canada recommends yearly screening, starting at diagnosis in type 2 diabetes and 5 years after puberty in type 1 diabetes, by testing sensation to a 10 g monofilament or to vibration with a 128 Hz tuning fork at the great toe (Bril et al., 2018). Painful neuropathy may be treated with anticonvulsant or antidepressant drugs, among other options (Bril et al., 2018; Chapter 5).



Figure 22.4 An adult with type 1 diabetes wearing an insulin pump on his waistband, with tubing to an infusion set on the abdomen, and a continuous glucose sensor. Pumps deliver rapid-acting insulin continuously, plus doses for meals. (credit: "Diabetic Type 1 adult man with insulin pump and CGM sensor" by Medtd1/Wikimedia Commons, CC BY-SA 4.0)

Autonomic neuropathy affects the nerves that control internal organs (Bril et al., 2018). Signs include:

- **Cardiovascular:** orthostatic hypotension (a systolic drop of more than 20 mm Hg on standing without an adequate rise in heart rate) and a resting heart rate above 100.
- **Gastrointestinal:** gastroparesis (slow stomach emptying), constipation and night-time diarrhea.
- **Bladder:** reduced sensation, incomplete emptying, overflow incontinence and urinary infections (Chapter 28).
- **Sexual:** erectile dysfunction.
- **Sweating:** less sweating in the hands and feet, more on the trunk, or sweating with meals.

These signs change nursing care. Orthostatic hypotension raises fall risk, so the nurse checks lying and standing blood pressure and teaches slow position changes. Autonomic neuropathy is also a risk factor for severe hypoglycemia (Lega et al., 2023).

Foot Care

Lower-limb complications are a major cause of illness and death in diabetes. In Canada, adults with diabetes are 20 times more likely than other adults to be hospitalized for a nontraumatic lower-limb amputation (Embil et al., 2018). Risk factors for ulcers and amputation include peripheral neuropathy, a previous ulcer or amputation, foot deformity, limited joint mobility, other microvascular complications, a higher A1C and fungal nail infection. Amputation rates are not shared equally; Chapter 19 describes higher rates among First Nations people in Ontario and in rural and remote regions.

Diabetes Canada recommends that health-care providers examine the feet at least yearly, and more often for people at high risk (Embil et al., 2018). The examination includes:

- **Neuropathy:** a person who cannot feel a 10 g monofilament on the sole is at higher risk of ulcers and amputation.
- **Skin:** calluses, blisters, cracks, ulcers and signs of infection, including between the toes.
- **Circulation:** pedal pulses and skin temperature (Chapter 19).
- **Structure:** deformities and the range of motion of the ankle and toe joints.
- **Footwear:** fit and wear.

Figure 22.5 A foot ulcer over a Charcot deformity, a collapse of the midfoot bones that can follow neuropathy. The ulcer sits where pressure falls on a foot that has lost sensation. (credit: "Diabetic Charcot Foot Deformity" by Medicalpal/Wikimedia Commons, CC BY-SA 4.0)

Wounds Canada's Inlow's 60-second Diabetic Foot Screen gives a quick, structured way to do this; it scores 12 elements for each foot, needs only a 10 g monofilament and clinical skill, and the scores guide follow-up (Wounds Canada, n.d.).

Redness does not look red on many skin tones. On darker skin, inflammation or infection may appear as a darker, purple or grey area. The nurse compares the area with the surrounding skin and the other foot, feels for warmth with the same hand, and looks for swelling, tightness and pain (Wounds International, 2023). Because neuropathy dulls pain, an ulcer or infection may hurt very little. Diabetes Canada recommends prompt treatment of ulcers or infection by an interprofessional team even when there is no pain. An uninfected neuropathic foot ulcer does not need antibiotics; care includes removing dead tissue, keeping the wound moist and taking pressure off it (offloading) (Embil et al., 2018). A hot, swollen foot may be an acute Charcot foot, which needs immobilization, often for months. Signs of poor circulation call for prompt referral to a vascular specialist. Wound care is covered in depth in Chapter 35.

A **diabetic foot ulcer** is a break in the skin of the foot in a person with diabetes, usually from pressure on a foot that has lost sensation (Figures 22.5 and 22.6). People at high risk need teaching about foot care and footwear fitted by a professional, with early referral to a foot care professional when problems appear (Embil et al., 2018).

Self-Management, Access and Equity

People with diabetes make most of their care decisions themselves, every day. Diabetes Canada recommends collaborative, interactive self-management education and support, delivered by an interprofessional team in groups, one-to-one or both, and supported by text messages or apps (Sherifali et al., 2018). Culturally appropriate programs, which may use peer or lay educators, and materials written for people with lower literacy and numeracy improve results. Gains are seldom kept after 3 months without ongoing support, so the nurse connects the person with a diabetes education program before discharge. Community-led programs in First Nations, Inuit and Métis communities are described in section 22.1.

Sick-day medication guidance tells people which medications to stop for a short time when they are ill and cannot keep up their fluid intake. Dehydration can reduce kidney function, and some drugs then harm the kidneys or build up in the body (Diabetes Canada, n.d.-b). Table 22.4 summarizes the guidance.

Figure 22.6 An arterial ulcer for comparison: a round, punched-out wound on the foot with little drainage, caused by poor blood flow rather than pressure. Many people with diabetes have both neuropathy and arterial disease (Chapter 19). (credit: "Arterial ulcer peripheral vascular disease" by Jonathan Moore/Wikimedia Commons, CC BY 3.0)

Cost shapes self-management. Supplies, CGM sensors and newer drugs are expensive, and public coverage differs across provinces and territories and changes often. In Ontario, for example, the Assistive Devices Program began funding real-time CGM in March 2022 for some people with type 1 diabetes at high risk from hypoglycemia, and as of 2022 the Ontario Drug Benefit program

covered flash glucose monitors for eligible recipients (Ontario Ministry of Health, 2022); coverage has continued to change since then. Diabetes Canada urges care teams to ask about affordability (Robinson et al., 2023), and food insecurity raises the risk of severe hypoglycemia (Lega et al., 2023; Chapter 2).

Living with diabetes is hard work. **Diabetes distress** is the negative emotion and burden of self-management that come from living with diabetes; it affects about one-third (36%) of people with diabetes (Robinson et al., 2023). Diabetes Canada recommends screening everyone with diabetes for distress at appropriate intervals, with tools such as the Diabetes Distress Scale or the Problem Areas in Diabetes scale, and regular screening for symptoms of mental health conditions such as depression. Distress and stigma can make people reluctant to start insulin, and some people use less insulin than prescribed because of its cost (Robinson et al., 2023). The nurse listens without blame, names distress as common, and refers the person for support.

Table 22.4 Sick-day guidance for adults with diabetes (Diabetes Canada, n.d.-b; Goguen & Gilbert, 2018; original wording)

What to do	Why	When to get help
Stop certain medications for a short time if unable to keep up fluids: angiotensin-converting enzyme (ACE) inhibitors, angiotensin II receptor blockers (ARBs), direct renin inhibitors, diuretics, nonsteroidal anti-inflammatory drugs (NSAIDs) and SGLT2 inhibitors	These drugs raise the risk of reduced kidney function; SGLT2 inhibitors also raise the risk of ketoacidosis	Discuss every medication change, including when to restart, with the care team
Stop metformin and sulfonylureas (gliclazide, glimepiride, glyburide) for a short time if unable to keep up fluids	Reduced clearance raises the risk of adverse effects	Call the care team if glucose runs too high or too low
Follow the sick-day plan for insulin; doses may need adjusting	Missed insulin is a common trigger for DKA	Call the care team for insulin dose advice when glucose is running high or low
Check glucose more often than usual, such as every 2 to 4 hours	Illness can push glucose up or down quickly	Glucose that stays high or low despite treatment
In type 1 diabetes, check blood ketones when glucose stays above 14.0 mmol/L or symptoms of DKA appear	Ketones are an early sign of DKA	Blood ketones above 1.5 mmol/L need further testing for DKA; vomiting, abdominal pain or fast, deep breathing need prompt assessment
Check with a pharmacist before using over-the-counter pain or cold remedies	Many contain NSAIDs	Any doubt about an over-the-counter product

PATIENT EDUCATION

Caring for Your Feet

Diabetes can reduce feeling in your feet and slow blood flow, so you may not notice an injury. These steps protect your feet (Embil et al., 2018):

- Look at your feet and legs every day, including the soles and between the toes.
- Watch for any change in colour (on darker skin, an area may look darker, purple or grey rather than red), warmth, swelling, a blister, a cut or drainage.
- Test bath water with your hand before you step in.
- Wear shoes that fit properly. If your feet are at high risk, ask about professionally fitted footwear.
- Care for your nails regularly. Do not cut corns, calluses or ingrown toenails yourself; see your health-care provider or a foot care specialist.
- Have your feet checked by a health-care provider at least once a year, and more often if you have been told your feet are at high risk.
- See a health-care provider right away if a foot is swollen, warm, discoloured or painful, or if you find a sore, even if it does not hurt.

LIFESPAN CONSIDERATIONS

Older Adults With Diabetes

Targets for older adults depend on health and function, not age alone (Meneilly et al., 2018):

- **Functionally independent older adults:** an A1C of 7.0% or less is suggested when treatment does not include insulin or a sulfonylurea, with glucose of 4 to 7 mmol/L before meals.
- **Frail older adults or those with dementia:** an A1C below 8.5% with low-risk treatment, or 7.1% to 8.5% if treatment includes insulin or a sulfonylurea, with glucose of 6 to 9 mmol/L before meals.
- **End of life:** A1C is not measured; the aim is to avoid symptomatic hyperglycemia and any hypoglycemia.

Older adults with diabetes are at greater risk of falls and fractures, and insulin and sulfonylureas add to that risk. Among the sulfonylureas, Diabetes Canada prefers gliclazide and glimepiride to glyburide in older people (Meneilly et al., 2018). Frail residents of long-term care (LTC) remain at high risk of hypoglycemia; Diabetes Canada recommends avoiding sliding-scale and correction-only insulin protocols for them and suggests regular rather than "diabetic" diets. Deprescribing and falls are covered in Chapter 8.

SCOPE IN PRACTICE

Insulin, Medical Directives and Who Adjusts Doses

Whether a nurse performs a task depends on **authority, competence and context** (Chapter 1, section 1.3); employer policy and the province or territory also matter.

- **Authority to give insulin:** in Ontario, administering a substance by injection is a controlled act that the *Nursing Act, 1991* authorizes for registered nurses (RNs) and registered practical nurses (RPNs) when it is ordered or permitted by regulation (College of Nurses of Ontario [CNO], 2025). Insulin needs a direct (client-specific) order or a directive.
- **Adjusting doses:** a nurse changes an insulin dose only as an order or a medical directive allows, for example a correction-insulin order or a titration protocol. A **medical directive** (CNO's term is "directive") is an order for a group of patients who meet stated conditions; the provider who issues it stays responsible for it (CNO, n.d.-b).
- **Prescribing:** Ontario RNs who prescribe may do so only for the purposes listed in the regulation, such as immunization, contraception and smoking cessation; managing diabetes is not one of the listed purposes (CNO, n.d.-a). RN prescribing is not used in public hospitals.
- **Hypoglycemia protocols:** nurse-initiated treatment by protocol is recommended in hospital (Malcolm et al., 2018).
- **Safeguards:** independent double checks of insulin and insulin infusions follow employer policy (section 22.3).
- **Context:** many employers assign insulin infusions to RNs; an RPN consults the RN when glucose is unstable or the patient's needs change. Rules differ in other provinces and territories.

PRACTICE STORY

The Supper Tray Came Late

Names and details are fictional; this is a composite story.

Nurse: Tomasz Nowak, RN. Years in practice: 4. Setting: medical unit, Ontario.

Mrs. Evelyn Mercier is 76 and was admitted with a urinary infection. She has type 2 diabetes and takes basal insulin at bedtime and insulin aspart with meals. At 1655 I heard the supper cart in the hall. Her glucose was 6.4 mmol/L, so I checked her order, gave her mealtime insulin and moved on to my next patient.

The cart was not ours. It belonged to the unit next door. Our trays were held up because the kitchen was short-staffed, and Mrs. Mercier's tray was being remade after her diet order changed that afternoon.

At 1730 her call bell rang. She said she felt "shaky and hollow." Her hands trembled and her forehead was damp. Her glucose was 3.6 mmol/L.

I knew what had happened. The monograph for insulin aspart says to give it no more than 5 to 10 minutes before a meal, and its onset is within 10 to 20 minutes (Novo Nordisk Canada, 2026). I had given it before I could see her food.

I followed our hypoglycemia protocol. I gave her 15 g of glucose tablets from the unit kit and stayed with her. At 1745 her glucose was 5.2 mmol/L, and her tray arrived a few minutes later. I sat with her while she ate and rechecked her glucose an hour later. It was 7.8 mmol/L.

I told the charge nurse and the physician, documented the event, and filed an incident report. I also apologized to Mrs. Mercier and explained what had gone wrong. She said, "Well, at least you came quickly."

> Our unit now has a simple rule for rapid-acting insulin: the tray is at the bedside, the patient is ready to eat, and then the insulin is given. For a patient who eats unpredictably, we ask the prescriber whether the dose can be given right after the meal. I still hear carts in the hall. I just don't trust them anymore.
>
> Reflect: What cues should the nurse confirm before giving mealtime insulin? If an RPN had given the insulin, which actions would be within the RPN's scope, and when should the RPN involve the RN?

Chapter 22 Summary

Introduction

- About 3.9 million people in Canada aged 1 year and older (9.7%) were living with diagnosed diabetes in 2023–2024.
- Nurses check glucose, give glucose-lowering drugs safely, recognize emergencies and support self-management on every unit.

22.1 Glucose Regulation and Types of Diabetes

- Insulin lowers glucose and holds back fat breakdown and ketone formation; glucagon and stress hormones raise glucose; incretins boost insulin after meals.
- Type 1 diabetes is mainly autoimmune beta-cell destruction with insulin deficiency; type 2 combines insulin resistance with a beta-cell defect.
- Diabetes Canada's risk factors include age 40 or older, family history, membership in listed high-risk populations, prediabetes, vascular risk factors, some conditions and some drugs; higher rates in some communities reflect structural causes, not biology.
- Diabetes is diagnosed by fasting glucose of 7.0 mmol/L or higher, A1C of 6.5% or higher, or a 2-hour or random glucose of 11.1 mmol/L or higher, confirmed on another day when there are no symptoms.
- First Nations data are governed under OCAP®; communities lead prevention programs such as the Kahnawake Schools Diabetes Prevention Project.

22.2 Monitoring Glucose

- Point-of-care glucose testing follows hospital policy; washing and drying hands, using the first drop and avoiding squeezing improve accuracy.
- CGM measures interstitial glucose, which trails blood glucose; symptoms that do not match a sensor reading call for a capillary check.
- Time in range (3.9–10.0 mmol/L) above 70% is the target for most adults, with lows kept under 4% and 1%.
- A1C reflects average glucose over 8 to 12 weeks; targets are individualized, usually 7.0% or less, and higher for frail older adults.
- Blood ketone testing is preferred to urine testing during illness with high glucose in type 1 diabetes.

22.3 Insulin and Non-Insulin Medications

- Insulins are grouped as rapid-acting, short-acting, intermediate-acting, long-acting, premixed and concentrated; the nurse knows each one's onset, peak and duration.
- Insulin is a high-alert medication: read the full product name, use "units", keep pens to one patient and time bolus insulin with the meal.
- Rotating sites and avoiding lipohypertrophy keeps insulin absorption predictable.
- Metformin is first-line; specific SGLT2 inhibitors and GLP-1 receptor agonists are recommended for heart and kidney protection whatever the A1C.
- Insulin and secretagogues cause hypoglycemia; SGLT2 inhibitors can cause euglycemic ketoacidosis; GLP-1-based drugs cause stomach effects.

22.4 Hypoglycemia

- Diabetes Canada's 2023 update uses an alert value below 3.9 mmol/L and three levels; level 3 means the person needs help, whatever the reading.
- In hospital, lows usually come from late or missed meals, NPO status, interrupted feeds, falling kidney function and steroid tapers; food insecurity raises risk at home.
- Autonomic and neuroglycopenic symptoms can be weak or absent with impaired awareness, in frail older adults and with beta-blockers; clammy skin is felt on every skin tone.
- Treat at once by protocol: 15 g of fast-acting carbohydrate (20 g for level 3 if able to swallow), recheck in 15 minutes, then a meal or snack; glucagon or IV dextrose if the person cannot swallow.
- Glucagon 1 mg injected or 3 mg intranasally; nasal glucagon is marketed in Canada, while injectable glucagon has relied on imports since the Canadian products were discontinued in 2023 and 2024.
- Teaching covers carrying glucose, wearing diabetes identification, glucagon for support persons, CGM for high-risk people and Diabetes Canada's driving advice.

22.5 Hyperglycemic Emergencies: DKA and HHS

- DKA combines hyperglycemia, ketones and a high anion gap acidosis; HHS combines extreme hyperglycemia and high osmolality with minimal acidosis.
- Triggers include missed insulin, new diabetes and infection; SGLT2 inhibitors can cause DKA with a near-normal glucose.
- Kussmaul respirations, vomiting, abdominal pain, dehydration and altered consciousness are key signs; HHS causes more severe dehydration and depressed consciousness.
- Treatment follows a protocol: fluids first, potassium replacement, insulin held if potassium is below 3.3 mmol/L, IV insulin until the anion gap closes, and dextrose once glucose reaches about 14.0 mmol/L.
- The nurse monitors closely, watches for falling potassium and neurologic change, finds the trigger and escalates deterioration at once.

22.6 Diabetes in Hospital, Complications and Living Well

- In-hospital targets are 5.0 to 8.0 mmol/L before meals and below 10.0 mmol/L at random times for most patients, and 6.0 to 10.0 mmol/L for critically ill patients.
- Basal-bolus-correction insulin is recommended; sliding-scale insulin alone is discouraged, and basal insulin is not withheld when intake is poor.
- Peripheral and autonomic neuropathy raise the risk of foot ulcers, falls and unpredictable glucose; screening uses a 10 g monofilament or a 128 Hz tuning fork.
- Feet are examined at least yearly; signs of infection are judged by warmth, swelling and change from surrounding skin on every skin tone, and ulcers get prompt interprofessional care.
- Self-management education, sick-day guidance, attention to cost and food security, and screening for diabetes distress support living well.
- RNs and RPNs give and adjust insulin only by order or directive; employer policy and province shape who manages infusions.

Key Terms (41)

A1C: the percentage of hemoglobin with glucose attached, reflecting average glucose over the previous 8 to 12 weeks

acanthosis nigricans: thick, velvety, darker skin in body folds such as the neck and armpits; a sign of insulin resistance

anion gap: the difference between measured positive and negative ions (sodium minus chloride and bicarbonate); a raised gap in DKA shows unmeasured ketoacids, and its return to normal marks resolution (see Chapter 3).

autonomic neuropathy: damage to the nerves that control internal organs, causing problems such as orthostatic hypotension, gastroparesis, bladder dysfunction and sweating changes.

basal insulin: background insulin that controls glucose between meals and overnight

basal-bolus insulin: an insulin plan that combines background (basal) insulin, mealtime (bolus) insulin and correction insulin for high readings.

biosimilar: a lower-cost insulin highly similar to an original brand-name insulin

bolus (prandial) insulin: insulin given with meals to cover the rise in glucose from food

continuous glucose monitoring (CGM): measurement of interstitial glucose every few minutes by a sensor under the skin

correction insulin: extra rapid- or short-acting insulin added to the scheduled dose when glucose is above target

diabetes distress: the negative emotions and burden of self-management that come from living with diabetes.

diabetic foot ulcer: a break in the skin of the foot in a person with diabetes, usually from pressure on a foot that has lost sensation.

diabetic ketoacidosis (DKA): a hyperglycemic emergency in which insulin deficiency leads to ketone production, metabolic acidosis with a high anion gap, and dehydration.

euglycemic diabetic ketoacidosis: ketoacidosis with glucose only mildly raised or normal, a rare risk with SGLT2 inhibitors

euglycemic diabetic ketoacidosis: DKA with a normal or only mildly raised glucose, seen especially with SGLT2 inhibitors.

GLP-1 receptor agonist: a drug that copies the incretin GLP-1, boosting glucose-dependent insulin release, lowering glucagon and slowing stomach emptying

glucagon: the alpha-cell hormone that raises glucose between meals by making the liver release and produce glucose

glucagon: a hormone that raises blood glucose by releasing liver glycogen; given by injection or intranasally to treat severe hypoglycemia when a person cannot swallow.

glucose management indicator (GMI): an estimate of A1C calculated from the mean glucose on a CGM report

high-alert medication: a drug with a heightened risk of serious harm when used in error

hyperglycemic hyperosmolar state (HHS): a hyperglycemic emergency with very high glucose, high plasma osmolality and severe dehydration, but minimal or no acidosis.

hypoglycemia: a blood glucose level low enough to cause symptoms or risk harm; Diabetes Canada's 2023 update uses an alert value below 3.9 mmol/L and grades severity in three levels.

impaired awareness of hypoglycemia: weak or absent warning symptoms of a low glucose, so that confusion or loss of consciousness may be the first sign.

incretins: gut hormones, mainly GLP-1 and GIP, released after meals that boost insulin release when glucose is high

insulin: the beta-cell hormone that moves glucose into cells, stops the liver releasing glucose and holds back fat breakdown and ketone formation

insulin resistance: a reduced response of body cells to insulin, so more insulin is needed to keep glucose normal

insulin secretagogue: a drug, such as a sulfonylurea or meglitinide, that makes the pancreas release insulin whatever the glucose level

ketones: acids made by the liver from fatty acids when insulin is lacking; beta-hydroxybutyrate is the main one in ketoacidosis

Kussmaul respirations: deep, rapid breathing that removes carbon dioxide to offset a metabolic acidosis, as in DKA.

lipohypertrophy: a lump of thickened fatty tissue at an overused injection site, from which insulin is absorbed poorly and unpredictably

medical directive: an order that authorizes care for a group of patients who meet stated conditions; the provider who issues it remains responsible for it.

monofilament testing: a screening test of protective sensation in which a 10 g nylon filament is pressed against the foot; loss of sensation predicts ulcers and amputation.

peripheral neuropathy: nerve damage from prolonged high glucose, mainly in the feet and legs, causing numbness, tingling, pain or loss of protective sensation.

point-of-care glucose testing: bedside measurement of capillary glucose with a meter approved and quality-checked under hospital policy

prediabetes: impaired fasting glucose, impaired glucose tolerance or an A1C of 6.0% to 6.4%; a high risk of developing diabetes

SGLT2 inhibitor: a drug that lowers glucose by making the kidneys excrete it, and protects the heart and kidneys

sick-day medication guidance: advice on which medications to pause for a short time when a person with diabetes is ill and cannot keep up fluids.

sliding-scale insulin: a correction-only approach that gives insulin only after glucose is already high; discouraged as the sole treatment in hospital.

time in range: the percentage of CGM readings between 3.9 and 10.0 mmol/L

type 1 diabetes: diabetes caused mainly by destruction of the pancreatic beta cells, usually autoimmune, leading to insulin deficiency and a tendency to ketoacidosis

type 2 diabetes: diabetes caused by insulin resistance together with a beta-cell defect that leaves insulin output too low

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mr. Gérald Beaulieu (Questions 1–4): Mr. Gérald Beaulieu, 76, has had type 2 diabetes for 14 years and takes metformin and gliclazide. He was admitted to a medical unit in Ontario with a lower leg infection, and his A1C is 9.6%. Before discharge, the prescriber orders insulin glargine once daily at bedtime and asks the registered practical nurse (RPN) to teach him to use a pen. He lives with his wife and has mild arthritis in his hands.

1. [CORE] Which statement by Mr. Beaulieu shows that he understands the purpose of his new insulin?

a. "I take this insulin right before supper so my sugar does not go up after I eat."

b. "If my sugar is normal when I get up, I can skip that night's injection."

c. "Once I start this insulin, I won't need to check my sugar with my meter in the mornings or at bedtime any more."

d. "This insulin works slowly in the background to keep my sugar steady overnight and between meals."

Answer: d — Glargine is a long-acting basal insulin with no peak that controls glucose between meals and overnight (d) (section 22.3, Table 22.2). Covering a meal (a) is the job of a bolus insulin. Basal insulin is not skipped because one reading is normal (b); the prescriber's plan guides any change. Starting insulin makes glucose checks more important, not less (c) (section 22.2).

2. [CORE] During a return demonstration, which action by Mr. Beaulieu requires further teaching?

a. He attaches a new pen needle before the injection.

b. He injects into the same spot near his navel each night because it hurts less there.

c. He inserts the short pen needle straight in at a 90-degree angle.

d. He keeps the pen for his own use and does not lend it to his wife, even with a fresh needle.

Answer: b — Injecting repeatedly into one spot causes lipohypertrophy, from which insulin is absorbed poorly and unpredictably; he needs to rotate across a wide area (b) (section 22.3). A new needle for each injection (a), a 4 mm needle at 90 degrees (c) and never sharing a pen (d) are all correct practice.

3. [CORE] Which teaching point about hypoglycemia is most important for Mr. Beaulieu now that he is starting insulin?

a. Hypoglycemia is unlikely with glargine because it has no peak, so shakiness or sweating at night needs no action.

b. Shakiness, sweating or confusion means checking his meter and treating a low at once, since gliclazide adds to the risk.

c. Low glucose happens mainly in type 1 diabetes, so he can rely on his wife to notice any warning signs and tell him.

d. If he feels unwell or shaky during the night, he should take an extra metformin tablet to steady his glucose until morning.

Answer: b — Insulin and sulfonylureas such as gliclazide carry the highest risk of hypoglycemia, and the risk adds up when they are combined and when meals are missed (b) (section 22.3; recognition and treatment in section 22.4). Basal insulin can still cause hypoglycemia (a). Hypoglycemia occurs in type 2 diabetes treated with insulin or secretagogues (c). Extra metformin does not treat symptoms and is not part of his plan (d).

4. [CORE] Mr. Beaulieu asks the RPN, "If my morning readings are high at home, can I just add a few units on my own?" Which response is most appropriate?

a. "Yes. Most people add 2 units each night until the morning reading is normal, so you can start that at home."

b. "You should never change your insulin dose under any circumstances."

c. "Your prescriber will give you a written plan for changes. Let's confirm you have it and a follow-up visit booked."

d. "If your morning reading is over 10 mmol/L, double that night's dose and call the clinic if it stays high after a week."

Answer: c — Changing an insulin dose requires an order or a written titration plan from the prescriber, and follow-up to review home readings is part of a safe discharge (c) (section 22.3; Scope in Practice box in section 22.6). The RPN cannot invent a titration rule (a, d). Many people safely adjust their own doses using a written plan, so "never" (b) is inaccurate and discourages self-management.

5. [CORE] A 52-year-old man with no symptoms has a fasting plasma glucose of 7.4 mmol/L at a routine visit. What does the nurse expect to happen next?

a. Repeat testing on another day to confirm the result

b. Diagnosis of type 2 diabetes based on this single result

c. Diagnosis of prediabetes, because he has no symptoms

d. No further testing, because one fasting value cannot diagnose diabetes

Answer: a — Without symptoms, a single result in the diabetes range is confirmed by a repeat test on another day, preferably the same test (a) (section 22.1, Table 22.1). One result is enough only when symptoms are present (b). A fasting value of 7.0 mmol/L or higher is in the diabetes range, not the prediabetes range (c). Fasting glucose is a valid test; it needs confirmation, not abandonment (d).

6. [CORE] A 47-year-old woman's A1C is 6.2%. Which interpretation is correct?

a. Prediabetes

b. Normal glucose regulation

c. Type 2 diabetes

d. Well-controlled type 1 diabetes

Answer: a — An A1C of 6.0% to 6.4% falls in the prediabetes range (a) (section 22.1, Table 22.1). It is above normal (b). Diabetes requires an A1C of 6.5% or higher (c). A1C is not used to diagnose or classify suspected type 1 diabetes, and nothing suggests she has it (d).

7. [CORE] Which findings in a 45-year-old patient's history are risk factors for type 2 diabetes listed by Diabetes Canada? Select all that apply.

a. Mother has type 2 diabetes

b. Takes prednisone daily for an inflammatory condition

c. Childhood asthma, now resolved

d. Velvety, darker patches of skin at the back of the neck

e. Age over 40 years

f. Eats a vegetarian diet

Answer: a, b, d, e — A first-degree relative with type 2 diabetes (a), glucocorticoid use (b), acanthosis nigricans (d) and age 40 or older (e) are on Diabetes Canada's list (section 22.1). Past asthma (c) and a vegetarian diet (f) are not listed risk factors.

8. [CORE] A patient on a medical unit has just eaten an orange when the nurse arrives to check her capillary glucose before lunch. What should the nurse do?

a. Wipe the fingertip with an alcohol swab and use the second drop
b. Use her forearm instead of her fingertip
c. Have her wash and dry her hands, then test using the first drop
d. Squeeze the fingertip firmly to get a large drop quickly

Answer: c — Sugar on the skin can falsely raise a reading, so washing and drying the hands and using the first drop gives the most accurate result (c) (section 22.2). Wiping and using a second drop (a) is a fallback only when hands are not visibly soiled or exposed to sugar. Forearm samples lag behind fingertip values (b). Hard squeezing distorts results (d).

9. [CORE] A patient with type 1 diabetes wears a continuous glucose monitor. The sensor shows 4.8 mmol/L, but the patient is sweaty, shaky and says, "I feel low." What should the nurse do first?

a. Check a capillary glucose with the point-of-care meter
b. Reassure the patient that the sensor shows a normal value
c. Remove the sensor and send it back to the manufacturer
d. Wait 30 minutes and recheck the sensor reading

Answer: a — Sensor glucose lags behind blood glucose, especially when glucose is falling fast, so symptoms that do not match the sensor call for a capillary check right away (a) (section 22.2). Reassurance (b) or waiting (d) could delay treatment of hypoglycemia. The sensor may be working correctly; removing it (c) does not help the patient.

10. [CORE] A patient with type 1 diabetes has had vomiting since yesterday and a glucose of 16.5 mmol/L. Which test does the nurse expect to perform, as ordered?

a. A1C
b. Urine glucose
c. Blood ketones
d. Oral glucose tolerance test

Answer: c — People with type 1 diabetes check ketones during illness with high glucose, and blood ketone testing detects ketosis earlier than urine testing (c) (section 22.2; section 22.5). A1C (a) shows average glucose over months, not the current risk. Urine glucose (b) adds nothing to a known high blood glucose. An oral glucose tolerance test (d) is a diagnostic test and is unsafe in this situation.

11. [CORE] An 84-year-old resident with type 2 diabetes, moderate dementia and frailty has an A1C of 7.9%. Which statement about the target is consistent with Diabetes Canada's guidance?

a. An A1C of 7.1% to 8.5% may be an appropriate target, to avoid hypoglycemia.
b. The A1C should be lowered to 7.0% or less, as for most adults.
c. The A1C should be lowered to 6.5% or less to prevent complications.
d. A1C targets do not apply to people with dementia, so glucose is not monitored.

Answer: a — Diabetes Canada suggests 7.1% to 8.5% for frail older adults or people with dementia, because hypoglycemia is the greater danger (a) (section 22.2). The usual target of 7.0% or less (b) and the tighter 6.5% (c) increase hypoglycemia risk in this person. Targets are individualized, not abandoned (d).

12. [CORE] Which medication in a patient's list carries the highest risk of hypoglycemia?

a. Metformin
b. Sitagliptin
c. Empagliflozin
d. Gliclazide

Answer: d — Gliclazide is a sulfonylurea, an insulin secretagogue that makes the pancreas release insulin whatever the glucose level (d) (section 22.3). Metformin (a), the DPP-4 inhibitor sitagliptin (b) and the SGLT2 inhibitor empagliflozin (c) rarely cause hypoglycemia on their own.

13. [CORE] A nurse finds an insulin pen labelled for another patient in a patient's bedside drawer and learns that a colleague used it, with a new needle, to give this patient's dose. What is the most appropriate action?

a. Accept the practice, since a new needle was attached
b. Put the pen back in the correct patient's bin
c. Remove the pen from use, report the event through the incident system and notify the charge nurse
d. Wipe the pen's rubber seal with an alcohol swab and return the pen to the patient it is labelled for

Answer: c — Insulin pens are single-patient devices; sharing one, even with a new needle, can transmit bloodborne infection, so the pen is removed from use and the event is reported (c) (section 22.3). A new needle does not make sharing safe (a). Returning (b) or wiping (d) the pen leaves both patients at risk and hides the event.

14. [CORE] An RPN reviews an order that reads "insulin glargine 14U subcut at bedtime." What should the RPN do?

a. Give 14 units, since the meaning is clear
b. Give 140 units, since "U" is read as a zero
c. Hold the dose and document in the record that the order was unclear, then reassess at the next shift
d. Contact the prescriber to clarify the order and have it written with "units" spelled out

Answer: d — "U" can be misread as a zero, turning 14 units into 140; the safe action is to clarify the order with the prescriber so that "units" is written in full (d) (section 22.3, Clinical Safety box). Giving either dose from an unsafe order (a, b) risks harm. Holding without contacting the prescriber (c) leaves the patient without basal insulin and the order uncorrected.

15. [CORE] A practical nurse (PN) is caring for a patient with type 2 diabetes who takes dapagliflozin. The patient now has nausea, abdominal pain and rapid breathing, and the capillary glucose is 9.8 mmol/L. What is the PN's most appropriate action?

a. Reassure the patient that the glucose is acceptable and offer an antiemetic as ordered
b. Report the findings to the RN or prescriber at once, because they may signal ketoacidosis
c. Give the next dose of dapagliflozin and recheck the glucose before supper
d. Encourage the patient to rest and reassess at the end of the shift

Answer: b — SGLT2 inhibitors can cause euglycemic diabetic ketoacidosis, in which glucose is only mildly raised; these symptoms need urgent escalation and ketone testing as ordered (b) (section 22.3; section 22.5). A near-normal glucose does not rule out ketoacidosis (a). Giving another dose (c) or waiting (d) delays treatment of a possible emergency.

16. [CORE] A patient who takes metformin is scheduled for a CT scan with iodinated contrast. Which nursing action is appropriate?

a. Give metformin as usual, because iodinated contrast does not interact with it and kidney function is unaffected

b. Confirm the order to hold metformin around the scan and that kidney function is rechecked before restarting

c. Stop metformin permanently after the scan

d. Give a double dose of metformin the morning after the scan to make up for the dose held before it

Answer: b — Canadian monographs advise stopping metformin at the time of or before an iodinated contrast procedure, holding it for 48 hours and restarting only after kidney function is confirmed normal (b) (section 22.3). Giving it as usual (a) ignores this advice. The hold is temporary (c). Doubling a dose (d) is never a way to make up a held dose unless ordered.

17. [CORE] A patient starting a once-weekly GLP-1 receptor agonist asks about side effects. Which response is accurate?

a. "Nausea is common, so the dose is raised slowly over several weeks; call if vomiting stops you keeping fluids down."

b. "This medicine often causes low blood sugar on its own, so you will need a snack every 2 hours, including during the night."

c. "The most common side effect is weight gain from fluid retention, so weigh yourself daily and watch your portions."

d. "Side effects are rare, so you do not need to report anything new."

Answer: a — Stomach effects such as nausea, vomiting and diarrhea are common, especially at higher doses, so doses are increased slowly, and vomiting that prevents drinking needs attention (a) (section 22.3). GLP-1 receptor agonists rarely cause hypoglycemia on their own (b) and lead to weight loss, not gain (c). New symptoms should be reported (d).

18. [RN] A patient's 14-day CGM report shows the sensor was worn 92% of the time, time in range 58%, time above 10.0 mmol/L 36%, time below 3.9 mmol/L 6% and time below 3.0 mmol/L 2.5%, with most lows between 0200 and 0500. Which interpretation should the nurse share with the prescriber?

a. The report cannot be used, because time in range is below 70%.

b. Overnight hypoglycemia exceeds the targets and is the first problem to address, even though high values are also common.

c. High glucose is the main problem, so bolus insulin should be increased first.

d. Time below range is within target because it is under 10%.

Answer: b — The report has enough data (worn more than 70% of the time). Time below 3.9 mmol/L should be under 4% and time below 3.0 mmol/L under 1%, so overnight lows are unsafe and are addressed first (b) (section 22.2, Going Deeper box). A low time in range (a) is a finding, not a reason to discard the report. Increasing insulin first (c) could deepen the lows. The targets for time below range are 4% and 1%, not 10% (d).

19. [RN] A patient receives NPH insulin at 0800 and eats breakfast at 0815. When is the patient at greatest risk of hypoglycemia from this dose?

a. 0830 to 0930

b. 1000 to 1100

c. 1300 to 1600

d. 2200 to 0200

Answer: c — NPH insulin peaks 5 to 8 hours after injection, so the highest risk from a 0800 dose falls in the early to mid afternoon, and a late or missed lunch adds to it (c) (section 22.3, Table 22.2). NPH starts working 1 to 3 hours after injection, so the morning hours (a, b) come before its peak. Its action lasts up to 18 hours, but by late evening (d) the effect is waning.

20. [RN] A patient with type 2 diabetes who takes empagliflozin has had a poor appetite for 3 days. Results show glucose 10.8 mmol/L, blood beta-hydroxybutyrate 4.2 mmol/L and a serum bicarbonate of 12 mmol/L. How should the nurse interpret these findings?

a. Glucose is only mildly raised, so ketoacidosis is unlikely.

b. The findings fit hyperglycemic hyperosmolar state.

c. The findings suggest starvation ketosis, which needs only a snack.

d. The findings suggest euglycemic diabetic ketoacidosis, which needs urgent treatment even though glucose is modest.

Answer: d — High blood ketones with a low bicarbonate show ketoacidosis; with an SGLT2 inhibitor and poor intake, it can occur with only a mildly raised glucose (d) (section 22.3; section 22.5; acid–base in Chapter 3). A modest glucose does not exclude it (a). Hyperglycemic hyperosmolar state involves extreme hyperglycemia without significant ketosis (b). Ketones this high with a low bicarbonate are not simple starvation ketosis (c).

Case: Jordan Tremblay (Questions 21–26): Jordan Tremblay, 22, has had type 1 diabetes for 10 years. He comes to the emergency department after 2 days of vomiting; he stopped his insulin because he was not eating. He is drowsy but answers questions. Vital signs: temperature 37.4 °C, heart rate 118, respiratory rate 30 with deep breaths, blood pressure 98/60 mm Hg. Laboratory results: glucose 28.4 mmol/L, venous pH 7.12, bicarbonate 9 mmol/L, sodium 132 mmol/L, chloride 97 mmol/L, potassium 4.8 mmol/L, capillary beta-hydroxybutyrate 5.8 mmol/L.

21. [CORE] Which findings require immediate follow-up? Select all that apply.

a. Respiratory rate of 30 with deep breaths
b. Temperature of 37.4 °C
c. Glucose of 28.4 mmol/L
d. Capillary beta-hydroxybutyrate of 5.8 mmol/L
e. Potassium of 4.8 mmol/L
f. Blood pressure of 98/60 mm Hg with a heart rate of 118

Answer: a, c, d, f — Deep, rapid breathing, high glucose, high ketones and low blood pressure with tachycardia together show ketoacidosis and fluid loss that need treatment now (section 22.5). The temperature is close to normal, although infection is still looked for as a trigger. A potassium of 4.8 mmol/L is within range at this moment; it becomes important once insulin starts, but it is not itself abnormal yet.

22. [CORE] Which explanation best accounts for Jordan's breathing pattern?

a. He is anxious and hyperventilating because of abdominal pain.
b. Fluid is collecting in his lungs because of dehydration.
c. He is breathing off carbon dioxide to offset a metabolic acidosis.
d. Ketones in his blood are irritating his airways and causing bronchospasm.

Answer: c — Kussmaul respirations are deep, rapid breaths that remove carbon dioxide and partly offset the acidosis caused by ketones (section 22.5; Chapter 3). Anxiety does not explain a pH of 7.12. Dehydration does not cause fluid in the lungs. Ketones do not cause bronchospasm.

23. [CORE] Which problem should the nurse treat as the first priority?

a. Fluid loss severe enough to lower his blood pressure
b. Knowledge gap about managing insulin during illness
c. Risk of hypoglycemia once insulin treatment has begun
d. Potential for skin breakdown from drowsiness

Answer: a — Fluid loss with hypotension and tachycardia threatens circulation now, and fluids are the first element of Diabetes Canada's protocol (section 22.5). Sick-day teaching matters before discharge, not first. Hypoglycemia is a later risk that the protocol manages with dextrose. Skin breakdown is a lower priority.

24. [CORE] Which order should the nurse expect to carry out first?

a. A dose of rapid-acting insulin injected subcutaneously
b. An infusion of 0.9% sodium chloride intravenously
c. An infusion of sodium bicarbonate intravenously
d. Oral fluids with electrolytes, encouraged as tolerated

Answer: b — Diabetes Canada's protocol starts with IV 0.9% sodium chloride to restore volume (section 22.5). Insulin is not the first step; it starts after fluids are running and the potassium is confirmed to be at least 3.3 mmol/L. Bicarbonate is considered only for shock or a pH of 7.0 or less. A vomiting, drowsy patient cannot rehydrate by mouth.

25. [CORE] Six hours later, Jordan's insulin infusion is running. His glucose is 13.6 mmol/L and his anion gap is 18 mmol/L. Which action should the nurse anticipate?

a. Stopping the insulin infusion because glucose is now below 14.0 mmol/L
b. Giving his usual long-acting insulin and stopping the infusion right away
c. Adding dextrose to the IV fluid while the insulin infusion continues
d. Lowering the IV fluid rate and giving juice to prevent hypoglycemia

Answer: c — When glucose reaches about 14.0 mmol/L, dextrose is added so that insulin can continue until the anion gap returns to normal (section 22.5). An anion gap of 18 mmol/L shows that ketoacids are still present, so stopping the infusion would let ketosis return. Changing to subcutaneous insulin waits until the gap has closed. Juice does not replace the protocol's dextrose and he may still be vomiting.

26. [CORE] The next morning, which findings show that Jordan's treatment is working? Select all that apply.

a. Anion gap of 11 mmol/L
b. Respiratory rate of 18 with normal depth
c. Potassium of 3.1 mmol/L
d. Alert, oriented and asking for breakfast
e. Urine output of 60 mL per hour
f. Glucose of 3.4 mmol/L

Answer: a, b, d, e — A normal anion gap, normal breathing, improved alertness and good urine output show that acidosis and fluid loss are resolving (section 22.5). A potassium of 3.1 mmol/L shows that potassium has fallen as insulin moved it into cells; it is below the protocol's limit and must be reported at once. A glucose of 3.4 mmol/L is hypoglycemia and needs treatment, not reassurance.

27. [CORE] A patient taking insulin says he feels shaky and sweaty. His glucose is 3.4 mmol/L, and he is alert and able to swallow. What should the nurse do first?

a. Give 15 g of fast-acting carbohydrate and recheck glucose in 15 minutes.
b. Give glucagon 1 mg intramuscularly and call the rapid response team.
c. Ask the kitchen to send his supper tray early and recheck glucose when it arrives.
d. Give 30 g of carbohydrate with protein and recheck in 1 hour.

Answer: a — An alert patient with a level 1 low takes 15 g of fast-acting carbohydrate, preferably glucose, with a recheck after 15 minutes (section 22.4). Glucagon is for people who cannot swallow. Waiting for a tray delays treatment. A larger amount risks rebound hyperglycemia, and a 1-hour recheck is too late.

28. [CORE] Fifteen minutes after treatment for hypoglycemia, a patient's glucose is 5.1 mmol/L. Supper will not arrive for 90 minutes. What should the nurse do next?

a. Give another 15 g of glucose tablets.
b. Hold the patient's mealtime insulin at supper.
c. Recheck glucose in 15 minutes without giving food.
d. Give a snack with 15 g of carbohydrate and a protein source.

Answer: d — Once glucose is corrected, a snack with 15 g of carbohydrate and protein is given if the next meal is more than an hour away (section 22.4). More glucose is not needed at 5.1 mmol/L. Holding insulin is a prescriber's decision. Rechecking alone ignores the long wait before supper.

29. [CORE] A nurse finds a patient with diabetes unresponsive. The point-of-care glucose is 1.9 mmol/L, and the patient has no IV access. Which action is most appropriate?

a. Place glucose gel inside the patient's cheek and wait 15 minutes.
b. Give glucagon 3 mg intranasally and call for help.
c. Start an IV and recheck glucose before giving any treatment.
d. Give juice through a syringe into the side of the mouth.

Answer: b — For an unconscious person without IV access, Diabetes Canada recommends glucagon 1 mg subcutaneously or intramuscularly or 3 mg intranasally, and calling for help (section 22.4). Nothing is given by mouth to an unconscious person because of the risk of aspiration. Starting an IV first delays treatment.

30. [CORE] A patient with type 1 diabetes is NPO for a procedure. The prescriber's order reads "correction insulin by scale only; hold all other insulin." What should the nurse do?

a. Follow the order, because a patient who is not eating does not need insulin.
b. Give half the usual basal insulin without consulting the prescriber.
c. Give the correction scale only if glucose rises above 14.0 mmol/L.
d. Contact the prescriber to question withholding all basal insulin.

Answer: d — Diabetes Canada discourages correction-only insulin as the sole treatment and advises that basal insulin is not withheld when a person is not eating (section 22.6). A person with type 1 diabetes without basal insulin is at risk of DKA. The nurse cannot change the dose on their own. Waiting for a high glucose leaves the patient without basal insulin.

31. [CORE] Which glucose target does Diabetes Canada recommend before meals for most adults in hospital who are not critically ill?

a. 5.0 to 8.0 mmol/L
b. 4.0 to 7.0 mmol/L
c. 6.0 to 10.0 mmol/L
d. 8.0 to 12.0 mmol/L

Answer: a — Diabetes Canada recommends a premeal glucose of 5.0 to 8.0 mmol/L and random values below 10.0 mmol/L if they can be reached safely (section 22.6). A range of 6.0 to 10.0 mmol/L is the target for critically ill patients. The other ranges are not the in-hospital targets.

32. [CORE] A patient with diabetes has the flu and cannot keep fluids down. She takes metformin, ramipril, empagliflozin and insulin glargine. Which statement shows that she understands sick-day guidance?

a. "I will stop all my diabetes medications, including my insulin, until I can eat and drink normally again."
b. "I will keep taking all my pills but skip my insulin to avoid a low."
c. "I will double my metformin, because being sick raises my blood sugar."
d. "I will keep taking my insulin and pause the metformin, ramipril and empagliflozin for now."

Answer: d — When a person cannot keep up fluids, Diabetes Canada's sick-day list advises pausing metformin, ACE inhibitors such as ramipril and SGLT2 inhibitors such as empagliflozin, while insulin continues with dose advice from the team (section 22.6). Stopping insulin risks DKA. Continuing the pills risks kidney injury and ketoacidosis. Doubling metformin is unsafe.

33. [CORE] Which instructions should the nurse include when teaching foot care to a patient with peripheral neuropathy? Select all that apply.

a. Check the bath water with your hand before stepping in.
b. Look at the soles and between the toes every day.
c. Soak your feet in hot water every evening to improve circulation.
d. Remove corns and calluses yourself with a sterile blade.
e. See a provider right away for a sore, even if it does not hurt.
f. Wear shoes that fit properly every time you are on your feet.

Answer: a, b, e, f — Daily inspection, testing water with the hand, properly fitting footwear and seeking care for painless sores protect a foot that has lost sensation (section 22.6). Hot soaks risk burns that the person cannot feel. Corns and calluses are treated by a provider or foot care specialist, not cut at home.

34. [CORE] During a foot examination, a patient cannot feel the 10 g monofilament on several sites on both soles. How should the nurse interpret this finding?

a. The patient has lost protective sensation and is at higher risk of foot ulcers.
b. The patient has peripheral arterial disease and needs an urgent vascular referral.
c. The finding is expected with age and needs no further action.
d. The patient has an active foot infection that needs antibiotics.

Answer: a — Being unable to feel the 10 g monofilament predicts ulcers and amputation and calls for education, footwear and closer follow-up (section 22.6). The monofilament tests sensation, not circulation, which is assessed with pulses and skin temperature. The finding is not a normal part of ageing and does not show infection.

35. [CORE] An older adult is admitted with confusion and severe dehydration. Glucose is 41.0 mmol/L, plasma osmolality is 345 mmol/kg, pH is 7.36 and serum ketones are trace. Which condition do these findings suggest?

a. Diabetic ketoacidosis
b. Euglycemic diabetic ketoacidosis
c. Hyperglycemic hyperosmolar state
d. Level 2 hypoglycemia

Answer: c — A glucose of 34.0 mmol/L or higher, osmolality above 320 mmol/kg, marked dehydration and minimal acidosis match Diabetes Canada's description of HHS (section 22.5). DKA requires acidosis and positive ketones. Euglycemic DKA has a near-normal glucose with acidosis. Hypoglycemia is a low glucose.

36. [CORE] An RPN on a medical unit finds a patient sweaty and confused. The glucose is 2.8 mmol/L. The patient can swallow. The unit has a nurse-initiated hypoglycemia protocol. What should the RPN do first?

a. Ask the RN to assess the patient before any treatment is given.
b. Page the physician for an order before giving glucose.
c. Recheck the glucose in 15 minutes to confirm the reading.
d. Treat the low according to the protocol, then inform the RN and prescriber.

Answer: d — Hospital hypoglycemia protocols allow nurses to start treatment at once (section 22.4), and the RPN has the authority, through the protocol, and the competence to do so (section 22.6). Waiting for the RN or a physician delays treatment of a brain short of glucose. Rechecking without treating wastes time. The RPN then reports the event so the cause can be reviewed.

37. [CORE] An RPN notes that a patient's premeal glucose has been above 14.0 mmol/L at every check for 2 days. There is a correction-insulin order but no order to change the basal dose. What should the RPN do?

a. Increase the bedtime basal insulin by a small amount, since the high pattern is clear and consistent.

b. Give the correction dose as ordered and report the pattern to the RN and prescriber.

c. Hold the next meal and offer only sugar-free fluids to bring the glucose down.

d. Give an extra dose of mealtime insulin at bedtime.

Answer: b — Nurses adjust insulin only as an order or medical directive allows (section 22.6). The RPN gives the ordered correction dose and reports the pattern so the prescriber can change the basal or bolus insulin. Changing the basal dose or giving extra insulin without an order is outside the nurse's authority. Holding a meal is unsafe.

38. [RN] A patient with DKA has a glucose of 9.8 mmol/L. Sodium is 138 mmol/L, chloride 104 mmol/L and bicarbonate 14 mmol/L. The insulin infusion is running with dextrose. What should the nurse anticipate?

a. Continuing the insulin infusion, because the anion gap is still raised

b. Stopping the infusion, because the glucose is now within the target range

c. Changing to subcutaneous insulin now, because the glucose is below 10.0 mmol/L

d. Removing the dextrose from the IV fluid, because glucose is falling too fast

Answer: a — The anion gap is 138 − (104 + 14) = 20 mmol/L, which shows that ketoacids are still present, so IV insulin continues until the gap returns to normal (section 22.5, Going Deeper). Glucose is not the endpoint. The change to subcutaneous insulin waits until the gap closes. Dextrose stays in the IV fluid so insulin can continue safely.

39. [RN] A patient with DKA has a potassium of 3.0 mmol/L before the insulin infusion is started. What should the nurse anticipate?

a. Starting the insulin infusion at once, because insulin will correct the potassium

b. Holding the insulin and giving potassium until it reaches at least 3.3 mmol/L

c. Giving an insulin bolus before replacing potassium

d. Withholding all IV fluids until the potassium is corrected

Answer: b — Diabetes Canada advises withholding insulin until potassium is at least 3.3 mmol/L, because insulin moves potassium into cells and can cause dangerous hypokalemia and dysrhythmias (section 22.5). Insulin lowers potassium further rather than correcting it. Diabetes Canada finds no conclusive evidence for an insulin bolus in adults, and any insulin now would worsen hypokalemia. Fluids continue because the patient is dehydrated.

40. [RN] A patient with suspected HHS has a sodium of 150 mmol/L and a glucose of 48.0 mmol/L. Using Diabetes Canada's formula for effective plasma osmolality, what is the result?

a. 198 mmol/kg

b. 300 mmol/kg

c. 348 mmol/kg

d. 396 mmol/kg

Answer: c — Effective plasma osmolality is (2 × sodium) + glucose: (2 × 150) + 48.0 = 348 mmol/kg, above the HHS threshold of 320 (section 22.5). The value 198 adds sodium and glucose without doubling sodium. The value 300 counts sodium only. The value 396 doubles both sodium and glucose.

References

Amphastar Pharmaceuticals. (2024). *Baqsimi (glucagon nasal powder) product monograph*. https://pdf.hres.ca/dpd_pm/00074561.PDF

Bari, B., Corbeil, M.-A., Farooqui, H., Menzies, S., Pflug, B., Smith, B. K., Vasquez, A., & Berard, L. (2020). Insulin injection practices in a population of Canadians with diabetes: An observational study. *Diabetes Therapy, 11*(11), 2595–2609. https://doi.org/10.1007/s13300-020-00913-y

Basu, A., Dube, S., Slama, M., Errazuriz, I., Amezcua, J. C., Kudva, Y. C., Peyser, T., Carter, R. E., Cobelli, C., & Basu, R. (2013). Time lag of glucose from intravascular to interstitial compartment in humans. *Diabetes, 62*(12), 4083–4087. https://doi.org/10.2337/db13-1132

Battelino, T., Danne, T., Bergenstal, R. M., Amiel, S. A., Beck, R., Biester, T., Bosi, E., Buckingham, B. A., Cefalu, W. T., Close, K. L., Cobelli, C., Dassau, E., DeVries, J. H., Donaghue, K. C., Dovc, K., Doyle, F. J., III, Garg, S., Grunberger, G., Heller, S., … Phillip, M. (2019). Clinical targets for continuous glucose monitoring data interpretation: Recommendations from the International Consensus on Time in Range. *Diabetes Care, 42*(8), 1593–1603. https://doi.org/10.2337/dci19-0028

Berard, L. D., Siemens, R., & Woo, V. (2018). Monitoring glycemic control. *Canadian Journal of Diabetes, 42*(Suppl. 1), S47–S53. https://doi.org/10.1016/j.jcjd.2017.10.007

Bril, V., Breiner, A., Perkins, B. A., & Zochodne, D. (2018). Neuropathy. *Canadian Journal of Diabetes, 42*(Suppl. 1), S217–S221. https://doi.org/10.1016/j.jcjd.2017.10.028

Butalia, S., Bajaj, H. S., Jain, R., Leung, K., Mansell, K., Reichert, S. M., Senior, P., & Shah, B. R. (2024). The user's guide to the pharmacologic glycemic management of type 2 diabetes in adults—2024 update. *Canadian Journal of Diabetes, 48*(7), 425–430. https://doi.org/10.1016/j.jcjd.2024.08.003

Canadian Society of Hospital Pharmacists Ontario Branch & ISMP Canada. (2014). *Safe delivery of insulin: Summary report and recommendations*. https://www.ismp-canada.org/download/insulin/SafeDeliveryOfInsulinReport_09Jun2014.pdf

Cheng, A. Y. Y., Feig, D. S., Ho, J., Siemens, R., Bajaj, H., Gilbert, J., Houlden, R., Kim, J., Mackay, D., Rabi, D. M., Senior, P., & Sherifali, D. (2021). Blood glucose monitoring in adults and children with diabetes: Update 2021. *Canadian Journal of Diabetes, 45*(7), 580–587. https://doi.org/10.1016/j.jcjd.2021.07.003

College of Nurses of Ontario. (2025). *An introduction to the Nursing Act, 1991* (Pub. No. 41064). https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41064_fsnursingact.pdf

College of Nurses of Ontario. (n.d.-a). *Navigating the RN prescribing medication list*. https://cno.org/en/learn-about-standards-guidelines/rn-prescribing/navigating-rn-prescribing-medication-list

College of Nurses of Ontario. (n.d.-b). *Understanding orders, directives and delegation*. https://www.cno.org/standards-learning/practice-support/practice-support-faqs/understanding-orders-directives-and-delegation

Crowshoe, L., Dannenbaum, D., Green, M., Henderson, R., Naqshbandi Hayward, M., & Toth, E. (2018). Type 2 diabetes and Indigenous peoples. *Canadian Journal of Diabetes, 42*(Suppl. 1), S296–S306. https://doi.org/10.1016/j.jcjd.2017.10.022

Diabetes Canada. (n.d.-a). *Appendix 6: Types of insulin*. Diabetes Canada Clinical Practice Guidelines. Retrieved October 26, 2026, from https://www.diabetes.ca/appendix-6

Diabetes Canada. (n.d.-b). *Appendix 8: Sick-day medication list* [Clinical practice guidelines appendix]. Retrieved October 26, 2026, from https://www.diabetes.ca/appendix-8

Ekoé, J.-M., Goldenberg, R., & Katz, P. (2018). Screening for diabetes in adults. *Canadian Journal of Diabetes, 42*(Suppl. 1), S16–S19. https://doi.org/10.1016/j.jcjd.2017.10.004

Embil, J. M., Albalawi, Z., Bowering, K., & Trepman, E. (2018). Foot care. *Canadian Journal of Diabetes, 42*(Suppl. 1), S222–S227. https://doi.org/10.1016/j.jcjd.2017.10.020

First Nations Information Governance Centre. (2018, March 14). *New report provides unprecedented look at trends over time in the health and well-being of First Nations communities* [News release]. https://fnigc.ca/news/new-report-provides-unprecedented-look-at-trends-over-time-in-the-health-and-well-being-of-first-nations-communities/

Goguen, J., & Gilbert, J. (2018). Hyperglycemic emergencies in adults. *Canadian Journal of Diabetes, 42*(Suppl. 1), S109–S114. https://doi.org/10.1016/j.jcjd.2017.10.013

Halperin, I. J., Wicklow, B., Amed, S., Chambers, A., Courage, C., Cummings, E., Kirkland, P., MacKay, D., Nakhla, M., Punthakee, Z., Ryan, P. M., Sawatsky, L., Senior, P. A., Sidhu, B. S., & Weisman, A. (2025). *Glycemic management across the lifespan for people with type 1 diabetes: A clinical practice guideline*. Diabetes Canada. https://www.diabetes.ca/chapter-41

Health Canada. (2026). *Glucagon for injection supply in Canada: Notice*. https://www.canada.ca/en/health-canada/services/drugs-health-products/drug-products/drug-shortages/information-consumers/supply-notices/glucagon-injection.html

Health Canada. (n.d.-a). *Baqsimi* [Drug Product Database entry, DIN 02492415]. Retrieved October 26, 2026, from https://health-products.canada.ca/dpd-bdpp/info?lang=eng&code=98243

Health Canada. (n.d.-b). *Regulatory decision summary for Awiqli*. Drug and Health Product Portal. Retrieved October 26, 2026, from https://dhpp.hpfb-dgpsa.ca/review-documents/resource/RDS1711383693011

Hortensius, J., Slingerland, R. J., Kleefstra, N., Logtenberg, S. J. J., Groenier, K. H., Houweling, S. T., & Bilo, H. J. G. (2011). Self-monitoring of blood glucose: The use of the first or the second drop of blood. *Diabetes Care, 34*(3), 556–560. https://doi.org/10.2337/dc10-1694

Houlden, R. L., Berard, L., Lakoff, J. M., Woo, V., & Yale, J.-F. (2018). Diabetes and driving. *Canadian Journal of Diabetes, 42*(Suppl. 1), S150–S153. https://doi.org/10.1016/j.jcjd.2017.10.018

Imran, S. A., Agarwal, G., Bajaj, H. S., & Ross, S. (2018). Targets for glycemic control. *Canadian Journal of Diabetes, 42*(Suppl. 1), S42–S46. https://doi.org/10.1016/j.jcjd.2017.10.030

Kasprzak, C., & Ho, C. (2016, Summer). Insulin medication incidents in the community: A multi-incident analysis by ISMP Canada. *Pharmacy Connection*, 26–29. https://www.ismp-canada.org/download/PharmacyConnection/PC2016-InsulinMedicationIncidentsintheCommunity.pdf

Korytkowski, M. T., Muniyappa, R., Antinori-Lent, K., Donihi, A. C., Drincic, A. T., Hirsch, I. B., Luger, A., McDonnell, M. E., Murad, M. H., Nielsen, C., Pegg, C., Rushakoff, R. J., Santesso, N., & Umpierrez, G. E. (2022). Management of hyperglycemia in hospitalized adult patients in non-critical care settings: An Endocrine Society clinical practice guideline. *Journal of Clinical Endocrinology & Metabolism, 107*(8), 2101–2128. https://doi.org/10.1210/clinem/dgac278

Lega, I. C., Yale, J.-F., Chadha, A., Paty, B., Roscoe, R., Snider, M., Steier, J., Bajaj, H. S., Barnes, T., Gilbert, J., Honshorst, K., Kim, J., Lewis, J., MacDonald, B., MacKay, D., Mansell, K., Senior, P., Rabi, D., & Sherifali, D. (2023). Hypoglycemia in adults. *Canadian Journal of Diabetes, 47*(7), 548–559. https://doi.org/10.1016/j.jcjd.2023.08.003

Lipscombe, L., Booth, G., Butalia, S., Dasgupta, K., Eurich, D. T., Goldenberg, R., Khan, N., MacCallum, L., Shah, B. R., & Simpson, S. (2018). Pharmacologic glycemic management of type 2 diabetes in adults. *Canadian Journal of Diabetes, 42*(Suppl. 1), S88–S103. https://doi.org/10.1016/j.jcjd.2017.10.034

Malcolm, J., Halperin, I., Miller, D. B., Moore, S., Nerenberg, K. A., Woo, V., & Yu, C. H. (2018). In-hospital management of diabetes. *Canadian Journal of Diabetes, 42*(Suppl. 1), S115–S123. https://doi.org/10.1016/j.jcjd.2017.10.014

McComber, A., & Macaulay, A. (2016, September 15). *Kahnawake Schools Diabetes Prevention Project* [Presentation]. Canadian Academy of Health Sciences Forum on Indigenous Health. https://cahs-acss.ca/wp-content/uploads/2016/09/Diabetes_Kahnawake-experience.pdf

Meneilly, G. S., Knip, A., Miller, D. B., Sherifali, D., Tessier, D., & Zahedi, A. (2018). Diabetes in older people. *Canadian Journal of Diabetes, 42*(Suppl. 1), S283–S295. https://doi.org/10.1016/j.jcjd.2017.10.021

Novo Nordisk Canada. (2026). *NovoRapid (insulin aspart injection): Product monograph*. https://pdf.hres.ca/dpd_pm/00084670.PDF

Ontario Ministry of Health. (2022). *Assistive Devices Program coverage for real-time continuous glucose monitoring systems: Questions and answers*. https://files.ontario.ca/moh-adp-memo-adp-coverage-for-real-time-continuous-glucose-monitoring-systems-qa-en-2022-03-04.pdf

Public Health Agency of Canada. (2011). Chapter 6: First Nations, Inuit, and Métis. In *Diabetes in Canada: Facts and figures from a public health perspective*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/diabetes-canada-facts-figures-a-public-health-perspective/chapter-6.html

Public Health Agency of Canada. (2025). *Diabetes in Canada: An interactive report on key statistics*. Health Infobase. https://health-infobase.canada.ca/diabetes/

Punthakee, Z., Goldenberg, R., & Katz, P. (2018). Definition, classification and diagnosis of diabetes, prediabetes and metabolic syndrome. *Canadian Journal of Diabetes, 42*(Suppl. 1), S10–S15. https://doi.org/10.1016/j.jcjd.2017.10.003

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Robinson, D. J., Hanson, K., Jain, A. B., Kichler, J. C., Mehta, G., Melamed, O. C., Vallis, M., Bajaj, H. S., Barnes, T., Gilbert, J., Honshorst, K., Houlden, R., Kim, J., Lewis, J., MacDonald, B., MacKay, D., Mansell, K., Rabi, D., Sherifali, D., & Senior, P. (2023). Diabetes and mental health. *Canadian Journal of Diabetes, 47*(4), 308–344. https://doi.org/10.1016/j.jcjd.2023.04.009

Rosella, L. C., Kornas, K., Green, M. E., Shah, B. R., Walker, J. D., Frymire, E., & Jones, C. (2020). Characterizing risk of type 2 diabetes in First Nations people living in First Nations communities in Ontario: A population-based analysis using cross-sectional survey data. *CMAJ Open, 8*(1), E178–E183. https://doi.org/10.9778/cmajo.20190210

Röder, P. V., Wu, B., Liu, Y., & Han, W. (2016). Pancreatic regulation of glucose homeostasis. *Experimental & Molecular Medicine, 48*(3), e219. https://doi.org/10.1038/emm.2016.6

sanofi-aventis Canada. (2018). *Glucophage (metformin hydrochloride tablets): Product monograph*. https://pdf.hres.ca/dpd_pm/00044067.PDF

Shah, B. R., Bajaj, H. S., Butalia, S., Dasgupta, K., Eurich, D. T., Jain, R., Leung, K., Mansell, K., & Simpson, S. (2024). Pharmacologic glycemic management of type 2 diabetes in adults—2024 update. *Canadian Journal of Diabetes, 48*(7), 415–424. https://doi.org/10.1016/j.jcjd.2024.08.002

Sherifali, D., Berard, L. D., Gucciardi, E., MacDonald, B., & MacNeill, G. (2018). Self-management education and support. *Canadian Journal of Diabetes, 42*(Suppl. 1), S36–S41. https://doi.org/10.1016/j.jcjd.2017.10.006

Sivem Pharmaceuticals. (2021). *Metoprolol-L (metoprolol tartrate tablets) product monograph*. https://pdf.hres.ca/dpd_pm/00060618.PDF

Wounds Canada. (n.d.). *Inlow's 60-second diabetic foot screen*. Retrieved October 26, 2026, from https://www.woundscanada.ca/news/19-healthcare-professional/resources-health-care-professionals/25-foot-screen

Wounds International. (2023). *Wound care and skin tone made easy*. https://woundsinternational.com/wp-content/uploads/2023/05/MULTI23_ME_SkinTones_WINT-web.pdf

23 Thyroid, Parathyroid, Adrenal and Pituitary Disorders

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain endocrine feedback and interpret thyroid, calcium, cortisol and water-balance tests in SI units, recognizing that ranges vary by laboratory.
2. Recognize and care for adults with hypothyroidism and hyperthyroidism, and respond to myxedema coma and thyroid storm.
3. Provide safe care after thyroid and parathyroid surgery, including early recognition of neck hematoma and hypocalcemia.
4. Recognize adrenal insufficiency, adrenal crisis and Cushing syndrome, and teach safe glucocorticoid use and sick-day rules.
5. Care for patients with pituitary tumours and after transsphenoidal surgery, and distinguish SIADH from arginine vasopressin deficiency.
6. Teach patients about endocrine medications, monitoring and emergency identification, with attention to older adults.
7. Distinguish RN and RPN roles in endocrine emergencies using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 5	Clinician; Scholar	Foundations of Practice
4, 6	Educator; Advocate	Foundations of Practice; Ethical Practice
7	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

Hormones from small glands in the neck, the abdomen and the base of the brain set the pace of metabolism, keep calcium and water within narrow limits and help the body survive stress. When one of these glands makes too much or too little hormone, the effects reach every system. The heart may race or slow, thinking may become anxious or dulled, and fluids and electrolytes may shift. Many endocrine disorders develop slowly and are easy to mistake for ageing, depression or another illness. Others, such as thyroid storm, myxedema coma and adrenal crisis, are emergencies in which early recognition by the nurse can save a life.

This chapter covers the thyroid, parathyroid, adrenal and pituitary glands. Section 23.1 explains how feedback loops control hormone levels and how common endocrine tests are collected and read. Section 23.2 covers hypothyroidism, hyperthyroidism and their emergencies, with thyroid nodules and cancer in brief. Section 23.3 describes nursing care after thyroid surgery, including two complications every nurse must recognize early, bleeding into the neck and low calcium, and then the parathyroid disorders. Section 23.4 turns to the adrenal glands, including adrenal insufficiency, adrenal crisis and Cushing syndrome. Section 23.5 covers pituitary tumours and the disorders of water balance.

The chapter builds on earlier ones. Scope of practice, the Clinical Judgment Measurement Model (CJMM) and consent are taught in Chapter 1 (sections 1.3 to 1.5). Sodium and calcium imbalances, including the bedside signs of low calcium and the safe limits for correcting low sodium, are in Chapter 3. Recognizing deterioration and calling for help are in Chapter 6, perioperative care in Chapter 7 and older adults in Chapter 8. Atrial fibrillation is in section 16.6, hypertension in Chapter 19, autoimmunity in section 21.6 and steroid-induced high blood glucose in Chapter 22.

23.1 Endocrine Feedback and Testing

Hormones and Feedback Loops

A **hormone** is a chemical messenger that a gland releases into the blood and that acts on target cells elsewhere in the body. Many endocrine glands are controlled through a chain of command called an **axis**. The hypothalamus, at the base of the brain, releases a hormone that stimulates the anterior pituitary gland. The pituitary then releases a stimulating hormone that travels to a target gland, such as the thyroid or the adrenal cortex, which makes the final hormone (Figure 23.1).

The final hormone signals back to the hypothalamus and pituitary. This is **negative feedback**: when the level of the final hormone rises, the hypothalamus and pituitary release less of their stimulating hormones, and when it falls, they release more. Like a thermostat, negative feedback keeps hormone levels within a narrow range.



Figure 23.1 The main endocrine glands. The hypothalamus and pituitary at the base of the brain control the thyroid, adrenal cortex and gonads through feedback loops; the parathyroid glands respond directly to blood calcium. (credit: Figure 17.2, “Endocrine System,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

In the thyroid axis, the pituitary releases **thyroid-stimulating hormone (TSH)**, also called thyrotropin. TSH drives the thyroid to make thyroxine (T4) and smaller amounts of triiodothyronine (T3). Much of the T4 is converted to the more active T3 in the tissues. Almost all thyroid hormone in the blood is bound to carrier proteins; the small unbound fraction of T4, **free T4**, is the part available to cells.

Because the pituitary responds quickly to small changes in free thyroid hormone, TSH is the most reliable single test of thyroid function in most people (Choosing Wisely Canada, n.d.; Ross et al., 2016). In primary hypothyroidism, the failing thyroid makes too little hormone and the pituitary responds with a high TSH. In hyperthyroidism, excess thyroid hormone suppresses TSH to a low or undetectable level. This mirror-image pattern breaks down when the problem lies in the pituitary or hypothalamus (central disease). Then TSH may be low, normal or only mildly raised even though free T4 is low, so free T4, not TSH, guides care (Garber et al., 2012; Choosing Wisely Canada, n.d.).

Not every gland sits in an axis. The parathyroid glands respond directly to the blood calcium level. When calcium falls, they release more **parathyroid hormone (PTH)**, which raises calcium through bone, the kidneys and activated vitamin D (Chapter 3, section 3.6). The posterior pituitary releases arginine vasopressin, the antidiuretic hormone, in response to the concentration of the blood (section 23.5).

Endocrine Tests the Nurse Sees

Results are always read against the reporting laboratory's reference range, because ranges vary with the laboratory, the method and the population. Typical adult values below come from one Canadian teaching reference (University of Ottawa, 2022).

- **TSH:** 0.4 to 5.0 mU/L (also written mIU/L). TSH is the first test for suspected thyroid disease and for monitoring levothyroxine in primary hypothyroidism. Choosing Wisely Canada (n.d.), with the Canadian Society of Endocrinology and Metabolism, advises against routinely ordering free T4 or T3 with TSH, because the extra tests rarely change management unless disease of the pituitary or hypothalamus is suspected or known.
- **Free T4:** 8.5 to 15.2 pmol/L. Free T4 is added when TSH is outside the reference range, or when disease of the pituitary or hypothalamus is suspected or known (Choosing Wisely Canada, n.d.).

- **Calcium:** total 2.12 to 2.52 mmol/L; ionized 1.14 to 1.28 mmol/L. **Ionized calcium** is the free, active form. Because much of the remaining calcium travels on albumin, a low albumin lowers the total calcium even when ionized calcium is normal. Albumin-adjusted ("corrected") calcium estimates allow for this but can mislead, so ionized calcium is more reliable when results do not fit the patient (Chapter 3, section 3.6).
- **PTH:** read together with a calcium drawn at the same time. A high calcium with a high or "inappropriately normal" PTH points to primary hyperparathyroidism (Bilezikian et al., 2022). A low calcium with a low or inappropriately normal PTH points to hypoparathyroidism (Khan et al., 2022).
- **Cortisol:** a morning serum cortisol, typically 185 to 624 nmol/L. Cortisol is normally highest in the early morning, so the time of collection matters. Stimulation tests, which measure cortisol after a dose of synthetic pituitary hormone, are ordered by specialists; adrenal testing is discussed in section 23.4.
- **Sodium and osmolality:** serum sodium 136 to 144 mmol/L and serum osmolality 275 to 295 mmol/kg, read with urine tests in water-balance disorders (section 23.5).

Much of the nurse's role in testing concerns timing and preparation. The nurse:

- collects time-sensitive samples, such as a morning cortisol, at the ordered time and records the collection time;
- follows the laboratory's instructions about fasting and the timing of medications before a sample;
- asks about **biotin** (vitamin B7) supplements, which are common in hair, skin and nail products. Biotin can interfere with the immunoassays used for thyroid tests and produce false results. The Canadian levothyroxine monograph advises stopping biotin supplements at least 2 days before blood is drawn, when possible (BGP Pharma ULC, 2024);
- tells the prescriber when a result does not fit the patient's condition, because drugs, acute illness and assay problems can all distort endocrine tests.

23.2 Thyroid Disorders

Hypothyroidism

Hypothyroidism is a deficiency of thyroid hormone. When thyroid hormone is low, metabolism slows in every tissue: heat production falls, the heart slows, the gut moves more slowly and thinking can feel dull. Most cases are primary, arising in the thyroid itself. Worldwide, the leading cause is iodine deficiency. Where diets contain enough iodine, the most common cause is **Hashimoto thyroiditis** (chronic autoimmune thyroiditis), in which the immune system gradually destroys thyroid tissue (Garber et al., 2012; section 21.6). About 75% of people with this condition have raised levels of antibodies against the thyroid, such as antibodies to the enzyme thyroid peroxidase (TPO). Other causes include radioactive iodine or surgery for hyperthyroidism, nodules or cancer; radiation to the head and neck; and drugs such as amiodarone, lithium, interferon alfa and some tyrosine kinase inhibitors used in cancer care (Garber et al., 2012). Central hypothyroidism from pituitary disease is uncommon (section 23.5). Canadian data on thyroid disease appear in the Canadian Context box in this section.

Common manifestations are fatigue, feeling cold, dry skin, muscle cramps, a change in the voice and constipation. Others include low mood, menstrual changes, raised cholesterol and slow relaxation of the ankle reflex. Severe disease can cause carpal tunnel syndrome, sleep apnea and low sodium (Garber et al., 2012). These symptoms overlap with many common conditions, especially in older adults. The skin may feel dry, cool and rough. Pallor is easier to see on lighter skin, so on darker skin the nurse checks the inner eyelids, lips and nail beds. Some patients have a **goitre**, an enlarged thyroid seen or felt as fullness at the front of the neck. Because a goitre is confirmed by inspection of the neck's contour and by palpation rather than by colour, it is assessed the same way on every skin tone.

A high TSH with a low free T4 confirms overt primary hypothyroidism. A TSH above the reference range with a normal free T4 is **subclinical hypothyroidism** (Garber et al., 2012; Going Deeper box).

Levothyroxine, a synthetic form of T4, is the standard replacement. It has a narrow therapeutic index, so small changes in dose or absorption change its effect. Products from different manufacturers should not be interchanged without retesting (BGP Pharma ULC, 2024). The dose is adjusted to TSH, which is checked about 6 to 8 weeks after each change and at least yearly once stable. Older

adults and people with heart disease start at lower doses (BGP Pharma ULC, 2024; Garber et al., 2012). Adrenal insufficiency must be treated before levothyroxine starts, because thyroid hormone can trigger an adrenal crisis (BGP Pharma ULC, 2024; section 23.4). Overtreatment is harmful: atrial fibrillation is the most common dysrhythmia in overtreated patients, and long-term overtreatment can reduce bone density. The monograph's boxed warning states that thyroid hormone must not be used to treat obesity or for weight loss (BGP Pharma ULC, 2024).

When TSH swings for no clear reason, the nurse first reviews how the patient takes the drug (Patient Education box). Nursing care also includes tracking energy, bowel pattern, weight, heart rate, mood and cognition, and keeping the patient warm.

Myxedema Coma

Myxedema coma is the most severe form of hypothyroidism, an emergency in which body systems slow to the point of failure. It is rare. The typical patient is an older woman, often with known hypothyroidism, and it often presents in winter. Mortality is high: in one Japanese cohort, 30% died (Ylli et al., 2019). A trigger is usually added to untreated or undertreated disease: cold exposure, infection (especially pneumonia), sedatives and other drugs that depress breathing, low blood glucose, low sodium, or stopping thyroid medication (Ylli et al., 2019).

Despite its name, coma is not required. The cues are:

- a falling level of consciousness, from lethargy to coma, sometimes with seizures;
- hypothermia, which can hide infection because fever and a fast heart rate may be absent;
- bradycardia;
- slow, shallow breathing with carbon dioxide retention;
- low sodium and low blood glucose;
- constipation or ileus, and edema (Ylli et al., 2019).

There is no single confirming test, so treatment starts on clinical suspicion, in an intensive care unit (ICU). The team gives IV thyroid hormone, with lower doses for older adults and people with heart disease. Hydrocortisone is given after a baseline cortisol is drawn, because adrenal insufficiency may coexist and thyroid hormone alone could trigger an adrenal crisis. Broad-spectrum antibiotics are usually started even without fever, and mechanical ventilation is often needed (Ylli et al., 2019). The nurse rewarms passively with ordinary blankets; rapid warming, such as with an electric heating blanket, can dilate blood vessels and cause low blood pressure or shock. Low sodium is corrected slowly (Chapter 3, section 3.4), and fluids are given cautiously (Ylli et al., 2019).

Nursing priorities are airway and breathing (respiratory rate, depth, oxygen saturation and level of consciousness), continuous cardiac monitoring, temperature, glucose and sodium checks, and protecting the skin and airway of a patient who cannot move or swallow safely. The nurse avoids sedatives unless clearly ordered, and calls for help early when a patient with hypothyroidism becomes drowsy, cold or slow to breathe (Chapter 6).

Hyperthyroidism

Thyrotoxicosis is the state caused by too much thyroid hormone acting on the tissues. **Hyperthyroidism** is thyrotoxicosis caused by a gland that makes too much hormone. The main causes are:

- **Graves disease:** an autoimmune disorder in which antibodies (TSH receptor antibodies, or TRAb) stimulate the thyroid like TSH does. It is the most common cause in the United States (Ross et al., 2016).
- **Toxic nodular goitre:** one or more nodules that make hormone on their own. It becomes more common with age and may outnumber Graves disease in older adults (Ross et al., 2016).
- **Thyroiditis:** inflammation that releases stored hormone for a time without increased production. It may be painless, painful (subacute, thought to follow a viral illness) or caused by drugs such as amiodarone. In one Toronto series, painless thyroiditis accounted for 6% of patients with thyrotoxicosis (Ross et al., 2016).

Excess hormone speeds metabolism and causes adrenergic symptoms. Common features include weight loss despite a bigger appetite, palpitations and a fast heart rate, nervousness or anxiety, tremor, muscle weakness, heat intolerance, sweating and diarrhea or more frequent bowel movements (BGP Pharma ULC, 2024; Ross et al., 2016). Untreated disease can cause atrial fibrillation (AF)

with embolic events, bone loss and, rarely, cardiovascular collapse (Ross et al., 2016; section 16.6). The skin may feel warm and moist from sweating. Flushing shows as redness on lighter skin but may be hard to see on darker skin, so the nurse feels for warmth and moisture and asks about heat intolerance.

Thyroid eye disease is an autoimmune disorder of the tissues around the eyes that is closely linked to Graves disease. It causes eyelid retraction, bulging eyes (proptosis), swelling around the eyes, pain, redness and double vision, and rarely damages the cornea or compresses the optic nerve. Smoking, uncontrolled thyroid function and radioactive iodine raise the risk (Burch et al., 2022). Redness of the eyelids may be subtle on darker skin, so the nurse also asks about pain, pressure and changes in vision. Care includes smoking cessation support, avoiding second-hand smoke, lubricants and night-time eye masks, and urgent referral for any threat to sight (Burch et al., 2022; Chapter 36).

TSH is low, often undetectable, with a high free T4, T3 or both. The cause is found with TRAb testing, a radioactive iodine uptake test or ultrasound (Ross et al., 2016).

Treatment has several options (Ross et al., 2016):

- **Beta-blockers** relieve palpitations, tremor and anxiety, especially in older adults and patients with a resting heart rate over 90 beats per minute or heart disease. Nonselective beta-blockers are generally avoided in asthma.
- **Antithyroid drugs** block hormone synthesis. **Methimazole** is preferred for nearly all patients. **Propylthiouracil (PTU)** is preferred in the first trimester of pregnancy and in thyroid storm; the Canadian monograph otherwise reserves it for people who cannot tolerate methimazole, because it can cause severe, sometimes fatal liver injury (Phebra Canada, 2021). Both drugs can cause **agranulocytosis**, a severe drop in neutrophils that is rare but life-threatening and usually appears within the first 3 months (Knight Therapeutics, 2025; Phebra Canada, 2021). The Canadian monographs tell patients to report fever, sore throat or other signs of infection right away; a white blood cell count with differential is checked, and the drug is stopped if agranulocytosis is suspected or found (Knight Therapeutics, 2025; Phebra Canada, 2021). The ATA guideline advises patients to stop the drug and call their physician when such symptoms appear (Ross et al., 2016). A baseline complete blood count and liver tests are recommended (Ross et al., 2016).
- **Radioactive iodine therapy (RAI)** is an oral dose of radioactive iodine that destroys overactive thyroid tissue. It is contraindicated in pregnancy and breastfeeding. Patients receive written radiation safety instructions, and another treatment is chosen if they cannot follow them. Most patients become hypothyroid, usually within 2 to 6 months, and need lifelong levothyroxine. Conception is delayed until thyroid function is stable (Ross et al., 2016). RAI can worsen eye disease, and glucocorticoid prophylaxis may be used (Burch et al., 2022).
- **Surgery** removes most or all of the gland (section 23.3).

Nursing care includes a cool, quiet environment, rest, adequate nutrition, daily weights, heart rate and rhythm checks, eye protection and teaching about adherence, since stopping antithyroid drugs can trigger thyroid storm (Ylli et al., 2019).

Thyroid Storm

Thyroid storm is life-threatening thyrotoxicosis with failure of one or more organs, often set off by another illness (Satoh et al., 2016). It occurs in about 1% to 2% of hospital admissions for thyrotoxicosis (Ylli et al., 2019). In Japanese national surveys, about 11% of patients died, most often from multiple organ failure or heart failure (Satoh et al., 2016). Triggers include stopping antithyroid drugs, infection, surgery, trauma, emotional stress, RAI and large iodine loads (Ylli et al., 2019). Thyroid surgery in a patient who is not yet prepared is a risk, which is why patients are made euthyroid first (Ross et al., 2016).

The cues are an exaggeration of thyrotoxicosis: high fever, marked tachycardia or AF, agitation progressing to delirium or coma, heart failure, nausea, vomiting, diarrhea, jaundice, dehydration and shock. Older adults may present less dramatically (Ylli et al., 2019). Diagnosis is clinical; on the Burch-Wartofsky point scale, a score of 45 or more makes storm likely and 25 to 44 suggests impending storm (Ylli et al., 2019).

Treatment begins in the ICU without waiting for laboratory confirmation. The team blocks new hormone production with a high dose of methimazole or PTU, then gives iodine to block hormone release, at least 30 to 60 minutes after the antithyroid drug, because iodine given first can worsen storm. A beta-blocker controls heart rate, and a glucocorticoid is given. Fever is treated with

acetaminophen and cooling; aspirin is avoided because it raises free thyroid hormone. IV fluids containing dextrose, and treatment of the trigger, complete care (Ylli et al., 2019).

The nurse calls a rapid response (Chapter 6), maintains continuous cardiac monitoring, tracks temperature, fluid balance and mental status, keeps a delirious patient safe and gives drugs in the ordered sequence.



Figure 23.2 Ultrasound of the thyroid, viewed in cross-section: a fluid-filled cyst and a small nodule with bright calcifications. Ultrasound features help decide which nodules need fine-needle aspiration. (credit: "Ultrasound of thyroid showing right lower pole cyst and a calcified nodule" by Cerevisae/Wikimedia Commons, CC BY-SA 4.0)

Thyroid Nodules and Cancer in Brief

Thyroid nodules are a common clinical problem (Haugen et al., 2016). Evaluation aims to find the nodules that need treatment, using imaging (Figure 23.2) and, for selected nodules, **fine-needle aspiration (FNA)**, in which cells are drawn through a thin needle for examination (Haugen et al., 2016). In Canada outside Quebec, thyroid cancer incidence rose steeply from 1984 to 2013, likely because of overdiagnosis, mainly of papillary thyroid cancer. Since 2013, rates have fallen by about 5.4% per year in females, a significant decline, and by about 2.4% per year in males, a change that was not statistically significant (Demers et al., 2022). Cancer treatment is covered in Chapter 9, and care after thyroid surgery in section 23.3.

Table 23.1 Hypothyroidism and hyperthyroidism compared (BGP Pharma ULC, 2024; Garber et al., 2012; Ross et al., 2016; Ylli et al., 2019)

Feature	Hypothyroidism	Hyperthyroidism
Common causes	Hashimoto thyroiditis; after radioactive iodine or surgery; amiodarone or lithium	Graves disease; toxic nodular goitre; thyroiditis
Energy and mood	Fatigue, slowed thinking, low mood	Anxiety, restlessness, tremor
Heart	Slower heart rate; bradycardia in myxedema coma	Fast heart rate, palpitations, atrial fibrillation
Skin and hair	Dry, cool, rough skin	Warm, moist skin; flushing that may be hard to see on darker skin
Weight and appetite	Weight gain may occur	Weight loss, often with increased appetite
Temperature tolerance	Feels cold	Feels hot, sweats
Bowels	Constipation	Diarrhea or more frequent bowel movements
Key test pattern	High TSH, low free T4 (primary disease)	Low or undetectable TSH, high free T4 or T3
Emergency	Myxedema coma: hypothermia, bradycardia, hypoventilation, low sodium, drowsiness	Thyroid storm: fever, marked tachycardia, delirium, heart failure, GI symptoms

The two disorders are compared side by side (Table 23.1).

GOING DEEPER

Reading Thyroid Function Tests

Required for RN students; optional for PN students.

Thyroid tests are read as a pair, TSH with free T4, and always against the laboratory's own range (Garber et al., 2012; Ross et al., 2016).

- **High TSH, low free T4:** overt primary hypothyroidism. TSH is usually above 10 mIU/L.

- **High TSH, normal free T4:** subclinical hypothyroidism. The diagnosis needs stable results over weeks, a normal pituitary and no recent severe illness. Positive TPO antibodies predict a higher yearly rate of progression to overt disease.
- **Low TSH, high free T4 or T3:** overt hyperthyroidism. A mild case may show only a high T3.
- **Low or normal TSH, low free T4:** suggests central (pituitary or hypothalamic) disease. TSH cannot be used to monitor replacement; free T4 is followed instead.

TSH upper limits rise slightly with age, so a mildly raised TSH in a very old adult may not mean disease (Garber et al., 2012). After a dose change, TSH takes weeks to settle: the Canadian monograph advises checking 6 to 8 weeks after each adjustment (BGP Pharma ULC, 2024). A TSH drawn a week after a change is misleading. Biotin, recent dose changes, a switch of levothyroxine product and acute illness are common reasons for a result that does not fit the patient.

PATIENT EDUCATION

Taking Levothyroxine

The nurse teaches the following, using the Canadian monograph (BGP Pharma ULC, 2024):

- Take levothyroxine once a day, on an empty stomach, 30 minutes to 1 hour before breakfast, with water.
- Take it the same way, at the same time, every day.
- Take it at least 4 hours apart from calcium, iron, antacids and other medicines known to block absorption. Some foods, such as high-fibre foods, walnuts and calcium-fortified juice, can also reduce absorption.
- Do not switch brands or generic products without telling the prescriber; a blood test is needed after a switch.
- Expect a TSH test about 6 to 8 weeks after any dose change, and at least once a year when the dose is stable.
- Stop biotin supplements at least 2 days before thyroid blood tests, if possible, and tell the laboratory about them.
- Report a racing or irregular heartbeat, chest pain or tremor (dose may be too high), or tiredness, feeling cold or constipation (dose may be too low).
- Never take thyroid hormone to lose weight.
- Most people need levothyroxine for life; do not stop it without advice.

LIFESPAN CONSIDERATIONS

Thyroid Disease in Older Adults

Older adults. Thyroid disease is easy to miss in later life.

- **Hypothyroidism:** symptoms such as tiredness, constipation, dry skin and slowed thinking are often subtle and overlap with normal ageing, depression or dementia (Garber et al., 2012). A new decline in memory or function prompts a question about thyroid testing. Myxedema coma most often affects older women (Ylli et al., 2019).
- **Hyperthyroidism:** older adults often have fewer of the classic adrenergic symptoms. Weight loss, weakness or new atrial fibrillation may be the only clue (Ross et al., 2016; section 16.6). Toxic nodular goitre is a more common cause than in younger adults.
- **Starting replacement:** levothyroxine is started at a lower dose in older adults and people with heart disease, and the nurse watches for chest pain and palpitations (BGP Pharma ULC, 2024).
- **Overtreatment:** too much levothyroxine raises the risk of atrial fibrillation, and long-term overtreatment can reduce bone density (BGP Pharma ULC, 2024; Chapter 33).
- **Thyroid storm:** may present less dramatically, sometimes as "apathetic" thyrotoxicosis, so a high index of suspicion is needed (Ylli et al., 2019).

Medication reviews and simple written levothyroxine instructions support safe care (Chapter 8).

CANADIAN CONTEXT

Thyroid Disease and Thyroid Cancer in Canada

- **Thyroid cancer:** the Canadian Cancer Society estimates that in 2026, 6,100 people in Canada will receive a thyroid cancer diagnosis and 310 will die of the disease. The estimates are 4,400 diagnoses and 170 deaths in women, and 1,750 diagnoses and 140 deaths in men, reported by sex assigned at birth (Canadian Cancer Society, 2026). Five-year net survival for thyroid cancer in Canada is 97% (Canadian Cancer Society, n.d.).

- **Trends:** in Canada outside Quebec, thyroid cancer incidence rose until 2013 and has fallen since, significantly so in females. The earlier rise was likely due to overdiagnosis, mainly of papillary thyroid cancer (Demers et al., 2022; section 23.2).
- **Hypothyroidism in older adults:** in the Canadian Study of Health and Aging, an estimated 9.6% of people aged 65 and older had hypothyroidism, defined as taking thyroid hormone or having a TSH above 10 mU/L. Some were inadequately treated and some untreated (Krueger et al., 2001). These data are from the 1990s.
- **Equity:** data gaps remain for people who are transgender, non-binary or gender-diverse (Canadian Cancer Society, 2026). People in rural, remote and northern communities, including many First Nations, Inuit and Métis communities, may live far from laboratories, endocrinologists and emergency care. For them, an emergency injection kit, family training and a clear plan for follow-up blood tests close to home matter even more.

23.3 Thyroid and Parathyroid Surgery

Care After Thyroidectomy

Thyroidectomy is the removal of all (total) or part of the thyroid gland, for nodules, cancer, a large goitre or hyperthyroidism. Before surgery for Graves disease, patients are made euthyroid with antithyroid drugs and receive a short course of iodine just before the operation, and calcium and vitamin D levels are checked and corrected (Ross et al., 2016). General perioperative care, including airway care after anesthesia, is in Chapter 7 (Figure 23.3).

Figure 23.3 A healing scar 2 months after total thyroidectomy. The incision lies low across the front of the neck.

After surgery, the nurse watches closely for problems in the neck. A consensus guideline from the Difficult Airway Society and surgical partners recommends observations at least hourly for the first 6 hours, including inspection of the wound, an early warning score and a pain score. After that, frequency depends on the patient's risk and local policy (Iliff et al., 2021, 2022).

Neck hematoma is a collection of blood under the incision. Blood collecting in the closed space of the neck can press on the airway, so a hematoma is an airway emergency. Cues include:

- swelling of the neck or a tense, firm wound;
- pain, pressure or a feeling of tightness;
- difficulty swallowing or a change in the voice;
- noisy breathing (stridor), breathlessness or falling oxygen saturation;
- anxiety, agitation or discomfort that seems out of proportion (Iliff et al., 2021).

The dressing may look nearly dry, because the blood collects deep in the wound. When a hematoma is suspected, the nurse calls for help at once and stays with the patient. The guideline calls for immediate senior surgical review on site and senior anesthesia help if the airway is compromised. Meanwhile, the patient is nursed head-up (sitting up) and given oxygen (Iliff et al., 2021). In Canadian hospitals this usually means activating the rapid response or emergency team and calling the surgeon, following employer policy (Chapter 6).

The same guideline describes a bedside procedure to release the blood, summarized as SCOOP: skin exposure, cut sutures, open skin, open muscles, pack the wound. An emergency box with scissors, a staple remover, gauze and a copy of the procedure stays at the bedside (Iliff et al., 2021, 2022). Who may open the wound depends on employer policy, orders or medical directives, and the nurse's training (Clinical Safety box).

The **recurrent laryngeal nerves** run close behind the thyroid and control the vocal cords. Temporary or permanent injury to these nerves, or to the superior laryngeal nerve, is a recognized complication (Ross et al., 2016). The nurse compares the voice after surgery with the patient's usual voice and reports new hoarseness, a weak voice or cough, coughing when drinking or noisy breathing. A voice change together with neck swelling points to a hematoma and is treated as an emergency.

Low calcium is the other complication every nurse watches for. The parathyroid glands sit behind the thyroid and can be bruised, lose their blood supply or be removed during surgery, so PTH falls and calcium falls with it. Surgery causes about 75% of all cases of hypoparathyroidism, and about 70% to 80% of people with parathyroid failure after surgery recover within a month (Khan et al., 2022). Calcium, with or without PTH, is measured after surgery, and calcium and calcitriol are given according to the results or as prophylaxis (Ross et al., 2016).

Early cues are numbness and tingling around the mouth and in the fingers and toes, then muscle cramps or stiffness. Tetany and seizures can follow (Khan et al., 2022). The bedside signs of low calcium (Figure 3.5 shows a positive Trousseau sign) and IV calcium treatment are taught in Chapter 3. The nurse asks about tingling at every assessment and reports symptoms at once.

After a total thyroidectomy, the patient needs levothyroxine for life, started after surgery at a dose suited to the patient. Antithyroid drugs stop at surgery, and beta-blockers are tapered (Ross et al., 2016). Discharge teaching covers wound care, signs of bleeding, calcium symptoms, levothyroxine and follow-up blood tests. For patients from rural, remote and northern communities, including many First Nations and Inuit communities, surgery may be far from home, so the plan confirms where follow-up tests will be done.

Parathyroid Disorders

In **primary hyperparathyroidism**, one or more parathyroid glands make too much PTH, raising blood calcium. About 85% of sporadic cases are caused by a single benign adenoma (Bilezikian et al., 2022). Most cases are now found by chance, when a routine blood test shows a high calcium (Bilezikian et al., 2022). The diagnosis is a high albumin-adjusted calcium with a high or inappropriately normal PTH, confirmed on two occasions at least 2 weeks apart.

The old memory aid "stones, bones and groans" describes the effects. "Stones" are kidney stones, which are found without symptoms in up to 22% of people with asymptomatic disease. "Bones" refers to bone loss, with a higher risk of spine and other fractures. "Groans" refers to symptoms of high calcium, such as thirst, frequent urination, nausea, constipation and confusion (Bilezikian et al., 2022; Chapter 3, section 3.6).

Parathyroidectomy, removal of the overactive gland or glands, is the only cure. Surgery is recommended for people with symptoms, and for those without symptoms who meet set criteria. These include age under 50, a calcium more than 0.25 mmol/L above the upper limit of normal, osteoporosis or a spine fracture, and kidney stones or reduced kidney function (Bilezikian et al., 2022). People who do not have surgery have yearly calcium and kidney tests and bone density scans every 1 to 2 years. Cinacalcet can lower calcium when surgery is declined or not appropriate (Bilezikian et al., 2022). After parathyroidectomy, the nurse watches for neck hematoma and low calcium, as after thyroid surgery (Chapter 3).

Hypoparathyroidism is too little PTH, which leads to low calcium. It is most often caused by neck surgery and is considered permanent when it lasts more than 12 months after the operation. The diagnosis is a low calcium with a low or inappropriately normal PTH (Khan et al., 2022). Standard treatment is oral calcium with an active form of vitamin D such as calcitriol. The target is a calcium in the lower half of the normal range or just below it. PTH replacement is considered when standard therapy is not enough (Khan et al., 2022).

Overtreatment also harms: high urine calcium can cause kidney stones, calcium deposits in the kidneys and loss of kidney function, so calcium is checked within several days of any major change in treatment (Khan et al., 2022). The nurse teaches the patient to take calcium and calcitriol exactly as prescribed, to report tingling or cramps, and to report thirst, nausea, constipation or confusion, which can mean calcium is too high.

CLINICAL SAFETY

Swelling in the Neck After Thyroid Surgery

Bleeding into the neck after thyroid or parathyroid surgery can block the airway within minutes. The nurse treats any of these as an emergency (Iliff et al., 2021, 2022):

- swelling of the neck, a tense wound or a feeling of tightness or pressure;
- difficulty swallowing, a change in voice or noisy breathing;
- rising breathing rate, falling oxygen saturation, anxiety or agitation.

What the nurse does:

- Calls for help at once (rapid response or emergency team and the surgeon, following employer policy) and stays with the patient.
- Positions the patient head-up (sitting up) and gives oxygen.
- Brings the bedside emergency box and prepares for the airway team.
- Does not wait for a dressing to soak through; blood can collect deep in the wound.

The UK consensus guideline describes opening the wound at the bedside (SCOOP: skin exposure, cut sutures, open skin, open muscles, pack) and calls for training, ideally with simulation, for all staff who care for these patients (Iliff et al., 2021, 2022). In Canada, whether a nurse may open the wound depends on employer policy, an order or medical directive, and the nurse's own competence (Chapter 1, section 1.3). Every nurse can recognize the signs, call for help and prepare.

23.4 Adrenal Disorders

The Adrenal Glands

Each adrenal gland, on top of a kidney, has an outer **adrenal cortex**, which makes steroid hormones, and an inner **adrenal medulla**, which releases the catecholamines epinephrine and norepinephrine. Three hormone groups matter at the bedside:

- **Cortisol:** the main glucocorticoid, released under the control of adrenocorticotropic hormone (ACTH) from the pituitary (section 23.1). Without enough cortisol, blood pressure falls and fatigue and, at times, low glucose follow (Bornstein et al., 2016).
- **Aldosterone:** the main mineralocorticoid, controlled mostly by the renin–angiotensin system (Chapter 3). It makes the kidneys hold sodium and water and excrete potassium (Adler et al., 2025).
- **Catecholamines:** fast-acting stress hormones that raise heart rate and blood pressure; excess causes the pheochromocytoma episodes described below (Hypertension Canada, n.d.).

Illness, injury, surgery, procedures and labour all raise the need for cortisol. A person who cannot make extra cortisol can become dangerously ill from stress a healthy person would tolerate (Society for Endocrinology, n.d.).

Adrenal Insufficiency

Adrenal insufficiency means the adrenal glands do not supply enough cortisol, with or without enough aldosterone. Its cause determines which hormones are missing:

- **Primary adrenal insufficiency (Addison disease):** the adrenal cortex itself is damaged, so cortisol and often aldosterone are low, and ACTH and renin rise. In Western countries, autoimmune destruction causes up to 90% of cases; other causes include tuberculosis, removal of the adrenals, cancer, adrenal bleeding during anticoagulant therapy and genetic conditions. People with autoimmune adrenal disease are screened periodically for other autoimmune conditions such as thyroid disease and diabetes (Bornstein et al., 2016; section 21.6).

- **Secondary adrenal insufficiency:** pituitary or hypothalamic disease, including pituitary tumours and surgery (section 23.5), lowers ACTH. Aldosterone is usually preserved because the renin–angiotensin system still works (Bornstein et al., 2016).
- **Glucocorticoid-induced adrenal insufficiency:** long-term glucocorticoid medication suppresses the hypothalamic–pituitary–adrenal (HPA) axis, so the adrenals stop making cortisol on their own. At least 1% of the population takes glucocorticoids long term. Risk comes from oral courses of 3 to 4 weeks or longer above the body's normal daily output, high-dose or long-term inhaled or topical products, joint injections in the past 2 months, and several products used together (Beuschlein et al., 2024). Any route can suppress the axis (Society for Endocrinology, n.d.).

Manifestations develop slowly and are easy to dismiss: fatigue, weight loss, poor appetite, dizziness on standing, abdominal discomfort, and back or leg cramps. Salt craving is the most specific symptom. Blood pressure is low, with a larger than usual drop on standing. Hyponatremia occurs in primary and secondary disease, but hyperkalemia only in primary disease, which removes aldosterone (Arlt & Society for Endocrinology Clinical Committee, 2016; Bornstein et al., 2016). More than half of patients first come to diagnosis through a crisis (Arlt & Society for Endocrinology Clinical Committee, 2016).

In primary disease, high ACTH causes **hyperpigmentation**, most noticeable on sun-exposed skin, skin creases such as the palms, the gums and inner cheeks, scars and the areolae (Bornstein et al., 2016). On darker skin, a general deepening of colour is easy to miss. The nurse asks whether the skin has darkened, compares creases, gums and scars with the person's usual colour, and inspects in natural light, because visual assessment alone is unreliable (Pusey-Reid et al., 2023). In secondary disease the skin may instead look unusually pale (Arlt & Society for Endocrinology Clinical Committee, 2016).

Diagnosis starts with cortisol and ACTH measured together (section 23.1). In the confirmatory corticotropin stimulation test, a cortisol peak below 500 nmol/L (assay dependent) after IV synthetic ACTH indicates adrenal insufficiency; if that test is not possible, an early-morning cortisol below 140 nmol/L, measured with ACTH, suggests adrenal insufficiency until it can be confirmed; a very high ACTH points to primary disease (Bornstein et al., 2016). During a glucocorticoid taper, a morning cortisol above 300 nmol/L suggests recovery (Beuschlein et al., 2024). Ranges vary by laboratory.

Treatment is lifelong replacement, usually hydrocortisone in two or three daily doses with the largest on waking. Dexamethasone is not suggested for replacement because it causes Cushing-like effects. People with primary disease who lack aldosterone also take fludrocortisone and should not restrict salt. Doses are adjusted by weight, lying and standing blood pressure, energy and signs of excess, not by blood levels (Bornstein et al., 2016).

Never stopping abruptly is the central safety rule. Sudden withdrawal after long-term use can cause fatal acute adrenal insufficiency, and suppression can last for months after therapy ends (Pfizer Canada ULC, 2025). Courses shorter than 3 to 4 weeks can usually stop without a taper; longer courses are tapered by the prescriber (Beuschlein et al., 2024).

In hospital, the nurse:

- asks about every glucocorticoid, including inhalers, creams and recent joint injections, during medication reconciliation;
- gives replacement doses on time and reports any missed dose;
- tells the prescriber at once when a patient cannot take oral doses or has prolonged vomiting or diarrhea, because parenteral glucocorticoids are then recommended, as they are for procedures under general or regional anesthesia (Beuschlein et al., 2024; Chapter 7);
- knows that thyroid hormone started before glucocorticoid replacement in untreated adrenal insufficiency can precipitate a crisis (BGP Pharma ULC, 2024; section 23.2).

Adrenal Crisis

Adrenal crisis is a life-threatening emergency: during illness or other stress, the adrenal glands cannot supply the extra cortisol the body needs. Its main features are hypotension and volume depletion. In one study, gastrointestinal illness and other infections were the most common triggers; surgery, procedures, injury, missed doses and abrupt withdrawal are others (Bornstein et al., 2016; Society for Endocrinology, n.d.).

The nurse recognizes a crisis from these cues (Arlt & Society for Endocrinology Clinical Committee, 2016; Bornstein et al., 2016):

- severe weakness, dizziness, fainting, low blood pressure or a drop of 20 mm Hg or more on standing, progressing to shock;

- nausea, vomiting and abdominal pain, which can mimic an acute abdomen;
- fever, confusion, drowsiness, delirium or coma;
- hyponatremia, hyperkalemia in primary disease, rising creatinine and, at times, low glucose.

In an older adult, confusion may be blamed on delirium (Chapter 8) and low blood pressure on sepsis (Chapter 4). Adrenal crisis is considered in anyone who takes or recently took glucocorticoids and has hemodynamic instability, vomiting or diarrhea, whatever the type, route or dose (Beuschlein et al., 2024).

Treatment is immediate, and tests must never delay it (Society for Endocrinology, n.d.). The Endocrine Society and Society for Endocrinology guidelines recommend these steps for adults (Arlt & Society for Endocrinology Clinical Committee, 2016; Bornstein et al., 2016):

- **Hydrocortisone:** 100 mg IV or IM at once, then 200 mg per 24 hours, either as a continuous IV infusion or as 50 mg IV or IM every 6 hours.
- **Fluids:** 1,000 mL of isotonic saline within the first hour, then IV fluid as needed, watching for overload in older adults and people with kidney impairment.
- **Monitoring:** blood pressure, lying and standing when safe; fluid balance; electrolytes, creatinine and glucose.
- **Expert help:** urgent endocrinology input and treatment of the trigger.

The nurse calls for help (the rapid response team in hospital, 9-1-1 in the community; Chapter 6), obtains IV access, gives hydrocortisone under an order or medical directive, and reports using SBAR. Blood for cortisol is drawn first only if it causes no delay (Arlt & Society for Endocrinology Clinical Committee, 2016). As cortisol is replaced, sodium can rise faster than intended (Society for Endocrinology, 2022; Chapter 3).

Prevention rests on teaching: sick-day rules, a steroid emergency card, medical alert identification, and a glucocorticoid emergency injection kit with training for the patient and family (Bornstein et al., 2016). In an international survey, only 12% of patients with primary disease who had a crisis in the previous year had injected themselves (Bornstein et al., 2016). The Practice Story at the end of section 23.5 shows a long-term care nurse recognizing a crisis early.

PATIENT EDUCATION

Steroid Sick-Day Rules and Medical Identification

People who take glucocorticoids for adrenal insufficiency, or who have taken them long term, follow the sick-day plan their prescriber writes (Beuschlein et al., 2024). For people taking hydrocortisone replacement for adrenal insufficiency, the nurse teaches these points from the Endocrine Society guideline (Bornstein et al., 2016):

- **Never stop or skip** your glucocorticoid. Refill your prescription before you run out.
- **Fever or illness:** if you have a fever of 38 °C or higher or an illness that keeps you in bed, or you start antibiotics, double your usual oral dose until you recover, which usually takes 2 to 3 days. For a fever of 39 °C or higher, triple it. Drink extra fluids that contain salt.
- **Vomiting or unable to keep pills down:** use your emergency hydrocortisone injection, or have a family member give it, and then go to hospital. The same applies after a serious injury.
- **Procedures and surgery:** tell the team you take glucocorticoids; you will need extra coverage.
- **Warning signs:** severe weakness, dizziness or fainting, vomiting, abdominal pain or confusion need emergency care. Call 9-1-1.
- **Carry identification:** wear medical alert jewellery and carry a steroid emergency card. Show the card to every health care provider, including paramedics and emergency staff.
- **Practise:** check your kit's expiry date, and practise the injection with the people you live with.

Cushing Syndrome

Cushing syndrome is the group of signs and symptoms caused by prolonged, inappropriately high exposure of tissues to glucocorticoids. The most common cause is prescribed glucocorticoid medication (Nieman et al., 2008). Less often, the body makes

too much cortisol itself, either because a tumour secretes excess ACTH (a pituitary tumour in Cushing disease, section 23.5, or a tumour elsewhere) or because an adrenal tumour overproduces cortisol (Nieman et al., 2008).

The features that best separate Cushing syndrome from common conditions are easy bruising, a full, flushed face (facial plethora), weakness of the proximal muscles (trouble rising from a chair or climbing stairs) and wide **striae**, or stretch marks (Nieman et al., 2008). The guideline highlights reddish-purple striae more than 1 cm wide, which is how new striae look on lighter skin. On darker skin, striae are often brown to black, and in one study they often looked white or skin-coloured in Black women; colour depends on stage and baseline skin tone (Elbuluk et al., 2025). The nurse therefore notes width, number and new appearance rather than colour alone, and compares facial colour with the person's usual appearance (Pusey-Reid et al., 2023; Figure 23.4).

Figure 23.4 Striae in a person with Cushing syndrome. On lighter skin, new striae are often red-purple, as here; on darker skin they are often brown to black, or may look pale. (credit: “Striae” by PanaromicTiger/Wikimedia Commons, CC BY-SA 3.0)

Less specific features include weight gain around the trunk, a fat pad behind the neck, thin skin, acne, excess hair growth, menstrual changes and depression. Hypertension, type 2 diabetes, vertebral osteoporosis, low potassium and unusual infections overlap with Cushing syndrome, which is more likely when they appear at a younger age than expected (Nieman et al., 2008). Glucocorticoids raise glucose (Chapter 22), increase infection risk and can mask its signs, and can cause mood changes from euphoria and insomnia to severe psychiatric reactions (Pfizer Canada ULC, 2025). Bone loss is a lasting concern (Chapter 33).

Diagnosis begins with a thorough drug history to exclude glucocorticoid medication. First-line tests include two 24-hour urine free cortisol collections, two late-night salivary cortisol samples taken between 2300 and 2400 hours, or an overnight dexamethasone suppression test, in which a morning cortisol above 50 nmol/L is abnormal (Nieman et al., 2008). The nurse teaches sample timing and how to complete a 24-hour collection.

Treatment depends on the cause. For medication-induced disease, the prescriber uses the lowest effective dose and tapers when possible, and patients are taught at the start about weight gain, high glucose, high blood pressure and bone loss (Beuschlein et al., 2024). Tumours are often treated with surgery, such as transsphenoidal surgery (section 23.5) or adrenalectomy (Nieman et al., 2008).

Nursing care focuses on fall prevention and gentle handling of thin, easily bruised skin; monitoring of blood pressure, glucose, weight and potassium; early reporting of low-grade fever, a new cough or a subtle wound change; and attention to mood, sleep and body image. Table 23.2 compares adrenal insufficiency with Cushing syndrome.

Table 23.2 Adrenal insufficiency and Cushing syndrome compared (Arlt & Society for Endocrinology Clinical Committee, 2016; Beuschlein et al., 2024; Bornstein et al., 2016; Elbuluk et al., 2025; Nieman et al., 2008)

Feature	Adrenal insufficiency	Cushing syndrome
Problem	Too little cortisol (and aldosterone in primary disease)	Too much glucocorticoid for a prolonged time
Most common causes	Autoimmune adrenal damage; pituitary disease; stopping or reducing long-term glucocorticoids	Prescribed glucocorticoids; pituitary or adrenal tumour

Feature	Adrenal insufficiency	Cushing syndrome
Weight and appetite	Weight loss, poor appetite, salt craving	Weight gain around the trunk, fat pad behind the neck
Blood pressure	Low, with a large drop on standing	High
Skin	Darkening in creases, gums and scars in primary disease (easy to miss on darker skin); pale in secondary disease	Thin skin, easy bruising, wide striae (red-purple on lighter skin, often brown to black on darker skin)
Muscles and energy	Fatigue, weakness, back and leg cramps	Proximal muscle weakness, fatigue
Laboratory pattern	Low sodium; high potassium in primary disease; low cortisol	High glucose; low potassium at times; high cortisol on screening tests
Emergency	Adrenal crisis: shock, vomiting, confusion	Infection masked by glucocorticoids; severe high blood pressure or glucose
Key nursing action	Never miss or stop doses; sick-day rules; emergency kit	Protect skin and bones, monitor glucose and blood pressure, never stop glucocorticoids abruptly

Primary Aldosteronism and Pheochromocytoma in Brief

Both conditions are adrenal causes of hypertension (Chapter 19), and both are easy to miss.

Primary aldosteronism is overproduction of aldosterone by one or both adrenal glands, at least partly independent of renin. Excess aldosterone retains sodium and raises blood pressure, sometimes with low potassium; the condition carries more cardiovascular risk than ordinary hypertension and remains underdiagnosed (Adler et al., 2025). Hypertension Canada advises considering screening when a person with hypertension has unexplained low potassium (below 3.5 mmol/L, or below 3.0 mmol/L on a diuretic), needs three drugs without control, or has an incidental adrenal adenoma (Hypertension Canada, n.d.). The 2025 Endocrine Society guideline, with Canadian authors, suggests screening everyone with hypertension using the aldosterone-to-renin ratio, drawn in the morning with the person seated. One-sided disease is treated by removing the gland; two-sided disease, lifelong with a mineralocorticoid receptor antagonist such as spironolactone (Adler et al., 2025).

A **pheochromocytoma** is a catecholamine-secreting tumour of the adrenal medulla. It is uncommon: these tumours and related paragangliomas occur in 0.2% to 0.6% of people with hypertension in general outpatient clinics (Lenders et al., 2014). Clues include sudden episodes (paroxysms) of high blood pressure or severe, hard-to-control hypertension, with headaches, palpitations, sweating, pallor or panic-like attacks. Beta-blockers, monoamine oxidase inhibitors, urination, changes in abdominal pressure, surgery or anesthesia can trigger episodes (Hypertension Canada, n.d.); the Endocrine Society also lists beta-blockers among drugs that can precipitate a crisis (Lenders et al., 2014). Testing measures plasma free or urine fractionated metanephrines, with plasma preferably drawn supine. Before surgery, alpha-adrenergic blockers are the first choice and are given for 7 to 14 days with a high-sodium diet and extra fluids; afterward, blood pressure, heart rate and glucose are monitored closely (Lenders et al., 2014).

MEDICATIONS

Thyroid and Adrenal Medications

Canadian brand names are given where a current Canadian product monograph was confirmed; doses are individualized by the prescriber.

- **Levothyroxine (Synthroid and others):** take on an empty stomach, 30 to 60 minutes before breakfast, at least 4 hours apart from calcium or iron products; start low in older adults (BGP Pharma ULC, 2024; section 23.2).
- **Liothyronine (Cytomel):** synthetic T3 with a rapid onset within hours and a short duration; not recommended for people with heart disease, including many older adults (Pfizer Canada ULC, 2019).
- **Methimazole (Tapazole):** teach to report fever or sore throat at once, as signs of agranulocytosis (Knight Therapeutics Inc., 2025).
- **Propylthiouracil:** can cause severe liver injury; reserved for people who cannot take methimazole and for early pregnancy; teach to report yellow skin or eyes, dark urine or abdominal pain (Phebra Canada Inc., 2021).

- **Beta-blockers (such as propranolol):** control tremor and fast heart rate in thyrotoxicosis; nonselective agents are avoided in asthma with bronchospasm (Ross et al., 2016).
- **Hydrocortisone (Solu-Cortef injection; oral tablets):** replacement of choice for adrenal insufficiency; the injection is the emergency treatment for adrenal crisis (Bornstein et al., 2016; Pfizer Canada ULC, 2025).
- **Prednisone:** never stop abruptly after long-term use; taper only as the prescriber directs (Beuschlein et al., 2024).
- **Dexamethasone:** long-acting and potent; not suggested for routine replacement because it causes Cushing-like effects (Bornstein et al., 2016).
- **Fludrocortisone (Florinef):** replaces aldosterone; monitor blood pressure, swelling, weight and electrolytes, especially potassium (Knight Therapeutics Inc., 2026).

23.5 Pituitary Disorders and Water Balance

Pituitary Tumours

Most pituitary tumours are benign **pituitary adenomas** (Figure 23.5). They cause problems in two ways: by making too much of a hormone (functioning tumours), and by pressing on nearby structures (mass effects). Nonfunctioning macroadenomas, larger tumours that make no active hormone, are the most common large pituitary tumours. They are usually found because of low pituitary hormones (in about 80% of patients) or vision problems (in about 85%) (Pelsma et al., 2020).

Mass effects include:

- **Visual field loss:** the tumour presses on the optic chiasm, where the nerve fibres from the inner half of each retina cross. Loss usually begins in the upper outer (temporal) fields and typically affects both eyes (**bitemporal visual field loss**). Visual acuity can fall too, and untreated compression can lead to blindness (Pelsma et al., 2020). Patients may bump into door frames or miss cars approaching from the side.
- **Headache** (Petersenn et al., 2023).
- **Low pituitary hormones (hypopituitarism):** low ACTH causes secondary adrenal insufficiency (section 23.4), and low thyroid-stimulating hormone causes central hypothyroidism (section 23.1) (Petersenn et al., 2023).



Figure 23.5 MRI of the head from the side, with an arrow marking a pituitary microadenoma, a tumour smaller than 1 cm. MRI is the main imaging test for pituitary tumours. (credit: "Adenome hypophyse esp" by Yakafaucon/Wikimedia Commons, CC BY-SA 4.0)

Sudden severe headache with new vision loss may mean bleeding into the tumour (pituitary apoplexy), which needs urgent imaging (Petersenn et al., 2023); the nurse escalates at once.

Two functioning tumours are worth knowing:

- **Prolactinomas** make up about half of all pituitary adenomas. High prolactin causes menstrual changes, infertility, low libido, breast milk discharge (galactorrhea) and erectile dysfunction. A dopamine agonist medication is usually first-line treatment; patients are taught to report compulsive behaviours such as gambling or shopping (Petersenn et al., 2023).
- **Acromegaly** results from excess growth hormone: enlarged hands and feet, coarse facial features and a protruding jaw, with diabetes, hypertension, heart disease and sleep apnea. Surgery is the usual first treatment (Endocrine Society, 2014).

An ACTH-secreting adenoma causes Cushing disease (section 23.4).

Care After Transsphenoidal Surgery

In **transsphenoidal surgery**, the surgeon reaches the pituitary through the nose and the sphenoid sinus. Most nursing priorities follow from the anatomy.

- **Vision:** the nurse checks visual acuity and fields as ordered and compares them with the preoperative baseline. Most patients' vision improves after decompression. New or worsening vision is reported at once, because it is often linked to bleeding in the surgical site and needs imaging (Pelsma et al., 2020).
- **Nose and cerebrospinal fluid:** nasal congestion, crusting and blood-stained mucus are expected. Clear, watery fluid dripping from the nose, or a salty taste from fluid running down the back of the throat, may be a **cerebrospinal fluid (CSF) leak** and is reported, as is headache with fever and a stiff neck (Cambridge University Hospitals NHS Foundation Trust, 2026).
- **Protecting the repair:** one centre advises no nose blowing for 2 weeks and no heavy lifting, bending or straining on the toilet, because these raise the risk of bleeding or CSF leak (Cambridge University Hospitals NHS Foundation Trust, 2026). Instructions vary, so the nurse follows the surgeon's orders and gives stool softeners as ordered.
- **Water balance:** the nurse measures intake and output closely, often hourly urine volumes at first, and reports a sharp rise in dilute urine. Temporary arginine vasopressin deficiency can follow pituitary surgery (Ferring Inc., 2019). Salt imbalance can also develop after discharge: one centre warns patients that feeling generally unwell and very tired 1 to 2 weeks after surgery may reflect a salt imbalance, and checks a blood test within 5 to 7 days of discharge (Cambridge University Hospitals NHS Foundation Trust, 2026).
- **Cortisol:** surgery can correct pituitary hormone deficiencies or cause new ones, so hormones are retested (Petersenn et al., 2023). The nurse gives glucocorticoids exactly as ordered and watches for signs of adrenal insufficiency (section 23.4). Glucocorticoid replacement can unmask arginine vasopressin deficiency, because cortisol is needed for the kidneys to excrete free water (Baldeweg et al., 2018).

SIADH

The **syndrome of inappropriate antidiuretic hormone secretion (SIADH)** is the release of antidiuretic hormone (ADH; also called arginine vasopressin) even though the plasma is dilute. Chapter 3 explains its mechanism, its diagnostic criteria and the safe limits for correcting sodium; this section adds the endocrine view. The kidneys keep returning water to the blood, so the urine stays concentrated, sodium falls, and the patient looks neither dry nor overloaded (euvolemic). Causes include lung disease such as pneumonia and small cell lung cancer, brain conditions such as stroke, head injury, subarachnoid hemorrhage and meningitis, and drugs such as selective serotonin reuptake inhibitors, carbamazepine and opioids. General anesthesia, nausea, pain and stress are strong triggers, so SIADH is a risk after any surgery (Spasovski et al., 2014).

Nausea, headache and confusion are moderately severe symptoms; vomiting, deep drowsiness, seizures and coma are severe (Spasovski et al., 2014). In an older adult, new confusion or a fall may be the first cue.

Treatment principles are to treat or remove the cause, stop drugs that may be responsible, and restrict fluid as the first-line treatment for moderate or profound hyponatremia from SIADH. Severe or moderately severe symptoms need hypertonic saline in a monitored setting (Society for Endocrinology, 2022; Spasovski et al., 2014). The nurse:

- keeps an accurate intake and output record and weighs the patient daily;
- helps the patient spread a fluid restriction across the day;
- checks neurologic status and keeps the patient safe from falls;
- reports a sudden rise in urine output, which can signal that sodium is rising too fast (Society for Endocrinology, 2022).

Arginine Vasopressin Deficiency and Resistance

In 2022, an international working group renamed diabetes insipidus because the shared word "diabetes" confused patients and staff with diabetes mellitus. In some hospital patients, desmopressin was withheld, with serious outcomes including death (Arima et al., 2022). **Arginine vasopressin deficiency (AVP-D; formerly central diabetes insipidus)** means the pituitary does not release enough vasopressin. **Arginine vasopressin resistance (AVP-R; formerly nephrogenic diabetes insipidus)** means the kidneys do not respond to it (Arima et al., 2022).

In both, the kidneys cannot concentrate urine, so large volumes of dilute urine are passed. Complete AVP deficiency can cause more than 10 L of urine in 24 hours (Baldeweg et al., 2018). A person with a working thirst mechanism and free access to water usually keeps sodium normal by drinking more. Danger comes when the person cannot drink enough: a patient who is confused, drowsy, frail or nothing by mouth, who cannot sense thirst, or whose desmopressin is missed. These patients can develop life-threatening dehydration and **hypernatremia** (Baldeweg et al., 2018). Older adults are at extra risk because thirst weakens with age (Yun et al., 2023).

Causes of AVP deficiency include pituitary and hypothalamic disease, pituitary surgery and head trauma (Baldeweg et al., 2018; Ferring Inc., 2019). Long-term lithium therapy is one cause of AVP resistance: it frequently reduces the kidney's ability to concentrate urine, with thirst and polyuria, and occasionally causes AVP resistance itself (Bausch Health, Canada Inc., 2019).

Desmopressin, a synthetic form of vasopressin, treats AVP deficiency but does not work for AVP resistance (Ferring Inc., 2019). Its most serious adverse effect is hyponatremia from water retention. Patients learn the fluid advice their prescriber gives and report headache, nausea, vomiting, weight gain or confusion. Adults over 65 need closer observation (Ferring Inc., 2019).

The Society for Endocrinology recommends the following inpatient care for known AVP deficiency (Baldeweg et al., 2018):

- **On admission:** identify the patient, alert the endocrine team and flag the need for desmopressin.
- **Every shift:** keep water and desmopressin within reach, and never omit or delay a dose.
- **Monitoring:** check sodium at least every 24 hours while the patient receives IV fluids and regular desmopressin, and at least every 12 hours if consciousness is impaired.
- **Hypernatremia:** treat as a medical emergency in a high-dependency setting.

Table 23.3 compares SIADH with AVP deficiency.

Table 23.3 SIADH and arginine vasopressin deficiency compared (Baldeweg et al., 2018; Ferring Inc., 2019; Spasovski et al., 2014)

Feature	SIADH	AVP deficiency (central diabetes insipidus)
Problem	Too much ADH action for the plasma osmolality	Too little vasopressin released by the pituitary
Urine volume	Not increased	Very high; can exceed 10 L in 24 hours
Urine concentration	Inappropriately concentrated (urine osmolality above 100 mOsm/kg)	Inappropriately dilute
Serum sodium	Low	Normal if the person can drink; high if they cannot
Fluid status	Euvolemic	Dehydration if intake falls behind losses
Common causes	Pneumonia, small cell lung cancer, brain injury or stroke, some drugs, surgery, pain, nausea	Pituitary or hypothalamic disease, pituitary surgery, head trauma
Key nursing actions	Fluid restriction as ordered, daily weight, neurologic checks, report a sudden rise in urine output	Water within reach, desmopressin on time, intake and output, sodium checks, report rising sodium

GOING DEEPER

Osmolality and Urine Tests in Water-Balance Disorders

Required for RN students; optional for PN students.

Serum osmolality is usually about 275 to 295 mOsm/kg, and urine osmolality can range from about 50 to 1,200 mOsm/kg, depending on how much water the kidneys must save or excrete; ranges vary by laboratory (University of Ottawa, 2022). The key is to read the urine against the blood.

- **SIADH:** serum osmolality below 275 mOsm/kg with urine osmolality above 100 mOsm/kg and urine sodium above 30 mmol/L in a euvolemic patient, without adrenal, thyroid, pituitary or kidney failure or recent diuretics (Spasovski et al., 2014). The urine is "too concentrated" for dilute blood.
- **AVP deficiency or resistance:** high-normal or high serum sodium and osmolality with a large volume of dilute urine. A large urine output with a low urine osmolality shows that desmopressin is needed in AVP deficiency (Baldeweg et al., 2018). The urine is "too dilute" for concentrated blood.

- **Very high water intake (as in primary polydipsia):** low serum sodium with very dilute urine, because the kidneys are correctly excreting the extra water. This is the opposite of SIADH, in which urine osmolality stays above 100 mOsm/kg (Spasovski et al., 2014).

Desmopressin given for AVP deficiency should reduce urine volume and raise urine osmolality, and the response is tracked with these measures (Ferring Inc., 2019). During treatment for hypernatremia, sodium is checked every 4 hours at first (Baldeweg et al., 2018).

CLINICAL JUDGMENT

Six Litres of Urine After Pituitary Surgery

Names and details are fictional; this is a composite story.

Daniel Okeke, 54, had transsphenoidal removal of a nonfunctioning pituitary macroadenoma yesterday morning. He is on a neurosurgical unit with hydrocortisone ordered.

- **Recognize cues:** Daniel has passed 6,050 mL of pale urine in the past 18 hours, including 420, 450 and 480 mL in the last three hours. He asks repeatedly for water and says he is "parched." His blood pressure is 118/72 mm Hg and heart rate 96. His vision is unchanged from baseline, and no clear fluid drips from his nose. Laboratory results: sodium 148 mmol/L (142 mmol/L before surgery), serum osmolality 304 mOsm/kg, urine osmolality 130 mOsm/kg.
- **Analyze cues:** Large volumes of dilute urine with a rising sodium and high serum osmolality fit arginine vasopressin deficiency after pituitary surgery (section 23.5). Excreting extra IV fluid would not make his sodium rise.
- **Prioritize hypotheses:** The main risk is dehydration and worsening hypernatremia, especially if he becomes drowsy and cannot drink.
- **Generate solutions:** Report now with SBAR, keep water at the bedside, measure hourly intake and output, recheck sodium as ordered and anticipate desmopressin.
- **Take action:** The nurse reports to the neurosurgical resident. Desmopressin is ordered, hydrocortisone continues on time, and a sodium recheck is ordered for 4 hours later.
- **Evaluate outcomes:** Over 4 hours his urine output falls to 90 mL/h, his sodium is 145 mmol/L, and his thirst eases. The nurse now watches for the opposite problem: water retention and falling sodium in the days ahead.

SCOPE IN PRACTICE

Endocrine Emergencies and the Nurse's Role

Adrenal crisis, severe hyponatremia and severe hypernatremia are life-threatening, so every nurse who notices the cues acts at once: stays with the patient, calls for help and reports using SBAR (Chapter 6). CNO's Scope of Practice standard explains the roles through **authority, competence and context** (College of Nurses of Ontario [CNO], 2025b; Chapter 1, section 1.3):

- **Authority:** administering a substance by injection is a controlled act authorized to RNs and RPNs. It needs an order, either a client-specific order or a medical directive (CNO, 2025a; CNO, n.d.). An emergency hydrocortisone injection is given under such an order. Guidelines also recommend teaching patients and family members to give the emergency injection themselves (Bornstein et al., 2016).
- **Competence:** the nurse must know the drug, route, expected response and what to monitor afterward.
- **Context:** in long-term care, an RPN may be the first nurse at the resident's side, with the physician or nurse practitioner (NP) off site, and calls 9-1-1, the physician or NP and the RN in charge without delay. In hospital, a patient in crisis has complex, changing needs. Employers commonly assign such patients to an RN, but this is employer practice, not a CNO rule. The RPN consults the RN as the patient's needs change and continues to act on what they see.

Employer policy, medical directives and province or territory all shape these roles. CNO's revised Scope of Practice and Medication standards take effect March 1, 2027 (CNO, 2026).

PRACTICE STORY

The Missed Prednisone

Names and details are fictional; this is a composite story.

Nurse: Mei-Lin Arsenault, RPN. Years in practice: 9. Setting: long-term care home, Ontario.

At 0630, the personal support worker (PSW) told me Mrs. Ruth Halvorsen, 84, had vomited twice overnight. Ruth has taken prednisone every morning for six years for polymyalgia rheumatica. At 0800 she brought her pills back up within minutes, and

again with crackers at 0900. By 1000 something had changed. Ruth, who usually teases me about my coffee, stared past me and could not tell me where she was. Her blood pressure was 86/50 mm Hg, which for Ruth, whose usual is about 140/80, was a big drop. Her heart rate was 112, her temperature 37.8 °C and her glucose 4.6 mmol/L. She was holding her stomach.

The night nurse had written "gastro, push fluids." I could see why. But I kept thinking about that missed prednisone. After six years, her own adrenal glands could not make the cortisol she needed for this illness. Vomiting, falling pressure, confusion: that was adrenal crisis until proven otherwise.

Six months earlier, after a hospital stay, her geriatrician had ordered an emergency hydrocortisone injection kit, with an order to give it IM if she could not keep her prednisone down. I asked our PSW to call 9-1-1 and page our RN supervisor while I checked the order, drew it up and gave it. While we waited, I phoned the NP and used SBAR: "Long-term prednisone, two missed doses from vomiting, BP 86/50 from a baseline of 140/80, new confusion. I've given the emergency hydrocortisone under her standing order and called 9-1-1." She agreed and called the emergency department.

I sent the steroid card, her medication list and the time of the injection with the paramedics. Ruth came back four days later, alert and joking again. Since then, our home's sick-day teaching covers residents on long-term steroids, not only those with diabetes.

Reflect: Which part of my response depended on an existing order, and what would I have done without one? How do authority, competence and context shape an RPN's actions when they are the first nurse at the resident's side?

Chapter 23 Summary

23.1 Endocrine Feedback and Testing

- Most endocrine glands are controlled by negative feedback through hypothalamic–pituitary–target gland axes.
- TSH is the most reliable single thyroid test: high in primary hypothyroidism and low in hyperthyroidism. In pituitary disease it is unreliable, and free T4 guides care.
- Ionized calcium is the active form; a low albumin lowers total calcium without changing ionized calcium. PTH is always read with a calcium.
- Reference ranges vary by laboratory. The nurse times samples such as morning cortisol and asks about biotin, which can distort thyroid immunoassays.

23.2 Thyroid Disorders

- Hypothyroidism, most often from Hashimoto thyroiditis, causes fatigue, cold intolerance, dry skin and constipation. It is treated with levothyroxine taken on an empty stomach and apart from calcium and iron, with TSH checked 6 to 8 weeks after dose changes.
- Myxedema coma (hypothermia, bradycardia, hypoventilation, low sodium, drowsiness) is an emergency needing ICU care, IV thyroid hormone, hydrocortisone and passive rewarming.
- Hyperthyroidism, most often from Graves disease or toxic nodular goitre, is treated with beta-blockers, methimazole (PTU in special cases), radioactive iodine or surgery. Fever or sore throat on an antithyroid drug needs urgent assessment for agranulocytosis.
- Thyroid storm causes fever, marked tachycardia, delirium and organ failure; the nurse calls a rapid response, and the antithyroid drug is given before iodine.
- Older adults often have subtle thyroid symptoms; new atrial fibrillation or weight loss may be the only sign of hyperthyroidism.
- Thyroid cancer incidence in Canada rose until 2013, likely from overdiagnosis, and has since declined.

23.3 Thyroid and Parathyroid Surgery

- After thyroid surgery, the nurse observes at least hourly for the first 6 hours. Neck swelling, tightness, voice change or breathing difficulty may be a hematoma: the nurse calls for help at once, sits the patient up and gives oxygen.
- Who may open the wound at the bedside depends on employer policy, orders or medical directives, and competence.
- Low calcium from parathyroid injury causes perioral and fingertip tingling and cramps; the nurse asks about tingling at every assessment and reports it.

- Primary hyperparathyroidism, usually from a single adenoma, is often found on routine tests; parathyroidectomy is the only cure.
- Hypoparathyroidism is treated with calcium and calcitriol, aiming for a low-normal calcium, with checks after treatment changes to prevent kidney harm.

23.4 Adrenal Disorders

- The adrenal cortex makes cortisol and aldosterone; the medulla releases catecholamines. Illness, surgery and injury raise cortisol needs.
- Adrenal insufficiency may be primary (Addison disease), secondary (pituitary or hypothalamic) or glucocorticoid-induced; hyperkalemia and hyperpigmentation point to primary disease, and darkening is easy to miss on darker skin.
- Long-term glucocorticoids are never stopped abruptly; inhaled, topical and injected products count too.
- Adrenal crisis causes shock, vomiting, abdominal pain and confusion; treatment is immediate: hydrocortisone 100 mg IV or IM, then 200 mg over 24 hours, with 1 L of isotonic saline in the first hour.
- Sick-day rules, a steroid emergency card, medical alert identification and an emergency injection kit prevent crises.
- Cushing syndrome is most often caused by prescribed glucocorticoids; easy bruising, proximal weakness and wide striae are the most telling signs. Primary aldosteronism and pheochromocytoma are adrenal causes of hypertension.

23.5 Pituitary Disorders and Water Balance

- Pituitary adenomas cause hormone excess, hormone deficiency or mass effects such as headache and bitemporal visual field loss; sudden headache with vision loss needs urgent escalation.
- After transsphenoidal surgery, the nurse checks vision, reports clear nasal drainage, protects the repair, measures intake and output, and gives glucocorticoids as ordered.
- SIADH causes euvolemic hyponatremia with concentrated urine; fluid restriction is first-line, and sodium is corrected within the limits in Chapter 3.
- Arginine vasopressin deficiency and resistance (formerly central and nephrogenic diabetes insipidus) cause large volumes of dilute urine; hypernatremia follows when the person cannot drink.
- Desmopressin treats AVP deficiency, must never be omitted in hospital, and can cause hyponatremia.
- Every nurse recognizes and escalates endocrine emergencies; injections are given under an order or directive, and the RPN consults the RN as needs change.

Key Terms (53)

acromegaly: a condition caused by excess growth hormone in adults, usually from a pituitary adenoma, with enlarged hands, feet and facial features.

Addison disease: primary adrenal insufficiency, in which the adrenal cortex is damaged, most often by autoimmune disease, so cortisol and usually aldosterone are low.

adrenal cortex: the outer part of the adrenal gland, which makes the steroid hormones cortisol and aldosterone.

adrenal crisis: a life-threatening emergency in which cortisol supply cannot meet the body's needs, causing hypotension, volume depletion, vomiting and confusion; treated at once with parenteral hydrocortisone and isotonic saline.

adrenal insufficiency: a condition in which the adrenal glands do not supply enough cortisol, with or without enough aldosterone.

adrenal medulla: the inner part of the adrenal gland, which releases the catecholamines epinephrine and norepinephrine.

agranulocytosis: A severe drop in neutrophils, a rare but life-threatening adverse effect of antithyroid drugs.

aldosterone: the main mineralocorticoid hormone; it makes the kidneys retain sodium and water and excrete potassium.

arginine vasopressin deficiency (AVP-D): the current name for central diabetes insipidus, in which too little vasopressin is released, so large volumes of dilute urine are passed.

arginine vasopressin resistance (AVP-R): the current name for nephrogenic diabetes insipidus, in which the kidneys do not respond to vasopressin.

axis: A chain of control in which the hypothalamus and pituitary stimulate a target gland, such as the thyroid or adrenal cortex.

bitemporal visual field loss: loss of the outer (temporal) visual fields of both eyes, caused by pressure on the optic chiasm.

cerebrospinal fluid (CSF) leak: escape of the fluid around the brain, seen after transsphenoidal surgery as clear, watery nasal drainage or salty fluid in the throat.

cortisol: the main glucocorticoid hormone; released under ACTH control, it helps maintain blood pressure and blood glucose and rises during stress.

Cushing disease: Cushing syndrome caused by an ACTH-secreting pituitary adenoma.

Cushing syndrome: the signs and symptoms of prolonged, inappropriately high glucocorticoid exposure, most often from prescribed glucocorticoids.

desmopressin: a synthetic form of vasopressin used to treat arginine vasopressin deficiency; its most serious adverse effect is hyponatremia.

fine-needle aspiration (FNA): A procedure in which cells are drawn from a thyroid nodule through a thin needle for examination.

free T4: The small unbound fraction of thyroxine in the blood that is available to cells.

glucocorticoid-induced adrenal insufficiency: adrenal insufficiency caused by long-term glucocorticoid medication suppressing the hypothalamic–pituitary–adrenal axis; it appears when the drug is stopped, reduced or not absorbed, or when stress raises cortisol needs.

goitre: An enlarged thyroid gland, seen or felt as fullness at the front of the neck.

Graves disease: An autoimmune disorder in which antibodies stimulate the TSH receptor and cause hyperthyroidism.

Hashimoto thyroiditis: Chronic autoimmune thyroiditis, the most common cause of hypothyroidism where diets contain enough iodine.

hormone: A chemical messenger released into the blood by a gland that acts on target cells elsewhere in the body.

hypernatremia: a serum sodium above the reference range, usually from water loss greater than sodium loss.

hyperpigmentation: darkening of the skin and mucous membranes caused by high ACTH in primary adrenal insufficiency, most visible in creases, gums, scars and sun-exposed skin.

hyperthyroidism: Thyrotoxicosis caused by a thyroid gland that makes too much hormone.

hypoparathyroidism: Too little PTH, causing low calcium; most often caused by neck surgery.

hypothyroidism: A deficiency of thyroid hormone that slows metabolism throughout the body.

ionized calcium: The free, physiologically active form of calcium in the blood, not bound to albumin.

myxedema coma: The most severe form of hypothyroidism, an emergency with a falling level of consciousness, hypothermia, bradycardia, hypoventilation and low sodium.

neck hematoma: A collection of blood under a neck incision that can compress the airway; an emergency after thyroid or parathyroid surgery.

negative feedback: The control loop in which a rising level of a final hormone reduces release of the hormones that stimulate it, and a falling level increases their release.

parathyroid hormone (PTH): The hormone from the parathyroid glands that raises blood calcium through bone, the kidneys and activated vitamin D.

parathyroidectomy: Surgical removal of one or more overactive parathyroid glands.

pheochromocytoma: a catecholamine-secreting tumour of the adrenal medulla that can cause episodes of high blood pressure, headache, palpitations and sweating.

pituitary adenoma: a benign tumour of the pituitary gland that may secrete a hormone, press on nearby structures, or both.

primary aldosteronism: overproduction of aldosterone by one or both adrenal glands, independent of renin, causing hypertension and sometimes low potassium.

primary hyperparathyroidism: Excess PTH from one or more parathyroid glands, most often a single benign adenoma, causing high calcium.

prolactinoma: a prolactin-secreting pituitary adenoma, the most common type, usually treated first with a dopamine agonist.

radioactive iodine therapy (RAI): An oral dose of radioactive iodine that destroys overactive thyroid tissue.

recurrent laryngeal nerve: A nerve running close behind the thyroid that controls the vocal cords; injury can cause hoarseness.

sick-day rules: instructions for people who take glucocorticoids to increase the dose during illness and to use an emergency injection when tablets cannot be taken.

steroid emergency card: a card carried by a person who depends on glucocorticoids, telling health care providers how to recognize and treat adrenal crisis.

striae: stretch marks; in Cushing syndrome they may be wide, appearing red to purple on lighter skin and often brown to black on darker skin.

subclinical hypothyroidism: A TSH above the reference range with a normal free T4.

syndrome of inappropriate antidiuretic hormone secretion (SIADH): continued ADH release despite dilute plasma, causing water retention, euvolemic hyponatremia and concentrated urine.

thyroid eye disease: An autoimmune disorder of the tissues around the eyes, closely linked to Graves disease, that causes eyelid retraction, proptosis, swelling and double vision.

thyroid storm: Life-threatening thyrotoxicosis with failure of one or more organs, usually triggered by another illness.

thyroid-stimulating hormone (TSH): The pituitary hormone that drives the thyroid to make thyroid hormone; the most reliable single test of thyroid function in most people.

thyroidectomy: Surgical removal of all (total) or part of the thyroid gland.

thyrotoxicosis: The state caused by too much thyroid hormone acting on the tissues, whatever the cause.

transsphenoidal surgery: removal of a pituitary tumour through the nose and sphenoid sinus.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Ms. Amira Haddad (Questions 1–6): Ms. Amira Haddad, 41, had a total thyroidectomy this morning for Graves disease and arrived on the surgical unit at 1100. At 1500, she tells the registered nurse (RN) that her neck "feels tight." The RN notes the front of her neck is visibly fuller than at the 1400 check, and her voice is hoarse and quieter than earlier. Vital signs: blood pressure 142/88 mm Hg, heart rate 108 beats per minute, respiratory rate 24 breaths per minute, oxygen saturation 93% on room air (97% at 1400), temperature 37.2 °C. The dressing has a small, unchanged spot of dried blood.

1. [CORE] Which findings at 1500 require urgent follow-up? Select all that apply.

a. The visibly increased fullness of the front of the neck since 1400
b. The new hoarse, quieter voice compared with earlier in the day
c. The small, unchanged spot of dried blood on the dressing
d. The feeling of tightness in her neck that she describes
e. The fall in oxygen saturation from 97% to 93% with a respiratory rate of 24
f. A temperature of 37.2 °C on the afternoon of surgery

Answer: a, b, d, e — Recognize cues (section 23.3). New neck swelling (a), a voice change (b), a sense of tightness (d) and rising respiratory rate with falling oxygen saturation (e) are cues of an expanding neck hematoma that can obstruct the airway. A small, unchanged dried stain (c) is expected; a nearly dry dressing does not rule out deep bleeding, but it is not itself a warning sign. A temperature of 37.2 °C (f) is within normal limits.

2. [CORE] Which explanation best accounts for Ms. Haddad's findings at 1500?

a. Low calcium from parathyroid injury causing laryngeal muscle spasm
b. Blood collecting under the incision and pressing on the airway
c. Thyroid storm triggered by handling of the gland during surgery
d. Expected throat irritation from the breathing tube used during anesthesia

Answer: b — Analyze cues (section 23.3). Increasing swelling, tightness, voice change and falling oxygen saturation a few hours after surgery point to a neck hematoma (b). Low calcium (a) begins with tingling around the mouth and in the fingers, and usually appears later; she reports none. Thyroid storm (c) causes high fever, marked tachycardia and agitation; her temperature is normal and she was prepared for surgery. Throat irritation from intubation (d) does not cause visible neck swelling or falling oxygen saturation.

3. [CORE] What is the RN's priority action?

a. Call for immediate help from the rapid response team and the surgeon, sit Ms. Haddad up and give oxygen
b. Reinforce the dressing with a firm pressure bandage over the incision and recheck her neck and breathing in 30 minutes
c. Give the ordered analgesic and reassess her voice and swallowing once the pain eases
d. Draw an ionized calcium and check for a positive Trousseau sign before calling the surgeon

Answer: a — Take action (section 23.3; Clinical Safety box). A suspected hematoma is an airway emergency: the nurse calls for help at once, stays with the patient, sits her up and gives oxygen (a). A tight pressure bandage (b) could worsen airway compression and delays help. Analgesia (c) treats a symptom while the airway is threatened. Calcium testing (d) addresses a different, later problem and delays escalation.

4. [CORE] Ms. Haddad returns to the operating room, the hematoma is evacuated, and she recovers. At 0700 the next day, she says her lips and fingertips are "tingling and numb" and her hands feel crampy. Her ionized calcium is 0.98 mmol/L (laboratory range 1.14 to 1.28 mmol/L). What is the most likely cause?

a. Recurrent laryngeal nerve injury affecting sensation in the face
b. A second, smaller hematoma pressing on nerves in the neck
c. Low PTH from parathyroid gland injury during surgery
d. Anxiety and fast breathing after a frightening night

Answer: c — Analyze cues (section 23.3). Perioral and fingertip tingling with cramps and a low ionized calcium after total thyroidectomy fit hypocalcemia from parathyroid injury and low PTH (c). The recurrent laryngeal nerve (a) controls the vocal cords and does not cause facial tingling. A hematoma (b) causes swelling, voice change and breathing difficulty, not a low calcium. Anxiety with overbreathing (d) can cause tingling, but it would not explain a measured ionized calcium well below the range.

5. [RN] Ms. Haddad's tingling is spreading, and she now has cramping in both hands. Which order does the RN anticipate first?

a. Oral levothyroxine given now instead of tomorrow morning
b. A fluid restriction and a repeat ionized calcium in 24 hours
c. IV magnesium sulfate alone, since magnesium often falls after surgery
d. IV calcium gluconate given with ECG monitoring

Answer: d — Generate solutions (section 23.3; Chapter 3, section 3.6). Symptomatic, worsening hypocalcemia is treated with IV calcium gluconate under ECG monitoring, followed by oral calcium and calcitriol as ordered (d). Levothyroxine (a) replaces thyroid hormone and does not raise calcium. Restricting fluids and waiting 24 hours (b) delays treatment of a progressing emergency. Magnesium is checked and corrected because low magnesium blocks PTH, but magnesium alone (c) does not treat symptomatic hypocalcemia.

6. [CORE] Before discharge, which statement by Ms. Haddad shows that teaching has been effective?

a. "I'll take my calcium and calcitriol as prescribed and call if the tingling comes back."
b. "I'll only need levothyroxine until the swelling in my neck goes down completely."
c. "If my lips tingle at home, I can double my levothyroxine that day to help."
d. "My calcium will be back to normal once I leave hospital, so I won't need blood tests."

Answer: a — Evaluate outcomes (section 23.3). She understands to take calcium and calcitriol as prescribed and to report returning symptoms (a). After total thyroidectomy, levothyroxine is lifelong (b). Levothyroxine does not treat low calcium, and the dose is never changed without advice (c). Most people recover parathyroid function within a month, but calcium is followed with blood tests, and some develop permanent hypoparathyroidism (d).

7. [CORE] A 58-year-old man reports tiredness, feeling cold and constipation. His TSH is high and his free T4 is low. How does the nurse interpret these results?

a. Primary hyperthyroidism, because the high TSH is pushing the thyroid to overproduce

b. Central hypothyroidism, because the pituitary is not making enough TSH

c. Primary hypothyroidism, because the pituitary is responding to low thyroid hormone

d. Normal thyroid function, because the TSH and free T4 balance each other out

Answer: c — Through negative feedback, a failing thyroid makes too little T4 and the pituitary raises TSH: high TSH with low free T4 is primary hypothyroidism (c) (section 23.1). In hyperthyroidism (a), TSH is low. In central disease (b), TSH is low, normal or mildly raised, not clearly high. The results are both abnormal and do not cancel each other out (d).

8. [CORE] A patient is scheduled for thyroid blood tests tomorrow morning. Which question by the nurse is most important to ask today?

a. "Do you take any vitamin or hair, skin and nail supplement that contains biotin?"

b. "Have you had any iodine-containing foods such as seafood in the last month?"

c. "Will you be able to fast from all food and fluids, including water, from midnight tonight until the test?"

d. "Did you have a cold or a sore throat at any time in the past year?"

Answer: a — Biotin can interfere with immunoassays used for thyroid tests and give false results; the Canadian levothyroxine monograph advises stopping biotin at least 2 days before sampling when possible (a) (section 23.1). Dietary seafood (b) is not a routine concern before thyroid tests. TSH and free T4 do not require a complete fluid fast (c). A remote cold (d) does not affect results.

9. [CORE] The nurse reviews levothyroxine teaching with a patient. Which statement shows a need for further teaching?

a. "I take my pill with a glass of water about 45 minutes before I eat breakfast."

b. "I take it every morning with my calcium supplement so I don't forget either one."

c. "I won't switch to a different brand unless my doctor knows and orders a blood test."

d. "I'll have a blood test about 6 to 8 weeks after my dose is changed."

Answer: b — Calcium reduces levothyroxine absorption; the Canadian monograph advises at least 4 hours between them (b) (section 23.2, Patient Education box). Taking it with water 30 to 60 minutes before breakfast (a), not switching products without retesting (c) and a TSH 6 to 8 weeks after a dose change (d) are correct.

10. [CORE] An 82-year-old woman with hypothyroidism is brought from home in January. She has been drowsy for 2 days and stopped taking her medications a week ago. Temperature 34.8 °C, heart rate 46 beats per minute, respiratory rate 8 breaths per minute, sodium 124 mmol/L. Which action is the priority?

a. Encourage her to drink warm fluids to raise her temperature and her sodium

b. Apply an electric warming blanket set to high to restore her temperature quickly

c. Give her usual oral levothyroxine dose now with a sip of water

d. Call for immediate help, support her breathing and prepare for ICU transfer

Answer: d — Hypothermia, bradycardia, slow breathing, low sodium and drowsiness after stopping thyroid medication suggest myxedema coma, an emergency needing ICU care; breathing comes first (d) (section 23.2). A drowsy patient with slow breathing should not be given oral fluids or pills, because of aspiration risk (a, c); oral fluids also lower sodium further, and IV thyroid hormone is used. Rapid active warming (b) can cause vasodilation and shock; rewarming is passive.

11. [CORE] A patient taking methimazole calls the clinic reporting a sore throat and a temperature of 38.6 °C that started today. What is the nurse's best advice?

a. "Take acetaminophen and continue methimazole; call back if you still have a fever in 3 days."

b. "Come in today for a white blood cell count, and hold your methimazole until we have the result."

c. "Gargle with salt water and take your methimazole with food to avoid stomach upset."

d. "Double your methimazole dose, since infections can make your thyroid more overactive."

Answer: b — Fever and sore throat in a patient taking an antithyroid drug may signal agranulocytosis, a rare but life-threatening complication. The Canadian monographs tell patients to report these symptoms right away; a white blood cell count with differential is checked, and the drug is stopped while agranulocytosis is suspected or once it is found (b) (section 23.2). Waiting 3 days (a) or treating it as a minor infection (c) delays diagnosis. Increasing the dose (d) would add to the risk.

12. [CORE] A patient with Graves disease is scheduled for radioactive iodine therapy. Which statement by the patient shows correct understanding?

a. "I may become hypothyroid within a few months and need thyroid hormone for life."

b. "This treatment works right away, so I can stop my beta-blocker after the dose."

c. "I can start trying to get pregnant as soon as the radioactive iodine is out of my body."

d. "The radiation safety instructions are only for patients who receive a second treatment."

Answer: a — Most patients become hypothyroid after radioactive iodine, usually within 2 to 6 months, and need lifelong levothyroxine (a) (section 23.2). The effect is not immediate, so symptom control continues (b). Conception is delayed until thyroid function is stable (c). Written radiation safety instructions apply to every patient who receives a treatment dose (d).

13. [CORE] An 84-year-old man has lost 5 kg over 4 months and has a new irregular pulse of 112 beats per minute. He denies anxiety, tremor or feeling hot. Which test result would the nurse expect to see in his chart?

a. A high TSH, because hypothyroidism is the usual cause of weight loss in older adults

b. A normal TSH, because thyroid disease is unlikely without classic symptoms

c. A high free T4 with a high TSH, the usual pattern in nodular goitre

d. A low TSH, because hyperthyroidism in older adults may cause few adrenergic symptoms

Answer: d — Older adults with hyperthyroidism may have few classic symptoms; weight loss or new atrial fibrillation may be the only clues, and TSH is low (d) (section 23.2, Lifespan box). Hypothyroidism (a) is more likely to cause weight gain and a slower heart rate. The absence of classic symptoms does not rule out thyroid disease (b). A toxic nodular goitre suppresses TSH; a high TSH with high free T4 (c) is not its pattern.

14. [CORE] A registered practical nurse (RPN) is caring for a patient 3 hours after a thyroidectomy. The patient's voice has become hoarse and the patient says swallowing feels harder. What is the most appropriate action by the RPN?

a. Document the hoarseness as an expected effect of surgery and recheck the voice at the end of the shift

b. Ask the patient to rest the voice and sip cold water, and report the change to the RN at the next break

c. Stay with the patient, call for immediate help according to policy, notify the RN and sit the patient up

d. Ask the RN to assume care of the patient and return to the other assigned patients

Answer: c — Voice change and difficulty swallowing soon after thyroid surgery may signal a neck hematoma. Every nurse who recognizes deterioration acts at once and escalates, and the RPN consults the RN as needs change (c) (section 23.3; Chapter 1, section 1.3). Documenting and waiting (a), delaying the report (b) or handing off and leaving the bedside (d) delay help for a threatened airway.

15. [CORE] A patient with known Graves disease is admitted with pneumonia and has missed her methimazole for a week. Her temperature is 39.8 °C, heart rate 154 beats per minute and irregular, and she is newly confused and agitated. What is the nurse's priority?

a. Give acetaminophen and reassess the temperature in 1 hour before calling anyone

b. Restart her oral methimazole and recheck her heart rate in 4 hours

c. Activate the rapid response team, because these cues suggest thyroid storm

d. Apply a cooling blanket and give a sedative ordered as needed for the agitation

Answer: c — High fever, marked tachycardia, AF and new confusion in a patient with Graves disease who has stopped her antithyroid drug and has an infection suggest thyroid storm, which needs ICU-level care without delay (c) (section 23.2; Chapter 6). Fever control alone (a), restarting oral medication and waiting (b) and sedation with cooling (d) delay escalation of a life-threatening emergency.

16. [CORE] A patient with primary hyperparathyroidism asks what the condition might do to the body. Which effects does the nurse include? Select all that apply.

a. Kidney stones, sometimes without symptoms

b. Thinning of the bones with a higher risk of fractures

c. Thirst and passing large amounts of urine

d. Tingling around the mouth and in the fingertips

e. Constipation and nausea

f. Muscle twitching when the cheek is tapped

Answer: a, b, c, e — Primary hyperparathyroidism raises calcium, causing kidney stones (a), bone loss and fractures (b), and symptoms of high calcium such as thirst and frequent urination (c) and constipation and nausea (e) (section 23.3; Chapter 3). Perioral tingling (d) and facial twitching on tapping (f) are signs of low calcium, as in hypoparathyroidism.

17. [CORE] A patient with chronic hypoparathyroidism after thyroid surgery takes calcium and calcitriol. Which teaching point is most important?

a. "Take a calcium supplement only when your lips or fingers tingle, then stop."

b. "Your calcium will need checking within days of any major change in your treatment."

c. "Avoid all dairy products, because the calcium in them could cause stones."

d. "Once you have taken these medicines for a year, they can be stopped for good."

Answer: b — Both too little and too much calcium cause harm; overtreatment can cause kidney stones and kidney damage, so calcium is checked within several days of any significant treatment change (b) (section 23.3). Treatment is regular, not only when symptoms occur (a). Avoiding all dairy (c) is not part of the plan. Hypoparathyroidism lasting more than 12 months is considered permanent, so the medicines usually continue (d).

18. [RN] A patient has a pituitary tumour. TSH is 0.6 mIU/L and free T4 is 6.1 pmol/L (laboratory ranges: TSH 0.4 to 5.0 mIU/L; free T4 8.5 to 15.2 pmol/L). How does the RN interpret these results?

a. Normal thyroid function, because the TSH is within the reference range

b. Central hypothyroidism, because the pituitary is not raising TSH in response to a low free T4

c. Subclinical hypothyroidism, because only one of the two results is abnormal

d. Early hyperthyroidism, because the TSH is near the lower limit of the range

Answer: b — With a low free T4, an intact axis should produce a high TSH. A TSH that is normal or low in the face of low free T4 points to central (pituitary or hypothalamic) disease, and free T4 guides treatment (b) (section 23.1, Going Deeper box). TSH alone is misleading in pituitary disease (a). Subclinical hypothyroidism (c) is a high TSH with a normal free T4. Hyperthyroidism (d) causes a high free T4.

19. [RN] A patient in thyroid storm has orders for propylthiouracil, an iodine solution, propranolol, hydrocortisone and acetaminophen. Which plan for timing is correct?

a. Give the iodine solution first, then the propylthiouracil once the heart rate falls below 100 beats per minute

b. Hold the propranolol until the propylthiouracil has been given for 24 hours

c. Give acetaminophen with ASA for fever, since both lower the temperature quickly

d. Give the propylthiouracil first, then the iodine solution at least 30 to 60 minutes later

Answer: d — The antithyroid drug is given first to block new hormone synthesis; iodine is given at least 30 to 60 minutes later, because iodine given first can worsen storm (d) (section 23.2). Giving iodine first (a) reverses the safe order. Beta-blockade controls the heart rate early and is not delayed (b). Aspirin (ASA) is avoided because it raises free thyroid hormone (c).

20. [RN] A patient on a medical unit has a total calcium of 1.98 mmol/L (range 2.12 to 2.52 mmol/L), an albumin of 22 g/L (range 35 to 50 g/L) and an ionized calcium of 1.20 mmol/L (range 1.14 to 1.28 mmol/L). She has no tingling or cramps. How does the RN interpret these results?

a. True hypocalcemia, which needs IV calcium gluconate before the next assessment

b. Hypercalcemia hidden by low albumin, so her ionized calcium will soon rise

c. Primary hypoparathyroidism, which needs an urgent PTH level drawn

d. A low total calcium explained by low albumin, with a normal active calcium

Answer: d — Because much of the calcium in plasma travels on albumin, a low albumin lowers total calcium while the ionized (active) calcium stays normal, as here; she needs no calcium treatment (d) (section 23.1; Chapter 3, section 3.6). Her normal ionized calcium and lack of symptoms rule out true hypocalcemia (a) and hypoparathyroidism (c). Nothing suggests high calcium (b).

Case: Harold Nakamura (Questions 21–24): Harold Nakamura, 81, lives at home and has taken prednisone every day for 2 years for polymyalgia rheumatica. For 2 days he has had vomiting and diarrhea, and he has not kept down a prednisone dose since yesterday morning. His daughter brings him to the emergency department because he is confused. Vital signs: temperature 37.9 °C, heart rate 116, respiratory rate 22, blood pressure 82/50 mm Hg lying (his usual is about 135/80 mm Hg), oxygen saturation (SpO_2) 95% on room air. Capillary glucose 4.4 mmol/L. Laboratory results: sodium 129 mmol/L, potassium 4.6 mmol/L, creatinine 148 µmol/L (90 µmol/L six months ago).

21. [CORE] Which explanation best accounts for Mr. Nakamura's condition?

a. Septic shock from an intestinal infection, with fever as the main driver of his low blood pressure

b. Adrenal crisis, because vomiting kept him from taking the prednisone his body now depends on

c. Fluid loss from diarrhea alone, which a large oral fluid intake at home would have prevented

d. Delirium from mild dehydration that should clear once he drinks enough oral fluids

Answer: b — After 2 years of daily prednisone, his HPA axis is suppressed, so missed doses during a gastrointestinal illness can trigger adrenal crisis, with hypotension, confusion and hyponatremia (section 23.4). Sepsis (a) remains possible, but his temperature is only mildly raised and the missed glucocorticoid explains the picture better; both are treated urgently. Fluid loss alone (c) ignores the missed prednisone, the most dangerous cue. Delirium (d) does not explain a systolic pressure of 82 mm Hg, and an older adult's new confusion must not be dismissed (Chapter 8).

22. [CORE] Which order should the nurse expect to carry out first?

a. Give hydrocortisone IV or IM without waiting for the cortisol result to return

b. Hold all glucocorticoids until a morning cortisol level confirms the diagnosis tomorrow

c. Give his usual oral prednisone dose with crackers and recheck in one hour

d. Send a 24-hour urine collection for free cortisol before giving any medication

Answer: a — Treatment of a suspected adrenal crisis must never wait for tests; hydrocortisone is given IV or IM at once, with isotonic saline (section 23.4). Holding glucocorticoids (b) could be fatal. Oral prednisone (c) is unreliable when he is vomiting, and parenteral glucocorticoid is recommended. A 24-hour urine collection (d) is a screening test for Cushing syndrome, not an emergency test.

23. [CORE] A practical nurse (PN) is helping with Mr. Nakamura's care and must report his status to the RN. Which information is most important to include?

a. He lives at home with support, and his daughter visits most days to help with meals and errands

b. His oxygen saturation is 95% on room air and his respiratory rate is 22

c. Daily prednisone with missed doses, blood pressure 82/50 mm Hg and new confusion

d. His last bowel movement was this morning, and he says his abdomen has felt sore since yesterday

Answer: c — An SBAR report leads with the cues that show danger and point to the cause: long-term glucocorticoid use, missed doses, hypotension and new confusion (section 23.4; Chapter 6). His home situation (a) matters for discharge planning, not now. His oxygenation (b) is acceptable. Bowel and abdominal details (d) are relevant but less urgent than shock.

24. [CORE] Before discharge, the nurse teaches Mr. Nakamura and his daughter about preventing another crisis. Which statement by the daughter shows understanding?

a. "If he feels unwell, he should skip his prednisone until his stomach settles."

b. "He can stop the prednisone on his own once his muscle pain has been gone for about a month."

c. "We only need his medical alert bracelet when he travels away from home."

d. "If he can't keep his prednisone down, he needs his emergency injection, then hospital."

Answer: d — Sick-day rules call for an emergency glucocorticoid injection when tablets cannot be kept down, followed by hospital care (section 23.4, Patient Education box). Skipping doses during illness (a) is what caused this crisis. Long-term prednisone is never stopped without a supervised taper (b). Medical alert identification and a steroid emergency card are worn and carried at all times (c).

25. [CORE] A patient has adrenal insufficiency. Which finding suggests primary disease (Addison disease) rather than insufficiency caused by long-term glucocorticoid use?

a. Fatigue, poor appetite and weight loss over several months

b. Dizziness and light-headedness when standing up from a chair

c. Potassium of 5.8 mmol/L with darkening of the palm creases

d. Sodium of 131 mmol/L on routine blood work done last week

Answer: c — In primary disease, aldosterone is lost, causing hyperkalemia, and high ACTH darkens creases, gums and scars; neither occurs when the HPA axis is suppressed by glucocorticoids (section 23.4). Fatigue and weight loss (a), postural dizziness (b) and hyponatremia (d) occur in both primary and secondary disease.

26. [CORE] A patient with deeply pigmented skin is being assessed for possible Addison disease. Which approach should the nurse use to look for hyperpigmentation?

a. Inspect gums, palm creases and scars in natural light and ask if the skin has darkened

b. Compare the colour of the patient's face with the nurse's own forearm under the room lights

c. Rely on the absence of visible darkening on the face to rule out hyperpigmentation

d. Inspect the abdomen under the room's fluorescent lights for wide purple stretch marks

Answer: a — Hyperpigmentation shows most in creases, mucous membranes and scars, and on darker skin it is best judged against the person's own usual colour, in natural light, with the patient's or family's report (section 23.4). Comparing with another person's skin (b) is not meaningful. General darkening is easy to miss on darker skin, so absence on the face (c) does not rule it out. Fluorescent light distorts colour, and wide striae (d) suggest Cushing syndrome, not Addison disease.

27. [CORE] A patient has taken prednisone for 8 months for an inflammatory condition and tells the nurse, "I feel great now, so I'm going to stop the pills this weekend." What is the nurse's best response?

a. "That's reasonable, as long as you taper off over the weekend by halving the dose each day."

b. "Stopping suddenly could cause a dangerous drop in cortisol; ask your prescriber about a taper."

c. "You can stop safely now, because your symptoms show that your adrenal glands are working again."

d. "Keep taking it, but switch to taking it every other day so your body can start making its own cortisol."

Answer: b — After long-term use, abrupt withdrawal can cause fatal adrenal insufficiency, and the HPA axis may stay suppressed for months; tapering is planned by the prescriber (section 23.4). A self-designed rapid taper (a) or an every-other-day schedule (d) is not something the nurse can direct. Feeling well (c) says nothing about adrenal recovery.

28. [CORE] During medication reconciliation, which products should the nurse identify as possible causes of glucocorticoid-induced adrenal insufficiency? Select all that apply.

a. Fluticasone inhaler used twice daily for 3 years

b. High-potency corticosteroid cream applied daily for 18 months

c. Corticosteroid injection into the knee 6 weeks ago

d. Acetaminophen taken as needed for knee pain

e. Levothyroxine taken every morning for 10 years

f. Calcium carbonate taken with supper

Answer: a, b, c — Glucocorticoids by any route can suppress the HPA axis, including inhaled or topical products used for more than a year and joint injections in the past 2 months (section 23.4). Acetaminophen (d), levothyroxine (e) and calcium (f) do not suppress the axis.

29. [CORE] Which finding in a patient with weight gain most suggests Cushing syndrome rather than common obesity?

a. Weight gain mainly around the abdomen and waist

b. Fatigue, low energy and difficulty sleeping at night

c. A blood pressure of 142/88 mm Hg at two visits

d. Difficulty rising from a chair and easy bruising

Answer: d — Proximal muscle weakness and easy bruising are among the features that best separate Cushing syndrome from common conditions (section 23.4). Central weight gain (a), fatigue and poor sleep (b) and high blood pressure (c) are common in many people and are less specific.

30. [CORE] A patient with hypertension takes three antihypertensive drugs, and their blood pressure is still not controlled. Their potassium is 3.2 mmol/L, and they do not take a diuretic. Which test should the nurse anticipate?

a. Plasma free metanephrines with the patient supine

b. Overnight dexamethasone suppression test

c. Aldosterone-to-renin ratio drawn in the morning with the patient seated

d. Corticotropin stimulation test with cortisol levels at 30 and 60 minutes

Answer: c — Hypertension resistant to three drugs and unexplained low potassium are Hypertension Canada's reasons to screen for primary aldosteronism with the aldosterone-to-renin ratio (section 23.4). Metanephrines (a) screen for pheochromocytoma, the dexamethasone test (b) for Cushing syndrome, and the stimulation test (d) for adrenal insufficiency.

31. [CORE] A patient with a large pituitary adenoma reports bumping into door frames on both sides. Which finding should the nurse expect on visual field testing?

a. Loss of the outer (temporal) fields of both eyes
b. Loss of all vision in one eye only
c. A blind spot in the centre of both visual fields
d. Loss of the lower fields of both eyes, starting at the bottom

Answer: a — A pituitary tumour pressing on the optic chiasm typically causes bitemporal visual field loss, often beginning in the upper outer quadrants (section 23.5). Loss in one eye only (b), central blind spots (c) and loss starting in the lower fields (d) are not the typical pattern.

32. [CORE] On the second day after transsphenoidal surgery, a patient tells the nurse that clear, watery fluid drips from their nose when they lean forward. What should the nurse do?

a. Encourage the patient to blow their nose gently to clear the drainage
b. Document the finding as expected nasal congestion and reassess at the end of the shift
c. Give a decongestant nasal spray from the patient's own supply
d. Report the finding promptly as a possible cerebrospinal fluid leak

Answer: d — Clear, watery nasal drainage after transsphenoidal surgery may be a CSF leak and is reported promptly (section 23.5). Nose blowing (a) is avoided after surgery. Congestion with crusting is expected, but clear watery fluid is not (b). Using a patient's own medication without an order (c) is unsafe.

33. [CORE] Twelve hours after pituitary surgery, a patient's urine output is 400 mL/h of pale urine, and the patient is very thirsty. What should the nurse do first?

a. Restrict the patient's oral fluids to slow the urine output
b. Report the output and request a serum sodium and urine osmolality
c. Encourage the patient to drink only when the next meal tray arrives
d. Increase the IV fluid rate to match the urine output without an order

Answer: b — Large volumes of dilute urine with thirst after pituitary surgery suggest arginine vasopressin deficiency; the nurse reports and expects sodium and osmolality checks to guide treatment (section 23.5). Restricting fluid (a) or delaying drinking (c) risks dehydration and hypernatremia. Changing IV fluids without an order (d) is outside the nurse's authority.

34. [CORE] A patient with small cell lung cancer has a sodium of 128 mmol/L, moist mucous membranes, no edema and concentrated urine. The patient has no symptoms. Which treatment should the nurse anticipate first?

a. A large IV bolus of 0.9% sodium chloride
b. Oral desmopressin at bedtime
c. Fluid restriction with daily weights and intake and output
d. Rapid hypertonic saline infusion given on the general medical unit

Answer: c — This picture fits SIADH, and fluid restriction is the first-line treatment for moderate or profound hyponatremia from SIADH when there are no severe symptoms (section 23.5). Isotonic saline (a) treats low volume, but this patient is euvolemic. Desmopressin (b) would cause more water retention. Hypertonic saline (d) is reserved for severe or moderately severe symptoms and is given in a monitored setting within safe limits (Chapter 3).

35. [CORE] A patient with arginine vasopressin deficiency is starting desmopressin at home. Which statement shows the patient understands the teaching?

a. "I'll call my clinic if I get a bad headache, nausea or sudden weight gain."
b. "I should drink as much water as I possibly can every day to keep my kidneys well flushed."
c. "This medicine will also work if my kidney problem from the lithium I take gets any worse."
d. "I can skip doses whenever I'm busy, because missing one is never a problem."

Answer: a — Hyponatremia from water retention is desmopressin's most serious adverse effect, and headache, nausea, vomiting, weight gain or confusion are warning signs (section 23.5). Drinking as much as possible (b) increases that risk. Desmopressin does not work for arginine vasopressin resistance, such as that caused by lithium (c). Missed doses can cause dangerous dehydration, especially when the patient cannot drink (d).

36. [CORE] An RPN in a long-term care home finds a resident with Addison disease vomiting, confused and hypotensive. The resident has an emergency hydrocortisone injection kit with a written order for IM use when vomiting. Which action is appropriate?

a. Wait for the physician's next scheduled visit before giving any medication
b. Give the resident's oral hydrocortisone with sips of water and recheck in 2 hours
c. Ask the personal support worker to give the injection while the RPN calls the NP
d. Give the IM hydrocortisone under the order, call 9-1-1 and report to the NP

Answer: d — Administering a substance by injection is a controlled act authorized to RPNs with an order; this resident's order covers the situation, and adrenal crisis needs immediate treatment and transfer (section 23.5, Scope in Practice box). Waiting (a) delays life-saving treatment. Oral medication (b) will not stay down. Asking the personal support worker to inject (c) is not appropriate: an emergency injection for an unstable resident is not a routine activity of living, no delegation is in place, and the RPN holds the order and the competence to act.

37. [CORE] An RPN on a surgical unit is caring for a patient after pituitary surgery. Over 2 hours, the patient's urine output rises sharply and the patient becomes drowsy and difficult to rouse. What should the RPN do?

a. Continue the assessment plan and document the change at the end of the shift
b. Report to the RN at once and stay with the patient, whose needs have changed
c. Encourage the patient to drink a full jug of water before reassessing
d. Hold the next dose of hydrocortisone until the patient is more alert

Answer: b — A deteriorating patient needs immediate escalation, and the RPN consults the RN when a patient's needs change; drowsiness may prevent the patient from drinking and lead to hypernatremia (section 23.5). Delaying (a) is unsafe. A drowsy patient may not swallow safely (c). Holding hydrocortisone (d) risks adrenal insufficiency.

38. [RN] A patient 2 days after pituitary surgery has passed 5 L of urine in 24 hours. Results: sodium 151 mmol/L, serum osmolality 310 mOsm/kg, urine osmolality 120 mOsm/kg. Which interpretation is correct?

a. SIADH, because the urine is too concentrated for the patient's serum osmolality

b. Very high water intake, because the serum sodium is low and the urine maximally dilute

c. Arginine vasopressin deficiency, because the urine is dilute despite high serum osmolality

d. Normal postoperative diuresis of IV fluids, because the results are within expected ranges

Answer: c — Dilute urine with a high serum sodium and osmolality means the kidneys are not conserving water as they should, which fits arginine vasopressin deficiency (section 23.5, Going Deeper box). SIADH (a) shows concentrated urine with low serum osmolality. Very high water intake (b) lowers sodium, but this sodium is high. Diuresis of IV fluids (d) would not raise sodium to 151 mmol/L.

39. [RN] A patient with known Addison disease arrives with blood pressure 78/44 mm Hg, sodium 126 mmol/L, potassium 5.9 mmol/L and glucose 3.2 mmol/L. Which set of orders should the RN carry out first?

a. Fludrocortisone by mouth and a low-sodium diet

b. Cortisol and ACTH levels, then a corticotropin stimulation test before starting any treatment

c. Oral potassium binder and repeat electrolytes in 6 hours

d. Hydrocortisone 100 mg IV, 1 L isotonic saline in the first hour, and glucose treatment

Answer: d — Adrenal crisis is treated at once with hydrocortisone 100 mg IV or IM and rapid isotonic saline, with monitoring of glucose and electrolytes; the low glucose also needs treatment (section 23.4). Fludrocortisone (a) is not emergency treatment, and salt is never restricted in primary disease. Tests (b) must not delay treatment. A potassium binder alone (c) ignores shock, the immediate threat; potassium is monitored while hydrocortisone and fluids are given.

40. [RN] A patient is scheduled for adrenalectomy for a pheochromocytoma in 2 weeks. Which preoperative plan should the RN expect?

a. An alpha-adrenergic blocker for 7 to 14 days with a high-sodium diet and extra fluids

b. A beta-blocker alone, started today, to control the heart rate before surgery

c. Fluid restriction and a low-sodium diet to keep blood pressure down

d. No medications before surgery, because removing the tumour will correct the blood pressure

Answer: a — The Endocrine Society guideline makes alpha-adrenergic blockers the first choice and recommends 7 to 14 days of preoperative treatment, with a high-sodium diet and fluids, to bring blood pressure and heart rate to normal (section 23.4). Beta-blockers are among the drugs that can precipitate a pheochromocytoma crisis, so a beta-blocker alone (b) is unsafe. Restricting fluid and sodium (c) works against restoring volume before surgery. Going without blockade (d) risks severe blood pressure swings during surgery.

References

Adler, G. K., Stowasser, M., Correa, R. R., Khan, N., Kline, G., McGowan, M. J., Mulatero, P., Murad, M. H., Touyz, R. M., Vaidya, A., Williams, T. A., Yang, J., Young, W. F., Zennaro, M.-C., & Brito, J. P. (2025). Primary aldosteronism: An Endocrine Society clinical practice guideline. *The Journal of Clinical Endocrinology & Metabolism, 110*(9), 2453–2495. https://doi.org/10.1210/clinem/dgaf284

Arima, H., Cheetham, T., Christ-Crain, M., Cooper, D., Gurnell, M., Drummond, J. B., Levy, M., McCormack, A. I., Verbalis, J., Newell-Price, J., & Wass, J. A. H. (2022). Changing the name of diabetes insipidus: A position statement of The Working Group for Renaming Diabetes Insipidus. *Endocrine Connections, 11*(11), Article e220378. https://doi.org/10.1530/EC-22-0378

Arlt, W., & Society for Endocrinology Clinical Committee. (2016). Society for Endocrinology endocrine emergency guidance: Emergency management of acute adrenal insufficiency (adrenal crisis) in adult patients. *Endocrine Connections, 5*(5), G1–G3. https://doi.org/10.1530/EC-16-0054

Baldeweg, S. E., Ball, S., Brooke, A., Gleeson, H. K., Levy, M. J., Prentice, M., Wass, J., & Society for Endocrinology Clinical Committee. (2018). Society for Endocrinology clinical guidance: Inpatient management of cranial diabetes insipidus. *Endocrine Connections, 7*(7), G8–G11. https://doi.org/10.1530/EC-18-0154

Bausch Health, Canada Inc. (2019). *Carbolith (lithium carbonate capsules USP) product monograph*. https://pdf.hres.ca/dpd_pm/00051552.PDF

Beuschlein, F., Else, T., Bancos, I., Hahner, S., Hamidi, O., van Hulsteijn, L., Husebye, E. S., Karavitaki, N., Prete, A., Vaidya, A., Yedinak, C., & Dekkers, O. M. (2024). European Society of Endocrinology and Endocrine Society joint clinical guideline: Diagnosis and therapy of glucocorticoid-induced adrenal insufficiency. *European Journal of Endocrinology, 190*(5), G25–G51. https://doi.org/10.1093/ejendo/lvae029

BGP Pharma ULC. (2024). *Synthroid (levothyroxine sodium tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00077400.PDF

Bilezikian, J. P., Khan, A. A., Silverberg, S. J., El-Hajj Fuleihan, G., Marcocci, C., Minisola, S., Perrier, N., Sitges-Serra, A., Thakker, R. V., Guyatt, G., Mannstadt, M., Potts, J. T., Clarke, B. L., & Brandi, M. L. (2022). Evaluation and management of primary hyperparathyroidism: Summary statement and guidelines from the Fifth International Workshop. *Journal of Bone and Mineral Research, 37*(11), 2293–2314. https://doi.org/10.1002/jbmr.4677

Bornstein, S. R., Allolio, B., Arlt, W., Barthel, A., Don-Wauchope, A., Hammer, G. D., Husebye, E. S., Merke, D. P., Murad, M. H., Stratakis, C. A., & Torpy, D. J. (2016). Diagnosis and treatment of primary adrenal insufficiency: An Endocrine Society clinical practice guideline. *The Journal of Clinical Endocrinology & Metabolism, 101*(2), 364–389. https://doi.org/10.1210/jc.2015-1710

Burch, H. B., Perros, P., Bednarczuk, T., Cooper, D. S., Dolman, P. J., Leung, A. M., Mombaerts, I., Salvi, M., & Stan, M. N. (2022). Management of thyroid eye disease: A consensus statement by the American Thyroid Association and the European Thyroid Association. *Thyroid, 32*(12), 1439–1470. https://doi.org/10.1089/thy.2022.0251

Cambridge University Hospitals NHS Foundation Trust. (2026). *Going home following removal of a pituitary tumour* (Version 5) [Patient information]. https://www.cuh.nhs.uk/patient-information/going-home-following-removal-of-a-pituitary-tumour/

Canadian Cancer Society. (2026). *Thyroid cancer statistics*. https://cancer.ca/en/cancer-information/cancer-types/thyroid/statistics

Canadian Cancer Society. (n.d.). *Survival statistics for thyroid cancer*. Retrieved October 26, 2026, from https://cancer.ca/en/cancer-information/cancer-types/thyroid/prognosis-and-survival/survival-statistics

Choosing Wisely Canada. (n.d.). *Thyroid function tests (TSH, fT4, fT3)* [Test description]. https://choosingwiselycanada.org/wp-content/uploads/2022/10/TSHfT3fT4.pdf

College of Nurses of Ontario. (2025a). *An introduction to the Nursing Act, 1991* (Pub. No. 41064). https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41064_fsnursingact.pdf

College of Nurses of Ontario. (2025b). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

College of Nurses of Ontario. (n.d.). *Understanding orders, directives and delegation*. https://www.cno.org/standards-learning/practice-support/practice-support-faqs/understanding-orders-directives-and-delegation

Demers, A. A., Saint-Jacques, N., Ellison, L., Brenner, D., Fitzgerald, N., Aziz, S., & Turner, D. (2022). Update on cancer incidence trends in Canada, 1984 to 2017. *Health Promotion and Chronic Disease Prevention in Canada, 42*(7), 301–305. https://doi.org/10.24095/hpcdp.42.7.04

Elbuluk, N., Saizan, A. L., Mora Hurtado, A. C., Hamilton, T., & Kang, S. (2025). Differences in clinical features and risk factors for striae distensae in Black and White women. *Archives of Dermatological Research, 317*(1), Article 592. https://doi.org/10.1007/s00403-025-04050-z

Endocrine Society. (2014, October 30). *Experts recommend tumor removal as first-line treatment for acromegaly* [News release]. https://support.endocrine.org/news-and-advocacy/news-room/2014/experts-recommend-tumor-removal-as-first-line-treatment-for-acromegaly

Ferring Inc. (2019). *DDAVP Spray and DDAVP Rhinyle (desmopressin acetate nasal spray and nasal solution) product monograph*. https://www.ferring.ca/media/1226/ddavp-spray-rhinyle-pm-en_24may2019.pdf

Garber, J. R., Cobin, R. H., Gharib, H., Hennessey, J. V., Klein, I., Mechanick, J. I., Pessah-Pollack, R., Singer, P. A., & Woeber, K. A. (2012). Clinical practice guidelines for hypothyroidism in adults: Cosponsored by the American Association of Clinical Endocrinologists and the American Thyroid Association. *Endocrine Practice, 18*(6), 988–1028. https://doi.org/10.4158/EP12280.GL

Haugen, B. R., Alexander, E. K., Bible, K. C., Doherty, G. M., Mandel, S. J., Nikiforov, Y. E., Pacini, F., Randolph, G. W., Sawka, A. M., Schlumberger, M., Schuff, K. G., Sherman, S. I., Sosa, J. A., Steward, D. L., Tuttle, R. M., & Wartofsky, L. (2016). 2015 American Thyroid Association management guidelines for adult patients with thyroid nodules and differentiated thyroid cancer. *Thyroid, 26*(1), 1–133. https://doi.org/10.1089/thy.2015.0020

Hypertension Canada. (n.d.). *XVIII. Assessment for endocrine hypertension* [Clinical practice guidelines]. Retrieved October 26, 2026, from https://hypertension.ca/guidelines/diagnosis-assessment/xviii-assessment-for-endocrine-hypertension/

Iliff, H. A., El-Boghdadly, K., Ahmad, I., Davis, J., Harris, A., Khan, S., Lan-Pak-Kee, V., O'Connor, J., Powell, L., Rees, G., & Tatla, T. S. (2022). Management of haematoma after thyroid surgery: Systematic review and multidisciplinary consensus guidelines from the Difficult Airway Society, the British Association of Endocrine and Thyroid Surgeons and the British Association of Otorhinolaryngology, Head and Neck Surgery. *Anaesthesia, 77*(1), 82–95. https://doi.org/10.1111/anae.15585

Iliff, H. A., El-Boghdadly, K., Davis, J., Lan-Pak-Kee, V., & Powell, L. (Eds.). (2021). *Management of haematoma following thyroid surgery: Supporting resources to aid implementing guidance* (Version 1.0). Difficult Airway Society. https://das.uk.com/wp-content/uploads/2024/07/Supporting-Information-Appendix-S3_R1.pdf

Khan, A. A., Bilezikian, J. P., Brandi, M. L., Clarke, B. L., Gittoes, N. J., Pasieka, J. L., Rejnmark, L., Shoback, D. M., Potts, J. T., Guyatt, G. H., & Mannstadt, M. (2022). Evaluation and management of hypoparathyroidism summary statement and guidelines from the Second International Workshop. *Journal of Bone and Mineral Research, 37*(12), 2568–2585. https://doi.org/10.1002/jbmr.4691

Knight Therapeutics Inc. (2025). *Tapazole (methimazole tablets) product monograph*. https://pdf.hres.ca/dpd_pm/00082875.PDF

Knight Therapeutics Inc. (2026). *Florinef (fludrocortisone acetate tablets) product monograph*. https://pdf.hres.ca/dpd_pm/00083992.PDF

Knight Therapeutics. (2025). *Tapazole (methimazole tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00082874.PDF

Krueger, P. D., Raina, P., Braun, E. A., Patterson, C., & Chambers, L. W. (2001). Prevalence and risk factors of hypothyroidism: Findings from the Canadian Study of Health and Aging. *Canadian Journal on Aging, 20*(1), 127–135. https://doi.org/10.1017/S0714980800012174

Lenders, J. W. M., Duh, Q.-Y., Eisenhofer, G., Gimenez-Roqueplo, A.-P., Grebe, S. K. G., Murad, M. H., Naruse, M., Pacak, K., & Young, W. F., Jr. (2014). Pheochromocytoma and paraganglioma: An Endocrine Society clinical practice guideline. *The Journal of Clinical Endocrinology & Metabolism, 99*(6), 1915–1942. https://doi.org/10.1210/jc.2014-1498

Nieman, L. K., Biller, B. M. K., Findling, J. W., Newell-Price, J., Savage, M. O., Stewart, P. M., & Montori, V. M. (2008). The diagnosis of Cushing's syndrome: An Endocrine Society clinical practice guideline. *The Journal of Clinical Endocrinology & Metabolism, 93*(5), 1526–1540. https://doi.org/10.1210/jc.2008-0125

Pelsma, I. C. M., Verstegen, M. J. T., de Vries, F., Notting, I. C., Broekman, M. L. D., van Furth, W. R., Biermasz, N. R., & Pereira, A. M. (2020). Quality of care evaluation in non-functioning pituitary adenoma with chiasm compression: Visual outcomes and timing of intervention clinical recommendations based on a systematic literature review and cohort study. *Pituitary, 23*(4), 417–429. https://doi.org/10.1007/s11102-020-01044-0

Petersenn, S., Fleseriu, M., Casanueva, F. F., Giustina, A., Biermasz, N., Biller, B. M. K., Bronstein, M., Chanson, P., Fukuoka, H., Gadelha, M., Greenman, Y., Gurnell, M., Ho, K. K. Y., Honegger, J., Ioachimescu, A. G., Kaiser, U. B., Karavitaki, N., Katznelson, L., Lodish, M., … Melmed, S. (2023). Diagnosis and management of prolactin-secreting pituitary adenomas: A Pituitary Society international consensus statement. *Nature Reviews Endocrinology, 19*(12), 722–740. https://doi.org/10.1038/s41574-023-00886-5

Pfizer Canada ULC. (2019). *Cytomel (liothyronine sodium tablets) product monograph*. https://webfiles.pfizer.com/file/667f786f-d0d8-45df-bff9-e8d7c05b8434

Pfizer Canada ULC. (2025). *Solu-Cortef (hydrocortisone sodium succinate for injection) product monograph*. https://webfiles.pfizer.com/file/27aaa750-8d70-4547-aed8-2cda44dfdd8f

Phebra Canada. (2021). *Propylthiouracil tablets* [Product monograph]. https://pdf.hres.ca/dpd_pm/00063842.PDF

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Ross, D. S., Burch, H. B., Cooper, D. S., Greenlee, M. C., Laurberg, P., Maia, A. L., Rivkees, S. A., Samuels, M., Sosa, J. A., Stan, M. N., & Walter, M. A. (2016). 2016 American Thyroid Association guidelines for diagnosis and management of hyperthyroidism and other causes of thyrotoxicosis. *Thyroid, 26*(10), 1343–1421. https://doi.org/10.1089/thy.2016.0229

Satoh, T., Isozaki, O., Suzuki, A., Wakino, S., Iburi, T., Tsuboi, K., Kanamoto, N., Otani, H., Furukawa, Y., Teramukai, S., & Akamizu, T. (2016). 2016 guidelines for the management of thyroid storm from the Japan Thyroid Association and Japan Endocrine Society (first edition). *Endocrine Journal, 63*(12), 1025–1064. https://doi.org/10.1507/endocrj.EJ16-0336

Society for Endocrinology. (2022). *Emergency management of severe and moderately severely symptomatic hyponatraemia in adult patients* [Endocrine emergency guidance; S. Ball, J. Barth, M. Levy, & Society for Endocrinology Clinical Committee]. https://www.endocrinology.org/media/xhrhxhxm/emergency-management-of-severe-and-moderately-severely-symptomatic-hyponatraemia-in-adult-patients-2022.pdf

Society for Endocrinology. (n.d.). *Adrenal crisis*. Retrieved October 26, 2026, from https://endocrinology.org/adrenal-crisis

Spasovski, G., Vanholder, R., Allolio, B., Annane, D., Ball, S., Bichet, D., Decaux, G., Fenske, W., Hoorn, E. J., Ichai, C., Joannidis, M., Soupart, A., Zietse, R., Haller, M., van der Veer, S., Van Biesen, W., & Nagler, E. (2014). Clinical practice guideline on diagnosis and treatment of hyponatraemia. *European Journal of Endocrinology, 170*(3), G1–G47. https://doi.org/10.1530/EJE-13-1020

University of Ottawa, Faculty of Medicine. (2022). *Lab results* [Reference values]. https://www.uottawa.ca/faculty-medicine/sites/g/files/bhrskd401/files/2023-05/Lab%20Results%20Template_2022_final-EN.pdf

Ylli, D., Klubo-Gwiezdzinska, J., & Wartofsky, L. (2019). Thyroid emergencies. *Polish Archives of Internal Medicine, 129*(7–8), 526–534. https://doi.org/10.20452/pamw.14876

Yun, G., Baek, S. H., & Kim, S. (2023). Evaluation and management of hypernatremia in adults: Clinical perspectives. *Korean Journal of Internal Medicine, 38*(3), 290–302. https://doi.org/10.3904/kjim.2022.346

VI Gastrointestinal, Hepatic, Biliary & Pancreatic Care

UNIT CLINICAL SCOPE & INTEGRATION

Presents evidence-informed nursing care for upper and lower gastrointestinal disorders, enteral and parenteral nutrition, bariatric surgery, peptic ulcer disease, gastrointestinal bleeding, inflammatory bowel disease, bowel obstruction, ostomy care, cirrhosis, portal hypertension, viral and autoimmune hepatitis, cholelithiasis, and acute and chronic pancreatitis.

Contents of UNIT VI

Chapter	Chapter Title	Visual Assets	Page
Chapter 24	Upper Gastrointestinal Disorders and Nutrition	6 Figs • 4 Tbls	p. 696
Chapter 25	Lower Gastrointestinal Disorders	6 Figs • 4 Tbls	p. 727
Chapter 26	Liver, Biliary and Pancreatic Disorders	9 Figs • 4 Tbls	p. 759

24 Upper Gastrointestinal Disorders and Nutrition

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Screen adults for malnutrition and refeeding risk using Canadian tools, and recognize the signs and causes of malnutrition.
2. Give enteral and parenteral nutrition safely, including feeding tube placement verification and medications by tube.
3. Recognize dysphagia, support screening and assessment, and apply texture-modified diets using the IDDSI framework.
4. Care for adults with GERD, gastritis and peptic ulcer disease, including H. pylori treatment and safe use and deprescribing of acid-suppressing drugs.
5. Recognize an upper GI bleed early on a range of skin tones, escalate it, and support resuscitation and endoscopy using the CJMM.
6. Provide respectful, weight-inclusive care for people living with obesity, and care for patients before and after bariatric surgery.
7. Distinguish RN and RPN roles in feeding tube and nutrition care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 5	Clinician; Scholar	Foundations of Practice
4, 6	Educator; Advocate	Foundations of Practice; Ethical Practice
7	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

Illness often takes away eating first. Pain, nausea, a sore mouth, trouble swallowing, fasting for tests and the hospital routine can all cut what a patient takes in, and many adults are already undernourished when they arrive. Nurses are often the first to notice. They see the half-eaten tray, the loose denture, the cough during a drink of water and the weight that has dropped since the last admission. Nurses also give most of the nutrition that does not come on a plate, through feeding tubes and intravenous lines, and they are the ones who check that a tube is in the right place before anything goes down it.

This chapter is the book's home for nutrition and for disorders of the upper gastrointestinal (GI) tract in adults. Section 24.1 reviews digestion and explains how to screen for and recognize malnutrition with Canadian tools. Section 24.2 covers enteral nutrition through feeding tubes, including how placement is confirmed and how medications are given by tube, and parenteral nutrition given into a vein. Section 24.3 deals with dysphagia and texture-modified diets. The second half of the chapter turns to gastroesophageal reflux disease, gastritis and peptic ulcer disease (24.4), upper GI bleeding (24.5), and obesity and bariatric surgery (24.6).

The chapter builds on earlier ones. Scope of practice, the Clinical Judgment Measurement Model (CJMM) and consent are taught in Chapter 1 (sections 1.3 to 1.5), and weight stigma, food insecurity and cultural safety in Chapter 2. Phosphate, potassium and magnesium are explained in Chapter 3, infection prevention and control in Chapter 4, and early warning scores and rapid response in Chapter 6. Older adults and deprescribing are covered in Chapter 8, palliative nutrition and hydration in Chapter 10 and aspiration pneumonia in Chapter 13. Lower GI disorders are in Chapter 25, and swallowing screening after stroke is taught in Chapter 31.

24.1 Digestion and Nutrition Assessment

The Upper GI Tract in Brief

The upper GI tract runs from the mouth to the duodenum, the first part of the small intestine (Figure 24.1). Chewing and saliva soften food and begin digestion. The tongue gathers the food into a soft, cohesive mass called a **bolus** and pushes it to the back of the mouth. Swallowing then becomes a fast reflex. The soft palate rises to close off the nose, the larynx lifts, the epiglottis folds over the airway and breathing pauses for a moment while the bolus passes into the esophagus. Waves of muscle contraction, called **peristalsis**, carry it down to the stomach. The lower esophageal sphincter relaxes to let the bolus in and then closes to keep stomach contents from flowing back up (section 24.4).

The stomach stores and mixes food. Its lining secretes hydrochloric acid, which kills many microbes and starts protein digestion, along with the enzyme pepsin and intrinsic factor, which is needed to absorb vitamin B12 (section 20.2). Because acid can injure tissue, the stomach protects itself with a layer of mucus and bicarbonate, a rich blood supply and rapid repair of its lining, and prostaglandins support these defences. When the balance tips toward injury, as with *Helicobacter pylori* infection or nonsteroidal anti-inflammatory drugs (NSAIDs), gastritis and ulcers can follow (section 24.4).

The stomach releases its contents a little at a time into the duodenum, where bile and pancreatic enzymes continue digestion and bicarbonate neutralizes the acid. Most nutrients are absorbed farther along the small intestine (Chapter 25). This layout matters for tube feeding: the stomach acts as a reservoir, while the small intestine does not, so where a feeding tube ends shapes how feeds can be given (section 24.2).



Figure 24.1 The digestive system: the alimentary canal from mouth to anus and the accessory organs (salivary glands, liver, gallbladder and pancreas). (credit: Figure 23.2, "Components of the Digestive System," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Screening for Malnutrition

In this chapter, **malnutrition** means undernutrition: the body is not taking in or not using enough energy and nutrients, so it loses muscle and fat and its function declines. In a Canadian Malnutrition Task Force study of 1,015 adults admitted to medical and surgical units in 18 hospitals for at least 2 days between 2010 and 2013, 45% were malnourished at admission when assessed with Subjective Global Assessment (SGA; described below) (Allard et al., 2016; Eckert & Cahill, 2018).

Every adult admitted to hospital is screened. The **Canadian Nutrition Screening Tool (CNST)** is a two-question screen from the Canadian Malnutrition Task Force. It asks:

- Over the last six months, has the person lost weight without meaning to?
- For more than a week, has the person been eating less than they usually do?

Answering yes to both questions means the person is at nutrition risk. If the patient cannot answer, a family member or someone else who knows them well may answer for them. Weight that was lost and then regained does not count as weight loss (Eckert & Cahill, 2018). Any hospital staff member can ask the questions (Eckert & Cahill, 2018), and each hospital or unit decides whose job it is (Keller et al., 2018).

The CNST is the first step of the **Integrated Nutrition Pathway for Acute Care (INPAC)**, a Canadian pathway that hospitals adapt to their own routines (Keller et al., 2018). In brief:

- **Screen:** every patient is screened with the CNST on admission.
- **Classify:** patients at risk are assessed with **Subjective Global Assessment (SGA)**, a structured bedside assessment that sorts nutrition status by weight change, intake, symptoms, function and physical signs of muscle and fat loss.
- **Standard care for all:** the team removes barriers to eating and monitors intake. Eating half a meal or less is treated as low intake that needs action.
- **Advanced care:** patients who are eating poorly or are malnourished receive diet changes and other measures to boost intake, and move back to standard care once intake improves.
- **Specialized care:** patients with more severe malnutrition, or who do not improve, receive a comprehensive assessment and an individual plan overseen by the dietitian.
- **Weigh and plan ahead:** a weight on admission and at least weekly is the minimum, and nutrition is part of discharge planning (Keller et al., 2018).

Nurses carry much of this pathway. They remove barriers at mealtimes, such as an unopened container, a missing denture or pain, estimate how much of each tray was eaten and refer to the registered dietitian when screening or intake shows risk. Screening also starts a conversation about home: a person who cannot afford, reach or prepare enough food will lose ground after discharge (Chapter 2).

Signs and Causes of Malnutrition

Screening flags risk; it does not make a diagnosis. The **Global Leadership Initiative on Malnutrition (GLIM)** criteria, an international consensus, use two steps: screen with a validated tool such as the CNST, then confirm malnutrition when the person meets at least one phenotypic criterion (what the body shows) and at least one etiologic criterion (the cause). Severity is then graded as moderate or severe (Cederholm et al., 2019).

- **Phenotypic criteria:** unintended weight loss of more than 5% within six months or more than 10% over a longer period; a low body mass index (BMI), below 20 kg/m² under age 70 or below 22 kg/m² over age 70; or reduced muscle mass measured with a validated method.
- **Etiologic criteria:** reduced intake or absorption, such as eating half or less of energy needs for more than a week, any reduction for more than two weeks, or a chronic GI condition that limits absorption; or inflammation from acute illness, injury or chronic disease (Cederholm et al., 2019).

Most malnutrition in hospital has more than one cause. Illness and inflammation raise the body's needs and break down muscle, while appetite falls. Intake drops with nausea, pain, low mood, confusion, fatigue and missed meals around tests. Oral health matters: missing teeth, poorly fitting dentures and mouth pain make chewing hard (Alberta Health Services [AHS], 2022). Medications can add nausea, dry mouth or drowsiness. Swallowing problems (section 24.3) and conditions that limit absorption deepen the deficit, and social factors such as living alone shape what happens at home (Allard et al., 2016).

The nurse also looks for muscle loss: wasting at the temples, shoulders and thighs, a weak grip and slower walking. In the Canadian study, weaker handgrip was linked with a longer stay (Allard et al., 2016).

Weight history tells more than BMI alone. A single BMI says nothing about recent change, and a person in a larger body can lose a great deal of weight and muscle while their BMI stays in or above the usual range. This is why GLIM counts weight loss and muscle mass as well as low BMI (Cederholm et al., 2019). The nurse asks about usual weight and recent change and weighs the patient on admission and weekly.

Blood tests have a limited role. Serum albumin and prealbumin were long used as nutrition markers, but the American Society for Parenteral and Enteral Nutrition (ASPEN) now states that they mainly reflect inflammation. During illness the liver makes less of them and they shift out of the bloodstream, so levels fall whether or not the person is malnourished. They predict the risk of poor outcomes, but they should not be used to diagnose malnutrition or to stand in for muscle mass (Evans et al., 2021).

CANADIAN CONTEXT

Malnutrition in Canadian Hospitals

Much of what is known about malnutrition in Canadian hospitals comes from the Canadian Malnutrition Task Force. Its cohort study followed 1,015 adults admitted to medical and surgical units in 18 Canadian hospitals for at least 2 days, from 2010 to 2013. Assessed with SGA, 45% were malnourished on arrival (Allard et al., 2016).

- **Who:** malnutrition at admission was linked with having many chronic conditions, living alone and relying on grown children to buy groceries (Allard et al., 2016).
- **Length of stay:** malnutrition at admission was linked with a longer stay, independent of other factors. A weaker handgrip and eating less than half of meals in hospital were also linked with longer stays (Allard et al., 2016).
- **Cost:** a CMAJ summary of this Canadian work reports stays 34% to 53% longer and costs 31% to 55% higher for malnourished patients than for well-nourished ones (Eckert & Cahill, 2018).
- **Response:** the task force built INPAC, a pathway that hospitals tailor to their own routines. Who screens, how meal intake is recorded and when weights are taken are decided locally (Keller et al., 2018).

For nurses, the message is that malnutrition is common, is often present before the first hospital meal, and can be found early with two screening questions, a look at the meal tray and a weekly weight.

GOING DEEPER

Refeeding Syndrome

Required for RN students; optional for PN students.

Refeeding syndrome is a fall in blood phosphate, potassium or magnesium, sometimes with thiamine deficiency, after nutrition is started or sharply increased in an undernourished person. ASPEN's consensus defines it as a fall of 10% or more in any of these electrolytes within five days, graded mild, moderate or severe by the size of the fall and any organ dysfunction (da Silva et al., 2020).

- **Mechanism:** carbohydrate triggers insulin release, which moves phosphate and potassium into cells; magnesium also falls, and thiamine demand rises. Body stores are already low, so levels can drop quickly even if normal before feeding (Chapter 3).
- **Who is at risk:** very low BMI, recent unintended weight loss, little or no intake for days, low electrolytes before feeding, loss of fat and muscle, and conditions such as eating disorders, long-term heavy alcohol or other drug use, malabsorption, cancer, previous bariatric surgery, and food insecurity or homelessness.
- **Why it matters:** low phosphate weakens the breathing muscles and the heart; thiamine deficiency can cause neurologic signs and heart dysfunction.
- **Prevention and monitoring:** check potassium, magnesium and phosphate before feeding; give thiamine before feeding or dextrose-containing IV fluids; start calories low and increase them gradually; in high-risk patients, check electrolytes every 12 hours for 3 days; take vital signs every 4 hours for the first 24 hours; and record daily weight and intake and output (da Silva et al., 2020). The nurse reports falling electrolytes promptly.

24.2 Enteral and Parenteral Nutrition

Feeding Tubes

Enteral nutrition means feeding into the GI tract. In this chapter, it refers to liquid formula given through a feeding tube to a person whose gut can digest and absorb but who cannot take enough by mouth, or cannot swallow safely. Common reasons include dysphagia after stroke (section 24.3), head and neck cancer, and critical illness. **Parenteral nutrition**, given into a vein, is used when the gut cannot be used or cannot meet the person's needs (see Parenteral Nutrition, below).

Feeding tubes are named by where they enter and where their tip ends (Table 24.1). A **nasogastric (NG) tube** passes through the nose and esophagus into the stomach (Figure 24.2). Nasal tubes, including those that end in the small intestine, are meant for short-term feeding. When tube feeding is expected to last longer, the team discusses a tube placed through the abdominal wall with the patient and family. A **gastrostomy tube** enters the stomach this way; a **percutaneous endoscopic gastrostomy (PEG)** is a gastrostomy placed with the help of an endoscope passed through the mouth (Figure 24.3). A **jejunostomy tube** enters the jejunum,

the middle part of the small intestine. Because the stomach acts as a reservoir, gastric tubes can take continuous, intermittent or bolus feeds; tubes that end in the small intestine usually need a slow, continuous feed by pump.

Choosing a tube, and deciding whether to feed by tube at all, is a shared decision. It weighs the person's goals, prognosis and wishes (Chapter 1, section 1.5; Chapter 10 for palliative nutrition). After a stroke, for example, the decision to start tube feeding is made as early as possible, usually within the first three days of admission, with the patient, family and team (Heart and Stroke Foundation of Canada, 2019).

Figure 24.2 Supplies gathered for nasogastric tube insertion, including the tube, lubricant, a securement device, pH strips, a large syringe and water for the patient to sip. Placement is confirmed before the tube is first used, as described later in this section. (credit: “Gather supplies” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 24.3 Equipment for placing a percutaneous endoscopic gastrostomy (PEG) tube: the tube with its internal disc (bumper), which holds it inside the stomach, an introducer needle and a guidewire. (credit: “PEG tube kit” by Gilo1969/Wikimedia Commons, CC BY-SA 3.0)

Table 24.1 Enteral feeding tubes compared (ASPEN, 2014; Lemyze, 2010; Nova Scotia Health Library, 2026)

Tube	Route and tip position	Usual use	Nursing points
Nasogastric (NG)	Through the nose and esophagus; tip in the stomach	Short-term feeding, medications and fluids	Radiograph before first use of a blindly placed tube; check the external length mark and other bedside checks before each use; protect the nostril from pressure
Nasojejunal (NJ)	Through the nose, past the stomach; tip in the jejunum	Short-term feeding when gastric feeding is not tolerated or aspiration risk is high	Placement confirmed by imaging; usually a continuous feed by pump; check medications with the pharmacist

Tube	Route and tip position	Usual use	Nursing points
Gastrostomy, including PEG	Through the abdominal wall into the stomach	Longer-term feeding; may be a low-profile "button"	Inspect and clean the site daily; watch for leakage, redness, pain or a tube that has moved; report a dislodged tube at once per policy
Jejunostomy (or gastrojejunostomy)	Through the abdominal wall; tip in the jejunum	Longer-term feeding when the stomach cannot be used	Continuous feed by pump; small bore blocks easily, so flush carefully; site care as for a gastrostomy

Confirming Placement

A tube passed blindly at the bedside can slip into the trachea instead of the esophagus. A tube in the airway can pierce the lung and cause a collapsed lung (pneumothorax), and formula or medication given through it can cause aspiration pneumonia; these complications can be life-threatening. Risk is highest in patients with a weak cough or gag reflex or reduced consciousness, and the absence of coughing during insertion does not prove the tube is in the stomach (Lemyze, 2010; Lortie & Charbonney, 2016).

First use. Canadian sources describe a radiograph as the reference standard. A tube placed blindly is confirmed by radiograph before any feed or medication is given, with no exceptions (Lortie & Charbonney, 2016). The nurse waits for confirmation that the tip is in the intended position before using the tube.

Every use after that. Tubes can move with coughing, vomiting, suctioning or a confused patient's pulling. After radiograph confirmation, the nurse records the centimetre mark at the nostril and compares it with the documented mark every 12 hours, as needed and before use (Nova Scotia Health Library, 2026). Tube position is checked at each initial assessment and before each feed or medication (ASPEN, 2014). Employer policy may add a pH test of fluid drawn back from the tube. Gastric fluid is usually acidic, often pH 5 or below, and is typically green or colourless (Lemyze, 2010). One Canadian provincial guide calls for pH testing before intermittent feeds, every 4 to 6 hours when a continuous feed can be paused, and at least 1 hour after medications (Nova Scotia Health Library, 2026).

pH has limits. Acid-suppressing drugs (section 24.4) raise gastric pH, so the test is of little use in patients taking them, and pH alone cannot always tell the stomach from the airway (Lemyze, 2010). Listening over the stomach while injecting air is not a valid check: similar sounds can be heard when the tube lies in the airway, the pleural space or the esophagus (Lemyze, 2010; Lortie & Charbonney, 2016).

When anything suggests the tube has moved, the nurse stops and does not use it. Warning signs include a mark that has changed, vomiting or retching, new coughing or breathing difficulty, or a pH that does not fit gastric placement. The nurse keeps the tube in place, secures it and reports to the prescriber; repeat imaging may be ordered. Employer policy sets which bedside checks are used, how often, and who may reinsert a tube (Scope in Practice box, this section).

CLINICAL SAFETY

Is the Tube in the Right Place?

A misplaced tube turns a routine feed into an emergency. Before anything goes down a nasal feeding tube, the nurse asks these questions.

- **Was placement confirmed after insertion?** A blindly placed tube needs radiograph confirmation before first use (Lortie & Charbonney, 2016). If the report is not back, the tube is not used.
- **Is the external mark where it should be?** The nurse compares the centimetre mark at the nostril with the documented mark (Nova Scotia Health Library, 2026).
- **Do the bedside checks fit gastric placement?** The nurse uses the checks that employer policy names, such as aspirate pH and appearance, and remembers that acid-suppressing drugs raise pH (Lemyze, 2010).
- **Has anything changed?** Vomiting, coughing fits, new breathing difficulty or falling oxygen saturation after insertion or during a feed are red flags.
- **Am I relying on a check that does not work?** Listening for air injected into the tube does not show where the tip lies and is never used to confirm placement (Lemyze, 2010).

If any answer is uncertain, the nurse holds the feed and medications, keeps the tube secured and reports to the prescriber. A patient with new respiratory distress needs urgent assessment and escalation (Chapter 6).

Giving Tube Feeds Safely

Formula can be given in three main ways. A **continuous feed** runs by pump over all or part of the day (Figure 24.4). An **intermittent feed** gives a set volume several times a day over a period of time. A **bolus feed** gives a volume by syringe over a short time, into the stomach only. Closed, ready-to-hang systems may hang for up to 24 hours, while formula poured into an open container may hang for up to 8 hours (ASPEN, 2014); employer policy may set shorter times.

Position is the simplest protection against aspiration, and lying flat is a known risk factor (Lemyze, 2010). The nurse keeps the head of the bed at 30 to 45 degrees during continuous feeds unless this is contraindicated, and for at least an hour after an intermittent feed (Nova Scotia Health Library, 2026). If the patient must lie flat for care, the feed is paused.

The nurse checks tolerance at each assessment. Abdominal distension or discomfort, nausea, vomiting, diarrhea and constipation are reported, along with stool pattern and intake and output. **Gastric residual volume (GRV)**, the volume of fluid drawn back from a gastric tube, was once checked routinely. In one Canadian provincial guide, routine GRV checks are no longer done unless ordered, and GRV is kept for patients who have other signs of intolerance (Nova Scotia Health Library, 2026). If a patient vomits, the nurse stops the feed, turns or sits the patient up and assesses breathing.

Water flushes keep the tube open and add to fluid intake. For adults who are not on a fluid restriction, ASPEN's nursing guidance calls for at least 30 mL of water before and after each intermittent feed (ASPEN, 2014). The prescriber or dietitian may order other flush volumes, especially for patients on fluid restrictions.

Figure 24.4 An enteral feeding pump with its feeding set. Enteral equipment is kept apart from IV lines, and ENFit connectors are designed so the two cannot be joined. (credit: "Enteral feeding pumps" by Ahmed Shawky Mohammedin, MD (Ashashyou)/Wikimedia Commons, CC BY-SA 3.0)

Formula belongs only in the GI tract. **ENFit** is a connector design for enteral equipment that does not fit IV or other non-enteral ports, to prevent misconnections (ASPEN, 2014). The nurse still traces every line from the patient to its source before connecting anything.

Skin care prevents harm. A nasal tube is secured without pressure on the nostril, and the skin is checked and the securement changed as policy directs. A gastrostomy or jejunostomy site is inspected daily for redness, swelling, drainage, leakage, pain or a tube that has moved. A tube that comes out is reported at once, as policy directs.

Medications by Feeding Tube

Medications are a common cause of blocked tubes. In about 15% of patients fed by tube, medications given through the tube block it (Institute for Safe Medication Practices Canada [ISMP Canada], 2013). Safe practice starts with the pharmacist.

- **Ask first.** Product monographs may say nothing about giving a drug by tube, so the nurse consults the pharmacist or another drug information source when unsure (ISMP Canada, 2013).
- **Do not assume a liquid is best.** Some liquid medications are thick or granular and block tubes readily (ISMP Canada, 2013).

Figure 24.5 A three-chamber parenteral nutrition bag. Amino acids, dextrose and lipid are kept in separate compartments until the seals between them are opened and the contents mixed, just before use. (credit: "Smofkabiven Zentral Bag" by Ibrahim Husain Meraj/Wikimedia Commons, CC BY-SA 4.0)

- **Never crush modified-release or enteric-coated drugs.** Extended-release, delayed-release and enteric-coated products, and drugs that irritate the mucosa, are not crushed (ISMP Canada, 2013). Beaded capsule contents are not given by tube (Nova Scotia Health Library, 2026). The prescriber and pharmacist choose another form or drug.
- **One at a time.** Each medication is prepared and given separately, never mixed with others and never added to the formula or flush bag (Nova Scotia Health Library, 2026).
- **Flush.** The nurse flushes with at least 15 mL of water before, between and after each medication (ASPEN, 2014).

Parenteral Nutrition

Parenteral nutrition provides dextrose, amino acids, lipid, electrolytes, vitamins, trace elements and water into a vein (Figure 24.5). It is a high-risk therapy. The patient should have a documented indication based on published guidelines (Ayers et al., 2014). Typical indications are a gut that does not work, such as with prolonged obstruction or severe malabsorption, or enteral feeding that cannot meet needs.

Most parenteral nutrition is concentrated. It is given through a **central venous access device**, such as a peripherally inserted central catheter (PICC), whose tip lies in a large central vein where blood flow dilutes the solution. A less concentrated formula can be given peripherally for a short time. The solution's osmolarity must suit the route (Ayers et al., 2014).

Safe administration includes these steps:

- **Check the bag against the order.** This includes the patient, the contents, the rate and the in-line filter named on the label (Ayers et al., 2014).
- **Give it safely.** It runs by infusion pump, through the line and filter that policy names. Employer policy usually reserves one lumen of the central line for parenteral nutrition and limits what else may run with it.
- **Prevent infection.** Line care, dressing changes and tubing changes follow infection-prevention policy (Chapter 4). A new fever or chills in a patient with a central line is reported at once.
- **Monitor.** Capillary glucose, electrolytes, weight and intake and output are monitored as ordered, because the dextrose load can cause hyperglycemia and the electrolyte shifts described in the Going Deeper box in section 24.1. ASPEN counts IV dextrose toward the calorie limits for patients at refeeding risk (da Silva et al., 2020).
- **Change only by order.** The nurse does not stop the infusion, change its rate or speed it up to make up lost time. Rate changes, interruptions and stopping follow the prescriber's order and employer policy, including any glucose checks the policy requires when the infusion is interrupted or stopped.

SCOPE IN PRACTICE

Feeding Tubes and the Nurse

In Ontario, putting an instrument "beyond the point in the nasal passages where they normally narrow" and putting an instrument "into an artificial opening into the body" are controlled acts authorized to nursing (College of Nurses of Ontario [CNO], 2025). Inserting a nasogastric tube is the first; reinserting a gastrostomy tube through an established stoma is the second.

- **Authority:** RNs and RPNs may perform these acts with an order from an authorized prescriber or a directive. Nurses cannot initiate controlled acts in public hospitals (Chapter 1, section 1.3). Starting, changing or stopping tube feeds also follows an order, and the dietitian usually recommends the formula and rate.
- **Competence:** the nurse must have the knowledge, skill and judgment to perform the act safely and to manage what follows (CNO, 2025). This includes confirming tube placement as section 24.2 describes and recognizing a misplaced tube.
- **Context:** employer policy decides who may replace a dislodged gastrostomy tube, after how long the stoma has healed, and with which equipment. Employers can limit a nurse's scope but cannot expand it (CNO, 2025). Policies often direct a dislodged tube in a new stoma, or in an unstable patient, to the surgical or interventional team.

Any nurse who finds a dislodged tube, coughing or breathing changes during a feed, or new abdominal pain stops the feed and escalates. Rules differ by province or territory and by employer, so nurses outside Ontario check their own regulator's standards.

24.3 Dysphagia and Texture-Modified Diets

Recognizing Dysphagia

Dysphagia is a swallowing disorder that can involve the mouth, the throat (pharynx), the esophagus or the junction with the stomach (American Speech-Language-Hearing Association [ASHA], n.d.). It is common after stroke and in other neurologic diseases, in head and neck cancer, and in frail older adults. Its consequences are serious: malnutrition, dehydration, aspiration pneumonia, choking and death (ASHA, n.d.).

Aspiration is the entry of food, fluid, saliva or stomach contents into the airway below the vocal folds. Nurses see patients eat and drink more often than anyone else on the team, so they are often first to notice the signs of dysphagia (ASHA, n.d.):

- coughing or clearing the throat while eating or drinking, or soon after;
- a voice that sounds wet or gurgly with or after meals and drinks;
- drooling or trouble controlling saliva or food in the mouth, such as food left in the cheeks;
- needing extra time to chew or swallow, so meals take much longer;
- weight loss, malnutrition or dehydration because the person cannot eat enough;
- repeated chest infections or aspiration pneumonia, sometimes with fever.

A cough is not a reliable alarm. In **silent aspiration**, material enters the airway with no cough or other obvious sign (ASHA, n.d.). Coughing can also occur without aspiration, so neither its presence nor its absence settles the question. For this reason, the nurse watches for later clues: a wet voice, a rising respiratory rate, new crackles, a falling oxygen saturation or a low-grade fever. These findings are reported promptly, because aspiration pneumonia can follow (Chapter 13).

Screening, Assessment and Diets

A **swallowing screen** is a brief pass-or-fail check that finds people who need a full assessment. Any trained member of the team, often the nurse, can do it with a validated protocol (ASHA, n.d.). After a stroke, people are screened before any oral intake, including medications, by a trained professional using a valid tool (Heart and Stroke Foundation of Canada, 2019; Chapter 31). A failed screen leads to a referral to the **speech-language pathologist (SLP)** (Heart and Stroke Foundation of Canada, 2019), and the person usually stays nothing by mouth, including oral medications, until assessed, as the plan directs. A passed screen does not remove all risk: no bedside screen has been shown to predict aspiration reliably (ASHA, n.d.).

The SLP leads the full assessment. It includes a clinical swallowing assessment and, for people at high risk, an instrumental study. These studies are a **videofluoroscopic swallowing study**, an X-ray of swallowing, or a **flexible endoscopic evaluation of swallowing**, which views the throat through a thin scope (ASHA, n.d.; Heart and Stroke Foundation of Canada, 2019). The SLP recommends food textures, drink thickness and swallowing strategies; the dietitian makes sure the diet meets nutritional needs.

A **texture-modified diet** changes the texture of food, the thickness of drinks, or both, to make swallowing safer. The **International Dysphagia Diet Standardisation Initiative (IDDSI)** framework gives these diets standard names and tests (Cichero et al., 2017). Some Canadian health authorities still use older diet names alongside it; Alberta Health Services, for example, has not fully moved

to IDDSI and maps its diet names onto IDDSI levels (AHS, 2022). The framework is a continuum of eight levels numbered 0 to 7, with drinks at levels 0 to 4 and foods at levels 3 to 7, each with a colour code and simple tests, such as a 10 mL syringe flow test for drinks and fork and spoon tests for foods (Cichero et al., 2017; International Dysphagia Diet Standardisation Initiative [IDDSI], 2026). Older names map onto it: "nectar-thick" fluids correspond to Level 2 and "honey-thick" to Level 3 (AHS, 2022). The levels are summarized here in this book's own words (Table 24.2); the framework and its detailed definitions belong to IDDSI and are released under a Creative Commons Attribution-ShareAlike licence (IDDSI, 2026).

Table 24.2 IDDSI drink and food levels in brief (IDDSI, 2026; Cichero et al., 2017)

Level	Name	What it is like	Example of who may need it
0	Thin (drinks)	Flows quickly, like water	A person who can manage all drinks safely
1	Slightly thick (drinks)	A little thicker than water; still flows through a straw	An adult who finds thin drinks move slightly too fast to control
2	Mildly thick (drinks)	Pours off a spoon and can be sipped, but flows more slowly than water	A person with mildly reduced tongue control
3	Moderately thick (drinks); liquidised (foods)	Can be drunk from a cup; smooth with no lumps; drips slowly through a fork	A person who needs more time to control a drink or food in the mouth
4	Extremely thick (drinks); pureed (foods)	Holds its shape on a spoon; cannot be poured, sipped or sucked through a straw; no chewing needed	A person with much reduced tongue control or who cannot chew
5	Minced and moist (foods)	Soft, moist food with small lumps (in adults, no wider than 4 mm) that the tongue can squash	A person who cannot bite and can chew only a little
6	Soft and bite-sized (foods)	Tender, moist pieces no larger than 1.5 cm; needs chewing but not biting	A person who can chew but not bite safely, or who tires with harder foods
7	Easy to chew; regular (foods)	Everyday soft foods (easy to chew) or foods of all textures (regular)	A person who can bite and chew soft foods, or all foods, safely

The framework also names **transitional foods**, which start firm but change texture with moisture or heat, such as some wafers (IDDSI, 2026).

Thickened drinks and modified textures lower risk but do not remove it (ASHA, n.d.). The nurse puts the plan into practice at each meal:

- **Position and pace:** the person sits upright, ideally in a chair, and eats at a steady pace with small mouthfuls, using the strategies the SLP recommends, under supervision if the plan calls for it.
- **Avoid hidden thin fluids:** foods that combine thin liquid and solids, such as cereal with milk, are avoided unless the plan allows them. Ice cream and jelly melt into thin fluid in the mouth (AHS, 2022).
- **Check the mouth:** after meals, the nurse checks for food left in the mouth and gives careful mouth care, which lowers pneumonia risk (Heart and Stroke Foundation of Canada, 2019).
- **Watch intake:** thick drinks and pureed food are less appealing, and a person eating pureed meals may not get enough energy and protein (AHS, 2022). The nurse tracks food and fluid intake closely and involves the dietitian.
- **Medications:** pills are not given with thin fluids when thin fluids are restricted (AHS, 2022). The nurse asks the pharmacist about a suitable form. Modified-release and enteric-coated products are never crushed (ISMP Canada, 2013).

A capable person may choose foods outside the plan. The nurse explains the risks and benefits and involves the SLP and team. Some sites use a documented managed-risk agreement (AHS, 2022). Consent and capacity are taught in Chapter 1, section 1.5.

LIFESPAN CONSIDERATIONS

Nutrition and Swallowing in Older Adults

Older adults in hospital are at high risk of both malnutrition and dysphagia, and the two problems feed each other.

- **Thresholds shift with age:** GLIM uses a higher BMI cut-off for low BMI over age 70 (below 22 kg/m² rather than below 20 kg/m²), so a BMI that seems acceptable in a younger adult may signal risk in an older one (Cederholm et al., 2019).
- **The mouth matters:** missing teeth, loose dentures and mouth pain make chewing hard (AHS, 2022). The nurse checks that dentures are in, fit well and are cleaned, and refers for dental care.
- **Life at home:** living alone and relying on adult children for groceries were linked with malnutrition on admission in the Canadian study (Allard et al., 2016). Discharge planning asks who shops and cooks and whether there is enough money for food (Chapter 2).
- **Texture and intake:** pureed meals and thick drinks can lower intake (AHS, 2022). Familiar foods, help with set-up and time to eat, company at meals and frequent small snacks help.
- **Watch for silence:** an older adult with dementia or after a stroke may aspirate without coughing (ASHA, n.d.). A new fever, confusion or fast breathing after meals is reported.
- **Medications:** reviewing medications that dry the mouth or reduce alertness, and deprescribing where possible, supports eating and swallowing (Chapter 8).

24.4 GERD, Gastritis and Peptic Ulcer Disease

Acid helps digestion, but the same acid can injure tissue when it reaches the esophagus or when the stomach's protective lining fails (section 24.1). This section covers the three most common acid-related disorders and the drugs used to treat them, including when and how to stop those drugs.

Gastroesophageal Reflux Disease

Gastroesophageal reflux disease (GERD) is present when stomach contents flow back into the esophagus and cause troublesome symptoms, complications or both (Katz et al., 2022). The main barrier to reflux is the lower esophageal sphincter, supported by the crural diaphragm that surrounds it. When this barrier works poorly, acid reaches the esophageal lining. Slow clearing of acid from the esophagus and a weakened lining make the injury worse (Katz et al., 2022).

The two classic symptoms are:

- **Heartburn:** a burning feeling behind the sternum that rises from the upper abdomen toward the neck.
- **Regurgitation:** stomach contents coming back up into the throat or mouth without effort, often with a sour or bitter taste (Katz et al., 2022).

Some symptoms are **alarm features** that suggest a more serious cause, such as cancer, a stricture or bleeding. Canadian and American gastroenterology guidance names difficulty swallowing (dysphagia), unintended weight loss, signs of gastrointestinal bleeding, anemia and persistent vomiting (Katz et al., 2022; Moayyedi et al., 2017). A person with an alarm feature needs prompt assessment by the prescriber, and endoscopy is usually the first test (Katz et al., 2022). The joint Canadian and American dyspepsia guideline also suggests endoscopy for people aged 60 or older whose main symptom is epigastric pain (Moayyedi et al., 2017). The nurse who hears about an alarm feature documents it and reports it rather than accepting "just heartburn" as the explanation.

Lifestyle measures are part of every plan (Farrell et al., 2017; Katz et al., 2022):

- Avoid eating within 2 to 3 hours of bedtime.
- Raise the head of the bed for night-time symptoms.
- Avoid tobacco and any foods the person finds trigger symptoms.
- Offer weight-loss support to people with a higher body weight who want it, using respectful, weight-inclusive language (section 24.6; Chapter 2).

Barrett esophagus is a precancerous change in the lining of the lower esophagus. GERD raises the risk of Barrett esophagus. Barrett esophagus is not cancer, but it can progress to esophageal cancer if it is not treated (Canadian Cancer Society, n.d.).

Gastritis and Peptic Ulcer Disease

Gastritis is inflammation of the stomach lining. **Peptic ulcer disease (PUD)** is a break through the lining of the stomach (gastric ulcer) or the first part of the duodenum (duodenal ulcer). The two leading causes are infection with **Helicobacter pylori (H. pylori)**, a bacterium that lives in the stomach, and NSAIDs, including acetylsalicylic acid (ASA). Each is an independent risk factor for ulcers and their complications (Malfertheiner et al., 2022; Tarasconi et al., 2020). Low-dose ASA for heart disease is discussed in Chapter 17; patients should not stop it without talking to the prescriber.

H. pylori infection is not spread evenly across Canada. In a multicentre Canadian study of people with dyspepsia, about 30% had the infection. Rates of 50% or more have been reported only in Indigenous communities. In Aklavik, Northwest Territories, 58% of residents tested had active infection, and gastric cancer was the second most common cancer among Inuit men in the territory (Cheung et al., 2014). The researchers worked with a community planning committee because residents had asked for the study. They pointed to structural causes, including crowded housing, challenges with water and sanitation, and distance from health care, rather than to individual behaviour (Cheung et al., 2014).

Manifestations. Dyspepsia, defined as epigastric pain as the main symptom for at least 1 month, is the usual complaint (Moayyedi et al., 2017). Nausea, early fullness and bloating may accompany it.

Complications. The nurse watches for three serious complications:

- **Bleeding:** by far the most common complication, covered in section 24.5 (Tarasconi et al., 2020).
- **Perforation:** the ulcer erodes through the wall of the stomach or duodenum, and contents leak into the abdomen. It usually begins with sudden abdominal pain. Signs of **peritonitis** (inflammation of the lining of the abdominal cavity), such as a tender, rigid abdomen, are typical, but they are absent in some patients (Tarasconi et al., 2020). Perforation is a surgical emergency: in pooled studies, 30-day mortality averaged 23.5%, and every hour's delay before surgery raises the risk of death (Tarasconi et al., 2020). The nurse keeps the patient NPO, assesses vital signs and escalates at once (Chapter 6).
- **Obstruction:** scarring near the outlet of the stomach can block emptying and cause repeated vomiting. Better medical treatment has made this complication rare (Tarasconi et al., 2020).

Diagnostics. H. pylori can be found with a non-invasive urea breath test or stool antigen test, or with biopsies taken during endoscopy. Guidance recommends non-invasive testing, and treatment if positive, for people under 60 with dyspepsia (Moayyedi et al., 2017). Some drugs suppress the bacteria and cause false-negative results. The European consensus that Canadian specialists contributed to advises stopping proton pump inhibitors 2 weeks before testing, stopping bismuth at least 4 weeks before, and avoiding any other drug that suppresses the bacteria, such as antibiotics. Antacids or H2-receptor antagonists may be used for symptoms in the meantime (Malfertheiner et al., 2022). The nurse checks the medication list when the test is booked and tells the prescriber if a recent drug could affect the result.

Treatment of H. pylori. The Toronto Consensus, the Canadian Association of Gastroenterology's guidance, recommends that every regimen last 14 days (Fallone et al., 2016). It names two first-line options:

- **Bismuth quadruple therapy:** a proton pump inhibitor, bismuth, metronidazole and tetracycline. It is the preferred first choice for people with a penicillin allergy.
- **Concomitant non-bismuth quadruple therapy:** a proton pump inhibitor, amoxicillin, metronidazole and clarithromycin.

Older three-drug regimens are restricted to areas where clarithromycin resistance is known to be low. A failed clarithromycin regimen is not repeated (Fallone et al., 2016). Success is confirmed with a breath or stool test at least 4 weeks after treatment ends; a blood antibody test cannot show eradication (Malfertheiner et al., 2022).

Patient education. The regimens involve many tablets several times a day, and missed doses lower the cure rate. The nurse teaches the patient to take every dose for the full 14 days, even when symptoms settle, and to ask the pharmacist which side effects to expect. Pharmacy blister packs can help (Fallone et al., 2016). The patient should report severe diarrhea (Chapter 4) or a rash, and should return for the confirmation test.

Acid-Suppressing Medications and Deprescribing

Three groups of drugs reduce or neutralize stomach acid (Table 24.3). **Proton pump inhibitors (PPIs)** block the final step of acid production in the stomach's acid-secreting cells and are the strongest of the three (Sun Pharma Canada, 2025). They are widely prescribed in Canada: in 2012, pantoprazole was the fifth most commonly prescribed drug in the country. Many people keep taking a PPI without a documented ongoing reason (Farrell et al., 2017).

Long-term PPI use has been linked with vitamin B12 deficiency, low magnesium, fractures, Clostridioides difficile infection and community-acquired pneumonia (Farrell et al., 2017; Sun Pharma Canada, 2025). These risks are small for any one person, but older adults may be more vulnerable (Farrell et al., 2017; Chapter 8). The goal is the lowest dose that controls symptoms, for no longer than needed.

Deprescribing is the planned, supervised reduction or stopping of a drug whose harms may now outweigh its benefits. The Canadian PPI deprescribing guideline applies to adults who have taken a PPI for more than 4 weeks for heartburn or esophagitis and whose symptoms have resolved (Farrell et al., 2017). In the book's own words, the process has five steps:

1. **Confirm the reason.** If no ongoing reason is documented, the risks may outweigh the benefit.

2. **Check for reasons to continue.** People with Barrett esophagus, severe esophagitis or a past bleeding ulcer, and those who take NSAIDs regularly and are at high risk of bleeding, usually stay on a PPI (Bruyère Research Institute, 2018; Farrell et al., 2017).

3. **Choose a plan with the patient.** Either lower the daily dose, or stop and switch to on-demand use, taking the drug daily only when symptoms return until they settle. An H2-receptor antagonist is a weaker alternative. No tapering method has been shown to be best (Farrell et al., 2017).

4. **Follow up** at about 4 and 12 weeks for heartburn, regurgitation and epigastric pain (Farrell et al., 2017).

5. **Manage symptoms that return** with lifestyle measures, an occasional antacid or alginate product, or on-demand use. If symptoms persist, the prescriber confirms H. pylori has been tested and treated (Bruyère Research Institute, 2018).

A PPI started in an intensive care unit to prevent stress ulcers and continued after the patient leaves the unit is one situation the Canadian algorithm lists for review (Bruyère Research Institute, 2018). Nurses notice these drugs during medication reconciliation and raise them with the prescriber or pharmacist.

Table 24.3 Drugs for acid-related disorders (Bruyère Research Institute, 2018; Fallone et al., 2016; Farrell et al., 2017; Malfertheiner et al., 2022; Pharmascience Inc., 2026; Sun Pharma Canada, 2025)

Class	Canadian examples	How it works	Nursing points
Proton pump inhibitors	Omeprazole, esomeprazole, lansoprazole, dexlansoprazole, pantoprazole, rabeprazole; pantoprazole is also given IV in hospital	Block the proton pump, the last step in acid secretion by stomach cells	Many work best 30 to 60 minutes before a meal; check each product's directions. Swallow delayed-release tablets whole. Review the need at every transition. Stop 2 weeks before H. pylori testing if the prescriber agrees.
H2-receptor antagonists	Famotidine	Block histamine-2 receptors on acid-secreting cells, lowering acid output	Weaker than PPIs. Used as a step-down option or for occasional symptoms. Can be used for symptoms in the weeks before H. pylori testing.
Antacids and alginates	Calcium carbonate; other antacid combinations; alginate products	Neutralize acid already in the stomach (antacids); form a barrier layer on top of stomach contents (alginates)	For occasional symptoms and during PPI deprescribing. Ask a pharmacist about spacing them from other medicines.
H. pylori regimens	Bismuth quadruple therapy; concomitant non-bismuth quadruple therapy	Combine acid suppression with antibiotics, plus bismuth in one option, to clear the infection	Every regimen runs 14 days. Teach adherence and side effects. Confirm cure at least 4 weeks after treatment with a breath or stool test.

PATIENT EDUCATION

Taking and Stopping a Proton Pump Inhibitor

- **Take it at the right time.** Many PPIs work best 30 to 60 minutes before a meal, usually breakfast (Katz et al., 2022). Some products can be taken with food, so follow the label or the pharmacist's directions.
- **Swallow it whole.** Do not crush or chew delayed-release tablets or capsules unless the pharmacist says that product allows it (Sun Pharma Canada, 2025).
- **Know why you take it.** Ask at each visit whether you still need it and for how long.
- **Do not stop on your own.** If your symptoms have settled, ask about lowering the dose or using it only when needed. Some heartburn may come back for a few days; this does not always mean you need the full dose again (Farrell et al., 2017).
- **Help yourself without pills.** Avoid eating 2 to 3 hours before bed, raise the head of your bed, avoid foods that trigger your symptoms and avoid tobacco (Katz et al., 2022).
- **Use rescue products wisely.** An antacid or alginate product can help with an occasional flare (Bruyère Research Institute, 2018).
- **Get help quickly** for trouble swallowing, weight loss you did not plan, vomiting that will not stop, vomit that looks like blood or coffee grounds, or black stools. Call 9-1-1 for heavy bleeding or fainting.

24.5 Upper Gastrointestinal Bleeding

Upper gastrointestinal bleeding (UGIB) is bleeding from the esophagus, stomach or duodenum. In one survey its yearly incidence fell from 78 to 61 cases per 100,000 people between 2001 and 2009. Even so, up to 11% of patients die within 30 days (Barkun et al., 2019). This section covers non-variceal bleeding; bleeding from esophageal varices in liver disease is covered in Chapter 26.

Causes and Risk

Peptic ulcer is the leading cause of non-variceal UGIB (Tarasconi et al., 2020). Other causes include:

- **Erosive disease:** severe esophagitis or erosive gastritis (section 24.4).
- **Mallory–Weiss tear:** a tear in the lining where the esophagus joins the stomach, typically after forceful retching or vomiting.
- **Cancer** of the esophagus or stomach.

The main risk factors are NSAIDs, ASA and H. pylori infection (Tarasconi et al., 2020). Anticoagulants and antiplatelet drugs do not cause ulcers but make any bleeding heavier and harder to stop (Barkun et al., 2019; Chapter 19). Older adults often take several of these drugs together, so the nurse reviews over-the-counter products such as naproxen and ibuprofen during every medication history.

Recognizing a Bleed

Blood can leave the body from either end of the gut:

- **Hematemesis:** vomiting bright red blood or clots, which usually means brisk bleeding.
- **Coffee-ground emesis:** dark, granular vomit; the blood has been altered by stomach acid.
- **Melena:** black, sticky, tar-like stool with a strong odour, formed when blood is digested on its way through the bowel.
- **Hematochezia:** red or maroon blood from the rectum. This usually signals a lower bleed, but a brisk upper bleed can cause it too. In a British guideline, 11% to 15% of patients first thought to have a lower bleed had an upper source, and red rectal bleeding with unstable vital signs suggests one (Oakland et al., 2019).

Blood loss produces the signs of hypovolemic shock described in Chapter 6. Early on, heart rate rises and blood vessels constrict to hold blood pressure steady. Low blood pressure is a late sign that compensation is failing (Schiller et al., 2017). Other cues are dizziness or fainting on standing, cool skin, slow capillary refill, restlessness or new confusion, and falling urine output.

Pallor can be hard to see on darker skin. Brown skin may look yellow-brown, and very dark skin may look ash grey. The nurse inspects the conjunctivae, lips, oral mucosa and nail beds in natural light and compares with the person's usual colour. A visual check alone is unreliable, so the nurse pairs it with vital signs and laboratory results (Pusey-Reid et al., 2023).

Two groups may not show the expected rise in heart rate. Beta-blockers blunt the heart-rate response that helps the body tolerate blood loss (Schiller et al., 2017), and guidance warns that shock measures based on heart rate must be read with care in people taking them (Oakland et al., 2019). Older adults may also mount a weaker response (Chapter 8). In these patients a modest rise in heart rate, new dizziness or a falling hemoglobin deserves the same urgency as frank tachycardia. The Clinical Judgment box "Melena on Day 2" shows these cues in a real-world sequence.

Care and Escalation

The nurse who suspects UGIB acts at once and does not wait for the next routine assessment. Every nurse who notices deterioration escalates, using SBAR and the rapid response team when criteria are met (Chapter 6). In Ontario, an RPN who finds melena or coffee-ground emesis assesses the patient, reports at once to the RN and the prescriber, and consults the RN as the patient's needs change. Many employers assign patients who are becoming unstable to an RN; this is a common employer practice, not a CNO rule, and employer policy shapes who does what (Chapter 1, section 1.3). Care proceeds in parallel:

- **Airway and position:** a patient who is vomiting blood or is drowsy is turned on their side, with suction ready.
- **Vital signs and early warning score:** repeated often, with intake and output.
- **IV access:** large-bore access, often two lines, as ordered or per policy, for fluids and blood.
- **Blood work:** complete blood count, group and screen (Chapter 20), coagulation tests, urea and creatinine.
- **Fluids:** fluid resuscitation begins for a patient whose circulation is unstable (Barkun et al., 2019).
- **Transfusion:** the international consensus, reviewed by the Canadian Association of Gastroenterology, suggests red cell transfusion when hemoglobin is below 80 g/L in a patient without cardiovascular disease. A higher threshold is suggested for people with cardiovascular disease. Neither threshold applies to massive bleeding (Barkun et al., 2019; section 20.6).
- **NPO:** in preparation for endoscopy (Chapter 7).
- **Medications:** an IV PPI may be ordered before endoscopy, but it must not delay the procedure. H2-receptor antagonists are not recommended for acute ulcer bleeding, and drugs that speed stomach emptying are not given routinely before endoscopy (Barkun et al., 2019).
- **Anticoagulants and antiplatelets:** held as the prescriber directs. Endoscopy is not delayed because a patient takes an anticoagulant (Barkun et al., 2019; Chapter 19).

Endoscopy both finds and treats the source. The consensus suggests it within 24 hours of presentation for patients admitted with UGIB (Barkun et al., 2019). An ulcer with active bleeding or a visible vessel has high-risk features. These lesions are treated during endoscopy, followed by high-dose IV PPI for 3 days and then an oral PPI twice daily until day 14 (Barkun et al., 2019). Patients with a clean-based ulcer may go home soon after the procedure. In rural and remote hospitals without endoscopy on site, meeting the 24-hour window can mean an early transfer, so a prompt report from the nurse starts that process sooner.

Monitoring for rebleeding. After endoscopy, the nurse watches for fresh hematemesis, new melena, a rising heart rate, a falling blood pressure or a drop in hemoglobin, and reports any of them at once. Melena may continue for a while as old blood passes, so the nurse looks at the trend in vital signs and hemoglobin as well as the stool.

Preventing a second bleed. Patients with an ulcer are tested for H. pylori and treated if positive (Tarasconi et al., 2020; section 24.4). NSAIDs are stopped where possible. Low-dose ASA for heart disease is restarted once the prescriber judges that the heart risk outweighs the bleeding risk. People with a past ulcer bleed who need an antiplatelet or anticoagulant usually take a PPI as well (Barkun et al., 2019). Before discharge, the nurse teaches the patient to avoid over-the-counter NSAIDs, including combination cold and pain products, and to seek help for black stools, vomiting of blood or fainting. The discharge summary lists which drugs were stopped or held and who will decide when to restart them, so the family physician, the community pharmacist and home care nurses share one plan. Iron deficiency after a bleed is followed up as section 20.2 describes.

> GOING DEEPER
>
> **Risk Scores in Upper GI Bleeding**
>
> *Required for RN students; optional for PN students.*

Risk scores help teams decide who needs admission and urgent endoscopy and who can safely be managed as an outpatient. The **Glasgow-Blatchford score** was built to predict which patients will need treatment, such as transfusion, endoscopic therapy or surgery, rather than only who will die (Blatchford et al., 2000). It uses information available before endoscopy:

- blood urea and hemoglobin;
- heart rate and systolic blood pressure;
- melena or fainting at presentation;
- a history of liver disease or heart failure.

Each item adds points, and higher totals mean greater need for treatment.

The international consensus suggests that a score of 1 or less identifies patients at very low risk of rebleeding or death. Such patients may not need admission or inpatient endoscopy. The consensus prefers this score because it is very sensitive: it wrongly labels as low risk 1% or fewer of patients who are truly at high risk (Barkun et al., 2019). It advises against another pre-endoscopy score, AIMS65, for this purpose.

A score supports the team's judgment; it never replaces it. A patient with a low score whose vital signs change, who faints or who keeps passing melena is reassessed and escalated. Nurses supply much of the score's data, so accurate, timely vital signs and a complete history of liver disease, heart failure and fainting matter.

CLINICAL JUDGMENT

Melena on Day 2

Names and details are fictional; this is a composite story.

Rosa Delgado, 81, was admitted for pneumonia. She takes apixaban for atrial fibrillation and metoprolol, and her daughter mentions she has taken naproxen for knee pain for 3 weeks. On day 2 the RPN caring for her reports two black, tarry stools since morning. Mrs. Delgado says she feels light-headed when she stands.

Recognize cues: Heart rate 92 (her usual 70s), blood pressure 108/64 mm Hg (usual 135/80 mm Hg), respiratory rate 20, SpO_2 95% on room air. Conjunctivae and lips are pale compared with her usual colour. Hemoglobin is 98 g/L, down from 121 g/L on admission.

Analyze cues: Melena, a falling hemoglobin, postural dizziness and a drop in blood pressure together point to an upper GI bleed. Naproxen and apixaban explain the risk. Metoprolol can hide how fast her heart would otherwise beat (section 24.5).

Prioritize hypotheses: Ongoing blood loss leading to shock is the most urgent concern. A fall from dizziness is a related risk.

Generate solutions: Report to the physician now using SBAR. Anticipate IV access, repeat blood work with group and screen, NPO, an IV PPI, holding apixaban and naproxen, and endoscopy within 24 hours. Keep her in bed with help to stand.

Take action: The RN and RPN stay with her, raise the early warning score and page the physician, who comes within 15 minutes. The RN starts IV access as ordered, sends blood and keeps her NPO.

Evaluate outcomes: One hour later her heart rate is 104 and her blood pressure is 96/58 mm Hg. Because her vital signs are worsening, the RN calls the rapid response team. After resuscitation and an endoscopy that treats a bleeding gastric ulcer, her vital signs settle and her hemoglobin holds steady. She is tested for H. pylori before discharge, and naproxen is stopped.

PRACTICE STORY

Coffee Grounds at Midnight

Names and details are fictional; this is a composite story.

Nurse: Jasleen Brar, RN. Years in practice: 4. Setting: medical unit, Ontario.

Just before midnight, the RPN on my team, Kwame, asked me to look at Mr. Leblanc. He was 76 and had been admitted with heart failure. Kwame had found a small amount of dark, gritty vomit in his basin. "It looks like coffee grounds," Kwame said, "and he says his stools were black yesterday. I didn't want to wait until morning."

Mr. Leblanc said he felt "washed out." His heart rate was 96, a little higher than earlier, but he takes bisoprolol, so I did not trust that number to tell me everything. His blood pressure had dropped from 128/74 to 106/62 mm Hg since the evening check. His skin is deep brown, so I checked his conjunctivae and gums under the bright exam light, and they looked pale. His chart showed he takes apixaban, and his wife had brought in ibuprofen for his back.

I asked Kwame to stay with him and keep him on his side in case he vomited again, and I called the physician on call with an SBAR report. I said "I am concerned about an upper GI bleed" in my first sentence. She ordered a stat hemoglobin, group and

> screen, two IV lines, NPO and an IV PPI, and she held his apixaban. His hemoglobin came back at 89 g/L; it had been 117 g/L two days earlier.
>
> At 0200 his heart rate was 108 and his pressure was 94/56 mm Hg. That met our rapid response criteria, so I called the team. He went for endoscopy in the morning, where a bleeding duodenal ulcer was treated.
>
> Kwame noticed the cue, and he was right not to wait. What I added was putting the cues together: the black stools, the beta-blocker, the drug list and the trend.
>
> Reflect: What cues allowed this bleed to be recognized before Mr. Leblanc's blood pressure fell sharply? How do the RPN's and the RN's roles in assessment and escalation differ here, and where do they overlap?

24.6 Obesity and Bariatric Surgery

Obesity as a Chronic Disease

The Canadian Adult Obesity Clinical Practice Guideline defines **obesity** as "a complex chronic disease in which abnormal or excess body fat (adiposity) impairs health" (Wharton et al., 2020). Like other chronic diseases, it has many causes, including biology, environment, income, stress and medications, and it needs long-term care rather than blame.

Body mass index (BMI), weight in kilograms divided by height in metres squared, is used to define obesity in practice: a BMI over 30 kg/m², divided into class 1 (30 to 34.9), class 2 (35 to 39.9) and class 3 (40 or more) (Wharton et al., 2020). BMI is useful for screening and for population statistics. It does not show where fat is stored or whether it is harming health (Statistics Canada, 2024; Wharton et al., 2020). Clinicians therefore add waist circumference, ethnicity-specific BMI cut-offs and an assessment of complications (Pedersen et al., 2025). The **Edmonton Obesity Staging System** is a five-stage tool that rates metabolic, physical and mental health effects. It predicted death better than BMI or waist size alone (Wharton et al., 2020).

Canadian data. In the 2022 Canadian Community Health Survey, about 30% of adults aged 18 and older had obesity, up from 21% in 2003. Rates were about equal in women and men and peaked at ages 50 to 64. They varied by province, from 26% in British Columbia to 43% in New Brunswick (Statistics Canada, 2024). These figures come from self-reported height and weight. People tend to under-report weight and over-report height, so Statistics Canada adjusts the data using measured surveys. Without that adjustment, obesity would be underestimated by about 6 to 7 percentage points (Statistics Canada, 2024).

Respectful care. Weight bias in health care lowers the quality of care for people living with obesity (Wharton et al., 2020). Chapter 2 covers weight stigma in depth. At the bedside, the nurse:

- uses person-first language ("a person living with obesity");
- asks permission before talking about weight or measuring the person;
- does not assume a new complaint is caused by body weight (Wharton et al., 2020);
- has right-sized equipment ready before it is needed, including blood pressure cuffs, gowns, chairs, beds, lifts and scales, and weighs people in private (Chapter 2).

Medications for Obesity

The guideline supports medication, added to nutrition, activity and psychological support, for adults with a BMI of 30 or more, or 27 or more with an obesity-related complication (Wharton et al., 2020). The 2025 update lists six drugs with Health Canada approval for chronic weight management (Pedersen et al., 2025). Five of them are:

- **Glucagon-like peptide-1 (GLP-1) receptor agonists:** semaglutide (Wegovy) and liraglutide (Saxenda).
- **Dual glucose-dependent insulinotropic polypeptide (GIP) and GLP-1 receptor agonist:** tirzepatide (Zepbound).
- **Naltrexone–bupropion** (Contrave).
- **Orlistat** (Xenical), which blocks fat absorption in the gut.

The sixth is limited to certain rare genetic forms of obesity. These drugs are meant for long-term use. People who stop them tend to regain weight and lose the health benefits they gained (Pedersen et al., 2025). Nausea, vomiting, diarrhea and constipation are common with the injectable drugs, especially as the dose is increased. Orlistat can cause oily stools and urgency. The guideline

recommends against compounded products and against drugs not approved for weight loss (Pedersen et al., 2025). Treatment goals are set with the patient before starting, based on their values and preferences. Semaglutide is also approved to reduce the risk of non-fatal heart attack in adults with established cardiovascular disease and a BMI of 27 or more (Pedersen et al., 2025). Cost can limit access, in part because some payers do not recognize obesity as a chronic disease (Pedersen et al., 2025). Diabetes use of GLP-1 receptor agonists is covered in Chapter 22, and holding them before procedures in Chapter 7.

Bariatric Surgery

Bariatric surgery changes the stomach, the intestine or both to support long-term weight loss and improve obesity-related disease. The Canadian guideline says surgery can be considered for adults with a BMI of 40 or more, or 35 or more with one or more obesity-related diseases. It should also be considered for people with a BMI of 30 to 35 whose type 2 diabetes stays poorly controlled despite the best medical care (Obesity Canada, 2020b). With behaviour change, surgery leads to a long-term loss of about 20% to 40% of body weight. Laparoscopic surgery is the standard approach. For most patients the death rate is under 0.1% and the serious complication rate is under 5%, and surgery improves life expectancy (Obesity Canada, 2020b). The choice of operation is a shared decision, made with an experienced interprofessional team after the patient has heard the risks, benefits and side effects of each option.



Figure 24.6 Roux-en-Y gastric bypass anatomy: a small proximal stomach pouch is created with surgical staples and anastomosed directly to a Roux limb of the jejunum, bypassing the distal stomach and duodenum. (credit: "Blausen 0776 Roux-En-Y 01" by BruceBlaus/Wikimedia Commons, CC BY 3.0)

Two widely used operations, sleeve gastrectomy and Roux-en-Y gastric bypass, are compared in Table 24.4. Adjustable gastric banding should no longer be offered because of its complications and long-term failure (Obesity Canada, 2020b; Figure 24.6).

Table 24.4 Sleeve gastrectomy and Roux-en-Y gastric bypass compared (Kim et al., 2015; Mechanick et al., 2020; Obesity Canada, 2020b; The Ottawa Hospital, 2023)

Feature	Sleeve gastrectomy	Roux-en-Y gastric bypass
What is done	A large part of the stomach is removed, leaving a narrow tube	A small new stomach pouch is made and joined to the small intestine; the rest of the stomach is bypassed
Leak rates in published series	0% to 7%	0.1% to 8.3%
Timing of leaks	Often appear later, sometimes after discharge	Signs may be subtle or delayed
Dumping syndrome	Can occur; sweets and high-fat foods are limited	Concentrated sweets are removed from the diet to limit symptoms
Diet progression	Pureed stage may last up to 2 weeks	Pureed stage usually about 1 week
NSAIDs	Avoided after surgery	Stopped before surgery and avoided after
Alcohol	Avoided because of changed alcohol metabolism and risk of alcohol use disorder	Avoided for the same reasons
Vitamins and minerals	Lifelong supplements and regular blood tests	Lifelong supplements and regular blood tests

Care After Bariatric Surgery

Early care follows the perioperative principles in Chapter 7, including VTE prevention. Early walking lowers the risk of clots (Mechanick et al., 2020). The nurse encourages calf and ankle exercises and short walks several times a day from the day of surgery (The Ottawa Hospital, 2023).

Anastomotic leak. An **anastomotic leak** is escape of stomach or intestinal contents through a staple or suture line. It is among the most dangerous early complications. After sleeve gastrectomy, the most common signs are tachycardia, fever and abdominal pain, and the pain often spreads to the left shoulder (Kim et al., 2015). Blood tests rarely help, and imaging can be normal even when a leak is present. A persistently high heart rate is therefore never explained away as pain or anxiety. Leaks after sleeve gastrectomy often show up after discharge (Kim et al., 2015), so discharge teaching names these signs. The nurse who finds them escalates at once (Chapter 6).

Staged diet. Eating restarts in stages: clear fluids, full fluids, pureed foods, soft foods, then regular textures over several weeks, as the surgical team's protocol directs (Mechanick et al., 2020). The nurse teaches the patient to:

- sip small amounts often;
- meet a protein target of at least 60 g a day (Mechanick et al., 2020);
- eat slowly and chew well;
- separate drinks from solid food by about 30 minutes (The Ottawa Hospital, 2023).

Dumping syndrome. In **dumping syndrome**, food moves too quickly into the small intestine and draws water in. It causes cramping, bloating, nausea, diarrhea, faintness and a fast heart rate, usually 10 to 90 minutes after eating (The Ottawa Hospital, 2023). Avoiding concentrated sweets and high-fat foods, eating small meals and separating liquids from solids reduce symptoms (Mechanick et al., 2020; The Ottawa Hospital, 2023).

Lifelong supplements. Surgery reduces absorption of several nutrients. Patients take supplements every day for life, usually including (Mechanick et al., 2020; Obesity Canada, 2020b; The Ottawa Hospital, 2023):

- a multivitamin with minerals;
- vitamin B12;
- calcium citrate and vitamin D;
- iron as blood work shows it is needed.

Calcium and iron are taken at least 2 hours apart. Blood tests check iron, vitamin B12, vitamin D and other nutrients at set intervals, then at least yearly (Obesity Canada, 2020a; The Ottawa Hospital, 2023). Deficiencies such as iron and B12 deficiency are discussed in section 20.2.

Medications and alcohol. Early after surgery, crushed or liquid immediate-release forms replace extended-release drugs (Mechanick et al., 2020). Only crush a tablet the pharmacist confirms can be crushed. NSAIDs are avoided, and acetaminophen is the usual pain reliever (Mechanick et al., 2020; The Ottawa Hospital, 2023). Diabetes and blood pressure medications often need adjustment as weight falls (Chapter 22). Surgery changes how the body handles alcohol and raises the risk of alcohol use disorder, so patients are advised to avoid alcohol (Mechanick et al., 2020; Chapter 11).

Mental health and follow-up. Mood, relationships and body image can all be affected after surgery. The risks include depression, thoughts of suicide, disordered eating and substance use (Obesity Canada, 2020a; The Ottawa Hospital, 2023). The nurse screens for these concerns and connects patients with the team's mental health supports. Pregnancy is avoided for 12 to 18 months after surgery, so contraception is discussed (Mechanick et al., 2020). Follow-up is shared among the surgical centre, primary care and the patient, with an annual review of nutrition, supplements, medications and blood work (Obesity Canada, 2020a). Weight is usually lowest 12 to 18 months after surgery and then rises somewhat. This is expected, but large regain is a reason to return to the bariatric team, not a personal failure (Obesity Canada, 2020a).

Chapter 24 Summary

24.1 Digestion and Nutrition Assessment

- The upper GI tract runs from the mouth to the duodenum; the stomach's acid is balanced by mucosal defences, and the stomach acts as a reservoir that shapes how tube feeds can be given.
- In a Canadian Malnutrition Task Force study, 45% of adults admitted to medical and surgical units in 18 hospitals were malnourished at admission, and malnutrition was linked with longer stays.
- Every adult admitted is screened with the two-question Canadian Nutrition Screening Tool, the first step of INPAC, which then guides assessment, levels of nutrition care, weekly weights and discharge planning.
- GLIM diagnoses malnutrition when a person meets at least one phenotypic and one etiologic criterion; weight history and muscle tell more than BMI alone, and albumin reflects inflammation rather than nutrition.
- Refeeding syndrome is a fall in phosphate, potassium or magnesium after nutrition starts in an undernourished person; at-risk patients need electrolytes checked, thiamine, a slow start and close monitoring.

24.2 Enteral and Parenteral Nutrition

- Feeding tubes are named by entry and tip position; nasal tubes are for short-term use, and gastrostomy or jejunostomy tubes for longer-term feeding.
- A blindly placed nasal tube is confirmed by radiograph before first use; afterwards, the nurse checks the external mark and does the bedside checks policy names before each use, and never relies on listening for injected air.
- Feeds are given with the head of the bed at 30 to 45 degrees unless contraindicated; routine gastric residual checks are no longer done unless ordered; ENFit connectors help prevent misconnections.
- Medications go through the tube one at a time with water flushes, after checking with the pharmacist; modified-release and enteric-coated products are never crushed, and nothing is added to the formula.
- Parenteral nutrition is a high-risk IV therapy, usually given through a central line; the nurse checks the bag against the order, prevents infection, monitors glucose and electrolytes, and changes or stops the infusion only by order.

24.3 Dysphagia and Texture-Modified Diets

- Signs of dysphagia include coughing or a wet voice with eating or drinking, trouble controlling food in the mouth, slow meals, weight loss and repeated chest infections; aspiration can be silent.
- A swallowing screen identifies who needs assessment; after a stroke, no food, drink or oral medication is given until the person is screened, and a failed screen usually means nothing by mouth until the speech-language pathologist assesses the person.
- The IDDSI framework describes drinks (levels 0 to 4) and foods (levels 3 to 7) on one continuum with standard tests.
- At meals, the nurse positions the person upright, follows the SLP's strategies, avoids hidden thin fluids, gives mouth care and watches food and fluid intake.
- Pills are not given with thin fluids when these are restricted, and a capable person's choices outside the plan are respected after an informed discussion.

24.4 GERD, Gastritis and Peptic Ulcer Disease

- GERD causes heartburn and regurgitation. Dysphagia, unplanned weight loss, bleeding, anemia and persistent vomiting are alarm features that need prompt assessment.
- Lifestyle measures include no meals 2 to 3 hours before bed, raising the head of the bed, and avoiding tobacco and personal trigger foods.
- H. pylori and NSAIDs, including ASA, are the main causes of peptic ulcers. H. pylori is much more common in some northern Indigenous communities, for structural reasons.
- Sudden severe abdominal pain with a rigid abdomen suggests perforation, a surgical emergency: keep the patient NPO and escalate.

- H. pylori treatment lasts 14 days (Toronto Consensus). PPIs are stopped 2 weeks before testing, and cure is confirmed at least 4 weeks after treatment.
- Long-term PPIs carry small risks. Adults whose symptoms have resolved can lower the dose or switch to on-demand use, with follow-up at 4 and 12 weeks.

24.5 Upper Gastrointestinal Bleeding

- Peptic ulcer is the leading cause of non-variceal UGIB. NSAIDs, ASA, H. pylori, anticoagulants and antiplatelets raise risk.
- Hematemesis, coffee-ground emesis and melena point to an upper bleed. A brisk upper bleed can also cause red rectal bleeding.
- Beta-blockers and older age can blunt tachycardia. Pallor on darker skin is assessed in the conjunctivae and oral mucosa in natural light.
- Care includes airway protection, IV access, group and screen, NPO, an IV PPI that does not delay endoscopy, and endoscopy within 24 hours.
- Transfusion is suggested below 80 g/L without cardiovascular disease, and at a higher threshold with it.
- A Glasgow-Blatchford score of 1 or less marks very low risk, but the score never replaces judgment.

24.6 Obesity and Bariatric Surgery

- Obesity is a chronic disease. BMI is a screening tool with limits; self-reported data underestimate prevalence (about 30% of Canadian adults in 2022, adjusted).
- Respectful care means asking permission before talking about weight or measuring, using person-first language and having right-sized equipment ready.
- Six drugs are approved in Canada for chronic weight management. They are meant for long-term use, and weight returns when they are stopped.
- Surgery can be considered at a BMI of 40 or more, or 35 or more with an obesity-related disease. Sleeve gastrectomy and Roux-en-Y gastric bypass are two widely used operations.
- Tachycardia, fever and abdominal pain after surgery suggest an anastomotic leak. Escalate even if imaging is normal.
- After surgery: staged diet, dumping prevention, lifelong vitamin and mineral supplements, no NSAIDs, no alcohol, and attention to mental health.

Key Terms (49)

alarm features: symptoms such as dysphagia, unplanned weight loss, bleeding, anemia or persistent vomiting that suggest a serious cause and call for prompt assessment.

anastomotic leak: escape of stomach or intestinal contents through a surgical staple or suture line.

aspiration: The entry of food, fluid, saliva or stomach contents into the airway below the vocal folds.

bariatric surgery: surgery on the stomach, intestine or both to support long-term weight loss and improve obesity-related disease.

Barrett esophagus: a precancerous change in the lining of the lower esophagus, linked with long-term reflux, that raises the risk of esophageal cancer.

bolus: A soft, cohesive mass of chewed food or fluid that the tongue shapes and moves to the back of the mouth for swallowing.

Canadian Nutrition Screening Tool (CNST): A two-question screen asking about unintended weight loss over the last six months and eating less than usual for over a week; a yes to both shows nutrition risk.

central venous access device: An IV catheter whose tip lies in a large central vein, such as a peripherally inserted central catheter (PICC), used for concentrated solutions such as most parenteral nutrition.

coffee-ground emesis: dark, granular vomit containing blood that has been altered by stomach acid.

deprescribing: the planned, supervised reduction or stopping of a drug whose harms may now outweigh its benefits.

dumping syndrome: cramping, nausea, diarrhea, faintness and fast heart rate after eating, caused by food moving too quickly into the small intestine.

dyspepsia: epigastric pain as the main symptom for at least 1 month.

dysphagia: A swallowing disorder involving the mouth, pharynx, esophagus or the junction of the esophagus and stomach.

Edmonton Obesity Staging System: a five-stage tool that rates the metabolic, physical and mental health effects of obesity.

ENFit: A connector design for enteral feeding equipment that does not fit IV or other non-enteral ports, used to prevent tubing misconnections.

enteral nutrition: Feeding into the GI tract; in this chapter, liquid formula given through a feeding tube.

gastric residual volume (GRV): The volume of fluid drawn back from a gastric feeding tube; no longer checked routinely unless ordered or when signs of intolerance appear.

gastritis: inflammation of the stomach lining.

gastroesophageal reflux disease (GERD): a condition in which stomach contents flow back into the esophagus and cause troublesome symptoms, complications or both.

gastrostomy tube: A feeding tube that passes through the abdominal wall into the stomach, used for longer-term feeding.

Glasgow-Blatchford score: a pre-endoscopy risk score for upper GI bleeding that predicts the need for treatment; a score of 1 or less marks very low risk.

Global Leadership Initiative on Malnutrition (GLIM) criteria: International criteria that diagnose malnutrition when a person at risk meets at least one phenotypic criterion (weight loss, low BMI or reduced muscle mass) and at least one etiologic criterion (reduced intake or absorption, or inflammation).

Helicobacter pylori (H. pylori): a bacterium that lives in the stomach and causes gastritis, peptic ulcers and some stomach cancers.

hematemesis: vomiting of bright red blood or clots.

hematochezia: red or maroon blood passed from the rectum.

Integrated Nutrition Pathway for Acute Care (INPAC): A Canadian pathway for hospital nutrition care that moves from screening with the CNST to assessment, standard, advanced and specialized nutrition care, and discharge planning.

International Dysphagia Diet Standardisation Initiative (IDDSI): The international framework that describes drink thickness and food texture on a continuum of eight levels numbered 0 to 7.

jejunostomy tube: A feeding tube that passes through the abdominal wall into the jejunum, usually used with a continuous feed by pump.

malnutrition: In this chapter, undernutrition: a state in which the body does not take in or use enough energy and nutrients, so muscle and fat are lost and function declines.

melena: black, sticky, tar-like stool containing digested blood.

nasogastric (NG) tube: A tube passed through the nose and esophagus into the stomach, used for short-term feeding, medications or drainage.

obesity: a chronic, complex disease in which excess or abnormal body fat harms health.

parenteral nutrition: Nutrition given into a vein, used when the gut cannot be used or cannot meet the person's needs.

peptic ulcer disease (PUD): a break through the lining of the stomach or duodenum, most often caused by H. pylori or NSAIDs.

percutaneous endoscopic gastrostomy (PEG): A gastrostomy tube placed with the help of an endoscope passed through the mouth into the stomach.

perforation: erosion of an ulcer through the wall of the stomach or duodenum, letting contents leak into the abdomen; a surgical emergency.

peristalsis: Waves of muscle contraction that move food along the GI tract.

peritonitis: inflammation of the lining of the abdominal cavity.

proton pump inhibitor (PPI): a drug that blocks the final step of acid production in the stomach.

refeeding syndrome: A fall in blood phosphate, potassium or magnesium, sometimes with thiamine deficiency, within days of starting or increasing nutrition in a person who has been undernourished.

Roux-en-Y gastric bypass: bariatric surgery that creates a small stomach pouch joined to the small intestine, bypassing the rest of the stomach.

silent aspiration: Aspiration that occurs without coughing or other obvious signs.

sleeve gastrectomy: bariatric surgery that removes a large part of the stomach, leaving a narrow tube.

speech-language pathologist (SLP): A regulated health professional who assesses swallowing and recommends food textures, drink thickness and swallowing strategies.

Subjective Global Assessment (SGA): A structured bedside assessment that classifies nutrition status using weight change, intake, symptoms, function and physical signs of muscle and fat loss.

swallowing screen: A brief pass-or-fail check, done by a trained team member with a validated protocol, that identifies people who need a full swallowing assessment.

texture-modified diet: A diet that changes food texture, drink thickness or both to make swallowing safer.

upper gastrointestinal bleeding (UGIB): bleeding from the esophagus, stomach or duodenum.

weight bias: negative attitudes, beliefs or actions toward people because of their body weight.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Gurdev Sandhu (Questions 1–4): Gurdev Sandhu, 82, was admitted 4 days ago with an ischemic stroke; he failed his bedside swallowing screen, the speech-language pathologist found that he aspirates thin fluids, a small-bore nasogastric tube was inserted yesterday with its tip confirmed in the stomach by radiograph and the 60 cm mark documented at the nostril, and he now receives continuous enteral formula by pump and his medications by tube, with nothing by mouth.

1. [CORE] Before giving Mr. Sandhu's 0900 medications through the tube, which action should the nurse take first?

a. Inject 20 mL of air into the tube while listening over the upper abdomen for a gurgling sound

b. Compare the mark at the nostril with the 60 cm documented and do the bedside checks policy requires

c. Ask the prescriber for a repeat radiograph of the tube before each medication pass for the rest of the day

d. Withdraw and discard about 60 mL of stomach contents to prove that the tube is open and working

Answer: b — After radiograph confirmation, the nurse checks that the tube has not moved before each use by comparing the external centimetre mark with the documented mark and doing the bedside checks policy names, such as aspirate pH (section 24.2, Confirming Placement). Listening for injected air is not a valid check, because similar sounds occur when the tube is in the airway or esophagus. A radiograph is needed for first use and when the tube may have moved, not before every medication pass. Withdrawing and discarding a large volume does not confirm the tip position and removes gastric fluid and formula.

2. [CORE] At 1400, the nurse finds Mr. Sandhu lying almost flat after a care aide repositioned him. The feed is running. What is the nurse's best action?

a. Stop the feed for the rest of the shift and report the flat position to the prescriber and dietitian

b. Leave him flat for now, because repositioning him again so soon could cause a pressure injury on his sacrum

c. Raise the head of the bed only during medication passes and flushes, when aspiration risk is highest

d. Raise the head of the bed to 30 to 45 degrees unless contraindicated, and keep it raised during the feed

Answer: d — Lying flat during a feed is a risk factor for aspiration; the head of the bed is kept at 30 to 45 degrees during continuous feeds unless contraindicated (section 24.2, Giving Tube Feeds Safely). Stopping the feed for the whole shift is not needed once he is repositioned and has no signs of aspiration. Pressure injury prevention is done with turning and support surfaces while the head stays raised, not by leaving him flat. Aspiration risk is present throughout a continuous feed, not only during medication passes.

3. [CORE] Mr. Sandhu's medication record lists an extended-release tablet once daily for blood pressure. What should the nurse do?

a. Crush the tablet into a fine powder, mix it into the formula in the feeding bag and restart the pump

b. Crush the tablet into a fine powder, dissolve it in warm water, give it and then flush with water

c. Hold the dose and contact the pharmacist and prescriber about a form that can go through the tube

d. Give the tablet whole by mouth with a small sip of water, because a single tablet carries little risk

Answer: c — Extended-release, delayed-release and enteric-coated products are never crushed; the pharmacist and prescriber choose another form or drug (section 24.2, Medications by Feeding Tube). Crushing alters the release and can cause a dangerous dose. Medications are never added to the formula. Mr. Sandhu aspirates thin fluids and is nothing by mouth, so oral medication with water is unsafe.

4. [CORE] On day 6, Mr. Sandhu becomes restless. His respiratory rate has risen from 18 to 28 breaths/min, his oxygen saturation has fallen from 96% to 89% on room air, his temperature is 38.2 °C and there are new coarse crackles at the right lung base. He has not coughed. What is the nurse's priority?

a. Stop the feed, keep the head of the bed up, assess the airway and escalate at once to the prescriber or rapid response team

b. Continue the feed, because he has not coughed and silent aspiration is rare, then recheck his vital signs in 4 hours

c. Give acetaminophen for the fever and record the new findings so that the day team can review them on morning rounds

d. Flush the tube with 30 mL of water and recheck the mark at the nostril before deciding whether anyone needs to be called

Answer: a — The findings suggest aspiration, possibly from a displaced tube or reflux of formula, and the patient is deteriorating; the nurse stops the feed, protects the airway and escalates at once (section 24.2, Confirming Placement; section 24.3, Recognizing Dysphagia; Chapter 6). Aspiration can be silent, so the lack of a cough is not reassuring. Treating the fever and waiting delays care for a patient with falling oxygen saturation. Flushing a tube that may be in the airway is dangerous, and the tube is not used until its position is confirmed.

5. [CORE] A nurse screens a newly admitted 70-year-old man with the Canadian Nutrition Screening Tool. Which pair of answers shows that he is at nutrition risk?

a. He lost 4 kg over the winter but has since regained it, and he has eaten less than usual for 3 days

b. He lost weight on purpose following a meal plan, and he has eaten normally over the past month

c. He has lost weight in the past 6 months without trying, and has eaten less than usual for over a week

d. He has not lost any weight, but he has eaten noticeably less than usual for more than 2 weeks in a row

Answer: c — The CNST asks about unintended weight loss over the last six months and eating less than usual for over a week; a yes to both shows nutrition risk (section 24.1, Screening for Malnutrition). Weight that was regained does not count as weight loss, and 3 days of lower intake does not meet the time frame. Planned weight loss with normal intake gives two "no" answers. One "yes" alone does not meet the CNST's definition of risk, although the nurse still watches intake.

6. [CORE] A patient admitted with pneumonia has a serum albumin of 26 g/L. A nursing student says this proves the patient is malnourished. Which response by the nurse is most accurate?

a. "Albumin falls with inflammation, so it can't diagnose malnutrition; weight change, intake and muscle tell us more."

b. "Low albumin confirms protein malnutrition, so the patient should start a high-protein supplement right away."

c. "Albumin is the best measure of muscle mass, so this result shows how much muscle the patient has lost."

d. "Albumin rises quickly once a patient eats well, so a repeat level in 2 days will show whether feeding works."

Answer: a — ASPEN states that albumin and prealbumin mainly reflect inflammation and should not be used to diagnose malnutrition or stand in for muscle mass (section 24.1, Signs and Causes of Malnutrition). Low albumin in pneumonia does not confirm malnutrition. Albumin is not a measure of muscle. Because inflammation drives the level, a short-term change does not show whether feeding is working.

7. [CORE] A 58-year-old woman with a BMI of 31 kg/m² has lost 10 kg in 4 months without trying and says food has "not tasted right" since chemotherapy began. Which conclusion is correct?

a. Her BMI is above the usual range, so her nutrition is adequate and no further screening is needed now

b. Losing weight in a larger body is a health benefit, so the team should encourage her to keep it up

c. Malnutrition can only be diagnosed once the BMI falls below 20 kg/m², so she should be rechecked later

d. She is at nutrition risk despite her BMI, so she needs screening and a referral to the dietitian

Answer: d — Unintended weight loss and reduced intake signal risk whatever the BMI; a person in a larger body can lose a great deal of muscle while the BMI stays high (section 24.1, Signs and Causes of Malnutrition). A high BMI does not show adequate nutrition. Unintended weight loss during cancer treatment is not a benefit, and framing it that way is weight bias (Chapter 2). GLIM counts weight loss and muscle loss as well as low BMI, so a low BMI is not required.

8. [CORE] Meal records show that a patient has eaten about one quarter of each meal for 2 days. Under the Integrated Nutrition Pathway for Acute Care (INPAC), what does this finding mean?

a. Intake is acceptable for a patient who is ill in hospital, so the nurse simply continues routine meal monitoring

b. Intake of half a meal or less is low, so the team acts on barriers to eating and considers more nutrition care

c. Intake has failed by mouth, so the nurse should request that parenteral nutrition be started today

d. Intake is reviewed only at the weekly weight, so the nurse waits until then before acting on it

Answer: b — INPAC treats eating half a meal or less as low intake that needs action, such as removing barriers to eating and moving to advanced care with dietitian involvement as needed (section 24.1, Screening for Malnutrition). Low intake is not acceptable to watch without acting. Parenteral nutrition is for a gut that cannot be used or cannot meet needs, not a first step for low oral intake. Waiting a week delays action.

9. [CORE] An RPN on a medical unit is about to restart a patient's intermittent tube feed and finds the 52 cm mark at the nostril. The mark was documented at 60 cm after radiograph confirmation. What should the RPN do?

a. Hold the feed, secure the tube without using it, and report to the RN or prescriber as employer policy directs

b. Push the tube in 8 cm until the 60 cm mark is back at the nostril, retape it and then start the feed as ordered

c. Inject air into the tube while listening over the stomach, and start the feed if a clear gurgle can be heard

d. Start the feed at half the ordered rate for now and recheck the mark at the nostril at the end of the shift

Answer: a — A changed external mark suggests the tube has moved, so the tube is not used until its position is confirmed; the RPN reports to the RN or prescriber, and repeat imaging may be ordered (section 24.2, Confirming Placement). Pushing a tube back in blindly can place it in the airway, and reinsertion follows an order or directive and employer policy. Listening for injected air does not confirm placement. A slower feed into a misplaced tube is still dangerous.

10. [CORE] A patient on an IDDSI Level 5 (minced and moist) diet with Level 2 (mildly thick) drinks asks the RPN for toast and coffee with no thickener. The patient is alert and capable. What is the best response?

a. Bring the toast and plain coffee right away, because a capable patient's wishes always override the diet plan

b. Decline the request and document in the chart that the patient is not complying with the diet order

c. Explain the reasons for the plan, offer safe choices and involve the SLP and team in a discussion of the risks

d. Soften the toast in milk and thicken the coffee to Level 4, so that both items fit the minced and moist level

Answer: c — A capable person may make choices that carry risk, but the choice must be informed; the nurse explains, offers safe options and involves the SLP and team, and some sites use a managed-risk agreement (section 24.3, Screening, Assessment and Diets; Chapter 1, section 1.5). Giving the food without discussion skips informed choice. Labelling the patient noncompliant without discussion is neither respectful nor safe. Toast soaked in milk mixes thin liquid with solids, and the nurse does not change texture levels without the SLP's plan.

11. [CORE] A patient receiving continuous gastric feeds has a soft, non-distended abdomen, no nausea and regular bowel movements. A new graduate asks whether to check gastric residual volume every 4 hours. Which reply fits the Canadian provincial guidance described in this chapter?

a. "Yes; residuals are checked every 4 hours in every adult who is receiving a continuous gastric feed."

b. "Not routinely; residuals are checked when they are ordered or when signs of intolerance appear."

c. "Yes; any fluid that returns is a sign of intolerance, so the feed is stopped whenever it occurs."

d. "Never; residuals are no longer measured for any reason, even if the abdomen becomes distended."

Answer: b — In one Canadian provincial guide, routine gastric residual checks are not done unless ordered and are reserved for patients with other signs of intolerance (section 24.2, Giving Tube Feeds Safely). Routine checks every 4 hours are no longer standard. Some fluid normally returns from the stomach and does not by itself mean intolerance. Residuals may still be checked when ordered or when signs such as distension appear.

12. [CORE] Why are hospitals using ENFit connectors on enteral feeding equipment?

a. They allow enteral syringes to fit IV lines too, so one syringe can be used for every route

b. They hold the tube firmly in place, so the nurse no longer needs to check the mark at the nostril

c. They allow formula to flow faster, so continuous feeds can be finished in fewer hours each day

d. They are designed so enteral equipment cannot connect to IV or other non-enteral ports

Answer: d — ENFit connectors are designed so enteral equipment cannot connect to IV or other non-enteral ports, to prevent misconnections (section 24.2, Giving Tube Feeds Safely). Allowing one syringe to fit every route is exactly the error they prevent. Connectors do not secure the tube or replace placement checks. They do not change the flow rate.

13. [CORE] A patient receiving parenteral nutrition through a peripherally inserted central catheter has a capillary glucose of 14.6 mmol/L. What should the nurse do?

a. Report the result to the prescriber, follow the glucose orders and keep monitoring as ordered

b. Stop the parenteral nutrition at once and hang normal saline until the next bag is delivered from pharmacy

c. Slow the infusion to half the ordered rate and recheck the glucose at the end of the shift

d. Move the infusion to a peripheral IV line so the dextrose enters the bloodstream more slowly

Answer: a — The dextrose in parenteral nutrition can cause hyperglycemia; the nurse reports, follows orders and keeps monitoring (section 24.2, Parenteral Nutrition). The nurse does not stop the infusion or change its rate without an order. A concentrated central formula is not moved to a peripheral line, and the route does not change the glucose load.

14. [CORE] A nurse watches an older adult with Parkinson disease eat lunch. Which findings suggest dysphagia? Select all that apply.

a. A wet, gurgly voice after sips of water

b. Coughing and throat clearing during the meal

c. Taking much longer than usual to finish meals

d. Asking for a second helping of dessert

e. Two chest infections with fever in the past 3 months

f. A clear, strong voice after eating and drinking

Answer: a, b, c, e — A wet voice, coughing or throat clearing during meals, needing extra time to eat, and repeated chest infections are signs of dysphagia (section 24.3, Recognizing Dysphagia). A good appetite does not suggest a swallowing problem. A clear, strong voice after eating does not point to dysphagia, though it does not rule out silent aspiration.

15. [CORE] After a stroke, a patient who is waiting for a swallowing assessment drinks some water during a family visit and does not cough. His daughter says this proves he swallows safely. What is the nurse's best response?

a. "That is reassuring; a person who swallows without coughing is protecting his airway well."

b. "Not coughing is a good sign, so he can keep having water until the assessment takes place."

c. "Some people aspirate without coughing, so he needs to stay on his plan until he is assessed."

d. "Coughing only matters when people eat solid food, so small sips of water are safe for him today."

Answer: c — Silent aspiration happens without a cough, so the absence of coughing does not show a safe swallow; he stays on his plan until the speech-language pathologist assesses him (section 24.3, Recognizing Dysphagia; Screening, Assessment and Diets). Thin water is often the hardest consistency to control, and a failed or pending screen means nothing by mouth. Coughing with fluids matters as much as coughing with solids.

16. [CORE] A patient's plan calls for IDDSI Level 2 (mildly thick) drinks. Which description fits this level?

a. Flows as quickly as water and can be drunk through any straw or cup

b. Pours off a spoon and can be sipped, but flows more slowly than water

c. Holds its shape on a spoon and cannot be poured, sipped or sucked through a straw

d. Smooth and lump-free, and falls slowly in small blobs between the tines of a fork

Answer: b — Level 2 drinks pour off a spoon and can be sipped but flow more slowly than thin drinks (section 24.3, Screening, Assessment and Diets). Flowing like water describes Level 0. Holding shape on a spoon describes Level 4 (extremely thick). Dripping slowly through a fork describes Level 3.

17. [CORE] A patient on an IDDSI Level 4 (pureed) diet is prescribed an enteric-coated tablet. What should the nurse do?

a. Crush the tablet finely and mix it into a spoonful of pureed fruit so that it fits the diet level

b. Give the tablet whole with a glass of thin water after making sure the patient is sitting upright

c. Split the tablet in half so that each piece is easier to swallow with a spoonful of thick drink

d. Keep the tablet whole and ask the pharmacist about another form that suits the diet level

Answer: d — Enteric-coated and modified-release products are never crushed or split; the pharmacist advises on a suitable form (section 24.3, Screening, Assessment and Diets; ISMP Canada, 2013). Crushing destroys the coating. A person on pureed food may not swallow a whole tablet safely, and pills are not given with thin fluids when thin fluids are restricted. Splitting also damages the coating.

18. [RN] A 34-year-old with a BMI of 15.5 kg/m² who has eaten almost nothing for 10 days started enteral feeds yesterday. Phosphate was 1.05 mmol/L before feeding and is 0.62 mmol/L today. Which interpretation and action are best?

a. The drop of about 40% after feeding began fits refeeding syndrome; report it promptly and expect replacement and a slower feed

b. The new value is most likely a laboratory error, because it changed so much within a single day, so the test should just be repeated

c. Phosphate always dips on the second day of feeding and returns to normal without treatment, so the feed should continue

d. The fall shows that the feed is being used well by the body, so the rate should be increased to reach the goal sooner

Answer: a — A fall of more than 30% in phosphate within 5 days of starting nutrition in an undernourished person fits severe refeeding syndrome by ASPEN's definition; the nurse reports promptly, and the prescriber and dietitian may replace electrolytes and slow the feed (section 24.1, Going Deeper: Refeeding Syndrome). The patient's risk makes a true fall likely, so it should not be dismissed as error. Low phosphate can weaken breathing muscles and the heart and needs treatment. Increasing the feed would worsen the shift.

19. [RN] A patient who has received parenteral nutrition through a central venous catheter for 9 days develops chills and a temperature of 38.7 °C, with no other obvious source. What should the nurse suspect, and what should the nurse do first?

a. Hyperglycemia from the dextrose load; give insulin by sliding scale and continue the infusion at the same rate

b. A reaction to the lipid emulsion; slow the infusion to half the ordered rate and recheck the temperature in an hour

c. A catheter-related bloodstream infection; report at once and prepare for cultures and sepsis screening per orders

d. Refeeding syndrome; hold the next bag and give an oral phosphate supplement from the ward stock right away

Answer: c — Fever and chills in a patient with a central line and parenteral nutrition suggest a catheter-related bloodstream infection; the nurse reports at once and prepares for cultures and sepsis assessment per orders (section 24.2, Parenteral Nutrition; Chapter 4). Hyperglycemia does not cause fever and chills, and insulin is given only by order. The nurse does not change the rate without an order. Refeeding syndrome causes falling electrolytes, not fever, and nurses do not give ward-stock supplements without an order.

20. [RN] Which patient meets the GLIM criteria for malnutrition?

a. A 66-year-old man admitted with pneumonia whose BMI is 24 kg/m², with stable weight and his usual intake

b. A 72-year-old woman who lost 7% of her weight in 3 months and has eaten under half her needs for 2 weeks

c. A 50-year-old man after surgery with a serum albumin of 28 g/L, stable weight and his usual intake

d. A 45-year-old runner who lost 6% of her weight in 4 months while eating as usual, with no illness at all

Answer: b — GLIM requires at least one phenotypic criterion and at least one etiologic criterion (section 24.1, Signs and Causes of Malnutrition). A weight loss of more than 5% within six months is phenotypic, and eating half or less of energy needs for more than a week is etiologic. Pneumonia is an etiologic criterion (inflammation) but there is no phenotypic criterion. Albumin is not a GLIM criterion, and surgery alone supplies only inflammation. Weight loss with usual intake and no illness meets only a phenotypic criterion.

Case: Ernest Kowalczyk (Questions 21–26): Ernest Kowalczyk, 79, was admitted 2 days ago to a medical unit with a urinary tract infection. He takes apixaban for atrial fibrillation and metoprolol for hypertension, and he has taken naproxen bought at a pharmacy for 3 weeks for hip pain. At 1000 he tells the practical nurse (PN) he has had two black, sticky, foul-smelling stools this morning and feels dizzy when he stands. Vital signs at 1000: temperature 37.0 °C, heart rate 94 (88 at 0800 and 72 yesterday), blood pressure 112/66 mm Hg (138/80 mm Hg yesterday), respiratory rate 20, SpO_2 95% on room air. His skin is dark brown; his conjunctivae and lips look paler than at admission. Hemoglobin is 101 g/L (124 g/L on admission). Blood urea has risen from 6.8 to 11.2 mmol/L.

21. [CORE] Which findings require immediate follow-up by the nurse? Select all that apply.

a. Temperature 37.0 °C after 2 days of treatment for a urinary tract infection

b. Two black, sticky stools this morning with a foul smell

c. Hemoglobin of 101 g/L, down from 124 g/L on admission

d. Oxygen saturation of 95% on room air with a respiratory rate of 20

e. Dizziness when he stands up, which is new this morning

f. Blood pressure of 112/66 mm Hg compared with 138/80 mm Hg yesterday

g. Hip pain for which he has been taking naproxen for 3 weeks

Answer: b, c, e, f — Melena (b), a 23 g/L drop in hemoglobin (c), new postural dizziness (e) and a fall in blood pressure (f) are cues of an active upper GI bleed with early hypovolemia (section 24.5). His temperature (a) is normal and shows the infection is responding. An SpO_2 of 95% with a respiratory rate of 20 (d) is acceptable for him and is not the urgent problem. Hip pain (g) explains why he took naproxen, which matters for risk, but the pain itself does not need immediate follow-up.

22. [CORE] The nurse notes that Mr. Kowalczyk's heart rate has risen only to 94. Which explanation best accounts for this?

a. Bleeding from the upper GI tract does not change heart rate until a person has lost more than half of their blood volume

b. Apixaban slows the sinus node, so patients taking it rarely develop a fast heart rate during bleeding

c. Metoprolol blunts the heart-rate rise that normally helps a person compensate for blood loss

d. A heart rate below 100 in an adult older than 75 shows that compensation for blood loss is adequate

Answer: c — Beta-blockers such as metoprolol blunt the sympathetic rise in heart rate that helps people tolerate blood loss, and older adults may also respond less, so a modest rise can hide a serious bleed (section 24.5). Heart rate normally rises early, long before half the blood volume is lost (a). Apixaban is an anticoagulant and does not slow the sinus node (b); it makes bleeding heavier. A heart rate under 100 (d) does not prove adequate compensation, especially with a falling blood pressure and hemoglobin.

23. [CORE] Which problem should the nurse address first?

a. Risk of hypovolemic shock from ongoing upper GI bleeding

b. Risk of falling because of dizziness when he stands up

c. Lack of knowledge about the risks of over-the-counter NSAIDs

d. Risk of acute kidney injury from naproxen and the infection

Answer: a — Ongoing blood loss that leads to shock threatens his life and drives the other problems, so it comes first (section 24.5; Chapter 6). Fall risk (b) is real and is managed at the same time by keeping him in bed with help, but it follows from the bleed. Teaching about NSAIDs (c) belongs to discharge planning once he is stable. Kidney injury (d) is possible and is monitored, but it is not the most urgent problem.

24. [CORE] The physician is notified and comes to assess Mr. Kowalczyk. Which plan should the nurse expect while he waits for endoscopy?

a. Clear fluids by mouth, oral iron three times a day and a repeat hemoglobin tomorrow morning

b. Continue apixaban to prevent stroke, and give naproxen with food to protect his stomach

c. Transfuse two units of red cells at once, because his hemoglobin has fallen below 110 g/L

d. NPO, IV access, group and screen, an IV PPI, holding apixaban and endoscopy within 24 hours

Answer: d — The expected plan is NPO for endoscopy, IV access, blood work with group and screen, an IV PPI that does not delay the procedure, holding the anticoagulant as the prescriber directs and endoscopy within 24 hours (section 24.5). Oral intake and oral iron with a next-day check (a) ignore an active bleed. Continuing apixaban and naproxen (b) would worsen bleeding; naproxen is a cause. A fall below 110 g/L is not a transfusion threshold; the decision depends on his hemoglobin, his cardiovascular history and his clinical status, so he is reassessed as results and vital signs change rather than given two units at once (c; section 20.6).

25. [CORE] At 1130, Mr. Kowalczyk vomits about 200 mL of bright red blood. He is drowsy but answers questions. Heart rate is 112 and blood pressure is 90/54 mm Hg. Which action should the nurse take first?

a. Insert a nasogastric tube to remove blood from his stomach before calling anyone

b. Turn him onto his side, stay with him and call the rapid response team

c. Measure his capillary refill time and document the volume of emesis in the chart

d. Give the next scheduled dose of metoprolol to slow his heart rate

Answer: b — Protecting his airway and getting immediate help come first: turning him on his side lowers the risk of aspiration, and his vital signs meet rapid response criteria (section 24.5; Chapter 6). A nasogastric tube (a) needs an order and is not the first action. Capillary refill and documentation (c) matter but must not delay escalation. Giving metoprolol (d) would lower his blood pressure further and hide his response to bleeding; the nurse holds the dose and discusses it with the prescriber.

26. [CORE] Mr. Kowalczyk has endoscopic treatment of a bleeding gastric ulcer and is receiving a high-dose IV PPI. Which finding the next morning best shows that the treatment is working?

a. He passed one more black stool overnight, and his heart rate is 104

b. His blood pressure is 102/60 mm Hg, and he says he is thirsty

c. Heart rate 80, blood pressure 128/74 mm Hg and hemoglobin steady at 92 g/L on two checks

d. He has had no stool since the procedure, and he is sleeping more than usual

Answer: c — Stable vital signs close to his usual values and a hemoglobin that holds steady on repeated checks show that bleeding has stopped (section 24.5). One more black stool can be old blood, but a heart rate of 104 (a) suggests ongoing loss. A blood pressure of 102/60 mm Hg with thirst (b) suggests he is still volume depleted. No stool (d) does not prove the bleed has stopped, and increased sleepiness in an older adult needs assessment (Chapter 8).

27. [CORE] A 52-year-old with heartburn for 2 years asks for a refill of an over-the-counter antacid. Which additional finding should the nurse report to the prescriber promptly?

a. Food sticking in the chest when swallowing, with 6 kg of weight loss she did not plan

b. Heartburn that is worse after large meals and when she lies down soon after eating

c. A sour taste in the mouth on waking that clears after she brushes her teeth

d. Relief of burning within minutes of chewing an antacid tablet

Answer: a — Dysphagia and unplanned weight loss are alarm features that call for prompt assessment, usually with endoscopy (section 24.4). Symptoms that worsen after large meals and when lying down (b), and a sour taste on waking (c), are typical GERD symptoms. Quick relief with an antacid (d) is expected and is not an alarm feature.

28. [CORE] The nurse teaches a patient with GERD about lifestyle measures. Which statement shows the patient needs more teaching?

a. "I'll put blocks under the head of my bed because my heartburn wakes me at night."

b. "I'll keep a note of which foods seem to bring on my heartburn so I can avoid them."

c. "I'll ask about the smoking cessation program, since tobacco can make reflux worse."

d. "I'll have my main meal later in the evening, right before I go to bed, so I sleep better."

Answer: d — Eating within 2 to 3 hours of bedtime worsens reflux, so a large meal right before bed needs correcting (section 24.4). Raising the head of the bed for night-time symptoms (a), avoiding personal trigger foods (b) and avoiding tobacco (c) are all recommended.

29. [CORE] A patient is booked for a urea breath test for H. pylori in 10 days. She takes pantoprazole every morning for heartburn. Which action should the nurse take?

a. Tell her to take an extra pantoprazole the morning of the test so the result is clearer

b. Contact the prescriber, because a PPI should usually be stopped 2 weeks before testing

c. Tell her the PPI has no effect on the test and she should keep taking it as usual

d. Advise her to switch to a bismuth product for her heartburn until the test is done

Answer: b — PPIs can suppress H. pylori and cause a false-negative result, so guidance advises stopping them 2 weeks before testing; with only 10 days left, the nurse contacts the prescriber about the timing (section 24.4). An extra dose (a) would make a false-negative more likely. Saying the PPI has no effect (c) is wrong. Bismuth (d) should also be avoided for 4 weeks before testing; an antacid or H2-receptor antagonist can be used for symptoms instead.

30. [CORE] A patient starting bismuth quadruple therapy for H. pylori asks why there are so many pills. Which response by the nurse is best?

a. "You can stop the antibiotics once your stomach pain is gone, but keep taking the acid reducer."

b. "Take whichever pills you can manage; even half the doses will usually clear the infection."

c. "Take every dose for the full 14 days. A pharmacy blister pack can help you keep track."

d. "If you miss a day, take a double dose of everything the next day to make up for it."

Answer: c — Canadian guidance recommends 14 days for every regimen, and missed doses lower the cure rate; adherence aids such as blister packs help (section 24.4). Stopping antibiotics when pain settles (a) or taking only some doses (b) risks treatment failure and resistance. Doubling doses (d) is unsafe and is not how missed doses are handled; the patient asks the pharmacist.

31. [CORE] A patient with known peptic ulcer disease suddenly reports severe abdominal pain. The abdomen is rigid and very tender, and heart rate has risen from 84 to 118. Which action should the nurse take first?

a. Keep the patient NPO and notify the physician urgently, using SBAR

b. Give the ordered oral antacid and reassess the pain in 30 minutes

c. Encourage the patient to walk to help relieve gas and bloating

d. Apply a warm compress to the abdomen and give the ordered acetaminophen by mouth

Answer: a — Sudden severe pain with a rigid abdomen and a rising heart rate suggests perforation, a surgical emergency in which delay raises mortality; the nurse keeps the patient NPO and escalates at once (section 24.4; Chapter 6). An oral antacid (b) and oral acetaminophen (d) add to stomach contents and delay escalation; heat can mask findings. Walking (c) treats the cues as gas and delays care.

32. [CORE] A nurse reviews the medication list of an older adult who has taken a proton pump inhibitor for 6 years. Which conditions have been linked with long-term PPI use? Select all that apply.

a. Vitamin B12 deficiency

b. High blood potassium

c. Low blood magnesium

d. Hip and other fractures

e. Clostridioides difficile infection

f. Community-acquired pneumonia

g. Low blood sugar during sleep

Answer: a, c, d, e, f — The Canadian PPI deprescribing guideline and product monographs link long-term PPI use with vitamin B12 deficiency (a), low magnesium (c), fractures (d), C. difficile infection (e) and community-acquired pneumonia (f) (section 24.4). High potassium (b) and nocturnal low blood sugar (g) are not listed harms of PPIs.

33. [CORE] The nurse is assessing a patient with dark brown skin for possible anemia after an upper GI bleed. Which approach is best?

a. Rely on the colour of the palms under the room's overhead fluorescent lighting

b. Ask the patient whether their skin looks paler than usual to them today

c. Check capillary refill alone, because colour cannot be judged on dark skin

d. Inspect the conjunctivae and oral mucosa in natural light against usual colour

Answer: d — Pallor on darker skin may look ash grey or yellow-brown and is best seen in the conjunctivae, lips and oral mucosa in natural light, compared with the person's usual colour, and confirmed with vital signs and hemoglobin (section 24.5). Fluorescent overhead light (a) distorts colour. The patient's own view (b) is useful history but is not an assessment. Colour can be assessed on dark skin with the right technique, and capillary refill alone (c) is not enough.

34. [CORE] In an Ontario hospital, a registered practical nurse (RPN) is asked to insert a nasogastric tube for a patient. Which statement about the RPN's authority is correct?

a. The RPN may insert the tube on their own judgment, because it is a routine nursing activity

b. The RPN may insert the tube with an order or directive if competent and if employer policy allows

c. Only an RN may insert a nasogastric tube, because it is a controlled act

d. The RPN may insert the tube only if a physician is present at the bedside

Answer: b — Putting an instrument beyond the point where the nasal passages normally narrow is a controlled act authorized to both RNs and RPNs; it needs an order or directive, the nurse must be competent and employer policy can limit it (Scope in Practice box, section 24.2). It is not something a nurse may initiate in a public hospital (a). The act is not limited to RNs (c), and the law does not require a physician at the bedside (d).

35. [CORE] A patient living with obesity is admitted for cellulitis. Which nursing action best reflects respectful, weight-inclusive care?

a. Ask the patient's permission before talking about weight or measuring them, and weigh them in private

b. Begin admission teaching by explaining that weight loss will help the cellulitis heal faster

c. Use the standard adult blood pressure cuff for all patients, so readings are consistent across the unit

d. Record "morbidly obese" in the nursing assessment so that other staff can plan equipment needs

Answer: a — The Canadian guideline recommends asking permission before talking about weight or measuring, and privacy protects dignity (section 24.6). Assuming the complaint is about weight (b) is a form of weight bias. A cuff that is too small (c) gives falsely high readings; right-sized equipment is needed. Stigmatizing labels (d) should be avoided; person-first language and a clear equipment plan meet the same need.

36. [CORE] A patient 6 weeks after Roux-en-Y gastric bypass reports cramping, nausea, sweating and a fast heart rate about 20 minutes after eating. Which teaching is most appropriate?

a. "Drink a large glass of fruit juice with each meal to replace the fluid that you are losing."

b. "These symptoms mean the surgery has failed, so you should call 9-1-1 every time they happen."

c. "Avoid concentrated sweets, eat small meals and wait about 30 minutes after eating to drink."

d. "Lie flat for an hour after meals and add an extra dessert to keep up your energy."

Answer: c — These are signs of dumping syndrome, which is reduced by avoiding concentrated sweets and high-fat foods, eating small meals and separating liquids from solids (section 24.6). Fruit juice with meals (a) and extra dessert (d) add sugar and liquid at the wrong time and worsen symptoms. Dumping does not mean surgery has failed (b), although severe or new symptoms should be reported to the bariatric team.

37. [CORE] A patient is preparing for discharge 2 days after sleeve gastrectomy. Which statement shows understanding of medication safety after bariatric surgery?

a. "I'll take ibuprofen for my incision pain because it works better than acetaminophen."

b. "I can stop my multivitamin once I am eating regular food again in a few months."

c. "I'll crush my extended-release blood pressure tablet so it is easier to swallow."

d. "I'll use acetaminophen for pain and ask the pharmacist before I crush any tablet."

Answer: d — Acetaminophen is the usual pain reliever after bariatric surgery, and only tablets the pharmacist confirms can be crushed should be crushed (section 24.6). NSAIDs such as ibuprofen (a) are avoided because of ulcer risk. Supplements are lifelong (b). Crushing an extended-release tablet (c) can release the whole dose at once; early after surgery, immediate-release or liquid forms are used instead.

38. [RN] A 46-year-old arrives in the emergency department after one episode of melena. Vital signs and hemoglobin are normal, and the Glasgow-Blatchford score is 0. How should the nurse interpret this score?

a. The patient has a high risk of rebleeding and needs endoscopy within the next hour

b. The patient is at very low risk and may not need admission or inpatient endoscopy

c. The score rules out a peptic ulcer, so no follow-up or teaching is needed

d. The score cannot be calculated until endoscopy has shown the source of bleeding

Answer: b — The international consensus suggests that a Glasgow-Blatchford score of 1 or less identifies patients at very low risk who may not need admission or inpatient endoscopy, with clinical judgment and follow-up (Going Deeper box, section 24.5). A score of 0 does not mean high risk (a). The score estimates risk; it does not rule out an ulcer, and the patient still needs follow-up and teaching (c). The score uses pre-endoscopy data such as urea, hemoglobin and vital signs (d).

39. [RN] A medication review is done for four adults who have taken a PPI for more than a year. For which patient is deprescribing the PPI most appropriate to discuss?

a. A 64-year-old whose heartburn from mild esophagitis resolved after an 8-week course

b. A 70-year-old with Barrett esophagus who has regular follow-up with a gastroenterologist

c. A 75-year-old with a documented bleeding duodenal ulcer last year who takes ASA daily

d. A 68-year-old with severe (grade D) esophagitis found on endoscopy 2 years ago

Answer: a — The Canadian deprescribing guideline applies to adults with resolved symptoms from GERD or mild to moderate esophagitis, who can lower the dose or switch to on-demand use (section 24.4). Barrett esophagus (b), a history of bleeding ulcer with ongoing ASA (c) and severe esophagitis (d) are reasons to continue a PPI.

40. [RN] On the day of discharge, 2 days after sleeve gastrectomy, a patient has a heart rate of 124 (88 yesterday), a temperature of 38.3 °C and abdominal pain that spreads to the left shoulder. A contrast study yesterday was normal. Which action should the nurse take?

a. Give the ordered hydromorphone and recheck vital signs in 4 hours, because pain explains the tachycardia

b. Proceed with discharge, because yesterday's normal contrast study rules out a leak

c. Encourage fluids by mouth and deep breathing, and report the findings at the next physician round

d. Hold the discharge and notify the surgeon urgently, because these are signs of an anastomotic leak

Answer: d — Tachycardia, fever and abdominal pain that often spreads to the left shoulder are the most common signs of a leak after sleeve gastrectomy, and imaging can be normal even when a leak is present, so the nurse escalates at once (section 24.6). Explaining the heart rate as pain (a) delays treatment of a life-threatening complication. A normal study does not rule out a leak (b). Waiting for rounds (c) delays care, and extra oral fluids may be unsafe if a leak is present.

References

Alberta Health Services. (2022). *Planning a healthy menu: Enhancing health through nutrition. Section 5: Dysphagia/texture modified diets*. https://albertahealthservices.ca/assets/info/nutrition/if-nfs-pahm-s5-texture-modified-diets.pdf

Allard, J. P., Keller, H., Jeejeebhoy, K. N., Laporte, M., Duerksen, D. R., Gramlich, L., Payette, H., Bernier, P., Vesnaver, E., Davidson, B., Teterina, A., & Lou, W. (2016). Malnutrition at hospital admission—Contributors and effect on length of stay: A prospective cohort study from the Canadian Malnutrition Task Force. *Journal of Parenteral and Enteral Nutrition, 40*(4), 487–497. https://doi.org/10.1177/0148607114567902

American Society for Parenteral and Enteral Nutrition. (2014). *Nursing care of the patient with an enteral feeding tube: What procedures should be updated with the ENFit connector*. https://nutritioncare.org/WorkArea/DownloadAsset.aspx?id=3186

American Speech-Language-Hearing Association. (n.d.). *Adult dysphagia* [Practice portal]. https://www.asha.org/practice-portal/clinical-topics/adult-dysphagia/

Ayers, P., Adams, S., Boullata, J., Gervasio, J., Holcombe, B., Kraft, M. D., Marshall, N., Neal, A., Sacks, G., Seres, D. S., Worthington, P., & American Society for Parenteral and Enteral Nutrition. (2014). A.S.P.E.N. parenteral nutrition safety consensus recommendations. *Journal of Parenteral and Enteral Nutrition, 38*(3), 296–333. https://doi.org/10.1177/0148607113511992

Barkun, A. N., Almadi, M., Kuipers, E. J., Laine, L., Sung, J., Tse, F., Leontiadis, G. I., Abraham, N. S., Calvet, X., Chan, F. K. L., Douketis, J., Enns, R., Gralnek, I. M., Jairath, V., Jensen, D., Lau, J., Lip, G. Y. H., Loffroy, R., Maluf-Filho, F., … Bardou, M. (2019). Management of nonvariceal upper gastrointestinal bleeding: Guideline recommendations from the International Consensus Group. *Annals of Internal Medicine, 171*(11), 805–822. https://doi.org/10.7326/M19-1795

Blatchford, O., Murray, W. R., & Blatchford, M. (2000). A risk score to predict need for treatment for upper-gastrointestinal haemorrhage. *The Lancet, 356*(9238), 1318–1321. https://doi.org/10.1016/S0140-6736(00)02816-6

Bruyère Research Institute. (2018). *Proton pump inhibitor (PPI) deprescribing algorithm*. deprescribing.org. https://deprescribing.org/wp-content/uploads/2018/08/ppi-deprescribing-algorithm_2018_En.pdf

Canadian Cancer Society. (n.d.). *Risks for esophageal cancer*. Retrieved October 26, 2026, from https://cancer.ca/en/cancer-information/cancer-types/esophageal/risks

Cederholm, T., Jensen, G. L., Correia, M. I. T. D., Gonzalez, M. C., Fukushima, R., Higashiguchi, T., Baptista, G., Barazzoni, R., Blaauw, R., Coats, A., Crivelli, A., Evans, D. C., Gramlich, L., Fuchs-Tarlovsky, V., Keller, H., Llido, L., Malone, A., Mogensen, K. M., Morley, J. E., … Compher, C. (2019). GLIM criteria for the diagnosis of malnutrition – A consensus report from the global clinical nutrition community. *Clinical Nutrition, 38*(1), 1–9. https://doi.org/10.1016/j.clnu.2018.08.002

Cheung, J., Goodman, K. J., Girgis, S., Bailey, R., Morse, J., Fedorak, R. N., Geary, J., Fagan-Garcia, K., Veldhuyzen van Zanten, S., & the CANHelp Working Group. (2014). Disease manifestations of *Helicobacter pylori* infection in Arctic Canada: Using epidemiology to address community concerns. *BMJ Open, 4*(1), Article e003689. https://doi.org/10.1136/bmjopen-2013-003689

Cichero, J. A. Y., Lam, P., Steele, C. M., Hanson, B., Chen, J., Dantas, R. O., Duivestein, J., Kayashita, J., Lecko, C., Murray, J., Pillay, M., Riquelme, L., & Stanschus, S. (2017). Development of international terminology and definitions for texture-modified foods and thickened fluids used in dysphagia management: The IDDSI framework. *Dysphagia, 32*(2), 293–314. https://doi.org/10.1007/s00455-016-9758-y

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

da Silva, J. S. V., Seres, D. S., Sabino, K., Adams, S. C., Berdahl, G. J., Citty, S. W., Cober, M. P., Evans, D. C., Greaves, J. R., Gura, K. M., Michalski, A., Plogsted, S., Sacks, G. S., Tucker, A. M., Worthington, P., Walker, R. N., Ayers, P., & Parenteral Nutrition Safety and Clinical Practice Committees, American Society for Parenteral and Enteral Nutrition. (2020). ASPEN consensus recommendations for refeeding syndrome. *Nutrition in Clinical Practice, 35*(2), 178–195. https://doi.org/10.1002/ncp.10474

Eckert, K. F., & Cahill, L. E. (2018). Malnutrition in Canadian hospitals. *CMAJ, 190*(40), E1207. https://doi.org/10.1503/cmaj.180108

Evans, D. C., Corkins, M. R., Malone, A., Miller, S., Mogensen, K. M., Guenter, P., Jensen, G. L., & ASPEN Malnutrition Committee. (2021). The use of visceral proteins as nutrition markers: An ASPEN position paper. *Nutrition in Clinical Practice, 36*(1), 22–28. https://doi.org/10.1002/ncp.10588

Fallone, C. A., Chiba, N., van Zanten, S. V., Fischbach, L., Gisbert, J. P., Hunt, R. H., Jones, N. L., Render, C., Leontiadis, G. I., Moayyedi, P., & Marshall, J. K. (2016). The Toronto Consensus for the treatment of *Helicobacter pylori* infection in adults. *Gastroenterology, 151*(1), 51–69. https://doi.org/10.1053/j.gastro.2016.04.006

Farrell, B., Pottie, K., Thompson, W., Boghossian, T., Pizzola, L., Rashid, F. J., Rojas-Fernandez, C., Walsh, K., Welch, V., & Moayyedi, P. (2017). Deprescribing proton pump inhibitors: Evidence-based clinical practice guideline. *Canadian Family Physician, 63*(5), 354–364. https://www.cfp.ca/content/63/5/354

Heart and Stroke Foundation of Canada. (2019). *Canadian stroke best practice recommendations: Stroke rehabilitation. Section 7: Assessment and management of dysphagia and malnutrition following stroke* (6th ed.). https://www.strokebestpractices.ca/recommendations/stroke-rehabilitation/assessment-and-management-of-dysphagia-and-malnutrition-following-stroke

Institute for Safe Medication Practices Canada. (2013). Some liquid medications may be unsuitable for administration by enteral tube. *ISMP Canada Safety Bulletin, 13*(5). https://ismpcanada.ca/wp-content/uploads/ISMPCSB2013-05_LiquidMedicationsEnteralTube.pdf

International Dysphagia Diet Standardisation Initiative. (2026). *Complete IDDSI framework: Detailed definitions* (Version 2.2). https://www.iddsi.org/images/Publications-Resources/DetailedDefnTestMethods/English/V2-2DetailedDefinitionsEnglishHR30Jul2026.pdf

Katz, P. O., Dunbar, K. B., Schnoll-Sussman, F. H., Greer, K. B., Yadlapati, R., & Spechler, S. J. (2022). ACG clinical guideline for the diagnosis and management of gastroesophageal reflux disease. *The American Journal of Gastroenterology, 117*(1), 27–56. https://doi.org/10.14309/ajg.0000000000001538

Keller, H., Laur, C., Atkins, M., Bernier, P., Butterworth, D., Davidson, B., Hotson, B., Nasser, R., Laporte, M., Marcell, C., Ray, S., & Bell, J. (2018). Update on the Integrated Nutrition Pathway for Acute Care (INPAC): Post implementation tailoring and toolkit to support practice improvements. *Nutrition Journal, 17*(1), Article 2. https://doi.org/10.1186/s12937-017-0310-1

Kim, J., Azagury, D., Eisenberg, D., DeMaria, E., & Campos, G. M. (2015). ASMBS position statement on prevention, detection, and treatment of gastrointestinal leak after gastric bypass and sleeve gastrectomy, including the roles of imaging, surgical exploration, and nonoperative management. *Surgery for Obesity and Related Diseases, 11*(4), 739–748. https://doi.org/10.1016/j.soard.2015.05.001

Lemyze, M. (2010). The placement of nasogastric tubes. *CMAJ, 182*(8), 802. https://doi.org/10.1503/cmaj.091099

Lortie, M.-A., & Charbonney, E. (2016). Confirming placement of nasogastric feeding tubes. *CMAJ, 188*(5), E96. https://doi.org/10.1503/cmaj.150609

Malfertheiner, P., Megraud, F., Rokkas, T., Gisbert, J. P., Liou, J.-M., Schulz, C., Gasbarrini, A., Hunt, R. H., Leja, M., O'Morain, C., Rugge, M., Suerbaum, S., Tilg, H., Sugano, K., & El-Omar, E. M. (2022). Management of *Helicobacter pylori* infection: The Maastricht VI/Florence consensus report. *Gut, 71*(9), 1724–1762. https://doi.org/10.1136/gutjnl-2022-327745

Mechanick, J. I., Apovian, C., Brethauer, S., Garvey, W. T., Joffe, A. M., Kim, J., Kushner, R. F., Lindquist, R., Pessah-Pollack, R., Seger, J., Urman, R. D., Adams, S., Cleek, J. B., Correa, R., Figaro, M. K., Flanders, K., Grams, J., Hurley, D. L., Kothari, S., … Still, C. D. (2020). Clinical practice guidelines for the perioperative nutrition, metabolic, and nonsurgical support of patients undergoing bariatric procedures – 2019 update: Cosponsored by American Association of Clinical Endocrinologists/American College of Endocrinology, The Obesity Society, American Society for Metabolic & Bariatric Surgery, Obesity Medicine Association, and American Society of Anesthesiologists. *Surgery for Obesity and Related Diseases, 16*(2), 175–247. https://doi.org/10.1016/j.soard.2019.10.025

Moayyedi, P. M., Lacy, B. E., Andrews, C. N., Enns, R. A., Howden, C. W., & Vakil, N. (2017). ACG and CAG clinical guideline: Management of dyspepsia. *The American Journal of Gastroenterology, 112*(7), 988–1013. https://doi.org/10.1038/ajg.2017.154

Nova Scotia Health Library. (2026). *Clinical practice nursing: Enteral*. https://library.nshealth.ca/Clinical-Practice-Nursing/Enteral

Oakland, K., Chadwick, G., East, J. E., Guy, R., Humphries, A., Jairath, V., McPherson, S., Metzner, M., Morris, A. J., Murphy, M. F., Tham, T., Uberoi, R., Veitch, A. M., Wheeler, J., Regan, C., & Hoare, J. (2019). Diagnosis and management of acute lower gastrointestinal bleeding: Guidelines from the British Society of Gastroenterology. *Gut, 68*(5), 776–789. https://doi.org/10.1136/gutjnl-2018-317807

Obesity Canada. (2020a). *Bariatric surgery: Postoperative management* [Canadian Adult Obesity Clinical Practice Guidelines chapter]. https://obesitycanada.ca/?p=4614

Obesity Canada. (2020b). *Bariatric surgery: Surgical options and outcomes* [Canadian Adult Obesity Clinical Practice Guidelines chapter]. https://obesitycanada.ca/?p=4612

Pedersen, S. D., Manjoo, P., Dash, S., Jain, A., Pearce, N., & Poddar, M. (2025). Pharmacotherapy for obesity management in adults: 2025 clinical practice guideline update. *CMAJ, 197*(27), E797–E809. https://doi.org/10.1503/cmaj.250502

Pharmascience Inc. (2026). *Acid controller maximum strength (famotidine tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00084317.PDF

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Schiller, A. M., Howard, J. T., & Convertino, V. A. (2017). The physiology of blood loss and shock: New insights from a human laboratory model of hemorrhage. *Experimental Biology and Medicine, 242*(8), 874–883. https://doi.org/10.1177/1535370217694099

Statistics Canada. (2024, March 4). *An overview of weight and height measurements on World Obesity Day* [StatsCAN Plus]. https://www.statcan.gc.ca/o1/en/plus/5742-overview-weight-and-height-measurements-world-obesity-day

Sun Pharma Canada. (2025). *SPC-Pantoprazole (pantoprazole sodium enteric-coated tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00082007.PDF

Tarasconi, A., Coccolini, F., Biffl, W. L., Tomasoni, M., Ansaloni, L., Picetti, E., Molfino, S., Shelat, V., Cimbanassi, S., Weber, D. G., Abu-Zidan, F. M., Campanile, F. C., Di Saverio, S., Baiocchi, G. L., Casella, C., Kelly, M. D., Kirkpatrick, A. W., Leppaniemi, A., Moore, E. E., … Catena, F. (2020). Perforated and bleeding peptic ulcer: WSES guidelines. *World Journal of Emergency Surgery, 15*, Article 3. https://doi.org/10.1186/s13017-019-0283-9

The Ottawa Hospital. (2023). *Your guide to bariatric surgery* (P1340). https://www.ottawahospital.on.ca/sites/default/files/2026-07/your-guide-to-bariatric-surgery.pdf

Wharton, S., Lau, D. C. W., Vallis, M., Sharma, A. M., Biertho, L., Campbell-Scherer, D., Adamo, K., Alberga, A., Bell, R., Boulé, N., Boyling, E., Brown, J., Calam, B., Clarke, C., Crowshoe, L., Divalentino, D., Forhan, M., Freedhoff, Y., Gagner, M., … Wicklum, S. (2020). Obesity in adults: A clinical practice guideline. *CMAJ, 192*(31), E875–E891. https://doi.org/10.1503/cmaj.191707

25 Lower Gastrointestinal Disorders

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Assess bowel function and manage constipation, fecal impaction, diarrhea and fecal incontinence, with attention to older adults.
2. Explain Crohn disease and ulcerative colitis, support their treatment, and recognize a severe flare.
3. Recognize and care for adults with diverticular disease and appendicitis, including signs of perforation and peritonitis.
4. Recognize bowel obstruction and ileus, escalate signs of strangulation, and provide nursing care using the CJMM.
5. Support colorectal cancer screening and care for patients after colorectal surgery.
6. Assess stomas and peristomal skin on a range of skin tones, and teach ostomy care and living well with an ostomy.
7. Distinguish RN and RPN roles in bowel and ostomy care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4	Clinician; Scholar	Foundations of Practice
5, 6	Educator; Advocate	Foundations of Practice; Ethical Practice
7	Professional; Collaborator	Legal Practice; Collaborative Practice

Introduction

Bowel habits are private, and many adults find them hard to talk about. Yet changes in bowel function are among the most common problems the nurse meets, in hospital and in the community. Consider four patients: a man who has not passed stool for four days after hip surgery; an older woman whose new "diarrhea" turns out to be liquid stool leaking around a hard mass; a young adult passing bloody stool ten times a day; and a patient whose abdominal pain has suddenly become constant, with a rigid abdomen. Each needs a nurse who asks clear questions, recognizes what is serious and acts early.

This chapter covers disorders of the lower gastrointestinal (GI) tract: the small and large intestines, the rectum and the anus. Section 25.1 explains normal bowel function and assessment, then constipation, fecal impaction, diarrhea and fecal incontinence. Section 25.2 covers inflammatory bowel disease, including how to recognize a severe flare. Section 25.3 covers diverticular disease and appendicitis, with the signs of perforation and peritonitis. Section 25.4 turns to bowel obstruction and ileus, section 25.5 to colorectal cancer screening and surgery, and section 25.6 to ostomy care and teaching.

The chapter builds on earlier ones. Scope of practice, the Clinical Judgment Measurement Model (CJMM) and consent are taught in Chapter 1 (sections 1.3 to 1.5), and cultural safety and body image in Chapter 2. Dehydration, potassium and magnesium are in Chapter 3; *Clostridioides difficile* (*C. difficile*) infection and contact precautions in section 4.4; and opioid-induced constipation in Chapter 5. Recognizing deterioration and calling for help are in Chapter 6, perioperative care in Chapter 7 and delirium in section 8.2. Nutrition, feeding tubes and upper GI bleeding are in Chapter 24, and skin care in Chapter 35.

25.1 Bowel Function, Constipation and Diarrhea

Normal Bowel Function and Assessment

The small intestine absorbs most nutrients and much of the water that enters the gut each day. The **colon** (large intestine) absorbs more water and electrolytes, stores waste and moves it toward the rectum with slow waves of muscle contraction. The longer stool stays in the colon, the more water is removed and the harder it becomes. When stool stretches the rectum, the person feels an urge to defecate. The internal anal sphincter relaxes without conscious control, while the external sphincter is under voluntary control, so a person can usually wait until a toilet is available.

"Normal" bowel habits vary widely, so the nurse compares each finding with the person's own usual pattern. A **bowel history** covers:

- usual frequency, consistency and timing, and any recent change;
- straining, urgency, pain, a feeling of incomplete emptying, and leakage;
- blood, mucus or black stool (upper GI bleeding is covered in section 24.5);
- fluid and fibre intake, activity, and toileting habits and privacy;
- medications, including over-the-counter laxatives, iron and calcium supplements, and recent antibiotics;
- past abdominal surgery, and any family history of colorectal cancer or inflammatory bowel disease.

Rectal bleeding, a lasting change in bowel habit, unplanned weight loss, anemia, or diarrhea that wakes the person at night is reported to the prescriber, because these findings need investigation (section 25.5).

By convention, the abdominal examination follows the order inspect, auscultate, percuss, then palpate, so that listening comes before touching. The nurse inspects the contour for distension, scars, hernias and stomas. Percussion sounds hollow (tympanic) over gas and dull over fluid, stool or a mass. Palpation starts lightly, away from any painful area, while the nurse watches the patient's face and feels for guarding or rigidity.

Bowel sounds are less useful than many clinicians believe. In a Danish study, 53 doctors listened to recordings of bowel sounds from 98 patients being assessed for possible obstruction. Their median sensitivity for an abnormal finding was 0.42 and their median specificity 0.78, agreement between listeners was poor, and senior doctors did no better than junior ones (Breum et al., 2015). The authors concluded that decisions should not be based on bowel sounds. The nurse still documents them, but gives more weight to the whole picture: passing of flatus and stool, distension, nausea and vomiting, pain, and tolerance of food and fluids.

The **Bristol Stool Form Scale** is a seven-point picture chart that describes stool form in words patients and nurses share (Lewis & Heaton, 1997). Types 1 and 2 are separate hard lumps or a lumpy sausage, which suggest slow transit and constipation. Types 3 and 4 are formed and smooth or slightly cracked. Types 5 to 7 range from soft blobs to entirely liquid stool, which suggest fast transit. The nurse records the type with the amount, colour, and any blood or mucus.

Constipation and Fecal Impaction

Constipation means stools that are infrequent, hard or difficult to pass, often with straining or a sense of incomplete emptying. Because people define it differently, the nurse asks what the patient means (Larkin et al., 2008). Common causes in hospital include:

- **medications:** opioids (section 5.4), drugs with anticholinergic effects, iron and calcium supplements;
- **immobility** and bed rest;
- **low fluid and fibre intake**, including during fasting for tests or surgery;
- **toileting barriers:** lack of privacy, bedpans, waiting for help, and ignoring the urge (Larkin et al., 2008);
- **neurologic disease**, such as Parkinson disease, stroke, multiple sclerosis and spinal cord injury;
- **metabolic causes**, such as hypothyroidism (Chapter 23) and a high calcium or low potassium (Chapter 3).

Fecal impaction is a mass of hard stool in the rectum or colon that the person cannot pass. Liquid stool from higher in the bowel can seep around the mass. This **overflow diarrhea** is easily mistaken for ordinary diarrhea. An antidiarrheal drug then makes the impaction worse. Impaction may cause abdominal or rectal discomfort, distension, loss of appetite, nausea, urinary retention and, in

older adults, new confusion. A digital rectal examination confirms it; in Ontario this is a controlled act, and who may do it is explained in the Scope in Practice box in section 25.6.

Prevention comes first. Unless fluids are restricted, the nurse encourages regular drinks, adds fibre gradually with enough fluid, helps the patient walk, and offers the toilet at a regular time, ideally after a meal. Sitting upright on a toilet or commode, with the feet supported and the door closed, makes passing stool easier than using a bedpan. When these measures are not enough, a laxative is added (Table 25.1). A joint guideline of two American gastroenterology societies made strong recommendations for polyethylene glycol and sodium picosulfate in chronic constipation, and conditional ones for fibre, lactulose, senna and magnesium oxide (Chang et al., 2023). For impaction, rectal measures such as a suppository or enema, or manual removal by an authorized nurse, clear the rectum; a regular oral plan then prevents recurrence (Larkin et al., 2008).

The nurse reports constipation at once when it comes with severe or worsening pain, vomiting, distension, no passing of gas, fever, or rectal bleeding. These findings may mean bowel obstruction (section 25.4) or another serious cause.

Diarrhea

Diarrhea is an increase in loose or watery stools above the person's usual pattern. Acute diarrhea starts suddenly and usually settles within days; chronic diarrhea lasts for weeks. Causes include:

- **infection**, including *C. difficile* after antibiotics. The nurse follows section 4.4 for testing and contact precautions as soon as it is suspected;
- **medications**, such as antibiotics, magnesium-containing products, laxative overuse and cancer treatment (Chapter 9);
- **enteral feeding** (section 24.2);
- **inflammatory bowel disease** (section 25.2);
- **overflow around an impaction**.

The nurse records the frequency, volume and Bristol type of each stool, and any blood, fever or pain. Large losses cause dehydration and low potassium and magnesium; the nurse watches for thirst, dizziness on standing, a rising heart rate and falling urine output, and monitors intake and output (sections 3.2, 3.5 and 3.6).

Liquid stool damages skin quickly. The nurse cleanses gently and promptly, pats the skin dry and applies a barrier product (Chapter 35). Irritation may look red on lighter skin but purple, grey or darker than surrounding skin on darker skin, so the nurse also feels for warmth and asks about burning and itching (Wounds International, 2023).

Antidiarrheal drugs are used only once infection has been considered. The Canadian monograph for loperamide states that it must not be used in acute dysentery (blood in the stool with fever), acute ulcerative colitis, bacterial enterocolitis from invasive organisms, or pseudomembranous colitis after broad-spectrum antibiotics (Kenvue Canada, 2026). It is stopped at once if the abdomen becomes distended, and in acute diarrhea it is stopped if there is no improvement within 48 hours. Doses above those recommended have caused serious heart rhythm problems. Loperamide never replaces fluid and electrolyte therapy.

Fecal Incontinence in Brief

Fecal incontinence is the involuntary loss of liquid or solid stool. Causes include diarrhea and urgency, overflow from impaction, sphincter injury from childbirth or anal surgery, nerve damage from diabetes, stroke or spinal cord injury, dementia, and limited mobility when help to the toilet is slow. Many people never mention it, so the nurse asks privately and plainly. Care treats the cause: managing diarrhea or impaction, a regular toileting schedule, prompt answers to call bells, and referral to a continence specialist, such as a Nurse Specialized in Wound, Ostomy and Continence (NSWOC). The nurse protects the skin as above (Chapter 35) and protects dignity: calling incontinence products "briefs" rather than "diapers," changing them promptly and keeping the patient covered.

Table 25.1 Laxatives and bowel care products (Chang et al., 2023; Larkin et al., 2008; Canadian product monographs)

Class	Canadian examples	How it works	Nursing points

Class	Canadian examples	How it works	Nursing points
Bulk-forming	Psyllium	Absorbs water and adds bulk, so stool is softer and easier to pass	Give with a full glass of fluid; avoid when fluid intake is poor or obstruction is suspected; bloating is common at first
Osmotic	Polyethylene glycol 3350; lactulose; magnesium hydroxide	Holds or draws water into the bowel to soften stool	Mix polyethylene glycol in fluid; gas and cramps may occur, especially with lactulose; check kidney function before magnesium products
Stimulant	Sennosides; bisacodyl	Stimulates the bowel's nerves and muscle to push stool along	Cramping is common; often paired with an osmotic laxative when opioids are used (Chapter 5)
Rectal suppositories and enemas	Glycerin suppository; bisacodyl suppository; sodium phosphate enema	Softens stool or triggers emptying of the lower bowel	For low impaction or when oral measures fail; position on the left side; stop if pain or resistance; read the product's cautions before using a phosphate enema, especially for an older adult or a person with kidney disease or dehydration
Bowel preparation products	Polyethylene glycol–electrolyte solutions; sodium picosulfate–magnesium oxide–citric acid	Empties the whole colon before colonoscopy or surgery	Follow the specific product's instructions; see section 25.5

LIFESPAN CONSIDERATIONS

Constipation and Impaction in Older Adults

Older adults are at high risk of constipation and impaction. Many take several drugs that slow the bowel, move less, and drink less because thirst is blunted or toileting is difficult. Cognitive impairment may stop them from reporting symptoms, so the first signs may be indirect: new or worse confusion (section 8.2), restlessness, falls, loss of appetite, urinary retention, or loose stool that is really overflow.

The nurse:

- keeps a bowel record each shift, with the Bristol type, and acts on the unit's plan when no stool has been passed;
- considers impaction before giving an antidiarrheal to an older adult with new loose stool and a history of constipation;
- reviews the medication list with the prescriber and pharmacist (section 8.5);
- checks kidney function before magnesium- or phosphate-containing products;
- offers the toilet after meals, with privacy, support for the feet and time.

Pregnancy: iron supplements and hormonal changes often cause constipation; the person checks with their prescriber or pharmacist before using any laxative.

Younger adults with constipation and warning signs, such as rectal bleeding or weight loss, still need assessment; age alone does not rule out serious disease.

25.2 Inflammatory Bowel Disease

Crohn Disease and Ulcerative Colitis

Inflammatory bowel disease (IBD) is a group of chronic conditions in which the immune system keeps the lining of the gut inflamed. The two main forms are Crohn disease and ulcerative colitis. Both are believed to arise when an inherited tendency meets environmental triggers and the immune response to the normal gut bacteria becomes excessive. Both follow a pattern of flares and remission, and both differ from irritable bowel syndrome, which does not inflame or damage the bowel.

Crohn disease can affect any part of the gut from the mouth to the anus, most often the end of the small intestine (the ileum) and the colon. Diseased segments are separated by normal "skip" areas, and inflammation runs through the full thickness of the bowel wall. Deep inflammation can scar the bowel into a narrowed **stricture** or create a **fistula**, an abnormal tunnel to the skin, bladder, vagina or another loop of bowel. Disease around the anus, with abscesses and fistulas, is common.

Ulcerative colitis (UC) affects only the colon. It begins in the rectum and spreads upward without gaps, and it inflames the inner lining rather than the whole wall. Its extent is described as **proctitis** (rectum only), left-sided colitis, or extensive colitis (Bressler et al., 2015). Table 25.2 compares the two diseases.

Canada has some of the highest rates of IBD in the world, and most people are diagnosed before age 30 (Crohn's and Colitis Canada, 2023). The Canadian Context box gives the numbers.

Manifestations depend on the form and location. UC typically causes bloody diarrhea, urgency, cramping and **tenesmus**, a painful feeling of needing to pass stool even when the rectum is empty. Crohn disease often causes abdominal pain, frequently in the right lower quadrant, with diarrhea, weight loss, fatigue and perianal pain or drainage. During a flare, either form may cause fever, a fast heart rate, anemia and dehydration.

Extraintestinal manifestations are features of IBD outside the gut. They include joint pain and swelling, eye inflammation (uveitis or episcleritis), mouth ulcers, and skin conditions such as erythema nodosum and pyoderma gangrenosum (Moran et al., 2025). **Erythema nodosum** appears as tender, warm, raised lumps, usually on the shins. On lighter skin they look pink to red. Inflammation often does not look red on medium and darker skin, where the lumps may look violet, brown or darker than the surrounding skin, or be hard to see at all, so the nurse also feels for warm, tender lumps and compares both legs (Wounds International, 2023). **Pyoderma gangrenosum** starts as a painful pustule or nodule that breaks down into a painful ulcer. A painful red eye, blurred vision or new sensitivity to light needs same-day assessment.

Diagnostics confirm the diagnosis, measure severity and rule out infection:

- **Stool tests** for bacteria and *C. difficile* (section 4.4), because infection can mimic or trigger a flare.
- **Fecal calprotectin**, a protein released by white blood cells into the stool. It is very sensitive for bowel inflammation but not specific, since infection and some drugs also raise it. In UC, a value under 100 mcg/g makes healing of the lining likely, while a value over 200 mcg/g should prompt discussion of endoscopy (Moran et al., 2025).
- **Endoscopy with biopsies:** colonoscopy confirms the diagnosis; in a severe flare, a limited flexible sigmoidoscopy is used instead.
- **Imaging**, such as computed tomography, magnetic resonance imaging or bowel ultrasound, to assess the small bowel and look for strictures, fistulas and abscesses.
- **Blood tests:** complete blood count for anemia, C-reactive protein (CRP, in mg/L) for inflammation, albumin, potassium and kidney function. Reference ranges vary by laboratory.

Treatment and Nursing Care

Treatment aims to bring a flare under control (**induction**), keep the disease quiet (**maintenance**) and heal the bowel lining. In UC, complete remission means normal stool frequency, no blood, and a healed lining on endoscopy (Bressler et al., 2015). Corticosteroids calm a flare but are not used for maintenance. A person who cannot stop them within three months, relapses within three months of stopping, or needs two or more courses in a year is **corticosteroid-dependent** and needs a steroid-sparing plan (Bressler et al., 2015).

Canadian guidelines match the drug to the disease. For mild to moderate UC, an aminosalicylate is first-line, given rectally for proctitis (Bressler et al., 2015). Rectal forms work best when the patient lies on the left side and holds the dose as long as possible. Each drug needs time to work, and the Toronto consensus sets check points: response to an aminosalicylate is judged at 4 to 8 weeks, to oral corticosteroids within 2 weeks, and to anti-TNF induction at 8 to 12 weeks (Bressler et al., 2015). The nurse explains these time frames so that patients do not stop a drug too soon. Patients often ask about probiotics and fecal microbiota transplant; the consensus does not recommend either for UC outside clinical trials (Bressler et al., 2015). For Crohn disease, the Canadian Association of Gastroenterology (CAG) suggests against using aminosalicylates or antibiotics for induction or maintenance (Panaccione et al., 2019). In both diseases, **biologic therapy**, made from living cells and given by infusion or injection, is recommended when conventional treatment fails. Newer biologics and oral small-molecule drugs have been approved since these guidelines, and the specialist team chooses among them. The Medications box summarizes the classes. Before a biologic or other immunosuppressant starts, the nurse confirms that screening for tuberculosis and hepatitis B and a vaccine review are done (section 21.3).

Nursing care during and between flares includes:

- **nutrition and anemia:** weighing the patient, recording intake and referring to a dietitian (Chapter 24); iron deficiency is common (section 20.2);
- **pain:** the nurse checks with the prescriber or IBD team before a patient with IBD is given a nonsteroidal anti-inflammatory drug (NSAID);
- **fatigue and mental health:** people with IBD are 1.5 to 2 times as likely as other people to have a psychiatric disorder (Crohn's and Colitis Canada, 2023), so the nurse asks about mood, sleep, anxiety and coping;
- **a flare action plan:** knowing the early signs (more stools, blood, pain, waking at night), whom to call, and continuing maintenance drugs when well.

Surgery is needed when drugs fail or complications develop. In UC, removing the colon and rectum cures the bowel disease and creates an ileostomy or an internal pouch (section 25.6). In Crohn disease, surgery removes or widens diseased segments, but the disease can return.

Across the lifespan, IBD looks different at each stage. Seniors are now the fastest-growing group living with IBD in Canada (Crohn's and Colitis Canada, 2023). Older adults often take other drugs and have other illnesses, so the nurse reviews interactions and infection risk with the pharmacist and watches closely for the effects of corticosteroids on glucose, mood, bone and sleep. Young adults are the group most often newly diagnosed. Their care includes school and work plans, relationships and sexuality, body image (Chapter 2), and planning for pregnancy, since some drugs, such as methotrexate, must be stopped well before conception. Young people moving from pediatric to adult care need a planned handover so that follow-up is not lost.

Recognizing a Severe Flare

Acute severe ulcerative colitis is a medical emergency that needs hospital admission and intravenous (IV) corticosteroids (Moran et al., 2025). Its most feared complication is **toxic megacolon**, in which the inflamed colon widens markedly on an abdominal X-ray and the patient becomes systemically ill. The thinned colon can perforate, and toxic megacolon is an indication for colectomy (Moran et al., 2025).

The nurse watches for:

- rising stool frequency with more blood;
- fever and a rising heart rate;
- new or increasing abdominal distension and tenderness;
- a fall in stool frequency in a patient who looks sicker, which should not be taken as a sign that the flare is settling, because it may come with colonic dilation.

The nurse keeps a stool chart (number of stools, consistency and blood), checks vital signs often, follows daily blood results, including CRP, and reports a rising pulse or temperature or worsening pain or tenderness at once (Chapter 6). The nurse keeps the patient NPO if surgery is possible, and gives VTE prophylaxis as ordered, because every patient admitted to hospital with IBD should receive it unless contraindicated (Moran et al., 2025). Antidiarrheals are not given: the Canadian loperamide monograph contraindicates loperamide in acute ulcerative colitis and says to stop it at once if the abdomen becomes distended (Kenvue Canada, 2026). Any drug that slows the bowel, including an opioid, is given only as the prescriber directs, with close reassessment. Replacing fluid and potassium matters, because diarrhea causes large losses (section 3.5). Some patients do not respond to IV steroids and need rescue drugs or surgery (Bitton et al., 2012), so the nurse prepares the patient early for the possibility of surgery and an ileostomy.

Table 25.2 Crohn disease and ulcerative colitis compared (Bressler et al., 2015; Panaccione et al., 2019; Moran et al., 2025)

Feature	Crohn disease	Ulcerative colitis
Location	Any part from mouth to anus; most often the ileum and colon	Colon only; always involves the rectum
Pattern	Patchy, with normal skip areas between diseased segments	Continuous, spreading upward from the rectum
Depth	Full thickness of the bowel wall	Inner lining of the colon

Feature	Crohn disease	Ulcerative colitis
Typical symptoms	Abdominal pain, diarrhea, weight loss, perianal pain or drainage	Bloody diarrhea, urgency, tenesmus, cramping
Complications	Strictures, fistulas, abscesses, perianal disease	Severe bleeding, toxic megacolon
Aminosalicylates	The CAG suggests against them for induction or maintenance	First-line for mild to moderate disease
Effect of surgery	Removes diseased bowel, but disease can recur	Removing the colon and rectum cures the bowel disease

CANADIAN CONTEXT

Inflammatory Bowel Disease in Canada

Crohn's and Colitis Canada's *2023 Impact of Inflammatory Bowel Disease in Canada* report, released on June 1, 2023, gives these estimates (Crohn's and Colitis Canada, 2023):

- About 322,600 people in Canada were living with IBD in 2023, or 0.8% of the population, up from about 270,000 (0.7%) in 2018.
- By 2035, about 470,000 people (1.1% of the population) are expected to be living with IBD.
- About 11,000 new diagnoses were expected in 2023, roughly one every 48 minutes, rising to about 14,000 a year by 2035.
- New diagnoses are rising fastest in children under 6, and seniors are the fastest-growing group living with IBD, because of better treatment and an aging population.

The report notes added barriers to IBD care for people with low incomes, for Indigenous peoples, and for people living in rural, remote and northern communities. It also notes that IBD is now appearing in newcomer families with no earlier history of it. For people far from larger centres, endoscopy, infusions and surgery can mean long travel.

The nurse asks about travel, costs, work and school, and access to drug coverage, and helps connect patients with virtual follow-up, IBD nurses and patient organizations. For cultural safety and structural barriers, see Chapter 2.

MEDICATIONS

Drugs for Inflammatory Bowel Disease

No doses are given. The specialist team selects drugs by disease, severity and response (Bressler et al., 2015; Panaccione et al., 2019).

- **Aminosalicylates (5-ASA):** mesalamine (also called mesalazine), sulfasalazine. Mainly for UC, orally or rectally. The nurse stresses taking them every day, even when well.
- **Corticosteroids:** prednisone, budesonide; IV methylprednisolone or hydrocortisone in hospital. For flares only, never maintenance. The nurse monitors glucose, mood, sleep and infection, and warns against stopping suddenly (Chapter 23).
- **Thiopurines:** azathioprine. For maintenance. The nurse reinforces regular blood tests and reporting of fever or sore throat.
- **Methotrexate:** mainly for Crohn disease, by injection. Given once weekly; the nurse confirms the weekly schedule to prevent fatal daily dosing errors and teaches pregnancy prevention.
- **Anti-tumour necrosis factor (anti-TNF) biologics:** infliximab, adalimumab, golimumab. The nurse confirms screening (section 21.3), watches for infusion reactions and teaches infection signs.
- **Anti-integrin:** vedolizumab, which acts selectively on the gut.
- **Interleukin (IL)-12/23 and IL-23 blockers:** ustekinumab, mirikizumab. The nurse teaches self-injection and storage.
- **Janus kinase (JAK) inhibitors:** tofacitinib, upadacitinib. Oral; the nurse reviews the monograph's serious warnings, which for tofacitinib include serious infections, blood clots, major heart events and cancer (Health Canada, 2022).
- **Sphingosine 1-phosphate (S1P) receptor modulators:** ozanimod. Oral; starting treatment causes a temporary fall in heart rate, so the dose is increased in steps (Bristol-Myers Squibb Canada, 2024).

GOING DEEPER

Acute Severe Ulcerative Colitis

Required for RN students; optional for PN students.

Acute severe UC is still defined by criteria first published by Truelove and Witts (1955), which current guidelines use (Moran et al., 2025). The patient has six or more bloody stools in 24 hours plus at least one sign of systemic illness: a heart rate over 90 beats per minute, fever, anemia, or a raised erythrocyte sedimentation rate (ESR). Guidelines and hospitals differ slightly in the exact cut-offs they use for temperature, hemoglobin and ESR, so the nurse follows the local protocol.

On admission, stool is tested for infection, including *C. difficile*, blood tests and abdominal imaging are done, and a flexible sigmoidoscopy is arranged. IV corticosteroids start, with fluid and electrolyte replacement as needed and VTE prophylaxis (Moran et al., 2025).

The CAG's Toronto consensus advises that patients who have not responded to IV steroids by 72 hours move early to rescue therapy with infliximab or cyclosporine at an experienced centre; giving one rescue drug after the other is not recommended (Bitton et al., 2012). Response is judged on day 3. More than 8 stools in 24 hours, or 3 to 8 stools with a CRP over 45 mg/L, predicted colectomy in about 85% of patients in the study that set these thresholds (Travis et al., 1996).

Colectomy with an ileostomy is needed when rescue therapy fails, or for toxic megacolon, perforation or severe bleeding. Early referral to the colorectal surgeon and stoma team matters, because delay increases surgical complications (Moran et al., 2025).

25.3 Diverticular Disease and Appendicitis

Diverticular Disease

Diverticulosis is the presence of **diverticula**, small pouches that bulge outward through weak points in the colon wall, often in the sigmoid colon. It becomes more common with age, and most people never have symptoms. **Diverticular disease** covers the problems these pouches can cause: inflammation and bleeding.

Diverticulitis is inflammation of one or more diverticula. It typically causes steady pain in the left lower quadrant, tenderness, fever, nausea and a change in bowel habit, with a raised white blood cell count and CRP. It is **uncomplicated** when inflammation stays local. It is **complicated** when an abscess, perforation, fistula, narrowing or obstruction develops. A fistula to the bladder can cause air or stool in the urine and repeated urinary infections. Bleeding from diverticula is a separate problem: sudden, usually painless passage of red or maroon blood from the rectum, which needs prompt assessment (Chapter 6).

Lifestyle factors linked to diverticulitis include a poor-quality diet, obesity, physical inactivity, smoking and NSAID use (Peery et al., 2021).

Computed tomography (CT) is often needed to confirm the diagnosis and look for complications (Peery et al., 2021). Colon cancer is rarely mistaken for diverticulitis, but it can be. A colonoscopy after recovery is therefore planned based on the person's history and previous colonoscopy results (Peery et al., 2021), and is advised after complicated diverticulitis (American Society of Colon and Rectal Surgeons [ASCRS], n.d.).

Treatment matches severity. The American Gastroenterological Association (AGA) advises that antibiotics can be used selectively in mild, uncomplicated diverticulitis in a patient whose immune system works normally, and are strongly advised for immunocompromised patients (Peery et al., 2021). Many patients with mild disease recover at home with rest, fluids and acetaminophen, advancing their diet as they feel able. Complicated diverticulitis needs hospital care, with IV fluids and antibiotics, and drainage of an abscess where needed. Urgent removal of the sigmoid colon is advised for diffuse peritonitis (ASCRS, n.d.), sometimes with a temporary colostomy (section 25.6). The decision on planned surgery after recovery is individualized, not based on the number of episodes alone (Peery et al., 2021).

In hospital, the nurse tracks the trend in pain, temperature, heart rate and white blood cell count. Worsening despite treatment suggests an abscess or perforation and is reported at once. Patients taking corticosteroids or other immunosuppressants may show few abdominal signs even when seriously ill, so subtle changes matter. The nurse also assesses hydration and intake and output, and teaches patients at home to return for worsening or spreading pain, fever, vomiting or inability to drink, rectal bleeding, or air or stool in the urine. After recovery, the nurse supports a high-quality diet with fibre, a healthy weight, regular activity and not smoking. Patients should avoid NSAIDs, except aspirin taken to prevent heart attack or stroke (Peery et al., 2021).

Appendicitis

Appendicitis is inflammation of the appendix, usually after its opening is blocked. Pressure builds, bacteria multiply and blood supply falls, and the wall can die and perforate. An **appendicolith**, a hard stone of stool, raises the risk of perforation (Di Saverio et al., 2020).

In the classic pattern, pain begins as a vague ache around the umbilicus that moves over hours to the right lower quadrant and becomes sharp and constant, worse with movement or coughing, with loss of appetite, nausea and a low-grade fever. Many patients do not follow this pattern. **Older adults** often report milder pain and seek care later. Perforation rates in patients over 50 have been reported at 55% to 70%, and the Alvarado score is unreliable for judging severity in older patients (Di Saverio et al., 2020). Pregnant people also present atypically and need early surgical review.

The World Society of Emergency Surgery (WSES) recommends clinical scores, such as the Appendicitis Inflammatory Response score and the Adult Appendicitis Score, with ultrasound, to reduce the use of CT. When CT is needed, low-dose CT with contrast is preferred. In pregnancy, magnetic resonance imaging (MRI) follows an inconclusive ultrasound (Di Saverio et al., 2020).

Laparoscopic appendectomy is the preferred treatment, and uncomplicated appendicitis in adults should be operated on within 24 hours of admission (Di Saverio et al., 2020). WSES also advises discussing an antibiotics-first approach with selected adults who have uncomplicated appendicitis and no appendicolith. Patients need to know the trade-offs: about 8% fail treatment during the first admission, about 20% are readmitted within a year, and one trial found recurrence of 39.1% at five years (Di Saverio et al., 2020). The nurse supports this informed choice (section 1.5). Antibiotics-first treatment is advised against in pregnancy (Di Saverio et al., 2020). A patient treated without surgery is taught to return at once if pain, fever or vomiting comes back or worsens.

WSES prefers the laparoscopic approach over open surgery where it is available (Di Saverio et al., 2020). After laparoscopic appendectomy for uncomplicated appendicitis, the hospital stay is often short, and some centres use an enhanced recovery pathway (Chapter 7). Discharge teaching is then a main safety measure: the nurse confirms that the patient can drink, pass urine, walk and manage pain, and knows to return for fever, increasing abdominal pain, vomiting or redness and drainage at a port site.

Before surgery, the nurse keeps the patient NPO, starts IV fluids and gives antibiotics and analgesia as ordered. Laxatives and enemas are not given. Analgesia should not be withheld: a Cochrane review found that opioid analgesia did not increase errors in diagnosis or treatment decisions (Manterola et al., 2011). After surgery, care follows Chapter 7. After perforated appendicitis, the nurse watches for fever, increasing pain or slow return of bowel function, which can signal an abscess. Mortality is about 5% after perforation compared with under 0.1% when the appendix is not gangrenous (Di Saverio et al., 2020), which is why early recognition matters.

CLINICAL SAFETY

A Rigid, Silent Abdomen

Peritonitis is inflammation of the lining of the abdominal cavity, most often from a perforated appendix, diverticulum or other part of the bowel. It can lead quickly to sepsis and shock (section 4.6; Chapter 6).

Warning signs:

- sudden, severe pain that becomes constant and spreads across the abdomen, sometimes after a short-lived easing of pain when the organ bursts;
- a hard, board-like abdomen with guarding and tenderness;
- the patient lying very still, because movement and coughing hurt;
- fever, a rising heart rate, fast breathing and falling blood pressure.

The nurse:

- calls the prescriber at once, or the rapid response team if vital signs are abnormal (Chapter 6);
- keeps the patient NPO and prepares for IV access, blood work and imaging;
- reports using SBAR (situation, background, assessment, recommendation).

Quiet or absent bowel sounds may accompany peritonitis, but present bowel sounds do not rule it out (Breum et al., 2015). Pain relief is not withheld while waiting for the surgeon: opioid analgesia does not increase diagnostic errors (Manterola et al., 2011).

25.4 Bowel Obstruction and Ileus

Mechanical Obstruction and Paralytic Ileus

A **bowel obstruction** is any problem that stops intestinal contents from moving forward. In a **mechanical obstruction**, something blocks the inside of the bowel, presses on it from outside or twists it. In **paralytic ileus**, nothing blocks the bowel: the muscle of the bowel wall stops moving contents along, so gas and fluid build up as if a blockage were present (Vogel et al., 2016).

Most obstructions involve the small bowel. **Adhesions**, bands of scar tissue that form inside the abdomen after surgery or inflammation, cause about 60% to 70% of small bowel obstructions (Di Saverio et al., 2013; ten Broek et al., 2018). Other causes include internal and groin hernias, tumours, Crohn disease (section 25.2), intussusception (one segment of bowel telescoping into the next) and, rarely, a gallstone (Di Saverio et al., 2013). In adults, the most common causes of large bowel obstruction are colorectal cancer, diverticular disease (section 25.3) and **volvulus**, a twist of a loop of colon on its own mesentery. In Western countries, sigmoid volvulus mostly affects people in their 60s to 80s who live with chronic illness, cognitive or neurologic impairment or long-standing constipation (Vogel et al., 2016). Table 25.3 compares the two levels.

Above a blockage, swallowed air, gas and digestive juices collect and stretch the bowel. Fluid trapped in the bowel and lost through vomiting leads to dehydration, and vomiting can cause electrolyte losses and metabolic alkalosis (Pisano et al., 2018; Chapter 3).

Manifestations of small bowel obstruction are crampy (colicky) pain that comes in waves, abdominal distension, and nausea with or without vomiting. As it progresses, the patient stops passing stool and gas. A partial obstruction can still let watery stool through, which can look like gastroenteritis. Older adults often report less pain, so a mild complaint does not rule out obstruction (ten Broek et al., 2018). In large bowel obstruction, the patient usually stops passing gas and stool and feels bloated; vomiting is less common than with small bowel obstruction (Pisano et al., 2018).

The most dangerous complication is **strangulation**: the blood supply to a trapped segment is cut off, so the bowel becomes ischemic, then dies and can perforate. A **closed-loop obstruction**, in which a segment is blocked at both ends, as in volvulus, calls for surgery without delay (ten Broek et al., 2018). Signs that suggest strangulation are pain that becomes constant, fever, tachycardia, signs of peritonitis (section 25.3), a rising white blood cell count and metabolic acidosis. A raised serum lactate can point to ischemia, but it is not specific (Di Saverio et al., 2013). Physical examination detects strangulation only about half the time (ten Broek et al., 2018), so the nurse treats these cues as an emergency, reports them at once and calls for rapid help when vital signs worsen (Chapter 6).

Postoperative ileus is the expected pause in bowel movement after surgery, measured from the operation until the patient passes gas or stool and tolerates an oral diet. When distension, vomiting and intolerance of food persist, it is called prolonged ileus. Reported rates of postoperative ileus range from 10% to 30% (Shereef et al., 2023). Prevention through enhanced recovery (fewer opioids, minimally invasive surgery, no routine nasogastric tubes, early eating and walking) is covered in Chapter 7 (Gustafsson et al., 2019). Ileus also accompanies peritonitis and serious infection, electrolyte disturbances such as low potassium (Chapter 3), and drugs that slow the bowel, especially opioids (Chapter 5) and anticholinergic drugs (Vogel et al., 2016).

Acute colonic pseudo-obstruction is marked swelling of the colon without any blockage. It mostly affects older, seriously ill hospital patients and people recovering from surgery or trauma. The risk of ischemia or perforation rises as the cecum widens beyond about 12 cm and when swelling lasts more than 6 days (Vogel et al., 2016).

Diagnosis and Nursing Care

CT is the preferred test. It confirms the obstruction, shows its level and often its cause, and detects a closed loop, ischemia or free fluid (ten Broek et al., 2018; Pisano et al., 2018). Plain X-rays add little (ten Broek et al., 2018; Figure 25.1). In adhesive small bowel obstruction, a water-soluble contrast drink also guides care: contrast that reaches the colon on an X-ray within 24 hours suggests the obstruction is resolving, and contrast that does not suggests nonoperative care is failing (ten Broek et al., 2018). Initial bloodwork includes a complete blood count, electrolytes, urea, creatinine and lactate, along with a nutrition assessment (ten Broek et al., 2018).

Nonoperative care resolves about 70% to 90% of adhesive obstructions (ten Broek et al., 2018). The nurse:

- keeps the patient NPO and supports **nasogastric (NG) decompression**: an NG tube drains swallowed air and fluid to relieve distension and vomiting (Di Saverio et al., 2013). Placement and verification are taught in Chapter 24. The nurse keeps the tube draining or on suction as ordered and records the amount and appearance of drainage.
- gives IV fluids and electrolyte replacement as ordered and follows potassium and creatinine results (Di Saverio et al., 2013; Chapter 3).
- keeps strict intake and output, counting NG drainage, vomitus and urine.
- reassesses vital signs, pain, distension and the passage of gas or stool at regular intervals, and escalates any sign of strangulation.
- takes steps to prevent aspiration (ten Broek et al., 2018), such as raising the head of the bed, and gives frequent mouth and nostril care.
- gives analgesia as ordered and reassesses; in ileus and pseudo-obstruction, opioids and anticholinergic drugs are kept to a minimum (Vogel et al., 2016).
- helps the patient walk as tolerated; walking is part of supportive care for pseudo-obstruction (Vogel et al., 2016).
- watches older adults for delirium and functional decline; frailty predicts a slower recovery (ten Broek et al., 2018; Chapter 8).



Figure 25.1 An upright abdominal X-ray in small bowel obstruction: dilated loops with many air-fluid levels. X-rays like this may be taken, but CT is the preferred test because it shows the level and cause and signs of ischemia. (credit: "Upright X-ray demonstrating small bowel obstruction" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

A trial of nonoperative care for adhesive obstruction can safely continue for up to 72 hours. Peritonitis, strangulation or ischemia calls for surgery without delay (ten Broek et al., 2018). Surgery may divide adhesions or remove dead bowel. In large bowel obstruction caused by cancer, options include resection, sometimes with an end colostomy, or a colonic stent (Pisano et al., 2018). Sigmoid volvulus without signs of ischemia is first untwisted through an endoscope, and colectomy is then often advised to prevent recurrence (Alavi et al., 2021). Pseudo-obstruction is first treated with supportive care; medication or endoscopic decompression follows if it does not resolve (Alavi et al., 2021).

Returning bowel function shows as passing gas or stool, less distension, falling NG drainage and returning appetite. The NG tube is then removed and the diet advanced on the prescriber's order.

Table 25.3 Small and large bowel obstruction compared (Di Saverio et al., 2013; ten Broek et al., 2018; Pisano et al., 2018; Vogel et al., 2016; Alavi et al., 2021)

Feature	Small bowel	Large bowel
Common causes	Adhesions (about 60% to 70%), hernias, tumours, Crohn disease	Colorectal cancer, diverticular disease, volvulus
Pain	Crampy pain in waves; older adults may report little pain	Crampy pain with bloating
Vomiting	Nausea, with or without vomiting	Less common than in small bowel obstruction
Stool and gas	Stop as it progresses; watery stool can pass a partial blockage	Usually no gas or stool
Main danger	Strangulation and ischemia	Perforation; ischemia in volvulus

Feature	Small bowel	Large bowel
Preferred imaging	CT; water-soluble contrast study in adhesive obstruction	CT
Usual first treatment	NPO, NG decompression, IV fluids; surgery for strangulation or no resolution	Depends on cause: surgery, stent or endoscopic untwisting of sigmoid volvulus

CLINICAL JUDGMENT

Vomiting and a Swollen Abdomen

Names and details are fictional; this is a composite story.

Grace Ningiuk, 79, is on day 3 after surgical repair of a hip fracture. She takes an oral opioid for pain and has been mostly in bed. She has not passed stool since admission.

- **Recognize cues:** Grace has vomited twice since breakfast. Her abdomen is round, tense and tender all over, and she says she has not passed gas today. Temperature 37.3 °C, heart rate 96, blood pressure 124/70 mm Hg. Potassium is 3.1 mmol/L. She has no hernia and no previous abdominal surgery.
- **Analyze cues:** Opioids, immobility, low potassium and recent surgery all slow the bowel. Paralytic ileus or colonic pseudo-obstruction fits, but a mechanical obstruction must be ruled out.
- **Prioritize hypotheses:** The main risks are aspiration from vomiting, worsening dehydration and low potassium, and, if the colon keeps widening, ischemia or perforation.
- **Generate solutions:** Stop oral intake, report to the prescriber using SBAR, anticipate imaging, an NG tube, IV fluids with potassium replacement and a review of her opioid, and help her move.
- **Take action:** The nurse sits Grace upright, stops oral intake until she has spoken with the prescriber, and reports. Abdominal imaging shows a widened colon without blockage. An NG tube is placed, IV fluids with potassium are started, and the prescriber switches her pain plan to an opioid-sparing regimen.
- **Evaluate outcomes:** By the next morning, Grace passes gas, her abdomen is softer and her potassium is 3.8 mmol/L. The nurse keeps checking her abdomen, intake and output, and watches for new pain, fever or tachycardia.

25.5 Colorectal Cancer Care

Risk and Screening

Colorectal cancer is cancer of the colon or rectum. It can develop from **adenomas**, a type of polyp (Figure 25.2); the risk depends on the polyp's type, size and number (Canadian Cancer Society [CCS], n.d.-a). In Canada, an estimated 25,300 people will be diagnosed with colorectal cancer in 2026 (14,100 men and 11,200 women), about 10% of all new cancers. Excluding non-melanoma skin cancers, it is the fourth most commonly diagnosed cancer and the third leading cause of cancer death in both men and women, with about 9,200 deaths expected in 2026. About 1 in 17 men and 1 in 19 women will develop it in their lifetime. New-case rates are falling, partly because screening finds and removes polyps before they become cancer (Brenner et al., 2026; CCS, 2026). About 67% of people diagnosed survive at least 5 years. Stage matters: Canadian estimates of 5-year net survival for colon cancer are about 92% at stage 1 and 11% at stage 4 (CCS, 2023).

Risk factors include (CCS, n.d.-a):

- **Factors a person cannot change:** older age; a parent, sibling or child with colorectal cancer; a personal history of polyps or colorectal cancer; inflammatory bowel disease, especially long-standing, extensive ulcerative colitis (section 25.2); and inherited syndromes such as familial adenomatous polyposis and Lynch syndrome.
- **Factors linked to how people live:** physical inactivity and long periods of sitting, overweight and obesity, alcohol, smoking, diets high in red and processed meat and low in fibre. Type 2 diabetes is also linked to higher risk.

Screening looks for cancer or polyps in people who have no symptoms. The **fecal immunochemical test (FIT)** is an at-home test that checks one stool sample for tiny amounts of blood. It needs no change in diet or medications (Ontario Health, 2026). **Colonoscopy** examines the whole colon with a flexible scope and lets the endoscopist remove polyps.

The Canadian Task Force on Preventive Health Care (CTFPHC, 2016) recommends screening adults aged 60 to 74 (strong recommendation) and 50 to 59 (weak recommendation) with FIT or a guaiac fecal test every 2 years, or flexible sigmoidoscopy every 10 years. It recommends against screening adults aged 75 and older and against colonoscopy as a screening test for people at average risk. These recommendations do not apply to people with symptoms, a personal history of colorectal cancer or polyps, inflammatory bowel disease, a parent, sibling or child with colorectal cancer, or an inherited syndrome.



Figure 25.2 A colon polyp seen during colonoscopy. Removing adenomatous polyps during colonoscopy can prevent them from becoming cancer.

Provinces and territories run their own programs. Ontario's ColonCancerCheck changed on July 1, 2026 (Government of Ontario, 2026a):

- **Average risk:** FIT every 2 years from age 45 to 74 (previously from age 50). Average risk means no parent, sibling or child with colon cancer, or only one diagnosed at age 60 or older (Ontario Health, 2026).
- **Abnormal FIT:** more testing is needed, which does not mean cancer. The program recommends colonoscopy within 8 weeks.
- **Increased risk:** one parent, sibling or child diagnosed before age 60, or two or more diagnosed at any age. These people have colonoscopy every 5 years, starting at age 40 or 10 years before the youngest relative's diagnosis, whichever comes first.

Screening is not for people with symptoms. Blood in the stool (bright red or very dark), new and lasting diarrhea or constipation, a feeling that the bowel does not empty, new and lasting abdominal discomfort, unexplained weight loss, iron-deficiency anemia or narrower stools call for assessment by a physician or nurse practitioner (NP) instead (Government of Ontario, 2026a).

Screening is not shared equally. In 2017 Canadian survey data, people with lower incomes, some immigrant groups and people who speak an Indigenous language were less likely to have been screened, and many recent immigrants had not been tested because they did not know the test existed (Canadian Partnership Against Cancer, 2025). Structural barriers, such as having no primary care provider, language, the cost of travel and past experiences of racism in health care, can also limit access (Chapter 2). In Ontario, people without a family physician or NP can order a FIT kit through Health811 (call 8-1-1), some regions run mobile screening coaches, and people in First Nations communities can ask their health centre or nursing station (Government of Ontario, 2026a). The nurse asks every eligible adult about screening, explains the test in plain language or through an interpreter, and helps the person get a kit.

Surgery and Recovery

Surgery is the main treatment for most colorectal cancers that have not spread. The surgeon removes the affected segment and joins the healthy ends in an **anastomosis**. A **colectomy** removes part of the colon, for example a right or left hemicolectomy or a sigmoid colectomy. A **low anterior resection** removes a tumour in the middle or upper rectum. An **abdominoperineal resection** removes a tumour close to the anus; because the lower rectum and anal sphincter are removed, the colostomy is permanent (CCS, n.d.-b). In an emergency, such as obstruction or perforation, the surgeon may remove the tumour and bring the colon out as an end colostomy instead of joining it (Hartmann procedure) (Pisano et al., 2018). A temporary colostomy or ileostomy, meant to be closed later, may be made to let the bowel rest and heal (CCS, n.d.-b). Protecting a new join from leaking is one of its main purposes (Parini et al., 2023). Stomas are covered in section 25.6.

Enhanced recovery recommendations for elective colorectal surgery include eating within hours of surgery, early walking, opioid-sparing pain control and early removal of the urinary catheter (Gustafsson et al., 2019; Chapter 7). Chemotherapy and radiation are covered in Chapter 9.

Complications include bleeding, infection, venous thromboembolism, ileus (section 25.4), and sexual and bladder problems after rectal surgery (CCS, n.d.-b). The most feared is an **anastomotic leak**, leakage of bowel contents from the join into the abdomen. It usually appears within the first week and can lead to peritonitis, abscess, sepsis and death (Vun et al., 2025). The nurse watches for:

- new or worsening abdominal pain, fever, tachycardia or low blood pressure;
- peritoneal signs such as guarding and rebound tenderness;
- ileus that does not resolve, or a patient who stops progressing;
- drain fluid that becomes cloudy, purulent or smells of stool, or increases in volume (Vun et al., 2025).

These findings are reported at once using SBAR (Chapter 6). The surgeon usually orders bloodwork and a contrast CT scan (Vun et al., 2025). In older adults, new confusion may be the first sign of any serious complication (Chapter 8).

Patients often fear cancer, the operation and a possible stoma all at once. The nurse invites questions, involves the people the patient chooses, and arranges a NSWOC visit before surgery when a stoma is possible (section 25.6). Before discharge, the nurse reviews wound care, activity, diet, signs to report and follow-up.

PATIENT EDUCATION

Bowel Preparation Before Colonoscopy

A clean colon lets the endoscopist see small polyps. The nurse teaches the person to:

- follow the written instructions for their own product exactly, including timing; products and schedules differ (Government of Alberta, 2022).
- eat low-fibre foods for the days the instructions state, then take only clear fluids, meaning liquids a person can see through, such as water, clear broth, clear juice and sports drinks, but nothing red, purple or blue and no milk (Government of Alberta, 2022).
- drink a variety of clear fluids, not water alone, which can lower sodium (Ferring Inc., 2024).
- change medications only as the prescriber or endoscopy team directs. Iron and fibre supplements are often stopped several days before; other medications, such as blood thinners and diabetes medications, may need to be adjusted or stopped, so the person asks for a specific plan (Government of Alberta, 2022; Chapters 19 and 22). People with diabetes check their blood glucose more often while on clear fluids.
- know that other pills taken close to the preparation may not be fully absorbed (Ferring Inc., 2024).
- report vomiting, dizziness on standing, confusion or very little urine (Ferring Inc., 2024).

Older adults, frail people and those with kidney disease or who take diuretics need extra attention to fluids and electrolytes, and some preparations are not used in severe kidney disease (Ferring Inc., 2024).

25.6 Ostomy Care and Teaching

Types of Ostomies

An **ostomy** is a surgically created opening into the bowel or urinary tract that lets stool or urine leave the body. The **stoma** is the end of bowel brought through the abdominal wall and folded back on itself at the skin (Ostomy Canada Society, 2025). More than 165,000 people in Canada are estimated to live with an ostomy (Ostomy Canada Society, 2025).

- A **colostomy** brings part of the colon to the skin (Figure 25.3). Output depends on location: a stoma in the ascending colon produces mushy stool, while a sigmoid colostomy produces more formed stool (Ostomy Canada Society, 2025).
- An **ileostomy** brings the end of the small bowel (ileum) to the skin. Output is liquid to paste-like and contains digestive enzymes that irritate skin (Ostomy Canada Society, 2025).

- An **end stoma** has one opening. In a **loop ostomy**, a loop of bowel is brought up and opened, and a plastic rod may support it for the first 1 to 2 weeks (Ostomy Canada Society, 2025).
- An ostomy is **temporary** when it protects healing bowel and will be closed later, and **permanent** when the rectum and anal sphincter have been removed (CCS, n.d.-b).

Urostomy and other urinary diversions are covered in Chapter 28. Table 25.4 compares colostomy and ileostomy.



Figure 25.3 A permanent colostomy after surgery for rectal cancer (inset). The end of the descending colon is brought out through the left lower abdomen, where stool is collected in a pouch. (credit: National Cancer Institute, public domain)

Stoma and Peristomal Skin Assessment

A healthy stoma (Figure 25.4) is moist, smooth and pink to red on every skin tone, because the nurse is looking at bowel lining, not skin. It may bleed slightly when cleaned. A stoma has no nerve endings, so it does not hurt to touch; pain usually comes from the skin around it (Ostomy Canada Society, 2025). A new stoma is often swollen at first and shrinks over the following weeks (Parini et al., 2023). The nurse assesses the stoma regularly after surgery and reports at once a stoma that loses its pink-to-red colour and looks dusky or black, because a change in stoma colour can mean the blood supply is failing (Nurses Specialized in Wound, Ostomy and Continence Canada [NSWOCC], 2023) and the tissue may die (stoma necrosis) (Parini et al., 2023). Other stomal complications are separation of the stoma from the skin, retraction below skin level, prolapse (the bowel pushing out farther than usual), narrowing and bleeding (Parini et al., 2023). Stoma complications are reported in 20% to 70% of patients, and most are managed without surgery (Parini et al., 2023).



Figure 25.4 A healthy ileostomy stoma: moist and red, with the skin barrier cut to fit closely around it. (credit: “Ostomy wafer being worn by an ileostomy patient” by Eric Polsinelli (VeganOstomy)/Wikimedia Commons, CC BY 4.0)

Figure 25.5 A large parastomal hernia around a colostomy in an older man: the abdominal wall bulges around the stoma, under the pouch. A flexible pouching system is preferred over a firm, convex one.

A **parastomal hernia** is a bulge of abdominal contents through the opening in the abdominal wall around the stoma (Figure 25.5). It is common and becomes easier to see when the person stands, coughs or strains. A hernia with increasing pain, nausea and vomiting, falling output or a change in stoma colour may be trapped or strangulated and is an emergency (NSWOCC, 2023).

Peristomal skin, the skin around the stoma, should look like the person's skin elsewhere on the abdomen. Peristomal skin problems are the most common complications after ostomy surgery (Chabal et al., 2021). They include (Zane Cohen Centre, n.d.):

- **Irritant dermatitis** from stool leaking under the barrier, often because the opening is too large or the skin is creased. The skin is sore, weepy or broken in the shape of the leak.
- **Mechanical injury** from pulling the barrier off too quickly, especially in older adults or people on long-term corticosteroids.
- **Allergic dermatitis**, an itchy rash or blisters matching the shape of a product.
- **Fungal (Candida) infection**: a solid patch with an irregular edge and small separate spots around it ("satellite lesions").
- **Folliculitis**: small pustules at hair follicles, often from removing a barrier too fast or shaving.

Inflammation does not always look red. On darker skin it may appear purple, brown or darker than the surrounding skin, and it can be easy to miss (Wounds International, 2023). The nurse compares the peristomal skin with the person's skin away from the stoma in

good natural or ambient light, feels for warmth, swelling and induration, and asks about burning, itching and stinging (Pusey-Reid et al., 2023; Wounds International, 2023). A history of repeated leaks is itself a finding to report.

Pouching and Daily Care

A **pouching system** has a skin barrier (wafer or flange) that sticks to the skin and a pouch that collects output. In a one-piece system the two are joined (Figure 25.6); in a two-piece system the pouch attaches to a separate barrier. Barriers can be flat or convex, and the NSWOC helps choose one that fits the person's abdomen; with a parastomal hernia, a flexible system is preferred over firm convexity (NSWOCC, 2023).

Good care prevents most leaks. The nurse teaches the person to:

- measure the stoma and cut the barrier opening no more than about 3 to 4 mm larger than the stoma base, then check the fit in a mirror (Zane Cohen Centre, n.d.). Stoma size changes, especially in the first weeks, so the opening is rechecked (Chabal et al., 2021).
- empty a drainable pouch when it is about one-third full (Ostomy Canada Society, 2023).
- change the system on a regular schedule, often every 3 to 7 days, and right away if it leaks (Ostomy Canada Society, 2023).
- remove the barrier gently, pushing the skin away from the adhesive (Zane Cohen Centre, n.d.).
- clean the skin gently with warm water, avoid oily products that stop the barrier sticking, dry it well and check it at each change (Ostomy Canada Society, 2023).

The nurse starts teaching early, has the person practise with each change, and includes a family member or friend if the person wishes.

Figure 25.6 A one-piece, drainable pouch over an ileostomy. The pouch is emptied when it is about one-third full. (credit: “Ileostomy with bag” by Remedios44/Wikimedia Commons, CC BY-SA 4.0)

Stoma site marking is done before planned surgery. An NSWOC or surgeon chooses a flat site within the rectus abdominis muscle, away from folds, scars and the navel, and checks it with the person sitting, standing and bending (NSWOCC, 2023). Canadian guidance recommends that everyone who expects or lives with an ostomy have access to an NSWOC, a registered nurse with advanced education in wound, ostomy and continence care, for marking, education and follow-up (Registered Nurses' Association of Ontario [RNAO], 2019). The nurse refers early when leaks continue, skin breaks down or the person struggles to cope.

High-Output Ileostomy and Dehydration

A **high-output ileostomy** produces enough output to cause water and sodium depletion, generally more than about 1.5 to 2 L in 24 hours (Nightingale, 2022). One Canadian patient resource defines it for adults as more than 1.5 L a day or emptying the pouch every 2 hours (Alberta Health Services [AHS], 2025). It can begin in the first weeks after surgery. Early causes include sepsis, ileus and sudden withdrawal of opioids (Nightingale, 2022).

Signs of dehydration include thirst, dry mouth, dizziness, low blood pressure, muscle cramps, less urine and dark urine (AHS, 2025). Untreated dehydration can damage the kidneys (Nightingale, 2022; Chapter 27). The nurse:

- measures and records output from the pouch and urine output;
- weighs the patient daily and checks blood pressure lying and standing;

- follows sodium, potassium, magnesium and creatinine results as ordered (Nightingale, 2022; Chapter 3);
- gives oral rehydration solution, IV fluids and antidiarrheal medication such as loperamide as ordered (Nightingale, 2022); and
- reports rising output, falling urine output, dizziness or abnormal results to the RN or prescriber.

Living With an Ostomy

- **Diet:** at first, the person eats soft, lower-fibre foods, chews well and eats small amounts often. Corn, nuts and seeds, dried fruit, stringy fruit, tough greens and sausage casings can block an ileostomy; cramps with little or no output, nausea or vomiting are signs of a blockage that need urgent care. Banana, applesauce, oatmeal, white bread or pasta and smooth peanut butter thicken output (AHS, 2025).
- **Fluids and salt:** people with an ileostomy are taught not to restrict salt and to drink regularly (AHS, 2025).
- **Medications:** when a large part of the bowel has been removed, medicines may not be fully absorbed, and extended-release and enteric-coated tablets must not be crushed. The nurse reports whole tablets seen in the pouch and asks the pharmacist about other forms (Ostomy Canada Society, 2024a).
- **Odour and gas:** these are normal. Eggs, fish, garlic, onions and some vegetables add odour; carbonated drinks, beer, straws and chewing gum add gas (AHS, 2025).
- **Travel:** pack supplies in carry-on luggage, take twice the usual amount and tell airport screeners about the pouch before screening (Ostomy Canada Society, 2024c).
- **Body image, sexuality and intimacy:** many people worry about their partner's reaction and about leaks. Guidance recommends assessing body image, sexuality, anxiety and depression (RNAO, 2019). The nurse raises the topic, suggests emptying the pouch beforehand and using a pouch cover or small pouch, and refers for sexual problems after rectal surgery, such as erectile changes or pain with intercourse (Ostomy Canada Society, 2024b). Cultural and religious practices around cleanliness and prayer, and the needs of 2SLGBTQI+ people, are discussed with the person (Chapter 2).
- **Peer support:** Ostomy Canada Society offers local chapters, peer support groups and a trained visitor program.
- **Supply costs:** coverage varies by province and territory. Ontario's Assistive Devices Program covers up to $975 a year for each ostomy for a permanent ostomy, or a temporary one needed for 6 months or longer, with a higher limit for people in long-term care or receiving social assistance (Government of Ontario, 2026b).

Table 25.4 Colostomy and ileostomy compared (Ostomy Canada Society, 2025; AHS, 2025; Nightingale, 2022; NSWOCC, 2023)

Feature	Colostomy	Ileostomy
Usual location	Colon; sigmoid colostomy on the left lower abdomen is common	End of the ileum; usually the right lower abdomen
Output consistency	Mushy (ascending colon) to formed (sigmoid colon)	Liquid at first, then paste-like
Output volume	Lower	Higher; more than about 1.5 L a day is high output
Skin risk	Lower; stool contains few digestive enzymes	Higher; enzymes in output irritate skin quickly
Dehydration risk	Low	High, especially in the first weeks after surgery
Pouch emptying	Less often	Often; many people empty 6 to 8 times a day
Diet notes	Usual diet; adjust for gas and odour	Low fibre at first; chew well; foods that can block; do not limit salt

GOING DEEPER

Fluid and Electrolyte Losses With a High-Output Ileostomy

Required for RN students; optional for PN students.

Ileostomy output is rich in sodium, and the small bowel lining near a stoma lets sodium move freely between blood and bowel. When a person drinks water, tea, coffee, juice or other fluids with less than about 90 mmol/L of sodium, sodium moves from the

blood into the bowel and is lost in the output. The person feels thirstier, drinks more of the same fluids and loses even more. Telling such a patient to "drink as much as possible" can make output and dehydration worse (Nightingale, 2022).

Management, as ordered, often includes:

- limiting hypotonic drinks and replacing them with an oral rehydration solution containing at least 90 mmol/L of sodium, sipped through the day; standard sports drinks contain too little sodium for this purpose;
- drugs that slow transit, such as loperamide, and sometimes acid suppression;
- IV fluids when the patient is dehydrated or has acute kidney injury.

Sodium depletion raises renin and aldosterone, which also increases potassium loss. Low magnesium is common and can cause fatigue, cramps, tetany and, if severe, seizures (Nightingale, 2022; Chapter 3). The RN tracks daily weight, intake and output, lying and standing blood pressure, and sodium, potassium, magnesium and creatinine, aiming with the team for a urine output of at least 800 mL a day (Nightingale, 2022).

SCOPE IN PRACTICE

Ostomy Care, Bowel Care and Who Does What

CNO's Scope of Practice standard explains nursing roles through **authority, competence and context** (College of Nurses of Ontario [CNO], 2025; Chapter 1, section 1.3).

- **Authority:** emptying and changing a pouch and teaching ostomy care do not involve putting anything into the body, and both RNs and RPNs do them routinely. Putting an instrument, hand or finger beyond the anal verge, as in a digital rectal examination or removal of impacted stool, or into an artificial opening such as a stoma, is a controlled act authorized to RNs and RPNs. It requires an order or medical directive unless the regulation lets the nurse initiate it in that setting. Nurses cannot initiate controlled acts in public hospitals (CNO, 2025).
- **Competence:** the nurse needs the knowledge, skill and judgment to perform the procedure safely and manage the outcomes, including knowing when to stop and report, such as when a stoma has changed colour.
- **Context:** an RPN may be the main nurse for a stable patient learning ostomy care. When output climbs, skin breaks down or a stoma changes colour, the patient's needs are changing: the RPN consults the RN and the NSWOC and keeps acting on what they see. Assigning patients by stability is an employer practice, not a CNO rule.

Employer policy and province or territory shape these roles. CNO's revised Scope of Practice and Medication standards take effect March 1, 2027 (CNO, 2026).

PRACTICE STORY

The Pouch That Kept Leaking

Names and details are fictional; this is a composite story.

Nurse: Farah Barakat, RPN. Years in practice: 6. Setting: surgical unit, Ontario.

Desmond Clarke, 34, was on day 4 after a total colectomy and end ileostomy for ulcerative colitis. When I started my evening shift, he showed me his third pouch of the day. "It just won't stay on," he said. "Maybe I'm doing it wrong."

I emptied the pouch and measured 650 mL of watery output. The flowsheet showed 2,300 mL from the stoma in the past 24 hours. He had been drinking water and ginger ale all day because the surgeon told him to "keep drinking." His urine was dark, and when he stood up he gripped the rail and said the room was moving.

When I removed the barrier, the stoma was moist and red, which was reassuring. The skin around it was another story. Desmond's skin is deep brown. Beside the stoma, a crescent of skin was darker than the rest of his abdomen, with a purplish sheen, shiny and weeping. It was not red at all. It matched exactly where the output had been tracking. He said it burned "like a sunburn." I measured the stoma: the opening in his barrier was almost a centimetre too big, likely cut when the stoma was still swollen.

I resized the barrier, protected the skin as our NSWOC had taught me, and fitted a new pouch. Then I reported to Joanne, the RN, using SBAR: high output, orthostatic dizziness, dark urine and broken peristomal skin. She assessed him, called the surgical resident, and orders followed for bloodwork, IV fluids, an oral rehydration solution and loperamide. I put in an NSWOC referral for the morning.

The next day the NSWOC changed his system and spent an hour teaching him. Desmond told me, "I thought the leaks were my fault." I learned that a leaking pouch is often a cue, not a nuisance. Sometimes it is telling you about the stoma, the skin and the whole patient.

> Reflect: Which parts of Desmond's care were within my authority and competence as an RPN, and at what point did his changing needs mean I had to consult the RN? What might have been missed if I had looked only for redness?

Chapter 25 Summary

Introduction

- Changes in bowel function are common and private; the nurse asks plainly, recognizes what is serious and acts early.
- This chapter covers bowel assessment, constipation and diarrhea, IBD, diverticular disease, appendicitis, obstruction, colorectal cancer and ostomy care.

25.1 Bowel Function, Constipation and Diarrhea

- The nurse compares bowel findings with the person's usual pattern, examines the abdomen in the order inspect, auscultate, percuss, palpate, and records stool with the Bristol Stool Form Scale.
- Bowel sounds are inaccurate and poorly agreed between listeners; the nurse weighs flatus, stool, distension, nausea, vomiting and pain more heavily.
- Constipation is prevented with fluids, fibre, activity, privacy and a regular toileting routine, and treated with laxatives chosen by class.
- Liquid stool after days without formed stool may be overflow around an impaction; an antidiarrheal makes it worse.
- Loperamide is not used in bloody diarrhea with fever, acute ulcerative colitis or antibiotic-associated colitis, and never replaces fluid and electrolyte replacement.
- Fecal incontinence is treated at its cause, with prompt toileting, skin protection and dignity.

25.2 Inflammatory Bowel Disease

- Crohn disease is patchy and full-thickness, anywhere from mouth to anus; ulcerative colitis is continuous from the rectum and limited to the colon lining.
- About 322,600 people in Canada were living with IBD in 2023, with about 470,000 expected by 2035.
- Extraintestinal manifestations include joint, eye, mouth and skin involvement; erythema nodosum may look violet, brown or darker on darker skin, so the nurse palpates and compares.
- Fecal calprotectin tracks inflammation; endoscopy with biopsy confirms the diagnosis; stool tests rule out infection.
- Corticosteroids treat flares but not maintenance; biologics and other advanced drugs follow screening for tuberculosis and hepatitis B (section 21.3).
- In a severe flare, fever, a rising heart rate, distension and tenderness, or fewer stools in a sicker patient, may mean toxic megacolon: the nurse escalates at once, and antidiarrheals are not given.

25.3 Diverticular Disease and Appendicitis

- Diverticulosis is common and usually silent; diverticulitis causes left lower quadrant pain and fever and may be complicated by abscess, perforation, fistula or obstruction.
- Antibiotics are used selectively in mild, uncomplicated diverticulitis and are strongly advised in immunocompromised patients.
- Appendicitis classically moves from periumbilical to right lower quadrant pain; older adults often present late and mildly, with high perforation rates.
- Laparoscopic appendectomy is preferred; antibiotics-first is an option for selected adults without an appendicolith.
- A rigid abdomen with fever and tachycardia suggests peritonitis: the nurse keeps the patient NPO and escalates at once; analgesia is not withheld.

25.4 Bowel Obstruction and Ileus

- Adhesions cause about 60% to 70% of small bowel obstructions; colorectal cancer, diverticular disease and volvulus are the main causes of large bowel obstruction.
- Crampy pain, distension, vomiting and no gas or stool are typical; older adults may report little pain.
- Constant pain, fever, tachycardia, peritoneal signs and a rising lactate suggest strangulation, which needs surgery without delay.
- Paralytic ileus and colonic pseudo-obstruction occur without a blockage, often with surgery, opioids, low potassium or serious illness.
- Nursing care includes NPO, NG decompression, IV fluids and electrolytes, strict intake and output, frequent reassessment and early escalation.

25.5 Colorectal Cancer Care

- About 25,300 people in Canada are expected to be diagnosed with colorectal cancer in 2026; screening helps explain falling rates.
- The CTFPHC (2016) recommends fecal testing every 2 years (or sigmoidoscopy every 10 years) from 50 to 74 (strong for 60 to 74, weak for 50 to 59); Ontario offers FIT every 2 years from 45 to 74 since July 1, 2026.
- People at increased risk need colonoscopy; people with symptoms need diagnostic assessment, not screening.
- Lower-income, some immigrant and Indigenous-language-speaking groups are screened less often; nurses help remove barriers.
- After colorectal surgery, the nurse watches for anastomotic leak: new pain, fever, tachycardia and changed drain fluid in the first week.

25.6 Ostomy Care and Teaching

- Colostomy output ranges from mushy to formed; ileostomy output is liquid to paste-like, irritates skin and raises dehydration risk.
- A healthy stoma is moist and pink to red on all skin tones; a dusky, purple or black stoma is reported at once.
- On darker skin, peristomal inflammation may look purple, brown or darker; the nurse compares skin, feels for warmth and asks about burning.
- A barrier opening only slightly larger than the stoma prevents most leaks; persistent leaks call for NSWOC referral.
- High-output ileostomy causes sodium, water and magnesium loss; hypotonic drinks make it worse.
- Teaching covers diet, fluids, medications, travel, intimacy, peer support and supply funding.

Key Terms (52)

abdominoperineal resection: surgery that removes the lower rectum and anal sphincter for a tumour near the anus, leaving a permanent colostomy.

acute colonic pseudo-obstruction: marked widening of the colon without a mechanical blockage, usually in older, seriously ill or postoperative patients.

acute severe ulcerative colitis: A flare of UC with frequent bloody stools and signs of systemic illness that needs hospital admission and IV corticosteroids.

adenoma: a type of polyp in the colon or rectum that can become cancer over time.

adhesions: bands of scar tissue inside the abdomen, usually after surgery or inflammation; the most common cause of small bowel obstruction.

anastomosis: a surgical join between two ends of bowel after a segment is removed.

anastomotic leak: leakage of bowel contents from a surgical join into the abdomen; it usually appears within the first week after surgery.

appendicitis: Inflammation of the appendix, usually after its opening is blocked.

appendicolith: A hard stone of stool in the appendix that raises the risk of perforation and of failure of antibiotic treatment.

biologic therapy: A drug made from living cells, such as an anti-TNF agent, given by infusion or injection to block a specific part of the immune response.

bowel obstruction: any problem that stops intestinal contents from moving forward, either a mechanical blockage or a loss of bowel movement (ileus).

Bristol Stool Form Scale: A seven-type picture chart that describes stool form, from separate hard lumps (type 1) to entirely liquid stool (type 7), and gives a rough guide to transit time.

closed-loop obstruction: an obstruction in which a segment of bowel is blocked at both ends, as in volvulus; it carries a high risk of strangulation.

colonoscopy: examination of the whole colon with a flexible scope, which allows polyps to be removed and tissue samples taken.

colorectal cancer: cancer of the colon or rectum, which can develop from an adenomatous polyp.

colostomy: an ostomy that brings part of the colon to the abdominal surface.

constipation: Stools that are infrequent, hard or difficult to pass, often with straining or a sense of incomplete emptying.

corticosteroid-dependent: Unable to stop corticosteroids within three months, relapsing within three months of stopping, or needing two or more courses in a year.

Crohn disease: A form of IBD that can affect any part of the gut from mouth to anus, in patchy segments, with inflammation through the full thickness of the bowel wall.

diarrhea: An increase in loose or watery stools above the person's usual pattern.

diverticulitis: Inflammation of one or more diverticula, usually causing left lower quadrant pain and fever.

diverticulosis: The presence of diverticula, small pouches that bulge outward through weak points in the colon wall.

erythema nodosum: Tender, warm, raised lumps, usually on the shins, that look pink to red on lighter skin and violet, brown or darker than surrounding skin on darker skin.

extraintestinal manifestations: Features of IBD outside the gut, such as joint pain, eye inflammation, mouth ulcers and erythema nodosum.

fecal calprotectin: A protein released by white blood cells into the stool; a sensitive but non-specific marker of bowel inflammation.

fecal immunochemical test (FIT): an at-home screening test that detects tiny amounts of human blood in a stool sample.

fecal impaction: A mass of hard stool in the rectum or colon that the person cannot pass.

fecal incontinence: The involuntary loss of liquid or solid stool.

fistula: An abnormal tunnel between the bowel and the skin, bladder, vagina or another loop of bowel.

high-output ileostomy: ileostomy output large enough to cause water and sodium depletion, generally more than about 1.5 to 2 L in 24 hours.

ileostomy: an ostomy that brings the end of the ileum to the abdominal surface; its output is liquid to paste-like.

inflammatory bowel disease (IBD): A group of chronic, relapsing conditions in which the immune system keeps the lining of the gut inflamed; the main forms are Crohn disease and ulcerative colitis.

loop ostomy: an ostomy made by bringing a loop of bowel to the surface and opening it, often as a temporary diversion.

low anterior resection: surgery that removes a tumour in the middle or upper rectum, usually joining the colon to the remaining rectum.

mechanical obstruction: a bowel obstruction caused by something that blocks, compresses or twists the bowel, such as adhesions, a hernia, a tumour or volvulus.

nasogastric decompression: drainage of swallowed air and gastrointestinal fluid through a nasogastric tube to relieve distension and vomiting.

Nurse Specialized in Wound, Ostomy and Continence (NSWOC): a registered nurse with advanced education and clinical skills in wound, ostomy and continence care.

ostomy: a surgically created opening into the bowel or urinary tract through which stool or urine leaves the body.

overflow diarrhea: Liquid stool that leaks around a fecal impaction and can be mistaken for ordinary diarrhea.

paralytic ileus: a loss of the bowel's propulsive movement without any physical blockage, causing gas and fluid to build up.

parastomal hernia: a bulge of abdominal contents through the abdominal wall opening around a stoma.

peristomal skin: the skin around a stoma, which should look like the person's skin elsewhere on the abdomen.

peritonitis: Inflammation of the lining of the abdominal cavity, often from a perforated organ, causing a rigid abdomen and risk of sepsis.

postoperative ileus: the expected pause in bowel movement after surgery, lasting until the patient passes gas or stool and tolerates oral intake.

pouching system: the skin barrier and pouch that protect the skin and collect stoma output; one-piece or two-piece.

stoma: the end of bowel brought through the abdominal wall and folded back at the skin; healthy stomas are moist and pink to red.

stoma site marking: choosing and marking the best location for a planned stoma before surgery, with the person sitting, standing and bending.

strangulation: loss of blood supply to a trapped segment of bowel, leading to ischemia, necrosis and perforation; a surgical emergency.

tenesmus: A painful feeling of needing to pass stool even when the rectum is empty.

toxic megacolon: Marked widening of an inflamed colon, seen on X-ray, with systemic illness and a risk of perforation.

ulcerative colitis (UC): A form of IBD limited to the colon, starting in the rectum and spreading upward without gaps, that inflames the inner lining.

volvulus: a twist of a loop of bowel, most often the sigmoid colon or cecum, on its own mesentery.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Ms. Leah Tremblay (Questions 1–4): Ms. Leah Tremblay, 24, a university student with ulcerative colitis diagnosed two years ago, is admitted to a medical unit in Ontario with a flare. She reports nine bloody stools in the past 24 hours, cramping and urgency. Vital signs: heart rate 104 beats per minute, temperature 37.9 °C, blood pressure 112/70 mm Hg. Hemoglobin is 112 g/L. IV methylprednisolone has been started. A registered practical nurse (RPN) is caring for her with a registered nurse (RN) on the team.

1. [CORE] Which set of data will best show the RPN whether Ms. Tremblay's flare is responding to treatment?

a. Bowel sounds in all four quadrants each shift, with a note of whether they are hypoactive or hyperactive

b. Her rating of cramping before and after each dose of analgesic, recorded on the pain flow sheet

c. The number of stools and amount of blood in each 24 hours, with her heart rate and temperature

d. Her daily meal intake and her fluid preferences, recorded by the dietary aide on the tray card

Answer: c — Recognize cues (section 25.2). Stool frequency, blood, heart rate and temperature are the markers used to track a UC flare and to judge response to IV steroids (c). Bowel sounds (a) are unreliable and do not measure flare activity. Pain ratings (b) matter for comfort but do not track inflammation. Meal intake and preferences (d) support nutrition but do not show response to treatment.

2. [CORE] On day 2, Ms. Tremblay's abdomen is more distended and tender. Her heart rate is 122 beats per minute and her temperature 38.6 °C. She says, "At least I've only had two bowel movements today." How should the RPN interpret these findings?

a. The fall in stool frequency shows the corticosteroid is working, and the fever is an expected drug effect

b. The findings may signal toxic megacolon, and the drop in stools is a warning sign rather than a sign of improvement

c. The distension most likely reflects gas from the cramping, and the fast heart rate reflects her anxiety

d. The findings suggest dehydration from the earlier diarrhea, which should settle once she drinks more fluid by mouth over the next few hours

Answer: b — Analyze cues (section 25.2, Recognizing a Severe Flare). Distension, tenderness, fever and tachycardia with fewer stools in a patient who looks sicker may mean the colon has dilated and stopped moving (b). Corticosteroids do not cause fever (a), and fewer stools are not reassuring with these signs. Gas and anxiety (c) do not explain fever with a rising heart rate. Dehydration (d) does not explain new distension and tenderness, and oral fluids would delay escalation.

3. [CORE] Before she became unwell, Ms. Tremblay asks whether she can take the loperamide she keeps at home when her bowel movements are frequent. Which response by the RPN is most accurate?

a. "Yes. It is safe to take whenever stools are frequent, as long as you drink plenty of extra fluid."

b. "Yes, but only at night, so your sleep is not interrupted by urgency during a flare."

c. "Only if your stools are also watery; it is not a problem when there is only a small amount of blood in them."

d. "Not during a flare. It can contribute to dangerous swelling of the colon, so call your team instead."

Answer: d — Take action, teaching (sections 25.1 and 25.2). The Canadian loperamide monograph contraindicates it in acute ulcerative colitis and in dysentery with blood and fever, and says to stop it at once if the abdomen becomes distended; slowing the bowel during a flare can contribute to colonic dilation (d). Extra fluid (a) does not make it safe. Timing (b) does not change the risk. Blood in the stool (c) is a reason not to use it.

4. [CORE] Later, Ms. Tremblay is tearful. She says she is afraid she will "end up with a bag," has missed her exams, and "doesn't see the point anymore." What should the RPN do first?

a. Acknowledge her fears, ask directly whether she is thinking of harming herself, and report her answers to the RN

b. Reassure her that most people with ulcerative colitis never need surgery, then suggest that she rest quietly and try to sleep until she feels more like herself

c. Give her a pamphlet about ostomies so she can learn more about the surgery and feel less worried

d. Tell her that feeling low is an expected side effect of corticosteroids and will pass once the dose is reduced

Answer: a — Take action (section 25.2; Chapter 1, section 1.3). "Doesn't see the point anymore" is a cue that needs a direct question about self-harm, and the RPN consults the RN and team as her needs change (a). False reassurance (b) dismisses her fear and misses the risk. A pamphlet (c) does not address her distress. Steroids can affect mood, but labelling her feelings as a side effect (d) leaves the safety risk unassessed. Psychiatric disorders are more common in people with IBD.

5. [CORE] A patient's stool is documented as Bristol type 1. What does this finding suggest?

a. Rapid transit through the bowel, with too little time for water to be absorbed

b. Slow transit through the bowel, with constipation and hard stool

c. Normal transit, with stool that is soft, smooth and easy to pass

d. Bleeding high in the gastrointestinal tract, with black, sticky stool

Answer: b — Section 25.1. Types 1 and 2 are hard lumps and suggest slow transit and constipation (b). Rapid transit (a) produces types 5 to 7. Smooth, soft, formed stool (c) is type 3 or 4. The scale describes form, not colour; black, tarry stool (d) suggests upper GI bleeding (section 24.5).

6. [CORE] On the second day after surgery, a nurse hears bowel sounds in all four quadrants. The patient has passed no gas, feels nauseated and has a firm, distended abdomen. Which conclusion is best supported?

a. The bowel is working normally because bowel sounds are present in all quadrants

b. The nausea is most likely caused by anxiety, because the bowel sounds are normal

c. Bowel sounds alone cannot confirm bowel function, and the other findings need to be reported

d. The patient should be given a stimulant laxative so that gas and stool can be passed

Answer: c — Section 25.1. Bowel sounds are inaccurate and poorly agreed between listeners, so they should not drive decisions (c); no flatus, nausea and distension need reporting. Present bowel sounds (a) do not prove normal function. Attributing nausea to anxiety (b) ignores the other cues. A laxative (d) could harm a patient with possible obstruction and is not given without assessment and an order.

7. [CORE] A patient is starting psyllium for constipation. Which instruction should the nurse include?

a. Take each dose with a full glass of water or other fluid, and keep drinking fluids through the day

b. Take each dose with only a small sip of water, so the powder stays thick and works faster

c. Take it only when you have not had a bowel movement for at least five days in a row

d. Stop drinking fluids for one hour after each dose so the fibre can absorb water from the bowel

Answer: a — Section 25.1, Table 25.1. Bulk-forming laxatives absorb water and need enough fluid to soften stool safely (a). Too little fluid (b, d) can make stool harder and risks blockage. Psyllium is a regular measure, not a rescue taken after days without stool (c).

8. [CORE] A patient on IV antibiotics for pneumonia develops five watery stools in 12 hours. The patient asks for "something to stop the diarrhea." What is the nurse's best action?

a. Give loperamide from the unit stock, then reassess the patient's stool pattern in 48 hours

b. Encourage the patient to eat more fibre and drink more fluids to firm the stool, and reassess the stool at the next shift

c. Hold the antibiotic until the diarrhea stops, then inform the prescriber at the next rounds

d. Start contact precautions as policy directs, notify the prescriber, and send a stool sample if ordered

Answer: d — Section 25.1; section 4.4. New diarrhea after antibiotics may be *C. difficile* infection, so precautions, testing and notification come first (d). Loperamide (a) must not be used until infection is considered; the monograph contraindicates it in pseudomembranous colitis after broad-spectrum antibiotics. Fibre (b) delays assessment. The nurse does not hold an ordered antibiotic (c) without speaking to the prescriber.

9. [CORE] An older adult with fecal incontinence is embarrassed and has started refusing fluids "to avoid accidents." Which nursing action best protects her dignity and health?

a. Place an absorbent pad under her and check it at the end of the shift, so that her sleep and rest are not interrupted

b. Set a regular toileting schedule, answer her call bell promptly, and explain why fluids still matter

c. Agree to limit her fluids to small sips, since this is her choice and will reduce leakage

d. Ask a family member to stay with her overnight so she can be helped to the toilet

Answer: b — Section 25.1, Fecal Incontinence in Brief. Regular toileting, prompt help and teaching address the cause and her fears while preventing dehydration (b). Leaving a pad until the end of the shift (a) harms skin and dignity. Restricting fluids (c) risks dehydration and constipation, and the nurse explores her choice rather than simply agreeing. Family presence (d) shifts nursing responsibility and does not address the problem.

10. [CORE] Which finding is more typical of Crohn disease than of ulcerative colitis?

a. Continuous inflammation starting in the rectum and spreading upward through the colon

b. Inflammation limited to the inner lining of the colon, with bloody diarrhea

c. Patchy disease with normal areas between, and inflammation through the full bowel wall

d. Tenesmus with urgency, from inflammation that always includes the rectum

Answer: c — Section 25.2, Table 25.2. Skip lesions and full-thickness inflammation are features of Crohn disease (c). Continuous disease from the rectum (a), inflammation of the inner lining with bloody diarrhea (b), and tenesmus from rectal involvement (d) are typical of ulcerative colitis.

11. [CORE] A patient with known ulcerative colitis has a fecal calprotectin of 450 mcg/g. Stool tests for infection are negative. How should the nurse understand this result?

a. It suggests active bowel inflammation and supports discussion of endoscopy with the specialist

b. It confirms a new diagnosis of colorectal cancer and will need surgery

c. It is within the range expected for a person whose ulcerative colitis is in remission and needs no change in treatment

d. It shows that the patient is dehydrated and needs IV fluids at once

Answer: a — Section 25.2. In UC, a calprotectin over 200 mcg/g suggests the lining is not healed and should prompt discussion of endoscopy (a). Calprotectin reflects inflammation; it does not diagnose cancer (b). Values under 100 mcg/g make healing likely, so 450 mcg/g is not consistent with remission (c). It does not measure hydration (d).

12. [CORE] Which findings in a patient with inflammatory bowel disease are extraintestinal manifestations? Select all that apply.

a. Tender, raised lumps on both shins that look dark brown on the patient's deep brown skin

b. A painful red eye with blurred vision and new sensitivity to light

c. Painful swelling of the knees and ankles during a flare

d. A fistula draining from the skin near the anus

e. Painful ulcers on the inside of the mouth

f. Cramping lower abdominal pain before each bowel movement

Answer: a, b, c, e — Section 25.2. Erythema nodosum (a), which may look violet, brown or darker than surrounding skin on darker skin tones; eye inflammation (b); joint involvement (c); and mouth ulcers (e) are extraintestinal manifestations. A perianal fistula (d) and cramping before bowel movements (f) are features of the bowel disease itself.

13. [CORE] A patient with Crohn disease is to start infliximab. What should the nurse confirm before the first infusion?

a. That the patient has stopped all other IBD medications for at least one week

b. That the patient has eaten a high-fibre meal beforehand to protect the bowel lining during the infusion

c. That a colonoscopy has been completed within the past 24 hours

d. That screening for tuberculosis and hepatitis B, and a vaccine review, have been completed

Answer: d — Section 25.2; section 21.3. Before a biologic starts, screening for tuberculosis and hepatitis B and a vaccine review are needed (d). Other IBD drugs (a) are adjusted only by the specialist, and some are given with anti-TNF therapy. Diet (b) and a recent colonoscopy (c) are not requirements for an infusion.

14. [CORE] A patient recovering from uncomplicated diverticulitis asks how to lower the risk of another episode. Which advice is consistent with current guidance?

a. Eat a low-fibre diet for life, so stool passes through the colon more slowly

b. Eat a high-quality diet with fibre, stay active, and avoid NSAIDs unless aspirin is prescribed for the heart

c. Take a course of antibiotics each month, even when well, to prevent the pouches in the colon from becoming infected again

d. Plan surgery to remove the sigmoid colon after a second episode, to prevent a third

Answer: b — Section 25.3. The AGA links diverticulitis to diet quality, inactivity, obesity, smoking and NSAIDs, with aspirin for cardiovascular prevention the exception (b). A lifelong low-fibre diet (a) is not advised. Routine antibiotics (c) are not recommended; antibiotics are used selectively for acute episodes. Surgery is individualized and not based on the number of episodes alone (d).

15. [CORE] An RPN is caring for a patient admitted with diverticulitis. The patient's pain is suddenly much worse and spreading, the abdomen is hard, and the heart rate has risen from 92 to 118 beats per minute. What should the RPN do first?

a. Call the RN and the prescriber at once, or a rapid response if criteria are met, and keep the patient NPO

b. Give the next scheduled dose of oral antibiotic early, then reassess the abdomen and vital signs in one hour

c. Apply a warm pack to the abdomen and help the patient into a comfortable position to rest

d. Document the findings and report them to the RN at the end-of-shift handover

Answer: a — Section 25.3, Clinical Safety box; Chapter 6. Sudden spreading pain, a rigid abdomen and tachycardia suggest perforation and peritonitis. Every nurse who notices deterioration acts at once and escalates, and the RPN consults the RN as the patient's needs change (a). Oral antibiotics (b) and a warm pack (c) delay urgent care. Waiting until handover (d) is unsafe.

16. [CORE] An RPN in an Ontario long-term care home suspects fecal impaction in a resident. The resident has no order or medical directive for a digital rectal examination or disimpaction. What should the RPN do?

a. Perform a digital rectal examination, because confirming the impaction is in the resident's best interest

b. Give a sodium phosphate enema from stock, then report the result to the prescriber the next day

c. Assess the abdomen and bowel record, then contact the prescriber for direction and an order

d. Ask an unregulated care provider to perform the examination, then document the findings

Answer: c — Section 25.1; Scope in Practice box in section 25.6; Chapter 1, section 1.3. Putting a finger beyond the anal verge is a controlled act; the RPN needs authority (an order or directive), competence and a supportive context (c). Acting without an order (a) or giving an unordered enema (b) is outside authority. Delegating to an unregulated care provider (d) is not appropriate without the required authority and employer policy.

17. [CORE] A patient in the emergency department has suspected appendicitis and rates her pain 8 out of 10. A colleague says analgesia should wait until the surgeon has examined her, "so we don't mask the signs." What is the nurse's best response?

a. Agree, because pain medicine given before the surgical examination is likely to hide a perforation

b. Offer a warm pack and repositioning instead, since these do not affect the diagnosis

c. Give only half of the ordered dose, so that some of the pain remains for the examination

d. Give the ordered analgesic, because evidence shows opioids do not increase diagnostic errors

Answer: d — Section 25.3, Clinical Safety box. A Cochrane review found opioid analgesia in acute abdominal pain does not increase errors in diagnosis or treatment decisions, so pain should be treated (d). Withholding (a) or underdosing (c) analgesia causes needless suffering. Comfort measures (b) are helpful additions but do not replace ordered analgesia.

18. [RN] **Ms. Okoro, 38, is on day 3 of IV methylprednisolone for acute severe ulcerative colitis. In the past 24 hours she has had 6 bloody stools, and her CRP is 62 mg/L. What is the RN's best interpretation?**

a. She meets day-3 criteria that predict colectomy, so rescue therapy or surgery should be discussed now

b. She is responding well to IV steroids, because her stool count is below the threshold of 8 a day

c. She should continue IV steroids for at least another 7 days before her response to treatment can be fairly judged

d. Her CRP is expected to rise with corticosteroids, so only her stool frequency should be followed

Answer: a — Section 25.2, Going Deeper box. On day 3, 3 to 8 stools a day with a CRP over 45 mg/L, or more than 8 stools, predicted colectomy in about 85% of patients; Canadian consensus advises moving early to rescue therapy when there is no response to IV steroids by 72 hours (a). Fewer than 8 stools (b) is not reassuring when CRP is high. Waiting 7 more days (c) delays rescue and raises surgical risk. Corticosteroids do not raise CRP (d), and CRP is part of the assessment.

19. [RN] **Mr. Hughes, 84, has had no formed stool for 6 days and has had small amounts of liquid stool leaking through the day. He is newly confused and has a firm abdomen. The prescriber is about to order loperamide. What is the RN's best action?**

a. Give the loperamide as ordered, since frequent liquid stool risks dehydration in older adults

b. Question the order, explain that overflow around an impaction is likely, and request assessment and a bowel plan

c. Restrict his fluids until the leakage stops, to reduce the volume of liquid stool

d. Start contact precautions and wait for the stool test results before taking any further action on his bowel symptoms

Answer: b — Section 25.1 and Lifespan box. Liquid leakage after days without formed stool, with confusion and a firm abdomen, suggests impaction with overflow; an antidiarrheal would worsen it, so the RN advocates for assessment and a bowel plan (b). Loperamide (a) is the wrong treatment. Fluid restriction (c) worsens constipation and dehydration. Infection is worth considering, but waiting for results (d) delays treating the likely cause.

20. [RN] **Mrs. Lavoie, 79, has had 2 days of mild lower abdominal discomfort and loss of appetite. Her temperature is 37.6 °C, and she says, "It's not that bad." Her white blood cell count is mildly raised. Which statement about appendicitis in older adults best guides the RN's actions?**

a. Older adults usually have more severe pain than younger adults, so mild pain makes appendicitis unlikely

b. Clinical scores such as the Alvarado score reliably rule out complicated appendicitis in older adults

c. Older adults often present late with milder symptoms and have high perforation rates, so prompt surgical assessment is needed

d. Appendicitis is rare after age 60, so the RN should first look for another cause such as constipation

Answer: c — Section 25.3. Older adults often present atypically and late, and perforation rates over age 50 have been reported at 55% to 70%, so mild symptoms need prompt surgical assessment (c). Pain is often milder, not more severe (a). The Alvarado score is unreliable for judging severity in older adults (b). Appendicitis occurs at any age, and assuming another cause (d) risks delay.

Case: Ernesto Salgado (Questions 21–26): Ernesto Salgado, 78, comes to the emergency department with 18 hours of crampy abdominal pain that comes in waves. He has vomited green fluid four times and has not passed gas since last evening. He had a sigmoid colectomy 6 years ago and an open appendectomy as a young man. His abdomen is distended, and he says the pain is "not too bad between the waves." Vital signs: temperature 37.2 °C, heart rate 98, blood pressure 128/76 mm Hg, respiratory rate 18, oxygen saturation 96% on room air. Laboratory results: potassium 3.2 mmol/L, creatinine 128 µmol/L (85 µmol/L three months ago), lactate 1.6 mmol/L. CT shows an adhesive small bowel obstruction without signs of ischemia. He is admitted to the surgical unit for nonoperative care.

21. [CORE] Which findings in Mr. Salgado's assessment are consistent with a small bowel obstruction? Select all that apply.

a. Crampy pain that comes in waves
b. Oxygen saturation of 96% on room air
c. Repeated vomiting of green fluid
d. No gas passed since last evening
e. Temperature of 37.2 °C
f. Previous abdominal surgery

Answer: a, c, d, f — Colicky pain in waves, vomiting and no passage of gas are typical of small bowel obstruction, and previous abdominal surgery points to adhesions, the most common cause (section 25.4). His oxygen saturation (b) is normal and unrelated. A temperature of 37.2 °C (e) is normal; fever would instead raise concern for strangulation.

22. [CORE] Which explanation best accounts for Mr. Salgado's potassium and creatinine results?

a. Muscle breakdown from lying on the floor for a long period before he came to hospital
b. Fluid and potassium lost through vomiting and fluid trapped in the swollen bowel
c. Chronic kidney disease that has slowly progressed over the past three months
d. A laboratory error, since an obstruction does not change potassium or creatinine

Answer: b — Vomiting and fluid held in the obstructed bowel cause dehydration and potassium loss; the creatinine rise from his recent baseline fits reduced kidney blood flow (section 25.4; Chapter 3). Nothing suggests a long lie (a). A rise over three months with this acute illness points to an acute cause, not slowly progressing kidney disease (c). Obstruction commonly causes fluid and electrolyte changes, so dismissing the results (d) is unsafe.

23. [CORE] Which problem should the nurse address first in Mr. Salgado's plan of care?

a. Constipation caused by low fibre intake before admission
b. Anxiety about a possible operation and a long hospital stay
c. Risk for falls related to his age and the unfamiliar hospital setting
d. Fluid volume deficit and low potassium from vomiting and bowel losses

Answer: d — Dehydration and hypokalemia are present now and can affect kidney function and heart rhythm, so they come first (section 25.4). His lack of stool is caused by the obstruction, not by low fibre (a). Anxiety (b) and fall risk (c) are real and are addressed, but they are less urgent than his physiologic losses.

24. [CORE] An NG tube has been inserted and placed on suction as ordered. Two hours later, it has drained nothing, Mr. Salgado feels more nauseated and his abdomen is more distended. What should the nurse do first?

a. Check that the tube is patent and working as policy directs, then report if drainage does not resume
b. Give him small sips of water to rinse his mouth and help loosen any thick secretions in the tube
c. Remove the NG tube, because the lack of drainage shows that it is no longer needed
d. Record the finding and reassess at the next scheduled check in four hours

Answer: a — No drainage with rising nausea and distension suggests a blocked or displaced tube, so the nurse checks it as policy directs and reports if drainage does not return (section 25.4; Chapter 24). Sips of water (b) break NPO. A silent tube with worsening symptoms does not mean decompression is no longer needed (c). Waiting four hours (d) risks vomiting and aspiration.

25. [RN] On day 2, Mr. Salgado says his pain is "constant now, not coming and going." Temperature 38.4 °C, heart rate 124, blood pressure 104/62 mm Hg. His abdomen is tender with guarding. Lactate is 4.1 mmol/L. Which action should the RN take first?

a. Give the ordered as-needed opioid and reassess the pain in one hour before calling anyone
b. Increase the NG suction to a higher setting to relieve the distension more quickly
c. Report to the surgeon at once using SBAR, because these cues suggest strangulation
d. Encourage him to walk in the hallway to stimulate the return of bowel movement

Answer: c — Constant pain, fever, tachycardia, guarding and a rising lactate suggest strangulation and ischemia, which need surgery without delay (section 25.4; Chapter 6). Analgesia (a) is given as ordered, but waiting an hour to report delays surgery. Changing suction settings without an order (b) does not treat ischemia. Walking (d) is part of care for an uncomplicated course, not for a deteriorating patient.

26. [CORE] Mr. Salgado has surgery to divide the adhesions and remove a short segment of dead bowel. Which finding 3 days later best shows that his bowel function is returning?

a. His NG drainage has increased from 200 mL to 700 mL over the past shift
b. He is passing gas, his abdomen is softer and he says he feels hungry
c. His pain score is 2 out of 10 after a dose of oral acetaminophen
d. His incision is clean and dry, with edges that are well approximated

Answer: b — Passing gas, less distension and a returning appetite are signs that bowel function is returning (section 25.4). Rising NG drainage (a) suggests ileus is continuing. Good pain control (c) and a healing incision (d) are positive, but neither shows bowel function.

27. [CORE] A patient had a bowel resection 4 days ago and has had postoperative ileus. Which finding best shows that the ileus is resolving?

a. Bowel sounds were heard once during a 1-minute check this morning

b. The abdomen is more rounded than yesterday but not tender to touch

c. The patient is passing gas and has kept down clear fluids for 12 hours

d. The patient has had no nausea since the antiemetic dose given an hour ago

Answer: c — Postoperative ileus ends when the patient passes gas or stool and tolerates oral intake (section 25.4). Bowel sounds (a) are unreliable on their own (section 25.1). Increasing roundness (b) suggests ongoing distension. Relief from an antiemetic (d) does not show that the bowel is moving.

28. [CORE] A 47-year-old in Ontario with no symptoms asks about colon cancer screening. No one in their family has had colon cancer. What should the nurse tell them?

a. "You are eligible for an at-home stool test, called FIT, every 2 years."

b. "Screening starts at age 50, so you can wait until then to think about it."

c. "You should book a colonoscopy every 5 years, starting as soon as possible."

d. "Screening is only needed if you notice blood in your stool or other symptoms."

Answer: a — Since July 1, 2026, Ontario's program offers FIT every 2 years to people at average risk from age 45 to 74 (section 25.5). Age 50 (b) was the previous starting age. Colonoscopy every 5 years (c) is for people at increased risk. Screening is for people without symptoms; symptoms need diagnostic assessment (d).

29. [CORE] A patient's FIT result is abnormal. They say, "So I have cancer." Which response by the nurse is most accurate?

a. "Not necessarily. Repeat the stool test in 2 years, and we will compare the two results."

b. "Yes, but colon cancer found through screening is almost always curable with surgery."

c. "Probably not. An abnormal result is usually caused by something you ate the day before."

d. "Not necessarily. It means you need a colonoscopy, ideally within the next 8 weeks."

Answer: d — An abnormal FIT means more testing is needed, not that cancer is present, and the program recommends colonoscopy within 8 weeks (section 25.5). Repeating FIT in 2 years (a) is for normal results. Option b states cancer as fact. FIT does not require diet changes, and blaming food (c) is false reassurance that may delay follow-up.

30. [CORE] A 58-year-old asks the nurse for a FIT kit. They mention 2 months of narrower stools, occasional dark red blood and fatigue. What is the best response?

a. "A FIT kit is a good idea; you can order one through Health811 and send it in."

b. "These symptoms need assessment by your physician or NP now, rather than a screening test."

c. "Narrow stools are common with age; screening every 2 years will catch any problem."

d. "Wait to see if the symptoms continue for another month before doing anything."

Answer: b — Screening is for people without symptoms. Rectal bleeding, narrower stools and possible anemia need prompt diagnostic assessment (section 25.5). A FIT kit (a) could delay diagnosis. Option c dismisses warning signs. Waiting (d) delays care.

31. [CORE] An 81-year-old with chronic kidney disease who takes a diuretic is preparing for colonoscopy. Which teaching point is most important for this patient?

a. "Stop all of your usual medications the day before, including the diuretic and heart pills."

b. "Drink only plain water during the preparation so that your bowel is as clear as possible."

c. "Drink a variety of clear fluids, and call if you vomit, feel dizzy or pass very little urine."

d. "Have a full meal the evening before so that you have the energy for the preparation."

Answer: c — Older adults and people with kidney disease or on diuretics are at higher risk of fluid and electrolyte problems during bowel preparation; drinking varied clear fluids and reporting vomiting, dizziness or low urine output are key (section 25.5, Patient Education box). Medications are changed only as the prescriber directs (a). Water alone (b) can lower sodium. A full meal (d) breaks the low-fibre and clear-fluid instructions.

32. [CORE] On the first day after surgery, the nurse finds that a patient's new colostomy is dark purple, almost black, and dry. What should the nurse do?

a. Report the finding to the surgeon at once, because the stoma's blood supply may be failing

b. Document the colour as expected swelling and reassess the stoma at the next pouch change

c. Apply a barrier ring and a convex pouch to support the stoma and protect the skin around it

d. Ask the patient to lie flat for an hour to improve blood flow to the stoma, then reassess

Answer: a — A healthy stoma is moist and pink to red on every skin tone; a dusky, dark or black stoma may be losing its blood supply and needs immediate surgical review (section 25.6). It is not expected (b). Changing pouching products (c) does not address ischemia, and convexity adds pressure. Repositioning (d) delays reporting.

33. [CORE] The nurse is assessing the peristomal skin of a patient with deep brown skin who has had several pouch leaks. Which findings suggest irritant dermatitis? Select all that apply.

a. The stoma is moist and red, and bleeds slightly when cleaned

b. The skin beside the stoma is darker and purplish compared with the rest of the abdomen

c. The patient describes burning and stinging under the barrier

d. The skin around the stoma looks the same as the skin on the opposite side

e. A shiny, weepy area matches the path where output has leaked

f. The affected area feels warmer than the surrounding skin

Answer: b, c, e, f — On darker skin, inflammation may look darker, purple or brown rather than red; burning, a weepy area that follows the leak and warmth all point to irritant dermatitis (section 25.6). A moist red stoma that bleeds slightly when cleaned (a) is normal. Skin that matches the rest of the abdomen (d) is healthy.

34. [CORE] A patient's ileostomy pouch has leaked twice today. The barrier opening is about 1 cm wider than the stoma all around. Which action should the nurse take?

a. Add tape around the edges of the barrier to hold it more firmly in place

b. Change the pouch less often, so the skin has time to rest between changes

c. Cut the next opening smaller than the stoma, so the barrier presses snugly against it

d. Re-measure the stoma and cut the opening no more than about 3 to 4 mm larger

Answer: d — An opening only slightly larger than the stoma base protects the skin and reduces leaks (section 25.6). Tape (a) does not stop output reaching exposed skin. Leaving a leaking pouch in place (b) worsens skin damage. An opening smaller than the stoma (c) can injure the stoma.

35. [CORE] Which statement by a patient with a new ileostomy shows understanding of diet teaching?

a. "I should eat lots of raw vegetables and nuts now to keep my output regular."

b. "I'll chew my food well and add foods like corn and nuts back slowly, in small amounts."

c. "I should cut back on salt, because the ileostomy will make me hold extra fluid."

d. "If I have cramps and no output for several hours, I'll eat more fibre to push it through."

Answer: b — Chewing well and reintroducing foods that can cause a blockage slowly and in small amounts lowers the risk of a food blockage (section 25.6). Raw vegetables and nuts early on (a) can cause blockage. People with an ileostomy lose sodium and should not limit salt (c). Cramps with no output may signal a blockage, which needs urgent care, not more fibre (d).

36. [CORE] An RPN in a long-term care home in Ontario suspects that a resident has a fecal impaction. Which statement about the RPN's authority to remove the impaction digitally is accurate?

a. The RPN cannot remove an impaction in any setting, because only RNs and physicians are authorized for this act.

b. The RPN may remove it whenever the resident seems uncomfortable, because no order or directive is ever needed.

c. It is a controlled act; the RPN needs an order or directive, or a setting where initiation is permitted.

d. A personal support worker should remove it, because helping with bowel care is a routine daily living activity.

Answer: c — Putting an instrument, hand or finger beyond the anal verge is a controlled act authorized to RNs and RPNs; it needs an order or directive unless initiation is permitted in that setting, and employer policy applies (section 25.6, Scope in Practice box). RPNs are authorized for this controlled act (a). Authority still requires the right mechanism, competence and a supportive setting (b). Disimpaction is not a routine activity of daily living (d).

37. [CORE] A patient with an ileostomy tells the nurse they have seen whole tablets of their extended-release heart medication in the pouch. What should the nurse do?

a. Report it to the prescriber and ask the pharmacist about another form of the medication

b. Crush the extended-release tablets from now on so that they dissolve before they reach the stoma

c. Reassure the patient that the medication was absorbed before the tablet shell passed through

d. Tell the patient to take a second tablet whenever a whole one is seen in the pouch

Answer: a — Medicines may not be fully absorbed after bowel surgery, and a whole tablet in the pouch suggests the dose was not absorbed, so the nurse reports it and asks for another form (section 25.6). Crushing extended-release tablets (b) can release a full day's dose at once. The nurse cannot assume the drug was absorbed (c). Extra doses without an order (d) are unsafe.

38. [RN] A patient with a new ileostomy has had 2,600 mL of output in 24 hours. He has been drinking about 3 L of water and tea a day "to keep up." Results: sodium 131 mmol/L, magnesium 0.58 mmol/L, creatinine 142 µmol/L (90 µmol/L at admission). Which plan should the RN expect the team to order?

a. Encourage him to drink even more water and tea, aiming for at least 4 L each day

b. Stop all oral fluids and food until the ileostomy output falls below 1 L each day

c. Give a diuretic to protect the kidneys and lower the extra fluid he is drinking

d. Limit hypotonic drinks, use a high-sodium oral rehydration solution and replace magnesium

Answer: d — Hypotonic fluids draw sodium into the bowel and increase output, so they are limited and replaced with an oral rehydration solution of at least 90 mmol/L sodium; low magnesium is replaced (section 25.6, Going Deeper box). More water (a) worsens losses. Stopping all intake (b) is not the standard first step. A diuretic (c) would worsen dehydration and kidney injury.

39. [RN] Five days after a low anterior resection, a patient reports new abdominal pain. Temperature 38.3 °C, heart rate 118, blood pressure 108/64 mm Hg. Drain fluid, clear yesterday, is now cloudy and smells foul. What should the RN suspect and do?

a. Postoperative ileus; keep the patient NPO and reassess tomorrow morning

b. Anastomotic leak; report to the surgeon at once and anticipate a CT scan

c. Surgical site infection; take a swab of the incision and continue to monitor

d. Expected inflammation after surgery; give acetaminophen and recheck in four hours

Answer: b — New pain, fever, tachycardia and cloudy, foul drain fluid within the first week suggest an anastomotic leak, which needs urgent surgical review and usually a contrast CT (section 25.5). Ileus (a) does not explain fever and changed drain fluid. A wound infection (c) does not explain the drain changes, and only monitoring delays treatment. These signs are not expected (d).

40. [CORE] A 39-year-old in Ontario has no symptoms. Their father was diagnosed with colon cancer at age 52. When should screening begin, and with which test?

a. Colonoscopy at age 40, repeated every 5 years if normal

b. Colonoscopy at age 42, which is 10 years before the father's diagnosis

c. FIT every 2 years starting at age 45, the same as people at average risk

d. FIT every 2 years starting now, because the father was diagnosed before 60

Answer: a — One parent diagnosed before age 60 means increased risk. Colonoscopy starts at age 40 or 10 years before the relative's diagnosis (42), whichever comes first, and is repeated every 5 years (section 25.5). Age 42 (b) is later than 40. FIT (c, d) is the test for people at average risk.

References

Alavi, K., Poylin, V., Davids, J. S., Patel, S. V., Felder, S., Valente, M. A., Paquette, I. M., & Feingold, D. L. (2021). The American Society of Colon and Rectal Surgeons clinical practice guidelines for the management of colonic volvulus and acute colonic pseudo-obstruction. *Diseases of the Colon & Rectum, 64*(9), 1046–1057. https://doi.org/10.1097/DCR.0000000000002159

Alberta Health Services. (2025). *Eating well after ileostomy surgery* (404252-NFS). https://www.albertahealthservices.ca/assets/info/nutrition/if-nfs-eating-well-after-ileostomy-surgery.pdf

American Society of Colon and Rectal Surgeons. (n.d.). *Treatment of left-sided colonic diverticulitis* [Patient guideline summary]. Guideline Central. https://www.guidelinecentral.com/guideline/41075/patient-summary/2014403/

Bitton, A., Buie, D., Enns, R., Feagan, B. G., Jones, J. L., Marshall, J. K., Whittaker, S., Griffiths, A. M., & Panaccione, R. (2012). Treatment of hospitalized adult patients with severe ulcerative colitis: Toronto consensus statements. *The American Journal of Gastroenterology, 107*(2), 179–194. https://doi.org/10.1038/ajg.2011.386

Brenner, D. R., Gillis, J., Demers, A. A., Ellison, L. F., Ng, C., Zhang, S. X., Finley, C., Fitzgerald, N., Saint-Jacques, N., Shack, L., Turner, D., Urquhart, R., & Woods, R. R. (2026). Projected estimates of cancer in Canada in 2026. *CMAJ, 198*(14), E526–E534. https://doi.org/10.1503/cmaj.252152

Bressler, B., Marshall, J. K., Bernstein, C. N., Bitton, A., Jones, J., Leontiadis, G. I., Panaccione, R., Steinhart, A. H., Tse, F., Feagan, B., & Toronto Ulcerative Colitis Consensus Group. (2015). Clinical practice guidelines for the medical management of nonhospitalized ulcerative colitis: The Toronto consensus. *Gastroenterology, 148*(5), 1035–1058. https://doi.org/10.1053/j.gastro.2015.03.001

Breum, B. M., Rud, B., Kirkegaard, T., & Nordentoft, T. (2015). Accuracy of abdominal auscultation for bowel obstruction. *World Journal of Gastroenterology, 21*(34), 10018–10024. https://doi.org/10.3748/wjg.v21.i34.10018

Bristol-Myers Squibb Canada. (2024). *Zeposia (ozanimod) capsules* [Product monograph]. https://www.bms.com/assets/bms/ca/documents/productmonograph/ZEPOSIA_EN_PM.pdf

Canadian Cancer Society. (2023). *Survival statistics for colorectal cancer*. https://cancer.ca/en/cancer-information/cancer-types/colorectal/prognosis-and-survival/survival-statistics

Canadian Cancer Society. (2026). *Colorectal cancer statistics*. https://cancer.ca/en/cancer-information/cancer-types/colorectal/statistics

Canadian Cancer Society. (n.d.-a). *Risk factors for colorectal cancer*. Retrieved October 26, 2026, from https://cancer.ca/en/cancer-information/cancer-types/colorectal/risks

Canadian Cancer Society. (n.d.-b). *Surgery for colorectal cancer*. Retrieved October 26, 2026, from https://cancer.ca/en/cancer-information/cancer-types/colorectal/treatment/surgery

Canadian Partnership Against Cancer. (2025). *Equity-focused interventions to increase colorectal cancer screening: Screening rates*. https://partnershipagainstcancer.ca/topics/equity-colorectal-cancer-screening/screening-rates

Canadian Task Force on Preventive Health Care. (2016). Recommendations on screening for colorectal cancer in primary care. *CMAJ, 188*(5), 340–348. https://doi.org/10.1503/cmaj.151125

Chabal, L. O., Prentice, J. L., & Ayello, E. A. (2021). Practice implications from the WCET® International Ostomy Guideline 2020. *WCET Journal, 41*(2), 10–21. https://doi.org/10.33235/wcet.41.2.10-21

Chang, L., Chey, W. D., Imdad, A., Almario, C. V., Bharucha, A. E., Diem, S., Greer, K. B., Hanson, B., Harris, L. A., Ko, C., Murad, M. H., Patel, A., Shah, E. D., Lembo, A. J., & Sultan, S. (2023). American Gastroenterological Association–American College of Gastroenterology clinical practice guideline: Pharmacological management of chronic idiopathic constipation. *The American Journal of Gastroenterology, 118*(6), 936–954. https://doi.org/10.14309/ajg.0000000000002227

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

Crohn's and Colitis Canada. (2023). *Impact of IBD in Canada report*. https://crohnsandcolitis.ca/2023report

Di Saverio, S., Coccolini, F., Galati, M., Smerieri, N., Biffl, W. L., Ansaloni, L., Tugnoli, G., Velmahos, G. C., Sartelli, M., Bendinelli, C., Fraga, G. P., Kelly, M. D., Moore, F. A., Mandalà, V., Mandalà, S., Masetti, M., Jovine, E., Pinna, A. D., Peitzman, A. B., … Catena, F. (2013). Bologna guidelines for diagnosis and management of adhesive small bowel obstruction (ASBO): 2013 update of the evidence-based guidelines from the World Society of Emergency Surgery ASBO working group. *World Journal of Emergency Surgery, 8*, Article 42. https://doi.org/10.1186/1749-7922-8-42

Di Saverio, S., Podda, M., De Simone, B., Ceresoli, M., Augustin, G., Gori, A., Boermeester, M., Sartelli, M., Coccolini, F., Tarasconi, A., de' Angelis, N., Weber, D. G., Tolonen, M., Birindelli, A., Biffl, W., Moore, E. E., Kelly, M., Soreide, K., Kashuk, J., … Catena, F. (2020). Diagnosis and treatment of acute appendicitis: 2020 update of the WSES Jerusalem guidelines. *World Journal of Emergency Surgery, 15*(1), Article 27. https://doi.org/10.1186/s13017-020-00306-3

Ferring Inc. (2024). *PICO-SALAX (magnesium oxide, citric acid and sodium picosulfate) powder for oral solution* [Product monograph]. https://ferring.ca/media/1372/en-pico-salax-pm-control-no-288383-en-18dec2024.pdf

Government of Alberta. (2022). *Your 5-day guide for your colonoscopy using a 4-litre bowel preparation*. MyHealth.Alberta.ca. https://myhealth.alberta.ca/Health/Pages/colonoscopy-5-day-guide.aspx

Government of Ontario. (2026a). *Colon cancer testing and prevention*. https://www.ontario.ca/page/colon-cancer-testing-and-prevention

Government of Ontario. (2026b). *Enteral feeding and ostomy*. https://www.ontario.ca/page/enteral-feeding-and-ostomy

Gustafsson, U. O., Scott, M. J., Hubner, M., Nygren, J., Demartines, N., Francis, N., Rockall, T. A., Young-Fadok, T. M., Hill, A. G., Soop, M., de Boer, H. D., Urman, R. D., Chang, G. J., Fichera, A., Kessler, H., Grass, F., Whang, E. E., Fawcett, W. J., Carli, F., … Ljungqvist, O. (2019). Guidelines for perioperative care in elective colorectal surgery: Enhanced Recovery After Surgery (ERAS®) Society recommendations: 2018. *World Journal of Surgery, 43*(3), 659–695. https://doi.org/10.1007/s00268-018-4844-y

Health Canada. (2022, January 12). *XELJANZ/XELJANZ XR (tofacitinib): Risk of major adverse cardiovascular events and malignancy* [Health professional risk communication]. Recalls and Safety Alerts. https://recalls-rappels.canada.ca/en/alert-recall/xeljanzxeljanz-xr-tofacitinib-risk-major-adverse-cardiovascular-events-malignancy

Kenvue Canada Inc. (2026). *Imodium Quick Dissolve, Imodium Calming Liquid, Imodium Liqui-Gels (loperamide hydrochloride)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00083869.PDF

Larkin, P. J., Sykes, N. P., Centeno, C., Ellershaw, J. E., Elsner, F., Eugene, B., Gootjes, J. R. G., Nabal, M., Noguera, A., Ripamonti, C., Zucco, F., & Zuurmond, W. W. A. (2008). The management of constipation in palliative care: Clinical practice recommendations. *Palliative Medicine, 22*(7), 796–807. https://doi.org/10.1177/0269216308096908

Lewis, S. J., & Heaton, K. W. (1997). Stool form scale as a useful guide to intestinal transit time. *Scandinavian Journal of Gastroenterology, 32*(9), 920–924.

Manterola, C., Vial, M., Moraga, J., & Astudillo, P. (2011). Analgesia in patients with acute abdominal pain. *Cochrane Database of Systematic Reviews*. https://doi.org/10.1002/14651858.CD005660.pub3

Moran, G. W., Gordon, M., Sinopoulou, V., Radford, S. J., Darie, A.-M., Vuyyuru, S. K., Alrubaiy, L., Arebi, N., Blackwell, J., Butler, T. D., Chew, T., Colwill, M., Cooney, R., De Marco, G., Din, S., Din, S., Feakins, R., Gasparetto, M., Gordon, H., … Wong, N. A. C. S. (2025). British Society of Gastroenterology guidelines on inflammatory bowel disease in adults: 2025. *Gut, 74*(Suppl. 2), s1–s101. https://doi.org/10.1136/gutjnl-2024-334395

Nightingale, J. M. D. (2022). How to manage a high-output stoma. *Frontline Gastroenterology, 13*(2), 140–151. https://doi.org/10.1136/flgastro-2018-101108

Nurses Specialized in Wound, Ostomy and Continence Canada. (2023). *Parastomal hernia prevention, assessment, and management: Canadian best practice recommendations* (1st ed.). https://www.nswoc.ca/_files/ugd/9d080f_35f5f525ff6944da831af9fdd1793bf5.pdf

Ontario Health. (2026). *Colon cancer screening eligibility is changing in Ontario*. https://ontariohealth.ca/news/colon-cancer-screening-eligibility-is-changing-in-ontario

Ostomy Canada Society. (2023). *Routine ostomy care*. https://www.ostomycanada.ca/ostomy-journey/colostomy/routine-ostomy-care/

Ostomy Canada Society. (2024a). *Medication & supplements*. https://www.ostomycanada.ca/medication-and-supplements/

Ostomy Canada Society. (2024b). *Sexuality*. https://ostomycanada.ca/sexuality/

Ostomy Canada Society. (2024c). *Travel tips*. https://ostomycanada.ca/travel-tips/

Ostomy Canada Society. (2025). *What is an ostomy?* https://ostomycanada.ca/what-is-an-ostomy/

Panaccione, R., Steinhart, A. H., Bressler, B., Khanna, R., Marshall, J. K., Targownik, L., Afif, W., Bitton, A., Borgaonkar, M., Chauhan, U., Halloran, B., Jones, J., Kennedy, E., Leontiadis, G. I., Loftus, E. V., Jr., Meddings, J., Moayyedi, P., Murthy, S., Plamondon, S., … Bernstein, C. N. (2019). Canadian Association of Gastroenterology clinical practice guideline for the management of luminal Crohn's disease. *Clinical Gastroenterology and Hepatology, 17*(9), 1680–1713. https://doi.org/10.1016/j.cgh.2019.02.043

Parini, D., Bondurri, A., Ferrara, F., Rizzo, G., Pata, F., Veltri, M., Forni, C., Coccolini, F., Biffl, W. L., Sartelli, M., Kluger, Y., Ansaloni, L., Moore, E., Catena, F., Danelli, P., & Multidisciplinary Italian Study group for STOmas (MISSTO). (2023). Surgical management of ostomy complications: A MISSTO–WSES mapping review. *World Journal of Emergency Surgery, 18*, Article 48. https://doi.org/10.1186/s13017-023-00516-5

Peery, A. F., Shaukat, A., & Strate, L. L. (2021). AGA clinical practice update on medical management of colonic diverticulitis: Expert review. *Gastroenterology, 160*(3), 906–911.e1. https://doi.org/10.1053/j.gastro.2020.09.059

Pisano, M., Zorcolo, L., Merli, C., Cimbanassi, S., Poiasina, E., Ceresoli, M., Agresta, F., Allievi, N., Bellanova, G., Coccolini, F., Coy, C., Fugazzola, P., Martinez, C. A., Montori, G., Paolillo, C., Penachim, T. J., Pereira, B., Reis, T., Restivo, A., … Ansaloni, L. (2018). 2017 WSES guidelines on colon and rectal cancer emergencies: Obstruction and perforation. *World Journal of Emergency Surgery, 13*, Article 36. https://doi.org/10.1186/s13017-018-0192-3

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Registered Nurses' Association of Ontario. (2019). *Supporting adults who anticipate or live with an ostomy* (2nd ed.). https://www.nswoc.ca/_files/ugd/9d080f_a078831eb3784e21bf9fe0a96a8085fb.pdf

Shereef, A., Raftery, D., Sneddon, F., Emslie, K., Mair, L., Mackay, C., Ramsay, G., & Forget, P. (2023). Prolonged ileus after colorectal surgery, a systematic review. *Journal of Clinical Medicine, 12*(18), Article 5769. https://doi.org/10.3390/jcm12185769

ten Broek, R. P. G., Krielen, P., Di Saverio, S., Coccolini, F., Biffl, W. L., Ansaloni, L., Velmahos, G. C., Sartelli, M., Fraga, G. P., Kelly, M. D., Moore, F. A., Peitzman, A. B., Leppaniemi, A., Moore, E. E., Jeekel, J., Kluger, Y., Sugrue, M., Balogh, Z. J., Bendinelli, C., … van Goor, H. (2018). Bologna guidelines for diagnosis and management of adhesive small bowel obstruction (ASBO): 2017 update of the evidence-based guidelines from the World Society of Emergency Surgery ASBO working group. *World Journal of Emergency Surgery, 13*, Article 24. https://doi.org/10.1186/s13017-018-0185-2

Travis, S. P., Farrant, J. M., Ricketts, C., Nolan, D. J., Mortensen, N. M., Kettlewell, M. G., & Jewell, D. P. (1996). Predicting outcome in severe ulcerative colitis. *Gut, 38*(6), 905–910. https://doi.org/10.1136/gut.38.6.905

Truelove, S. C., & Witts, L. J. (1955). Cortisone in ulcerative colitis: Final report on a therapeutic trial. *British Medical Journal, 2*(4947), 1041–1048. https://doi.org/10.1136/bmj.2.4947.1041

Vogel, J. D., Feingold, D. L., Stewart, D. B., Turner, J. S., Boutros, M., Chun, J., & Steele, S. R. (2016). Clinical practice guidelines for colon volvulus and acute colonic pseudo-obstruction. *Diseases of the Colon & Rectum, 59*(7), 589–600. https://doi.org/10.1097/DCR.0000000000000602

Vun, T., Wu, Z., Chea, C., Liu, W., Tao, R., & Deng, Y. (2025). C-reactive protein in peritoneal fluid for predicting anastomotic leakage after colorectal cancer surgery: A systematic review and meta-analysis. *Journal of Clinical Medicine, 14*(6), Article 2099. https://doi.org/10.3390/jcm14062099

Wounds International. (2023). *Wound care and skin tone made easy*. https://woundsinternational.com/wp-content/uploads/2023/05/MULTI23_ME_SkinTones_WINT-web.pdf

Zane Cohen Centre for Digestive Diseases. (n.d.). *Peristomal skin complications*. Retrieved October 26, 2026, from https://zanecohencentre.com/surgical-programs/rachel-m-flood-education-program/ostomy-care/peristomal-skin-complications

26 Liver, Biliary and Pancreatic Disorders

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain liver, biliary and pancreatic function, and interpret liver tests and jaundice on a range of skin tones.
2. Describe viral hepatitis A, B and C and steatotic liver disease, and support testing, treatment, vaccination and Canada's elimination goals without stigma.
3. Recognize and manage the complications of cirrhosis, including ascites, spontaneous bacterial peritonitis, variceal bleeding and hepatic encephalopathy.
4. Provide non-judgmental care for people with alcohol-related liver disease, recognize acute liver failure, and support patients through liver transplant.
5. Care for adults with gallstones, cholecystitis and cholangitis, and after ERCP and cholecystectomy.
6. Recognize and manage acute and chronic pancreatitis, including early recognition of organ failure, using the CJMM.
7. Distinguish RN and RPN roles in liver and pancreatic care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 3, 5, 6	Clinician; Scholar	Foundations of Practice
2, 4	Advocate; Educator	Foundations of Practice; Ethical Practice
7	Professional; Collaborator	Legal Practice; Collaborative Practice

Introduction

The liver works quietly. It can lose much of its function before a person feels unwell, and many adults learn they have liver disease only when a blood test comes back abnormal or a complication brings them to hospital. By then, the nurse may be caring for someone with a swollen abdomen, yellow eyes, sudden confusion or vomited blood. Each of these findings has a cause that can be found and treated, and the nurse is often the first to notice it.

Liver disease is common in Canada. In 2021, an estimated 262,000 people were living with chronic hepatitis B and 214,000 with chronic hepatitis C, and about four in ten of them did not know it (Périnet et al., 2025). Steatotic liver disease linked to metabolic risk factors is even more common. These conditions fall hardest on groups that already face barriers to care, so stigma-free nursing is part of treatment.

This chapter is the book's home for the liver, the biliary tree and the pancreas. Section 26.1 reviews what these organs do, the liver tests nurses see and how to assess jaundice on a range of skin tones. Section 26.2 covers viral hepatitis and steatotic liver disease, and section 26.3 covers cirrhosis and its complications. The second half of the chapter turns to alcohol-related liver disease, acute liver failure and transplant (26.4), gallbladder and biliary disease (26.5), and acute and chronic pancreatitis (26.6).

The chapter builds on earlier ones. Scope of practice, the Clinical Judgment Measurement Model (CJMM) and consent are taught in Chapter 1 (sections 1.3 to 1.5), and stigma and cultural safety in Chapter 2. Fluids, sodium and potassium are in Chapter 3, sepsis in Chapter 4, acetaminophen and opioid safety in Chapter 5, and rapid response in Chapter 6. Delirium is in Chapter 8, alcohol use disorder and harm reduction in Chapter 11, transfusion in section 20.6, and hepatitis vaccines in section 21.6.

26.1 The Liver, Biliary Tree and Pancreas

What These Organs Do

The liver sits in the right upper abdomen, under the ribs (Figure 26.1). It receives blood from two sources: the hepatic artery brings oxygen, and the **portal vein** brings blood from the stomach, intestines, pancreas and spleen. Everything absorbed from the gut therefore passes through the liver before it reaches the rest of the body. This layout explains why scarring of the liver raises pressure in the portal vein, the problem behind many complications of cirrhosis (section 26.3).



Figure 26.1 The liver, gallbladder and pancreas, with the ducts that carry bile and pancreatic juice to the duodenum. The image is cropped to the upper abdomen. (credit: modification of Figure 23.24, "Accessory Organs," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

The liver does several jobs that nurses see at the bedside:

- **Metabolism:** it stores glucose as glycogen and releases it between meals, makes glucose when stores run low, and processes fats and proteins. It turns ammonia, a toxic product of protein breakdown, into urea, which the kidneys excrete.
- **Proteins:** it makes albumin, the main protein that holds fluid in the blood vessels, and most clotting factors.
- **Bilirubin and bile:** it takes up bilirubin, a yellow pigment from the breakdown of old red blood cells, joins it to another molecule (conjugation) and secretes it into bile. Bile also contains bile salts, which help the gut absorb fats and fat-soluble vitamins, including vitamin K.
- **Drug and toxin clearance:** it breaks down many drugs, hormones and alcohol, so liver disease can make usual drug doses act longer or more strongly.

Bile flows from the liver through small ducts into the hepatic ducts and then the common bile duct, which empties into the duodenum. The gallbladder stores and concentrates bile between meals and contracts after a fatty meal. The pancreatic duct usually joins the common bile duct near the duodenum, which is why a gallstone stuck at that point can cause both jaundice and pancreatitis (sections 26.5 and 26.6).

The pancreas has two roles. Its exocrine part makes digestive enzymes (lipase, amylase and proteases) and bicarbonate, which flow into the duodenum. Its endocrine part, the islets, makes insulin and glucagon; diabetes is covered in Chapter 22.

Liver Tests the Nurse Sees

The blood tests often called "liver function tests" are better called liver tests, because most of them show injury rather than function (Kwo et al., 2017). Results are reported in SI units, and reference ranges vary by laboratory, so the nurse always compares a result with the range on the report.

- **Alanine aminotransferase (ALT) and aspartate aminotransferase (AST), in U/L:** enzymes released when liver cells are injured. ALT is found mainly in the liver; AST also comes from heart and muscle (Kwo et al., 2017). As an example of a Canadian range, Alberta's provincial laboratory lists adult ALT as below 40 U/L for females and below 60 U/L for males (Alberta Precision Laboratories, 2020).
- **Alkaline phosphatase (ALP) and gamma-glutamyl transferase (GGT), in U/L:** rise when bile flow is blocked (cholestasis). A raised GGT suggests that a raised ALP comes from the liver rather than bone (Kwo et al., 2017).
- **Total and conjugated bilirubin, in µmol/L:** a raised conjugated bilirubin usually points to liver cell disease or blocked bile ducts (Kwo et al., 2017).
- **Albumin (g/L) and the international normalized ratio (INR):** reflect the liver's ability to make proteins. The INR changes faster than albumin, which has a half-life of about three weeks. Both can also change for reasons outside the liver, such as poor nutrition, vitamin K deficiency or warfarin (Kwo et al., 2017).
- **Platelets (× 10^9/L):** an adult range in one Canadian laboratory is 140 to 400 × 10^9/L (Alberta Health Services, 2023). In chronic liver disease, a low count can be a clue to portal hypertension, because an enlarged spleen holds back platelets.
- **Lipase (U/L):** a pancreatic enzyme used to diagnose acute pancreatitis (section 26.6).

Patterns help more than single values. Injury to liver cells (hepatocellular injury) raises ALT and AST more than ALP, while blocked bile flow (cholestatic injury) raises ALP more than ALT and AST. In alcohol-related liver injury, AST is often at least twice ALT. An ALT above 1,000 U/L calls for a careful history of acetaminophen use and points toward drug or toxin injury, very low blood flow to the liver or acute viral hepatitis (Kwo et al., 2017).

Figure 26.2 Yellow sclerae in jaundice. The sclerae are a reliable place to look for jaundice on every skin tone. The image is cropped to the eye. (credit: modification of “Jaundice” by OpenRN/Nursing Skills, 2e, CC BY 4.0)

Jaundice

Jaundice is a yellow colour of the skin, sclerae and mucous membranes caused by a high level of bilirubin in the blood. Its causes fall into three groups:

- **Prehepatic:** too much bilirubin is produced, as when red blood cells break down quickly in hemolytic anemia (Chapter 20). The excess is mostly unconjugated. The most common cause of a mildly raised unconjugated bilirubin is Gilbert syndrome, a harmless inherited difference in conjugation (Kwo et al., 2017).
- **Hepatic:** sick liver cells cannot take up, conjugate or secrete bilirubin, as in hepatitis or cirrhosis.
- **Posthepatic:** bile cannot drain because a stone, stricture or tumour blocks the ducts. Conjugated bilirubin backs up into the blood and spills into the urine, which turns dark, while stools turn pale because little bilirubin reaches the gut.

Jaundice is easy to miss on darker skin, where changes in skin colour are harder to see (Pusey-Reid et al., 2023). The nurse looks at the sclerae (Figure 26.2), especially the part nearest the cornea, and inside the mouth, especially the hard palate. Calluses can make the palms and soles look yellow when no jaundice is present, so these sites can mislead (Pusey-Reid et al., 2023). The light matters: natural or indirect light is best, and fluorescent light, which casts a bluish tint, can hide true colour (Pusey-Reid et al., 2023). The

nurse compares findings with the patient's usual appearance and asks the patient or family whether the eyes or skin look different. Dark urine and pale stools are useful clues on any skin tone.

Cholestasis can cause **pruritus** (itching), which can be intense and disrupt sleep. Simple comfort measures, such as keeping the skin moisturized and the nails short, may ease discomfort and limit skin damage from scratching. The nurse checks for scratch injuries and reports itching that disturbs sleep, because drug treatment may help.

26.2 Viral Hepatitis and Steatotic Liver Disease

Hepatitis A, B and C

Hepatitis means inflammation of the liver. Viruses are a leading cause, and the three seen most in Canada differ in how they spread, whether they last and how they are prevented and treated (Table 26.1).

Hepatitis A is caused by the hepatitis A virus, which spreads by the fecal-oral route: from person to person, on contaminated objects, or in contaminated food or water. Symptoms appear 15 to 50 days after exposure. Young children often have no symptoms, while adults usually have poor appetite, nausea, fatigue, fever and jaundice for less than two months. Hepatitis A does not become chronic, but older adults and people with chronic liver disease have a higher risk of acute liver failure (Public Health Agency of Canada [PHAC], 2023). Hand hygiene and the hepatitis A vaccine, recommended for adults with chronic liver disease and other groups at risk, prevent it (PHAC, 2023; section 21.6).

Hepatitis B is caused by the hepatitis B virus, which spreads through infected blood and body fluids, mainly by sharing drug-use equipment, through sex and from a birthing parent to the newborn (PHAC, 2026). Up to half of adults have no symptoms. The age at infection decides the course: 90% to 95% of infected infants develop chronic infection, compared with 3% to 10% of adolescents and adults. Chronic hepatitis B can lead to cirrhosis and **hepatocellular carcinoma** (liver cancer) (PHAC, 2026). In 2021, an estimated 0.68% of people in Canada were living with chronic hepatitis B; the estimate was 4.2% among immigrants from countries where hepatitis B is common (Périnet et al., 2025). The 2025 guideline from the Canadian Association for the Study of the Liver (CASL) and the Association of Medical Microbiology and Infectious Disease (AMMI) Canada recommends one-time screening for all adults with a three-test panel: hepatitis B surface antigen (HBsAg), antibody to the surface antigen (anti-HBs) and antibody to the core antigen (anti-HBc) (Osiowy et al., 2025). The antivirals entecavir, tenofovir disoproxil fumarate and tenofovir alafenamide control the virus (Osiowy et al., 2025) and help prevent cirrhosis and liver cancer (PHAC, 2024). The hepatitis B vaccine is covered in section 21.6.

Hepatitis C is caused by the hepatitis C virus (HCV), which spreads mainly through blood. PHAC (2021) advises offering a test to anyone with a risk factor, such as ever sharing drug-use equipment, tattooing or piercing with unsterile equipment, blood products or transplant before 1992, or birth in a region where hepatitis C is common. Hepatitis C is often silent (PHAC, 2021). Testing takes two steps. A positive antibody (anti-HCV) test shows current or past infection, and a test for HCV ribonucleic acid (RNA), the virus's genetic material, then shows whether the virus is still present (PHAC, 2021; Shah et al., 2018). In 2021, an estimated 36.9% of people who had injected drugs in the past 12 months were living with chronic hepatitis C, and half of them did not know it (Périnet et al., 2025). Many people have never been offered a test: PHAC (2021) reports that 67% of Canadians say they have never been tested for hepatitis C.

Hepatitis C is curable. Tablets called **direct-acting antivirals**, taken for 8 to 24 weeks, cure more than 90% of people, measured as a **sustained virologic response**: no virus found 12 weeks after treatment ends (PHAC, 2021; Shah et al., 2018). Pan-genotypic regimens, which work against all genotypes, include sofosbuvir–velpatasvir and glecaprevir–pibrentasvir (Shah et al., 2018). Side effects are few, and anyone with a positive HCV RNA test is referred to a provider experienced in hepatitis care (PHAC, 2021). There is no vaccine.

In hospital, routine practices protect staff and other patients from hepatitis B and C (Chapter 4). The nurse helps a patient on antiviral treatment take every dose, asks the pharmacist to check new drugs for interactions, and makes sure follow-up testing is booked. A nurse exposed to blood through a needlestick follows the employer's exposure protocol at once.

Canadian screening advice differs. The Canadian Task Force on Preventive Health Care (2017) recommends against screening adults who are not at elevated risk. CASL recommends risk-based testing plus one-time screening of everyone born from 1945 to 1975, and disagrees with the Task Force (Shah et al., 2018). PHAC (2021) advises testing anyone with a risk factor or clinical sign of liver disease.

Stigma keeps people from testing and treatment. People in key populations report discrimination in health care, and PHAC (2024) names structural causes: anti-Indigenous racism rooted in colonial policies, anti-Black racism, and unequal income, housing and food security. In 2021, an estimated 3.3% of First Nations people were living with chronic hepatitis C; estimates for Inuit and Métis were not available (Périnet et al., 2025). The nurse uses person-first language ("a person who injects drugs"), offers testing without judgment, links people to treatment, supports Indigenous-led and peer-based services (PHAC, 2024), and offers harm reduction supplies (Chapter 11).

Table 26.1 Hepatitis A, B and C compared (PHAC, 2021, 2023, 2026; Osiowy et al., 2025; Shah et al., 2018)

Feature	Hepatitis A	Hepatitis B	Hepatitis C
How it spreads	Fecal-oral: contaminated hands, objects, food or water	Blood and body fluids: shared drug-use equipment, sex, birthing parent to newborn	Mainly blood: shared drug-use equipment, unsterile tattooing or medical equipment, blood products before 1992
Becomes chronic?	Never	3% to 10% of infected adults; 90% to 95% of infected infants	Often; some people clear the virus on their own
Vaccine?	Yes	Yes	No
Key tests	Hepatitis A antibody tests	HBsAg, anti-HBs and anti-HBc; one-time screening for all adults	Anti-HCV antibody, then HCV RNA to confirm current infection
Treatment	Supportive care	Long-term antivirals for those who meet criteria	Direct-acting antivirals for 8 to 24 weeks; cure in more than 90%
Nursing focus	Hand hygiene; vaccinate people with chronic liver disease; watch older adults for liver failure	Screening, vaccination of contacts, adherence and cancer surveillance	Offer testing without stigma, link to cure, harm reduction

CANADIAN CONTEXT

Toward Eliminating Viral Hepatitis in Canada

Canada's sexually transmitted and blood-borne infections (STBBI) action plan for 2024 to 2030 commits Canada to the World Health Organization's 2030 targets for hepatitis B and C (PHAC, 2024):

- a 90% reduction in new chronic infections;
- a 65% reduction in deaths;
- 90% of infections diagnosed;
- 80% of eligible people treated.

How close is Canada? A national modelling study estimated that, in 2021, 57.5% of people with chronic hepatitis B and 58.5% with chronic hepatitis C had been diagnosed. Both figures were close to the 2025 interim target of 60%. Deaths from hepatitis C had fallen below the 2025 target, and more people were treated for hepatitis C than were newly infected each year from 2015 to 2021. New hepatitis C infections, estimated at 8,212 in 2021 (21.47 per 100,000 people), remained well above target (Périnet et al., 2025).

The plan notes that hepatitis B and C rates have not fallen in line with global targets, even though a vaccine prevents hepatitis B and treatment cures hepatitis C (PHAC, 2024). Nurses help close the gap each time they offer a test, explain a result without blame, help a patient start and finish treatment, give a hepatitis B vaccine or connect someone with harm reduction.

Metabolic Dysfunction-Associated Steatotic Liver Disease

Steatotic liver disease is the umbrella term for fat build-up in the liver (steatosis) from any cause. In 2023, an international Delphi process with 236 experts from 56 countries replaced the older names, partly because many panel members found "fatty" and "nonalcoholic" stigmatizing or inaccurate (Rinella et al., 2023). The new terms are:

- **Metabolic dysfunction-associated steatotic liver disease (MASLD)** (formerly nonalcoholic fatty liver disease, NAFLD): steatosis plus at least one cardiometabolic risk factor, such as overweight or a large waist, raised blood glucose or type 2 diabetes, high blood pressure, high triglycerides or low high-density lipoprotein (HDL) cholesterol, with no other cause found.
- **Metabolic dysfunction-associated steatohepatitis (MASH)** (formerly nonalcoholic steatohepatitis, NASH): MASLD with inflammation and liver cell injury.
- **MetALD:** MASLD in a person who also drinks more alcohol, about 20 to 50 g a day for women and 30 to 60 g a day for men (Rinella et al., 2023).

MASLD is common. Diabetes Canada's 2025 chapter reports that it affects about 20.8% of Canadians and MASH about 5.2%, and that worldwide, about 69% of people with type 2 diabetes have MASLD (Kim et al., 2025). The amount of scarring (fibrosis) decides the outlook. Only about 20% of people with MASH develop severe liver complications, and cardiovascular disease is still the most common cause of death in this group. MASLD is on track to become the main reason for liver transplant in Canada (Kim et al., 2025).

Most people have no symptoms. Diabetes Canada recommends screening everyone with prediabetes or type 2 diabetes with the FIB-4 index, a score calculated from age, AST, ALT and platelets. A low score can be managed in primary care, an intermediate score needs further testing, such as transient elastography (a scan that measures liver stiffness), and a high score calls for referral to a liver specialist. Screening is repeated every 1 to 2 years, and statins are continued unless cirrhosis becomes decompensated (Kim et al., 2025). MASLD is not limited to type 2 diabetes; the chapter reports that about 22% of adults with type 1 diabetes also have it (Kim et al., 2025).

Care centres on lifestyle and on the conditions that drive the disease. Sustained weight loss of at least 5% to 10% of body weight is recommended, and more than 10% is preferred to reverse fibrosis; people without overweight are encouraged to lose 3% to 5%. Regular aerobic and resistance exercise lowers liver fat, and alcohol should be limited because it speeds progression (Kim et al., 2025). Diabetes, blood pressure and lipids are managed as usual (Chapter 22). The nurse avoids blaming language about weight (Chapter 2), sets small goals with the patient and links them to a dietitian.

26.3 Cirrhosis and Its Complications

How Cirrhosis Develops

Cirrhosis is advanced scarring of the liver. Long-term injury from hepatitis B or C, alcohol or MASLD inflames liver cells. As cells die and are replaced, bands of scar tissue form and the remaining cells grow into nodules. The scarred liver resists blood flow, and the number of working cells falls.

Two problems follow. First, blood backs up in the portal vein, causing **portal hypertension**. Pressure builds in the veins that drain the gut and spleen, the spleen enlarges and new veins form to bypass the liver. Second, liver function fails, so albumin and clotting factors fall, bilirubin and ammonia rise, and drugs clear more slowly.

Cirrhosis is **compensated** when the person has no major complications. It becomes **decompensated** when overt ascites, variceal bleeding or overt hepatic encephalopathy develops (de Franchis et al., 2022). Decompensation marks a turning point in survival, and AASLD guidance advises that clinically significant ascites should prompt consideration of referral for transplant assessment (Biggins et al., 2021).

Manifestations include fatigue, weight and muscle loss, jaundice, easy bruising, a swollen abdomen and leg edema. Breast enlargement in men and swollen veins on the abdominal wall can also appear (Kwo et al., 2017). Two skin signs suggest advanced disease with portal hypertension (Kwo et al., 2017):

- **Spider angioma:** a small, red central spot with fine vessels radiating outward, usually on the face, neck, upper chest or arms. Pressing the centre makes it fade. Redness is harder to see on darker skin and may show as an area darker than the surrounding skin (Pusey-Reid et al., 2023), so the nurse looks closely and checks blanching under good light (Figure 26.3).
- **Palmar erythema:** redness of the palms, mostly at the base of the thumb and little finger (Figure 26.4). On darker skin the change may be subtle (Pusey-Reid et al., 2023); the nurse compares the palms with the backs of the hands and asks whether the

colour is new.

Clinicians grade severity with the Child-Pugh class and the Model for End-Stage Liver Disease (MELD) score (de Franchis et al., 2022; Kamath et al., 2001), described in the Going Deeper box.

Ascites and Spontaneous Bacterial Peritonitis

Ascites (Figure 26.5) is fluid in the peritoneal cavity and is often the first sign of decompensation (Biggins et al., 2021). Portal hypertension pushes fluid out of the vessels, and the body responds to the shift by holding on to sodium and water. The nurse sees a swollen abdomen, bulging flanks, weight gain, shortness of breath when the abdomen is tense, and leg edema.

Treatment starts with diet and diuretics. AASLD guidance calls for dietary sodium of about 2 g (about 90 mmol) a day; fluid is restricted only when serum sodium becomes very low, at about 125 mmol/L or below (Biggins et al., 2021). The usual diuretics are spironolactone with furosemide. Nonsteroidal anti-inflammatory drugs (NSAIDs) such as ibuprofen and naproxen are avoided because they can cause low sodium, diuretic resistance and kidney injury (Biggins et al., 2021). The nurse weighs the patient daily on the same scale, measures abdominal girth at the marked site, tracks intake and output, and watches sodium, potassium and creatinine (Chapter 3).

Figure 26.3 Spider angiomas on lighter skin: a red central point with fine vessels radiating outward. (credit: "SpiderAngioma" by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

Figure 26.4 Palmar erythema in a 79-year-old woman: redness of the palms, most marked at the base of the thumb and little finger. (credit: "Palmar erythema" by Jmarchn/Wikimedia Commons, CC BY-SA 3.0)

When ascites is large or tense, a **paracentesis** drains fluid through a needle or catheter in the abdominal wall (Figure 26.6). When more than 5 L is removed, albumin is given to prevent a drop in circulating volume (Biggins et al., 2021). Safety points are in the Clinical Safety box, and role details in section 26.4. When ascites keeps returning despite treatment, a transjugular intrahepatic portosystemic shunt (TIPS), a stent placed through the liver to connect the portal and hepatic veins, may be considered to lower portal pressure; it can make hepatic encephalopathy worse (Biggins et al., 2021).

Spontaneous bacterial peritonitis (SBP) is infection of ascitic fluid without an obvious source. Signs can be fever, abdominal pain or tenderness, new confusion, worsening kidney function, or nothing at all: up to a third of patients have no symptoms (Biggins et al., 2021). For this reason, a diagnostic paracentesis is done for every patient with ascites admitted to hospital. SBP is diagnosed when the fluid holds more than 250 neutrophils/mm³ (0.25×10^9/L), and intravenous (IV) antibiotics start at once (Biggins et al., 2021). The nurse reports fever, new pain or confusion promptly and watches for sepsis (Chapter 4). Preventive antibiotics are given to patients who have had SBP before and to patients with cirrhosis who have upper gastrointestinal (GI) bleeding (Biggins et al., 2021).

Varices and Variceal Bleeding

Portal hypertension enlarges the veins at the lower esophagus and upper stomach. These thin-walled **esophageal varices** can rupture and bleed heavily. For people with clinically significant portal hypertension, a nonselective beta-blocker, such as propranolol or carvedilol, should be considered to prevent decompensation (de Franchis et al., 2022). The nurse checks heart rate and blood pressure before each dose and teaches the patient not to stop it suddenly.

A variceal bleed is an emergency. The patient may vomit bright red blood or coffee-ground material, pass black stools, or show only rising heart rate, falling blood pressure and confusion. The nurse stays with the patient, turns them to the side if vomiting, calls for help through the rapid response process (Chapter 6), and starts care while the team gathers. Baveno VII sets the priorities (de Franchis et al., 2022):

- **Airway:** intubation before endoscopy for patients with altered consciousness or active vomiting of blood.
- **Volume and blood:** large-bore IV access, cautious fluid and a restrictive transfusion strategy, targeting hemoglobin of 70 to 80 g/L (section 20.6). Fresh frozen plasma is not recommended, because it does not correct the clotting problem.
- **Vasoactive drug:** a drug such as octreotide, started as soon as possible and continued for 2 to 5 days.
- **Antibiotics:** antibiotic prophylaxis is part of treatment; ceftriaxone is considered in advanced cirrhosis.
- **Endoscopy:** within 12 hours of arrival, to band the varices (Figure 26.7).
- **Bridge:** if bleeding cannot be controlled, balloon tamponade or an esophageal stent holds pressure until definitive treatment.

Figure 26.5 Massive ascites from portal hypertension in cirrhosis: a tense, rounded abdomen with prominent surface veins. (credit: "Hepaticfailure" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)



Figure 26.6 Abdominal paracentesis: a needle or catheter in the abdominal wall drains ascitic fluid into a collection container. (credit: "Blausen 0004 AbdominalParacentesis" by BruceBlaus/Wikimedia Commons, CC BY 3.0)

Because blood in the gut can trigger encephalopathy, lactulose by mouth or enema is used to remove it (de Franchis et al., 2022). For selected patients with advanced cirrhosis who are at high risk of treatment failure, a TIPS within 72 hours, ideally within 24 hours, is indicated (de Franchis et al., 2022). After the bleed, the nurse watches for fresh bleeding, infection and confusion. Non-variceal bleeding is covered in Chapter 24.

Hepatic Encephalopathy

Hepatic encephalopathy (HE) is a disturbance of brain function that results from liver failure, from blood

bypassing the liver, or from both (Vilstrup et al., 2014). Ammonia and other toxins from the gut reach the brain. HE ranges from subtle changes found only by testing to coma. The West Haven grades describe it in plain terms (Vilstrup et al., 2014):

- **Grade I:** mild loss of awareness, anxiety or euphoria, short attention span, trouble with simple arithmetic, and a changed sleep pattern.
- **Grade II:** lethargy, disorientation to time, obvious personality change, inappropriate behaviour and asterixis.
- **Grade III:** very drowsy but rousable, confused and grossly disoriented.
- **Grade IV:** coma.

Asterixis is a flapping of the hands when the patient holds the arms out with wrists bent back and fingers spread. It is a brief loss of muscle tone, not a tremor, and kidney failure can also cause it (Vilstrup et al., 2014).



Figure 26.7 Esophageal varices and endoscopic band ligation: elastic bands are placed around the enlarged veins to stop or prevent bleeding. (credit: "Endoscopic Banding for Esophageal Varices" by Kel898/Wikimedia Commons, CC BY-SA 4.0)

Most episodes have a trigger, and finding and treating it is the first step; nearly 90% of patients can be treated by correcting the trigger (Vilstrup et al., 2014). Common triggers are infection, GI bleeding, too much diuretic or dehydration, electrolyte problems such as low sodium, and constipation. Sedating drugs such as benzodiazepines and opioids, and alcohol, can cause confusion that looks like HE or adds to it (Vilstrup et al., 2014). The nurse checks vital signs, blood glucose and the bowel record, looks for melena (black, tarry stool) and signs of infection, and reviews recent drugs.

Lactulose is the first-choice treatment. It is titrated to two to three soft bowel movements a day (Vilstrup et al., 2014). Gut bacteria break it down into acids, which trap ammonia in the colon so that it leaves in the stool (Sanis Health, 2015). Too much lactulose can cause dehydration, high sodium, perianal skin breakdown and aspiration, and can even worsen HE (Vilstrup et al., 2014), so the nurse counts and describes every stool. When a patient cannot swallow safely, lactulose can be given by nasogastric tube or as an enema (Vilstrup et al., 2014). Rifaximin, an antibiotic that stays mostly in the gut, is added to lactulose to prevent overt HE from coming back (Lupin Pharma Canada, 2025; Vilstrup et al., 2014).

Safety comes first. Patients with HE fall, wander, pull out lines and cannot always swallow safely. The nurse uses fall precautions, checks swallowing before oral drugs, and reassesses orientation every shift. Patients at grade III or IV who cannot protect their airway need intensive monitoring, ideally in critical care (Vilstrup et al., 2014). Delirium from other causes can look the same (Chapter 8).

Living With Cirrhosis

People with cirrhosis do best with steady, practical support:

- **Alcohol:** stopping completely protects the liver; the nurse offers support without judgment (Chapter 11).
- **Medications:** NSAIDs are avoided (Biggins et al., 2021). People with liver disease may need a lower acetaminophen limit than the label states and should ask their prescriber or pharmacist (Health Canada, 2016; Chapter 5). The nurse teaches patients to check every product for hidden acetaminophen and to avoid sleeping pills unless prescribed.
- **Nutrition:** protein is not restricted; guidance is 1.2 to 1.5 g/kg a day, with small meals spread through the day and a late-evening snack, because fasting speeds muscle loss (Vilstrup et al., 2014). Sodium stays at about 2 g a day if ascites is present.
- **Vaccines:** hepatitis A and B vaccines for people who are not immune (PHAC, 2023, 2026; section 21.6).

- **Liver cancer surveillance:** ultrasound, often with a blood test for alpha-fetoprotein, every 6 months for people with cirrhosis (Kim et al., 2025; Osiowy et al., 2025).
- **Driving:** people who have had HE should stop driving until the licensing authority clears them (Vilstrup et al., 2014).
- **Planning ahead:** palliative care can run alongside treatment and transplant assessment (Biggins et al., 2021; Chapter 10).

Access shapes all of this. A person in a rural, remote or northern community may need to travel far for endoscopy, ultrasound or transplant assessment. The nurse plans visits ahead, explains travel support, and makes sure the patient knows which warning signs need 9-1-1 rather than waiting for the next appointment.

Table 26.2 brings together the main complications of cirrhosis and the nurse's first actions.

Table 26.2 Complications of cirrhosis and the nurse's first actions (Biggins et al., 2021; de Franchis et al., 2022; Vilstrup et al., 2014)

Complication	What the nurse sees	First nursing actions	Treatment principles
Ascites	Swollen abdomen, bulging flanks, weight gain, breathlessness when tense	Daily weight, abdominal girth, intake and output; check sodium, potassium and creatinine	Sodium about 2 g a day; spironolactone and furosemide; paracentesis with albumin when more than 5 L is drained
Spontaneous bacterial peritonitis	Fever, abdominal pain, new confusion, rising creatinine, or no symptoms	Report promptly; prepare for diagnostic paracentesis; screen for sepsis	IV antibiotics when the fluid neutrophil count exceeds 250/mm³; prevention in high-risk patients
Variceal bleeding	Vomited blood, black stools, rising heart rate, falling blood pressure, confusion	Turn to side, call rapid response, large-bore IV access, prepare blood and drugs	Vasoactive drug, antibiotics, restrictive transfusion, endoscopy within 12 hours
Hepatic encephalopathy	Day-night reversal, confusion, asterixis, drowsiness	Look for triggers, check glucose, count stools, fall and aspiration precautions	Treat the trigger; lactulose to 2 to 3 soft stools a day; rifaximin to prevent recurrence
Hepatorenal syndrome	Falling urine output and rising creatinine	Report; strict intake and output; ask the prescriber about holding diuretics and nephrotoxic drugs	Stop diuretics; albumin with a vasoconstrictor; urgent transplant assessment

GOING DEEPER

Portal Hypertension, the Hepatorenal Syndrome and the MELD Score

Required for RN students; optional for PN students.

Portal pressure is measured as the hepatic venous pressure gradient, the difference between pressure in a wedged hepatic vein catheter and the free hepatic vein. A gradient of 10 mm Hg or higher defines clinically significant portal hypertension, the point at which varices and ascites become likely and beta-blockers are considered (de Franchis et al., 2022).

Portal hypertension also widens blood vessels in the gut and around the body. Effective blood volume falls, so the kidneys sense poor perfusion and constrict their own arteries. When this goes far enough, the **hepatorenal syndrome** develops: acute kidney injury (AKI) in cirrhosis without shock, kidney damage or nephrotoxic drugs to explain it. AASLD defines AKI as a rise in creatinine of at least 26.5 µmol/L within 48 hours or of 50% within 7 days. Treatment stops diuretics, gives albumin with a vasoconstrictor drug, and prompts urgent transplant referral (Biggins et al., 2021). AKI is covered in Chapter 27.

The MELD score combines bilirubin, creatinine and INR to predict the risk of death within 3 months, and transplant programs use it to rank patients on the waiting list (Kamath et al., 2001). Updated versions add other values. Because creatinine is part of the score, hepatorenal syndrome raises MELD and the urgency of transplant.

CLINICAL SAFETY

Paracentesis and Sedatives in Liver Disease

Before paracentesis, the nurse confirms consent (section 1.5), records baseline vital signs, weight and girth, asks the patient to empty the bladder and checks whether blood tests were ordered. In cirrhosis, the INR does not accurately reflect how well the blood clots (de Franchis et al., 2022), so the nurse follows the team's orders on any blood products rather than expecting a raised INR to be corrected first.

During and after, the nurse watches for hypotension, dizziness, bleeding or leakage at the site, new abdominal pain and fever. When a large volume is drained, albumin is given as ordered (Biggins et al., 2021). The nurse records the volume and colour of the fluid and labels samples promptly.

Sedatives: benzodiazepines, opioids and other sedating drugs can cause or deepen confusion in people with cirrhosis and hide the signs of HE (Vilstrup et al., 2014). The liver clears many of these drugs slowly. The nurse:

- assesses orientation and asterixis before giving any sedating drug;
- questions a new sedative order for a patient with cirrhosis who is agitated, and looks first for a trigger such as bleeding, infection or constipation;
- uses non-drug measures for sleep and agitation;
- reports any drop in level of consciousness at once.

PATIENT EDUCATION

Taking Lactulose at Home

Lactulose keeps ammonia from building up and protects thinking. Teach the patient and family to:

- take it every day as prescribed, even when feeling well;
- aim for two to three soft bowel movements a day and adjust the dose as the prescriber has shown (Sanis Health, 2015; Vilstrup et al., 2014);
- mix it with water, juice or milk if the sweet taste is a problem (Sanis Health, 2015);
- expect gas, bloating or cramps at first; these usually settle (Sanis Health, 2015);
- avoid other laxatives unless the prescriber advises them (Sanis Health, 2015);
- call the prescriber for frequent watery stools, dizziness or very little urine, which may mean dehydration;
- call the prescriber for fewer than two stools a day, or for confusion, sleepiness by day or flapping hands;
- call 9-1-1 for black or bloody stools, vomited blood or a person who is hard to wake;
- protect the skin around the anus with gentle cleaning and a barrier cream.

Lactulose contains some sugars, so people with diabetes should check blood glucose as advised (Sanis Health, 2015).

SCOPE IN PRACTICE

Paracentesis, Large-Volume Fluids and Who Does What

Paracentesis is performed by a physician, or by a nurse practitioner (NP) who has the competence and employer authorization to do it. Before the procedure, the nurse confirms that the person doing it has obtained consent (section 1.5), and records baseline vital signs, weight and abdominal girth. During and after it, the nurse monitors blood pressure, heart rate, mental status and the puncture site.

CNO's Scope of Practice standard frames who does what through authority, competence and context (College of Nurses of Ontario [CNO], 2025; section 1.3):

- **Authority:** Giving albumin or other IV solutions is the controlled act of administering a substance by injection, which RNs and RPNs are authorized to perform with an order. Albumin is a blood product, so the employer's blood product policy also applies (section 20.6). Draining an existing peritoneal catheter requires an order and follows employer policy.
- **Competence:** The nurse needs the knowledge, skill and judgment to manage a drain, recognize a drop in blood pressure or new confusion after fluid removal, and act.
- **Context:** In many settings, RNs and RPNs both care for a patient whose ascites is drained routinely and whose condition is stable; this is a common employer practice, not a CNO rule. When blood pressure falls, urine output drops or confusion appears, the patient's needs have changed. The RPN consults the RN, and any nurse who sees deterioration acts at once and escalates (Chapter 6).

Employers can limit but not expand a nurse's scope; employer policy and province or territory matter. CNO's revised Scope of Practice and Medication standards take effect March 1, 2027 (CNO, 2026).

PRACTICE STORY

Drowsy After Dinner

Names and details are fictional; this is a composite story.

Nurse: Kavita Pillai, RN. Years in practice: 7. Setting: medical unit, Ontario.

At 1900, my RPN colleague, Dale, told me that Mr. Antoine Lefebvre, 64, "just seems tired tonight." Mr. Lefebvre has cirrhosis and was admitted 3 days ago with ascites. At lunch, he had joked with me about the hospital food. At 1900, he was asleep with his dinner tray untouched, and he took a long time to answer my questions. He thought it was morning. When he held his arms out, his hands flapped. That was asterixis, and it told me that hepatic encephalopathy had worsened.

Lactulose was ordered, but I didn't want to stop there. I asked myself what had set this off. I thought of infection, constipation, sedatives, dehydration and electrolytes. Then I thought of bleeding. His chart showed two soft stools today, and Dale said the second one had been very dark. When I checked his brief, the stool was black, tarry and foul-smelling. His heart rate was 108, up from 84 at noon, and his blood pressure was 102/60, down from 128/74. He takes a beta-blocker, which can blunt a rising heart rate (Chapter 24).

I called the hospitalist and gave an SBAR report: worsening encephalopathy and melena with a falling blood pressure in a patient with cirrhosis and known varices. She came within minutes. We placed a second large-bore IV, sent blood work, including a group and screen, and kept him NPO. I raised the head of the bed and turned him on his side to protect his airway. The hospitalist ordered IV octreotide and ceftriaxone and arranged endoscopy. She called the ICU because his airway might need protection.

Later, endoscopy showed a bleeding varix. Over the next 2 days, as the bleed stopped and the lactulose worked, his confusion cleared. Dale's "just seems tired" was the first cue, and it was right.

Reflect: Which cues told the nurses that this was more than tiredness? When Dale noticed the change, what should an RPN do next, and why does the change in the patient's condition matter for who provides his care?

26.4 Alcohol-Related Liver Disease, Acute Liver Failure and Transplant

This section covers liver injury from alcohol, sudden failure of a previously healthy liver, and liver transplant. Cirrhosis and its complications are covered in section 26.3.

Alcohol-Related Liver Disease

Alcohol-related liver disease (ALD) is liver injury caused by drinking alcohol over time. Fat builds up in liver cells first (steatosis). Some people go on to an acute inflammatory illness, then to fibrosis and cirrhosis, and some develop liver cancer (Jophlin et al., 2024). This book uses "alcohol-related liver disease"; American guidelines use "alcohol-associated liver disease," which means the same thing.

ALD is one of the main reasons people develop advanced liver disease or die of liver disease, and it is often diagnosed late (Jophlin et al., 2024). In Canada, deaths and hospitalizations wholly caused by alcohol rose during the COVID-19 pandemic. A study of people aged 15 and older estimated that, from April 2020 to December 2022, deaths fully attributable to alcohol were 17.6% higher, and hospitalizations 8.1% higher, than expected. Alcoholic liver disease contributed more to this excess than any other condition, with deaths up 22% and hospitalizations up 23% (Shi et al., 2025). Excess hospitalizations rose more among females (15.6%) than among males (5.7%) (Shi et al., 2025).

Risk rises with the amount of alcohol and the years of drinking, with daily or binge drinking and with drinking outside meals. Sex, inherited gene variants, obesity, metabolic syndrome and chronic viral hepatitis also add risk (Jophlin et al., 2024). Canada's Guidance on Alcohol and Health describes risk as a continuum: 2 standard drinks a week or fewer is low risk, and each added drink raises the risk of several conditions, liver disease among them (Canadian Centre on Substance Use and Addiction [CCSA], 2023; Chapter 11).

Alcohol-associated hepatitis is the acute inflammatory stage. The typical picture is jaundice that begins within about 2 months of heavy drinking in a person who has drunk heavily for at least 6 months, with a raised bilirubin and an AST that is higher than the ALT (Jophlin et al., 2024). The nurse checks for jaundice in the sclerae, palms and oral mucosa, which works on every skin tone (section 26.1). A MELD score above 20 marks severe disease with a high risk of death in the short term (Jophlin et al., 2024; see the Going Deeper box in section 26.3).

Stopping alcohol is the most important treatment at every stage. Care for severe alcohol-associated hepatitis includes:

- **Corticosteroids,** which the guideline suggests for severe disease unless there is an untreated infection, GI bleeding, uncontrolled diabetes or severe kidney failure. The response is checked after 4 to 7 days, and the drug is stopped if the patient is not responding (Jophlin et al., 2024).
- **N-acetylcysteine,** which may be added to the corticosteroid for a short course (Jophlin et al., 2024).
- **Nutrition support,** including thiamine and other vitamins (Jophlin et al., 2024; Chapter 11; Chapter 24).
- **Early liver transplant** for a few carefully selected people who do not respond, and palliative care for those who are not candidates (Jophlin et al., 2024; Chapter 10).

Nursing care starts with the CJMM (section 1.4). The nurse watches for withdrawal, infection, bleeding and hepatic encephalopathy. Benzodiazepines for withdrawal can bring on hepatic encephalopathy in a person with poor liver function, so they are used with care and close monitoring (Jophlin et al., 2024; Chapter 11). The guideline recommends screening for alcohol use at every visit with a short tool such as the Alcohol Use Disorders Identification Test–Consumption (AUDIT-C), a brief intervention, and treatment of alcohol use disorder by a team that includes addiction specialists (Jophlin et al., 2024). The nurse uses person-first, non-judgmental language ("a person who drinks alcohol," not "an alcoholic") (Chapter 2; Chapter 11).

Acute Liver Failure

Acute liver failure (ALF) is a sudden, severe loss of liver function in a person without cirrhosis. It is defined by an INR of 1.5 or higher and any degree of encephalopathy, arising within 26 weeks of the start of the illness (Lee et al., 2011).

Causes. Acetaminophen overdose is the leading cause in the United States and Europe (Lee et al., 2011), and ISMP Canada (2017) reports that acetaminophen is the most common cause of liver failure in Canada. Other causes include hepatitis A, B and E, other drugs, a sudden drop in blood flow to the liver ("shock liver"), autoimmune hepatitis, Wilson disease and some pregnancy-related conditions. About 15% of cases have no cause found (Lee et al., 2011).

About 4,500 Canadians are hospitalized each year for acetaminophen overdose, and about 6% of them have liver injury (ISMP Canada, 2017). Most overdoses are intentional, but nearly 20% are not. Between 2006 and 2011, the proportion of acetaminophen-related injuries that followed an unintentional overdose climbed from 27% to 45% (ISMP Canada, 2017). Unintentional overdose often comes from taking two products that both contain acetaminophen, from prescription products that combine acetaminophen with an opioid, and from one brand name covering products with different ingredients. Most injuries occur above the maximum daily dose (Chapter 5), but injury at lower doses has been reported in people with liver disease, heavy alcohol use or malnutrition, or with long-term use (ISMP Canada, 2017). A person who took an intentional overdose also needs a suicide risk assessment and mental health follow-up.

Treatment of acetaminophen overdose. N-acetylcysteine (NAC), marketed in Canada as acetylcysteine, is the antidote. Clinicians give it to anyone who may have taken an acetaminophen overdose, even when the time of ingestion is unknown or the blood level is low, and it can still be of value 2 days or more after ingestion. Activated charcoal may help when the overdose was taken within about 3 to 4 hours (Lee et al., 2011). The nurse or prescriber can call the Ontario Poison Centre (1-800-268-9017) at any hour for expert advice; it serves both the public and health professionals (Ontario Poison Centre, n.d.). Other provinces and territories have their own poison centres.

Nursing priorities in ALF (Lee et al., 2011):

- **Brain:** frequent neurological checks, a quiet room and no sedatives unless ordered. Worsening encephalopathy can signal brain swelling.
- **Glucose:** frequent checks, because confusion can hide hypoglycemia. A continuous glucose infusion is often needed.
- **Bleeding:** watching for bleeding. Plasma and platelets are kept for active bleeding or invasive procedures, because routine plasma hides the INR trend.
- **Infection:** cultures and prompt reporting of fever, new confusion or falling blood pressure (Chapter 4).
- **Kidneys and electrolytes:** urine output, kidney function, avoiding nephrotoxic drugs, and phosphate, magnesium and potassium (Chapter 3).
- **Nutrition:** early enteral feeding (Chapter 24).

A patient with any encephalopathy belongs in an intensive care unit (ICU), and the transplant centre is called early. Transfer is advised even for mild encephalopathy, because moving the patient later may become unsafe (Lee et al., 2011).

Liver Transplant in Brief

A **liver transplant** replaces a failing liver with a whole liver from a deceased donor or part of a liver from a living donor. In 2025, Canada performed 3,174 organ transplants, and 19% were liver transplants. At the end of 2025, 4,344 people were waiting for an organ. Of the 678 people removed from wait-lists in 2025, 31% had died while waiting (Canadian Institute for Health Information [CIHI], 2026).

Ontario has two adult liver transplant programs, in Toronto and London. Provincial criteria call for referral of people with decompensated cirrhosis, typically at a MELD 3.0 score of 11 or more, and of people with acute liver failure; listing typically requires a score of 15 or more (Ontario Health [Trillium Gift of Life Network], 2025). Complications such as ascites, encephalopathy, bleeding from portal hypertension (including varices) and liver cancer prompt referral (section 26.3). People with ALD must be prepared to commit to not drinking alcohol at all (Ontario Health [Trillium Gift of Life Network], 2025), and a psychosocial assessment, rather than a fixed period without alcohol alone, guides the decision (Jophlin et al., 2024). The University Health Network program in Toronto reports more than 800 living donor liver transplants; donors are assessed carefully, and their recovery takes at least 6 weeks (University Health Network, n.d.).

After transplant, the person takes immunosuppressants for life (section 21.3). Teaching covers (Johns Hopkins Medicine, 2017):

- Never stop or skip anti-rejection drugs, and check with the transplant team before starting any new prescription, over-the-counter or herbal product.
- Have drug-level blood tests at the scheduled times; rejection may cause no symptoms and show only in blood work.
- Report fever, jaundice, dark urine, generalized itching, pain over the new liver, swelling or unusual tiredness.
- Report early signs of infection, a common cause of readmission.
- Avoid live vaccines, protect the skin from the sun, avoid alcohol and keep lifelong follow-up.

26.5 Gallbladder and Biliary Disease

The gallbladder stores bile and squeezes it into the duodenum after meals (section 26.1). Stones that form in it cause pain when they block the outflow, and the most serious problems arise when a stone moves into the common bile duct.

Gallstones and Cholecystitis

Cholelithiasis means stones in the biliary tract, most often in the gallbladder (Figure 26.8). A Canadian surgical guideline estimates that about 10% of the general population have gallstones. Most never have symptoms, and about 1% to 3% a year develop significant symptoms (Aubin & Ball, 2018). Risk factors include (Aubin & Ball, 2018):

- older age, female sex and a family history;
- obesity, rapid weight loss and pregnancy;
- parenteral nutrition and some drugs, such as ceftriaxone;
- conditions that slow bile flow or change bile, such as spinal cord injury, cirrhosis, Crohn disease and removal of the last part of the small intestine.

Biliary colic is pain caused when a stone briefly blocks the cystic duct. The pain is in the right upper quadrant (RUQ) or epigastrium, often after a meal, and may spread to the back with nausea and vomiting. It usually lasts from about 30 minutes to 4 hours. Pain that lasts longer suggests cholecystitis (Aubin & Ball, 2018).

Acute cholecystitis is inflammation of the gallbladder, usually because a stone stays stuck in its neck. The wall can become ischemic and gangrenous, and it can perforate (Aubin & Ball, 2018). The pain persists, and fever and RUQ tenderness are common. A **Murphy sign** is present when the patient suddenly stops breathing in because of pain as the examiner presses under the right rib margin (Aubin & Ball, 2018). No single finding confirms or rules out cholecystitis (Pisano et al., 2020). A suspected diagnosis rests

on a local sign (Murphy sign or RUQ pain, tenderness or mass) plus a sign of inflammation (fever, a high white cell count or a raised C-reactive protein), and imaging confirms it (Aubin & Ball, 2018). Abdominal ultrasound is the first test (Pisano et al., 2020). Older adults, men, people with diabetes and people who are immunosuppressed are at higher risk of complicated disease, so clinicians keep a low threshold for suspecting it (Aubin & Ball, 2018).

Early treatment is nothing by mouth (NPO), IV fluids, pain relief (Chapter 5) and antibiotics (Aubin & Ball, 2018). Where a surgeon is available, laparoscopic cholecystectomy is done early: ideally within 7 days of admission and within 10 days of the start of symptoms. Patients too unwell for surgery have the gallbladder drained instead (Pisano et al., 2020). The nurse reassesses pain, watches for sepsis (Chapter 4) and escalates a rising heart rate, falling blood pressure or new confusion (Chapter 6). Preoperative care is in Chapter 7.

Figure 26.8 Gallstones removed from one patient, on a 1 mm grid. (credit: "Human gallstones 2015 G1" by George Chernilevsky/Wikimedia Commons, CC BY-SA 4.0)

Laparoscopic cholecystectomy removes the gallbladder through small incisions. Patients often go home soon after, so teaching starts early (Interior Health, 2015; Quinte Health, 2022):

- **Shoulder or neck pain:** common in the first 48 hours. It comes from the carbon dioxide gas used to inflate the abdomen and fades as the gas is absorbed. Lying flat and warmth to the shoulders, not the abdomen, may help.
- **Breathing and walking:** deep breathing and coughing every hour while awake, with a pillow pressed against the abdomen, and regular walks.
- **Eating:** fluids first, then foods as tolerated. Loose stools from bile trickling into the bowel usually settle; persistent diarrhea is reported.
- **Bowels:** opioids can cause constipation, so the patient avoids straining and may need a mild laxative.
- **Return to work:** often within about 7 to 10 days; heavy work and sports are cleared with the surgeon.

The patient calls the surgeon or goes to an emergency department for:

- fever (Interior Health uses above 38.3 °C) or chills;
- abdominal pain that grows worse or is not controlled;
- nausea or vomiting lasting more than 24 hours;
- yellow eyes or skin, or dark urine;
- redness, pus or bleeding at an incision;
- trouble breathing, chest pain or being unable to pass urine (Interior Health, 2015; Quinte Health, 2022).

These signs can point to a complication, such as bleeding or infection, that needs prompt review.

Choledocholithiasis and Cholangitis

Choledocholithiasis is a stone in the common bile duct. It blocks bile flow and can cause jaundice, acute pancreatitis (section 26.6) or cholangitis. Raised liver tests or bilirubin alone do not prove a duct stone. A second imaging test, such as magnetic resonance cholangiopancreatography (MRCP) or endoscopic ultrasound, is used when the risk is moderate (Pisano et al., 2020). A confirmed duct stone is removed before cholecystectomy (Aubin & Ball, 2018).

Acute cholangitis is infection of the bile ducts behind a blockage. The **Charcot triad** of fever, jaundice and abdominal pain points strongly to cholangitis, but it appeared in only about 1 in 4 patients (26.4%) in the study behind the Tokyo criteria (Kiriyama et al., 2012). The nurse therefore does not wait for all three. The Tokyo Guidelines diagnose cholangitis from signs of inflammation, signs



Figure 26.9 Endoscopic retrograde cholangiopancreatography (ERCP): the endoscope enters through the mouth and passes through the stomach to the duodenum, where instruments reach the common bile duct. (credit: "ERCP" by Drus1a/Wikimedia Commons, CC BY-SA 4.0)

of blocked bile flow and imaging (Kiriyama et al., 2012). They grade severity: age 75 or older is one of five factors, and any two of them make the disease moderate (Kiriyama et al., 2012). Severe cholangitis means organ dysfunction, such as low blood pressure or confusion (Chandrasekhara et al., 2017; Kiriyama et al., 2018).

Treatment is antibiotics, fluids and drainage of the blocked duct. Drainage is urgent in severe cholangitis and early in moderate cholangitis (Kiriyama et al., 2012, 2018). When cholangitis accompanies acute pancreatitis, the American College of Gastroenterology (ACG) guideline supports **endoscopic retrograde cholangiopancreatography (ERCP)** within 24 hours (Tenner et al., 2024). Sepsis care is in Chapter 4.

ERCP passes an endoscope through the mouth into the duodenum to reach the bile and pancreatic ducts (Figure 26.9). Through it, the endoscopist can cut the duct opening (sphincterotomy), remove stones and place stents. After ERCP, the nurse monitors for (Chandrasekhara et al., 2017):

- **Post-ERCP pancreatitis:** the most common serious complication, seen in about 3% to 10% of patients. New or worse abdominal pain is the key cue. A raised enzyme level alone does not make the diagnosis, because levels rise briefly in many patients.
- **Bleeding:** right away or delayed by hours to weeks.
- **Perforation:** severe epigastric or back pain, a rigid abdomen, fever and a fast heart rate. Signs may take hours to appear.
- **Cholangitis:** fever, jaundice and pain.
- **Sedation problems:** low oxygen levels, low blood pressure and aspiration.

To prevent post-ERCP pancreatitis, the ACG guideline supports a rectal nonsteroidal anti-inflammatory drug (NSAID) for patients having ERCP unless it is contraindicated, and a temporary pancreatic duct stent for those at high risk (Tenner et al., 2024).

CLINICAL JUDGMENT

Fever, Jaundice and Pain After a Gallstone Attack

Names and details are fictional; this is a composite story.

Kwame Mensah, 71, was seen in the emergency department 2 days ago for biliary colic and sent home with a surgical referral. He returns with RUQ pain, chills and less to eat or drink. His daughter says he is "not himself." He has dark brown skin.

- **Recognize cues:** Temperature 38.9 °C, heart rate 114, blood pressure 98/58 mm Hg, respiratory rate 24. His sclerae and the mucosa under his tongue look yellow; his skin colour is unchanged. His urine is dark. He is slow to answer and unsure of the date.
- **Analyze cues:** Fever with jaundice and pain after a known gallstone attack suggests a stone in the common bile duct with infection behind it. New confusion and low blood pressure suggest organ dysfunction.
- **Prioritize hypotheses:** Severe acute cholangitis with sepsis comes first. Acute cholecystitis and delirium from another cause are possible, but neither changes the urgent plan.
- **Generate solutions:** Early recognition and escalation, IV access, blood work and cultures, IV fluids and antibiotics as ordered, NPO, and urgent biliary drainage, usually by ERCP.
- **Take action:** The nurse calls the rapid response team using SBAR (Chapter 6), draws blood cultures before the first antibiotic dose as ordered (Chapter 4), starts IV fluids as ordered and keeps him NPO. The nurse turns on the bed alarm and stays with him.

- **Evaluate outcomes:** After ERCP removes the stone, his blood pressure and alertness improve over 24 hours. The nurse keeps watching for post-ERCP pancreatitis and bleeding, and checks his sclerae each shift.

26.6 Acute and Chronic Pancreatitis

The pancreas makes digestive enzymes and hormones such as insulin (section 26.1). When it becomes inflamed, it can injure itself and trigger inflammation throughout the body. Diabetes after pancreatic disease is covered in Chapter 22.

Acute Pancreatitis

Acute pancreatitis is acute inflammation of the pancreas (Tenner et al., 2024). In most patients it is **interstitial edematous pancreatitis**, in which the gland swells. About 5% to 10% develop **necrotizing pancreatitis**, in which pancreatic tissue or the tissue around it dies (Banks et al., 2013).

Causes. Gallstones (about 40% to 70% of cases) and alcohol (about 25% to 35%) are the most common causes (Tenner et al., 2024). Other causes include (Tenner et al., 2024):

- very high triglycerides, usually above about 11.3 mmol/L (1,000 mg/dL), with a fasting level repeated about a month after discharge;
- ERCP (section 26.5);
- a small number of drugs, although blaming a drug is often wrong;
- in adults over 40 with no clear cause, a pancreatic tumour, which is looked for.

Alcohol is not judged to be the cause unless a person has drunk moderately or heavily for more than 5 years (Tenner et al., 2024). Canadian data on alcohol-related harm are in section 26.4 and Chapter 11.

Diagnosis. Acute pancreatitis is diagnosed when two of three features are present (Banks et al., 2013; Tenner et al., 2024):

- abdominal pain typical of the disease, usually epigastric and often spreading to the back;
- serum **lipase** (or amylase) at least three times the upper limit of normal; lipase is preferred;
- typical findings on imaging.

The onset is the time the pain began, not the time of admission (Banks et al., 2013). Every patient has an abdominal ultrasound to look for gallstones. A computed tomography (CT) scan is not used routinely to grade severity. It is kept for an unclear diagnosis or a patient who is not improving after 48 to 72 hours (Tenner et al., 2024). Triglyceride and calcium levels are part of the search for a cause (Tenner et al., 2024).

Cullen and Grey Turner signs. The **Cullen sign** is bruising around the umbilicus, and the **Grey Turner sign** is bruising of the flanks. Both form when blood from behind the peritoneum tracks into the abdominal wall. They are rare in acute pancreatitis (about 1% of patients each in older case series), usually appear a few days into the illness and point to serious disease (Wright, 2016). Neither is specific to pancreatitis; a ruptured ectopic pregnancy and other causes of internal bleeding can produce them (Wright, 2016). On light skin, the bruise may look blue-purple and turn green or yellow as it ages (Wright, 2016). On dark skin, a bruise may look only darker than the skin around it (Pusey-Reid et al., 2023). The nurse inspects both flanks and the umbilicus in natural or ambient light, compares one side with the other, and palpates for tenderness and swelling.

Severity. The **revised Atlanta classification** grades acute pancreatitis by organ failure and complications (Banks et al., 2013; Table 26.3). **Organ failure** means failure of the lungs, the circulation or the kidneys. It is **transient** if it resolves within 48 hours and **persistent** if it lasts longer (Banks et al., 2013). The early phase usually lasts about a week; a late phase of weeks to months occurs only in moderately severe or severe disease (Banks et al., 2013). No score or scan reliably predicts severity at the start, so the first 48 hours call for close watching (Tenner et al., 2024).

Table 26.3 Severity of acute pancreatitis (revised Atlanta classification) and what it means for care (Banks et al., 2013)

Severity	Definition (in own words)	Nursing focus

Severity	Definition (in own words)	Nursing focus
Mild	No organ failure and no local or body-wide complications; usually settles within the first week	Early oral feeding as tolerated, pain control, finding the cause, discharge teaching, and cholecystectomy before discharge if gallstones caused it
Moderately severe	Organ failure that resolves within 48 hours, or local complications (such as fluid collections or necrosis), or a flare of an existing illness such as heart or lung disease, without persistent organ failure	Close monitoring of vital signs, oxygen and urine output; enteral nutrition if eating is not possible; watching for collections, infection and worsening of chronic illness
Severe	Organ failure in one or more systems that lasts longer than 48 hours	Intensive care, organ support, careful fluid balance, enteral feeding and support for the patient and family

Early Care and Nursing Priorities

Most patients have mild disease and recover within days. The nurse's job in the first 48 hours is to support the circulation, control pain, feed early and recognize organ failure early.

IV fluids. The ACG guideline suggests moderately aggressive IV fluids, with extra boluses for hypovolemia, and prefers lactated Ringer's solution to normal saline (Tenner et al., 2024). Fluids matter most in the first 24 hours. Volume status is reassessed within 6 hours of arrival and repeatedly over the next 24 to 48 hours. The aim is a falling blood urea and a hematocrit that does not rise (Tenner et al., 2024). The guideline found too little evidence that strict goal-directed protocols improve outcomes, and it urges caution in patients with heart or kidney disease (Tenner et al., 2024). In a large trial, early aggressive fluids caused fluid overload in 20.5% of patients, compared with 6.3% given moderate fluids, without better outcomes (de-Madaria et al., 2022).

The nurse therefore watches both sides of the balance:

- **Too little fluid:** rising heart rate, falling blood pressure, low urine output, and rising urea, creatinine or hematocrit.
- **Too much fluid:** shortness of breath, crackles, falling oxygen saturation, rising weight and edema.

Accurate intake and output, daily weights and frequent vital signs make both visible (Chapter 3).

Pain. Pain is often severe and is a priority. The nurse gives analgesia as ordered, reassesses and watches for opioid sedation and slow breathing (Chapter 5).

Feeding. In mild disease, the guideline suggests eating by mouth within 24 to 48 hours as tolerated, starting with a low-fat solid diet rather than stepping up from clear fluids. Keeping the patient NPO for days is no longer standard (Tenner et al., 2024). In moderately severe or severe disease, enteral feeding, including by nasogastric tube, is preferred because it appears to prevent infection. Parenteral nutrition is used only when enteral feeding is not possible or not enough (Tenner et al., 2024; Chapter 24).

Monitoring and escalation. The nurse checks glucose, electrolytes and calcium as ordered (Chapter 3; Chapter 22). The nurse also watches the respiratory rate, work of breathing and oxygen saturation. A systolic blood pressure below 90 mm Hg, low oxygen levels, low urine output or rising creatinine can mean organ failure (Tenner et al., 2024). These findings call for immediate escalation, using the early warning score and the rapid response team (Chapter 6). Antibiotics are not given to prevent infection. They are used when infection is present, such as cholangitis or infected necrosis (Tenner et al., 2024).

Gallstone pancreatitis. In gallstone pancreatitis without cholangitis, the guideline favours medical care over early ERCP; with cholangitis, ERCP within 24 hours is advised (Tenner et al., 2024). After mild gallstone pancreatitis, cholecystectomy is done early, preferably before discharge, to prevent another attack (Tenner et al., 2024).

Alcohol. When alcohol is a cause, the nurse offers non-judgmental support, watches for withdrawal and connects the patient with treatment (Chapter 11).

> GOING DEEPER
>
> **Fluids and Organ Failure in Severe Acute Pancreatitis**
>
> *Required for RN students; optional for PN students.*

The revised Atlanta classification scores three organ systems (respiratory, cardiovascular and renal) with the modified Marshall score. Organ failure is a score of 2 or more in any one system (Banks et al., 2013). The ACG guideline gives practical markers: a systolic blood pressure below 90 mm Hg, a PaO_2 below 60 mm Hg, or a creatinine above about 177 µmol/L (2 mg/dL) after rehydration (Tenner et al., 2024). Persistent systemic inflammatory response syndrome (SIRS) is another warning: two or more of a heart rate above 90, a respiratory rate above 20, a temperature above 38 °C or below 36 °C, and an abnormal white cell count (Tenner et al., 2024).

Fluids cut both ways: leaking capillaries lower blood volume and organ perfusion, but extra fluid collects in the lungs and tissues. In the WATERFALL trial, aggressive goal-directed lactated Ringer's caused more fluid overload than a moderate approach (20.5% vs 6.3%) and did not reduce moderately severe or severe disease (de-Madaria et al., 2022). The RN therefore treats the fluid order as a hypothesis to test. The RN reassesses within hours, trends urea, hematocrit, urine output, lung sounds and oxygen needs, and reports early when the response is poor or overload appears. Patients with heart or kidney disease need the closest watch (Tenner et al., 2024).

Table 26.4 summarizes the gallbladder and pancreatic emergencies in this chapter and the nurse's first actions.

Table 26.4 Gallbladder and pancreatic emergencies at a glance (Aubin & Ball, 2018; Chandrasekhara et al., 2017; Kiriyama et al., 2012; Tenner et al., 2024)

Condition	Key signs	First nursing actions
Acute cholecystitis	RUQ pain lasting more than a few hours, fever, Murphy sign	NPO, IV access and fluids as ordered, analgesia, antibiotics as ordered; watch for sepsis; prepare for early surgery
Acute cholangitis	Fever, jaundice and abdominal pain (often not all three); confusion or low blood pressure in severe disease	Escalate at once; IV access, cultures and antibiotics as ordered; NPO; prepare for urgent ERCP
Acute pancreatitis	Epigastric pain often spreading to the back, vomiting, raised lipase; rising heart rate and falling urine output in early hypovolemia	IV fluids as ordered with reassessment within hours; analgesia; intake, output and weight; watch for organ failure and fluid overload
After ERCP	New or worse abdominal pain, vomiting, bleeding, severe pain with a rigid abdomen, fever	Assess vital signs and abdomen; report new pain promptly; keep NPO until assessed; escalate signs of perforation or bleeding

Chronic Pancreatitis

Chronic pancreatitis is a long-lasting fibroinflammatory disease. In people who are susceptible, repeated or ongoing injury leaves the pancreas scarred and slowly destroys its function (Gardner et al., 2020). Alcohol and smoking are the main toxic causes. Inherited, obstructive and autoimmune causes, and repeated attacks of acute pancreatitis, also lead to it (Gardner et al., 2020).

Abdominal pain is the main complaint. When enough enzyme-producing tissue is lost, fat is not digested and the person has **steatorrhea** (bulky, greasy, foul-smelling stools) and weight loss. Low levels of the fat-soluble vitamins, malnutrition and osteoporosis follow. Diabetes develops when insulin-producing cells are lost (Chapter 22), and the risk of pancreatic cancer is higher (Gardner et al., 2020). CT or magnetic resonance imaging (MRI) is the first imaging test, and a stool elastase test helps show poor enzyme output (Gardner et al., 2020).

Care focuses on four areas:

- **Stopping alcohol and tobacco:** the guideline's first step (Gardner et al., 2020; Chapter 11).
- **Pain:** managed with a long-term plan (Chapter 5). Endoscopic or surgical treatment helps some people with a blocked duct (Gardner et al., 2020).
- **Nutrition:** support with a dietitian (Chapter 24).
- **Pancreatic enzyme replacement therapy (PERT):** replaces the missing enzymes and treats malabsorption and malnutrition, but it is not a treatment for pain (Gardner et al., 2020).

In Canada, PERT is available as pancreatin capsules, for example Creon, made from pig pancreas (BGP Pharma ULC, 2024). The nurse discusses the porcine source with any patient for whom it matters.

LIFESPAN CONSIDERATIONS

Liver and Biliary Disease in Older Adults

- **Cholecystitis can be quieter and more dangerous.** Older adults are among the groups at higher risk of complicated cholecystitis, and advanced age raises the risk of a gangrenous gallbladder. Clinicians therefore keep a low threshold for suspecting it (Aubin & Ball, 2018). Because illness often presents atypically in older adults (Chapter 8), the nurse treats new confusion, poor intake or a fall in an older adult with gallstones as a possible cue.
- **Age alone does not rule out surgery.** Studies favour early laparoscopic cholecystectomy even after age 80, although the evidence is of low quality (Pisano et al., 2020).
- **Age counts in cholangitis grading.** Age 75 or older is one of the five Tokyo factors, any two of which make cholangitis moderate, a grade that calls for early drainage (Kiriyama et al., 2012).
- **Drugs act longer.** Many drugs are cleared by the liver (section 26.1). In liver disease, sedatives, opioids and benzodiazepines can build up and bring on hepatic encephalopathy, so the nurse watches older adults closely after each dose (Jophlin et al., 2024; Chapter 8).
- **Falls and delirium.** Hepatic encephalopathy, lactulose-driven trips to the toilet and diuretics combine to raise fall risk (section 26.3). The nurse uses a toileting schedule, a low bed and a bed alarm, and screens for delirium (Chapter 8).

Chapter 26 Summary

26.1 The Liver, Biliary Tree and Pancreas

- The liver receives portal blood from the gut and handles metabolism, albumin and clotting factor production, bilirubin and bile, and drug clearance; the pancreas makes digestive enzymes and, in its islets, insulin and glucagon.
- ALT and AST show liver cell injury, ALP and GGT show blocked bile flow, and albumin and the INR reflect synthetic function; reference ranges vary by laboratory.
- A cholestatic pattern (ALP higher than ALT) suggests blocked bile flow; an ALT above 1,000 U/L calls for an acetaminophen history.
- Jaundice may be prehepatic, hepatic or posthepatic; on darker skin, the nurse checks the sclerae and hard palate in natural or indirect light.
- Pruritus from cholestasis can disrupt sleep; skin care, short nails and reporting help.

26.2 Viral Hepatitis and Steatotic Liver Disease

- Hepatitis A spreads by the fecal-oral route and never becomes chronic; hepatitis B spreads through blood and body fluids and is prevented by vaccine; hepatitis C spreads mainly through blood and is curable.
- In 2021, an estimated 262,000 people in Canada were living with chronic hepatitis B and 214,000 with chronic hepatitis C, and about four in ten did not know it.
- CASL and AMMI Canada now recommend one-time hepatitis B screening for all adults; hepatitis C screening advice differs among the Canadian Task Force, CASL and PHAC.
- Direct-acting antivirals cure more than 90% of people with hepatitis C; Canada is committed to the WHO 2030 elimination targets.
- MASLD replaces NAFLD; it affects about one in five Canadians and most people with type 2 diabetes, and weight loss of 5% to 10% or more with exercise is the core of care.

26.3 Cirrhosis and Its Complications

- Cirrhosis causes portal hypertension and liver failure; decompensation is marked by overt ascites, variceal bleeding or overt hepatic encephalopathy.
- Ascites is managed with about 2 g of sodium a day, diuretics, avoidance of NSAIDs, daily weights and paracentesis with albumin when more than 5 L is removed; SBP may cause fever, pain, confusion or no symptoms.

- A variceal bleed is an emergency: protect the airway, call for help, use a restrictive transfusion strategy, start a vasoactive drug and antibiotics, and arrange endoscopy within 12 hours.
- Hepatic encephalopathy usually has a trigger; lactulose is titrated to two to three soft stools a day, rifaximin helps prevent recurrence, and safety and airway protection come first.
- Living with cirrhosis means no alcohol, no NSAIDs, cautious acetaminophen, a late-evening snack without protein restriction, vaccines, liver cancer surveillance every 6 months and early palliative care.

26.4 Alcohol-Related Liver Disease, Acute Liver Failure and Transplant

- Alcohol-related liver disease ranges from fatty liver through alcohol-associated hepatitis to cirrhosis; alcoholic liver disease led the rise in alcohol-attributable deaths and hospitalizations in Canada during the COVID-19 pandemic.
- Stopping alcohol is the key treatment; severe alcohol-associated hepatitis may be treated with corticosteroids, nutrition support and, for a few selected people, early transplant. The nurse uses person-first, non-judgmental language and links the person to treatment (Chapter 11).
- Acute liver failure is an INR of 1.5 or higher with any encephalopathy, in a person without cirrhosis, within 26 weeks; acetaminophen is the most common cause of liver failure in Canada.
- N-acetylcysteine is given whenever acetaminophen overdose is suspected, even if the timing is unknown; the Ontario Poison Centre (1-800-268-9017) gives advice at any hour.
- Patients with acute liver failure need frequent neurological and glucose checks, ICU care and early contact with a transplant centre.
- Liver transplant recipients take immunosuppressants for life, report fever, jaundice and other warning signs, and keep lifelong follow-up.

26.5 Gallbladder and Biliary Disease

- About 10% of people have gallstones; most never have symptoms. Biliary colic lasts about 30 minutes to 4 hours; longer pain suggests cholecystitis.
- Acute cholecystitis causes persistent RUQ pain, fever and a Murphy sign; ultrasound is the first test, and early laparoscopic cholecystectomy is preferred.
- After laparoscopic cholecystectomy, shoulder pain from the gas is common; worsening pain, fever, vomiting beyond 24 hours, jaundice and wound problems are reported.
- The Charcot triad (fever, jaundice, pain) is specific but appears in only about 1 in 4 patients with cholangitis; severe cholangitis needs urgent escalation, antibiotics and duct drainage.
- After ERCP, new or worse abdominal pain suggests post-ERCP pancreatitis, the most common serious complication; bleeding and perforation are also watched for.

26.6 Acute and Chronic Pancreatitis

- Gallstones and alcohol cause most acute pancreatitis; diagnosis needs two of typical pain, lipase at least three times the upper limit of normal, and typical imaging.
- The revised Atlanta classification grades severity by organ failure: transient (under 48 hours) or persistent (over 48 hours), plus local and systemic complications.
- Early care is moderately aggressive IV fluids (lactated Ringer's preferred) with reassessment within hours, watching for both hypovolemia and fluid overload.
- Patients with mild disease eat early, starting with a low-fat solid diet; enteral feeding is preferred over parenteral in more severe disease; prophylactic antibiotics are not used.
- Cullen and Grey Turner signs are rare signs of serious disease; on dark skin, bruising may look only darker than the surrounding skin.
- Chronic pancreatitis causes pain, steatorrhea, weight loss and diabetes; pancreatic enzymes are taken during or right after meals and snacks and swallowed whole.

Key Terms (49)

acute cholecystitis: Inflammation of the gallbladder, usually because a stone is stuck in its neck; the pain persists for longer than biliary colic and is often accompanied by fever and right upper quadrant tenderness.

acute liver failure (ALF): A sudden, severe loss of liver function in a person without cirrhosis, with an INR of 1.5 or higher and any degree of encephalopathy, arising within 26 weeks of the start of the illness.

acute pancreatitis: Acute inflammation of the pancreas, diagnosed when two of three features are present: typical pain, lipase or amylase at least three times the upper limit of normal, and typical imaging findings.

alcohol-associated hepatitis: The acute inflammatory stage of alcohol-related liver disease, typically with new jaundice in a person who has been drinking heavily.

alcohol-related liver disease (ALD): Liver injury caused by drinking alcohol over time, ranging from fatty liver through alcohol-associated hepatitis and fibrosis to cirrhosis and liver cancer.

ascites: A build-up of fluid in the peritoneal cavity, most often caused by portal hypertension in cirrhosis.

asterixis: A flapping movement of the outstretched hands with the wrists bent back, caused by brief loss of muscle tone; a sign of hepatic encephalopathy.

biliary colic: Pain, usually lasting about 30 minutes to 4 hours, caused when a gallstone briefly blocks the cystic duct; felt in the right upper quadrant or epigastrium, often after a meal.

bilirubin: A yellow pigment made when old red blood cells break down; the liver conjugates it and secretes it into bile.

Charcot triad: Fever, jaundice and abdominal pain; a highly specific but insensitive combination of signs of acute cholangitis.

cholangitis: Infection of the bile ducts behind a blockage, most often a stone; severe cases cause organ dysfunction and need urgent drainage.

choledocholithiasis: A stone in the common bile duct.

cholelithiasis: Stones in the biliary tract, most often in the gallbladder.

chronic pancreatitis: A long-lasting fibroinflammatory disease in which ongoing injury scars the pancreas and slowly destroys its digestive and hormone-producing function.

cirrhosis: Advanced scarring of the liver, with nodules of regenerating cells, that impairs blood flow through the liver and liver function.

compensated cirrhosis: Cirrhosis without overt ascites, variceal bleeding or overt hepatic encephalopathy.

Cullen sign: Bruising around the umbilicus caused by blood tracking from behind the peritoneum; rare and not specific to pancreatitis, but a sign of serious disease.

decompensated cirrhosis: Cirrhosis in which overt ascites, variceal bleeding or overt hepatic encephalopathy has developed.

direct-acting antiviral: A drug that blocks a step in hepatitis C virus replication; taken as tablets for 8 to 24 weeks, these drugs cure most people.

endoscopic retrograde cholangiopancreatography (ERCP): A procedure in which an endoscope passed through the mouth into the duodenum is used to image and treat the bile and pancreatic ducts, for example by removing stones.

esophageal varices: Enlarged, thin-walled veins in the lower esophagus caused by portal hypertension, which can bleed heavily.

Grey Turner sign: Bruising of the flanks caused by blood tracking from behind the peritoneum; rare and not specific to pancreatitis, but a sign of serious disease.

hepatic encephalopathy (HE): Brain dysfunction caused by liver failure, blood bypassing the liver, or both, ranging from subtle changes to coma.

hepatitis: Inflammation of the liver.

hepatitis A: A liver infection spread by the fecal-oral route that does not become chronic and is prevented by vaccine and hand hygiene.

hepatitis B: A liver infection spread through blood and body fluids that becomes chronic in a minority of infected adults and most infected infants; preventable by vaccine.

hepatitis C: A liver infection spread mainly through blood that often becomes chronic and is curable with direct-acting antivirals; no vaccine exists.

hepatocellular carcinoma: Cancer arising from liver cells, a long-term risk of cirrhosis and chronic hepatitis B.

hepatorenal syndrome: Acute kidney injury in a person with cirrhosis, caused by constriction of the kidneys' blood vessels rather than kidney damage, shock or nephrotoxic drugs.

jaundice: A yellow colour of the skin, sclerae and mucous membranes caused by a high blood level of bilirubin.

laparoscopic cholecystectomy: Removal of the gallbladder through small abdominal incisions using a camera and instruments.

lipase: A pancreatic digestive enzyme; a blood level at least three times the upper limit of normal is one of the diagnostic features of acute pancreatitis.

liver transplant: Replacement of a failing liver with a whole liver from a deceased donor or part of a liver from a living donor.

metabolic dysfunction-associated steatohepatitis (MASH): MASLD with inflammation and liver cell injury; formerly called nonalcoholic steatohepatitis (NASH).

metabolic dysfunction-associated steatotic liver disease (MASLD): Fat build-up in the liver with at least one cardiometabolic risk factor and no other cause; formerly called nonalcoholic fatty liver disease (NAFLD).

Murphy sign: A sudden stop in breathing in, caused by pain, when the examiner presses under the right rib margin; a local sign of acute cholecystitis.

N-acetylcysteine (NAC): The antidote for acetaminophen overdose (marketed in Canada as acetylcysteine), given whenever overdose is suspected, even if the timing is unknown.

palmar erythema: Redness of the palms, mostly at the base of the thumb and little finger, seen in advanced liver disease.

pancreatic enzyme replacement therapy (PERT): Capsules of pancreatic enzymes taken with meals and snacks to digest food when the pancreas no longer makes enough enzymes.

paracentesis: Drainage of ascitic fluid through a needle or catheter in the abdominal wall, for diagnosis or to relieve a large or tense ascites.

portal hypertension: Raised pressure in the portal vein system, usually caused by resistance to blood flow through a scarred liver.

portal vein: The vein that carries blood from the stomach, intestines, pancreas and spleen to the liver.

pruritus: Itching; in liver disease, often caused by cholestasis.

revised Atlanta classification: An international system that defines acute pancreatitis and grades it as mild, moderately severe or severe according to organ failure and complications.

spider angioma: A small red spot with fine vessels radiating outward that fades when the centre is pressed; seen in advanced liver disease.

spontaneous bacterial peritonitis (SBP): Infection of ascitic fluid without an obvious source, diagnosed by a fluid neutrophil count above 250/mm³.

steatorrhea: Bulky, greasy, foul-smelling stools caused by undigested fat.

steatotic liver disease: The umbrella term for fat build-up in the liver from any cause.

sustained virologic response: No hepatitis C virus found in the blood 12 weeks after treatment ends; considered a cure.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Lorraine Bouchard (Questions 1–4): Lorraine Bouchard, 63, has cirrhosis related to MASLD and type 2 diabetes and was admitted to a medical unit in Ontario with confusion; her daughter says that for three days Lorraine has slept most of the day, been awake at night and mixed up the days of the week, and that Lorraine cut back her lactulose because she was afraid of accidents while shopping.

1. [CORE] On admission, which finding best supports the nurse's concern that Ms. Bouchard's hepatic encephalopathy is worsening?

a. A soft, nontender abdomen with active bowel sounds in all four quadrants

b. Yellow sclerae that her daughter says have looked the same to her for several months now

c. A flapping movement of the hands when she holds her arms out with wrists bent back

d. A capillary blood glucose of 7.8 mmol/L taken one hour after she ate breakfast

Answer: c — Asterixis, a flapping of the outstretched hands caused by brief loss of muscle tone, appears at West Haven grade II and with day-night reversal signals overt HE (section 26.3, Hepatic Encephalopathy). A soft abdomen with bowel sounds is a normal finding. Long-standing scleral jaundice reflects her liver disease but does not show a change in brain function. A glucose of 7.8 mmol/L after a meal is not low; hypoglycemia, not this value, can mimic HE.

2. [CORE] The nurse looks for a trigger for Ms. Bouchard's encephalopathy. Which finding is most likely the trigger?

a. Only one hard bowel movement in the past two days since she reduced her lactulose

b. A serum sodium of 138 mmol/L on the admission blood work drawn this morning

c. A temperature of 36.8 °C, clear lungs on auscultation in all lobes, and no new cough

d. A potassium of 4.2 mmol/L with no change from her clinic visit last month

Answer: a — Constipation lets ammonia build up in the gut and is a common trigger of HE; cutting back lactulose explains it (section 26.3, Hepatic Encephalopathy). A sodium of 138 mmol/L and a potassium of 4.2 mmol/L are within usual ranges, so they do not point to an electrolyte trigger. A normal temperature and clear lungs make infection less likely, though the nurse still watches for it.

3. [CORE] On day 2, Ms. Bouchard is alert and oriented, and the nurse begins discharge teaching. Which statement shows that she understands her lactulose?

a. "I will take lactulose only on the days when I have not had a bowel movement."

b. "I will take it every day and aim for two or three soft bowel movements a day."

c. "If I have more than one soft stool, I will stop it until I feel constipated."

d. "I will add a stimulant laxative at bedtime every night to make sure the lactulose works."

Answer: b — Lactulose is taken daily and titrated to two to three soft bowel movements a day to prevent HE from returning (section 26.3, Patient Education box). Taking it only when constipated allows ammonia to build up again. Stopping it after one soft stool undertreats her. Other laxatives are avoided unless prescribed, because loose stools could hide whether the lactulose dose is right.

4. [CORE] That evening, Ms. Bouchard is hard to rouse, responds only to a loud voice and has vomited once. The RPN caring for her is due to give her oral lactulose. What is the RPN's priority?

a. Give the lactulose with a small amount of juice so she can swallow it more easily

b. Document the change and recheck her level of consciousness at the next scheduled round

c. Wake her fully with a cool cloth and then offer the lactulose and fluids by mouth

d. Hold the oral dose, turn her onto her side, and get help from the RN and team now

Answer: d — A patient who is hard to rouse and vomiting cannot protect her airway, so oral lactulose risks aspiration; positioning her on her side and escalating at once are the priorities (section 26.3, Hepatic Encephalopathy; Chapter 6). Any nurse who notices deterioration acts and escalates, and the RPN consults the RN as the patient's needs change. Giving the dose orally, with or without juice or after rousing her, ignores the aspiration risk. Waiting until the next round delays care for a patient who may need critical care.

5. [CORE] Which laboratory result best reflects the liver's ability to make proteins?

a. Alanine aminotransferase (ALT) activity

b. International normalized ratio (INR)

c. Gamma-glutamyl transferase (GGT)

d. Aspartate aminotransferase (AST)

Answer: b — The INR depends on clotting factors that the liver makes, so it reflects the liver's synthetic function and changes faster than albumin (section 26.1, Liver Tests the Nurse Sees). ALT and AST are enzymes released when liver cells are injured; they show injury, not function. GGT rises with blocked bile flow and helps show that a raised ALP comes from the liver.

6. [CORE] The nurse assesses a patient with dark skin for jaundice. Which approach is best?

a. Inspect the skin of the forearms under the room's overhead fluorescent lights

b. Press on the nail beds and watch how long the colour takes to return

c. Rely on the bilirubin result, because jaundice cannot be seen on dark skin

d. Inspect the sclerae and the hard palate in natural or indirect light

Answer: d — Jaundice is harder to see on darker skin, so the nurse looks at the sclerae and inside the mouth, especially the hard palate, in natural or indirect light (section 26.1, Jaundice). Fluorescent light casts a bluish tint and can hide true colour, and the forearms are a poor site. Capillary refill tests circulation, not bilirubin. Jaundice can be seen on any skin tone when the right sites and light are used; the blood test confirms it but does not replace assessment.

7. [CORE] A restaurant worker is diagnosed with acute hepatitis A. Which teaching is accurate?

a. Careful hand hygiene after using the toilet helps prevent spread to others

b. The infection often becomes chronic, so lifelong blood tests will be needed

c. The virus spreads mainly through sexual contact and shared drug equipment

d. Antiviral tablets taken for 8 to 12 weeks will cure the infection completely

Answer: a — Hepatitis A spreads by the fecal-oral route, so hand hygiene is central to preventing spread (section 26.2, Hepatitis A, B and C). Hepatitis A never becomes chronic. Spread by sex and shared drug equipment describes hepatitis B and C. Hepatitis A is treated with supportive care; direct-acting antivirals are for hepatitis C.

8. [CORE] A patient's anti-HCV (hepatitis C antibody) test is positive. What does the nurse explain?

a. The result proves that the patient has a current infection that needs treatment

b. The result shows that the patient is immune because of an earlier vaccination

c. A second test for HCV RNA is needed to show whether the virus is still present

d. The patient should repeat the same antibody test in one year to confirm it

Answer: c — A positive antibody test shows current or past infection; because some people clear the virus, an HCV RNA test confirms whether infection is current (section 26.2, Hepatitis A, B and C). There is no hepatitis C vaccine. Repeating the antibody test does not help, because antibodies stay positive after the virus clears.

9. [CORE] Which statement about hepatitis B in Canada is accurate?

a. Adults who are infected usually develop lifelong chronic infection

b. The 2025 CASL and AMMI Canada guideline recommends screening all adults once

c. Antiviral tablets cure chronic hepatitis B in 8 to 12 weeks in most people

d. Hepatitis B spreads mainly through contaminated food and water in Canada

Answer: b — The 2025 CASL and AMMI Canada guideline recommends one-time screening of all adults with HBsAg, anti-HBs and anti-HBc (section 26.2, Hepatitis A, B and C). Only 3% to 10% of infected adults develop chronic infection; infants are at far higher risk. Antivirals control the virus over the long term rather than curing it in weeks. Food and water spread hepatitis A, not hepatitis B.

10. [CORE] A patient with type 2 diabetes is told that she has MASLD. Which goal is most appropriate to discuss?

a. Avoiding all dietary fat until her next liver ultrasound

b. Stopping her statin, because statins are harmful in MASLD

c. Following a low-protein diet to reduce strain on her liver

d. Losing at least 5% to 10% of her body weight over time

Answer: d — Sustained weight loss of at least 5% to 10% is recommended for MASLD, with more than 10% preferred to reverse fibrosis, along with regular exercise (section 26.2, Metabolic Dysfunction-Associated Steatotic Liver Disease). Cutting out all fat is not the recommended approach. Diabetes Canada advises continuing statins unless cirrhosis becomes decompensated. Protein restriction is not advised in liver disease.

11. [CORE] The nurse cares for a patient with cirrhosis and ascites. Which actions are appropriate? Select all that apply.

a. Weigh the patient daily on the same scale

b. Measure abdominal girth at a marked site

c. Restrict fluid to 1 L a day for every patient with ascites

d. Offer ibuprofen for back discomfort from the tense abdomen

e. Track intake and output and watch sodium and creatinine

f. Encourage salty broth to replace salt lost through diuretics

Answer: a, b, e — Daily weights, girth at a marked site, and intake, output and laboratory monitoring track ascites and diuretic effects (section 26.3, Ascites and Spontaneous Bacterial Peritonitis). Fluid is restricted only when serum sodium becomes very low, at about 125 mmol/L or below. NSAIDs such as ibuprofen are avoided because they can cause low sodium, diuretic resistance and kidney injury. Salty broth works against the sodium restriction of about 2 g a day.

12. [CORE] A patient with cirrhosis and ascites develops a temperature of 38.1 °C, mild diffuse abdominal tenderness and new forgetfulness. What should the nurse suspect and do?

a. Spontaneous bacterial peritonitis; report promptly and prepare for a diagnostic paracentesis

b. Normal discomfort after a meal; offer a heating pad and reassess the abdomen again in four hours

c. Dehydration from diuretics; encourage oral fluids and recheck the temperature at bedtime

d. Constipation from reduced activity; give an extra dose of lactulose and document it

Answer: a — Fever, abdominal tenderness and new confusion in a patient with ascites suggest spontaneous bacterial peritonitis, which needs prompt reporting, a diagnostic paracentesis and IV antibiotics (section 26.3, Ascites and Spontaneous Bacterial Peritonitis). Fever and confusion are not normal after meals. Dehydration does not explain fever with abdominal tenderness. Changing lactulose without an order and without looking for infection delays treatment.

13. [CORE] A patient with cirrhosis suddenly vomits a large amount of bright red blood. What is the nurse's first action?

a. Insert a nasogastric tube to drain the stomach and measure the blood loss

b. Give the next scheduled dose of the nonselective beta-blocker by mouth

c. Turn the patient onto the side and call for help through rapid response

d. Ask the patient to describe when the bleeding started and how it felt

Answer: c — Protecting the airway by turning the patient to the side and calling for help at once come first in a variceal bleed (section 26.3, Varices and Variceal Bleeding). Inserting a tube is not a first action and may injure varices. Oral drugs are unsafe while the patient is vomiting blood. History can wait until the airway is protected and the team is coming.

14. [CORE] An RPN on a medical unit cares for a patient with cirrhosis who was stable. At 0300, the patient has black, tarry stool, a heart rate of 118 beats per minute and new restlessness. What should the RPN do?

a. Finish the rest of the assessment round, then report all findings to the RN in the morning

b. Act at once to stay with the patient, escalate per policy and consult the RN immediately

c. Ask the unregulated care provider to recheck the vital signs in an hour and report back

d. Call the patient's family to ask whether this has happened before during earlier stays

Answer: b — Melena, a rising heart rate and restlessness suggest GI bleeding with deterioration; every nurse who notices this acts at once and escalates, and the RPN consults the RN because the patient's needs have changed (section 26.3, Varices and Variceal Bleeding; Chapter 1, section 1.3). Waiting until morning or an hour delays care. Calling the family does not address the emergency.

15. [CORE] An RPN's patient with cirrhosis now has grade III hepatic encephalopathy, needs frequent neurological checks and may need transfer to critical care. Which response best reflects CNO's scope framework?

a. The RPN keeps the patient because RPNs may care only for stable, predictable patients

b. The RPN must transfer care at once because CNO bans RPNs from neurological checks

c. The RPN keeps the patient without discussion because the assignment is already set

d. The RPN consults the RN about authority, competence and context, including unit policy

Answer: d — CNO's Scope of Practice standard uses authority, competence and context (College of Nurses of Ontario, 2025); as the patient's needs change, the RPN consults the RN, and they decide together who is best placed to provide care, within employer policy (section 26.3; Chapter 1, section 1.3). Assigning RPNs to stable patients is a common employer practice, not a CNO rule. CNO does not ban RPNs from neurological checks. Keeping the assignment without discussion ignores the change in the patient's needs.

16. [CORE] A patient asks why rifaximin was added to the lactulose he takes for hepatic encephalopathy. What is the best response?

a. "Rifaximin is added to lactulose to lower the chance that confusion comes back."

b. "Rifaximin replaces lactulose, so you can stop the lactulose when you go home."

c. "Rifaximin treats the scarring in your liver and will slowly reverse your cirrhosis over time."

d. "Rifaximin is a sedative that will help you sleep through the night again."

Answer: a — Rifaximin is an antibiotic that stays mostly in the gut and is added to lactulose to prevent overt HE from coming back (section 26.3, Hepatic Encephalopathy). It does not replace lactulose. It does not reverse cirrhosis. It is not a sedative, and sedatives can worsen HE.

17. [CORE] A patient with compensated cirrhosis asks what to take for a headache. Which response is best?

a. "Ibuprofen is the safest choice, because it is not processed by the liver."

b. "Take any cold remedy you like, since these do not contain pain relievers."

c. "Avoid ibuprofen and naproxen, and ask your prescriber how much acetaminophen is safe."

d. "Take extra-strength acetaminophen as often as you need to until the headache has completely gone."

Answer: c — NSAIDs are avoided in cirrhosis, and people with liver disease may need a lower acetaminophen limit than the label states, so the patient checks with the prescriber or pharmacist (section 26.3, Living With Cirrhosis; Chapter 5). Ibuprofen can cause kidney injury and fluid retention in cirrhosis. Many cold remedies contain acetaminophen. Taking acetaminophen as often as needed risks liver injury.

18. [RN] A patient has jaundice, dark urine and pale stools. Results: ALT 95 U/L, ALP 620 U/L, GGT 540 U/L and a raised conjugated bilirubin. Which interpretation is most accurate?

a. A hepatocellular pattern that suggests acute viral hepatitis or acetaminophen injury

b. A cholestatic pattern that suggests blocked bile flow, such as a stone in the bile duct

c. A prehepatic pattern caused by rapid breakdown of red blood cells in the circulation

d. A normal pattern for an older adult that needs no further assessment or follow-up

Answer: b — ALP far above ALT, with a raised GGT confirming a liver source and a raised conjugated bilirubin, is a cholestatic pattern; with dark urine and pale stools, it suggests posthepatic obstruction (section 26.1, Liver Tests the Nurse Sees; Jaundice). A hepatocellular pattern would show ALT and AST raised more than ALP. Hemolysis raises unconjugated bilirubin without this enzyme pattern. These results are abnormal at any age.

19. [RN] A patient with cirrhosis arrives with hematemesis. Hemoglobin is 74 g/L and INR 1.8. Which plan matches Baveno VII?

a. Start a vasoactive drug now, give antibiotic prophylaxis, and plan endoscopy within 12 hours

b. Transfuse red cells until hemoglobin is above 100 g/L, then plan endoscopy within 72 hours

c. Give fresh frozen plasma first to bring the INR back to normal before any other treatment is started

d. Withhold antibiotics until a fever develops, to avoid antibiotic resistance on the unit

Answer: a — Baveno VII calls for a vasoactive drug as soon as possible, antibiotic prophylaxis and endoscopy within 12 hours (section 26.3, Varices and Variceal Bleeding). Transfusion is restrictive, targeting hemoglobin of 70 to 80 g/L, so transfusing to above 100 g/L goes against the guidance, and 72 hours is too late for endoscopy. Fresh frozen plasma is not recommended, because it does not correct the clotting problem. Antibiotics are part of treatment, not reserved for fever.

20. [RN] A patient with cirrhosis and ascites has a creatinine that rose from 88 to 150 µmol/L over 48 hours, with falling urine output, no shock and no nephrotoxic drugs. Which statement is accurate?

a. The rise is expected with ascites and needs no change in the plan of care

b. Diuretics should be increased to clear the ascites and restore urine output

c. The rise in creatinine raises the MELD score and signals higher 3-month mortality risk

d. MELD is calculated from albumin and the amount of ascites, so creatinine does not change the score

Answer: c — Creatinine is part of the MELD score, which predicts 3-month mortality; this picture fits hepatorenal syndrome, which calls for stopping diuretics, albumin with a vasoconstrictor and urgent transplant assessment (section 26.3, Going Deeper box). A creatinine rise of this size is acute kidney injury and is never expected. Increasing diuretics worsens kidney perfusion. MELD uses bilirubin, creatinine and INR, not albumin and ascites.

Case: Lorraine Bouchard (Questions 21–26): Lorraine Bouchard, 62, was admitted to a surgical unit at 0400 with epigastric pain that began 10 hours earlier after a large meal, spreads to her back and has caused vomiting four times; ultrasound shows gallstones with a common bile duct of normal size; her lipase is 2,400 U/L (laboratory upper limit 60 U/L) and her weight is 70 kg; at 0800 her temperature was 37.6 °C, heart rate 104, blood pressure 124/72 mm Hg, respiratory rate 20 and SpO_2 96% on room air, and at 1200 her temperature is 37.6 °C, heart rate 118, blood pressure 104/64 mm Hg, respiratory rate 22, SpO_2 95% on room air, urine output 60 mL over the past 4 hours, blood urea 9.8 mmol/L (7.1 mmol/L at 0400), creatinine 118 µmol/L (82 µmol/L at 0400) and total bilirubin 19 µmol/L.

21. [CORE] At 1200, which findings require immediate follow-up by the nurse? Select all that apply.

a. Heart rate of 118, up from 104 at 0800

b. Lipase of 2,400 U/L with a laboratory upper limit of 60 U/L

c. Urine output of 60 mL over the past 4 hours

d. Blood pressure of 104/64 mm Hg, down from 124/72 mm Hg at 0800

e. Temperature of 37.6 °C, unchanged since 0800

f. Blood urea of 9.8 mmol/L, up from 7.1 mmol/L at 0400

g. Gallstones on ultrasound with a common bile duct of normal size

Answer: a, c, d, f — A rising heart rate (a), a falling blood pressure (d), low urine output (c) and a rising urea (f) are cues of falling blood volume and reduced kidney perfusion. The ACG guideline aims for a falling, not rising, urea in the first 24 to 48 hours (section 26.6). The lipase level (b) confirms the diagnosis that has already been made; it does not call for new action now. A stable temperature of 37.6 °C (e) is not the urgent problem. The ultrasound result (g) explains the cause and shows no dilated duct; it does not need immediate follow-up.

22. [CORE] Which interpretation best fits Ms. Bouchard's findings at 1200?

a. Loss of fluid from the circulation, with early signs of reduced blood flow to her kidneys

b. Acute cholangitis from a stone lodged in the common bile duct, causing sepsis and a falling blood pressure

c. Urinary retention from opioid analgesia, causing low urine output and a rise in heart rate from discomfort

d. Fluid overload from the IV fluids she received in the emergency department, which is now straining her heart and lowering her blood pressure

Answer: a — Inflammation makes capillaries leak, and vomiting adds to the loss, so blood volume falls; the rising heart rate, falling blood pressure, low urine output and rising urea and creatinine fit this picture (section 26.6). Cholangitis (b) is unlikely with a normal-sized duct, no fever and a normal bilirubin (section 26.5). Urinary retention (c) would not explain the rising urea, creatinine and falling blood pressure, although a bladder scan is reasonable. Fluid overload (d) would show breathlessness, crackles and falling oxygen saturation, which she does not have.

23. [CORE] Which problem should the nurse address first?

a. Acute pain related to inflammation of the pancreas

b. Risk of malnutrition because she has vomited and is not eating

c. Hypovolemia that could progress to organ failure

d. Need for teaching about gallstones and a low-fat diet

Answer: c — Hypovolemia threatens perfusion of the kidneys and other organs and can progress to organ failure, which defines severe disease, so it comes first (section 26.6). Pain (a) is a high priority and is treated at the same time, but it is not the life-threatening problem. Nutrition (b) matters, and early feeding is planned once she can tolerate it. Teaching (d) belongs later in her stay.

24. [CORE] The physician reviews Ms. Bouchard at 1215. Which plan should the nurse expect?

a. A fixed 4 L of normal saline over the next 2 hours, with no further assessment until the morning blood work

b. Strict NPO for at least 5 days with clear fluids only after the lipase level returns to normal

c. IV antibiotics started now to prevent infected necrosis, and an ERCP this afternoon to clear stones from the common bile duct

d. A lactated Ringer's bolus, then a continuous infusion, with reassessment of vital signs, urine output and urea within hours

Answer: d — The ACG guideline suggests moderately aggressive fluids with boluses for hypovolemia, prefers lactated Ringer's, and calls for reassessment within 6 hours and over the next 24 to 48 hours (section 26.6). A large fixed volume without reassessment (a) risks fluid overload, which a large trial linked to aggressive fluids. Prolonged NPO (b) is no longer standard; early oral feeding is suggested in mild disease. Prophylactic antibiotics (c) are not recommended, and early ERCP is reserved for patients with cholangitis.

25. [CORE] On day 2, after several fluid boluses, Ms. Bouchard says she cannot catch her breath. Her respiratory rate is 28, SpO_2 89% on room air and heart rate 110. Crackles are heard at both lung bases, and her weight is 3 kg above her admission weight. What should the nurse do first?

a. Increase the IV rate, because a heart rate of 110 shows she still needs more fluid

b. Raise the head of the bed, apply oxygen as ordered and call the physician or rapid response team at once

c. Give her next ordered dose of opioid analgesic, because pain is making her breathe quickly

d. Encourage her to use the incentive spirometer every hour and recheck her oxygen saturation at the next scheduled vital signs

Answer: b — New breathlessness, crackles, low oxygen saturation and weight gain after boluses suggest fluid overload or a lung complication of pancreatitis. Both can mean respiratory organ failure, so the nurse supports breathing and escalates at once (section 26.6; Chapter 6). Increasing fluids (a) could worsen overload. An opioid (c) may slow breathing and does not treat the cause. Waiting for the next check (d) delays care for a patient with an SpO_2 of 89%.

26. [CORE] On day 4, the nurse evaluates Ms. Bouchard's response to care. Which set of findings best shows that her plan is meeting its goals?

a. Urea 6.0 mmol/L, hematocrit unchanged, respiratory rate 18, SpO_2 95% on room air, tolerating a low-fat solid diet

b. Lipase down to 300 U/L and pain well controlled with oral analgesia, but urea 11.4 mmol/L and hematocrit higher than on admission

c. Weight 4 kg above admission with crackles at both bases, IV fluids running at the day 1 rate, eating well

d. Urine output 15 mL/hour for 6 hours, SpO_2 93% on 2 L of oxygen, blood pressure 96/58 mm Hg, nausea settled

Answer: a — A falling urea and a hematocrit that is not rising are the guideline's markers that fluid therapy is working. Normal breathing on room air and tolerance of a low-fat solid diet show recovery (section 26.6). A falling lipase (b) does not show adequate fluid therapy, and the rising urea and hematocrit show that it is not working. Weight gain with crackles (c) shows fluid overload. Low urine output, a new oxygen need and low blood pressure (d) suggest ongoing organ dysfunction.

27. [CORE] A nurse is admitting a patient with alcohol-associated hepatitis. Which statement by the nurse best reflects non-judgmental, person-centred care?

a. "You need to understand that your drinking caused this, and you will die if you don't stop."

b. "Can you tell me about your alcohol use, so we can plan your care and the supports you would find helpful?"

c. "As an alcoholic, you should expect to be watched closely for withdrawal while you are here."

d. "We can't offer you much treatment for your liver until you have shown us that you can stay sober for several months."

Answer: b — An open, respectful question invites an honest history and partnership, and it fits the guideline's call for screening and brief intervention at every visit (section 26.4; Chapter 11). Threats and blame (a) increase shame and make honest talk less likely. Labelling a person an "alcoholic" (c) is stigmatizing; person-first language is used. Treatment is not withheld until sobriety is proven (d); stopping alcohol is a central goal, but care, including nutrition and treatment of severe disease, starts at once.

28. [CORE] A patient arrives in the emergency department and says she took "a lot of extra-strength acetaminophen" sometime yesterday but cannot say when. She feels well. Which statement about N-acetylcysteine is accurate?

a. It is not given, because the time of ingestion is unknown and a level cannot be interpreted

b. It is given only if her liver tests are already abnormal when they return from the laboratory

c. It is not useful once more than 24 hours have passed since the overdose was taken

d. It is given whenever acetaminophen overdose is suspected, even if the timing is unknown

Answer: d — Acute liver failure guidance recommends N-acetylcysteine for anyone who may have taken an acetaminophen overdose, even when the timing is unknown or the level is low, and notes that it can still be of value 2 days or more after ingestion (section 26.4). An unknown time (a) is a reason to give it, not to withhold it. Waiting for abnormal liver tests (b) delays an antidote that works best early. It can still help after 24 hours (c).

29. [CORE] A patient with acute liver failure from a drug reaction has become more confused over the past hour. Which assessment should the nurse complete first?

a. Check the INR result from this morning's blood work

b. Measure urine output for the last 4 hours

c. Check the capillary blood glucose

d. Weigh the patient to compare with yesterday

Answer: c — Hypoglycemia is common in acute liver failure and can be hidden by or mistaken for worsening encephalopathy. A glucose check is quick and the result is treatable at once (section 26.4). The INR (a) tracks liver function but does not explain a change in the last hour. Urine output (b) and weight (d) matter for kidney function and fluid balance but are not the first check for new confusion.

30. [CORE] Which statement by a patient preparing for discharge after a liver transplant shows that teaching has been effective?

a. "If I feel well, my anti-rejection pills are working, so a missed blood test doesn't matter."

b. "I can stop my anti-rejection medicine for a few days if my stomach is upset."

c. "I'll ask my pharmacist whether a cold remedy is safe, but I won't tell the transplant team."

d. "I'll call the transplant team if my eyes look yellow or I develop a fever."

Answer: d — Jaundice and fever can signal rejection or infection and need prompt reporting (section 26.4). Rejection may cause no symptoms and show only in blood work, so scheduled tests matter (a). Anti-rejection drugs are never stopped without the team's direction (b). The transplant team must know about any new prescription, over-the-counter or herbal product (c), because drug interactions can change immunosuppressant levels.

31. [CORE] An RPN is caring for a patient with cirrhosis who had 6 L of ascitic fluid removed 2 hours ago. The patient's blood pressure has dropped from 118/70 to 92/54 mm Hg, and he is newly drowsy. What should the RPN do?

a. Document the findings and recheck the vital signs in 1 hour, since some drop is expected after paracentesis

b. Assess the patient further, report the change to the RN and physician at once, and stay with the patient

c. Start the albumin infusion that is due to be given tomorrow, since albumin helps prevent this problem

d. Give the patient's scheduled diuretic and encourage oral fluids to raise his blood pressure

Answer: b — A falling blood pressure with new drowsiness after large-volume paracentesis is a change in condition. Every nurse acts at once and escalates, and the RPN consults the RN as the patient's needs change (section 26.3, Scope in Practice box; Chapter 6). Waiting an hour (a) delays care for a deteriorating patient. Giving a drug outside its order (c) is beyond the nurse's authority; albumin needs an order for the dose and time. A diuretic (d) would further lower his blood volume.

32. [CORE] A patient with RUQ pain is being assessed for acute cholecystitis. The physician presses under the right rib margin and asks the patient to breathe in deeply. The patient stops breathing in mid-breath because of pain. How should the nurse record this finding?

a. Positive Grey Turner sign

b. Positive Cullen sign

c. Charcot triad

d. Positive Murphy sign

Answer: d — A Murphy sign is the sudden stop in breathing in when the examiner presses over the gallbladder, a local sign of cholecystitis (section 26.5). The Grey Turner sign (a) and the Cullen sign (b) are bruising of the flanks and around the umbilicus from retroperitoneal bleeding (section 26.6). The Charcot triad (c) is fever, jaundice and abdominal pain in cholangitis.

33. [CORE] The day after a laparoscopic cholecystectomy, a patient calls the surgical unit worried about pain in her right shoulder. She has no fever, and her incisions look clean. What should the nurse explain?

a. Shoulder pain after this surgery usually means a stone has moved into the bile duct

b. She should go to the emergency department now, because shoulder pain signals bleeding

c. Gas used to inflate the abdomen often causes shoulder pain; lying flat and warmth to the shoulders may help

d. Shoulder pain shows that the incisions are infected, so she should begin applying warm, moist compresses directly to them

Answer: c — Carbon dioxide used during laparoscopy commonly causes shoulder or neck discomfort for about 48 hours; lying flat and warmth to the shoulders may help (section 26.5). A duct stone (a) causes worsening abdominal pain, jaundice or dark urine. Shoulder pain alone, without fever, worsening abdominal pain or other warning signs, does not mean bleeding (b). Incision infection (d) shows as redness, pus or drainage at the incisions.

34. [CORE] A patient admitted 2 days ago with biliary colic now has a temperature of 39.0 °C, yellow sclerae and abdominal pain. Her blood pressure is 94/56 mm Hg, down from 132/80 mm Hg. What is the nurse's priority?

a. Give acetaminophen for the fever and reassess her temperature in 1 hour

b. Escalate at once for suspected cholangitis with sepsis, and prepare for cultures, fluids and antibiotics

c. Check her sclerae again at the next shift to confirm that the jaundice is real

d. Encourage oral fluids and ask the dietitian to review her low-fat diet

Answer: b — Fever, jaundice and pain with a falling blood pressure suggest acute cholangitis with sepsis, which needs urgent escalation, antibiotics and drainage of the duct (section 26.5; Chapter 4; Chapter 6). Treating the fever alone (a) and waiting a shift (c) delay care for a deteriorating patient. Oral fluids and a diet review (d) do not address the cause, and she may need to be NPO for ERCP.

35. [CORE] Three hours after an ERCP with stone removal, a patient reports new, steady epigastric pain spreading to his back and has vomited once. What should the nurse suspect first?

a. Post-ERCP pancreatitis

b. A normal reaction to the sedation used during the procedure

c. Retained air from the procedure, which will pass without treatment

d. Biliary colic from a new stone forming in the gallbladder

Answer: a — Post-ERCP pancreatitis is the most common serious complication of ERCP, and new or worse abdominal pain is the key cue; the nurse assesses, keeps the patient NPO until assessed and reports promptly (section 26.5). Sedation (b) causes drowsiness or low oxygen levels, not new epigastric pain spreading to the back. Assuming the pain is harmless air (c) could miss pancreatitis or perforation. A new stone (d) does not form within hours.

36. [CORE] A patient with chronic pancreatitis is starting pancreatic enzyme replacement therapy. Which instruction should the nurse include?

a. Take the capsules at bedtime so the enzymes work overnight while the bowel is resting

b. Crush the capsules into a drink if they are hard to swallow, so the enzymes start working sooner

c. Take extra capsules whenever abdominal pain flares, because the enzymes calm the pancreas

d. Take the capsules during or right after meals and snacks, and swallow them whole with fluid

Answer: d — The Canadian monograph directs patients to take the enzymes during or right after meals and snacks and to swallow capsules whole with fluid (section 26.6). Bedtime dosing (a) misses the food the enzymes must digest. Crushing (b) damages the enteric coating, so the enzymes are released too early, and it can irritate the mouth; if swallowing is hard, the capsule can be opened and the granules sprinkled on acidic soft food such as applesauce. Enzymes are not a treatment for pain (c).

37. [CORE] The nurse is teaching a patient going home the day after a laparoscopic cholecystectomy. Which findings should the patient report to the surgeon or the emergency department? Select all that apply.

a. Yellow eyes or skin, with dark urine

b. Mild bloating on the first day after surgery

c. Abdominal pain that is getting worse instead of better

d. Nausea and vomiting lasting more than 24 hours

e. Shoulder discomfort that eases when lying flat

f. Pus or foul-smelling drainage from an incision

g. Persistent fever or chills

Answer: a, c, d, f, g — Jaundice with dark urine (a), worsening abdominal pain (c), vomiting beyond 24 hours (d), wound infection (f) and persistent fever (g) can signal a complication such as bleeding or infection, and need prompt review (section 26.5). Mild bloating on the first day (b) and shoulder discomfort from the gas used in surgery (e) are common and expected.

38. [RN] A patient with acute pancreatitis developed respiratory failure on admission that resolved after 30 hours of oxygen therapy. CT on day 5 shows an acute peripancreatic fluid collection. She has no other organ failure. How is her pancreatitis classified under the revised Atlanta classification?

a. Mild, because the respiratory failure has resolved and she is now improving

b. Severe, because she had organ failure and has a local complication

c. Moderately severe, because organ failure resolved within 48 hours and a local complication is present

d. It cannot be classified until the fluid collection has been drained

Answer: c — Moderately severe disease is defined by organ failure that clears within 48 hours, local or systemic complications, or both, without persistent organ failure (section 26.6, Table 26.3). Mild disease (a) has no organ failure and no complications. Severe disease (b) requires organ failure lasting longer than 48 hours. The classification does not depend on drainage (d).

39. [RN] An RN is caring for a 78-year-old patient with heart failure and acute pancreatitis who is receiving IV lactated Ringer's. Which finding should most concern the RN about the fluid plan?

a. Blood urea falling from 10.2 to 8.1 mmol/L over 12 hours

b. New crackles at both lung bases with a 2 kg weight gain since admission

c. Hematocrit unchanged from admission at 12 hours

d. Heart rate falling from 112 to 96 after the first bolus

Answer: b — New crackles and weight gain suggest fluid overload, the main risk of aggressive fluids. Patients with heart or kidney disease need the closest watch (section 26.6, Going Deeper box). A falling urea (a), an unchanged hematocrit (c) and a slowing heart rate (d) all suggest that fluids are restoring circulating volume as intended.

40. [RN] A patient is admitted to a community hospital with acute liver failure after an acetaminophen overdose. She is now mildly confused (grade 1 encephalopathy), and her INR is 2.8. Which action should the RN anticipate as the priority?

a. Early contact with the liver transplant centre and transfer to intensive care while she can still travel safely

b. Routine plasma transfusion to bring the INR below 1.5 before any other treatment

c. A sedative at bedtime so she can rest, with neurological checks every 8 hours

d. Holding N-acetylcysteine until her acetaminophen level can be compared with the time of ingestion

Answer: a — Any encephalopathy in acute liver failure calls for ICU care and early contact with a transplant centre. Transfer is advised even at grades 1 and 2, because deterioration can make transport unsafe later (section 26.4). Plasma (b) is kept for bleeding or procedures, because routine use hides the INR trend. Sedatives (c) are avoided, and neurological checks are frequent. N-acetylcysteine (d) is given whenever acetaminophen overdose is suspected, without waiting for timing.

References

Alberta Health Services. (2023). *CBC and differential provincial reference intervals and critical values – Epic* (Form HE02-100, Rev. 3.00). https://www.albertahealthservices.ca/assets/wf/lab/if-lab-cbc-and-differential-provincial-reference-intervals-and-critical-values-epic.pdf

Alberta Precision Laboratories. (2020, June 15). *Changes to reference intervals of alanine aminotransferase, vitamin B12, ferritin, gamma glutamyl transferase, magnesium and urea* [Laboratory bulletin]. https://www.albertahealthservices.ca/assets/wf/lab/wf-apl-lab-bulletin-changes-reference-intervals-of-alanine-aminotransferase-vit-b12-ferritin-gamma-glutamyl-transferase-magnesium-urea.pdf

Aubin, J.-M., & Ball, C. G. (2018). Biliary colic and cholecystitis (Chapter 8). In *Dynamic practice guidelines for emergency general surgery*. Committee on Acute Care Surgery, Canadian Association of General Surgeons. https://cags-accg.ca/wp-content/uploads/2019/07/ACS-Handbook-CPG-Ch-8-Biliary-Colic-and-Cholecystitis.pdf

Banks, P. A., Bollen, T. L., Dervenis, C., Gooszen, H. G., Johnson, C. D., Sarr, M. G., Tsiotos, G. G., & Vege, S. S. (2013). Classification of acute pancreatitis—2012: Revision of the Atlanta classification and definitions by international consensus. *Gut, 62*(1), 102–111. https://doi.org/10.1136/gutjnl-2012-302779

BGP Pharma ULC. (2024). *Creon Minimicrospheres (pancreatin) product monograph*. https://pdf.hres.ca/dpd_pm/00076423.PDF

Biggins, S. W., Angeli, P., Garcia-Tsao, G., Ginès, P., Ling, S. C., Nadim, M. K., Wong, F., & Kim, W. R. (2021). Diagnosis, evaluation, and management of ascites, spontaneous bacterial peritonitis and hepatorenal syndrome: 2021 practice guidance by the American Association for the Study of Liver Diseases. *Hepatology, 74*(2), 1014–1048. https://doi.org/10.1002/hep.31884

Canadian Centre on Substance Use and Addiction. (2023, January 17). *More than 6 drinks a week puts your health at risk: New Canada's Guidance on Alcohol and Health* [News release]. https://ccsa.ca/more-6-drinks-week-puts-your-health-risk-new-canadas-guidance-alcohol-and-health

Canadian Institute for Health Information. (2026). *Summary statistics on organ transplants, wait-lists and donors*. https://www.cihi.ca/en/summary-statistics-on-organ-transplants-wait-lists-and-donors

Canadian Task Force on Preventive Health Care. (2017). Recommendations on hepatitis C screening for adults. *CMAJ, 189*(16), E594–E604. https://doi.org/10.1503/cmaj.161521

Chandrasekhara, V., Khashab, M. A., Muthusamy, V. R., Acosta, R. D., Agrawal, D., Bruining, D. H., Eloubeidi, M. A., Fanelli, R. D., Faulx, A. L., Gurudu, S. R., Kothari, S., Lightdale, J. R., Qumseya, B. J., Shaukat, A., Wang, A., Wani, S. B., Yang, J., & DeWitt, J. M. (2017). Adverse events associated with ERCP. *Gastrointestinal Endoscopy, 85*(1), 32–47. https://doi.org/10.1016/j.gie.2016.06.051

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

de Franchis, R., Bosch, J., Garcia-Tsao, G., Reiberger, T., Ripoll, C., & Baveno VII Faculty. (2022). Baveno VII – Renewing consensus in portal hypertension. *Journal of Hepatology, 76*(4), 959–974. https://doi.org/10.1016/j.jhep.2021.12.022

de-Madaria, E., Buxbaum, J. L., Maisonneuve, P., García García de Paredes, A., Zapater, P., Guilabert, L., Vaillo-Rocamora, A., Rodríguez-Gandía, M. Á., Donate-Ortega, J., Lozada-Hernández, E. E., Collazo Moreno, A. J. R., Lira-Aguilar, A., Llovet, L. P., Mehta, R., Tandel, R., Navarro, P., Sánchez-Pardo, A. M., Sánchez-Marin, C., Cobreros, M., … Bolado, F. (2022). Aggressive or moderate fluid resuscitation in acute pancreatitis. *New England Journal of Medicine, 387*(11), 989–1000. https://doi.org/10.1056/NEJMoa2202884

Gardner, T. B., Adler, D. G., Forsmark, C. E., Sauer, B. G., Taylor, J. R., & Whitcomb, D. C. (2020). ACG clinical guideline: Chronic pancreatitis. *American Journal of Gastroenterology, 115*(3), 322–339. https://doi.org/10.14309/ajg.0000000000000535

Health Canada. (2016). *Let's talk about acetaminophen*. https://www.canada.ca/en/health-canada/services/publications/drugs-health-products/let-s-talk-about-acetaminophen.html

Interior Health. (2015). *Laparoscopic cholecystectomy (gallbladder removal) instruction sheet* [828103]. https://www.interiorhealth.ca/sites/default/files/2021-11/828103-Gallbladder.pdf

ISMP Canada. (2017). Acetaminophen: Preventing harm through safe use. *ISMP Canada Safety Bulletin, 17*(4). https://ismpcanada.ca/wp-content/uploads/ISMPCSB2017-04-Acetaminophen.pdf

Johns Hopkins Medicine. (2017). *Liver transplant handbook*. https://www.hopkinsmedicine.org/-/media/transplant/liver-transplant-handbook.pdf

Jophlin, L. L., Singal, A. K., Bataller, R., Wong, R. J., Sauer, B. G., Terrault, N. A., & Shah, V. H. (2024). ACG clinical guideline: Alcohol-associated liver disease. *American Journal of Gastroenterology, 119*(1), 30–54. https://doi.org/10.14309/ajg.0000000000002572

Kamath, P. S., Wiesner, R. H., Malinchoc, M., Kremers, W., Therneau, T. M., Kosberg, C. L., D'Amico, G., Dickson, E. R., & Kim, W. R. (2001). A model to predict survival in patients with end-stage liver disease. *Hepatology, 33*(2), 464–470. https://doi.org/10.1053/jhep.2001.22172

Kim, J., Bajaj, H. S., Ramji, A., Bemeur, C., & Sebastiani, G. (2025). *Diabetes and metabolic dysfunction-associated steatotic liver disease in adults* [Clinical practice guideline, chapter 42]. Diabetes Canada. https://www.diabetes.ca/for-professionals/full-guidelines/chapter-42

Kiriyama, S., Kozaka, K., Takada, T., Strasberg, S. M., Pitt, H. A., Gabata, T., Hata, J., Liau, K.-H., Miura, F., Horiguchi, A., Liu, K.-H., Su, C.-H., Wada, K., Jagannath, P., Itoi, T., Gouma, D. J., Mori, Y., Mukai, S., Giménez, M. E., … Yamamoto, M. (2018). Tokyo Guidelines 2018: Diagnostic criteria and severity grading of acute cholangitis (with videos). *Journal of Hepato-Biliary-Pancreatic Sciences, 25*(1), 17–30. https://doi.org/10.1002/jhbp.512

Kiriyama, S., Takada, T., Strasberg, S. M., Solomkin, J. S., Mayumi, T., Pitt, H. A., Gouma, D. J., Garden, O. J., Büchler, M. W., Yokoe, M., Kimura, Y., Tsuyuguchi, T., Itoi, T., Yoshida, M., Miura, F., Yamashita, Y., Okamoto, K., Gabata, T., Hata, J., … Chen, M.-F. (2012). New diagnostic criteria and severity assessment of acute cholangitis in revised Tokyo guidelines. *Journal of Hepato-Biliary-Pancreatic Sciences, 19*(5), 548–556. https://doi.org/10.1007/s00534-012-0537-3

Kwo, P. Y., Cohen, S. M., & Lim, J. K. (2017). ACG clinical guideline: Evaluation of abnormal liver chemistries. *The American Journal of Gastroenterology, 112*(1), 18–35. https://doi.org/10.1038/ajg.2016.517

Lee, W. M., Larson, A. M., & Stravitz, R. T. (2011). *AASLD position paper: The management of acute liver failure: Update 2011*. American Association for the Study of Liver Diseases. https://www.aasld.org/sites/default/files/2023-03/Acute%20Liver%20Failure%20Update2011.pdf

Lupin Pharma Canada. (2025). *Lupin-Rifaximin (rifaximin tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00081927.PDF

Ontario Health (Trillium Gift of Life Network). (2025). *Ontario's adult referral and listing criteria for liver transplantation* (Version 6.0). https://www.giftoflife.on.ca/resources/pdf/transplant/AdultLiverTxRefListCriteria_EN.pdf

Ontario Poison Centre. (n.d.). *Ontario Poison Centre*. https://www.ontariopoisoncentre.ca/

Osiowy, C., Alvarez, F., Coffin, C. S., Cooper, C. L., Fung, S. K., Ko, H. H., Poulin, S., & van Gennip, J. (2025). The management of chronic hepatitis B: 2025 guidelines update from the Canadian Association for the Study of the Liver and Association of Medical Microbiology and Infectious Disease Canada. *Canadian Liver Journal, 8*(2), 368–440. https://doi.org/10.3138/canlivj-2025-0012-e

Pisano, M., Allievi, N., Gurusamy, K., Borzellino, G., Cimbanassi, S., Boerna, D., Coccolini, F., Tufo, A., Di Martino, M., Leung, J., Sartelli, M., Ceresoli, M., Maier, R. V., Poiasina, E., De Angelis, N., Magnone, S., Fugazzola, P., Paolillo, C., Coimbra, R., … Ansaloni, L. (2020). 2020 World Society of Emergency Surgery updated guidelines for the diagnosis and treatment of acute calculus cholecystitis. *World Journal of Emergency Surgery, 15*(1), Article 61. https://doi.org/10.1186/s13017-020-00336-x

Public Health Agency of Canada. (2021). *Hepatitis C virus (HCV): Screening and testing for health professionals*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/hepatitis-c-screening-testing-health-professionals.html

Public Health Agency of Canada. (2023). *Hepatitis A vaccines: Canadian Immunization Guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-4-active-vaccines/page-6-hepatitis-a-vaccine.html

Public Health Agency of Canada. (2024). *Government of Canada's sexually transmitted and blood-borne infections (STBBI) action plan 2024–2030*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/sexually-transmitted-blood-borne-infections-action-plan-2024-2030.html

Public Health Agency of Canada. (2026). *Hepatitis B vaccines: Canadian Immunization Guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-4-active-vaccines/page-7-hepatitis-b-vaccine.html

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Périnet, S., Williams, A., Campeau, L., Elliott, J., Zhang, F., Yang, Q., Cox, J., Davis, K., Feld, J. J., Klein, M. B., Kronfli, N., Biondi, M. J., Daley, P. K., & Popovic, N. (2025). National hepatitis B and C estimates for 2021: Measuring Canada's progress towards eliminating viral hepatitis as a public health concern. *Canada Communicable Disease Report, 51*(6/7), 223–237. https://doi.org/10.14745/ccdr.v51i67a02

Quinte Health. (2022). *Laparoscopic cholecystectomy (gallbladder removal)* [Form 390]. https://quintehealth.ca/wp-content/uploads/2023/07/Form-390-Laparoscopic-Cholecystectomy.pdf

Rinella, M. E., Lazarus, J. V., Ratziu, V., Francque, S. M., Sanyal, A. J., Kanwal, F., Romero, D., Abdelmalek, M. F., Anstee, Q. M., Arab, J. P., Arrese, M., Bataller, R., Beuers, U., Boursier, J., Bugianesi, E., Byrne, C. D., Castro Narro, G. E., Chowdhury, A., Cortez-Pinto, H., … Newsome, P. N. (2023). A multisociety Delphi consensus statement on new fatty liver disease nomenclature. *Journal of Hepatology, 79*(6), 1542–1556. https://doi.org/10.1016/j.jhep.2023.06.003

Sanis Health. (2015). *Lactulose solution USP* [Prescribing information]. https://pdf.hres.ca/dpd_pm/00031381.PDF

Shah, H., Bilodeau, M., Burak, K. W., Cooper, C., Klein, M., Ramji, A., Smyth, D., Feld, J. J., & Canadian Association for the Study of the Liver. (2018). The management of chronic hepatitis C: 2018 guideline update from the Canadian Association for the Study of the Liver. *CMAJ, 190*(22), E677–E687. https://doi.org/10.1503/cmaj.170453

Shi, Y., Macrae, K., de Groh, M., Thompson, W., & Stockwell, T. (2025). Mortality and hospitalizations fully attributable to alcohol use before versus during the COVID-19 pandemic in Canada. *CMAJ, 197*(4), E87–E95. https://doi.org/10.1503/cmaj.241146

Tenner, S., Vege, S. S., Sheth, S. G., Sauer, B., Yang, A., Conwell, D. L., Yadlapati, R. H., & Gardner, T. B. (2024). American College of Gastroenterology guidelines: Management of acute pancreatitis. *American Journal of Gastroenterology, 119*(3), 419–437. https://doi.org/10.14309/ajg.0000000000002645

University Health Network. (n.d.). *Living liver donor*. https://uhn.ca/Transplant/Living_Donor_Program/Pages/living_liver_donor.aspx

Vilstrup, H., Amodio, P., Bajaj, J., Cordoba, J., Ferenci, P., Mullen, K. D., Weissenborn, K., & Wong, P. (2014). Hepatic encephalopathy in chronic liver disease: 2014 practice guideline by the American Association for the Study of Liver Diseases and the European Association for the Study of the Liver. *Hepatology, 60*(2), 715–735. https://doi.org/10.1002/hep.27210

Wright, W. F. (2016). Cullen sign and Grey Turner sign revisited. *Journal of the American Osteopathic Association, 116*(6), 398–401. https://doi.org/10.7556/jaoa.2016.081

VII Renal, Urologic & Reproductive Health Care

UNIT CLINICAL SCOPE & INTEGRATION

Grounds renal, urologic, and reproductive nursing in Canadian nephrology and SOGC guidance, spanning acute kidney injury (AKI), chronic kidney disease (CKD), hemodialysis and peritoneal dialysis access and exchanges, urinary tract infections, urolithiasis, benign prostatic hyperplasia (BPH), continuous bladder irrigation, and adult breast and reproductive health.

Contents of UNIT VII

Chapter	Chapter Title	Visual Assets	Page
Chapter 27	Acute Kidney Injury and Chronic Kidney Disease	6 Figs • 3 Tbls	p. 791
Chapter 28	Urinary Tract and Prostate Disorders	5 Figs • 4 Tbls	p. 822
Chapter 29	Reproductive and Breast Health in Adult Care	6 Figs • 3 Tbls	p. 852

27 Acute Kidney Injury and Chronic Kidney Disease

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain kidney function and interpret creatinine, eGFR, urea, urine albumin-to-creatinine ratio, urinalysis and urine output in SI units.
2. Recognize and stage acute kidney injury, identify its causes, and provide nursing care and escalation using the CJMM.
3. Describe chronic kidney disease staging and complications, and support measures that slow progression, including medication safety and diet.
4. Care for patients receiving hemodialysis and peritoneal dialysis, including vascular access protection and recognition of peritonitis.
5. Support patients before and after kidney transplant, and discuss conservative kidney management and advance care planning.
6. Describe kidney health in First Nations, Inuit and Métis communities and remote Canada with a distinctions-based, strengths-based lens.
7. Distinguish RN and RPN roles in kidney and dialysis care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4	Clinician; Scholar	Foundations of Practice
3, 5, 6	Educator; Advocate	Foundations of Practice; Ethical Practice
7	Professional; Collaborator	Legal Practice; Collaborative Practice

Introduction

Healthy kidneys do their work without being noticed. They clear wastes, balance water and salts, and help control blood pressure, red cell production and bone health. When they fail, every one of these jobs slips at once. Kidney disease is common in Canada. The Kidney Foundation of Canada reports that chronic kidney disease affects 1 in 10 Canadians, and that the number of people in Canada with it is projected to grow from 4.5 million in 2024 to more than 6.2 million by 2050 (Kidney Foundation of Canada, 2025). In 2024, more than 50,000 people in Canada had end-stage kidney disease (kidney failure), and 30,213 of them were on dialysis (Canadian Institute for Health Information [CIHI], 2025b).

Sudden loss of kidney function is just as common in acute care. In a study of two emergency departments in Vancouver, 10.7% of patients whose creatinine was measured had acute kidney injury, and their median age was 74 (Scheuermeyer et al., 2017). Nurses on every unit care for these patients. The nurse is often the first to notice a urine output that is falling, a weight that is climbing or a medication that should be questioned.

This chapter starts with what the kidneys do and how kidney tests are read in SI units (section 27.1). It then covers acute kidney injury (27.2) and chronic kidney disease (27.3). The second half turns to dialysis and vascular access (27.4), kidney transplant (27.5), and kidney health in Canada, including First Nations, Inuit and Métis communities and conservative kidney management (27.6).

The chapter builds on earlier ones. Scope of practice and the Clinical Judgment Measurement Model (CJMM) are taught in Chapter 1. Fluids, potassium, calcium, phosphate and acid–base balance, including emergency care for high potassium, are in Chapter 3. Sepsis is in Chapter 4, and recognizing deterioration in Chapter 6. Anemia is covered in section 20.2, and diabetes and sick-day medication guidance in Chapter 22. Urinary tract infection, urinary retention and catheters are in Chapter 28.

27.1 Kidney Function and Kidney Tests

What the Kidneys Do

Each kidney holds about a million tiny filtering units called **nephrons** (Figures 27.1 and 27.2). Each nephron has two parts. The **glomerulus** is a knot of capillaries that filters blood, letting water and small molecules pass while keeping blood cells and most proteins in the bloodstream. The **tubule** then reclaims what the body needs and adds wastes to what will leave as urine (National Institute of Diabetes and Digestive and Kidney Diseases [NIDDK], 2018). Almost all of the filtered fluid returns to the blood; only a small fraction becomes urine.



Figure 27.1 A frontal section of the left kidney: the outer cortex, the pyramids of the medulla, and the calyces and renal pelvis that collect urine into the ureter. (credit: Figure 25.8, "Left Kidney," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

The **glomerular filtration rate (GFR)** is the volume of blood plasma the glomeruli filter each minute. It is the main measure of kidney function and is reported in millilitres per minute, adjusted to a standard body surface area (mL/min/1.73 m²) (Kidney Disease: Improving Global Outcomes [KDIGO] CKD Work Group, 2024). When the GFR falls, every job the kidneys do is affected:

- **Clearing wastes:** the kidneys remove urea, creatinine, acids and many drugs. When filtration falls, these build up, and drugs cleared by the kidneys can reach toxic levels.
- **Fluid and electrolytes:** the kidneys keep water, sodium, potassium, calcium and phosphate in balance (NIDDK, 2018). Chapter 3 covers these in depth.
- **Acid–base balance:** the kidneys remove the acid that cells produce every day (NIDDK, 2018), so failing kidneys lead to metabolic acidosis (section 3.7).
- **Blood pressure:** by controlling sodium and water and by releasing hormones, the kidneys help set blood pressure (NIDDK, 2018). Chapter 19 covers hypertension.
- **Red blood cells:** the kidneys release erythropoietin, the hormone that drives red cell production (section 20.1). Damaged kidneys make too little, causing anemia.

- **Bone health:** the kidneys make hormones that help keep bones strong (NIDDK, 2018), and they turn vitamin D into its active form, calcitriol, which bones need (NIDDK, 2021).

These links explain why kidney disease causes fluid overload, high potassium, acidosis, anemia and bone disease, the complications described in sections 27.2 and 27.3.

Kidney Tests

Results are reported in SI units. Reference ranges vary by laboratory, so the nurse compares each result with the range printed on the report and, above all, with the patient's own earlier results.

Creatinine is a waste product of normal muscle activity. The glomeruli filter it, so its blood level rises when the GFR falls. Typical adult ranges are about 35 to 88 µmol/L for females and 62 to 106 µmol/L for males (University of Ottawa, 2022). Because creatinine comes from muscle, a frail person with little muscle can have a "normal" creatinine even when kidney function is reduced (KDIGO CKD Work Group, 2024). A rise from the patient's own baseline matters more than a single value.



Figure 27.2 A nephron and its blood supply. Blood is filtered in the glomerulus, and the tubule then reclaims water and solutes into the peritubular capillaries; what remains flows on as urine. (credit: Figure 25.10, “Blood Flow in the Nephron,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

The **estimated glomerular filtration rate (eGFR)** is calculated by the laboratory from serum creatinine, age and sex, and reported in mL/min/1.73 m² beside the creatinine. KDIGO advises using a validated equation, using the same equation across a region, and not using race in the calculation (KDIGO, 2024a; Levin et al., 2024). Canadian laboratories are moving to the 2021 CKD-EPI equation, which has no race term; Alberta Precision Laboratories, for example, began reporting it on January 20, 2026 (Alberta Precision Laboratories, 2026). Chapter 2, section 2.6, explains why the race term was removed.

Urea is a waste product of protein breakdown, with a typical adult range of about 2.5 to 8.0 mmol/L (University of Ottawa, 2022). It rises when filtration falls, and also with dehydration (section 3.2).

The **urine albumin-to-creatinine ratio (ACR)** measures albumin, a protein that healthy glomeruli hold back, in a random urine sample. It is reported in mg/mmol. Albumin in the urine is called **albuminuria**, and it is an early sign of kidney damage, often present while the eGFR is still normal. KDIGO considers an ACR below 3 mg/mmol normal to mildly increased and asks that a raised result be confirmed on repeat testing (Levin et al., 2024). For people with diabetes, Diabetes Canada uses a lower cut-off of 2.0 mg/mmol and diagnoses diabetic kidney disease from albuminuria only when at least two of three ACRs over at least three months are abnormal. Infection, recent exercise, menstruation and very high glucose or blood pressure can raise a single result (Tobe et al., 2025).

A **urinalysis** uses a dipstick (Figure 27.3) to screen for protein, blood, glucose and concentration, and **microscopy** looks for cells and casts in the urine sediment. Persistent blood or abnormal sediment can mark kidney damage (KDIGO CKD Work Group, 2024). Chapter 28 covers urine specimen collection and dipstick testing.

Urine output is the bedside measure of kidney function. KDIGO uses an output below 0.5 mL/kg per hour for 6 hours as one sign of acute kidney injury, and advises measuring both creatinine and urine output in patients at increased risk (KDIGO Acute Kidney Injury Work Group, 2012). To make that judgment, the nurse needs the patient's weight, an accurate start time and every millilitre recorded: urine measured in a graduated container, never estimated, and catheter drainage emptied and recorded on schedule.



Figure 27.3 Two urine dipsticks: one with colour changes on several pads (left) beside one with little reaction (right). Each pad is compared with the colour chart on the container at the time stated. (credit: "Comp.Urine.Test.Strip" by J3D3/Wikimedia Commons, CC BY-SA 3.0)

Imaging, such as ultrasound, shows kidney size and structure and whether urine flow is blocked; structural abnormalities seen on imaging are one marker of kidney damage (KDIGO CKD Work Group, 2024).

GOING DEEPER

What eGFR Can and Cannot Tell You

Required for RN students; optional for PN students.

The 2021 CKD-EPI equations estimate GFR from creatinine, age and sex without a race term (Inker et al., 2021). An eGFR is still an estimate, and the nurse should know where it misleads.

- **Muscle mass:** creatinine-based eGFR overestimates true GFR in people with sarcopenia, which can lead to drug overdosing (KDIGO CKD Work Group, 2024). Very high muscle mass also makes the estimate less reliable (Tobe et al., 2025).
- **Rapid change:** during acute kidney injury, creatinine is still changing, so a single eGFR can misrepresent kidney function. KDIGO advises adapting drug doses when GFR is not in a steady state, and excluding acute kidney injury before calling a low eGFR chronic (Levin et al., 2024; KDIGO, 2024a).
- **Cystatin C:** this second blood marker is not affected by muscle mass (Parekh et al., 2022). KDIGO recommends an equation using both creatinine and cystatin C when creatinine-based eGFR is less accurate and the result will change care (Levin et al., 2024).
- **Drug dosing:** for most people, creatinine-based eGFR is adequate for dosing drugs cleared by the kidneys. When a drug has a narrow margin between effective and toxic levels, a more accurate measure may be needed (Levin et al., 2024). Some Canadian product monographs still state kidney limits as creatinine clearance, in mL/min (Nora Pharma, 2026), so the pharmacist confirms which measure the monograph uses.

27.2 Acute Kidney Injury

Acute kidney injury (AKI) is a sudden fall in kidney function, over hours to days. KDIGO defines AKI by any one of three findings (KDIGO Acute Kidney Injury Work Group, 2012):

- serum creatinine rises by 26.5 µmol/L or more within 48 hours;
- serum creatinine rises to 1.5 times baseline or more, known or presumed to have happened within the past 7 days;
- urine output stays below 0.5 mL/kg per hour for 6 hours.

Causes

AKI is grouped by where the problem starts (Table 27.1). KDIGO asks that the cause be found whenever possible and warns that labelling every case "prerenal" leads to wrong decisions (KDIGO Acute Kidney Injury Work Group, 2012).

Prerenal AKI means the kidneys are not getting enough blood flow. Causes include bleeding, vomiting, diarrhea, poor intake, low blood pressure, sepsis (Chapter 4) and heart failure (Chapter 18). Some drugs reduce filtration pressure when blood flow is already low. In a large study, people taking a diuretic, an angiotensin-converting enzyme (ACE) inhibitor or an angiotensin receptor blocker (ARB), and a nonsteroidal anti-inflammatory drug (NSAID) together had more AKI, with the highest risk in the first 30 days of the combination (Lapi et al., 2013). In that study, an NSAID taken with only one of the other drugs was not linked to more AKI. Even so, a Canadian NSAID monograph lists dehydration, older age, heart failure and existing kidney disease as conditions that raise kidney risk on their own (Nora Pharma, 2026), so the nurse questions an NSAID in any patient who is volume depleted. Prerenal AKI often reverses when blood flow is restored, but if low flow lasts, the kidney tissue itself is injured.

Intrinsic AKI is damage within the kidney. A common form in hospital is **acute tubular injury**, in which tubule cells are harmed by prolonged low blood flow, sepsis or toxins. A **nephrotoxic** substance is one that can damage the kidneys. Examples include NSAIDs and aminoglycoside antibiotics; KDIGO suggests avoiding aminoglycosides when a less nephrotoxic alternative exists and recommends monitoring drug levels when they are given more than once a day for over 24 hours (KDIGO Acute Kidney Injury Work Group, 2012). Iodinated contrast for computed tomography (CT) is a risk mainly in people with poor kidney function. Canadian radiology guidance considers preventive measures, such as IV fluids, only when the eGFR is below 30 mL/min/1.73 m², says emergency scans should not be delayed while waiting for a creatinine result, and does not recommend routinely stopping drugs before contrast, apart from metformin when the eGFR is below 30 (Macdonald et al., 2022). Inflammation of the glomeruli or of the tissue between the tubules can also cause intrinsic AKI.

Postrenal AKI results from blocked urine flow. Causes include an enlarged prostate, stones, tumours, blood clots and a kinked or blocked catheter. Chapter 28 covers urinary retention and obstruction.

Table 27.1 Prerenal, intrinsic and postrenal acute kidney injury compared (KDIGO Acute Kidney Injury Work Group, 2012; Lapi et al., 2013; Macdonald et al., 2022; Nora Pharma, 2026)

Type	Common causes	Clues	Nursing focus
Prerenal (reduced blood flow to the kidneys)	Bleeding, vomiting, diarrhea, poor intake, low blood pressure, sepsis, heart failure; NSAIDs with ACE inhibitors or ARBs and diuretics	Signs of low fluid volume (section 3.2): falling blood pressure, fast heart rate, dry mouth, weight loss; low, concentrated urine	Report early; accurate intake, output and weight; fluids as prescribed; ask for review of drugs that lower kidney blood flow
Intrinsic (damage within the kidney, such as acute tubular injury)	Prolonged low blood flow or shock, sepsis, nephrotoxic drugs such as aminoglycosides and NSAIDs, contrast in people with very low eGFR, inflammation of the glomeruli or kidney tissue	Rising creatinine; abnormal cells or casts on urine microscopy; output may be low or normal	Prevent further harm: medication review, drug levels as prescribed; watch for fluid overload, high potassium and acidosis
Postrenal (blocked urine flow)	Enlarged prostate, stones, tumours, clots, blocked or kinked catheter, drugs that cause urinary retention	Little or no urine, full bladder on bladder scan, blockage seen on ultrasound	Check catheter and tubing; bladder scan; relieve the blockage as prescribed; measure output closely afterward (Chapter 28)

Recognizing and Staging AKI

KDIGO advises judging each patient's risk by their susceptibilities and exposures, and checking creatinine and urine output in those at higher risk (KDIGO Acute Kidney Injury Work Group, 2012). Susceptibilities include dehydration, older age, chronic kidney

disease, diabetes, cancer, anemia and chronic heart, lung or liver disease. Exposures include sepsis, critical illness, shock, burns, trauma, major surgery, nephrotoxic drugs and contrast. Older adults carry several of these at once; Chapter 8 discusses why.

Recognizing AKI depends on two habits. First, the nurse compares each creatinine with the patient's baseline, looking back through earlier results in the record, because a value inside the reference range can still be a large rise for that person. Second, the nurse converts urine output to mL/kg per hour. For a patient who weighs 70 kg, the KDIGO threshold of 0.5 mL/kg per hour is 35 mL per hour; three hours at 20 mL per hour is a trend worth reporting, even before the 6-hour mark.

Once AKI is present, KDIGO stages it by severity (Table 27.2). The patient is assigned the highest stage that either the creatinine or the urine output reaches.

Table 27.2 KDIGO stages of acute kidney injury in brief (KDIGO Acute Kidney Injury Work Group, 2012)

Stage	Serum creatinine	Urine output
1	1.5 to 1.9 times baseline, or a rise of 26.5 µmol/L or more	Below 0.5 mL/kg per hour for 6 to 12 hours
2	2.0 to 2.9 times baseline	Below 0.5 mL/kg per hour for 12 hours or more
3	3.0 times baseline; or a rise to 353.6 µmol/L or more; or the start of kidney replacement therapy (dialysis); or, in patients under 18, an eGFR below 35 mL/min/1.73 m²	Below 0.3 mL/kg per hour for 24 hours or more, or no urine for 12 hours or more

Oliguria is an abnormally low urine output; **anuria** is little or no urine. Urine output can also stay normal in AKI (KDIGO Acute Kidney Injury Work Group, 2012), so a rising creatinine may be the only early clue. As AKI progresses, the nurse watches for:

- **Fluid overload:** weight gain, swelling, crackles in the lungs, shortness of breath and falling oxygen saturation (Chapter 18).
- **High potassium:** weakness, palpitations or no symptoms before a dangerous rhythm. Section 3.5 covers ECG changes and emergency treatment.
- **Metabolic acidosis:** fast, deep breathing and a low serum bicarbonate (section 3.7).
- **Uremia:** the effects of retained wastes. Reduced appetite, nausea and tiredness are typical uremic symptoms (Levin et al., 2024); severe uremia can cause bleeding, confusion or a drop in alertness (encephalopathy), and inflammation of the sac around the heart (pericarditis) (Bagshaw et al., 2021).

Nursing Care

Nursing care aims to find and treat the cause, prevent further injury, and catch complications early.

Fluid status: the nurse measures intake and output accurately, weighs the patient daily on the same scale at the same time, and assesses blood pressure, heart rate, mucous membranes, edema and lung sounds. When volume is low and the patient is not in shock from bleeding, KDIGO suggests isotonic crystalloids rather than colloids such as albumin to restore volume. It recommends against diuretics to prevent AKI and suggests against them to treat AKI, except to manage fluid overload, and recommends vasopressors together with fluids in shock caused by widened blood vessels (vasomotor shock) (KDIGO Acute Kidney Injury Work Group, 2012; Chapter 6). Because 1 L of water weighs about 1 kg, a gain of more than 1 kg in a day mostly reflects fluid (section 3.2). Once output falls, fluid given can no longer be cleared, so the balance can swing from too little to too much within a day. The nurse totals intake and output at least every shift, compares the totals with the weight, and reports a growing positive balance, new crackles or rising oxygen needs. When overload develops, care may include a diuretic, a fluid limit and sitting the patient upright, each as prescribed.

Medication review: the nurse reviews every drug with the prescriber and pharmacist. Drugs that lower kidney blood flow or are cleared by the kidneys may be held or adjusted. KDIGO's CKD guideline suggests considering a planned, temporary stop of metformin, ACE inhibitors, ARBs and sodium-glucose cotransporter-2 (SGLT2) inhibitors before elective surgery or while an adverse effect is being managed, and warns that failing to restart them can cause harm; when drugs are stopped during an acute illness, a clear restart plan is given to the patient and documented (KDIGO, 2024b; Levin et al., 2024). The nurse holds a drug only as prescribed or as policy allows. Sick-day medication guidance is taught in section 22.6.

Bloodwork and monitoring: creatinine, urea, electrolytes and bicarbonate are repeated as prescribed, and the nurse looks for each new result rather than waiting for it to be called. A potassium that is rising is reported with the patient's heart rhythm and any symptoms; section 3.5 explains when an ECG and cardiac monitoring are needed.

Ruling out obstruction: when output falls, the nurse checks the catheter and tubing for kinks or clots, or uses a bladder scanner if the patient has no catheter (Chapter 28).

Escalation: a falling output, a rising creatinine or potassium, new crackles or new confusion are reported promptly using SBAR (Chapter 6). Any nurse who sees these changes acts and escalates at once. A registered practical nurse (RPN) consults the registered nurse (RN) as the patient's needs change, and calls the rapid response team when criteria are met (Chapter 1, section 1.3).

Urgent dialysis: KDIGO advises starting dialysis urgently when life-threatening fluid, electrolyte or acid–base changes are present, and judging the decision on the whole clinical picture rather than on a single creatinine or urea result (KDIGO Acute Kidney Injury Work Group, 2012). A Canadian-led review describes urgent indications as fluid overload affecting oxygenation, metabolic acidosis with a pH below 7.20 or bicarbonate below 12 mmol/L, potassium of 6.0 mmol/L or higher, and complications of uremia such as bleeding, encephalopathy and pericarditis (Bagshaw et al., 2021). These are weighed against the response to medical treatment: for high potassium, KDIGO notes that once treatment to shift potassium into the cells has been used, only dialysis can remove the excess. Dialysis can also help remove some poisons and drug overdoses that cause acidosis and AKI, such as salicylates, ethylene glycol, methanol and metformin (KDIGO Acute Kidney Injury Work Group, 2012). When dialysis is planned, the nurse prepares the patient as section 27.4 describes.

Recovery: as the kidneys recover, creatinine falls and urine output returns. After a blockage is relieved, some patients pass very large volumes of urine, more than 200 mL per hour for two hours in a row, which can cause dehydration and electrolyte loss; output, weight, blood pressure and electrolytes are checked closely (Khara et al., 2019). Recovery is not the end of the story. About 30% of people who recover from AKI remain at higher risk of chronic kidney disease, cardiovascular disease and death, so KDIGO advises checking kidney function three months after the episode (KDIGO Acute Kidney Injury Work Group, 2012). In the Vancouver study, only 4 of 31 patients sent home with AKI had kidney follow-up arranged in the emergency department (Scheuermeyer et al., 2017). The nurse makes sure the discharge plan says when to repeat bloodwork, which drugs to restart and when, and which over-the-counter products to avoid.

Patient and family teaching: the nurse explains in plain language that the kidneys were injured suddenly, that they often recover, and that the episode leaves them more sensitive. Teaching covers:

- avoiding NSAIDs such as ibuprofen unless the prescriber approves, and checking with a pharmacist before buying any pain, cold or herbal product;
- following the written sick-day plan when vomiting, diarrhea or fever make it hard to keep up fluids (section 22.6);
- keeping the follow-up blood test appointment and bringing an up-to-date medication list to every visit;
- reporting much less urine than usual, new swelling, rapid weight gain or shortness of breath.

CLINICAL SAFETY

Protecting the Kidneys From Medications

Many cases of AKI involve medications, and many are preventable. The nurse:

- **Questions NSAIDs:** a Canadian NSAID product monograph lists the highest kidney risk in people with existing kidney disease, dehydration, heart failure, liver disease or older age, and in those also taking ACE inhibitors, ARBs or diuretics (Nora Pharma, 2026). Choosing Wisely Canada advises against NSAIDs for people with hypertension, heart failure or CKD of any cause, including diabetes (Canadian Society of Nephrology, 2025).
- **Watches the combination:** an NSAID added to a diuretic plus an ACE inhibitor or ARB raises AKI risk most in the first month (Lapi et al., 2013).
- **Checks drug levels:** aminoglycoside levels are drawn on time and results reported before the next dose (KDIGO Acute Kidney Injury Work Group, 2012).
- **Knows the contrast plan:** preventive steps are considered when the eGFR is below 30 mL/min/1.73 m², and metformin may be held (Macdonald et al., 2022).

- **Asks about kidney dosing:** drugs cleared by the kidneys are dosed to kidney function (Levin et al., 2024); the pharmacist is a key partner.
- **Asks about home products:** over-the-counter, dietary and herbal products can harm the kidneys (Levin et al., 2024).
- **Plans the restart:** drugs held during illness need a documented restart plan (KDIGO, 2024b).

CLINICAL JUDGMENT

Only 60 mL in Four Hours

Names and details are fictional; this is a composite story.

Grace Mensah, 79, was admitted to a medical unit last night after three days of vomiting and diarrhea. She takes ramipril and furosemide for heart failure and has been taking ibuprofen from the pharmacy for knee pain. She weighs 60 kg. At 1200, the RPN caring for her totals her urine since 0800: 60 mL.

- **Recognize cues:** 60 mL in 4 hours is 15 mL per hour, or 0.25 mL/kg per hour. Blood pressure is 98/56 mm Hg (her usual is about 130/80), heart rate 108 beats/min, mouth dry. This morning's creatinine is 142 µmol/L (88 µmol/L two months ago), and potassium is 5.4 mmol/L.
- **Analyze cues:** her losses and poor intake point to low blood flow to the kidneys, made worse by three drugs that reduce filtration together. The creatinine is more than 1.5 times her baseline, which meets the definition of AKI.
- **Prioritize hypotheses:** prerenal AKI from volume loss is most likely. Retention must be ruled out, and her potassium could keep rising. The RPN does not wait for the 6-hour mark: the trend is already clear.
- **Generate solutions:** a bladder scan, repeat bloodwork, and a report to the RN and the physician asking for fluid orders and a review of all three drugs.
- **Take action:** the bladder scan shows 70 mL. Because her needs are changing, the RPN consults the RN (Chapter 1, section 1.3), then calls the physician using SBAR. An isotonic IV fluid is prescribed, ibuprofen is stopped, ramipril and furosemide are held, and potassium and creatinine are added to the next blood draw. The RPN starts hourly output and records a daily weight.
- **Evaluate outcomes:** over the next 4 hours, output rises to 40 to 50 mL per hour and blood pressure to 118/70 mm Hg. Potassium is 5.2 mmol/L. The next morning's creatinine is 110 µmol/L, and the team plans when to restart her heart failure drugs.

27.3 Chronic Kidney Disease

Defining and Staging CKD

Chronic kidney disease (CKD) is an abnormality of kidney structure or function that has lasted more than three months and has implications for health (KDIGO CKD Work Group, 2024). Either of the following, present for more than three months, meets the definition:

- **markers of kidney damage,** such as an ACR of 3 mg/mmol or more, abnormal urine sediment, persistent blood in the urine, imaging or biopsy abnormalities, or a past kidney transplant; or
- **a GFR below 60 mL/min/1.73 m².**

KDIGO classifies CKD by cause, GFR category and albuminuria category (KDIGO, 2024a). The GFR categories, in mL/min/1.73 m², are (KDIGO CKD Work Group, 2024):

- **G1:** 90 or more (normal or high)
- **G2:** 60 to 89 (mildly decreased)
- **G3a:** 45 to 59 (mildly to moderately decreased)
- **G3b:** 30 to 44 (moderately to severely decreased)
- **G4:** 15 to 29 (severely decreased)
- **G5:** below 15 (kidney failure)

The albuminuria categories, by ACR, are A1, below 3 mg/mmol (normal to mildly increased); A2, 3 to 30 mg/mmol (moderately increased); and A3, above 30 mg/mmol (severely increased). G1 and G2 count as CKD only when a marker of damage is also

present.

Before a low eGFR or a raised ACR is called chronic, AKI must be ruled out and the finding confirmed after three months (KDIGO, 2024a). A single low result during an acute illness may reflect AKI rather than CKD, which is why repeat testing matters. KDIGO also notes that point-of-care tests for creatinine and urine albumin, once quality-assured, are accurate enough to guide care where laboratory access is limited (KDIGO, 2024a), which matters for rural and remote communities (section 27.6).

The two scales work together. Risk of kidney failure, AKI, heart disease and death climbs as the GFR falls and as albuminuria rises, so a person in G3a with heavy albuminuria may face more risk than a person in G3b with none. KDIGO shows this as a coloured grid from low to very high risk, and notes that the grid shows relative risk; individual risk is estimated with validated tools (KDIGO CKD Work Group, 2024). Diabetes Canada recommends the Kidney Failure Risk Equation and suggests referral to a nephrologist when the five-year risk of kidney failure is 5% or more (Tobe et al., 2025).

Causes in Canada: the Kidney Foundation of Canada reports diabetes as the leading cause of kidney failure, at 36%, based on Canadian registry data for 2011 to 2020 that exclude Quebec (Kidney Foundation of Canada, 2022). It names an aging population and rising rates of diabetes and high blood pressure as drivers of CKD in Canada, and notes that Indigenous peoples in Canada have a higher prevalence of CKD, with faster progression and poorer outcomes at younger ages (Kidney Foundation of Canada, 2025). Section 27.6 discusses the structural causes behind these differences. Other causes include glomerular diseases, which damage the glomeruli, and inherited diseases such as polycystic kidney disease (NIDDK, 2025). Diabetes Canada recommends yearly screening of people with diabetes with an eGFR and an ACR (Tobe et al., 2025).

Complications

As GFR falls, complications build up:

- **Anemia:** failing kidneys make too little erythropoietin (section 20.2). Treatment may include iron and an erythropoiesis-stimulating agent. The aim is not a normal hemoglobin, because using these agents to normalize hemoglobin has not improved survival or cardiovascular outcomes and may cause harm (Canadian Society of Nephrology, 2025). On every skin tone, the nurse looks for pallor where pigment does not hide it, such as the conjunctiva and the lining of the mouth (Pusey-Reid et al., 2023; section 20.2).
- **CKD–mineral and bone disorder (CKD–MBD):** damaged kidneys cannot clear phosphate or make enough active vitamin D (calcitriol). Blood calcium falls, the parathyroid glands release extra parathyroid hormone that draws calcium out of bone, and bones become thin and weak; high phosphate can also harden (calcify) blood vessels (NIDDK, 2021). Section 3.6 covers calcium and phosphate.
- **Metabolic acidosis:** KDIGO suggests considering drug treatment, with or without diet changes, to prevent acidosis in CKD (Levin et al., 2024).
- **High potassium:** reduced excretion and drugs such as ACE inhibitors, ARBs and mineralocorticoid receptor antagonists raise potassium, so potassium is checked when these drugs are started or increased (Tobe et al., 2025). KDIGO notes that a high potassium caused by these drugs can often be managed by lowering the potassium rather than stopping the kidney-protecting drug (Levin et al., 2024).
- **Fluid overload:** edema (Figure 3.1 shows pitting edema), weight gain, high blood pressure and shortness of breath (Chapter 18).
- **Cardiovascular disease:** people with diabetes and CKD have a high risk of heart attack, stroke and heart failure (Tobe et al., 2025).
- **Uremic symptoms:** KDIGO lists fatigue (about 70%) and itch (about 46%) among the most common symptoms in CKD (KDIGO, 2024b), and asks clinicians to check for reduced appetite, nausea and tiredness at each visit (Levin et al., 2024). The nurse asks about symptoms directly, because assessing them can change care, and inspects the skin for dryness and scratch marks (Figure 27.4).

Slowing Progression and Living With CKD

Blood pressure: KDIGO suggests a systolic target below 120 mm Hg, when tolerated, measured with standardized office readings (Levin et al., 2024). Targets are individualized for people who are frail, prone to falls, have dizziness on standing or have a very

limited life expectancy (KDIGO, 2024b). Chapter 19 covers hypertension and accurate measurement.

Kidney-protecting drugs: an ACE inhibitor or an ARB, not both, is started for people with albuminuria, and both KDIGO and Diabetes Canada advise against combining them (Levin et al., 2024; Tobe et al., 2025). SGLT2 inhibitors are recommended for people with type 2 diabetes and CKD with an eGFR of 20 mL/min/1.73 m² or more, and for other adults with CKD who have heavier albuminuria or heart failure (Levin et al., 2024). Diabetes Canada notes that their kidney and heart protection persists at low eGFR, even though their glucose-lowering effect is weaker there (Tobe et al., 2025). For people with type 2 diabetes and persistent albuminuria despite an ACE inhibitor or ARB, a nonsteroidal mineralocorticoid receptor antagonist (finerenone) is suggested when potassium is normal and the eGFR is above 25 (Levin et al., 2024). Diabetes Canada also lists glucagon-like peptide-1 (GLP-1) receptor agonists among kidney-protecting therapies (Tobe et al., 2025; Chapter 22). The Medications box summarizes the nursing points.

Figure 27.4 Uremic frost on the forehead and scalp of a young Black man: fine white crystals left on the skin as sweat evaporates. It is a rare sign of severe, untreated uremia. (credit: "Uremic frost on forehead and scalp of young Afro-Caribbean male" by Fythrion/Wikimedia Commons, CC BY-SA 3.0)

A small early dip in eGFR is expected after an ACE inhibitor, ARB or SGLT2 inhibitor is started. A fall of 30% or more from baseline is larger than expected and calls for a search for causes such as volume depletion, AKI or NSAID use (KDIGO, 2024b). Once started, an SGLT2 inhibitor can usually continue when the eGFR later drops under 20, unless it is not tolerated or dialysis begins (Levin et al., 2024). The nurse reports a large drop rather than stopping a drug on their own.

Lifestyle: KDIGO encourages people with CKD not to use tobacco and to build up to at least 150 minutes of moderate activity a week (Levin et al., 2024). Good glucose management for people with diabetes is covered in Chapter 22.

Diet: a dietitian tailors the plan. KDIGO suggests protein of 0.8 g/kg of body weight per day for adults in G3 to G5, and advises avoiding more than 1.3 g/kg per day in people at risk of progression. It suggests limiting sodium to less than 2 g per day (Levin et al., 2024). KDIGO favours a diet built more on plant foods than on animal foods, with fewer ultra-processed foods, which may help with acidosis, high potassium and high phosphate (KDIGO, 2024b). People with G3 to G5 who have had high potassium may be advised to limit foods rich in readily absorbed potassium, such as processed foods (Levin et al., 2024). Food insecurity can make these changes hard; the nurse asks about access rather than assuming a choice (Chapter 2).

Vaccines: the Canadian Immunization Guide recommends that people with CKD or on dialysis receive all routine vaccines, yearly influenza and COVID-19 vaccines, and hepatitis B and pneumococcal conjugate vaccines. A higher-dose hepatitis B vaccine is used, and antibody levels are checked afterward. For people aged 65 years or over with kidney disease, a respiratory syncytial virus (RSV) vaccine is a particular priority (Public Health Agency of Canada [PHAC], 2026).

Medication safety: people with CKD are more vulnerable to the kidney-damaging effects of drugs. Medications are reviewed at every transition of care, doses are matched to kidney function, and over-the-counter and herbal products are limited (Levin et al., 2024). The nurse teaches the patient to avoid NSAIDs unless the prescriber approves, to tell every pharmacist and prescriber about their kidney disease, and to follow a written sick-day plan (section 22.6).

Self-management and planning ahead: KDIGO describes CKD care as a combined strategy of education, lifestyle, diet and medications (KDIGO, 2024b). The nurse helps the person learn their own numbers (eGFR, ACR and blood pressure), keep a current medication list, and know when to call. As CKD progresses, plans for future care, including the choice between dialysis, transplant and conservative kidney management, should be discussed early and shared with everyone involved (KDIGO, 2024b; sections 27.4 to 27.6). Chapter 10 covers advance care planning.

MEDICATIONS

Drugs Used in Chronic Kidney Disease

No doses are given here; follow the current Canadian product monograph and the prescription.

- **ACE inhibitors (ramipril) and ARBs (candesartan):** check blood pressure, creatinine and potassium within 2 to 4 weeks of starting or increasing the dose. A small creatinine rise is expected; KDIGO advises continuing unless creatinine climbs more than 30% within 4 weeks (Levin et al., 2024). Held on sick days (section 22.6).
- **SGLT2 inhibitors (dapagliflozin, empagliflozin):** teach genital hygiene and to report genital itching or discharge; ketoacidosis is rare but serious (Tobe et al., 2025), and Chapter 22 explains why glucose may be only mildly raised. Held on sick days.
- **Finerenone:** monitor potassium, the main risk (Tobe et al., 2025).
- **Erythropoiesis-stimulating agents (darbepoetin alfa) and iron (iron sucrose IV):** follow hemoglobin and iron results and blood pressure; the aim is not a normal hemoglobin (Canadian Society of Nephrology, 2025).
- **Phosphate binders (sevelamer):** bind phosphate from food, so they are taken with meals; some other oral drugs are given at least 1 hour before or 3 hours after them (Sanofi-aventis Canada, 2026). Monitor phosphate and calcium.
- **Active vitamin D (calcitriol):** monitor calcium and phosphate.
- **Treatment for metabolic acidosis:** when prescribed, monitor bicarbonate so that it does not rise above the normal range (Levin et al., 2024), along with blood pressure and edema.
- **Potassium binders (sodium zirconium cyclosilicate):** lower potassium so that kidney-protecting drugs can often continue (Levin et al., 2024).
- **Diuretics (furosemide):** for fluid overload; monitor weight, blood pressure, potassium and output.

LIFESPAN CONSIDERATIONS

Kidney Disease in Older Adults

- **Older adults:** creatinine-based eGFR overestimates kidney function when muscle mass is low, which can lead to overdosing (KDIGO CKD Work Group, 2024). The nurse treats a "normal" creatinine in a frail older adult with caution and asks the pharmacist to check kidney dosing. KDIGO keeps the same GFR threshold, 60 mL/min/1.73 m², for diagnosing CKD in older adults as in younger adults (KDIGO, 2024a).
- **Drug accumulation:** many drugs cleared by the kidneys, including some opioids and sedatives, build up and can cause confusion and falls (Chapter 8, section 8.5).
- **Blood pressure:** strict lowering can cause dizziness, falls and fractures, so targets are individualized (KDIGO CKD Work Group, 2024). The nurse checks for a drop in blood pressure on standing.
- **AKI risk:** older age is a susceptibility for AKI (KDIGO Acute Kidney Injury Work Group, 2012), and older adults often carry several exposures at once, such as surgery, new drugs and poor intake.
- **Choices about treatment:** for some older adults with kidney failure, conservative kidney management, without dialysis, fits their priorities better (section 27.6). Choices about kidney replacement therapy or conservative care should reflect the person's own priorities (KDIGO CKD Work Group, 2024).
- **Younger adults:** CKD in younger adults can affect school, work and family planning, so referral and education start early.

27.4 Dialysis

When chronic kidney disease reaches kidney failure (section 27.3), the kidneys can no longer clear wastes and extra fluid well enough to sustain life. **Kidney replacement therapy (KRT)** is the term for treatments that take over this work: dialysis or a kidney transplant. Dialysis can also be needed for a short time in acute kidney injury (section 27.2). This section covers how each type of dialysis works, access care and the complications that need quick action.

Choosing Kidney Replacement Therapy

People approaching kidney failure in Canada may be offered several paths:

- **In-centre hemodialysis:** treatment in a hospital or community dialysis unit, usually several times a week.
- **Home hemodialysis:** the patient or a family member, after training, runs the machine at home.

- **Peritoneal dialysis:** treatment at home that uses the lining of the abdomen as the filter.
- **Kidney transplant:** from a living or deceased donor (section 27.5). A **pre-emptive transplant** is done before dialysis is ever needed.
- **Conservative kidney management:** active, planned care without dialysis or transplant (section 27.6).

In-centre hemodialysis is by far the most common choice. The Canadian Organ Replacement Register (CORR), kept by the Canadian Institute for Health Information (CIHI), counted 30,213 people receiving dialysis at the end of 2024 and 19,940 living with a functioning kidney transplant (CIHI, 2025a). These CORR figures exclude Quebec. Of the people on dialysis, 77.7% had in-centre hemodialysis, 11.4% automated peritoneal dialysis, 6.8% continuous ambulatory peritoneal dialysis and 4.1% home hemodialysis. Among people who started KRT in 2024, 76.8% began with in-centre hemodialysis, 19.7% with peritoneal dialysis, 3.1% with a pre-emptive transplant and 0.5% with home hemodialysis (CIHI, 2025a).

Planning ahead matters. In 2024, 28.6% of people who started dialysis had first seen a nephrologist less than 90 days earlier, which CIHI calls late referral (CIHI, 2025a). Late referral leaves little time to weigh options, train for home therapy or create a fistula.

The choice of therapy is a **shared decision**. The kidney team explains what each option involves and what the evidence shows. The patient weighs the options against their own values, health, work, family and home. Written or online decision aids help people compare options side by side (Kidney Supportive Care Research Group [KSCRG], n.d.). Distance matters too, because people in remote communities may have to move to reach dialysis (see the Canadian Context box in section 27.6). The nurse supports these decisions by checking what the patient understands, answering questions within their competence and referring others to the kidney team. Consent and capacity are discussed in Chapter 1, section 1.5.

Hemodialysis and Vascular Access

In **hemodialysis**, blood leaves the body through a vascular access, passes through a filter called a **dialyzer** in the dialysis machine (Figure 27.5), and returns to the body cleaned of wastes and extra fluid (Peterborough Regional Health Centre [PRHC], 2024). Inside the dialyzer, wastes such as urea and potassium move across a thin membrane from the blood into a cleansing fluid called dialysate. Extra water is pulled out of the blood by pressure, a process called **ultrafiltration**. Most people on in-centre hemodialysis have three or more treatments a week, each lasting about 4 hours or longer (PRHC, 2024). Many feel tired afterward, and blood pressure can swing (PRHC, 2024).

Hemodialysis needs a high blood flow, which an ordinary vein cannot supply. There are three types of access (Kidney Foundation of Canada, 2020; Lok et al., 2020):

- **Arteriovenous fistula (AV fistula):** a surgeon joins an artery to a vein, usually in the arm. The extra flow makes the vein larger and thicker so it can take dialysis needles. A fistula uses the person's own vessels, so it has lower rates of infection and clotting and tends to last longer. It usually needs 4 to 6 weeks or more to mature before use.
- **Arteriovenous graft (AV graft):** a tube of synthetic or biological material joins an artery to a vein. Needles are placed in the graft.
- **Central venous catheter (CVC) for dialysis:** a large catheter in a central vein, usually in the neck, that allows high flow. A tunnelled catheter, which travels under the skin before entering the vein, carries a lower infection risk than a non-tunnelled one.

Guidelines favour an AV fistula or graft over a catheter for most people because of the lower infection risk (Lok et al., 2020). Yet most Canadians still start hemodialysis with a catheter: 88.4% in 2024, up from 82.4% in 2015, while fistula use at the start fell from 15.9% to 10.6% (CIHI, 2025a). Because a future fistula depends on healthy arm veins, guidelines advise protecting the veins of people with CKD categories G3 to G5 and avoiding peripherally inserted central catheters (PICCs) and unnecessary blood draws (Lok et al., 2020). The nurse raises this with the team before a PICC is placed in a patient with advanced CKD.

Assessing an AV fistula or graft. Examining the access means looking, feeling and listening (Lok et al., 2020; Salman & Beathard, 2013):

- **Look:** at the access, arm and hand. Swelling, redness, warmth, pus or thin, shiny or ulcerated skin over a bulge are warning signs. A hand that is pale, bluish, cold, numb or painful may mean the access is "stealing" blood from the hand. Colour changes

can look different on darker skin, so the nurse uses natural or other good ambient light rather than fluorescent light, feels for warmth, swelling and tenderness, and compares with the other arm (Pusey-Reid et al., 2023).

- **Feel:** a **thrill** is the buzzing vibration of blood flowing through the access. A normal thrill is soft and continuous. A thrill that is strong in only one spot, or one that has changed, can mean narrowing.
- **Listen:** a **bruit** is the sound of that flow heard with a stethoscope. A normal bruit is low-pitched and continuous, like a soft whoosh. A high-pitched bruit, or one heard only in pulses, suggests narrowing.
- **No thrill and no bruit** suggests the access has clotted. The nurse reports this to the dialysis team or prescriber at once, because a clotted access may be saved if treated quickly.

Figure 27.5 A hemodialysis machine beside a treatment chair. The blood pump moves blood through the dialyzer, and the screen shows pressures, flow and fluid removal. (credit: "Hemodialysis machine INNOVA" by Vitaly Pospelov (Виталий Поспелов) at Russian Wikipedia/Wikimedia Commons, CC BY-SA 3.0)

Protecting the access arm. No blood pressure readings, blood draws or IV starts are done in the arm with a fistula (Health PEI, 2022; Kidney Foundation of Canada, 2020). The same protection applies to a graft arm. The nurse also avoids tight sleeves, tight watches and anything that compresses the arm. Many patients carry a wallet card describing their access. The nurse asks for it, documents the location of the access and makes sure the whole team knows. After two incidents in which an IV was placed in a fistula arm, Health PEI (2022) reminded staff that a dialysis access is for dialysis only, except in a life-threatening emergency.

Caring for a dialysis catheter. A dialysis catheter is a direct line to the heart. Misuse can cause severe bleeding, infection, clots or air embolism (Health PEI, 2022). For this reason, only staff trained and authorized in hemodialysis open or use it, and it is not used for blood work or IV medications on the ward except in a life-threatening emergency. The nurse keeps the dressing dry and intact and does not get the site wet. Fever, chills, or redness, tenderness or drainage at the exit site are reported promptly. Infection prevention for central lines is covered in Chapter 4.

Before and after dialysis. Before a treatment, the nurse weighs the patient on the same scale each time, measures blood pressure on the non-access arm and reports laboratory results as ordered, such as potassium (hyperkalemia is covered in Chapter 3). The nurse confirms with the prescriber or dialysis unit which medications to give or hold before the treatment. Blood pressure drugs taken just before dialysis add to the risk of low blood pressure during treatment (Chou et al., 2017). After the treatment, the nurse:

- weighs the patient and compares the result with the pre-dialysis weight;
- checks blood pressure, including for dizziness on standing, and helps the patient up slowly to prevent a fall;
- checks the needle sites. If a site bleeds, light, direct pressure is held for about 10 minutes. Bleeding that does not stop is reported at once (Kidney Foundation of Canada, 2020);
- watches for headache, nausea or vomiting, dizziness, confusion or agitation during or soon after early treatments. These can signal **dialysis disequilibrium syndrome**, brain swelling caused by rapid removal of urea, which is most likely in a patient's first treatments (Mistry, 2019).

Peritoneal Dialysis

Peritoneal dialysis (PD) uses the **peritoneum**, the thin membrane lining the abdomen, as the filter. A soft catheter is placed through the abdominal wall. Dialysate runs into the abdomen, stays there for a set time (the dwell), and is then drained out along with wastes

and extra fluid. The drained fluid is called **effluent**. Each fill, dwell and drain cycle is an exchange. There are two main methods: (Figure 27.6)

- **Continuous ambulatory peritoneal dialysis (CAPD):** the patient does several manual exchanges by hand through the day.
- **Automated peritoneal dialysis (APD):** a machine called a cycler does exchanges overnight while the patient sleeps.



Figure 27.6 Peritoneal dialysis: sterile dialysate flows through an indwelling catheter into the peritoneal cavity, where water and uremic solutes diffuse across the semipermeable peritoneal membrane before the effluent is drained. (credit: "Peritoneal dialysis" by Manu5 [Scientific Animations]/Wikimedia Commons, CC BY-SA 4.0)

Most dialysate contains glucose to draw water out of the blood. Some of this glucose is absorbed. In one study, people on PD had increases in fat mass and blood sugar measures over time (Law & Davenport, 2021). The nurse therefore watches blood glucose closely in a patient with diabetes, and the dietitian plans energy and protein intake with the patient.

Exit-site care and infection prevention. The catheter's exit site is a door for bacteria. Patients and nurses wash hands thoroughly before and after every exchange (Li et al., 2022). The nurse checks that the dressing is dry and intact each shift, cleans the site as the program directs and applies the prescribed antibiotic cream to the skin around the exit site (Li et al., 2022; The Ottawa Hospital [TOH], 2015). Scabs are left in place, and the catheter is secured against tugging. Patients should not soak the exit site in a bath, because this can cause an exit-site infection and peritonitis (TOH, 2015). Any drainage from the exit site is reported and swabbed. If sterile technique breaks during an exchange, the patient contacts the PD unit right away (Li et al., 2022).

Recognizing peritonitis. PD-related peritonitis is infection of the peritoneum. It is the complication the nurse must not miss. The International Society for Peritoneal Dialysis (ISPD) guideline diagnoses peritonitis when at least two of three criteria are present: abdominal pain or cloudy effluent; an effluent white cell count above 100 per microlitre (0.1×10^9/L) after a dwell of at least 2 hours, with more than half neutrophils; and a positive effluent culture (Li et al., 2022). Fever, chills, nausea, vomiting or diarrhea may also occur (TOH, 2015).

First actions follow the ISPD guideline (Li et al., 2022):

- **Treat cloudy effluent as peritonitis** until it is proven otherwise.

- **Notify the PD unit or nephrologist at once,** and follow the unit's directions for getting an effluent sample to the laboratory quickly. ISPD advises that specimens reach the laboratory within 6 hours.
- **Send effluent** for a Gram stain, a cell count with differential and a culture, with the culture in blood culture bottles.
- **Start antibiotics as soon as specimens are collected,** without waiting for results. Antibiotics are often given into the peritoneal fluid (intraperitoneal), and a patient with mild pain may be treated at home if this can be arranged.
- **Consider peritonitis even if the effluent is clear** when a PD patient has abdominal pain.

Fluid balance on PD. The nurse tracks weight, blood pressure, edema and the volume drained compared with the volume instilled, as the PD program directs. A drain that is much smaller than expected, or rising weight with edema, means fluid is building up and is reported (fluid overload is covered in Chapter 18).

Table 27.3 compares hemodialysis and peritoneal dialysis.

Table 27.3 Hemodialysis and peritoneal dialysis compared (CIHI, 2025a; Kidney Foundation of Canada, 2020; Li et al., 2022; PRHC, 2024; TOH, 2015)

Feature	Hemodialysis	Peritoneal dialysis
How it works	Blood passes through a dialyzer outside the body	Dialysate fills the abdomen; the peritoneum acts as the filter
Access	AV fistula, AV graft or central venous catheter	Soft catheter through the abdominal wall
Where and how often	Most often in a dialysis unit, three or more sessions a week of about 4 hours or longer; home hemodialysis for some	At home every day, by hand through the day (CAPD) or by cycler overnight (APD)
Share of people on dialysis, 2024 (excluding Quebec)	77.7% in-centre and 4.1% home	11.4% APD and 6.8% CAPD
Main infection risk	Catheter-related bloodstream infection; infection at needle sites	Peritonitis; exit-site infection
Key nursing checks	Thrill and bruit; no blood pressure, blood draws or IVs in the access arm; weight and blood pressure before and after	Cloudy effluent and abdominal pain; exit site; drain volumes; blood glucose

PATIENT EDUCATION

Caring for Your Fistula

Your fistula is your lifeline. These steps help it last (Health PEI, 2022; Kidney Foundation of Canada, 2020):

- **Check it every day.** Feel for the buzz (thrill) over your fistula. Tell your kidney team right away if the buzz is gone or feels different.
- **Check your hand.** Report a hand that is cold, a different colour, numb, tingling, swollen or painful.
- **Watch the site.** Report redness, warmth, swelling, pain or bleeding.
- **Protect your arm.** Do not let anyone take your blood pressure, draw blood or start an IV in that arm. Carry your wallet card and show it in every hospital, clinic and lab.
- **Avoid pressure.** Skip tight sleeves and watches. Do not sleep on the arm or keep it bent for long periods.
- **After dialysis,** hold light pressure on each needle site for about 10 minutes, or as your team teaches you. If a site bleeds again at home, hold light pressure for 20 minutes. If it still bleeds, go to the nearest emergency department and tell your kidney team.
- **Speak up.** You are an important member of your own safety team.

GOING DEEPER

Fluid and Electrolyte Shifts During Dialysis

Required for RN students; optional for PN students.

Between hemodialysis sessions, most patients make little or no urine, so the fluid they drink builds up. The weight gained between sessions is called **interdialytic weight gain**. During the next session, ultrafiltration must remove this fluid in a few hours. The faster fluid is pulled from the blood, the harder it is for fluid in the tissues to refill the blood vessels.

When refilling cannot keep up, blood pressure falls. **Intradialytic hypotension** has been defined in research as a lowest systolic pressure below 90 mm Hg in more than 30% of treatments. It is linked with poorer survival and with harmful effects on the heart, brain and gut (Chou et al., 2017). Risk rises with large interdialytic weight gains, high ultrafiltration rates and blood pressure drugs taken before treatment (Chou et al., 2017). This is why teaching about fluid and sodium limits matters, and why the prescriber decides which antihypertensives to hold or time on dialysis days.

Electrolytes shift too. Potassium moves from the blood into dialysate that contains less potassium, so the blood potassium level falls during treatment. Rapid removal of urea can also draw water into the brain, which causes dialysis disequilibrium syndrome (Mistry, 2019).

27.5 Kidney Transplant

For many people with kidney failure, a transplant offers the most freedom from dialysis. Kidney transplants are very successful for most recipients (TOH, n.d.). This section describes how donation works in Canada and what nurses teach and watch for after a transplant.

Donation and Transplant in Canada

A kidney can come from a **living donor**, who gives one of their two kidneys, or a **deceased donor**. Living donors may be related to the recipient, such as a sibling, or unrelated, such as a spouse or friend. In 2020, 26% of kidney transplants in Canada came from living donors, and more than 45% of living donors were not related to the recipient (Kidney Foundation of Canada, 2022). A transplant from a living donor can sometimes be done before dialysis starts, which is a pre-emptive transplant. In 2024, 3.1% of Canadians starting KRT received a pre-emptive transplant (CIHI, 2025a).

Kidneys are the organ transplanted most often in Canada. CIHI reported 3,174 organ transplants of all types in 2025, and 59% of them were kidney transplants (CIHI, 2026). Across all organs, 81% of transplants used organs from deceased donors and 19% from living donors. The 888 deceased donors in 2025 donated after neurological determination of death (62%), after circulatory death not related to medical assistance in dying (MAID) (30%) or after MAID (8%) (CIHI, 2026). MAID is discussed in Chapter 10.

The need is greater than the supply. On December 31, 2025, 4,344 Canadians were on transplant wait-lists for any organ. Of the 678 people removed from wait-lists during 2025, 31% had died while waiting (CIHI, 2026). For adults on dialysis, CIHI reported a median wait of 3.4 years for a deceased-donor kidney in 2023, down from 3.8 years in 2014 (CIHI, 2024). Waits vary widely by province: in 2020, the median ranged from 2 years and 8 months in British Columbia to 7 years and 2 months in Manitoba (Kidney Foundation of Canada, 2022).

Each province and territory has an organ donation organization. In Ontario, Ontario Health (Trillium Gift of Life Network) coordinates organ and tissue donation and transplant services (Ontario Health [Trillium Gift of Life Network], 2026). Ontarians aged 16 or older can register their consent online with their health card in a few minutes. Nurses can encourage people to register and to share their wishes with their families.

Care After Transplant

After surgery, the recipient takes **immunosuppressants** for as long as the kidney works. These drugs lower the immune response so the body does not attack the new kidney. How they work, their adverse effects and the safety precautions they require are covered in section 21.3. Nursing care after transplant centres on five areas.

Watching for rejection. Rejection is an immune attack on the new kidney, which the body sees as foreign tissue (TOH, n.d.). Acute rejection can occur at any time but is most common in the first year. It may or may not cause symptoms and is often found on routine blood work, so keeping every laboratory appointment matters. Chronic rejection develops slowly over time. The Ottawa Hospital (n.d.) teaches recipients to report these possible signs:

- a temperature of 38 °C or above, or symptoms like the flu;
- less urine, darker urine or blood in the urine;
- shortness of breath, sudden weight gain or swelling of the legs or around the eyes;
- pain or tenderness over the new kidney;

- high blood pressure or a rising creatinine.

Small changes in creatinine are normal and can reflect hydration, medications or the timing of the test. The transplant team decides whether a change matters (TOH, n.d.). The nurse reports any of these signs promptly rather than waiting for the next clinic visit. Rejection found early can often be treated, which helps save kidney function.

Preventing and recognizing infection. Immunosuppression raises the risk of infection, and it can also blunt the usual signs, such as fever (section 21.3). The nurse uses strict hand hygiene, assesses wounds and lines closely and teaches the patient to report fever or new symptoms early. Infection prevention is covered in Chapter 4.

Supporting adherence. Missed doses of immunosuppressant raise the risk of rejection. Recipients are taught to take every dose as prescribed, to never run out and to bring a current medication list to every clinic visit (TOH, n.d.). The nurse asks about barriers such as cost, side effects, complex schedules and low mood, and refers to the transplant pharmacist or social worker. Before the patient starts any new drug, including over-the-counter and natural health products, the transplant team or pharmacist checks it for interactions with immunosuppressants (section 21.3).

Lowering cancer risk. Kidney transplant recipients have a much higher rate of skin cancer than the general population (Kidney Disease: Improving Global Outcomes [KDIGO] Transplant Work Group, 2009). The nurse teaches the recipient to limit sun exposure for life, use sunscreen and protective clothing, check their skin and lips regularly and report any new spot.

Lifelong follow-up and emotional care. A transplant is a treatment, not a cure. On average, a kidney from a living donor works for up to about 18 years and one from a deceased donor for up to about 12 years (TOH, n.d.). Recipients need regular blood work and clinic visits for life. Fear of rejection, grief and worry are common. The nurse asks about them and offers the support of the team, including the social worker (TOH, n.d.).

27.6 Kidney Health in Canada and Living Well With CKD

Kidney disease does not affect all communities equally, and kidney care is not equally easy to reach. This section looks at kidney health in First Nations, Inuit and Métis communities and in remote Canada. It then turns to conservative kidney management for people who choose not to have dialysis.

Kidney Disease in First Nations, Inuit and Métis Communities

A distinctions-based approach recognizes that First Nations, Inuit and Métis peoples have their own histories, governance and health priorities (Chapter 2). Findings for one group are not assumed to apply to the others.

The strongest Canadian kidney data describe First Nations adults. In a population-based study in Alberta, adults tested from 2002 to 2008 who were First Nations reached kidney failure at rates two to three times higher than other adults with the same eGFR and albuminuria category (Samuel et al., 2014). First Nations adults in the study were also less likely to have had their urine albumin measured: 53.8% had no measure, compared with 38.5% of other adults. The authors point to gaps in the quality of care and in access to kidney specialists. These patterns are not explained by biology. They reflect structural causes:

- **Diabetes burden,** itself shaped by colonial policies and loss of traditional food systems (Chapter 22).
- **Water and food insecurity** in some communities (Chapter 2).
- **Distance** from kidney specialists, laboratories and dialysis units.
- **Colonialism and systemic racism** in health care, which make relocation for dialysis especially harmful (Trachtenberg & Goldberg, 2021).

Inuit and Métis kidney health deserves its own distinctions-based data. When this chapter cites First Nations data, it does not apply them to Inuit or Métis patients. The nurse asks each patient about their own community and needs.

Community-led work shows what is possible. In Manitoba, the FINISHED project brought point-of-care screening to rural and remote First Nations communities in two Tribal Councils. It was designed with Indigenous leaders and organizations, approved by Band Council Resolutions and run under the First Nations principles of OCAP® (ownership, control, access and possession)

(Harasemiw et al., 2021). Mobile teams measured blood chemistry, glycated hemoglobin (HbA1c), the urine albumin-to-creatinine ratio and blood pressure, and shared the results with each person during counselling the same day. Among the 1,353 adults studied, 44% had a risk of kidney failure at screening. After screening, complete laboratory testing, diabetes treatment and nephrology visits all increased compared with a matched group that was not screened (Harasemiw et al., 2021). Any use of First Nations data follows OCAP® (Chapter 2).

What this means for nursing practice:

- **Test early.** Adults with diabetes or high blood pressure need both eGFR and urine albumin checked (section 27.1). The nurse makes sure the urine test is not the one that gets missed.
- **Explain results.** The nurse explains in plain language what a result means and what happens next, and offers an interpreter when one is wanted.
- **Plan around distance.** The nurse asks where the patient lives, how they travel and who supports them, and links them with Indigenous patient navigators or liaison services where they exist (Chapter 2).
- **Name the barrier, not the person.** A missed appointment often reflects distance, cost or past harm in health care, not a lack of interest.

Culturally safe kidney care means building trust, inviting family and community supports, offering interpreters, including traditional foods in diet planning and respecting traditional healing alongside dialysis or transplant care (Chapter 2).

Conservative Kidney Management and Advance Care Planning

Not everyone with kidney failure chooses dialysis. **Conservative kidney management (CKM)** is planned, comprehensive, person-centred care for kidney failure that does not include dialysis (KSCRG, n.d.). It is an active treatment choice, not a withdrawal of care (Kidney Foundation of Canada, n.d.). The KDIGO 2024 CKD guideline advises telling people with CKD about both kidney replacement therapy and comprehensive conservative care, and supporting conservative management for those who choose not to have kidney replacement therapy (Kidney Disease: Improving Global Outcomes [KDIGO] CKD Work Group, 2024). People may choose CKM because they have other life-limiting illnesses, are not transplant candidates or feel that the burden of dialysis would outweigh its benefits. A nephrologist may raise the option when dialysis is unlikely to help, especially for frail older adults (section 27.3). Age shapes the trade-offs. Among people aged 75 or older on dialysis, CIHI reported unadjusted survival of 72.9% at 1 year and 24.6% at 5 years (CIHI, 2025a). Numbers like these help older adults and families weigh time spent travelling to and receiving dialysis against what matters most to them.

CKM combines kidney care with palliative care principles (KSCRG, n.d.). It includes:

- slowing the loss of kidney function with medications and diet;
- preventing and managing complications;
- treating symptoms such as itch, breathlessness, nausea and fatigue;
- psychosocial, spiritual and family support, and screening for depression;
- advance care planning, including a plan for crises and for the last weeks of life.

The CKM team works with the person's primary care provider and with palliative care services (KSCRG, n.d.). The nurse's part is to ask regularly about symptoms, mood and sleep, to report symptoms that are not controlled, and to make sure the person and family know whom to call in a crisis. The decision belongs to the person, who can change their mind at any time (Kidney Foundation of Canada, n.d.). Some people already on dialysis decide later to stop. That decision follows the same informed, shared process and moves the focus to comfort. The nurse confirms that the person understands the choice and has capacity, or involves the substitute decision-maker (Chapter 1, section 1.5). Advance care planning and end-of-life care are covered in Chapter 10.

CANADIAN CONTEXT

Dialysis Far From Home

Hemodialysis needs a machine, treated water and trained staff several times a week. Many rural and remote communities have no local dialysis unit. People who live there often must move to a city to survive (Trachtenberg & Goldberg, 2021). Moving can split

families, end jobs and cause money problems. It can also leave people far from their community and culture (Trachtenberg & Goldberg, 2021).

In an Alberta survey, 121 people on hemodialysis who lived in remote areas were asked to compare two futures. One was a shorter life at home with their usual supports. The other was a longer life at a referral centre without those supports. On average (median), 6 years of life at home with supports was valued the same as 10 years at the referral centre without them, so participants would give up about 4 years of life to stay where they were. Older participants would give up even more (Tonelli et al., 2015).

Ways to shrink the distance include:

- home dialysis, especially peritoneal dialysis, with training and remote support;
- satellite dialysis units closer to home;
- early referral, so a home option and access can be ready in time;
- considering priority for transplant when local dialysis is not possible (Trachtenberg & Goldberg, 2021).

Nurses help by asking where home is, what matters there and who will support the patient through the change.

SCOPE IN PRACTICE

Dialysis Care and Who Does What

In Ontario, the College of Nurses of Ontario (CNO) frames every nursing activity by authority, competence and context (CNO, 2025; Chapter 1, section 1.3).

- **Authority:** an activity must be within the nurse's legal scope, with an order where one is required.
- **Competence:** dialysis nursing needs education beyond entry to practice. In Ontario, for example, Confederation College's nephrology nursing program admits both registered nurses (RNs) and registered practical nurses (RPNs) and covers hemodialysis and peritoneal dialysis care (Confederation College, n.d.). Without the education a role requires, a nurse does not cannulate an access or run a treatment.
- **Context:** employer policy sets who may start and run hemodialysis, cannulate a fistula or graft and access a dialysis catheter. These tasks are usually limited to staff trained and authorized for hemodialysis (Health PEI, 2022). Employers decide how RNs and RPNs share work in dialysis units, home dialysis programs and medical units. On a medical unit, a nurse who has been taught and is authorized by the employer may do PD exchanges for an admitted patient. A nurse who has not been taught asks for help and makes sure the exchange is not missed.

Some duties belong to every nurse:

- protecting the access arm and assessing the thrill and bruit;
- recognizing cloudy effluent, a lost thrill, bleeding or signs of infection, and escalating at once;
- teaching and supporting the patient.

An RPN who sees a change in the patient's condition consults the RN. Employer policy and the rules of each province or territory shape these roles.

PRACTICE STORY

The Arm With the Thrill

Names and details are fictional; this is a composite story.

Nurse: Teresa Bouchard, RPN. Years in practice: 4. Setting: medical unit, Ontario.

Mr. Lucien Arsenault was 71 and had been admitted with pneumonia. He went to hemodialysis three times a week. At handover I heard "left forearm fistula," and I wrote it at the top of my sheet.

At 0800 a new staff member wheeled the vital signs machine in and reached for his left arm. Mr. Arsenault was drowsy and didn't say a word. I asked her to stop and use his right arm. Then I put my fingers on his left forearm and felt that steady buzz. The thrill was there, and so was the soft whoosh when I listened.

At 1000 his IV came out. The nurse who came to restart it had tried his right arm twice without success, and she began looking at his left hand. I told her about the fistula and showed her the thrill. She hadn't known. Together we called the charge nurse, who arranged for the IV team to try again on the right side.

None of this was anyone's bad intention. The information just wasn't where people looked. I asked Mr. Arsenault for his wallet card, and his wife found it in his coat. I documented the access location and put up the arm sign our unit uses. I added it to the whiteboard and the handover tool, and I told the charge nurse that the fistula needed to be raised at safety huddle.

When Mr. Arsenault was more awake, we talked. He said that at the dialysis unit everyone knows, so he had stopped mentioning it. I asked him to tell every nurse, lab worker and doctor who touched that arm. I also showed his wife how to check the buzz each day. He laughed and said he'd been "promoted to safety officer."

At the huddle the next day, I showed two new staff members how to feel a thrill. It took less than a minute each.

Reflect: What parts of protecting a fistula arm fall within every nurse's scope, and which dialysis tasks need further education and employer authorization? What would you do if a colleague insisted on using the fistula arm in a non-emergency?

Chapter 27 Summary

Introduction

- Chronic kidney disease affects 1 in 10 Canadians, and in 2024 more than 50,000 people in Canada had kidney failure.
- Acute kidney injury is common in acute care, and nurses are often first to notice falling urine output or a medication that should be questioned.

27.1 Kidney Function and Kidney Tests

- Nephrons filter blood and adjust its contents; the GFR is the main measure of kidney function.
- The kidneys clear wastes and drugs, balance fluid, electrolytes and acid, help set blood pressure, and support red cell production and bone health.
- Creatinine depends on muscle mass, so trends from the patient's baseline matter more than single values; eGFR is calculated from creatinine, increasingly with the race-free 2021 CKD-EPI equation.
- The urine ACR detects albuminuria early; Diabetes Canada uses 2.0 mg/mmol for people with diabetes and needs two of three abnormal samples.
- Accurate, timed urine output related to body weight is essential to recognizing AKI.

27.2 Acute Kidney Injury

- KDIGO defines AKI by a creatinine rise of 26.5 µmol/L in 48 hours, a rise to 1.5 times baseline within 7 days, or output below 0.5 mL/kg per hour for 6 hours, and stages it 1 to 3.
- Causes are prerenal (low blood flow), intrinsic (such as acute tubular injury) and postrenal (obstruction); NSAIDs combined with diuretics and ACE inhibitors or ARBs raise risk.
- Nursing care includes accurate intake, output and weights, medication review with the team, ruling out obstruction, and prompt escalation of falling output, high potassium or fluid overload.
- Urgent dialysis is considered for life-threatening fluid overload, acidosis, high potassium or uremic complications, weighed against the response to medical treatment, and for some poisonings.
- Recovery needs a follow-up plan, because many people remain at higher risk of CKD.

27.3 Chronic Kidney Disease

- CKD is an abnormality of kidney structure or function for more than three months, classified by cause, GFR category (G1 to G5) and albuminuria category (A1 to A3).
- Diabetes is the leading cause of kidney failure in Canada; Indigenous peoples face higher rates and worse outcomes for structural reasons (section 27.6).
- Complications include anemia, mineral and bone disorder, acidosis, high potassium, fluid overload, cardiovascular disease, fatigue and itch.
- Progression is slowed with blood pressure control, an ACE inhibitor or ARB, SGLT2 inhibitors and other kidney-protecting drugs, no tobacco, activity, and a dietitian-guided diet lower in sodium.
- People with CKD need vaccines, medication review at every transition, kidney-adjusted doses and avoidance of NSAIDs.

27.4 Dialysis

- Kidney replacement therapy includes in-centre or home hemodialysis, peritoneal dialysis and transplant. Conservative kidney management is another option. Choices are shared decisions.
- At the end of 2024, 30,213 people were on dialysis in Canada outside Quebec, and 77.7% of them had in-centre hemodialysis (CIHI, CORR). Most people still start hemodialysis with a catheter.
- Assess a fistula or graft by looking, feeling for the thrill and listening for the bruit. Loss of both suggests clotting and is reported at once.
- No blood pressure, blood draws or IV starts in the access arm. Dialysis catheters are for dialysis staff only, except in a life-threatening emergency.
- Before and after hemodialysis, check weight and blood pressure, confirm which medications to hold, watch needle sites for bleeding and watch for dialysis disequilibrium.
- In PD, cloudy effluent is treated as peritonitis. Notify the PD unit, send effluent for testing and start antibiotics once specimens are taken.

27.5 Kidney Transplant

- Kidneys made up 59% of the 3,174 organ transplants in Canada in 2025. In 2025, 31% of people removed from wait-lists for any organ had died while waiting.
- Donors may be living (related or unrelated) or deceased. In Ontario, Ontario Health (Trillium Gift of Life Network) coordinates donation, and people aged 16 or older can register online.
- Lifelong immunosuppression prevents rejection (section 21.3). Missed doses raise the risk of rejection, which may cause no symptoms.
- Report fever, less urine, swelling, sudden weight gain, tenderness over the graft or a rising creatinine.
- Teach infection prevention, careful checking of new drugs and lifelong sun protection, because skin cancer is much more common after transplant.

27.6 Kidney Health in Canada and Living Well With CKD

- In Alberta, First Nations adults progressed to kidney failure at two to three times the rate of other adults. The causes are structural: quality of care, access, diabetes burden, water and food insecurity, distance and racism.
- Distinctions-based care does not apply First Nations data to Inuit or Métis people. Use of First Nations data follows OCAP®.
- Community-led screening in Manitoba, under OCAP®, improved testing and specialist care.
- Relocating for dialysis harms people and communities. Home dialysis, satellite units and early referral help.
- Conservative kidney management is active, person-centred care without dialysis. It includes symptom care and advance care planning, and the person can change their mind (Chapter 10).

Key Terms (35)

acute kidney injury (AKI): a sudden fall in kidney function over hours to days, defined by KDIGO by a rise in creatinine or a fall in urine output

acute tubular injury: damage to the kidney tubule cells from prolonged low blood flow, sepsis or toxins; a common form of intrinsic AKI in hospital

albuminuria: albumin in the urine, an early marker of kidney damage; classified by KDIGO as A1, A2 or A3

arteriovenous fistula (AV fistula): a surgical joining of an artery and a vein, usually in the arm, that creates a large, strong vein for hemodialysis needles.

arteriovenous graft (AV graft): a tube of synthetic or biological material that joins an artery to a vein and is used for hemodialysis needles.

bruit: the sound of blood flow through a fistula or graft heard with a stethoscope; normally low-pitched and continuous.

central venous catheter for dialysis: a large catheter in a central vein, usually in the neck, used for hemodialysis and reserved for dialysis staff.

chronic kidney disease (CKD): an abnormality of kidney structure or function lasting more than three months with implications for health, classified by cause, GFR category and albuminuria category

CKD–mineral and bone disorder (CKD–MBD): imbalance of calcium, phosphate, parathyroid hormone and vitamin D in CKD that affects bone and blood vessels

conservative kidney management (CKM): planned, active, person-centred care for kidney failure that does not include dialysis, combining kidney care with palliative care principles.

creatinine: a waste product of muscle activity, filtered by the kidneys; its blood level rises as GFR falls and depends on muscle mass

dialysis disequilibrium syndrome: headache, vomiting, confusion and, in severe cases, seizures caused by brain swelling when urea is removed quickly, most often in early treatments.

dialyzer: the filter in a hemodialysis machine, in which wastes move from the blood across a membrane into dialysate.

effluent: the fluid drained out of the abdomen at the end of a peritoneal dialysis dwell.

erythropoiesis-stimulating agent: a drug that acts like erythropoietin to raise red blood cell production in anemia of CKD

estimated glomerular filtration rate (eGFR): a GFR calculated by the laboratory from serum creatinine, age and sex; in Canada increasingly with the race-free 2021 CKD-EPI equation

glomerular filtration rate (GFR): the volume of plasma filtered by the glomeruli each minute; the main measure of kidney function, reported in mL/min/1.73 m^2

hemodialysis: dialysis in which blood passes through a filter (dialyzer) outside the body to remove wastes and extra fluid, then returns to the body.

interdialytic weight gain: weight gained from fluid between hemodialysis sessions.

intradialytic hypotension: a fall in blood pressure during hemodialysis, linked with rapid fluid removal and with poorer outcomes.

kidney replacement therapy (KRT): treatment that takes over the work of failed kidneys: hemodialysis, peritoneal dialysis or a kidney transplant.

kidney transplant: surgery to place a healthy kidney from a living or deceased donor into a person with kidney failure.

nephron: one of about a million filtering units in each kidney, made up of a glomerulus and a tubule

nephrotoxic: able to damage the kidneys, as some drugs and contrast agents can

oliguria: an abnormally low urine output

peritoneal dialysis (PD): dialysis at home that uses the peritoneum as the filter, with dialysate drained in and out through an abdominal catheter.

peritonitis (PD-related): infection of the peritoneum in a person on peritoneal dialysis, signalled by cloudy effluent and abdominal pain.

postrenal acute kidney injury: AKI caused by blocked outflow of urine

pre-emptive transplant: a kidney transplant done before dialysis has started.

prerenal acute kidney injury: AKI caused by reduced blood flow to the kidneys

rejection: an immune attack on a transplanted organ; acute rejection is most common in the first year and may cause no symptoms.

thrill: the vibration felt over a working fistula or graft; normally soft and continuous.

ultrafiltration: removal of extra water from the blood by pressure during dialysis.

uremia: the effects of wastes retained when the kidneys fail, such as reduced appetite, nausea, fatigue and itch, and in severe cases bleeding, encephalopathy and pericarditis

urine albumin-to-creatinine ratio (ACR): a random urine test, reported in mg/mmol, that measures albumin in the urine and is used to detect and classify kidney damage

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mr. Harjit Gill (Questions 1–6): Mr. Harjit Gill, 81, is on day 2 after surgical repair of a hip fracture on an orthopedic unit. His home medications include ramipril, and ibuprofen was added after surgery for pain. He weighs 70 kg. He has been nauseated and drinking little. Over the last 12 hours his urine output was 300 mL. Blood pressure 102/60 mm Hg (usually about 138/82 mm Hg), heart rate 102 beats/min, respiratory rate 20 breaths/min, temperature 37.4 °C, SpO2 95% on room air. A bladder scan shows 70 mL. Today's results: creatinine 168 µmol/L (82 µmol/L before surgery), potassium 6.1 mmol/L, urea 14.2 mmol/L. His incision is dry, and he rates his pain 3 out of 10 when turning.

1. [CORE] Which findings are most important for the nurse to follow up? Select all that apply.

a. Urine output of 300 mL over the last 12 hours
b. Creatinine of 168 µmol/L, up from 82 µmol/L before surgery
c. Potassium of 6.1 mmol/L
d. Blood pressure of 102/60 mm Hg when his usual reading is about 138/82 mm Hg
e. Pain rated 3 out of 10 when he turns in bed
f. Bladder scan volume of 70 mL
g. Temperature of 37.4 °C

Answer: a, b, c, d — His output is about 0.36 mL/kg per hour, his creatinine has doubled from baseline, his potassium is high and his blood pressure is well below his usual, all cues of acute kidney injury and its complications (a, b, c, d) (section 27.2). Pain of 3 out of 10 on turning (e) is expected and controlled. A bladder scan of 70 mL (f) shows that retention is not the cause. A temperature of 37.4 °C (g) is not a fever and does not change the priority.

2. [CORE] Which explanation best fits Mr. Gill's findings?

a. Urinary retention caused by opioid analgesia, with urine backing up from the bladder into both kidneys
b. Low kidney blood flow from poor intake and a lower blood pressure, worsened by ibuprofen and ramipril
c. Fluid overload from IV fluids given during surgery, diluting his blood and lowering his blood pressure
d. Kidney damage from the iodinated contrast dye that was given for his hip imaging before surgery

Answer: b — Poor intake, a lower blood pressure and two drugs that reduce filtration pressure point to prerenal acute kidney injury (b) (section 27.2). The small bladder scan volume rules out retention (a). Fluid overload (c) would raise weight and cause edema or crackles, not low blood pressure with poor intake. Plain X-ray imaging of a hip fracture does not use iodinated contrast, and nothing in the case suggests he received any (d).

3. [CORE] Which problem should the nurse treat as the highest priority?

a. Risk of a pressure injury from limited movement after hip surgery
b. Risk of constipation from opioid analgesia and reduced activity
c. Risk of delirium related to age, surgery and an unfamiliar setting
d. Risk of a dangerous heart rhythm from the high potassium level

Answer: d — A potassium of 6.1 mmol/L with worsening kidney function can cause a life-threatening rhythm without warning, so it comes first (d) (sections 27.2 and 3.5). Pressure injury (a), constipation (b) and delirium (c) are real risks for an older adult after hip surgery, but none threatens life as quickly.

4. [CORE] Which plan should the nurse propose when reporting to the surgical team?

a. Encourage 3 L of oral fluid today, continue his current medications and repeat the creatinine at his follow-up visit
b. Give the next scheduled ibuprofen dose for pain control and ask the team to review all medications on morning rounds
c. Ask for review of ibuprofen and ramipril, an ECG, repeat electrolytes and creatinine, and hourly urine output monitoring
d. Insert an indwelling urinary catheter now, before calling, so that an exact hourly output is available to report to the team

Answer: c — The plan addresses the likely cause (drugs that reduce kidney blood flow), checks the heart for effects of high potassium and tracks the trend (c) (section 27.2). Forcing a large volume of oral fluid in a nauseated older adult and waiting days (a) delays care. Giving more ibuprofen (b) adds to the injury. A catheter needs a prescription and is not a reason to delay reporting (d).

5. [RN] An ECG shows tall, peaked T waves. The prescriber orders IV calcium gluconate, IV insulin with dextrose, oral sodium zirconium cyclosilicate and IV furosemide. Which should the RN give first?

a. IV calcium gluconate
b. IV insulin with dextrose
c. Oral sodium zirconium cyclosilicate
d. IV furosemide

Answer: a — When high potassium causes ECG changes, IV calcium is given first to protect the heart, although it does not lower the potassium (a) (sections 27.2 and 3.5). Insulin with dextrose (b) shifts potassium into cells and follows calcium. A potassium binder (c) removes potassium more slowly. Furosemide (d) is not a first-line treatment for hyperkalemia and could worsen volume depletion in prerenal kidney injury.

6. [CORE] Which findings 24 hours later best show that Mr. Gill's treatment is working?

a. Urine output 20 mL/h, creatinine 175 µmol/L, potassium 5.6 mmol/L and much less nausea than yesterday
b. Urine output 45 mL/h, creatinine 131 µmol/L, potassium 4.9 mmol/L and blood pressure 126/74 mm Hg
c. Blood pressure 106/62 mm Hg, weight up 2.5 kg since yesterday and new crackles at both lung bases
d. Pain 2 out of 10, potassium 6.0 mmol/L, urine output 25 mL/h and a dry incision

Answer: b — Output above 0.5 mL/kg per hour, a falling creatinine, a normal potassium and a restored blood pressure show recovery (b) (section 27.2). Option a shows worsening kidney function despite less nausea. Weight gain with crackles (c) suggests fluid overload. Better pain control (d) does not offset an unchanged potassium and low output.

7. [CORE] An 88-year-old woman who weighs 44 kg has a serum creatinine of 70 µmol/L. How should the nurse interpret this result?

a. Her kidney function must be normal, because the result is inside the laboratory's reference range

b. Her creatinine is low because she is overhydrated, and her fluid intake should be restricted

c. Low muscle mass can keep creatinine low, so her kidney function may be worse than the result suggests

d. Creatinine does not depend on body size, so the result can be compared directly with a younger adult's

Answer: c — Creatinine comes from muscle, so in a frail person with little muscle a "normal" result can hide reduced kidney function, and eGFR can overestimate it (c) (section 27.1). A result in range (a) does not prove normal function in this case. Nothing suggests overhydration (b). Creatinine does depend on muscle mass (d).

8. [CORE] A patient's urine albumin-to-creatinine ratio is 12 mg/mmol on two tests taken four months apart. How is this albuminuria classified by KDIGO?

a. A1, normal to mildly increased

b. A2, moderately increased

c. A3, severely increased

d. Not albuminuria, because the eGFR has not been reported

Answer: b — An ACR of 3 to 30 mg/mmol is category A2, moderately increased (b) (section 27.3). A1 (a) is below 3 mg/mmol, and A3 (c) is above 30 mg/mmol. Albuminuria is classified on its own, whatever the eGFR (d).

9. [CORE] Which action by the nurse supports an accurate assessment of urine output in a patient at risk of acute kidney injury?

a. Measuring each voiding in a graduated container, noting the time, and relating output to current weight

b. Estimating the volume in the urinal by eye and recording a rounded total to the nearest 100 mL at shift end

c. Recording only the voidings that the patient reports, so that the patient is not disturbed overnight

d. Emptying the catheter bag only when it is full, so that one large volume can be recorded for the shift

Answer: a — AKI is judged by output per kilogram per hour over time, so each volume must be measured, timed and related to the patient's weight (a) (section 27.1). Estimating by eye (b), relying on reports (c) and emptying the bag only when full (d) all make the hourly trend impossible to judge.

10. [CORE] A 76-year-old man has passed no urine for 8 hours. He has lower abdominal discomfort, and the bladder scan shows 850 mL. Which type of acute kidney injury is most likely if his creatinine is rising?

a. Prerenal, from reduced blood flow to the kidneys

b. Intrinsic, from acute tubular injury

c. Intrinsic, from inflammation of the glomeruli

d. Postrenal, from blocked outflow of urine

Answer: d — A full bladder with no urine passed points to obstruction below the kidneys (d) (section 27.2). Prerenal injury (a) comes from low blood flow and would not fill the bladder. Acute tubular injury (b) and glomerular inflammation (c) are causes within the kidney, and neither explains 850 mL of retained urine.

11. [CORE] Which finding meets the KDIGO definition of acute kidney injury?

a. Creatinine rising from 80 to 98 µmol/L over 2 weeks in an outpatient

b. Urine output of 0.6 mL/kg per hour for 8 hours after surgery

c. Creatinine rising from 80 to 110 µmol/L within 36 hours

d. Urea of 9.0 mmol/L in a patient with a normal creatinine

Answer: c — A rise of 26.5 µmol/L or more within 48 hours meets the definition; this rise is 30 µmol/L in 36 hours (c) (section 27.2). Option a is an 18 µmol/L rise, about 1.2 times baseline, over two weeks, which meets neither creatinine criterion. An output of 0.6 mL/kg per hour (b) is above the 0.5 threshold. Urea alone (d) is not a KDIGO criterion.

12. [CORE] An RPN is caring for a patient on day 1 after bowel surgery. Urine output has been 10 mL per hour for 3 hours, and a new potassium result is 6.3 mmol/L. What should the RPN do?

a. Assess the patient, then report at once to the RN and the surgical team using SBAR

b. Wait until 6 hours of low output have passed so that the KDIGO definition is met before reporting

c. Document the findings and pass them on at the end of the shift, because the patient was stable this morning

d. Encourage the patient to drink more fluids and recheck the output in 4 hours before reporting anyone

Answer: a — Every nurse who notices deterioration acts at once and escalates; the RPN assesses, reports using SBAR and consults the RN as the patient's needs change (a) (section 27.2; Chapter 1, section 1.3). Waiting for a definition (b) or until shift end (c) delays treatment of a dangerous potassium. Oral fluids (d) may be unsafe after bowel surgery and do not address the risk.

13. [CORE] A patient with an eGFR of 25 mL/min/1.73 m² is booked for an elective CT scan with IV iodinated contrast. Which statement is consistent with Canadian radiology guidance?

a. Contrast must never be given to anyone whose eGFR is below 60 mL/min/1.73 m², even in an emergency

b. All of the patient's ACE inhibitors and diuretics must be stopped before any contrast scan

c. Creatinine must be rechecked routinely after every contrast scan, for every patient, whatever their eGFR

d. The team considers preventive steps, such as IV fluids, because the eGFR is below 30 mL/min/1.73 m²

Answer: d — Canadian guidance considers prevention only when the eGFR is below 30 mL/min/1.73 m², which applies here (d) (section 27.2). It does not forbid contrast at an eGFR below 60 (a), does not recommend routinely stopping drugs other than metformin at an eGFR below 30 (b), and does not require routine follow-up creatinine tests (c).

14. [CORE] Which patients have a higher risk of acute kidney injury? Select all that apply.

a. A 70-year-old taking furosemide and ramipril who starts ibuprofen for back pain

b. A patient receiving an aminoglycoside antibiotic for several days

c. A patient with severe diarrhea and poor intake for three days

d. A healthy 30-year-old who takes acetaminophen at the recommended dose for a headache

e. A patient with sepsis and low blood pressure

f. A patient with chronic kidney disease scheduled for major surgery

Answer: a, b, c, e, f — An NSAID added to a diuretic and an ACE inhibitor (a), aminoglycosides (b), volume loss (c), sepsis with low blood pressure (e) and chronic kidney disease with major surgery (f) are all KDIGO exposures or susceptibilities (section 27.2). A healthy young adult taking acetaminophen as directed (d) has no added kidney risk from the evidence presented.

15. [CORE] A patient has an eGFR of 52 mL/min/1.73 m² on two tests taken four months apart. How is this GFR category classified?

a. G2, mildly decreased

b. G3a, mildly to moderately decreased

c. G3b, moderately to severely decreased

d. Acute kidney injury, because the eGFR is below 60

Answer: b — An eGFR of 45 to 59 mL/min/1.73 m² for more than three months is category G3a (b) (section 27.3). G2 (a) is 60 to 89, and G3b (c) is 30 to 44. A stable result over four months is chronic, not acute (d).

16. [CORE] Two weeks after starting ramipril, a patient's creatinine has risen from 120 to 138 µmol/L, and potassium is 5.0 mmol/L. What does the nurse understand about this result?

a. The drug must be stopped at once, because any rise in creatinine after starting it means kidney injury

b. The patient should double the dose to protect the kidneys more strongly

c. A small rise is expected; ramipril usually continues unless creatinine rises more than 30% in 4 weeks

d. The potassium result means a potassium binder must be started before the next ramipril dose is given

Answer: c — The rise is 15%, an expected effect of ACE inhibitors; KDIGO advises continuing unless the rise exceeds 30% within 4 weeks (c) (section 27.3). Stopping (a) would lose the kidney protection. Patients never change a dose on their own (b). A potassium of 5.0 mmol/L does not on its own call for a binder (d).

17. [CORE] The nurse teaches a patient with CKD G3b about diet. Which statement shows understanding?

a. "I'll keep my sodium under 2 g a day and choose more plant foods and fewer processed foods."

b. "I should eat as much protein as I can every day, because extra protein helps my kidneys heal."

c. "I need to avoid all fruits and vegetables, because every one of them is high in potassium."

d. "I can use as much table salt as I like, as long as I drink extra water every day."

Answer: a — KDIGO suggests sodium below 2 g a day, plant-based foods and fewer ultra-processed foods, and a dietitian tailors the plan (a) (section 27.3). High protein intake (b) is avoided in people at risk of progression. Plant foods are not banned (c); potassium advice is individualized. KDIGO suggests limiting sodium to below 2 g a day whatever the fluid intake, so drinking extra water does not make unlimited salt safe (d).

18. [CORE] An RPN on a medical unit is caring for a patient with CKD G4. The patient becomes short of breath, with crackles in both lungs, SpO2 89% on room air and a weight 3 kg higher than yesterday. What should the RPN do first?

a. Give the next scheduled diuretic dose early, because the patient clearly has fluid overload and needs it now

b. Restrict the patient's fluids for the rest of the day and reassess the breathing at the end of the shift

c. Document the weight gain and ask the dietitian to review the patient's sodium intake tomorrow

d. Stay with the patient, sit them upright, and call the RN and the physician or rapid response team

Answer: d — Acute shortness of breath with low saturation is deterioration; the RPN acts at once, supports breathing and escalates, and the RPN consults the RN as the patient's needs change (d) (section 27.3; Chapter 6). Giving a dose early (a) needs a prescriber's direction. Fluid restriction alone with delayed reassessment (b) and a dietitian referral (c) do not address an emergency.

19. [RN] A patient's baseline creatinine is 90 µmol/L. Three days after a cardiac arrest, it is 280 µmol/L, and urine output has been 0.4 mL/kg per hour for the last 10 hours. What is the KDIGO stage?

a. Stage 1, because the urine output has been low for less than 12 hours

b. Stage 2, because the creatinine is about twice the baseline value

c. Stage 3, because the creatinine is more than 3.0 times baseline

d. The stage cannot be assigned until 24 hours of urine output are available

Answer: c — 280 ÷ 90 is about 3.1 times baseline, which meets stage 3; the patient is assigned the highest stage reached by either criterion (c) (section 27.2). The urine output alone meets stage 1 (a), but the creatinine criterion is higher. Option b miscalculates the ratio. Staging does not require 24 hours of output (d).

20. [RN] Which finding in a patient with acute kidney injury is an urgent indication to discuss starting dialysis?

a. Potassium of 6.4 mmol/L that persists after shifting treatment and a potassium binder

b. Creatinine of 410 µmol/L in an alert patient with good urine output, clear lungs and normal electrolytes

c. Urea of 22 mmol/L with mild nausea that settles with an antiemetic

d. Urine output of 0.4 mL/kg per hour for 7 hours with stable vital signs, clear lungs and normal potassium

Answer: a — Potassium of 6.0 mmol/L or higher that persists despite medical treatment, including shifting treatment and a binder, is an urgent indication (a) (section 27.2). KDIGO advises against starting dialysis on a single creatinine (b) or urea (c) value alone, and low output (d) without fluid overload, acidosis or uremic complications is not an urgent indication.

Case: Daniel Osei (Questions 21–24): Daniel Osei, 58, has done continuous ambulatory peritoneal dialysis (CAPD) at home for 14 months. He has type 2 diabetes. A practical nurse (PN) from home care visits for a scheduled diabetes check. Daniel says his belly has ached since last night, and the bag he drained this morning looks "milky, like you can't read through it." His temperature is 37.9 °C, heart rate 96, blood pressure 132/78 mm Hg. His capillary blood glucose is 11.2 mmol/L. He says that four days ago his cat jumped onto the table during an exchange and brushed the tubing, but "nothing seemed wrong," so he did not call anyone. The exit site is dry, with no drainage.

21. [CORE] Which finding should the nurse recognize as the most important cue?

a. A capillary blood glucose of 11.2 mmol/L in a person who has type 2 diabetes and uses glucose-containing dialysate

b. A heart rate of 96 and a blood pressure of 132/78 mm Hg measured while he is sitting at home

c. Cloudy drained fluid together with abdominal pain that began last night

d. A dry exit site with no drainage and no change since the home care nurse's last visit

Answer: c — Cloudy effluent with abdominal pain meets the clinical criterion for PD-related peritonitis, and the ISPD guideline says cloudy effluent is treated as peritonitis until proven otherwise (section 27.4, Peritoneal Dialysis). A glucose of 11.2 mmol/L (a) is worth noting, because dialysate glucose is absorbed and infection raises glucose, but it is not the main cue. A heart rate of 96 (b) is a little high and fits infection, but on its own it does not identify the problem. A dry exit site (d) is reassuring and makes an exit-site infection less likely. It does not rule out peritonitis.

22. [CORE] What should the nurse do first?

a. Call the PD unit or nephrologist now, and keep the drained fluid for testing as the unit directs

b. Have him drain and discard the cloudy bag, do a fresh exchange and phone the clinic if the next bag is also cloudy

c. Encourage oral fluids and rest, give acetaminophen for the pain and recheck the effluent at tomorrow's visit

d. Teach him to clean the exit site twice a day and arrange for the home care team to check it again in 2 days

Answer: a — Cloudy effluent is presumed to be peritonitis. The PD team is notified at once so effluent can be sent for a Gram stain, a cell count with differential and a culture, and antibiotics can start (section 27.4). Discarding the bag and waiting for the next one (b) delays diagnosis and loses the specimen. Fluids, rest and acetaminophen with a recheck tomorrow (c) let a serious infection progress and can mask fever. Exit-site cleaning (d) does not treat infection of the peritoneum, and the exit site looks healthy.

23. [CORE] The PD nurse arranges for testing. Which statement by Daniel shows he understands the plan?

a. "I'll hold off on antibiotics until the lab confirms which germ is growing, so I get the right one."

b. "Because the fluid is cloudy, they'll probably need to take my catheter out today to clear the infection."

c. "The fluid will clear up once my blood sugar is back under control, so I need to watch my diet."

d. "Once they take a sample of my drained fluid, the antibiotics start right away, before the results are back."

Answer: d — The ISPD guideline starts antibiotics as soon as effluent specimens are collected, without waiting for results (section 27.4). Waiting for culture results (a) delays treatment of a serious infection. Catheter removal (b) is not the first step; it is considered when peritonitis does not respond to appropriate antibiotics. Blood glucose control (c) matters but does not clear an infection.

24. [CORE] Daniel asks how to prevent another episode. Which teaching should the nurse give?

a. "Soak in a warm bath each evening to keep the skin around the exit site clean and soft."

b. "Wash your hands before and after each exchange and after touching your cat, and call the PD unit at once if the tubing is touched."

c. "Gently pull off any crust at the exit site each day so bacteria cannot hide underneath it."

d. "You only need to call the PD unit if your temperature goes above 39 °C, because a little cloudiness in the drained bag is common and usually clears on its own."

Answer: b — The ISPD guideline stresses careful hand washing before and after exchanges and after handling pets, and tells patients to contact their dialysis centre right away after a possible contamination (section 27.4). Soaking the exit site in a bath (a) can cause exit-site infection and peritonitis. Crusts are not pulled off (c). Cloudy effluent is never normal and needs a call whether or not there is fever (d).

25. [CORE] The nurse assesses a newly admitted patient's right forearm AV fistula, which was used for dialysis yesterday. Which finding is expected?

a. A high-pitched bruit heard only in short pulses, with a strong thrill felt in a single small spot

b. A low-pitched, continuous whooshing bruit with a soft vibration felt along the access

c. No vibration over the access, with a firm, cord-like vein and a faint pulse below the fistula

d. A cool, pale right hand with numb fingertips that improves when the arm hangs down

Answer: b — A normal fistula has a soft, continuous thrill and a low-pitched, continuous bruit (section 27.4, Hemodialysis and Vascular Access). A high-pitched, pulsing bruit and a localized strong thrill (a) suggest narrowing. A missing thrill with a firm vein (c) suggests clotting. A cool, pale, numb hand (d) suggests the access is stealing blood from the hand and is reported.

26. [CORE] A patient has a left forearm AV fistula. A student nurse plans to take the patient's blood pressure on the left arm because the right arm is bruised from yesterday's blood work. What should the nurse tell the student?

a. "The left arm is fine today, because the fistula is in the forearm and the cuff goes on the upper arm."

b. "Use the left arm, but inflate the cuff slowly and only partly so that the fistula is not damaged."

c. "Use the right arm with the cuff away from the bruise, or another limb as policy allows. Never use the fistula arm."

d. "Ask the patient which arm they prefer, because both arms are equally safe for a single reading."

Answer: c — No blood pressure readings, blood draws or IV starts are done in the arm with a fistula (section 27.4). Bruising is not a reason to use the access arm; the nurse uses the other arm or another suitable limb as agency policy allows. Using the fistula arm (a, b), whatever the cuff position or speed of inflation, risks damaging or clotting the access. The patient's preference (d) does not override access protection.

27. [CORE] At 0600, the nurse cannot feel a thrill or hear a bruit over a patient's left arm AV graft. Both were present at 2200. What should the nurse do?

a. Report the finding to the dialysis team or prescriber now, because the graft may have clotted

b. Apply a warm compress for 20 minutes and recheck the thrill at the next scheduled assessment

c. Gently massage along the graft for several minutes to restart the flow, then document the result in the chart

d. Raise the arm on a pillow and recheck at 1000, before the scheduled dialysis run

Answer: a — Loss of thrill and bruit suggests the access has clotted. Prompt reporting gives the best chance of restoring flow before the next treatment (section 27.4). Warm compresses (b), massage (c) and waiting until a later check (d) delay treatment, and massage could dislodge a clot.

28. [CORE] A patient returns to the medical unit after hemodialysis. Which finding needs the nurse's action first?

a. The patient feels tired and wants to sleep until lunch

b. The patient's weight is 2.1 kg less than before the treatment

c. The patient asks when the dietitian will visit to talk about fluid limits

d. Bright red blood is soaking through the dressing over a needle site

Answer: d — Bleeding from a needle site needs light, direct pressure right away, and bleeding that does not stop is reported (section 27.4). Fatigue after dialysis (a) is common. A weight loss after treatment (b) reflects fluid removed by ultrafiltration and is expected. The dietitian question (c) is important but not urgent.

29. [CORE] A patient receives hemodialysis at 0900. At 0800 the nurse is due to give an antihypertensive medication. What should the nurse do?

a. Give the medication on time, because skipping a dose could make blood pressure rise during dialysis

b. Give half the dose now and the rest after dialysis to balance the risks

c. Check with the prescriber or dialysis unit whether to give or hold the medication before dialysis

d. Hold the medication without telling anyone, because all medications are held on dialysis days

Answer: c — Blood pressure drugs taken just before dialysis add to the risk of low blood pressure during treatment. The prescriber decides which drugs to give or hold on dialysis days (section 27.4). Giving it automatically (a) ignores this risk. The nurse never changes a dose without an order (b). Holding it without a prescriber decision or communication (d) is unsafe, and not every medication is held.

30. [CORE] A patient with kidney failure asks how peritoneal dialysis differs from hemodialysis. Which response is accurate?

a. "Peritoneal dialysis is done at home every day. The lining of your abdomen is the filter, and fluid flows in and out through a catheter."

b. "Peritoneal dialysis cleans your blood through a machine at the hospital two times a week, using needles placed in a fistula in your arm."

c. "Peritoneal dialysis removes fluid only. You would still need hemodialysis once a week to clear wastes."

d. "Peritoneal dialysis is only used for a few weeks after acute kidney injury. It is not a long-term option."

Answer: a — PD uses the peritoneum as the filter. Exchanges are done at home every day, by hand (CAPD) or by cycler overnight (APD) (section 27.4). In-centre treatment through a fistula (b) describes hemodialysis. PD removes both wastes and fluid (c). PD is a long-term home therapy, used by about 18% of people on dialysis in 2024 (CORR figures excluding Quebec) (d).

31. [CORE] A patient with a tunnelled dialysis catheter in the right internal jugular vein needs blood work and an IV antibiotic. The peripheral veins are difficult. Which action is appropriate?

a. Draw the blood and connect the antibiotic through the dialysis catheter, using sterile technique

b. Flush the dialysis catheter with saline before and after each use so it can serve as the main IV line

c. Ask the dialysis unit to remove the catheter so a peripherally inserted central catheter can be placed in the arm

d. Seek peripheral access or other help, following agency policy, and leave the dialysis catheter for dialysis staff only

Answer: d — A dialysis catheter is for dialysis only and is used only by trained, authorized staff, except in a life-threatening emergency, because of the risk of infection, bleeding, clots and air embolism (section 27.4). Using it for routine care (a, b) breaks this rule. Removing the dialysis access (c) is not appropriate, and PICCs are avoided in people with advanced CKD to protect veins for a future fistula.

32. [CORE] A patient had a kidney transplant 1 year ago. Which teaching about skin protection should the nurse give?

a. "Your skin cancer risk returns to normal after the first year, so using sunscreen on summer holidays is enough from now on."

b. "Limit sun exposure for life, use sunscreen and protective clothing, and report any new spot on your skin or lips."

c. "Tanning beds are safer than the sun, so use one if you want a tan before your trip."

d. "Skin checks are needed only if a family member has had skin cancer in the past."

Answer: b — Kidney transplant recipients have a much higher rate of skin cancer than the general population. They are taught to limit sun exposure for life, use ultraviolet protection, check their skin and lips and report new lesions (section 27.5). The risk does not return to normal after a year (a). Tanning beds are another source of ultraviolet light (c). The risk applies to every recipient, not just those with a family history (d).

33. [CORE] A man who had a kidney transplant 6 months ago says, "I feel great, so sometimes I skip my evening immunosuppressant." Which response is best?

a. "That's fine as long as you never miss your morning dose."

b. "Ask your family doctor to switch you to once-a-month dosing."

c. "Feeling well means your new kidney has fully accepted your body, so you can stop the medication after talking to your pharmacist."

d. "Missing doses can trigger rejection even when you feel well. What makes the evening dose hard to take?"

Answer: d — Rejection may cause no symptoms. Missed immunosuppressant doses can trigger it, so the nurse explains the risk and explores barriers to adherence (section 27.5). Skipping evening doses (a) and stopping the medication (c) both risk rejection. Dosing decisions belong to the transplant team, and the suggested change (b) is not an option.

34. [CORE] Which statement about conservative kidney management (CKM) is accurate?

a. CKM is active, planned care that treats symptoms and slows kidney decline without dialysis, and the person can change their decision

b. CKM means stopping all kidney care, blood work and medications so that the person can be discharged home with comfort measures only

c. CKM is offered only to people who have been on dialysis for at least a year and are no longer benefiting

d. CKM is chosen by the nephrologist when dialysis is unavailable, and the family cannot ask to change the plan

Answer: a — CKM is an active treatment choice. It includes slowing kidney decline, managing complications and symptoms, psychosocial support and advance care planning, and the person can change their mind (section 27.6). It is not a withdrawal of care (b). It can be chosen by people who have never had dialysis (c). It is a shared, person-centred decision, not one imposed by the nephrologist (d).

35. [CORE] Which statement best reflects a distinctions-based, structural understanding of kidney failure among First Nations adults?

a. First Nations people have a genetic tendency toward kidney failure, so screening and earlier treatment in the community are not likely to change outcomes.

b. In Alberta, First Nations adults had more kidney failure and less urine albumin testing, which the authors linked to quality of care and specialist access.

c. Kidney data from First Nations studies can be applied directly to Inuit and Métis patients, because the causes and the health systems involved are the same.

d. Higher rates of kidney failure in First Nations communities are mainly due to people choosing not to attend clinic visits or follow treatment plans.

Answer: b — The Alberta study found progression rates two to three times higher and less albumin testing among First Nations adults, and the authors point to quality of care and specialist access. These are structural causes, not biology (section 27.6). A genetic explanation (a) treats race as biology. Distinctions-based care does not apply First Nations data to Inuit or Métis people (c). Blaming individual choices (d) ignores structural causes such as distance and systemic racism.

36. [CORE] An RPN on a medical unit is assigned a patient on peritoneal dialysis who needs an exchange at 1400. The RPN has never been taught to do PD exchanges. What should the RPN do?

a. Do the exchange by following the steps printed on the dialysate bag, then document it

b. Ask the patient to do the exchange alone, because patients on home PD are trained to do their own exchanges every day

c. Tell the charge nurse now and ask for a nurse who is competent and authorized to do the exchange on time

d. Skip the 1400 exchange and ask the night nurse to add extra dialysate time to make up for it

Answer: c — Under CNO's framework, the nurse needs competence as well as authority. An RPN who has not been taught does not do the exchange alone. The RPN asks for help in good time and makes sure the treatment is not missed (section 27.6, Scope in Practice). Following printed steps (a) does not give competence. A patient who is acutely ill may not be able to do their own exchange safely, and agency policy decides whether they can (b). Skipping an exchange or changing the prescription (d) is unsafe.

37. [CORE] The nurse is teaching a patient who has a new AV fistula how to care for it. Which instructions should the nurse include? Select all that apply.

a. Check for the buzz (thrill) over the fistula every day

b. Do not wear tight watches or sleeves on the fistula arm

c. Allow blood to be drawn from the fistula arm if the veins in the other arm are hard to find

d. Avoid sleeping on the fistula arm

e. Report redness, warmth, swelling, pain, bleeding or a change in the thrill

f. After dialysis, hold light pressure on each needle site for about 10 minutes, or as your team teaches

g. Keep the fistula arm bent for long periods to rest the vessels

Answer: a, b, d, e, f — Daily thrill checks (a), avoiding tight clothing or watches (b), not sleeping on the arm (d), reporting warning signs (e) and holding light pressure after dialysis (f) all protect the fistula (section 27.4, Patient Education box). Blood draws in the fistula arm (c) are not allowed. Keeping the arm bent for long periods (g) is to be avoided.

38. [RN] A patient on hemodialysis gained 4.5 kg since the last treatment and took his usual antihypertensive before arriving. Ninety minutes into dialysis, his blood pressure falls from 148/86 to 84/50 mm Hg, and he has leg cramps and nausea. Which explanation best fits these findings?

a. Fluid is being removed from the blood faster than it can refill from the tissues, made worse by the antihypertensive

b. Potassium is rising quickly as it moves from the dialysate into the blood, which lowers blood pressure

c. Urea is moving from the dialysate into the blood, which pulls fluid into the brain and lowers pressure

d. The dialyzer is removing red blood cells with the fluid, which causes sudden anemia and a drop in pressure

Answer: a — A large interdialytic weight gain requires fast ultrafiltration. When refilling of the blood vessels cannot keep up, blood pressure falls, and antihypertensives taken before treatment add to the risk (section 27.4, Going Deeper box). Potassium moves out of the blood into dialysate, so its level falls (b). Urea moves out of the blood, not in (c), and dialysis disequilibrium causes neurologic symptoms, not this picture. The dialyzer membrane does not remove red blood cells (d).

39. [RN] Which group of findings 5 months after a kidney transplant most strongly suggests rejection and needs prompt reporting to the transplant team?

a. Mild hand tremor, a craving for sweets and a small increase in appetite since the last clinic visit

b. A runny nose and sneezing for 2 days, with normal temperature, urine output and blood pressure

c. Rising creatinine, less urine, a 2 kg weight gain over 3 days and tenderness over the transplanted kidney

d. A creatinine that is 3 micromol/L higher than last week, with no other change in symptoms or output

Answer: c — Rising creatinine, less urine, sudden weight gain and tenderness over the graft are signs the Ottawa Hospital teaches recipients to report as possible rejection (section 27.5). Tremor and appetite changes (a) may be drug adverse effects (section 21.3) but do not suggest rejection. Cold symptoms with normal findings (b) are less concerning, although infection is still watched closely. A very small change in creatinine (d) can reflect hydration, medications or test timing, and the transplant team judges its meaning.

40. [RN] An 86-year-old woman with kidney failure, heart failure and frailty chooses conservative kidney management. Her son says, "So we're just giving up on her." Which response by the nurse is best?

a. "Dialysis would not help her at her age, so there is nothing else the team can offer."

b. "This is active care. We will keep treating her symptoms, slow her kidney decline, plan ahead with her and support you. She can change her mind."

c. "I understand how you feel. I will ask the nephrologist to arrange dialysis for tomorrow so that the whole family can feel better about the plan."

d. "She has made her decision, so the family will not be part of her care planning from now on."

Answer: b — CKM is planned, active, person-centred care. It continues measures to slow decline, manages symptoms, includes advance care planning and family support, and the person may change the decision (section 27.6). Saying nothing more can be offered (a) is inaccurate and takes away hope. Starting dialysis against the patient's informed choice (c) ignores her autonomy and capacity (Chapter 1, section 1.5). Excluding the family (d) contradicts the supportive, family-centred nature of CKM, within the limits of the patient's privacy wishes.

References

Alberta Precision Laboratories. (2026, January 19). *Estimated glomerular filtration rate (eGFR) calculation update for adult patients* [Laboratory bulletin]. https://albertahealthservices.ca/assets/wf/lab/if-lab-hp-bulletin-2026-01-19-estimated-glomerular-filtration-rate-egfr-calculation-update-for-adult-patients.pdf

Bagshaw, S. M., Hoste, E. A., & Wald, R. (2021). When should we start renal-replacement therapy in critically ill patients with acute kidney injury: Do we finally have the answer? *Critical Care, 25*, Article 179. https://doi.org/10.1186/s13054-021-03600-x

Canadian Institute for Health Information. (2024, December 18). *Annual statistics on organ replacement in Canada, 2014 to 2023*. https://www.cihi.ca/en/annual-statistics-on-organ-replacement-in-canada-2014-to-2023

Canadian Institute for Health Information. (2025a, December 18). *Annual statistics on renal replacement therapy in Canada, 2015 to 2024*. https://www.cihi.ca/en/annual-statistics-on-renal-replacement-therapy-in-canada-2015-to-2024

Canadian Institute for Health Information. (2025b, December 18). *Renal replacement therapy in Canada: CORR annual statistics, 2015 to 2024*. https://www.cihi.ca/en/node/10981

Canadian Institute for Health Information. (2026, June 4). *Summary statistics on organ transplants, wait-lists and donors*. https://www.cihi.ca/en/summary-statistics-on-organ-transplants-wait-lists-and-donors

Canadian Society of Nephrology. (2025). *Nephrology* [Choosing Wisely Canada recommendations]. Choosing Wisely Canada. https://choosingwiselycanada.org/recommendation/nephrology/

Chou, J. A., Kalantar-Zadeh, K., & Mathew, A. T. (2017). A brief review of intradialytic hypotension with a focus on survival. *Seminars in Dialysis, 30*(6), 473–480. https://doi.org/10.1111/sdi.12627

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

Confederation College. (n.d.). *Nephrology nursing* [Program description]. Retrieved October 26, 2026, from https://confederationcollege.ca/program/nephrology-nursing

Harasemiw, O., Ferguson, T., Lavallee, B., McLeod, L., Chartrand, C., Rigatto, C., Tangri, N., Dart, A., & Komenda, P. (2021). Impact of point-of-care screening for hypertension, diabetes and progression of chronic kidney disease in rural Manitoba Indigenous communities. *CMAJ, 193*(28), E1076–E1084. https://doi.org/10.1503/cmaj.201731

Health PEI. (2022). *Protecting central line/fistula access in hemodialysis patients: A shared responsibility* [Safer practice notice]. https://src.healthpei.ca/sites/src.healthpei.ca/files/Quality%20and%20Patient%20Safety/Safer%20Practice%20Notices/Safer%20Practice%20Notice%20Dialysis%20Fistulas%20-%20-%202022-11-01.pdf

Inker, L. A., Eneanya, N. D., Coresh, J., Tighiouart, H., Wang, D., Sang, Y., Crews, D. C., Doria, A., Estrella, M. M., Froissart, M., Grams, M. E., Greene, T., Grubb, A., Gudnason, V., Gutiérrez, O. M., Kalil, R., Karger, A. B., Mauer, M., Navis, G., … Levey, A. S. (2021). New creatinine- and cystatin C–based equations to estimate GFR without race. *New England Journal of Medicine, 385*(19), 1737–1749. https://doi.org/10.1056/NEJMoa2102953

Khara, S., Hashemzehi, T., & Batura, D. (2019). Post-obstructive diuresis: A complication of urinary retention. *British Journal of Hospital Medicine, 80*(7), C103–C105. https://doi.org/10.12968/hmed.2019.80.7.c103

Kidney Disease: Improving Global Outcomes (KDIGO) Transplant Work Group. (2009). KDIGO clinical practice guideline for the care of kidney transplant recipients. *American Journal of Transplantation, 9*(Suppl. 3), S1–S155. https://doi.org/10.1111/j.1600-6143.2009.02834.x

Kidney Disease: Improving Global Outcomes Acute Kidney Injury Work Group. (2012). KDIGO clinical practice guideline for acute kidney injury. *Kidney International Supplements, 2*(1), 1–138. https://doi.org/10.1038/kisup.2012.1

Kidney Disease: Improving Global Outcomes CKD Work Group. (2024). KDIGO 2024 clinical practice guideline for the evaluation and management of chronic kidney disease. *Kidney International, 105*(4S), S117–S314. https://doi.org/10.1016/j.kint.2023.10.018

Kidney Disease: Improving Global Outcomes. (2024a). *KDIGO 2024 CKD guideline: Top 10 takeaways for nephrologists: Evaluation*. https://kdigo.org/wp-content/uploads/2024/03/KDIGO-2024-CKD-Guideline-Top-10-Takeaways-for-Nephrologists-Evaluation.pdf

Kidney Disease: Improving Global Outcomes. (2024b). *KDIGO 2024 CKD guideline: Top 10 takeaways for nephrologists: Management*. https://kdigo.org/wp-content/uploads/2024/03/KDIGO-2024-CKD-Guideline-Top-10-Takeaways-for-Nephrologists-Management.pdf

Kidney Foundation of Canada. (2020). *AV fistula* [Patient information sheet]. https://rein.ca/files/av-fistula.pdf

Kidney Foundation of Canada. (2022). *Facing the facts 2022*. https://kidney.ca/KFOC/media/images/PDFs/Facing-the-Facts-2022.pdf

Kidney Foundation of Canada. (2025, November 18). *Global kidney disease data a wake-up call for Canada* [News release]. https://kidney.ca/news-and-media/news/global-kidney-disease-data-a-wake-up-call-for-canada

Kidney Foundation of Canada. (n.d.). *Conservative kidney management*. Retrieved October 26, 2026, from https://kidney.ca/en/kidney-health/treatment-options/conservative-kidney-management

Kidney Supportive Care Research Group. (n.d.). *Conservative kidney management pathway*. University of Alberta. Retrieved October 26, 2026, from https://sites.ualberta.ca/~kscrg/ckm-pathway.html

Lapi, F., Azoulay, L., Yin, H., Nessim, S. J., & Suissa, S. (2013). Concurrent use of diuretics, angiotensin converting enzyme inhibitors, and angiotensin receptor blockers with non-steroidal anti-inflammatory drugs and risk of acute kidney injury: Nested case-control study. *BMJ, 346*, Article e8525. https://doi.org/10.1136/bmj.e8525

Law, S., & Davenport, A. (2021). The effect of glucose absorption from peritoneal dialysates on changes in lipid profiles in prevalent peritoneal dialysis patients. *Peritoneal Dialysis International, 41*(1), 115–117. https://doi.org/10.1177/0896860820903655

Levin, A., Ahmed, S. B., Carrero, J. J., Foster, B., Francis, A., Hall, R. K., Herrington, W. G., Hill, G., Inker, L. A., Kazancıoğlu, R., Lamb, E., Lin, P., Madero, M., McIntyre, N., Morrow, K., Roberts, G., Sabanayagam, D., Schaeffner, E., Shlipak, M., … Stevens, P. E. (2024). Executive summary of the KDIGO 2024 clinical practice guideline for the evaluation and management of chronic kidney disease: Known knowns and known unknowns. *Kidney International, 105*(4), 684–701. https://doi.org/10.1016/j.kint.2023.10.016

Li, P. K.-T., Chow, K. M., Cho, Y., Fan, S., Figueiredo, A. E., Harris, T., Kanjanabuch, T., Kim, Y.-L., Madero, M., Malyszko, J., Mehrotra, R., Okpechi, I. G., Perl, J., Piraino, B., Runnegar, N., Teitelbaum, I., Wong, J. K.-W., Yu, X., & Johnson, D. W. (2022). ISPD peritonitis guideline recommendations: 2022 update on prevention and treatment. *Peritoneal Dialysis International, 42*(2), 110–153. https://doi.org/10.1177/08968608221080586

Lok, C. E., Huber, T. S., Lee, T., Shenoy, S., Yevzlin, A. S., Abreo, K., Allon, M., Asif, A., Astor, B. C., Glickman, M. H., Graham, J., Moist, L. M., Rajan, D. K., Roberts, C., Vachharajani, T. J., & Valentini, R. P. (2020). KDOQI clinical practice guideline for vascular access: 2019 update. *American Journal of Kidney Diseases, 75*(4, Suppl. 2), S1–S164. https://doi.org/10.1053/j.ajkd.2019.12.001

Macdonald, D. B., Hurrell, C. D., Costa, A. F., McInnes, M. D. F., O'Malley, M., Barrett, B. J., Brown, P. A., Clark, E. G., Hadjivassiliou, A., Kirkpatrick, I. D. C., Rempel, J., Jeon, P., & Hiremath, S. (2022). Canadian Association of Radiologists guidance on contrast-associated acute kidney injury. *Canadian Journal of Kidney Health and Disease, 9*, Article 20543581221097455. https://doi.org/10.1177/20543581221097455

Mistry, K. (2019). Dialysis disequilibrium syndrome prevention and management. *International Journal of Nephrology and Renovascular Disease, 12*, 69–77. https://doi.org/10.2147/IJNRD.S165925

National Institute of Diabetes and Digestive and Kidney Diseases. (2018). *Your kidneys & how they work*. https://www.niddk.nih.gov/health-information/kidney-disease/kidneys-how-they-work

National Institute of Diabetes and Digestive and Kidney Diseases. (2021). *Mineral & bone disorder in chronic kidney disease*. https://www.niddk.nih.gov/health-information/kidney-disease/mineral-bone-disorder

National Institute of Diabetes and Digestive and Kidney Diseases. (2025). *Causes of chronic kidney disease in adults*. https://www.niddk.nih.gov/health-information/kidney-disease/chronic-kidney-disease-ckd/causes

Nora Pharma. (2026). *NRA-Celecoxib (celecoxib capsules)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00084512.PDF

Ontario Health (Trillium Gift of Life Network). (2026). *About*. beadonor.ca. https://beadonor.ca/about

Parekh, R. S., Perl, J., Auguste, B., & Sood, M. M. (2022). Elimination of race in estimates of kidney function to provide unbiased clinical management in Canada. *CMAJ, 194*(11), E421–E423. https://doi.org/10.1503/cmaj.210838

Peterborough Regional Health Centre. (2024). *In-centre hemodialysis* [Patient information pamphlet]. https://prhc.on.ca/wp-content/uploads/2024/05/In-Centre-Hemodialysis-Pamphlet-2024.pdf

Public Health Agency of Canada. (2026). *Immunization of persons with chronic diseases: Canadian immunization guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-3-vaccination-specific-populations/page-7-immunization-persons-with-chronic-diseases.html

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Salman, L., & Beathard, G. (2013). Interventional nephrology: Physical examination as a tool for surveillance for the hemodialysis arteriovenous access. *Clinical Journal of the American Society of Nephrology, 8*(7), 1220–1227. https://doi.org/10.2215/CJN.00740113

Samuel, S. M., Palacios-Derflingher, L., Tonelli, M., Manns, B., Crowshoe, L., Ahmed, S. B., Jun, M., Saad, N., & Hemmelgarn, B. R. (2014). Association between First Nations ethnicity and progression to kidney failure by presence and severity of albuminuria. *CMAJ, 186*(2), E86–E94. https://doi.org/10.1503/cmaj.130776

Sanofi-aventis Canada. (2026). *Renvela (sevelamer carbonate tablets)* [Product monograph]. https://www.sanofi.com/assets/countries/canada/docs/products/prescription-products/renvela-en.pdf

Scheuermeyer, F. X., Grafstein, E., Rowe, B., Cheyne, J., Grunau, B., Bradford, A., & Levin, A. (2017). The clinical epidemiology and 30-day outcomes of emergency department patients with acute kidney injury. *Canadian Journal of Kidney Health and Disease, 4*, Article 2054358117703985. https://doi.org/10.1177/2054358117703985

The Ottawa Hospital. (2015). *Peritoneal dialysis (PD) catheter care* (Policy No. 01492). Kidney Care Resources, Canadian Society of Nephrology. https://kcr.csnscn.ca/search-by-keyword/peritoneal-dialysis/peritoneal-dialysis-catheter/522-ottawa-peritoneal-dialysis-catheter-care-july-2015/file

The Ottawa Hospital. (n.d.). *Understanding rejection* [Kidney post-transplant clinic]. Retrieved October 26, 2026, from https://www.ottawahospital.on.ca/en/departments-and-services/nephrology/renal-transplant/kidney-post-transplant-clinic/understanding

Tobe, S. W., Bajaj, H. S., Tangri, N., Jain, R., Pham, T., Beaudin, V., & McFarlane, P. (2025). Chronic kidney disease in diabetes: A clinical practice guideline. *Canadian Journal of Diabetes, 49*(2), 73–86.e14. https://doi.org/10.1016/j.jcjd.2025.01.004

Tonelli, M., Molzahn, A., Wiebe, N., Davison, S. N., Gill, J. S., Hemmelgarn, B. R., Manns, B. J., Pannu, N., Pelletier, R., Thompson, S., & Klarenbach, S. W. (2015). Relocation of remote dwellers living with hemodialysis: A time trade-off survey. *Nephrology Dialysis Transplantation, 30*(10), 1767–1773. https://doi.org/10.1093/ndt/gfv112

Trachtenberg, A. J., & Goldberg, A. (2021). Patients with kidney failure who cannot access dialysis in rural and remote areas of Canada should be prioritized for kidney transplantation. *CMAJ, 193*(46), E1772–E1773. https://doi.org/10.1503/cmaj.211020

University of Ottawa, Faculty of Medicine. (2022). *Lab results* [Reference values]. https://www.uottawa.ca/faculty-medicine/sites/g/files/bhrskd401/files/2023-05/Lab%20Results%20Template_2022_final-EN.pdf

28 Urinary Tract and Prostate Disorders

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Recognize and care for adults with urinary tract infection, collect urine specimens correctly, and distinguish asymptomatic bacteriuria from infection.
2. Use urinary catheters only when indicated, insert and maintain them safely, and prevent catheter-associated urinary tract infection.
3. Assess and manage urinary retention and the main types of urinary incontinence, with attention to dignity and older adults.
4. Care for adults with kidney stones, including recognizing an obstructed, infected kidney as an emergency.
5. Care for patients with benign prostatic hyperplasia and after prostate surgery, including continuous bladder irrigation and TUR syndrome, using the CJMM.
6. Support patients with prostate and bladder cancer, including informed discussion of PSA screening and urostomy care.
7. Distinguish RN and RPN roles in catheter, bladder and prostate care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 5	Clinician; Scholar	Foundations of Practice
3, 6	Educator; Advocate	Foundations of Practice; Ethical Practice
7	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

Problems of the bladder and urinary tract are among the most common reasons adults need nursing care, and among the most private. A person with burning on urination, leakage when they cough, a bladder that will not empty or blood in the urine may feel embarrassed to say so. A calm, matter-of-fact approach from the nurse makes it easier for the person to describe what is happening and to accept care. These problems are common: about 3.3 million Canadians, roughly 10% of the population, experience urinary incontinence (Bettez et al., 2012).

Much of the nursing work in this area is about doing less, wisely. Urine tests sent without symptoms lead to antibiotics that do not help and can harm, and urinary catheters left in without a reason cause infection and injury (Choosing Wisely Canada, n.d.; Leis & Soong, 2019). Nurses decide when to collect specimens, notice catheters that are no longer needed and check that the bladder still empties after a catheter comes out.

This chapter is the book's home for the lower urinary tract and the prostate. Section 28.1 covers urinary tract infection, urine specimens and asymptomatic bacteriuria. Section 28.2 covers urinary catheters and the prevention of catheter-associated infection, and section 28.3 covers urinary retention and incontinence. The second half of the chapter turns to kidney stones (28.4), benign prostatic hyperplasia and prostate surgery (28.5), and prostate and bladder cancer (28.6).

The chapter builds on earlier ones. Scope of practice and the Clinical Judgment Measurement Model (CJMM) are taught in Chapter 1 (sections 1.3 and 1.4), and dignity and cultural safety in Chapter 2. Kidney tests, including the basic urinalysis, are in section 27.1. Specimen collection, infection prevention and control (IPAC), antimicrobial stewardship and sepsis are in Chapter 4, pain in Chapter 5, postoperative urinary retention in section 7.6, delirium in section 8.2 and skin care for incontinence in Chapter 35.

28.1 Urinary Tract Infection

Cystitis, Pyelonephritis and Urosepsis

A **urinary tract infection (UTI)** is an infection anywhere from the urethra to the kidneys. Most begin when bacteria from the skin around the urethra travel up into the bladder. **Cystitis** is infection limited to the bladder. **Pyelonephritis** is infection that has reached the kidney, and it is more serious. When a UTI triggers a dysregulated body-wide response with organ dysfunction, the result is **urosepsis**, sepsis that starts in the urinary tract (section 4.6).

Women have a short urethra that opens near the vagina and anus, so bacteria reach the bladder more easily. Other risks the nurse looks for are an indwelling catheter, for which the length of time it stays in is the most important risk factor (Patel et al., 2023); a bladder that does not empty fully, which is linked with repeated UTIs and pyelonephritis (Stoffel et al., 2016); a blockage such as a kidney stone (section 28.4); and recent urologic procedures.

Cystitis usually causes new **dysuria** (pain or burning on urination), urgency, frequency, pain above the pubic bone, and sometimes visible blood in the urine or new incontinence (Choosing Wisely Canada, n.d.). Pyelonephritis adds signs that infection has moved beyond the bladder: fever, shaking chills (rigors) and pain in the flank or tenderness at the **costovertebral angle**, the angle between the lowest rib and the spine. A 2025 guideline from the Infectious Diseases Society of America (IDSA) now classes a UTI as complicated mainly by bedside signs that infection has spread beyond the bladder, especially fever (Trautner et al., 2025).

Fever with rigors, a rising heart rate or breathing rate, low blood pressure, new confusion or falling urine output in a patient with a suspected UTI may signal urosepsis. Any nurse who notices these changes acts at once and escalates through the early warning and rapid response process (sections 6.1 and 6.2) while sepsis care begins (section 4.6). Fever and flank pain in a person with a known kidney stone may mean an obstructed, infected kidney, which needs urgent drainage (section 28.4).

Specimens and Urinalysis

A **midstream clean-catch specimen** is urine collected from the middle of the stream after the genital area has been cleaned, so that the first urine flushes skin bacteria away. The nurse teaches the person to wash their hands, open the sterile container without touching the inside and clean the area with the towelettes provided. A person with a vulva sits well back on the toilet, holds the labia apart throughout and wipes with downward strokes. A person with a penis retracts the foreskin, if present, and wipes the head of the penis. The person starts to void into the toilet, moves the container into the stream without stopping, fills it one-half to three-quarters full and finishes in the toilet. The specimen is labelled with two identifiers and the date and time, and reaches the laboratory within 2 hours or is refrigerated (Alberta Precision Laboratories [APL], 2020).

For a patient with an indwelling catheter, the nurse disinfects the sampling port, briefly clamps the tubing below it and withdraws urine with a sterile syringe. Urine for culture is never taken from the drainage bag, and the closed system is not opened (APL, n.d.; Centers for Disease Control and Prevention [CDC], 2009). Section 4.2 shows the steps.

A urine dipstick gives quick results for several chemicals; two relate to infection. **Leukocyte esterase** is an enzyme from white blood cells, so a positive result suggests **pyuria**, white blood cells in the urine. **Nitrites** form when certain bacteria convert nitrate in the urine. A dipstick is better at ruling infection out than in: in adults without added risk factors, negative nitrite and leukocyte esterase results reliably exclude UTI (Corcos et al., 2017). A positive result proves little, because pyuria and bacteria are also common without infection (Nicolle et al., 2019). Choosing Wisely Canada advises against using a dipstick or urinalysis to diagnose UTI in long-term care, and its clinician leads recommend that dipsticks not be used for adults older than 65 in any setting (Choosing Wisely Canada, n.d.; Leis et al., n.d.).

A **urine culture** identifies the organism, counts it and tests which antibiotics work against it (susceptibility). It is collected before the first antibiotic dose. Choosing Wisely Canada advises against sending a culture routinely on admission or at a check-up, or because urine looks dark, cloudy or smells strong, or because behaviour has changed. A culture is sent when minimum criteria for UTI are met. For a long-term care resident without a catheter, these are new dysuria alone, or two or more new findings from a short list: fever, urgency, frequency, suprapubic pain, flank pain, visible blood in the urine or new incontinence (Choosing Wisely Canada, n.d.; Leis et al., n.d.).

GOING DEEPER

Reading a Urinalysis and Urine Culture

Required for RN students; optional for PN students.

Reference ranges vary by laboratory. One Canadian laboratory lists nitrite and leukocyte esterase as normally negative, specific gravity as 1.005 to 1.030 and pH as 5.0 to 8.0 (University Health Network [UHN], n.d.).

- **Nitrite:** Some gram-negative bacteria convert nitrate from the diet into nitrite, but only if urine has stayed in the bladder for about 4 hours or more. *Enterococcus* and some other organisms do not make nitrite, so a negative result does not exclude bacteriuria (Beaumont Hospital, 2023).
- **Leukocyte esterase:** a marker of pyuria. Pyuria occurs with both infection and asymptomatic bacteriuria, so it cannot tell them apart (Nicolle et al., 2019).
- **Colony count:** Growth of 10^8 colony-forming units (CFU) per litre (10^5 CFU/mL) or more is the usual threshold for significant bacteriuria, in voided and catheter specimens alike. In women without symptoms, the IDSA asks for two consecutive specimens before calling it asymptomatic bacteriuria, because many first results do not persist (Nicolle et al., 2019).
- **Number of organisms:** Surveillance definitions of catheter infection count only cultures with one or two organisms (Patel et al., 2023).
- **Susceptibility:** The nurse checks that the ordered antibiotic matches the report and tells the prescriber when it does not, or when the culture is negative (Choosing Wisely Canada, n.d.).

Asymptomatic Bacteriuria

Asymptomatic bacteriuria (ASB) is bacteria in the urine, at the threshold above, in a person without signs or symptoms of UTI. It applies whether or not pyuria is present (Nicolle et al., 2019). It is common, especially in older adults: as many as half of long-term care residents have it (Choosing Wisely Canada, n.d.).

ASB is not an infection that needs treatment. The IDSA guideline recommends against screening for or treating it in healthy non-pregnant women, older adults with functional impairment living in the community, older adults in long-term care, people with diabetes or spinal cord injury, people with short- or long-term indwelling catheters, kidney transplant recipients after the first month, and patients having non-urologic surgery (Nicolle et al., 2019). Antibiotics given for ASB do not help the person and can cause harm, including adverse drug effects, *Clostridioides difficile* infection and antimicrobial resistance (Choosing Wisely Canada, n.d.; section 4.4). The two main exceptions are pregnancy (Chapter 29) and urologic procedures that break the lining of the urinary tract, before which ASB is screened for and treated (Nicolle et al., 2019).

The hardest case is the older adult who becomes confused or falls and has a positive urine test. When there are no urinary or systemic signs such as fever or low blood pressure, the IDSA recommends looking for other causes and observing carefully rather than giving antibiotics. If fever or other signs of sepsis appear without a clear source, broad antibiotics that cover urinary and other sources are started (Nicolle et al., 2019). The Lifespan box and section 8.2 describe the approach.

LIFESPAN CONSIDERATIONS

Older Adults, Confusion and the Urine Test

Many older adults, especially in long-term care, have bacteria in the urine without infection (Choosing Wisely Canada, n.d.). A positive dipstick or culture is therefore expected in many and does not explain a change in health. Bacteriuria and delirium often occur together, but a causal link has not been shown, and treating bacteriuria in delirium without sepsis has not improved mental status (Leis et al., n.d.).

When an older adult becomes newly confused, sleepy or agitated, or falls, the nurse:

- screens for delirium and looks for other causes: dehydration, constipation, urinary retention, pain, new or changed medications, poor sleep and infection elsewhere (section 8.2);
- examines the perineal skin and offers fluids if urine is dark or strong-smelling, then reassesses (Choosing Wisely Canada, n.d.);
- sends a urine culture only when minimum criteria for UTI are met;
- listens to family concerns, explains the possible causes and why a urine test may not help (Choosing Wisely Canada, n.d.).

> Fever with a rising heart rate, falling blood pressure or other signs of sepsis is a different situation: the nurse escalates at once (section 4.6).

Treatment and Teaching

Antibiotic choice depends on the type of UTI, local resistance patterns, allergies, kidney function and culture results. For acute uncomplicated cystitis in women, the IDSA guideline names nitrofurantoin, fosfomycin and, where local resistance is low, trimethoprim-sulfamethoxazole as appropriate choices. Fluoroquinolones such as ciprofloxacin work well but are reserved for more important uses, and beta-lactam antibiotics are alternatives when the preferred drugs cannot be used (Gupta et al., 2011). The four conditions in this section are compared side by side (Table 28.1).

For pyelonephritis, a urine culture with susceptibility testing is always done (Gupta et al., 2011). Patients well enough to stay home may take an oral antibiotic such as ciprofloxacin when local resistance allows; patients admitted to hospital start with intravenous (IV) therapy (Gupta et al., 2011). The 2025 IDSA guideline suggests switching to an oral antibiotic once the patient is improving and can take one, notes that options such as first-generation cephalosporins (for example, cephalexin) are less well studied but may suit some patients, and favours about 7 days of treatment for many patients rather than 10 to 14 (Trautner et al., 2025). All of these drugs are marketed in Canada (Health Canada, 2026).

Nursing care with the CJMM. For a patient admitted with pyelonephritis, the nurse *recognizes cues* such as temperature, heart rate, blood pressure, mental status, flank pain and urine output, and *analyzes* them against the patient's baseline and kidney tests (section 27.1). When cues point that way, the nurse *prioritizes* the hypotheses of sepsis or an obstructed kidney over simple infection. The nurse *generates solutions* and *takes action* with the team: antibiotics, fluids and pain relief as ordered, and early escalation. In *evaluating outcomes*, the nurse expects fever, pain and appetite to improve as treatment works, and reports a patient who is not improving, because a complication such as obstruction may need imaging and drainage (section 28.4).

The nurse gives antibiotics on time, checks culture results and helps the team reassess treatment within about 3 days, stopping it if the culture taken before treatment is negative (Choosing Wisely Canada, n.d.). These are core stewardship actions (section 4.5). The nurse also encourages fluids unless restricted, offers pain relief (Chapter 5) and monitors temperature, vital signs and intake and output.

Teaching covers how to take the antibiotic exactly as prescribed, not to save or share leftover tablets, and to seek care if fever, flank pain or vomiting develop or symptoms are not improving. Many people ask about cranberry products. A 2023 Cochrane review found that they probably reduce symptomatic, culture-confirmed UTIs in women with recurrent UTIs, but the evidence does not support them for older adults in institutions, people with bladder-emptying problems or pregnant people. Products and doses varied widely (Williams et al., 2023).

Table 28.1 Asymptomatic bacteriuria, cystitis, pyelonephritis and urosepsis compared (Nicolle et al., 2019; Gupta et al., 2011; Trautner et al., 2025; Choosing Wisely Canada, n.d.)

Condition	Typical findings	Culture or antibiotics?	Nursing focus
Asymptomatic bacteriuria	Bacteria in urine with no urinary symptoms, fever or systemic signs; pyuria may be present	No screening and no antibiotics, except in pregnancy and before urologic procedures that break the mucosa	Look for other causes of any change in health; avoid dipsticks and routine cultures; explain to families
Cystitis	New dysuria, urgency, frequency, suprapubic pain, visible blood or new incontinence; no fever or flank pain	Antibiotics such as nitrofurantoin, fosfomycin or trimethoprim-sulfamethoxazole as ordered; culture as ordered, and before treatment in long-term care	Correct specimen technique; fluids; antibiotic teaching; reassess within about 3 days
Pyelonephritis	Fever, rigors, flank pain or costovertebral angle tenderness, with or without bladder symptoms	Culture and susceptibility always; oral or IV antibiotics depending on severity; often about 7 days	Vital signs, intake and output; antibiotics on time; watch for sepsis; report fever with a known stone at once

Condition	Typical findings	Culture or antibiotics?	Nursing focus
Urosepsis	UTI with signs of organ dysfunction such as new confusion, low blood pressure, fast breathing or low urine output	Cultures, then IV antibiotics without delay	Escalate at once; sepsis care (section 4.6); team looks for an obstruction that needs drainage

28.2 Urinary Catheters and CAUTI Prevention

Indwelling Catheters

An **indwelling urinary catheter** is a flexible tube passed through the urethra (or, for a suprapubic catheter, through the lower abdominal wall) into the bladder and held in place by an inflated balloon (Figure 7.3 shows a catheter being prepared for insertion). It drains urine continuously into a closed bag. Catheters are useful but carry real harm. UTIs are among the most common health care-associated infections, and the length of time a catheter stays in is the strongest single risk factor for infection (Patel et al., 2023). Catheters also tether patients to the bed, which adds to functional decline and delirium in older adults (sections 8.2 and 8.4).

Catheters are often used without a good reason. A review of inpatients at Sunnybrook Health Sciences Centre, a Toronto hospital, found that 18% had a urinary catheter, and 69% of them had no appropriate guideline-based reason (Leis & Soong, 2019). Studies cited in the same toolkit found that physicians did not know their patient had a catheter in as many as 40% of cases.

Appropriate indications. The United States Centers for Disease Control and Prevention (CDC) guideline, which Canadian programs draw on, gives these examples (CDC, 2009):

- sudden inability to void (acute retention) or a blockage at the bladder outlet;
- accurate measurement of urine output in critically ill patients;
- selected surgical procedures, with removal as soon as possible afterward, preferably within 24 hours;
- helping open sacral or perineal wounds heal in patients with incontinence;
- prolonged immobilization, such as after trauma;
- comfort at the end of life.

The Choosing Wisely Canada toolkit adds continuous bladder irrigation for visible blood in the urine (section 28.5), a long-term catheter already in place before admission, spinal cord injury and some pelvic cancer surgery (Leis & Soong, 2019).

Inappropriate uses include managing incontinence in place of nursing care, collecting urine from a patient who can void, measuring a post-void residual, continuing a catheter after surgery without a reason, and convenience (CDC, 2009; Leis & Soong, 2019). Delirium, dementia and being confined to bed are not indications on their own.

Insertion. In Ontario, inserting a catheter is a controlled act authorized to registered nurses (RNs) and registered practical nurses (RPNs); it needs an order or medical directive unless the nurse has authority to initiate it (College of Nurses of Ontario [CNO], 2025c; section 28.6, Scope in Practice box). The nurse explains the procedure, gains consent and protects privacy (Chapter 1; Chapter 2). In acute care, the nurse performs hand hygiene and uses aseptic technique with sterile equipment, including a single-use lubricant, and a new sterile kit for each attempt (CDC, 2009; Leis & Soong, 2019). The smallest catheter that drains well limits urethral injury, and the catheter is secured after insertion to prevent movement and pulling on the urethra (CDC, 2009).

Maintenance. The CDC (2009) and the Society for Healthcare Epidemiology of America compendium (Patel et al., 2023) set out these practices:

- Keep the drainage system closed. If it is opened, disconnected or leaking, replace the catheter and bag using aseptic technique.
- Keep urine flowing: no kinks or loops in the tubing.
- Keep the bag lower than the bladder throughout, including during transfers and walks, and never rest it on the floor.
- Empty the bag regularly into a separate clean container for each patient, without letting the spout touch the container (Figure 28.1).

- Clean the meatus during routine bathing; antiseptic cleaning around the catheter does not prevent infection.
- Do not change catheters or bags at fixed intervals, and do not use routine bladder irrigation or preventive antibiotics.

Review and removal. Every day, the nurse asks whether each catheter still has an indication, and the team reviews it on rounds (Patel et al., 2023). Many hospitals use a **nurse-driven catheter removal protocol**, often a medical directive, that lets nurses remove a catheter when no listed indication remains, and the compendium recommends considering one (Patel et al., 2023). Other tools are reminders and orders that expire unless renewed (Leis & Soong, 2019). After removal, the nurse checks that the patient voids and that the bladder empties (section 28.3).

Going home with a catheter. Some patients leave hospital with an indwelling catheter, for example after prostate surgery or with chronic retention. The nurse teaches hand hygiene before and after touching the catheter or bag, keeping the bag below the bladder and the tubing free of kinks, securing the catheter, cleaning the meatus during daily washing and emptying the bag regularly (CDC, 2009). The patient also learns how to change between a daytime leg bag and a larger night bag, and to report fever, flank pain, no drainage for several hours or leaking around the catheter. Home and community care nurses often continue this teaching (section 1.7).

Figure 28.1 Emptying a urinary drainage bag: the spout drains into a separate measuring container without touching it, and the bag stays below the level of the bladder. (credit: "Empty the Urinary Drainage Bag" by BruceBlaus/Wikimedia Commons, CC BY-SA 4.0)

CLINICAL SAFETY

Lose the Tube

Lose the Tube is a Choosing Wisely Canada toolkit for appropriate urinary catheter use in hospitals, written by physicians at Sunnybrook Health Sciences Centre and Sinai Health in Toronto (Leis & Soong, 2019). It grew from a finding that most catheters in Sunnybrook's inpatients had no appropriate reason and were often put back at the first sign of retention.

The team agreed on criteria for appropriate use, wrote a medical directive that let nurses remove catheters without a listed indication, trained nurses with practice cases in about 30 minutes, and added an algorithm for checking the bladder after removal. Catheter use on the medical wards fell by half for more than a year, and no inappropriate removals were found (Leis & Soong, 2019).

For the bedside nurse, the lessons are:

- Ask every day whether each catheter still has an indication.
- Remove it when it does not, under a directive or by asking the prescriber.
- After removal, follow the unit's algorithm to confirm the bladder empties, using intermittent catheterization when needed rather than reinserting an indwelling catheter.
- Offer alternatives first: toileting help, a commode, a urinal or bedpan, or an external catheter.

Intermittent and External Catheters

Intermittent catheterization means passing a catheter into the bladder to drain it and then removing it. For patients whose bladder does not empty, the CDC (2009) prefers it to an indwelling catheter. In hospital, the nurse uses sterile technique; at home, a clean technique is an acceptable, practical alternative (CDC, 2009). For long-term retention, clean intermittent self-catheterization, done by the patient or a caregiver, is the preferred approach when it is possible (Stoffel et al., 2016). The nurse teaches the technique, a schedule set with the care team, hand hygiene and the signs of infection to report.

An **external catheter** collects urine from outside the body, so nothing enters the bladder. A male external catheter fits over the penis like a sheath; external devices for female anatomy sit against the vulva and carry urine away to a collection container. The CDC (2009) suggests male external catheters for cooperative patients without retention or obstruction. A more recent compendium recommends keeping both male and female external catheters on every unit, but notes that evidence on their skin injury and infection risks, especially for female devices, is still developing (Patel et al., 2023). The nurse checks the skin under and around the device regularly and follows the manufacturer's instructions for fit and changes (Chapter 35).

Recognizing CAUTI

A **catheter-associated urinary tract infection (CAUTI)** is a UTI in a person who has, or recently had, a urinary catheter. Because the catheter drains the bladder continuously, the usual urgency and frequency are absent, so recognition rests on other signs. Surveillance definitions require significant bacteriuria plus at least one clinical finding such as fever, suprapubic tenderness or costovertebral angle pain or tenderness (Patel et al., 2023). In long-term care, minimum criteria for a resident with a catheter are any one of fever, new flank tenderness, rigors or new delirium, after other causes have been considered (Leis et al., n.d.).

Cloudy, dark or foul-smelling urine alone is not a reason to send a culture (Patel et al., 2023). Bacteria in the urine of a catheterized patient without signs of infection is asymptomatic bacteriuria and is neither screened for nor treated (Nicolle et al., 2019). When the nurse suspects CAUTI, the nurse assesses vital signs and the catheter, reports to the prescriber, collects the specimen from the sampling port, and asks whether the catheter can be removed. Signs of sepsis call for immediate escalation (section 4.6).

28.3 Urinary Retention and Incontinence

Urinary Retention

Urinary retention is the inability to empty the bladder completely or at all. **Acute urinary retention** comes on suddenly. The person may have lower abdominal discomfort and an urge they cannot act on, although after anesthesia or with sedation many people feel no urge at all (section 7.6). Chronic retention develops slowly and is often painless. A consensus statement from the American Urological Association defines chronic urinary retention as a post-void residual above 300 mL on two or more occasions that persists for at least 6 months (Stoffel et al., 2016).

Common causes include:

- an enlarged prostate blocking outflow (section 28.5);
- drugs with anticholinergic effects, which weaken bladder contraction, and opioids (Serlin et al., 2018; Chapter 5; section 8.5);
- anesthesia and surgery, especially pelvic surgery and spinal anesthesia (section 7.6);
- constipation or stool impaction (Serlin et al., 2018; Leis & Soong, 2019);
- neurologic disease or injury, such as spinal cord injury.

The nurse suspects retention when a patient has not voided for several hours, passes small amounts often, has fullness or discomfort above the pubic bone, leaks small amounts (overflow), or becomes restless or newly confused.

The **post-void residual (PVR)** is the volume of urine left in the bladder right after voiding. It can be measured with a catheter or with a **bladder scanner**, a portable ultrasound device that estimates bladder volume without entering the body (Stoffel et al., 2016). Where scanners are used, indications must be clear, staff must be trained, and the device is disinfected between patients (CDC, 2009). The nurse scans soon after the patient voids, follows the device instructions and employer policy, and documents the voided volume and the scan result together.

No single PVR threshold fits every setting. One infection prevention compendium defines postoperative retention as a PVR over 500 mL in a patient without symptoms, or over 300 mL in a patient who has symptoms (Patel et al., 2023). The Canadian Urological Association's overactive bladder guideline says a PVR above 250 to 300 mL needs attention before an antimuscarinic drug is started (Corcos et al., 2017). The nurse uses the thresholds and actions in the unit's protocol or medical directive and reports results outside them.

For retention after catheter removal or surgery, intermittent catheterization is preferred to reinserting an indwelling catheter, and the nurse also treats constipation and helps the patient walk (CDC, 2009; Leis & Soong, 2019). Acute retention from an obstruction is an indication for an indwelling catheter (CDC, 2009). For chronic retention, patients with high-risk features such as hydronephrosis or recurrent infections need treatment, while low-risk patients without symptoms are not offered catheterization just to lower the PVR (Stoffel et al., 2016).

When a large volume is drained, nurses were long taught to empty the bladder gradually to prevent bleeding, low blood pressure and a sudden large urine output. A 2022 meta-analysis of four studies found that rapid, complete drainage did not increase bleeding and reported no circulatory collapse, but the evidence was of very low certainty (Wu et al., 2022). The nurse follows the order and policy and monitors vital signs, urine colour and urine output after drainage.

Retention that comes with fever, flank pain, a rising creatinine or very low urine output needs prompt reporting. A blocked outflow can damage the kidneys, and chronic retention with hydronephrosis, reduced kidney function or repeated infections is considered high risk (Stoffel et al., 2016; Chapter 27).

Urinary Incontinence

Urinary incontinence is any involuntary leakage of urine (Bettez et al., 2012). It affects about 30% to 60% of people over 65, and more in frail older adults, yet it is not a normal or inevitable part of aging and can often be cured or improved (Bettez et al., 2012; Health Canada, 2006). Many people do not mention it, so the nurse asks directly and privately.

The main types are compared side by side (Table 28.2). **Stress incontinence** is leakage with coughing, sneezing or exertion. **Urgency (urge) incontinence** is leakage with or right after a sudden, strong need to void; it is part of overactive bladder, which affects an estimated 14% to 18% of Canadians (Corcos et al., 2017). Mixed incontinence combines the two. **Overflow incontinence** is leakage from a bladder that overfills because it cannot empty. **Functional incontinence** is leakage because a person cannot reach or use the toilet in time, for example because of limited mobility, dementia or poor vision (Bettez et al., 2012; Health Canada, 2006).

Table 28.2 Types of urinary incontinence (Bettez et al., 2012; Corcos et al., 2017; Health Canada, 2006)

Type	What happens	Common causes	Nursing and treatment focus
Stress	Small leaks when pressure in the abdomen rises: coughing, sneezing, laughing, lifting	Weak pelvic floor, for example after childbirth; prostate surgery	Pelvic floor muscle training first; weight loss and constipation control; pessary or surgery if needed
Urgency	Leaks with or right after a sudden, strong urge that is hard to delay; often frequency and night-time voiding	Overactive bladder; caffeine; stroke, Parkinson disease or multiple sclerosis	Bladder training, pelvic floor training and less caffeine; antimuscarinic or beta-3 agonist if needed
Mixed	Both stress and urgency leaks	A combination of the above; common in older women	Combine the approaches for both types
Overflow	Frequent small leaks from a bladder that cannot empty, often without a feeling of fullness	Blockage such as an enlarged prostate; weak bladder muscle	Measure the PVR; restore emptying first by treating the cause or using intermittent catheterization
Functional	Leaks because the person cannot get to or use the toilet in time	Limited mobility, dementia, poor vision, mental health conditions, barriers in the room	Toileting help and prompted voiding; call bell in reach; raised seat, grab bars and easy clothing

Assessment. The nurse asks about the type, amount and timing of leakage, how much it bothers the person, fluid and caffeine intake, bowel habits and medications such as diuretics. The team also considers mobility, dexterity, cognition and access to a toilet. A urinalysis and a **bladder diary**, a record of fluid intake, voids, urgency and leaks over 3 or more days, are part of the first assessment (Bettez et al., 2012; Corcos et al., 2017). A PVR is measured when there are voiding symptoms or concern about emptying. Temporary, treatable causes are looked for first, including delirium, infection, medications, high urine output, restricted mobility and stool impaction (Bettez et al., 2012).

Because incontinence is common and often hidden in frail older adults, the CUA guideline recommends screening them for it every year. Their assessment includes medications, cognition, fluid intake, access to a toilet and support from caregivers (Bettez et al.,

2012). Nurse continence advisors and continence physiotherapists can help, and simple changes such as a raised toilet seat, grab bars and clothing that is easy to remove support people with functional incontinence (Health Canada, 2006).

Conservative treatment comes first, and a fair trial takes 8 to 12 weeks (Bettez et al., 2012; Corcos et al., 2017):

- **Lifestyle:** less caffeine, weight loss when relevant, constipation control, sensible fluid intake (less in the hours before bed for night-time voiding) and stopping smoking.
- **Pelvic floor muscle training (PFMT):** repeated, correctly performed contractions of the pelvic floor muscles. It is first-line for stress incontinence and also helps urgency incontinence; intensive, supervised training is preferred where available.
- **Bladder training:** a voiding schedule with intervals lengthened gradually, by about 15 to 30 minutes a week, combined with urge-suppression techniques.
- **Scheduled and prompted voiding:** recommended for frail people (Bettez et al., 2012). In **prompted voiding**, staff regularly prompt the person to use the toilet, help them there and praise success (Eustice et al., 2000).

Medications. For urgency incontinence that persists, the prescriber may add an antimuscarinic such as oxybutynin, or the beta-3 agonist mirabegron, both marketed in Canada (Corcos et al., 2017; Health Canada, 2026). Antimuscarinics cause dry mouth, constipation and central nervous system effects, add to anticholinergic burden and are linked with cognitive impairment. They are considered potentially inappropriate for frail older adults and are contraindicated in uncontrolled narrow-angle glaucoma. Mirabegron is contraindicated in severe uncontrolled hypertension, so blood pressure is checked (Corcos et al., 2017). The nurse reports new confusion, falls, constipation or difficulty voiding. Section 28.6 summarizes these drugs in a table (Table 28.3).

Containment and dignity. Pads, briefs and external catheters keep a person dry while treatment works, and containment is sometimes the most realistic goal, for example with advanced dementia (Bettez et al., 2012). An indwelling catheter is never a substitute for continence care (CDC, 2009). The nurse answers call bells promptly, offers toileting help on a schedule, changes wet products quickly, protects the skin (Chapter 35) and uses respectful language. Continence care is skilled nursing work that preserves dignity, mobility and independence.

28.4 Kidney Stones

A kidney stone forms when minerals that are normally dissolved in urine come out of solution and build up into a hard mass. **Urolithiasis** is the general term for stones anywhere in the urinary tract. Trouble starts when a stone moves into the ureter and blocks the flow of urine. Kidney function and acute kidney injury are covered in Chapter 27.

How Stones Form and Who Gets Them

Stones form when urine carries more of a substance than it can keep dissolved, so crystals form and grow. Concentrated urine makes this more likely. Most stones range from the size of a grain of sand to a pea (National Institute of Diabetes and Digestive and Kidney Diseases [NIDDK], 2017a). The main types are:

- **Calcium stones:** the most common type, mostly calcium oxalate and less often calcium phosphate.
- **Uric acid stones:** these develop in urine that is too acidic; diets heavy in meat, fish and shellfish raise the risk.
- **Struvite stones:** linked to urinary tract infection; they can appear suddenly and enlarge fast.
- **Cystine stones:** the result of cystinuria, an inherited disorder (NIDDK, 2017a).

Risk factors include male sex, a family history of stones, a low fluid intake, a past stone, obesity, gout, inflammatory bowel disease or past bowel surgery, hyperparathyroidism, repeated urinary tract infections and long-term use of some drugs, such as topiramate (NIDDK, 2017a). The Canadian Urological Association (CUA) describes stone disease as a systemic condition linked with obesity, metabolic syndrome and diabetes (Bhojani et al., 2022).

In a Canadian study of hospital and emergency department records (all provinces and territories except Quebec), kidney stone episodes needing acute care or a procedure rose from 277 per 100,000 people in 2013 to 290 per 100,000 in 2018, and 59.9% of episodes involved men (Ordon et al., 2024). Stones often come back: the CUA reports recurrence rates of 30% to 50% within 10 years of a first symptomatic stone (Bhojani et al., 2022).

Renal Colic and Care

Renal colic is the severe pain of a stone moving through or blocking the ureter. The pain is sharp, is felt in the back, side, lower abdomen or groin, and may come in waves. Nausea, vomiting, frequent or painful voiding and **hematuria**, blood in the urine that can turn it pink, red or brown, are common. Fever and chills point to infection (NIDDK, 2017b).

The CUA recommends ultrasound with a plain X-ray of the kidneys, ureters and bladder (KUB) as the first imaging for an acute ureteral stone, and careful use of computed tomography (CT), preferably at a low dose (Lee et al., 2021; Figure 28.2). The team also checks for infection (section 28.1).

Pain relief. The CUA guideline reports that nonsteroidal anti-inflammatory drugs (NSAIDs) relieved renal colic better than morphine in comparison studies. It recommends keeping opioid use to a minimum and teaching the patient what to expect (Lee et al., 2021). NSAIDs are not safe for everyone; the prescriber weighs kidney function and bleeding risk (Chapter 5). The nurse reassesses pain after each dose.

Passing the stone. Small stones, under about 5 mm, often pass on their own (Dushinski, 2021). **Medical expulsive therapy (MET)** is the use of a drug to help a ureteral stone pass. The CUA states that any benefit is for larger (5 to 10 mm) stones in the lower ureter, and that the pros and cons are weighed with the patient. If an obstructing stone has not passed after 4 to 6 weeks, surgery should likely be considered (Lee et al., 2021). The CUA recommends that any stone the patient collects, for example by straining the urine as instructed, be sent for analysis, because knowing its composition guides prevention (Bhojani et al., 2022).

Figure 28.2 Non-contrast CT showing a stone in the upper right ureter (the bright white spot) causing mild blockage. CT is used carefully, preferably at a low dose. (credit: "KidneyStone" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

An obstructed, infected kidney is an emergency. When a stone blocks the ureter and the urine above it is infected, the infected urine is trapped under pressure, and sepsis can follow quickly (Chapter 4). The CUA states that obstructive pyelonephritis needs early, goal-directed treatment that includes timely **decompression**, drainage of the blocked kidney (Lee et al., 2021). Drainage is by a **ureteral stent**, a thin tube passed up the ureter from the bladder, or a **nephrostomy tube**, placed through the skin of the back into the kidney (Lee et al., 2021). Antibiotics are essential, but they cannot drain a blocked kidney. Early intervention may also be needed for uncontrolled pain, worsening kidney function or significant frailty (Lee et al., 2021). A nurse who finds fever, chills, a rising heart rate, falling blood pressure, new confusion or falling urine output in a patient with a known or suspected stone escalates at once (Chapter 6).

Procedures. In **shock wave lithotripsy (SWL)**, shock waves from outside the body break the stone into fragments that pass in the urine (Figure 28.3). In **ureteroscopy**, a thin scope is passed through the urethra and bladder into the ureter to break up or remove the stone. For ureteral stones, SWL gives stone-free rates similar to ureteroscopy, with more repeat treatments but fewer complications (Lee et al., 2021). Ureteroscopy made up 73.5% of first stone procedures in Canada (Ordon et al., 2024).

Routine stenting after uncomplicated ureteroscopy is likely unnecessary, but a stent is placed for a suspected ureteral injury or narrowing, a single kidney or reduced kidney function (Lee et al., 2021). Stents make urinary symptoms markedly worse; an alpha-blocker, an anticholinergic drug or both may ease them (Lee et al., 2021). The nurse makes sure the patient knows the stent is temporary and when it will be removed.

Preventing Recurrence

The CUA makes fluid the first line of prevention: every person who has had a stone should aim for a urine output of 2.5 L a day, mostly from water. Each extra 200 mL of fluid a day was linked with a 13% lower stone risk (Bhojani et al., 2022). Diet advice

Figure 28.3 Kidney stone fragments after shock wave lithotripsy, beside a millimetre scale. Patients may be asked to strain their urine so that fragments can be analyzed. (credit: "Kidney stones" by Arconsoli/Wikimedia Commons, CC BY-SA 4.0)

depends on the stone type (Bhojani et al., 2022):

- **Calcium:** do not cut calcium; the goal is 1,000 to 1,200 mg a day, with any supplements taken with meals.
- **Sodium:** with recurrent calcium stones, limit sodium to 1,500 mg a day and never more than 2,300 mg.
- **Animal protein:** people who have had repeated calcium or uric acid stones eat moderate amounts.
- **Oxalate and vitamin C:** limit high-oxalate foods and avoid vitamin C supplements above 1,000 mg a day.
- **Cystine stones:** the urine target rises to 3 L a day.

People at high risk of recurrence, such as those with repeated or non-calcium stones or a single kidney, are offered a full metabolic evaluation, and some need a preventive drug. Those on preventive treatment have repeat testing within 6 months and then yearly (Bhojani et al., 2022).

PATIENT EDUCATION

Preventing Another Kidney Stone

- **Drink through the day.** Aim to pass about 2.5 L of urine every day, which means drinking more than that. Water is the best choice. Keep a water bottle with you, and drink more in hot weather and when you exercise.
- **Keep calcium in your diet.** Do not cut out milk products or other calcium-rich foods unless your health care provider tells you to. Take any calcium supplement with a meal.
- **Go easy on salt.** Read labels on processed and restaurant foods, which are often high in sodium.
- **Eat moderate amounts of meat, fish and poultry.** Large servings raise the risk of calcium and uric acid stones.
- **Ask before taking vitamin C.** High-dose supplements can raise oxalate in the urine.
- **Save the stone.** If you are asked to strain your urine, bring any stone you catch to your appointment so it can be tested.
- **Get help right away** for fever or chills with flank pain, pain that medicine does not control, vomiting that stops you from keeping fluids down, or passing very little urine. Call 9-1-1 if you feel faint or confused.

28.5 Benign Prostatic Hyperplasia and Prostate Surgery

The prostate sits just below the bladder and wraps around the urethra. When it enlarges, it can squeeze the urethra and make the bladder harder to empty. This section covers benign enlargement of the prostate, its drugs and care after prostate surgery, including continuous bladder irrigation. Urinary retention is covered in section 28.3.

Benign Prostatic Hyperplasia

Benign prostatic hyperplasia (BPH) is a non-cancerous enlargement of the prostate and one of the most common age-related conditions in men (Elterman et al., 2022). BPH does not raise the risk of prostate cancer (Canadian Cancer Society [CCS], n.d.-f), but the two can occur together, and both are assessed when symptoms begin (Figure 28.4).

BPH causes **lower urinary tract symptoms (LUTS)**. Voiding symptoms include a weak or interrupted stream, hesitancy, straining and a feeling of incomplete emptying. Storage symptoms, such as urgency, frequency and **nocturia** (waking at night to void), are often the most bothersome (Elterman et al., 2022). The CUA guideline recommends a formal symptom inventory, such as the **International Prostate Symptom Score (IPSS)**, a short questionnaire the patient completes, at the first visit and to follow the response to treatment (Elterman et al., 2022).

BPH can lead to complications. The CUA lists them as reasons to consider surgery: repeated or ongoing urinary retention, repeated urinary tract infections, bladder stones, repeated hematuria and kidney damage caused by the obstruction (Elterman et al., 2022). Acute urinary retention, the sudden inability to void with a painful, distended bladder, is urgent and is managed as section 28.3 describes. The nurse asks about drugs that can trigger it, such as those with anticholinergic effects.



Figure 28.4 Comparison of a normal prostate and urethra (top) with benign prostatic hyperplasia (bottom), in which nodular enlargement of the prostate compresses the prostatic urethra and obstructs bladder outflow. (credit: "Benign Prostatic Hyperplasia (BPH)" by BruceBlaus/Wikimedia Commons, CC BY-SA 4.0)

Drugs for BPH. Two drug classes are the mainstay (Table 28.3).

- **Alpha-blockers** (for example, tamsulosin and silodosin) relax the smooth muscle of the prostate and bladder neck. The most common adverse effect is dizziness, and ejaculatory changes are reported most often with tamsulosin and silodosin (Elterman et al., 2022). The Canadian product monograph for tamsulosin warns that blood pressure can drop. Patients should sit or lie down at the first sign of dizziness or weakness, and they should not drive or do hazardous tasks for 12 hours after the first dose (Teva Canada, 2021). Tamsulosin is linked to **intraoperative floppy iris syndrome**, a problem with the iris during cataract or glaucoma surgery. The patient's eye surgeon needs to know about the drug, and starting tamsulosin when such surgery is already planned is not recommended (Teva Canada, 2021). Controlled-release tablets are swallowed whole. Older adults who become dizzy are at risk of falls (Chapter 8).
- **5-alpha reductase inhibitors (5-ARIs)** (for example, finasteride and dutasteride) shrink the prostate by about 25% to 30% (Elterman et al., 2022). They work slowly; the finasteride monograph says a trial of at least 6 months is generally needed. Finasteride lowers the prostate-specific antigen (PSA) level (section 28.6) by about half within 6 months, so anyone reading a PSA result must know the patient takes it (Sanis Health, 2020). People who are or may become pregnant should not touch finasteride tablets that are crushed or broken; the tablet coating stops contact with the drug when whole tablets are handled normally (Sanis Health, 2020). Sexual side effects can occur. The monograph also asks patients to report mood changes and any breast lumps, pain or nipple discharge (Sanis Health, 2020).

Table 28.3 Drugs for urinary and prostate conditions, without doses (Auro Pharma, 2026; Elterman et al., 2022; Kokorovic et al., 2022; Lee et al., 2021; Sanis Health, 2020; Teva Canada, 2021; Verity Pharmaceuticals, 2021)

Class	Canadian examples	Used for	Nursing points
Alpha-blockers	tamsulosin, silodosin	BPH and LUTS; sometimes to help pass a ureteral stone or ease stent symptoms	Dizziness and low blood pressure, especially after the first dose: rise slowly, no driving for 12 hours after the first dose; tell the eye surgeon before cataract or glaucoma surgery; swallow controlled-release tablets whole; report a prolonged painful erection; fall risk in older adults.

Class	Canadian examples	Used for	Nursing points
5-alpha reductase inhibitors	finasteride, dutasteride	BPH with an enlarged prostate	Takes about 6 months to judge the effect; lowers PSA by about half, so tell whoever orders a PSA test; people who are or may become pregnant should not touch crushed or broken finasteride tablets; report mood changes and breast lumps or discharge.
Antimuscarinics	oxybutynin, solifenacin	Urge incontinence and storage symptoms (section 28.3)	Anticholinergic effects, a particular concern in older adults (section 28.3); use with caution when there is obstruction or a high post-void residual.
Beta-3 agonists	mirabegron	Urge incontinence and storage symptoms (section 28.3)	Can raise blood pressure: measure it before starting and periodically; use with caution when the bladder outlet is obstructed.
NSAIDs	ketorolac, ibuprofen	Renal colic	Check kidney function, bleeding risk and other conditions before giving; reassess pain; aim to keep opioid use low.
Androgen deprivation therapy	leuprolide, degarelix	Advanced or higher-risk prostate cancer	Hot flashes, bone loss, weight gain, diabetes risk, lipid changes, muscle loss, fatigue, mood and memory changes, loss of libido; teach calcium, vitamin D and exercise; support bone density testing and metabolic monitoring.
Intravesical BCG (live bacteria)	VERITY-BCG	Non-muscle-invasive bladder cancer after TURBT	Biohazard handling; delay after traumatic catheterization, visible hematuria or infection; retain 2 hours, void sitting, bleach the toilet for 6 hours; report fever above 39 °C lasting more than 12 hours.

Using both classes together lowers the risk of urinary retention and of needing surgery in men with a larger prostate (Elterman et al., 2022). When storage symptoms dominate, an antimuscarinic drug or a beta-3 agonist may help. The CUA advises caution when there is significant obstruction or a high post-void residual, because these drugs can worsen retention (Elterman et al., 2022; section 28.3).

Surgery and Continuous Bladder Irrigation

In a **transurethral resection of the prostate (TURP)**, the surgeon passes a scope through the urethra and uses an electrical wire loop to cut away the inner part of the gland while the outer shell stays in place (The Ottawa Hospital [TOH], 2010). The CUA calls standard (monopolar) TURP the reference surgical treatment for moderate to severe symptoms. Alternatives include bipolar TURP, holmium laser enucleation, laser vaporization, a prostatic urethral lift, water vapour therapy and simple prostatectomy by open, laparoscopic or robotic surgery (Elterman et al., 2022). A urethral lift, for example, may suit a man who wants to preserve ejaculation (Elterman et al., 2022).

After TURP, the patient usually returns with a large **three-way catheter**. One channel inflates the balloon, one drains urine, and one carries irrigation fluid into the bladder. **Continuous bladder irrigation (CBI)** runs sterile 0.9% sodium chloride into the bladder and out through the drainage channel without stopping. It keeps blood from clotting in the bladder and keeps the catheter open (Agency for Clinical Innovation [ACI], 2026). No Canadian bladder irrigation guideline was found, so the steps below follow one published toolkit from New South Wales, Australia, as an example protocol; the nurse always follows the local protocol and orders. The fluid is kept at room temperature, because cold fluid can cause bladder spasms and leaking around the catheter (ACI, 2026).

Nursing care during CBI centres on four tasks.

- **Adjust the flow to the bleeding.** The nurse raises the irrigation rate when the drainage becomes redder or shows more clots, then watches the drainage and the patient's comfort (ACI, 2026). Each unit's protocol names a target drainage colour and how to titrate, and the nurse follows the protocol and the order.
- **Calculate true urine output.** The drainage bag holds urine plus irrigation fluid. **True urine output** is the total volume drained minus the volume of irrigation instilled (ACI, 2026). If 3,000 mL of irrigation ran in and 3,350 mL drained out, the patient made 350 mL of urine. The nurse records irrigation in, total out, true output, drainage colour and clots on the fluid balance record.
- **Watch for clot retention. Clot retention** occurs when clots block the catheter. The signs are slowed or absent drainage, lower abdominal pain that worsens as the bladder fills, a distended bladder above the pubic bone, urine leaking around the catheter and

sometimes sweating, a rapid pulse and low blood pressure (ACI, 2026). Because irrigation keeps flowing in, a blocked bladder fills fast.

- **Act in order.** When drainage is less than the irrigation going in, or pain rises, the nurse turns off the irrigation inflow and checks the catheter and tubing for kinks, loops and clots. Next, the nurse palpates the bladder, considers a bladder scan and recalculates the output. If a clot is the cause, the protocol may allow closed or manual irrigation to remove it. Manual irrigation is done only when ordered, by a clinician who is authorized and competent to do it. If these steps fail, the nurse notifies the urology team (ACI, 2026). Nurses do not reinsert or replace a catheter after urologic surgery without the urologist's authorization (ACI, 2026).

Bladder spasms cause a strong urge to void and cramping pain above the pubic bone (TOH, 2010). Because spasms and a blocked catheter feel alike, the nurse rules out blockage first, then gives any ordered antispasmodic. If the drainage stays red or the clots increase even after the irrigation rate is raised, the nurse notifies the urology team (ACI, 2026). Bright red drainage together with a rising heart rate and falling blood pressure suggests hemorrhage, and the nurse escalates at once (Chapter 6). The catheter is secured to the thigh to limit movement (ACI, 2026). CBI stops only on a medical order, and the urology team reviews it at least daily (ACI, 2026). New confusion or agitation after TURP is reported at once (see the Going Deeper box).

Before discharge, the nurse teaches the patient to drink 1 to 2 L of fluid a day unless his fluids are restricted, and to rest and drink more if blood appears in the urine. He should avoid heavy lifting (more than 7 kg) and strenuous exercise for 2 weeks, avoid straining at stool by eating high-fibre foods, and avoid long car rides until his follow-up visit (TOH, 2010). Sexual activity can usually resume after 3 to 4 weeks, as discussed with the urologist. Semen may now flow backward into the bladder, called **retrograde ejaculation**. This is harmless, though urine may look cloudy afterward and fertility may be affected (TOH, 2010). He calls the urologist for a fever above 38.5 °C, chills, trouble passing urine, or flank or low back pain (TOH, 2010). Large clots that make it hard to void, or being unable to void even with a full bladder, need a call to the surgeon or, if the surgeon cannot be reached, a visit to the nearest emergency department (Toronto East Health Network [TEHN], 2019).

GOING DEEPER

Transurethral Resection Syndrome

Required for RN students; optional for PN students.

Monopolar TURP needs an irrigating fluid without electrolytes, such as glycine, because electrolyte solutions disperse the cutting current. As prostate tissue is cut, open veins absorb this fluid (Gupta et al., 2010). Large volumes cause **transurethral resection syndrome (TUR syndrome)**: dilutional hyponatremia with fluid overload (section 3.4). Absorbing 1 L of fluid within an hour can lower serum sodium by about 5 to 8 mmol/L. Risk rises with resections longer than 60 minutes and with large glands (Gupta et al., 2010).

Early signs include dizziness, headache, nausea, shortness of breath, high blood pressure, a slow heart rate and dysrhythmias. Restlessness, confusion and blurred vision follow. Without treatment, the patient can become hypotensive and go into cardiac arrest (Gupta et al., 2010). Signs can begin during surgery or after it, for example 30 to 45 minutes after the operation ends (Gupta et al., 2010). A nurse who notices new confusion or agitation after TURP checks orientation and vital signs and reports at once, including when the change began, any analgesia given, the irrigation volume and the true urine output (ACI, 2026). The team checks the sodium urgently and corrects it carefully (section 3.4).

Bipolar TURP uses saline instead, and a Cochrane review found that it probably slightly reduces TUR syndrome, by about 20 cases per 1,000 patients (moderate-certainty evidence; Alexander et al., 2019).

CLINICAL JUDGMENT

No Drainage and Rising Pain

Names and details are fictional; this is a composite story.

Wilfred Osei-Bonsu, 79, is on day 1 after a TURP, with CBI running through a three-way catheter. At 06:00, he rings the bell, grimacing and saying he needs to void "right now."

- **Recognize cues:** The drainage bag has gained only 40 mL in the past hour while irrigation ran at the ordered rate. The tubing is dark red with small clots. Urine is leaking around the catheter onto the pad. His lower abdomen is firm and tender above the pubic bone. His heart rate is 98, up from 80 overnight.
- **Analyze cues:** Fluid is going in but not coming out. The firm bladder and leaking point to a blocked catheter, not just a spasm.

- **Prioritize hypotheses:** Clot retention is the most likely cause and the most urgent, because the bladder is filling with irrigation fluid. A bladder spasm, a kinked tube or bleeding are also possible.
- **Generate solutions:** Stop the inflow. Check the tubing. Confirm the bladder volume. Follow the unit's catheter irrigation protocol. Notify urology if the blockage does not clear.
- **Take action:** The nurse clamps the irrigation inflow and finds no kinks, but sees a clot in the drainage port. A bladder scan shows a large volume. Under the protocol and the standing order for manual irrigation, the nurse withdraws several clots with sterile technique. Drainage flows again. The nurse pages the urology resident with an SBAR report, restarts the irrigation at a higher rate as the order allows and records the volumes.
- **Evaluate outcomes:** Within 30 minutes, the drainage is lighter, Mr. Osei-Bonsu's pain has dropped from 8 to 2 out of 10, and leaking has stopped. His heart rate is 82. The nurse rechecks hourly and documents the true urine output.

PRACTICE STORY

Bright Red and Clotted

Names and details are fictional; this is a composite story.

Nurse: Camille Marchand, RN. Years in practice: 6. Setting: surgical unit, Ontario.

Bernard came back from his TURP at suppertime, 81 years old, with continuous bladder irrigation running. At handover, the drainage was cherry red but flowing. By 21:00, Priya, the RPN on our team, came to find me. "Bernard's bag has hardly changed, and he's rocking in the bed."

I went in. The drainage tubing was bright red and clotted, and the bag had gained maybe 30 mL in an hour while the irrigation ran. He was sweaty and his lips had lost their colour, and he was gripping the bed rail. His pad was soaked; urine was leaking around the catheter. Heart rate 112, up from 84 at 19:00. Blood pressure 138/80.

I clamped the inflow first. A bladder full of saline and clots was not going to get better with more saline. I checked the tubing from his body to the bag: no kinks, but a dark clot was sitting in the drainage port. The bladder scanner showed a large volume. Our protocol lets RNs hand-irrigate after a urology order, and there was one. I pulled back several clots and the drainage started again, still bright red.

Then I paged the urology resident. "Bernard Lavoie, day 0 after TURP. Clot retention, partly cleared by hand irrigation. Drainage still bright red, heart rate 112, up from 84. I've stopped the inflow. I'd like you to see him now." She came within 20 minutes, washed out more clots and adjusted the irrigation rate. By midnight the drainage was light pink and his heart rate was 88.

What stays with me is that Priya noticed first. She saw a bag that wasn't filling and a man who couldn't settle, and she didn't wait.

Reflect: Priya's employer allows only RNs to hand-irrigate after urologic surgery. Using authority, competence and context, what could Priya do safely on her own, and when should she bring in the RN? What would change if her employer's policy allowed RPNs to perform this skill?

28.6 Prostate and Bladder Cancer

Prostate and bladder cancer are common in Canada, and both affect urinary function and quality of life. General cancer treatment is covered in Chapter 9 and sexual health after treatment in Chapter 29.

Prostate Cancer

Apart from non-melanoma skin cancers, prostate cancer is the cancer diagnosed most often in men in Canada. In 2026, an estimated 29,300 men will be diagnosed with it (23% of new cancers in men) and 5,300 will die of it, which ranks it second among causes of cancer death in men. Roughly 1 in 9 men will be diagnosed with prostate cancer, and roughly 1 in 34 will die of it (Brenner et al., 2026; CCS, n.d.-c). Prostate cancers vary: some grow slowly, while others are fast-growing, and telling them apart drives decisions about testing and treatment.

Risk factors. Risk rises with age; most cases are found in men in their 60s. A father, brother or son with prostate cancer raises the risk, more so with several affected relatives or a relative diagnosed before 65. Inherited gene changes, most often in *BRCA2* or *HOXB13*, explain a small share of cases, and excess body weight also raises risk (CCS, n.d.-f). Prostate cancer is diagnosed more often among Black men (including those of African or Caribbean ancestry), who also tend to have faster-growing tumours and a

higher chance of dying from the disease (CCS, n.d.-f). This finding describes groups, not the cause in any one person. The nurse avoids assumptions and makes sure Black patients receive clear, unhurried information about testing and treatment (Chapter 2).

Screening with PSA. PSA is a protein made by the prostate and measured in a blood test. Canadian guidance on PSA screening differs (Table 28.4). The Canadian Task Force on Preventive Health Care (2014) recommends against PSA screening at any age, while the CUA (2022) suggests offering it, after shared decision-making, to men expected to live more than 10 years (Bell et al., 2014; Mason et al., 2022). The nurse presents both positions accurately, helps the patient name what matters to him and refers him to his primary care provider to decide.

Table 28.4 PSA screening: what two Canadian bodies recommend (Bell et al., 2014; Mason et al., 2022)

Body	Recommendation (in this book's words)	Date	What the nurse discusses
Canadian Task Force on Preventive Health Care	Do not screen for prostate cancer with PSA. Against for men under 55 (strong recommendation, low-quality evidence), 55 to 69 (weak recommendation, moderate-quality evidence) and 70 and older (strong recommendation, low-quality evidence). Applies to men never diagnosed with prostate cancer, including those with urinary symptoms or BPH.	November 2014 (CMAJ)	A weak recommendation means the right choice depends more on a man's own values; explain possible benefits and harms; urinary symptoms alone are not a reason to screen under this guideline.
Canadian Urological Association	Offer PSA screening, through shared decision-making, to men with a life expectancy over 10 years. Start at 50 for most men and at 45 for men at higher risk, such as those with a family history. Repeat every 4 years if PSA is below 1 mcg/L (1 ng/mL) and every 2 years if 1 to 3 mcg/L. Stop at 70 (consider stopping at 60 if PSA is below 1 mcg/L). Recommends MRI before biopsy for men who would choose curative treatment.	April 2022 update (Canadian Urological Association Journal)	Ask about family history and life expectancy; explain that a raised PSA leads to more tests, often MRI and possibly biopsy; support the patient's own decision with his primary care provider.

Active surveillance. Active surveillance is planned monitoring of a low-risk cancer, with the intent to cure if it changes. A CUA-endorsed guideline names it the preferred strategy for low-risk localized prostate cancer (Gleason score 6 or lower, now often reported as Grade Group 1). Monitoring includes PSA testing every 3 to 6 months, a digital rectal exam yearly, a confirmatory biopsy within 6 to 12 months and further biopsies at least every 3 to 5 years. Treatment is offered if the cancer is reclassified as higher risk. Active surveillance differs from watchful waiting, which avoids curative treatment in people with a limited life expectancy (Morash et al., 2015). The nurse explains the schedule and listens for the anxiety of living with an untreated cancer.

Radical prostatectomy. A **radical prostatectomy** removes the whole prostate and some nearby tissue, including the seminal vesicles, and a urinary catheter stays in for a time after surgery (CCS, n.d.-h; section 28.2). Urinary leakage is common after the catheter comes out and improves over time for most men, whatever the management. Pelvic floor muscle training is widely taught, but a Cochrane review found the evidence for its benefit after prostatectomy conflicting (Anderson et al., 2015). The nurse teaches the exercises as ordered, sets realistic expectations, suggests containment products and protects the skin (Chapter 35). Erectile changes are covered in Chapter 29.

Radiation and androgen deprivation therapy. Radiation therapy can cause bladder effects (frequent or burning urination, leakage, blood in the urine) and bowel effects (diarrhea, rectal pain or bleeding), some months or years later (CCS, n.d.-d; Chapter 9). **Androgen deprivation therapy (ADT)** lowers androgens such as testosterone, which help prostate cancer cells grow. Drugs such as leuprolide are given as an injection or an implant under the skin,, and degarelix is another option (CCS, n.d.-b; Table 28.3). The CUA guideline on ADT adverse effects describes these effects and responses (Kokorovic et al., 2022):

- **Hot flashes:** help patients identify and avoid triggers.
- **Bone loss:** adequate calcium (1,200 mg a day from food and supplements) and vitamin D from the start, bone density testing when long-term ADT begins and drug treatment when fracture risk is high.
- **Metabolic effects:** weight and fat gain, higher risk of diabetes, higher lipids and cardiac risk. Blood pressure, glucose and lipids are checked every 6 to 12 months, with support to stop smoking, eat well and exercise.
- **Muscle loss and fatigue:** supervised resistance and aerobic exercise.
- **Mood, thinking and sexual effects:** watch for depression and cognitive decline; loss of libido affects up to 90% of men.

People with a prostate who are not men. Transgender women keep the prostate after gender-affirming surgery. Estrogen and anti-androgen therapy changes PSA levels, which may be lower than in cisgender men with prostate cancer. Transgender women appear to develop prostate cancer less often than cisgender men, and no established screening guidelines exist for them (Ismail et al., 2025). The nurse uses the person's name, pronouns and preferred anatomical terms and helps them discuss testing with their provider (Chapter 2; Chapter 29).

Bladder Cancer

Smoking is the main risk factor for bladder cancer; risk rises the more and longer a person smokes and falls after quitting. Risk also rises with age, especially after 65, and men are affected more often than women. Other risks include workplace chemicals (painting, rubber, metal, textile and dye manufacturing, transportation), arsenic in drinking water, past cyclophosphamide chemotherapy or pelvic radiation, and long-term bladder irritation, including from long-term catheters (CCS, n.d.-e).

Blood in the urine (Figure 28.5) is the most frequent sign of bladder cancer; it may be visible or found only on urinalysis, and early bladder cancer may cause no symptoms at all (CCS, n.d.-g). The CUA recommends imaging, especially with visible hematuria, with contrast CT as the first choice (Bhindi et al., 2021). Cystoscopy, a look inside the bladder with a scope, finds the tumour.

Figure 28.5 Visible blood in the urine (gross hematuria), with a dipstick that is positive for blood. Visible hematuria in an adult is always reported and investigated.

Resection and intravesical therapy. Transurethral resection of bladder tumour (TURBT) removes the tumour through a scope, with a sample of the muscle beneath it to show how deep the cancer goes. Patients with a presumed low-risk tumour are offered a single dose of chemotherapy into the bladder within 24 hours. For higher-risk non-muscle-invasive cancer, the standard is **intravesical BCG**, live, weakened bacillus Calmette-Guérin bacteria instilled into the bladder through a catheter, weekly for 6 weeks and then as maintenance for 1 to 3 years. Bladder cancer often recurs, so surveillance cystoscopy starts 3 months after TURBT (Bhindi et al., 2021).

Because BCG is a live organism, the Canadian monograph sets out precautions (Verity Pharmaceuticals, 2021):

- **Before:** treatment starts 2 to 3 weeks after resection, once the lining has healed. It is postponed after a traumatic catheterization, during visible hematuria, during a urinary tract infection and for fever until it is assessed. The patient takes no fluids for 4 hours before the treatment and for 2 hours after it.
- **Handling:** it is prepared aseptically in a biological safety cabinet, with personal protective equipment, and supplies are discarded as biohazardous waste.
- **After:** the patient holds the drug for 2 hours, then voids sitting down. For 6 hours, bleach is added to the toilet after each void and left 15 minutes before flushing. The patient avoids intercourse for a week after each instillation or uses a condom.
- **Effects:** frequency, urgency, painful voiding and hematuria usually settle within 2 days; fever and flu-like symptoms are also common. A fever above 39 °C lasting more than 12 hours needs urgent assessment, because systemic BCG infection can be fatal.

Cystectomy and ileal conduit. For high-risk cancer that does not respond to BCG, removal of the bladder (radical cystectomy) is the standard for patients fit for surgery (Bhindi et al., 2021). In an **ileal conduit**, a short piece of small intestine becomes a channel: the ureters drain into one end, and the other end forms a stoma, a **urostomy**, that drains urine into a pouch. Before surgery, the surgeon or a nurse specialized in wound, ostomy and continence (NSWOC) marks a site the patient can see, away from skin creases (Nurses Specialized in Wound, Ostomy and Continence Canada [NSWOCC], 2022). Ostomy principles are covered in section 25.6. Urostomy points include (NSWOCC, 2022):

- **Stoma:** moist and pinkish-red; swollen at first, shrinking over 6 to 8 weeks, so the barrier opening is re-measured.
- **Stents and mucus:** stents drain the ureters for anywhere from about 5 days to 2 weeks, sometimes longer; mucus threads in the urine are normal, because the conduit is intestine.
- **Pouching:** empty at one-third to one-half full, and use a night drainage bag; clean the skin with warm water.
- **Report:** urine flow that slows or stops, heavy bleeding, a marked change in stoma size or colour, blood or clots in the urine, gritty white deposits or wart-like skin changes near the stoma, and signs of infection.

CANADIAN CONTEXT

Prostate and Bladder Cancer in Canada

Bladder cancer is projected to affect 13,200 people in Canada in 2026: 9,900 men and 3,300 women. About 2,500 people will die from it, including 1,750 men and 720 women (CCS, n.d.-a). Together with prostate cancer, that is a large group of people living with urinary changes after treatment, often for many years.

These figures are reported by sex assigned at birth (CCS, n.d.-a). Transgender women and non-binary people with a prostate are therefore hard to see in the data, and research on their risk is limited (CCS, n.d.-f).

Several bladder cancer risks are preventable at the population level. Smoking is the main one. Workplace exposures in painting, rubber, metal, textile and dye manufacturing and transportation also matter, as does arsenic in drinking water (CCS, n.d.-e). Asking about work history, offering support to quit smoking and asking about drinking water sources are practical nursing actions.

Black men are diagnosed with prostate cancer more often than other men and tend to have faster-growing tumours and higher death rates from it (CCS, n.d.-f). Clear information about the screening options in Table 28.4, and fair access to testing and follow-up, are the nurse's focus (Chapter 2).

SCOPE IN PRACTICE

Catheters, Bladder Scans and Who Does What

- **Authority:** in Ontario, putting an instrument "beyond the opening of the urethra" is one of the controlled acts authorized to nursing, and inserting or irrigating a urinary catheter falls under it. RNs and RPNs need an order or directive unless they have authority to initiate; CNO allows initiation of this act only for limited purposes, such as assisting a patient with health management activities, and not in public hospitals (College of Nurses of Ontario [CNO], 2025a, 2025c). RNs and RPNs have authority to use portable bladder ultrasound for routine nursing assessments (CNO, 2025b). Catheter removal and scan-based catheterization protocols usually work through a medical directive (section 28.2; Chapter 1, section 1.3).
- **Competence:** CBI, manual irrigation of a blocked three-way catheter and BCG handling need specific knowledge and skill; a nurse not yet taught a skill seeks education and supervision first.
- **Context:** employer policy decides who manages CBI, hand-irrigates after urologic surgery or gives intravesical drugs; limiting these to RNs or urology nurses is an employer decision, not a CNO rule. An RPN consults the RN as a patient's needs change, and every nurse who sees clot retention, heavy bleeding or new confusion acts at once and escalates.
- **Across Canada:** the province or territory matters; practical nurses (PNs), called licensed practical nurses (LPNs) in some provinces, follow their own regulator and employer. CNO's revised Scope of Practice and Medication standards take effect March 1, 2027 (CNO, 2026).

Chapter 28 Summary

28.1 Urinary Tract Infection

- Cystitis causes dysuria, urgency, frequency and suprapubic pain; fever, rigors and flank or costovertebral angle tenderness suggest pyelonephritis, and signs of organ dysfunction suggest urosepsis, which needs immediate escalation.
- A midstream clean-catch specimen is collected after cleaning, and a catheter specimen comes from the sampling port, never the bag.
- Negative nitrite and leukocyte esterase results help rule out UTI, but a positive dipstick proves little; dipsticks are not used to diagnose UTI in long-term care or for adults over 65.

- Asymptomatic bacteriuria is common in older adults and is not screened for or treated, except in pregnancy and before urologic procedures that break the mucosa; a confused older adult without urinary or systemic signs needs a search for other causes.
- Nitrofurantoin, fosfomycin and, where resistance allows, trimethoprim-sulfamethoxazole are guideline choices for cystitis; pyelonephritis always needs a culture, and treatment is reassessed within about 3 days.
- Cranberry products probably reduce UTIs in women with recurrent UTIs but are not supported for older adults in institutions.

28.2 Urinary Catheters and CAUTI Prevention

- The length of time a catheter stays in is the most important risk factor for CAUTI, and many catheters have no appropriate indication.
- Appropriate indications include acute retention or obstruction, output monitoring in critical illness, selected surgery, open sacral or perineal wounds with incontinence, prolonged immobilization and comfort at the end of life; incontinence and convenience are not indications.
- Insertion is aseptic with the smallest catheter that drains well; the system stays closed, the bag stays below the bladder and off the floor, and catheters are not changed at fixed intervals.
- Daily review, nurse-driven removal protocols and alternatives such as intermittent and external catheters reduce catheter use.
- CAUTI is suspected with fever, suprapubic tenderness or flank pain; cloudy or smelly urine alone is not a reason to culture.

28.3 Urinary Retention and Incontinence

- Retention may be acute or chronic; causes include prostate enlargement, anticholinergic drugs and opioids, anesthesia, constipation and neurologic disease.
- A bladder scanner measures the post-void residual; the nurse follows the unit protocol's thresholds and prefers intermittent catheterization to reinserting an indwelling catheter.
- Incontinence affects 30% to 60% of people over 65 but is not a normal part of aging; the main types are stress, urgency, mixed, overflow and functional.
- Assessment includes a bladder diary, urinalysis, a search for temporary causes and, when needed, a PVR.
- Pelvic floor muscle training, bladder training, lifestyle changes and prompted voiding come first; antimuscarinics carry cognitive risk in older adults, and an indwelling catheter is never a substitute for continence care.

28.4 Kidney Stones

- Stones form when urine carries more of a substance than it can keep dissolved; calcium stones are most common, followed by uric acid, struvite (infection) and cystine stones.
- Renal colic causes sharp, wave-like pain in the back, side or groin, often with nausea and hematuria; the CUA recommends ultrasound with KUB X-ray first and low-dose CT when needed.
- The CUA guideline found that NSAIDs relieved renal colic better than morphine and recommends keeping opioid use low; any benefit of medical expulsive therapy is for 5 to 10 mm stones in the lower ureter.
- An obstructed, infected kidney is an emergency that needs antibiotics and urgent decompression by stent or nephrostomy; the nurse escalates at once.
- Prevention starts with a urine output of 2.5 L a day, normal dietary calcium, less sodium, moderate animal protein and diet advice matched to the stone type.

28.5 Benign Prostatic Hyperplasia and Prostate Surgery

- BPH causes voiding and storage symptoms; the CUA recommends a symptom score such as the IPSS, and complications include retention, infections, stones, hematuria and kidney damage.
- Alpha-blockers can cause dizziness and low blood pressure and are linked to floppy iris syndrome in eye surgery; 5-alpha reductase inhibitors take months to work, halve the PSA and should not be handled crushed by people who are or may become pregnant.

- During continuous bladder irrigation, the nurse adjusts the flow to the bleeding, calculates true urine output and watches for clot retention: no drainage, rising pain, a full bladder and leaking.
- For a blocked catheter, the nurse stops the inflow, checks the tubing, assesses the bladder, follows the protocol and calls urology if it does not clear.
- TUR syndrome is dilutional hyponatremia from absorbed irrigating fluid during monopolar TURP; new confusion, nausea, slow pulse and high blood pressure after TURP need urgent escalation.

28.6 Prostate and Bladder Cancer

- Prostate cancer is the most common cancer in men in Canada; an estimated 29,300 men will be diagnosed in 2026, and it is diagnosed more often in Black men.
- The Canadian Task Force (2014) recommends against PSA screening, while the CUA (2022) suggests offering it through shared decision-making; the nurse presents both accurately.
- Active surveillance is the preferred option for low-risk cancer; after prostatectomy, leakage is common and usually improves; ADT causes hot flashes, bone and muscle loss, metabolic, mood and sexual effects that need monitoring and exercise.
- Smoking is the main risk factor for bladder cancer, and visible hematuria needs investigation; intravesical BCG is a live agent with strict handling, voiding and fever precautions.
- After cystectomy with an ileal conduit, mucus in the urine is normal; a marked change in stoma colour, stopped urine flow or signs of infection are reported at once, and an NSWOC supports teaching.

Key Terms (60)

5-alpha reductase inhibitor (5-ARI): a drug that shrinks the prostate over months and lowers the PSA level by about half.

active surveillance: planned monitoring of a low-risk prostate cancer with PSA tests, examinations and biopsies, with treatment offered if the cancer changes.

alpha-blocker: a drug that relaxes smooth muscle in the prostate and bladder neck, improving urine flow; can cause dizziness and low blood pressure.

androgen deprivation therapy (ADT): treatment that lowers testosterone to slow the growth of prostate cancer.

asymptomatic bacteriuria (ASB): Bacteria in the urine at a significant count in a person with no signs or symptoms of urinary tract infection; usually not screened for or treated.

benign prostatic hyperplasia (BPH): non-cancerous enlargement of the prostate that can narrow the urethra.

bladder diary: A record of fluid intake, voids, urgency and leaks kept over several days to assess bladder problems.

bladder scanner: A portable ultrasound device that estimates the volume of urine in the bladder.

bladder training: A schedule of voiding at set times, with intervals lengthened gradually, combined with urge-suppression techniques.

catheter-associated urinary tract infection (CAUTI): A urinary tract infection in a person who has, or recently had, a urinary catheter.

clot retention: blockage of a urinary catheter by blood clots, so the bladder fills and cannot drain.

continuous bladder irrigation (CBI): constant flow of sterile 0.9% sodium chloride into and out of the bladder through a three-way catheter to prevent clots.

costovertebral angle: The angle on the back between the lowest rib and the spine; tenderness here suggests kidney involvement.

cystitis: Infection limited to the bladder, usually causing dysuria, urgency, frequency and suprapubic pain.

decompression: drainage of a kidney blocked by a stone, by ureteral stent or nephrostomy tube; urgent when the blocked kidney is infected.

dysuria: Pain or burning on urination.

external catheter: A device that collects urine from outside the body, such as a sheath over the penis or a suction device against the vulva.

functional incontinence: Leakage because a person cannot reach or use the toilet in time, for example because of limited mobility or dementia.

hematuria: blood in the urine, which may make it pink, red or brown or be seen only on testing.

ileal conduit: a channel made from a short piece of small intestine that carries urine from the ureters to a stoma on the abdomen.

indwelling urinary catheter: A tube passed into the bladder through the urethra or abdominal wall, held by a balloon and draining continuously into a closed bag.

intermittent catheterization: Passing a catheter into the bladder to drain it and then removing it; done with sterile technique in hospital and clean technique at home.

International Prostate Symptom Score (IPSS): a short questionnaire used to rate the severity of lower urinary tract symptoms and follow the response to treatment.

intraoperative floppy iris syndrome: a problem with the iris during cataract or glaucoma surgery linked to alpha-blockers such as tamsulosin.

intravesical BCG: live, weakened bacillus Calmette-Guérin bacteria instilled into the bladder to treat non-muscle-invasive bladder cancer.

leukocyte esterase: An enzyme from white blood cells; a positive dipstick result suggests pyuria.

lower urinary tract symptoms (LUTS): voiding symptoms (weak stream, hesitancy, straining, incomplete emptying) and storage symptoms (urgency, frequency, nocturia).

medical expulsive therapy (MET): use of a drug to help a ureteral stone pass; any benefit is for larger (5 to 10 mm) stones in the lower ureter.

midstream clean-catch specimen: A urine sample collected from the middle of the stream after the genital area is cleaned, to reduce contamination by skin bacteria.

nephrostomy tube: a tube placed through the skin of the back into the kidney to drain urine.

nitrites: Chemicals formed when certain bacteria convert nitrate in urine; a negative result does not rule out bacteriuria.

nocturia: waking at night to pass urine.

nurse-driven catheter removal protocol: A protocol, often a medical directive, that lets nurses remove a urinary catheter when no listed indication remains.

overflow incontinence: Leakage from a bladder that overfills because it cannot empty.

pelvic floor muscle training (PFMT): Repeated, correctly performed contractions of the pelvic floor muscles to improve continence.

post-void residual (PVR): The volume of urine left in the bladder right after voiding.

prompted voiding: A toileting approach for frail or cognitively impaired people in which staff check regularly, ask about the need to void, help to the toilet and give praise.

prostate-specific antigen (PSA): a protein made by the prostate and measured in a blood test, used in prostate cancer screening and follow-up.

pyelonephritis: Infection that has reached the kidney, usually with fever, rigors and flank pain or costovertebral angle tenderness.

pyuria: White blood cells in the urine; it occurs with both infection and asymptomatic bacteriuria.

radical prostatectomy: surgical removal of the whole prostate and some nearby tissue, including the seminal vesicles.

renal colic: severe, often wave-like pain in the back, side, lower abdomen or groin caused by a stone moving through or blocking the ureter.

retrograde ejaculation: flow of semen backward into the bladder rather than out through the urethra, common after TURP.

shock wave lithotripsy (SWL): use of shock waves from outside the body to break a stone into fragments that pass in the urine.

stress incontinence: Leakage of urine with coughing, sneezing, laughing, lifting or other exertion.

three-way catheter: an indwelling urinary catheter with separate channels for the balloon, drainage and irrigation inflow.

transurethral resection of bladder tumour (TURBT): removal of a bladder tumour through a scope passed into the bladder, with a sample of the muscle beneath.

transurethral resection of the prostate (TURP): removal of the inner prostate tissue with an electrical wire loop passed through the urethra.

transurethral resection syndrome (TUR syndrome): dilutional hyponatremia and fluid overload caused by absorption of irrigating fluid during transurethral surgery.

true urine output: during bladder irrigation, the total volume drained minus the volume of irrigation instilled.

ureteral stent: a thin, flexible tube placed in the ureter, from the kidney to the bladder, to keep urine draining.

ureteroscopy: passing a thin scope through the urethra and bladder into the ureter to break up or remove a stone.

urge incontinence: Leakage of urine with or right after a sudden, strong urge to void that is hard to delay; also called urgency incontinence.

urinary incontinence: Any involuntary leakage of urine.

urinary retention: Inability to empty the bladder completely or at all; it may be acute or chronic.

urinary tract infection (UTI): An infection anywhere in the urinary tract, from the urethra to the kidneys.

urine culture: A laboratory test that identifies bacteria in urine, counts them and tests their susceptibility to antibiotics.

urolithiasis: stones anywhere in the urinary tract.

urosepsis: Sepsis that starts from an infection of the urinary tract.

urostomy: a stoma that drains urine into a pouch on the abdomen.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Dorothy Kowalchuk (Questions 1–4): Dorothy Kowalchuk, 86, lives in a long-term care home in Nova Scotia; she has moderate dementia, walks with a walker and is usually continent with reminders, and today the licensed practical nurse (LPN) finds her sleepier and more confused than usual since yesterday, with dark, strong-smelling urine, a urine dipstick (done by a care aide) positive for leukocyte esterase and nitrites, no bowel movement for 4 days, poor fluid intake, no complaints of pain on voiding, a temperature of 37.2 °C, blood pressure 118/70 mm Hg, heart rate 84 beats/min and respiratory rate 18 breaths/min.

1. [CORE] Which interpretation of Mrs. Kowalchuk's positive dipstick is most accurate?

a. It confirms a bladder infection, which is the most likely explanation for her new confusion, sleepiness and dark urine.

b. It suggests pyelonephritis, because both the nitrite and leukocyte esterase results were positive today.

c. It cannot separate infection from bacteriuria, which is common in residents, so other causes need to be assessed.

d. It is a false result caused by her concentrated urine, so it can be ignored and the test repeated tomorrow.

Answer: c — As many as half of long-term care residents have bacteriuria without infection, and dipsticks are not used to diagnose UTI in this setting, so a positive result does not explain her change in health (section 28.1, Asymptomatic Bacteriuria and Lifespan box). Option a assumes a UTI that has not been shown. Option b is wrong because pyelonephritis is recognized by fever, rigors and flank pain, not by dipstick results. Option d is wrong because concentration does not make both pads falsely positive, and repeating a dipstick would not help.

2. [CORE] Which assessment should the LPN do next to find the cause of Mrs. Kowalchuk's change?

a. Assess her abdomen and bowel pattern, fluid intake, recent medication changes and her attention and thinking.

b. Collect a midstream clean-catch urine specimen so that a culture can be sent to the laboratory today.

c. Insert an in-and-out catheter to obtain a clean specimen, because she cannot follow collection steps.

d. Check her temperature every 15 minutes for the next 2 hours so that a fever is detected as soon as it begins to rise.

Answer: a — The nurse looks for other causes of a change in an older adult, such as constipation, dehydration, medications and delirium, before assuming a UTI (section 28.1, Lifespan box; section 8.2). She has not had a bowel movement in 4 days and has been drinking little. Options b and c are wrong because she does not meet minimum criteria for a culture, and catheterizing to collect urine adds risk. Option d is excessive for a resident with stable vital signs; regular reassessment is enough.

3. [CORE] Mrs. Kowalchuk's daughter visits and says, "Mom always gets confused with a bladder infection. Please send her urine and get her started on antibiotics." Which response by the LPN is best?

a. "I understand. I'll collect a urine sample now and ask the nurse practitioner for an antibiotic today."

b. "Antibiotics are never used for older adults in long-term care, so we will not be testing her urine."

c. "The dipstick was positive, so the nurse practitioner will decide about antibiotics once the culture results come back from the lab."

d. "You know her well. Many residents have bacteria in the urine without infection, so we're checking other causes first."

Answer: d — Choosing Wisely Canada advises staff to understand family concerns and explain the other possible causes and the reason for any test before collecting a culture (section 28.1, Lifespan box). Option a agrees to a test and treatment that are not indicated. Option b is false; antibiotics are used when an infection meets criteria. Option c treats the dipstick as meaningful and implies antibiotics are likely, which is misleading.

4. [CORE] The LPN reports to the nurse practitioner (NP). Which statement best fits the situation?

a. "Mrs. Kowalchuk has a positive dipstick and dark urine; can I get an order for an antibiotic for a UTI?"

b. "Mrs. Kowalchuk is more confused, has had no bowel movement in 4 days and is drinking poorly; vital signs are stable and she has no urinary symptoms. I'd like you to assess her."

c. "Mrs. Kowalchuk is more confused today, so I'll recheck her at the end of my shift and call you if she gets worse."

d. "Mrs. Kowalchuk's dipstick is positive, so I'd like an order to send a urine culture before you decide on treatment."

Answer: b — A situation, background, assessment, recommendation (SBAR) report gives the change, the relevant findings (including the absence of urinary symptoms and fever) and a clear request (section 28.1; section 6.2). Option a asks for treatment based on a dipstick, which is not used to diagnose UTI. Option c delays reporting a change in mental status. Option d asks for a culture that minimum criteria do not support.

5. [CORE] The nurse teaches a woman to collect a midstream clean-catch urine specimen. Which statement shows she understands?

a. "I'll clean with the wipes, start peeing into the toilet, then move the cup into the stream to catch the middle part."

b. "I'll fill the cup with the very first urine of the day, because that part has the most bacteria in it."

c. "I'll clean from back to front with a single wipe, then catch all of my urine in the container so that none of it is missed."

d. "I'll leave the cup in the bathroom until the afternoon, when I can bring it to the lab with my other papers."

Answer: a — The first part of the stream flushes skin bacteria away, so the midstream portion is collected after cleaning with downward strokes (section 28.1, Specimens and Urinalysis). Option b collects the first urine, which is more likely to be contaminated. Option c wipes in the wrong direction and collects the whole void. Option d is wrong because the specimen must reach the laboratory within 2 hours or be refrigerated.

6. [CORE] A urine culture is ordered for a patient with an indwelling catheter who has a new fever. How should the nurse collect the specimen?

a. Pour urine from the drainage bag into a sterile container, because the bag holds the most recently produced urine.

b. Disconnect the catheter from the tubing and let urine drip from the catheter end into a sterile cup.

c. Disinfect the sampling port, clamp the tubing briefly below it and withdraw urine with a sterile syringe.

d. Remove the catheter and ask the patient to provide a midstream specimen within the next 2 hours.

Answer: c — Catheter specimens are taken aseptically from the sampling port, keeping the system closed (section 28.1, Specimens and Urinalysis; section 4.2). Option a is wrong because urine for culture is never taken from the bag. Option b opens the closed system, which raises infection risk. Option d delays the culture and removes a catheter that may still be needed, without an order.

7. [CORE] A patient admitted with cystitis develops new findings. Which finding most strongly suggests the infection has reached the kidney?

a. Burning on urination and needing to void every hour

b. Cloudy urine with a strong odour noted in the drainage bag and urinal this morning

c. Pink-tinged urine and mild discomfort above the pubic bone

d. A temperature of 38.9 °C with chills and tenderness at the costovertebral angle

Answer: d — Fever, rigors and flank or costovertebral angle tenderness show that infection has moved beyond the bladder, as in pyelonephritis (section 28.1, Cystitis, Pyelonephritis and Urosepsis). Options a and c are bladder symptoms of cystitis. Option b is not a reliable sign of infection at all.

8. [CORE] A 52-year-old woman with type 2 diabetes has a urine culture sent with her routine blood work. It grows more than 10^8 CFU/L of one organism. She has no urinary symptoms and no fever. What does the nurse expect?

a. A short course of an antibiotic, because diabetes raises her risk of developing a kidney infection later

b. No antibiotic, because guidelines advise against treating bacteriuria without symptoms in diabetes

c. A repeat culture every month until the bacteria clear, to prevent pyelonephritis from developing

d. Admission for IV antibiotics, because of the high colony count and her diabetes

Answer: b — This is asymptomatic bacteriuria, and the IDSA guideline recommends against screening for or treating it in people with diabetes (section 28.1, Asymptomatic Bacteriuria). Option a treats bacteriuria that does not need treatment and risks adverse effects and resistance. Option c is screening, which is not recommended. Option d is wrong because a colony count without symptoms is not an infection.

9. [CORE] A 34-year-old woman is starting nitrofurantoin for cystitis. Which statement shows she needs more teaching?

a. "I'll take every dose as prescribed for the number of days on the label."

b. "I'll call the clinic if I get a fever, pain in my side or back, or start throwing up."

c. "I'll drink fluids through the day unless I've been told to limit them."

d. "I'll keep any pills I have left over for the next time I get these symptoms."

Answer: d — Saving leftover antibiotics leads to self-treatment without assessment and fuels resistance, so she needs more teaching (section 28.1, Treatment and Teaching; section 4.5). Options a, b and c are correct: take the antibiotic as prescribed, seek care if signs of kidney infection appear, and drink fluids unless restricted.

10. [CORE] Which situations are appropriate indications for an indwelling urinary catheter? Select all that apply.

a. A patient with acute urinary retention from bladder outlet obstruction

b. A critically ill patient in septic shock who needs hourly urine output

c. A patient with dementia who is incontinent at night

d. A patient receiving comfort care at the end of life who prefers a catheter

e. A patient who can void but needs a urine sample for culture

f. An incontinent patient with an open stage 4 sacral pressure injury

g. A patient with delirium who keeps getting out of bed to use the toilet

Answer: a, b, d, f — Acute retention or obstruction, accurate output measurement in critical illness, comfort at the end of life and helping an open sacral or perineal wound heal when the patient is incontinent are appropriate indications (section 28.2, Indwelling Catheters). Incontinence (c) is managed with continence care, not a catheter. Collecting urine from a patient who can void (e) is an inappropriate use. Delirium (g) is not an indication, and a catheter can worsen delirium and immobility.

11. [CORE] The nurse sees a care aide helping a catheterized patient walk in the hall. Which action needs correction?

a. The care aide carries the drainage bag at waist height as they walk together.

b. The care aide keeps the tubing free of kinks and loops during the walk.

c. The care aide has emptied the bag into the patient's own labelled measuring container.

d. The care aide reminds the patient not to pull on the catheter or tubing.

Answer: a — The bag must stay lower than the bladder throughout, including during walks, so urine does not flow back (section 28.2, Indwelling Catheters). Options b, c and d are correct practices: unobstructed flow, a separate container for each patient and preventing traction.

12. [CORE] A patient has had an indwelling catheter for 4 days after a hip fracture. Which finding should the nurse report as a possible catheter-associated urinary tract infection?

a. Urine in the bag that is cloudy and darker than yesterday, with no other changes

b. A new temperature of 38.6 °C with suprapubic tenderness and no other source found

c. Sediment in the tubing that the nurse notices while emptying the bag this morning

d. A urine culture sent on admission, before the catheter, that grew a small amount of mixed organisms

Answer: b — CAUTI is suspected when a catheterized patient has signs such as fever, suprapubic tenderness or costovertebral angle pain (section 28.2, Recognizing CAUTI). Cloudy or dark urine (a) or sediment (c) alone is not a reason to culture. Option d is an old result, taken before the catheter, that does not indicate a current infection.

13. [CORE] An older man's indwelling catheter was removed at 0600. At 1300 he has not voided, says he feels "full," and his lower abdomen is firm above the pubic bone. What should the nurse do first?

a. Encourage him to drink two large glasses of water to help him void.

b. Reinsert an indwelling catheter so that the bladder does not overfill again.

c. Scan his bladder as the unit protocol allows and report the result.

d. Document the findings and reassess him at the end of the shift.

Answer: c — The findings suggest retention after catheter removal; the nurse measures the bladder volume as the protocol allows and acts on the result, often with intermittent catheterization rather than an indwelling catheter (section 28.3, Urinary Retention). Option a adds volume to a bladder that may not be able to empty. Option b skips assessment and reinserts a catheter, which the post-removal algorithm aims to avoid. Option d delays care and risks bladder injury.

14. [CORE] An 80-year-old woman with severe hip arthritis says, "I know when I need to go, but by the time I get my walker and reach the bathroom, I've already leaked." Which plan best addresses this type of incontinence?

a. Teach her to do pelvic floor contractions several times a day for 12 weeks.

b. Offer help to the toilet on a regular schedule and keep a commode and call bell close by.

c. Ask the prescriber to start an antimuscarinic medication to calm her overactive bladder muscle.

d. Measure her post-void residual after each void for the next 24 hours.

Answer: b — She has functional incontinence: she senses the need to void but cannot reach the toilet in time because of limited mobility (section 28.3, Urinary Incontinence; Table 28.2). Scheduled toileting help, a nearby commode and a call bell target the cause. Option a treats stress incontinence. Option c treats urgency incontinence and adds anticholinergic risk. Option d is used when emptying is in question, which her history does not suggest.

15. [CORE] An 84-year-old man started oxybutynin 1 week ago for urgency incontinence. Which finding should the nurse report to the prescriber?

a. He is voiding every 3 hours during the day.

b. He reports one leak in the past 2 days.

c. He has a slightly dry mouth after meals.

d. He has new confusion and has not had a bowel movement in 4 days.

Answer: d — Antimuscarinics such as oxybutynin can cause confusion and constipation in older adults and add to anticholinergic burden, so new confusion with constipation needs prompt reporting (section 28.3, Urinary Incontinence). Options a and b suggest the treatment is helping. Option c is a common, mild adverse effect that can be managed with sips of water and mouth care.

16. [CORE] An RPN on a medical unit finds that a patient with a urinary catheter has a temperature of 39.1 °C, heart rate 122 beats/min, blood pressure 88/52 mm Hg and new confusion. What should the RPN do first?

a. Call for help at once through the rapid response process and inform the RN.

b. Collect a urine specimen from the sampling port and send it for culture.

c. Remove the catheter, because it is the likely source of the infection.

d. Give acetaminophen as ordered for the fever and recheck all of the vital signs in 1 hour.

Answer: a — These findings suggest sepsis, possibly from the urinary tract. Every nurse who notices deterioration acts and escalates at once, and the RPN consults the RN as the patient's needs change (section 28.1, Cystitis, Pyelonephritis and Urosepsis; Chapter 6). Options b and c may be part of later care, but they do not come before escalation. Option d delays treatment of a possibly septic patient.

17. [CORE] An RPN is asked to perform intermittent catheterization for a patient with retention. The order is in place, but the RPN has not performed the procedure since school. Using CNO's scope framework, what should the RPN do?

a. Perform it, because an order exists and RPNs are authorized for the controlled act.

b. Decline and tell the charge nurse that intermittent catheterization is outside the scope of practice of RPNs.

c. Ask an RN to perform it every time it is needed for this patient from now on.

d. Tell the charge nurse and get support or supervision to perform it safely, following employer policy.

Answer: d — CNO's Scope of Practice standard asks nurses to have authority, competence and context; here the RPN has authority (an order and a controlled act authorized to RPNs) but needs to confirm competence, so the RPN seeks support as employer policy allows (CNO, 2025c; Chapter 1, section 1.3; section 28.6, Scope in Practice box). Option a ignores competence. Option b is wrong because the act is within RPN scope with an order. Option c hands off the task without building the needed competence. Employer policy and province or territory also matter.

18. [RN] A 30-year-old woman has dysuria and frequency. Her urinalysis shows positive leukocyte esterase and negative nitrite, and the culture grows *Enterococcus faecalis* at 10^8 CFU/L. Which explanation for the negative nitrite is most accurate?

a. The bacteria were not in the bladder long enough to multiply into a significant count.

b. *Enterococcus* does not convert nitrate to nitrite, so the nitrite test stays negative.

c. A negative nitrite result means the culture was probably contaminated during collection.

d. Leukocyte esterase blocks the nitrite reaction when both are present in the same sample.

Answer: b — The nitrite test depends on bacteria that convert nitrate to nitrite, and *Enterococcus* does not, so a negative nitrite does not exclude infection (section 28.1, Going Deeper box). Option a is wrong because the count of 10^8 CFU/L is significant. Option c misreads the meaning of a negative nitrite. Option d is not how the reagent pads work.

19. [RN] **A medical unit uses a nurse-driven catheter removal directive. Which patient's catheter should the nurse remove under the directive?**

a. A man receiving continuous bladder irrigation after transurethral resection of the prostate

b. A woman admitted with pneumonia who had a catheter placed in the emergency department "to monitor output," and who is now stable and walking

c. A man with a long-term catheter that was in place before admission for chronic retention

d. A woman with an open stage 4 sacral pressure injury and ongoing incontinence

Answer: b — A catheter placed for output monitoring in a patient who is now stable and walking has no remaining indication, so the directive supports removal (section 28.2, Indwelling Catheters; Clinical Safety box). Continuous bladder irrigation (a), a long-term catheter present before admission (c) and an open sacral wound with incontinence (d) are listed indications to keep the catheter.

20. [RN] **Six hours after knee surgery under spinal anesthesia, a patient voids 150 mL and has no discomfort. A bladder scan right afterward shows 560 mL. The unit protocol defines retention as a PVR over 500 mL in a patient without symptoms or over 300 mL in one who has symptoms. What should the nurse do?**

a. Repeat the scan in 6 hours, because the patient has no discomfort.

b. Insert an indwelling catheter and keep it until the patient is walking.

c. Perform intermittent catheterization as the protocol directs and reassess voiding.

d. Encourage the patient to drink more fluid to stimulate another void within an hour.

Answer: c — A PVR above 500 mL meets the protocol's definition of retention even without symptoms, and intermittent catheterization is preferred to an indwelling catheter (section 28.3, Urinary Retention). Option a waits while the bladder overfills; many patients feel no urge after spinal anesthesia. Option b uses an indwelling catheter when intermittent drainage is preferred. Option d adds volume to a bladder that is not emptying.

Case: Gerald Fontaine (Questions 21–26): Gerald Fontaine, 76, returned to the surgical unit at 14:00 after a monopolar transurethral resection of the prostate (TURP) for benign prostatic hyperplasia. He has a three-way catheter with continuous bladder irrigation (CBI) of 0.9% sodium chloride. His preoperative serum sodium was 139 mmol/L. At 17:00 he tells the nurse, "It feels like I have to pee, and it's getting worse." The drainage is dark red with several clots, and only 50 mL has drained in the past hour although the irrigation is running at the ordered rate. His lower abdomen is firm above the pubic bone, and urine is leaking around the catheter onto the bed pad. Heart rate 104, blood pressure 148/86 mm Hg, respiratory rate 20, temperature 36.8 °C, SpO2 96% on room air.

21. [CORE] **Which findings should the nurse recognize as cues that the catheter may be blocked? Select all that apply.**

a. Dark red drainage containing several clots

b. Only 50 mL drained in an hour while the irrigation runs at the ordered rate

c. A firm lower abdomen above the pubic bone

d. Urine leaking around the catheter onto the bed pad

e. A temperature of 36.8 °C

f. An SpO2 of 96% on room air

g. A strong urge to void that is getting worse

Answer: a, b, c, d, g — Clots in the drainage, drainage far below the irrigation running in, a firm, distended bladder, leaking around the catheter and a growing urge to void are all signs of clot retention (section 28.5, Surgery and Continuous Bladder Irrigation). A normal temperature (e) does not point to blockage; it makes infection less likely at this stage. An SpO2 of 96% (f) is normal and unrelated to catheter patency.

22. [CORE] **Which explanation best fits Mr. Fontaine's findings?**

a. Bladder spasms from cold irrigation fluid, with the catheter still draining freely

b. Clot retention, with irrigation fluid collecting in a bladder that cannot drain

c. Expected bleeding after the resection that needs no change in his care

d. A urinary tract infection caused by the three-way catheter placed in surgery

Answer: b — Fluid is going in but not coming out, the bladder is firm and urine is bypassing the catheter, which together point to clot retention (section 28.5). Spasms (a) cause urgency and leaking, but a freely draining catheter would not let the bladder fill and harden; blockage is ruled out first. Some bleeding is expected after TURP (c), but clots that stop drainage need action. Infection (d) is unlikely within 3 hours of surgery and would not explain the lack of drainage.

23. [CORE] What should the nurse do first?

a. Increase the irrigation rate so the extra fluid can flush the clots through the catheter

b. Deflate the catheter balloon and pull the catheter back slightly to free the clot

c. Stop the irrigation inflow and check the catheter and tubing for kinks, loops and clots

d. Give the ordered as-needed antispasmodic and reassess the drainage in 1 hour

Answer: c — When drainage is less than the irrigation going in, the nurse turns off the inflow so the bladder stops filling, then checks the tubing before taking further steps under the protocol (section 28.5). Raising the rate (a) pushes more fluid into a blocked bladder. The nurse does not deflate, reposition or replace a catheter after urologic surgery without the urologist's authorization (b). An antispasmodic (d) does not clear a blockage, and waiting an hour lets the bladder overfill.

24. [CORE] The urology resident clears the clots, and the irrigation is restarted. Over the next 4 hours, 4,200 mL of irrigation is instilled and 4,650 mL drains. The drainage is light pink, and Mr. Fontaine rates his pain 2 out of 10. What is his true urine output for these 4 hours?

a. 4,200 mL

b. 8,850 mL

c. 4,650 mL

d. 450 mL

Answer: d — True urine output is the total drained minus the irrigation instilled: 4,650 − 4,200 = 450 mL, about 112 mL an hour, which is adequate (section 28.5). 4,200 mL (a) is the irrigation volume. 8,850 mL (b) wrongly adds the two volumes. 4,650 mL (c) is the total drainage, which includes the irrigation fluid.

25. [RN] At 21:00, Mr. Fontaine is restless and asks why he is "at the train station." He has vomited once. Heart rate 52, blood pressure 176/96 mm Hg. His serum sodium is now 124 mmol/L. Which hypothesis should the nurse treat as the priority?

a. Transurethral resection syndrome from irrigation fluid absorbed during surgery

b. Postoperative delirium caused by unfamiliar surroundings, disrupted sleep and pain

c. Hypovolemia from bleeding into the bladder after the resection

d. Nausea and vomiting as delayed side effects of the spinal anesthesia

Answer: a — New confusion, vomiting, a slow heart rate, high blood pressure and a sodium that has fallen from 139 to 124 mmol/L after monopolar TURP fit TUR syndrome, a dilutional hyponatremia with fluid overload (Going Deeper box, section 28.5). Delirium (b) is possible in an older adult, but it does not explain the falling sodium, and an acute cause must be found first (Chapter 8). Hypovolemia from bleeding (c) would cause a fast heart rate and low blood pressure, not the opposite. Anesthesia (d) does not explain the confusion, slow pulse or low sodium.

26. [CORE] Which action should the nurse take first?

a. Give the ordered as-needed antiemetic, then recheck his orientation and vital signs at the next scheduled assessment

b. Notify the surgeon urgently using SBAR, reporting the sodium, vital signs, change in orientation and fluid totals

c. Increase the maintenance infusion of 0.9% sodium chloride to bring his serum sodium back up

d. Encourage oral fluids to settle his stomach and help clear any remaining clots from the bladder

Answer: b — TUR syndrome can progress to hypotension and cardiac arrest, so the nurse escalates at once with the time of onset, vital signs, sodium, irrigation in and true urine output (section 28.5; Chapter 6). An antiemetic and a later recheck of orientation and vital signs (a) delay treatment. Changing the infusion (c) is not within the nurse's authority without an order, and sodium must be corrected carefully under the prescriber's direction (section 3.4). Extra oral fluid (d) adds free water and could lower the sodium further.

27. [CORE] A patient in the emergency department has a 4-mm stone in the lower ureter and severe colicky pain. Which statement about pain relief reflects the Canadian Urological Association guideline?

a. Opioids are the first choice, because NSAIDs are too weak to relieve the pain of a moving stone

b. Pain relief should be held until a CT scan has confirmed the exact size and position of the stone

c. Once medical expulsive therapy has started, the stone will pass quickly and analgesia can stop

d. NSAIDs relieved renal colic better than morphine in comparisons, and opioid use should be kept low

Answer: d — The CUA guideline reports that NSAIDs outperformed morphine and recommends minimizing opioids for renal colic, with patient teaching (section 28.4, Renal Colic and Care). Opioids are not the preferred first choice (a). Pain relief is never held for imaging (b). Medical expulsive therapy is not a pain treatment, and its benefit is limited to larger stones (c).

28. [CORE] A patient who has had two calcium oxalate stones asks how to prevent another. Which advice matches the Canadian Urological Association guideline?

a. Cut out milk, cheese and other calcium-rich foods to lower the calcium in the urine

b. Take vitamin C supplements of at least 1,000 mg each day to keep the urine acidic

c. Drink enough, mostly water, to pass about 2.5 L of urine every day

d. Drink about 1 L of fluid a day, because larger amounts dilute the blood sodium

Answer: c — The CUA recommends that stone formers aim for a urine output of 2.5 L a day, with water as the first-line choice (section 28.4, Preventing Recurrence). Dietary calcium is not restricted; the goal is 1,000 to 1,200 mg a day (a). Vitamin C supplements above 1,000 mg a day are not recommended because they can raise urine oxalate (b). One litre a day (d) is far below the target and leaves the urine concentrated.

29. [CORE] A patient is going home with a ureteral stent after ureteroscopy. Which statement shows that the teaching was effective?

a. "The stent will dissolve on its own, so I don't need any follow-up for it."

b. "Needing to pass urine often and urgently is common while the stent is in, and I know when it will come out."

c. "If I feel the urge to void often, it means the stent has moved out of place, and I should go to the emergency department."

d. "Because the stone is gone, I can stop drinking extra fluids as soon as I get home."

Answer: b — Stents commonly cause urinary symptoms such as frequency and urgency, and the patient needs to know the stent is temporary and when it will be removed (section 28.4). A stent does not dissolve and must be removed or changed as planned (a). Frequency and urgency are expected stent symptoms, not a sign of movement in themselves (c). Fluid remains the main way to prevent recurrence (d).

30. [CORE] A 68-year-old man is starting tamsulosin for benign prostatic hyperplasia. Which teaching point should the nurse include?

a. "Get up slowly, and don't drive or do anything hazardous for 12 hours after your first dose."

b. "Crush the tablet and mix it into applesauce if it is hard to swallow, so the drug can work faster."

c. "This drug shrinks the prostate, so it will take about 6 months before you notice any change in your stream."

d. "Your PSA level will fall by about half on this drug, so your doctor will need to double the result."

Answer: a — The tamsulosin monograph warns that blood pressure can drop, especially at the start, and advises no driving or hazardous tasks for 12 hours after the first dose (section 28.5, Drugs for BPH). Controlled-release tablets must be swallowed whole (b). Shrinking the prostate over about 6 months (c) and halving the PSA (d) describe 5-alpha reductase inhibitors such as finasteride, not alpha-blockers.

31. [CORE] A patient taking finasteride says his daughter-in-law, who is pregnant, sometimes sets out his pills. What should the nurse teach?

a. Finasteride affects only the prostate, so it poses no risk to anyone else in the home

b. She can handle the whole coated tablets but should not touch any that are crushed or broken

c. He should stop taking finasteride until the baby is born to protect his daughter-in-law

d. She must wear gloves to touch the pill bottle and should wash the bottle after each use

Answer: b — The finasteride monograph states that people who are or may become pregnant should not touch crushed or broken tablets, and that the coating stops contact with the drug when whole tablets are handled (section 28.5; Table 28.3). The drug can affect a developing fetus, so (a) is wrong. Stopping treatment (c) is unnecessary and is a decision for the prescriber. Gloves for the bottle (d) are not required.

32. [CORE] A patient is going home 2 days after TURP. Which statement shows a need for more teaching?

a. "I'll drink 1 to 2 litres a day unless my doctor tells me to limit fluids."

b. "If my urine looks cloudy after sex, it's because semen can now flow back into my bladder."

c. "I'll eat more fibre so I don't strain when I have a bowel movement."

d. "I'll be back at the gym lifting weights later this week, since I feel fine."

Answer: d — Heavy lifting (more than 7 kg) and strenuous exercise are avoided for about 2 weeks after TURP because they can cause bleeding (section 28.5). Drinking 1 to 2 L a day (a), understanding retrograde ejaculation (b) and preventing constipation (c) are correct.

33. [CORE] An RPN on a surgical unit in Ontario is caring for a patient on continuous bladder irrigation whose catheter has stopped draining. The unit protocol allows manual irrigation after urologic surgery only by RNs. What should the RPN do?

a. Stop the irrigation inflow, check the tubing and bladder volume, and get the RN and the urology team involved at once

b. Hand-irrigate the catheter, because RPNs in Ontario are authorized to put an instrument beyond the opening of the urethra

c. Wait for the next RN assessment, because a patient on CBI is outside the RPN's scope of practice

d. Remove the three-way catheter and insert a new one to restore drainage, then report the change

Answer: a — The RPN acts at once within their own role: stopping the inflow, checking for kinks and assessing the bladder, then bringing in the RN and urology as the patient's needs change (Scope in Practice box, section 28.6; section 28.5). Legal authority (b) is not enough when the employer limits the skill to RNs; context matters. Waiting (c) is unsafe; every nurse who notices deterioration acts and escalates, and CNO has no rule placing CBI outside RPN practice. Nurses do not replace a catheter after urologic surgery without the urologist's authorization (d).

34. [CORE] A 57-year-old man with no symptoms asks the nurse whether he should have a PSA test. Which response is most accurate?

a. "Every major Canadian group now recommends a yearly PSA test for all men from age 50, so you are already due for one."

b. "PSA testing is recommended only for men who are having trouble passing urine, so you would not need one until symptoms start."

c. "Canadian groups differ, so let's talk through the benefits and harms and what matters to you before you see your provider."

d. "PSA testing is no longer done in Canada, because an MRI scan of the prostate has now replaced the blood test."

Answer: c — The Canadian Task Force (2014) recommends against PSA screening, while the CUA (2022) suggests offering it through shared decision-making to men with a life expectancy over 10 years; the nurse presents both and supports the man's own decision (section 28.6; Table 28.4). No Canadian body recommends yearly testing for everyone from age 50 (a). The Task Force recommendation applies to men with urinary symptoms too, and urinary symptoms are not a screening indication (b). PSA is still used; the CUA recommends MRI before biopsy, not instead of PSA (d).

35. [CORE] A man with low-risk prostate cancer has chosen active surveillance. Which statement shows he understands it?

a. "I'll have regular PSA tests and biopsies, and treatment is offered if the cancer changes."

b. "Active surveillance means my cancer has been cured without any treatment."

c. "Since nothing is being done, I won't need any more tests unless I get symptoms."

d. "This is the same as watchful waiting, which is used when cure is no longer the goal."

Answer: a — Active surveillance is planned monitoring with PSA tests, rectal exams and biopsies, with the intent to cure if the cancer is reclassified to higher risk (section 28.6, Prostate Cancer). The cancer is still present (b). Monitoring is scheduled, not symptom-driven (c). Watchful waiting (d) is different: it avoids treatment with curative intent in people with a limited life expectancy.

36. [CORE] The nurse is teaching a patient who has just had intravesical BCG instilled for bladder cancer. Which instructions are correct? Select all that apply.

a. Keep the drug in the bladder for 2 hours, as instructed.

b. Sit down to void when emptying the bladder after treatment.

c. For 6 hours after treatment, add bleach to the toilet after each void and wait 15 minutes before flushing.

d. Drink at least 1 L of water just before the instillation to protect the bladder.

e. Report a fever above 39 °C that lasts more than 12 hours.

f. Avoid intercourse for 1 week after each treatment, or use a condom during the whole course and for 1 week beyond it.

g. A fever after BCG is expected, so there is no need to call about any fever.

Answer: a, b, c, e, f — The VERITY-BCG monograph directs a 2-hour retention, voiding sitting down, bleach in the toilet for 6 hours, reporting a high or prolonged fever and protecting sexual partners (section 28.6, Bladder Cancer). Fluids are avoided for 4 hours before the instillation and for 2 hours after it (d). Mild flu-like symptoms are common, but a high or prolonged fever may signal systemic BCG infection, which can be fatal (g).

37. [CORE] On day 3 after cystectomy with an ileal conduit, which finding should the nurse report at once?

a. Mucus threads in the urine collecting in the pouch

b. A swollen, moist, pinkish-red stoma that bleeds slightly when cleaned

c. A dark purple-black stoma with no urine draining for the past 2 hours

d. Two small stents coming out of the stoma and draining urine

Answer: c — A marked change in stoma colour and urine flow that slows or stops must be reported at once (section 28.6, Bladder Cancer). Mucus threads are normal because the conduit is made from intestine (a). A swollen, moist, pinkish-red stoma with slight bleeding on cleaning is expected early after surgery (b). Stents draining urine are expected for days to weeks after surgery (d).

38. [CORE] Three hours after TURP, a patient's drainage is bright red with large clots even though the nurse has increased the irrigation rate. His heart rate has risen from 82 to 118, his blood pressure has fallen from 132/80 to 98/60 mm Hg, his lips and nail beds look pale, and his skin is clammy. What should the nurse do?

a. Increase the irrigation rate again and recheck the drainage colour and vital signs in 1 hour

b. Stop the irrigation completely so that the clots can seal the bleeding vessels in the prostate

c. Encourage oral fluids and reassure him that heavy bleeding is expected on the day of surgery

d. Escalate at once through the rapid response process, because these signs suggest active bleeding

Answer: d — Bright red drainage with clots that does not lighten with more irrigation, together with a rising heart rate, falling blood pressure, pallor and clammy skin, suggests hemorrhage and early shock; the nurse escalates immediately (section 28.5; Chapter 6). Waiting an hour (a) delays treatment. Stopping irrigation (b) lets clots block the catheter. Some bleeding is expected, but these vital sign changes are not (c).

39. [RN] A patient with a known 6-mm stone in the upper ureter now has a temperature of 39.2 °C, rigors, a heart rate of 124, a blood pressure of 88/52 mm Hg and a serum creatinine higher than on admission. Which plan should the nurse anticipate?

a. Start tamsulosin as medical expulsive therapy and observe for 4 to 6 weeks to see whether the stone passes

b. Book shock wave lithotripsy for later today to break the stone into fragments small enough to pass

c. Begin sepsis care with antibiotics and prepare for urgent drainage of the kidney by ureteral stent or nephrostomy tube

d. Give IV fluids and analgesia overnight and repeat the CT scan in the morning before deciding on any procedure

Answer: c — This is an obstructed, infected kidney with sepsis. The CUA states that obstructive pyelonephritis needs early goal-directed therapy with timely decompression by stent or nephrostomy, alongside sepsis care (section 28.4; Chapter 4). Medical expulsive therapy and observation (a) are for stable patients without infection. Treating the stone itself (b) is not the first step; the CUA calls for timely decompression of the blocked, infected kidney. Waiting until morning (d) risks worsening sepsis and kidney injury.

40. [RN] A 71-year-old man is starting long-term androgen deprivation therapy for prostate cancer. Which plan reflects the Canadian Urological Association guideline on managing its adverse effects?

a. Bone density testing at the start, calcium and vitamin D, supervised exercise, and regular metabolic checks

b. Breast irradiation or tamoxifen started before the first injection to prevent breast enlargement in every patient

c. Rest and reduced activity to manage the fatigue that ADT causes, with exercise resumed after treatment ends

d. Bone density testing only after he has a fracture, because bone loss from ADT is uncommon in men

Answer: a — The CUA guideline recommends bone density screening for men starting long-term ADT, adequate calcium and vitamin D from the start, supervised exercise and metabolic monitoring every 6 to 12 months (section 28.6, Prostate Cancer; Table 28.3). Routine prevention of breast enlargement is not recommended (b). Exercise is the recommended response to fatigue, not rest (c). Bone loss is an expected effect of ADT, and screening is not delayed until a fracture (d).

References

Agency for Clinical Innovation. (2026). *Bladder irrigation toolkit*. NSW Health. https://aci.health.nsw.gov.au/networks/urology/resources/bladder-irrigation/print-all

Alberta Precision Laboratories. (2020). *Laboratory patient collection instructions: Midstream urine (MSU)* (PA17.01-035). https://www.albertahealthservices.ca/assets/wf/lab/if-lab-pc-frm-midstream-urine-msu-pa17-01-035.pdf

Alberta Precision Laboratories. (n.d.). *Catheter collection for urine culture: Guidelines for physicians or other health care providers* (MI6173). https://www.albertahealthservices.ca/assets/wf/lab/if-lab-tc-cal-catheter-collection-mi6173.pdf

Alexander, C. E., Scullion, M. M. F., Omar, M. I., Yuan, Y., Mamoulakis, C., N'Dow, J. M. O., Chen, C., & Lam, T. B. L. (2019). Bipolar versus monopolar transurethral resection of the prostate for lower urinary tract symptoms secondary to benign prostatic obstruction. *Cochrane Database of Systematic Reviews*, (12), Article CD009629. https://doi.org/10.1002/14651858.CD009629.pub4

Anderson, C. A., Omar, M. I., Campbell, S. E., Hunter, K. F., Cody, J. D., & Glazener, C. M. A. (2015). Conservative management for postprostatectomy urinary incontinence. *Cochrane Database of Systematic Reviews*, (1), Article CD001843. https://doi.org/10.1002/14651858.CD001843.pub5

Auro Pharma. (2026). *Auro-Mirabegron (mirabegron extended-release tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00083326.PDF

Beaumont Hospital, Royal Oak. (2023). *Nitrite in urine (Multistix 10 SG)* [Laboratory procedure]. https://ltac.medtraining.org/ltac/docs/custom/154/84228_Nitrite%20in%20Urine%20-Multistix%2010%20SG-%20-%20Royal%20Oak.pdf

Bell, N., Connor Gorber, S., Shane, A., Joffres, M., Singh, H., Dickinson, J., Shaw, E., Dunfield, L., Tonelli, M., & Canadian Task Force on Preventive Health Care. (2014). Recommendations on screening for prostate cancer with the prostate-specific antigen test. *CMAJ*, *186*(16), 1225–1234. https://doi.org/10.1503/cmaj.140703

Bettez, M., Tu, L. M., Carlson, K., Corcos, J., Gajewski, J., Jolivet, M., & Bailly, G. (2012). 2012 update: Guidelines for adult urinary incontinence collaborative consensus document for the Canadian Urological Association. *Canadian Urological Association Journal, 6*(5), 354–363. https://doi.org/10.5489/cuaj.10

Bhindi, B., Kool, R., Kulkarni, G. S., Siemens, D. R., Aprikian, A. G., Breau, R. H., Brimo, F., Fairey, A., French, C., Hanna, N., Izawa, J. I., Lacombe, L., McPherson, V., Rendon, R. A., Shayegan, B., So, A. I., Zlotta, A. R., Black, P. C., & Kassouf, W. (2021). Canadian Urological Association guideline on the management of non-muscle-invasive bladder cancer – Full-text. *Canadian Urological Association Journal*, *15*(8), E424–E457. https://doi.org/10.5489/cuaj.7367

Bhojani, N., Bjazevic, J., Wallace, B., Lee, L., Kaler, K. S., Dion, M., Cowan, A., Sultan, N., Chew, B. H., & Razvi, H. (2022). UPDATE – Canadian Urological Association guideline: Evaluation and medical management of kidney stones. *Canadian Urological Association Journal*, *16*(6), 175–188. https://doi.org/10.5489/cuaj.7872

Brenner, D. R., Gillis, J., Demers, A. A., Ellison, L. F., Ng, C., Zhang, S. X., Finley, C., Fitzgerald, N., Saint-Jacques, N., Shack, L., Turner, D., Urquhart, R., & Woods, R. R. (2026). Projected estimates of cancer in Canada in 2026. *CMAJ*, *198*(14), E526–E534. https://doi.org/10.1503/cmaj.252152

Canadian Cancer Society. (n.d.-a). *Bladder cancer statistics*. https://cancer.ca/en/cancer-information/cancer-types/bladder/statistics

Canadian Cancer Society. (n.d.-b). *Hormone therapy for prostate cancer*. https://cancer.ca/en/cancer-information/cancer-types/prostate/treatment/hormone-therapy

Canadian Cancer Society. (n.d.-c). *Prostate cancer statistics*. https://cancer.ca/en/cancer-information/cancer-types/prostate/statistics

Canadian Cancer Society. (n.d.-d). *Radiation therapy for prostate cancer*. https://cancer.ca/en/cancer-information/cancer-types/prostate/treatment/radiation-therapy

Canadian Cancer Society. (n.d.-e). *Risk factors for bladder cancer*. https://cancer.ca/en/cancer-information/cancer-types/bladder/risks

Canadian Cancer Society. (n.d.-f). *Risk factors for prostate cancer*. https://cancer.ca/en/cancer-information/cancer-types/prostate/risks

Canadian Cancer Society. (n.d.-g). *Signs and symptoms of bladder cancer*. https://cancer.ca/en/cancer-information/cancer-types/bladder/signs-and-symptoms

Canadian Cancer Society. (n.d.-h). *Surgery for prostate cancer*. https://cancer.ca/en/cancer-information/cancer-types/prostate/treatment/surgery

Centers for Disease Control and Prevention. (2009). *Summary of recommendations: Guideline for prevention of catheter-associated urinary tract infections (2009)*. https://www.cdc.gov/infection-control/hcp/cauti/summary-of-recommendations.html

Choosing Wisely Canada. (n.d.). *Are you using antibiotics wisely?* [Clinician tool, Using Antibiotics Wisely in Long-Term Care]. https://choosingwiselycanada.org/download/825

College of Nurses of Ontario. (2025a). *An introduction to the Nursing Act, 1991* (Pub. No. 41064). https://www.cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/41064_fsnursingact.pdf

College of Nurses of Ontario. (2025b). *Forms of energy*. https://cno.org/standards-learning/educational-tools/forms-of-energy

College of Nurses of Ontario. (2025c). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

Corcos, J., Przydacz, M., Campeau, L., Witten, J., Hickling, D., Honeine, C., Radomski, S. B., Stothers, L., & Wagg, A. (2017). CUA guideline on adult overactive bladder. *Canadian Urological Association Journal, 11*(5), E142–E173. https://doi.org/10.5489/cuaj.4586

Dushinski, J. (2021). Both patient and stone factors determine "best" treatment for urolithiasis. *Canadian Urological Association Journal*, *15*(12), 394. https://doi.org/10.5489/cuaj.7681

Elterman, D., Aubé-Peterkin, M., Evans, H., Elmansy, H., Meskawi, M., Zorn, K. C., & Bhojani, N. (2022). UPDATE – 2022 Canadian Urological Association guideline on male lower urinary tract symptoms/benign prostatic hyperplasia (MLUTS/BPH). *Canadian Urological Association Journal*, *16*(8), 245–256. https://doi.org/10.5489/cuaj.7906

Eustice, S., Roe, B., & Paterson, J. (2000). Prompted voiding for the management of urinary incontinence in adults. *Cochrane Database of Systematic Reviews, 2000*(2), Article CD002113. https://doi.org/10.1002/14651858.CD002113

Gupta, K., Hooton, T. M., Naber, K. G., Wullt, B., Colgan, R., Miller, L. G., Moran, G. J., Nicolle, L. E., Raz, R., Schaeffer, A. J., & Soper, D. E. (2011). International clinical practice guidelines for the treatment of acute uncomplicated cystitis and pyelonephritis in women: A 2010 update by the Infectious Diseases Society of America and the European Society for Microbiology and Infectious Diseases. *Clinical Infectious Diseases, 52*(5), e103–e120. https://doi.org/10.1093/cid/ciq257

Gupta, K., Rastogi, B., Jain, M., Gupta, P. K., & Sharma, D. (2010). Electrolyte changes: An indirect method to assess irrigation fluid absorption complications during transurethral resection of prostate: A prospective study. *Saudi Journal of Anaesthesia*, *4*(3), 142–146. https://doi.org/10.4103/1658-354X.71505

Health Canada. (2006). *Seniors and aging: Bladder control problems (incontinence)*. https://www.canada.ca/en/health-canada/services/healthy-living/your-health/medical-information/seniors-aging-bladder-control-problems-incontinence.html

Health Canada. (2026). *Drug Product Database online query*. https://health-products.canada.ca/dpd-bdpp/

Ismail, A., Hadi, R. A., Alaradi, H., Jani, K., Elmansy, H., Zakaria, A., & Kotb, A. (2025). Rethinking prostate cancer screening in transgender women: Bridging the gap in inclusive healthcare. *Canadian Urological Association Journal*, *19*(5), E195–E198. https://doi.org/10.5489/cuaj.8994

Kokorovic, A., So, A. I., Serag, H., French, C., Hamilton, R. J., Izard, J. P., Nayak, J. G., Pouliot, F., Saad, F., Shayegan, B., Aprikian, A., & Rendon, R. A. (2022). UPDATE – Canadian Urological Association guideline on androgen deprivation therapy: Adverse events and management strategies (Full-text). *Canadian Urological Association Journal*, *16*(8), E416–E431. https://doi.org/10.5489/cuaj.8054

Lee, J. Y., Andonian, S., Bhojani, N., Bjazevic, J., Chew, B. H., De, S., Elmansy, H., Lantz-Powers, A. G., Pace, K. T., Schuler, T. D., Singal, R. K., Wang, P., & Ordon, M. (2021). Canadian Urological Association guideline: Management of ureteral calculi – Abridged version. *Canadian Urological Association Journal*, *15*(12), 383–393. https://doi.org/10.5489/cuaj.7652

Leis, J., & Soong, C. (2019). *Lose the tube: A toolkit for appropriate use of urinary catheters in hospitals* (Version 1.3). Choosing Wisely Canada. https://choosingwiselycanada.org/toolkit/lose-the-tube/

Leis, J., Feldman, S., & Piggott, K. (n.d.). *How urine tests drive system-wide antibiotic overuse* [Presentation slides]. Choosing Wisely Canada. https://choosingwiselycanada.org/wp-content/uploads/2026/05/Session-1-How-Urine-Tests-Drive-Overuse-.pdf

Mason, R. J., Marzouk, K., Finelli, A., Saad, F., So, A. I., Violette, P. D., Breau, R. H., & Rendon, R. A. (2022). UPDATE – 2022 Canadian Urological Association recommendations on prostate cancer screening and early diagnosis: Endorsement of the 2021 Cancer Care Ontario guidelines on prostate multiparametric magnetic resonance imaging. *Canadian Urological Association Journal*, *16*(4), E184–E196. https://doi.org/10.5489/cuaj.7851

Morash, C., Tey, R., Agbassi, C., Klotz, L., McGowan, T., Srigley, J., & Evans, A. (2015). Active surveillance for the management of localized prostate cancer: Guideline recommendations. *Canadian Urological Association Journal*, *9*(5–6), 171–178. https://doi.org/10.5489/cuaj.2806

National Institute of Diabetes and Digestive and Kidney Diseases. (2017a). *Definition & facts for kidney stones*. https://www.niddk.nih.gov/health-information/urologic-diseases/kidney-stones/definition-facts

National Institute of Diabetes and Digestive and Kidney Diseases. (2017b). *Symptoms & causes of kidney stones*. https://www.niddk.nih.gov/health-information/urologic-diseases/kidney-stones/symptoms-causes

Nicolle, L. E., Gupta, K., Bradley, S. F., Colgan, R., DeMuri, G. P., Drekonja, D., Eckert, L. O., Geerlings, S. E., Köves, B., Hooton, T. M., Juthani-Mehta, M., Knight, S. L., Saint, S., Schaeffer, A. J., Trautner, B., Wullt, B., & Siemieniuk, R. (2019). Clinical practice guideline for the management of asymptomatic bacteriuria: 2019 update by the Infectious Diseases Society of America. *Clinical Infectious Diseases, 68*(10), e83–e110. https://doi.org/10.1093/cid/ciy1121

Nurses Specialized in Wound, Ostomy and Continence Canada. (2022). *A guide to living with an ileal conduit* (2nd ed.). https://nswoc.ca/_files/ugd/9d080f_b7e102b2e98f4dc9827441efdc60924e.pdf

Ordon, M., Lantz Powers, A., Chew, B. H., Lee, J. Y., Kogon, M., Sivalingam, S., De, S., Bhojani, N., & Andonian, S. (2024). Incidence and trends in the treatment of kidney stones in Canada: A population-based cohort study. *Canadian Urological Association Journal*, *18*(6), 158–164. https://doi.org/10.5489/cuaj.8596

Patel, P. K., Advani, S. D., Kofman, A. D., Lo, E., Maragakis, L. L., Pegues, D. A., Pettis, A. M., Saint, S., Trautner, B., Yokoe, D. S., & Meddings, J. (2023). Strategies to prevent catheter-associated urinary tract infections in acute-care hospitals: 2022 update. *Infection Control & Hospital Epidemiology, 44*(8), 1209–1231. https://doi.org/10.1017/ice.2023.137

Sanis Health. (2020). *Finasteride (finasteride tablets, USP) 5 mg* [Product monograph]. https://pdf.hres.ca/dpd_pm/00056582.PDF

Serlin, D. C., Heidelbaugh, J. J., & Stoffel, J. T. (2018). Urinary retention in adults: Evaluation and initial management. *American Family Physician, 98*(8), 496–503. https://www.aafp.org/pubs/afp/issues/2018/1015/p496.html

Stoffel, J., Lightner, D., Peterson, A., Sandhu, J., Suskind, A., & Wei, J. (2016). *Non-neurogenic chronic urinary retention: Consensus definition, management strategies, and future opportunities* [White paper]. American Urological Association. https://www.auanet.org/x1883.xml

Teva Canada. (2021). *Teva-Tamsulosin CR (tamsulosin hydrochloride controlled-release tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00060229.PDF

The Ottawa Hospital. (2010). *Transurethral resection of the prostate (TURP): Patient information* (6th ed.). https://www.ottawahospital.on.ca/en/documents/2017/01/transurethral-resection-of-the-prostate-turp.pdf

Toronto East Health Network. (2019). *Care guide after TURP or TURBT surgery* [Patient education]. https://www.tehn.ca/documents/patient-education/care-after-turp-or-turbt-surgery

Trautner, B. W., Cortés-Penfield, N. W., Gupta, K., Hirsch, E. B., Horstman, M., Moran, G. J., Colgan, R., O'Horo, J. C., Ashraf, M. S., Connolly, S., Drekonja, D. M., Grigoryan, L., Huttner, A., Lazenby, G., Nicolle, L., Schaeffer, A., Yawetz, S., & Lavergne, V. (2025). *IDSA 2025 guideline update on complicated urinary tract infections*. Infectious Diseases Society of America. https://www.idsociety.org/practice-guideline/complicated-urinary-tract-infections/

University Health Network. (n.d.). *Urinalysis, routine* [Laboratory test dictionary]. https://forms.uhn.ca/LabDictionary/Public/View?lid=315

Verity Pharmaceuticals. (2021). *VERITY-BCG (bacillus Calmette-Guérin, strain Russian BCG-I)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00061917.PDF

Williams, G., Stothart, C. I., Hahn, D., Stephens, J. H., Craig, J. C., & Hodson, E. M. (2023). Cranberries for preventing urinary tract infections. *Cochrane Database of Systematic Reviews, 2023*(11), Article CD001321. https://doi.org/10.1002/14651858.CD001321.pub7

Wu, M.-Y., Chang, J.-R., Lee, Y.-K., Lin, P.-C., & Tsai, T.-Y. (2022). The effect and safety of rapid and gradual urinary decompression in urine retention: A systematic review and meta-analysis. *Medicina, 58*(10), Article 1441. https://doi.org/10.3390/medicina58101441

29 Reproductive and Breast Health in Adult Care

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Hold respectful, inclusive sexual health conversations and take a focused sexual health history in medical-surgical care.
2. Care for adults with breast cancer before and after breast surgery, including drain care, lymphedema risk and body image.
3. Provide nursing care for adults with common gynecologic conditions and after hysterectomy, and explain breast and cervical screening as Canadian programs state it.
4. Support informed discussion of menopause symptoms and treatment options, including menopausal hormone therapy.
5. Recognize, test for and support treatment of sexually transmitted and blood-borne infections, including partner notification and public health reporting.
6. Recognize the danger of PDE5 inhibitors with nitrates and provide affirming care for transgender and nonbinary patients, using the CJMM.
7. Distinguish RN and RPN roles in sexual and reproductive health care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 5, 6	Clinician; Scholar	Foundations of Practice
1, 4, 5, 6	Educator; Advocate	Foundations of Practice; Ethical Practice
7	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

Questions about sex, breasts and reproductive organs touch almost every adult a medical-surgical nurse cares for, even when the reason for admission lies elsewhere. A new drug can dampen desire or cause erectile problems. Surgery and cancer treatment can change how the body looks and works. A pill a patient forgot to mention can turn a routine nitrate order into a danger. Many patients will not raise these topics unless the nurse does. This chapter gives the nurse the knowledge and the words to open these conversations and to give safe care when reproductive and breast health are part of the picture.

Section 29.1 shows how to talk about sexual health, take a focused sexual health history and respond when a patient might be pregnant. Section 29.2 covers breast cancer, from screening to breast surgery, drain care and lymphedema. Section 29.3 covers common gynecologic conditions, hysterectomy, gynecologic cancers in brief and the breast and cervical screening programs. The second half of the chapter turns to menopause and midlife health (29.4), sexually transmitted and blood-borne infections (29.5), and erectile dysfunction and gender-affirming care (29.6).

The chapter builds on earlier ones. Scope of practice for registered nurses (RNs) and registered practical nurses (RPNs) is taught in section 1.3 and the Clinical Judgment Measurement Model (CJMM) in section 1.4; consent, privacy and documentation are in Chapter 1. Care of Two-Spirit, lesbian, gay, bisexual, transgender, queer, intersex and additional sexually and gender diverse (2SLGBTQI+) people, cultural safety and trauma- and violence-informed care are in Chapter 2. Perioperative care and surgical drains are in Chapter 7, pain in Chapter 5, cancer treatment in Chapter 9, HIV and adult immunization in Chapter 21, and urinary incontinence and prostate cancer in Chapter 28. Pregnancy, labour and birth are outside this book.

When a source reports data for "women," this chapter keeps that word. When care depends on anatomy, the chapter names the organ, because not everyone with a cervix or breasts is a woman.

29.1 Sexual Health in Medical-Surgical Care

Talking About Sexual Health

Illness and its treatment often reach into sexual life. Breast surgery can change body image, hysterectomy can bring vaginal dryness or painful intercourse, and removal of both ovaries brings on menopause at once (Canadian Cancer Society [CCS], n.d.-f, n.d.-g). Fatigue, pain, stomas, drains and many medications affect desire and function too. Patients rarely bring these worries up on their own, so the nurse makes room for them.

The Public Health Agency of Canada (PHAC) notes that sexual health visits can feel intrusive and prefers a brief, routine assessment, because extensive ones may make some people uncomfortable (PHAC, 2026b). In practice, the nurse:

- chooses a private place and a moment when the patient is comfortable, and asks permission before starting;
- says why the questions matter, such as "Some of the medicines you are taking can affect sex, so I ask everyone about it";
- tells the patient that they may skip any question, and explains how their information is kept confidential and the limits of that confidentiality, such as reporting duties (Chapter 1; section 29.5);
- uses plain words, asks which terms the patient uses for their body and which pronouns they use, and then uses those terms (PHAC, 2026b);
- leaves the door open: a person who is not ready today may want to talk at another visit.

PHAC's guide suggests telling people that testing for sexually transmitted and blood-borne infections (STBBIs) is offered to everyone, and it notes that many people who may be at risk do not see themselves that way (PHAC, 2026b). The same principle applies to sexual health conversations. The nurse does not assume that age, disability, illness, relationship status or a hospital bed means a person is not sexually active or does not care about sex. Older adults, people with disabilities and people living in long-term care have sexual health needs, and they are often the people no one asks.

Many patients carry a history of sexual violence or other trauma. A trauma- and violence-informed approach (section 2.2) means explaining each step, offering choices, keeping the body covered and stopping when the person asks. PHAC includes intimate partner and sexual violence among the topics of a sexual health assessment (PHAC, 2026b); if a patient discloses violence, the nurse responds with belief and support and follows the employer's process for safety planning and referral.

Documentation follows the College of Nurses of Ontario (CNO) Documentation standard (Chapter 1). The nurse records what care needs, such as a medication the patient takes for erectile dysfunction or a pregnancy test result, and not every detail of a patient's sexual life.

Taking a Sexual Health History

A **sexual health history** is a focused set of questions about a person's sexual activity, partners, protection, past infections and reproductive health. PHAC's guide groups the content into a few areas (PHAC, 2026b):

- **Sexual activity and partners:** the types of sex (oral, vaginal, anal) and the number and kinds of partners, without assumptions about the partners' gender.
- **Protection:** condoms and other barriers, vaccines, regular testing, human immunodeficiency virus (HIV) pre-exposure and post-exposure prophylaxis (PrEP and PEP; section 21.4), and any barriers to protection, including whether the person can freely negotiate safer sex.
- **Past STBBIs:** earlier testing, results and treatment, for the person and their partners.
- **Symptoms:** discharge, sores, pain or bleeding.
- **Reproductive health:** for people with a uterus, the first day of the last menstrual period, contraception and the date of the last cervical screening test.

Questions work best when they ask about bodies and behaviours, not identity. "Do you have sex with men, women or both?" misses people whose partners are nonbinary and says nothing about which infections or screening tests are relevant. "What parts of your body do you use for sex?" or "Could any of your partners become pregnant?" gives the nurse what care requires. An **organ**

inventory is a respectful record of the reproductive and sex organs a person has at present, such as a cervix, uterus, ovaries, breasts, prostate or testes. Screening follows organs: in Ontario, cervical screening is for people who have a cervix, whatever their gender (Ontario Health, n.d.-b). Section 29.6 applies the organ inventory to gender-affirming care.

In a medical-surgical setting, the nurse usually needs only part of the history. A patient starting a drug that can harm a fetus needs questions about pregnancy and contraception. A patient with chest pain needs to be asked about erectile dysfunction pills before a nitrate is given (section 29.6). A patient going home after pelvic surgery needs to know when sexual activity can safely resume.

When a Patient Might Be Pregnant

Pregnancy changes what is safe. Before surgery, imaging that uses radiation and some drugs, the nurse asks about the possibility of pregnancy and arranges a pregnancy test when the employer's policy calls for one (section 7.2). Asking about the date of the last menstrual period, which PHAC also includes in a sexual health assessment, is part of this (PHAC, 2026b). Some common drugs must be avoided in pregnancy; for example, angiotensin-converting enzyme (ACE) inhibitors and angiotensin receptor blockers (ARBs) are avoided and are stopped in people trying to become pregnant (section 19.2). The nurse makes sure people who could become pregnant know this.

Pregnancy is also one of the few situations in which bacteria in the urine without symptoms are looked for and treated. In 2018, the Canadian Task Force on Preventive Health Care recommended screening pregnant women once in the first trimester with a urine culture for **asymptomatic bacteriuria** (a weak recommendation based on very low-quality evidence; Moore et al., 2018). The Infectious Diseases Society of America also recommends screening and treatment in pregnancy, whereas most other adults are not screened (Nicolle et al., 2019; section 28.1). Gestational diabetes, glucose intolerance first recognized in pregnancy, is defined in section 22.1.

Blood pressure in pregnancy follows its own rules. The Society of Obstetricians and Gynaecologists of Canada (SOGC) guideline on hypertensive disorders of pregnancy sets definitions and thresholds specific to pregnancy (Magee et al., 2022), so the adult targets in Chapter 19 do not apply. A pregnant patient with severe hypertension, or with new symptoms such as headache or changes in vision, may be developing a serious complication, so the nurse escalates at once for urgent obstetric assessment. Care of pregnancy, labour and birth belongs to obstetric teams and is outside this book.

29.2 Breast Cancer Care

Breast Cancer in Canada

Not counting non-melanoma skin cancers, breast cancer is the most common cancer among women in Canada. The Canadian Cancer Society estimates that in 2026, 32,400 women in Canada will receive a breast cancer diagnosis (26% of new cancer cases in women) and 5,400 will die of the disease (13% of cancer deaths in women) (Brenner et al., 2026; CCS, 2026a). Over their lifetime, an estimated 1 in 8 women in Canada are expected to be diagnosed with breast cancer, and 1 in 35 to die of it (CCS, 2026a).

The Canadian Cancer Society lists these risk factors (CCS, n.d.-c):

- older age, with the highest numbers of cases in women aged 50 to 69;
- breast cancer in a first-degree relative, which roughly doubles the risk;
- inherited changes in the BRCA1 or BRCA2 gene, which are rare but raise lifetime risk sharply;
- dense breast tissue;
- alcohol, with risk rising as intake rises;
- physical inactivity, and excess body weight after menopause;
- menopausal hormone therapy used for a long time, particularly estrogen combined with a progestin for 5 years or longer (section 29.4);
- starting periods at 11 or younger or reaching menopause after 55;
- having a first full-term pregnancy after age 35, never giving birth, or not breastfeeding;
- radiation to the chest, especially before age 30.

Everyone has some breast tissue, so breast cancer can occur in anyone (CCS, n.d.-c). In 2026, an estimated 300 men in Canada will receive a breast cancer diagnosis and 60 will die of it (CCS, 2026a). Men with an inherited BRCA change, especially BRCA2, and men with Klinefelter syndrome have a higher risk (CCS, n.d.-c). Whatever the person's sex or gender, the nurse encourages anyone with a breast change to have it assessed.

Little research describes breast cancer risk in transgender and nonbinary people (CCS, n.d.-c). Screening programs set eligibility by body and history rather than by gender. The Ontario Breast Screening Program, for example, includes trans and nonbinary people, and transfeminine people become eligible after at least 5 consecutive years of feminizing hormones (Ontario Health, n.d.-a). Section 29.6 returns to screening by organ.



Figure 29.1 Craniocaudal (CC) and mediolateral oblique (MLO) mammogram views showing grouped microcalcifications (arrows) that warrant diagnostic follow-up. (credit: "Mammogram images of clustered calcifications at CC view and MLO view" by Cerevisae/Wikimedia Commons, CC BY-SA 4.0)

Screening and Diagnosis

A **screening mammogram** is an X-ray of the breasts in a person with no symptoms, taken to find cancer early. Recommendations about when to start and how often to screen have changed in recent years, and they differ between provinces (Figure 29.1).

The Canadian Task Force on Preventive Health Care released draft breast screening recommendations in May 2024 (Canadian Task Force on Preventive Health Care [CTFPHC], 2024). The draft treated screening from 40 to 74 as a personal choice informed by benefits and harms. For ages 40 to 49, it suggested not screening everyone but offering mammography every 2 to 3 years to those who choose it; for 50 to 74, it suggested mammography every 2 to 3 years; for 75 and older, it suggested no screening. All three were conditional recommendations with very low certainty. The draft was not finalized before the Task Force's mandate ended on March 31, 2026, and PHAC now supports a new National Advisory Committee on Preventive Health Services (CTFPHC, n.d.).

Provinces run their own programs (Table 29.1). In October 2024, the Ontario Breast Screening Program (OBSP) expanded to people aged 40 to 49. It now screens women, Two-Spirit, trans and nonbinary people aged 40 to 74, most of them every 2 years, and people can book their own mammogram. The program suggests that people in their 40s first discuss screening with a family doctor, nurse practitioner (NP) or Health811 navigator. The High Risk OBSP offers yearly mammography and breast magnetic resonance imaging (MRI) to people aged 30 to 69 with, for example, a known BRCA1, BRCA2, TP53 or PALB2 gene change or chest radiation before age 30 (Ontario Health, n.d.-a). After 74, screening continues only with a referral.

Table 29.1 Breast and cervical screening in Canada (CTFPHC, 2013, 2024; Ontario Health, n.d.-a, n.d.-b; Government of Ontario, 2026)

Screening	Who and how often (as stated, with date)	Test	What the nurse discusses
Breast: Ontario Breast Screening Program (expanded October 2024)	Women, Two-Spirit, trans and nonbinary people aged 40 to 74 without symptoms; most every 2 years; people aged 40 to 49 encouraged to talk with a provider first and may book their own appointment; over 74 by referral	Mammogram	Benefits and harms; how to book; breast changes need assessment at any time
Breast: High Risk OBSP	Ages 30 to 69 with, for example, a known BRCA1, BRCA2, TP53 or PALB2 gene change or chest radiation before age 30; every year	Mammogram and breast MRI (ultrasound if MRI is not appropriate)	Referral through a primary care provider; genetic counselling
Breast: Canadian Task Force draft (May 2024; not finalized)	Ages 40 to 49: offered every 2 to 3 years to those who choose it; 50 to 74: every 2 to 3 years; 75 and older: not suggested	Mammogram	Screening as an informed personal choice

Screening	Who and how often (as stated, with date)	Test	What the nurse discusses
Cervical: Ontario Cervical Screening Program (HPV test since March 2025)	People with a cervix aged 25 or older who have ever had sexual contact; most every 5 years; every 3 years for people who are immunocompromised; most can stop between 65 and 69	HPV test on a sample taken with a small brush	Starting at 25; screening after HPV vaccination; what a positive result means
Cervical: Canadian Task Force (2013)	Ages 25 to 69 every 3 years; not routinely before 25; may stop at 70 or older after adequate screening (3 negative Pap tests in 10 years)	Pap test	Recommendation published before HPV testing; provincial programs now differ

Dense breast tissue raises the risk of breast cancer (CCS, n.d.-c). The 2024 draft did not suggest added ultrasound or MRI for dense breasts alone, because no evidence showed better outcomes (CTFPHC, 2024). The nurse explains the program that applies to the patient, encourages a shared decision with the primary care provider and does not give a personal opinion.

Screening is for people without symptoms. A lump, a thick or hard area, or a change in the skin or nipple needs assessment, whatever the date of the last mammogram. Diagnosis usually starts with a diagnostic mammogram and ultrasound, which shows whether a lump is solid or a fluid-filled cyst. A **biopsy**, such as a core needle biopsy, is needed to confirm breast cancer; no other test gives a definite diagnosis (CCS, n.d.-a). The pathologist also reports whether the cancer cells carry hormone receptors and extra HER2 protein, which guides treatment (see the Going Deeper box). Waiting for biopsy results is a time of high anxiety; the nurse gives clear information about when and how results will come and who to call.

GOING DEEPER

Hormone Receptor and HER2 Status

Required for RN students; optional for PN students.

Breast cancer cells are tested for three proteins. **Hormone receptor status** tells whether the cells carry **estrogen receptors (ER)**, progesterone receptors (PR) or both. Receptor-positive cancers use these hormones to grow, so knowing the status helps the team predict whether hormone-blocking treatment will work. These cancers tend to be less aggressive and to have a better short-term outlook, but they can come back many years after treatment (CCS, 2023).

Human epidermal growth factor receptor 2 (HER2) is a protein on the cell surface. A HER2-positive cancer makes more of it than normal, grows and spreads faster and is more likely to recur. It is also more likely to respond to drugs that target HER2 (CCS, 2023; CCS, n.d.-a). A cancer that lacks hormone receptors tends to be more aggressive (CCS, 2023).

These results shape the plan. People with receptor-positive cancer are usually offered **endocrine therapy**, which blocks the production or action of hormones, such as tamoxifen or an aromatase inhibitor. People with HER2-positive cancer are offered treatment that includes HER2-targeted drugs. Chapter 9 covers these treatments. The nurse supports adherence, because daily tablets with side effects such as hot flashes and sexual changes (section 9.3) can be hard to sustain.

Figure 29.2 Healed surgical scar across the breast mound and lateral chest wall following mastectomy and breast reconstruction. (credit: "Breast reconstruction (1)" by Linda Bartlett/National Cancer Institute, Public domain)

Breast Surgery and Nursing Care

Most people with breast cancer have surgery to the breast and to the lymph nodes under the arm (Table 29.2). **Breast-conserving surgery** takes out the tumour along with a rim of healthy tissue around it and is usually followed by radiation. A **mastectomy** removes all the breast tissue; a skin-sparing mastectomy keeps the skin when reconstruction is done at the same operation (CCS, n.d.-f). A **sentinel lymph node biopsy** removes the first node or nodes that drain the tumour to check them for cancer, while an **axillary lymph node dissection** removes the underarm nodes, usually when cancer has reached them. Lymphedema is more common after dissection than after sentinel node biopsy (CCS, n.d.-f; Figure 29.2).

Table 29.2 Breast cancer surgery and nursing care (CCS, n.d.-f; Hôpital Montfort, n.d.; Interior Health, n.d.)

Procedure	What is removed	Main nursing points	Teaching
Breast-conserving surgery (lumpectomy)	The tumour and a rim of normal tissue	Pain; bleeding or fluid collection at the site; usually followed by radiation	Wound care; signs of infection; radiation appointments
Total (simple) mastectomy	All breast tissue and the tissue over the chest muscle	Closed suction drain; pain; chest numbness; body image	Drain care and output log; arm exercises; bra or breast form
Sentinel lymph node biopsy	The first lymph node or nodes that drain the tumour	Underarm pain and numbness; arm and shoulder movement	Arm exercises; lymphedema warning signs
Axillary lymph node dissection	Underarm lymph nodes	Drain under the arm; shoulder stiffness; highest lymphedema risk of these procedures	Lymphedema risk reduction; early report of swelling or infection

Procedure	What is removed	Main nursing points	Teaching
Mastectomy with reconstruction	Breast tissue, with the breast reshaped at the same operation (skin-sparing mastectomy keeps the skin)	Care of the reconstructed area as the surgeon orders	Surgeon's limits on activity; signs to report

General postoperative care follows section 7.6, and pain care follows Chapter 5. Some people develop **post-mastectomy pain syndrome**, nerve pain in the chest, armpit or arm that lasts after healing (CCS, n.d.-f). Numbness along the inner upper arm is common after mastectomy or node dissection (Interior Health, n.d.).

A **closed suction drain** is a soft tube from the wound to a compressible bulb that draws out blood and lymph. Many patients go home with it, and it is removed when drainage has fallen (CCS, n.d.-f). To empty it, the nurse or patient washes their hands, opens the plug, pours the fluid into a measuring container, taking care not to touch the inner surface of the plug, squeezes the bulb flat and closes the plug while it is still squeezed to restore suction (Interior Health, n.d.). Each amount and its colour go on an output log that the patient brings to follow-up. The fluid is often bloody at first and, over time, turns from red to pink and then to light yellow or clear, while the amount should fall (Alberta Health Services, 2022).

Bleeding is the early danger. A drain filling quickly with bright red fluid, a tense and growing swelling of the chest wall, a rising heart rate or a falling blood pressure suggests a collection of blood (hematoma) or active bleeding. Any nurse who sees these acts at once and escalates (sections 6.1 and 7.6). A **seroma**, a collection of fluid under the skin flap, can build up in the wound, including after the drain comes out; it is reported to the surgical team, because some collections need to be drained (CCS, n.d.-f). Redness, warmth, fever or foul drainage suggests infection.

Gentle arm and shoulder exercises begin soon after surgery to prevent stiffness. One Ontario hospital program has patients exercise slowly, within their pain limit, two to three times a day, and keep the arm below shoulder height for overhead movements while a drain is in place; fuller stretches are added at 3 to 6 weeks (Hôpital Montfort, n.d.). The nurse reinforces the program the surgeon or physiotherapist gives.

Breast surgery can change body image and self-esteem (CCS, n.d.-f), and loss of a breast can affect identity, sexuality and relationships. The nurse invites the patient to look at the incision when ready, answers questions about reconstruction and offers peer support, such as Canadian Cancer Society programs. An **external breast form** (breast prosthesis) is a shape made of foam, silicone or another material and worn inside a bra; some people choose one when they do not want reconstruction or while they wait for it (Waterloo Regional Health Network, 2026). A soft, supportive bra without underwires may be more comfortable (Interior Health, n.d.).

PATIENT EDUCATION

Going Home After Breast Surgery

- **Your drain:** Wash your hands. Open the plug, pour the fluid into the measuring cup and write down the amount and colour. Squeeze the bulb flat and close the plug while it is squeezed. Wash your hands again.
- **Your output log:** Bring it to your follow-up visit; the surgeon uses it to decide when the drain comes out.
- **Washing:** Sponge bathe while you have a drain, unless your surgeon says otherwise.
- **Arm exercises:** Do your exercises 2 or 3 times a day, slowly and within your comfort. Keep your arm below shoulder height for overhead exercises while the drain is in.
- **Lifting:** Avoid heavy lifting and any pushing or pulling that needs effort until your surgeon says you can.
- **Call your surgeon's office (or, if you cannot reach them, go to the emergency department) if you have:** pain that keeps getting worse despite medicine; more redness or swelling at the incision; more drainage or foul-smelling drainage; a temperature of 38.5 °C or higher (Interior Health, n.d.).
- **Swelling of your arm, hand or chest:** report it early.
- **Feelings:** It is normal to have strong feelings about your body. Ask about support groups and peer visitors.

Lymphedema

Lymphedema is swelling that develops when lymph cannot drain normally and builds up in the tissues. After breast cancer treatment it affects the arm, hand or chest on the treated side. The risk rises with the number of lymph nodes removed and with radiation to the nodes, spread of cancer to the nodes, infection and excess body weight (CCS, n.d.-b).

Early signs are subtle: a feeling of fullness or heaviness, aching or burning, skin that feels tight or warm, rings or sleeves that feel tight, and swelling of the hand or fingers. Other signs include hardening or thickening of the skin and difficulty moving a nearby joint (CCS, n.d.-b). The nurse teaches patients to report these changes early, so that assessment and treatment can begin.

Advice about protecting the arm is changing. The Canadian Cancer Society advises avoiding blood pressure readings and needle sticks (blood draws, intravenous lines, injections) in the affected arm, and alternating arms when nodes were removed on both sides (CCS, n.d.-b). The research behind this advice is limited. In a prospective study of patients screened for lymphedema at one centre from 2005 to 2014, blood draws, injections and air travel were not associated with increases in arm volume, while axillary dissection, regional node radiation, a body mass index of 25 or more and cellulitis were; the authors concluded that blood draws, injections and blood pressure readings in the arm on the treated side, and air travel, may not raise the risk (Ferguson et al., 2016). In practice, the nurse follows the employer's policy and the patient's wishes, uses the other arm when possible and never delays urgent care to avoid the at-risk arm.

What the sources agree on is protecting the skin, because infection raises the risk. Patients keep the skin clean and moisturized, protect it from cuts, burns and bites, treat small wounds promptly and report redness, warmth or fever at once. Staying active and keeping a healthy weight also help (CCS, n.d.-b). The nurse refers anyone with signs of lymphedema to the team; treatment such as manual lymph drainage and compression is provided by physiotherapists or massage therapists with special training, and compression garments are used only when a physician or physiotherapist recommends them (CCS, n.d.-b).

29.3 Gynecologic Conditions and Surgery

Common Gynecologic Conditions

Abnormal uterine bleeding (AUB) is uterine bleeding that differs from the person's usual menstrual pattern in amount, duration, frequency or regularity, or that occurs between periods. Heavy bleeding over months can lead to **iron deficiency anemia** (Chen et al., 2025; section 20.2). The nurse asks about the number of pads or tampons used, clots and flooding, and looks for fatigue, shortness of breath on exertion and pallor, which on medium and dark skin is checked where pigment does not hide colour, such as the conjunctiva, mouth, nail beds and palms (section 20.2) (Figure 29.3).

Uterine fibroids are non-cancerous growths of the muscle of the uterus. The SOGC describes them as very common; most cause no symptoms and need no treatment. When fibroids cause AUB, iron deficiency anemia, or pelvic pain or pressure, the SOGC advises a low threshold for investigation. Many treatments exist, and the choice depends on the fibroids, the symptoms and the person's plans for pregnancy (Chen et al., 2025). Untreated symptomatic fibroids reduce quality of life, so the nurse takes heavy bleeding and pressure symptoms seriously.

In **endometriosis**, tissue similar to the uterine lining grows outside the uterus and causes chronic inflammation. Common sites are the ovaries, the fallopian tubes, the ligaments behind the uterus and the bowel. The SOGC estimates that it affects about 10% of women, plus transgender, nonbinary and gender-diverse people in numbers that are not known, and that diagnosis in Canada is delayed by at least 5 years (Society of Obstetricians and Gynaecologists of Canada [SOGC], n.d.-a). Pain is the main symptom: painful periods (dysmenorrhea), pain with intercourse (dyspareunia), painful bowel movements or urination and pelvic pain lasting more than 3 months. Fatigue, bloating and infertility also occur. Under the 2024 SOGC guideline, endometriosis can be diagnosed clinically, from the symptoms, a physical examination and ultrasound, so that treatment need not wait for surgery (Singh et al., 2024; SOGC, n.d.-a). Hormonal treatment, such as combined hormonal contraceptives or a progestin, is first-line, with non-steroidal anti-inflammatory drugs (NSAIDs) for pain, physiotherapy and counselling (SOGC, n.d.-a). Persistent pelvic pain is real pain; the nurse believes the patient and uses the approaches in Chapter 5.

Pelvic organ prolapse is the descent of the bladder, uterus, top of the vagina or rectum into or beyond the vaginal opening, as the muscles and connective tissue that support them weaken. People may describe a bulge or heaviness in the vagina, sometimes with urinary or bowel symptoms. Options include pelvic floor muscle training, a **pessary** (a removable device placed in the vagina to support the organs) and surgery. A patient with a pessary needs it removed and cleaned on the schedule their provider sets, and reports new bleeding, discharge or pain. In hospital, the nurse asks about a pessary on admission so that its care is included in the care plan (Figure 29.4).



Figure 29.3 Lateral (sagittal) and anterior views of the internal and external female reproductive organs within the pelvis. (credit: "Figure 27.9, Female Reproductive System" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)



Figure 29.4 Axial (left) and coronal (right) pelvic CT scans showing a vaginal ring pessary in place supporting the pelvic organs. (credit: "Vaginaler Pessar in der Computertomografie 78W - CT axial und koronar arterielle Phase - 001" by Hellerhoff/Wikimedia Commons, CC BY-SA 4.0)

Hysterectomy and Gynecologic Surgery

A **hysterectomy** is removal of the uterus. A total hysterectomy takes out both the uterus and the cervix; a radical hysterectomy, used for some cancers, also removes the upper vagina and nearby tissue. A **bilateral salpingo-oophorectomy (BSO)** removes both ovaries and fallopian tubes and is often done at the same time. For uterine cancer, most people have laparoscopic surgery through several small incisions, sometimes with robotic assistance; the open abdominal route is now used less often because serious complications such as infection are more likely and recovery takes longer, and the vaginal route removes the uterus through the vagina (CCS, n.d.-g).

After surgery, the nurse watches for the complications the Canadian Cancer Society lists: pain, infection, vaginal bleeding, blood clots, bowel obstruction and bladder problems (CCS, n.d.-g). In practice, this means:

- **Bleeding:** checking pads and the wound, and treating a rising heart rate, falling blood pressure or swelling abdomen as possible internal bleeding even when the pad is dry (sections 6.1 and 7.6);
- **Voiding:** confirming that the patient passes urine after the catheter is removed and using a bladder scan as the unit protocol directs (sections 7.6 and 28.3);
- **Bowel function and mobility:** early walking, return of bowel function and venous thromboembolism (VTE) prevention as ordered (sections 7.6 and 19.6);
- **The wound:** monitoring incisions for redness, drainage and separation (section 7.6);
- **Sensation:** asking about tingling or numbness of the thighs, which can follow surgery for uterine cancer (CCS, n.d.-g).

Removing both ovaries before natural menopause causes **surgical menopause**, an abrupt drop in hormones (CCS, n.d.-g); menopausal symptoms such as hot flashes are described in section 29.4. Other effects can include vaginal dryness, painful intercourse and, before menopause, the end of fertility (CCS, n.d.-g). Some people feel relief, others grief, and many feel both. The nurse asks how the patient feels about the surgery, answers questions about sex after surgery and refers to the surgical team for specific limits on lifting, driving and intercourse.

Gynecologic Cancers in Brief

For 2026, the Canadian Cancer Society estimates these numbers of new diagnoses and deaths among women in Canada: uterine cancer, 8,800 diagnoses and 1,750 deaths; ovarian cancer, 3,000 and 1,950; and cervical cancer, 1,700 and 450 (CCS, 2026b, 2026c, 2026d).

Cervical cancer is caused by persistent infection with high-risk types of **human papillomavirus (HPV)**. Ontario replaced the Pap test with an HPV test as its cervical screening test in March 2025 (Government of Ontario, 2026; Table 29.1). A positive result shows a high-risk HPV type, one that can occasionally lead to cancer; it does not mean that cancer is present, and depending on the situation, the next step may be a repeat test in 2 years or a colposcopy, a closer look at the cervix by a specialist (Government of Ontario, 2026). The Ontario program includes women, Two-Spirit people, and transmasculine and nonbinary people who have a cervix. Screening does not need to start before 25, even after sexual contact, and is not needed by a person who has never had sexual contact with another person. People who have had the HPV vaccine (section 21.6) still need screening (Ontario Health, n.d.-b). Table 29.1 compares the national and Ontario recommendations.

Ovarian cancer often causes no symptoms early. Later symptoms are vague and easy to blame on other problems: bloating, abdominal or pelvic pain or pressure, feeling full quickly, urinary urgency or frequency, back pain and fatigue (CCS, n.d.-d). The nurse encourages a person with symptoms that persist to have them assessed.

Uterine (endometrial) cancer most often shows itself through abnormal vaginal bleeding, including any bleeding or spotting after menopause. Other signs include unusual discharge that may be blood-stained or foul-smelling, pain with sex and pelvic pain or pressure (CCS, n.d.-e). Bleeding after menopause is never treated as normal; the nurse makes sure it is reported and assessed. Treatment for gynecologic cancers is covered in Chapter 9. After surgery that removes pelvic lymph nodes, lymphedema of the legs or pelvis can occur (CCS, n.d.-g).

LIFESPAN CONSIDERATIONS

Older Adults and Reproductive Health

- **Bleeding after menopause:** Abnormal vaginal bleeding, including any bleeding or spotting after menopause, is the sign of uterine cancer seen most often, so it is always reported for assessment (CCS, n.d.-e). Older adults may not mention it unless asked.
- **Prolapse and pessaries:** On admission, the nurse asks whether the patient uses a pessary and who removes and cleans it, and includes it in the care plan and the discharge plan.
- **Sexual health:** Many older adults remain sexually active, and STBBIs occur at every age. The nurse offers the same respectful questions and testing as for younger adults (PHAC, 2026b) and remembers that medications, surgery and dementia can affect intimacy and consent (Chapter 1).
- **When screening ends:** In Ontario, most people can stop cervical screening between 65 and 69 (Ontario Health, n.d.-b), and the OBSP stops mailing invitations and results letters after age 74; screening continues by referral (Ontario Health, n.d.-a). Stopping screening does not mean ignoring symptoms.
- **Breast cancer:** Risk rises with age (CCS, n.d.-c). After surgery, older adults may need extra help with drain care at home, arm exercises and transport to follow-up.

29.4 Menopause and Midlife Health

Menopause is a normal life stage, not a disease. Still, its symptoms can disrupt sleep, work and relationships, and they often surface during care for something else. The sources in this section mostly describe women. The same physiology applies to transgender men and nonbinary people who have ovaries, so the nurse uses each person's own words for their body (section 29.1).

Menopause and Its Symptoms

Menopause is the permanent end of menstruation caused by the loss of ovarian follicles. It is confirmed in hindsight, after 12 months in a row with no period and no other cause. In Canada, menopause occurs at an average age of 51, and most people reach it between about 45 and 55 (Society of Obstetricians and Gynaecologists of Canada [SOGC], n.d.-b). **Perimenopause** is the transition before menopause, when periods change and symptoms often begin. It can start 4 to 8 years before the final period and includes the 12 months after it. Menopause before age 45 is called early menopause, and loss of ovarian function before 40 is called premature ovarian insufficiency (SOGC, n.d.-b).

Surgical menopause follows removal of both ovaries (bilateral oophorectomy; section 29.3). Chemotherapy or pelvic radiation can also bring on menopause. Induced menopause is often more sudden and its symptoms more severe than natural menopause (SOGC, n.d.-b). When a person loses ovarian function before age 45, the SOGC recommends considering hormone replacement until the average age of natural menopause (Yuksel et al., 2021).

Vasomotor symptoms, mainly hot flashes and night sweats, top the list of menopause symptoms. As many as 80% of women have them, about 20% to 25% have symptoms severe enough to disrupt daily life, and they last an average of 7.4 years (SOGC, n.d.-b). A hot flash is a sudden feeling of heat in the face, neck and chest. On lighter skin it may show as redness; on darker skin, flushing can be hard to see, so the nurse relies on the person's report and on sweating. Sleep problems affect 40% to 60% of people in the transition. Perimenopause is also a time of greater vulnerability to new or worsening mood disorders, including depression (SOGC, n.d.-b).

Genitourinary syndrome of menopause (GSM) describes a group of symptoms in the vulva, vagina and lower urinary tract caused by falling estrogen. It includes vaginal dryness, itching, pain with intercourse and light bleeding, as well as urinary frequency, urgency and stress incontinence (SOGC, n.d.-b). Many people do not mention it unless asked (section 29.1). Continence care is covered in section 28.3.

Treatment Options

The nurse supports an informed choice rather than recommending a treatment.

Menopausal hormone therapy (MHT) is estrogen, given alone or with a progestogen, to relieve menopause symptoms. The SOGC states that no treatment relieves vasomotor symptoms better than MHT, and that it is safe to start in women who have no contraindications and are younger than 60 or within 10 years of their final period. The choice and the length of treatment are individualized, based on symptoms, health conditions, family history, goals and preferences, and are reviewed over time (Yuksel et al., 2021). People who still have a uterus need a progestogen, or another option the prescriber chooses, to protect the uterine lining; after a hysterectomy, estrogen can be used on its own (Yuksel et al., 2021).

The North American Menopause Society, now called The Menopause Society, reaches the same conclusion. For people under 60 or within 10 years of menopause who have no contraindications, the benefits outweigh the risks for treating bothersome hot flashes and preventing bone loss. For people who start MHT after 60 or more than 10 years after menopause, the balance is less favourable because the absolute risks of stroke, coronary heart disease, dementia and VTE are higher. Transdermal routes and lower doses may lower the risk of VTE and stroke (The 2022 Hormone Therapy Position Statement of The North American Menopause Society Advisory Panel [NAMS Advisory Panel], 2022). Short-term use of estrogen with a progestogen does not appreciably raise breast cancer risk, and estrogen alone may carry a lower risk; longer use may carry a rare added risk (NAMS Advisory Panel, 2022).

The Canadian product monograph for a transdermal estradiol gel lists who should not take estrogen. Contraindications include known, suspected or past breast cancer; other estrogen-dependent cancers; untreated endometrial hyperplasia; undiagnosed abnormal genital bleeding; current or past venous or arterial thromboembolism (including stroke, myocardial infarction or angina); known clotting disorders; active liver disease; pregnancy or breastfeeding; classical migraine; and porphyria. Estrogen should not be used to prevent heart disease, and the prescriber chooses the lowest dose that works, for the shortest time that meets the treatment goal (Organon Canada, 2026).

Vaginal estrogen is a low-dose estrogen placed in the vagina to treat GSM. The Menopause Society recommends low-dose vaginal estrogen or other local therapies for bothersome GSM that over-the-counter moisturizers and lubricants do not relieve; it suits people of any age and can continue for as long as needed (NAMS Advisory Panel, 2022).

For people who cannot or prefer not to take hormones, the SOGC names non-hormonal prescription options: certain antidepressants, gabapentinoids, clonidine and oxybutynin, each with its own adverse effects. Cognitive behavioural therapy also shows benefit. The evidence does not support any single natural health product, and compounded "bioidentical" hormones have not been tested as rigorously as Health Canada–approved products. The SOGC also recommends offering people the option of working with a cultural leader on traditional therapies (Yuksel et al., 2021).

The nurse:

- asks about symptoms, sleep, mood and sexual comfort in plain language;
- recognizes cues that matter for treatment choices, such as a past clot, breast cancer or unexplained bleeding, and passes them to the prescriber;
- explains why a progestogen is added when a uterus is present;
- teaches that any bleeding after menopause must be reported and investigated (section 29.3).

Midlife Health

Estrogen loss speeds bone loss, so bone health and osteoporosis screening matter (Chapter 33). Cardiovascular risk factors such as blood pressure, lipids and glucose deserve attention (Chapters 17, 19 and 22), and MHT is not a way to prevent heart disease (Organon Canada, 2026). Bladder symptoms and pelvic floor health are addressed in section 28.3. Sexual health remains part of whole-person care in midlife and older age. The nurse invites questions about desire, comfort and relationships without assuming that interest in sex ends with menopause.

29.5 Sexually Transmitted and Blood-Borne Infections

A **sexually transmitted and blood-borne infection** (STBBI) is an infection that spreads through sexual contact, blood or both. Medical-surgical nurses meet STBBIs in many ways: a positive test during admission, a pelvic infection after a missed diagnosis, a rash that turns out to be syphilis, or a patient's question asked in private. This section covers common bacterial, viral and parasitic

sexually transmitted infections. HIV, pre-exposure prophylaxis (PrEP) and post-exposure prophylaxis (PEP) are in Chapter 21; hepatitis B and C are in Chapter 26.

STBBIs in Canada

Chlamydia is the sexually transmitted infection reported most often in Canada (Public Health Agency of Canada [PHAC], 2025b), and gonorrhea is the second most common (PHAC, 2026a). Syphilis rates rose steeply from 2014. In 2023, 12,135 cases of infectious syphilis were reported, a rate of 30.5 per 100,000 population. That rate was 16% lower than in 2022, the first national decrease since 2014, but still 77% higher than in 2018 (PHAC, 2025c). Congenital syphilis has also re-emerged (Canadian Context: Syphilis in Canada).

These numbers are not spread evenly. PHAC states that health inequities and the social and structural determinants of health help explain differences between populations (PHAC, 2025c), and its technical report on syphilis names stigma, discrimination, poverty and exposure to violence as conditions that can limit access to health care and treatment (PHAC, 2020). For patients from rural, remote and northern communities, the nurse also considers how distance from services may affect testing and follow-up. Rates in 2023 were highest in the Northwest Territories, Nunavut, Saskatchewan, Yukon and Manitoba (PHAC, 2025c). Regional rates describe the conditions people live in, not the people themselves. Cultural safety, distinctions-based care for First Nations, Inuit and Métis patients, and trauma-informed care are covered in Chapter 2.

Common Infections

Chlamydia is caused by the bacterium *Chlamydia trachomatis*, and **gonorrhea** by *Neisseria gonorrhoeae*. Both infect the cervix, urethra, rectum or throat. Both often cause no symptoms. As many as 70% of sexually active females and more than half of males with chlamydia have none (Thunder Bay District Health Unit [TBDHU], 2026), and gonorrhea is frequently present without symptoms, which is why screening is essential for finding cases (PHAC, 2026a). When chlamydia does cause symptoms, they may include discharge from the cervix or urethra and burning or frequency on urination (TBDHU, 2026). Untreated chlamydia can spread and cause **pelvic inflammatory disease** (PID), an infection of the uterus, fallopian tubes and nearby pelvic structures, which can lead to ectopic pregnancy, infertility and chronic pelvic pain. Chlamydia can also cause epididymo-orchitis and reactive arthritis (PHAC, 2025b).

N. gonorrhoeae can quickly develop resistance to several classes of antibiotics (PHAC, 2026a). This is why the national guide recommends ceftriaxone alone, given intramuscularly, for uncomplicated gonorrhea; why culture is collected in some situations, because it shows which drugs still work; and why everyone treated needs a test of cure (PHAC, 2026a). Doxycycline or azithromycin is recommended for chlamydia in adults who are not pregnant (PHAC, 2025b). Provincial and territorial guidance may differ because resistance patterns vary.

Syphilis is caused by the bacterium *Treponema pallidum*. It moves through stages, and it can be missed at each one:

- **Primary:** a painless open sore (chancre) at the site of contact, with swollen nearby lymph nodes. Because it does not hurt and heals on its own within weeks, it is easy to ignore (Figure 29.5).
- **Secondary:** a rash that usually does not itch, which can be subtle on darker skin and may appear on the trunk, palms and soles, with fever, malaise, swollen lymph nodes and mucous patches; headache, meningitis and eye inflammation can occur.
- **Latent:** no symptoms; a positive blood test is the only sign.
- **Tertiary:** years later, damage to the heart and blood vessels, the nervous system or other tissues (Hastings Prince Edward Public Health, 2023; Sexually Active Client? Think Syphilis!, n.d.; PHAC, 2025d).

Syphilis is diagnosed with blood tests. Infectious syphilis is treated with benzathine penicillin G given intramuscularly, and neurosyphilis needs specialist care and intravenous antibiotics (PHAC, 2025d). **Congenital syphilis** is syphilis passed from a pregnant person to the fetus.

Genital herpes is a lifelong infection with herpes simplex virus (HSV). HSV-2 has been the usual cause, but genital HSV-1 infections have risen considerably. Recurrences can be noticed or unnoticed, and the virus is often shed without symptoms, so it can spread from a person with no sores. A recent infection also raises the risk of acquiring and passing on HIV. Oral acyclovir,

famciclovir or valacyclovir treats outbreaks, and daily suppressive therapy is recommended for frequent or severe recurrences and can lower transmission to a partner (PHAC, 2021).

HPV (section 29.3) has many types. Types 6 and 11 cause most **anogenital warts**, which are spread by skin-to-skin contact and are usually diagnosed by looking at them. Most warts eventually go away on their own but often come back, and treatment removes warts without clearing the virus (PHAC, 2025a). Oncogenic HPV types and cervical screening are discussed in section 29.3, and the HPV vaccine in Chapter 21.

Trichomoniasis is caused by the parasite *Trichomonas vaginalis*. It can cause a purulent vaginal discharge, itching, pain on urination and pain with intercourse. It raises the risk of acquiring HIV and of preterm birth. Metronidazole is the first-line treatment, and partners are treated together with the patient to prevent reinfection (Cenkowski et al., 2022).

Figure 29.5 A primary syphilitic chancre on the tongue, showing the characteristic firm, round, painless ulcerated lesion at the site of inoculation. (credit: "Circular primary syphilitic chancre on the tongue" by CDC/Robert E. Sumpter, Public Health Image Library #12623, Public domain)

The main points for each infection are compared side by side (Table 29.3).

Table 29.3 Common sexually transmitted infections at a glance (PHAC, 2021, 2025a, 2025b, 2025d, 2026a; Cenkowski et al., 2022; TBDHU, 2026)

Infection	Common findings	Testing	Treatment (named only)	Nursing and public health points
Chlamydia	Often none; discharge, burning or frequency on urination	NAAT on first-void urine or vaginal, cervical, rectal or throat swab	Doxycycline or azithromycin	Reportable; partners from the past 60 days tested and treated; retest 3 months after treatment
Gonorrhea	Frequently none; serious complications if untreated	NAAT; culture when needed to check which antibiotics work	Ceftriaxone, intramuscular	Reportable; partners from the past 60 days; test of cure at every positive site
Infectious syphilis	Painless sore; later rash, swollen lymph nodes; may have no signs	Blood tests (serology)	Benzathine penicillin G, intramuscular	Reportable; contacts traced by stage; repeat blood tests to confirm response
Genital herpes	Genital sores during outbreaks; often shed without symptoms	NAAT or viral culture from a sore	Acyclovir, famciclovir or valacyclovir	Lifelong; suppressive therapy option; patients encouraged to tell partners
Anogenital warts (HPV)	Growths on genital or anal skin	Diagnosed by looking; biopsy if unusual	Removal or topical therapies	Treatment does not clear HPV; review vaccination and cervical screening
Trichomoniasis	Discharge, itching, pain on urination or with intercourse	NAAT (most sensitive in women)	Metronidazole	Treat partners at the same time to prevent reinfection

Testing, Treatment and Public Health

A **nucleic acid amplification test** (NAAT) detects the genetic material of an organism and is the most sensitive test for chlamydia and gonorrhea. Specimens can be first-void urine (the first part of the stream) or vaginal, cervical or urethral swabs; throat and rectal swabs are taken based on the sexual history and on what the local laboratory offers (PHAC, 2025b, 2026a). The nurse explains each specimen, offers self-collection where policy allows, and labels specimens with the site. A positive test is a reason to offer testing for other STBBIs, including HIV and syphilis (Chapter 21).

Partner notification is the process of telling sexual partners that they may have been exposed so that they can be tested and treated. For chlamydia and gonorrhea, the national guides call for testing and treating all partners from the 60 days before symptoms began or, without symptoms, before the test was taken (PHAC, 2025b, 2026a). Syphilis tracing goes back further, depending on the stage (PHAC, 2025d). Partner notification is not a public health requirement for herpes or warts, but patients are encouraged to tell partners (PHAC, 2021, 2025a). Public health staff can help notify partners without naming the patient.

In Ontario, chlamydia, gonorrhea and syphilis are diseases of public health significance under the *Health Protection and Promotion Act* and its regulations. As Ontario law sets out, physicians and other health care providers, laboratories and hospital administrators report suspected or confirmed cases to the local medical officer of health as soon as possible or by the next working day, and Ontario's privacy law allows this disclosure (Middlesex-London Health Unit, 2026). Chlamydia and syphilis are reportable in every province and territory (PHAC, 2025b, 2025d), though each sets its own rules. The nurse follows employer policy on who files the report and protects the patient's privacy within the team (Chapter 1).

Follow-up completes treatment:

- **Gonorrhea:** a test of cure at every positive site. Culture can be taken at least 3 days after treatment; NAAT should wait 3 to 4 weeks or longer, because leftover genetic material can give a false positive (PHAC, 2026a).
- **Chlamydia:** a test of cure at 3 weeks in some situations, such as pregnancy or doubtful adherence, and repeat screening for everyone 3 months after treatment (PHAC, 2025b).
- **Syphilis:** repeat blood tests at set intervals to confirm the response (PHAC, 2025d).

Nursing care follows the clinical judgment model (Chapter 1, section 1.4). The nurse **recognizes cues** that may point to an STBBI in a patient admitted for something else: unexplained discharge, genital or mouth sores, a new rash, pelvic or testicular pain, or a positive result in the chart. The nurse **analyzes** these cues alongside the sexual health history (section 29.1) and **takes action** by reporting them, offering testing as ordered or as a medical directive allows, and using calm, non-judgmental language. Fever, worsening pelvic pain or signs of sepsis in a patient with possible PID are escalated at once (Chapters 4 and 6).

Teaching covers:

- taking every dose of oral treatment and returning for follow-up tests;
- avoiding sex until treatment is complete and partners have been treated, as the prescriber or public health advises;
- regular testing; for example, the national guide recommends syphilis screening every 3 to 6 months for people with multiple partners (PHAC, 2025d);
- condoms, other prevention and vaccines (Chapter 21);
- returning if symptoms persist or come back.

Age is never a reason to skip a sexual health conversation or an offer of testing. Older adults may have new partners later in life, and in an older patient, discharge or burning on urination can be mistaken for a urinary tract infection or for menopause changes (sections 28.1 and 29.4).

CANADIAN CONTEXT

Syphilis in Canada

After years of increases, Canada reported 12,135 cases of infectious syphilis in 2023, or 30.5 per 100,000 population. The rate fell 16% from 2022, the first national drop since 2014, but remained 77% above the 2018 level. PHAC cautions that one year of data is not a trend (PHAC, 2025c).

- **Who is affected:** 64% of 2023 cases were in males, and cisgender gay, bisexual and other men who have sex with men accounted for 27% of all cases. The rate in females was 204% higher than in 2018 (PHAC, 2025c).
- **Congenital syphilis:** 53 confirmed early cases were reported in 2023, a rate of 14.5 per 100,000 live births. That was 56% lower than in 2022 but 220% higher than in 2018. Of the provincial rates published, Manitoba's was the highest, and Ontario had the most confirmed cases (PHAC, 2025c).
- **Prevention:** The national guide recommends syphilis screening for everyone early in pregnancy, and again later for those at ongoing risk (PHAC, 2025d).

- **Treatment supply:** Health Canada reports a shortage of Bicillin L-A, the benzathine penicillin G product that Pfizer markets in Canada, caused by a manufacturing disruption and expected to last until February 2027. Health Canada has allowed a Portuguese-authorized benzathine penicillin product to be imported in the meantime (Health Canada, 2026).

29.6 Erectile Dysfunction and Gender-Affirming Care

Erectile Dysfunction

Erectile dysfunction (ED) is the inability to get or keep an erection firm enough for satisfying sex. It is common in Canada and becomes more common and more severe with age (Domes et al., 2021). An erection depends on healthy blood vessels, nerves, hormones and emotional well-being, so ED often signals a problem elsewhere (Figure 29.6).

The Canadian Urological Association (CUA) notes that ED and cardiovascular disease share many risk factors, and that in some people ED may be an early signal of later heart and blood vessel events. Risk factors include older age, diabetes, high cholesterol, hypertension, obesity, metabolic syndrome, inactivity and smoking. The CUA suggests considering blood glucose, glycated hemoglobin (HbA1c) and lipid tests to look for undiagnosed diabetes and high cholesterol (Domes et al., 2021). Medications, stress, performance anxiety and mental illness can also contribute, and including the partner in care improves outcomes. Exercise, quitting smoking and cutting down on alcohol and cannabis are first steps (Domes et al., 2021). The nurse who hears about ED does not dismiss it as a private matter; it is a reason to check blood pressure, glucose and cardiovascular risk (Chapters 17, 19 and 22).



Figure 29.6 Sagittal view of the male reproductive and lower urinary structures, including the erectile tissue of the corpus cavernosum and corpus spongiosum (cropped to panel [c]). (credit: modification of "Figure 27.2, Male Reproductive System" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

The CUA strongly recommends a **phosphodiesterase type 5 (PDE5) inhibitor** as the first drug for ED. These drugs block the PDE5 enzyme, which allows more blood flow into the penis during sexual arousal. Sildenafil, tadalafil and vardenafil are the PDE5 inhibitors the guideline names. Common adverse effects are headache, flushing, indigestion and nasal congestion; vision changes can occur with sildenafil and vardenafil, and muscle aches with tadalafil. A lower dose may be needed for people over 65, people with liver or kidney impairment and people taking drugs that strongly block the liver enzyme CYP3A4 (Domes et al., 2021). Other options include vacuum devices, alprostadil inserted into the urethra or injected into the penis, and a penile implant (Domes et al., 2021).

The most dangerous interaction is with **nitrates**, such as nitroglycerin and isosorbide. Both drug groups act on the same nitric oxide pathway that relaxes blood vessels, and together they can cause a sudden, severe and potentially life-threatening drop in blood pressure (Sun Pharma Canada, 2024). The CUA lists regular or occasional nitrate use as an absolute contraindication to PDE5 inhibitors (Domes et al., 2021). The Canadian product monographs describe the time windows differently for each drug:

- **Sildenafil:** the monograph states that it is not known when nitrates, if needed, can be safely given after a dose (BGP Pharma, 2023).
- **Tadalafil:** if a nitrate is judged medically necessary because a situation is life-threatening, at least 48 hours should pass after the last dose, and the nitrate is then given only with close medical supervision and hemodynamic monitoring (Sun Pharma Canada, 2024).
- **Vardenafil:** the same conditions apply, with at least 24 hours after the last dose (Angita Pharma, 2022).

Because of this, every nurse asks about PDE5 inhibitors before giving a nitrate, every time (Chapter 17). Patients may not list them as "medications"; some buy them online, and some feel embarrassed to mention them.

Nursing care for ED centres on asking, listening and linking. The nurse includes erections in the sexual health history and medication review, uses plain words, and lets the patient know that ED is common and treatable. Cues such as new ED with chest discomfort on exertion, high blood pressure or high glucose are passed to the prescriber. Surgery or illness that affects nerves or blood flow, such as prostate surgery (Chapter 28) or diabetes (Chapter 22), can lead to ED, and the nurse helps the patient prepare questions for the surgeon or prescriber. Teaching for a person prescribed a PDE5 inhibitor includes taking it only as prescribed, telling every care provider about it, never combining it with a nitrate, and getting help at once for chest pain or the warning signs below. For older adults, who may take several heart and blood pressure drugs, the medication review is especially important.

Priapism is a prolonged erection that is not linked to sexual desire. The monographs tell patients to seek immediate medical help for an erection that lasts more than 4 hours, because without prompt treatment it can damage penile tissue and cause permanent loss of erections (BGP Pharma, 2023; Sun Pharma Canada, 2024). The nurse treats it as an emergency and reports it at once. Patients also stop the drug and get prompt care for sudden loss of vision or hearing (BGP Pharma, 2023).

Gender-Affirming Care in Medical-Surgical Settings

Gender-affirming care is care that respects and supports a person's gender identity. In a medical-surgical setting, it starts with basics. The basics of 2SLGBTQI+ inclusive care are in Chapter 2.

- **Names and pronouns:** Using the name a person uses in daily life and the correct pronouns is fundamental to good care (Bourns, 2019). The nurse asks once, privately, records the answer where the health record allows, and uses it consistently. When the legal name on a health card differs, the nurse uses it only where identification requires it.
- **Organ inventory:** Care and screening follow the organs a person has, not their gender identity (section 29.1). A transgender man may need cervical screening; a transgender woman still has a prostate (section 28.6). Ontario's breast and cervical screening programs include transgender and nonbinary people who meet their criteria (sections 29.2 and 29.3; Table 29.1).
- **Hormones around surgery:** Gender-affirming hormones include estradiol, anti-androgens such as spironolactone or cyproterone, and testosterone (Bourns, 2023). Clinicians once stopped estrogen before surgery out of concern for VTE. A review of the evidence found no data showing that holding hormones before gender-affirming surgery lowers that risk, and it recommends individual assessment for older patients and those with other risk factors (Zucker et al., 2021). Hormone therapy is generally expected before genital surgery or removal of the gonads unless it is contraindicated (Bourns, 2019). Of all routes, only transdermal estradiol has direct evidence of a lower clot risk, and the Sherbourne guidelines prefer it for people over 40 or with clot risk factors (Bourns, 2019). The nurse does not stop or hold hormones without an order, asks the surgical team or prescriber for a plan, and gives VTE prophylaxis as ordered (Chapters 7 and 19).
- **After gender-affirming surgery:** Patients may have surgery far from home and then return to a local hospital or clinic. A US gender-affirming care guideline states that, after vaginoplasty, following the dilation schedule is critical to healing and to keeping the vagina open, and that dilation continues regularly for at least a year (Meltzer, 2016). Bleeding, a hematoma, separation of the wound, trouble voiding and signs of infection are reported to the surgical team. After removal of the testes, anti-androgens are often no longer needed, but that decision belongs to the prescriber (Bourns, 2023).
- **Privacy and safety:** A person's gender history is shared only with those who need it for care. Room assignment follows hospital policy and the patient's identity, and questions are asked only when they matter for care, never out of curiosity.

Two-Spirit is a term chosen in 1990 by Indigenous people to describe the wide range of Indigenous understandings of gender and sexual diversity; its meaning varies from person to person and from community to community (Bourns, 2019). Many Two-Spirit identities exist across North America, and some carry spiritual or ceremonial meaning (Coleman et al., 2022). The nurse asks how a Two-Spirit patient wants to be identified and supported, including involving family, Elders or traditional practices, rather than assuming a meaning.

CLINICAL SAFETY

PDE5 Inhibitors and Nitrates

A PDE5 inhibitor taken with a nitrate can cause a sudden, severe and sometimes life-threatening drop in blood pressure (Domes et al., 2021).

- **Ask every time:** Before giving nitroglycerin in any form (spray, tablet, patch, ointment or infusion) or isosorbide, ask directly: "Have you taken any medicine for erections, such as sildenafil, tadalafil or vardenafil, in the past few days?" Ask privately, without judgment, and explain why it matters.
- **If the answer is yes, or unknown:** hold the nitrate, record the drug and the time of the last dose, and tell the prescriber at once. The time windows differ by drug and apply only to life-threatening situations under close monitoring (BGP Pharma, 2023; Sun Pharma Canada, 2024; Angita Pharma, 2022).
- **Document clearly:** add the PDE5 inhibitor to the medication history and flag it for the team.
- **Teach:** a patient who has been prescribed a nitrate should not use a PDE5 inhibitor, and anyone who gets chest pain after taking one calls 9-1-1 and tells the paramedics and the hospital what they took and when.

CLINICAL JUDGMENT

Chest Pain After an Erectile Dysfunction Pill

Names and details are fictional; this is a composite story.

Teodoro Alvarez, 58, is on day 2 after a laparoscopic cholecystectomy on a surgical unit. At 06:00 he reports a tight pressure in his chest. He has hypertension and type 2 diabetes. His heart rate is 102, blood pressure 128/78 mm Hg, respiratory rate 22 and SpO_2 94% on room air, and his skin is damp. A standing order allows sublingual nitroglycerin for chest pain.

- **Recognize cues:** New chest pressure, diaphoresis, a fast heart rate and cardiac risk factors. The nurse asks about erection medicines before reaching for the nitroglycerin. Mr. Alvarez says quietly that he takes tadalafil daily and took a tablet from his home supply yesterday at 20:00.
- **Analyze cues:** Fewer than 48 hours have passed since the last tadalafil dose, and daily tadalafil keeps a steady level of the drug in the blood (Sun Pharma Canada, 2024). His blood pressure is normal now, but nitroglycerin could drop it suddenly and dangerously. He had not listed tadalafil on admission because he did not think of it as a medicine.
- **Prioritize hypotheses:** Acute coronary syndrome is the leading concern; the drug interaction is the immediate safety risk.
- **Generate solutions:** Hold the nitroglycerin, escalate at once and prepare for cardiac assessment as ordered.
- **Take action:** The nurse calls the rapid response team using Situation, Background, Assessment, Recommendation (SBAR; Chapter 6), states the tadalafil timing clearly, stays with the patient, and obtains a 12-lead electrocardiogram (ECG) as the team directs. The physician orders other treatment and no nitrate.
- **Evaluate outcomes:** The pain eases, vital signs settle and the team documents the PDE5 inhibitor as a nitrate alert. The nurse updates the medication reconciliation and, before discharge, teaches Mr. Alvarez to tell every care provider, including paramedics, about his tadalafil.

SCOPE IN PRACTICE

Sexual Health Care and Who Does What

CNO's Scope of Practice standard asks whether a nurse has the **authority**, the **competence** and the right **context** for an activity (Chapter 1, section 1.3).

- **Testing:** RNs and RPNs collect STBBI specimens, such as urine and swabs, under an order or a medical directive and as employer policy allows. Both teach patients how to self-collect where that is offered.
- **Treatment:** STBBI treatment is given under a prescriber's order or a medical directive. Authorized RNs in Ontario can prescribe drugs from a set list, each for set purposes such as immunization, contraception, travel health and smoking cessation; treating STBBIs is not one of those purposes (College of Nurses of Ontario [CNO], n.d.), and RN prescribing does not apply in public hospitals. CNO's revised Scope of Practice and Medication standards take effect March 1, 2027.
- **Competence:** Taking a sexual health history, counselling on partner notification and giving intramuscular injections need knowledge and practice. A nurse who has not developed these skills seeks education and support before taking them on.
- **Context:** The RPN consults the RN when a patient's needs become more complex, such as signs of PID with fever or pain, a positive test during pregnancy, or a disclosure of sexual violence. Every nurse escalates deterioration at once.
- **Confidentiality and reporting:** Both RNs and RPNs protect sexual health information and follow employer policy on reporting diseases of public health significance.

Employer policy and the province or territory shape these roles.

PRACTICE STORY

The Question I Almost Didn't Ask

Names and details are fictional; this is a composite story.

Nurse: Leila Khoury, RPN. Years in practice: 4. Setting: medical unit, Ontario.

Mr. Lachance was 66, admitted with pneumonia and heart failure. On my admission checklist there was a line about sexual health. I usually skipped it for older men on the medical unit. It felt awkward, and I told myself it was not why he was here.

That evening his wife had gone home, and he was chatting about his garden. I remembered a workshop where the instructor said that skipping the question is a decision too. So I said, "I ask everyone this. Some illnesses and medicines affect sexual health. Is there anything about that you want to mention, or any medicines for it that you take?"

He laughed, then went quiet. "My doctor doesn't know, but I get pills online. For erections." He had taken one the night before he came in. He did not know the name, but he described the blue tablet and the package.

I knew there was a new order for a nitroglycerin patch, due to be applied that night, written because of chest discomfort he had reported in the emergency department. I checked: the patch had not been applied yet. I asked him if I could share what he told me with the team, explained why, and he agreed.

I told Daniel, the RN on our team, right away, and together we called the physician. The patch was held, his blood pressure was monitored, and the pharmacist added the drug to his record as an alert. The next morning the physician talked with him about safer options and about bringing the package in so the drug could be identified.

What stays with me is how close I came to not asking. He would not have volunteered it, and no one else had asked.

Reflect: Which parts of this situation were within the RPN's own scope, and when did she need to involve the RN and the physician? How would you phrase a sexual health question so that it feels routine rather than intrusive?

Chapter 29 Summary

29.1 Sexual Health in Medical-Surgical Care

- Illness, surgery and medications often affect sexual health, and patients rarely raise it; the nurse asks every patient, in private, with permission and an explanation of why.
- PHAC prefers brief, routine assessments that use the patient's own terms for their body, explain confidentiality and its limits, and follow a trauma- and violence-informed approach.
- A sexual health history covers activity and partners, protection, past STBBIs, symptoms and reproductive health; questions about bodies and practices, and an organ inventory, are more useful than questions about identity.
- The nurse asks about possible pregnancy before surgery, radiation-based imaging and some drugs and follows the employer's testing policy; Canadian and US guidelines recommend screening for asymptomatic bacteriuria in pregnancy.
- Hypertension in pregnancy has its own definitions in the SOGC guideline; severe hypertension or new headache or visual change in pregnancy needs urgent obstetric assessment.

29.2 Breast Cancer Care

- Breast cancer is the most common cancer among women in Canada (excluding non-melanoma skin cancers): an estimated 32,400 women and 300 men will be diagnosed in 2026, and about 1 in 8 women will be diagnosed over their lifetime.
- The 2024 Canadian Task Force draft was not finalized before the Task Force's mandate ended in March 2026; since October 2024 the OBSP screens people aged 40 to 74, most every 2 years, with yearly mammography and MRI for high-risk people aged 30 to 69.
- Only a biopsy can confirm breast cancer; hormone receptor and HER2 status guide treatment.
- After breast surgery, the nurse manages the closed suction drain and output log, watches for bleeding, seroma and infection, reinforces arm exercises and supports body image.

- Lymphedema causes heaviness, aching and swelling; advice to avoid blood pressure and needles in the affected arm continues, though evidence for it is limited, while skin protection, infection prevention and early referral are well supported.

29.3 Gynecologic Conditions and Surgery

- Abnormal uterine bleeding, often from fibroids, can cause iron deficiency anemia; most fibroids cause no symptoms and need no treatment.
- Endometriosis affects about 10% of women, with a diagnostic delay of at least 5 years in Canada; the 2024 SOGC guideline supports clinical diagnosis so that treatment is not delayed.
- After hysterectomy, the nurse watches for bleeding (including internal bleeding with a dry pad), voiding problems, bowel function, VTE and infection; removing both ovaries causes surgical menopause.
- Ontario replaced the Pap test with HPV testing in March 2025: most eligible people with a cervix are screened every 5 years from age 25; a positive result is not a cancer diagnosis.
- Ovarian cancer has vague symptoms; any bleeding after menopause needs assessment, because abnormal bleeding is the sign of uterine cancer seen most often.

29.4 Menopause and Midlife Health

- Menopause is confirmed after 12 months in a row without a period; the average age in Canada is 51, and perimenopause can begin years earlier.
- Surgical or medically induced menopause is often sudden and more severe; the SOGC recommends considering hormone replacement until about age 51 when ovarian function is lost before 45.
- Hot flashes, night sweats, sleep problems, mood changes and genitourinary syndrome of menopause are common and treatable.
- The SOGC and The Menopause Society describe menopausal hormone therapy as the most effective treatment for hot flashes and as favourable for people under 60 or within 10 years of menopause who have no contraindications; a progestogen is added when a uterus is present.
- Contraindications include breast cancer, past clots, stroke or heart attack, undiagnosed bleeding and active liver disease; low-dose vaginal estrogen treats GSM at any age.
- The nurse supports an informed choice, reports contraindication cues and links midlife care to bone, heart and bladder health.

29.5 Sexually Transmitted and Blood-Borne Infections

- Chlamydia is the sexually transmitted infection reported most often in Canada; infectious syphilis fell in 2023 for the first time since 2014 but remains well above 2018 levels.
- Gonorrhea is frequently silent and can quickly develop antibiotic resistance; ceftriaxone is recommended, with a test of cure at every positive site.
- Syphilis can be missed at every stage; a painless sore or a subtle rash is a reason to test.
- NAAT on first-void urine or swabs is the most sensitive test for chlamydia and gonorrhea; partners from the past 60 days are tested and treated.
- In Ontario, chlamydia, gonorrhea and syphilis are reported to the medical officer of health; the nurse follows employer policy and protects privacy.
- A Health Canada–reported shortage of benzathine penicillin G is expected to last until February 2027.

29.6 Erectile Dysfunction and Gender-Affirming Care

- Erectile dysfunction shares risk factors with cardiovascular disease and may be an early warning sign.
- PDE5 inhibitors (sildenafil, tadalafil, vardenafil) with nitrates can cause severe hypotension; the nurse asks about them before every nitrate and holds the nitrate and escalates if the answer is yes or unknown.
- Canadian monographs give no safe interval for sildenafil and allow nitrates only in life-threatening situations, with close monitoring, after 48 hours for tadalafil and 24 hours for vardenafil.
- An erection lasting more than 4 hours is an emergency.

- Gender-affirming care uses the patient's name and pronouns, bases screening on organs present, and does not stop hormones around surgery without an order.
- Two-Spirit identities carry different meanings for different people and communities; the nurse asks rather than assumes.

Key Terms (48)

abnormal uterine bleeding: Uterine bleeding that differs from a person's usual menstrual pattern in amount, duration, frequency or regularity, or that occurs between periods.

anogenital warts: Skin growths in the genital or anal area caused mainly by HPV types 6 and 11.

asymptomatic bacteriuria: Bacteria in the urine without symptoms of urinary tract infection; screened for and treated in pregnancy but not in most other adults.

axillary lymph node dissection: Surgery that removes lymph nodes from the armpit, usually when breast cancer has spread to them.

bilateral salpingo-oophorectomy: Surgical removal of both ovaries and both fallopian tubes.

biopsy: Removal of a tissue sample for examination by a pathologist; the only test that confirms breast cancer.

breast-conserving surgery: Surgery that takes out a breast tumour with a rim of healthy tissue and keeps the rest of the breast; usually followed by radiation.

chlamydia: A sexually transmitted infection caused by Chlamydia trachomatis; the sexually transmitted infection reported most often in Canada.

closed suction drain: A soft tube from a wound to a compressible bulb that draws out blood and lymph by suction.

congenital syphilis: Syphilis passed from a pregnant person to the fetus.

endocrine therapy: Treatment that blocks the production or action of hormones that some cancers use to grow, such as tamoxifen or an aromatase inhibitor for breast cancer.

endometriosis: A chronic inflammatory condition in which tissue similar to the uterine lining grows outside the uterus, causing pain and sometimes infertility.

erectile dysfunction: The inability to get or keep an erection firm enough for satisfying sex.

external breast form: A breast prosthesis of foam, silicone or another material, worn inside a bra to restore shape after breast tissue is removed.

gender-affirming care: Care that respects and supports a person's gender identity.

genital herpes: A lifelong infection with herpes simplex virus that causes recurrent genital sores and can spread without symptoms.

genitourinary syndrome of menopause: A group of vulvar, vaginal and lower urinary tract symptoms, such as dryness, painful intercourse and urgency, caused by falling estrogen.

gonorrhea: A sexually transmitted infection caused by Neisseria gonorrhoeae, a bacterium that can quickly develop antibiotic resistance.

HER2: Human epidermal growth factor receptor 2, a cell-surface protein that some breast cancers make in excess; these cancers may respond to HER2-targeted drugs.

hormone receptor status: Whether cancer cells carry estrogen receptors, progesterone receptors or both, which predicts whether hormone-blocking treatment will work.

human papillomavirus: A common sexually transmitted virus; persistent infection with high-risk types causes cervical cancer.

hysterectomy: Surgical removal of the uterus; a total hysterectomy also removes the cervix.

lymphedema: Swelling caused by a build-up of lymph in the tissues when lymph cannot drain normally, often after lymph nodes are removed or treated with radiation.

mastectomy: Surgery that removes all of the breast tissue.

menopausal hormone therapy: Estrogen, alone or with a progestogen, used to relieve menopause symptoms.

menopause: The permanent end of menstruation caused by the loss of ovarian follicles, confirmed after 12 months in a row with no period and no other cause.

nucleic acid amplification test: A laboratory test that detects an organism's genetic material; the most sensitive test for chlamydia and gonorrhea.

organ inventory: A respectful record of the reproductive and sex organs a person has at present, used to guide screening and care without assumptions based on gender.

partner notification: The process of informing sexual partners of a possible exposure so they can be tested and treated.

PDE5 inhibitor: A drug that blocks phosphodiesterase type 5 to improve erections, such as sildenafil, tadalafil or vardenafil; contraindicated with nitrates.

pelvic inflammatory disease: Infection of the uterus, fallopian tubes and nearby pelvic structures, often a complication of chlamydia or gonorrhea.

pelvic organ prolapse: Descent of the bladder, uterus, top of the vagina or rectum into or beyond the vaginal opening because their supports have weakened.

perimenopause: The transition before menopause, when periods change and symptoms often begin; it can start 4 to 8 years before the final period and includes the 12 months after it.

pessary: A removable device placed in the vagina to support prolapsed pelvic organs.

post-mastectomy pain syndrome: Nerve pain in the chest, armpit or arm that persists after healing from breast surgery.

priapism: A prolonged erection not linked to sexual desire; an erection lasting more than 4 hours is an emergency.

screening mammogram: An X-ray of the breasts in a person with no symptoms, taken to find breast cancer early.

sentinel lymph node biopsy: Removal of the first lymph node or nodes that drain a tumour, to check whether cancer has spread to them.

seroma: A collection of fluid under the skin after surgery, such as under the skin flap after mastectomy.

sexual health history: A focused set of questions about a person's sexual activity, partners, protection, past sexually transmitted and blood-borne infections, symptoms and reproductive health.

sexually transmitted and blood-borne infection: An infection spread through sexual contact, blood or both.

surgical menopause: Menopause that begins abruptly when both ovaries are removed before natural menopause.

syphilis: A sexually transmitted infection caused by Treponema pallidum that progresses through primary, secondary, latent and tertiary stages.

trichomoniasis: A sexually transmitted infection caused by the parasite Trichomonas vaginalis.

Two-Spirit: A term chosen by Indigenous people in 1990 to describe the wide range of Indigenous understandings of gender and sexual diversity.

uterine fibroids: Non-cancerous growths of the muscle of the uterus.

vaginal estrogen: Low-dose estrogen placed in the vagina to treat genitourinary syndrome of menopause.

vasomotor symptoms: Hot flashes and night sweats, the most common symptoms of menopause.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mei Lin (Questions 1–4): Mei Lin Zhou, 58, is on day 1 after a left total mastectomy with sentinel lymph node biopsy on a surgical unit in Nova Scotia. A closed suction drain exits below the left chest incision and collected 60 mL of serosanguineous fluid overnight. At 0800 her blood pressure is 128/76 mm Hg, heart rate 82 beats/min, respiratory rate 16 breaths/min, temperature 37.1 °C and oxygen saturation 97% on room air, and she rates her pain 3 out of 10 with oral analgesics. She is expected to go home tomorrow with the drain in place. A licensed practical nurse (LPN) is caring for her.

1. [CORE] The LPN empties Ms. Zhou's drain at 0800. Which action is correct?

a. Measure and record the fluid, squeeze the bulb flat and close the plug while it is still squeezed.

b. Leave the bulb fully expanded after emptying it so that the fluid can flow into it freely by gravity.

c. Disconnect the bulb from the tubing and rinse it with tap water before closing the system again.

d. Empty the bulb only once each day, because opening the plug more often adds a risk of infection.

Answer: a — Suction depends on closing the plug while the bulb is compressed; the amount and colour are recorded on an output log (section 29.2, Breast Surgery and Nursing Care). Option b removes the suction the drain needs to work. Option c opens the closed system and invites contamination. Option d is wrong because the bulb is emptied as ordered and whenever it is about half full, not once a day; a full bulb loses suction (Alberta Health Services, 2022).

2. [CORE] At 1400, the LPN finds the bulb full of bright red fluid (90 mL in 2 hours) and the chest wall under the dressing tense and swollen. Ms. Zhou's heart rate is 108 beats/min and blood pressure 104/64 mm Hg. Which action should the LPN take first?

a. Empty the bulb, record the 90 mL on the output log and reassess the drainage again in one hour.

b. Apply an ice pack over the dressing and help Ms. Zhou turn onto her left side to apply pressure.

c. Stay with Ms. Zhou, recheck her vital signs and report the findings to the RN and surgeon at once.

d. Reinforce the dressing, remind her to keep the left arm low and document the change at the end of the shift.

Answer: c — Rapid bright red drainage, a tense swollen chest wall, a rising heart rate and a falling blood pressure suggest active bleeding or a hematoma, and any nurse who notices them acts and escalates at once (section 29.2; sections 6.1 and 7.6). Options a and d delay reporting a possible hemorrhage. Option b is not an ordered treatment and does not address the danger.

3. [CORE] Ms. Zhou says, "My friend said I can never have my blood pressure taken on my left arm again, for the rest of my life." Which response by the LPN is most accurate?

a. "Your friend is right: no blood pressures, blood tests or needles in that arm for life, or you will get lymphedema."

b. "Lymphedema does not happen after a sentinel node biopsy, so you can use that arm in any way you like."

c. "Many sources still advise using the other arm, though studies have not shown that it raises risk; protecting the skin from infection matters most."

d. "A compression sleeve worn every day from now on will prevent lymphedema, so I will ask for one before you go home."

Answer: c — The Canadian Cancer Society advises avoiding blood pressure readings and needles in the affected arm, but a prospective study found that blood draws and injections on the treated side were not linked to increases in arm volume and concluded that blood pressure readings may not be either, while cellulitis, axillary dissection, node radiation and higher body mass index were linked (section 29.2, Lymphedema). Option a overstates the evidence. Option b is wrong; lymphedema can follow sentinel node biopsy, though it is more common after dissection. Option d is wrong because compression garments are used only when a physician or physiotherapist recommends them.

4. [CORE] While the LPN changes the dressing, Ms. Zhou turns away and says, "My husband hasn't looked at me since the surgery. I don't know how I'll ever look at myself." Which response is best?

a. "Please don't worry. Most husbands get used to it quickly, and you can always have reconstruction later on."

b. "Try to focus on healing first. There will be plenty of time to think about your appearance after treatment."

c. "I will ask the surgeon to come and explain reconstruction to you and your husband before you go home."

d. "Many people feel this way after a mastectomy. Can you tell me more about what worries you most right now?"

Answer: d — Loss of a breast affects body image and relationships, and the nurse first acknowledges the feeling and invites the patient to say more (section 29.2, Breast Surgery and Nursing Care). Option a offers false reassurance and closes the conversation. Option b dismisses her concern. Option c jumps to a solution before the nurse knows what she needs; reconstruction may not be her concern at all.

5. [CORE] Ali Rahimi, 71, is recovering from abdominal surgery and has a new prescription for a drug that can affect sexual function. Which opening by the nurse best follows Canadian guidance for a sexual health conversation?

a. "I need to ask you some questions about your sex life now. Please answer every one, because they all matter for your care."

b. "Some of your new medicines can affect sex, so I ask everyone about it. Is it all right if I ask a few questions now?"

c. "At your age I don't suppose sex is much of a concern, but I'm required to ask, so please answer just yes or no."

d. "Your wife is here, so this is a good time for both of you to tell me whether sex has been a problem since surgery."

Answer: b — The nurse explains why the questions matter, makes them routine for everyone and asks permission, and the patient may decline any question (section 29.1, Talking About Sexual Health). Option a removes the patient's choice. Option c makes an ageist assumption. Option d breaches privacy by assuming the patient wants his partner present and assumes the partner's role.

6. [CORE] A nurse is completing an admission history for Jordan Tremblay, 34, a transgender man admitted for a bowel obstruction. Which question best supports an accurate organ inventory?

a. "Some of my questions depend on anatomy. Which of these organs do you have now: a cervix, uterus, ovaries or breasts?"

b. "Since you were born female, I will assume you still have all of your female organs unless you tell me otherwise."

c. "Have you finished your transition yet, or are you still planning to have more gender-affirming surgery at some point in the future?"

d. "Do you have sex with men, women or both, so that I know which tests you are likely to need?"

Answer: a — An organ inventory asks which organs the person has now, in a respectful, matter-of-fact way, because screening and care follow organs, not gender (section 29.1, Taking a Sexual Health History). Option b makes an assumption and uses language that may be distressing. Option c asks about transition in a way that is not needed for care. Option d asks about identity rather than body parts and practices, and does not tell the nurse which tests are relevant.

7. [CORE] Sophie Gagnon, 27, is scheduled for a computed tomography (CT) scan of the abdomen later today. Which action by the nurse is most appropriate?

a. Assume pregnancy is unlikely, because she was admitted for a medical problem and has not mentioned it to anyone on the unit.

b. Ask the radiology department to delay the CT for 2 weeks so that pregnancy can be safely ruled out.

c. Tell her to inform the CT technologist if she thinks she could be pregnant, and then continue with the plan as scheduled.

d. Ask about the possibility of pregnancy and her last menstrual period, and arrange a pregnancy test if policy requires it.

Answer: d — Before imaging that uses radiation, surgery and some drugs, the nurse asks about the possibility of pregnancy, including the last menstrual period, and follows the employer's testing policy (section 29.1, When a Patient Might Be Pregnant). Option a makes an unsafe assumption. Option b delays care without reason. Option c passes the nurse's responsibility to the patient.

8. [CORE] A patient who is 31 weeks pregnant is admitted to a medical unit with a kidney infection. At 1600 she reports a new severe headache and blurred vision, and her blood pressure is 166/112 mm Hg. Which action should the nurse take?

a. Give the acetaminophen ordered for headache and recheck her blood pressure in 4 hours.

b. Escalate at once for urgent obstetric assessment while staying with the patient.

c. Dim the room lights and encourage rest, since a kidney infection often causes a headache.

d. Treat her blood pressure using the adult targets the unit uses for patients with hypertension.

Answer: b — Hypertension in pregnancy has its own definitions and thresholds in the SOGC guideline, and a pregnant patient with severe hypertension or new symptoms such as headache or visual change needs urgent obstetric assessment (section 29.1, When a Patient Might Be Pregnant). Options a and c delay escalation of a possible emergency. Option d is wrong because the adult targets in Chapter 19 do not apply in pregnancy.

9. [CORE] Priya Sharma, 44, lives in Ontario, has no symptoms or family history of breast cancer and asks whether she can have a mammogram. Which response is accurate?

a. "Since October 2024, Ontario's program includes people in their 40s, most screened every 2 years; you can book it yourself."

b. "Ontario does not screen anyone in their 40s, so you will need to wait until you turn 50 before you can book a mammogram there."

c. "Everyone in Ontario over 40 must have a mammogram every year, and your family doctor will book it for you automatically."

d. "Because the national task force recommended against screening in your 40s, the Ontario program cannot offer it to you."

Answer: a — The OBSP expanded in October 2024 to people aged 40 to 49, most of whom are screened every 2 years, and people can book their own appointment; people in their 40s are encouraged to talk with a provider first (section 29.2, Screening and Diagnosis; Table 29.1). Option b is out of date. Option c is wrong about the interval and about screening being required. Option d misstates the task force draft, which suggested offering screening to people in their 40s who choose it and was not finalized.

10. [CORE] A nurse is teaching a patient who had an axillary lymph node dissection 3 months ago about early signs of lymphedema. Which findings should the patient report? Select all that apply.

a. A feeling of heaviness or fullness in the arm on the treated side

b. Rings or sleeves that feel tighter than usual on that side

c. Numbness along the inner upper arm that has been present since surgery

d. Swelling of the hand or fingers on the treated side

e. Aching or a burning feeling in the arm on the treated side

f. A healed incision that looks flat and pale

Answer: a, b, d, e — Early lymphedema causes fullness or heaviness, tight jewellery or clothing, swelling of the hand or fingers and aching or burning (section 29.2, Lymphedema). Option c describes numbness from nerve injury during surgery, which is common and not a sign of lymphedema. Option f is a normal healed incision.

11. [CORE] Two days after her drain was removed, a patient who had a mastectomy notices a soft, fluid-filled swelling under her incision. She has no fever, redness or increase in pain. Which is the nurse's best interpretation and action?

a. The swelling is lymphedema of the chest, so a compression garment should be fitted today.

b. The swelling is expected after any drain is removed and will always disappear without any follow-up.

c. The swelling is likely a seroma, so the nurse reports it to the surgical team, who may drain it.

d. The swelling is a sign of wound infection, so the nurse asks the surgeon for an antibiotic order.

Answer: c — A seroma is a collection of fluid under the skin flap that can build up after the drain is removed; the surgical team assesses it and may drain it (section 29.2, Breast Surgery and Nursing Care). Option a confuses seroma with lymphedema. Option b gives false reassurance. Option d does not fit; she has no signs of infection.

12. [CORE] Danielle Okafor, 39, has had heavy periods from uterine fibroids for a year. She reports changing a pad every hour on her heaviest days and becoming short of breath on stairs. Which nursing action is most important?

a. Reassure her that fibroids are very common and that most of them cause no symptoms and need no treatment.

b. Assess for iron deficiency anemia, including fatigue, pallor and her most recent hemoglobin result.

c. Teach her that fibroids are an early stage of uterine cancer and need to be removed promptly.

d. Advise her to limit fluids on heavy days to reduce the amount of bleeding during her period.

Answer: b — Fibroids that cause abnormal uterine bleeding can lead to iron deficiency anemia, and her shortness of breath on exertion suggests it (section 29.3, Common Gynecologic Conditions; section 20.2). Option a is true in general but ignores her symptoms. Option c is false; fibroids are not cancer. Option d is unsafe and would not reduce bleeding.

13. [CORE] Sarah Bjornson, 29, has had painful periods and pelvic pain for 6 years and asks, "Do I have to have surgery before anyone will treat me for endometriosis?" Which response reflects the 2024 SOGC guideline?

a. "Yes. Endometriosis can be confirmed only by surgery, and hormonal treatment cannot begin until it is."

b. "Yes, but only if a blood test for endometriosis is positive. That test comes first, before anything else."

c. "No. Treatment is mainly surgical, so the surgeon will decide whether the disease needs to be removed."

d. "No. It can be diagnosed from your history, an examination and ultrasound, and treatment can start then."

Answer: d — Under the SOGC guideline, endometriosis can be diagnosed clinically from symptoms, examination and ultrasound so that treatment is not delayed; surgery is not the main way to investigate it (section 29.3, Common Gynecologic Conditions). Option a describes an older approach that delays care. Option b is wrong; no blood test is described for diagnosis. Option c is wrong because hormonal treatment, not surgery, is first-line.

14. [CORE] Six hours after an indwelling catheter was removed following a laparoscopic hysterectomy, a patient has not voided and reports fullness above the pubic bone. What should the nurse do next?

a. Use a bladder scanner to measure the urine in her bladder and follow the unit protocol.

b. Reinsert an indwelling catheter right away and leave it in overnight to rest the bladder.

c. Encourage her to drink 1 L of water over the next hour to stimulate the urge to void.

d. Document the finding and reassess at the next routine check in 4 hours.

Answer: a — After catheter removal, the nurse confirms voiding and uses a bladder scan as the unit protocol directs (section 29.3, Hysterectomy and Gynecologic Surgery; sections 7.6 and 28.3). Option b skips assessment and adds catheter risk. Option c adds volume to a bladder that may already be overfull. Option d delays care for a patient with symptoms.

15. [CORE] Nadia Haddad, 42, is going home after a total hysterectomy with bilateral salpingo-oophorectomy for endometriosis. Which statement shows she understands her teaching?

a. "Since my uterus was removed, my periods will stop, but my hormone levels won't change until my natural menopause."

b. "Hot flashes are a sign of infection, so I should call the surgeon if I get them at home."

c. "Because both ovaries were removed, I may get hot flashes and vaginal dryness soon, and I can ask about treatment."

d. "I will need to keep having cervical screening every 5 years, just as I did before the surgery."

Answer: c — Removing both ovaries before natural menopause causes surgical menopause, with an abrupt drop in hormones that can bring hot flashes and vaginal dryness (section 29.3, Hysterectomy and Gynecologic Surgery; section 29.4). Option a would be true only if the ovaries remained. Option b mistakes a menopausal symptom for infection. Option d is wrong; a total hysterectomy removes the cervix, and cervical screening follows organs (section 29.1).

16. [CORE] An Ontario registered practical nurse (RPN) is caring for a patient 4 hours after a vaginal hysterectomy. The patient becomes pale and restless, her heart rate rises from 84 to 116 beats/min and her pad is soaked with bright red blood. Which action by the RPN is best?

a. Change the pad, document the amount of blood lost and recheck the patient's vital signs again in one hour's time.

b. Stay with the patient, call for help, report to the RN at once and activate the rapid response process as policy directs.

c. Ask the RN to take over the patient's care completely, because unexpected postoperative bleeding is outside the RPN's scope.

d. Raise the head of the bed and give the next dose of analgesic as ordered, because pain can raise the heart rate.

Answer: b — Every nurse who notices deterioration acts at once and escalates; the RPN consults the RN as the patient's needs change and follows the rapid response process (section 29.3; sections 1.3 and 6.2). Option a delays escalation. Option c is wrong: the RPN does not step away from a deteriorating patient but acts and consults. Option d treats a possible hemorrhage as pain.

17. [CORE] A new RPN asks whether RPNs in Ontario take sexual health histories. Which response by the charge nurse is most accurate?

a. "No. Only RNs and nurse practitioners may ask patients about sexual health, because asking is a controlled act."

b. "Yes, but only when the patient's physician has written a specific order that allows the RPN to ask those questions."

c. "No. Sexual health questions are always left to the primary care provider after discharge."

d. "Yes, when you have the competence and employer policy supports it, and you consult the RN if needs become complex."

Answer: d — CNO describes scope through authority, competence and context; taking a sexual health history is not a controlled act, and the RPN consults the RN as the patient's needs become more complex. Employer policy and province or territory matter (section 29.1; section 1.3). Option a is wrong; history-taking is not a controlled act. Option b adds a requirement that does not exist. Option c misses the medical-surgical reasons for asking, such as medications and the possibility of pregnancy.

18. [RN] A pathology report for a patient with invasive breast cancer shows that the tumour is estrogen receptor-positive, progesterone receptor-positive and HER2-negative. Which treatment should the RN expect the oncology team to discuss as part of the long-term plan?

a. Endocrine therapy, such as tamoxifen or an aromatase inhibitor, to block the effects of the hormones

b. A HER2-targeted drug, given because the tumour cells are making more of the HER2 protein than normal cells do

c. No drug therapy at all, because receptor-positive tumours do not respond to systemic treatment

d. Menopausal hormone therapy to replace the estrogen that the tumour's receptors are binding

Answer: a — Hormone receptor-positive cancers use estrogen or progesterone to grow, so endocrine therapy that blocks hormone effects is usually offered (section 29.2, Going Deeper: Hormone Receptor and HER2 Status). Option b applies to HER2-positive cancers. Option c is wrong; receptor status predicts response to hormone-blocking therapy. Option d would feed a hormone-sensitive cancer.

19. [RN] Eight hours after an abdominal hysterectomy, a patient's heart rate has risen from 88 to 124 beats/min, her blood pressure has fallen from 132/80 to 88/54 mm Hg and her abdomen is more distended and tender. Her perineal pad has only a small amount of drainage. Which interpretation and action are correct?

a. The light pad rules out bleeding, so the RN gives the ordered analgesic and reassesses in an hour.

b. These findings suggest internal bleeding and early shock, so the RN escalates at once, gives oxygen and prepares for fluid resuscitation as ordered.

c. The findings suggest paralytic ileus, so the RN keeps the patient fasting and inserts a nasogastric tube.

d. The findings suggest pain from the incision, so the RN repositions the patient and rechecks vital signs in 30 minutes.

Answer: b — After hysterectomy, a rising heart rate, falling blood pressure and a distending abdomen suggest internal bleeding even when the pad is dry, and the RN treats this as possible hypovolemic shock and escalates at once (section 29.3, Hysterectomy and Gynecologic Surgery; sections 6.4 and 7.6). Option a wrongly relies on the pad. Options c and d explain away hemodynamic signs of bleeding and delay escalation.

20. [RN] A 36-year-old patient in Ontario received a positive result on her HPV screening test and asks the RN, "Does this mean I have cervical cancer?" Which response is most accurate?

a. "Yes. A positive HPV test means cancer cells were found, and you will need treatment right away."

b. "No. A positive result never needs any follow-up, because most HPV infections clear on their own."

c. "Not necessarily. It shows a type of HPV that can occasionally lead to cancer; a repeat test or colposcopy may come next."

d. "We can't say yet. You will need a Pap test every year from now on to see whether cancer develops."

Answer: c — In the Ontario program, a positive HPV result shows a high-risk type that can occasionally lead to cervical cancer; it does not mean cancer, and the next step may be a repeat test in 2 years or a colposcopy (section 29.3, Gynecologic Cancers in Brief; Table 29.1). Option a confuses HPV detection with cancer. Option b ignores the need for follow-up. Option d describes a test and interval that the Ontario program no longer uses.

Case: Normand Arsenault (Questions 21–26): Normand Arsenault, 64, arrives at the emergency department at 08:30 with chest pressure that began 40 minutes ago and spreads to his jaw. He has hypertension, type 2 diabetes and a 40-pack-year smoking history. His skin is pale and damp. Heart rate 98, blood pressure 138/84 mm Hg, respiratory rate 20, SpO_2 95% on room air, temperature 36.9 °C, capillary blood glucose 8.4 mmol/L. The triage protocol includes sublingual nitroglycerin for ischemic chest pain. While the nurse completes the medication history, Mr. Arsenault says he took sildenafil at about 22:00 last night.

21. [CORE] Which information should the nurse recognize as cues that need immediate attention? Select all that apply.

a. Chest pressure spreading to the jaw

b. Sildenafil taken about 10 hours ago

c. A triage protocol that includes nitroglycerin

d. Capillary blood glucose of 8.4 mmol/L

e. Pale, damp skin

f. Temperature of 36.9 °C

g. A 40-pack-year smoking history

Answer: a, b, c, e — Chest pressure spreading to the jaw with pale, damp skin suggests possible acute coronary syndrome (a, e). The recent sildenafil dose and the nitroglycerin protocol together create an immediate safety risk, because nitrates combined with a PDE5 inhibitor can cause a severe drop in blood pressure (b, c; section 29.6). A glucose of 8.4 mmol/L in a person with diabetes is not an urgent cue here (d). The temperature is normal (f). The smoking history is a background risk factor, not a cue that changes the immediate plan (g).

22. [CORE] Why does the sildenafil dose matter for Mr. Arsenault's care?

a. Sildenafil lowers the heart rate, so the nurse must check the pulse before any cardiac drug is given.

b. Sildenafil with a nitrate can cause a severe drop in blood pressure, and its monograph does not state when nitrates become safe.

c. Sildenafil commonly causes chest pain as a side effect, so the pain is probably harmless and needs no further tests.

d. Sildenafil raises blood glucose, which explains his capillary result and calls for an insulin correction dose.

Answer: b — The Canadian sildenafil monograph contraindicates all nitrates and states that it is unknown when a nitrate, if needed, can be safely given (b; section 29.6). Sildenafil does not slow the heart rate (a). Chest pain after a PDE5 inhibitor is never assumed to be harmless; it may be cardiac (c). Sildenafil does not explain the glucose result, and no correction dose is indicated (d).

23. [RN] Which hypothesis should the nurse treat as the priority?

a. Possible acute coronary syndrome, with a risk of severe hypotension if a nitrate is given

b. Anxiety about disclosing the sildenafil use, causing chest tightness and a rapid heart rate

c. Indigestion from the sildenafil, which commonly causes upper abdominal and chest discomfort

d. Hyperglycemia from poorly controlled diabetes, which needs correction before the chest pain is assessed

Answer: a — Chest pressure radiating to the jaw with diaphoresis in a person with several cardiac risk factors points to acute coronary syndrome until proven otherwise, and the recent PDE5 inhibitor makes nitrate use dangerous (a; sections 29.6 and Chapter 17). Anxiety and indigestion are possible, but assuming them first could miss a life-threatening problem (b, c). The glucose is only mildly raised and does not take priority (d).

24. [CORE] What should the nurse do first?

a. Give half of the usual nitroglycerin dose and recheck the blood pressure in 5 minutes before deciding on a second dose.

b. Give the nitroglycerin as the protocol directs because more than 6 hours have passed since the sildenafil dose.

c. Hold the nitroglycerin and tell the physician at once that sildenafil was taken at about 22:00 last night.

d. Ask Mr. Arsenault to wait until 24 hours have passed since his sildenafil dose before any chest pain treatment is given.

Answer: c — The nurse holds the nitrate and reports the drug and the timing at once so that the physician can choose another treatment (c; section 29.6). A smaller nitrate dose is still contraindicated (a). No 6-hour window exists, and the sildenafil monograph gives no safe interval (b). Delaying all chest pain treatment is unsafe; other treatments can be ordered (d).

25. [CORE] The physician orders no nitrates. Which plan should the nurse expect while Mr. Arsenault's chest pain is assessed?

a. Continuous cardiac monitoring, a 12-lead ECG and other treatments as ordered, with frequent vital signs

b. Discharge home with advice to stop sildenafil and to see his family doctor about his chest pain within a week

c. A nitroglycerin patch instead of the spray, because the slow release prevents a drop in blood pressure

d. An extra dose of sildenafil to widen the coronary arteries, since it acts on the same pathway as nitrates

Answer: a — Without nitrates, the team still assesses and treats possible acute coronary syndrome with monitoring, an ECG and other ordered drugs (a; section 29.6 and Chapter 17). Discharging a patient with possible ischemic chest pain is unsafe (b). A nitrate patch is still a nitrate and is contraindicated (c). Sildenafil is not a treatment for chest pain, and more would add to the risk (d).

26. [CORE] Mr. Arsenault's tests show no heart attack, and he will follow up with cardiology. Which statement shows that the teaching was effective?

a. "Next time I have chest pain I will use a nitroglycerin spray at home, as long as it has been 12 hours since my pill."

b. "If I get chest pain after taking my erection pill, I'll call 9-1-1 and tell the paramedics what I took and when."

c. "Erection pills only interact with nitroglycerin given by needle, so the spray and tablets are safe for me to use."

d. "I should stop telling health care staff about my erection pills because they are private and not real medications."

Answer: b — The patient calls 9-1-1 for chest pain and tells responders about the PDE5 inhibitor and the time it was taken so a nitrate is not given (b; section 29.6). No 12-hour safe window exists for sildenafil (a). The interaction applies to nitrates in every form (c). PDE5 inhibitors must always be reported as medications (d).

27. [CORE] A 50-year-old patient says she has not had a period for 8 months and asks whether she is "in menopause now." Which response is most accurate?

a. "You are in menopause, because 6 months without a period is enough to confirm it at your age."

b. "Menopause is confirmed only by a blood test of your hormone levels, so you will need to book one with your doctor this week."

c. "You are probably in perimenopause; menopause is confirmed after 12 months in a row with no period and no other cause."

d. "You cannot be in menopause yet, because menopause in Canada does not usually happen until the age of 55 or later."

Answer: c — Menopause is confirmed in hindsight after 12 months in a row with no period and no other cause; until then, she is in the perimenopausal transition (c; section 29.4). Six months is not enough (a). The SOGC definition is clinical and does not depend on a hormone test (b). The average age is 51, usually between 45 and 55 (d).

28. [CORE] A 63-year-old patient admitted for pneumonia mentions vaginal dryness, pain with intercourse and urinary urgency that have worsened over several years. Lubricants have not helped. What should the nurse do?

a. Explain that these are normal effects of aging that cannot be treated and will fade over time.

b. Advise her to start an over-the-counter herbal product for menopause, because natural products work as well as prescriptions.

c. Tell her that vaginal estrogen is unsafe after age 60 and that she should avoid all hormone products.

d. Recognize possible genitourinary syndrome of menopause and suggest she ask her prescriber about treatment options.

Answer: d — Dryness, painful intercourse and urinary urgency after menopause fit genitourinary syndrome of menopause, and The Menopause Society recommends low-dose vaginal estrogen or other local therapies when over-the-counter products fail; it can be used at any age (d; section 29.4). GSM is treatable, and local therapy can continue for as long as needed (a). The SOGC finds no single natural health product supported by evidence (b). The age limit for starting systemic hormone therapy does not apply to low-dose vaginal estrogen (c).

29. [CORE] A patient with a uterus is starting menopausal hormone therapy and asks why she must take a progestogen as well as estrogen. What should the nurse explain?

a. "The progestogen protects the lining of your uterus, which estrogen alone can cause to thicken."

b. "The progestogen makes the estrogen work faster, so your hot flashes will stop within a few days."

c. "The progestogen prevents blood clots, which removes the clotting risk that estrogen carries."

d. "The progestogen is only needed for the first month while your body gets used to the estrogen."

Answer: a — People with a uterus take estrogen with a progestogen (or another protective option) to protect the uterine lining; after a hysterectomy, estrogen can be used on its own (a; section 29.4). A progestogen does not speed symptom relief (b). Adding a progestogen does not remove clotting risk (c). It is taken for as long as estrogen is taken, continuously or in cycles (d).

30. [CORE] A man is being tested for chlamydia and gonorrhea. He reports only vaginal sex and has no symptoms. Which specimen does the nurse expect to collect for nucleic acid amplification testing?

a. A blood sample drawn from a vein, because both infections are diagnosed with serology tests

b. A first-void urine sample, collected from the first part of the urine stream

c. A midstream clean-catch urine sample, collected after cleansing the urethral opening

d. A swab of the throat, because the throat is the most common site of infection in men

Answer: b — For men, NAAT for chlamydia and gonorrhea is done on first-void urine; throat or rectal swabs are added based on the sexual history (b; section 29.5). Serology is used for syphilis, not chlamydia or gonorrhea (a). A midstream sample is used for urine culture, not for chlamydia and gonorrhea NAAT (c). Throat swabs are based on reported practices, not routine for everyone (d).

31. [CORE] A patient has a positive test for gonorrhea. Her symptoms began 3 weeks ago. Which partners should be tested and treated?

a. Only her current partner, because past partners are no longer at risk once the relationship has ended

b. Only partners who have symptoms, because people without symptoms do not spread gonorrhea

c. All partners from the past 12 months, because gonorrhea can stay silent for at least a year

d. All sexual partners from the 60 days before her symptoms began

Answer: d — The national gonorrhea guide calls for testing and treating all sexual partners from the 60 days before symptoms began, or before the test date without symptoms (d; section 29.5). Past partners within that window may be infected (a). Gonorrhea is frequently present without symptoms (b). The 12-month window does not match the guide (c).

32. [CORE] A patient on a medical unit mentions a painless sore on his penis that appeared 2 weeks ago and is now healing. Which response by the nurse is best?

a. "That kind of sore can be a sign of syphilis, even after it heals; I'll tell the team so that you can be tested."

b. "A painless sore that heals by itself is harmless, so there is no need to mention it to your physician."

c. "That sounds like genital herpes, which always causes painless sores, so you will need daily antiviral pills for life."

d. "You should wait to see whether a rash appears on your hands before anyone orders a test."

Answer: a — Primary syphilis often causes a painless sore that heals on its own while the infection continues, so testing is needed (a; section 29.5). Healing does not mean cure (b). Herpes does not always cause painless sores, does not always need lifelong daily treatment, and the diagnosis cannot be assumed without testing (c). Waiting for a secondary-stage rash delays treatment and allows spread (d).

33. [CORE] A patient newly diagnosed with genital herpes says, "I'll just avoid sex when I have sores, so my partner won't catch it." What should the nurse teach?

a. "That's correct; herpes spreads only when sores or blisters are visible."

b. "Your partner must be reported to public health by law, and public health staff will contact them and arrange testing."

c. "Herpes is cured after the first full course of antiviral pills, so after that you can no longer pass it on to any partner."

d. "Herpes can spread without sores, so ask your prescriber about ways to lower the risk, such as daily suppressive therapy."

Answer: d — HSV is often shed without symptoms, so transmission can occur without sores; daily suppressive therapy can reduce transmission (d; section 29.5). Visible sores are not the only risk (a). Partner notification for herpes is not a public health requirement; patients are encouraged to tell partners (b). Herpes is lifelong and not cured by treatment (c).

34. [CORE] A patient is prescribed metronidazole for trichomoniasis. Which instruction is most important to prevent the infection from coming back?

a. Use a vaginal douche daily for one week after finishing the medicine.

b. Repeat the course of metronidazole every month for the next 6 months.

c. Make sure your sexual partner or partners are treated at the same time.

d. Avoid all dairy products while taking the medicine and for 3 days afterward.

Answer: c — Treating partners together with the patient prevents reinfection (c; section 29.5). Douching is not a treatment (a). Monthly repeat courses are not recommended (b). Dairy avoidance is not part of trichomoniasis care (d).

35. [CORE] An RN on a medical unit in an Ontario public hospital holds authorization to prescribe. A patient's urine NAAT is positive for chlamydia, and the RN thinks the patient should start doxycycline. What should the RN do?

a. Write a prescription for doxycycline, because the RN prescribing list includes doxycycline.

b. Report the result to the physician or NP so that treatment can be ordered, and follow any medical directive in place.

c. Ask the RPN to give a dose of doxycycline from ward stock, then obtain the order later in the shift.

d. Tell the patient to buy doxycycline at a pharmacy after discharge, since it is available without a prescription.

Answer: b — RN prescribing does not apply in public hospitals, and the CNO list includes doxycycline only for malaria prevention, not for STBBI treatment, so the RN obtains an order or uses a medical directive (b; section 29.6, Scope in Practice). Prescribing here exceeds the RN's authority (a). Giving a drug without an order is outside every nurse's authority (c). Doxycycline needs a prescription (d).

36. [CORE] A patient in the emergency department says he has had a painful erection for 5 hours after taking a PDE5 inhibitor. What should the nurse do?

a. Recognize priapism as an emergency and notify the physician at once.

b. Ask him to walk around the department, because activity usually ends the erection within an hour.

c. Apply an ice pack, reassure him that the erection will settle on its own, and reassess in 2 hours.

d. Offer a nitroglycerin spray to relax the blood vessels and help the erection subside.

Answer: a — An erection lasting more than 4 hours needs immediate medical care, because delay can damage penile tissue and cause permanent loss of erections (a; section 29.6). Walking or waiting delays treatment (b, c). A nitrate is dangerous after a PDE5 inhibitor (d).

37. [CORE] A transgender woman is admitted for an appendectomy. She takes estradiol and spironolactone. Which actions by the nurse are appropriate? Select all that apply.

a. Ask privately for her name and pronouns and use them consistently.

b. Hold her estradiol on admission, since estrogen must always be stopped before surgery.

c. Ask the surgical team or prescriber for a plan for her hormones around surgery.

d. Share her gender history only with team members who need it for her care.

e. Ask about her past gender-affirming surgeries out of interest during the admission assessment.

f. Give VTE prophylaxis as ordered.

Answer: a, c, d, f — Using the patient's name and pronouns is fundamental to care (a). The nurse obtains a plan from the surgical team or prescriber rather than stopping hormones, because evidence does not show that holding hormones lowers VTE risk (c), protects privacy (d) and gives VTE prophylaxis as ordered (f; section 29.6). Stopping estradiol without an order is not supported (b). Questions are asked only when relevant to care, never out of curiosity (e).

38. [CORE] A 52-year-old man mentions new erectile dysfunction during a pre-operative visit. What is the nurse's best understanding of this finding?

a. ED at this age is a normal part of aging and needs no further follow-up from the health care team.

b. ED means his testosterone level is low, so the nurse should expect a testosterone prescription and hormone blood tests.

c. ED is almost always psychological at his age, so the nurse should refer him to a counsellor and avoid medical tests.

d. ED shares risk factors with heart disease and may be an early warning sign, so his heart health deserves attention.

Answer: d — The CUA notes that ED and cardiovascular disease share risk factors and that ED may be an early signal of later vascular events, and it suggests checking glucose and lipids (d; section 29.6). ED is common with age but still deserves attention (a). Low testosterone is only one possible cause (b). Psychological factors are possible, but the CUA lists many vascular and metabolic risk factors (c).

39. [RN] A 56-year-old patient with severe hot flashes asks about menopausal hormone therapy. Which finding in her history is a contraindication that the nurse should report to the prescriber?

a. A hysterectomy 10 years ago for uterine fibroids

b. Osteopenia found on her last bone density scan

c. A deep vein thrombosis 3 years ago after a long flight

d. Her last menstrual period was 3 years ago

Answer: c — A current or past venous thromboembolism is a contraindication to estrogen in the Canadian monograph (c; section 29.4). After a hysterectomy, estrogen can be used on its own (a). Preventing bone loss is a benefit of MHT, not a contraindication (b). She is under 60 and within 10 years of menopause, the group in which the benefit-risk balance is favourable (d).

40. [RN] A patient is treated with intramuscular ceftriaxone for gonorrhea found on a rectal NAAT and a throat NAAT. Which follow-up plan matches the national guide?

a. No follow-up testing, because ceftriaxone cures every gonorrhea infection when it is given correctly

b. A single repeat urine NAAT 3 days after treatment to confirm cure at all sites

c. A repeat test only if symptoms appear, because rectal and throat infections clear without retesting

d. A test of cure at both the rectum and the throat, by culture at least 3 days or NAAT 3 to 4 weeks or more after treatment

Answer: d — Because N. gonorrhoeae can quickly develop antimicrobial resistance, everyone needs a test of cure at each positive site; culture can be taken at least 3 days after treatment and NAAT should wait 3 to 4 weeks to avoid false positives (d; section 29.5). Treatment failure can occur (a). A urine test does not check the rectum or throat, and NAAT at 3 days may detect leftover genetic material (b). Rectal and throat infections are often silent, so waiting for symptoms is unsafe (c).

References

Sexually active client? Think syphilis! Key messages for health care providers in Nunavut. (n.d.). https://www.irespectmyself.ca/sites/default/files/news/syphilis_hcp_resource.pdf

Alberta Health Services. (2022). *Breast cancer surgery: Drain care*. MyHealth.Alberta.ca. https://myhealth.alberta.ca/breast-cancer-surgery/at-home/drain-care

Angita Pharma Inc. (2022). *AG-Vardenafil (vardenafil hydrochloride tablets): Product monograph*. https://pdf.hres.ca/dpd_pm/00066919.PDF

BGP Pharma ULC. (2023). *VIAGRA (sildenafil citrate tablets; sildenafil orodispersible film): Product monograph*. https://pdf.hres.ca/dpd_pm/00073993.PDF

Bourns, A. (2019). *Guidelines for gender-affirming primary care with trans and non-binary patients* (4th ed.). Sherbourne Health; Rainbow Health Ontario. https://www.rainbowhealthontario.ca/wp-content/uploads/2025/08/Guidelines-4th-Edition-2026.pdf

Bourns, A. (2023). *Guidelines for gender-affirming primary care with trans and non-binary patients: Quick reference guide for primary care providers*. Rainbow Health Ontario. https://www.rainbowhealthontario.ca/wp-content/uploads/2020/10/QRG_full_rev2023.pdf

Brenner, D. R., Gillis, J., Demers, A. A., Ellison, L. F., Ng, C., Zhang, S. X., Finley, C., Fitzgerald, N., Saint-Jacques, N., Shack, L., Turner, D., Urquhart, R., & Woods, R. R. (2026). Projected estimates of cancer in Canada in 2026. *Canadian Medical Association Journal, 198*(14), E526–E534. https://doi.org/10.1503/cmaj.252152

Canadian Cancer Society. (2023). *Prognosis and survival for breast cancer*. https://cancer.ca/en/cancer-information/cancer-types/breast/prognosis-and-survival

Canadian Cancer Society. (2026a). *Breast cancer statistics*. https://cancer.ca/en/cancer-information/cancer-types/breast/statistics

Canadian Cancer Society. (2026b). *Cervical cancer statistics*. https://cancer.ca/en/cancer-information/cancer-types/cervical/statistics

Canadian Cancer Society. (2026c). *Ovarian cancer statistics*. https://cancer.ca/en/cancer-information/cancer-types/ovarian/statistics

Canadian Cancer Society. (2026d). *Uterine cancer statistics*. https://cancer.ca/en/cancer-information/cancer-types/uterine/statistics

Canadian Cancer Society. (n.d.-a). *Diagnosis of breast cancer*. https://cancer.ca/en/cancer-information/cancer-types/breast/diagnosis

Canadian Cancer Society. (n.d.-b). *Lymphedema*. https://cancer.ca/en/treatments/side-effects/lymphedema

Canadian Cancer Society. (n.d.-c). *Risk factors for breast cancer*. https://cancer.ca/en/cancer-information/cancer-types/breast/risks

Canadian Cancer Society. (n.d.-d). *Signs and symptoms of ovarian cancer*. https://cancer.ca/en/cancer-information/cancer-types/ovarian/signs-and-symptoms

Canadian Cancer Society. (n.d.-e). *Signs and symptoms of uterine cancer*. https://cancer.ca/en/cancer-information/cancer-types/uterine/signs-and-symptoms

Canadian Cancer Society. (n.d.-f). *Surgery for breast cancer*. https://cancer.ca/en/cancer-information/cancer-types/breast/treatment/surgery

Canadian Cancer Society. (n.d.-g). *Surgery for uterine cancer*. https://cancer.ca/en/cancer-information/cancer-types/uterine/treatment/surgery

Canadian Task Force on Preventive Health Care. (2013). Recommendations on screening for cervical cancer. *Canadian Medical Association Journal, 185*(1), 35–45. https://doi.org/10.1503/cmaj.121505

Canadian Task Force on Preventive Health Care. (2024). *[Archived] Breast cancer (update) – Draft recommendations (2024)*. https://canadiantaskforce.ca/guidelines/published-guidelines/breast-cancer-update-2024/

Canadian Task Force on Preventive Health Care. (n.d.). *Archived content – Canadian Task Force on Preventive Health Care*. https://canadiantaskforce.ca/?p=18835

Cenkowski, M., Wudel, B., & Poliquin, V. (2022). Vaginal trichomoniasis. *CMAJ, 194*(6), E217. https://doi.org/10.1503/cmaj.211088

Chen, I., Kives, S., Randle, E., Rattray, D., Sanders, A., & Vilos, G. (2025). Guideline No. 461: The management of uterine fibroids. *Journal of Obstetrics and Gynaecology Canada, 47*(8), Article 102970. https://doi.org/10.1016/j.jogc.2025.102970

Coleman, E., Radix, A. E., Bouman, W. P., Brown, G. R., de Vries, A. L. C., Deutsch, M. B., Ettner, R., Fraser, L., Goodman, M., Green, J., Hancock, A. B., Johnson, T. W., Karasic, D. H., Knudson, G. A., Leibowitz, S. F., Meyer-Bahlburg, H. F. L., Monstrey, S. J., Motmans, J., Nahata, L., . . . Arcelus, J. (2022). Standards of care for the health of transgender and gender diverse people, version 8. *International Journal of Transgender Health, 23*(Suppl. 1), S1–S259. https://doi.org/10.1080/26895269.2022.2100644

College of Nurses of Ontario. (n.d.). *RN prescribing drug list*. Retrieved October 27, 2026, from https://www.cno.org/standards-learning/rn-prescribing/rn-prescribing-drug-list

Domes, T., Najafabadi, B. T., Roberts, M., Campbell, J., Flannigan, R., Bach, P., Patel, P., Langille, G., Krakowsky, Y., & Violette, P. D. (2021). Canadian Urological Association guideline: Erectile dysfunction. *Canadian Urological Association Journal, 15*(10), 310–322. https://doi.org/10.5489/cuaj.7572

Ferguson, C. M., Swaroop, M. N., Horick, N., Skolny, M. N., Miller, C. L., Jammallo, L. S., Brunelle, C., O'Toole, J. A., Salama, L., Specht, M. C., & Taghian, A. G. (2016). Impact of ipsilateral blood draws, injections, blood pressure measurements, and air travel on the risk of lymphedema for patients treated for breast cancer. *Journal of Clinical Oncology, 34*(7), 691–698. https://doi.org/10.1200/JCO.2015.61.5948

Government of Ontario. (2026). *Cervical cancer screening and prevention*. https://www.ontario.ca/page/cervical-cancer-screening-and-prevention

Hastings Prince Edward Public Health. (2023). *Syphilis* [Fact sheet]. https://www.hpepublichealth.ca/wp-content/uploads/2023/04/2023-01-30-syphilis-8.5x11.pdf

Health Canada. (2026). *Bicillin L-A (penicillin G benzathine) in short supply: Notice*. https://www.canada.ca/en/health-canada/services/drugs-health-products/drug-products/drug-shortages/information-consumers/supply-notices/bicillin-la-penicillin-g-benzathine.html

Hôpital Montfort. (n.d.). *Exercise program after breast surgery* (A-108). https://hopitalmontfort.com/sites/default/files/2026-05/A_108%20-%20Exercise%20program%20after%20breast%20surgery_web.pdf

Interior Health. (n.d.). *Discharge information following breast surgery* (808637). Vernon Jubilee Hospital. https://www.interiorhealth.ca/sites/default/files/2021-11/VJH-808637_Discharge%20Information%20Following%20Breast%20Surgery.pdf

Magee, L. A., Smith, G. N., Bloch, C., Côté, A.-M., Jain, V., Nerenberg, K., von Dadelszen, P., Helewa, M., & Rey, E. (2022). Guideline No. 426: Hypertensive disorders of pregnancy: Diagnosis, prediction, prevention, and management. *Journal of Obstetrics and Gynaecology Canada, 44*(5), 547–571.e1. https://doi.org/10.1016/j.jogc.2022.03.002

Meltzer, T. (2016). *Vaginoplasty procedures, complications and aftercare*. UCSF Gender Affirming Health Program. https://transcare.ucsf.edu/guidelines/vaginoplasty

Middlesex-London Health Unit. (2026). *Reporting diseases of public health significance*. https://www.healthunit.com/health-care-professionals/infectious-diseases-for-healthcare-providers/reporting-diseases-of-public-health-significance/

Moore, A., Doull, M., Grad, R., Groulx, S., Pottie, K., Tonelli, M., Courage, S., Jaramillo Garcia, A., & Thombs, B. D. (2018). Recommendations on screening for asymptomatic bacteriuria in pregnancy. *Canadian Medical Association Journal, 190*(27), E823–E830. https://doi.org/10.1503/cmaj.171325

Nicolle, L. E., Gupta, K., Bradley, S. F., Colgan, R., DeMuri, G. P., Drekonja, D., Eckert, L. O., Geerlings, S. E., Köves, B., Hooton, T. M., Juthani-Mehta, M., Knight, S. L., Saint, S., Schaeffer, A. J., Trautner, B., Wullt, B., & Siemieniuk, R. (2019). Clinical practice guideline for the management of asymptomatic bacteriuria: 2019 update by the Infectious Diseases Society of America. *Clinical Infectious Diseases, 68*(10), e83–e110. https://doi.org/10.1093/cid/ciy1121

Ontario Health. (n.d.-a). *Breast cancer screening*. https://www.cancercareontario.ca/en/types-of-cancer/breast-cancer/screening

Ontario Health. (n.d.-b). *Cervical cancer screening*. https://www.cancercareontario.ca/en/types-of-cancer/cervical/screening

Organon Canada Inc. (2026). *ESTROGEL (17β-estradiol transdermal gel 0.06%): Product monograph*. https://www.organon.com/canada-en/estrogel-pm_e/

Public Health Agency of Canada. (2020). *Syphilis in Canada: Technical report on epidemiological trends, determinants and interventions*. https://www.canada.ca/en/services/health/publications/diseases-conditions/syphilis-epidemiological-report.html

Public Health Agency of Canada. (2021). *Genital herpes guide: Key information and resources*. https://www.canada.ca/en/public-health/services/infectious-diseases/sexual-health-sexually-transmitted-infections/canadian-guidelines/herpes-simplex-virus.html

Public Health Agency of Canada. (2025a). *Anogenital warts guide: Key information and resources*. https://www.canada.ca/en/public-health/services/infectious-diseases/sexual-health-sexually-transmitted-infections/canadian-guidelines/anogenital-warts.html

Public Health Agency of Canada. (2025b). *Chlamydia and lymphogranuloma venereum guide: Key information and resources*. https://www.canada.ca/en/public-health/services/infectious-diseases/sexual-health-sexually-transmitted-infections/canadian-guidelines/chlamydia-lgv.html

Public Health Agency of Canada. (2025c). Infectious syphilis and congenital syphilis in Canada, 2023. *Canada Communicable Disease Report, 51*(2/3). https://www.canada.ca/en/public-health/services/reports-publications/canada-communicable-disease-report-ccdr/monthly-issue/2025-51/issue-2-3-february-march-2025/infectious-congenital-syphilis-2023.html

Public Health Agency of Canada. (2025d). *Syphilis guide: Key information and resources*. https://www.canada.ca/en/public-health/services/infectious-diseases/sexual-health-sexually-transmitted-infections/canadian-guidelines/syphilis.html

Public Health Agency of Canada. (2026a). *Gonorrhea guide: Key information and resources*. https://www.canada.ca/en/public-health/services/infectious-diseases/sexual-health-sexually-transmitted-infections/canadian-guidelines/gonorrhea.html

Public Health Agency of Canada. (2026b). *STBBI prevention guide: Assessment and counselling*. Government of Canada. https://www.canada.ca/en/public-health/services/infectious-diseases/sexual-health-sexually-transmitted-infections/canadian-guidelines/stbbi-prevention-guide/assessment-counselling.html

Singh, S. S., Allaire, C., Al-Nourhji, O., Bougie, O., Bridge-Cook, P., Duigenan, S., Kroft, J., Lemyre, M., Leonardi, M., Leyland, N., Maheux-Lacroix, S., Wessels, J., Wahl, K., & Yong, P. J. (2024). Guideline No. 449: Diagnosis and impact of endometriosis – A Canadian guideline. *Journal of Obstetrics and Gynaecology Canada, 46*(5), Article 102450. https://doi.org/10.1016/j.jogc.2024.102450

Society of Obstetricians and Gynaecologists of Canada. (n.d.-a). *Endometriosis*. https://www.sogc.org/en/content/events/HUB-Pages/Endometriosis.aspx

Society of Obstetricians and Gynaecologists of Canada. (n.d.-b). *Menopause hub*. Retrieved October 27, 2026, from https://sogc.org/en/content/events/HUB-Pages/Menopause.aspx

Sun Pharma Canada Inc. (2024). *TARO-TADALAFIL (tadalafil tablets): Product monograph*. https://pdf.hres.ca/dpd_pm/00074886.PDF

The 2022 Hormone Therapy Position Statement of The North American Menopause Society Advisory Panel. (2022). The 2022 hormone therapy position statement of The North American Menopause Society. *Menopause, 29*(7), 767–794. https://doi.org/10.1097/GME.0000000000002028

Thunder Bay District Health Unit. (2026). *Chlamydia trachomatis infections*. https://www.tbdhu.com/professionals/health-care-providers/infectious-diseases-toolkit/chlamydia-trachomatis-infections

Waterloo Regional Health Network. (2026). *Bras and breast prosthetics* [Patient education handout]. https://www.wrhn.ca/wp-content/uploads/2026/03/PEMWRHNCC0057_BrasandProsthetics_March2026_AODA_FINAL.pdf

Yuksel, N., Evaniuk, D., Huang, L., Malhotra, U., Blake, J., Wolfman, W., & Fortier, M. (2021). Guideline No. 422a: Menopause: Vasomotor symptoms, prescription therapeutic agents, complementary and alternative medicine, nutrition, and lifestyle. *Journal of Obstetrics and Gynaecology Canada, 43*(10), 1188–1204.e1. https://doi.org/10.1016/j.jogc.2021.08.003

Zucker, R., Reisman, T., & Safer, J. D. (2021). Minimizing venous thromboembolism in feminizing hormone therapy: Applying lessons from cisgender women and previous data. *Endocrine Practice, 27*(6), 621–625. https://doi.org/10.1016/j.eprac.2021.03.010

VIII Neurologic & Cerebrovascular Nursing Care

UNIT CLINICAL SCOPE & INTEGRATION

Focuses on high-acuity neurologic assessment (Glasgow Coma Scale, cranial nerves, pupillary and motor responses), pathophysiological management of increased intracranial pressure (ICP) and Cushing triad, Canadian Stroke Best Practice Recommendations for acute ischemic and hemorrhagic stroke, traumatic brain injury, spinal cord injury (autonomic dysreflexia), seizures, multiple sclerosis, Parkinson disease, myasthenia gravis, and Guillain–Barré syndrome.

Contents of UNIT VIII

Chapter	Chapter Title	Visual Assets	Page
Chapter 30	Neurologic Assessment and Increased Intracranial Pressure	6 Figs • 4 Tbls	p. 883
Chapter 31	Stroke	6 Figs • 4 Tbls	p. 913
Chapter 32	Traumatic Brain and Spinal Cord Injury and Chronic Neurologic Disorders	6 Figs • 4 Tbls	p. 943

30 Neurologic Assessment and Increased Intracranial Pressure

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Relate the structure and function of the nervous system, cerebral blood flow and cerebrospinal fluid to neurologic assessment findings.
2. Perform a focused neurologic assessment, including the Glasgow Coma Scale, pupils and motor checks, and report change from baseline.
3. Prepare and care for adults having neurologic diagnostic tests, including MRI safety screening and lumbar puncture.
4. Recognize early and late signs of increased intracranial pressure and provide nursing care that protects cerebral perfusion, using the CJMM.
5. Respond safely to seizures and status epilepticus and support adults living with epilepsy.
6. Recognize headache red flags, bacterial meningitis and brain tumours, and provide care after craniotomy.
7. Distinguish RN and RPN roles in neurologic care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 5, 6	Clinician; Scholar	Foundations of Practice
2, 5	Educator; Advocate	Foundations of Practice; Ethical Practice
7	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

The brain and spinal cord shape every part of a person's life, from breathing and swallowing to speech, movement, memory and mood. When they are injured or under pressure, the first signs can be small: a patient who needs to be asked twice, a hand that drifts, a pupil that reacts a little more slowly than it did an hour ago. The nurse at the bedside is often the person who sees these changes first. A careful, repeatable neurologic assessment, compared with the patient's own baseline and reported without delay, can mean the difference between a problem found early and a brain injury that cannot be undone.

This chapter is the book's home for the nervous system. Section 30.1 reviews the structures and processes behind neurologic findings: neurons, the regions of the brain, the spinal cord, cerebral blood flow and cerebrospinal fluid. Section 30.2 teaches a focused neurologic assessment, including the Glasgow Coma Scale, pupils, limb strength, speech and how to report change. Section 30.3 covers common neurologic tests and the nursing care around them. The second half of the chapter covers increased intracranial pressure (30.4), seizures and status epilepticus (30.5), and headache red flags, central nervous system infections and brain tumours (30.6).

The chapter builds on earlier ones. Scope of practice for registered nurses (RNs) and registered practical nurses (RPNs) is taught in section 1.3 and the Clinical Judgment Measurement Model (CJMM) in section 1.4. Recognizing deterioration, the SBAR (situation, background, assessment, recommendation) format and rapid response are in Chapter 6, and delirium and dementia are in Chapter 8. Stroke is covered in Chapter 31, and traumatic brain injury, spinal cord injury and chronic neurologic disorders in Chapter 32. In other provinces and territories, practical nurses (PNs) are usually called licensed practical nurses (LPNs); this chapter uses "the nurse" unless the roles differ.

30.1 The Nervous System: A Focused Review

Cells, Brain and Spinal Cord

The basic working unit of the nervous system is the **neuron**, a nerve cell that receives, processes and sends signals. Each neuron has a cell body, branching dendrites that receive messages and a single axon that carries signals onward. Support cells, called glia, surround neurons; some wrap axons in myelin, a fatty layer that lets signals travel faster and farther. Where one neuron meets the next, at the synapse, chemical messengers called neurotransmitters cross a small gap and attach to receptors on the next cell (National Institute of Neurological Disorders and Stroke [NINDS], n.d.-a; Figure 30.1).



Figure 30.1 Structure of a multipolar neuron in the central nervous system, showing the cell body (soma), dendrites, axon, myelin sheath formed by an oligodendrocyte, nodes of Ranvier and synaptic terminals. (credit: "Figure 12.8, Parts of a Neuron" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

The brain and spinal cord form the **central nervous system (CNS)**. The nerves outside them, including the 12 pairs of cranial nerves and the spinal nerves, form the peripheral nervous system. Part of the peripheral system, the autonomic nervous system, runs functions such as breathing and heartbeat that happen without conscious thought (NINDS, n.d.-b).

The **cerebrum** makes up most of the forebrain, the largest part of the brain, and is the source of conscious thought, memory and voluntary action. It has two hemispheres joined by a thick band of fibres, the corpus callosum. Each hemisphere has four lobes (NINDS, n.d.-a): (Figure 30.2)

- **Frontal lobe:** planning, reasoning and judgment; the motor cortex at its back plans and carries out voluntary movement.
- **Parietal lobe:** receives touch, temperature and position sense, and supports reading and arithmetic.
- **Temporal lobe:** hearing and the forming and recalling of memories.
- **Occipital lobe:** processes what the eyes see; damage here can cause loss of vision.

Language depends mainly on the left hemisphere in most people. Because the pathways between the brain and the body cross over, each hemisphere mainly controls the opposite side of the body: a tumour or stroke in the right hemisphere can weaken the left arm and leg (NINDS, n.d.-a). This crossing is why the nurse compares the two sides of the body at every check.

Deep in the brain, the thalamus acts as a relay station for information travelling between the spinal cord and the cerebrum, and the hypothalamus helps regulate emotions and waking (NINDS, n.d.-a). The **brainstem**, made up of the midbrain, pons and medulla, connects the brain to the spinal cord. It controls breathing and heart rate, carries reflex circuits, and helps control eye movements (NINDS, n.d.-a). A network of neurons in the upper brainstem, the ascending reticular activating system, sends signals through the thalamus to the cortex and keeps a person awake and alert (Taran et al., 2023).

This network explains a key idea in neurologic assessment. Consciousness needs both arousal (being awake) and awareness (knowing oneself and one's surroundings). Damage to the arousal network in the brainstem can cause coma, while widespread damage to the cortex or to both sides of the thalamus can leave a person with sleep-wake cycles but little or no awareness (Taran et al., 2023). A falling level of consciousness therefore suggests a problem in the brainstem or in large areas of both hemispheres, which is one reason it is treated as a serious cue.

The **cerebellum**, at the back of the brain below the cerebrum, coordinates movement and helps with learned, skilled actions (NINDS, n.d.-a). Problems here show up as clumsy, poorly aimed movements and an unsteady gait rather than weakness.



Figure 30.2 Lateral view of the cerebral cortex showing the frontal, parietal, occipital and temporal lobes and major sulci and gyri. (credit: "Figure 13.7, Lobes of the Cerebral Cortex" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

The spinal cord carries long axons from the brain down to the nerves that move the body, and carries sensory messages back up (NINDS, n.d.-a). Spinal cord injury is covered in Chapter 32.

Blood Flow, Cerebrospinal Fluid and the Skull

The brain makes up only 2% to 3% of body mass, yet under normal conditions it receives about 15% of the cardiac output and uses about 20% of the body's oxygen (Claassen et al., 2021). Because demand is so high, low oxygen or low blood pressure can harm brain tissue quickly.

Autoregulation is the ability of the brain's blood vessels to widen or narrow so that blood flow stays fairly steady when blood pressure changes. Older teaching described a flat, protected range of mean arterial pressure from about 50 to 150 mm Hg. A major review points out that this curve was built from group averages, and that in individual people the protected range is smaller and depends on how fast pressure changes; sudden swings reach the brain more directly (Claassen et al., 2021). When autoregulation is overwhelmed, low pressure leads to too little flow and ischemia, and severe high pressure pushes flow up (Claassen et al., 2021).

Carbon dioxide also controls cerebral blood flow. A rise in the arterial partial pressure of carbon dioxide ($PaCO_2$) widens cerebral vessels and increases blood flow, by roughly 3% to 6% for each 1 mm Hg rise; a fall in $PaCO_2$ narrows them and reduces flow (Claassen et al., 2021). This link matters for breathing and ventilation in brain injury (section 30.4; Chapter 15).

The **blood–brain barrier** is formed by tightly joined cells that limit which substances can pass from the blood into brain tissue, protecting the brain but also keeping out some drugs (Paszkowycz et al., 2025).

Cerebrospinal fluid (CSF) is a clear fluid that bathes the brain and spinal cord. A typical adult has about 150 mL of CSF at any time, but makes roughly 400 to 600 mL a day, mostly in the choroid plexus, a network of specialized tissue in the brain's fluid-filled chambers (ventricles). CSF flows from the lateral ventricles to the third ventricle, through a narrow channel (the cerebral aqueduct) to the fourth ventricle, and then into the space around the brain and spinal cord. It cushions the brain against shock, makes the brain buoyant and carries away waste. How CSF is absorbed back into the body is still being studied (Paszkowycz et al., 2025). Because production continues all day, anything that blocks flow or absorption can make fluid build up (hydrocephalus, section 30.4).

In an adult, the skull is a rigid, closed box. Brain tissue, blood and CSF share this fixed space, so when one of them grows, for example from swelling, bleeding or a tumour, the others must make room or the pressure inside the skull rises. Section 30.4 explains what happens next.

GOING DEEPER

Cranial Nerves at the Bedside

Required for RN students; optional for PN students.

The 12 pairs of cranial nerves leave the brain and brainstem directly. Each can be checked quickly, comparing the two sides (Larsen & Stensaas, n.d.-a):

- **I Olfactory:** smell; a familiar, non-irritating scent, one nostril at a time.
- **II Optic:** vision; the patient reads print or counts fingers. Nerve II carries the light signal for the pupil reflex; nerve III constricts the pupil.
- **III Oculomotor, IV Trochlear, VI Abducens:** eye movements; the patient follows a finger in all directions; watch whether the eyes move together and ask about double vision. Nerve III also lifts the eyelid, so a new drooping lid or a widening pupil on one

side can mean it is under threat (section 30.4).

- **V Trigeminal:** facial feeling and chewing; touch the forehead, cheek and jaw on both sides; feel the jaw muscles as the patient bites down.
- **VII Facial:** facial movement; the patient wrinkles the forehead, closes the eyes tightly and smiles; look for asymmetry.
- **VIII Vestibulocochlear:** hearing and balance; rub the fingers together beside each ear and compare.
- **IX Glossopharyngeal and X Vagus:** palate and gag reflex; the patient says "ah" while the nurse watches the palate rise evenly.
- **XI Accessory:** shoulder shrug and head turning against resistance.
- **XII Hypoglossal:** the patient sticks out the tongue and moves it side to side; a deviating tongue points toward the weak side.

30.2 Focused Neurologic Assessment

Level of Consciousness and the Glasgow Coma Scale

Level of consciousness describes how awake a person is (arousal) and how well the person understands self and surroundings (awareness). It is the core of every neurologic check. Vague words such as "drowsy" or "lethargic" mean different things to different people, so nurses describe what they see and use a shared scale.

The **Glasgow Coma Scale (GCS)** was described by Graham Teasdale and Bryan Jennett in 1974 to help clinicians communicate about consciousness after acute brain injury, and it is now used for impaired consciousness from many causes (Royal College of Physicians and Surgeons of Glasgow [RCPSG], n.d.-a; Teasdale et al., 2014). It rates three behaviours: eye opening, verbal response and motor response (Table 30.1). The authors' current structured approach has four steps (RCPSG, n.d.-c; Teasdale, 2015):

- **Check:** identify anything that could interfere with the assessment, such as a language difference, hearing loss, a prior neurologic deficit, sedation, a breathing tube or an injury.
- **Observe:** before speaking or touching, watch for spontaneous eye opening, speech and movement on both sides of the body.
- **Stimulate:** if there is no spontaneous response, speak in a normal voice and then a louder one; if there is still no response, apply physical pressure.
- **Rate:** score each component by the best response seen.

Physical stimulation follows a set order. Fingertip pressure on the nail bed is used first, and the finger pressed is changed over time. If a central stimulus is needed, the nurse uses a trapezius pinch at the top of the shoulder or pressure at the supraorbital notch above the eye. The authors advise against routine jaw pressure and strongly discourage rubbing the sternum with the knuckles, which can bruise and gives responses that are hard to interpret (RCPSG, n.d.-c).

Several details make the scale reliable:

- **Obeys commands** requires the patient to carry out a two-part request, such as "Squeeze my fingers, then let go" (Teasdale, 2015).
- **Localising** means the patient brings a hand above the collarbone toward a stimulus on the head or neck (Teasdale, 2015).
- **Orientated** means the patient correctly gives their name, the place and the date (Teasdale, 2015).
- **Not testable (NT):** when a factor prevents a valid rating, such as a breathing tube for the verbal response or swollen eyelids for eye opening, the nurse records "NT", never a score of 1 or 0. A total is not reported when a component is NT, because a falsely low total could mislead the team (RCPSG, n.d.-a; Teasdale, 2015).

The nurse reports the three components, not only the total. Written as E3V4M6, for example, the scores add to 13, but the same total of 8 could describe a patient who is E2V2M4 or one who is E1V1M6, and these patients are very different (RCPSG, n.d.-b). The nurse uses the words with the numbers, for example "opens eyes to voice, confused, obeys commands". The total ranges from 3 to 15, and the components carry more information than the sum (RCPSG, n.d.-a).

Interfering factors are handled rather than ignored. For a patient who speaks another language, the nurse adapts the check by using a professional interpreter (Chapter 2), written communication or, where possible, an assessor who shares the patient's language and

culture. When sedation or a paralyzing drug blocks the assessment, the prescriber may order a planned, brief pause in sedation so that responses can be seen. For a patient with a spinal cord injury who cannot move the hands, the nurse watches eye and tongue movements instead (RCPSG, n.d.-a). Each limitation is written in the record so the next nurse can repeat the check the same way.

Training and a standard method improve agreement between assessors, and nurses and physicians score the scale equally well (RCPSG, n.d.-a). The frequency of checks is set by the order or employer policy and is increased when the patient's condition changes.

Table 30.1 Glasgow Coma Scale components (Glasgow structured approach; original wording) (Teasdale, 2015; RCPSG, n.d.-a, n.d.-c)

Component	Responses from best to worst	Score	Practical tips
Eye opening	Spontaneous: eyes open before any stimulus	4	Watch first, before speaking or touching.
Eye opening	To sound: eyes open after a spoken or shouted request	3	Use a normal voice first, then a louder one.
Eye opening	To pressure: eyes open after fingertip pressure	2	Press the nail bed; change fingers over time.
Eye opening	None: no eye opening at any time, with nothing interfering	1	Record NT, not 1, if swelling or a dressing keeps the eyes closed.
Verbal response	Orientated: correctly states own name, current place and the date	5	Ask open questions, not yes-or-no questions.
Verbal response	Confused: speaks coherently but gets name, place or date wrong	4	Note which items are wrong.
Verbal response	Words: says only single, understandable words	3	Record the words heard.
Verbal response	Sounds: only moans or groans	2	Make sure hearing aids are in and the room is quiet.
Verbal response	None: no sound at all, with nothing interfering	1	Record NT if a breathing tube or other factor prevents speech.
Motor response	Obeys commands: follows a two-part request	6	Ask the patient to squeeze and then let go.
Motor response	Localising: brings a hand above the collarbone toward a stimulus on the head or neck	5	Use a trapezius pinch or supraorbital pressure.
Motor response	Normal flexion: bends the arm at the elbow quickly, moving it away from the body	4	Score the best response of either arm.
Motor response	Abnormal flexion: slow, stereotyped bending with the arm across the chest, forearm turning and thumb clenched	3	Describe the posture in the notes; report at once if new.
Motor response	Extension: straightens the arm at the elbow	2	A new extension response is an emergency.
Motor response	None: no movement of arms or legs, with nothing interfering	1	Record NT if paralysis or sedation prevents testing.

Pupils, Movement and Sensation

Pupil checks are done in dim light. The nurse estimates each pupil's size in millimetres against a pupil gauge, notes its shape, and shines a light into each eye to see whether the pupil constricts briskly, sluggishly or not at all. Manual checks are subjective. In one study of neurocritical care patients, nurses using a penlight and gauge missed half of the cases of unequal pupils (a difference of 1 mm or more) that an automated pupillometer detected, and the two methods disagreed about light reaction in 18% of checks (Couret et al., 2016). Where automated pupillometers are available, policy guides their use.

A **pupillary response** that changes, for example a pupil that becomes larger than the other or reacts sluggishly, is an urgent cue, especially with a falling level of consciousness, because it can signal brain herniation pressing on the brainstem (Couret et al., 2016; section 30.4). The nurse first checks the record for a known baseline difference or eye condition, but does not delay reporting a new finding.

Limb strength is compared side to side. The Medical Research Council scale grades power from 0 (no contraction) through 1 (flicker of contraction), 2 (movement with gravity eliminated), 3 (movement against gravity) and 4 (movement against gravity and resistance) to 5 (normal power). Within grade 4, the subgrades 4−, 4 and 4+ describe slight, moderate or strong resistance overcome (Medical Research Council, 1976). Many units use simpler words, such as "strong", "weak" or "no movement", for each limb.

Subtle one-sided weakness is easy to miss with strength testing alone. **Pronator drift** is a quick screen: the patient holds both arms straight out in front with palms up and eyes closed, and the nurse watches whether one forearm turns palm-down and drifts downward, a sign of a problem in the motor pathway from the brain (Larsen & Stensaas, n.d.-b). In a Canadian study of 170 patients suspected of having mild one-sided brain lesions, arm drift testing (pronator drift and a related straight-arm test) detected 92% of the lesions confirmed by CT, while muscle-by-muscle strength testing detected only 39% (Teitelbaum et al., 2002).

When a patient cannot follow commands, the motor response to pressure gives vital information. **Abnormal flexion** is a slow, stereotyped bending of the arm across the chest, with the forearm turning, the thumb clenched and the leg extending; it differs from normal flexion, a quick withdrawal of the arm away from the body. **Abnormal extension** is a straightening of the arm at the elbow (Teasdale, 2015). These postures show severe brain dysfunction, and extension ranks lower on the GCS than abnormal flexion. Any new posturing is reported at once.

The nurse also checks sensation by touching both arms and legs lightly, asking whether the feeling is the same on each side, and asks about new numbness or tingling. Simple coordination tests, such as touching a finger to the nose, help detect cerebellar problems in a patient who is alert enough to take part.

Speech, Orientation and Cranial Nerve Screening

Orientation to person, place and date is part of the verbal score. The nurse also listens to how the patient speaks. **Aphasia** is a disorder of language, caused by damage to the language areas of the brain; it can affect speaking, understanding, reading and writing (National Institute on Deafness and Other Communication Disorders [NIDCD], n.d.). **Dysarthria** is a disorder of speech caused by weakness or poor control of the muscles used for talking, so speech sounds slurred, slow, soft or mumbled, but the person's language is intact (American Speech-Language-Hearing Association [ASHA], n.d.). A patient with aphasia may seem confused when the real problem is language, so the nurse records the speech problem and treats it as a factor that affects the verbal score (RCPSG, n.d.-a). New aphasia or dysarthria may signal a stroke (Chapter 31). New facial weakness, slurred speech or a wet, gurgly voice also raise concern about safe swallowing; the patient takes nothing by mouth until a swallowing screen is done (Chapter 31) (Figure 30.3).

Recognizing and Reporting Change

A single neurologic check means little on its own. Serial findings are recorded on a neurologic observation chart so that a trend can be seen at a glance (RCPSG, n.d.-b). Their value comes from comparison with the patient's baseline: the findings recorded at the previous check, and the patient's usual state as described by the family or the record. At handover, the outgoing and incoming nurses can check the patient together so that both agree on the starting point.

The GCS authors give no fixed number of points that defines a significant change. They advise the team to weigh the earlier pattern, the starting level, which component changed (a fall in the motor score usually needs a faster response) and whether the change persists or is confirmed by a colleague (RCPSG, n.d.-a). Any decline calls for urgent medical review to look for treatable causes, which may include imaging of the head, usually a computed tomography (CT) scan (RCPSG, n.d.-b).

The nurse also asks what kind of change it is. Delirium (Chapter 8) usually causes fluctuating attention and confusion without a new one-sided sign. A new focal sign, such as pronator drift, one-sided weakness, a new pupil difference or new aphasia, points to a structural problem in the brain. Both need reporting, but a focal sign is an emergency. Low blood glucose can also lower consciousness and cause focal signs; a point-of-care glucose check is part of the response (section 22.4). Late signs of rising pressure inside the skull, such as posturing, a fixed and dilated pupil and the Cushing triad, are covered in section 30.4.

When the nurse finds a decline, the nurse stays with the patient, rechecks the airway, breathing, circulation and glucose, and calls the most responsible provider or the rapid response team using SBAR (Chapter 6). An RPN reports to the RN at the same time but does not wait for the RN to reassess before calling for help when the patient is deteriorating (section 1.3). The record states the time, each GCS component in words and numbers, pupil size and reaction, limb strength on each side, who was told, when and what was done (Chapter 1).



Figure 30.3 Inferior view of the brain showing where the 12 pairs of cranial nerves (CN I to CN XII) emerge from the forebrain and brainstem. (credit: "Figure 13.23, The Cranial Nerves" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

LIFESPAN CONSIDERATIONS

Neurologic Assessment in Older Adults

- **Know the baseline.** Many older adults have some memory loss, hearing loss or slowed movement before admission. The nurse asks family members or caregivers what is usual for the person and records it, so that a new change stands out.
- **Remove barriers to communication.** Hearing loss, a language difference and a prior neurologic deficit can all interfere with the GCS (RCPSG, n.d.-a). The nurse makes sure hearing aids and glasses are in place and uses a professional interpreter when needed.
- **Review medications.** Sedation is a known interfering factor (RCPSG, n.d.-a). New sedating drugs, such as opioids or sleep medicines, are a common reason for drowsiness, but the nurse does not assume a drug is the cause until a structural problem has been considered.
- **Think of delirium.** Older adults are at high risk of delirium, which can mask or mimic other neurologic changes (Chapter 8).
- **Take falls seriously.** A fall in an older adult who takes an anticoagulant is reported promptly even when the person seems well, and neurologic checks follow the order or policy (Chapter 32).

30.3 Neurologic Diagnostics

Table 30.2 summarizes the common neurologic tests and the nursing care before and after each.

Imaging

Computed tomography (CT) uses an X-ray beam that rotates around the body to build cross-sectional images. It is fast and good at showing bleeding, clots, injuries and tumours in the head, which makes it the usual first test when a patient's neurologic status declines suddenly (National Institute of Biomedical Imaging and Bioengineering [NIBIB], n.d.-a; RCPSG, n.d.-b). CT uses ionizing radiation; the cancer risk from a single scan is generally small, but it grows with repeated exposure (NIBIB, n.d.-a).

Iodine-based contrast is injected into a vein to highlight blood vessels and some lesions, as in CT angiography. Some patients react to contrast agents, so the nurse asks about previous reactions (NIBIB, n.d.-a). The Canadian Association of Radiologists advises screening kidney risk with a short questionnaire, not delaying an emergency scan to wait for a creatinine result, considering preventive measures only when the estimated glomerular filtration rate (eGFR) is below 30 mL/min/1.73 m², and holding no medicines routinely except metformin at that eGFR (Macdonald et al., 2022). The nurse follows the local protocol. Catheter angiography, which images vessels by threading a catheter into an artery, is discussed with stroke (Chapter 31).

Magnetic resonance imaging (MRI) uses a strong magnet and radio waves and involves no ionizing radiation. It shows the brain, spinal cord and nerves in much more detail than CT (NIBIB, n.d.-b). The machine is loud, and the patient must lie very still in a

narrow tube, which can be hard for people with claustrophobia or pain; options include preparation, music and, when ordered, sedation (NIBIB, n.d.-b). Gadolinium-based contrast may be given; in people with severe kidney failure on dialysis, some of these agents have been linked to a rare but serious condition called nephrogenic systemic fibrosis (NIBIB, n.d.-b). The magnet is always on, so every person and object entering the scanner room must be screened (see Clinical Safety box).

Electroencephalography

Electroencephalography (EEG) records the brain's electrical activity through small electrodes attached to the scalp. It is a key test in diagnosing epilepsy and can help identify other brain disorders (The Ottawa Hospital, 2021). Before a routine EEG, the patient washes the hair and leaves out conditioners, creams, sprays and gels; eats a normal meal; avoids caffeine on the day of the test; and takes usual medicines unless told otherwise. When sleep is needed during the test, the patient may be asked to sleep less the night before. The recording usually lasts up to an hour; the patient may be asked to breathe deeply or look at a flashing light, which can bring on a seizure in a person with epilepsy, so staff are ready to respond (The Ottawa Hospital, 2021). Ambulatory EEG records for hours or days.

In intensive care, continuous EEG monitoring is recommended to diagnose seizures and status epilepticus that cause no obvious movements, and to judge whether seizure treatment is working; it may also help detect ischemia, assess consciousness during sedation and guide prognosis after cardiac arrest (Herman et al., 2015). Seizures and their care are covered in section 30.5.

Lumbar Puncture

A **lumbar puncture (LP)** is a procedure in which a thin needle is passed between two vertebrae in the lower back into the space that holds CSF. The CSF pressure is measured and fluid is collected for tests that look for infection, bleeding or abnormal cells; less often, fluid is removed to lower high pressure (Brain & Spine Foundation, 2022; Figure 30.4).



Figure 30.4 Lateral recumbent and seated positions for lumbar puncture, flexing the lumbar spine to widen the interspinous space for needle entry into the subarachnoid space. (credit: “Blausen 0617 LumbarPuncture” by BruceBlaus/Wikimedia Commons, CC BY 3.0)

When pressure inside the skull may be high or a mass may be present, removing CSF from below can be dangerous, so a head CT is done first. For adults with suspected bacterial meningitis, the Infectious Diseases Society of America (IDSA) recommends CT before LP for patients with features linked to abnormal head CT findings: age 60 years or older, a history of central nervous system disease, a weakened immune system, a seizure in the week before presentation, or abnormal neurologic findings such as a reduced level of consciousness, arm or leg drift, or abnormal language. In these patients, blood cultures are drawn and antibiotics are started before

the CT, so that imaging does not delay treatment (Tunkel et al., 2004; section 30.6). The nurse also tells the team if the patient takes an anticoagulant (Brain & Spine Foundation, 2022), and the prescriber decides whether to hold it.

Before the test, the nurse confirms consent (Chapter 1), explains what will happen and helps the patient into position: lying on one side, curled with knees drawn to the chest and the back at the edge of the bed, or sitting and leaning forward so that the back curves outward (Brain & Spine Foundation, 2022). During the test, the nurse supports the position, offers reassurance and watches the patient's response. A sudden sharp pain down a leg can occur if the needle touches a nerve; the clinician adjusts the needle (Brain & Spine Foundation, 2022). The nurse labels the CSF tubes in order and sends them promptly.

Afterward, the nurse checks the puncture site, vital signs and neurologic status. Routines such as lying flat for a time vary between facilities; the nurse follows the order and local policy. The most common problem is **post–dural puncture headache**, which begins within 5 days, is caused by CSF leaking through the puncture and usually comes with neck stiffness or hearing symptoms. It is usually worse when sitting or standing and better lying down, and it usually settles within 2 weeks or after an epidural blood patch seals the leak (Headache Classification Committee of the International Headache Society, 2018). Up to 35% of patients may develop this headache. A Canadian-led clinical practice guideline strongly recommends atraumatic (pencil-point) needles, which cut the risk by more than half compared with conventional needles without making the test less likely to succeed (Rochwerg et al., 2018). Patients are taught to report a headache that persists or comes with vomiting, fever or new neurologic symptoms.

Table 30.2 Neurologic tests and nursing care (NIBIB, n.d.-a, n.d.-b; Macdonald et al., 2022; Mhatre, n.d.; The Ottawa Hospital, 2021; Herman et al., 2015; Tunkel et al., 2004; Brain & Spine Foundation, 2022)

Test	What it shows	Before	After
CT of the head	Bleeding, clots, injury, swelling and tumours; fast in emergencies	Ask about pregnancy when relevant; keep the patient safe and monitored during transfer	Resume neurologic checks; report results as they arrive
CT with iodine-based contrast or CT angiography	Blood vessels and some lesions	Ask about past contrast reactions; complete the kidney risk questionnaire; follow the protocol for metformin when eGFR is below 30	Watch for delayed reactions; follow the local protocol
MRI of the brain or spine	Detailed images of brain, spinal cord and nerves	Complete the MRI safety screen; remove all metal and medication patches as directed; prepare for noise and confined space	Check that devices removed or reprogrammed for the scan are restored as directed
Routine EEG	Electrical activity; seizure patterns	Clean hair without products; regular meal; no caffeine; usual medicines unless told otherwise; less sleep if ordered	Wash out electrode paste; watch for drowsiness if a sedative was given
Continuous EEG	Seizures without movements; response to treatment	Explain the purpose to patient and family; protect the scalp and electrodes	Check the skin under electrodes; report events and seizures promptly
Lumbar puncture	CSF pressure; infection, bleeding or abnormal cells	Confirm consent; report anticoagulant use; ensure CT first when criteria apply; position the patient	Check the site, vital signs and neurologic status; teach about post–dural puncture headache

CLINICAL SAFETY

Screening Before MRI

The MRI magnet is always on. Metal objects can be pulled into the scanner as dangerous projectiles, and heating from the scanner can cause burns, among the most common MRI injuries. Careful screening prevents both (Mhatre, n.d.).

- Screen before every MRI, even if a previous scan went well. Every question on the form is answered, and every "yes" is explained.
- A nurse may complete the first screening form; trained MRI staff review it and do a final check before the scan.
- For a patient who cannot answer, ask a family member or substitute decision-maker, review the chart and imaging, and look for scars from implanted devices; X-rays may be needed when no reliable history exists.

- Record the type, make and model of any implant or device. An "MR Conditional" device is safe only under the conditions its maker specifies.
- Ask about past injuries with metal fragments, especially near the eyes.
- Remove jewellery, phones, external pumps and devices, and medication patches with metal as directed; dress the patient in a gown with no metal.
- Take only equipment labelled MR Safe or MR Conditional into the scanner room; ordinary metal oxygen tanks, monitors and pumps can become projectiles.

30.4 Increased Intracranial Pressure

Intracranial pressure (ICP) is the pressure inside the skull. A rise in ICP is one of the most dangerous problems in neurologic care, because it can reduce blood flow to the brain and push brain tissue out of place. Many conditions in this chapter and in Chapters 31 and 32 share this final pathway. This section explains why ICP rises, how the nurse recognizes the rise early, and which nursing measures protect the brain while the team treats the cause.

What Raises ICP

In an adult, the skull is a closed, rigid box. It holds three things: brain tissue, blood and cerebrospinal fluid (CSF; section 30.1). Because the box cannot expand, the total volume of these three stays the same (Wilson, 2016). When something new takes up space, such as a blood clot or a growing tumour, the body first makes room by moving CSF out of the skull and then by pushing venous blood out of the head. While this buffer lasts, the pressure changes very little. Once it is used up, even a small added volume makes the pressure climb steeply (Wilson, 2016). This explains why a patient can look stable for hours and then deteriorate within minutes.

Common causes of raised ICP include:

- **Bleeding:** a hemorrhage in or around the brain, including bleeding after surgery (Chapters 31 and 32).
- **Swelling: Cerebral edema** is swelling of brain tissue. It can surround a tumour or an abscess or accompany some infections (Bhalla et al., 2024), and it can follow a brain injury or a stroke (Chapters 31 and 32).
- **Tumours:** a growing mass plus the edema around it (section 30.6).
- **Hydrocephalus: Hydrocephalus** is a buildup of CSF in the ventricles. In obstructive hydrocephalus, something blocks the flow of CSF, and the ventricles enlarge (Bhalla et al., 2024).
- **Infection:** meningitis, encephalitis or a brain abscess (section 30.6).

The brain needs a steady supply of oxygen and glucose. **Cerebral perfusion pressure** (CPP) is the pressure that drives blood into the brain. In plain terms, it is the blood pressure pushing blood in minus the pressure inside the skull pushing back. When ICP rises, or when blood pressure falls, CPP drops and parts of the brain may not get enough blood. Section 30.1 described autoregulation, which keeps blood flow fairly steady as blood pressure changes. That protection works only within limits, and when it fails on the low-pressure side the result is poor perfusion and possible ischemia (Claassen et al., 2021). The calculation for CPP appears in the Going Deeper box at the end of this section.

Carbon dioxide also matters. A rise in the blood level of carbon dioxide widens brain blood vessels and increases blood flow; a fall narrows them and reduces flow (Claassen et al., 2021). In a tight skull, extra blood volume raises the pressure, while too little flow starves the tissue. For this reason, the team manages breathing and ventilation with care (Chapter 15).

Recognizing Rising ICP and Herniation

The nurse's most useful tool is a careful neurologic assessment, repeated as ordered and compared with the patient's own baseline (section 30.2). Early signs are often subtle and easy to blame on something else.

Raised ICP can cause headache, nausea and vomiting, pupil changes and a change in mental status (Bhalla et al., 2024). The first change is often in level of consciousness. The patient becomes restless or irritable, answers more slowly, is newly confused, or is harder to wake. A family member may say, "She isn't herself." In a patient at risk, the nurse treats new restlessness as a possible

neurologic cue, completes a neurologic assessment before giving any sedative, which could mask further change, and reports the finding.

As pressure rises further, the Glasgow Coma Scale (GCS) score falls, a pupil may enlarge and react slowly or not at all, and abnormal flexion or extension posturing may appear (section 30.2). The **Cushing triad** is a combination of high blood pressure, a slow heart rate and an irregular breathing pattern or apnea. All three together are uncommon and often appear late (Bhalla et al., 2024). The nurse never waits for the triad before acting.

Herniation is the displacement of brain tissue, under pressure, from one compartment of the skull into another or down through the opening at the base of the skull. It can occur under the fold between the two hemispheres, across the tentorium (uncal herniation) or through the foramen magnum (tonsillar herniation) (Bhalla et al., 2024). In uncal herniation, consciousness drops suddenly, the pupil on the same side as the lesion dilates, and weakness appears on the opposite side of the body (Bhalla et al., 2024). Herniation is an emergency. The nurse calls for immediate help through the hospital's process (Chapter 6), stays with the patient, supports the airway and breathing, and prepares for urgent imaging and treatment. Table 30.3 groups early and late signs with the nursing response (Figure 30.5).

Figure 30.5 Non-contrast head CT showing an acute left-sided subdural hematoma (solid arrows) with mass effect, ventricular compression and midline shift to the right (open arrows). (credit: “Trauma subdural arrows” by Glitzy queen00/Wikimedia Commons, Public domain)

Table 30.3 Early and late signs of increased intracranial pressure and the nursing response (Bhalla et al., 2024; sections 30.2 and 30.4)

Area assessed	Early signs	Late signs	Nursing action
Level of consciousness	Restlessness, irritability, slower answers, new confusion, drowsiness	Falling GCS score; responds only to pressure or not at all	Compare with baseline; report any decline at once; do not sedate before assessing
Pupils	Subtle change in size or a slightly slower reaction on one side	One pupil dilated and sluggish or fixed; both pupils fixed	Treat a new unequal or sluggish pupil as urgent; escalate immediately
Movement	New weakness or pronator drift on one side	Abnormal flexion or extension posturing; no movement	Check both sides each time; describe exactly what is seen
Vital signs	May be unchanged early	High blood pressure, slow heart rate, irregular breathing or apnea (Cushing triad)	Do not wait for these signs; call for immediate help if they appear
Other	New or worsening headache; nausea or vomiting	Seizures; airway at risk as consciousness falls	Protect the airway; report vomiting and headache; follow seizure care (section 30.5)

Nursing Care

Nursing care aims to keep oxygen and blood flowing to the brain and to avoid anything that pushes ICP higher while the team treats the cause. The measures below follow the Neurocritical Care Society's basic measures for anyone at risk of raised ICP (Bhalla et al., 2024) and an international consensus algorithm for severe traumatic brain injury (Hawryluk et al., 2019). The patient's own orders always guide care.

Figure 30.6 An external ventricular drain (EVD) system mounted on a bedside pole with the pressure transducer levelled at the external auditory meatus and blood-tinged cerebrospinal fluid in the collection chamber. (credit: "EVD-ICH" by Rmosler2100/Wikimedia Commons, CC BY-SA 3.0)

- **Position:** The Neurocritical Care Society protocol advises raising the head of the bed above 30° and keeping the head in the midline to help venous blood drain from the head (Bhalla et al., 2024). The nurse avoids sharp bending or turning of the neck and checks that collars, tube ties and dressings do not press on the neck. Some patients need a different position, so the nurse follows the order (Figure 30.6).
- **Oxygen and breathing:** The nurse keeps oxygen saturation (SpO_2) above 94% (Bhalla et al., 2024), protects the airway and reports noisy or irregular breathing. Deliberate fast breathing to lower carbon dioxide is used only briefly, as a bridge ordered by the team, because prolonged use may worsen ischemia (Bhalla et al., 2024).
- **Blood pressure:** Low blood pressure lowers CPP, so the nurse reports hypotension promptly.
- **Temperature:** Fever increases the brain's demands. The aim is a normal temperature (Bhalla et al., 2024), and the severe brain injury algorithm defines fever to avoid as a core temperature above 38 °C (Hawryluk et al., 2019).
- **Sodium and glucose:** The protocol calls for correcting low sodium (Bhalla et al., 2024; section 3.4). The nurse watches sodium and glucose results as ordered and reports values outside the ranges the team has set; low glucose is managed as described in section 22.4.
- **Comfort and calm:** The protocol advises keeping painful or distressing stimuli to a minimum and giving analgesia and sedation as ordered (Bhalla et al., 2024). The nurse plans care so that the patient has rest periods, keeps the room quiet and explains each step.
- **Avoiding strain:** The nurse helps the patient avoid straining, gives stool softeners as ordered and reports constipation.
- **Seizures:** The nurse gives antiseizure medicines on time as ordered and reports any seizure activity (section 30.5).
- **Osmotherapy: Osmotherapy** is the use of a concentrated solution to draw water out of brain tissue into the bloodstream and lower ICP. Mannitol and hypertonic saline are described as equally effective, and both depend on an intact blood–brain barrier (Bhalla et al., 2024). The nurse gives them as ordered or per protocol and monitors the laboratory values the order sets (Table 30.4). Corticosteroids are reserved for edema around tumours, abscesses and certain infections and are otherwise avoided (Bhalla et al., 2024); routine steroids are not recommended for severe traumatic brain injury (Hawryluk et al., 2019).
- **Escalation:** Any decline in level of consciousness, a new pupil change or new weakness is reported at once using SBAR (Chapter 6). The Neurocritical Care Society suggests that handovers include the patient's worst, best and current neurologic examination, the steps taken and the response (Bhalla et al., 2024).

Families are often the first to notice that something has changed. The nurse explains why the head of the bed stays raised, why checks continue through the night, and why the patient should avoid straining. The nurse asks the family to report any change in alertness, speech or behaviour, however small. For older adults, the family's description of the person's usual thinking, hearing and vision helps the nurse set an accurate baseline (section 30.2). An older adult who takes an anticoagulant and has a fall needs prompt assessment as the employer's policy directs (Chapter 32). When the patient moves to another unit or goes home, the nurse hands over the latest neurologic findings and the warning signs the patient and family should watch for.

GOING DEEPER

ICP Monitoring and External Ventricular Drains

Required for RN students; optional for PN students.

In critical care, ICP can be measured with a monitor placed in the brain or a ventricle. CPP is calculated as mean arterial pressure (MAP) minus ICP: a MAP of 80 mm Hg and an ICP of 25 mm Hg give a CPP of 55 mm Hg.

- **Thresholds:** The Brain Trauma Foundation's fourth edition, a guideline for severe traumatic brain injury, recommends treating ICP above 22 mm Hg (Carney et al., 2017). The Neurocritical Care Society defines adult intracranial hypertension as ICP above 22 mm Hg for more than 5 minutes and gives a CPP target of 60 to 70 mm Hg (Bhalla et al., 2024). These numbers come from brain injury research; for other conditions, the team sets the targets.
- **External ventricular drain:** An **external ventricular drain** (EVD) is a catheter placed through the skull into a ventricle that measures ICP and drains CSF into a closed system. It is used to treat raised ICP (Hawryluk et al., 2019) and obstructive hydrocephalus (Bhalla et al., 2024).
- **Nursing care:** The drain is levelled and set at the height that the neurosurgical order and employer policy specify, re-levelled whenever the patient's position changes, and clamped only as ordered or as policy allows. The nurse records CSF volume, colour and clarity and reports sudden changes.
- **Infection:** CSF infection is a recognized complication of an EVD (Fried et al., 2016), so the nurse handles the system only as policy allows and uses aseptic technique.

CLINICAL JUDGMENT

Restless After Surgery

Names and details are fictional; this is a composite story.

Lorraine Bouchard, 63, is on a neurosurgery unit on day 2 after removal of a brain metastasis from her right frontal lobe. At 02:00 the RPN caring for her finds her trying to climb out of bed and pulling at her intravenous (IV) line. At 22:00 her GCS score was 15, her pupils were equal and brisk, and she had no drift. She is on dexamethasone and levetiracetam.

- **Recognize cues:** She is restless and says her head "is pounding." She vomited once. Her GCS score is now 14 because she is confused about the date. Her pupils are equal and brisk, and she has no drift. Blood pressure is 158/88 mm Hg, up from 132/76; heart rate is 84. The head of her bed has slid down to about 15°.
- **Analyze cues:** The RPN considers delirium (Chapter 8), pain, a full bladder, low sodium and high glucose from dexamethasone (Table 30.4). New confusion with headache and vomiting after brain surgery could also mean rising ICP.
- **Prioritize hypotheses:** Rising ICP from postoperative edema or bleeding is the most dangerous possibility and must be ruled out first.
- **Generate solutions:** Hold the as-needed sedative, raise the head of the bed as ordered, check capillary glucose, recheck the neurologic assessment within minutes, and involve the RN and the neurosurgery resident.
- **Take action:** The RPN raises the head of the bed to the ordered 30°, keeps her head midline and calls the RN to the bedside. Capillary glucose is 9.2 mmol/L. The RN calls the resident using SBAR. The resident orders an urgent CT scan, sodium and glucose levels, and neurologic checks every 15 minutes.
- **Evaluate outcomes:** The CT shows more edema but no new bleeding. After the dexamethasone order is changed, her headache eases, and by 06:00 her GCS score is 15.

30.5 Seizures and Status Epilepticus

Seizures and Epilepsy

A **seizure** is a short-lived event of signs or symptoms caused by abnormal, excessive or synchronized electrical activity of neurons in the brain (Fisher et al., 2014). A seizure is a symptom, not a diagnosis. **Epilepsy** is a brain disease marked by a lasting tendency to have seizures. The International League Against Epilepsy (ILAE) diagnoses epilepsy when a person has two unprovoked seizures more than 24 hours apart, or one unprovoked seizure and a high chance of more (at least 60% over the next 10 years), or a recognized epilepsy syndrome (Fisher et al., 2014). A **provoked seizure**, also called an acute symptomatic seizure, is caused by a temporary problem acting on an otherwise normal brain, such as a concussion, a fever or alcohol withdrawal. A provoked seizure does not on its own count toward a diagnosis of epilepsy (Fisher et al., 2014).

The ILAE updated its seizure classification in 2025, building on its 2017 framework. The update keeps four classes (Beniczky et al., 2025):

- **Focal:** A **focal seizure** starts in networks limited to one hemisphere. Focal seizures are further described by whether consciousness, meaning both awareness and responsiveness, is preserved or impaired.
- **Generalized:** A **generalized seizure** starts in networks spread across both hemispheres. Examples are absence seizures and generalized tonic-clonic seizures.
- **Unknown:** The information available is not enough to say whether the seizure was focal or generalized.
- **Unclassified:** No information is available to describe the seizure, but the clinician is confident it was epileptic.

A **tonic-clonic seizure** has a stiffening (tonic) phase followed by rhythmic jerking (clonic) of the limbs. It may be generalized from the start, or it may begin as a focal seizure that spreads to both hemispheres, called a focal-to-bilateral tonic-clonic seizure (Beniczky et al., 2025). The update also asks clinicians to describe signs in the order they appeared, not just the first sign (Beniczky et al., 2025). The nurse's careful description of what happened first, and what followed, therefore helps the team classify the seizure.

Seizures in hospital have many possible causes. Stopping an antiseizure medicine abruptly can increase seizure frequency (BGP Pharma, 2023), so the nurse treats missed or vomited doses as a possible trigger. Low blood glucose (section 22.4) and alcohol withdrawal (Chapter 11) are possible causes of prolonged seizures (National Institute for Health and Care Excellence [NICE], 2022). Other causes include low sodium (section 3.4), brain tumours (National Cancer Institute, n.d.), encephalitis (Tunkel et al., 2008) and injury to the brain (Fisher et al., 2014). The nurse looks for a cause the team can correct and asks people with epilepsy about their own triggers, such as lack of sleep.

Care During and After a Seizure

Most seizures stop on their own within seconds to a few minutes (Epilepsy Ontario, 2018). The nurse's role during a seizure is to stay with the patient, keep the patient safe and observe closely. Epilepsy Ontario's first aid advice, adapted to the hospital, is:

- **Stay and call:** Stay calm and with the patient, and call for help with the call bell or the unit's emergency process.
- **Time it:** Note the time the seizure started and the time it ended (Epilepsy Ontario, 2018).
- **Make the space safe:** Move hard or sharp objects away, cushion the head and lower the bed. Once the jerking eases, turn the patient onto the side so that saliva can drain (Epilepsy Ontario, 2018).
- **Nothing in the mouth, no restraint:** Never place anything in the mouth, including a tongue blade or a finger, and never hold the person down (Epilepsy Ontario, 2018).
- **Oxygen and suction:** Give oxygen and suction the mouth as employer policy and the patient's orders direct.
- **Watch for emergency cues:** Epilepsy Ontario advises calling for emergency help when a seizure lasts more than 5 minutes, when seizures repeat without full recovery in between, when consciousness or normal breathing does not return, or when the person is injured, pregnant or has diabetes (Epilepsy Ontario, 2018). In hospital, the nurse activates the rapid response or code process (Chapter 6).

During the seizure, the nurse observes and later records the details: what the patient was doing beforehand; any warning the patient describes; where the movements started and how they spread; the eyes and head; skin colour; breathing; incontinence or tongue biting; and how long the seizure lasted. Colour changes such as cyanosis can be harder to see on darker skin (Chapter 12), so the nurse also looks at the lips and inside the mouth and checks SpO_2.

The **post-ictal state** is the recovery period after a seizure. The patient may be drowsy or confused for a time and may not recall the seizure. The nurse keeps the patient on the side, checks vital signs, SpO_2 and capillary glucose, completes a neurologic assessment and looks for injury. The nurse stays until the patient is fully aware again and offers calm reassurance (Epilepsy Ontario, 2018). A patient who does not wake as expected, or who has new weakness, needs prompt reassessment by the team. **Seizure precautions** are the safety measures the employer's policy sets for patients at risk, such as a low bed, suction and oxygen ready at the bedside, and IV access.

Status Epilepticus

Status epilepticus is a seizure that lasts too long, or seizures that follow one another without recovery, because the mechanisms that normally stop a seizure have failed (Trinka et al., 2015). For a convulsive (tonic-clonic) seizure, the ILAE defines two time points. After 5 minutes, the seizure is treated as continuous seizure activity that is unlikely to stop on its own. After 30 minutes, it carries a risk of long-term harm to the brain. The authors note that the evidence behind these times is incomplete (Trinka et al., 2015).

This chapter uses the American Epilepsy Society (AES) guideline (Glauser et al., 2016) for treatment timing. The guideline divides care into phases:

- **Stabilization (0 to 5 minutes):** standard initial first aid for seizures.
- **Initial therapy (from 5 minutes):** a benzodiazepine, such as intramuscular midazolam, intravenous lorazepam or intravenous diazepam.
- **Second therapy (from 20 minutes):** if the seizure continues, an intravenous second-line medicine, such as fosphenytoin, valproic acid or levetiracetam.
- **Third therapy (from 40 minutes):** further medicines or anesthetic drugs, with continuous electroencephalography (EEG), in critical care.

Medicines are given as ordered or per protocol. A UK guideline also advises a second benzodiazepine dose when the seizure has not stopped 5 to 10 minutes after the first, and asks clinicians to consider causes such as low blood glucose and alcohol withdrawal (NICE, 2022). The nurse checks capillary glucose as soon as it can be done safely and treats a low value per protocol (section 22.4). The nurse calls for help early, before the 5-minute mark if the patient is struggling to breathe or is injured. Benzodiazepines can cause dangerous respiratory depression, so equipment to support the airway and breathing is kept ready, and after a dose the nurse watches breathing, SpO_2 and level of consciousness closely (Sandoz Canada, 2022).

Living With Epilepsy

Many people with epilepsy live full lives with good seizure control. The nurse supports this goal in several ways:

- **Taking medicines as prescribed:** The phenytoin monograph warns that stopping an antiseizure medicine suddenly can increase seizures, including status epilepticus, and that changes should be made gradually under a prescriber's direction (BGP Pharma, 2023). On admission, the nurse confirms each antiseizure medicine, the dose and the timing, and makes sure doses are not missed when the patient cannot take anything by mouth.
- **Drug levels and interactions:** For phenytoin, the monograph states that the effective serum level is usually 40 to 80 µmol/L, that early signs of toxicity are involuntary eye movements (nystagmus), unsteadiness and slurred speech, and that many drugs raise or lower phenytoin levels (BGP Pharma, 2023). The nurse reports these signs, and the pharmacist reviews new medicines for interactions (Table 30.4).
- **Mood:** Antiseizure medicines can raise the chance of suicidal thinking and behaviour, so every patient taking them is monitored (BGP Pharma, 2023). The nurse asks about mood and provides crisis resources.
- **Driving:** In Ontario, physicians and nurse practitioners must report patients with certain high-risk medical conditions to the Ministry of Transportation under the *Highway Traffic Act* (Government of Ontario, 2026). For seizures, the main concern is that the driver could suddenly become incapacitated. The ministry reviews each report against national medical standards and may suspend a licence (Ministry of Transportation, 2019). The nurse teaches the patient not to drive until the prescriber and the ministry say it is safe. Each province and territory sets its own driver fitness policies, and only some make reporting by health professionals mandatory (Canadian Council of Motor Transport Administrators [CCMTA], 2021).
- **Safety and stigma:** The nurse asks about safety at home and work, helps the patient plan for seizures, and links the patient to Epilepsy Ontario or a local epilepsy agency. Epilepsy still carries stigma; the nurse uses person-first language, such as "a person with epilepsy."

Table 30.4 Medicines for seizures and raised intracranial pressure (Canadian product monographs and sources cited)

Drug or class	Canadian examples	Used for	Nursing points

Drug or class	Canadian examples	Used for	Nursing points
Benzodiazepines	lorazepam, midazolam, diazepam	First treatment for status epilepticus (Glauser et al., 2016)	Give as ordered or per protocol; record the time; watch breathing, SpO_2 and level of consciousness; have airway equipment ready (Sandoz Canada, 2022)
Antiseizure medicines	levetiracetam, phenytoin, fosphenytoin, valproic acid, lacosamide, carbamazepine	Second-line treatment of status epilepticus (levetiracetam, fosphenytoin, valproic acid); long-term seizure control	Give on time; do not stop suddenly; for phenytoin, levels as ordered (usually 40 to 80 µmol/L), report nystagmus, unsteadiness or slurred speech, teach good dental hygiene; monitor mood (BGP Pharma, 2023)
Osmotherapy	mannitol, hypertonic saline	Lowering ICP (Bhalla et al., 2024)	Give as ordered or per protocol; for hypertonic saline, check sodium as ordered (the protocol suggests every 4 to 6 hours); for mannitol, follow the osmolality or osmolar gap results the order sets; report results outside the set limits
Corticosteroid	dexamethasone	Edema around brain tumours; adjunct in some bacterial meningitis	Monitor glucose (may unmask diabetes or raise insulin needs); watch for signs of infection, which steroids can mask, and mood change; do not stop suddenly (Sandoz Canada, 2026)

CANADIAN CONTEXT

Epilepsy in Canada

The Public Health Agency of Canada (PHAC) tracks epilepsy through the Canadian Chronic Disease Surveillance System. In 2021–2022, almost 1 in 100 Canadians were living with epilepsy: 13% were children and youth aged 1 to 19, 63% were adults aged 20 to 64, and 24% were older adults aged 65 and older. New cases were most frequent in older adults, at 87 per 100,000, compared with 51 per 100,000 adults aged 20 to 64 and 66 per 100,000 children and youth. After adjustment for population aging, the share of Canadians living with epilepsy rose by about 2% a year, from 0.78% in 2011–2012 to 0.95% in 2021–2022. The data do not include Quebec or the Northwest Territories, and PHAC advises caution with 2021–2022 figures because of the COVID-19 pandemic (PHAC, 2024).

Care is not equally easy to reach. In the Kivalliq region of Nunavut, for example, EEG is not available locally, and treating prolonged seizures beyond first- and second-line medicines can mean air transfer more than a thousand kilometres away (Ng, 2024). Ng notes that local epilepsy care falls short of what is recommended and names the lasting effects of cultural and socioeconomic trauma as part of the challenge. Losing a driver's licence after a seizure can make travel to appointments harder. The nurse asks how the patient will reach follow-up care and connects the patient with virtual care and community epilepsy agencies where they are available.

30.6 Headache, Central Nervous System Infections and Brain Tumours

Headache Red Flags

Most headaches are primary headaches, such as migraine or tension-type headache. Only a minority are secondary headaches, caused by another condition (Do et al., 2019). The nurse's task is to notice the features that suggest a dangerous cause and to report them. One widely used list, called SNNOOP10, names these red flags (Do et al., 2019):

- **Systemic symptoms,** including fever.
- **Neoplasm** (cancer) in the person's history.
- **Neurologic deficit,** including decreased consciousness.
- **Onset that is sudden or abrupt.** A **thunderclap headache** is a severe headache that reaches its peak almost at once; it can signal bleeding around the brain and needs emergency assessment (Chapter 31).
- **Older age,** with headache that begins after age 65.
- **A change in pattern** or a recent new headache.

- **Position** that changes the headache, or headache **precipitated** by sneezing, coughing or exercise.
- **Papilledema,** a swelling of the optic disc seen on eye examination.
- **Progressive** headache or an unusual presentation.
- **Pregnancy** or the period after giving birth.
- **A painful eye** with features such as tearing or a red eye.
- **Posttraumatic** onset, after a head injury (Chapter 32).
- **Pathology of the immune system,** for example human immunodeficiency virus (HIV) infection.
- **Painkiller overuse** or a new drug started when the headache began.

The authors note that the evidence for many red flags is limited (Do et al., 2019). The nurse therefore reports any red flag, together with vital signs and a neurologic assessment, and does not decide alone that a headache is harmless. A headache with fever and neck stiffness points to meningitis.

Meningitis and Encephalitis

Bacterial meningitis is a bacterial infection of the meninges, the membranes covering the brain and spinal cord. It is a medical emergency. In a large Dutch study of adults with community-acquired bacterial meningitis, the most common causes were *Streptococcus pneumoniae* (51% of episodes) and *Neisseria meningitidis* (37%) (van de Beek et al., 2004).

In meningococcal meningitis, PHAC lists sudden fever, severe headache and neck stiffness, sometimes with nausea, vomiting, sensitivity to light and a change in consciousness (Public Health Agency of Canada [PHAC], 2026). Not every patient has all the classic signs. In the Dutch study, only 44% of episodes showed all three of fever, a stiff neck and altered mental status, yet almost every patient had two or more of headache, fever, neck stiffness and altered mental status (van de Beek et al., 2004).

Infection with *N. meningitidis* can cause a petechial rash, sometimes with pink spots or blisters, and a rash that does not blanch with pressure in meningococcal sepsis. The rash is harder to see on darker skin, so the nurse checks paler areas such as the palms, the soles and the inside of the eyelids, as well as the palate (PHAC, 2026). A non-blanching rash with fever is reported at once. Sepsis is covered in Chapter 4.

Care moves fast:

- **Cultures and antibiotics:** Blood cultures are drawn at once. When the lumbar puncture will be delayed or a CT is needed first, antibiotics and adjunctive therapy are given before the lumbar puncture or before the patient goes for CT (Tunkel et al., 2004). Antibiotics are never delayed for testing. The prescriber chooses intravenous antibiotics based on the patient's age and risk factors; examples are ceftriaxone, often with vancomycin, and ampicillin in some patients (Tunkel et al., 2004). The nurse gives them as ordered and without delay.
- **Dexamethasone:** When an adult has suspected or confirmed pneumococcal meningitis, the first dose of dexamethasone is given 10 to 20 minutes before, or at the same time as, the first antibiotic dose (Tunkel et al., 2004).
- **CT before lumbar puncture:** CT is done first in some adults: those aged 60 or older and those with a weakened immune system, a history of central nervous system disease, a seizure in the past week, or abnormal neurologic findings such as a reduced level of consciousness or a focal deficit (Tunkel et al., 2004; section 30.3).
- **Precautions:** Ontario public health guidance calls for droplet precautions for a hospitalized patient with invasive meningococcal disease until 24 hours of antibiotic therapy have been given (Thunder Bay District Health Unit, 2026). Infection prevention and control are covered in Chapter 4.
- **Public health:** Invasive meningococcal disease is nationally notifiable, and suspected cases must be reported by health care providers to the local public health unit (PHAC, 2026), in Ontario immediately by phone (Thunder Bay District Health Unit, 2026). Public health staff find close contacts, who are offered preventive antibiotics whatever their vaccination status (PHAC, 2026).
- **Monitoring:** The nurse watches for rising ICP, seizures, shock and changes in the rash, and reports them at once.

In Canada, 104 of 738 people with invasive meningococcal disease and a known outcome died between 2012 and 2021, and 15% to 20% of survivors have lasting effects such as hearing loss, seizures or limb loss (PHAC, 2026). Vaccines protect against several

serogroups (Chapter 21).

Encephalitis is inflammation of the brain tissue itself, with signs of neurologic dysfunction. It shares many features with meningitis, and some patients have both (meningoencephalitis). Encephalitis can cause confusion, behaviour change, focal weakness and seizures (Tunkel et al., 2008). In the IDSA guideline, herpes simplex virus is among the most commonly identified causes. Acyclovir is started in every patient with suspected encephalitis while test results are pending (Tunkel et al., 2008). Because a change in mental status cannot reliably separate encephalitis from bacterial meningitis, the team considers both at first (Tunkel et al., 2008).

Brain Tumours and Craniotomy Care

A **primary brain tumour** starts in the brain or its coverings. A metastatic (secondary) brain tumour spreads to the brain from cancer elsewhere. The Brain Tumour Foundation of Canada (2025) states that each day, 27 people in Canada learn they have a brain tumour, and for 8 of them it is brain cancer. Of all primary brain tumours, 62% are non-malignant, and brain metastases develop at some point in 20% to 40% of people with cancer (Brain Tumour Foundation of Canada, 2025). For 2026, the Canadian Cancer Society (2026) projects 3,300 new diagnoses of brain and other nervous system cancer in Canada and 2,700 deaths from it.

Symptoms depend on the size and location of the tumour (National Cancer Institute, n.d.). General symptoms include persistent headache, vomiting, drowsiness and subtle changes in personality, memory or thinking. Other symptoms reflect the area involved (section 30.1), such as weakness on one side, or problems with speech, vision or coordination. A new seizure in an adult with no history of seizures can be a sign of a brain tumour (National Cancer Institute, n.d.). Edema around the tumour can raise ICP (section 30.4).

Dexamethasone may be used to treat cerebral edema, including edema around brain tumours (Sandoz Canada, 2026). It can unmask diabetes or raise insulin needs, mask signs of infection, cause mood changes and stomach ulcers, and must not be stopped suddenly (Sandoz Canada, 2026). The nurse checks glucose as ordered and teaches the patient to taper only as directed. Cancer treatment is covered in Chapter 9, and palliative care in Chapter 10.

A **craniotomy** is surgery in which part of the skull is opened to reach the brain. General perioperative care is in Chapter 7. After a craniotomy, the nurse:

- completes neurologic checks as ordered and compares each with the last, reporting any decline at once (section 30.2);
- keeps the head of the bed at the angle the surgeon orders;
- watches the incision for bleeding, swelling and infection, and reports any clear fluid from the wound, nose or ear, which can be a sign of a CSF leak;
- monitors sodium and fluid balance, because sodium problems can follow brain surgery (section 3.4; section 23.5);
- gives antiseizure medicines on time and follows seizure precautions as ordered;
- manages pain and nausea as ordered (Chapter 5) and helps the patient avoid straining (section 30.4); and
- supports the patient and family facing a new cancer diagnosis, and involves palliative care early when goals call for it (Chapter 10).

> **SCOPE IN PRACTICE**
>
> **Neurologic Care and Who Does What**
>
> The College of Nurses of Ontario's (CNO's) Scope of Practice standard asks whether a nurse has the **authority**, the **competence** and the right **context** for an activity (Chapter 1, section 1.3).
>
> - **Neurologic checks:** RNs and RPNs both complete neurologic assessments, including the GCS, pupils and limb strength, for patients in their care.
> - **Escalation is every nurse's duty:** Any nurse who finds a falling GCS score, a new pupil change or new weakness acts at once and escalates. The RPN does not wait for the next scheduled check; the RPN informs the RN and the physician or nurse practitioner immediately.
> - **Competence:** EVD care, continuous EEG monitoring and titrated infusions, such as hypertonic saline, need specialized education. Many employers limit them to RNs, often in critical care or on neurosurgical units. A nurse who has not been educated for these activities does not perform them and asks for help.

- **Context:** The RPN consults the RN when a patient's needs grow more complex, such as rising ICP, status epilepticus or suspected meningitis. Assigning patients by stability is a common employer practice, not a CNO rule.
- **Standards:** CNO's revised Scope of Practice and Medication standards take effect March 1, 2027.

Employer policy and the province or territory shape these roles.

PRACTICE STORY

Thirty Degrees

Names and details are fictional; this is a composite story.

Nurse: Deepa Nair, RN. Years in practice: 3. Setting: neurosurgery unit, Ontario.

Mr. Delorme was 71, the day after a craniotomy to remove a meningioma. At 08:00 he was chatty, telling me about his grandson's hockey team. GCS 15. Pupils 3 mm, equal and brisk. Strong grips on both sides.

At 11:30, after physiotherapy, I found him lying almost flat. The order said thirty degrees. I raised the bed and started my checks, and something felt off. He still knew where he was, but he answered in short phrases and kept closing his eyes. "Just tired," he said. His GCS was still 15 when I scored it. Then I looked at his pupils. The left one was 4 mm and slower than the right.

It was a millimetre. I could have talked myself out of it. I asked my charge nurse to look, and she saw it too. His blood pressure was higher than at 08:00, and his heart rate was a little lower.

I called the neurosurgery resident and gave it to her in SBAR: day 1 after a left frontal craniotomy; new left pupil, 4 mm and sluggish; drowsier than at 08:00, though still scoring 15; blood pressure up. I told her I was worried. She came within minutes, ordered an urgent CT scan and asked me to repeat his checks every 15 minutes. The scan showed a small collection of blood under the bone flap, and he went back to the operating room that afternoon.

Two days later, he was telling me about hockey again. What stays with me is that the total score had not changed. The pupil, and the way he talked, told me more than the number did.

Reflect: Which cues did Priya act on, even though the GCS total had not changed? If an RPN on the same unit had noticed the pupil change first, what should the RPN have done, and who should the RPN have told?

Chapter 30 Summary

Introduction

- Early neurologic changes are often small, and the bedside nurse is often the first to notice them; careful, repeatable checks compared with baseline allow early action.

30.1 The Nervous System: A Focused Review

- Neurons send signals along axons, sped by myelin, and pass them to the next cell with neurotransmitters; the brain and spinal cord form the central nervous system.
- The four lobes of each cerebral hemisphere have distinct roles, and pathways cross so that each hemisphere mainly controls the opposite side of the body.
- The brainstem controls breathing, heart rate and arousal; consciousness needs both arousal and awareness, so a falling level of consciousness suggests a brainstem or widespread hemispheric problem.
- The brain uses about 20% of the body's oxygen; autoregulation keeps blood flow fairly steady over a narrower range than once taught, and rising carbon dioxide widens cerebral vessels.
- An adult has about 150 mL of CSF but makes 400 to 600 mL a day; the skull is a closed box shared by brain, blood and CSF (section 30.4).

30.2 Focused Neurologic Assessment

- The GCS is done with the structured approach (check, observe, stimulate, rate), using fingertip pressure first and avoiding a sternal rub.

- Each component is reported in words and numbers; untestable components are recorded as NT, not 1, and no total is reported when a component is NT.
- A new unequal or sluggish pupil, new pronator drift, new posturing or a falling motor score is an urgent cue; pronator drift detects subtle weakness better than strength testing alone.
- Aphasia is a language disorder and dysarthria a muscle-control speech disorder; both can affect the verbal score and swallowing safety.
- Change is judged against baseline; a new focal sign points to a structural problem and is escalated at once with SBAR, with precise documentation.

30.3 Neurologic Diagnostics

- CT is fast and the usual first test for sudden decline; Canadian guidance limits kidney precautions for iodine contrast to an eGFR below 30 mL/min/1.73 m² and does not delay emergency scans.
- MRI gives more detail without ionizing radiation but needs a full safety screen before every scan, because the magnet is always on.
- Routine EEG needs clean hair without products and usual medicines; continuous EEG in intensive care detects seizures without movements.
- Lumbar puncture is preceded by CT when criteria such as reduced consciousness or a focal deficit are present, without delaying antibiotics in suspected meningitis.
- Post–dural puncture headache is positional and usually resolves; atraumatic needles reduce it by more than half.

30.4 Increased Intracranial Pressure

- The skull is a closed box holding brain, blood and CSF; once the body's buffer is used up, a small added volume makes ICP rise steeply.
- Bleeding, cerebral edema, tumours, hydrocephalus and infection can all raise ICP and lower cerebral perfusion pressure.
- Early signs are subtle changes in level of consciousness, restlessness, headache and vomiting; a falling GCS score, pupil changes, posturing and the Cushing triad are late signs.
- Herniation is an emergency: the nurse calls for immediate help and stays with the patient.
- Nursing care includes raising the head of the bed above 30° with the head midline as ordered, keeping SpO_2 above 94%, avoiding fever and low blood pressure, limiting distressing stimuli and giving osmotherapy as ordered or per protocol.

30.5 Seizures and Status Epilepticus

- Epilepsy is a lasting tendency to have seizures; a provoked seizure caused by a temporary problem does not on its own count toward the diagnosis.
- The ILAE's 2025 classification keeps four classes (focal, generalized, unknown and unclassified) and asks for signs to be described in the order they appeared.
- During a seizure, the nurse stays, times it, protects the head, turns the patient to the side as it eases and never restrains or puts anything in the mouth.
- A convulsive seizure lasting 5 minutes is status epilepticus; the AES guideline gives a benzodiazepine from 5 minutes and a second-line medicine from 20 minutes, as ordered or per protocol.
- Antiseizure medicines are never stopped suddenly; phenytoin toxicity shows as nystagmus, unsteadiness and slurred speech.
- In Ontario, physicians and nurse practitioners must report high-risk conditions to the Ministry of Transportation; the nurse teaches the patient not to drive until cleared.

30.6 Headache, Central Nervous System Infections and Brain Tumours

- Headache red flags include fever, a history of cancer, neurologic deficits, sudden onset, onset after 65, a changed pattern and immune system disease.
- Bacterial meningitis is an emergency; the classic triad is often incomplete, and antibiotics are never delayed for testing.

- A petechial rash is harder to see on darker skin, so the nurse checks the palms, soles, eyelids and palate.
- In Ontario, patients with invasive meningococcal disease are on droplet precautions for 24 hours after antibiotics start, and suspected cases are reported to public health at once.
- Acyclovir is started for suspected encephalitis while tests are pending.
- After a craniotomy, the nurse compares each neurologic check with the last, watches for CSF leak and sodium problems, monitors glucose on dexamethasone, and escalates any decline at once.

Key Terms (44)

abnormal extension: A motor response in which the arm straightens at the elbow in response to a stimulus; it ranks lower on the GCS than abnormal flexion.

abnormal flexion: A slow, stereotyped motor response with the arm bent across the chest, forearm turning, thumb clenched and leg extended; a sign of severe brain dysfunction.

antiseizure medication: A medicine used to prevent or stop seizures, such as levetiracetam, phenytoin or lacosamide.

aphasia: A disorder of language from damage to the brain's language areas that can affect speaking, understanding, reading and writing.

autoregulation: The ability of cerebral blood vessels to widen or narrow to keep brain blood flow fairly steady when blood pressure changes.

bacterial meningitis: A bacterial infection of the meninges that cover the brain and spinal cord; a medical emergency.

blood–brain barrier: Tightly joined cells that limit which substances pass from the blood into brain tissue.

brainstem: The midbrain, pons and medulla, which link the brain to the spinal cord and control breathing, heart rate, many reflexes and arousal.

central nervous system (CNS): The brain and spinal cord.

cerebellum: The part of the brain at the back, below the cerebrum, that coordinates movement and learned motor skills.

cerebral edema: Swelling of brain tissue, for example around a tumour or after an injury.

cerebral perfusion pressure: The pressure that drives blood into the brain; mean arterial pressure minus intracranial pressure.

cerebrospinal fluid (CSF): The clear fluid made mainly in the choroid plexus of the ventricles that cushions the brain and spinal cord and carries away waste.

cerebrum: The main part of the forebrain, the largest part of the brain, made of two hemispheres and four lobes; it controls conscious thought, memory, language and voluntary movement.

computed tomography (CT): An imaging test that uses a rotating X-ray beam to build cross-sectional images; fast and useful for finding bleeding in the head.

craniotomy: Surgery in which part of the skull is opened to reach the brain.

Cushing triad: A late sign of raised intracranial pressure: high blood pressure, a slow heart rate and an irregular breathing pattern or apnea.

dysarthria: A speech disorder caused by weakness or poor control of the muscles used for talking, producing slurred, slow or soft speech with intact language.

electroencephalography (EEG): A test that records the brain's electrical activity through electrodes on the scalp.

encephalitis: Inflammation of the brain tissue itself, with signs of neurologic dysfunction such as confusion, behaviour change or seizures.

epilepsy: A brain disease marked by a lasting tendency to have seizures, diagnosed by the ILAE's practical definition.

external ventricular drain: A catheter placed through the skull into a ventricle that measures intracranial pressure and drains cerebrospinal fluid into a closed system.

focal seizure: A seizure that starts in networks limited to one hemisphere of the brain.

generalized seizure: A seizure that starts in networks spread across both hemispheres of the brain.

Glasgow Coma Scale (GCS): A standard scale that rates eye opening, verbal response and motor response to describe level of consciousness; the components are reported separately, and the total ranges from 3 to 15.

herniation: The displacement of brain tissue, under pressure, from one compartment of the skull into another or through the opening at the base of the skull.

hydrocephalus: A buildup of cerebrospinal fluid in the ventricles of the brain, often because its flow is blocked.

intracranial pressure: The pressure inside the skull, produced by the brain tissue, blood and cerebrospinal fluid it contains.

level of consciousness: How awake a person is (arousal) and how well the person understands self and surroundings (awareness).

lumbar puncture (LP): A procedure in which a needle is passed between lower back vertebrae into the CSF space to measure pressure and collect fluid.

magnetic resonance imaging (MRI): An imaging test that uses a strong magnetic field and radio waves to make detailed images of soft tissues such as the brain and spinal cord.

neuron: A nerve cell that receives, processes and sends signals; it has a cell body, dendrites and an axon.

osmotherapy: The use of a concentrated solution, such as mannitol or hypertonic saline, to draw water out of brain tissue and lower intracranial pressure.

post-ictal state: The recovery period after a seizure, when the person may be drowsy or confused.

post–dural puncture headache: A headache that starts in the 5 days after a lumbar puncture, caused by CSF leaking through the puncture, often worse upright and better lying down.

primary brain tumour: A tumour that starts in the brain or its coverings, as opposed to one that spreads to the brain from elsewhere.

pronator drift: A sign of subtle arm weakness in which one outstretched arm, held palm up with the eyes closed, turns palm-down and drifts downward.

provoked seizure: A seizure caused by a temporary problem, such as a concussion, a fever or alcohol withdrawal, acting on an otherwise normal brain.

pupillary response: The size, shape and reaction to light of the pupils; a new unequal or sluggish pupil is an urgent cue.

seizure: A short-lived event of signs or symptoms caused by abnormal, excessive or synchronized electrical activity of neurons in the brain.

seizure precautions: Safety measures set by employer policy for patients at risk of seizures.

status epilepticus: A seizure that lasts too long, or repeated seizures without recovery between them; for a convulsive seizure, treatment starts at 5 minutes.

thunderclap headache: A severe headache that reaches its peak almost at once; it needs emergency assessment.

tonic-clonic seizure: A seizure with a stiffening phase followed by rhythmic jerking of the limbs.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Margaret Okafor (Questions 1–4): Margaret Okafor, 58, has a known left frontal brain tumour and is on a neurosurgery unit in Ontario awaiting surgery. She is on hourly neurologic checks, which were unchanged all morning. At 1000 her GCS was 15 (E4V5M6), her pupils were 3 mm, round and brisk, and both arms were strong with no drift. At 1100 the RPN assigned to her finds that she opens her eyes only when spoken to, knows her name but says it is 2019 and that she is "at the bank", and still squeezes and releases on request. When she holds her arms out with palms up and eyes closed, her right forearm turns palm-down and drifts. Vital signs are unchanged from 1000.

1. [CORE] Which action should the RPN take next to complete the assessment of Ms. Okafor?

a. Ask Ms. Okafor to rest for half an hour and then repeat the Glasgow Coma Scale to see whether the change persists.

b. Check the size, shape and light reaction of both pupils and compare strength and sensation on both sides of her body.

c. Apply a firm sternal rub to see whether Ms. Okafor can localize the stimulus before scoring her motor response.

d. Review the medication record to find a sedating drug given this morning that could explain why she has become drowsy and confused.

Answer: b — A new change in level of consciousness with a new focal sign calls for a complete, focused check, including pupils and side-to-side motor and sensory comparison (section 30.2, Pupils, Movement and Sensation). Option a delays action; a decline with a focal sign is not left for 30 minutes. Option c uses a stimulus the GCS authors strongly discourage, and she already obeys commands, so her motor score is 6. Option d assumes a drug cause; a new one-sided sign points to a structural problem and is reported first.

2. [CORE] Which statement by the RPN best compares Ms. Okafor's 1100 findings with her baseline?

a. "Her GCS fell from 15 to 13: her eyes now open only to voice, she is confused, her motor score is unchanged, and her right arm newly drifts."

b. "Her GCS is 13, which is within the expected range for a person with a known brain tumour, and her vital signs have not changed at all since 1000."

c. "Her GCS has dropped by two points since 1000, which is too small a change to report until it has fallen by at least three points."

d. "Her GCS has fallen from 15 to 13 because her motor score has dropped, and the new weakness in her right arm accounts for the lower total this morning."

Answer: a — The nurse reports each component and the direction of change, not only the total (E3V4M6 = 13 compared with E4V5M6 = 15), plus the new focal sign (section 30.2, Level of Consciousness and the Glasgow Coma Scale; Recognizing and Reporting Change). Option b is wrong; there is no "normal" GCS for a diagnosis, and a decline from baseline matters. Option c is wrong because the GCS authors give no fixed point threshold for reporting. Option d misreads the scores; her motor score is still 6, since she obeys a two-part command.

3. [CORE] The RPN calls the RN and the neurosurgery resident. Which statement is the best recommendation in the RPN's SBAR report?

a. "I am going to keep checking her every hour as ordered, and I will let you know at the end of my shift if anything else about her changes."

b. "I think she is just tired from not sleeping well last night, so I would like an order for something to help her sleep tonight."

c. "I am concerned her tumour is causing a new deficit. Please come and assess her now; do you want neurologic checks every 15 minutes and a CT?"

d. "Could you review her chart sometime when you have a moment today? Her daughter mentioned that she seemed a little more forgetful than usual this morning."

Answer: c — The recommendation names the concern and asks for prompt bedside assessment and clear orders, such as more frequent checks and imaging (section 30.2, Recognizing and Reporting Change; Chapter 6). Option a delays escalation. Option b attributes a focal sign to fatigue and requests a sedative, which could mask further decline. Option d understates an urgent change and gives no clear request or timeline.

4. [CORE] Which entry best documents the RPN's 1100 assessment of Ms. Okafor?

a. "1100: Patient more lethargic and confused than earlier. GCS 13. Will continue to monitor. Resident aware."

b. "1100: Neuro status changed. Patient appears drowsy. Right arm weak. Pupils fine. Will reassess at 1200 as ordered."

c. "1100: GCS 13. Pupils equal and reactive. Patient confused and drowsy. Pronator drift noted on testing. MD to be called if she gets any worse; will reassess at 1200."

d. "1100: Eyes open to voice (E3), confused, gives year as 2019 (V4), obeys commands (M6), GCS 13; pupils 3 mm, round, brisk; right pronator drift, new. RN and neurosurgery resident informed 1105; resident to assess."

Answer: d — The record states the time, each GCS component in words and numbers, pupil size and reaction, the side and type of motor change, who was told and when, and the plan (section 30.2, Recognizing and Reporting Change). Options a and b use vague words such as "lethargic", "drowsy" and "fine" and give no components or side. Option c omits the side of the drift and the components, and it delays reporting a change that is already significant.

5. [CORE] A patient has a tumour in the right parietal and frontal region of the brain. Where would the nurse most expect to find new weakness?

a. In the right arm and right leg, because each hemisphere controls the same side of the body.

b. In the left arm and left leg, because pathways cross so each hemisphere controls the opposite side.

c. In both legs equally, because the frontal lobe controls movement of the lower body on both sides at once.

d. In the face only, because tumours in the frontal region affect the cranial nerves before the limbs.

Answer: b — Pathways between the brain and body cross over, so a right hemisphere lesion can weaken the left arm and leg (section 30.1, Cells, Brain and Spinal Cord). Option a reverses the crossing. Option c is wrong; each motor cortex mainly controls the opposite side, not both legs. Option d is wrong; frontal lesions commonly cause limb weakness, and there is no rule that the face is affected first.

6. [CORE] A patient with a brain injury is breathing slowly and shallowly, and the arterial partial pressure of carbon dioxide is rising. How does this affect blood flow to the brain?

a. Cerebral vessels narrow, so blood flow to the brain falls and the brain becomes ischemic.

b. Cerebral vessels are not affected by carbon dioxide, only by changes in blood pressure.

c. Cerebral vessels widen, so blood flow and blood volume inside the skull increase.

d. Cerebral vessels widen at first, then narrow again within minutes as autoregulation corrects them.

Answer: c — A rise in $PaCO_2$ widens cerebral vessels and increases blood flow, adding volume inside the closed skull (section 30.1, Blood Flow, Cerebrospinal Fluid and the Skull; section 30.4). Option a describes the effect of a fall in $PaCO_2$. Option b is wrong; carbon dioxide is a strong regulator of cerebral blood flow. Option d is not described by the source; autoregulation responds to blood pressure changes, not by reversing the carbon dioxide effect.

7. [CORE] A patient on a medical unit was intubated an hour ago for respiratory failure. The patient opens the eyes to voice and obeys commands. How should the nurse record the GCS?

a. E3 V1 M6, total 10

b. E3 VNT M6, total 13 out of 15

c. E3 V5 M6, total 14, assuming the patient is oriented

d. E3 VNT M6, with no total reported

Answer: d — When a breathing tube prevents speech, the verbal component is recorded as not testable (NT), not 1, and a total is not reported because it could mislead the team (section 30.2, Level of Consciousness and the Glasgow Coma Scale). Option a gives a falsely low score. Option b adds a total that cannot be calculated. Option c guesses a score that was not observed.

8. [CORE] A patient does not open the eyes when spoken to in a normal or loud voice. Which physical stimulus should the nurse use first?

a. Fingertip pressure on the nail bed

b. A knuckle rub on the sternum

c. Firm pressure at the angle of the jaw

d. A pinch on the inner thigh

Answer: a — The structured approach uses fingertip pressure first, and trapezius or supraorbital pressure when a central stimulus is needed (section 30.2, Level of Consciousness and the Glasgow Coma Scale). Option b is strongly discouraged because it bruises and gives hard-to-read responses. Option c is not recommended for routine use. Option d is not part of the standard method.

9. [CORE] At 0200, the nurse finds that a patient's right pupil is 5 mm and sluggish, while the left is 3 mm and brisk. At 0100 both pupils were 3 mm and brisk. The patient is harder to rouse. What should the nurse do first?

a. Document the finding and recheck both pupils at the next scheduled check in one hour.

b. Ask the patient whether they use any eye drops and wait for the answer before acting.

c. Stay with the patient and escalate at once to the most responsible provider or rapid response team.

d. Dim the lights further and repeat the pupil check several times to make sure the finding is accurate.

Answer: c — A new unequal, sluggish pupil with a falling level of consciousness can signal herniation and needs immediate escalation (section 30.2, Pupils, Movement and Sensation; section 30.4). Option a delays action for an hour. Option b is reasonable background, but it does not come before getting help for a patient who is harder to rouse. Option d repeats checks instead of acting; confirming a finding must not delay reporting it.

10. [CORE] A patient with a new left temporal lesion answers "yes" to every question, speaks fluently in sentences that make little sense and cannot follow simple requests. The patient's face and limbs move normally. Which interpretation by the nurse is most accurate?

a. The patient has dysarthria from weakness of the muscles that are used for both speaking and swallowing.

b. The patient has aphasia, a language problem that can make the verbal score look like confusion.

c. The patient has delirium, so a full neurologic check is not needed until the delirium resolves.

d. The patient is hard of hearing, so the nurse should raise their voice, face the patient and repeat each of the questions.

Answer: b — Fluent speech with little meaning and poor understanding, after damage to a language area, fits aphasia, which affects the verbal score and is recorded as a factor (section 30.2, Speech, Orientation and Cranial Nerve Screening). Option a is wrong; dysarthria causes slurred speech with intact language, and the patient's face moves normally. Option c is wrong; a new focal lesion is not assumed to be delirium, and checks continue. Option d mislabels a language problem as a hearing problem.

11. [CORE] Which factors can interfere with an accurate Glasgow Coma Scale assessment? Select all that apply.

a. Hearing loss without hearing aids in place

b. Sedating medication given in the past hour

c. An endotracheal tube

d. Severe swelling of both eyelids

e. A language different from the nurse's, with no interpreter

f. A blood pressure of 142/88 mm Hg

g. Age over 75 years

Answer: a, b, c, d, e — The GCS authors list pre-existing factors (language differences, hearing loss, prior deficits), current treatment (sedation, intubation) and injuries, such as eyelid swelling, as factors that can prevent a valid rating (section 30.2, Level of Consciousness and the Glasgow Coma Scale). A blood pressure of 142/88 mm Hg (f) does not itself prevent a rating. Age (g) is not an interfering factor; the nurse compares the older adult with their own baseline.

12. [CORE] An RPN on a medical unit is caring for a patient on neurologic checks every 2 hours. The patient's GCS has fallen from 14 to 11, and the right arm now drifts. What should the RPN do?

a. Notify the RN and wait for the RN to repeat the assessment before anyone calls the physician.

b. Recheck the patient in 2 hours as ordered, because an RPN cannot report changes in a patient's condition directly to a physician.

c. Stay with the patient, call the rapid response team or physician per policy, and inform the RN at the same time.

d. Ask a colleague to repeat the GCS in an hour and report only if both nurses agree that the score has changed.

Answer: c — Every nurse who notices deterioration acts at once and escalates; the RPN involves the RN but does not wait for a reassessment before calling for help (section 30.2, Recognizing and Reporting Change; section 1.3; Chapter 6). Options a and d delay escalation. Option b is wrong; the RPN can and must report a deteriorating patient directly according to employer policy.

13. [CORE] An RPN is assigned a patient whose care began with neurologic checks every 4 hours. Overnight the patient's condition becomes less predictable and checks are increased to every 15 minutes. Which action best reflects CNO's Scope of Practice standard?

a. The RPN keeps the patient because performing neurologic checks is within the RPN's authority in every situation.

b. The RPN transfers the patient's care to an RN, because CNO rules state that RPNs may care only for patients who are stable and predictable.

c. The RPN considers authority, competence and context, consults the RN, and follows employer policy about who should be assigned.

d. The RPN continues care without consulting anyone, because the frequency of checks does not affect the nursing role.

Answer: c — CNO's standard asks nurses to consider authority, competence and context, and the RPN consults the RN as the patient's needs change; employer policy also matters (section 1.3; section 30.2). Option a ignores competence and context. Option b presents a common employer practice as a CNO rule, which it is not. Option d ignores the change in context and the duty to consult.

14. [CORE] A 79-year-old patient was alert and oriented on admission. Today the patient is restless, says it is night when it is noon, and pulls at the intravenous line. The left arm drifts downward when held out. Which interpretation should guide the nurse's action?

a. The restlessness and disorientation are typical of delirium, so the nurse can address sleep and hydration first.

b. Disorientation is common in older adults in hospital, so the findings can be reported at the next routine round.

c. The arm drift is likely due to the IV line, so the nurse should check the line and reassess later in the shift.

d. The new one-sided arm drift points to a structural brain problem, so the nurse escalates urgently.

Answer: d — A new focal sign, such as one-sided drift, points to a structural cause and is an emergency, even if delirium is also present (section 30.2, Recognizing and Reporting Change; Chapter 8). Option a addresses delirium but misses the focal sign. Option b treats a new change as expected and delays reporting. Option c blames the intravenous line and delays assessment of a serious sign.

15. [CORE] A patient scheduled for an MRI of the brain says, "I have a pacemaker, but my cardiologist said it is MRI-safe." What should the nurse do?

a. Record that the patient has an MRI-safe pacemaker and send the patient for the scan as scheduled.

b. Record the device's make and model, find the device card or notes, and alert the MRI team before the scan.

c. Cancel the MRI, because no patient with a pacemaker can ever have an MRI scan.

d. Ask the patient to sign a waiver accepting the risk, and then send the patient for the scan.

Answer: b — Implants are identified by type, make and model with written documentation, and an MR Conditional device is safe only under the maker's conditions, which the MRI team must confirm (section 30.3, Clinical Safety box). Option a accepts a verbal report without checking the device. Option c is wrong; some pacemakers are MR Conditional. Option d does not replace screening.

16. [CORE] A patient is booked for a routine outpatient EEG tomorrow morning. Which instruction should the nurse give?

a. "Do not eat or drink anything after midnight, and skip all of your morning medicines."

b. "Apply conditioner after washing your hair so the electrodes slide on easily."

c. "Drink a strong coffee before the test so that you stay awake the whole time."

d. "Wash your hair the night before or that morning, and do not use any hair products."

Answer: d — Clean hair without conditioners, creams, sprays or gels helps the electrodes attach (section 30.3, Electroencephalography). Option a is wrong; the patient eats a normal meal to keep blood glucose stable and takes usual medicines unless told otherwise. Option b adds a product that interferes with the electrodes. Option c is wrong; caffeine is avoided on the day of the test.

17. [CORE] A patient had a lumbar puncture yesterday. Today the patient reports a headache that is worse when sitting up and eases when lying down, with mild neck stiffness. The patient has no fever. Which explanation by the nurse is most accurate?

a. "This sounds like a headache from a small CSF leak at the puncture site. It usually settles, and I will let your team know."

b. "This headache means the test has caused meningitis, so you will need antibiotics and another lumbar puncture."

c. "This is a migraine, which is common after any procedure, so you should take a migraine tablet and rest."

d. "This headache is a warning sign of bleeding inside your skull, so you will need an emergency CT scan of your head right away."

Answer: a — A headache that starts in the 5 days after a lumbar puncture and is worse upright and better lying down, often with neck stiffness, fits post–dural puncture headache from a CSF leak; it usually resolves, and the team is informed (section 30.3, Lumbar Puncture). Option b is not supported; there is no fever, and the pattern is positional. Option c mislabels the cause. Option d overstates the risk; the positional pattern after a puncture points to a leak, although a headache with fever or new neurologic signs would be escalated.

18. [RN] An RN assesses a patient. The patient's eyes open only to fingertip pressure. The patient says single words such as "stop" and "no" but no sentences. With a trapezius pinch, the patient's right hand moves up to the shoulder and pushes the nurse's hand away. How should the RN record the GCS?

a. E2 V3 M5, GCS 10

b. E3 V3 M5, GCS 11

c. E2 V2 M4, GCS 8

d. E2 V4 M6, GCS 12

Answer: a — Eyes opening to pressure score 2, single understandable words score 3, and moving a hand above the collarbone toward a stimulus at the head or neck is localising, which scores 5 (section 30.2, Table 30.1). Option b scores eye opening as "to sound". Option c treats words as sounds and localising as normal flexion. Option d treats single words as confused speech and localising as obeying commands.

19. [RN] During a neurologic check, an RN applies a trapezius pinch to a patient who does not respond to voice. Both arms bend slowly at the elbows and lie across the chest, the forearms rotate, the thumbs clench and the legs extend. Fifteen minutes ago, the patient withdrew the arm quickly away from the body. What does this change indicate?

a. An improvement, from normal flexion to localising, showing the patient is becoming more aware.

b. A change from normal flexion to abnormal flexion, a sign of serious brain dysfunction that needs immediate escalation.

c. A change from abnormal extension to abnormal flexion, which is an expected pattern as the effects of sedating medicines gradually wear off.

d. A seizure, so the RN should time the movements and wait for them to stop before reporting.

Answer: b — Slow, stereotyped flexion with the arm across the chest, forearm rotation, thumb clenching and leg extension is abnormal flexion (M3); the earlier quick withdrawal was normal flexion (M4), so the motor response has fallen, which needs urgent escalation (section 30.2, Pupils, Movement and Sensation). Option a is wrong; localising means reaching toward the stimulus. Option c misreads the earlier response. Option d confuses posturing provoked by a stimulus with a seizure and delays action.

20. [RN] Four adults with suspected bacterial meningitis are waiting for a lumbar puncture in the emergency department. For which patient should the RN expect a head CT before the lumbar puncture?

a. A 32-year-old patient with fever, headache and neck stiffness who is alert, oriented and has a normal neurologic exam.

b. A 45-year-old patient with fever and headache who has a history of migraine and a normal neurologic exam.

c. A 28-year-old patient with fever, rash and headache whose only medicine is an oral contraceptive.

d. A 51-year-old patient with fever, headache, a reduced level of consciousness and new left arm drift.

Answer: d — The IDSA features that call for a CT before lumbar puncture include an abnormal level of consciousness and abnormal neurologic findings such as arm drift, which may signal a mass or raised pressure; blood cultures and antibiotics are not delayed for the CT (section 30.3, Lumbar Puncture; section 30.6). Options a, b and c describe patients under 60 with no criteria; migraine and oral contraceptives are not on the list.

Case: Marc Belanger (Questions 21–26): Marc Belanger, 46, has had epilepsy since age 20 and takes levetiracetam twice daily. He was admitted to a medical unit 2 days ago with pneumonia. He vomited his last two doses of levetiracetam. At 14:10 the nurse finds him having a generalized tonic-clonic seizure. At 14:16 he is still seizing. SpO_2 is 88% on room air, heart rate 128, temperature 38.1 °C, and capillary blood glucose 5.6 mmol/L. He has a working IV, and his orders include intravenous lorazepam per the unit's seizure protocol.

21. [CORE] Which findings should the nurse recognize as cues that need immediate attention? Select all that apply.

a. The seizure has lasted more than 5 minutes

b. SpO_2 of 88% on room air

c. Capillary blood glucose of 5.6 mmol/L

d. Two vomited doses of levetiracetam

e. A history of epilepsy since age 20

f. A working IV line

Answer: a, b, d — A convulsive seizure lasting longer than 5 minutes meets the ILAE time point for status epilepticus and needs treatment now (a; section 30.5). An SpO_2 of 88% shows that oxygenation is falling during the seizure (b). Missed antiseizure doses can increase seizures and are a likely trigger to report (d). A glucose of 5.6 mmol/L is not low, so it does not explain the seizure (c). A long history of epilepsy is background information, not an immediate cue (e). The working IV is useful for treatment but is not a problem that needs attention (f).

22. [CORE] Why is the time of 14:16 important in Mr. Belanger's care?

a. Seizures that last 6 minutes usually stop by themselves within the next few minutes, so the nurse can keep watching for now.

b. After 5 minutes, a convulsive seizure is unlikely to stop on its own and is treated as status epilepticus.

c. After 5 minutes, the risk of permanent brain harm is already established, so treatment will no longer change the outcome.

d. The time matters mainly for documentation, because the seizure protocol starts only after 30 minutes of seizure activity.

Answer: b — The ILAE treats a convulsive seizure lasting 5 minutes as continuous seizure activity that needs treatment, and the AES guideline starts initial therapy at 5 minutes (b; section 30.5). Waiting for the seizure to stop is unsafe after 5 minutes (a). The 30-minute time point, not the 5-minute one, marks the risk of long-term harm, and treatment is urgent precisely because it can prevent harm (c). Treatment begins at 5 minutes, not 30 (d).

23. [RN] Which hypothesis should the nurse treat as the priority?

a. Convulsive status epilepticus with low oxygen, possibly triggered by missed levetiracetam doses and fever

b. Hypoglycemia causing a prolonged seizure that will stop as soon as intravenous dextrose is given by the nurse

c. A non-epileptic event related to anxiety about his pneumonia, his fever and the long hospital stay

d. Alcohol withdrawal seizures that need a withdrawal protocol started before any other treatment is given

Answer: a — The seizure has lasted more than 5 minutes with an SpO_2 of 88%, and he missed two doses of his antiseizure medicine while febrile, so convulsive status epilepticus with hypoxemia is the priority (a; section 30.5). His glucose is 5.6 mmol/L, so hypoglycemia is not the cause (b). Calling the event non-epileptic could delay life-saving treatment (c). Nothing in the case suggests alcohol use, and withdrawal is managed as described in Chapter 11 (d).

24. [CORE] Which action should the nurse take first at 14:16?

a. Place a padded tongue blade between his teeth to protect his tongue and keep his airway open.

b. Hold his arms and legs firmly to prevent injury until the seizure team arrives at the bedside.

c. Leave the room to get the seizure protocol binder and check the lorazepam order before calling anyone.

d. Call for help at once, turn him to his side when it is safe and give oxygen per policy.

Answer: d — The nurse stays with the patient, activates help, protects the airway by positioning him on his side and gives oxygen as policy directs while the benzodiazepine is prepared (d; section 30.5). Nothing is ever placed in the mouth (a), and the person is never restrained (b). Leaving the patient alone during status epilepticus delays help and is unsafe (c).

25. [CORE] Lorazepam is given at 14:18. At 14:28 Mr. Belanger is still seizing. What should the nurse expect next?

a. The team will wait until 14:40 before giving any more medicine, because lorazepam needs about 20 minutes to work.

b. The nurse will give a second dose of levetiracetam by mouth once the jerking slows enough for him to swallow.

c. The team will give a repeat benzodiazepine dose or a second-line intravenous medicine as the protocol directs.

d. The nurse will stop all medicines and wait for an EEG to confirm the diagnosis before treatment continues.

Answer: c — Guidance supports a second benzodiazepine dose when a seizure continues 5 to 10 minutes after the first, and the AES guideline moves to a second-line intravenous medicine, such as levetiracetam, fosphenytoin or valproic acid, from 20 minutes (c; section 30.5). Waiting longer delays treatment (a). Nothing is given by mouth during a seizure (b). Treatment does not wait for an EEG (d).

26. [CORE] At 14:45 the seizure has stopped. Which finding best shows that care is working?

a. He is breathing regularly, SpO_2 is 95% with oxygen, and he opens his eyes to his name, though he is still confused.

b. He is breathing regularly but does not respond to voice or pressure, and his eyes stay closed 30 minutes later.

c. He has no jerking, but his left arm and leg are newly weak, and his speech is slurred compared with this morning.

d. He is sleeping on his back, SpO_2 is 90% on oxygen, and his breathing is noisy with gurgling sounds.

Answer: a — Regular breathing, a safe SpO_2 and early return of response, with expected post-ictal confusion, show that the plan is working (a; section 30.5). Not responding 30 minutes later is not expected recovery and needs prompt reassessment (b). New one-sided weakness and slurred speech need urgent assessment for another cause (c). Lying on his back with noisy breathing and a low SpO_2 suggests airway compromise; he should be on his side (d).

27. [CORE] A patient is on day 1 after a craniotomy. Which finding is most likely an early sign of rising intracranial pressure?

a. A blood pressure of 176/70 mm Hg with a heart rate of 48 and irregular breathing

b. A fixed, dilated right pupil with no response to light on either side

c. New restlessness and slower answers to questions compared with 2 hours earlier

d. Abnormal extension of both arms and legs in response to pressure on a nail bed

Answer: c — A subtle change in level of consciousness, such as restlessness or slower answers, is often the first sign of rising ICP (c; section 30.4, Table 30.3). High blood pressure with a slow heart rate and irregular breathing (Cushing triad) is a late sign (a). A fixed, dilated pupil is a late sign (b). Abnormal extension posturing is a late sign (d).

28. [CORE] A patient with a brain tumour has a blood pressure of 184/72 mm Hg (previously 136/78), a heart rate of 46 (previously 82) and irregular breathing. What should the nurse do?

a. Recheck the vital signs in 1 hour and report them at the next scheduled update to the physician.

b. Give the as-needed antihypertensive and recheck the blood pressure in 30 minutes before calling anyone.

c. Lower the head of the bed flat to improve blood flow to the brain and recheck the heart rate.

d. Call for immediate help, stay with the patient and support the airway, because these are late signs of raised pressure.

Answer: d — High blood pressure, a slow heart rate and irregular breathing form the Cushing triad, a late sign of raised ICP and possible herniation; the nurse calls for immediate help and stays with the patient (d; section 30.4). Waiting an hour is unsafe (a). Treating the blood pressure alone misses the emergency and could lower cerebral perfusion (b). Lying flat can impair venous drainage from the head (c).

29. [CORE] Which position best supports a patient at risk of increased intracranial pressure, unless the orders say otherwise?

a. Head of bed raised above 30°, with the head in the midline and the neck not bent or turned

b. Head of bed flat, with a pillow under the shoulders to extend the neck and open the airway

c. Head of bed raised to 15°, with the head turned toward the window to keep the patient calm

d. Head of bed flat, with the knees and hips sharply bent to reduce pressure in the abdomen

Answer: a — The Neurocritical Care Society advises raising the head of the bed above 30° with the head midline to help venous drainage (a; section 30.4). Lying flat with the neck extended can impair venous drainage (b). Turning the head can compress the veins of the neck (c). Lying flat with sharp hip flexion can raise abdominal and chest pressure and does not help venous drainage (d).

30. [CORE] During a generalized tonic-clonic seizure, which action is correct?

a. Hold the patient's shoulders down firmly so that the jerking movements stop sooner.

b. Note the start time, cushion the head and turn the patient onto the side as the jerking eases.

c. Insert an oral airway between the teeth as soon as the seizure begins to protect the tongue.

d. Give the patient a sip of water once the jerking slows so that the throat does not become dry.

Answer: b — Epilepsy Ontario advises timing the seizure, cushioning the head and rolling the person onto the side as the seizure eases (b; section 30.5). Restraint can cause injury and does not stop a seizure (a). Nothing is placed in the mouth during a seizure (c). Nothing is given by mouth until the patient is fully awake and can swallow safely (d).

31. [CORE] A patient with epilepsy says, "My seizures have been gone for a year, so I'm going to stop my medicine this week." What is the nurse's best response?

a. "That sounds reasonable after a full year without seizures, so you can stop it this week."

b. "Stopping suddenly can bring on seizures, so any change needs to be planned with your prescriber."

c. "You can stop it if you take half the dose this week and none at all after that."

d. "You should stop it only if your next blood test shows a low level of the medicine."

Answer: b — The phenytoin monograph warns that stopping an antiseizure medicine suddenly can increase seizures, including status epilepticus, and that changes should be gradual and directed by the prescriber (b; section 30.5). Stopping on one's own is unsafe (a). A self-made taper is still not directed by the prescriber (c). A drug level does not decide whether to stop treatment (d).

32. [CORE] A patient taking phenytoin has new unsteadiness, slurred speech and jerking eye movements when looking to the side. What should the nurse do?

a. Encourage the patient to walk more often to improve balance before the next dose.

b. Give the next dose early to prevent a seizure, because these signs suggest a low level.

c. Hold the next dose until the patient's symptoms improve and document the findings.

d. Report the findings to the prescriber, because they are signs of phenytoin toxicity.

Answer: d — The monograph lists nystagmus, unsteadiness and slurred speech as early signs of phenytoin toxicity, so the nurse reports them promptly and expects a serum level (d; section 30.5, Table 30.4). Walking more increases the risk of falls (a). These are signs of a high level, not a low one (b). The nurse does not decide alone to hold or change an antiseizure dose; the prescriber decides (c).

33. [CORE] In Ontario, a patient has a first seizure and asks the nurse whether he can drive home from the hospital. Which statement is accurate?

a. "Physicians and nurse practitioners must report certain conditions, so do not drive until you are told it is safe."

b. "Only the police can report a seizure to the Ministry of Transportation, so you may drive until the ministry contacts you."

c. "Reporting is optional in Ontario, so your licence is not affected unless you decide to tell the ministry yourself."

d. "You can drive as long as you feel well, because a single seizure does not count as a reportable medical condition."

Answer: a — Ontario's Highway Traffic Act requires physicians and nurse practitioners to report high-risk medical conditions, and the ministry reviews seizure reports against national standards; the nurse teaches the patient not to drive until cleared (a; section 30.5). Physicians, nurse practitioners and others report; reporting is not left to police (b). Reporting is mandatory for these clinicians (c). A seizure is a form of sudden incapacitation, the main concern the ministry names, so feeling well does not make driving safe (d).

34. [CORE] Which headache features should the nurse report as red flags? Select all that apply.

a. A sudden, severe headache that reached its peak within moments

b. A new headache in a 72-year-old with no previous headaches

c. A headache with a temperature of 38.9 °C and a stiff neck

d. A familiar migraine pattern that the patient has had for 15 years

e. A headache in a patient receiving treatment for lung cancer

f. A headache that eases with the patient's usual acetaminophen dose

Answer: a, b, c, e — The SNNOOP10 list includes sudden onset (a), onset after age 65 (b), systemic symptoms such as fever (c) and a history of cancer (e) (section 30.6). A long-standing, unchanged migraine pattern is not a red flag on its own (d). A headache that responds to usual treatment is not a red flag, although new painkiller overuse would be (f).

35. [CORE] A patient admitted with suspected meningococcal meningitis started antibiotics 6 hours ago. Which precautions should the nurse use?

a. Airborne precautions in a negative-pressure room until the patient's CSF culture becomes negative

b. Droplet precautions until 24 hours after antibiotics started, in addition to routine practices

c. Contact precautions only, because the infection spreads mainly through contaminated surfaces

d. Routine practices only, because antibiotics have already started and the patient is no longer contagious

Answer: b — Ontario public health guidance calls for droplet precautions for a hospitalized patient with invasive meningococcal disease until 24 hours of antibiotics have been given (b; section 30.6). The organism spreads by respiratory droplets and throat secretions, not by the airborne route (a) and not mainly by surfaces (c). Six hours of antibiotics is not enough to stop precautions (d).

36. [CORE] A patient with fever and confusion has dark skin. The nurse suspects meningococcal disease. Where should the nurse look most closely for a petechial rash?

a. On the back and the buttocks, where pressure makes petechiae easiest to see on any skin tone

b. On the forehead and the cheeks, where the rash of meningitis always begins first

c. On the palms, the soles and the inside of the eyelids, where the skin is paler

d. On the chest only, because a petechial rash does not appear on the hands or the feet

Answer: c — PHAC notes that the rash is harder to see on darker skin and advises checking paler areas such as the palms, soles and inside of the eyelids, as well as the palate (c; section 30.6). Pressure areas are not where the rash is most visible (a). The rash does not always start on the face (b). Petechiae can appear on the hands and feet (d).

37. [CORE] An RPN on a neurosurgery unit notices that a patient's right pupil is now larger and slower than the left. One hour ago the pupils were equal and brisk. What should the RPN do?

a. Document the finding and recheck the pupils at the next scheduled neurologic check in 1 hour.

b. Ask the patient whether the light is bothering the eyes, and dim the room before rechecking.

c. Notify the RN and the physician immediately, stay with the patient and repeat the neurologic check.

d. Wait to report the finding until the GCS score has also dropped, so the report will be complete.

Answer: c — A new unequal or sluggish pupil is an urgent cue; every nurse acts at once and escalates, and the RPN informs the RN and the physician immediately (c; section 30.6, Scope in Practice box). Waiting an hour could allow herniation to progress (a). Dimming the room delays escalation (b). The nurse does not wait for other signs before reporting (d).

38. [CORE] An RPN is asked to take over the care of a patient with an external ventricular drain. The RPN has never been taught EVD care, and the unit's policy limits EVD care to RNs with neurosurgical education. What should the RPN do?

a. Accept the assignment and learn EVD care by watching the RN level the drain at the start of the shift.

b. Accept the assignment but clamp the drain for the whole shift so that it does not need adjusting.

c. Accept the assignment and ask the patient's family to report any change in the drain's fluid.

d. Explain the limit to the charge nurse so that an educated RN manages the EVD, and ask how to help.

Answer: d — The RPN lacks the competence, and the employer's policy (context) does not support the activity, so the RPN declines EVD care and works with the charge nurse to arrange an educated RN (d; section 30.6, Scope in Practice box). Watching once does not provide competence (a). Clamping a drain without an order can let ICP rise dangerously (b). Families cannot take on nursing monitoring (c).

39. [RN] A patient with a severe brain injury has a mean arterial pressure of 78 mm Hg and an intracranial pressure of 24 mm Hg. Which interpretation is correct?

a. The CPP is 102 mm Hg, which is above the target range and calls for lowering the blood pressure.

b. The CPP is 54 mm Hg, which is below the 60 to 70 mm Hg target and should be reported at once.

c. The CPP is 54 mm Hg, which is within the expected range for a patient with a brain injury.

d. The CPP cannot be calculated without the systolic blood pressure and the heart rate.

Answer: b — CPP equals MAP minus ICP: 78 − 24 = 54 mm Hg, which is below the Neurocritical Care Society target of 60 to 70 mm Hg, and the ICP is also above 22 mm Hg; both need prompt reporting (b; section 30.4, Going Deeper box). Adding the values gives the wrong answer (a). A CPP of 54 mm Hg is below target (c). The calculation uses MAP and ICP only (d).

40. [RN] A patient is receiving hypertonic saline per protocol to lower intracranial pressure. Which monitoring is the priority?

a. Serum sodium checked at the intervals the protocol sets, with results outside the set limit reported

b. Serum potassium checked once daily, because hypertonic saline mainly lowers the potassium level

c. Blood glucose checked every hour, because hypertonic saline causes severe hyperglycemia

d. Hemoglobin checked every 4 hours, because hypertonic saline commonly causes bleeding

Answer: a — The Neurocritical Care Society protocol calls for serum sodium checks every 4 to 6 hours during hypertonic saline and sets an upper sodium limit, so the nurse follows the ordered schedule and reports results outside the limit (a; section 30.4, Table 30.4). Potassium is not the main concern with hypertonic saline (b). Hypertonic saline does not cause severe hyperglycemia (c). Bleeding is not a common effect that needs this monitoring (d).

References

American Speech-Language-Hearing Association. (n.d.). *Dysarthria*. https://www.asha.org/public/speech/disorders/dysarthria/

Beniczky, S., Trinka, E., Wirrell, E., Abdulla, F., Al Baradie, R., Alonso Vanegas, M., Auvin, S., Bhushan Singh, M., Blumenfeld, H., Bogacz Fressola, A., Caraballo, R., Carreno, M., Cendes, F., Charway, A., Cook, M., Craiu, D., Ezeala-Adikaibe, B., Frauscher, B., French, J., . . . Cross, J. H. (2025). Updated classification of epileptic seizures: Position paper of the International League Against Epilepsy. *Epilepsia, 66*(6), 1804–1823. https://doi.org/10.1111/epi.18338

BGP Pharma ULC. (2023). *Dilantin Infatabs; Dilantin-30 and Dilantin-125 suspension (phenytoin) [Product monograph]*. https://pdf.hres.ca/dpd_pm/00071910.PDF

Bhalla, P., Dingman, J. S., & Aysenne, A. (2024). *Emergency Neurological Life Support: Intracranial hypertension and herniation* (Protocol version 6.0). Neurocritical Care Society. https://neurocriticalcare.org/Portals/0/ENLS%205.0/ENLS%206.0/Protocol%20V6_0_Intracranial%20Hypertension%20and%20Herniation.pdf

Brain & Spine Foundation. (2022). *What is a lumbar puncture?* https://www.brainandspine.org.uk/health-information/fact-sheets/lumbar-puncture/

Brain Tumour Foundation of Canada. (2025). *Facts about brain tumours*. https://braintumour.ca/facing-a-brain-tumour/facts-about-brain-tumours

Canadian Cancer Society. (2026). *Brain and spinal cord cancer statistics*. https://www.cancer.ca/en/cancer-information/cancer-type/brain-spinal/statistics

Canadian Council of Motor Transport Administrators. (2021). *National Safety Code Standard 6: Determining driver fitness in Canada*. https://www.gov.nl.ca/motorregistration/files/determining-fitness-to-drive-in-canada.pdf

Carney, N., Totten, A. M., O'Reilly, C., Ullman, J. S., Hawryluk, G. W. J., Bell, M. J., Bratton, S. L., Chesnut, R., Harris, O. A., Kissoon, N., Rubiano, A. M., Shutter, L., Tasker, R. C., Vavilala, M. S., Wilberger, J., Wright, D. W., & Ghajar, J. (2017). Guidelines for the management of severe traumatic brain injury, fourth edition. *Neurosurgery, 80*(1), 6–15. https://doi.org/10.1227/NEU.0000000000001432

Claassen, J. A. H. R., Thijssen, D. H. J., Panerai, R. B., & Faraci, F. M. (2021). Regulation of cerebral blood flow in humans: Physiology and clinical implications of autoregulation. *Physiological Reviews, 101*(4), 1487–1559. https://doi.org/10.1152/physrev.00022.2020

Couret, D., Boumaza, D., Grisotto, C., Triglia, T., Pellegrini, L., Ocquidant, P., Bruder, N. J., & Velly, L. J. (2016). Reliability of standard pupillometry practice in neurocritical care: An observational, double-blinded study. *Critical Care, 20*(1), Article 99. https://doi.org/10.1186/s13054-016-1239-z

Do, T. P., Remmers, A., Schytz, H. W., Schankin, C., Nelson, S. E., Obermann, M., Hansen, J. M., Sinclair, A. J., Gantenbein, A. R., & Schoonman, G. G. (2019). Red and orange flags for secondary headaches in clinical practice: SNNOOP10 list. *Neurology, 92*(3), 134–144. https://doi.org/10.1212/WNL.0000000000006697

Epilepsy Ontario. (2018). *First aid*. https://epilepsyontario.org/?p=4258

Fisher, R. S., Acevedo, C., Arzimanoglou, A., Bogacz, A., Cross, J. H., Elger, C. E., Engel, J., Jr., Forsgren, L., French, J. A., Glynn, M., Hesdorffer, D. C., Lee, B. I., Mathern, G. W., Moshé, S. L., Perucca, E., Scheffer, I. E., Tomson, T., Watanabe, M., & Wiebe, S. (2014). A practical clinical definition of epilepsy. *Epilepsia, 55*(4), 475–482. https://doi.org/10.1111/epi.12550

Fried, H. I., Nathan, B. R., Rowe, A. S., Zabramski, J. M., Andaluz, N., Bhimraj, A., Guanci, M. M., Seder, D. B., & Singh, J. M. (2016). The insertion and management of external ventricular drains: An evidence-based consensus statement. *Neurocritical Care, 24*(1), 61–81. https://doi.org/10.1007/s12028-015-0224-8

Glauser, T., Shinnar, S., Gloss, D., Alldredge, B., Arya, R., Bainbridge, J., Bare, M., Bleck, T., Dodson, W. E., Garrity, L., Jagoda, A., Lowenstein, D., Pellock, J., Riviello, J., Sloan, E., & Treiman, D. M. (2016). Evidence-based guideline: Treatment of convulsive status epilepticus in children and adults: Report of the Guideline Committee of the American Epilepsy Society. *Epilepsy Currents, 16*(1), 48–61. https://doi.org/10.5698/1535-7597-16.1.48

Government of Ontario. (2026). *Reporting a driver for medical review*. https://www.ontario.ca/page/reporting-driver-medical-review

Hawryluk, G. W. J., Aguilera, S., Buki, A., Bulger, E., Citerio, G., Cooper, D. J., Diaz Arrastia, R., Diringer, M., Figaji, A., Gao, G., Geocadin, R., Ghajar, J., Harris, O., Hoffer, A., Hutchinson, P., Joseph, M., Kitagawa, R., Manley, G., Mayer, S., . . . Chesnut, R. M. (2019). A management algorithm for patients with intracranial pressure monitoring: The Seattle International Severe Traumatic Brain Injury Consensus Conference (SIBICC). *Intensive Care Medicine, 45*(12), 1783–1794. https://doi.org/10.1007/s00134-019-05805-9

Headache Classification Committee of the International Headache Society. (2018). The International Classification of Headache Disorders, 3rd edition. *Cephalalgia, 38*(1), 1–211. https://doi.org/10.1177/0333102417738202

Herman, S. T., Abend, N. S., Bleck, T. P., Chapman, K. E., Drislane, F. W., Emerson, R. G., Gerard, E. E., Hahn, C. D., Husain, A. M., Kaplan, P. W., LaRoche, S. M., Nuwer, M. R., Quigg, M., Riviello, J. J., Schmitt, S. E., Simmons, L. A., Tsuchida, T. N., & Hirsch, L. J. (2015). Consensus statement on continuous EEG in critically ill adults and children, part I: Indications. *Journal of Clinical Neurophysiology, 32*(2), 87–95. https://doi.org/10.1097/WNP.0000000000000166

Larsen, P. D., & Stensaas, S. S. (n.d.-a). *Cranial nerve exam: Normal* [Web page]. NeuroLogic Examination Videos and Descriptions: An Anatomical Approach. University of Utah. https://neurologicexam.med.utah.edu/adult/html/cranialnerve_normal.html

Larsen, P. D., & Stensaas, S. S. (n.d.-b). *Motor exam: Normal* [Web page]. NeuroLogic Examination Videos and Descriptions: An Anatomical Approach. University of Utah. https://neurologicexam.med.utah.edu/adult/html/motor_normal.html

Macdonald, D. B., Hurrell, C., Costa, A. F., McInnes, M. D. F., O'Malley, M. E., Barrett, B., Brown, P. A., Clark, E. G., Hadjivassiliou, A., Kirkpatrick, I. D. C., Rempel, J. L., Jeon, P. M., & Hiremath, S. (2022). Canadian Association of Radiologists guidance on contrast associated acute kidney injury. *Canadian Association of Radiologists Journal, 73*(3), 499–514. https://doi.org/10.1177/08465371221083970

Medical Research Council. (1976). *Aids to the examination of the peripheral nervous system* (Memorandum No. 45). Her Majesty's Stationery Office. https://www.ukri.org/publications/aids-to-the-examination-of-the-peripheral-nervous-system/

Mhatre, P. (n.d.). *Basics of MRI patient screening*. Image Wisely. https://imagewisely.org/Imaging-Modalities/Magnetic-Resonance/Basics-of-MRI-Patient-Screening

Ministry of Transportation. (2019). *Drivers with seizures* [Fact sheet]. Government of Ontario. https://files.ontario.ca/mto-fact-sheet-epilepsy-en-2022-03-29.pdf

National Cancer Institute. (n.d.). *Signs & symptoms* [SEER Training Modules: Brain tumors]. https://training.seer.cancer.gov/brain/tumors/symptoms.html

National Institute for Health and Care Excellence. (2022). *Epilepsies in children, young people and adults* (NICE Guideline NG217). https://www.nice.org.uk/guidance/ng217/chapter/7-Treating-status-epilepticus

National Institute of Biomedical Imaging and Bioengineering. (n.d.-a). *Computed tomography (CT)*. https://www.nibib.nih.gov/science-education/science-topics/computed-tomography-ct

National Institute of Biomedical Imaging and Bioengineering. (n.d.-b). *Magnetic resonance imaging (MRI)*. https://www.nibib.nih.gov/science-education/science-topics/magnetic-resonance-imaging-mri

National Institute of Neurological Disorders and Stroke. (n.d.-a). *Brain basics: Know your brain*. https://www.ninds.nih.gov/health-information/public-education/brain-basics/brain-basics-know-your-brain

National Institute of Neurological Disorders and Stroke. (n.d.-b). *Dysautonomia*. https://www.ninds.nih.gov/health-information/disorders/dysautonomia

National Institute on Deafness and Other Communication Disorders. (n.d.). *Aphasia*. https://www.nidcd.nih.gov/health/aphasia

Ng, M. C. (2024). The challenges of treating status epilepticus in rural Canada. *Epilepsy & Behavior, 158*, Article 109901. https://doi.org/10.1016/j.yebeh.2024.109901

Paszkowycz, H., Olewnik, Ł., Gonera, B., Haładaj, R., & Zielinska, N. (2025). Morphological changes in cerebrospinal fluid production. *Folia Morphologica, 84*(4), 793–807. https://doi.org/10.5603/fm.99964

Public Health Agency of Canada. (2024). *Epilepsy in Canada*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/epilepsy.html

Public Health Agency of Canada. (2026). *Invasive meningococcal disease: For health professionals*. https://www.canada.ca/en/public-health/services/immunization/vaccine-preventable-diseases/invasive-meningococcal-disease/health-professionals.html

Rochwerg, B., Almenawer, S. A., Siemieniuk, R. A. C., Vandvik, P. O., Agoritsas, T., Lytvyn, L., Alhazzani, W., Archambault, P., D'Aragon, F., Darbellay Farhoumand, P., Guyatt, G., Laake, J. H., Beltrán-Arroyave, C., McCredie, V., Price, A., Chabot, C., Zervakis, T., Badhiwala, J., St-Onge, M., … Lamontagne, F. (2018). Atraumatic (pencil-point) versus conventional needles for lumbar puncture: A clinical practice guideline. *BMJ, 361*, Article k1920. https://doi.org/10.1136/bmj.k1920

Royal College of Physicians and Surgeons of Glasgow. (n.d.-a). *GCS FAQ*. Glasgow Coma Scale. https://glasgowcomascale.org/faq/

Royal College of Physicians and Surgeons of Glasgow. (n.d.-b). *Recording the GCS*. Glasgow Coma Scale. https://glasgowcomascale.org/recording-gcs/

Royal College of Physicians and Surgeons of Glasgow. (n.d.-c). *The Glasgow structured approach to assessment of the Glasgow Coma Scale*. Glasgow Coma Scale. https://glasgowcomascale.org/gcs-aid/

Sandoz Canada. (2022). *Lorazepam injection USP [Product monograph]*. https://pdf.hres.ca/dpd_pm/00064249.PDF

Sandoz Canada. (2026). *Dexamethasone sodium phosphate injection USP [Product monograph]*. https://pdf.hres.ca/dpd_pm/00083916.PDF

Taran, S., Gros, P., Gofton, T., Boyd, G., Briard, J. N., Chassé, M., & Singh, J. M. (2023). The reticular activating system: A narrative review of discovery, evolving understanding, and relevance to current formulations of brain death. *Canadian Journal of Anesthesia, 70*(4), 788–795. https://doi.org/10.1007/s12630-023-02421-6

Teasdale, G. (2015). *Glasgow Coma Scale: Do it this way* [Assessment aid]. Institute of Neurological Sciences, NHS Greater Glasgow and Clyde. https://glasgowcomascale.org/downloads/GCS-Assessment-Aid-English.pdf

Teasdale, G., Maas, A., Lecky, F., Manley, G., Stocchetti, N., & Murray, G. (2014). The Glasgow Coma Scale at 40 years: Standing the test of time. *The Lancet Neurology, 13*(8), 844–854. https://doi.org/10.1016/S1474-4422(14)70120-6

Teitelbaum, J. S., Eliasziw, M., & Garner, M. (2002). Tests of motor function in patients suspected of having mild unilateral cerebral lesions. *Canadian Journal of Neurological Sciences, 29*(4), 337–344. https://doi.org/10.1017/S0317167100002201

The Ottawa Hospital. (2021). *Electroencephalography (EEG) information sheet*. https://www.ottawahospital.on.ca/en/documents/2021/02/electroencephalography-information-sheet.pdf

Thunder Bay District Health Unit. (2026). *Meningococcal disease, invasive*. https://www.tbdhu.com/professionals/health-care-providers/infectious-diseases-toolkit/meningococcal-disease-invasive

Trinka, E., Cock, H., Hesdorffer, D., Rossetti, A. O., Scheffer, I. E., Shinnar, S., Shorvon, S., & Lowenstein, D. H. (2015). A definition and classification of status epilepticus: Report of the ILAE Task Force on Classification of Status Epilepticus. *Epilepsia, 56*(10), 1515–1523. https://doi.org/10.1111/epi.13121

Tunkel, A. R., Glaser, C. A., Bloch, K. C., Sejvar, J. J., Marra, C. M., Roos, K. L., Hartman, B. J., Kaplan, S. L., Scheld, W. M., & Whitley, R. J. (2008). The management of encephalitis: Clinical practice guidelines by the Infectious Diseases Society of America. *Clinical Infectious Diseases, 47*(3), 303–327. https://doi.org/10.1086/589747

Tunkel, A. R., Hartman, B. J., Kaplan, S. L., Kaufman, B. A., Roos, K. L., Scheld, W. M., & Whitley, R. J. (2004). Practice guidelines for the management of bacterial meningitis. *Clinical Infectious Diseases, 39*(9), 1267–1284. https://doi.org/10.1086/425368

van de Beek, D., de Gans, J., Spanjaard, L., Weisfelt, M., Reitsma, J. B., & Vermeulen, M. (2004). Clinical features and prognostic factors in adults with bacterial meningitis. *New England Journal of Medicine, 351*(18), 1849–1859. https://doi.org/10.1056/NEJMoa040845

Wilson, M. H. (2016). Monro-Kellie 2.0: The dynamic vascular and venous pathophysiological components of intracranial pressure. *Journal of Cerebral Blood Flow & Metabolism, 36*(8), 1338–1350. https://doi.org/10.1177/0271678X16648711

31 Stroke

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Explain the types of stroke and TIA, the penumbra and why time matters, and describe who is at risk in Canada.
2. Recognize stroke using FAST, rule out common mimics and act on a suspected stroke, including in hospital.
3. Provide nursing care for adults receiving thrombolysis or endovascular thrombectomy as the Canadian Stroke Best Practice Recommendations describe.
4. Care for adults with intracerebral and subarachnoid hemorrhage, recognizing neurologic deterioration.
5. Provide stroke unit care, including dysphagia screening, positioning, communication with aphasia and prevention of complications, using the CJMM.
6. Support secondary prevention, rehabilitation, transitions and caregivers after stroke.
7. Distinguish RN and RPN roles in stroke care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 5	Clinician; Scholar	Foundations of Practice
5, 6	Educator; Collaborator; Advocate	Collaborative Practice; Foundations of Practice
7	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

A stroke can change a life in minutes. A person who was talking at breakfast may, by lunch, be unable to lift an arm, find a word or swallow safely. Stroke is common in Canada, and it is one of the leading causes of death and of lasting disability. Yet much of the harm is not fixed at the moment symptoms start. Brain tissue at risk can still be saved when blood flow returns quickly, and many complications in the days after a stroke can be prevented. Nurses shape both outcomes. They are often the first to notice new signs, in the community and on hospital units, and they deliver much of the care that follows.

This chapter is the book's home for stroke. Section 31.1 explains the types of stroke, why time matters and who has a stroke in Canada. Section 31.2 teaches how to recognize stroke with the FAST signs, how to rule out conditions that look like stroke and how a code stroke unfolds, including a stroke that begins in hospital. Section 31.3 covers hyperacute treatment: clot-dissolving medicine, clot removal and organized stroke unit care. The second half of the chapter covers intracerebral and subarachnoid hemorrhage (31.4), stroke unit nursing care and secondary prevention (31.5), and rehabilitation, transitions and life after stroke (31.6).

Throughout, the chapter follows the Canadian Stroke Best Practice Recommendations (CSBPR) from Heart & Stroke and states each recommendation as the current module gives it. It builds on earlier chapters. Scope of practice for registered nurses (RNs) and registered practical nurses (RPNs) is taught in section 1.3, and the Clinical Judgment Measurement Model (CJMM) in section 1.4. Recognizing deterioration and the SBAR (situation, background, assessment, recommendation) format are in Chapter 6. The neurologic assessment and the Glasgow Coma Scale (GCS) are in section 30.2. In other provinces and territories, practical nurses (PNs) are often called licensed practical nurses (LPNs); this chapter uses "the nurse" unless the roles differ.

31.1 Understanding Stroke

Types of Stroke

A **stroke** is a sudden loss of brain, spinal cord or retinal function caused by a blocked or bleeding blood vessel, with evidence of brain injury on imaging (Heart and Stroke Foundation of Canada, 2022). The cause decides the treatment, so the first question in every suspected stroke is whether the vessel is blocked or bleeding (Figure 31.1).

An **ischemic stroke** happens when a blocked artery starves part of the brain, spinal cord or retina of blood until cells die (Heart and Stroke Foundation of Canada, 2022). Most strokes are ischemic (Heart and Stroke Foundation of Canada, n.d.-d). A widely used research classification, the Trial of Org 10172 in Acute Stroke Treatment (TOAST) classification, sorts ischemic strokes by cause into large-artery atherosclerosis, cardioembolism, small-vessel occlusion, other known causes and unknown causes (Adams et al., 1993). In plain terms, there are three common mechanisms:

- **Thrombotic:** a clot forms on a fatty plaque inside a large artery in the neck or brain and narrows or closes it.
- **Embolic:** a clot forms elsewhere, often in the heart, then travels and lodges in a brain artery. Atrial fibrillation is a common source (Chapter 16).
- **Small vessel (lacunar):** one of the tiny deep arteries closes, causing a small but sometimes disabling stroke.



Figure 31.1 Intraparenchymal hemorrhagic stroke: (a) schematic axial view and (b) corresponding non-contrast head CT showing a large hemorrhage compressing the ipsilateral ventricle and shifting the midline. (credit: “1602 The Hemorrhagic Stroke-02” by OpenStax College/Wikimedia Commons, CC BY 3.0)

A **hemorrhagic stroke** is caused by a vessel that ruptures and bleeds into or around the brain (Heart and Stroke Foundation of Canada, 2022). An **intracerebral hemorrhage (ICH)** is bleeding into the brain tissue itself that is not caused by trauma. A **subarachnoid hemorrhage (SAH)** is bleeding into the space between the brain and its thin covering membranes, often from a ruptured aneurysm. Both are covered in section 31.4.

A **transient ischemic attack (TIA)** is a brief episode of stroke-like symptoms caused by ischemia, with no infarct on imaging. Symptoms resolve completely within 24 hours, and usually within an hour (Heart and Stroke Foundation of Canada, 2022). A TIA is a warning. People seen within 48 hours of a new TIA or stroke are at the highest risk of another stroke, so the CSBPR call for urgent assessment (Heart and Stroke Foundation of Canada, 2022). Section 31.5 describes TIA triage. Table 31.1 compares the main types of stroke.

Why Time Matters

When an artery closes, brain tissue does not all die at once. Blood flow falls most at the centre of the affected area, the **ischemic core**, where damage quickly becomes permanent. Around it lies the **penumbra**, tissue whose cells have stopped working but can still recover if blood flow returns (Mangiardi et al., 2023). Small side branches called collateral vessels keep the penumbra alive for a time. Their strength varies from person to person, which is why some people can still benefit from treatment many hours after onset. Collaterals cannot protect the penumbra forever, however. Without restored blood flow, it becomes part of the core (Mangiardi et al., 2023).

The phrase "time is brain" captures this race. One widely cited estimate is that a typical person with an untreated large-vessel ischemic stroke loses about 1.9 million neurons every minute. By the same estimate, each untreated hour ages the affected brain by about 3.6 years (Saver, 2006). Treatments that restore blood flow are the only ones that change the course of an ischemic stroke, and their effect on recovery depends directly on how early they are given (Mangiardi et al., 2023). For the nurse, the lesson is practical:

every step in finding, reporting and treating a stroke should happen without delay. A few minutes lost while waiting to see whether a weak arm improves, or while looking for a missing chart, are minutes of brain lost.

Who Has a Stroke in Canada

Heart & Stroke reports that Canada has more than 108,000 strokes a year, about one every five minutes, and that close to one million people in Canada live with the effects of stroke (Heart and Stroke Foundation of Canada, 2025e). Stroke ranks fourth among causes of death in Canada. About 60% of survivors have some stroke-related disability, and more than 40% have moderate to severe disability (Heart and Stroke Foundation of Canada, 2025e).

Stroke can happen at any age, but about 80% of strokes occur in people over 60, and about 1 in 20 occur in people under 45 (Heart and Stroke Foundation of Canada, 2025e). Age and sex cannot be changed. Family history also adds risk, although many Canadians wrongly believe it is the biggest risk factor (Heart and Stroke Foundation of Canada, 2025e).

Most risk can be changed. High blood pressure is the single most important risk factor that people can change (Public Health Agency of Canada [PHAC], 2017; Heart and Stroke Foundation of Canada, 2025e). People with atrial fibrillation have double the risk of stroke (Heart and Stroke Foundation of Canada, 2025e). Heart & Stroke also lists diabetes, high cholesterol, smoking, physical inactivity, unhealthy diet, unhealthy weight, stress and excessive alcohol use as risk factors (Heart and Stroke Foundation of Canada, n.d.-b). Nine in 10 people in Canada have one or more risk factors for heart disease or stroke, and Heart & Stroke estimates that as many as 80% of premature cases of stroke or heart disease could be prevented through healthy behaviours (Heart and Stroke Foundation of Canada, 2025e). Every hospital stay is therefore a chance to find and treat risk factors, such as an undiagnosed high blood pressure or an irregular pulse, and to teach the person about them. Hypertension is taught in Chapter 19, diabetes in Chapter 22 and secondary prevention after stroke in section 31.5.

Women face particular risks. Men have higher stroke rates, but women have more strokes than men each year, partly because women live longer (PHAC, 2017). About 30 in 100,000 women have a stroke during pregnancy (Heart and Stroke Foundation of Canada, 2025e). The 2022 update of the CSBPR acute module added sex and gender considerations (Heart and Stroke Foundation of Canada, 2022).

Stroke risk and care are also shaped by structural factors. In an Ontario study of adults with diabetes, First Nations people had higher rates of hospital admission for stroke or TIA than other Ontarians with diabetes in most years studied. They were less likely to receive clot-dissolving treatment (6.3% vs. 11.0%) (Kapral et al., 2020). The authors place these gaps in the context of the ongoing effects of colonization and marginalization, note that First Nations people are more likely to live outside urban settings, and call for research on Indigenous-specific determinants of health (Kapral et al., 2020). Distance is a barrier for many rural, remote and northern communities (see the Canadian Context box in section 31.3). Culturally safe care is taught in Chapter 2.

Table 31.1 Types of stroke compared (Adams et al., 1993; Heart and Stroke Foundation of Canada, 2022, 2025a)

Type	Cause	Typical onset and signs	Key early treatment	Nursing focus
Ischemic, thrombotic (large artery)	Clot forms on plaque in a large neck or brain artery	Sudden, sometimes stuttering or worse on waking; weakness, speech or vision loss	Clot-dissolving medicine if eligible; clot removal for a large-vessel blockage	Last known well, glucose, rapid imaging, nothing by mouth until swallow screen
Ischemic, embolic	Clot travels from the heart (often atrial fibrillation) or a large artery	Sudden and often maximal at onset	As for thrombotic; prevent another embolus (Chapter 16)	Same as thrombotic; heart rhythm monitoring
Ischemic, small vessel (lacunar)	Closure of a small deep artery	Sudden pure weakness or numbness of one side, often without language loss	Clot-dissolving medicine if eligible and disabling	Do not dismiss mild deficits; frequent neurologic checks
Intracerebral hemorrhage	Bleeding into brain tissue, not from trauma	Sudden deficit, often with headache, vomiting or falling level of consciousness	Blood pressure lowering and anticoagulant reversal as ordered (31.4)	Neurologic checks, airway, signs of rising pressure (section 30.4)

Type	Cause	Typical onset and signs	Key early treatment	Nursing focus
Subarachnoid hemorrhage	Bleeding around the brain, often from a ruptured aneurysm	Sudden, very severe headache; may lose consciousness	Securing the aneurysm in a specialized centre (31.4)	Neurologic checks, pain, early signs of rebleeding or new deficit
Transient ischemic attack	Brief ischemia without infarct	Stroke signs that fully resolve, usually within an hour	Urgent assessment and imaging; start prevention (31.5)	Treat as an emergency; teach FAST and calling 9-1-1

31.2 Recognizing Stroke and Code Stroke

Signs of Stroke

Heart & Stroke teaches the public to recognize stroke with **FAST**, a memory aid for the most common signs (Heart and Stroke Foundation of Canada, 2023): (Figure 31.2)

- **F**ace: is it drooping?
- **A**rms: can you raise both?
- **S**peech: is it slurred or jumbled?
- **T**ime: to call 9-1-1.

The FAST signs are the signs most likely to be caused by stroke rather than another condition (Heart and Stroke Foundation of Canada, n.d.-a). Heart & Stroke also lists less common sudden signs: blurred, double or otherwise changed vision; a sudden, severe headache, which usually comes with other signs; numbness, most often of one side of the body; and trouble with balance (Heart and Stroke Foundation of Canada, n.d.-a). Not everyone has every sign; one is enough to call 9-1-1. Knowing the exact time the signs began matters for treatment (Heart and Stroke Foundation of Canada, n.d.-a). Heart & Stroke advises against driving to hospital, because an ambulance will take the person to the nearest hospital able to give urgent stroke care (Heart and Stroke Foundation of Canada, n.d.-c). Stroke awareness campaigns work: mass media education can raise symptom recognition and the likelihood of calling emergency services (Heran et al., 2024).



Figure 31.2 Unilateral facial droop—asymmetry of the lower face and mouth—one of the core signs in the FAST™ stroke recognition tool. (credit: "Stroke-facial-droop" by Another-anon-artist-234/Wikimedia Commons, CC0)

The key word is **sudden**. Stroke signs appear over seconds to minutes. Each hemisphere controls the opposite side of the body (section 30.1), so a stroke in one hemisphere causes **hemiparesis**, weakness of the face, arm or leg on the opposite side. A left hemisphere stroke can also cause **aphasia**, a disorder of language that affects speaking, understanding, reading or writing, because language depends mainly on the left hemisphere in most people (section 30.2). A right hemisphere stroke can cause **neglect**, in which the person does not attend to one side of space or their own body. The person may eat from only one side of the plate or not notice a weak arm. In a systematic review, neglect occurred in about 38% of people after right brain damage and 18% after left brain damage (Esposito et al., 2021). Slurred speech from weak muscles, called dysarthria, is different from aphasia (section 30.2).

Stroke signs are judged by movement, symmetry, speech and vision, not by skin colour, so the nurse finds them the same way on every skin tone. The nurse compares the two sides of the face during a smile, watches for one arm drifting down and listens to the person's speech.

Stroke Mimics

A **stroke mimic** is a condition that causes sudden stroke-like signs but is not a stroke. Mimics are common. Depending on who does the assessment, they make up about 20% to 50% of suspected strokes (Buck et al., 2021). Common mimics include:

- **Low blood glucose:** hypoglycemia can cause one-sided weakness, confusion or slurred speech that resolves once glucose is corrected (section 22.4). High glucose can also mimic stroke (Buck et al., 2021).
- **Seizure:** after a seizure, a person can have temporary weakness of one side, called postictal (Todd's) paralysis (Buck et al., 2021). Seizures are covered in section 30.5.
- **Migraine with aura:** aura, sometimes without headache, can cause temporary neurologic signs (Buck et al., 2021).
- **Infection and sepsis:** infection can cause confusion and other stroke-like signs (Buck et al., 2021; Chapter 4).
- **Functional neurologic disorders, tumours and other causes** (Buck et al., 2021).

A gradual onset, fluctuating signs, a history of migraine or seizures, or signs that do not match one blood vessel's territory raise the suspicion of a mimic (Buck et al., 2021). These are clues for the team, not reasons for the nurse to delay. The safe approach is to treat every sudden deficit as a stroke until proved otherwise, check the glucose early, and let brain imaging and the stroke team decide.

CLINICAL SAFETY

Check the Glucose

A low blood glucose can look exactly like a stroke, and it is quick to find and fix. The CSBPR recommend a capillary blood glucose check by paramedics on scene and a glucose check on arrival in the emergency department. Hypoglycemia is corrected at once using local protocols (Heart and Stroke Foundation of Canada, 2022).

- Check the point-of-care glucose as soon as new stroke signs are found, including on a hospital unit.
- If the glucose is low, treat it at once as the hypoglycemia protocol directs (section 22.4), and still call for help: the person may have both a low glucose and a stroke.
- Report the value and time in the handover.
- Never give food or drink to treat a low glucose if swallowing is uncertain. Use the protocol's non-oral route.

The First Hour

Last known well (LKW) is the last time the person was known to be at their usual self, without the new signs. When no one saw the signs begin, such as when a person wakes with symptoms or a nurse finds them on rounds, treatment decisions use the LKW time, not the time the signs were found. Paramedics are asked to record both the onset time and the LKW time, the person's medications (especially anticoagulants) and any advance directives (Heart and Stroke Foundation of Canada, 2022). A family member or substitute decision-maker should come to hospital or stay reachable by phone, because the team may need facts and decisions quickly.

Before hospital. Anyone who sees stroke signs should call 9-1-1 immediately. Paramedics use a validated screening tool that includes the FAST components, then a second screen for stroke severity that helps identify a likely **large vessel occlusion (LVO)**, a blockage of a major brain artery (Heart and Stroke Foundation of Canada, 2022). On-scene time should be as short as possible, ideally a median under 20 minutes. Transport protocols direct possible candidates for clot-dissolving treatment or clot removal to the most appropriate stroke centre, which may mean bypassing a closer hospital. Paramedics notify the receiving emergency department on the way so it can activate a code stroke (Heart and Stroke Foundation of Canada, 2022). Pre-notification raised the odds of receiving clot-dissolving treatment in studies reviewed for the CSBPR (Heran et al., 2024).

In the emergency department. A **code stroke** is a hospital's emergency process that brings the stroke team, imaging and laboratory together at once for a person with suspected acute stroke. Most patients with suspected stroke are triaged at Canadian Triage and Acuity Scale (CTAS) level 2, or level 1 if airway, breathing or circulation is compromised (Heart and Stroke Foundation of Canada, 2022). The team checks airway, breathing and circulation, does a rapid neurologic examination that includes a standardized stroke

scale, for example the National Institutes of Health Stroke Scale (NIHSS), and records vital signs, heart rhythm, oxygen saturation, temperature and point-of-care glucose. The team also asks about anticoagulant use and the time of the last dose (Heart and Stroke Foundation of Canada, 2022). Blood tests include electrolytes, glucose, a complete blood count, clotting tests and creatinine, but they must not delay imaging or treatment decisions. A 12-lead electrocardiogram (ECG) looks for atrial fibrillation but also must not delay assessment for treatment (Heart and Stroke Foundation of Canada, 2022). A seizure at onset does not by itself rule out clot-dissolving treatment or clot removal. Supplemental oxygen is not needed when the oxygen saturation is normal (Heart and Stroke Foundation of Canada, 2022). The nurse's role in the emergency department is to keep the process moving: weighing the patient, starting intravenous (IV) access, sending blood work, getting the patient to computed tomography (CT) and recording times.

Brain and vessel imaging is the most urgent test. For a person who arrives within 6 hours and may be eligible for treatment, the CSBPR recommend immediate non-contrast CT of the head with **CT angiography (CTA)**, which uses contrast dye to show the arteries from the aortic arch to the top of the head (Heart and Stroke Foundation of Canada, 2022). The non-contrast CT shows whether there is bleeding; the CTA shows where an artery is blocked. A performance measure is brain imaging within 15 minutes of arrival for eligible patients (Heart and Stroke Foundation of Canada, 2022). Between 6 and 24 hours, perfusion imaging may help select patients for clot removal.

In-hospital stroke. Some strokes begin in people who are already in hospital for another reason. An Ontario Stroke Registry study found that these patients were diagnosed and treated significantly later than patients who came from the community (Saltman et al., 2015). The study's authors called for standardized approaches. Many hospitals now have an in-hospital code stroke or use the rapid response team (Chapter 6). The nurse who finds new stroke signs stays with the patient and calls for help as policy directs. The nurse then finds the LKW time, checks glucose and vital signs, gives nothing by mouth, and gives a clear SBAR report.

Nothing by mouth. Stroke can weaken the muscles of swallowing. The CSBPR state that patients stay **NPO** (nothing by mouth), including oral medications, until a swallowing screen with a validated tool has been completed by a trained professional (Heart and Stroke Foundation of Canada, 2022). Medications needed before then are given by another route as ordered. Section 31.5 describes the screen.

GOING DEEPER

The NIH Stroke Scale

Required for RN students; optional for PN students.

The NIHSS is a structured checklist that measures how severe a stroke is (National Institute of Neurological Disorders and Stroke [NINDS], n.d.). It rates 11 categories, including level of consciousness, gaze, visual fields, facial movement, arm and leg strength, coordination, sensation, language, speech and neglect. Each category has defined responses, and the examiner must choose a score even when a breathing tube or language barrier limits the examination (NINDS, n.d.). The maximum possible total is 42 points, and higher scores mean more severe deficits (Lyden, 2017).

Why the score matters:

- The CSBPR recommend a standardized scale such as the NIHSS in the initial emergency assessment (Heart and Stroke Foundation of Canada, 2022).
- The total relates to the size of the stroke, helps predict outcome and is used in treatment decisions. For example, the CSBPR describe disabling stroke for clot removal with an example threshold of an NIHSS score above 5 (Heart and Stroke Foundation of Canada, 2025a).
- Repeated scores show improvement or worsening over time.

The scale has limits. It captures brainstem function poorly, and left hemisphere strokes score about 4 points higher than right hemisphere strokes of the same size (Lyden, 2017). Because its rules are not intuitive, reliable scoring requires training and certification (Lyden, 2017); employers set their own certification requirements for nurses who use it.

31.3 Hyperacute Treatment

Thrombolysis

Thrombolysis is treatment with an intravenous medicine that dissolves the clot blocking a brain artery. Two thrombolytics are used in Canada: **alteplase** and **tenecteplase**. Tenecteplase was authorized by Health Canada for acute ischemic stroke in adults in November 2025, with treatment to start within 4.5 hours of symptom onset after bleeding in the brain has been ruled out (Hoffmann-La Roche Limited, 2025a, 2025b). Alteplase is given as a bolus followed by a 60-minute infusion; tenecteplase is a single bolus given over about 5 seconds (Hoffmann-La Roche Limited, 2025a). Doses are calculated by weight and prepared by protocol.

Eligibility in principle. The CSBPR recommend that eligible patients with a disabling ischemic stroke who can be treated within 4.5 hours of symptom onset or LKW be offered thrombolysis with alteplase or tenecteplase (Heart and Stroke Foundation of Canada, 2022). The Canadian alteplase product monograph states that treatment should start within 3 hours of symptom onset (Hoffmann-La Roche Limited, 2024), a narrower window than the CSBPR recommendation; the stroke physician makes the treatment decision. Eligibility depends on the LKW time, imaging that rules out hemorrhage, the severity of the deficit and the person's bleeding risk, including recent anticoagulant use. A stroke expert, on site or by telestroke, makes the decision with the person and family. Treatment beyond 4.5 hours may be considered with stroke expertise and advanced imaging (Heart and Stroke Foundation of Canada, 2022). People taking a direct oral anticoagulant are not routinely given thrombolysis; it may be considered only in comprehensive stroke centres with specialized testing and expert advice (Heart and Stroke Foundation of Canada, 2022). The nurse supports a fast, informed decision by telling the team about any anticoagulant and the time of the last dose, and by helping the family reach the bedside or the phone. Consent for emergency treatment is taught in section 1.5.

Door-to-needle time is the time from hospital arrival to the start of thrombolysis. The CSBPR target is a median of 30 minutes or less, and 60 minutes or less for at least 90% of treated patients (Heart and Stroke Foundation of Canada, 2022). Nurses help meet it by having weight, IV access, glucose and vital signs ready, and by moving the patient straight from CT to treatment when the protocol allows.

Blood pressure. For a person who will receive thrombolysis, the CSBPR state that blood pressure should be lowered and kept below 185/110 mm Hg when treatment starts, during treatment and for the next 24 hours (Heart and Stroke Foundation of Canada, 2022). For people who are not receiving reperfusion treatment, moderately high blood pressure is usually not treated in the first hours, and rapid or excessive lowering is avoided, because the penumbra depends on blood pressure to receive blood flow. Lowering may be considered when the pressure is extremely high, for example a systolic pressure above 220 mm Hg or a diastolic pressure above 120 mm Hg (Heart and Stroke Foundation of Canada, 2022). The prescriber orders the antihypertensive and the targets. Hypertension and its medicines are taught in Chapter 19.

Monitoring. The CSBPR call for close monitoring for the first 24 hours after thrombolysis (Heart and Stroke Foundation of Canada, 2022). The exact schedule of neurologic checks and blood pressure readings comes from the employer's post-thrombolysis protocol and orders (Table 31.2). The alteplase monograph advises minimizing arterial and venous punctures, avoiding intramuscular injections and avoiding nonessential handling during and right after treatment (Hoffmann-La Roche Limited, 2024).

Bleeding. The most feared complication is **symptomatic intracranial hemorrhage**, bleeding in the brain that worsens the person's condition. The CSBPR name a decline in neurologic status, a sudden rise in blood pressure or a new headache as reasons to suspect it (Heart and Stroke Foundation of Canada, 2022). Nausea, vomiting and a falling level of consciousness are also signs of rising intracranial pressure (section 30.4). If any of these appear, the nurse stops the infusion if it is still running, as the protocol directs, and calls the stroke physician at once. An urgent non-contrast CT and blood work follow (Heart and Stroke Foundation of Canada, 2022). Bleeding elsewhere also matters: gums, IV sites, urine, stool and vomit are checked. Bruising can be harder to see on darker skin, so the nurse also checks the mouth and asks about new pain or swelling.

Orolingual angioedema is swelling of the lips, tongue or throat that can follow thrombolysis and threaten the airway. It occurred in 1.1% of people who received tenecteplase in a Canadian trial, a rate similar to that with alteplase (Hoffmann-La Roche Limited, 2025b). The alteplase monograph notes that many affected people were taking an angiotensin-converting enzyme (ACE) inhibitor (Hoffmann-La Roche Limited, 2024). At the first sign, the CSBPR advise stopping the infusion if it is still running and treating with antihistamines, with other medicines and airway management as needed (Heart and Stroke Foundation of Canada, 2022). The nurse

stays with the patient, calls for help and prepares for airway support. Angioedema is taught in section 21.2 and anaphylaxis in section 6.5.

Endovascular Thrombectomy

Endovascular thrombectomy (EVT) removes a clot from a large brain artery with a catheter threaded from an artery in the groin or wrist (Elfil et al., 2023). It is done by a neurointerventionist in a comprehensive stroke centre and can follow thrombolysis or be used when thrombolysis is not possible. Neither treatment should delay the other (Heart and Stroke Foundation of Canada, 2025a).

The 2025 CSBPR interim update on EVT describes eligibility in principle. Candidates are adults who were independent before the stroke, have a disabling stroke and a blockage of a large artery in the front of the brain or the basilar artery that the catheter can reach, and have a core of damage on imaging that is not too large (Heart and Stroke Foundation of Canada, 2025a). Patients within 6 hours of onset should be screened without delay. Selected patients may be treated up to 24 hours from LKW, often with advanced imaging (Heart and Stroke Foundation of Canada, 2022, 2025a). The decision is shared among the stroke physician, the neurointerventionist and the patient and family (Heart and Stroke Foundation of Canada, 2025a). Procedural sedation is generally preferred over general anesthesia (Heart and Stroke Foundation of Canada, 2025a).

Figure 31.3 A mobile telestroke system with a high-definition camera and two-way video screen, enabling a remote stroke specialist to examine the patient and review imaging in real time with the bedside team. (credit: "10.1.15 FCC Connect2Health Task Force Beyond the Beltway Series – Jacksonville, FL (22193326376)" by Federal Communications Commission/Wikimedia Commons, Public domain)

After EVT, the nurse monitors neurologic status and blood pressure as ordered and checks the arterial access site and the limb beyond it. The nurse looks for bleeding, swelling or a growing lump at the site, and checks pulse, colour, warmth, sensation and movement of the limb. In a meta-analysis, access through the wrist (radial artery) had fewer access-site complications than access through the groin (femoral artery) (Elfil et al., 2023). Bed rest, limb positioning and how often the site is checked follow the post-procedure order or protocol (Table 31.2).

Many people first reach a hospital that cannot perform EVT. These hospitals use **telestroke**, a video assessment by a stroke physician at another centre, to decide on thrombolysis and to arrange urgent transfer to a comprehensive stroke centre (Heart and Stroke Foundation of Canada, 2022). The nurse prepares the patient and records for a rapid transfer, which is often time-critical (Figure 31.3).

The Stroke Unit

A **stroke unit** is a hospital unit in one fixed location that is set aside for people with stroke and staffed by an interprofessional team with stroke training (Heart and Stroke Foundation of Canada, 2022). Patients cared for on stroke units are more likely to be alive, living at home and independent than patients on general units (Heran et al., 2024). Compared with less organized care, stroke unit care lowered the odds of death (odds ratio 0.76) and of death or dependency (odds ratio 0.75) (Heran et al., 2024).

The benefit comes from organization rather than any single treatment. The core team includes physicians, nurses, occupational therapists, physiotherapists, speech-language pathologists, dietitians, social workers and pharmacists, with the patient and family as members of the team (Heart and Stroke Foundation of Canada, 2022). The team follows standard protocols for swallowing, mobility, prevention of complications and early rehabilitation, which are described in sections 31.5 and 31.6.

Table 31.2 Nursing care after thrombolysis (Heart and Stroke Foundation of Canada, 2022, 2025a; Hoffmann-La Roche Limited, 2024)

What to monitor	How often (as the protocol states)	Warning signs	First actions

What to monitor	How often (as the protocol states)	Warning signs	First actions
Neurologic status (stroke scale or neurologic check, level of consciousness, pupils)	Closely for the first 24 hours, at the intervals in the employer protocol	New or worse weakness, speech change, drowsiness, new headache	Stop infusion if running; call stroke physician now; prepare for urgent CT
Blood pressure and heart rate	At the protocol intervals; below 185/110 mm Hg for 24 hours	Reading at or above the ordered limit; sudden rise	Give ordered antihypertensive; recheck; report a sudden rise as a possible bleed
Lips, tongue and throat	During and for several hours after treatment	Swelling, hoarse voice, noisy breathing, trouble swallowing saliva	Stop infusion if running; call for help; airway support; ordered medicines
Bleeding sites (IV sites, gums, urine, stool, vomit)	With each set of vital signs	Oozing, blood in urine or stool, bruising or swelling	Apply pressure to compressible sites; report; avoid new punctures and intramuscular injections
Arterial access site and limb after EVT	As the post-procedure order states	Bleeding, growing lump, cool or pale limb, weak pulse, numbness	Firm pressure above the site; call for help; keep limb still
Swallowing and intake	Until a validated swallowing screen is completed	Coughing, wet voice, drooling	Keep NPO including oral medications; mouth care; request the screen

CANADIAN CONTEXT

Getting Stroke Care Across Canada

Canada's stroke systems sort hospitals by the care they can give. The CSBPR describe primary stroke centres that give thrombolysis, sometimes supported by telestroke; centres that also have acute stroke units; and comprehensive stroke centres that also provide endovascular treatment (Heart and Stroke Foundation of Canada, 2022).

Distance shapes access. A 2017 geospatial analysis of the eight provinces with available data, using 2011 census populations, found that the share of residents within a 4.5-hour road ambulance trip of a stroke centre ranged from 47.1% in Newfoundland and Labrador to 96.4% in Ontario (Eswaradass et al., 2017). Telestroke, transfer agreements and pre-notification help close these gaps.

Gaps also follow structural lines. In Ontario, First Nations people with diabetes were less likely than other Ontarians with diabetes to receive thrombolysis; the researchers set this gap in the context of colonization and marginalization and called for research on Indigenous-specific determinants of health (Kapral et al., 2020). The study was guided by the First Nations principles of OCAP® (ownership, control, access and possession) and approved by the Chiefs of Ontario Data Governance Committee (Kapral et al., 2020). Nurses in rural, remote, northern and Indigenous communities recognize stroke early, find the LKW time, check glucose and arrange rapid transfer, often by telephone or video with a stroke centre.

PRACTICE STORY

Last Known Well

Names and details are fictional; this is a composite story.

Nurse: Ama Owusu, RPN. Years in practice: 4. Setting: medical unit, Ontario.

At 0240 I went in to check Mr. Bouchard's IV. He was 74, in for a urinary tract infection, and on my midnight round he had been chatting about curling. Now he was awake and trying to tell me something, but the words came out thick. The right side of his mouth sagged. When I asked him to hold both arms up with his eyes closed, the right one drifted down to the bed.

My first thought was that he was just sleepy or delirious. Then I remembered how quickly he had talked at midnight. This was sudden, and it was on one side.

I pressed the call bell and asked the personal support worker (PSW) to get Daniel, the RN. While I waited, I checked his glucose: 6.2 mmol/L. Not low, so hypoglycemia wasn't the cause. His blood pressure was 178/96 mm Hg, higher than his usual. I asked Mr. Bouchard to nod if he understood me. He nodded. I told him I thought something was happening in his brain and that help was coming.

When Daniel arrived, I gave him the facts: "Last known well at midnight, when I spoke with him. Found at 0240 with right facial droop, right arm drift and slurred speech. Glucose 6.2. BP 178/96." Daniel looked once and said, "Call it." Our policy lets any nurse activate the in-hospital code stroke, so I called switchboard while he stayed at the bedside. I took the water jug off the table and put up a sign: NPO.

The team arrived within minutes, and he went to CT. I learned later that he had a clot in a large artery and was transferred for thrombectomy.

What stays with me is the time. If I had written "found at 0240," the team might have thought the clock started then. Midnight was the truth.

Reflect: What did the RPN's assessment add to the team's decision? Which parts of this response were within the RPN's authority, competence and context, and how would employer policy on who may activate a code stroke change what the RPN did?

31.4 Hemorrhagic Stroke

In a hemorrhagic stroke, a blood vessel breaks and blood escapes into or around the brain (Table 31.1, section 31.1). Both main types are emergencies, and both can raise intracranial pressure (ICP; section 30.4).

Intracerebral Hemorrhage

In an ICH (section 31.1), the escaped blood collects as a clot, called a hematoma, that presses on and injures the brain around it, and its added volume can raise ICP. In Canada, ICH accounts for 10% to 15% of the strokes seen in hospitals, and its mortality is much higher than that of ischemic stroke (40% compared with 15%), as the CSBPR on ICH reports (Shoamanesh et al., 2021; Figure 31.4).

Risk factors. The CSBPR lists older age, high blood pressure, ongoing anticoagulant use and an earlier small-vessel (lacunar) stroke as clinical factors that raise the risk of another ICH (Shoamanesh et al., 2021). A bleed in a lobe near the surface of the brain suggests **cerebral amyloid angiopathy**, and the team uses imaging criteria to make this diagnosis (Shoamanesh et al., 2021). In this condition, a protein called beta-amyloid builds up in the walls of small blood vessels in the outer brain and its coverings; it is a leading cause of lobar bleeds in older adults.

Manifestations and diagnostics. An ICH causes sudden deficits that look like an ischemic stroke (section 31.2). Only urgent brain imaging, with CT or magnetic resonance imaging (MRI), can tell bleeding from a clot (Shoamanesh et al., 2021). As the hematoma or the swelling around it grows, signs of rising ICP, such as a falling level of consciousness, headache and vomiting, may appear (section 30.4).

Blood pressure. The CSBPR states that blood pressure is checked on arrival in the emergency department and every 15 minutes after that. It states that lowering systolic pressure to a target below 140 mm Hg does not worsen neurologic outcomes, although clinical benefit has not been proven, and it suggests that an individual systolic target below 140 to 160 mm Hg during the first 24 to 48 hours may be reasonable (Shoamanesh et al., 2021). The nurse



Figure 31.4 Non-contrast head CT showing an acute intracerebral hemorrhage with intraventricular extension. (credit: “Intracerebral hemorrage (CT scan)” by Glitzy queen00/Wikimedia Commons, Public domain)

measures blood pressure as often as ordered, gives antihypertensives as ordered or per protocol, and reports readings outside the target at once.

Anticoagulants. The nurse finds out early whether the patient takes an anticoagulant and when the last dose was taken (Heart and Stroke Foundation of Canada, 2022). The CSBPR states that anticoagulation is withheld in anticoagulant-related ICH and immediate reversal is considered, and that reversal should not wait for laboratory results but be based on the clinical history (Shoamanesh et al., 2021). The nurse prepares to give reversal agents as ordered without delay (section 19.7).

Ongoing care. The nurse compares each neurologic check with the last, using the Glasgow Coma Scale and pupil checks (Chapter 30), and escalates any decline at once (Chapter 6). The CSBPR recommends intermittent pneumatic compression (IPC) devices from the day of admission to prevent venous thromboembolism (VTE). It does not recommend graduated compression stockings, and it allows low-molecular-weight heparin only after 48 hours and once imaging shows the hematoma is stable (Shoamanesh et al., 2021). Corticosteroids are not recommended for raised ICP (section 30.4), and an external ventricular drain may be considered for a patient with a reduced level of consciousness and hydrocephalus (Shoamanesh et al., 2021). In the long term, the CSBPR aims to keep blood pressure consistently below 130/80 mm Hg after ICH (Shoamanesh et al., 2021).

Subarachnoid Hemorrhage

In an SAH (section 31.1), blood enters the space around the brain where cerebrospinal fluid (CSF) flows. Trauma can cause an SAH (Chapter 32), but a non-traumatic SAH is mostly caused by the rupture of a **cerebral aneurysm**, a weak, bulging area in the wall of a brain artery (Korkmaz Dilmen & Bonhomme, 2023). The CSBPR does not have a module on aneurysmal SAH, so this section draws on the 2023 guideline of the American Heart Association and American Stroke Association (AHA/ASA; Hoh et al., 2023; Figure 31.5).



Figure 31.5 Non-contrast head CT showing acute subarachnoid hemorrhage filling the basal cisterns and left Sylvian fissure, along with a left temporal hemorrhage. (credit: "CT brain showing subarachnoid haemorrhage and left temporal haemorrhage" by Cerevisae/Wikimedia Commons, CC BY-SA 4.0)

Recognizing SAH. In an awake patient, the classic sign is a headache that begins suddenly (Hoh et al., 2023). Patients often describe it as the worst headache of their life (Korkmaz Dilmen & Bonhomme, 2023). A sudden, severe headache is a red flag that needs emergency assessment (section 30.6).

Securing the aneurysm. A ruptured aneurysm can bleed again, most often in the first 24 hours (Korkmaz Dilmen & Bonhomme, 2023). The AHA/ASA guideline recommends prompt treatment of the ruptured aneurysm, preferably within 24 hours, because early treatment lowers the risk of rebleeding (Hoh et al., 2023). In **coiling**, a catheter is threaded through an artery and small coils are placed inside the aneurysm so that blood no longer enters it. In **clipping**, a surgeon opens the skull and places a clip across the neck of the aneurysm. The guideline recommends timely transfer to experienced centres with dedicated neurocritical care units. Before the aneurysm is secured, it advises gradual lowering of very high blood pressure while strictly avoiding low pressure (Hoh et al., 2023).

Complications. The nurse watches for four complications:

- **Delayed cerebral ischemia: Delayed cerebral ischemia** (DCI) is new brain ischemia that develops days after the bleed, often linked to narrowing of brain arteries (vasospasm). One review places this risk between days 5 and 15, sometimes up to day 21 (Korkmaz Dilmen & Bonhomme, 2023). New confusion, drowsiness, weakness or speech

change suggests DCI and is reported at once. The guideline states that this monitoring needs trained nurses who can detect changes in the neurologic examination quickly (Hoh et al., 2023).

- **Hydrocephalus:** Blood can block the flow of CSF and cause hydrocephalus; an external ventricular drain may be placed (Korkmaz Dilmen & Bonhomme, 2023; section 30.4).
- **Hyponatremia:** Low sodium is a prominent feature of aneurysmal SAH. The AHA/ASA guideline names two causes: cerebral salt wasting, in which the kidneys lose sodium and water, and the syndrome of inappropriate antidiuretic hormone (SIADH; Hoh et al., 2023; section 3.4). Sodium loss through the kidneys can lower blood volume, and low blood volume is associated with DCI (Hoh et al., 2023). For this reason, cerebral salt wasting is treated by replacing sodium and fluid rather than by restricting fluid (Korkmaz Dilmen & Bonhomme, 2023). The nurse tracks intake, output and sodium results and reports a falling sodium.
- **Rebleeding:** A sudden new headache or a drop in level of consciousness before the aneurysm is secured needs immediate escalation.

Medications. The AHA/ASA guideline states that early **nimodipine**, given by the enteral route (by mouth or feeding tube), helps prevent DCI and improves outcomes (Hoh et al., 2023). It does not recommend routine extra fluids or raised blood pressure to prevent DCI (Hoh et al., 2023). If the patient cannot swallow safely, the nurse asks how it is to be given rather than omitting it.

31.5 Stroke Unit Care

Section 31.3 explained why organized stroke unit care saves lives; this section describes the nursing care on the unit. The CSBPR asks the team to build an individual plan for nutrition, oral care, mobility and continence for every patient, to reduce the risk of urinary tract infection, aspiration pneumonia and VTE, and to begin planning for discharge from admission (Heart and Stroke Foundation of Canada, 2022).

Swallowing, Nutrition and Hydration

Dysphagia, or difficulty swallowing, is common after stroke (section 24.3). **Aspiration** is the entry of food, fluid, saliva or stomach contents into the airway below the vocal cords. A patient may aspirate without coughing, without a wet voice and without reporting a problem, and aspiration can lead to pneumonia (Heart and Stroke Foundation of Canada, 2022; section 13.2).

Screening before anything by mouth. The CSBPR states that a trained professional should screen swallowing with a valid tool before the patient takes anything by mouth, including medications, food and fluids, and that the screen should happen as early as possible, ideally on the day of admission (Heart and Stroke Foundation of Canada, 2022). This is **dysphagia screening**. The employer chooses the screening tool and trains the staff who use it. The CSBPR rationale cites a large trial in which pneumonia developed in 10.0% of patients who failed the swallowing screen and 1.5% of those who passed (Heart and Stroke Foundation of Canada, 2022). Until then, the patient stays NPO; the nurse gives mouth care and reports the need for another route for essential medications.

Assessment and the plan. A failed screen leads to referral to a speech-language pathologist (SLP), an occupational therapist, a dietitian or another dysphagia clinician, who sets an individual plan for diet and therapy (Heart and Stroke Foundation of Canada, 2022, 2025c). The nurse follows the plan at every meal: the diet texture and fluid thickness (section 24.3), sitting upright, supervision and pacing. If eating by mouth is unsafe or not enough, the CSBPR states that enteral feeding, for example through a nasogastric tube, is considered with the patient, family or substitute decision-maker, usually within the first 3 days (Heart and Stroke Foundation of Canada, 2022). The nurse also watches intake and hydration, since dehydration raises the risk of VTE (Heart and Stroke Foundation of Canada, 2022).

Medications. Once the patient may swallow, medications are given in the form the plan allows. The nurse checks with the pharmacist before crushing any tablet, because extended-release and enteric-coated products must not be crushed (section 24.3).

Oral care. The CSBPR calls for an assessment of the mouth and teeth on or shortly after admission, a check that the patient can use dentures safely, and oral care according to Canadian Dental Association guidance, ideally after meals and at bedtime (Heart and Stroke Foundation of Canada, 2022). Families who bring food from home need to know the plan, because a well-meant meal can be the wrong texture.

Positioning, Mobility and Prevention of Complications

Early mobilization. The 2025 CSBPR rehabilitation module advises against very early, high-intensity mobilization in the first 24 hours; once the patient is medically stable, mobilization should start, ideally 24 to 48 hours after the stroke, with caution (Heart and Stroke Foundation of Canada, 2025b). The acute module adds that early prolonged out-of-bed activity in the first 24 to 48 hours, especially after a severe stroke, is not recommended. It lists cautions such as a recent arterial puncture for a procedure, an unstable condition, low oxygen saturation and a leg fracture (Heart and Stroke Foundation of Canada, 2022).

The hemiplegic shoulder. A **hemiplegic shoulder** is the shoulder on the weak side, which can partly slip out of its joint and become painful. Shoulder pain after stroke affects roughly 22% to 47% of people (Heart and Stroke Foundation of Canada, 2025c). The CSBPR recommends supporting and positioning the arm at rest; never pulling on the weak arm; protecting it during transfers; avoiding overhead pulleys; limiting passive movement above 90 degrees unless the shoulder blade and arm are positioned for it; and teaching staff, the patient and family how to handle the arm. Slings are used only in the flaccid stage when no other support is possible (Heart and Stroke Foundation of Canada, 2025c).

Venous thromboembolism. Every patient is assessed for VTE risk. For high-risk patients, the CSBPR recommends thigh-high IPC or an anticoagulant for prophylaxis from the day of admission unless contraindicated. IPC stops when the patient walks independently, at discharge, if adverse effects occur or at 30 days, whichever comes first; graduated compression stockings are not recommended (Heart and Stroke Foundation of Canada, 2022). The nurse checks the skin under the sleeves (Chapter 7; section 19.6).

Skin, continence and bowels. The team assesses skin breakdown risk on admission (Heart and Stroke Foundation of Canada, 2022; Chapter 35). Indwelling urinary catheters are used with caution, reassessed daily and removed as soon as possible. Patients are screened for incontinence, retention and constipation; a portable bladder scanner measures urine left after voiding; and timed and prompted toileting and a bowel program are used as needed (Heart and Stroke Foundation of Canada, 2022).

Temperature, glucose and oxygen. The CSBPR recommends checking temperature along with the other vital signs, ideally every 4 hours during the first 48 hours. A temperature above 37.5 °C prompts closer monitoring, cooling, a search for infection such as pneumonia or urinary tract infection, and treatment as ordered (Heart and Stroke Foundation of Canada, 2022). Low blood glucose is corrected immediately using local protocols, and high glucose is treated per local protocols (Heart and Stroke Foundation of Canada, 2022; Chapter 22). Supplemental oxygen is not needed when oxygen saturation is normal (Heart and Stroke Foundation of Canada, 2022); it is given as ordered when saturation falls (Chapter 12).

Communication, Cognition and Mood

Aphasia (section 31.2) can affect speaking, understanding, reading and writing. In **expressive aphasia**, the person understands more than they can say and struggles to find or form words. In **receptive aphasia**, the person has trouble understanding spoken or written language and may speak fluently but without clear meaning. **Dysarthria** is different: language is intact, but weak or poorly coordinated speech muscles make speech slurred. Between 21% and 38% of people are aphasic in the early days after stroke (Heart and Stroke Foundation of Canada, 2025c).

The CSBPR states that every person with stroke needs a screen for communication problems, that an SLP should assess those with suspected problems, and that staff and families should be trained in supported conversation (Heart and Stroke Foundation of Canada, 2025c). Practical strategies:

- Reduce noise and face the person; one person speaks at a time.
- Use short sentences and questions with a yes or no answer, and allow time.
- Add gestures, writing, pictures or a tablet, and confirm what the person meant.
- Speak to the person as an adult, never as if they were absent.

Aphasia alone does not mean that a person lacks capacity to consent. Capacity is assessed for each decision, with communication supports in place (Chapter 1).

Unilateral neglect (section 31.2) usually affects the left side after a stroke in the right hemisphere. The patient may eat food from only half the tray or bump into door frames. The CSBPR recommends early screening of everyone with stroke for visual-perceptual

problems, education for the person and family on safety, and compensatory strategies such as cues and changes to the surroundings; visual scanning training is one therapy option (Heart and Stroke Foundation of Canada, 2025c). On the unit, the nurse cues the patient to turn the head and scan, checks the neglected side of the body for injury, and keeps the call bell where the patient can find it. The CSBPR also asks the team to screen for vascular cognitive impairment when indicated; delirium is covered in Chapter 8 (Heart and Stroke Foundation of Canada, 2022).

Mood and fatigue. About one-third of people show symptoms of depression at some point after a stroke (Heart and Stroke Foundation of Canada, 2025d). **Post-stroke depression** is depression that develops after a stroke. The CSBPR states that everyone with stroke should be screened for it if medically appropriate, by trained professionals using a validated tool, especially at transition points such as moving to rehabilitation or going home. Treatment can include psychological therapy, an antidepressant and supervised exercise (Heart and Stroke Foundation of Canada, 2025d). The 2025 module also addresses sleep and post-stroke fatigue, so the nurse asks about tiredness and plans rest between therapies (Heart and Stroke Foundation of Canada, 2025d). Families are part of the core team, and they too are at risk of depression (Heart and Stroke Foundation of Canada, 2022, 2025d).



Figure 31.6 Vascular surgeons performing a carotid endarterectomy to remove atherosclerotic plaque from the internal carotid artery for secondary stroke prevention. (credit: "David Grant USAF Medical Center 110523-F-ML202-008" by Staff Sgt. Liliana Moreno/U.S. Air Force, Public domain)

Secondary Prevention

Secondary prevention is care that lowers the risk of another stroke after a stroke or TIA. The CSBPR states that people seen within 48 hours of new stroke or TIA symptoms are at the highest risk of another stroke and should be sent immediately to an emergency department that can provide stroke care; those seen later should have a full evaluation by a clinician with stroke expertise as soon as possible (Heart and Stroke Foundation of Canada, 2022; Figure 31.6).

Table 31.3 summarizes the targets in the CSBPR secondary prevention module (Heart and Stroke Foundation of Canada, 2020). **Antiplatelet therapy** uses medicines that keep platelets from clumping to form clots. After an ischemic stroke or TIA, long-term antiplatelet therapy is recommended unless the person needs an anticoagulant. For a high-risk TIA or minor stroke, two antiplatelets are given together for a short time and then reduced to one. People with atrial fibrillation (section 16.6) receive an oral anticoagulant instead, with a direct oral anticoagulant preferred over warfarin for most patients. The CSBPR states that the best time to start it has not been well defined; by expert consensus, timing ranges from within 1 day after a TIA to 12 to 14 days after a severe stroke (Heart and Stroke Foundation of Canada, 2020). The CSBPR secondary prevention module dates from 2020, while Hypertension Canada updated its guideline in 2025 (Chapter 19), so the nurse follows the target the team sets for each patient.

Table 31.3 Secondary prevention after stroke or TIA (Heart and Stroke Foundation of Canada, 2020; original wording)

Risk factor	Target or recommendation as the CSBPR states it	Medicines (named only)	Teaching
Blood pressure	Consistently lower than 140/90 mm Hg after ischemic stroke or TIA (2020 module); systolic consistently lower than 130 mm Hg after a small subcortical stroke; consistently lower than 130/80 mm Hg with diabetes and after ICH; follow the target the team sets	ACE inhibitor plus a thiazide or thiazide-like diuretic; others per Hypertension Canada	Home blood pressure checks; take medicines daily even when feeling well
Lipids	Low-density lipoprotein (LDL) cholesterol below 1.8 mmol/L	A statin, such as atorvastatin; ezetimibe may be added	Take the statin as prescribed; report muscle pain
Clots (no atrial fibrillation)	Long-term antiplatelet therapy; two antiplatelets for a short period after high-risk TIA or minor stroke	Acetylsalicylic acid (ASA), clopidogrel; ticagrelor with ASA as a short-term option	Do not stop without advice; report bleeding or black stools

Risk factor	Target or recommendation as the CSBPR states it	Medicines (named only)	Teaching
Atrial fibrillation	Oral anticoagulation; direct oral anticoagulant preferred over warfarin	Apixaban or another direct oral anticoagulant; warfarin	Never double or skip doses; report bleeding; carry a medication list
Smoking	Status asked and recorded in every setting; medicine plus counselling to quit	Nicotine replacement therapy, varenicline, bupropion	Avoid second-hand smoke; ask for quit support
Diet and weight	Mediterranean-type or DASH (Dietary Approaches to Stop Hypertension) eating pattern; limit sodium to 2,000 mg or less per day	None	Read labels for sodium; healthy weight targets differ across populations
Physical activity	At least 150 minutes per week of aerobic activity, 4 to 7 days a week, intensity individualized	None	Start with what is safe and build up with the rehabilitation team
Alcohol, drugs and hormones	Avoid heavy alcohol use; stop cocaine and amphetamines; estrogen-containing contraception or hormone therapy discouraged	None	Ask about safer contraception options

PATIENT EDUCATION

Stroke Warning Signs and Preventing Another Stroke

Before discharge, the nurse teaches the patient and family two things: how to spot a new stroke and how to prevent one.

- **Know FAST:** Heart & Stroke's FAST message asks: Face — is it drooping? Arms — can you raise both? Speech — is it slurred or jumbled? Time — to call 9-1-1 right away (Heart and Stroke Foundation of Canada, 2023). Section 31.2 describes the other signs.
- **Call, don't drive:** Do not drive to the hospital; the ambulance goes to a hospital that provides urgent stroke care (Heart and Stroke Foundation of Canada, n.d.-c). Note the time the signs started or the person was last seen well.
- **Treat a TIA as urgent:** Signs that go away still need emergency care.
- **Take medicines every day:** Antiplatelets, anticoagulants, statins and blood pressure medicines protect the brain only if taken. Never stop one without speaking to the prescriber.
- **Know your numbers:** Learn your blood pressure target and how to check it at home.
- **Build habits:** Stop smoking, limit sodium, be active most days and avoid heavy drinking (Heart and Stroke Foundation of Canada, 2020).
- **Keep follow-up visits:** See the primary care provider, ideally within the first month after discharge (Heart and Stroke Foundation of Canada, 2025d).

The nurse uses teach-back and gives written material in the person's preferred language, with pictures for people with aphasia.

CLINICAL JUDGMENT

Coughing at Lunch

Names and details are fictional; this is a composite story.

Tomasz Kowalczyk, 66, is on day 2 after a right hemisphere ischemic stroke with left arm weakness. He passed the nurse's swallowing screen yesterday and is eating a regular diet. At lunch, the nurse hears him cough three times while drinking tea. His voice now sounds wet and gurgly.

- **Recognize cues:** Coughing with fluids and a wet voice after swallowing. He is pocketing food in his left cheek. His oxygen saturation is 95%, unchanged; his temperature is 36.9 °C.
- **Analyze cues:** A screen is a first check, not a full assessment. These cues suggest that he is not handling thin fluids safely, and left neglect may stop him noticing food on his left side.
- **Prioritize hypotheses:** Aspiration of thin fluids is the main concern. Pneumonia has not developed yet, but the risk is high.
- **Generate solutions:** Stop oral intake for now, clear his mouth, keep him upright, inform the team and request an SLP assessment as policy directs.
- **Take action:** The nurse stops the meal, suctions the mouth per policy, sits him upright and checks his breathing. Using SBAR (Chapter 6), the nurse reports to the RN in charge and the physician, and refers him to the SLP. The nurse also asks the

pharmacist and prescriber how his noon medicines should be given while he is NPO. Mouth care removes the pocketed food.

- **Evaluate outcomes:** That afternoon, the SLP assesses him and recommends thickened fluids, supervised meals and cueing to check his left cheek. The nurse updates the care plan and the bedside sign. Over the next 48 hours his temperature, breathing and saturation stay normal, and he clears his left cheek when cued.

31.6 Rehabilitation, Transitions and Living After Stroke

Recovery after stroke continues long after the patient leaves the acute unit. In 2025, Heart & Stroke reorganized its CSBPR rehabilitation recommendations into three parts: planning rehabilitation, delivering it, and supporting activity and community participation (Heart and Stroke Foundation of Canada, 2025b, 2025c, 2025d). This section summarizes what the nurse needs to know from them.

Rehabilitation

Rehabilitation is the coordinated, goal-directed care that helps a person regain function and take part in daily life after illness or injury. The CSBPR states that every person with stroke should receive rehabilitation as early as possible once medically stable and able to take part (Heart and Stroke Foundation of Canada, 2025b). The plan is person-centred, decisions are shared, and goals are culturally appropriate and agreed on by the person (Heart and Stroke Foundation of Canada, 2025b). Rehabilitation needs are assessed early: the acute module asks rehabilitation professionals to assess each patient, ideally within 48 hours of admission, and to assess rehabilitation needs within the first 72 hours (Heart and Stroke Foundation of Canada, 2022). For inpatient rehabilitation, the CSBPR recommends direct, task-specific therapy for three hours a day, five days a week, once the person is medically and neurologically stable. Therapy uses repeated, demanding tasks that challenge the person (Heart and Stroke Foundation of Canada, 2025b).

The interdisciplinary team includes physicians, nurses, physiotherapists, occupational therapists, speech-language pathologists, dietitians, social workers and pharmacists, with the patient and family as members (Heart and Stroke Foundation of Canada, 2022). The CSBPR asks the team to help the person practise therapy skills in daily routines (Heart and Stroke Foundation of Canada, 2025b). Nurses do this all day: a patient who learned a safe transfer in physiotherapy uses the same steps to reach the toilet with the nurse, and a patient practising dressing with the occupational therapist dresses that way each morning. The same is true of the swallowing plan, communication strategies and toileting schedules: each works only if every shift follows it. Nurses also screen for depression at transition points, such as transfer to rehabilitation or discharge home (Heart and Stroke Foundation of Canada, 2025d). Table 31.4 links common effects of stroke to nursing strategies and team members.

Rehabilitation can also take place in outpatient clinics, at home, in long-term care and by video. The 2025 module includes virtual rehabilitation, which can extend therapy, education and transition planning to people far from a stroke centre (Heart and Stroke Foundation of Canada, 2025b). In **early supported discharge**, a rehabilitation team continues therapy at home so that a person with a mild or moderate stroke can leave hospital sooner; the CSBPR states that it should be considered where appropriate and that services should start within 48 hours of discharge from acute care (Heart and Stroke Foundation of Canada, 2025b). When function declines months or years later, the person should be able to re-enter rehabilitation (Heart and Stroke Foundation of Canada, 2025b, 2025d).

Table 31.4 Common effects of stroke and nursing strategies (Heart and Stroke Foundation of Canada, 2022, 2025c, 2025d; original wording)

Effect	What the nurse sees	Nursing strategies	Team member
Hemiparesis	Weakness of the arm and leg on one side; unsteady standing	Safe transfers that follow the therapy plan; fall prevention; position the weak limbs	Physiotherapist, occupational therapist
Hemiplegic shoulder	Painful or partly dislocated shoulder on the weak side	Support the arm at rest; never pull on it; no overhead pulleys; teach the family	Physiotherapist, occupational therapist
Dysphagia	Coughing or a wet voice with eating; pocketed food; weight loss	NPO until screened; follow the diet and fluid plan; upright for meals; mouth care	SLP, dietitian

Effect	What the nurse sees	Nursing strategies	Team member
Aphasia	Trouble finding words or understanding speech	Quiet setting, short sentences, yes or no questions, pictures, time	SLP
Unilateral neglect	Ignores one side of space or of the body	Cue scanning; check the neglected side for injury; keep the call bell within reach	Occupational therapist
Bladder and bowel changes	Incontinence, retention, constipation	Bladder scan, timed toileting, bowel program; remove catheters early	Trained continence staff, physician
Depression and fatigue	Low mood, tearfulness, loss of interest, tiredness	Screen with a validated tool; plan rest; refer early	Physician, psychologist, social worker

Going Home and Living After Stroke

Transitions of care are moves from one setting or team to another, such as from the stroke unit to rehabilitation, home or long-term care. The CSBPR states that transition planning begins at admission (Heart and Stroke Foundation of Canada, 2022). Families take part in transition planning meetings, and the CSBPR suggests a review with the primary care provider, ideally within the first month after discharge (Heart and Stroke Foundation of Canada, 2025b, 2025d). The nurse's handover includes the swallowing plan, mobility, communication needs, medicines and the goals set with the person. Before discharge, the nurse checks that the patient and family know the medicines, the follow-up appointments, whom to call with questions and when to call 9-1-1.

Caregivers. The CSBPR states that people with stroke and their families should be supported through every transition with psychosocial support, education and skills training (Heart and Stroke Foundation of Canada, 2025b). **Caregiver strain** is the physical, emotional and financial stress of caring for someone. The team assesses the caregiver's willingness and ability to learn care skills, how they are coping, and needs such as money, housing and transportation (Heart and Stroke Foundation of Canada, 2025b). Without enough support, caregivers may develop burnout, depression or anxiety. The evidence the CSBPR cites found depressive symptoms in about 40% of stroke caregivers and high burden in 35% of spouses six months after the stroke (Heart and Stroke Foundation of Canada, 2025b). The nurse teaches skills hands-on before discharge, such as transfers, safe feeding and medicine routines, and shares information about peer and caregiver support groups (Heart and Stroke Foundation of Canada, 2025b).

Driving. The CSBPR advises people not to drive for a minimum of one month after a stroke, consistent with national medical standards for drivers. After a TIA, the person does not drive until a full neurologic assessment shows no remaining loss of function and no clear risk that symptoms will suddenly return (Heart and Stroke Foundation of Canada, 2025d). Fitness to drive is assessed for vision, neglect, movement and thinking, sometimes with an on-road test, and provincial and territorial law governs reporting and licensing (Heart and Stroke Foundation of Canada, 2025d). In Ontario, physicians and nurse practitioners must report certain medical conditions to the Ministry of Transportation (section 30.5). People who cannot drive need help with other transportation and support for the loss of independence.

Work and community. The CSBPR asks the team to screen early for work, school and volunteer roles, to support a gradual return with accommodations, and to refer to vocational services and review finances and benefits (Heart and Stroke Foundation of Canada, 2025d). After discharge, primary care and community teams keep following the person. The CSBPR asks them to track recovery, to screen for changes in thinking, mood and anxiety compared with before the stroke, and to keep secondary prevention on track in every setting, including long-term care. People whose function declines should receive targeted help even years later, and everyone with stroke should have access to evidence-based community exercise programs (Heart and Stroke Foundation of Canada, 2025d). The CSBPR also addresses leisure, relationships and sexuality (Heart and Stroke Foundation of Canada, 2025d). The nurse invites questions about intimacy rather than waiting for the person to raise them.

Equity. The 2025 module states that equity in access to services must be considered at every stage of recovery (Heart and Stroke Foundation of Canada, 2025b). Rural and remote communities may lack local rehabilitation, so virtual rehabilitation and travel support matter. People who speak French or another language need professional interpreters and translated materials. Care with First Nations, Inuit and Métis people is distinctions-based and culturally safe, and it involves community health services and family (Chapter 2; section 31.3).

Severe Stroke and Palliative Care

Some strokes are catastrophic, or occur in people who already have serious illness. The CSBPR recommends a palliative approach for these patients (Heart and Stroke Foundation of Canada, 2022). The team discusses with the patient, if able, and the substitute decision-maker the diagnosis, prognosis, values and wishes, and whether the aim of care should be comfort or a longer life. These conversations continue as the situation changes and are documented (Heart and Stroke Foundation of Canada, 2022). Decisions about feeding tubes, intravenous fluids and other life-prolonging treatments consider the person's prior wishes and best interests (Heart and Stroke Foundation of Canada, 2022). The nurse manages pain, secretions, mouth and eye care, and supports the family, including after death (Heart and Stroke Foundation of Canada, 2022). For people living in the community after stroke, the CSBPR recommends revisiting the person's goals of care and advance care planning at intervals, for example yearly, and whenever health changes; these plans may name a substitute decision-maker and must follow provincial or territorial law (Heart and Stroke Foundation of Canada, 2025d). Goals of care and end-of-life care are covered in Chapter 10.

SCOPE IN PRACTICE

Stroke Care and Who Does What

The College of Nurses of Ontario's (CNO's) Scope of Practice standard asks every nurse to consider **authority**, **competence** and **context** (section 1.3).

- **Every nurse:** Any nurse who sees new stroke signs, such as a facial droop, arm drift or new trouble speaking, acts at once. The nurse notes the time the patient was last known well, checks glucose and calls for help per policy (section 31.2). No nurse waits for someone else to notice.
- **Dysphagia screening:** RNs and RPNs can screen swallowing when the employer authorizes it and they have completed the training for the employer's validated tool. A nurse who has not been trained keeps the patient NPO and finds a trained colleague.
- **Thrombolysis and titrated infusions:** Many employers limit giving thrombolytics and titrating intravenous antihypertensive infusions to RNs with specialized education. This is an employer policy based on context and competence, not a CNO rule.
- **Changing needs:** When a patient's condition changes or becomes less predictable, the RPN consults the RN and works with the team; the RN may take over parts of care as needs change.
- **Teaching and transitions:** Both RNs and RPNs teach patients and families and contribute to transition planning within their competence.

Employer policy and the province or territory matter. In other provinces, practical nurses (licensed practical nurses in many provinces) follow their own regulator's standards.

LIFESPAN CONSIDERATIONS

Stroke in Older Adults

Older adults. The risk of stroke rises with age (section 31.1). Atrial fibrillation becomes much more common with age (section 16.6), and lobar bleeds from cerebral amyloid angiopathy are a concern in this group (section 31.4). Several points need extra attention:

- **Delirium and baseline:** A new stroke and delirium can both cause sudden confusion. The nurse asks the family about the person's usual thinking and reports any change (Chapter 8).
- **Swallowing and nutrition:** Older adults may already have poor teeth, dentures that fit badly or low weight. The nurse checks dentures and weight and follows the swallowing plan.
- **Medicines:** Antithrombotic, blood pressure and statin therapy add to existing medicines. The nurse reviews the full list with the pharmacist and watches for dizziness, falls and bleeding.
- **Caregivers:** The caregiver is often an older spouse with health problems of their own. The team assesses the caregiver's capacity and needs before discharge.
- **Goals:** Recovery is still possible in later life. Rehabilitation goals are set with the person, not decided by age.

Younger adults. Stroke also occurs in younger adults, and the team may look for less common causes. Return to work, parenting and driving are often central goals.

Chapter 31 Summary

Introduction

- Much of the harm from stroke can be limited by fast treatment and by preventing complications, and nurses are often the first to see new signs.
- The chapter follows the Canadian Stroke Best Practice Recommendations and builds on the scope, CJMM, deterioration and neurologic assessment content of earlier chapters.

31.1 Understanding Stroke

- Ischemic strokes (thrombotic, embolic or small vessel) are caused by blocked arteries; hemorrhagic strokes (intracerebral or subarachnoid) are caused by bleeding.
- A TIA causes stroke signs that resolve fully, usually within an hour; it is a warning that calls for urgent assessment.
- The penumbra around the ischemic core can recover if blood flow returns in time; "time is brain."
- Heart & Stroke reports more than 108,000 strokes a year in Canada; high blood pressure is the most important modifiable risk factor.
- Women, First Nations people and rural and remote communities face particular risks and access gaps, shaped by structural causes such as colonization and distance from services.

31.2 Recognizing Stroke and Code Stroke

- FAST, as Heart & Stroke presents it: Face: is it drooping? Arms: can you raise both? Speech: is it slurred or jumbled? Time: to call 9-1-1. Other sudden signs include vision changes, severe headache, one-sided numbness and balance problems.
- Stroke causes weakness on the opposite side of the body; aphasia is typical of left hemisphere and neglect of right hemisphere strokes.
- Stroke mimics are common; glucose is checked early, but every sudden deficit is treated as a stroke until the team rules it out.
- Last known well, not the time signs were found, guides treatment; paramedics pre-notify and stroke centres run a code stroke with immediate CT and CTA.
- In-hospital strokes have had longer delays; the nurse acts at once as policy directs, and patients stay NPO, including oral medications, until a validated swallowing screen.

31.3 Hyperacute Treatment

- The CSBPR recommend thrombolysis with alteplase or tenecteplase for eligible patients with disabling ischemic stroke within 4.5 hours, with a median door-to-needle target of 30 minutes or less.
- Blood pressure is kept below 185/110 mm Hg before, during and for 24 hours after thrombolysis; monitoring frequency follows the employer protocol.
- Neurologic decline, a sudden rise in blood pressure or a new headache suggests intracranial hemorrhage; lip or tongue swelling suggests orolingual angioedema; both call for stopping the infusion and urgent help.
- Endovascular thrombectomy treats large vessel occlusions up to 24 hours from last known well in selected patients; the nurse checks the access site and limb.
- Organized stroke unit care by an interprofessional team improves survival and independence.

31.4 Hemorrhagic Stroke

- Intracerebral hemorrhage is bleeding into brain tissue; in Canada it accounts for 10% to 15% of hospital stroke cases and has higher mortality than ischemic stroke.
- The CSBPR checks blood pressure every 15 minutes at first and states that lowering systolic pressure below 140 mm Hg does not worsen outcomes; the long-term target is below 130/80 mm Hg.

- In anticoagulant-related ICH, the anticoagulant is withheld and immediate reversal is considered without waiting for laboratory results (section 19.7).
- Aneurysmal subarachnoid hemorrhage typically starts with a sudden, severe headache; the aneurysm is secured promptly by coiling or clipping.
- After SAH, the nurse watches for delayed cerebral ischemia, hydrocephalus, hyponatremia and rebleeding; enteral nimodipine helps prevent delayed cerebral ischemia.

31.5 Stroke Unit Care

- Nothing is given by mouth, including medications, until a trained professional screens swallowing with a valid tool; a failed screen leads to SLP assessment.
- The CSBPR advises against very early, high-intensity mobilization in the first 24 hours; mobilization begins once the patient is stable.
- The hemiplegic shoulder is supported and never pulled; high-risk patients receive IPC or anticoagulant prophylaxis, and compression stockings are not used.
- Aphasia calls for quiet, short questions, visual supports and time; all patients are screened for communication problems and for depression.
- Secondary prevention targets blood pressure, LDL cholesterol below 1.8 mmol/L, antithrombotic therapy, smoking, diet and activity; a TIA within 48 hours needs immediate emergency assessment.

31.6 Rehabilitation, Transitions and Living After Stroke

- Rehabilitation starts as early as the person is medically stable, with person-centred, culturally appropriate goals.
- Nurses help patients practise therapy skills in daily care.
- Caregivers need education, hands-on skills training, assessment of their own needs and links to support groups.
- The CSBPR advises no driving for a minimum of one month after a stroke, followed by an assessment of fitness to drive.
- After a catastrophic stroke, the team uses a palliative approach and holds ongoing goals-of-care discussions with the patient or substitute decision-maker.

Key Terms (43)

antiplatelet therapy: Medicines, such as ASA or clopidogrel, that keep platelets from clumping to form clots.

aphasia: A disorder of language that affects speaking, understanding, reading or writing.

aspiration: The entry of food, fluid, saliva or stomach contents into the airway below the vocal cords.

caregiver strain: The physical, emotional and financial stress of caring for someone.

cerebral amyloid angiopathy: A condition in which a protein called beta-amyloid builds up in the walls of small blood vessels in the outer brain and its coverings; a leading cause of bleeds in the outer lobes of the brain in older adults.

cerebral aneurysm: A weak, bulging area in the wall of a brain artery that can rupture and bleed.

clipping: Surgery in which the skull is opened and a clip is placed across the neck of an aneurysm.

code stroke: A hospital emergency process that brings the stroke team, imaging and laboratory together at once for a person with suspected acute stroke.

coiling: An endovascular treatment in which a catheter places small coils inside an aneurysm so that blood no longer enters it.

CT angiography (CTA): CT imaging with contrast dye that shows the arteries of the neck and brain and where an artery is blocked.

delayed cerebral ischemia: New brain ischemia that develops days after an aneurysmal subarachnoid hemorrhage, often linked to narrowing of brain arteries.

door-to-needle time: The time from hospital arrival to the start of thrombolysis.

dysarthria: Slurred or unclear speech caused by weak or poorly coordinated speech muscles, with language itself intact.

dysphagia screening: A brief check of swallowing safety, done by a trained professional with a valid tool before a patient with stroke takes anything by mouth.

early supported discharge: Rehabilitation provided at home by a specialized team so that a person with a mild or moderate stroke can leave hospital sooner.

endovascular thrombectomy (EVT): Removal of a clot from a large brain artery with a catheter threaded from an artery in the groin or wrist.

expressive aphasia: Aphasia in which the person understands more than they can say and struggles to find or form words.

FAST: Heart & Stroke's memory aid for the most common stroke signs: Face: is it drooping? Arms: can you raise both? Speech: is it slurred or jumbled? Time: to call 9-1-1.

hemiparesis: Weakness of the face, arm or leg on one side of the body.

hemiplegic shoulder: The shoulder on the weak side after a stroke, which can partly dislocate and become painful.

hemorrhagic stroke: A stroke caused by a blood vessel that ruptures and bleeds into or around the brain.

intracerebral hemorrhage (ICH): Bleeding into the brain tissue itself that is not caused by trauma.

ischemic core: The central area of an ischemic stroke, where blood flow is lowest and damage quickly becomes permanent.

ischemic stroke: A stroke in which a blocked artery deprives part of the brain, spinal cord or retina of blood until cells die.

large vessel occlusion (LVO): A blockage of a major brain artery, which may be treated with endovascular thrombectomy.

last known well (LKW): The last time a person was known to be at their usual self without the new stroke signs; used to time treatment when onset was not witnessed.

neglect: A disorder in which a person does not attend to one side of space or of their own body, most often the left side after a right hemisphere stroke.

nimodipine: A medicine given by the enteral route after aneurysmal subarachnoid hemorrhage to help prevent delayed cerebral ischemia.

orolingual angioedema: Swelling of the lips, tongue or throat that can follow thrombolysis and threaten the airway.

penumbra: Brain tissue around the ischemic core that has stopped working but can recover if blood flow returns in time.

post-stroke depression: Depression that develops after a stroke; about one-third of people show symptoms at some point.

receptive aphasia: Aphasia in which the person has trouble understanding spoken or written language.

rehabilitation: Coordinated, goal-directed care that helps a person regain function and take part in daily life after illness or injury.

secondary prevention: Care that lowers the risk of another stroke after a stroke or transient ischemic attack.

stroke: A sudden loss of brain, spinal cord or retinal function caused by a blocked or bleeding blood vessel, with evidence of injury on imaging.

stroke mimic: A condition, such as low blood glucose, seizure or migraine, that causes sudden stroke-like signs but is not a stroke.

stroke unit: A hospital unit in one fixed location, set aside for people with stroke, where a stroke-trained interprofessional team provides care.

subarachnoid hemorrhage (SAH): Bleeding into the space between the brain and its thin covering membranes, often from a ruptured aneurysm.

symptomatic intracranial hemorrhage: Bleeding in the brain that worsens the person's condition, the most serious complication of thrombolysis.

telestroke: A video assessment by a stroke physician at another centre to support treatment and transfer decisions.

thrombolysis: Treatment with an intravenous medicine, such as alteplase or tenecteplase, that dissolves a clot blocking an artery.

transient ischemic attack (TIA): A brief episode of stroke-like symptoms caused by ischemia, with no infarct on imaging; symptoms resolve within 24 hours, usually within an hour.

transitions of care: Moves of a patient from one setting or team to another, such as from the stroke unit to rehabilitation or home.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Edward Tran (Questions 1–4): Edward Tran, 68, is on a medical unit in Ontario with community-acquired pneumonia. He has hypertension and takes apixaban for atrial fibrillation. At 0100 the RPN found him awake, talking clearly and asking for a blanket. At 0300 the RPN finds him sitting up and unable to lift his left arm. His speech is slurred, and the left side of his mouth droops. He is alert and follows simple requests with his right hand. Blood pressure is 182/98 mm Hg, heart rate 94 and irregular, and oxygen saturation 95% on room air.

1. [CORE] Which time should the RPN report to the team as Mr. Tran's last known well?

a. 0300, because that is when the RPN first saw his weakness and slurred speech on rounds.

b. 0100, because that is the last time he was seen at his usual self without the new signs.

c. The time of his last dose of apixaban, because that time decides whether he may receive thrombolysis.

d. The time he was admitted to hospital, because his pneumonia may have caused the new deficits.

Answer: b — Last known well is the last time the person was known to be at baseline without the new signs (section 31.2, The First Hour). He was talking clearly at 0100. Option a is the time the signs were found, not when he was last well; using it would make the treatment window look longer than it is. Option c is important information the team also needs, but it is not the LKW time. Option d confuses the reason for admission with the onset of new signs.

2. [CORE] While help is on the way, which action should the RPN take?

a. Give Mr. Tran a sip of water so that he can take his scheduled oral antibiotic on time.

b. Lower the head of the bed flat and recheck his arm strength in 30 minutes to see whether it improves.

c. Give his scheduled dose of acetylsalicylic acid early, because it may help to dissolve the clot.

d. Check his capillary blood glucose with a point-of-care meter and report the value with the time.

Answer: d — Low glucose can mimic stroke and is quickly found and treated; a glucose check is recommended early in every suspected stroke (section 31.2, Clinical Safety: Check the Glucose). Option a is unsafe; he must stay NPO, including oral medications, until a validated swallowing screen is completed. Option b delays action; stroke treatment is time-critical. Option c is unsafe; antithrombotic medicine is never given until imaging rules out hemorrhage and the stroke team decides.

3. [CORE] Mr. Tran's glucose is 7.4 mmol/L. Which action by the RPN is most appropriate?

a. Activate the in-hospital code stroke or rapid response as policy directs and notify the RN at the same time.

b. Page the attending physician and wait at the nursing station for a return call before taking any further action.

c. Document the findings and plan to reassess him at 0400 with the next set of scheduled vital signs.

d. Call his daughter to ask whether he has ever had weakness like this before deciding whom to call.

Answer: a — Every nurse who finds new stroke signs acts at once and calls for help through the hospital's in-hospital code stroke or rapid response process, keeping the RN informed (section 31.2, The First Hour; Chapter 6). Option b leaves the patient and adds delay. Option c delays care for a time-critical emergency. Option d delays escalation; family information can be gathered while the team is on its way.

4. [CORE] Mr. Tran says, slowly and with slurred words, "I'm so thirsty. Can I have some juice?" Which response by the RPN is best?

a. "You can have a small sip of juice through a straw, which is safer for you than drinking from a cup."

b. "I know you're thirsty. You can't drink until your swallowing is checked. I'll moisten your mouth for you."

c. "Please try not to talk right now, because talking will make the weakness in your face and arm worse."

d. "The doctor will explain everything later, so try to rest and stop worrying about it until the doctor arrives."

Answer: b — The CSBPR keep people with suspected stroke NPO until a validated swallowing screen is done; the nurse explains this simply, acknowledges his thirst and offers mouth care as policy allows (section 31.2, The First Hour). Option a is unsafe because a straw does not make swallowing safe before screening. Option c is false and discourages communication. Option d dismisses his concern and gives no explanation.

5. [CORE] A patient asks why the team is rushing to treat her stroke. Which explanation by the nurse is most accurate?

a. "The whole area of your brain affected by the stroke died at the moment it began, so treatment now is only meant to prevent another stroke."

b. "The medicines work only if they are given within the first hour after the stroke, and after that they cannot help anyone."

c. "Around the most damaged area is brain tissue that has stopped working but can still recover if blood flow returns soon."

d. "Rushing treatment is mainly a hospital policy for keeping emergency department waiting times short for all patients."

Answer: c — The penumbra is tissue that has stopped working but can recover if blood flow returns before it becomes part of the core; "time is brain" (section 31.1, Why Time Matters). Option a is wrong; not all tissue dies at once. Option b is wrong; thrombolysis can be given within 4.5 hours of onset and clot removal up to 24 hours in selected patients. Option d misstates the reason for speed.

6. [CORE] A 59-year-old man reports that his right hand went numb and his speech was jumbled for 20 minutes yesterday, and that he now feels "back to normal." Which response by the nurse is best?

a. "Because your symptoms went away completely, this was most likely a pinched nerve and is not an emergency."

b. "If the same symptoms happen again and last more than 24 hours, then you should call 9-1-1 for an ambulance."

c. "Make an appointment with your family doctor within the next month to have your blood pressure and cholesterol checked."

d. "This sounds like a warning stroke. Stroke risk is highest in the next few days, so you need urgent assessment today."

Answer: d — Brief stroke-like symptoms that fully resolve suggest a TIA, a warning of stroke; risk is highest in the first 48 hours, and the CSBPR call for urgent assessment (section 31.1, Types of Stroke; section 31.5). Option a dismisses a TIA. Option b is unsafe; any new stroke sign calls for 9-1-1 at once, without waiting. Option c delays assessment far too long.

7. [CORE] The nurse teaches a community group about the FAST signs of stroke. Which statement by a participant shows a need for more teaching?

a. "If my husband's face suddenly droops on one side, I should call 9-1-1 even if his arms are fine."

b. "If my sister can't raise both of her arms, I should note the time and call 9-1-1 right away."

c. "If my father's speech is suddenly slurred or jumbled, that is one of the FAST signs of stroke I should act on."

d. "If I have stroke signs, I should drive myself to the nearest hospital because it is faster than waiting."

Answer: d — Heart & Stroke advises calling 9-1-1 and not driving to hospital, because an ambulance will take the person to the nearest hospital able to give urgent stroke care (section 31.2, Signs of Stroke). Options a, b and c are correct: one FAST sign is enough to act, and the time the signs began matters.

8. [CORE] Besides the FAST signs, which sudden signs can indicate a stroke? Select all that apply.

a. Blurred or double vision

b. A sudden, severe headache that usually comes with other signs

c. Numbness that mostly affects one side of the body

d. Trouble with balance

e. Gradual memory loss over several months

f. A dry cough that has lasted for two weeks

Answer: a, b, c, d — Heart & Stroke lists sudden vision changes, sudden severe headache, one-sided numbness and balance problems as less common signs of stroke (section 31.2, Signs of Stroke). Gradual memory loss (e) is not sudden and suggests another cause, such as dementia (Chapter 8). A two-week cough (f) is not a neurologic sign.

9. [CORE] A patient has an ischemic stroke in the right cerebral hemisphere. Which findings should the nurse expect?

a. Weakness of the left arm and leg and inattention to the left side of the body and space

b. Weakness of the right arm and leg and difficulty finding words and understanding speech

c. Weakness of both legs with normal arm strength and normal attention to both sides

d. Loss of hearing in the right ear with no weakness of the face, arms or legs

Answer: a — Each hemisphere controls the opposite side of the body, and neglect is more common after right hemisphere damage (section 31.2, Signs of Stroke). Option b describes a typical left hemisphere stroke. Option c does not fit a single hemisphere stroke. Option d is not a typical hemisphere stroke pattern.

10. [CORE] A 70-year-old man with type 2 diabetes who takes insulin is found confused, sweating, with slurred speech and weakness of the right arm. What should the nurse do first after calling for help?

a. Keep him NPO and wait for the CT scan, because a stroke is the most likely cause of his signs.

b. Ask him to drink a glass of orange juice right away, because the signs suggest low blood glucose.

c. Check his capillary blood glucose and treat a low value at once using the hypoglycemia protocol.

d. Give his scheduled insulin dose so that his glucose does not rise during the stroke assessment.

Answer: c — Hypoglycemia is a common stroke mimic that causes one-sided weakness and slurred speech; the glucose is checked early and a low value is treated at once by protocol, while stroke assessment continues (section 31.2, Stroke Mimics; section 22.4). Option a skips a quick, reversible cause. Option b is unsafe because his swallowing is uncertain; the protocol's non-oral route is used. Option d could worsen a low glucose.

11. [CORE] An RPN on a medical unit finds new facial droop and arm drift in a patient assigned to the RPN. The hospital's policy allows any nurse to activate the in-hospital code stroke. Which action reflects the RPN's role?

a. Ask the RN to come and confirm the findings before the RPN calls anyone, because only an RN may decide that a patient is unstable.

b. Wait until the RN has finished giving medications to another patient, then report the findings so that the RN can decide what to do.

c. Activate the code stroke as policy allows, stay with the patient and inform the RN, because every nurse acts at once on new stroke signs.

d. Transfer the patient's care to the RN and return to other assigned patients, because stroke care is outside the RPN's scope of practice.

Answer: c — Every nurse who notices deterioration acts at once and escalates; here the employer policy gives the RPN the authority to call the code stroke, and the RPN consults the RN as the patient's needs change (section 31.2, The First Hour; section 1.3). Options a and b delay time-critical care, and no CNO rule makes the RPN wait for an RN to escalate. Option d abandons the patient; the RPN continues to care for the patient within their competence while the team takes over.

12. [CORE] On a stroke unit, an RPN is caring for a patient who received tenecteplase 6 hours ago. The employer's policy states that patients in the first 24 hours after thrombolysis are assigned to an RN. What should the RPN do?

a. Continue the assignment, because CNO standards allow an RPN to care for any patient once 6 hours have passed since thrombolysis.

b. Discuss the assignment with the charge nurse, because the employer's policy sets this context in addition to the RPN's own competence.

c. Refuse to enter the room until the patient is 24 hours past treatment, because the RPN is not allowed to give any care to this patient.

d. Accept the assignment without comment, because an RPN's scope is defined only by the RPN's own competence and experience.

Answer: b — Using CNO's authority, competence and context, the RPN considers employer policy as part of the practice context and raises the mismatch with the charge nurse (section 1.3; section 31.3). Option a is wrong; CNO does not set time-based or patient-type rules for RPN assignments, and the employer policy applies. Option c is wrong; the RPN can still help and must act on any deterioration. Option d ignores context and employer policy.

13. [CORE] Thirty minutes into an alteplase infusion, a patient says, "I have a terrible headache," and vomits. The patient is now harder to rouse. What should the nurse do first?

a. Give the ordered antiemetic and an analgesic for the headache, then recheck the neurologic status in one hour.

b. Slow the infusion rate by half and recheck the patient's blood pressure in 15 minutes before calling anyone.

c. Raise the head of the bed and offer a few sips of water to help settle the patient's nausea.

d. Stop the infusion as the protocol directs and call the stroke physician at once for an urgent assessment.

Answer: d — A new headache, vomiting and a falling level of consciousness suggest intracranial hemorrhage; the infusion is stopped and the stroke physician called at once, with urgent CT to follow (section 31.3, Thrombolysis; Table 31.2). Option a treats symptoms and delays recognition of a bleed. Option b continues the thrombolytic and delays escalation. Option c gives fluid by mouth to a patient who may be unsafe to swallow and delays care.

14. [CORE] During an alteplase infusion, the nurse notices that the patient's upper lip and tongue are swelling. The patient takes ramipril, an ACE inhibitor, at home. Which action should the nurse take first?

a. Document the swelling and recheck it in 30 minutes, because mild swelling is expected during thrombolysis.

b. Stop the infusion if it is still running, call for help and assess the airway, preparing for airway support.

c. Give the patient a cold drink to reduce the swelling, because the cold will shrink the swollen tissue.

d. Tell the patient to stop taking ramipril after discharge, because it caused the swelling, and then continue the infusion.

Answer: b — Orolingual angioedema can threaten the airway; the CSBPR advise stopping the infusion at the first sign and treating it, and ACE inhibitor use is linked to higher risk (section 31.3, Thrombolysis). Option a delays care. Option c is unsafe; the patient is NPO and may not be able to swallow. Option d continues the trigger and leaves the airway risk untreated.

15. [CORE] Two hours after endovascular thrombectomy through the right femoral artery, the nurse finds a growing, firm swelling at the right groin site. What is the nurse's priority action?

a. Apply firm pressure above the site and call for help at once while checking the right leg's pulses and colour.

b. Help the patient walk to the bathroom so that the nurse can see whether the swelling gets worse with movement.

c. Apply a warm compress to the groin to improve blood flow and reduce the size of the swelling over the next hour.

d. Remove the dressing and wash the site with soap and water to check whether the swelling is caused by an infection.

Answer: a — A growing, firm lump at the access site suggests bleeding into the tissue; the nurse applies pressure, calls for help and checks circulation to the limb (section 31.3, Endovascular Thrombectomy; Table 31.2). Option b increases bleeding and is unsafe. Option c can increase bleeding. Option d delays treatment of a bleed and does not reflect the likely cause.

16. [CORE] Why is non-contrast CT of the head done first for a person with suspected acute stroke?

a. It shows the size of the penumbra exactly, so that the team knows how much brain can be saved.

b. It is used mainly to find out whether the person has had a stroke at some time in the past.

c. It shows whether there is bleeding in the brain, which changes treatment completely.

d. It replaces the need for a neurologic examination, so the team can skip that step to save time.

Answer: c — Non-contrast CT rules out hemorrhage, which decides whether clot-dissolving treatment can be considered; CTA then shows the blocked artery (section 31.2, The First Hour). Option a is wrong; perfusion imaging, not non-contrast CT, estimates tissue at risk. Option b is not its main purpose. Option d is wrong; the rapid neurologic examination is still done.

17. [CORE] A family member asks why their father is being moved to the stroke unit instead of staying on the general medical floor. Which reply by the nurse is most accurate?

a. "The stroke unit is mainly for patients who have had a hemorrhagic stroke; your father had a clot, so it is just where a bed was free."

b. "He will stay on the stroke unit only until his imaging is done, and then he will return to the medical floor for rehabilitation."

c. "On the stroke unit, a stroke-trained team works together, and people cared for there are more likely to survive and return home."

d. "Stroke units are used because they have more equipment for intensive care, such as a ventilator ready at every bed."

Answer: c — Organized stroke unit care by an interprofessional team lowers death and dependency, and patients are more likely to be alive, living at home and independent (section 31.3, The Stroke Unit). Option a is wrong; stroke units care for all stroke types. Option b misdescribes the unit's purpose. Option d confuses a stroke unit with an intensive care unit.

18. [RN] A 64-year-old woman with a large vessel occlusion is last known well 11 hours ago. Imaging shows a small core and a large area of penumbra, and the team plans thrombectomy. Her son asks how treatment can still help so late. Which explanation by the RN is most accurate?

a. "Her strong collateral vessels have kept the area at risk alive longer than usual, so restoring flow can still save that tissue."

b. "After 6 hours all of the tissue at risk has died, so the procedure now is only to prevent a second stroke in the same artery."

c. "Thrombectomy works at any time after a stroke, because the time since last known well no longer matters with modern treatment."

d. "The imaging shows that the stroke was caused by bleeding, which can be removed safely at any time after it starts."

Answer: a — Collateral circulation varies between people and can keep the penumbra viable for longer; selected patients with a small core and salvageable tissue can benefit from thrombectomy up to 24 hours from LKW (section 31.1, Why Time Matters; section 31.3, Endovascular Thrombectomy). Option b is wrong; imaging shows tissue still at risk. Option c is wrong; time still matters, and the window is limited. Option d is wrong; thrombectomy treats a blocked artery, not a hemorrhage.

19. [RN] Three hours after tenecteplase, a patient's blood pressure has risen from 168/90 to 204/110 mm Hg. She reports a new headache, and her NIHSS score has risen by 4 points. Which interpretation and action by the RN are best?

a. The headache is a common, harmless effect of tenecteplase, so the RN gives acetaminophen as ordered and rechecks in an hour.

b. These findings suggest a symptomatic intracranial hemorrhage, so the RN calls the stroke physician now and prepares for urgent CT.

c. The rise in NIHSS reflects normal fluctuation after stroke, so the RN continues neurologic checks at the scheduled interval.

d. The high blood pressure is the only problem, so the RN gives the ordered antihypertensive and waits for it to take effect.

Answer: b — The CSBPR name neurologic decline, a sudden rise in blood pressure and a new headache as signs of symptomatic intracranial hemorrhage after thrombolysis, calling for immediate assessment and non-contrast CT (section 31.3, Thrombolysis). Option a misses a bleed. Option c dismisses a 4-point rise. Option d treats one finding without recognizing the pattern; blood pressure is managed as ordered, but the physician is called at once.

20. [RN] A patient with an acute ischemic stroke is a candidate for thrombolysis. Her blood pressure is 196/112 mm Hg. Which statement reflects the CSBPR?

a. Thrombolysis can start now, because blood pressure is treated only if it rises above 220/120 mm Hg.

b. Blood pressure should be lowered quickly to below 120/80 mm Hg before treatment to prevent bleeding in the brain.

c. Blood pressure targets do not apply once thrombolysis has started, so the RN checks it only if the patient has symptoms.

d. Blood pressure should be lowered and kept below 185/110 mm Hg before and during treatment and for the next 24 hours.

Answer: d — For thrombolysis candidates, the CSBPR state that blood pressure is lowered and kept below 185/110 mm Hg as treatment starts, during it and for 24 hours (section 31.3, Thrombolysis). Option a confuses the threshold for patients who are not receiving reperfusion treatment. Option b is wrong; rapid or excessive lowering is avoided because the penumbra depends on blood pressure. Option c is wrong; close monitoring continues for 24 hours.

Case: Margaret Hill (Questions 21–26): Margaret Hill, 72, is on day 3 after a left hemisphere ischemic stroke with right-sided weakness and expressive aphasia. She failed the swallowing screen on admission. The SLP assessed her on day 2 and ordered a minced and moist diet with mildly thick fluids, upright positioning and supervision for all meals. At lunch, the nurse finds her daughter feeding her homemade chicken noodle soup with thin broth. Ms. Hill coughed several times. At 1900 the same day, her temperature is 38.3 °C, heart rate 104, respiratory rate 26, blood pressure 138/82 mm Hg and oxygen saturation 89% on room air, down from 95% that morning. Her voice sounds wet. Crackles are heard over the right lower lobe. Capillary glucose is 6.4 mmol/L. Her right-sided weakness is unchanged.

21. [CORE] Which findings at 1900 should the nurse recognize as cues that need follow-up? Select all that apply.

a. Temperature of 38.3 °C

b. Oxygen saturation of 89% on room air

c. Right-sided weakness that is unchanged from the morning

d. Crackles over the right lower lobe

e. Capillary glucose of 6.4 mmol/L

f. Wet-sounding voice and respiratory rate of 26

Answer: a, b, d, f — A temperature above 37.5 °C needs closer monitoring and a search for infection such as pneumonia (a; section 31.5). A fall in saturation from 95% to 89% shows worsening oxygenation (b). New crackles, a wet voice and a fast respiratory rate point to fluid or secretions in the lungs (d, f). Weakness that is unchanged is not a new neurologic cue (c). A glucose of 6.4 mmol/L is within a normal range and does not explain her findings (e).

22. [CORE] Which explanation best links Ms. Hill's findings?

a. The fever and crackles are signs of a urinary tract infection that has spread to the lungs through the bloodstream since admission.

b. Thin broth, which her swallowing plan did not allow, likely entered her airway and has led to aspiration pneumonia.

c. Her new stroke symptoms have extended to the brainstem, causing a fever and low saturation without lung involvement.

d. Her aphasia has made her anxious, and anxiety explains the rapid breathing, the fast heart rate and the wet-sounding voice.

Answer: b — She has dysphagia, was given thin fluids that her plan did not allow, coughed while eating, and now has fever, crackles, a wet voice and falling saturation, a pattern that suggests aspiration pneumonia (b; sections 31.5 and 13.2). Nothing suggests a urinary source (a). Her neurologic findings are unchanged, and crackles show lung involvement (c). Anxiety does not cause fever, crackles or low saturation (d).

23. [RN] Which hypothesis should the nurse treat as the priority at 1900?

a. Dehydration from limited fluid intake since admission, which needs an increase in thickened fluids offered by mouth tonight

b. Constipation from reduced mobility, which can cause fever in older adults and needs a bowel program started tonight

c. Aspiration pneumonia with hypoxemia, which can progress to respiratory failure and sepsis and needs escalation now

d. Post-stroke depression shown by refusing the hospital meals, which needs a validated screening tool used before discharge

Answer: c — Falling saturation, tachypnea, fever and crackles after likely aspiration threaten her airway and breathing, so aspiration pneumonia with hypoxemia is the priority (c; section 31.5; Chapters 4 and 6). Dehydration may need attention, but offering more fluids by mouth now is unsafe (a). Constipation does not explain her lung findings (b). Mood screening matters but is not urgent (d).

24. [CORE] What should the nurse do first?

a. Stop all oral intake, sit her upright, give oxygen per order or policy, and report to the RN and physician using SBAR.

b. Give acetaminophen by mouth with mildly thick fluids to lower the fever, and recheck her temperature in 1 hour.

c. Ask her daughter to bring a thicker soup tomorrow so that Ms. Hill can continue to eat the foods she likes.

d. Document the findings in her chart, increase vital signs to every 4 hours, and ask the night nurse to report any further change.

Answer: a — The nurse stops oral intake to prevent further aspiration, positions her upright, treats low saturation as ordered or per policy, and escalates at once with SBAR (a; section 31.5; Chapter 6). Giving medicine by mouth before her swallowing is reassessed adds risk (b). Changing the soup does not address her current deterioration (c). Waiting with less frequent checks delays care for a deteriorating patient (d).

25. [CORE] The physician orders a chest X-ray, antibiotics and NPO status. Which statement by the nurse to Ms. Hill's daughter is best?

a. "Your mother can have whatever she likes to eat as long as you stay with her and watch her closely while she eats."

b. "The soup caused this infection, so it is best that you do not visit at mealtimes for the rest of her stay in hospital."

c. "Thin liquids are the main problem, so any solid food from home is safe if you cut it into small pieces before feeding her."

d. "Her swallowing is not yet safe for thin liquids. The speech-language pathologist will reassess her, and we will show you how to help with meals."

Answer: d — The nurse explains the reason for the plan without blame, refers her to the SLP for reassessment and involves the daughter in supervised mealtime teaching (d; sections 31.5 and 24.3). Supervision alone does not make unsafe textures safe (a). Blaming the family and excluding them works against the CSBPR's call to include families as team members (b). Food from home must match the texture the SLP sets, so small pieces of any food are not automatically safe (c).

26. [CORE] Two days later, which finding best shows that Ms. Hill's care is working?

a. She asks for regular-textured toast and coffee with breakfast and says that she is hungry this morning.

b. Her temperature is 37.0 °C, her oxygen saturation is 95% on room air, and her chest is clear on auscultation.

c. Her daughter has brought a small blender so that she can prepare soups and other soft meals at home after discharge.

d. Her heart rate is 112, her respiratory rate is 24, and she is coughing up thick yellow sputum after meals.

Answer: b — A normal temperature, saturation back to her baseline and a clear chest show that the pneumonia is resolving (b; section 31.5). Asking for regular food shows appetite, not safe swallowing, and diet changes come from the SLP (a). A blender may help later, but it does not show her condition improving (c). Ongoing tachycardia, tachypnea and sputum after meals suggest that the problem persists (d).

27. [CORE] A patient with an intracerebral hemorrhage had a Glasgow Coma Scale score of 14 at 0800. At 1000 the score is 11, and the patient vomits and reports a worse headache. What should the nurse do?

a. Recheck the score in 1 hour, because a change of three points is expected in the first 24 hours after a hemorrhage.

b. Give the as-needed antiemetic and analgesic and document that the headache improved after treatment.

c. Call for urgent help now, keep the airway clear, and report the decline in score with the new signs using SBAR.

d. Lower the head of the bed flat to improve blood flow to the brain and wait for the physician's morning rounds.

Answer: c — A falling GCS score with vomiting and a worse headache suggests that the bleed or swelling is growing and ICP is rising, so the nurse escalates at once and protects the airway (c; sections 31.4 and 30.4; Chapter 6). A three-point drop is never an expected change (a). Treating symptoms and documenting hides a dangerous decline (b). Lying flat can worsen ICP, and waiting delays care (d).

28. [CORE] A 52-year-old man arrives at the emergency department. Which statement most strongly suggests subarachnoid hemorrhage?

a. "I have had a dull headache on and off for the past week, worse in the evening after a long day at work."

b. "My headache came on suddenly while I was lifting boxes. It is the worst headache of my life."

c. "I get headaches with flashing lights before them, usually about once a month, and today's feels the same."

d. "My headache started after I bumped my head on a cupboard door this morning, and now there is a small lump."

Answer: b — A headache that starts suddenly and is described as the worst of the person's life is the classic presentation of aneurysmal SAH (b; section 31.4). A recurring dull headache (a) and a familiar migraine pattern with aura (c) do not fit SAH. A minor bump with a lump suggests a local injury, which is assessed under head injury (d; Chapter 32).

29. [CORE] A patient admitted 30 minutes ago with an ischemic stroke asks for water to take her usual morning tablets. The swallowing screen has not been done. What should the nurse do?

a. Explain that nothing can be taken by mouth until her swallowing is screened, and arrange the screen and mouth care.

b. Give the tablets with a small sip of water while watching her closely for coughing, choking or a wet-sounding voice afterward.

c. Crush the tablets into applesauce, since puréed food is safe for people with dysphagia after a stroke.

d. Hold the tablets until discharge and record them as refused, because the stroke team will review them later.

Answer: a — The CSBPR states that a trained professional screens swallowing with a valid tool before any oral intake, including medications (a; section 31.5). A patient may aspirate silently, so watching for coughing is not safe (b). Puréed food is not automatically safe, and some tablets must not be crushed (c). Essential medicines are not simply withheld; the nurse reports the need for another route (d).

30. [CORE] A patient had an ischemic stroke 10 hours ago. A family member asks why the patient is not being walked in the hallway right away. What is the best response?

a. "Patients are kept on bed rest for a full week after a stroke so that the brain can heal before any movement."

b. "Patients are walked as far as possible within the first few hours, because the sooner they walk, the better."

c. "Guidelines advise against intense activity in the first 24 hours. The team will get your relative up once stable."

d. "Your relative will not walk until the rehabilitation unit, because nurses on the stroke unit do not mobilize patients."

Answer: c — The CSBPR advises against very early, high-intensity mobilization in the first 24 hours and starts mobilization once the patient is stable, ideally 24 to 48 hours after the stroke, with caution (c; section 31.5). A week of bed rest leads to complications (a). Intense walking in the first hours is the practice the CSBPR advises against (b). Nurses mobilize patients on the stroke unit with the team (d).

31. [CORE] A patient has a flaccid left arm after a stroke. Which actions protect the hemiplegic shoulder? Select all that apply.

a. Support the arm on a pillow or lap tray when the patient is sitting.

b. Help the patient move up in bed by pulling on both arms.

c. Teach the family to support the arm during transfers.

d. Set up an overhead pulley to keep the shoulder moving.

e. Avoid passive movement above 90 degrees unless the shoulder is positioned for it.

f. Keep the arm in a sling at all times, including after tone returns.

Answer: a, c, e — The CSBPR recommends supporting the arm at rest, teaching staff and family to handle it, protecting it during transfers and limiting passive movement above 90 degrees (a, c, e; section 31.5). Pulling on the weak arm (b) and overhead pulleys (d) can injure the shoulder. Slings are used only in the flaccid stage when no other support is possible and are discouraged afterward (f).

32. [CORE] A patient with expressive aphasia is trying to tell the nurse something. Which approach is best?

a. Speak loudly and slowly, because people with aphasia usually also have a hearing loss.

b. Finish each of the patient's sentences quickly so that the patient does not become frustrated.

c. Ask the family to answer for the patient so that the conversation is quicker and more accurate.

d. Reduce noise, ask short yes or no questions, offer a picture board, and give the patient time.

Answer: d — A quiet setting, short yes or no questions, visual supports and extra time help the person communicate (d; section 31.5). Aphasia is a language disorder, not a hearing problem (a). Finishing sentences for the patient can guess wrong and takes away the patient's voice (b). The patient remains the person the nurse speaks with; family can support but should not replace the patient (c).

33. [CORE] A patient with left unilateral neglect after a right hemisphere stroke is eating lunch. Which observation should the nurse expect?

a. Food eaten only from the right side of the tray

b. Inability to understand spoken instructions

c. Slurred speech with normal language content

d. Loss of sensation on the right side of the face

Answer: a — In left neglect, the person fails to notice the left side of space, so food on the left side of the tray is often left uneaten (a; section 31.5). Trouble understanding speech is receptive aphasia, which usually follows a left hemisphere stroke (b). Slurred speech with intact language is dysarthria (c). A right hemisphere stroke affects sensation on the left side of the body, not the right (d).

34. [CORE] Which statement about post-stroke depression reflects the CSBPR?

a. Screening is needed only after severe strokes, because mild strokes rarely affect mood in the first year.

b. Screening is done once, at admission, because the timing of post-stroke depression is well established in the research.

c. All people with stroke are screened if medically appropriate, by trained professionals using a validated tool.

d. Families are not screened or supported, because depression affects only the person who had the stroke.

Answer: c — The CSBPR states that all people with stroke should be screened for depression if medically appropriate, by trained professionals with a validated tool, especially at transition points (c; section 31.5). Depression can follow a mild stroke too (a). Repeated screening may be needed because the ideal timing is unclear (b). Family caregivers are also at risk of depression and need support (d).

35. [CORE] A patient says, "My arm went numb and weak for 20 minutes yesterday afternoon, but it is fine now." Based on the CSBPR, what should the nurse advise?

a. Book a routine appointment with your family doctor in the next few weeks, since the symptoms have gone away completely by themselves.

b. Take an ASA tablet at home and call 9-1-1 only if the numbness and weakness come back again later this week.

c. Go to an emergency department that provides stroke care immediately, because the risk of another stroke is highest now.

d. Rest for a few days and keep a diary of the symptoms to bring to the stroke prevention clinic next month.

Answer: c — The CSBPR states that people seen within 48 hours of new stroke or TIA symptoms are at the highest risk and should go at once to an emergency department able to provide stroke care (c; section 31.5). A routine visit (a) or a diary for next month (d) delays urgent assessment. Taking ASA before imaging is not the nurse's advice, and waiting for symptoms to return is unsafe (b).

36. [CORE] A patient who had a stroke 2 weeks ago is going home and asks, "When can I drive again?" What should the nurse explain?

a. "You may drive as soon as you feel confident, because the rules about driving apply only to commercial drivers."

b. "You can drive short distances right away if someone sits beside you to help watch the road."

c. "You can never drive again after a stroke, so we will help you sell your car before you go home."

d. "The guidelines advise not driving for a minimum of one month, and your team will check whether you are fit to drive."

Answer: d — The CSBPR advises not driving for a minimum of one month after a stroke and calls for assessment of fitness to drive, with provincial or territorial law governing licensing (d; section 31.6). Confidence alone does not show fitness, and the advice is not limited to commercial drivers (a). A passenger cannot make up for deficits such as neglect (b). Many people return to driving after assessment (c).

37. [CORE] An RPN on a stroke unit has not completed the employer's dysphagia screening training. A newly admitted patient is NPO and asks for a drink. What should the RPN do?

a. Use a screening tool the RPN learned in school, because any swallowing screen is acceptable on a stroke unit.

b. Keep the patient NPO, give mouth care, and ask a nurse trained in the employer's screening tool to complete the screen.

c. Give the patient a few ice chips, because ice chips do not count as oral intake during the stroke workup.

d. Tell the patient that only a physician may decide when a person with a stroke can drink, so the wait may be quite long tonight.

Answer: b — Screening is done by a trained professional with a valid tool that the employer authorizes, so a nurse without that training lacks competence and authority in this context (b; sections 31.5 and 1.3). Not every tool or method is acceptable (a). Ice chips are oral intake and can be aspirated (c). Trained nurses can screen when policy allows; it is not only a physician's decision (d).

38. [CORE] An RPN is caring for a patient on day 4 after an ischemic stroke. The patient suddenly cannot lift the left arm, which was strong an hour ago. What should the RPN do first?

a. Note the time the patient was last known well, check the glucose, and call for help at once per the in-hospital stroke policy, informing the RN.

b. Document the weakness and reassess at the next scheduled neurologic check in 4 hours, since some change is expected.

c. Wait for the RN to finish a medication pass before mentioning the change, because RPNs do not escalate neurologic changes.

d. Help the patient to the chair and encourage exercise of the arm to see whether the strength returns by itself with movement.

Answer: a — Every nurse who notices new stroke signs acts at once: noting the last known well time, checking glucose and activating help per policy, with the RN informed (a; section 31.2; Scope in Practice box, section 31.6). New weakness is not an expected change (b). RPNs escalate deterioration without delay (c). Moving the patient delays assessment and adds fall risk (d).

39. [RN] A patient with an acute intracerebral hemorrhage has a blood pressure of 188/96 mm Hg. Which statement reflects the CSBPR on blood pressure in acute ICH?

a. Blood pressure is not treated in the first 48 hours, because lowering it always reduces blood flow to the brain.

b. Systolic pressure is lowered to below 100 mm Hg within the first hour to stop the bleeding as fast as possible.

c. Blood pressure is checked every 4 hours, and treatment starts only if systolic pressure stays above 220 mm Hg for a day.

d. Lowering systolic pressure to below 140 mm Hg does not worsen neurologic outcomes, and blood pressure is checked every 15 minutes at first.

Answer: d — The CSBPR states that lowering systolic pressure to a target below 140 mm Hg does not worsen neurologic outcomes, that checks begin on arrival and every 15 minutes after that, and that an individual target below 140 to 160 mm Hg for 24 to 48 hours may be reasonable (d; section 31.4). Leaving high pressure untreated (a) and checking only every 4 hours with a very high threshold (c) do not match the CSBPR. A systolic pressure below 100 mm Hg is not a target and risks poor brain perfusion (b).

40. [RN] On day 7 after coiling of a ruptured aneurysm, a patient who had been alert becomes drowsy and confused and has new weakness of the right arm. The serum sodium is 129 mmol/L. Which interpretation and action are best?

a. These are expected effects of the anesthetic used during the coiling; the nurse reassesses at the next routine neurologic check.

b. These suggest delayed cerebral ischemia, possibly worsened by low sodium and volume loss; the nurse escalates immediately.

c. These suggest the aneurysm is still bleeding; the nurse restricts all fluids to 1 L per day to correct the sodium level.

d. These suggest a migraine; the nurse dims the lights, gives an as-needed analgesic and reassesses in 2 hours.

Answer: b — New neurologic decline days after aneurysmal SAH suggests delayed cerebral ischemia, and low sodium with volume loss can contribute, so the nurse reports at once (b; section 31.4). Anesthetic effects do not appear on day 7 (a). The aneurysm has been secured, and restricting fluid can worsen the low blood volume that sodium loss through the kidneys causes, which is linked to DCI (c; sections 31.4 and 3.4). A migraine does not explain new focal weakness and confusion (d).

References

Adams, H. P., Jr., Bendixen, B. H., Kappelle, L. J., Biller, J., Love, B. B., Gordon, D. L., & Marsh, E. E., III. (1993). Classification of subtype of acute ischemic stroke: Definitions for use in a multicenter clinical trial. TOAST. Trial of Org 10172 in Acute Stroke Treatment. *Stroke, 24*(1), 35–41. https://doi.org/10.1161/01.STR.24.1.35

Buck, B. H., Akhtar, N., Alrohimi, A., Khan, K., & Shuaib, A. (2021). Stroke mimics: Incidence, aetiology, clinical features and treatment. *Annals of Medicine, 53*(1), 420–436. https://doi.org/10.1080/07853890.2021.1890205

Elfil, M., Ghaith, H. S., Doheim, M. F., Aboutaleb, P. E., Romeo, D., Salem, M. M., Aladawi, M., Jankowitz, B. T., Burkhardt, J. K., Nguyen, T. N., Al-Mufti, F., & Nogueira, R. G. (2023). Transradial versus transfemoral access for mechanical thrombectomy: A systematic review and meta-analysis. *Stroke: Vascular and Interventional Neurology, 3*(4), Article e000758. https://doi.org/10.1161/SVIN.122.000758

Esposito, E., Shekhtman, G., & Chen, P. (2021). Prevalence of spatial neglect post-stroke: A systematic review. *Annals of Physical and Rehabilitation Medicine, 64*(5), Article 101459. https://doi.org/10.1016/j.rehab.2020.10.010

Eswaradass, P. V., Swartz, R. H., Rosen, J., Hill, M. D., & Lindsay, M. P. (2017). Access to hyperacute stroke services across Canadian provinces: A geospatial analysis. *CMAJ Open, 5*(2), E454–E459. https://doi.org/10.9778/cmajo.20160166

Heart and Stroke Foundation of Canada. (2020). *Canadian stroke best practice recommendations: Secondary prevention of stroke* (7th ed.). https://www.strokebestpractices.ca/recommendations/secondary-prevention-of-stroke

Heart and Stroke Foundation of Canada. (2022). *Canadian stroke best practice recommendations: Acute stroke management* (7th ed., 2022 update). https://www.strokebestpractices.ca/recommendations/acute-stroke-management

Heart and Stroke Foundation of Canada. (2023). *Know the signs of stroke* [Poster]. https://heartandstroke.ca/-/media/fast-poster-11x17-en-final.ashx

Heart and Stroke Foundation of Canada. (2025a). *Canadian stroke best practice recommendations: Acute stroke management. Section 5: Acute ischemic stroke treatment* (Endovascular thrombectomy interim update 2025). https://strokebestpractices.ca/recommendations/acute-stroke-management/acute-ischemic-stroke-treatment

Heart and Stroke Foundation of Canada. (2025b). *Canadian stroke best practice recommendations: Rehabilitation, recovery and community participation following stroke. Part one: Stroke rehabilitation planning for optimal care delivery* (7th ed.). https://www.strokebestpractices.ca/recommendations/stroke-rehabilitation-planning

Heart and Stroke Foundation of Canada. (2025c). *Canadian stroke best practice recommendations: Rehabilitation, recovery and community participation following stroke. Part two: Delivery of stroke rehabilitation to optimize functional recovery* (7th ed.). https://www.strokebestpractices.ca/recommendations/stroke-rehabilitation-delivery

Heart and Stroke Foundation of Canada. (2025d). *Canadian stroke best practice recommendations: Rehabilitation, recovery and community participation following stroke. Part three: Optimizing activity and community participation following stroke* (7th ed.). https://www.strokebestpractices.ca/recommendations/activity-participation-following-stroke

Heart and Stroke Foundation of Canada. (2025e). *Stroke Month 2025 backgrounder*. https://www.heartandstroke.ca/-/media/pdf-files/what-we-do/news/hsf-stroke-month-backgrounder-2025.pdf

Heart and Stroke Foundation of Canada. (n.d.-a). *FAST signs of stroke... what are the other signs?* Retrieved October 26, 2026, from https://www.heartandstroke.ca/stroke/signs-of-stroke/fast-signs-of-stroke-are-there-other-signs

Heart and Stroke Foundation of Canada. (n.d.-b). *Risk & prevention*. Retrieved October 27, 2026, from https://www.heartandstroke.ca/stroke/risk-and-prevention

Heart and Stroke Foundation of Canada. (n.d.-c). *Signs of stroke*. Retrieved October 26, 2026, from https://www.heartandstroke.ca/stroke/signs-of-stroke

Heart and Stroke Foundation of Canada. (n.d.-d). *Types of stroke*. Retrieved October 27, 2026, from https://www.heartandstroke.ca/stroke/what-is-stroke/types-of-stroke

Heran, M., Lindsay, P., Gubitz, G., Yu, A., Ganesh, A., Lund, R., Arsenault, S., Bickford, D., Derbyshire, D., Doucette, S., Ghrooda, E., Harris, D., Kanya-Forstner, N., Kaplovitch, E., Liederman, Z., Martiniuk, S., McClelland, M., Milot, G., Minuk, J., … Shamy, M. (2024). Canadian stroke best practice recommendations: Acute stroke management, 7th edition practice guidelines update, 2022. *Canadian Journal of Neurological Sciences, 51*(1), 1–31. https://doi.org/10.1017/cjn.2022.344

Hoffmann-La Roche Limited. (2024). *Activase rt-PA (alteplase for injection)* [Product monograph]. https://www.rochecanada.com/PMs/Activase/Activase_AIS_PM_E.pdf

Hoffmann-La Roche Limited. (2025a). *Health Canada authorizes TNKase® (tenecteplase) for the treatment of acute ischemic stroke (AIS)* [News release]. https://www.rochecanada.com/media/health-canada-authorizes-tnkase-tenecteplase-for-the-treatment-of-acute-ischemic-stroke-ais-

Hoffmann-La Roche Limited. (2025b). *TNKase (tenecteplase for injection)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00082731.PDF

Hoh, B. L., Ko, N. U., Amin-Hanjani, S., Chou, S. H.-Y., Cruz-Flores, S., Dangayach, N. S., Derdeyn, C. P., Du, R., Hänggi, D., Hetts, S. W., Ifejika, N. L., Johnson, R., Keigher, K. M., Leslie-Mazwi, T. M., Lucke-Wold, B., Rabinstein, A. A., Robicsek, S. A., Stapleton, C. J., Suarez, J. I., … Welch, B. G. (2023). 2023 guideline for the management of patients with aneurysmal subarachnoid hemorrhage: A guideline from the American Heart Association/American Stroke Association. *Stroke, 54*(7), e314–e370. https://doi.org/10.1161/STR.0000000000000436

Kapral, M. K., Shah, B. R., Green, M. E., Porter, J., Griffiths, R., Frymire, E., Slater, M., Jacklin, K., Sutherland, R., & Walker, J. D. (2020). Hospital admission for stroke or transient ischemic attack among First Nations people with diabetes in Ontario: A population-based cohort study. *CMAJ Open, 8*(1), E156–E162. https://doi.org/10.9778/cmajo.20190199

Korkmaz Dilmen, Ö., & Bonhomme, V. (2023). Management of aneurysmal subarachnoid haemorrhage and its complications: A clinical guide. *Turkish Journal of Anaesthesiology and Reanimation, 51*(3), 170–178. https://doi.org/10.4274/TJAR.2023.231205

Lyden, P. (2017). Using the National Institutes of Health Stroke Scale: A cautionary tale. *Stroke, 48*(2), 513–519. https://doi.org/10.1161/STROKEAHA.116.015434

Mangiardi, M., Bonura, A., Iaccarino, G., Alessiani, M., Bravi, M. C., Crupi, D., Pezzella, F. R., Fabiano, S., Pampana, E., Stilo, F., Alfano, G., & Anticoli, S. (2023). The pathophysiology of collateral circulation in acute ischemic stroke. *Diagnostics, 13*(14), Article 2425. https://doi.org/10.3390/diagnostics13142425

National Institute of Neurological Disorders and Stroke. (n.d.). *NIH Stroke Scale*. Retrieved October 26, 2026, from https://www.ninds.nih.gov/node/9970

Public Health Agency of Canada. (2017). *Stroke in Canada: Highlights from the Canadian Chronic Disease Surveillance System*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/stroke-canada-fact-sheet.html

Saltman, A. P., Silver, F. L., Fang, J., Stamplecoski, M., & Kapral, M. K. (2015). Care and outcomes of patients with in-hospital stroke. *JAMA Neurology, 72*(7), 749–755. https://doi.org/10.1001/jamaneurol.2015.0284

Saver, J. L. (2006). Time is brain—quantified. *Stroke, 37*(1), 263–266. https://doi.org/10.1161/01.STR.0000196957.55928.ab

Shoamanesh, A., Lindsay, M. P., Castellucci, L. A., Cayley, A., Crowther, M., de Wit, K., English, S. W., Hoosein, S., Huynh, T., Kelly, M., O'Kelly, C. J., Teitelbaum, J., Yip, S., Dowlatshahi, D., Smith, E. E., Foley, N., Pikula, A., Mountain, A., Gubitz, G., & Gioia, L. C. (2021). Canadian stroke best practice recommendations: Management of spontaneous intracerebral hemorrhage, 7th edition update 2020. *International Journal of Stroke, 16*(3), 321–341. https://doi.org/10.1177/1747493020968424

32 Traumatic Brain and Spinal Cord Injury and Chronic Neurologic Disorders

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Recognize concussion and traumatic brain injury, including hematomas in older adults on anticoagulants, and prevent secondary brain injury.
2. Provide early and ongoing care for adults with spinal cord injury, including spinal motion restriction, breathing, bladder, bowel and skin.
3. Recognize autonomic dysreflexia as an emergency and take the first actions in order.
4. Support adults living with multiple sclerosis and Parkinson disease, including giving Parkinson medications on time in hospital.
5. Recognize respiratory decline in myasthenia gravis and Guillain–Barré syndrome and escalate early, using the CJMM.
6. Support adults and families living with ALS and other progressive neurologic diseases, including advance care planning.
7. Distinguish RN and RPN roles in neurologic injury and chronic neurologic care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 5	Clinician; Scholar	Foundations of Practice
4, 6	Educator; Advocate	Foundations of Practice; Ethical Practice
7	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

An injury to the brain or spinal cord can happen in a second: a slip on an icy step, a crash on the highway, a hard check into the boards. Other neurologic diseases unfold over months or years. Both kinds of illness can change how a person moves, thinks, breathes and lives, and both ask nurses to notice small changes early. A patient who is a little drowsier after a head injury, a sudden rise in blood pressure in a person with a high spinal cord injury, or a weaker cough in a person with a neuromuscular disease can each be the first sign of a threat to life.

This chapter is the book's home for traumatic and chronic neurologic conditions in adults. Section 32.1 covers traumatic brain injury, from concussion to bleeding around the brain, with attention to older adults who fall while taking anticoagulants (blood thinners). Section 32.2 covers spinal cord injury: early care, breathing, autonomic dysreflexia and life after injury. The second half of the chapter turns to chronic and progressive disorders: multiple sclerosis (32.3), Parkinson disease (32.4), myasthenia gravis and Guillain–Barré syndrome (32.5), and amyotrophic lateral sclerosis and living with progressive neurologic disease (32.6).

The chapter builds on earlier ones. Scope of practice for registered nurses (RNs) and registered practical nurses (RPNs) is taught in section 1.3, and the Clinical Judgment Measurement Model (CJMM) in section 1.4. In other provinces and territories, practical nurses (PNs) are often called licensed practical nurses (LPNs); this chapter uses "the nurse" unless the roles differ. Neurologic assessment and the Glasgow Coma Scale (GCS) are in section 30.2, increased intracranial pressure (ICP) in section 30.4 and seizures in section 30.5. Recognizing deterioration, shock and rapid response are in Chapter 6, airway and ventilation in Chapter 15, anticoagulant reversal in Chapter 19, and fractures and spinal surgery in Chapter 33. Disability and accessibility are in Chapter 2.

32.1 Traumatic Brain Injury and Concussion

How Brain Injury Happens

A **traumatic brain injury (TBI)** is damage to the brain from an outside force, such as a blow to the head or a jolt that moves the brain quickly inside the skull (Ng & Lee, 2019; Poblete & Shaw, 2024). TBI is a major cause of injury in Canada. The Public Health Agency of Canada (PHAC) reports that more than 20,000 people are hospitalized for TBI each year (PHAC, 2020). From 2006/07 to 2017/18 there were 399,376 hospitalizations for head injuries in Canada, 63% of them among males, and falls were the leading cause. Rates of head injury hospitalization peaked among seniors over 85, at 897 per 100,000 males and 750 per 100,000 females (PHAC, 2020).

The cause of injury changes with age. In the PHAC (2020) report, falls were among the leading causes of TBI hospitalization for infants and for seniors aged 65 and older, sports and recreation for young teens aged 10 to 14, transportation for older teens and for adults of all ages, and assault for older teens and young adults aged 20 to 29. From 2002 to 2016, 22.6% of injury deaths in Canada involved a TBI, and TBI death rates rose sharply from age 65 (PHAC, 2020). These patterns point to prevention: fall prevention for older adults (Chapter 8), safe driving and helmets for younger adults.

Brain damage after trauma happens in two stages. **Primary brain injury** occurs at the moment of impact or sudden acceleration and deceleration (Poblete & Shaw, 2024). It may be **focal**, such as a bruise or a collection of blood in one area, or **diffuse**, spread through the brain when shearing forces stretch nerve fibres (Ng & Lee, 2019). Nurses cannot undo primary injury. **Secondary brain injury** is further damage in the hours and days that follow, from low oxygen, poor blood flow, swelling and harmful chemical changes in injured cells (Ng & Lee, 2019; Poblete & Shaw, 2024). Much of the nursing care in this section aims to prevent it.

Severity is often described with the GCS score after resuscitation: mild TBI is a score of 13 to 15, moderate 9 to 12, and severe 3 to 8 (Poblete & Shaw, 2024). The GCS itself is taught in section 30.2. Table 32.1 compares the main types of TBI.

Table 32.1 Types of traumatic brain injury: causes, signs and nursing focus (Government of British Columbia, 2024; Ng & Lee, 2019; Poblete & Shaw, 2024; Sundblom et al., 2022; Ottawa Hospital Research Institute, n.d.-a)

Injury	Typical cause	Key signs	Urgent nursing focus
Concussion (mild TBI)	A blow or jolt that moves the brain inside the skull, such as a fall, sports contact or collision	Headache, dizziness, blurred vision, fatigue, slowed thinking; brief loss of consciousness may or may not occur; standard imaging is normal	Check for red flags; give written and verbal teaching; plan follow-up and a gradual return to activity
Epidural hematoma	Impact to the head that causes bleeding between the skull and the dura	May lose consciousness briefly, wake and seem well, then become drowsy as the clot grows	Frequent neurologic checks even when the patient seems well; report any decline at once; prepare for urgent surgery
Acute subdural hematoma	Impact or rapid acceleration and deceleration that causes bleeding between the dura and the brain	A falling level of consciousness soon after injury; unequal or non-reacting pupils as pressure rises	Report decline at once; support oxygen and blood pressure; ask about anticoagulant or antiplatelet use
Chronic subdural hematoma	Often a low-energy fall in an older adult, sometimes weeks earlier or not remembered at all	New confusion or memory loss, headache, weakness, falls; may be mistaken for dementia	Treat new confusion as a possible brain injury; report; ask about falls and medications
Contusion	Impact that bruises brain tissue	Signs depend on the area injured; may worsen as swelling develops	Serial neurologic checks; prevent secondary injury
Diffuse axonal injury	Rapid acceleration and deceleration of the brain, without the need for a direct blow, that stretches and tears nerve fibres	Altered consciousness from the moment of injury; severity varies	Serial neurologic checks; prevent secondary injury; support the family

Concussion and Mild TBI

A **concussion** is a form of mild TBI in which a force, applied to the head or elsewhere on the body, makes the brain move rapidly inside the skull. The person may or may not black out briefly. Neurologic changes begin right away or within about 72 hours and usually settle on their own, and standard brain imaging, if done, shows nothing abnormal (Government of British Columbia, 2024). Concussion is a clinical diagnosis: the nurse and the clinician look for an injury that could reasonably have caused it, along with new signs, or symptoms that the examination supports (Government of British Columbia, 2024). Common symptoms include headache, dizziness, blurred vision, fatigue, trouble thinking, poor sleep and changes in mood (Government of British Columbia, 2024; Ottawa Hospital Research Institute, n.d.-b). In older adults, loss of consciousness is less common and GCS scores tend to be higher, so a concussion is easier to miss (Government of British Columbia, 2024).

Recognizing concussion. The Living Concussion Guidelines, the current Canadian guideline for adults, recommend that a suspected concussion be recognized as early as possible and that the person see a physician or nurse practitioner (NP), who confirms the diagnosis (Ottawa Hospital Research Institute, n.d.-a). The nurse asks how the injury happened, what the person remembers and how symptoms have changed since. Some findings point to a more serious injury and call for emergency care, including repeated vomiting (more than twice), a severe or worsening headache, increasing drowsiness, a seizure, new weakness or clumsiness, slurred speech, and ongoing fluid or blood from the ear or nose (*Brain Injury Advice Card*, n.d.). In the emergency department, the guideline lists factors that may justify keeping a person under observation, such as a GCS that stays abnormal, new focal neurologic signs, vomiting or severe headache, a bleeding disorder or anticoagulant use, ongoing intoxication, injuries to other body systems and age over 65 (Ottawa Hospital Research Institute, n.d.-a).

Deciding on a CT scan. Most people with concussion do not need imaging. The **Canadian CT Head Rule** (Stiell et al., 2001) is a clinical decision rule for people with a minor head injury. The BC guideline describes it as a way to rule out brain injuries that need neurosurgery without computed tomography (CT) in people older than 16 with a GCS of 13 to 15 (Government of British Columbia, 2024). The Living Concussion Guidelines recommend using it to decide on imaging in the first 24 to 48 hours, and note that it does not apply to people taking anticoagulants, who need extra consideration; plain skull x-rays are not recommended (Ottawa Hospital Research Institute, n.d.-a). The physician or NP applies the rule; the nurse makes sure that the history, including medications, reaches that clinician.

Rest and a graded return. Rest is brief. After a period of relative rest of about 24 to 48 hours, the guideline encourages a gradual return to daily activities, work and school, staying below the level of activity that clearly worsens symptoms (Ottawa Hospital Research Institute, n.d.-b, n.d.-c). Complete bed rest for more than three days should be avoided, and activities with a high risk of another concussion should be avoided, particularly in the first 7 to 10 days (Ottawa Hospital Research Institute, n.d.-c). A brief rise in symptoms with more activity is common. If symptoms worsen a lot or stay worse for more than about 24 hours, the person slows the pace (Ottawa Hospital Research Institute, n.d.-c). The BC guideline adds that the first 24 to 48 hours are a time of relative physical and mental rest, with little screen time and no driving; gentle activity, for example an easy walk, is fine if any rise in symptoms is small and passes quickly; and progress through its return-to-activity steps is no faster than one step per day (Government of British Columbia, 2024). Return to some form of work is encouraged when it does not risk another injury, with accommodations if needed. A person who still has symptoms should not drive (Ottawa Hospital Research Institute, n.d.-b, n.d.-c).

Persistent symptoms. Most adults are fully recovered and back to their usual activities within about a month (Ottawa Hospital Research Institute, n.d.-b). The BC guideline defines persisting symptoms as those lasting more than four weeks and states that at least one in six adults has them (Government of British Columbia, 2024). The Living Concussion Guidelines recommend follow-up with a primary care provider within one to two weeks, routine monitoring for depression and anxiety, and considering referral to interdisciplinary concussion services when symptoms last more than one month (Ottawa Hospital Research Institute, n.d.-b). The nurse teaches the person and a support person in writing and aloud, as the guideline recommends (Ottawa Hospital Research Institute, n.d.-a).

PATIENT EDUCATION

After a Concussion

Teach aloud and in writing, to the patient and a support person (Ottawa Hospital Research Institute, n.d.-a):

- **Go to the emergency department or call 9-1-1 for warning signs:** fainting, being very drowsy or impossible to wake; a constant severe headache, or one that is getting worse; throwing up more than twice; new confusion or trouble remembering new events; acting strangely or speech that makes no sense; a seizure; weakness, clumsiness or being unable to move part of the body; slurred speech or blurred vision; unsteadiness or loss of balance; or fluid or blood that keeps coming from the ear or nose (*Brain Injury Advice Card*, n.d.).
- **Rest briefly, then build up.** Take it easy for a day or two, then return to activities gradually. If symptoms stay worse for more than a day, slow down (Ottawa Hospital Research Institute, n.d.-c).
- **Avoid another head injury.** Stay out of contact sports and risky activities until a physician or NP says it is safe (Ottawa Hospital Research Institute, n.d.-c).
- **Do not drive** until symptoms have settled enough to drive safely (Ottawa Hospital Research Institute, n.d.-b).
- **Avoid alcohol, recreational drugs and sleeping pills** for at least the first 48 hours; they can make you feel worse and make it harder for others to tell whether the injury is affecting you (*Brain Injury Advice Card*, n.d.).
- **Expect recovery.** Most adults recover within about a month. See your primary care provider within one to two weeks (Ottawa Hospital Research Institute, n.d.-b).

Moderate and Severe TBI

Epidural hematoma. An **epidural hematoma** is a collection of blood between the skull and the dura, the tough outer covering of the brain. Some people lose consciousness briefly, wake up and seem well, then deteriorate as the clot grows. This period of seeming wellness is called the **lucid interval** (Ganz, 2013). A patient who is talking and joking can therefore still be in danger, and neurologic checks continue on schedule. A large clot is an indication for urgent surgery (Poblete & Shaw, 2024).

Subdural hematoma. A **subdural hematoma** is a collection of blood between the dura and the surface of the brain. An acute subdural hematoma appears soon after the injury and often causes a falling level of consciousness; a large one is removed surgically (Poblete & Shaw, 2024). A **chronic subdural hematoma** develops more slowly, often in older adults, when small veins that bridge from the brain surface to the dura tear after minor trauma and the collection keeps bleeding and growing (Sundblom et al., 2022). In one series of surgically treated patients, the mean age was nearly 80, falls on level ground were the most common cause, about half took an anticoagulant or antiplatelet medicine, the injury came from 72 hours to two months before diagnosis, and almost one-third had no known injury at all (Sundblom et al., 2022). Cognitive impairment was the main symptom in older adults and can be mistaken for dementia. Drainage through a small hole drilled in the skull (burr-hole drainage) improved neurologic function in most patients (Sundblom et al., 2022). Anticoagulant and antiplatelet medicines are a common cause of bleeding problems after TBI (Poblete & Shaw, 2024); reversal is covered in Chapter 19.

Contusion and diffuse axonal injury. A **contusion** is a bruise of brain tissue. **Diffuse axonal injury** is widespread stretching and tearing of nerve fibres caused by rapid acceleration and deceleration rather than a direct blow (Ng & Lee, 2019). Like other primary injuries, it typically alters consciousness from the moment of injury (Poblete & Shaw, 2024).

Preventing secondary injury. The injured brain is very sensitive to low oxygen and low blood pressure. The Emergency Neurological Life Support (ENLS) protocol for TBI from the Neurocritical Care Society recommends keeping oxygen saturation by pulse oximetry (SpO_2) at 94% or higher; keeping systolic blood pressure at or above 110 mm Hg for adults aged 15 to 49 or over 70, and at or above 100 mm Hg for those aged 50 to 69; raising the head of the bed to 30 degrees when ICP may be raised; keeping body temperature normal and preventing fever; and avoiding routine (prophylactic) hyperventilation, which is reserved for signs of brain herniation (Poblete & Shaw, 2024). The team may also consider a seizure-prevention medicine for the first seven days (Poblete & Shaw, 2024; section 30.5). The nurse also keeps values such as glucose and sodium within the targets the team sets. Managing raised ICP is taught in section 30.4.

Neurologic checks and escalation. The nurse performs neurologic checks, including GCS, pupils and limb strength, at the frequency ordered (section 30.2) and compares each result with the last. Using the CJMM (section 1.4), the nurse *recognizes cues* such as new drowsiness, a new headache, vomiting or a pupil change, *analyzes* them as possible bleeding or swelling, and *takes action* by reporting at once and calling the rapid response team if criteria are met (Chapter 6).

Agitation and post-traumatic amnesia. As people recover from moderate or severe TBI, many pass through **post-traumatic amnesia (PTA)**, a stage when awareness is poor and fluctuates, the person is disoriented, and new events are not reliably remembered. Its length helps predict outcome. The Canadian clinical practice guideline for rehabilitation after moderate to severe

TBI recommends assessing PTA repeatedly with a validated tool until it resolves, and keeping the person in a secure, supervised setting with low stimulation, consistent staff and orienting cues (KITE Research Institute, 2023). Restraints and sedating medicines are kept to a minimum, because antipsychotics and benzodiazepines may slow recovery and delay the person's emergence from PTA (KITE Research Institute, 2023). Agitation in PTA can look like delirium, which is covered in Chapter 8.

Supporting the family. Family members can play a useful role early in care (KITE Research Institute, 2023). The nurse explains what PTA and agitation mean, helps families keep visits short and calm when the person is easily overwhelmed, and includes them in planning for rehabilitation.

LIFESPAN CONSIDERATIONS

Head Injury in Older Adults

In older adults, falls cause more concussions than any other mechanism, and medicines such as sedatives, psychotropics and antithrombotics can increase the risk of injury (Government of British Columbia, 2024). In Canada, rates of hospitalization for head injury peak among people over 85 (PHAC, 2020).

- **Anticoagulants change the decision.** The Canadian CT Head Rule does not apply to people taking anticoagulants, and the Living Concussion Guidelines call for extra consideration of these patients; age over 65 and a bleeding disorder are among the factors that may justify observation (Ottawa Hospital Research Institute, n.d.-a). An older adult who hits their head while taking an anticoagulant is assessed promptly by a physician or NP, even if they seem well. Reversal of anticoagulants is in Chapter 19.
- **Signs can be subtle.** Older adults lose consciousness less often and may have a near-normal GCS after a concussion (Government of British Columbia, 2024).
- **Late bleeding.** A chronic subdural hematoma can appear days to weeks after a minor fall, or with no fall remembered, as new confusion, memory loss, weakness or more falls (Sundblom et al., 2022). The nurse does not assume that new confusion is dementia or delirium alone (Chapter 8) and reports it.

32.2 Spinal Cord Injury

Types and Levels of Injury

A **spinal cord injury (SCI)** is damage to the spinal cord that interrupts messages between the brain and the body below the injury, affecting movement, sensation and automatic functions such as blood pressure, bladder and bowel control. A **traumatic SCI** results from an outside force, such as a fall or a collision. A **non-traumatic SCI** results from disease; in Canada's national SCI registry, the most common cause of non-traumatic SCI was degenerative disease, followed by tumours (malignant, then benign), inflammation, vascular disorders, congenital or genetic disorders and infection (Praxis Spinal Cord Institute, 2024; Figure 32.1).



Figure 32.1 Cross-section of the thoracic spinal cord showing the sensory (posterior), autonomic (lateral) and motor (anterior) grey-matter horns and the surrounding white-matter tracts (cropped to the anatomical diagram panel). (credit: modification of "Figure 13.14, Cross-section of Spinal Cord" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Praxis Spinal Cord Institute (2024) estimates that about 86,000 people in Canada live with SCI, about 30,000 of them after a traumatic injury, and that about 1,100 people are discharged from hospital with a new traumatic SCI each year. Among registry participants in 2022, falls were the most common cause of traumatic SCI, followed by transportation, sports, other causes (such as work-related injuries) and assault. The average age at injury was 55 years for participants with traumatic SCI and 62 for those with non-traumatic SCI, and 76% of participants with traumatic SCI were male (Praxis Spinal Cord Institute, 2024).

Level. The **neurologic level of injury** is the lowest segment of the spinal cord with normal sensation and antigravity muscle strength on both sides, with all function above it intact (Snider et al., n.d.). An injury to the cervical (neck) cord causes **tetraplegia**: weakness or paralysis that affects the arms, trunk and legs. An injury to the thoracic, lumbar or sacral cord causes **paraplegia**, which spares the arms but affects the trunk, legs or both, depending on the level. Among people with traumatic SCI in the registry, tetraplegia was more common than paraplegia (Praxis Spinal Cord Institute, 2024; Figure 32.2).

Completeness. An injury is **complete** when no sensation or movement is preserved in the lowest sacral segments (S4–S5), around the anus. It is **incomplete** when some sensation or voluntary movement remains there, which means some messages still cross the injury (Snider et al., n.d.). Incomplete injuries were more common than complete ones in the Canadian registry (Praxis Spinal Cord Institute, 2024). Table 32.2 summarizes the function usually expected at each level after a motor-complete injury, in which no voluntary movement is kept below the level (Consortium for Spinal Cord Medicine, 2026).



Figure 32.2 Human dermatome map showing the cutaneous sensory territories supplied by spinal nerves C2 through S5, used alongside key muscle testing to determine the neurologic level of spinal cord injury. (credit: "1611 Dermatomes-02" by OpenStax Anatomy and Physiology/Wikimedia Commons, CC BY 4.0)

Table 32.2 Spinal cord injury level and expected function after a motor-complete injury (Consortium for Spinal Cord Medicine, 2026; Jang, 2020; Peterson & Delparte, 2022)

Level	Muscles and function kept	Breathing	Main care needs
C1 to C4	Face and neck muscles; talking, chewing and sipping; partial diaphragm and shoulder shrug at C3 to C4	Diaphragm weak or not working; a ventilator is often needed	Airway and ventilator care; suctioning; full assistance with care; power wheelchair with head, chin or breath controls; autonomic dysreflexia risk
C5	Shoulder movement and elbow bending (biceps)	Diaphragm works, but chest and abdominal muscles do not; weak cough and lower vital capacity	Assisted cough; full help with bladder and bowel care; mechanical lift, or a transfer board with help, for transfers; autonomic dysreflexia risk
C6	Wrist extension, which allows a tenodesis grasp	As for C5	Some help with bladder and bowel care; may manage some tasks with adaptive equipment; autonomic dysreflexia risk
C7 to C8	Elbow straightening (triceps), wrist and finger movement	As for C5, with weak cough	Independent bladder and bowel care with adaptive equipment; manual wheelchair; autonomic dysreflexia risk
T1 to T12	Arms fully; trunk control improves the lower the level; abdominal muscles from T7 down	Breathing and cough improve the lower the level	Manual wheelchair; skin and pressure care; autonomic dysreflexia risk at T6 and above
L1 to S1	Hip and knee movement; lower levels add ankle and foot movement	Main breathing muscles spared	May walk with aids and braces; wheelchair for long distances; bladder, bowel and skin care

GOING DEEPER

Classifying Spinal Cord Injury (ISNCSCI and the ASIA Impairment Scale)

Required for RN students; optional for PN students.

The **International Standards for Neurological Classification of Spinal Cord Injury (ISNCSCI)**, maintained by the American Spinal Injury Association (ASIA), describe how to examine and classify SCI. The current standard is the 2019 revision (American Spinal Injury Association, n.d.; Rupp et al., 2021). The examiner tests light touch and pinprick in each dermatome, key muscles on both sides, deep anal pressure and voluntary anal contraction. The neurologic level of injury is the higher of the sensory and motor levels (Snider et al., n.d.).

The **ASIA Impairment Scale (AIS)** grades completeness (Snider et al., n.d.):

- **AIS A, complete:** no sensory or motor function preserved in the lowest sacral segments, S4–S5.
- **AIS B, sensory incomplete:** sensation, but not motor function, is preserved below the neurologic level and includes S4–S5, and no motor function is preserved more than three levels below the motor level on either side.
- **AIS C, motor incomplete:** motor function is preserved below the level (voluntary anal contraction, or, in a sensory incomplete injury, some motor function more than three levels below the motor level), and less than half of the key muscles below the neurologic level have a muscle grade of 3 or more (movement against gravity).
- **AIS D, motor incomplete:** motor incomplete as in AIS C, but half or more of the key muscles below the neurologic level have a muscle grade of 3 or more.
- **AIS E, normal:** sensation and motor function test normal in all segments in a person who had deficits from a documented SCI.

A label such as "C5 AIS B" gives level and completeness at a glance; repeat examinations track change.

Early Care

Spinal motion restriction. Ontario's paramedic standards direct paramedics to consider **spinal motion restriction**, keeping the spine as still as possible, for any patient who may have a spine or spinal cord injury (Ontario Ministry of Health, 2023). Risk criteria include spine tenderness, neck or back pain, neurologic signs or symptoms, an altered level of consciousness, suspected intoxication, a distracting painful injury, a deformity of the spine and a high-energy mechanism, which for a person aged 65 or older includes a fall from standing height. The standard uses a cervical collar, applied before moving the patient when possible, and secures the patient to the stretcher. Patients are log rolled off extrication devices when enough staff are present, and rigid spine boards are removed as soon as it is safe (Ontario Ministry of Health, 2023; Figure 32.3).

In hospital, the nurse continues these precautions until a physician or NP documents that the spine is cleared or stable. A **log roll** turns the patient with the head, shoulders, trunk and hips moving together as one unit, so that the spine does not twist; it needs enough trained staff, and employer policy sets the technique. Skin under and around a cervical collar is checked as policy directs, because medical devices can cause pressure injuries (Chapter 35). Spinal fractures and surgery are covered in Chapter 33.

Breathing. The diaphragm, the main muscle for breathing in, is supplied mainly by spinal nerves C3 to C5 through the phrenic nerve. The intercostal and abdominal muscles, supplied by thoracic nerves, help force air out and produce a strong cough (Jang, 2020). Injuries in the cervical and upper thoracic cord therefore reduce lung volumes, vital capacity and cough strength, and the higher the injury, the greater the need for a ventilator (Jang, 2020). Between 36% and 83% of people with acute SCI develop respiratory complications. The most common are respiratory failure and atelectasis, and pneumonia is more frequent with higher and more severe injuries (SCIRE Professional, 2023). Intense secretion management has been suggested as the key to prevention, and chest percussion, postural drainage and manually assisted coughing have been reported to reduce deaths from lung complications (SCIRE Professional, 2023). In a **manually assisted cough**, the nurse or a trained caregiver presses on the abdomen or chest just as the patient breathes out to cough; machines can also assist a cough (Jang, 2020). An abdominal binder puts pressure around the abdomen to help keep the diaphragm in a better position for breathing (Jang, 2020). The nurse reports at once any increase in breathing effort, a weaker cough, thicker or more secretions, or a fall in oxygen saturation. Airway management and ventilation are covered in Chapter 15.

Spinal shock and neurogenic shock. Two terms are often confused. **Spinal shock** is a temporary state, beginning immediately after SCI, in which reflexes carried by the spinal cord are lost below the injury (SCIRE Community, 2024). It is a change in reflexes, not a circulation problem. **Neurogenic shock** is low blood pressure together with a slow heart rate, with no other cause, after a cervical or

Figure 32.3 A rigid cervical collar applied to restrict cervical spine motion until spinal injury is ruled out or stabilized (upper facial profile pixelated). (credit: modification of "LateralCollar" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

high thoracic SCI; the injury suddenly cuts sympathetic nerve output, so blood vessels relax and the heart slows (SCIRE Professional, 2022). The slow heart rate helps tell it apart from shock caused by blood loss, in which the heart rate is usually fast. Shock is managed as described in Chapter 6. An international guideline panel suggests keeping the mean arterial pressure (MAP) at no less than 75 to 80 mm Hg, and not actively raising it above 90 to 95 mm Hg, for three to seven days after acute SCI; both are weak recommendations based on very low-quality evidence (Kwon et al., 2024).

Venous thromboembolism. Immobility after SCI slows blood flow in the legs. Deep vein thrombosis has its highest incidence in the first three months after injury, with most events in the first two weeks, and it can lead to a fatal pulmonary embolism; prevention uses medicines and mechanical methods (Mirkowski et al., 2020). Venous thromboembolism (VTE) prevention is covered in Chapter 19.

Autonomic Dysreflexia

Autonomic dysreflexia (AD) is a sudden rise in blood pressure of 20 to 40 mm Hg above the person's usual level, triggered by an irritating stimulus below the level of SCI (Alberta Health Services [AHS], 2021). It typically occurs with injuries at T6 or above (AHS, 2021). The stimulus sets off a strong reflex that narrows blood vessels below the injury, and because messages from the brain cannot pass the injury, the reflex continues until the cause is removed. Most people at risk have their first episode within six months of injury (Peterson & Delparte, 2022). Untreated AD can cause a stroke, a seizure or death (AHS, 2021).

Triggers. A full bladder is the most common cause, including a blocked or kinked catheter. Other causes are a full bowel or constipation, pressure on the skin from lying or sitting on something hard, tight clothing or devices, skin wounds and ingrown toenails, infections, menstrual cramps, sexual activity and procedures (AHS, 2021; Peterson & Delparte, 2022).

Recognizing AD. Signs include a pounding headache, flushing and sweating above the injury, pale or cool skin and goosebumps below it, blurred vision, a stuffy nose, anxiety and a slow heart rate (AHS, 2021; Peterson & Delparte, 2022). Because flushing is easier to see on some skin tones than others, the nurse does not rely on colour alone: the patient's report, sweating and the blood pressure reading matter more. Many people with an injury at T6 or above have a usual systolic pressure of about 90 to 110 mm Hg, so a systolic reading above 130 mm Hg, which would not alarm most clinicians, can be a sign of AD (Peterson & Delparte, 2022). Knowing the patient's baseline is essential.

First actions. AD is an emergency, and any nurse who recognizes it acts at once. Alberta's adult protocol lists these steps in order (AHS, 2021):

- Ask the patient whether they know what is causing it; many people with SCI recognize their own triggers.
- Sit the patient up at 90 degrees; lowering the legs also helps lower blood pressure (Peterson & Delparte, 2022).
- Remove the cause if it is known, and loosen tight clothing, straps and devices.
- Check the blood pressure every 2 to 5 minutes.
- Check the bladder: look for a kinked, clamped or blocked catheter and a full drainage bag, or empty the bladder as ordered.
- Check the bowel for stool, gently and following the employer's protocol.

- Check the skin for pressure areas, wounds and anything tight.

The nurse notifies the physician or NP (and the RN, when an RPN holds the assignment) early, and calls the medical emergency or rapid response team if the blood pressure does not come down or the patient becomes unresponsive (AHS, 2021). Medicines to lower blood pressure are given only as ordered. After the episode, blood pressure is checked often and the nurse watches for low blood pressure (Peterson & Delparte, 2022). The nurse documents the trigger and teaches prevention.

Teaching. People at risk, and their families and caregivers, learn the signs, the first steps and their usual blood pressure. They are encouraged to carry a wallet card that lists these, and to show it to health care staff, who may not know about AD (Peterson & Delparte, 2022). Prevention includes regular bladder and bowel routines, catheter tubing that drains freely, loose clothing, regular skin checks and early treatment of infections (Peterson & Delparte, 2022).

CLINICAL SAFETY

Autonomic Dysreflexia Is an Emergency

A person with an SCI at T6 or above who reports a pounding headache, or who looks flushed and sweaty above the injury, may have dangerously high blood pressure (AHS, 2021).

- **Do not lay the patient flat.** Sit them up at 90 degrees and lower the legs (AHS, 2021; Peterson & Delparte, 2022).
- **Check the blood pressure at once and every 2 to 5 minutes.** Compare it with the person's usual reading, which is often low; a "normal-looking" pressure may be high for them (AHS, 2021; Peterson & Delparte, 2022).
- **Look for the cause, starting with the bladder,** then the bowel, then the skin and clothing (AHS, 2021).
- **Call for help early.** Notify the physician or NP and the RN, and activate the emergency response if the pressure does not fall or the patient becomes unresponsive (AHS, 2021).
- **Watch afterward** for low blood pressure once the cause is removed (Peterson & Delparte, 2022).
- **Record the person's usual blood pressure and known triggers** in the care plan so that every shift can act quickly.

Ongoing Care and Rehabilitation

After the acute phase, care shifts to preventing complications and building independence.

- **Bladder:** People with SCI often need a planned bladder program to empty the bladder regularly. A full bladder is the most common trigger of AD (AHS, 2021). Catheters and urinary retention are covered in Chapter 28.
- **Bowel:** A regular bowel routine prevents constipation, accidents and AD (Peterson & Delparte, 2022). Bowel programs are covered in section 25.1.
- **Skin:** Loss of sensation and movement puts skin at high risk. Regular position changes, pressure redistribution and daily skin checks are taught in Chapter 35.
- **Temperature:** People with tetraplegia or an injury at T6 or above usually have more trouble regulating body temperature than people with lower injuries. People with tetraplegia can have episodes of low body temperature in a normal room and are more affected by cold (SCIRE Professional, 2025). The nurse checks temperature, adjusts covers and room temperature, and teaches the person to avoid extremes.
- **Spasticity: Spasticity** is increased muscle tone with involuntary spasms and overactive reflexes. It affects up to three-quarters of people with SCI, especially those with cervical or incomplete injuries (SCIRE Community Team, 2017). It can help with transfers and standing but can also cause pain, contractures and skin breakdown. A sudden or unexplained change may point to a new health problem, most often a bladder infection or skin breakdown, so the nurse looks for a cause (SCIRE Community Team, 2017).
- **Sexuality and fertility:** These are important parts of rehabilitation and are covered in Chapter 29.
- **Mood and adjustment:** Adjusting to SCI takes time. The nurse asks about mood, sleep, substance use and thoughts of self-harm, and helps the person reach mental health care and peer support; the Consortium for Spinal Cord Medicine publishes a guideline on mental health disorders, substance use and suicide in adults with SCI.

Rehabilitation and community living. Rehabilitation teams help each person reach the function expected for their level and completeness of injury (Consortium for Spinal Cord Medicine, 2026). In the Canadian registry, 90% of people with non-traumatic

SCI went home to the community after rehabilitation, and 44% developed at least one secondary complication while in rehabilitation (Praxis Spinal Cord Institute, 2024). Living in the community depends on accessible housing, transportation, equipment, attendant care and work. Accessible care, including asking the person how they want to be moved and helped, is taught in Chapter 2. People with SCI are the experts on their own bodies and routines, and the nurse plans care with them.

32.3 Multiple Sclerosis

Multiple sclerosis (MS) is a long-term autoimmune disease that affects the central nervous system (CNS). Its course is hard to predict, and many people move between periods of new or worse symptoms and periods of recovery (Public Health Agency of Canada [PHAC], 2024). MS is usually diagnosed in early adulthood, at a time of study, work and raising children. Nurses often meet people with MS when they are admitted for another reason.

What Happens in MS

In MS, the immune system damages **myelin**, the fatty covering that insulates nerve fibres in the optic nerves, brain and spinal cord (PHAC, 2024). This damage is called **demyelination**. Without intact myelin, nerve signals travel slowly or not at all, so the symptoms depend on where the damaged areas lie. A lesion in the optic nerve blurs vision; one in the spinal cord can cause weakness, numbness or bladder problems. On magnetic resonance imaging (MRI), new or enlarging lesions are one sign of active disease (Oh et al., 2025).

Course of the disease. MS Canada (then the Multiple Sclerosis Society of Canada, 2021) describes several forms:

- **Clinically isolated syndrome (CIS):** a single episode of symptoms that suggests MS.
- **Radiologically isolated syndrome (RIS):** MRI findings that strongly suggest MS in a person with no symptoms.
- **Relapsing-remitting MS (RRMS):** clear relapses followed by recovery. It is the most common diagnosis at first; about 90% of Canadians with MS are first diagnosed with this form.
- **Secondary progressive MS (SPMS):** a later phase that most people with RRMS eventually enter, with fewer relapses and gradual worsening.
- **Primary progressive MS (PPMS):** steady worsening from the start, usually without clear relapses. About 10% of people with MS are diagnosed with this form.

A **relapse** is the appearance of new symptoms, or a clear worsening of existing ones, lasting at least 24 to 48 hours when no outside factor such as infection, fever, heat, stress or fatigue explains it (Multiple Sclerosis Society of Canada, 2021). Between relapses, the person is in **remission**, which may last years.

Risk factors. The cause of MS is not fully understood. Genes are thought to interact with lifestyle (for example, smoking and obesity) and with the environment (for example, low vitamin D levels) (PHAC, 2024). Infection with Epstein–Barr virus in childhood is linked to about 10 times the usual risk, and a past episode of infectious mononucleosis to about 20 times the risk. A parent, sibling or child of a person with MS has a risk of about 3% to 5%, compared with about 0.25% in the general population (Multiple Sclerosis Society of Canada, 2021). About 7 in 10 Canadians living with MS are women (PHAC, 2024). Canadian data appear in the Canadian Context box.

Diagnostics. A neurologist makes the diagnosis from the history, the neurologic examination and MRI evidence of lesions in the CNS. Other causes are ruled out first.

Living With MS

Common symptoms. PHAC (2024) lists walking problems, weakness and poor coordination; vision changes; pain, tingling and numbness; fatigue; changes in mood and thinking; and bladder and bowel problems. Fatigue affects about 90% of people with MS, and bladder dysfunction about 80% (Multiple Sclerosis Society of Canada, 2021). Spasticity, muscle stiffness with involuntary spasms, can make transfers and sleep difficult. Fatigue, pain and cognitive changes are invisible to others, so the nurse asks about them directly.

Heat and pseudo-relapse. A **pseudo-relapse** is a short-lived return or worsening of symptoms the person has had before. It is triggered by a rise in body temperature or by stress on the body, such as fever, infection, hot baths, sun, exercise, fatigue or strong emotion. No new inflammation is involved, and the symptoms settle as body temperature returns to normal (Multiple Sclerosis Society of Canada, 2021). The nurse therefore looks for a cause, such as a urinary tract infection, before assuming a relapse. Fever is reported and treated as ordered, and cool rooms and fans help.

When to report. People with MS are taught to contact their MS team about new symptoms or symptoms that clearly worsen and last more than a day or two. They also report changes in bladder function or a suspected urinary tract infection, new pain, and sexual concerns (Multiple Sclerosis Society of Canada, 2021). Routine visits with the MS team usually happen every 6 to 12 months. Corticosteroids, such as prednisone by mouth or methylprednisolone intravenously, can lessen a relapse and speed recovery, but long-term use is avoided because of side effects (Multiple Sclerosis Society of Canada, 2021).

Disease-modifying therapies. MS cannot be cured, but diagnosing and treating it early can make relapses fewer and milder, slow the build-up of disability and progression, and ease symptoms (PHAC, 2024). A **disease-modifying therapy (DMT)** is a long-term medication that changes the course of MS by acting on the immune system. By 2024, Health Canada had authorized 18 DMTs. Examples include fingolimod, siponimod, ozanimod and cladribine, taken by mouth, and the monoclonal antibodies ocrelizumab, ofatumumab, alemtuzumab and natalizumab, given by infusion or injection (Oh et al., 2025). The neurologist chooses the drug with the person, considering disease activity, safety and plans for pregnancy (Oh et al., 2025). Nursing points for these drugs are summarized with other neurologic medicines in a table in section 32.6.

Because DMTs act on the immune system, infection is the main safety concern. Natalizumab is an example. Its Canadian monograph carries a boxed warning about **progressive multifocal leukoencephalopathy (PML)**, a rare and serious brain infection caused by the John Cunningham (JC) virus. Natalizumab is available only through a controlled distribution program, and the risk rises with longer treatment, with prior immunosuppressant use and when antibodies to the JC virus are present (Biogen Canada, 2025). The monograph asks that patients be observed during each infusion and for an hour after it ends, to watch for reactions. It also warns of herpes infections of the brain and its coverings. Signs of PML develop over days to weeks: weakness on one side of the body, clumsiness, vision changes, and changes in memory, thinking or personality that the person may not notice. Family members are therefore included in teaching (Biogen Canada, 2025).

Rehabilitation and self-management. Physiotherapy and occupational therapy help with mobility, spasticity, fatigue and safety at home and work. People with MS live, on average, about 95% of a normal life expectancy (Multiple Sclerosis Society of Canada, 2021), so the focus is on living well for decades. MS Canada's MS Navigators offer information and support by phone and email.

Care in hospital. When a person with MS is admitted, the nurse:

- records the DMT, the date of the last dose or infusion and the person's usual routines, and asks the prescriber whether to continue the DMT;
- looks for infection, and reports fever early, since it can worsen symptoms;
- follows the person's bladder and bowel routines (Chapter 28; section 25.1) and checks the skin (Chapter 35);
- plans activity and rest to manage fatigue, and assesses fall risk (Chapter 8);
- screens for low mood and asks about pain (Chapter 5); and
- asks what the person needs to stay independent, such as mobility aids or more time for tasks (Chapter 2).

CANADIAN CONTEXT

Multiple Sclerosis in Canada

Canadian numbers on MS depend on how MS is counted.

- **Surveillance data:** PHAC's Canadian Chronic Disease Surveillance System (CCDSS) uses health-care records. In fiscal year 2021–2022, about 290 in every 100,000 adults (aged 20 and older) in Canada had MS. About 7 in 10 were women. Of new diagnoses, about 65% were in people aged 20 to 49 (PHAC, 2024).
- **Trends:** From 2011–2012 to 2021–2022, the proportion of adults with MS grew on average 1.5% per year (from 0.25% to 0.29%), while the rate of new diagnoses stayed flat. People may be diagnosed younger, living longer, or both (PHAC, 2024).

Data for Quebec, the Northwest Territories and Yukon were not available, New Brunswick and Saskatchewan data were not available for 2021–2022, and PHAC cautions that the COVID-19 pandemic affected 2021–2022 measures.

- **Survey-based estimates:** MS Canada estimates that about 90,000 people in Canada have MS (Multiple Sclerosis Society of Canada, 2021). It notes that survey-based counts may overestimate the number, while CCDSS counts rely on health-care records (MS Canada, n.d.).

For nurses, the message is the same: MS is common, and most people with it are working-age adults. Access to MS clinics, infusion centres and rehabilitation is harder in rural, remote and northern communities, and travel adds cost and fatigue. Virtual visits and local primary care partners help close the gap.

32.4 Parkinson Disease

Parkinson disease (PD) is a chronic, progressive neurologic disease that affects movement and many other body systems (Grimes et al., 2019). More than 100,000 Canadians live with PD, and about 25 more are diagnosed each day (Parkinson Canada, 2021). Most are older adults, and many are admitted to hospital for other reasons, such as a fall, a fracture or an infection. How the nurse handles their medications can change the course of the whole stay.

Signs and Course

PD is best known for its effects on movement. In a deep part of the brain called the substantia nigra, nerve cells that make **dopamine**, a chemical messenger needed for smooth movement, are lost. Parkinson Canada stresses that PD is a multi-system disease: the clumps of abnormal protein seen in PD, called Lewy bodies, may first appear in the lower brain stem and the nerves of smell rather than in the substantia nigra (Parkinson Canada, 2010).

Motor signs. The classic signs are tremor, rigidity, slow movement and poor balance. The diagnosis is clinical: neurologists look for two of the three main signs plus a response to levodopa (Parkinson Canada, 2010; Figure 32.4).

- **Resting tremor:** rhythmic shaking, often of one hand, that is present at rest.
- **Rigidity:** stiffness of the muscles when a limb is moved by someone else.
- **Bradykinesia:** slowness of movement, with small steps, a soft voice and small handwriting.
- **Poor balance:** a higher risk of falls as the disease advances.



Figure 32.4 Progression of posture, gait and mobility across the five stages of Parkinson disease on the Hoehn and Yahr scale. (credit: "5 Stages of Parkinson's Disease, Hoehn & Yahr Scale" by Bbmime/Wikimedia Commons, CC BY 4.0)

Non-motor symptoms. People with PD are often more disabled by non-motor symptoms than by motor ones (Parkinson Canada, 2010). These include loss of smell, constipation, depression, anxiety, apathy, restless legs, swallowing problems and mild cognitive impairment. Some, such as acting out dreams during sleep (rapid eye movement [REM] sleep behaviour disorder), low mood and

loss of smell, often appear years before the tremor (Parkinson Canada, 2010). **Orthostatic hypotension**, a drop in blood pressure on standing that causes dizziness or fainting, is common (Grimes et al., 2019). Later, dementia and psychosis with hallucinations may develop (Grimes et al., 2019).

Treatment over time. Levodopa, combined with carbidopa, remains the most effective medication for motor symptoms, and the Canadian guideline sees no reason to delay it once symptoms are bothersome (Grimes et al., 2019). Over years, people often notice **wearing off**, the return of symptoms before the next dose is due, and **dyskinesia**, involuntary writhing movements. Dyskinesia was the most frequent adverse reaction reported in the levodopa-carbidopa controlled-release monograph (Pharmascience, 2020). Levodopa can also cause orthostatic hypotension, hallucinations and confusion, and sudden sleep during daily activities, sometimes without warning (Pharmascience, 2020). A speech-language pathologist helps with swallowing, speech and drooling, and a physiotherapist with balance (Grimes et al., 2019). For carefully selected people with severe motor fluctuations despite the best medication plan, **deep brain stimulation**, in which electrodes are placed in the brain, is the surgical treatment of choice (Grimes et al., 2019).

Care in Hospital

Medications on time, every time. Parkinson Canada's ACT on Time campaign asks that people with PD receive their medications on time in every setting: at home, in the emergency department, in hospital and in long-term care. The person's schedule may not match the unit's medication rounds. Late or missed doses can leave symptoms uncontrolled and lengthen recovery (Parkinson Canada, 2019, 2021). Levodopa-carbidopa has a half-life of about 2 hours, so even a short delay matters (Emergency Care BC, 2023). Canadian data show how often this goes wrong. In one Canadian hospital study of 104 admissions of people with PD, 12.9% of scheduled doses were given at the wrong time and 8.7% were omitted, and 88% of admissions involved one or more doses given over 60 minutes off schedule (Cowley et al., 2021).

The nurse:

- confirms the exact home times with the person or family on admission, not just the number of doses a day;
- enters those clock times in the medication record and gives each dose on time, within the window that employer policy sets;
- supports self-administration where policy allows, and asks to see the person's medication card; Parkinson Canada's Medical Alert Card lists current medications and medications to avoid (Parkinson Canada, 2019); and
- reports any dose that cannot be given.

Never stopping levodopa suddenly. A rapid dose cut or withdrawal of PD medication can cause a reaction like neuroleptic malignant syndrome, with rigidity, fever, altered consciousness and unstable vital signs (Pharmascience, 2020). It is rare but dangerous; treatment includes restarting dopamine medication (Emergency Care BC, 2023).

NPO and surgery. When a person with PD must have nothing by mouth (NPO), the nurse does not simply hold the medications. The nurse contacts the prescriber, the anesthesia team and the pharmacist early to plan how doses will continue around the procedure, and confirms the plan before the first dose is due (Chapter 7). If swallowing is unsafe, the nurse asks about another route or form, and checks with the pharmacist before crushing any tablet (section 24.3).

Drugs that block dopamine. Many antipsychotics and the antiemetic metoclopramide block dopamine and should be avoided (Emergency Care BC, 2023). The levodopa-carbidopa monograph warns that dopamine blockers, such as the phenothiazines, the butyrophenones and risperidone, can blunt the effect of levodopa, and that metoclopramide may worsen disease control (Pharmascience, 2020). The metoclopramide monograph states that people with PD should receive it cautiously, if at all (JAMP Pharma, 2023). Before giving a new antiemetic, sedative or antipsychotic, the nurse checks it against these lists, questions any dopamine blocker, and asks the prescriber or pharmacist for an alternative. For psychosis in PD, the Canadian guideline names quetiapine as possibly useful and clozapine as useful with monitoring (Grimes et al., 2019). Iron supplements and high-protein meals can reduce levodopa absorption (Pharmascience, 2020), so the nurse asks the pharmacist how to time them.

Delirium, falls and swallowing. Hospital stays bring new risks. Hallucinations and confusion may come from the disease, from medications or from **delirium**; any new change is reported and screened for (Chapter 8). The nurse checks orthostatic vital signs, helps the person rise slowly and keeps aids within reach to prevent falls (Chapter 8). Swallowing is watched closely, since missed doses and aspiration are linked (Parkinson Canada, 2011; section 24.3).

PRACTICE STORY

Every Dose on Time

Names and details are fictional; this is a composite story.

Nurse: Chidinma Adeyemi, RN. Years in practice: 6. Setting: surgical unit, Ontario.

Mr. Henri Lavoie, 76, came to our unit after surgery to repair a broken hip. He has lived with Parkinson disease for 11 years. His wife, Monique, handed me a laminated card at the bedside. It listed his levodopa-carbidopa at 0600, 0930, 1300, 1630 and 2000, and two medicines he should never be given.

The admission orders said "four times daily," and the system had set the doses at 0900, 1300, 1700 and 2100. His 0600 dose had been held for surgery, and it was already 1100. He lay stiff, his voice was a whisper, and he could not roll to let me check his skin. Monique said, "This is not him. He's frozen."

I called the surgical resident and the pharmacist. We restarted his levodopa at once, and the resident rewrote the order to match his clock times. I entered each time in the record and added a note to the whiteboard and the handover sheet. By 1300, Henri could turn with help and swallow his tablets with applesauce, as the speech-language pathologist had advised.

That evening he was nauseated, and the order set included metoclopramide. Metoclopramide was on Monique's card. I held it and paged the resident, explaining that it blocks dopamine and can worsen Parkinson symptoms. The pharmacist suggested another antiemetic, and the resident ordered it. His nausea settled.

Before I went home, I talked with the night nurse about the 2000 dose and the 0600 dose, and asked for the 0600 dose to be planned with the physiotherapy session. The next morning, Henri stood at the bedside with the physiotherapist. Monique told me it was the first time a hospital had followed his card.

Reflect: Which parts of this plan could an RPN on the same unit lead, and when should the RPN involve the RN? How do authority, competence and context apply when a nurse holds a prescribed medication and asks for a new order?

32.5 Myasthenia Gravis and Guillain–Barré Syndrome

Myasthenia gravis and Guillain–Barré syndrome both cause weakness through an immune attack outside the brain and spinal cord. Myasthenia gravis is a chronic disease with flare-ups; Guillain–Barré syndrome is an acute illness from which most people recover. In both, the main danger is weakness of the muscles that breathe and swallow (Table 32.3).

Myasthenia Gravis

Myasthenia gravis (MG) is an autoimmune disease in which antibodies attack acetylcholine receptors, or related proteins, on the muscle side of the **neuromuscular junction**, where a nerve passes its signal to a muscle (Sheikh et al., 2021). Fewer working receptors mean the signal weakens with repeated use. The result is weakness that gets worse with activity and improves with rest.

Manifestations. MG often affects the eyes first. **Ptosis**, a drooping upper eyelid, and double vision are common. Weakness of the face, jaw and throat (bulbar weakness) causes a nasal voice, tiring while chewing, choking and trouble swallowing. Limb weakness and weakness of the breathing muscles may follow. Symptoms are often worse late in the day or after effort, such as a long meal (Figure 32.5).

Figure 32.5 Asymmetric ptosis (drooping upper eyelid, right greater than left) and strabismus causing diplopia in a person with myasthenia gravis attempting to open the eyes. (credit: "DiplopiaMG1" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Myasthenic crisis. International consensus guidance defines a **myasthenic crisis** as weakness that worsens until the person needs intubation, or noninvasive ventilation to prevent intubation. An impending crisis is rapid worsening that, in the treating physician's opinion, could lead to crisis within days to weeks (Sanders et al., 2016). The 2020 update of this guidance did not change these definitions (Narayanaswami et al., 2021). Impending crisis calls for hospital admission and close watching of breathing and swallowing. A crisis calls for intensive care or a step-down unit (Sanders et al., 2016).

Triggers and medications. Infection, surgery and some medications can worsen MG. A review of drugs linked to MG lists fluoroquinolone and macrolide antibiotics, aminoglycosides, magnesium, beta-blockers, calcium channel blockers, some antiarrhythmics, neuromuscular blockers used in anesthesia and botulinum toxin. Immune checkpoint inhibitors used in cancer care can trigger MG for the first time or worsen existing MG (Narayanaswami et al., 2021; Sheikh et al., 2021). The review advises avoiding fluoroquinolones and macrolides when a safer alternative exists and using magnesium with extreme caution (Sheikh et al., 2021). High starting doses of corticosteroids can cause a short-term worsening of weakness (Sanders et al., 2016; Sheikh et al., 2021). When a new order arrives, the nurse checks it against these classes and asks the prescriber or pharmacist if it is on the list. The nurse then watches swallowing and breathing closely after any change.

Pyridostigmine. Pyridostigmine, a cholinesterase inhibitor, should be part of the first treatment for most people with MG (Sanders et al., 2016). It lets acetylcholine act longer at the junction. The Canadian monograph states that tablets are swallowed whole and not crushed, and that a larger share of the daily dose may be timed for periods when the person tires more easily, such as meals (Bausch Health, 2019). The nurse gives each dose on time and works with the team so that meals fall when the medication is working. Its cholinergic effects include more saliva and airway secretions, sweating, cramps and diarrhea. Too much can itself cause weakness, a **cholinergic crisis**. Because a myasthenic crisis and a cholinergic crisis both cause severe weakness but need very different treatment, the nurse reports any worsening rather than giving an extra dose (Bausch Health, 2019).

Other treatments. For severe generalized MG and crisis, **plasma exchange** (removing the antibody-containing plasma and replacing it) and **intravenous immune globulin (IVIG)** are probably equally effective, although expert opinion favours plasma exchange for faster effect in crisis (Sanders et al., 2016). Corticosteroids and other immune-suppressing drugs are used for long-term control.

Guillain–Barré Syndrome

Guillain–Barré syndrome (GBS) is an acute immune attack on the peripheral nerves. About two-thirds of patients recall an infection during the 6 weeks before the weakness starts. *Campylobacter jejuni*, a common cause of diarrheal illness, is one of six infections linked to GBS, along with cytomegalovirus, hepatitis E virus, *Mycoplasma pneumoniae*, Epstein–Barr virus and Zika

virus. A recent infection is not required for the diagnosis (Leonhard et al., 2019). Worldwide, GBS affects about 1 to 2 people per 100,000 each year. It is most common between ages 50 and 70, and men are about 1.5 times more likely to be affected (van Doorn et al., 2023).

Manifestations. GBS usually starts with tingling or numbness in the feet and hands. Weakness then begins in the legs and climbs to the arms and the muscles of the face and throat; this pattern is called **ascending paralysis** (Leonhard et al., 2019). Weakness of both sides of the face is common. Reflexes are reduced or absent in most patients when they arrive and in almost all at the worst point, a finding called **areflexia**. Pain is common, often in the back and limbs. **Autonomic dysfunction**, damage to the nerves that control heart rate, blood pressure, bowel and bladder, causes swings in blood pressure, abnormal heart rhythms and urinary retention. Most patients reach their worst point within 2 weeks (Leonhard et al., 2019). Within the first week after admission, up to 22% need a ventilator (Leonhard et al., 2019). Respiratory failure can develop without breathlessness, so the nurse cannot rely on the patient's report alone.

Diagnostics. The diagnosis rests on the pattern of weakness and reflexes, supported by nerve conduction studies (Leonhard et al., 2019).

Nursing care. The nurse measures breathing strength as ordered (see the Going Deeper box), watches swallowing and cough, and monitors heart rhythm, blood pressure, and bladder and bowel function (Leonhard et al., 2019). Reasons to involve critical care include worsening breathing, severe swings in heart rate or blood pressure, severe trouble swallowing, a weak cough and rapidly spreading weakness (Leonhard et al., 2019). The nurse escalates early using SBAR (Chapter 6).

A patient who cannot move needs prevention of deep vein thrombosis (Chapter 19), pressure injuries (Chapter 35) and hospital-acquired infections (Leonhard et al., 2019). Facial weakness can stop the eye from closing, so the eyes are protected from corneal damage. Positioning and range-of-motion exercises help prevent contractures. Pain, hallucinations, anxiety and depression are common, so the nurse asks about them, especially when the patient cannot speak easily (Leonhard et al., 2019). Most patients stay fully conscious and can see and hear. The nurse explains every procedure, sets up a call system the patient can use and speaks to the patient, not about the patient, at the bedside.

Treatment. The guideline from the European Academy of Neurology and Peripheral Nerve Society strongly recommends IVIG as soon as possible for patients who cannot walk unaided and are within 2 weeks of onset, or plasma exchange within 4 weeks. It recommends against corticosteroids (van Doorn et al., 2023).

Recovery. About 80% of patients walk independently again by 6 months. Between 3% and 10% die, mostly from heart and breathing complications, and many deaths happen during the recovery phase, so monitoring continues even when the patient is improving (Leonhard et al., 2019). In 6% to 10% of patients, weakness worsens again within 2 months after first improving or stabilizing with treatment (Leonhard et al., 2019). Physiotherapy, occupational therapy and speech therapy start during the hospital stay and continue for more than 6 months when needed (van Doorn et al., 2023).

Table 32.3 Chronic and acute neuromuscular and neurologic disorders compared (Grimes et al., 2019; Leonhard et al., 2019; Multiple Sclerosis Society of Canada, 2021; Sanders et al., 2016; Shoesmith et al., 2020)

Disorder	What goes wrong	Key signs	Danger signs to report	Nursing focus
Multiple sclerosis	Immune damage to myelin in the optic nerves, brain and spinal cord	Fatigue, vision changes, weakness, numbness, spasticity, bladder problems	New or worse symptoms lasting more than 24 to 48 hours; fever; signs of infection on a DMT	Look for infection or heat as a cause; keep routines; manage fatigue; teach when to report
Parkinson disease	Loss of dopamine-making nerve cells and wider nervous system changes	Tremor, rigidity, slow movement, poor balance; constipation, low mood, low blood pressure on standing	Rigidity with fever and confusion after missed doses; new confusion or hallucinations; falls; choking	Give medications at the person's own times; avoid dopamine blockers; prevent falls and aspiration
Myasthenia gravis	Antibodies block signals at the neuromuscular junction	Weakness that worsens with use; drooping eyelids; double vision; tiring while chewing	Trouble swallowing saliva; weak cough; shortness of breath; falling breathing measures	Time pyridostigmine on schedule; check new drug orders; monitor breathing and swallowing

Disorder	What goes wrong	Key signs	Danger signs to report	Nursing focus
Guillain–Barré syndrome	Acute immune attack on peripheral nerves, often after an infection	Tingling, then weakness rising from the legs; lost reflexes; pain	Falling vital capacity; weak cough; swallowing trouble; swings in heart rate or blood pressure	Measure breathing strength; monitor heart rhythm; prevent clots and pressure injuries; explain and reassure
Amyotrophic lateral sclerosis	Loss of motor nerve cells in the brain and spinal cord	Weakness, muscle wasting, twitching, stiffness; slurred speech	Breathlessness lying flat; weak cough; choking; weight loss	Support breathing and nutrition decisions; communication tools; advance care planning

GOING DEEPER

Watching the Breathing Muscles

Required for RN students; optional for PN students.

In MG and GBS, the lungs are usually healthy; the problem is the pump. Bedside measures of muscle strength show the decline early.

- **Vital capacity (VC):** the largest volume of air a person can breathe out after a full breath in, recorded in litres or millilitres per kilogram. Forced vital capacity (FVC) uses a forceful breath out. For GBS, the European Academy of Neurology and Peripheral Nerve Society guideline advises checking FVC three to six times daily, according to how severe the illness is. It states that a fall of more than 30% in 24 hours likely means immediate transfer to intensive care, and that planned (elective) ventilation should be considered once FVC reaches 20 mL/kg or less (van Doorn et al., 2023).
- **Negative inspiratory force (NIF):** also called maximum inspiratory pressure, the strongest pull the person can make when breathing in against a closed valve. The "20/30/40 rule" flags a risk of respiratory failure when VC is below 20 mL/kg, maximum inspiratory pressure is below 30 cm H_2O or maximum expiratory pressure is below 40 cm H_2O (Leonhard et al., 2019).
- **Single-breath count:** the patient counts aloud on one breath. A count below 20 is a useful bedside sign that intensive care may be needed (van Doorn et al., 2023).

Oxygen saturation is a late sign. Because the lungs exchange gas normally, saturation can stay normal until the muscles are close to failing, and respiratory failure can occur without breathlessness (Leonhard et al., 2019). A falling VC is the signal to escalate, even when saturation is normal. In MG, the same measures are used, with thresholds set by the treating team.

CLINICAL JUDGMENT

Weak, Then Weaker

Names and details are fictional; this is a composite story.

Amira Haddad, 58, has had MG for 6 years. She is admitted to a medical unit with pneumonia and started on antibiotics. On day 2, the nurse notices that she leaves half her lunch and holds her chin up with her hand to speak.

- **Recognize cues:** Her voice is nasal and fades during conversation. She coughs while swallowing water and pockets pills in her cheek. Her eyelids droop more than this morning. She counts only to 14 on one breath. Her FVC is 1.6 L, down from 2.3 L at 0800. Her oxygen saturation is 95%. Her 1200 pyridostigmine was given on time.
- **Analyze cues:** Infection is a known trigger for MG. Her swallowing, voice and breathing measures are worsening together, which points to bulbar and respiratory muscle weakness. A normal saturation does not rule out a problem.
- **Prioritize hypotheses:** Impending myasthenic crisis, with a risk of aspiration and respiratory failure, comes first. A cholinergic reaction is less likely, but the team must judge it.
- **Generate solutions:** Stop food and fluids by mouth; sit her upright; have suction ready; escalate now; check new medication orders against the list of drugs that can worsen MG.
- **Take action:** The nurse makes her NPO, sits her upright and calls the rapid response team per policy. Using SBAR (situation, background, assessment, recommendation; Chapter 6), the nurse reports the trend in FVC, the single-breath count and swallowing to the RN in charge and the physician (Chapter 6). The nurse asks the pharmacist to review her antibiotic, which is a macrolide. The nurse stays with her and explains each step.
- **Evaluate outcomes:** The critical care outreach team transfers her to a step-down unit. Plasma exchange is started, and her antibiotic is changed. Two days later her FVC is 2.4 L, her voice is clear and she passes a swallowing assessment.

32.6 Amyotrophic Lateral Sclerosis and Living With Progressive Neurologic Disease

Some neurologic diseases cannot be cured, and they progress. Nursing care then aims to keep the person as independent, comfortable and in control as possible, and to support the family who share the work of care.

Amyotrophic Lateral Sclerosis

Amyotrophic lateral sclerosis (ALS) is a progressive disease in which the motor nerve cells of the brain and spinal cord degenerate (Shoesmith et al., 2020). Loss of upper motor neurons, in the brain, causes stiffness and spasticity. Loss of lower motor neurons, in the brainstem and spinal cord, causes weakness, muscle wasting and twitching called fasciculations. In about 70% of people, ALS starts in a limb, for example with a weak hand or a dropped foot. In about 25%, it starts in the bulbar muscles, with slurred speech or trouble swallowing (Shoesmith et al., 2020). Sensation, bladder control and, often, thinking are spared at first. About half of people with ALS develop detectable changes in thinking or behaviour linked to the frontal and temporal lobes, and in about 20% these changes reach the level of dementia (Shoesmith et al., 2020; Figure 32.6).

ALS in Canada. ALS Canada (2025) reports that nearly 4,000 Canadians are living with ALS, and that each year about 1,000 Canadians die of it and a similar number are diagnosed. More than 90% of people diagnosed have no family history of the disease, and about 80% of people with ALS die 2 to 5 years after diagnosis (ALS Canada, 2025), usually from respiratory failure (Shoesmith et al., 2020).



Figure 32.6 Distribution of upper motor neuron (UMN) and lower motor neuron (LMN) involvement across classical spinal-onset, bulbar-onset and variant subtypes of amyotrophic lateral sclerosis (ALS). (credit: "ALS subtypes UMN LMN distribution" by PaulWicks/Wikimedia Commons, CC BY-SA 4.0)

Care. The Canadian best practice recommendations advise regular follow-up in a multidisciplinary ALS clinic together with primary care. Such clinics have been linked with longer survival and fewer hospital admissions (Shoesmith et al., 2020). Two medications are approved in Canada. Riluzole, approved in 2000, gives a modest survival benefit, and liver enzymes and blood counts are monitored. Edaravone, approved in October 2018, is rated "probably effective" only in a select group of patients (Shoesmith et al., 2020).

Breathing and feeding decisions. As breathing muscles weaken, **noninvasive ventilation (NIV)**, breathing support through a mask, eases breathlessness and helps sleep. The recommendations suggest starting NIV in a person without symptoms when FVC falls to 65% of predicted or other criteria are met, and starting it within 4 weeks of meeting criteria (Shoesmith et al., 2020). A cough-assist device is considered when the cough becomes weak (Chapter 15). As swallowing fails and weight drops, a feeding tube may be offered, with no more than 4 weeks' delay after criteria are met (Shoesmith et al., 2020; section 24.3). These are personal choices that depend on the person's goals, and they are best discussed early, before an emergency.

Communication. When speech fails, communication tools range from letter and picture boards to speech-generating devices and eye-gaze computers (Shoesmith et al., 2020). Early referral to a speech-language pathologist lets the person bank their voice or learn a device while they still have the strength to do so.

Living Well With Progressive Disease

Advance care planning. Advance care planning is the ongoing process of reflecting on values and wishes for future care, sharing them with family and the care team, and choosing a substitute decision-maker. The ALS recommendations favour bringing palliative

care in early and adjusting it as needs change, and starting advance care planning when the person is ready (Shoesmith et al., 2020). The same approach suits advanced MS, PD and other progressive diseases. The nurse invites the conversation, listens and documents wishes (Chapter 10). Some people with ALS and other serious illnesses ask about medical assistance in dying (MAID). The nurse responds respectfully and follows Chapter 10 and employer policy.

Caregivers. A **caregiver** is a family member or friend who provides unpaid care and support. Caring for a person with ALS affects the caregiver's own quality of life, and strain rises with advanced disability and changes in thinking (Shoesmith et al., 2020). The nurse asks how the caregiver is coping, includes them in planning, teaches skills such as transfers and feeding, and links them with respite.

Home, equipment and access. People with progressive disease need mobility aids, home changes, home care and help with costs, and their needs grow over time. The nurse refers early to occupational therapy, social work and home care, and treats accessibility as a right (Chapter 2). People in rural, remote and northern communities may need to travel far to specialty clinics. Virtual visits, outreach clinics and local primary care partners help. Care is offered in French and other languages through interpreters, and care with First Nations, Inuit and Métis people involves community health services and family as the person wishes (Chapter 2).

Hospital stays. When a person with ALS or another progressive disease is admitted, the nurse keeps the person's own NIV machine, communication device and routines in place wherever policy allows. The nurse asks the person and caregiver how care is done at home, since they often know the safest way to transfer, position and feed. Discharge planning starts at admission, because needs may have changed during the stay.

Peer support. National organizations, such as MS Canada, Parkinson Canada and ALS Canada, offer information, equipment programs and peer support. The nurse shares these resources at diagnosis and again at each transition.

Table 32.4 summarizes nursing points for the medicines named in sections 32.3 to 32.6.

Table 32.4 Medicines for chronic neurologic disorders (Canadian monographs and guidelines)

Drug or class	Canadian examples	Used for	Nursing points
Levodopa with carbidopa	Levodopa-carbidopa tablets, including controlled release; intestinal gel	Motor symptoms of Parkinson disease	Give at the person's own clock times; never stop suddenly; watch for low blood pressure on standing, sudden sleep, hallucinations and dyskinesia; ask the pharmacist about iron and high-protein meals
Dopamine blockers (to avoid in Parkinson disease)	Metoclopramide; phenothiazine and butyrophenone antipsychotics; risperidone	Nausea, agitation or psychosis in other patients	Question the order; ask the prescriber or pharmacist for an alternative; for psychosis in Parkinson disease, the guideline names quetiapine or clozapine with monitoring
Disease-modifying therapies for MS	Oral: fingolimod, siponimod, ozanimod, cladribine. Infusion or injection: ocrelizumab, ofatumumab, alemtuzumab, natalizumab	Reducing relapses and slowing MS	Record the last dose; report fever and infection; for natalizumab, observe during and 1 hour after infusion and teach PML warning signs
Corticosteroids	Prednisone; methylprednisolone	MS relapses; MG	Avoid long-term use when possible; in MG, report new weakness after starting
Cholinesterase inhibitor	Pyridostigmine (regular and slow-release tablets)	Symptoms of MG	Give on time; swallow whole, do not crush; watch for excess saliva, cramps and diarrhea; report any worsening weakness
Immune therapies	IVIG; plasma exchange (a procedure)	Severe MG or crisis; GBS in patients who cannot walk unaided	Given per order and employer policy; monitor vital signs, breathing and reactions
ALS medications	Riluzole; edaravone	Slowing ALS	Riluzole: monitor liver enzymes and blood counts as ordered; edaravone: benefit limited to selected patients

SCOPE IN PRACTICE

Neurologic Care and Who Does What

The College of Nurses of Ontario (CNO) Scope of Practice standard asks every nurse to consider **authority**, **competence** and **context** before taking on an activity (section 1.3).

- **Spinal precautions:** Log rolling a patient with a spinal injury is a team task; trained nurses take part, and no nurse moves the patient alone (section 32.2).
- **Autonomic dysreflexia:** Any nurse who sees the signs starts the first actions at once and calls for help (section 32.2). No nurse waits for someone else.
- **Breathing in MG and GBS:** RNs and RPNs both measure vital capacity or single-breath counts when the employer authorizes it and they are trained. Any nurse who sees a falling trend escalates at once. The RPN consults the RN as the patient's needs change; depending on employer policy, the RN may take over care of a patient who is becoming unstable.
- **IVIG and plasma exchange:** IVIG is a blood product. Employer policy sets who may give it, and plasma exchange is often done in specialized units. These limits come from employer policy, based on context and competence, not from a CNO rule.
- **Medications on time:** Every nurse who gives medications to a person with PD gives them at the person's own times and questions an order for a dopamine blocker.
- **Advance care planning:** Both RNs and RPNs listen to and document wishes within their competence.

Employer policy and the province or territory matter. In other provinces, practical nurses (licensed practical nurses in many provinces) follow their own regulator's standards.

Chapter 32 Summary

32.1 Traumatic Brain Injury and Concussion

- More than 20,000 people in Canada are hospitalized for TBI each year; falls are the leading cause of head injury hospitalization, and rates are highest among people over 85.
- Primary injury happens at impact; nurses work to prevent secondary injury by protecting oxygenation, blood pressure, temperature and positioning, and by reporting neurologic decline at once.
- Concussion is a clinical diagnosis. After about 24 to 48 hours of relative rest, people return to activity gradually; most adults recover within about a month, and those with symptoms beyond a month are considered for interdisciplinary care.
- Warning signs such as repeated vomiting, a worsening headache or increasing drowsiness need emergency care.
- An epidural hematoma can follow a lucid interval; a chronic subdural hematoma can appear weeks after a minor fall in an older adult as new confusion. Older adults taking anticoagulants need prompt assessment after a head injury.
- During post-traumatic amnesia, a calm, low-stimulation setting with consistent staff is preferred to restraints and sedation.

32.2 Spinal Cord Injury

- About 86,000 people in Canada live with SCI; falls are the most common cause of traumatic SCI, and degenerative disease the most common cause of non-traumatic SCI.
- The neurologic level and completeness (sacral sparing on the ISNCSCI examination) predict function; cervical injuries cause tetraplegia and threaten breathing.
- Early care includes spinal motion restriction and log rolling, close respiratory monitoring with secretion clearance and assisted cough, and recognition of neurogenic shock and VTE risk.
- Autonomic dysreflexia, usually with injuries at T6 or above, is an emergency: sit the person up, loosen clothing, check the bladder, then the bowel and skin, monitor blood pressure every 2 to 5 minutes and call for help early.
- Ongoing care covers bladder, bowel, skin, temperature, spasticity, sexuality and mood, with rehabilitation aimed at living in the community.

32.3 Multiple Sclerosis

- MS is a chronic autoimmune disease in which the immune system damages myelin in the optic nerves, brain and spinal cord.
- Most people are first diagnosed with relapsing-remitting MS; a relapse lasts at least 24 to 48 hours with no outside cause.
- Heat, fever and infection can cause a pseudo-relapse, so the nurse looks for infection before assuming a relapse.
- In 2021–2022, about 290 per 100,000 Canadian adults lived with MS, and about 7 in 10 were women.
- Disease-modifying therapies act on the immune system; nurses report infection and teach warning signs such as those of PML with natalizumab.

32.4 Parkinson Disease

- PD causes tremor, rigidity, slow movement and poor balance, plus non-motor symptoms such as constipation, low mood, sleep problems and orthostatic hypotension.
- Levodopa-carbidopa is the most effective treatment for motor symptoms; it must be given at the person's own clock times, every time.
- Stopping PD medication suddenly can cause a dangerous reaction with rigidity, fever and confusion; NPO plans are made ahead with the team.
- Dopamine blockers, such as metoclopramide and many antipsychotics, are avoided; the nurse questions these orders.

32.5 Myasthenia Gravis and Guillain–Barré Syndrome

- MG causes weakness that worsens with use; myasthenic crisis is weakness that needs ventilatory support.
- Infection and some drugs, such as fluoroquinolones, macrolides and magnesium, can worsen MG; the nurse checks new orders.
- GBS often follows an infection and causes tingling, rising weakness, lost reflexes, pain and autonomic swings.
- In both disorders, a falling vital capacity, weak cough or swallowing trouble means early escalation; oxygen saturation falls late.
- IVIG and plasma exchange are used in both disorders; corticosteroids are not recommended for GBS.

32.6 Amyotrophic Lateral Sclerosis and Living With Progressive Neurologic Disease

- ALS destroys motor nerve cells, causing weakness, wasting and, eventually, respiratory failure; nearly 4,000 Canadians live with it.
- Multidisciplinary ALS clinics, riluzole and edaravone, NIV, feeding tubes and communication devices support quality of life.
- Advance care planning and early palliative care are best started when the person is ready, before a crisis (Chapter 10).
- Caregivers need assessment, teaching and respite, and accessible care reaches rural, francophone and Indigenous communities.

Key Terms (49)

advance care planning: The ongoing process of reflecting on values and wishes for future care, sharing them with family and the care team, and choosing a substitute decision-maker.

amyotrophic lateral sclerosis (ALS): A progressive disease in which the motor nerve cells of the brain and spinal cord degenerate, causing weakness, muscle wasting and, eventually, respiratory failure.

areflexia: Absence of deep tendon reflexes.

ascending paralysis: Weakness that starts in the legs and spreads upward to the arms and the muscles of breathing, swallowing and the face.

autonomic dysfunction: Damage to the nerves that control heart rate, blood pressure, bowel and bladder, causing swings in vital signs and other problems.

autonomic dysreflexia: A sudden, dangerous rise in blood pressure, triggered by a stimulus below a spinal cord injury, usually at T6 or above.

bradykinesia: Slowness of movement, seen as small steps, a soft voice and small handwriting.

caregiver: A family member or friend who provides unpaid care and support to a person with an illness or disability.

cholinergic crisis: Severe weakness, with excess secretions and other cholinergic effects, caused by too much cholinesterase inhibitor.

complete injury: A spinal cord injury with no sensation or movement preserved in the lowest sacral segments (S4–S5).

concussion: A type of mild traumatic brain injury from a force that moves the brain within the skull, causing neurologic changes that usually resolve on their own, with normal standard imaging.

demyelination: Damage to or loss of the myelin covering of nerve fibres, which slows or blocks nerve signals.

diffuse axonal injury: Widespread stretching and tearing of nerve fibres caused by rapid acceleration and deceleration of the brain.

disease-modifying therapy (DMT): A long-term medication that changes the course of MS by acting on the immune system, reducing relapses and slowing disability.

dyskinesia: Involuntary writhing or jerking movements, often a side effect of long-term levodopa treatment.

epidural hematoma: A collection of blood between the skull and the dura.

Guillain–Barré syndrome (GBS): An acute immune attack on the peripheral nerves, often after an infection, causing rapidly rising weakness and loss of reflexes.

incomplete injury: A spinal cord injury with some sensation or voluntary movement preserved in the lowest sacral segments.

levodopa: A medication that the brain converts to dopamine; combined with carbidopa, it is the most effective treatment for the motor symptoms of Parkinson disease.

log roll: Turning a patient so that the head, shoulders, trunk and hips move together as one unit and the spine does not twist.

lucid interval: A period after a head injury when the person wakes and seems well before deteriorating, typical of an epidural hematoma.

multiple sclerosis (MS): A chronic autoimmune disease in which the immune system damages myelin in the optic nerves, brain and spinal cord.

myasthenia gravis (MG): An autoimmune disease in which antibodies block signals at the neuromuscular junction, causing weakness that worsens with use and improves with rest.

myasthenic crisis: MG weakness that worsens until the person needs intubation, or noninvasive ventilation to prevent intubation.

myelin: The fatty covering that insulates nerve fibres and lets signals travel quickly.

neurogenic shock: Low blood pressure with a slow heart rate, without another cause, after a cervical or high thoracic spinal cord injury, from sudden loss of sympathetic nerve output.

neuromuscular junction: The site where a motor nerve passes its signal to a muscle fibre.

noninvasive ventilation (NIV): Breathing support given through a mask rather than a tube in the airway.

orthostatic hypotension: A drop in blood pressure on standing that causes dizziness, light-headedness or fainting.

paraplegia: Weakness or paralysis of the trunk, legs or both, sparing the arms, from an injury below the cervical cord.

Parkinson disease (PD): A chronic, progressive neurologic disease marked by tremor, rigidity, slow movement and poor balance, with many non-motor symptoms.

post-traumatic amnesia: A stage of recovery after TBI in which awareness is poor and fluctuates, the person is disoriented and new events are not reliably remembered.

primary brain injury: Damage that occurs at the moment of impact or sudden acceleration and deceleration.

progressive multifocal leukoencephalopathy (PML): A rare, serious brain infection caused by the JC virus; a risk with some immune-modifying drugs such as natalizumab.

pseudo-relapse: A short-lived return or worsening of earlier MS symptoms caused by heat, fever, infection or fatigue, without new inflammation.

ptosis: Drooping of the upper eyelid.

relapse: In MS, new symptoms or a clear worsening of existing ones lasting at least 24 to 48 hours when no outside factor such as infection or heat explains it.

resting tremor: Rhythmic shaking, often of one hand, that is present when the limb is at rest.

rigidity: Stiffness of the muscles felt when another person moves the limb.

secondary brain injury: Further brain damage in the hours and days after injury from low oxygen, poor blood flow, swelling and harmful chemical changes.

spasticity: Increased muscle tone with involuntary spasms and overactive reflexes after damage to the brain or spinal cord.

spinal cord injury (SCI): Damage to the spinal cord that interrupts messages between the brain and the body below the injury.

spinal motion restriction: Keeping the spine as still as possible, for example with a cervical collar and careful movement, when a spine injury is possible.

spinal shock: A temporary state, beginning immediately after a spinal cord injury, in which spinal reflexes are lost below the injury.

subdural hematoma: A collection of blood between the dura and the surface of the brain; it may be acute or chronic.

tetraplegia: Weakness or paralysis of the arms, trunk and legs from an injury to the cervical spinal cord.

traumatic brain injury (TBI): Damage to the brain from an outside force, such as a blow to the head or a jolt that moves the brain quickly inside the skull.

vital capacity: The largest volume of air a person can breathe out after a full breath in; a bedside measure of breathing muscle strength.

wearing off: The return of Parkinson symptoms before the next dose of medication is due.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Amara Osei (Questions 1–4): Amara Osei, 32, has a complete T4 spinal cord injury from a car crash five months ago and is on a rehabilitation unit in Ontario with an indwelling urinary catheter. Her usual blood pressure is 98/62 mm Hg. While lying flat in bed, she calls the RPN and says she has a pounding headache. Her face and neck are flushed and sweaty, the skin on her legs is cool with goosebumps, her blood pressure is 188/104 mm Hg and her heart rate is 52 beats/min.

1. [CORE] Which action should the RPN take first?

a. Lower the head of the bed and raise her legs to improve blood flow to her brain.

b. Give the analgesic she has ordered as needed for headache and recheck her in one hour.

c. Sit her up at 90 degrees and lower her legs over the side of the bed or into a dependent position.

d. Leave the room to call the physician, and plan to recheck her vital signs once orders are received.

Answer: c — Ms. Osei has the signs of autonomic dysreflexia: an injury above T6, pounding headache, flushing and sweating above the injury, goosebumps below, and a blood pressure far above her baseline with a slow heart rate (section 32.2, Autonomic Dysreflexia). Sitting her upright and lowering her legs helps lower the pressure at once. Option a raises the pressure further and is the opposite of what is needed. Option b treats the headache but ignores the dangerous blood pressure and its cause. Option d delays action; any nurse who recognizes AD starts the first steps at once and calls for help while staying with the patient.

2. [CORE] Ms. Osei is now sitting upright and her clothing is loosened. Her blood pressure is 182/100 mm Hg. Which action should the RPN take next?

a. Check the catheter and tubing for kinks or clamps and look at whether urine is draining into the bag.

b. Perform a digital rectal check for stool before looking at the bladder, because constipation is the most common cause.

c. Ask her to rate her headache on a 0 to 10 scale and document it before taking any other action.

d. Turn her onto her side to check her sacrum and heels for pressure areas that may be the trigger.

Answer: a — A full bladder, often from a blocked or kinked catheter, is the most common trigger of AD, so the bladder is checked before the bowel and skin (section 32.2, Autonomic Dysreflexia; Clinical Safety box). Option b reverses the order; the bowel is checked after the bladder, and constipation is not the most common cause. Option c delays the search for the cause. Option d checks the skin before the more likely causes and moves her out of the upright position.

3. [CORE] The RPN finds a kink in the catheter tubing and straightens it. Urine begins to drain. Which action should the RPN take at the same time?

a. Document the episode in detail at the end of the shift, because the cause has now been found and removed.

b. Notify the RN and the physician or NP, and keep checking her blood pressure every 2 to 5 minutes.

c. Clamp the catheter after 500 mL so that the bladder does not empty too quickly.

d. Lay her flat in bed as soon as urine is draining so that she can rest comfortably after the episode.

Answer: b — The RPN reports AD early and keeps monitoring the blood pressure every 2 to 5 minutes until it settles, calling the emergency response if it does not fall (section 32.2, Autonomic Dysreflexia). Option a delays reporting; the team needs to know now in case the pressure stays high and medicine is needed. Option c is not part of the first actions taught in this chapter and could leave the trigger in place. Option d is premature; she stays upright until the pressure is back to her usual level.

4. [CORE] Ms. Osei's blood pressure returns to 104/66 mm Hg. Which teaching point is most important for her before discharge?

a. "Lying flat during an episode is the safest way to bring your blood pressure down quickly."

b. "A blood pressure of 130 over 80 is normal for adults, so you only need to get help if it goes above 160."

c. "This happens only in the first few months after an injury, so you will not need to watch for it once you are home."

d. "Carry a wallet card with the warning signs, first steps and your usual blood pressure, and show it to staff."

Answer: d — A wallet card helps her and health care staff, who may not know about AD, act quickly (section 32.2, Autonomic Dysreflexia). Option a is wrong; she should sit up. Option b is dangerous; her usual pressure is about 98/62 mm Hg, and for people like her a systolic reading above 130 mm Hg can already be a sign of AD. Option c is wrong; episodes are not limited to the first months after injury (almost everyone at risk has an episode within the first year), so she keeps her prevention routines and her wallet card at home.

5. [CORE] An adult is seen in a clinic two days after a concussion from a fall while skating. Which statement by the patient shows understanding of the plan for activity?

a. "I will stay in bed in a dark, quiet room until every one of my symptoms is completely gone, however long it takes."

b. "I can go back to playing hockey tomorrow if my headache is gone by the morning."

c. "I'll increase my activity a little at a time, and slow down if my symptoms stay worse for more than a day."

d. "I should avoid all walking and reading for at least two weeks so my brain can fully heal."

Answer: c — After about 24 to 48 hours of relative rest, the Living Concussion Guidelines encourage a gradual return to activity, slowing the pace if symptoms worsen for more than about 24 hours (section 32.1, Concussion and Mild TBI). Option a is wrong; complete bed rest for more than three days should be avoided. Option b is unsafe; activities with a high risk of another concussion should be avoided, particularly in the first 7 to 10 days. Option d prolongs rest beyond what the guideline recommends; light activity such as walking is encouraged.

6. [CORE] The nurse is teaching a patient and a support person before discharge after a concussion. Which findings should prompt them to go to the emergency department or call 9-1-1? Select all that apply.

a. Vomiting more than twice

b. A headache that keeps getting worse

c. Feeling more tired than usual in the evening

d. Fluid or blood coming from the nose or ear

e. Being very hard to wake up

f. Mild trouble concentrating while reading

Answer: a, b, d, e — Vomiting more than twice, a worsening headache, fluid or blood from the ear or nose, and being hard to wake are warning signs that call for emergency care (section 32.1, Patient Education: After a Concussion). Options c and f are common, expected symptoms of concussion that usually improve with a gradual return to activity; they need follow-up if they persist, not emergency care.

7. [CORE] An 82-year-old woman who takes an anticoagulant for atrial fibrillation tripped in her kitchen and struck her head an hour ago. She is alert, oriented and says she feels fine. Which action by the nurse in the community clinic is most appropriate?

a. Arrange urgent assessment by a physician or NP and report her anticoagulant use.

b. Reassure her that she does not need assessment because she is alert and did not lose consciousness.

c. Tell her to hold her next anticoagulant dose and to call the clinic tomorrow if she has a headache.

d. Apply the Canadian CT Head Rule to decide whether she needs a CT scan and tell her the result.

Answer: a — The Canadian CT Head Rule does not apply to people taking anticoagulants, who need extra consideration, and age over 65 is a risk factor; she needs prompt assessment even though she seems well (section 32.1, Lifespan Considerations: Head Injury in Older Adults). Option b misses that bleeding may develop later and that older adults often have few early signs. Option c delays assessment and changes a medicine without an order. Option d is outside the nurse's role, and the rule does not apply to people taking anticoagulants.

8. [CORE] A patient admitted after a fall with a skull fracture was talking and oriented two hours ago. Now he is harder to wake and answers with confused words. Which action should the RPN take first?

a. Document the change and plan to repeat the neurologic check at the next scheduled time.

b. Give the ordered analgesic, because pain may be making him drowsy, restless and less cooperative with checks.

c. Report the change to the RN at once and call the rapid response team if criteria are met.

d. Encourage him to sleep, because rest is the main treatment for a brain injury.

Answer: c — A falling level of consciousness after a head injury may mean an expanding hematoma, such as an epidural hematoma after a lucid interval, and needs immediate escalation (section 32.1, Moderate and Severe TBI; Chapter 6). Option a delays action for a possibly life-threatening change. Option b may hide further decline and does not address its cause. Option d ignores a sign of deterioration.

9. [CORE] An 84-year-old man is brought to the clinic by his daughter because he has become forgetful and unsteady over the past three weeks. She mentions that he slipped on his front step about a month ago but "didn't hit hard." Which response by the nurse is most appropriate?

a. Tell the daughter that these changes are typical of normal aging and suggest a memory clinic referral next year.

b. Report the new confusion and recent fall to the physician or NP as a possible chronic subdural hematoma.

c. Suggest that the family increase his fluid intake and recheck his memory in two weeks.

d. Advise the daughter that a minor fall a month ago is too long ago to explain his symptoms.

Answer: b — A chronic subdural hematoma can appear days to weeks after a low-energy fall in an older adult, and cognitive impairment is its main symptom, so it can be mistaken for dementia (section 32.1, Moderate and Severe TBI). Option a assumes aging and delays assessment. Option c delays assessment of a possibly serious cause. Option d is wrong; the interval from injury can be up to two months.

10. [CORE] A patient with a moderate TBI is receiving oxygen. Which finding should the nurse act on first to prevent secondary brain injury?

a. Temperature 37.2 °C

b. Head of the bed at 30 degrees

c. Oxygen saturation 89%

d. Systolic blood pressure 128 mm Hg

Answer: c — Low oxygen causes secondary brain injury; the ENLS protocol recommends keeping SpO_2 at 94% or higher (section 32.1, Moderate and Severe TBI). Option a is a normal temperature. Option b is the recommended head-of-bed position. Option d is above the recommended minimum systolic pressure.

11. [CORE] A patient recovering from a severe TBI is in post-traumatic amnesia. He is restless, pulls at his blanket and tries to climb out of bed. Which nursing approach is most appropriate?

a. Keep the room quiet, limit visitors, use consistent staff and give simple orienting cues.

b. Ask for an order for a benzodiazepine to keep him calm through the night shift.

c. Apply bilateral wrist restraints and recheck his behaviour every four hours.

d. Turn on the television and invite several family members to visit at once to stimulate him.

Answer: a — The Canadian rehabilitation guideline recommends a secure, supervised, low-stimulation environment with consistent staff and orienting information during PTA (section 32.1, Moderate and Severe TBI). Options b and c run against the guideline, which advises minimizing sedating medicines and restraints because they may slow emergence from PTA. Option d adds stimulation that the injured brain may not tolerate.

12. [CORE] Six weeks after a concussion, a 38-year-old office worker still has headaches and trouble concentrating and has not returned to work. Which action is most consistent with the Living Concussion Guidelines?

a. Advise her to stay in bed until the headaches stop, then return to full duties.

b. Tell her that symptoms lasting six weeks are no longer related to the concussion and need no follow-up.

c. Recommend that she resume her usual contact sports to test whether her brain has fully recovered.

d. Support referral to interdisciplinary concussion services and screen for depression and anxiety.

Answer: d — For symptoms lasting more than one month, the guideline recommends considering referral to interdisciplinary concussion services, and it recommends routine monitoring for depression and anxiety (section 32.1, Concussion and Mild TBI). Option a promotes prolonged bed rest, which should be avoided. Option b dismisses persisting symptoms, which affect at least one in six adults. Option c risks a second injury.

13. [CORE] A patient with a suspected cervical spine injury needs to be turned to check the skin on his back. Which action by the nurse is correct?

a. Ask the patient to grab the side rail and pull himself over while the nurse supports his head and neck.

b. Log roll him with enough trained staff, moving the head, shoulders and hips as one unit.

c. Remove the cervical collar first so that the skin under it can be checked during the turn.

d. Raise the head of the bed to 45 degrees before turning so that he can breathe more easily.

Answer: b — Until the spine is cleared, the patient is moved with a log roll so that the spine does not twist, using enough trained staff and following employer policy (section 32.2, Early Care). Option a twists the spine. Option c removes spinal motion restriction without an order. Option d bends the spine during the turn.

14. [CORE] A patient admitted yesterday with a C4 spinal cord injury has a weaker cough than this morning and is working harder to breathe. Which explanation best guides the nurse's response?

a. A C4 injury weakens the diaphragm and the muscles used to cough, so breathing can fail.

b. Weak coughing is expected after any SCI and does not need to be reported unless a fever also develops.

c. Lung problems after an SCI usually develop only after the first month, once the person starts rehabilitation.

d. The injury affects only the legs, so the breathing change is probably caused by anxiety.

Answer: a — The diaphragm is supplied mainly by C3 to C5, and the muscles for coughing by thoracic nerves, so a C4 injury puts breathing at serious risk; respiratory complications are common in acute SCI and need immediate reporting (section 32.2, Early Care). Option b delays escalation. Option c is wrong; respiratory complications are a major problem of the acute phase. Option d is wrong; a cervical injury causes tetraplegia and affects breathing.

15. [CORE] A patient with an acute C6 spinal cord injury has a blood pressure of 82/48 mm Hg and a heart rate of 46 beats/min. His skin is warm and dry, and there is no sign of bleeding. Which condition do these findings suggest?

a. Hypovolemic shock from internal bleeding

b. Autonomic dysreflexia

c. Spinal shock

d. Neurogenic shock

Answer: d — Neurogenic shock is low blood pressure with a slow heart rate, without another cause, after a cervical or high thoracic SCI (section 32.2, Early Care). Option a usually causes a fast heart rate. Option b causes high blood pressure. Option c is a temporary loss of reflexes below the injury, not a circulation problem.

16. [CORE] A man with paraplegia from an SCI two years ago tells the home care nurse that his leg spasms have suddenly become much worse over the past two days. What should the nurse assess for first?

a. Recovery of voluntary movement returning to his legs

b. A need for a firmer mattress to hold his legs still at night

c. A bladder infection or a new area of skin breakdown

d. Muscle strain from the exercises he does with his arms

Answer: c — When spasticity suddenly worsens for no clear reason, look for a problem below the injury; a bladder infection and a pressure area are common causes (section 32.2, Ongoing Care and Rehabilitation). Option a is unlikely to appear as a sudden worsening of spasms. Option b does not look for a cause. Option d does not explain a change in leg spasms below the injury.

17. [CORE] On a rehabilitation unit in Ontario, an RPN is assigned a patient with a cervical SCI who has had autonomic dysreflexia twice this week. Which statement best reflects CNO's approach to scope of practice?

a. RPNs may not care for patients with SCI, because CNO classifies every patient with an SCI as unstable and unpredictable.

b. She may provide care if she has the authority and competence, the context supports her, and she consults the RN as needs change.

c. The RPN must hand the patient over to an RN, but only after the patient's next episode of autonomic dysreflexia occurs.

d. The RPN may care for the patient only if the patient's condition is predictable and the risk of negative outcomes is low.

Answer: b — CNO's Scope of Practice standard uses authority, competence and context; employer policy and province or territory also matter, and the RPN consults the RN as the patient's needs change (section 1.3; section 32.2). Option a presents a patient classification as a CNO rule, which it is not. Option c waits for harm before getting support. Option d uses a retired three-factor framework that is no longer part of CNO's standard.

18. [RN] Two patients were admitted after head injuries. Patient A lost consciousness briefly, woke and talked normally, and two hours later became drowsy with a dilated right pupil. Patient B, 79 and taking an antiplatelet medicine, became confused and unsteady three weeks after a minor fall. Which interpretation is most accurate?

a. Patient A's picture fits a chronic subdural hematoma, and Patient B's picture fits an acute epidural hematoma.

b. Patient A's picture fits an epidural hematoma after a lucid interval, and Patient B's fits a chronic subdural hematoma.

c. Both patients most likely have concussions, which can be safely monitored at home with written discharge teaching.

d. Both patients most likely have diffuse axonal injury from acceleration and deceleration forces.

Answer: b — A brief loss of consciousness followed by a lucid interval and then decline is typical of an epidural hematoma; new confusion weeks after a low-energy fall in an older adult taking an antithrombotic medicine suggests a chronic subdural hematoma (section 32.1, Moderate and Severe TBI; Table 32.1). Option a reverses the two. Option c misses red flags that need urgent assessment. Option d does not fit; diffuse axonal injury follows acceleration and deceleration and alters consciousness from the moment of injury, not after a lucid interval or weeks later.

19. [RN] On day 1 after a C5 spinal cord injury, a patient has no reflexes in his legs, a blood pressure of 86/50 mm Hg and a heart rate of 50 beats/min. Which statement about this patient is accurate?

a. The absent reflexes show spinal shock, and the low blood pressure with a slow heart rate shows neurogenic shock.

b. The absent reflexes and the low blood pressure both show neurogenic shock, which is another name for spinal shock.

c. The slow heart rate shows that he is bleeding internally and needs a blood transfusion before any other care is given.

d. The absent reflexes prove that the injury is complete and that no recovery of function is possible.

Answer: a — Spinal shock is a temporary loss of reflexes below the injury; neurogenic shock is hypotension with bradycardia from loss of sympathetic tone after a cervical or high thoracic injury (section 32.2, Early Care). Option b confuses the two terms. Option c is wrong; bleeding usually causes a fast heart rate. Option d is wrong; completeness depends on sacral sparing on the ISNCSCI examination, not on reflexes during spinal shock.

20. [RN] An ISNCSCI examination shows a neurologic level of C6. The patient feels light touch and pinprick around the anus but cannot contract the anal sphincter and has no voluntary movement below C6. Which classification fits?

a. AIS A, complete, with no sacral sparing

b. AIS C, motor incomplete

c. AIS D, motor incomplete

d. AIS B, sensory incomplete

Answer: d — Preserved sensation in S4–S5 makes the injury incomplete; with no motor function below the level, it is AIS B, sensory incomplete (section 32.2, Going Deeper: Classifying Spinal Cord Injury). Option a requires no sacral sensation or movement. Options b and c require preserved motor function below the neurologic level.

Case: Daniel Kowalski (Questions 21–26): Daniel Kowalski, 44, was admitted to a medical unit 2 days ago with tingling in his feet and leg weakness that began 3 days after a bout of diarrhea 2 weeks earlier. He weighs 80 kg. The neurologist diagnosed Guillain–Barré syndrome, and IVIG was started yesterday. Today at 1400 he cannot lift his arms off the bed. His cough is weak, he speaks in short phrases and he counts to 14 on one breath. His FVC is 1.5 L, down from 2.4 L at 0800 and 3.6 L on admission. Over the past 4 hours his heart rate has varied from 52 to 128 beats/min and his blood pressure from 96/58 to 168/96 mm Hg. Oxygen saturation is 96% on room air, temperature 36.9 °C. His knee and ankle reflexes are absent. He says, "I can't get a proper breath. Am I going to die?"

21. [CORE] Which findings at 1400 should the nurse recognize as cues that need immediate follow-up? Select all that apply.

a. FVC of 1.5 L, down from 2.4 L at 0800

b. Weak cough and speaking in short phrases

c. Oxygen saturation of 96% on room air

d. Heart rate varying from 52 to 128 beats/min

e. Absent knee and ankle reflexes

f. New inability to lift his arms off the bed

Answer: a, b, d, f — A falling FVC, a weak cough with short phrases and weakness that has spread to his arms show that the weakness is rising toward the breathing muscles (a, b, f; section 32.5). Wide swings in heart rate show autonomic dysfunction, which can cause dangerous rhythms (d). A normal saturation is not reassuring in GBS, because it falls late (c; Going Deeper box). Absent reflexes are an expected finding in GBS and not a new change (e).

22. [CORE] Which explanation best links Mr. Kowalski's findings?

a. Anxiety about his diagnosis is causing him to breathe shallowly, which lowers his FVC and speeds up his heart rate.

b. A new chest infection from lying in bed is filling his lungs with secretions and making both his cough and his FVC worse.

c. GBS is spreading upward to his breathing muscles and has damaged the autonomic nerves that control heart rate and blood pressure.

d. IVIG started yesterday is causing an infusion reaction, which explains his blood pressure changes, breathing trouble and weakness.

Answer: c — GBS causes weakness that climbs from the legs to the arms and the muscles of breathing and swallowing, and autonomic involvement causes swings in heart rate and blood pressure (c; section 32.5). Anxiety does not explain a steady fall in FVC and spreading weakness (a). He has no fever, and his saturation is normal, so infection is less likely (b). An infusion reaction would not explain weakness that rises in the typical GBS pattern (d).

23. [RN] Which hypothesis should the nurse treat as the priority?

a. Impending respiratory failure, because his FVC has fallen by more than 30% today and is now about 19 mL/kg

b. Deep vein thrombosis, because he has been unable to move his legs for several days and is at high risk of a clot

c. Urinary retention from autonomic dysfunction, because a full bladder can raise blood pressure and heart rate

d. Severe anxiety, because he has asked whether he is going to die and needs reassurance and support right away

Answer: a — His FVC fell from 2.4 L to 1.5 L in 6 hours, a drop of more than 30%, and 1.5 L in an 80-kg man is about 19 mL/kg. The EAN/PNS guideline states that such a fall likely means transfer to intensive care and that elective ventilation should be considered at 20 mL/kg or less (a; Going Deeper box). Clot prevention, bladder checks and emotional support all matter, but breathing comes first (b, c, d).

24. [CORE] What should the nurse do first?

a. Give oxygen by nasal prongs, raise the head of the bed, and recheck his FVC and oxygen saturation again in 4 hours.

b. Ask the physician for an order for a sedative to relieve his anxiety and help him breathe more slowly and deeply.

c. Document the findings, increase his vital signs to every 2 hours and report them at the next scheduled handover.

d. Call the rapid response or critical care outreach team per policy and report the falling FVC and vital signs using SBAR.

Answer: d — A falling FVC, weak cough and autonomic swings are reasons to involve critical care now, so the nurse escalates at once with SBAR (d; section 32.5; Chapter 6). Oxygen does not treat weak muscles, and waiting 4 hours could allow respiratory failure (a). A sedative can depress breathing further (b). Documenting and waiting delays care for a deteriorating patient (c).

25. [CORE] While Mr. Kowalski waits for transfer and after he moves to the intensive care unit, which actions belong in his plan of care? Select all that apply.

a. Give VTE prophylaxis as ordered and check the fit of compression devices.

b. Reposition him on a schedule and inspect the skin over pressure points.

c. Explain each procedure to him and set up a call system that he can use.

d. Limit visits from his family so that he can rest and conserve his strength.

e. Offer thin fluids often to prevent dehydration while his cough is weak.

f. Ask him about pain and give analgesia as ordered, then reassess its effect.

Answer: a, b, c, f — Immobile patients with GBS need prevention of clots and pressure injuries (a, b; section 32.5; Chapters 19 and 35). He is fully awake and frightened, so explaining procedures and giving him a way to call for help are essential (c). Pain is common in GBS and must be assessed and treated (f). Family presence usually comforts rather than tires him, and limiting it is not part of the plan (d). Thin fluids are unsafe with a weak cough and possible swallowing weakness; his swallowing must be assessed first (e).

26. [CORE] Three days later, which finding best shows that his care is working?

a. He sleeps through most of the day and no longer asks questions about his illness or his treatment plan.

b. His FVC is stable at 2.0 to 2.1 L on three checks, his heart rate stays 72 to 90 beats/min and he uses the call system.

c. His oxygen saturation is 98% on 2 L of oxygen by nasal prongs, and his knee and ankle reflexes remain absent.

d. His blood pressure ranges from 100/60 to 170/98 mm Hg, and his weakness has spread to the muscles of his face.

Answer: b — A stable FVC on repeated checks, a steady heart rate and his ability to call for help show stable breathing, autonomic control and communication (b; section 32.5). Sleeping all day and no longer asking questions may signal fatigue, low mood or rising carbon dioxide, not improvement (a). Saturation on oxygen is a poor measure of muscle strength, and reflexes return late (c). Wide blood pressure swings and spreading weakness show the disease is still progressing (d).

27. [CORE] A woman with relapsing-remitting MS has had worse numbness and weakness in her legs since yesterday. Her temperature is 38.4 °C, and her urine is cloudy and foul-smelling. What is the best interpretation?

a. She is having a new relapse caused by fresh inflammation in her spinal cord, and high-dose corticosteroids should be started now.

b. Her MS has changed to the secondary progressive form, so her symptoms are expected to worsen steadily from now on.

c. Her disease-modifying therapy has stopped working, and she should ask her neurologist to change it to a different drug.

d. Her fever from a likely urinary tract infection may be causing a pseudo-relapse, so the infection should be reported and treated.

Answer: d — Fever and infection can bring back old symptoms without new inflammation, a pseudo-relapse that settles as the temperature returns to normal (d; section 32.3). A relapse is diagnosed only when no outside factor such as infection explains the change (a). One day of worse symptoms with fever does not show a change in disease course (b) or a failed DMT (c).

28. [CORE] A patient with MS receives natalizumab infusions. Which statement shows correct understanding of the teaching?

a. "My partner and I will report weakness on one side, clumsiness, vision changes or changes in my memory or personality."

b. "I can skip the hour of observation after my infusions now, because I have never had a reaction to the medicine before."

c. "If I have a cold sore, I should keep it to myself, because it is a minor problem that has nothing to do with this drug."

d. "This medicine has no serious infection risks, so I don't need regular check-ups with my prescriber while I am taking it."

Answer: a — The Canadian monograph warns of PML, which develops over days to weeks with one-sided weakness, clumsiness, vision changes and changes in thinking that the person may not notice, so partners are included (a; section 32.3). The monograph asks that patients be observed during each infusion and for an hour after it ends (b). The drug increases the risk of herpes infections of the brain and its coverings, so herpes symptoms are reported (c). Regular prescriber review is required (d).

29. [CORE] A patient with Parkinson disease is NPO after midnight for surgery at 1000. His home levodopa-carbidopa schedule is 0600, 0900, 1200, 1500 and 1800. What should the nurse do?

a. Hold all doses until after surgery, because nothing at all may be given by mouth while the patient is NPO for anesthesia.

b. Give the 0600 and 0900 doses together at 0600, so that he has enough medication on board to last through the surgery.

c. Contact the prescriber, anesthesia team and pharmacist before 0600 to plan how his doses will continue around surgery.

d. Ask his wife to give him his tablets from home at the usual times, because family members are not bound by NPO orders.

Answer: c — Missed or late doses can leave symptoms uncontrolled, and sudden withdrawal can cause a dangerous reaction, so the nurse plans with the team ahead of the first dose (c; section 32.4; Chapter 7). Simply holding doses is unsafe (a). Doubling doses is not ordered and may cause side effects (b). Asking family to give medications secretly bypasses the NPO plan and the care team (d).

30. [CORE] A patient with Parkinson disease says that he feels dizzy every morning when he gets out of bed. Which action is most appropriate?

a. Encourage him to get up quickly so that the dizziness passes before he walks to the bathroom.

b. Measure his blood pressure lying and standing and teach him to sit at the bedside before he stands.

c. Hold his morning levodopa-carbidopa dose until the dizziness has passed and his balance has returned.

d. Restrict his fluid intake in the evening so that he has fewer trips to the bathroom during the night.

Answer: b — Dizziness on rising suggests orthostatic hypotension, which is common in Parkinson disease and can be worsened by levodopa; the nurse measures orthostatic vital signs and teaches him to rise slowly (b; section 32.4). Getting up quickly increases the risk of falls (a). Holding levodopa worsens motor symptoms and is not the nurse's decision alone (c). Restricting fluids can worsen low blood pressure (d).

31. [CORE] Which findings in a patient with Parkinson disease are non-motor symptoms? Select all that apply.

a. Constipation

b. Loss of the sense of smell

c. Acting out dreams during sleep

d. Stiffness when the nurse moves the patient's arm

e. Low mood and loss of interest

f. Slowness of movement with small steps

Answer: a, b, c, e — Constipation, loss of smell, REM sleep behaviour disorder and depression or apathy are non-motor symptoms of Parkinson disease, and some may appear before the tremor (a, b, c, e; section 32.4). Rigidity (d) and bradykinesia (f) are motor signs.

32. [CORE] A patient with myasthenia gravis is starting pyridostigmine. Which teaching is accurate?

a. "If your weakness gets worse, take an extra tablet, because a larger dose of this medicine always improves your strength."

b. "Crush the slow-release tablets into applesauce if you have trouble swallowing them, so that the medicine works faster."

c. "Take your doses whenever you remember them, because the timing makes no difference to how well this medicine works."

d. "Take each dose on time, swallow the tablets whole, and report any worsening weakness instead of taking extra doses."

Answer: d — The monograph states that tablets are swallowed whole and not crushed, and that patients should not raise their dose without consulting the prescriber; too much can cause cholinergic weakness (d; section 32.5). Extra doses can cause a cholinergic crisis (a). Slow-release tablets must not be crushed (b). Timing matters so that strength peaks when it is needed, such as at meals (c).

33. [CORE] A patient with myasthenia gravis develops a urinary tract infection. The prescriber orders ciprofloxacin. What should the nurse do?

a. Contact the prescriber or pharmacist before giving it, because fluoroquinolones can worsen MG and a safer alternative may exist.

b. Give the first dose as ordered and then ask the patient to rate her weakness on a scale of 0 to 10 every morning for a week.

c. Give the medication with a double dose of pyridostigmine, so that any extra weakness from the antibiotic is prevented.

d. Hold the antibiotic until her MG symptoms are fully controlled, because infections do not affect MG and treatment can safely wait.

Answer: a — Fluoroquinolones are linked to MG worsening and are best avoided if a safer alternative exists, so the nurse questions the order before giving it (a; section 32.5). Giving it without question and only checking weakness daily may miss a crisis (b). Doubling pyridostigmine is not ordered and can cause a cholinergic crisis (c). Infection is itself a trigger for MG worsening, so it should not be left untreated (d).

34. [CORE] Which finding would the nurse expect when assessing a patient with early Guillain–Barré syndrome?

a. Weakness that started in the face and is now moving down toward the arms and legs

b. Brisk knee and ankle reflexes with a sustained beating of the foot when it is flexed upward

c. Tingling in the feet followed by leg weakness, with reduced or absent knee and ankle reflexes

d. Weakness on one side of the body only, with drooping of the face and slurred speech on the same side

Answer: c — GBS typically starts with tingling in the feet and hands, followed by weakness that rises from the legs, with reduced or absent reflexes (c; section 32.5). Weakness spreading downward from the face is not the typical pattern (a). Brisk reflexes suggest a problem in the brain or spinal cord, not the peripheral nerves (b). One-sided weakness with facial droop suggests a stroke (d; Chapter 31).

35. [CORE] A man with ALS says to the nurse, "My breathing is getting worse. I don't know whether I would want a breathing machine." What is the best response?

a. "That decision belongs to your neurologist, who will tell you which breathing support is best for you at your next visit."

b. "It helps to think about this early. What matters most to you as your illness changes, and who would you want involved?"

c. "Most people with ALS choose a breathing machine, so I would not worry about deciding this until you need it."

d. "Let's not talk about that today. Your breathing is still fine, and thinking about it will only make you feel anxious."

Answer: b — Advance care planning starts when the person is ready, and decisions about breathing support are best made early, before an emergency; the nurse explores his values and who he wants involved (b; section 32.6; Chapter 10). The decision is his, made with the team, not the neurologist's alone (a). Waiting until he needs it risks a crisis decision, and the claim about most people is unsupported (c). Closing the conversation ignores his concern (d).

36. [CORE] A patient with ALS is taking riluzole. Which tests should the nurse expect to be monitored?

a. Serum sodium and potassium levels

b. Thyroid-stimulating hormone level

c. Hemoglobin A1C and fasting glucose

d. Liver enzymes and blood counts

Answer: d — The Canadian ALS recommendations state that riluzole is generally well tolerated with monitoring of liver enzymes and blood counts (d; section 32.6; Table 32.4). The other tests are not the specific monitoring linked to riluzole (a, b, c).

37. [CORE] An RPN is caring for a patient with Guillain–Barré syndrome. At 1000, the patient's FVC is 2.1 L; at 1300, it is 1.5 L, and the patient has a weaker cough. What should the RPN do?

a. Report the change to the RN and the physician at once and stay with the patient, because a falling FVC needs urgent review.

b. Recheck the FVC at the next scheduled time, because a single low reading may simply be caused by poor effort from the patient.

c. Ask the patient to cough and deep breathe every hour and record the FVC result in the chart for the day shift to review.

d. Give oxygen by nasal prongs and wait for the RN to finish another patient's admission before reporting the change.

Answer: a — Any nurse who sees a deteriorating trend acts at once and escalates; the RPN consults the RN as the patient's needs change (a; Scope in Practice box; Chapter 6). Waiting for the next check delays care (b). Coughing exercises and documentation without reporting do not address the danger (c). Oxygen does not treat weak breathing muscles, and the report must not wait (d).

38. [CORE] On a medical unit, an RPN is asked to start an IVIG infusion for a patient with myasthenia gravis. What determines whether the RPN may do this?

a. A CNO rule that only RNs may give any intravenous medication or blood product to patients in hospital.

b. The patient's diagnosis, because MG is a chronic disease and RPNs may give any medication for chronic diseases.

c. The RPN's authority, competence and the context, including the employer's policy on who may give blood products.

d. The physician's order, because any nurse must give an ordered medication once a physician has written and signed the order.

Answer: c — CNO's Scope of Practice standard asks nurses to consider authority, competence and context, and employer policy sets who may give blood products such as IVIG (c; Scope in Practice box; section 1.3). No CNO rule limits all IV medications to RNs (a). The diagnosis alone does not decide who gives a medication (b). An order is needed, but the nurse must still have the authority and competence and must work in a suitable context (d).

39. [RN] A patient with myasthenia gravis, on day 2 of treatment for pneumonia, has a nasal voice, coughs when drinking, counts to 12 on one breath and has an FVC that has fallen from 2.2 L to 1.4 L since morning. Oxygen saturation is 96%. Which interpretation and action are best?

a. Cholinergic crisis from too much pyridostigmine is most likely, so the nurse gives an extra dose of pyridostigmine to see if strength improves.

b. Impending myasthenic crisis is likely, so the nurse makes the patient NPO, sits the patient upright and escalates for critical care review now.

c. The pneumonia is improving, because the oxygen saturation is normal, so the nurse continues the current plan and rechecks the FVC tomorrow morning.

d. The patient is tired from coughing, so the nurse plans rest periods, offers thin fluids slowly and reports the findings at handover.

Answer: b — Infection is a known trigger, and worsening swallowing, voice and breathing measures point to impending myasthenic crisis, which needs close monitoring and intensive care or step-down care if it progresses (b; section 32.5; Clinical Judgment box). Giving extra pyridostigmine is unsafe; the team judges whether cholinergic weakness is present (a). Normal saturation is a late sign and does not rule out muscle failure (c). Thin fluids are unsafe, and waiting for handover delays escalation (d).

40. [RN] A patient with Parkinson disease is on day 1 after abdominal surgery. Her levodopa-carbidopa is due at 1400; it is 1340. She is nauseated, and the postoperative order set includes metoclopramide intravenously as needed. What should the nurse do?

a. Give metoclopramide now and delay the levodopa-carbidopa until her nausea has settled, to make sure she keeps the tablets down.

b. Give metoclopramide now and give the levodopa-carbidopa on time, because metoclopramide speeds levodopa absorption and helps it work.

c. Hold both drugs until the surgeon's rounds tomorrow, because nausea after surgery usually resolves without any medication.

d. Give the levodopa-carbidopa on time and ask the prescriber for an antiemetic that does not block dopamine instead of metoclopramide.

Answer: d — Levodopa is time-critical, and metoclopramide blocks dopamine, may worsen disease control and should be given in Parkinson disease cautiously, if at all; the nurse gives the levodopa on time and asks for an alternative antiemetic (d; section 32.4). Delaying levodopa risks loss of motor control (a). Faster absorption does not offset metoclopramide's dopamine-blocking effect (b). Holding levodopa until tomorrow risks a dangerous withdrawal reaction and leaves nausea untreated (c).

References

Brain injury advice card (short version). (n.d.). [Appendix 1.4, Guidelines for concussion/mTBI and persistent symptoms, 3rd ed.]. Living Concussion Guidelines. Retrieved October 27, 2026, from https://concussionsontario.org/sites/default/files/2023-03/appendix-1-4.pdf

Alberta Health Services, Neurosciences, Rehabilitation & Vision Strategic Clinical Network. (2021). *Autonomic dysreflexia: Adult protocol* [Pocket card]. https://albertahealthservices.ca/assets/about/scn/ahs-scn-nrv-autonomic-dysreflexia-card.pdf

ALS Canada. (2025). *ALS quick facts* [Fact sheet]. https://als.ca/wp-content/uploads/2024/05/ALS-Canada-Quick-Facts-Fact-Sheet-2025.pdf

American Spinal Injury Association. (n.d.). *International Standards Committee updates*. Retrieved October 27, 2026, from https://asia-spinalinjury.org/international-standards-committee-updates/

Bausch Health, Canada Inc. (2019). *Mestinon (pyridostigmine bromide tablets USP) and Mestinon-SR (pyridostigmine bromide slow release tablets) product monograph*. https://pdf.hres.ca/dpd_pm/00052033.PDF

Biogen Canada Inc. (2025). *Tysabri (natalizumab) product monograph*. https://pdf.hres.ca/dpd_pm/00078272.PDF

Consortium for Spinal Cord Medicine. (2026). *Outcomes following traumatic spinal cord injury: Clinical practice guideline for health care professionals* (2nd ed.). Paralyzed Veterans of America. https://pva.org/wp-content/uploads/2021/09/CPG_Outcomes_07.20.pdf

Cowley, E., Miller, M. R., Yin, C., & Kelly, L. (2021). Correlation between medication administration–related errors in patients with Parkinson disease and timing of pharmacy-led best possible medication histories. *The Canadian Journal of Hospital Pharmacy, 74*(1), 15–20. https://doi.org/10.4212/cjhp.v74i1.3036

Emergency Care BC. (2023). *Managing patients with Parkinson's disease in the emergency department*. https://emergencycarebc.ca/clinical_resource/managing-patients-with-parkinsons-disease-in-the-emergency-department/

Ganz, J. C. (2013). The lucid interval associated with epidural bleeding: Evolving understanding. *Journal of Neurosurgery, 118*(4), 739–745. https://doi.org/10.3171/2012.12.JNS121264

Government of British Columbia. (2024). *Concussion/mild traumatic brain injury (mTBI)* [BC Guidelines]. https://www2.gov.bc.ca/gov/content/health/practitioner-professional-resources/bc-guidelines/concussion-mild-traumatic-brain-injury-mtbi

Grimes, D., Fitzpatrick, M., Gordon, J., Miyasaki, J., Fon, E. A., Schlossmacher, M., Suchowersky, O., Rajput, A., Lafontaine, A. L., Mestre, T., Appel-Cresswell, S., Kalia, S. K., Schoffer, K., Zurowski, M., Postuma, R. B., Udow, S., Fox, S., Barbeau, P., & Hutton, B. (2019). Canadian guideline for Parkinson disease. *CMAJ, 191*(36), E989–E1004. https://doi.org/10.1503/cmaj.181504

JAMP Pharma Corporation. (2023). *Metoclopramide hydrochloride injection product monograph*. https://pdf.hres.ca/dpd_pm/00070463.PDF

Jang, S. (2020). *Respiratory changes after spinal cord injury*. SCIRE Community. https://community.scireproject.com/wp-content/uploads/SCIRE-C.-Respiratory-Changes-After-SCI.-3-Download.pdf

KITE Research Institute, University Health Network. (2023). Post-traumatic amnesia. In *Canadian clinical practice guideline for the rehabilitation of adults with moderate to severe TBI*. https://kite-uhn.com/brain-injury/en/guidelines/post-traumatic-amnesia

Kwon, B. K., Tetreault, L. A., Martin, A. R., Arnold, P. M., Marco, R. A. W., Newcombe, V. F. J., Zipser, C. M., McKenna, S. L., Korupolu, R., Neal, C. J., Saigal, R., Glass, N. E., Douglas, S., Ganau, M., Rahimi-Movaghar, V., Harrop, J. S., Aarabi, B., Wilson, J. R., Evaniew, N., … Fehlings, M. G. (2024). A clinical practice guideline for the management of patients with acute spinal cord injury: Recommendations on hemodynamic management. *Global Spine Journal, 14*(3_suppl), 187S–211S. https://doi.org/10.1177/21925682231202348

Leonhard, S. E., Mandarakas, M. R., Gondim, F. A. A., Bateman, K., Ferreira, M. L. B., Cornblath, D. R., van Doorn, P. A., Dourado, M. E., Hughes, R. A. C., Islam, B., Kusunoki, S., Pardo, C. A., Reisin, R., Sejvar, J. J., Shahrizaila, N., Soares, C., Umapathi, T., Wang, Y., Yiu, E. M., . . . Jacobs, B. C. (2019). Diagnosis and management of Guillain–Barré syndrome in ten steps. *Nature Reviews Neurology, 15*(11), 671–683. https://doi.org/10.1038/s41582-019-0250-9

Mirkowski, M., Harnett, A., McIntyre, A., Hsieh, J. T. C., Loh, E., & Teasell, R. (2020). *Venous thromboembolism following spinal cord injury*. SCIRE Professional. https://scireproject.com/wp-content/uploads/2022/03/Venous-Thromboembolism_2020.pdf

MS Canada. (n.d.). *PHAC releases incidence and prevalence rates of multiple sclerosis in Canada*. https://mscanada.ca/ms-research/latest-research/phac-releases-incidence-and-prevalence-rates-of-multiple-sclerosis-in

Multiple Sclerosis Society of Canada. (2021). *Multiple sclerosis: A newly diagnosed guide*. https://mscanada.ca/media/553

Narayanaswami, P., Sanders, D. B., Wolfe, G., Benatar, M., Cea, G., Evoli, A., Gilhus, N. E., Illa, I., Kuntz, N. L., Massey, J., Melms, A., Murai, H., Nicolle, M., Palace, J., Richman, D., & Verschuuren, J. (2021). International consensus guidance for management of myasthenia gravis: 2020 update. *Neurology, 96*(3), 114–122. https://doi.org/10.1212/WNL.0000000000011124

Ng, S. Y., & Lee, A. Y. W. (2019). Traumatic brain injuries: Pathophysiology and potential therapeutic targets. *Frontiers in Cellular Neuroscience, 13*, Article 528. https://doi.org/10.3389/fncel.2019.00528

Oh, J., Bhan, V., Traboulsee, A., Morrow, S. A., Lee, L., Levin, M., Casserly, C., Freedman, M. S., Giacomini, P. S., Émond, F., Smyth, P., Clift, F., & Selchen, D. (2025). Health Canada drug approval process: A barrier to personalized care in multiple sclerosis. *Canadian Journal of Neurological Sciences, 52*(2), 175–178. https://doi.org/10.1017/cjn.2024.267

Ontario Ministry of Health. (2023). *Basic life support patient care standards* (Version 3.4). https://www.ontario.ca/document/patient-care-documents-reference/basic-life-support-patient-care-standards

Ottawa Hospital Research Institute. (n.d.-a). *Diagnosis*. Living Concussion Guidelines. Retrieved October 27, 2026, from https://concussionsontario.org/concussion/guideline-section/diagnosis

Ottawa Hospital Research Institute. (n.d.-b). *Initial management*. Living Concussion Guidelines. Retrieved October 27, 2026, from https://concussionsontario.org/concussion/guideline-section/initial_management

Ottawa Hospital Research Institute. (n.d.-c). *Return-to-activity/work/school considerations*. Living Concussion Guidelines. Retrieved October 27, 2026, from https://concussionsontario.org/concussion/guideline-section/return-to-activity_work_school_considerations

Parkinson Canada. (2010). *Parkinson's much more than a movement disorder*. https://www.parkinson.ca/parkinsons-much-more-than-a-movement-disorder/

Parkinson Canada. (2011). *Medication timing critical in Parkinson's disease*. https://www.parkinson.ca/medication-timing-critical-in-parkinsons-disease/

Parkinson Canada. (2019). *Working to improve good communication between people with Parkinson's, their care partners and health professionals*. https://www.parkinson.ca/working-to-improve-good-communication-between-people-with-parkinsons-their-care-partners-and-health-professionals/

Parkinson Canada. (2021). *Parkinson Canada and Catalyst announce partnership focused on promoting medication adherence for Canadians with Parkinson's*. https://www.parkinson.ca/parkinson-canada-and-catalyst-announce-partnership-focused-on-promoting-medication-adherence-for-canadians-with-parkinsons/

Peterson, J., & Delparte, J. (2022). *Autonomic dysreflexia (AD)* [Spinal Cord Essentials]. Toronto Rehab, University Health Network. https://www.uhn.ca/TorontoRehab/Spinal-Cord-Rehab/Spinal-Cord-Essentials/Documents/General-Health/SCE2-Ge2-Autonomic-Dysreflexia.pdf

Pharmascience Inc. (2020). *Levodopa-carbidopa CR (levodopa and carbidopa controlled release tablets) product monograph*. https://pdf.hres.ca/dpd_pm/00059018.PDF

Poblete, R. A., & Shaw, K. M. (2024). *Emergency Neurological Life Support: Traumatic brain injury protocol* (Version 6.0). Neurocritical Care Society. https://neurocriticalcare.org/Portals/0/ENLS%205.0/ENLS%206.0/Protocol%20V6_0_Traumatic%20Brain%20Injury.pdf

Praxis Spinal Cord Institute. (2024). *Rick Hansen Spinal Cord Injury Registry (RHSCIR): A look at spinal cord injury in Canada in 2022*. https://praxisinstitute.org/wp-content/uploads/2024/10/Praxis-Registry-Annual-Report-2022.pdf

Public Health Agency of Canada. (2020). *Injury in review, 2020 edition: Spotlight on traumatic brain injuries across the life course*. https://www.canada.ca/en/public-health/services/injury-prevention/canadian-hospitals-injury-reporting-prevention-program/injury-reports/2020-spotlight-traumatic-brain-injuries-life-course.html

Public Health Agency of Canada. (2024). *Multiple sclerosis in Canada* [Infographic]. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/multiple-sclerosis-infographic.html

Rupp, R., Biering-Sørensen, F., Burns, S. P., Graves, D. E., Guest, J., Jones, L., Read, M. S., Rodriguez, G. M., Schuld, C., Tansey, K. E., Walden, K., & Kirshblum, S. (2021). International Standards for Neurological Classification of Spinal Cord Injury (revised 2019). *Topics in Spinal Cord Injury Rehabilitation, 27*(2), 1–22. https://doi.org/10.46292/sci2702-1

Sanders, D. B., Wolfe, G. I., Benatar, M., Evoli, A., Gilhus, N. E., Illa, I., Kuntz, N., Massey, J. M., Melms, A., Murai, H., Nicolle, M., Palace, J., Richman, D. P., Verschuuren, J., & Narayanaswami, P. (2016). International consensus guidance for management of myasthenia gravis: Executive summary. *Neurology, 87*(4), 419–425. https://doi.org/10.1212/WNL.0000000000002790

SCIRE Community Team. (2017). *Spasticity*. SCIRE Community. https://community.scireproject.com/wp-content/uploads/SCIRE-C_Spasticity_Download.pdf

SCIRE Community. (2024). *Spinal shock* [Glossary]. https://community.scireproject.com/glossary/spinal-shock

SCIRE Professional. (2022). *Neurogenic shock*. Spinal Cord Injury Research Evidence. https://scireproject.com/evidence/cardiovascular-complications-acute-phase/cardiovascular-complications/neurogenic-shock/

SCIRE Professional. (2023). *Pulmonary complications during acute SCI*. Spinal Cord Injury Research Evidence. https://scireproject.com/evidence/respiratory-management-acute-phase/introduction/pulmonary-complications-during-acute-sci/

SCIRE Professional. (2025). *Thermodysregulation*. Spinal Cord Injury Research Evidence. https://scireproject.com/evidence/autonomic-dysreflexia/other-autonomic-dysfunctions/thermodysregulation/

Sheikh, S., Alvi, U., Soliven, B., & Rezania, K. (2021). Drugs that induce or cause deterioration of myasthenia gravis: An update. *Journal of Clinical Medicine, 10*(7), Article 1537. https://doi.org/10.3390/jcm10071537

Shoesmith, C., Abrahao, A., Benstead, T., Chum, M., Dupre, N., Izenberg, A., Johnston, W., Kalra, S., Leddin, D., O'Connell, C., Schellenberg, K., Tandon, A., & Zinman, L. (2020). Canadian best practice recommendations for the management of amyotrophic lateral sclerosis. *CMAJ, 192*(46), E1453–E1468. https://doi.org/10.1503/cmaj.191721

Snider, B., Kirshblum, S., Rupp, R., Schuld, C., Read, M. S., Biering-Sørensen, F., Burns, S., Guest, J., Jones, L., Krassioukov, A., Rodriguez, G., Tansey, K., & Walden, K. (n.d.). *The International Standards for Neurological Classification of Spinal Cord Injury: Classification workbook*. American Spinal Injury Association. Retrieved October 27, 2026, from https://asia-spinalinjury.org/wp-content/uploads/2024/05/ISNCSCI-Classification-Workbook-Cases-and-Answers.pdf

Stiell, I. G., Wells, G. A., Vandemheen, K., Clement, C., Lesiuk, H., Laupacis, A., McKnight, R. D., Verbeek, R., Brison, R., Cass, D., Eisenhauer, M. A., Greenberg, G. H., & Worthington, J. (2001). The Canadian CT Head Rule for patients with minor head injury. *The Lancet, 357*(9266), 1391–1396. https://doi.org/10.1016/S0140-6736(00)04561-X

Sundblom, J., Sandberg, E., & Ronne-Engström, E. (2022). Trauma mechanisms and surgical outcomes in the elderly patient with chronic subdural hematoma. *Canadian Geriatrics Journal, 25*(1), 40–48. https://doi.org/10.5770/cgj.25.519

van Doorn, P. A., Van den Bergh, P. Y. K., Hadden, R. D. M., Avau, B., Vankrunkelsven, P., Attarian, S., Blomkwist-Markens, P. H., Cornblath, D. R., Goedee, H. S., Harbo, T., Jacobs, B. C., Kusunoki, S., Lehmann, H. C., Lewis, R. A., Lunn, M. P., Nobile-Orazio, E., Querol, L., Rajabally, Y. A., Umapathi, T., . . . Willison, H. J. (2023). European Academy of Neurology/Peripheral Nerve Society guideline on diagnosis and treatment of Guillain–Barré syndrome. *Journal of the Peripheral Nervous System, 28*(4), 535–563. https://doi.org/10.1111/jns.12594

IX Musculoskeletal, Integumentary & Sensory Care

UNIT CLINICAL SCOPE & INTEGRATION

Concludes with orthopedic trauma, fracture fixation, compartment syndrome and fat embolism surveillance, hip fracture standards and arthroplasty, osteoarthritis, rheumatoid arthritis, systemic lupus erythematosus, gout, Wounds Canada pressure injury and burn resuscitation care, and acute/chronic ophthalmic and otologic disorders.

Contents of UNIT IX

Chapter	Chapter Title	Visual Assets	Page
Chapter 33	Musculoskeletal Trauma and Orthopedic Surgery	9 Figs • 4 Tbls	p. 976
Chapter 34	Arthritis and Connective Tissue Disorders	7 Figs • 4 Tbls	p. 1008
Chapter 35	Skin, Wounds and Burns	14 Figs • 4 Tbls	p. 1040
Chapter 36	Eye and Ear Disorders	12 Figs • 4 Tbls	p. 1075

33 Musculoskeletal Trauma and Orthopedic Surgery

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Describe how fractures happen and heal, and give first care and ongoing care for casts, splints, traction and external fixators.
2. Perform and interpret a neurovascular assessment of an injured limb and report changes at once.
3. Recognize compartment syndrome and fat embolism syndrome early and take the first nursing actions, using the CJMM.
4. Teach adults about osteoporosis, fracture risk and bone health, including how to take osteoporosis medicines safely.
5. Plan care for an older adult with a hip fracture from arrival to home, including delirium prevention, early mobilization and secondary fracture prevention.
6. Provide care before and after joint replacement, spine surgery and amputation, including teaching for home.
7. Move patients safely with appropriate equipment, and distinguish RN and RPN roles in orthopedic care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 5, 6	Clinician; Collaborator	Foundations of Practice; Collaborative Practice
4, 6	Educator; Advocate	Foundations of Practice
7	Professional; Coordinator	Legal Practice; Collaborative Practice

Introduction

A broken wrist after a slip on ice, a shattered shin bone after a dirt-bike crash, a hip that gives way in a kitchen at 2 a.m.: injuries to bones and joints are among the most common reasons adults come to hospital. Many heal well with a cast and time. Others need surgery, weeks of rehabilitation and careful nursing to prevent complications that can cost a limb or a life. Nurses on emergency, surgical, orthopedic and community teams are often the first to notice that something is wrong: pain that keeps climbing, a foot that is turning pale, a patient who is suddenly short of breath on the second day after a fracture.

This chapter is the book's home for musculoskeletal trauma and orthopedic surgery. Section 33.1 explains how bones break and heal, first care after injury, casts, splints, traction and external fixators, and the neurovascular assessment of an injured limb. Section 33.2 covers the serious complications that can follow, especially compartment syndrome and fat embolism syndrome. Section 33.3 turns to osteoporosis and bone health. The second half of the chapter covers hip fracture in older adults (33.4), joint replacement and spine surgery (33.5), amputation (33.6), and mobility and safe patient handling (33.7).

The chapter builds on earlier ones. Scope of practice for registered nurses (RNs) and registered practical nurses (RPNs) is taught in section 1.3, and the Clinical Judgment Measurement Model (CJMM) in section 1.4. In other provinces and territories, practical nurses (PNs) are often called licensed practical nurses (LPNs); this chapter uses "the nurse" unless the roles differ. Pain and multimodal analgesia are in Chapter 5, deterioration and SBAR (Situation, Background, Assessment, Recommendation) communication in Chapter 6, perioperative care in Chapter 7, delirium and falls in Chapter 8, and venous thromboembolism (VTE) in Chapter 19.

33.1 Fractures and Their Care



Figure 33.1 Anterior and posterior views of the adult human skeleton, showing the 80 bones of the axial skeleton (cranium, vertebral column, thoracic cage) and the 126 bones of the appendicular skeleton (pectoral girdle, pelvic girdle, upper and lower limbs). (credit: "Figure 7.2, Axial and Appendicular Skeleton" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

How Bones Break and Heal

A **fracture** is a break in the continuity of a bone. Nurses describe fractures in plain terms because the words guide care and tell the team how serious the injury is (Figure 33.1).

- **Closed fracture:** the skin over the break is intact.
- **Open fracture:** the bone has broken through the skin, or a wound connects the outside world with the fracture. Bacteria can reach the bone, so infection is the main early concern (British Orthopaedic Association [BOA] & British Association of Plastic, Reconstructive and Aesthetic Surgeons [BAPRAS], 2017).
- **Complete and incomplete fractures:** a complete fracture goes all the way through the bone; an incomplete fracture breaks only part of it.
- **Displaced fracture:** the bone ends have moved out of their normal line.
- **Comminuted fracture:** the bone has broken into three or more pieces.
- **Pathologic fracture:** a break through bone already weakened by disease, such as a tumour that has spread to bone (Chapter 9).
- **Fragility fracture:** a break from low trauma, such as a fall from standing height, that would not normally break a healthy bone. A fragility fracture is a warning sign of osteoporosis (section 33.3) (Morin et al., 2023; Figure 33.12).

Treatment aims to put the pieces back in line and hold them there until they heal. **Reduction** is the return of the bone ends to their normal position, either by hand without an incision (closed reduction) or in surgery (open reduction). The bone is then held still with

a cast, splint, traction, an external fixator or internal fixation.

Most fractures heal through overlapping phases (Bahney et al., 2019). In the inflammatory phase, a blood clot forms within minutes, and inflammatory cells arrive to clear debris and send signals for repair. Next, new blood vessels grow into the area and repair cells move in from the bone's outer and inner linings. These cells form cartilage and then woven bone, called callus, that bridges the gap. Finally, during remodelling, bone-resorbing cells remove the temporary bone and replace it with strong, mature bone that slowly regains the bone's original shape. Inflammation is needed early but must settle for healing to go on (Bahney et al., 2019).



Figure 33.2 Common fracture patterns compared with intact bone: (a) closed, (b) open, (c) transverse, (d) spiral, (e) comminuted, (f) impacted, (g) greenstick and (h) oblique. (credit: "612 Types of Fractures" by OpenStax College/Wikimedia Commons, CC BY 4.0)

Some patients heal slowly or not at all. In a large cohort of more than 309,000 fractures in the United States, 4.9% did not unite (Zura et al., 2016). The odds of **nonunion**, a fracture that fails to heal, were higher with more severe injuries (several fractures, an open fracture, high-energy trauma) and with diabetes, smoking, obesity, osteoporosis, vitamin D deficiency and kidney disease. Some medicines were also linked to higher odds, including opioids alone or with anti-inflammatory drugs and anticoagulants (Zura et al., 2016). Laboratory work shows how some of these factors act: smoking slows the growth of new blood vessels, diabetes keeps inflammation from settling, and anti-inflammatory drugs block an enzyme the callus needs (Bahney et al., 2019). Poor blood supply to the injured bone also delays healing, and older age is linked to inflammation that is slow to settle and fewer repair cells (Bahney et al., 2019). Older adults may therefore need longer support, follow-up and protection from falls while a fracture heals. Nurses can use these links in teaching: stopping smoking, keeping blood glucose in the target range (Chapter 22) and eating well all support the body's repair work. Questions about which pain medicines to use belong with the prescriber and Chapter 5.

First Care After Injury

Life comes before limb. A patient with a fracture after major trauma is first assessed for airway, breathing, circulation and bleeding, as taught in Chapter 6. A long-bone or pelvic fracture can hide a large blood loss (Figure 33.3).

For the injured limb, the nurse supports it and assesses and documents its circulation and nerve function before any splint is applied. Clinicians realign and splint the limb, and the neurovascular assessment is repeated after any reduction or splinting, because these steps can change blood flow or press on nerves (BOA & BAPRAS, 2017). The nurse never tries to straighten a deformed limb alone. Pain relief is part of first care; Chapter 5 covers assessment and multimodal analgesia.

An open fracture needs urgent, specific care. The UK standards for open fractures from BOA and BAPRAS (2017) set out these steps:

- intravenous (IV) prophylactic antibiotics are given as soon as possible, ideally within one hour of the injury;
- the wound is touched only to clear gross contamination and to allow photographs, which are taken when the wound is first exposed so the team does not need to keep reopening it;
- the wound is dressed with gauze soaked in saline under an occlusive film until surgery;
- washing out the wound happens in the operating room, not at the bedside;



Figure 33.3 Anterior and posterior views of the major skeletal muscles of the human body. (credit: "Figure 11.5, Overview of the Muscular System" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

- debridement, the surgical removal of dead and contaminated tissue, is done urgently, at once for heavily contaminated wounds or a limb with poor blood supply.

Wound photographs are part of the health record and follow privacy rules (Chapter 1). Infection prevention is covered in Chapter 4.

Many fractures in older adults follow a fall from standing height. The nurse looks for the cause of the fall, asks about anticoagulants, and checks for head injury and hip pain as well as the obvious fracture. Chapter 8 covers falls and frailty; hip fracture is in section 33.4.

Casts, Splints and Traction

A **cast** is a rigid shell of plaster or fibreglass that wraps around the limb to hold a fracture still. A **back slab** is a splint of plaster or fibreglass moulded along one side of the limb and held on with a bandage. Because it does not wrap all the way around, a back slab leaves room for swelling and is often used soon after injury or surgery. Plaster takes longer to harden than fibreglass: in one Canadian emergency discharge guide, patients with plaster casts are told to avoid weight on the cast for three days, while fibreglass can bear weight right away if weight bearing is allowed (Emergency Care BC, 2024; Figure 33.4).

Some swelling is expected for the first two to three days. For a routine cast, one Canadian discharge guide advises raising the limb above heart level on pillows and using wrapped ice for the first one to three days (Emergency Care BC, 2024). Care is different for a patient at risk of compartment syndrome: consensus guidance from the UK Royal College of Nursing (RCN) advises keeping an injured limb at heart level in bed (RCN, 2022b), and a limb with suspected compartment syndrome is kept at heart level, not raised above it (Donaldson et al., 2014; section 33.2). The nurse checks the skin at the cast edges for rubbing and pressure, pads rough edges as policy allows, and keeps the cast clean and dry. Any new burning or stinging under a cast can mean a pressure area forming (Emergency Care BC, 2024).

Traction is a pulling force applied to a limb to restore and keep the alignment and length of a broken bone. In skin traction, the pull is applied through straps or a stirrup on the skin; in skeletal traction, it is applied through a pin or wire placed through the bone. Both use weights, ropes and pulleys. Traction may be used for a short time, for example while a patient waits for surgery. The Going Deeper box covers its care.

An **external fixator** is a frame outside the body joined to the bone by pins or wires that pass through the skin. It holds the fracture while allowing access to wounds. **Pin-site care** is the cleaning and dressing of the skin where pins enter. The evidence on pin-site care is limited and mostly of poor quality, so no single method has been shown to prevent infection best (Lethaby et al., 2013). RCN consensus guidance suggests cleaning with chlorhexidine in alcohol (or saline if chlorhexidine cannot be used), keeping the sites covered, and changing dressings about weekly unless they are wet, there is heavy drainage or infection is suspected (RCN, 2022a). Local protocols vary, and the nurse follows the one in place. Increasing pain at a pin site, spreading redness, more swelling, more drainage, or the patient bearing less weight than before can signal infection and are reported (RCN, 2022a; Figure 33.5).

Internal fixation uses plates, screws, rods or nails placed in surgery to hold the bone from inside.

Figure 33.4 A short-leg fibreglass cast immobilizing the ankle and foot while leaving the toes exposed for neurovascular checks. (credit: "Purple short leg cast" by Pagemaker787/Wikimedia Commons, CC BY-SA 4.0)

Figure 33.5 A unilateral external fixator stabilizing the femur, with metal pins passing through the skin and clamped to an external frame. (credit: "Patient with external fixator in the femur" by Ortopedikus/Wikimedia Commons, CC BY-SA 4.0)

PATIENT EDUCATION

Living With a Cast or Splint

- For the first one to three days, rest the limb on pillows and use wrapped ice for short periods while awake, keeping the cast dry (Emergency Care BC, 2024).
- Wiggle your fingers or toes often to keep them from stiffening.

- Keep the cast dry. Cover it with a plastic bag sealed with tape when washing, and do not swim or soak in a bath.
- If your skin itches under the cast, blow cool air into it with a hair dryer. Do not push anything inside the cast, such as a pencil or coat hanger, and do not use powders or lotions under it.
- Do not trim, cut or remove the cast yourself, and do not pull out the padding.
- Put weight on the cast only when your health care team says you may.
- Go to the nearest emergency department at once if you have pain that keeps getting worse or is not eased by your pain medicine, numbness or tingling, fingers or toes that look blue or grey, you cannot move your fingers or toes, the cast feels very tight, or the skin under it stings or burns (Emergency Care BC, 2024).

GOING DEEPER

Traction and External Fixation

Required for RN students; optional for PN students.

Traction works only when the pull is steady and in line. The weights must hang freely, never resting on the bed or floor, and the ropes must stay in their pulley tracks; if the patient slides down the bed until the weights touch the floor, the pull is lost. The nurse follows the local traction policy for the set-up and its checks, and does not lift, remove or change the weights unless an order and policy allow it.

Skin traction presses on the skin and on bony areas such as the heels. The nurse inspects the skin under the straps as policy directs, keeps sheets smooth and dry, and repositions the patient to relieve pressure (Chapter 35). Like a cast or a circumferential bandage, skin traction compresses the limb, so UK consensus guidance counts patients in it as at risk of compartment syndrome and restarts hourly neurovascular checks after any procedure that may affect the limb compartments (RCN, 2022b). Immobility in traction also raises the risk of venous thromboembolism (section 33.2).

For skeletal traction and external fixators, pin sites are cared for as described in section 33.1. The nurse handles the frame and limb as the surgeon's orders and local policy direct, and teaches the patient how to recognize pin-site infection and keep the dressings dry (RCN, 2022a).

Neurovascular Assessment

A **neurovascular assessment** is a check of blood flow and nerve function in a limb below an injury, cast, splint, bandage or surgical site. It finds compartment syndrome, vascular injury and nerve compression early, while they can still be treated. Table 33.1 sets out what the nurse checks.

The most important finding is pain. Pain that is out of proportion to the injury, does not ease with the expected analgesia, or increases when the nurse gently stretches the muscles of the injured compartment is the earliest and most sensitive sign of compartment syndrome (RCN, 2022b). To check pain on passive stretch, the nurse slowly straightens (extends) the fingers or toes of the affected limb without the patient's help (RCN, 2026). Numbness and tingling, weakness, colour change and weak or absent pulses are late signs, so a normal pulse does not rule out compartment syndrome (RCN, 2022b, 2026).

Colour alone is not a reliable guide on every skin tone. For patients whose skin is not white, RCN guidance advises also checking skin temperature, swelling, shininess and mottling, and comparing the injured limb with the other limb (RCN, 2026); these checks are useful for every patient. Patients who cannot report pain, such as those who are unconscious or who have a nerve block or epidural, need closer monitoring, and the nurse seeks medical advice early if compartment syndrome is suspected (RCN, 2026).

The frequency of checks follows the order or protocol. For patients at risk, RCN guidance advises checks at least hourly for the first 24 hours, then every four hours for a further 24 hours if pain is stable, and a return to hourly checks after any procedure that may affect the limb compartments, such as surgery or applying traction (RCN, 2022b). Any abnormal finding is reported at once (RCN, 2026).

Table 33.1 Neurovascular assessment of an injured limb (BOA, 2025; Emergency Care BC, 2024; RCN, 2022b, 2026)

What to check	How to check it	Expected finding	Report at once if
Pain	Ask the patient to rate pain at rest and since the last dose of analgesia; note how much analgesia has been needed	Pain is easing or stable and responds to the ordered analgesia	Pain is out of proportion to the injury, keeps rising or needs more and more analgesia

What to check	How to check it	Expected finding	Report at once if
Pain on passive stretch	Gently extend the fingers or toes beyond the injury while watching the patient's face	Mild discomfort only	Stretching the muscles causes sharp or severe pain
Sensation	Touch the skin on each side of the hand or foot and ask what the patient feels, comparing with the other limb	Normal feeling, the same as the other limb	New numbness, tingling, burning or reduced feeling
Movement	Ask the patient to wiggle and spread the fingers or toes, and to bend and straighten them	Moves fully as the injury and cast allow	New weakness or inability to move
Colour and capillary refill	Look at the skin and nail beds; press a nail bed and watch the colour return; compare with the other limb	Colour and refill match the other limb	Pale, grey, blue or mottled skin, or slow refill
Temperature	Feel the skin with the back of the hand and compare with the other limb	Warm, like the other limb	Cool or cold skin, especially if new
Pulses	Palpate the pulses beyond the injury, or use a Doppler device if the pulse cannot be felt	Pulses present and equal to the other side	A weak or absent pulse (a late sign; a present pulse does not rule out compartment syndrome)
Swelling, cast and dressing	Look at the limb and check the fit of the cast, slab or bandage	Swelling is stable and the cast or bandage does not feel tight	Swelling is increasing, the skin is tight and shiny, or the cast or bandage feels too tight

33.2 Complications After Musculoskeletal Injury

Compartment Syndrome

Muscles in the arms and legs are grouped in **compartments**, each wrapped in tough fascia that does not stretch. **Acute compartment syndrome** is a rise in pressure inside one of these closed compartments, high enough to cut off blood flow to the muscles and nerves within it (BOA, 2025). Bleeding or swelling inside the compartment, or a cast or bandage squeezing it from outside, can start the rise. As pressure climbs, small vessels collapse, tissue becomes starved of oxygen, and muscle and nerve begin to die. Without prompt treatment, the damage to muscle and nerve can become permanent.

UK consensus guidance treats every patient with an acute limb injury, limb surgery, or a cast, skin traction or circumferential bandage as at risk (RCN, 2022b). It lists higher risk with male sex, age 35 or younger, a bleeding disorder or anticoagulant use, closed fractures of the tibia or forearm, a crush injury or long-lasting compression, high-energy trauma including open fractures, and treatment with casts, circumferential bandages or fracture realignment (RCN, 2022b). A hip fracture alone is not usually considered high risk (RCN, 2022b). The nurse teaches at-risk patients and their families the warning signs, gives written information, and asks them to report rising pain or tightness at once (RCN, 2022b).

The early signs are about pain. Pain out of proportion to the injury and pain on passive stretch of the muscles in the compartment are the key early findings (BOA, 2025; RCN, 2022b). A steady rise in the amount of opioid a patient needs is itself a warning. UK standards require the dose and timing of analgesics, especially opioids, to be recorded, and call for a joint decision by the patient, anesthesiologist and surgeon, with an agreed monitoring plan, before a regional nerve block is used in an at-risk patient, because a block can hide the pain (BOA, 2025). Numbness, tingling, weakness, colour change and a weak or absent pulse are late signs that do not help with early diagnosis (RCN, 2022b), so a pulse that can be felt does not rule out compartment syndrome. Late signs can also point to other nerve or blood vessel injuries, and any change is reported at once (RCN, 2022b).

When compartment syndrome is suspected, every nurse acts at once:

- **Notify urgently.** The nurse reports the suspicion to the surgeon or most responsible clinician immediately (RCN, 2022b), using SBAR (Chapter 6). The RPN consults the RN at the same time. This is an emergency, not a concern for the next round.

- **Release pressure.** All circumferential dressings and bandages are loosened or released down to the skin (BOA, 2025; Donaldson et al., 2014). A cast may be split or bivalved (cut along both sides) by a trained clinician, as ordered or as policy allows.
- **Position the limb at heart level.** The limb is kept at the level of the heart, not raised above it, so that arterial blood flow into the compartment is not reduced further (Donaldson et al., 2014). Letting the limb hang down would add to the swelling.
- **Support perfusion.** The nurse helps keep blood pressure normal, gives oxygen to keep saturation at the target the team sets, and stays with the patient (Donaldson et al., 2014; RCN, 2022b).
- **Reassess and record.** The nurse repeats the neurovascular assessment often, records pain scores and all analgesia, and documents the times of each finding, call and action; UK standards expect the limb to be re-evaluated within 30 minutes (BOA, 2025).

If the findings are unclear, the team may measure the pressure inside the compartment (BOA, 2025). A **fasciotomy** is surgery to cut the fascia open along the length of the compartment so the muscle can swell without being crushed. UK standards call for immediate surgical decompression once compartment syndrome is diagnosed (BOA, 2025). The wounds are left open at first and closed or grafted later, so the patient needs wound care (Chapter 35) and support to cope with the scars.

Fat Embolism Syndrome

When a long bone such as the femur breaks, droplets of fat from the marrow can enter the bloodstream and lodge in small vessels of the lungs, brain and skin. **Fat embolism syndrome (FES)** is the illness that can follow. Fat in the blood is common after long-bone fractures, but the full syndrome is much less common. Reported rates vary widely with how studies looked for it (Timon et al., 2021). FES occurs mostly after fractures of the femur, tibial shaft and pelvis, after multiple fractures, and sometimes after hip replacement (Timon et al., 2021).

Signs usually appear 24 to 48 hours after the injury (Timon et al., 2021), and some reports describe onset up to 72 hours (Seixas & Ferreira, 2018; Sogunuru & Moka, 2010). That delay is why a patient who seemed stable on admission can become unwell on the second day. The classic picture combines three groups of findings:

- **Breathing problems**, the most common feature: rapid breathing, shortness of breath and low oxygen saturation, ranging from mild distress to respiratory failure needing a ventilator (Timon et al., 2021).
- **Neurologic changes:** restlessness, confusion, drowsiness and, rarely, seizures or coma (Timon et al., 2021).
- **A petechial rash:** tiny red-purple spots that do not blanch, usually on the head, neck, front of the chest and armpits (Sogunuru & Moka, 2010; Timon et al., 2021) and in the conjunctivae (Seixas & Ferreira, 2018; Sogunuru & Moka, 2010); one report also names the inside of the mouth and skin folds (Seixas & Ferreira, 2018). The rash is not seen in every patient (Sogunuru & Moka, 2010). On every skin tone, the nurse checks the conjunctivae and the inside of the mouth as well as the skin of the upper body.

Fever, a fast heart rate, and a falling hemoglobin and platelet count may also occur (Timon et al., 2021). Several sets of diagnostic criteria exist, but none has been validated or is accepted as a standard; FES is a clinical diagnosis made after other causes, such as pulmonary embolism (Chapter 15), are ruled out (Seixas & Ferreira, 2018; Timon et al., 2021).

There is no specific treatment. Care is supportive: oxygen, close monitoring of breathing and level of consciousness, and ventilation if needed (Timon et al., 2021). Early stabilization of long-bone fractures is thought to lower the risk (Timon et al., 2021). With supportive care, most patients recover fully (Timon et al., 2021). The nurse's role is to recognize the pattern early and escalate at once (Chapter 6).

Other Complications

Venous thromboembolism, a deep vein thrombosis or pulmonary embolism, is a major risk after lower-limb fractures and orthopedic surgery because of immobility, vessel injury and changes in clotting. The nurse watches for calf pain or swelling, sudden shortness of breath or chest pain, and reports them at once. Prevention and anticoagulants are covered in Chapters 7 and 19, and pulmonary embolism in Chapter 15.

Fracture-related infection is a frequent and serious problem after fracture surgery (Metsemakers et al., 2018). When it involves the bone itself, it is called **osteomyelitis**. Open fractures and implants raise the risk. An international expert consensus treats a sinus or

fistula, wound breakdown, or pus draining from the wound as confirming infection (Metsemakers et al., 2018). Earlier signs, such as new redness, warmth, swelling, rising pain or ongoing wound drainage, call for further assessment. Infection is covered in Chapter 4.

Delayed union means healing is slower than expected; nonunion means the fracture has stopped progressing toward healing. Between 5% and 10% of patients have a fracture that fails to heal (Zura et al., 2016). The nurse reports pain or movement at the fracture site that persists long after the expected healing time and supports teaching on the risk factors in section 33.1.

Complex regional pain syndrome, a long-lasting pain condition that can follow a limb injury, is described in Chapter 5.

Table 33.2 compares the serious complications described in this section.

Table 33.2 Serious complications after fractures compared (BOA, 2025; Metsemakers et al., 2018; RCN, 2022b; Seixas & Ferreira, 2018; Timon et al., 2021)

Complication	Usual timing	Early signs	First nursing actions
Compartment syndrome	After injury, surgery, casting or traction; checks are closest in the first 48 hours	Pain out of proportion to the injury; pain on passive stretch; rising analgesic need; a tight, swollen limb	Notify urgently; release bandages to the skin; limb at heart level; support blood pressure and oxygen; reassess and record
Fat embolism syndrome	Usually 24 to 48 hours after a long-bone or pelvic fracture; reported up to 72 hours	Rapid breathing and falling oxygen saturation; new restlessness or confusion; petechiae on the upper body, conjunctivae or mouth	Give oxygen as ordered or per protocol; call for urgent help; monitor breathing and level of consciousness closely
Venous thromboembolism	While mobility is reduced after injury or surgery	Calf pain or swelling; sudden shortness of breath or chest pain	Report at once; see Chapters 15 and 19
Fracture-related infection	Early or late after injury or surgery	New redness, warmth, swelling, rising pain or ongoing drainage; pus or a draining sinus confirms infection	Report and document; wound swab or culture as ordered; follow infection prevention (Chapter 4)
Delayed union or nonunion	Weeks to months after injury	Ongoing pain or movement at the fracture site beyond the expected healing time	Report; review risk factors; support follow-up imaging and appointments

CLINICAL JUDGMENT

Short of Breath on Day Two

Names and details are fictional; this is a composite story.

Malik Haddad, 30, was admitted after a motorcycle crash with a closed fracture of his right femur. He is in skin traction awaiting surgery later today. On day two at 0600, the nurse finds him restless and pulling at his gown.

Recognize cues: His respiratory rate is 28 breaths/min, heart rate 118 beats/min, temperature 38.4 °C and oxygen saturation 89% on room air, down from 97% last evening. He asks the same question twice. When the nurse checks his eyes, there are tiny red spots on the conjunctivae and a few across his upper chest.

Analyze cues: A long-bone fracture, timing of about 36 hours, low oxygen saturation, new confusion and petechiae fit fat embolism syndrome. Pulmonary embolism, pneumonia and opioid effects can also cause some of these findings.

Prioritize hypotheses: Falling oxygenation with a change in mental status is a threat to life. Fat embolism syndrome is the most likely cause; pulmonary embolism must also be ruled out.

Generate solutions: Give oxygen, raise the head of the bed, call for urgent review, monitor closely, and prepare for tests that rule out other causes.

Take action: The nurse applies oxygen as the protocol allows, raises the head of the bed, stays with him and calls the rapid response team, giving an SBAR report that names the petechiae and the confusion (Chapter 6). The nurse checks his traction and leg and records all findings.

Evaluate outcomes: With oxygen, his saturation rises to 94%. He is moved to a higher level of care for monitoring, and his surgery is postponed until his breathing settles.

33.3 Osteoporosis and Bone Health

Osteoporosis

Osteoporosis is a disease in which bones lose mass and strength, so they break more easily. Throughout life, bone is broken down and rebuilt. With age, and especially in women after menopause, breakdown can outpace rebuilding. The bones become thinner and more porous, often with no symptoms until a fracture happens. Common sites of fragility fractures are the forearm, hip, spine, upper arm and pelvis (Public Health Agency of Canada [PHAC], 2024).

In 2019–2020, almost 2.5 million people aged 40 and older in Canada were living with diagnosed osteoporosis, and about 81% of them were women (PHAC, 2024). The risk of a diagnosis doubled every five years between ages 40 and 65. In the same period there were 156 hip fractures per 100,000 people aged 40 and older, and more than one in five people who broke a hip died, from any cause, within the next year (PHAC, 2024). Because osteoporosis usually causes no symptoms, a fracture is often the first sign. Any low-trauma fracture in an adult aged 50 or older is a reason to ask about bone health (Morin et al., 2023). Yet many people are not treated after a fracture. Among people in Canada who had a fracture at a site most linked to osteoporosis, only 21% of those aged 65 and older received a prescription for an osteoporosis medicine, and only 15% of those aged 40 and older had a bone density test; men were less likely to receive any intervention (PHAC, 2024).

Bone mineral density (BMD) is the amount of mineral in a given area of bone, measured with a low-dose X-ray scan called dual-energy X-ray absorptiometry (DXA). A T-score of −2.5 or lower on a BMD test confirms osteoporosis (Morin et al., 2023). Osteoporosis can also be diagnosed clinically in people aged 50 or older who have had a low-trauma fracture of the hip, spine, upper arm or pelvis after age 40, or whose 10-year risk of a major osteoporotic fracture is 20% or higher (Morin et al., 2023).

The Osteoporosis Canada 2023 guideline targets testing by age and risk factors (Morin et al., 2023; Osteoporosis Canada, 2024). For postmenopausal women and for men, it suggests BMD testing for:

- adults aged 70 and older;
- adults aged 65 to 69 with one risk factor;
- adults aged 50 to 64 with a previous osteoporosis-related fracture or at least two risk factors.

Risk factors include a fragility fracture after age 40, glucocorticoid use for more than three months in the past year, two or more falls in the past year, a parent who broke a hip, low body weight, conditions that cause bone loss, current smoking and drinking three or more alcoholic drinks a day (Osteoporosis Canada, 2024). The nurse can screen for clues during assessment, such as height loss or a stooped posture, which can signal spinal fractures. The guideline prefers the Canadian version of the Fracture Risk Assessment Tool (FRAX), which estimates the 10-year chance of a major fracture; the Canadian Association of Radiologists and Osteoporosis Canada (CAROC) tool is also validated (Morin et al., 2023). The guideline recommends medicine for postmenopausal women and men aged 50 and older who have had a hip or spine fracture or two or more osteoporosis-related fractures, who have a 10-year major fracture risk of 20% or more, or who are 70 or older with a T-score of −2.5 or lower; it suggests medicine at some lower levels of risk as well (Morin et al., 2023; Figure 33.6).

Prevention and Treatment

Exercise is central. The guideline found high-certainty evidence that balance and functional training reduces falls. It recommends this training, and suggests progressive resistance training, at least twice a week (Morin et al., 2023). Preventing falls is part of preventing fractures; Chapter 8 covers falls prevention in hospital and at home.

Osteoporosis Canada suggests meeting calcium needs with calcium-rich foods, and taking a daily vitamin D supplement along with vitamin D-rich foods (Osteoporosis Canada, 2024). For people who eat a balanced diet and do not take an osteoporosis medicine, calcium and vitamin D supplements likely have little or no effect on fractures (Morin et al., 2023). Some osteoporosis medicines, however, require enough calcium and vitamin D; for example, people taking denosumab must have adequate supplementation (Amgen Canada, 2026).

Medicines reduce fracture risk in people at high risk. **Antiresorptive** medicines slow bone breakdown; **anabolic** medicines build new bone (Morin et al., 2023). The Medications box lists those named in the guideline and the teaching each needs.

Adults aged 50 and older who break a bone from low trauma need assessment for osteoporosis (Morin et al., 2023). A **fracture liaison service** is a coordinated program that identifies people with a recent fragility fracture and makes sure they are assessed and treated to prevent the next fracture. The Osteoporosis Canada guideline recommends that postmenopausal women and men aged 50 and older with a recent fracture have access to one (Morin et al., 2023). Section 33.4 applies this to hip fracture.

Figure 33.6 Lateral spine X-ray showing osteoporotic wedge compression fractures of the L1 and L2 vertebrae, which can cause height loss and a stooped posture.

MEDICATIONS

Medicines for Osteoporosis

Doses are not given here; follow the current product monograph and prescriber's order (Morin et al., 2023).

- **Oral bisphosphonates (alendronate, risedronate):** Teach the patient to take alendronate first thing in the morning with a full glass of plain water only, swallow it whole, stay upright for at least 30 minutes, and let 30 minutes or more pass before eating, drinking anything else or taking other medicines, including calcium (Sandoz Canada, 2022). Report pain or trouble swallowing, chest pain or new heartburn. The prescriber reviews therapy after several years, because the rare risks of long-term use rise over time (Morin et al., 2023).
- **Zoledronic acid:** a bisphosphonate given by IV infusion.
- **Denosumab:** an injection. Teach the patient not to stop or delay it without a plan from the prescriber, because stopping is linked to rapid bone loss and spinal fractures (Amgen Canada, 2026; Morin et al., 2023). Report tingling or muscle spasms, which can signal low calcium, and signs of skin infection.
- **Teriparatide and romosozumab:** anabolic injections. For people who meet treatment criteria and have had a recent severe spinal fracture, or more than one spinal fracture with a T-score of −2.5 or lower, the guideline suggests seeking advice from an osteoporosis specialist about these medicines (Morin et al., 2023).
- **For bisphosphonates and denosumab:** Keep up good oral hygiene, have a dental check-up if advised before starting, and tell the dentist and prescriber about the medicine before any dental surgery; report jaw pain, loose teeth or a sore that will not heal in the mouth, and new thigh, hip or groin pain (Amgen Canada, 2026; Sandoz Canada, 2022).

33.4 Hip Fracture in Older Adults

A hip fracture is often the event that changes an older adult's life most. A fall that a younger person would walk away from can break the hip of a person with fragile bones, and recovery depends on fast, coordinated care from the first hour. This section follows the

older adult from the emergency department (ED) to home, using the Ontario Health quality standard as the guide (Ontario Health, 2024).

Why Hip Fractures Matter

A **hip fracture** is a break in the upper part of the femur, near the hip joint. In older adults, most hip fractures are fragility fractures (section 33.1): they follow a low-energy fall, such as a fall from standing height, in a person whose bones are weakened by osteoporosis (section 33.3). Falls and frailty, the main reasons older adults fall, are taught in Chapter 8.

Ontario Health's quality standard, *Hip Fracture: Care for People With Fragility Fractures* (2024 update), describes the burden in Ontario. About 12,000 people in the province have a hip fracture each year. Within a year, about 20% have died, and about 20% of people who lived on their own before the fracture have moved to long-term care. Of those who lived independently before, fewer than half can later walk without an aid. Hip fractures cost the Ontario health system nearly $500 million each year (Ontario Health, 2024). For the person, the larger cost is often the loss of independence, a home or a familiar routine.

The type of fracture guides the surgery. A **femoral neck fracture** breaks the narrow neck of the femur just below the ball (femoral head), inside the joint capsule, so it is called an intracapsular fracture. An **intertrochanteric fracture** breaks the femur lower down, between the two bony bumps (trochanters) where hip muscles attach, outside the capsule. The quality standard calls for arthroplasty for most displaced intracapsular fractures; one choice is **hemiarthroplasty**, which replaces only the femoral head and neck with a prosthesis. Stable intertrochanteric fractures are fixed with a sliding hip screw or a nail inside the bone, and unstable intertrochanteric fractures and fractures just below the trochanters (subtrochanteric fractures) are fixed with a nail (Ontario Health, 2024; Figure 33.7).

Figure 33.7 (a) Hip X-ray showing a mildly compressed femoral neck fracture (white arrows) in an older adult after an indoor fall; (b) postoperative X-ray after internal fixation with two parallel pins.

Before Surgery

The quality standard expects the diagnosis within 1 hour of arrival at hospital, transfer to an inpatient unit within 8 hours of arrival, and a pain assessment within 30 minutes of arrival (Ontario Health, 2024). The nurse assesses the injured leg, which is often shortened and turned outward, and checks circulation, movement and sensation below the injury (Table 33.1, section 33.1). The nurse also gathers the person's baseline: usual thinking and memory, mobility, living situation, medications and who makes decisions if the person cannot (Chapter 1). Family members and long-term care staff are often the best source of this baseline, and it is needed later to tell whether confusion is new. The team also asks why the person fell. A fall may follow a faint, a new illness, a medication change or a hazard at home, and the cause shapes the plan to prevent the next fall (Chapter 8). While the person waits on a stretcher or in bed, the nurse protects the heels and sacrum from pressure (Chapter 35).

Pain. Untreated pain adds to distress and is a known contributor to delirium (Chapter 8). The standard calls for multimodal analgesia that includes nonopioid medicines and consideration of a peripheral nerve block, such as a fascia iliaca or femoral nerve block, which numbs the hip region with local anesthetic (Ontario Health, 2024). Pain assessment in people who cannot report pain clearly is taught in Chapter 5.

Timely surgery. The standard states that surgery should take place as early as possible and no later than 48 hours after the person first arrives at any hospital; time spent at a hospital that does not do the surgery counts (Ontario Health, 2024). The nurse helps by preparing the person promptly: fasting as ordered, blood work, consent (Chapter 7) and a review of anticoagulants, which may need planning or reversal (Chapter 19).

Delirium prevention. The standard calls for screening for delirium at the first assessment, using a standardized, validated tool, and then at least every 12 hours while in hospital, whenever the person moves to a new setting and whenever their medical condition changes (Ontario Health, 2024). Prevention starts in the ED: glasses and hearing aids, a calm space, family presence, fluids and good pain control (Chapter 8).

After Surgery

Mobilization. The standard expects the person to reach weight bearing as tolerated in the first 24 hours after surgery and then to be mobilized every day, moving step by step from sitting on the edge of the bed to assisted walking (Ontario Health, 2024). Early movement protects the lungs, skin and muscles and helps prevent delirium and loss of function. Before each move, the nurse checks vital signs, oxygen saturation, pain and alertness, and stops if the person becomes faint, short of breath or newly drowsy (Chapter 6).

Delirium and pain. Screening continues at least every 12 hours (Ontario Health, 2024). A new or worse confusion is a cue to look for causes, such as low oxygen, pain, urinary retention, infection, dehydration, low hemoglobin and medications, and to report it (Chapter 8). Pain is reassessed with movement, not only at rest, because pain that blocks walking delays recovery (Chapter 5).

Bleeding and anemia. Hip fracture and its surgery cause blood loss, and hemoglobin often falls in the days after surgery. The standard states that a person who has no symptoms of anemia and a postoperative hemoglobin of at least 80 g/L should not receive a transfusion (Ontario Health, 2024). The nurse watches for symptoms such as dizziness, a fast heart rate, low blood pressure, shortness of breath and new confusion, and reports them (Chapter 20).

Geriatric care. The standard asks for interprofessional care that follows geriatric principles, including nutrition, hydration, careful use of urinary catheters, pressure injury risk assessment, medication review, VTE prevention and assessment of fall risk (Ontario Health, 2024). The nurse removes catheters as soon as allowed, watches for urinary retention and constipation, and encourages food and fluids. Many older adults arrive undernourished or eat little after surgery, so the nurse tracks intake, offers help with meals and refers to the dietitian when intake stays low. The standard also asks that the person and family receive information tailored to them, spoken and in writing or another format, at the right times (Ontario Health, 2024). VTE prophylaxis is described in section 33.5 and Chapter 19; pressure injury prevention is taught in Chapter 35.

Secondary fracture prevention. One fragility fracture signals a high risk of another. **Secondary fracture prevention** is care that aims to prevent the next fracture by finding and treating osteoporosis and reducing falls. The standard calls for a clinician with expertise in osteoporosis to assess fracture risk during the hospital stay, for osteoporosis medicine to be offered when appropriate, and for access to a fracture liaison service (section 33.3) to coordinate this care (Ontario Health, 2024).

Rehabilitation and home. The standard calls for an interprofessional rehabilitation program, in hospital, in the community or both, that aims to return the person to their function before the fracture. It also calls for information that is tailored to the person and family, a scheduled primary care visit no more than 2 weeks after discharge and an orthopedic follow-up no more than 12 weeks after surgery (Ontario Health, 2024) (Table 33.3).

Equity. Because the 48-hour clock starts at the first hospital, people in rural, remote and northern communities who must be transferred lose time before they reach a surgeon. Residents of long-term care homes are often frail and may live with dementia, so the nurse obtains their baseline from the home and shares a clear plan at transfer. First Nations, Inuit and Métis older adults may be flown far from family and community for surgery; culturally safe care involves family, interpreters where needed and early links with community health services for the return home (Chapter 2).

Table 33.3 Care of the older adult with a hip fracture, from arrival to home (Ontario Health, 2024; original wording)

Phase	Nursing priorities	Team members	What to watch for
Arrival in the emergency department	Assess pain within 30 minutes; check circulation, movement and sensation of the leg; learn the person's baseline thinking and function; screen for delirium	ED physician, nurses, anesthesia (nerve block), family	Uncontrolled pain, delirium, dehydration, anticoagulant use
Waiting for surgery	Prepare for surgery quickly; keep pain controlled; keep glasses, hearing aids and family close; give fluids as ordered	Orthopedic surgeon, anesthesia, nurses, pharmacist	Delays beyond 48 hours from first hospital arrival; skin breakdown; confusion
Days 0 to 2 after surgery	Bear weight as tolerated within 24 hours; mobilize at least daily; screen for delirium every 12 hours; manage pain with movement; remove the catheter early	Nurses, physiotherapist, occupational therapist, physician, dietitian	Low oxygen saturation, falling hemoglobin with symptoms, urinary retention, VTE signs, pressure injury
Recovery on the unit	Support nutrition and bowel function; review medications; start secondary fracture prevention; teach the person and family	Interprofessional team, osteoporosis clinician or fracture liaison service, pharmacist	Ongoing delirium, poor intake, falls, low mood
Transition to rehabilitation or home	Share a clear plan; arrange rehabilitation; book primary care within 2 weeks and orthopedic follow-up within 12 weeks	Rehabilitation team, home and community care, primary care, family	Loss of function, a second fall, missed osteoporosis treatment

CANADIAN CONTEXT

Hip Fracture Surgery in Canada

Canada has tracked how fast people with a hip fracture reach surgery for two decades. In December 2005, the federal, provincial and territorial governments agreed on a benchmark of hip fracture repair within 48 hours (Canadian Institute for Health Information [CIHI], n.d.-a). CIHI now reports two related indicators. One measures the risk-adjusted share of adults (18 and older) whose hip fracture surgery happens within 48 hours of their first admission to an acute care hospital; when a person is transferred, the whole wait is counted against the hospital that does the surgery (CIHI, n.d.-a). The other counts the hours from first registration in an ED to surgery (CIHI, n.d.-b).

CIHI explains that timely surgery leads to better outcomes and reduces the chance of lasting pain, complications and death (CIHI, n.d.-a). In its 2025 report on wait times for priority procedures, CIHI reported that 83% of patients had hip fracture repair within 48 hours in 2024, 3 percentage points lower than in 2019 (CIHI, 2025). In Ontario, about a quarter of patients waited longer than 48 hours in 2022/23, and the share varied from 3% to 69% across hospitals (Ontario Health, 2024). Nurses help close these gaps by preparing patients quickly and by escalating delays.

PRACTICE STORY

Up on Day One

Names and details are fictional; this is a composite story.

Nurse: Samira Darwish, RPN. Years in practice: 6. Setting: orthopedic unit, Ontario.

Mr. Doucette was 84, a retired mail carrier who told me twice before breakfast that he had walked every street in town. He'd had his hip fixed with a nail the afternoon before, after a fall in his kitchen. The order said weight bearing as tolerated, and the physiotherapist was booked for the afternoon. My plan was to get him sitting at the edge of the bed, then standing with the walker, before lunch.

At 0900 he was chatty and sharp. His oxygen saturation was 95% on room air, and his pain was 4 out of 10 after his morning medicines. At 1100, when I came back with the walker, he was harder to wake. He answered my questions, but his eyes kept closing and he couldn't tell me where he was. I sat him up slowly and dangled his legs. His saturation read 88%, and his breathing was quicker than before.

I didn't stand him. I lowered him back with the head of the bed up, stayed with him, and pressed the call bell for the RN on my team, Grace. While I waited, I rechecked the saturation on a warm finger and took a full set of vital signs. His heart rate had gone from 78 to 102. I checked his medication record: he'd had an opioid dose at 0930.

> When Grace came, I gave her what I had in order: what I'd found at 0900, what had changed, the numbers and the opioid time. She assessed him, started oxygen per our protocol and called the surgical resident. Later that day they were looking into a possible pulmonary embolism.
>
> The next morning, Mr. Doucette asked when he could go for his walk. I told him soon, and that we'd do it together.
>
> Reflect: Samira's plan was to mobilize Mr. Doucette, but she stopped when he changed. How did his new drowsiness, falling saturation and faster heart rate change the context of his care, and why did that call for consulting the RN?

33.5 Joint Replacement and Spine Surgery

Joint replacement is one of the most common operations in Canada, and spine surgery relieves pain and nerve pressure for many adults. Both rely on good preparation, early movement and clear teaching for home.

Hip and Knee Replacement

In a **total hip arthroplasty** (THA), the surgeon replaces the ball of the femur and lines the hip socket with artificial parts. In a **total knee arthroplasty** (TKA), the worn surfaces of the femur and tibia, and often the kneecap, are resurfaced. Most people have these operations for osteoarthritis that limits walking and sleep despite other treatment (Chapter 34). A hip fracture may also be treated with a hemiarthroplasty or a THA (section 33.4) (Figure 33.8).

The Canadian Joint Replacement Registry (CJRR), run by CIHI, reported 175,242 hip and knee replacements in 2024–2025, 5.3% more than the year before and 26.5% more than in 2019–2020. Day surgery is growing fast: it accounted for 35.8% of hip and 31.1% of knee replacements for osteoarthritis, increases of 3.5-fold and 4.5-fold, respectively, since 2020–2021. In Ontario, Manitoba and Alberta, the provinces with these data, 9 in 10 patients reported 1 year after surgery that their outcomes had improved and that they were satisfied (CIHI, 2026).

Figure 33.8 Anteroposterior pelvic X-ray showing a right total hip arthroplasty, with a metal stem in the femur and a prosthetic ball seated in the replaced hip socket.

Before surgery. The Enhanced Recovery After Surgery (ERAS) Society recommends routine preoperative education, which reduces anxiety, and recommends finding and correcting anemia before surgery (Wainwright et al., 2020). The nurse teaches what to expect, how pain will be managed (Chapter 5), how to use a walker or crutches, and how to prepare the home. Preparation also lowers infection risk: anemia, malnutrition, obesity and tobacco use are risk factors for joint infection that can be changed before surgery, and diabetes with poor glucose control raises the risk as well (Patel, 2023). The nurse supports stopping smoking and good glucose control (Chapter 22). **Prehabilitation** means exercise and conditioning before surgery to improve recovery afterward. The ERAS Society states that the evidence does not show physiotherapy before surgery to be an essential part of care, so programs vary by surgeon and region (Wainwright et al., 2020).

After surgery. ERAS recommends mobilizing patients as soon as they are able, an opioid-sparing multimodal approach to pain, no routine wound drains and no routine urinary catheters; when a catheter is used, it comes out once the person can void, ideally within 24 hours (Wainwright et al., 2020). Objective discharge criteria, such as getting dressed, transferring to the bed and toilet, and walking a set distance with a walker or crutches, help people go directly home (Wainwright et al., 2020). In same-day pathways, the person meets these criteria before leaving the hospital on the day of surgery. Before discharge, the nurse confirms that the person has voided, that pain is controlled with oral medicines, that they can move safely with their aid, that an adult will be with them at home, and that they know whom to call.

Hip precautions. Hip precautions are limits on bending, crossing the legs and turning the leg inward, traditionally taught after THA done through a posterior (back) approach to prevent dislocation. A 2023 systematic review and meta-analysis found that precautions after posterior-approach THA may make little or no difference to dislocation in the first 3 months (low- to very-low-certainty evidence), and concluded that current evidence does not support prescribing them routinely (Korfitsen et al., 2023). Practice therefore varies: the nurse teaches the precautions that the surgeon's protocol orders, no more and no less, and makes sure the person and family know them.

VTE prophylaxis. For THA and TKA, an international guideline from the American Society of Hematology (ASH) suggests either acetylsalicylic acid (ASA) or an anticoagulant; when an anticoagulant is used, it suggests a direct oral anticoagulant (DOAC), such as apixaban or rivaroxaban, over a low-molecular-weight heparin (LMWH), such as enoxaparin or dalteparin. After hip fracture surgery, it suggests drug prophylaxis with an LMWH or unfractionated heparin (Anderson et al., 2019). When drug prophylaxis is not used, it suggests mechanical prophylaxis, preferring intermittent pneumatic compression over stockings (Anderson et al., 2019). The nurse gives the ordered regimen, teaches how long to continue it at home, and teaches the signs of deep vein thrombosis and pulmonary embolism (Chapters 15 and 19).

Complications. A **hip dislocation** occurs when the ball of the prosthesis comes out of the socket. It usually follows a low-energy event, such as a movement that takes the hip beyond its safe range, and causes sudden pain; after a posterior dislocation, the leg is typically shortened and turned inward (Dawson-Amoah et al., 2018). The person usually cannot move or bear weight on the leg. The nurse keeps the person still, checks circulation and sensation in the foot (section 33.1) and notifies the surgeon at once. A **periprosthetic joint infection** is an infection of the artificial joint and the tissue around it. Pain in the joint is the symptom seen most often, and fever is often absent; redness, swelling and warmth may be present, and a draining tract from the joint to the skin is a sure sign (Patel, 2023). The risk is highest soon after surgery but lasts for the life of the joint. A Canadian population-based study cited in one review found that about 0.5% of people who had a hip replacement developed a joint infection within 1 year (Patel, 2023). Wound care is taught in Chapter 35, and infection basics in Chapter 4. After TKA, regaining the ability to bend and fully straighten the knee is a main goal of recovery, so the nurse gives analgesia before exercise sessions and supports the exercises the physiotherapist teaches.

Spine Surgery in Brief

Spine surgery relieves pressure on the spinal cord or nerve roots, or stabilizes the spine. A **laminectomy** removes part of the lamina, the bony arch at the back of a vertebra, to make more room for nerves. A **discectomy** removes the part of a herniated disc that presses on a nerve root. A **spinal fusion** joins two or more vertebrae with a bone graft, often held with screws and rods, so that they heal as one bone. These operations are most often done for a herniated disc or a narrowed spinal canal that causes leg pain, numbness or weakness despite other treatment, or for an unstable spine. Spinal cord injury is taught in Chapter 32.

Neurologic and limb checks. Before surgery, the nurse records a baseline of leg (or arm, for neck surgery) strength, sensation and bladder and bowel function. After surgery, the nurse compares each check with the baseline and with the other side. New or worsening weakness or numbness, reduced feeling in the saddle area (the buttocks, perineum and inner thighs) or new bladder or bowel problems are reported at once. These can signal pressure on the nerves from blood collecting in the spinal canal (spinal epidural hematoma), a rare but serious complication that needs early detection and prompt surgery (Liu et al., 2025). A tear in the dura, the membrane around the spinal cord and nerve roots, can leak cerebrospinal fluid and cause head or neck pain that changes with posture (Floman et al., 2015). The nurse reports a new or worsening headache, unusual drainage on the dressing or any drop in alertness.

Ongoing care. The ERAS Society recommends preoperative education, early mobilization and physiotherapy, multimodal analgesia, risk-based prevention of nausea and vomiting, early return to a normal diet, and mechanical VTE prophylaxis with early walking for all patients, with drug prophylaxis reserved for higher-risk groups (Debono et al., 2021). The nurse turns the person by log rolling, keeping the shoulders and hips moving together, when ordered. Urinary catheters are not used routinely after short fusions and, when used, are removed within hours; the nurse then checks that the person empties the bladder, using a bladder scan as ordered, because urinary retention can occur (Debono et al., 2021). Teaching covers bending, lifting and driving limits as the surgeon orders, walking every day and signs to report.

PATIENT EDUCATION

Going Home After a Hip or Knee Replacement

- **Keep moving:** walk several times a day with your walker or crutches, and do the exercises your physiotherapist taught you. Short, frequent walks help more than one long one.
- **Follow your own instructions:** do the hip movements and limits your surgeon gave you. Rules differ between surgeons, so ask before following advice from friends or the internet.
- **Prevent falls:** clear floors of rugs and cords, use a night light, wear shoes that hold your heel, and use a raised toilet seat or grab bars if they were recommended.
- **Take your blood clot medicine** for as long as you were told, even if you feel well.
- **Manage pain:** take pain medicines as directed, especially before exercises, and use ice as taught.
- **Look after your incision:** keep it clean and dry, and don't soak it in a bath, pool or hot tub until your surgeon says so.
- **Call your surgeon's office** for redness, warmth, swelling or drainage from the incision; a fever; or pain that keeps getting worse.
- **Go to the nearest ED or call 9-1-1** for sudden severe hip pain with a leg that looks shorter or turned, chest pain or sudden shortness of breath. New calf pain or swelling needs care the same day.

GOING DEEPER

Blood Loss and Anemia After Joint and Hip Fracture Surgery

Required for RN students; optional for PN students.

Blood is lost during joint replacement and hip fracture surgery, and more can be lost into the tissues afterward, so hemoglobin may keep falling in the first days after surgery.

Before surgery. The ERAS Society recommends identifying, investigating and correcting anemia before planned hip and knee replacement (Wainwright et al., 2020).

During surgery. The ERAS Society gives a strong recommendation, based on high-quality evidence, for tranexamic acid to reduce blood loss and the need for transfusion in hip and knee replacement (Wainwright et al., 2020). Tranexamic acid slows the breakdown of clots.

Transfusion decisions. The Ontario standard for hip fracture states that a person without symptoms whose postoperative hemoglobin is 80 g/L or more should not be transfused (Ontario Health, 2024). The 2023 AABB international guideline recommends considering transfusion for most hospitalized adults who are hemodynamically stable when hemoglobin is below 70 g/L; clinicians may choose 80 g/L for people having orthopedic surgery or with existing cardiovascular disease (Carson et al., 2023). The Canadian Society for Transfusion Medicine's Choosing Wisely list sets no number; it bases decisions on symptoms and hemoglobin and advises transfusing a single unit of red cells at a time for stable patients who are not bleeding (Canadian Society for Transfusion Medicine [CSTM], 2025). A number alone does not decide: chest pain, a rising heart rate, low blood pressure, shortness of breath or new confusion with a falling hemoglobin is reported at once. Transfusion safety is taught in Chapter 20.

33.6 Amputation

An **amputation** is the removal of all or part of a limb. Most amputations in Canada are of the lower limb, and many follow years of vascular disease. Caring well for a person after amputation means caring for the residual limb, preventing complications and supporting grief, body image and rehabilitation.

Why Amputations Happen

Peripheral arterial disease (PAD) narrows the arteries to the legs (Chapter 19), and diabetes damages nerves and blood vessels so that foot wounds heal poorly (Chapter 22). Together they cause most lower-limb amputations. In an Ontario study of adults 40 and older who had an amputation related to diabetes or PAD from 2005 to 2016, about 82% of the 20,062 patients had diabetes, about 94% had PAD and about 76% had both; about 64% had a major amputation above the ankle. After falling from 2005 to 2010, the rate of amputation rose again, reaching 10.0 per 100,000 adults aged 40 or older by early 2016 (Hussain et al., 2019). Trauma, severe infection and cancer are other causes.

The burden is not shared equally. Among Ontarians with diabetes, First Nations people had lower-limb amputations 3 to 5 times as often as other Ontarians with diabetes from 1995/96 to 2014/15, and more than 6 times as often among those 44 and younger, while rates of surgery to restore blood flow were similar (Shah et al., 2019). Risk was highest in remote communities. The authors point to underdiagnosed or undertreated PAD, poor access to specialized wound care and rehabilitation, and the social, economic and cultural conditions that shape health (Shah et al., 2019). These are structural causes rooted in colonial policies, distance and underfunded services, not in the people themselves (Chapter 2). The study was a research partnership with the Chiefs of Ontario, whose Data Governance Committee approved it; this book respects First Nations data governance under the OCAP® principles (Chapter 2). Where the person wishes, the nurse works with their community's own health services during care and in planning the return home.

Care After Amputation

The residual limb. The **residual limb** is the part of the limb that remains after amputation. The nurse checks the dressing for bleeding and drainage, assesses pain, and watches the incision for signs of infection. Swelling must be controlled so that the limb takes a stable shape for a prosthesis. A Canadian rapid review by CADTH (now Canada's Drug Agency) found that removable rigid dressings after below-knee amputation may reduce limb volume faster in the first month than soft dressings, with similar complications, but the evidence was of low certainty (Vu & Butcher, 2022). The team chooses the dressing, elastic wrap or shrinker sock, and the nurse applies it as ordered and checks the skin under it. Before discharge, the nurse teaches the person to inspect the residual limb every day, using a mirror if needed. For a person with diabetes or PAD, the remaining foot is at high risk too, so daily foot checks and proper footwear are taught (Chapter 22).

Preventing contracture. A **contracture** is a fixed shortening of muscles and joint tissues that stops a joint from straightening. After an above-knee amputation, the hip tends to stay bent; after a below-knee amputation, the knee does. A contracture can make fitting a prosthesis difficult or impossible. The nurse avoids propping the residual limb on pillows or letting it hang over the edge of the bed, encourages lying prone for periods each day as ordered and tolerated, keeps the knee as straight as possible after a below-knee amputation, and supports the exercises the physiotherapist teaches (National Rehabilitation Hospital, n.d.). In one trial in that review, a person treated with an elastic bandage developed a knee flexion contracture (Vu & Butcher, 2022).

Phantom limb sensation and pain. Many people feel that the removed limb is still there, which is called phantom limb sensation. **Phantom limb pain** is pain felt in the part of the limb that has been removed. It is real pain. A 2020 meta-analysis found a pooled prevalence of 64%, and identified ongoing pain before surgery, a higher amputation level, pain in the residual limb, lower-limb amputation and phantom sensations as risk factors (Limakatso et al., 2020). The nurse asks about phantom pain directly, describes it as common and real, and treats it with the team (Chapter 5).

Grief, body image and function. Losing a limb is a loss of function, identity and often work and independence. The nurse makes room for grief and anger, notices signs of depression and refers as needed, and involves family in care when the person wishes. Some people find meeting someone who lives with an amputation helpful, and the team can suggest peer support where it exists.

Rehabilitation and the prosthesis. A **prosthesis** is an artificial device that replaces a missing body part. Rehabilitation teams teach transfers, wheelchair use, strengthening and, when the limb is ready, walking with a prosthesis. Funding varies by province and insurance. The War Amps Adult Amputee Program provides financial help toward the cost of artificial limbs for adults living in Canada after provincial or private coverage is used, along with information on living with an amputation, including phantom limb pain (The War Amps, n.d.; Figure 33.9).

Figure 33.9 A transtibial (below-knee) prosthesis in use during outdoor walking, cropped to the lower limbs. (credit: modification of "Transtibial amputee with Lunaris foot prosthesis" by Axiles Bionics/Wikimedia Commons, CC BY-SA 2.0)

33.7 Mobility and Safe Patient Handling

Moving a patient safely protects both the patient and the nurse. Bed rest weakens muscles and leads quickly to loss of function in older adults, so mobility is part of treatment, not an extra (Chapter 8). **Functional decline** is a loss of the ability to carry out daily activities, such as walking, dressing and toileting, that a person could do before an illness or hospital stay. On an orthopedic unit, the person's weight-bearing order (non-weight-bearing, partial weight-bearing or weight-bearing as tolerated) and any movement limits shape every move. At the same time, manual lifting injures health care workers.

Injury Risk for Nurses

Musculoskeletal disorders are common among Ontario health care workers. Using 2021 Workplace Safety and Insurance Board (WSIB) data, the Centre of Research Expertise for the Prevention of Musculoskeletal Disorders (CRE-MSD) reports that the lost-time injury rate for these disorders in health care was about twice the provincial average. Back injuries made up 48% of lost-time claims, and 48% of musculoskeletal injuries in health care were linked to lifting, transferring or repositioning clients (CRE-MSD, 2025). The highest rates were in residential care facilities for older adults, home care services and hospitals.

Safe patient handling is an organized approach that uses assessment, equipment, policy and training to move patients without manual lifting where possible. CRE-MSD notes that effective programs involve more than equipment, and that patients have fewer falls, skin tears and pressure injuries when they are in place (CRE-MSD, 2025). Good body mechanics alone do not make manual lifting of an adult safe.

Assessing Before Every Move

Before each move, the nurse assesses what the person can do today: alertness and ability to follow directions, ability to bear weight, sitting balance and trunk control, pain, lines and drains, and any weight-bearing or movement orders. The Public Services Health & Safety Association (PSHSA) client mobility plan records the method and equipment for each type of move (repositioning, transfers that use the person's own weight bearing, lifts for people who cannot bear weight, and lateral transfers) so that every staff member moves the person the same way (PSHSA, 2025). Abilities change after surgery, with delirium or with a new illness, so the nurse

reassesses and updates the plan. The nurse also explains each move before starting, asks the person to help as much as they can, and respects their preferences and dignity. The plan is shared at handover and kept where every staff member can see it.

Choosing Equipment

A **mechanical lift** is a device that raises and moves a person in a sling, from the floor or a ceiling track, so that staff do not bear the person's weight. Sit-to-stand devices help people who can bear some weight, and slider sheets reduce friction when repositioning a person in bed or moving them to a stretcher (PSHSA, 2025). CRE-MSD cautions that equipment that gives more support than needed can take away chances for the person to work their own muscles, and that clinical judgment and assessment remain the main guide to choosing a method (CRE-MSD, 2024). The aim is the least support that is safe (Table 33.4). Before each use, the nurse checks that the lift is charged and working, that the sling is the right type and size for the person, and that enough trained staff are present. People with a larger body size need equipment rated for their weight; the PSHSA plan lists bariatric portable and ceiling lifts (PSHSA, 2025).

Walking aids, such as canes, walkers and crutches, are chosen and fitted by the physiotherapist. The nurse checks that the aid is the right height and in good repair, that the person uses it as taught, and that the path is clear. Employer policy sets the training, the number of staff for each lift and when equipment must be used. Employer policy also sets the response when a person starts to fall or is found on the floor: the nurse calls for help, assesses for injury before the person is moved, and uses the equipment that policy requires to get them up (Chapter 8).

Table 33.4 Matching the move to the person: mobility and handling equipment (PSHSA, 2025; CRE-MSD, 2024; original wording)

What the person can do	Safe approach	Equipment	Nursing points
Moves independently and safely	Supervise or stand by; encourage independence	Walking aid if prescribed	Check footwear, path and the aid; reassess after any change
Bears weight and follows directions, needs a little help	Assist with one staff member as the plan states	Transfer belt, walking aid	Stand at the person's side; stop if dizzy or short of breath
Bears some weight, has fair sitting balance	Sit-to-stand transfer	Sit-to-stand device, correct sling size	Confirm weight-bearing orders; watch for fatigue
Cannot bear weight, or is unable to follow directions	Full mechanical lift with the number of staff policy requires	Ceiling or portable lift, correct sling	Check the sling and lift before use; never lift manually
Needs repositioning in bed or a move to a stretcher	Slide rather than lift	Slider sheet, lateral transfer device	Use enough staff; protect skin, lines and the surgical site

SCOPE IN PRACTICE

Orthopedic Care and Who Does What

The College of Nurses of Ontario (CNO) Scope of Practice standard asks each nurse to consider authority, competence and context before taking on an activity (Chapter 1, section 1.3). On an orthopedic unit, RNs and RPNs share much of the work, and employer policy and the province or territory shape the details.

- **Every nurse:** performs neurovascular checks, recognizes signs of compartment syndrome, fat embolism, bleeding, VTE or delirium, acts at once and escalates (sections 33.1 and 33.2; Chapter 6). An RPN consults the RN as the patient's needs change, and every nurse who sees deterioration acts immediately.
- **Traction, external fixators and casts:** caring for a patient in traction, pin-site care, bivalving a cast or applying a splint depend on an order where needed, employer policy and the nurse's competence. A nurse who has not been taught a skill seeks education and supervision first.
- **Mobilization:** nurses mobilize patients as the plan and orders allow and work with physiotherapists on progression. Using a mechanical lift requires training on that device.
- **Context:** a patient whose condition is changing quickly, such as one who is newly hypoxic or confused, may need the RN to take a larger role. Assigning by stability is a common employer practice, not a CNO rule.

Chapter 33 Summary

33.1 Fractures and Their Care

- Fractures are described as closed or open, complete or incomplete, displaced, comminuted, pathologic or fragility fractures; the terms guide care.
- Bone heals through overlapping phases of inflammation, new blood vessel growth, callus formation and remodelling. Severe injury, smoking, diabetes and some medicines raise the odds of nonunion.
- Open fractures need IV antibiotics as soon as possible, ideally within one hour, minimal wound handling, photographs and a saline-soaked dressing until surgery.
- Cast, traction and external fixator care protect the skin and alignment. Pin-site care follows local protocol, because no single method has been shown to be best.
- Neurovascular assessment compares the injured limb with the other limb. Pain out of proportion and pain on passive stretch are the earliest warning signs, and colour alone is not a reliable guide on every skin tone.

33.2 Complications After Musculoskeletal Injury

- Compartment syndrome is a surgical emergency. Pain is the early sign; numbness, weakness, colour change and absent pulses are late.
- When compartment syndrome is suspected, the nurse notifies urgently, releases bandages to the skin, keeps the limb at heart level and reassesses.
- Fat embolism syndrome usually appears 24 to 48 hours after a long-bone or pelvic fracture, with low oxygen, confusion and petechiae; care is supportive and escalation is urgent.
- Other complications include venous thromboembolism, fracture-related infection and osteomyelitis, and delayed union or nonunion.

33.3 Osteoporosis and Bone Health

- Almost 2.5 million people aged 40 and older in Canada were living with diagnosed osteoporosis in 2019–2020, and most people with a fracture linked to osteoporosis are not tested or treated.
- The Osteoporosis Canada 2023 guideline targets BMD testing by age and risk factors and prefers the Canadian FRAX tool to estimate 10-year fracture risk.
- Balance, functional and resistance exercise and falls prevention are central. Medicines include bisphosphonates, denosumab, teriparatide and romosozumab.
- Nurses teach how to take oral bisphosphonates safely, not to stop denosumab without a plan, and to report jaw or thigh pain; fracture liaison services close the treatment gap.

33.4 Hip Fracture in Older Adults

- Most hip fractures in older adults are fragility fractures after a low-energy fall; in Ontario about 12,000 occur each year, and about 1 in 5 people die within a year.
- Ontario Health's 2024 quality standard calls for surgery no later than 48 hours after the person first arrives at any hospital, pain assessment within 30 minutes and consideration of a nerve block.
- After surgery, the person reaches weight bearing as tolerated in the first 24 hours, is mobilized at least daily and is screened for delirium at least every 12 hours.
- People without symptoms whose hemoglobin is 80 g/L or higher are not transfused under the standard; symptoms of anemia are reported.
- Secondary fracture prevention, interprofessional rehabilitation and follow-up within 2 and 12 weeks complete the plan; rural, long-term care and First Nations, Inuit and Métis patients need plans that account for distance and transitions.

33.5 Joint Replacement and Spine Surgery

- CIHI's joint replacement registry reported 175,242 hip and knee replacements in 2024–2025, with a fast rise in day surgery.
- Enhanced recovery care includes preoperative education, early mobilization, multimodal analgesia, no routine drains or catheters and objective discharge criteria.
- Evidence does not support routine hip precautions after posterior-approach THA; the nurse teaches what the surgeon's protocol orders.
- VTE prophylaxis follows the order (the international ASH guideline suggests ASA or an anticoagulant after THA or TKA); dislocation and periprosthetic joint infection are reported at once.
- After spine surgery, the nurse compares leg strength and sensation with the baseline, reports new deficits at once and checks for urinary retention.

33.6 Amputation

- Diabetes and PAD underlie most lower-limb amputations in Ontario, and rates rose again after 2010.
- First Nations people with diabetes in Ontario had amputations 3 to 5 times as often as other Ontarians with diabetes (1995/96 to 2014/15), reflecting structural barriers to care.
- Nursing care protects the residual limb, controls swelling and prevents hip and knee contractures through positioning and exercise.
- Phantom limb pain affects about 64% of people with amputation and is real pain that needs treatment.
- Grief, body image, rehabilitation and funding for a prosthesis are part of the plan.

33.7 Mobility and Safe Patient Handling

- Mobility is treatment, and bed rest leads to functional decline in older adults.
- Ontario health care workers have lost-time musculoskeletal injury rates roughly double the Ontario average, and almost half of these injuries are linked to moving clients.
- The nurse assesses the person before every move and follows and updates the mobility plan.
- Equipment is matched to the person's abilities, using the least support that is safe, and no adult is lifted manually.
- After a fall, the nurse calls for help, assesses for injury and uses the equipment policy requires to get the person up.

Key Terms (42)

amputation: The removal of all or part of a limb.

back slab: A plaster or fibreglass splint moulded along one side of a limb and held on with a bandage, leaving room for swelling.

bone mineral density (BMD): The amount of mineral in a given area of bone, measured with dual-energy X-ray absorptiometry (DXA).

cast: A rigid shell of plaster or fibreglass that wraps around a limb to hold a fracture still.

closed fracture: A fracture in which the skin over the break is intact.

comminuted fracture: A fracture in which the bone breaks into three or more pieces.

compartment syndrome: A rise in pressure within a closed muscle compartment that cuts off blood flow to the muscles and nerves inside it; a surgical emergency.

contracture: A fixed shortening of muscles and joint tissues that stops a joint from straightening fully.

discectomy: Surgery that removes the part of a herniated disc that presses on a nerve root.

external fixator: A frame outside the body joined to the bone by pins or wires that pass through the skin, used to hold a fracture still.

fasciotomy: Surgery that cuts open the fascia along a muscle compartment to relieve pressure.

fat embolism syndrome (FES): An illness, usually after a long-bone or pelvic fracture, in which fat droplets in the blood cause breathing problems, neurologic changes and a petechial rash.

femoral neck fracture: A break in the narrow neck of the femur just below the femoral head, inside the hip joint capsule (an intracapsular fracture).

fracture: A break in the continuity of a bone.

fracture liaison service: A coordinated program that identifies people with a recent fragility fracture and makes sure they are assessed and treated to prevent another fracture.

fragility fracture: A fracture from low trauma, such as a fall from standing height, that would not normally break a healthy bone.

hemiarthroplasty: Surgery that replaces the femoral head and neck with a prosthesis while leaving the hip socket in place.

hip dislocation: Displacement of the ball of a hip prosthesis (or a natural femoral head) out of the socket.

hip fracture: A break in the upper part of the femur near the hip joint.

internal fixation: Plates, screws, rods or nails placed in surgery to hold a broken bone from inside.

intertrochanteric fracture: A break in the femur between the greater and lesser trochanters, outside the hip joint capsule.

laminectomy: Surgery that removes part of the lamina, the bony arch at the back of a vertebra, to relieve pressure on the spinal cord or nerves.

mechanical lift: A device that raises and moves a person in a sling, from the floor or a ceiling track, so that staff do not bear the person's weight.

neurovascular assessment: A check of blood flow and nerve function in a limb below an injury, cast, splint, bandage or surgical site.

nonunion: A fracture that fails to heal.

open fracture: A fracture in which the bone breaks through the skin or a wound connects with the break, allowing bacteria to reach the bone.

osteomyelitis: Infection of the bone.

osteoporosis: A disease in which bones lose mass and strength and break more easily.

pathologic fracture: A fracture through bone already weakened by disease, such as a tumour that has spread to bone.

periprosthetic joint infection: An infection of an artificial joint and the tissue around it.

phantom limb pain: Pain felt in the part of a limb that has been removed.

pin-site care: The cleaning and dressing of the skin where external fixator or traction pins enter the body.

prehabilitation: Exercise and conditioning before surgery intended to improve recovery afterward.

prosthesis: An artificial device that replaces a missing body part.

reduction: The return of broken bone ends to their normal position, either by hand without an incision (closed) or in surgery (open).

residual limb: The part of a limb that remains after amputation.

safe patient handling: An organized approach that uses assessment, equipment, policy and training to move patients without manual lifting where possible.

secondary fracture prevention: Care that aims to prevent another fracture after a fragility fracture by finding and treating osteoporosis and reducing falls.

spinal fusion: Surgery that joins two or more vertebrae with a bone graft, often held with screws and rods, so that they heal as one bone.

total hip arthroplasty: Surgery that replaces the femoral head and lines the hip socket with artificial parts.

total knee arthroplasty: Surgery that resurfaces the worn ends of the femur and tibia, and often the kneecap, with artificial parts.

traction: A pulling force applied to a limb, through the skin or through a pin in the bone, to restore and keep a broken bone's alignment and length.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Daniel Kovac (Questions 1–4): Daniel Kovac, 24, fractured the shaft of his left tibia playing hockey and is on an orthopedic unit in Ontario awaiting surgery. His leg is in a long-leg back slab held on with a crepe bandage and is raised on three pillows. At 0200 he tells the RPN that his pain is 9 out of 10 even though he received his ordered opioid one hour ago. He says his leg feels "really tight" and his foot is tingling. His left foot pulse is palpable.

1. [CORE] Which assessment should the RPN complete first?

a. Gently extend Daniel's toes while watching whether stretching the muscles in his lower leg sharply increases his pain.

b. Take his temperature and review his most recent white blood cell count to look for an early wound infection.

c. Reposition him, then ask him to rate his pain again in 30 minutes to see whether the opioid has taken full effect.

d. Recheck his foot pulse with a Doppler device, since a strong pulse means that blood flow to the leg is adequate.

Answer: a — Pain out of proportion to the injury that does not respond to analgesia, with tightness and tingling, suggests compartment syndrome. Pain on passive stretch is one of the earliest and most sensitive signs, so the RPN checks it first (section 33.1, Neurovascular Assessment; section 33.2, Compartment Syndrome). Option b looks for infection, which does not explain these findings in a closed fracture. Option c delays assessment of a possible emergency. Option d is wrong because pulse changes are a late sign; a present pulse does not rule compartment syndrome out.

2. [CORE] Daniel's pain increases sharply when his toes are extended. How should the RPN position his leg while help is called?

a. Add a fourth pillow so that the leg is raised well above the level of his heart to reduce swelling.

b. Remove the extra pillows so that the leg rests at the level of his heart, and keep it supported.

c. Lower the leg over the side of the bed so that gravity can increase blood flow to the foot.

d. Keep the leg on three pillows and place ice packs over the back slab along the length of the calf.

Answer: b — With suspected compartment syndrome, the limb rests at heart level (section 33.2, Compartment Syndrome). Option a raises the limb above the heart, which lowers the pressure driving blood into the compartment and can worsen ischemia. Option c lets the limb hang down and increases swelling. Option d keeps the limb raised and adds nothing to relieve pressure; ice does not treat compartment syndrome.

3. [CORE] Which action should the RPN take next regarding the back slab and bandage?

a. Leave the bandage and back slab untouched until the surgeon arrives, because loosening them could displace the fracture.

b. Rewrap the crepe bandage more firmly over the back slab to hold the fracture still and reduce bleeding into the muscles.

c. Loosen the crepe bandage down to the skin, as policy allows, while keeping the back slab in place to support the leg.

d. Remove the back slab and bandage completely, and leave the leg unsupported on the bed so that it can swell freely.

Answer: c — All circumferential dressings and bandages are released down to the skin when compartment syndrome is suspected; the slab stays in place to support the fracture (section 33.2, Compartment Syndrome). Option a leaves a possible cause of compression in place. Option b adds compression and could make the syndrome worse. Option d removes support from an unstable fracture, which can cause more injury and pain.

4. [CORE] Which action best reflects the RPN's responsibility after loosening the bandage?

a. Document the findings in detail and plan to report them to the surgeon during morning rounds in a few hours.

b. Give the as-needed dose of opioid that is ordered and reassess Daniel's pain and toes in one hour.

c. Ask Daniel to try to rest, and check his neurovascular status again at the next scheduled hourly check.

d. Consult the RN and call the surgeon at once with an SBAR report, then stay with Daniel and reassess.

Answer: d — Compartment syndrome is a surgical emergency, and every nurse who recognizes it notifies urgently and stays with the patient; the RPN consults the RN as the patient's needs change (section 33.2, Compartment Syndrome). Options a and c delay notification. Option b may mask the key sign of rising pain and also delays the call; a rising need for opioids is itself a warning.

5. [CORE] A 67-year-old woman tripped on a rug while walking in her home and broke her wrist. She has no history of cancer. How should the nurse describe this fracture to the team?

a. A pathologic fracture, because the bone was weakened by a disease such as cancer that has spread to bone.

b. An open fracture, because any fracture of the wrist allows bacteria from the skin to reach the bone.

c. A fragility fracture, because a fall from standing height would not usually break a healthy bone.

d. A comminuted fracture, because any fracture from a fall breaks the bone into three or more pieces.

Answer: c — A fragility fracture results from low trauma, such as a fall from standing height, and is a warning sign of osteoporosis (section 33.1, How Bones Break and Heal; section 33.3). Option a describes a break through bone weakened by a disease such as a tumour, which is not suggested here. Option b is wrong because an open fracture requires a wound that connects with the fracture. Option d is wrong because "comminuted" describes the number of pieces, which depends on the injury, not on the fact of a fall.

6. [CORE] A man arrives in the emergency department with an open fracture of the lower leg. The bone ends are visible in a dirty wound. Which action by the nurse is appropriate before he goes to the operating room?

a. Dress the wound with gauze soaked in saline under an occlusive film after it has been photographed.

b. Irrigate the wound thoroughly at the bedside with a large volume of saline to remove all contamination.

c. Leave the wound open to the air so that the surgeon can inspect it at any time without removing a dressing.

d. Push the exposed bone ends gently back under the skin so that the wound can be closed and dressed.

Answer: a — UK open fracture standards call for touching the wound only to clear gross contamination and take photographs, then dressing it with saline-soaked gauze under an occlusive film until surgery (section 33.1, First Care After Injury). Option b is wrong because wound washout is done in the operating room, not at the bedside. Option c leaves the wound exposed to contamination and drying; photographs avoid the need to reopen the dressing. Option d can drive contamination deeper and is never done by the nurse.

7. [CORE] A 52-year-old man with a tibial fracture asks the nurse what he can do to help his bone heal. Which response is most accurate?

a. "Healing depends only on the type of fracture you have, so there is little you can do to change it."

b. "Eating extra calcium every day is the single most important thing you can do to make bones heal faster."

c. "As long as you keep your cast dry, your bone will heal on schedule regardless of other health habits."

d. "Stopping smoking will help, because smoking slows the growth of the new blood vessels the bone needs."

Answer: d — Smoking is linked to higher odds of nonunion and slows the growth of new blood vessels into the healing area (section 33.1, How Bones Break and Heal). Option a is wrong because patient factors such as smoking, diabetes and nutrition also matter. Option b overstates the role of calcium; no single nutrient is described as the most important factor. Option c ignores the patient factors that affect healing.

8. [CORE] The nurse is teaching a patient going home with a new fibreglass forearm cast. Which statement by the patient shows understanding?

a. "If my skin gets itchy under the cast, I'll slide a knitting needle inside to scratch it very gently."

b. "If my fingers turn grey or I can't move them, I'll go to the emergency department right away."

c. "If the cast feels tight tomorrow, I'll trim the top edge with kitchen scissors so it doesn't rub my skin."

d. "I'll sprinkle some baby powder inside the cast every day to keep the skin dry."

Answer: b — Grey or blue fingers, or being unable to move them, can signal compromised circulation or nerve function and need urgent care (section 33.1, Patient Education box). Option a can scrape the skin and lead to infection or pressure injury. Option c is wrong; patients do not cut or trim their casts, and a tight cast needs assessment. Option d is wrong because powders and lotions are not used under a cast.

9. [CORE] The nurse is assessing the foot of a patient with dark skin after surgery to fix an ankle fracture. Which approach gives the most reliable information about circulation?

a. Relying on the colour of the skin of the foot, because pallor is easy to see on all skin tones.

b. Relying on the pedal pulse alone, because a strong pulse rules out any problem with circulation.

c. Asking the patient whether the foot looks normal to them, because they know their own skin best.

d. Checking capillary refill, skin temperature and swelling, and comparing them with the other foot.

Answer: d — Colour alone is not a reliable guide on every skin tone, so the nurse uses capillary refill, temperature, swelling and comparison with the other limb (section 33.1, Neurovascular Assessment). Option a is wrong because skin colour on its own is not a reliable guide to circulation. Option b is wrong because a pulse can be present even when compartment syndrome is developing. Option c may add useful information, but it does not replace a structured assessment by the nurse.

10. [CORE] A patient has a long-leg cast applied for a tibial fracture. Which findings should the nurse report at once? Select all that apply.

a. Numbness and tingling in the toes that were not present an hour ago

b. Pain that keeps rising despite the analgesia that has been given

c. Mild itching under the cast that eases with cool air from a fan

d. Toes that are cool and pale compared with the toes on the other foot

e. Being unable to move the toes when asked to wiggle them

f. Warm, pink toes with capillary refill that matches the other foot

Answer: a, b, d, e — New numbness or tingling, pain that keeps rising despite analgesia, cool and pale toes, and loss of movement are all signs of neurovascular compromise and are reported at once (section 33.1, Table 33.1 and Neurovascular Assessment). Option c is a common, harmless complaint that the patient can manage safely. Option f is an expected finding.

11. [CORE] A patient has an external fixator on the lower leg. Which finding at a pin site suggests infection and should be reported?

a. A small amount of dried, clear crust sealing the edge of the skin around one pin

b. Pin sites that are clean and covered with the dressing applied six days earlier

c. Increasing pain at one pin site with spreading redness and more drainage than before

d. Mild tenderness when the patient first stands, which settles after a few minutes of rest

Answer: c — Increasing pain, spreading redness, more swelling and more drainage are signs of pin-site infection (section 33.1, Casts, Splints and Traction). Option a is common; dried drainage sealing a site is not by itself a sign of infection. Option b fits guidance that supports weekly dressing changes when sites are dry. Option d is a short-lived discomfort without signs of infection.

12. [CORE] A 28-year-old woman is on day two after a fractured femur and pelvis from a car crash. She has become restless and confused, her oxygen saturation has fallen to 88% on room air, and the nurse sees small red spots in her armpits. Which action should the nurse take first?

a. Reorient her and dim the lights, then recheck her mental status in one hour.

b. Apply oxygen per protocol and call for urgent help, such as the rapid response team.

c. Ask the pharmacist whether any of her new medicines could be causing a skin rash and confusion.

d. Encourage her to take deep breaths and use her incentive spirometer every hour.

Answer: b — Falling oxygen saturation, new confusion and petechiae two days after long-bone and pelvic fractures suggest fat embolism syndrome, which needs oxygen and urgent escalation (section 33.2, Fat Embolism Syndrome). Option a treats the confusion as minor and delays care. Option c explores a less likely cause while she is hypoxic. Option d may help breathing in general but does not address a falling saturation with neurologic change.

13. [CORE] Which adult should the nurse expect to be offered bone mineral density testing under the Osteoporosis Canada 2023 guideline?

a. A 66-year-old man whose father broke his hip after a fall in his late seventies.

b. A 55-year-old woman with no previous fractures and no known risk factors for osteoporosis.

c. A 45-year-old man who broke his ankle playing soccer and has no other risk factors.

d. A 60-year-old woman who smokes but has no other risk factors and no fracture history.

Answer: a — The guideline suggests testing at age 65 to 69 with one risk factor, and a parent with a hip fracture is a risk factor (section 33.3, Osteoporosis). Option b has no risk factors and is under 70. Option c is under 50, and a sports injury is not a fragility fracture. Option d is between 50 and 64 with only one risk factor; at that age, testing is suggested only after a previous osteoporosis-related fracture or with at least two risk factors.

14. [CORE] A woman starting alendronate asks how to take it. Which instruction is correct?

a. "Take it at bedtime with a glass of milk so it doesn't upset your stomach overnight."

b. "Take it with breakfast and your calcium pill so you remember to take them together."

c. "Chew the tablet well before swallowing it, then lie down for a few minutes so that it is absorbed."

d. "Take it first thing in the morning with plain water, then stay upright for 30 minutes."

Answer: d — Alendronate is taken first thing in the morning with a full glass of plain water, swallowed whole, and the patient stays upright and lets 30 minutes or more pass before eating, drinking or taking other medicines (section 33.3, Medications box). Option a is wrong because it is never taken at bedtime or with milk. Option b is wrong because food and calcium block absorption. Option c is wrong because the tablet is not chewed and lying down raises the risk of irritating the esophagus.

15. [CORE] A man who has received denosumab for three years tells the nurse he plans to skip his next injection because he feels fine. Which response by the nurse is best?

a. "That's reasonable, because the medicine keeps protecting your bones for years after the last dose."

b. "You could switch to calcium tablets instead, since they work the same way as your injection."

c. "Please talk with your prescriber before stopping, because stopping can cause rapid bone loss."

d. "You can stop safely now, because three years is the usual full course for this medicine."

Answer: c — Stopping or delaying denosumab without a plan is linked to rapid bone loss and spinal fractures, so the patient needs to talk with the prescriber first (section 33.3, Medications box). Option a is wrong because the protective effect fades quickly after stopping. Option b is wrong because calcium does not replace denosumab. Option d gives incorrect information about the course of treatment.

16. [CORE] On an orthopedic unit in Ontario, an RPN who has not cared for a patient with an external fixator is assigned to one. Employer policy allows RPNs to do pin-site care after education. Which action best reflects the College of Nurses of Ontario's (CNO's) approach to scope of practice?

a. Decline the assignment, because only RNs may care for patients with external fixators in Ontario hospitals.

b. Tell the charge nurse about the learning need and complete the education before giving the care.

c. Perform the care using what the RPN remembers from school, since the employer policy allows it.

d. Ask the patient to clean the pin sites, since patients learn the care before they go home anyway.

Answer: b — CNO's approach to scope looks at authority, competence and context; here the employer allows the care, but the RPN must also have the competence, so the RPN speaks up and gets the education first (section 1.3; section 33.1, Casts, Splints and Traction). Option a states a rule that is not part of CNO's standards; who gives this care depends on authority, competence and context, and employer policy allows it here. Option c ignores the need for current competence. Option d hands the nurse's responsibility to the patient before teaching has happened.

17. [CORE] A patient returned from surgery on a forearm fracture two hours ago with a nerve block in the arm. The nurse notes that the fingers are more swollen and cooler than the other hand, but the patient feels no pain. Which action is most appropriate?

a. Report the findings now, because the nerve block can hide the pain of compartment syndrome.

b. Reassure the patient that the absence of pain shows that the circulation in the arm is working normally.

c. Raise the arm on two more pillows above the heart and recheck the fingers at the next scheduled check.

d. Wait until the nerve block wears off so that the patient can report pain before calling the surgeon.

Answer: a — Patients with a nerve block cannot report the pain that is usually the earliest sign of compartment syndrome, so other changes, such as increasing swelling and coolness, need medical review early (section 33.1, Neurovascular Assessment). Option b is wrong because the absence of pain is expected with a block and does not show good circulation. Option c may worsen ischemia if compartment syndrome is developing and delays reporting. Option d delays care until damage may already be done.

18. [RN] A patient with a femoral fracture is in skin traction while waiting for surgery. The nurse finds that the patient has slid down the bed and the weights are resting on the floor. Which action is correct?

a. Lift the weights and tie the rope shorter so that the weights hang just below the end of the bed frame.

b. Remove the weights until the patient's surgery, because traction is no longer needed when it has slipped.

c. Help the patient move up the bed with enough staff so that the weights hang freely again, then check the leg.

d. Leave the weights on the floor, since the pull of traction continues as long as the rope stays in the pulley.

Answer: c — Traction works only when the weights hang freely; the patient is moved up the bed safely so the pull is restored, and the skin and neurovascular status are then checked (section 33.1, Going Deeper: Traction and External Fixation). Option a changes the traction set-up without an order. Option b stops treatment without an order. Option d is wrong because weights resting on the floor exert no pull.

19. [RN] A patient has signs that suggest fat embolism syndrome on day two after a femoral fracture. A student asks how the diagnosis is made. Which response by the nurse is accurate?

a. "A single blood test for fat in the blood confirms the diagnosis and rules out other conditions."

b. "It is a clinical diagnosis, made from the pattern of findings after other causes such as pulmonary embolism are ruled out."

c. "The diagnosis is confirmed only when all three classic signs, including the rash, are present together."

d. "A chest X-ray is the standard test, because it shows the fat droplets lodged in the lung vessels."

Answer: b — Several criteria sets exist, but none has been validated or accepted as a standard; the diagnosis rests on the clinical pattern after other causes are excluded (section 33.2, Fat Embolism Syndrome). Option a is wrong; fat in the blood is common after fractures and does not confirm the syndrome. Option c is wrong because the rash is not seen in every patient, and not all features need to be present. Option d is wrong because a chest X-ray may show changes but does not show fat droplets and does not confirm the diagnosis.

20. [RN] The nurse is teaching new graduates about compartment syndrome. Which statement correctly compares its early and late signs?

a. "Early signs include absent pulses and paralysis, while pain is a late sign that appears only after the nerves are damaged."

b. "Early signs include pale skin and a weak pulse, while pain on passive stretch is a late sign of muscle death."

c. "Early and late signs are the same, so any one finding is enough to rule compartment syndrome in or out."

d. "Pain out of proportion and pain on passive stretch are early signs, while numbness, weakness and absent pulses are late."

Answer: d — Pain out of proportion to the injury and pain on passive stretch are the earliest findings; numbness, weakness, colour change and weak or absent pulses are late (section 33.2, Compartment Syndrome). Options a and b reverse the order of the signs. Option c is wrong because the signs differ in timing and no single finding rules the condition out; a present pulse, for example, does not exclude it.

Case: Edna Kowalczyk (Questions 21–26): Edna Kowalczyk, 86, had a hemiarthroplasty yesterday afternoon for a displaced femoral neck fracture after a fall at home, where she lived alone and walked with a cane. On admission she was alert and oriented and wore glasses and hearing aids. At 0300 the nurse finds her trying to climb out of bed and pulling at her IV. She says she must get home to feed her children, cannot keep track of the nurse's questions, and dozes between answers. Vital signs: temperature 37.4 °C, heart rate 104, respiratory rate 22, blood pressure 108/62 mm Hg and oxygen saturation 91% on room air (96% at 2000). She has no urinary catheter and has voided 120 mL since 2000. Her hemoglobin at 1800 yesterday was 84 g/L (112 g/L before surgery). She grimaces when her leg is moved; her last opioid dose was at 1800, and she declined a dose at 2200. Her glasses and hearing aids are in the bedside drawer.

21. [CORE] Which findings at 0300 should the nurse recognize as cues that need follow-up? Select all that apply.

a. New confusion with inattention and drowsiness
b. Oxygen saturation of 91% on room air
c. Urine output of 120 mL since 2000
d. Temperature of 37.4 °C
e. Heart rate of 104
f. Lived alone and walked with a cane before the fall
g. Hemoglobin of 84 g/L, down from 112 g/L

Answer: a, b, c, e, g — Confusion that began suddenly, with inattention and drowsiness, is a cue for delirium (a; section 33.4; Chapter 8). A fall in saturation from 96% to 91% suggests hypoxemia (b). An output of 120 mL over 7 hours is low and may mean low volume or urinary retention (c). A heart rate of 104 may reflect pain, hypoxemia, low volume or bleeding (e). A hemoglobin drop to 84 g/L reflects surgical blood loss and needs watching with her other findings (g). A temperature of 37.4 °C is within a normal range on day 1 after surgery (d). Her living situation and cane use are background for discharge planning, not a change that needs follow-up tonight (f).

22. [CORE] Which explanation best links Mrs. Kowalczyk's findings?

a. She has dementia that was missed before surgery, and the unfamiliar hospital setting at night is now making it visible to staff.
b. She is having a normal reaction to anesthesia that will pass on its own within a few hours without any treatment.
c. She has delirium, likely with several causes, including low oxygen, untreated pain, low urine output and blood loss.
d. She is anxious about her children and her home, and anxiety explains her fast heart rate, breathing and low output.

Answer: c — Her confusion began suddenly, fluctuates and comes with inattention and drowsiness, which fits delirium (c; section 33.4; Chapter 8). Hypoxemia, pain, possible urinary retention or low volume, and anemia are all possible contributors. She was oriented on admission, so a long-standing dementia does not explain a sudden change (a). Anesthetic effects do not explain new findings at 0300 on day 1, and delirium needs a search for causes (b). Anxiety does not cause a falling saturation or low urine output (d).

23. [RN] Which concern should the nurse treat as the priority?

a. Possible hypoxemia with a fast heart rate after surgery, which could signal pulmonary embolism, pneumonia or bleeding and needs urgent assessment.
b. Constipation from opioids and bed rest, which can cause restlessness in older adults and needs a bowel routine started in the morning.
c. Disturbed sleep in a noisy unit, which is common after surgery and needs a quiet room and fewer checks overnight to let her rest.
d. Risk of a fall from climbing out of bed, which needs a bed alarm and a sitter so that she cannot leave the bed before the morning.

Answer: a — A falling saturation with a fast heart rate threatens oxygen delivery to the brain and heart, and causes such as pulmonary embolism, pneumonia or bleeding can become life-threatening, so this comes first (a; sections 33.4 and 33.5; Chapters 6 and 15). Constipation does not explain hypoxemia (b). Fewer checks would be unsafe while she is unstable (c). Fall prevention matters, but it does not address the cause of her change (d).

24. [CORE] Which plan best addresses the likely causes of Mrs. Kowalczyk's delirium?

a. Ask the physician for an order for wrist restraints and a sedative so that she stays in bed and keeps her IV in place until morning.
b. Apply oxygen per protocol, treat her pain, check her bladder with a scanner as ordered, and give back her glasses and hearing aids.
c. Hold all further opioid doses, since opioids cause confusion, and reassess her thinking after she has slept for the rest of the night.
d. Move her to a bed near the nursing station, dim the lights, and recheck her vital signs and saturation at the next scheduled time.

Answer: b — Oxygen, pain control, finding and treating urinary retention and restoring her glasses and hearing aids each address a likely cause of delirium (b; section 33.4; Chapter 8). Restraints and sedatives can worsen delirium and are not first-line (a). Untreated pain also causes delirium, so holding all analgesia is not the answer; the team chooses the analgesic approach (c; Chapter 5). Waiting for the next scheduled check delays action for an unstable patient (d).

25. [CORE] The nurse calls the on-call surgical resident. Which report best follows SBAR?

a. "Mrs. Kowalczyk in room 12 is very confused and pulling at her IV, and we cannot keep her in bed. Can you order something to calm her down?"

b. "I'm calling about Mrs. Kowalczyk, day 1 after hemiarthroplasty. Her vitals are a bit off and she is confused. Could you come and see her when you get a chance?"

c. "Mrs. Kowalczyk's hemoglobin was 84 last evening. Should we transfuse? She also seems confused, but her daughter said she gets mixed up at night."

d. "Mrs. Kowalczyk, 86, day 1 after hemiarthroplasty, has new confusion and a saturation of 91%, down from 96%. Heart rate 104, hemoglobin 84 from 112, output 120 mL since 2000. I think she has delirium with hypoxemia. Please come now."

Answer: d — Option d gives the situation, background, assessment with specific numbers and the nurse's interpretation, and a clear request, which is the SBAR structure (d; section 33.4; Chapter 6). Option a asks for sedation without data or a search for causes (a). Option b is vague and does not state urgency (b). Option c focuses on the hemoglobin, includes unverified information and leaves out the hypoxemia (c).

26. [CORE] By 1000, Mrs. Kowalczyk is on oxygen and her pain is treated. Which finding best shows that her plan of care is working?

a. She is sleeping soundly with bed rails up, and she has not tried to get out of bed since the sedative given at 0400.

b. Her daughter has asked to take her home today, and the team has agreed to discharge her without further assessment.

c. She answers attention questions correctly, has a saturation of 95%, and has sat at the bedside and walked a few steps with the physiotherapist.

d. Her hemoglobin is unchanged at 84 g/L, and she has been kept in bed so that her new hip can rest until she is less confused.

Answer: c — Improved attention, better oxygenation and mobilization on day 1 show that delirium is clearing and recovery is on track (c; section 33.4). Sleeping after a sedative does not show that delirium has resolved and may hide it (a). Discharge on day 1 without assessment is unsafe and does not measure her response (b). Keeping her in bed works against the standard's goal of weight bearing within 24 hours, and her family can help by sitting with her, reorienting her and joining her walks (d).

27. [CORE] An 81-year-old man with a hip fracture arrived at a small rural hospital at 0800 on Monday and was transferred to a regional centre, arriving at 1600 on Monday. According to the Ontario hip fracture quality standard, by what time should his surgery take place?

a. By 0800 on Wednesday, 48 hours after he first arrived at the rural hospital

b. By 1600 on Wednesday, 48 hours after he arrived at the regional centre

c. By 1600 on Tuesday, 24 hours after he arrived at the regional centre

d. Within 48 hours of the time the orthopedic surgeon first assessed him at the centre

Answer: a — The standard starts the 48-hour clock when the person first arrives at any hospital, so time at a hospital that does not do the surgery counts (a; section 33.4). Starting the clock at the regional centre or at the surgeon's assessment would hide the delay caused by transfer (b, d). The standard's target is 48 hours, not 24 (c).

28. [CORE] On the first day after surgery for a hip fracture, a 79-year-old woman tells the nurse, "I'll just stay in bed until the pain is gone." Her surgeon has ordered weight bearing as tolerated. What is the nurse's best response?

a. "That's fine. Your hip needs a few days of rest so the bone can heal before you put any weight through it."

b. "Getting up today, with your pain treated first, lowers your risk of complications and helps you get home sooner."

c. "You'll need to walk the full length of the hall today, even if it hurts, or you won't be able to go home."

d. "Let's wait until the physiotherapist comes tomorrow, and they can decide whether you are ready to get out of bed."

Answer: b — The quality standard calls for weight bearing as tolerated in the first 24 hours after surgery and daily mobilization, with pain treated so that the person can move (b; section 33.4). Bed rest increases complications and delays recovery (a). Forcing a long walk through pain is unsafe and unkind (c). Nurses mobilize patients as ordered, and waiting a day delays care (d).

29. [CORE] A 74-year-old woman is recovering from surgery for a fragility hip fracture. Which action best supports secondary fracture prevention before she leaves hospital?

a. Teach her to avoid walking outdoors for the next year so that she does not fall on uneven ground.

b. Tell her to ask her family physician about a bone density test and treatment at her next routine visit next year.

c. Arrange a fracture risk assessment in hospital and an offer of osteoporosis treatment when appropriate.

d. Advise her to take a high dose of calcium each day, since that alone will prevent another fracture.

Answer: c — The standard calls for a clinician with expertise in osteoporosis to assess fracture risk in hospital and for osteoporosis medicine to be offered when appropriate (c; sections 33.3 and 33.4). Avoiding walking leads to weakness and more falls (a). Leaving assessment for a later visit misses the chance to act (b). Calcium alone does not prevent fractures, and doses follow the guideline (d; section 33.3).

30. [CORE] A man is to have a posterior-approach total hip arthroplasty. He asks whether he will have to follow "hip rules" for life, as his neighbour did. What is the nurse's best response?

a. "Everyone who has a hip replacement must follow the same set of hip rules for the rest of their life to avoid dislocation."

b. "Hip rules are no longer used anywhere, so you can move any way you like as soon as you wake up from surgery."

c. "You should follow your neighbour's rules, because they worked for him and his surgery was done the same way."

d. "Practice varies, and recent evidence questions routine rules. Follow the instructions your own surgeon gives you."

Answer: d — A 2023 meta-analysis found that routine hip precautions after posterior-approach THA may make little or no difference to early dislocation, and practice varies, so the patient follows his surgeon's protocol (d; section 33.5). There is no single lifelong rule for everyone (a). Some surgeons still order precautions, so saying they are never used is wrong (b). Another person's rules may not apply (c).

31. [CORE] The nurse is teaching a patient going home after a total knee arthroplasty. Which findings should the patient report promptly? Select all that apply.

a. Redness, warmth and new drainage from the incision
b. New pain and swelling in the calf
c. Mild stiffness in the knee after sitting for an hour
d. Sudden shortness of breath or chest pain
e. Fever with knee pain that keeps getting worse
f. Bruising around the knee that is fading

Answer: a, b, d, e — Redness, warmth, drainage, fever and increasing pain may signal infection, including a periprosthetic joint infection (a, e; section 33.5). Calf pain and swelling may signal deep vein thrombosis, and sudden shortness of breath or chest pain may signal pulmonary embolism (b, d; Chapters 15 and 19). Mild stiffness after sitting and fading bruising are expected during recovery (c, f).

32. [CORE] Four hours after a lumbar laminectomy, a patient tells the RPN that her left foot "feels numb and won't lift properly." Her preoperative baseline showed full strength and normal sensation in both legs. What should the RPN do first?

a. Reposition her on her side, since numbness is usually caused by lying on the back for too long.
b. Recheck the finding at the next scheduled assessment in 4 hours and document the change.
c. Give her ordered analgesic, since pain can make it hard to lift the foot after spine surgery.
d. Compare both legs with the baseline and report the change to the RN and surgeon at once.

Answer: d — New weakness or numbness after spine surgery may signal bleeding or swelling pressing on the nerves, such as an epidural hematoma, so the RPN confirms the change against the baseline and escalates at once (d; section 33.5; Chapter 6). Assuming a position cause or waiting delays care (a, b). Analgesia does not address a new neurologic deficit (c).

33. [CORE] Six hours after spinal fusion, a patient whose urinary catheter was removed in the recovery room has not voided and says his lower abdomen feels full. What should the nurse do next?

a. Encourage him to drink more fluids and recheck in 4 hours, since he is probably dehydrated.
b. Assess his bladder with a scanner as ordered and report retention to the prescriber.
c. Insert a urinary catheter and leave it in place for the rest of his hospital stay.
d. Tell him that this is expected after spine surgery and that he will void in time.

Answer: b — Urinary retention is common after spine surgery, and the ERAS guideline advises checking that the bladder empties after catheter removal (b; section 33.5). More fluid could worsen an already full bladder (a). Catheterization follows orders, and leaving a catheter in raises infection risk (c). A full bladder with discomfort needs action, not reassurance (d).

34. [CORE] A patient had an above-knee amputation 2 days ago. Which nursing action best helps prevent a hip flexion contracture?

a. Keep a pillow under the residual limb at all times to reduce swelling and pain.
b. Keep the head of the bed raised high so that he is sitting up most of the day.
c. Help him lie prone or flat for periods as ordered and avoid propping the limb.
d. Have him rest in a chair with the hip bent for most of the day to build tolerance.

Answer: c — Lying flat or prone and keeping the hip straight stretch the hip flexors and help prevent a contracture that would make a prosthesis hard to fit (c; section 33.6). Pillows under the limb, a high head of bed and long periods sitting all keep the hip bent (a, b, d).

35. [CORE] Three days after a below-knee amputation, a patient says, "My missing foot is burning. I must be going crazy." What is the nurse's best response?

a. "Phantom pain is common and real. Tell me more about it so we can treat it with the team."
b. "Your foot has been removed, so the pain must be coming from somewhere else in your leg."
c. "Try to think about something else, and the feeling will go away once you stop focusing on it."
d. "That feeling usually means the incision is infected, so I will ask the surgeon to see you."

Answer: a — Phantom limb pain is pain felt in the removed part of the limb; it affects about 64% of people with amputation and needs assessment and treatment (a; section 33.6; Chapter 5). Dismissing it or blaming the person's thinking is inaccurate and unhelpful (b, c). Phantom pain is not a sign of infection (d).

36. [CORE] A 58-year-old First Nations man from a remote fly-in community is recovering from a below-knee amputation related to diabetes and PAD. Which nursing action best reflects culturally safe care?

a. Plan his care as for any patient, since his background does not affect his recovery after amputation.
b. Tell him that his amputation was caused by not managing his diabetes well and that he must do better.
c. Arrange discharge to a city rehabilitation centre without discussing it, since his community lacks services.
d. Ask about his goals and supports, and plan with him, his family and his community's health services.

Answer: d — Culturally safe, strengths-based care plans with the person, family and community services, and recognizes structural barriers such as distance and limited wound care and rehabilitation services (d; section 33.6; Chapter 2). Ignoring his context can create gaps at discharge (a). Blaming the person ignores the structural causes of higher amputation rates (b). Decisions are made with him, not for him (c).

37. [CORE] A patient on day 2 after a hip fracture repair is newly confused, cannot follow directions and cannot bear weight today, although yesterday she stood with one assist. She needs to move from the bed to a chair. What is the safest approach?

a. Reassess, update the mobility plan, and use a full mechanical lift with the staff that policy requires.

b. Ask two staff to lift her under the arms and swing her into the chair quickly.

c. Stand and pivot her with one nurse using a transfer belt, as the mobility plan said yesterday.

d. Leave her in bed for the day, since moving her while she is confused is never safe.

Answer: a — The nurse reassesses before every move. A person who cannot follow directions or bear weight needs a full mechanical lift, and the plan is updated (a; section 33.7). Manual lifting injures staff and patients (b). Yesterday's plan no longer fits (c). Staying in bed adds risk; safe equipment allows movement (d).

38. [CORE] An RPN new to an orthopedic unit is asked to transfer a patient with a ceiling lift. She has never been trained on this model. What should the RPN do?

a. Use the lift anyway, since all lifts work the same way and the patient is waiting.

b. Ask for training or for a trained colleague to help before she uses the lift.

c. Move the patient manually with help, since that is faster than learning the lift.

d. Refuse to move the patient and document that the transfer was not possible.

Answer: b — Competence is one of CNO's three considerations: a nurse who has not been trained in a skill gets education or help before doing it (b; section 33.7; Chapter 1, section 1.3). Using unfamiliar equipment risks injury (a). Manual lifting is unsafe (c). The patient still needs to move, so the RPN finds a safe way to help (d).

39. [RN] On the first day after a posterior-approach total hip arthroplasty, a patient bends forward to pick up his slipper and cries out. His leg now looks shorter and turned inward, and he cannot move it. What should the nurse do?

a. Keep him still, check circulation and sensation in his foot, and notify the surgeon at once.

b. Help him back into bed and gently straighten his leg to see whether the hip moves back into place.

c. Give his ordered analgesic, apply ice, and reassess his hip and leg position in 1 hour.

d. Have him stand with a walker to check whether he can bear weight on the operated leg.

Answer: a — Sudden pain with a shortened, rotated leg after a movement suggests a hip dislocation. The nurse keeps the person still, checks the limb's circulation and sensation, and notifies the surgeon at once (a; section 33.5). Moving the leg can injure nerves and vessels (b). Analgesia matters, but waiting delays reduction (c). Standing on a dislocated hip is unsafe (d).

40. [RN] Which patient's hemoglobin result most clearly needs a prompt report to the prescriber for a transfusion decision?

a. Day 2 after a hip fracture repair, hemoglobin 86 g/L, no symptoms, walking with a walker

b. Day 1 after total knee arthroplasty, hemoglobin 98 g/L, mild incision pain, vital signs at baseline

c. Day 3 after a hip fracture repair, hemoglobin 82 g/L, no symptoms, eating and sleeping well

d. Day 2 after hemiarthroplasty, hemoglobin 74 g/L, dizzy on standing, heart rate 112, new chest discomfort

Answer: d — The Ontario hip fracture standard advises against transfusion for people without symptoms whose postoperative hemoglobin is at least 80 g/L, and the AABB guideline suggests considering transfusion below 70 g/L for most stable adults, or below 80 g/L after orthopedic surgery or with cardiovascular disease (d; section 33.5; Chapter 20). A hemoglobin of 74 g/L with dizziness, tachycardia and chest discomfort needs a prompt report. The other three patients have no symptoms and a hemoglobin above 80 g/L, so they are monitored (a, b, c).

References

Amgen Canada Inc. (2026). *Prolia (denosumab injection) product monograph*. https://www.amgen.ca/-/media/Themes/CorporateAffairs/amgen-ca/amgen-ca/documents/products/en/prolia_pm.pdf

Anderson, D. R., Morgano, G. P., Bennett, C., Dentali, F., Francis, C. W., Garcia, D. A., Kahn, S. R., Rahman, M., Rajasekhar, A., Rogers, F. B., Smythe, M. A., Tikkinen, K. A. O., Yates, A. J., Baldeh, T., Balduzzi, S., Brożek, J. L., Etxeandia-Ikobaltzeta, I., Johal, H., Neumann, I., … Dahm, P. (2019). American Society of Hematology 2019 guidelines for management of venous thromboembolism: Prevention of venous thromboembolism in surgical hospitalized patients. *Blood Advances, 3*(23), 3898–3944. https://doi.org/10.1182/bloodadvances.2019000975

Bahney, C. S., Zondervan, R. L., Allison, P., Theologis, A., Ashley, J. W., Ahn, J., Miclau, T., Marcucio, R. S., & Hankenson, K. D. (2019). Cellular biology of fracture healing. *Journal of Orthopaedic Research, 37*(1), 35–50. https://doi.org/10.1002/jor.24170

British Orthopaedic Association & British Association of Plastic, Reconstructive and Aesthetic Surgeons. (2017). *BOAST: Open fractures*. https://www.bssh.ac.uk/_userfiles/pages/files/professionals/Radius/BOAST-Open-Fractures.pdf

British Orthopaedic Association. (2025). *BOAST: Diagnosis and management of compartment syndrome of the extremities*. https://www.boa.ac.uk/resource/boast-10-pdf.html

Canadian Institute for Health Information. (2025). *Wait times for priority procedures in Canada, 2025*. https://www.cihi.ca/en/wait-times-for-priority-procedures-in-canada-2025

Canadian Institute for Health Information. (2026). *CJRR annual report: Hip and knee replacements in Canada, 2024–2025*. https://www.cihi.ca/en/cjrr-annual-report-hip-and-knee-replacements-in-canada-2024-2025

Canadian Institute for Health Information. (n.d.-a). *Hip fracture surgery within 48 hours* [Indicator]. Retrieved October 27, 2026, from https://www.cihi.ca/en/indicators/hip-fracture-surgery-within-48-hours

Canadian Institute for Health Information. (n.d.-b). *Wait times for hip fracture repair: From ED registration (percentage meeting benchmark)* [Indicator]. Retrieved October 27, 2026, from https://www.cihi.ca/en/indicators/wait-times-for-hip-fracture-repair-from-ed-registration-percentage-meeting-benchmark

Canadian Society for Transfusion Medicine. (2025). *CSTM Choosing Wisely list*. https://transfusion.ca/Education/Choosing-Wisely/CSTM-Choosing-Wisely-List

Carson, J. L., Stanworth, S. J., Guyatt, G., Valentine, S., Dennis, J., Bakhtary, S., Cohn, C. S., Dubon, A., Grossman, B. J., Gupta, G. K., Hess, A. S., Jacobson, J. L., Kaplan, L. J., Lin, Y., Metcalf, R. A., Murphy, C. H., Pavenski, K., Prochaska, M. T., Raval, J. S., … Pagano, M. B. (2023). Red blood cell transfusion: 2023 AABB international guidelines. *JAMA, 330*(19), 1892–1902. https://doi.org/10.1001/jama.2023.12914

Centre of Research Expertise for the Prevention of Musculoskeletal Disorders. (2024). *Transfer equipment resource: Considerations for promoting restorative care and optimal client function*. University of Waterloo. https://uwaterloo.ca/centre-of-research-expertise-for-the-prevention-of-musculoskeletal-disorders/sites/default/files/uploads/documents/transfer-equipment-resource-20240325_final.pdf

Centre of Research Expertise for the Prevention of Musculoskeletal Disorders. (2025). *MSD prevention resources for healthcare*. University of Waterloo. https://uwaterloo.ca/centre-of-research-expertise-for-the-prevention-of-musculoskeletal-disorders/node/404

Dawson-Amoah, K., Raszewski, J., Duplantier, N., & Waddell, B. S. (2018). Dislocation of the hip: A review of types, causes, and treatment. *Ochsner Journal, 18*(3), 242–252. https://doi.org/10.31486/toj.17.0079

Debono, B., Wainwright, T. W., Wang, M. Y., Sigmundsson, F. G., Yang, M. M. H., Smid-Nanninga, H., Bonnal, A., Le Huec, J.-C., Fawcett, W. J., Ljungqvist, O., Lonjon, G., & de Boer, H. D. (2021). Consensus statement for perioperative care in lumbar spinal fusion: Enhanced Recovery After Surgery (ERAS®) Society recommendations. *The Spine Journal, 21*(5), 729–752. https://doi.org/10.1016/j.spinee.2021.01.001

Donaldson, J., Haddad, B., & Khan, W. S. (2014). The pathophysiology, diagnosis and current management of acute compartment syndrome. *The Open Orthopaedics Journal, 8*(1), 185–193. https://doi.org/10.2174/1874325001408010185

Emergency Care BC. (2024). *Cast and splint care* [Patient discharge instructions]. https://emergencycarebc.ca/wp-content/uploads/2024/09/Cast-and-Splint-Care.pdf

Floman, Y., Millgram, M. A., Ashkenazi, E., & Rand, N. (2015). Remote cerebellar hemorrhage complicating unintended durotomy in lumbar spine surgery. *International Journal of Spine Surgery, 9*, Article 29. https://doi.org/10.14444/2029

Hussain, M. A., Al-Omran, M., Salata, K., Sivaswamy, A., Forbes, T. L., Sattar, N., Aljabri, B., Kayssi, A., Verma, S., & de Mestral, C. (2019). Population-based secular trends in lower-extremity amputation for diabetes and peripheral artery disease. *CMAJ, 191*(35), E955–E961. https://doi.org/10.1503/cmaj.190134

Korfitsen, C. B., Mikkelsen, L. R., Mikkelsen, M.-L., Rohde, J. F., Holm, P. M., Tarp, S., Carlsen, H.-H. F., Birkefoss, K., Jakobsen, T., Poulsen, E., Leonhardt, J. S., Overgaard, S., & Mechlenburg, I. (2023). Hip precautions after posterior-approach total hip arthroplasty among patients with primary hip osteoarthritis do not influence early recovery: A systematic review and meta-analysis of randomized and non-randomized studies with 8,835 patients. *Acta Orthopaedica, 94*, 141–151. https://doi.org/10.2340/17453674.2023.11958

Lethaby, A., Temple, J., & Santy-Tomlinson, J. (2013). Pin site care for preventing infections associated with external bone fixators and pins. *Cochrane Database of Systematic Reviews, 2013*(12), Article CD004551. https://doi.org/10.1002/14651858.CD004551.pub3

Limakatso, K., Bedwell, G. J., Madden, V. J., & Parker, R. (2020). The prevalence and risk factors for phantom limb pain in people with amputations: A systematic review and meta-analysis. *PLOS ONE, 15*(10), Article e0240431. https://doi.org/10.1371/journal.pone.0240431

Liu, G., Li, Q., Ruan, H., Zhu, B., Ma, W., & Hu, Y. (2025). Cauda equina syndrome without perineal sensory changes or lower extremity neurological deficits following postoperative spinal epidural hematoma: A case report and literature review. *Orthopaedic Surgery, 17*(2), 653–659. https://doi.org/10.1111/os.14343

Metsemakers, W. J., Morgenstern, M., McNally, M. A., Moriarty, T. F., McFadyen, I., Scarborough, M., Athanasou, N. A., Ochsner, P. E., Kuehl, R., Raschke, M., Borens, O., Xie, Z., Velkes, S., Hungerer, S., Kates, S. L., Zalavras, C., Giannoudis, P. V., Richards, R. G., & Verhofstad, M. H. J. (2018). Fracture-related infection: A consensus on definition from an international expert group. *Injury, 49*(3), 505–510. https://doi.org/10.1016/j.injury.2017.08.040

Morin, S. N., Feldman, S., Funnell, L., Giangregorio, L., Kim, S., McDonald-Blumer, H., Santesso, N., Ridout, R., Ward, W., Ashe, M. C., Bardai, Z., Bartley, J., Binkley, N., Burrell, S., Butt, D., Cadarette, S. M., Cheung, A. M., Chilibeck, P., Dunn, S., . . . Wark, J. D. (2023). Clinical practice guideline for management of osteoporosis and fracture prevention in Canada: 2023 update. *CMAJ, 195*(39), E1333–E1348. https://doi.org/10.1503/cmaj.221647

National Rehabilitation Hospital. (n.d.). *DO and DON'T after your amputation: Positioning advice* [Patient information]. Retrieved October 27, 2026, from https://www.nrh.ie/wp-content/uploads/2026/05/Do-and-Dont-after-your-Amputation.pdf

Ontario Health. (2024). *Hip fracture: Care for people with fragility fractures* (Quality standard, 2024 update). https://ontariohealth.ca/content/dam/ontariohealth/documents/filter-list/qs/qs-hip-fracture-2024-en.pdf

Osteoporosis Canada. (2024). *Quick reference guide: Clinical practice guideline*. https://osteoporosis.ca/quick-reference-guide-clinical-practice-guideline/

Patel, R. (2023). Periprosthetic joint infection. *The New England Journal of Medicine, 388*(3), 251–262. https://doi.org/10.1056/NEJMra2203477

Public Health Agency of Canada. (2024). *Osteoporosis and related fractures in Canada, 2023*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/osteoporosis-related-fractures-canada-2021.html

Public Services Health & Safety Association. (2025). *Client mobility plan* [Form]. https://www.pshsa.ca/wp-content/uploads/2025/09/PSHSA-Client-Mobility-Plan.pdf

Royal College of Nursing. (2022a). *Guidance on pin site care* (Publication code 009 907). https://www.rcn.org.uk/-/media/Royal-College-Of-Nursing/Documents/Publications/2022/February/009-907.pdf

Royal College of Nursing. (2022b). *Peripheral neurovascular observations for acute limb compartment syndrome: RCN consensus guidance* (Publication code 009 905). https://www.rcn.org.uk/-/media/Royal-College-Of-Nursing/Documents/Publications/2022/February/009-905.pdf

Royal College of Nursing. (2026). *Acute limb compartment syndrome observation chart* (Publication code 012 564). https://www.rcn.org.uk/-/media/Royal-College-Of-Nursing/Documents/Publications/2026/August/012-564.pdf

Sandoz Canada Inc. (2022). *Sandoz Alendronate (alendronate sodium tablets) product monograph*. https://pdf.hres.ca/dpd_pm/00067677.PDF

Seixas, E., & Ferreira, P. G. (2018). Fat embolism syndrome presenting as diffuse alveolar hemorrhage: A rare (known) association. *Pulmonology, 24*(5), 314–315. https://doi.org/10.1016/j.pulmoe.2018.06.007

Shah, B. R., Frymire, E., Jacklin, K., Jones, C. R., Khan, S., Slater, M., Walker, J. D., & Green, M. E. (2019). Peripheral arterial disease in Ontario First Nations people with diabetes: A longitudinal population-based cohort study. *CMAJ Open, 7*(4), E700–E705. https://doi.org/10.9778/cmajo.20190162

Sogunuru, G., & Moka, N. (2010). Fat embolism syndrome. *International Journal of Emergency Medicine, 3*(4), 471. https://doi.org/10.1007/s12245-010-0160-5

The War Amps. (n.d.). *Adult amputees*. Retrieved October 27, 2026, from https://www.waramps.ca/ways-we-help/adult-amputees/

Timon, C., Keady, C., & Murphy, C. G. (2021). Fat embolism syndrome – A qualitative review of its incidence, presentation, pathogenesis and management. *Malaysian Orthopaedic Journal, 15*(1), 1–11. https://doi.org/10.5704/MOJ.2103.001

Vu, T., & Butcher, R. (2022). Removable rigid dressings for the post-operative management of leg amputations. *Canadian Journal of Health Technologies, 2*(6). https://doi.org/10.51731/cjht.2022.371

Wainwright, T. W., Gill, M., McDonald, D. A., Middleton, R. G., Reed, M., Sahota, O., Yates, P., & Ljungqvist, O. (2020). Consensus statement for perioperative care in total hip replacement and total knee replacement surgery: Enhanced Recovery After Surgery (ERAS®) Society recommendations. *Acta Orthopaedica, 91*(1), 3–19. https://doi.org/10.1080/17453674.2019.1683790

Zura, R., Xiong, Z., Einhorn, T., Watson, J. T., Ostrum, R. F., Prayson, M. J., Della Rocca, G. J., Mehta, S., McKinley, T., Wang, Z., & Steen, R. G. (2016). Epidemiology of fracture nonunion in 18 human bones. *JAMA Surgery, 151*(11), Article e162775. https://doi.org/10.1001/jamasurg.2016.2775

34 Arthritis and Connective Tissue Disorders

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Assess an adult with joint symptoms, including inflammatory signs on a range of skin tones, and recognize a hot joint as urgent.
2. Support adults with osteoarthritis through exercise, self-management and safe use of pain medicines.
3. Explain rheumatoid arthritis and its treat-to-target care, and teach safe use of methotrexate as a once-weekly medicine.
4. Care for adults with gout during and between flares, including teaching about urate-lowering therapy.
5. Recognize flares and organ involvement in lupus, and recognize giant cell arteritis as an emergency, using the CJMM.
6. Give safe care to adults taking disease-modifying drugs, biologics, JAK inhibitors and corticosteroids, including screening, infection risk and access.
7. Distinguish RN and RPN roles in arthritis care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 5	Clinician; Educator	Foundations of Practice
6	Clinician; Advocate	Foundations of Practice; Ethical Practice
7	Professional; Collaborator	Legal Practice; Collaborative Practice

Introduction

Arthritis is one of the most common reasons adults in Canada live with pain and limited movement. Arthritis Society Canada (n.d.-a) reports that about 6 million people, or 1 in 5 adults, have arthritis, and that half of them are younger than 65. Nurses meet these patients in every setting: a man with knee osteoarthritis admitted with pneumonia, a woman with rheumatoid arthritis whose weekly medicine must continue safely after surgery, an older adult whose joints keep them from getting out of bed. Arthritis is often not the reason for admission, but it shapes how a person moves, sleeps, works and copes, and the medicines used to treat it carry real risks.

This chapter is the book's home for arthritis and connective tissue disorders in adults. Section 34.1 reviews how joints work, how nurses assess joint symptoms and what arthritis looks like in Canada. Section 34.2 covers osteoarthritis, and section 34.3 covers rheumatoid arthritis, including the safe use of methotrexate as a once-weekly medicine. The second half of the chapter covers gout (34.4), systemic lupus erythematosus and other connective tissue disorders (34.5), medicines for inflammatory arthritis (34.6) and living well with chronic arthritis (34.7).

The chapter builds on earlier ones. Scope of practice for registered nurses (RNs) and registered practical nurses (RPNs) is taught in section 1.3, and the Clinical Judgment Measurement Model (CJMM) in section 1.4. Outside Ontario, practical nurses (PNs) are often called licensed practical nurses (LPNs); this chapter uses "the nurse" unless the roles differ. Inflammation and infection are covered in Chapter 4, pain and multimodal analgesia in Chapter 5, and recognizing deterioration and reporting with SBAR (Situation, Background, Assessment, Recommendation) in Chapter 6. Older adults and their medicines are in Chapter 8, the immune system in Chapter 21, kidney disease in Chapter 27, and osteoporosis and joint replacement in Chapter 33. Cultural safety and Indigenous health are in Chapter 2.

34.1 Joints, Inflammation and Arthritis in Canada

How Joints Work

Most joints that move freely, such as the knees, hips, shoulders and fingers, are **synovial joints**. In a synovial joint, the ends of two bones are capped with smooth **articular cartilage**, a firm, slippery tissue that lets the bones glide and spreads the load across the joint. A fibrous capsule encloses the joint. Its inner lining, the **synovium** (synovial membrane), makes a small amount of thick synovial fluid that lubricates the joint and nourishes the cartilage, which has no blood supply of its own. Ligaments, tendons and the muscles that cross the joint hold it steady (Figure 34.1).



Figure 34.1 Structure of a synovial joint, showing the articulating bones, hyaline articular cartilage, joint cavity containing synovial fluid, and the articular capsule composed of an outer fibrous membrane and an inner synovial membrane. (credit: "Figure 9.8, Synovial Joints" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Inflammation is the body's response to injury, infection or an immune attack. Blood vessels widen, fluid and immune cells move into the tissue, and the area becomes warm, swollen, painful and harder to use (section 4.1). In a joint, the inflamed synovium thickens and makes extra fluid, so the joint swells and may feel soft or boggy. Short-lived inflammation settles once the cause is removed. Inflammation that continues for months, as in untreated rheumatoid arthritis, can wear away cartilage and bone and loosen the tissues that hold the joint steady.

Arthritis literally means inflammation of a joint, but the word covers many conditions that affect joints and the tissues around them. Nurses find it helpful to sort them into two broad groups. In **non-inflammatory arthritis**, mainly osteoarthritis, the joint wears down because the body's repair processes cannot keep up with tissue damage (Arthritis Society Canada, n.d.-b). In **inflammatory arthritis**, the immune system or crystals inflame the synovium, a process called **synovitis**. Rheumatoid arthritis is an **autoimmune disease**: the immune system attacks the body's own tissue, in this case the lining of the joints (Arthritis Society Canada, n.d.-c). Gout is a crystal arthritis (section 34.4). Some inflammatory diseases, such as lupus, also affect the skin, kidneys and other organs (section 34.5).

The difference matters. Inflammatory arthritis can damage joints. In rheumatoid arthritis, for example, people who are diagnosed and treated early are less likely to have long-term joint damage and loss of function (Public Health Agency of Canada [PHAC], 2020c). Damaged joints generally cannot be repaired except by surgery (Arthritis Society Canada, n.d.-c).

Assessing the Person With Joint Symptoms

The nurse starts with the person's story. Useful questions include:

- **Onset and pattern:** Did symptoms begin suddenly or over months? Is one joint involved, a few or many? Are the same joints affected on both sides of the body?
- **Morning stiffness:** How long does stiffness last after getting up? Stiffness from osteoarthritis usually eases in less than 30 minutes (Arthritis Society Canada, n.d.-b), whereas **morning stiffness** that lasts 30 minutes or longer is one warning sign of rheumatoid arthritis (Arthritis Society Canada, n.d.-c).
- **Pain:** Is it worse with use and better with rest, or worst after rest? Pain assessment tools are in section 5.2.

- **Whole-body symptoms:** Fatigue, low-grade fever, weight loss and poor appetite can come with rheumatoid arthritis (Arthritis Society Canada, n.d.-c). A rash, mouth ulcers or chest pain that is worse with breathing points toward a connective tissue disorder (section 34.5).
- **Function:** What has become hard to do: dressing, opening jars, climbing stairs, working, caring for others?
- **Background:** Past joint injury, family history, smoking, other conditions and all medicines, including over-the-counter anti-inflammatory drugs.

On examination, the nurse looks at each joint and compares it with the same joint on the other side. Swelling, loss of the normal joint outline, deformity and firm lumps under the skin are noted. The nurse gently feels for warmth, tenderness and soft swelling, checks how far the person can move the joint, listens or feels for grinding (crepitus), and watches the person walk and use their hands.

Function deserves the same care as the joints themselves. The nurse watches the person rise from a chair, walk, reach and grip, and asks about self-care, household tasks, work, sleep and the activities that matter most to them, such as gardening, playing with grandchildren or getting to ceremony or church. These findings set a baseline for judging whether treatment is working and guide referrals to physiotherapy and occupational therapy.

Redness can be hard to see on darker skin tones, so the nurse does not rely on colour alone and also checks for warmth, swelling and tenderness, which can be assessed on every skin tone. The nurse compares warmth over the joint with the same spot on the other side using the back of the hand, and asks the person whether the joint looks or feels different from usual. Skin assessment on a range of skin tones is taught in Chapter 35.

A **red flag** is a finding that needs prompt action. A single hot, swollen joint that has become painful and hard to move over a short time is treated as **septic arthritis** (infection inside the joint) until proven otherwise, even if the person has no fever (Weston & Coakley, 2006). This UK guideline also advises that joint fluid be drawn off (aspirated) before antibiotics are started (Weston & Coakley, 2006). The nurse therefore reports the finding to the prescriber at once and watches for signs of sepsis (section 4.6), escalating immediately if they appear. Other red flags in this chapter include a new headache with jaw pain in an older adult (section 34.5) and fever or a new cough in a person taking methotrexate (section 34.3).

CANADIAN CONTEXT

Arthritis in Canada

- **How common:** About 6 million people in Canada, or 1 in 5 adults, report arthritis. It is more common among people assigned female at birth (1 in 4) than male at birth (1 in 6), and the number is expected to grow by 50% by 2045 (Arthritis Society Canada, n.d.-a). These survey figures leave out people living on reserves and in the territories.
- **Diagnosed disease:** In 2016–2017, about 3.9 million Canadians aged 20 and older (13.6%) lived with diagnosed osteoarthritis (PHAC, 2020b), and about 374,000 aged 16 and older (1.2%) lived with diagnosed rheumatoid arthritis (PHAC, 2020c). These counts come from the Canadian Chronic Disease Surveillance System (CCDSS), which uses physician and hospital records.
- **Daily life:** More than 40% of people with arthritis have pain that limits their activities (Arthritis Society Canada, n.d.-a).
- **First Nations:** In an Alberta population study, rheumatoid arthritis affected about three times as many First Nations residents as non–First Nations residents. First Nations patients with rheumatoid arthritis had more primary care visits but fewer specialist visits (Barnabe et al., 2017). This book follows the First Nations principles of OCAP® (ownership, control, access and possession), under which First Nations govern how data about them are collected and used (Chapter 2). Structural causes, including the ongoing effects of colonization, racism in health care and distance from specialist care, shape these gaps (Chapter 2).
- **Rural and remote:** People far from a rheumatology clinic may travel long distances for care; telephone and virtual follow-up are discussed in section 34.7.

GOING DEEPER

Blood Tests and Joint Fluid in Arthritis

Required for RN students; optional for PN students.

No single blood test diagnoses arthritis. Results are read alongside the history and examination, and reference ranges vary by laboratory.

- **C-reactive protein (CRP) and erythrocyte sedimentation rate (ESR):** Both rise with inflammation from any cause, including infection. They support a diagnosis of inflammatory arthritis but are not specific (Jung & Barra, 2015).
- **Rheumatoid factor (RF) and anti-CCP antibodies:** RF also appears in other conditions, such as hepatitis C and bacterial endocarditis. Antibodies to cyclic citrullinated peptides (anti-CCP) are more specific for rheumatoid arthritis: in one Canadian review, specificity was 96% for anti-CCP compared with 86% for RF (Jung & Barra, 2015). Many people with rheumatoid arthritis test negative for both, so a negative result does not rule it out (Arthritis Society Canada, n.d.-c; Jung & Barra, 2015). The 2010 American College of Rheumatology (ACR) and European Alliance of Associations for Rheumatology (EULAR) classification criteria combine joint count, these antibodies, CRP or ESR and symptom duration (Jung & Barra, 2015).
- **Antinuclear antibodies (ANA):** A positive ANA is the entry requirement of the 2019 EULAR/ACR classification criteria for systemic lupus erythematosus (Aringer et al., 2019); see section 34.5.
- **Serum urate:** Reported in µmol/L; used mainly in gout (section 34.4).
- **Joint fluid:** Fluid aspirated from a swollen joint can be tested for infection and examined for crystals: uric acid crystals in gout, or calcium pyrophosphate crystals in pseudogout (PHAC, 2020a). When infection is possible, aspiration comes before antibiotics (Weston & Coakley, 2006).

34.2 Osteoarthritis

What Happens in Osteoarthritis

Osteoarthritis (OA) is the form of arthritis that people in Canada have most often (Arthritis Society Canada, n.d.-b; PHAC, 2020b). It is a progressive disease of the whole joint. The cartilage and the bone underneath it slowly break down when the joint's repair processes cannot keep pace with damage (Arthritis Society Canada, n.d.-b). As cartilage thins, the joint space narrows, the bone ends change shape and the joint becomes stiff and painful. OA most often affects the knees, hips, big toes, hands and spine (Arthritis Society Canada, n.d.-b; Figure 34.2).

Figure 34.2 Bony enlargements at the distal interphalangeal joints (Heberden nodes) in hand osteoarthritis. (credit: “Heberden-Arthrose” by Drahreg01/Wikimedia Commons, CC BY-SA 3.0)

OA is common and becoming more so. In 2016–2017, about 3.9 million Canadians aged 20 and older lived with diagnosed OA, and about 219,000 were newly diagnosed that year. Prevalence was higher among females (16.1%) than males (11.1%), and both prevalence and new diagnoses rise with age (PHAC, 2020b). OA is not only a disease of old age: nearly one third of people with OA in Canada were diagnosed before age 45 (Arthritis Society Canada, n.d.-a).

Arthritis Society Canada (n.d.-b) lists these risk factors:

- older age, female sex and family history;
- excess body weight;
- a previous joint injury, or repeated stress on a joint from work or sport;
- a joint that formed abnormally, or weak muscles around the joint;
- a sedentary lifestyle.

Symptoms usually build over months or years and often come and go at first. Heavy use typically makes the pain worse, and rest eases it; as OA advances, pain can come with ordinary activity, at rest and at night. Morning stiffness is usually brief, lasting less than 30 minutes. The person may notice less movement, swelling, grinding or creaking, and a feeling that the joint is unstable. OA

Figure 34.3 Anteroposterior X-ray of the left knee showing features of osteoarthritis: joint-space narrowing, increased density of the bone beneath the cartilage and marginal osteophytes (bone spurs). (credit: "Osteoarthritis on X-ray" by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

also reaches beyond the joint: poor sleep, low mood, fatigue and **pain sensitization**, in which the nervous system amplifies pain signals, are common (Arthritis Society Canada, n.d.-b). Pain physiology and sensitization are taught in section 5.1.

There is no single test for OA. The diagnosis rests on symptoms and a physical examination. When a person over 40 has typical symptoms, imaging is usually not needed unless an injury must be ruled out, treatment is not working or surgery is being planned, and what an X-ray shows does not always match how the joint feels (Arthritis Society Canada, n.d.-b). Table 34.1 compares OA with rheumatoid arthritis (Figure 34.3).

Table 34.1 Osteoarthritis and rheumatoid arthritis compared (Arthritis Society Canada, n.d.-b, n.d.-c; PHAC, 2020b, 2020c)

Feature	Osteoarthritis	Rheumatoid arthritis
Main process	Breakdown of cartilage and underlying bone when repair cannot keep up with damage	Autoimmune inflammation of the joint lining (synovitis)
Diagnosed cases in Canada, 2016–2017	About 3.9 million adults aged 20 and older (13.6%)	About 374,000 people aged 16 and older (1.2%)
Usual onset	Gradual, over months to years; more common with age	Over weeks to months; often begins between ages 40 and 60
Joints usually affected	Knees, hips, big toes, hands and spine; often one side more than the other	Small joints of the hands, wrists and feet, as well as larger joints; usually the same joints on both sides
Morning stiffness	Usually less than 30 minutes	30 minutes or more
Whole-body effects	Poor sleep, low mood and fatigue linked to pain	Fatigue, low-grade fever, weight loss; can affect the eyes, lungs, heart, skin and nerves
Blood tests	No blood test diagnoses it	Inflammation markers often raised; RF or anti-CCP may be positive
Main treatment	Education, exercise and weight management; topical or oral medicines as needed	Early disease-modifying drugs aimed at remission, plus self-management

Care and Self-Management

The Osteoarthritis Research Society International (OARSI) guideline for knee, hip and polyarticular (many-joint) OA names **core treatments** for everyone with OA: education about arthritis and a structured, land-based exercise program. For knee OA, the core treatments also include mind–body exercise such as tai chi or yoga, and the exercise program may be combined with dietary weight management (Bannuru et al., 2019). Arthritis Society Canada (n.d.-b) gives the same message: movement, not rest, protects the joint. Strengthening, range-of-motion, endurance and balance exercises all help, and low-impact activities such as walking, cycling and water exercise are good choices. The long-term goal for adults is 150 minutes of moderate to vigorous activity a week, built up gradually. For people carrying extra weight, a loss of about one tenth of body weight can ease knee strain and pain (Arthritis Society Canada, n.d.-b).

Physiotherapists and occupational therapists design exercise programs and recommend walking aids, braces, splints, orthotics and changes at home or work (Arthritis Society Canada, n.d.-b). The nurse reinforces the program, checks that a cane or walker is the right height and is used correctly, and asks what makes exercise hard: pain, fear of damaging the joint, cost or lack of a safe place to walk in winter.

Medicines support, but do not replace, exercise and weight management. The OARSI guideline ranks them by the person's other health conditions (Bannuru et al., 2019):

- **Topical NSAIDs:** A **nonsteroidal anti-inflammatory drug (NSAID)** applied to the skin is strongly recommended for knee OA, including for people with gastrointestinal or cardiovascular conditions or frailty. Only a small amount reaches the blood: the Canadian monograph for one over-the-counter diclofenac gel, which is labelled for recent muscle and joint injuries, reports that about 6% of the applied dose is absorbed and warns against using it with oral NSAIDs (Haleon Canada ULC, 2026).
- **Oral NSAIDs:** Oral NSAIDs, such as naproxen and ibuprofen, or a cyclooxygenase-2 (COX-2) inhibitor such as celecoxib, are conditionally recommended for people without other major conditions. For people with stomach or bowel conditions, the guideline favours a COX-2 inhibitor, or a non-selective NSAID taken with a medicine that protects the stomach. Oral NSAIDs are not recommended for people with cardiovascular disease or frailty (Bannuru et al., 2019).
- **Acetaminophen:** The OARSI panel conditionally advised against acetaminophen for OA because it showed little or no benefit and a possible signal of liver harm (Bannuru et al., 2019). Arthritis Society Canada (n.d.-b) still lists it among the options a person can discuss with a prescriber or pharmacist. When it is used, the nurse counts every source toward the daily limit (section 5.3).
- **Duloxetine:** This antidepressant is an option for knee OA in people who also have widespread pain or depression (Bannuru et al., 2019).
- **Opioids:** The guideline strongly recommends against oral and transdermal opioids for OA because of the risk of dependence and little or no benefit (Bannuru et al., 2019). Opioid safety is taught in section 5.4.

NSAID risks are serious, and many people buy NSAIDs without a prescription. The Canadian celecoxib monograph, which describes risks shared across the class, warns of heart attack and stroke, stomach ulcers and bleeding that can occur without warning, fluid and sodium retention that can raise blood pressure and worsen heart failure, and kidney injury (Nora Pharma Inc., 2026). Kidney risk is highest in people who are older or dehydrated, who have kidney disease, heart failure or liver disease, or who take diuretics, angiotensin-converting enzyme (ACE) inhibitors or angiotensin receptor blockers (ARBs). Before giving an oral NSAID, the nurse reviews kidney function, blood pressure, fluid status, signs of bleeding and the full medication list, and reports concerns to the prescriber. Kidney disease is covered in section 27.3.

A **corticosteroid injection** into the knee is conditionally recommended in the OARSI guideline, but not for hip OA (Bannuru et al., 2019). The nurse teaches the person to report a joint that becomes hotter, more swollen or more painful in the days after an injection, because infection must be ruled out (section 34.1). Joint replacement is considered when pain and disability are significant and other treatments have not worked (Arthritis Society Canada, n.d.-b); surgery and recovery are taught in section 33.5.

OA affects more than the joint. Among working-age adults with OA in Canada, 42% are not in the labour force or in school, compared with 19% of the general population (Arthritis Society Canada, n.d.-a). The nurse asks about sleep, mood, work and caregiving, screens for low mood, and connects the person with physiotherapy, occupational therapy and community programs

(section 34.7). Cold packs may relieve swelling and brief flares of pain, and heat may relieve stiffness, but heat is not used on an inflamed joint. Pacing activities and relaxation techniques help many people cope (Arthritis Society Canada, n.d.-b).

Using the CJMM (section 1.4), the nurse watches for cues that the plan is causing harm or that something new is happening. Black stools, a rising creatinine or new swelling in the legs in a person taking an oral NSAID, or a single joint that is suddenly hot and swollen, are cues to hold the next NSAID dose as appropriate, report at once using SBAR (section 6.2) and evaluate the response.

PATIENT EDUCATION

Moving With Osteoarthritis

- Keep moving. Activity protects your joints; long periods of rest make stiffness and weakness worse.
- Start slowly and build up. Aim, over time, for 150 minutes of moderate activity a week, such as walking, cycling, swimming, water exercise, tai chi or yoga.
- Strengthen the muscles around the sore joint with the exercises your physiotherapist gives you.
- If you carry extra weight, losing about 10% of your body weight can ease knee pain.
- On a bad day, keep doing gentle range-of-motion exercises rather than stopping completely.
- Use cold packs for swelling. Use heat for stiffness, but not on a joint that is hot and swollen.
- Pace your day: break big jobs into smaller ones and rest between them.
- Use a cane, brace or other aid if your therapist recommends it, and ask how to use it correctly.
- Read medicine labels. Many cold, flu and pain products contain an NSAID or acetaminophen. Ask a pharmacist before combining products, and do not use a skin gel and an anti-inflammatory pill at the same time unless your prescriber says to.
- Get help quickly if a joint suddenly becomes hot, red or very swollen, or if you have black stools or vomit blood.

(Arthritis Society Canada, n.d.-b; Haleon Canada ULC, 2026)

LIFESPAN CONSIDERATIONS

Arthritis in Older Adults

- **NSAIDs:** Older adults are more sensitive to NSAID side effects and tolerate stomach ulcers and bleeding less well; most reports of fatal stomach and bowel events with celecoxib involved older adults (Nora Pharma Inc., 2026). The OARSI guideline does not recommend oral NSAIDs for people with frailty or cardiovascular disease (Bannuru et al., 2019). Older age also raises the risk of kidney injury from NSAIDs (Nora Pharma Inc., 2026).
- **Falls:** Pain, stiffness, weak muscles and poor balance raise the risk of falling. The nurse checks footwear, walking aids, lighting and the route to the bathroom (section 8.4). Osteoporosis, which makes a fracture after a fall more likely, is covered in section 33.3.
- **Many medicines:** An older adult may take several prescription and over-the-counter products for pain. The nurse reviews them all for duplicates and interactions (section 8.5).
- **Living alone:** Stiff hands and painful knees can make cooking, bathing and opening pill bottles difficult. Occupational therapy, easy-open containers and home supports help people stay independent.
- **Mood:** Chronic pain and lost independence can lead to depression, which may look like withdrawal, poor appetite or poor sleep rather than sadness (section 8.3).

34.3 Rheumatoid Arthritis

What Happens in Rheumatoid Arthritis

Rheumatoid arthritis (RA) is a chronic autoimmune disease in which the immune system attacks the lining of the joints, causing inflammation, swelling, pain and stiffness (Arthritis Society Canada, n.d.-c; PHAC, 2020c). The inflamed synovium thickens and, if not controlled, wears away cartilage and bone, leaving joints damaged and deformed. There is no cure, but treatment can control the inflammation (Arthritis Society Canada, n.d.-c; Figure 34.4).

RA often starts in a few joints and spreads to others over weeks to months, although it sometimes progresses quickly. It typically affects the same joints on both sides of the body, especially the small joints of the hands, wrists and feet, but also the elbows,

shoulders, knees and ankles. Morning stiffness lasting 30 minutes or more, warmth over the joints, reduced movement and firm lumps under the skin (rheumatoid nodules), most often near the elbows, hands or feet, are typical. Early symptoms can be vague: feeling unwell or tired, aching muscles, a low-grade fever, weight loss and poor appetite (Arthritis Society Canada, n.d.-c). A **flare** is a period when symptoms suddenly return or worsen; flares usually settle within a few weeks (Arthritis Society Canada, n.d.-c).

Figure 34.4 Chronic joint changes of rheumatoid arthritis on both hands, including swelling and subluxation at the metacarpophalangeal joints and ulnar deviation of the fingers.

RA is a whole-body disease. Inflammation can also affect the eyes, lungs, heart, skin and nerves (Arthritis Society Canada, n.d.-c). People with diagnosed RA in Canada have a higher death rate than people without it (PHAC, 2020c). The nurse therefore pays attention to new shortness of breath, cough, chest pain or eye symptoms, and supports preventive care and screening tailored to the person's risk factors (Nikolic et al., 2026).

In 2016–2017, about 374,000 Canadians aged 16 and older had diagnosed RA, and about 23,000 were newly diagnosed. Prevalence was 1.7% among females and 0.8% among males, and rose with age (PHAC, 2020c). Known risk factors include family history and smoking (PHAC, 2020c). Smoking is the strongest known environmental risk factor, and gum disease is more common in people with RA (Arthritis Society Canada, n.d.-c). RA most often begins between ages 40 and 60 (Arthritis Society Canada, n.d.-c). In Alberta, RA affects about three times as many First Nations residents as non–First Nations residents (Barnabe et al., 2017; see the Canadian Context box in section 34.1).

Diagnosis and Treat-to-Target

Time matters in RA. The Canadian Rheumatology Association (CRA) states that all people with RA should be able to see a rheumatologist early, with fair (equitable) access to that care (Nikolic et al., 2026). Swelling of the joint lining that persists for 6 weeks or more on examination is the most reliable reason for an urgent referral to a rheumatologist, even before formal criteria are met (Jung & Barra, 2015). Arthritis Society Canada (n.d.-c) advises people to see a doctor if joint symptoms last more than 6 weeks; the family physician or nurse practitioner (NP) usually makes the referral.

No single test confirms RA. Diagnosis combines the history, joint examination, blood tests and sometimes X-rays or ultrasound (Arthritis Society Canada, n.d.-c). X-rays of the hands and feet may be normal early in the disease, while bone erosions typical of RA support the diagnosis (Jung & Barra, 2015). Blood tests are summarized in Table 34.2 and the Going Deeper box in section 34.1.

Treat-to-target means setting a clear goal for disease control, measuring disease activity at regular visits and changing treatment until the goal is reached. The CRA states that treatment should aim for remission or, when that is not possible, minimal disease activity, and should be tailored to the person through shared decision-making (Nikolic et al., 2026). The 2025 EULAR update recommends starting with methotrexate, ideally with short-term glucocorticoids (corticosteroids), and adding a biologic medicine if the response is not good enough after 3 to 6 months (Smolen et al., 2026). The CRA suggests short-term corticosteroids while disease-modifying drugs start to work, and recommends against routine long-term (more than 6 months) low-dose corticosteroids (Nikolic et al., 2026). When a person has been in remission or low disease activity for at least 6 months, gradually reducing medicines may be considered, but only through shared decisions and only when the person can reach rheumatology care quickly and restart treatment if the disease flares (Nikolic et al., 2026).

Nursing Care and Medicines

A **disease-modifying antirheumatic drug (DMARD)** slows or stops the immune process that damages joints, rather than only easing symptoms. NSAIDs relieve pain and swelling but do not change the course of RA (Arthritis Society Canada, n.d.-c).

Methotrexate is central to RA care. Arthritis Society Canada (n.d.-c) names it as the most common DMARD, and the 2025 EULAR update recommends it as the first treatment, ideally with short-term glucocorticoids (Smolen et al., 2026). The CRA living guideline update does not name a first drug in its published letter. For RA, methotrexate is taken **once a week**, on the same day each week, not daily. The Canadian monograph warns that taking the weekly dose every day by mistake has caused fatal toxicity (JAMP Pharma Corporation, 2024). Institute for Safe Medication Practices Canada (ISMP Canada) has received reports of serious harm and death from daily use, often when orders were written, transcribed or dispensed as daily or when patients misunderstood the schedule. Because most medicines are taken daily, a weekly schedule is easy to get wrong (Blinova et al., 2008). Safety strategies include:

- naming a specific day of the week on every order, label and medication administration record (avoiding Monday, which can be misread as "morning");
- taking extra care with the medication history whenever a person taking methotrexate is admitted, and checking frequency and indication before any dose;
- teaching every person who starts or changes methotrexate, with written information about the weekly schedule and a calendar to record doses and blood tests (Blinova et al., 2008).

Methotrexate is usually prescribed together with **folic acid**, which helps limit side effects (Arthritis Society Canada, n.d.-c). The monograph notes that folic or folinic acid may lessen some toxicities, such as stomach and bowel upset, mouth sores and hair loss (JAMP Pharma Corporation, 2024). The person takes folic acid exactly as ordered, on the days the prescriber specifies.

Monitoring is part of every methotrexate plan. The Canadian monograph calls for baseline blood, liver and kidney tests and a chest X-ray, then blood counts at least monthly and liver and kidney tests every 1 to 2 months in people with RA (JAMP Pharma Corporation, 2024); the rheumatologist sets each person's schedule. The monograph lists alcohol use with methotrexate as contraindicated, and the patient information tells people not to drink alcohol (JAMP Pharma Corporation, 2024).

Methotrexate lowers the body's defences. Mouth sores can be an early sign of toxicity. The person should report fever, sore throat or other signs of infection, diarrhea or vomiting, unusual bruising or bleeding, and a dry cough or shortness of breath, which can signal lung inflammation (JAMP Pharma Corporation, 2024). Whether to hold a dose during an infection or before surgery is decided by the prescriber; the nurse does not stop or restart methotrexate on their own. Live vaccines are generally not recommended during treatment (JAMP Pharma Corporation, 2024); adult immunization is taught in section 21.6.

Pregnancy needs planning. Methotrexate can cause fetal death and birth defects, and pregnancy should be avoided if either partner is taking it. Published advice on how long to wait after stopping before trying to conceive ranges from 3 months to one year (JAMP Pharma Corporation, 2024). The nurse encourages anyone who may want a pregnancy to talk with the rheumatologist well before stopping contraception.

Other conventional DMARDs, such as hydroxychloroquine, sulfasalazine and leflunomide, may be added, and biologic and targeted medicines are used when conventional DMARDs are not enough (Arthritis Society Canada, n.d.-c). These medicines, and the screening needed before starting them, are covered in section 34.6.

Nurses also teach ways to live well with RA. EULAR recommends that nurses offer education based on each person's needs, psychosocial support and help with self-management, within a team and through shared decisions (Bech et al., 2020). Therapy, education and medicines are all part of RA care (PHAC, 2020c). Key strategies include:

- **Joint protection:** keeping joints aligned, limiting high-stress tasks, pacing activities and using assistive devices such as jar openers (Arthritis Society Canada, n.d.-b).
- **Energy conservation:** planning the day, spreading tasks out and resting before becoming exhausted can help with fatigue.
- **Splints and therapy:** occupational therapists provide splints and adaptive equipment; physiotherapists build safe exercise programs (Arthritis Society Canada, n.d.-b; PHAC, 2020c).

- **Mental health:** People with arthritis are up to 2 to 3 times as likely as people without it to have a mood disorder such as depression (Arthritis Society Canada, n.d.-a). The nurse asks about mood, sleep and concentration and offers support.
- **Work:** Flexible hours, workplace changes and early discussion with an employer help people keep working (section 34.7).

Hospital admission is a risky time for people with RA. Applying the CJMM, the nurse recognizes cues such as a weekly medicine ordered daily, a fever in a person taking methotrexate, or one joint far more swollen than the others; analyzes them against the person's usual pattern; and acts and escalates with SBAR (section 6.2).

Table 34.2 Tests used in arthritis and what they show (Aringer et al., 2019; Arthritis Society Canada, n.d.-c; JAMP Pharma Corporation, 2024; Jung & Barra, 2015; PHAC, 2020a; Weston & Coakley, 2006)

Test	What it measures	Typical finding	Nursing point
C-reactive protein (CRP), mg/L	A protein the liver makes during inflammation	Often raised in active inflammatory arthritis; also raised by infection and injury	Not specific; compare with earlier results and the person's symptoms
Erythrocyte sedimentation rate (ESR), mm/h	How quickly red blood cells settle; rises with inflammation	Often raised in active inflammatory arthritis	Not specific; affected by many other conditions
Rheumatoid factor (RF)	An antibody often present in RA	May be positive in RA; also positive in some other conditions	A negative result does not rule out RA
Anti-CCP antibodies	Antibodies to cyclic citrullinated peptides	More specific for RA than RF	A negative result does not rule out RA
Antinuclear antibodies (ANA)	Antibodies against parts of the cell nucleus	A positive ANA is required to classify lupus under the 2019 EULAR/ACR criteria	See section 34.5
Serum urate, µmol/L	Uric acid in the blood	Used to diagnose and monitor gout	See section 34.4
Complete blood count, liver tests, creatinine	Blood cells, liver injury and kidney function	Used at baseline and regularly during methotrexate treatment	Report low white cells or platelets, rising liver enzymes or rising creatinine
Joint fluid analysis	Infection and crystals in fluid drawn from a joint	Uric acid crystals in gout; calcium pyrophosphate crystals in pseudogout	When infection is possible, fluid is drawn before antibiotics start
Hand and foot X-rays	Bone and joint changes	May be normal early in RA; erosions support the diagnosis	Prepare the person; explain why images are repeated

PRACTICE STORY

Once a Week

Names and details are fictional; this is a composite story.

Nurse: Kwabena Asante, RN. Years in practice: 7. Setting: medical unit, Ontario.

Mr. Henri Gagnon was 81 and came up from emergency with worsening heart failure. His daughter, Sylvie, had brought a bag of his medicines and a blister pack from his pharmacy. During medication reconciliation, I compared the admission orders with what he actually took at home.

One line stopped me: methotrexate, by mouth, once daily. Mr. Gagnon had rheumatoid arthritis, and in the blister pack his methotrexate sat in one slot only, on Saturday. Sylvie confirmed it: "Dad takes those little pills on Saturdays. The folic acid is separate." The daily order had come from a list that was transcribed in emergency.

His next dose on the electronic record was due that evening. I did not give it. I flagged the order, documented why, and called the hospitalist and our unit pharmacist. Within the hour, the order was corrected to once weekly on Saturday, with a note from the prescriber about whether to give this week's dose while he was acutely ill. The pharmacist and I also checked that no dose had been given in emergency. None had.

I filed a safety report. It was not about blame; a daily order for a weekly medicine had passed through two steps, and the unit needed to know.

> Before discharge, I sat with Mr. Gagnon and Sylvie. We wrote "METHOTREXATE: SATURDAY ONLY" on a calendar and talked about what to watch for: mouth sores, fever, a sore throat, a new dry cough, bruising. Sylvie said she had never known why the pills were in only one slot. "Now I'll check every time he goes anywhere," she said.
>
> I think about how easy it would have been to click "given."
>
> Reflect: Which parts of Kwabena's actions could an RPN on the same unit carry out within their own scope, and at what point should the RPN involve the RN or the prescriber? What system changes could stop a daily methotrexate order from reaching the medication record again?

34.4 Gout

The Public Health Agency of Canada (PHAC) describes gout as the most common form of inflammatory arthritis (PHAC, 2020a). Taken over the long term, the right medicines can prevent flares and joint damage. Nurses meet people with gout in clinics and emergency departments, and on medical and surgical units, where a sudden hot joint can appear during a stay for something else.

What Happens in Gout

Uric acid is a waste product the body makes when it breaks down purines, substances found in body cells and in many foods. The kidneys remove most of it. When the level of urate in the blood stays high for a long time (hyperuricemia), crystals of monosodium urate can form and settle in and around joints and in other tissues. **Gout** is the disease caused by this crystal deposit (Neogi et al., 2015). Many people with a high urate level never develop gout, and the 2020 ACR gout guideline (a US guideline) advises against treating a high level that causes no symptoms (FitzGerald et al., 2020).

A **gout flare** happens when the immune system reacts to the crystals. Over a few hours, a joint becomes swollen, warm and very painful. The joint at the base of the big toe (the first metatarsophalangeal joint), the ankle and the midfoot are common sites (Neogi et al., 2015). Redness is easy to see on lighter skin but may be hard to see on darker skin, so the nurse feels for warmth, looks for swelling, compares the joint with the other side and asks the person how it feels (section 34.1; Chapter 35). Over time, flares may come more often and last longer, and repeated flares can damage the joint permanently (PHAC, 2020a).

Over years, crystals can build up as a **tophus** (plural tophi), a firm, chalk-like lump under the skin, often on the ear, the elbow or the pads of the fingers (Neogi et al., 2015). Urate can also form kidney stones (Chapter 28) (Figure 34.5).

Data from the Canadian Chronic Disease Surveillance System show that in 2016–2017, about 681,000 people in Canada aged 20 and older (2.4%) had diagnosed gout or another crystal arthritis, and about 54,000 were newly diagnosed that year. Prevalence was 3.7% among males and 1.1% among females and rose with age, and age-standardized prevalence increased between 2007–2008 and 2016–2017 (PHAC, 2020a). PHAC names obesity, diet, alcohol and certain medicines as contributing factors. The US guideline also addresses chronic kidney disease, thiazide diuretics such as hydrochlorothiazide, and drinks sweetened with high-fructose corn syrup (FitzGerald et al., 2020). Because kidney disease and medicines also play a part, the nurse avoids language that treats gout as the result of poor choices.

Finding urate crystals in joint fluid or in a tophus confirms gout (Neogi et al., 2015; see the Going Deeper box in section 34.1). A hot, swollen joint can also be septic arthritis, which is an emergency, so a new hot joint in a person with fever or who looks unwell is reported promptly (Chapter 4).

Care During a Flare and Between Flares

During a flare, the goal is to relieve pain and inflammation quickly. The nurse helps the person find a comfortable position for the joint and applies ice; the US guideline supports topical ice as an add-on to medicine (FitzGerald et al., 2020). The guideline names three first-line choices: colchicine, an NSAID, or a corticosteroid given by mouth, into the joint or into a muscle. When colchicine is used, it prefers low-dose over high-dose colchicine, and it suggests a corticosteroid for people who cannot take anything by mouth (FitzGerald et al., 2020). Colchicine works best when it is started early in a flare. Its Canadian product monograph warns that stomach and bowel symptoms, such as nausea, vomiting and diarrhea, are the first signs of toxicity, that drugs such as clarithromycin can raise colchicine to dangerous levels, and that older adults and people with kidney or liver disease need extra care (Pharmascience, 2016). NSAID risks are covered in section 34.2, and corticosteroid effects in section 34.6.

Between flares, the aim is to dissolve the crystals by lowering the urate level. **Urate-lowering therapy** (ULT) is a long-term medicine that lowers the amount of urate in the body. The US guideline strongly recommends ULT for people with one or more tophi, joint damage on imaging or two or more flares a year (FitzGerald et al., 2020). Allopurinol is the preferred first medicine, including for people with chronic kidney disease of stage 3 or higher (Chapter 27). Febuxostat is an alternative, but the guideline suggests switching to another medicine for people with cardiovascular disease. ULT starts at a low dose and is raised step by step, guided by repeated blood tests, until the serum urate stays below 360 µmol/L (6 mg/dL in the US guideline; FitzGerald et al., 2020; conversion from Neogi et al., 2015). The ACR guideline (US) strongly recommends this treat-to-target approach and keeping the urate below the target once it is reached, and it suggests continuing ULT indefinitely. It also supports dose adjustment by nurses and other non-physician providers who follow a protocol and provide education and shared decision-making (FitzGerald et al., 2020).

Figure 34.5 Tophaceous gout at the first metatarsophalangeal joint with hallux valgus in an older adult; cropped to the foot for patient privacy. (credit: modification of "Tophaceous gout of Lt MTP joint, elder female patient, Thailand" by Chainwit./Wikimedia Commons, CC BY 4.0)

Flares can occur in the first months of ULT. For this reason, the guideline strongly recommends a preventive anti-inflammatory medicine (colchicine, an NSAID or prednisone) for 3 to 6 months after ULT begins, and it suggests that ULT can be started during a flare (FitzGerald et al., 2020). The nurse explains this in advance, so that the person does not decide that the new medicine has failed and stop it.

The US guideline suggests testing for HLA-B*5801, a gene variant linked to severe allergic reactions to allopurinol, before allopurinol is started in patients of Southeast Asian descent (for example, Han Chinese, Korean or Thai) and in African American patients, and not routinely in others (FitzGerald et al., 2020). Every person starting allopurinol is taught to report any new rash at once (Chapter 21).

The guideline also suggests limiting alcohol, purine-rich foods and high-fructose corn syrup, and losing weight for people who are overweight; it does not support vitamin C supplements (FitzGerald et al., 2020). The nurse presents these steps as support for the medicines, not as a test of willpower. The prescriber may change hydrochlorothiazide to another blood pressure medicine, and the guideline advises against stopping low-dose acetylsalicylic acid (ASA) that a person takes for a heart or stroke condition (FitzGerald et al., 2020).

In hospital, a person with gout can flare during a stay for another problem, and certain medicines, such as thiazide diuretics, can contribute (PHAC, 2020a; FitzGerald et al., 2020). The nurse continues ULT unless the prescriber holds it and reports a new hot joint promptly, especially with fever, because septic arthritis must be ruled out (section 34.1; Chapter 4). Older adults face higher risks from colchicine and NSAIDs, so the nurse watches kidney function and new medicines closely (Chapter 8).

PATIENT EDUCATION

Preventing Gout Flares

- **Take your urate-lowering medicine every day,** even when your joints feel fine. It works slowly and prevents flares only when it is taken long term.
- **Go for your blood tests.** Your dose is adjusted until your urate level reaches the target your prescriber has set.

- **Expect some flares at first.** Flares in the first months do not mean the medicine is failing. Take the preventive medicine for as long as it is prescribed.
- **Have a flare plan.** Know which medicine to start and start it early. Rest the joint, raise it and use ice.
- **If you take colchicine,** stop it and call your prescriber or pharmacist if you get diarrhea or vomiting. Tell every prescriber and pharmacist that you take it before you start a new medicine, such as an antibiotic. Store it out of reach of children, because an overdose can kill a child.
- **If you take allopurinol,** call your prescriber at once if you get a rash.
- **Limit alcohol, purine-rich foods and sweet drinks** made with high-fructose corn syrup. A dietitian can help you plan meals you enjoy.
- **Get care the same day** for a hot, swollen joint with fever or chills, or if you feel unwell.

34.5 Lupus and Other Connective Tissue Disorders

Connective tissue disorders are autoimmune diseases that can affect the skin, joints, blood vessels and internal organs. This section covers systemic lupus erythematosus in depth and four related conditions in brief (Table 34.3). Autoimmunity is reviewed in Chapter 21.

Systemic Lupus Erythematosus

Systemic lupus erythematosus (SLE, often called lupus) is a chronic autoimmune disease in which the immune system makes antibodies against parts of the body's own cells, causing inflammation in many organs. The 2019 European League Against Rheumatism/American College of Rheumatology (EULAR/ACR) classification criteria require a positive ANA test as the starting point and then score findings across clinical and immune domains. The criteria are designed to classify people for research, not to diagnose an individual (Aringer et al., 2019).

SLE affects women far more often than men. In an Alberta study of health records from 1994 to 2007, SLE prevalence was 27.3 per 10,000 females and 3.2 per 10,000 males. Among women older than 45, the combined prevalence of SLE or systemic sclerosis was twice as high for First Nations women as for non–First Nations women. The authors noted that this could reflect a true difference or systematic differences in health care delivery, and they called for adequate access to specialists and treatment (Barnabe et al., 2012). The study used provincial administrative data; the OCAP® principles described in section 34.1 apply to how such data are used (Chapter 2). In a Canadian cohort of 1,416 adults with SLE, kidney involvement was more common among Asian and Afro-Caribbean participants. Low income, not ethnicity, predicted organ damage over time. Indigenous participants had the lowest incomes, and the authors noted that lower rates of specialist contact have been documented for Indigenous people (Peschken et al., 2009). These findings point to structural causes, such as poverty and distance from care, rather than to race as biology (Chapter 2).

SLE varies widely from person to person. The clinical findings that the classification criteria score include the following (Aringer et al., 2019):

- fever;
- joint involvement;
- lupus skin rashes and mouth ulcers; (Figure 34.6)
- inflammation of the lining around the lungs or heart (serositis), or fluid around them;
- kidney inflammation (lupus nephritis);
- a low white blood cell count;
- delirium, psychosis or seizures.

People with SLE also often report fatigue, pain, low mood and problems with thinking, which may not improve with immunosuppressive medicines (Fanouriakis et al., 2024). Lupus is characteristically sensitive to sunlight, a feature called **photosensitivity** (Fanouriakis et al., 2024). Redness can be harder to see on darker skin, so the nurse compares any rash with the person's usual skin colour, asks what has changed and checks the scalp, ears and mouth (Chapter 35).

Lupus nephritis, inflammation of the kidneys caused by SLE, is one of its most serious forms. The team tracks protein in the urine, kidney function and blood pressure, which EULAR advises keeping below 130/80 mm Hg (Fanouriakis et al., 2024). New swelling, rising blood pressure and falling urine output are reported promptly (Chapter 27). Treatment combines immunosuppressive medicines and continues for at least 3 years after the kidneys respond (Fanouriakis et al., 2024).

In SLE, a flare (section 34.3) is a period of increased disease activity. Because of the disease's photosensitivity, EULAR advises people with lupus to avoid sun exposure in particular (Fanouriakis et al., 2024). Fever in a person with SLE may be a flare or an infection, and the two can look alike, especially in someone taking corticosteroids or other immunosuppressants. The nurse reports fever promptly so that the team can look for infection before more immunosuppression is given (Chapter 4).



Figure 34.6 Systemic lupus erythematosus: (a) common organ and tissue involvement across the body; (b) a butterfly (malar) rash across the cheeks and nasal bridge, sparing the creases beside the nose. (credit: "OSC Microbio 19 02 Lupus" by CNX OpenStax/Wikimedia Commons, CC BY 4.0)

EULAR's treatment goal is remission or, when that is not possible, low disease activity. Disease activity is checked at every visit, and care is multidisciplinary, with education and shared decision-making (Fanouriakis et al., 2024). Medicines include the following:

- **Hydroxychloroquine** is recommended for everyone with SLE unless it is unsafe for them, and EULAR advises against stopping it in remission (Fanouriakis et al., 2024). Because it can damage the retina, a current Canadian monograph calls for an examination of both eyes before long-term treatment and at least once a year after that. It also warns of severe hypoglycemia, which can cause loss of consciousness, and that children are especially sensitive to this drug group, with deaths reported after accidental swallowing (Auro Pharma, 2026). EULAR advises closer eye follow-up for people at higher risk of retinal damage, such as those with kidney disease (Fanouriakis et al., 2024).
- **Corticosteroids** control active disease. EULAR advises reducing them to the lowest maintenance dose and stopping them when possible (Fanouriakis et al., 2024).
- **Methotrexate, other immunosuppressants and biologics** such as belimumab are added when hydroxychloroquine is not enough or corticosteroids cannot be reduced (Fanouriakis et al., 2024). The belimumab monograph warns of serious infections, hypersensitivity reactions, depression and suicidal thoughts (GlaxoSmithKline, 2025).
- **Long-term anticoagulation** is used for people whose SLE is complicated by blood clots from antiphospholipid antibodies (Fanouriakis et al., 2024; Chapter 19).

EULAR also calls for vaccines (including influenza, pneumococcal, shingles, human papillomavirus and COVID-19), bone health care, kidney protection, cardiovascular risk management and cancer screening, along with sun protection, not smoking, a healthy diet and regular exercise (Fanouriakis et al., 2024). Pregnancy planning is covered in separate EULAR recommendations. The nurse encourages people who could become pregnant to plan with their rheumatology team, because some medicines need to be reviewed before conception.

Other Connective Tissue Disorders and Vasculitis

Systemic sclerosis (SSc, also called scleroderma) is a rare autoimmune disease that damages small blood vessels and causes fibrosis, a thickening and scarring of the skin and internal organs. Among rheumatic diseases, it has the highest rates of illness and death (Del Galdo et al., 2025). **Raynaud phenomenon** is one of its blood vessel features: in cold or under stress, small arteries in the fingers or toes spasm, and the skin changes colour and may feel numb or painful until blood flow returns. Colour changes may be harder to see on darker skin, so the nurse asks about numbness, pain and colour change compared with the person's usual skin. EULAR recommends a calcium channel blocker as first-line treatment. SSc can also cause finger ulcers, lung scarring, high pressure in the lung arteries and reflux. **Scleroderma renal crisis** is a serious kidney complication. It is treated at once with an ACE inhibitor, and

EULAR recommends regular blood pressure checks for people with SSc who take corticosteroids so that it is found early (Del Galdo et al., 2025; Figure 34.7).

Figure 34.7 Well-demarcated digital pallor on exposure to cold in Raynaud phenomenon.

Sjögren disease (also called Sjögren syndrome) is a systemic autoimmune disease marked by dry eyes and a dry mouth, with fatigue and pain. It can affect other organs, and lymphoma develops in about 2% to 5% of people (Ramos-Casals et al., 2020). Care protects the teeth and eyes: sugar-free gum or lozenges, saliva substitutes, fluoride gel, regular dental care, artificial tears in the day and ointment at night (Ramos-Casals et al., 2020).

Vasculitis is inflammation of blood vessel walls. **Polymyalgia rheumatica** (PMR) affects adults aged 50 and older. It causes aching and stiffness in both shoulders and often the hips, morning stiffness that lasts more than 45 minutes and a raised CRP or ESR (section 34.1; Dasgupta et al., 2012). PMR is treated with corticosteroids rather than NSAIDs, for the shortest effective time, with a taper planned for each person, and an exercise program helps keep muscle strength and prevent falls (Dejaco et al., 2015). The 2025 EULAR recommendations allow methotrexate or an interleukin-6 (IL-6) blocker such as tocilizumab to be added for selected people (Mukhtyar et al., 2026).

Giant cell arteritis (GCA) is a vasculitis of large arteries, including arteries of the head, in adults older than 50. Typical presentations include headache, pain in the jaw when chewing (jaw claudication), visual symptoms and PMR; the scalp may also be very tender, as in a recent Canadian case report (Ghebrial et al., 2026). GCA is a rheumatologic emergency because it can cause permanent loss of vision and stroke (Ghebrial et al., 2026). The international 2025 EULAR recommendations state that anyone suspected of having GCA needs urgent specialist referral, that people with cranial symptoms (such as headache, jaw pain or visual changes) are at high risk of permanent vision loss and should be referred immediately, and that when suspicion is strong, corticosteroid treatment should start without delay while confirmatory tests are pending. Fast-track clinics have reduced permanent vision loss (Mukhtyar et al., 2026). A CRP test and, where available, an urgent ultrasound of the temporal arteries support the diagnosis, and a temporal artery biopsy remains the reference test (Ghebrial et al., 2026). An IL-6 blocker such as tocilizumab may be added for some people, especially those whose disease relapses or who are at high risk of corticosteroid side effects (Mukhtyar et al., 2026). Any nurse who hears these symptoms escalates the same day.

Table 34.3 Connective tissue disorders and vasculitis compared (Aringer et al., 2019; Dasgupta et al., 2012; Del Galdo et al., 2025; Fanouriakis et al., 2024; Ghebrial et al., 2026; Mukhtyar et al., 2026; Ramos-Casals et al., 2020; original wording)

Disorder	Main features	Danger signs to report	Nursing focus
Systemic lupus erythematosus	Fatigue, fever, joint pain, rashes, mouth ulcers, serositis, kidney and blood changes	Fever; chest pain with breathing; new swelling or less urine; rising blood pressure; confusion or seizure	Hydroxychloroquine every day and yearly eye checks; sun protection; urine, creatinine and blood pressure; infection watch
Systemic sclerosis	Thick, tight skin; Raynaud phenomenon; finger ulcers; reflux; lung and kidney involvement	A finger that stays pale or dark or has an ulcer; a rise in blood pressure or less urine; new shortness of breath	Warmth and skin care; blood pressure checks, especially with corticosteroids; reflux and swallowing care

Disorder	Main features	Danger signs to report	Nursing focus
Sjögren disease	Dry eyes, dry mouth, fatigue, pain	Worsening eye or mouth symptoms; new symptoms in other organs	Mouth and dental care; artificial tears; referral to dentist and eye specialist as needed
Polymyalgia rheumatica	Age 50 or older; aching and stiffness of both shoulders and hips; morning stiffness; raised CRP or ESR	New headache, scalp tenderness, jaw pain on chewing or any vision change (possible GCA)	Corticosteroid teaching; exercise and fall prevention; teaching the warning signs of GCA
Giant cell arteritis	New headache, scalp tenderness, jaw pain on chewing, visual symptoms, PMR symptoms	Any vision change, even brief; symptoms of stroke	Same-day escalation; corticosteroids without delay as ordered; safety if vision is affected

CLINICAL JUDGMENT

A Headache and Jaw Pain

Names and details are fictional; this is a composite story.

Hélène Gagnon, 76, has had polymyalgia rheumatica for 8 months and takes prednisone. On Tuesday morning she calls the rheumatology clinic's nurse line. For 4 days she has had a new headache on the right side, her scalp hurts when she brushes her hair, and her jaw aches when she chews, so she stops partway through meals. This morning the vision in her right eye "went blurry for a few minutes." Her shoulder stiffness is no worse.

- **Recognize cues:** A new headache, scalp tenderness, jaw pain with chewing and a brief change in vision in a 76-year-old woman with PMR.
- **Analyze cues:** Together, these findings fit giant cell arteritis, which can occur in people with PMR. Brief blurred vision is a warning that permanent vision loss may follow.
- **Prioritize hypotheses:** GCA threatening her sight comes ahead of a tension headache, a dental problem or a side effect of prednisone.
- **Generate solutions:** She needs specialist assessment and treatment today, through the clinic's urgent pathway or, if that cannot happen within hours, the emergency department. She should not drive.
- **Take action:** The nurse tells Mrs. Gagnon not to wait and stays on the line while they confirm that her son can bring her in. The nurse reaches the rheumatologist at once and gives an SBAR report (Chapter 6). The rheumatologist sees her that afternoon, orders blood tests and starts high-dose corticosteroids. The nurse documents the call.
- **Evaluate outcomes:** The next day, Mrs. Gagnon's headache is easing and her vision has not changed again. Her temporal artery ultrasound is booked. The nurse teaches her to go to the emergency department at once for any new vision change and not to stop or reduce prednisone on her own.

34.6 Medicines for Inflammatory Arthritis

A DMARD (section 34.3) slows the disease process and protects joints and organs, rather than only easing symptoms. DMARDs fall into three groups: conventional synthetic DMARDs, biologics and targeted synthetic DMARDs (JAK inhibitors). Corticosteroids are also used, mainly for short periods. Gout medicines are described in section 34.4. Table 34.4 summarizes the main medicines in this chapter.

Conventional DMARDs

Methotrexate is the anchor drug for rheumatoid arthritis and is taken once a week (section 34.3). Hydroxychloroquine, sulfasalazine and leflunomide are other conventional DMARDs; hydroxychloroquine's eye and blood sugar warnings are described in section 34.5.

Biologics and Biosimilars

A **biologic** is a medicine made in living cells, usually a protein such as an antibody, that blocks one part of the immune response. Biologics are given by injection under the skin or by intravenous infusion. In arthritis and connective tissue disease, they include the

tumour necrosis factor (TNF) inhibitors adalimumab, etanercept, infliximab and golimumab; IL-6 blockers such as tocilizumab; rituximab, which removes B cells; and belimumab for SLE (section 34.5).

A **biosimilar** is a highly similar and generally less expensive version of an original (originator) biologic. Health Canada approves a biosimilar only after finding that it does not differ in any meaningful way from the originator in safety or effectiveness, and studies show little or no difference when people switch (Government of Ontario, 2025). Under Ontario's policy, people covered by the Ontario Drug Benefit program who took originator adalimumab, etanercept, infliximab or rituximab had to switch to a biosimilar during 2023 to keep their coverage, with some exemptions, and further biologics have since been added to the policy (Government of Ontario, 2025). Policies differ by province and territory. The nurse reassures the person, teaches the new injection device and updates the medication list with the new brand name.

JAK Inhibitors

A **JAK inhibitor** is a tablet that blocks Janus kinase (JAK) enzymes inside immune cells, interrupting signals from many inflammatory messengers. Tofacitinib and upadacitinib are examples. In November 2022, Health Canada announced that the Canadian labelling of all JAK inhibitors was being updated to include "risks of serious heart-related problems, fatal blood clots and cancer." Health Canada advises particular caution in older adults; in current or past smokers; in people who have other risk factors for heart disease or cancer, or who have cancer; and in people with a higher risk of blood clots. It tells people taking a JAK inhibitor to stop it and contact their health care professional immediately if they develop symptoms of a heart problem, such as new or worsening chest pain, shortness of breath, irregular heartbeats or swelling of the legs. People with symptoms of a blood clot, such as swelling, pain or tenderness in an arm or leg, or sudden unexplained chest pain or shortness of breath, should stop the medicine and seek immediate medical help (Health Canada, 2022).

Screening Before Starting

Before a biologic or JAK inhibitor begins, the team checks for infections that the medicine could reactivate:

- **Tuberculosis (TB):** The Canadian Tuberculosis Standards list people starting TNF inhibitors, other biologics and DMARDs, and higher-dose corticosteroids among those to test for TB infection, using a tuberculin skin test (TST) or an interferon-gamma release assay (IGRA) (Campbell et al., 2022). Anyone with a positive result is referred for a medical evaluation to exclude TB disease (Campbell et al., 2022), and TB infection is treated before therapy starts (AbbVie, 2022).
- **Hepatitis B:** People at risk are checked for past hepatitis B infection (AbbVie, 2022).
- **Vaccines:** The Canadian Immunization Guide advises immunizing before planned immunosuppression when possible, so vaccines are given before starting, as the guide and the prescriber direct. Influenza, pneumococcal and recombinant shingles vaccines are recommended for immunocompromised adults (PHAC, 2026). Live vaccines are avoided during treatment (AbbVie, 2022; GlaxoSmithKline, 2025).

Infection Risk and Injections at Home

These medicines lower defences against infection. The adalimumab monograph says that treatment should not start during an active infection and should stop if a serious infection develops (AbbVie, 2022). The nurse teaches the person to call the prescriber before the next dose if they have a fever, chills, a cough, burning on urination or a red, hot, painful area of skin, and to hold a dose only as the prescriber directs. Many people learn to inject at home. The nurse teaches the technique and site rotation, how to store the medicine as the label directs and how to use a puncture-resistant sharps container. Belimumab's first self-injection is supervised by a health care professional (GlaxoSmithKline, 2025).

Corticosteroids

Corticosteroids act quickly and are used for flares of gout, RA and SLE and as the main treatment for PMR and GCA. A joint guideline lists weight gain, high blood glucose, high blood pressure and bone loss among the effects to discuss when they start (Beuschlein et al., 2024). Long-term use also raises infection risk (see Screening Before Starting) and contributes to osteoporosis (Chapter 33). Taken for more than a few weeks, corticosteroids, including those injected into joints, can suppress the body's own cortisol production. A person on long-term therapy therefore never stops suddenly. The dose is tapered as ordered, and extra doses

may be needed during illness or surgery to prevent adrenal crisis (Beuschlein et al., 2024; Chapter 23). The general rule is the lowest dose for the shortest time (Dejaco et al., 2015; Fanouriakis et al., 2024).

In Hospital

At medication reconciliation, the nurse asks about injections and infusions taken weekly, every few weeks or monthly, and the date of the last dose, and does not rely only on a list of daily medicines. Methotrexate's weekly schedule needs the same care (section 34.3). DMARDs, biologics and JAK inhibitors are held or continued only as the prescriber directs, including around surgery (Chapter 7). Corticosteroids are not stopped, and the prescriber orders intravenous or intramuscular doses when the person cannot take them by mouth, is vomiting or is having surgery (Beuschlein et al., 2024).

Cost, Coverage and Access

Coverage shapes who can get these medicines. People may rely on provincial or territorial drug plans, private insurance or both. For eligible First Nations and Inuit, the Non-Insured Health Benefits (NIHB) program covers drugs on its list: open benefits, limited-use benefits that meet set criteria and, in special circumstances, exception drugs. NIHB covers benefits that are not available under other federal, provincial, territorial or private plans, and when the pharmacy bills NIHB directly, the person pays no deductible or co-payment (Indigenous Services Canada, n.d.). The nurse helps people with coverage forms and links them with the pharmacist and the prescriber's office, so that cost does not stop treatment.

Table 34.4 Medicines for arthritis and connective tissue disorders (Canadian product monographs; Health Canada, 2022; Government of Ontario, 2025; FitzGerald et al., 2020; Fanouriakis et al., 2024; original wording)

Drug or class	Canadian examples	Used for	Nursing points
Colchicine	colchicine	Gout flares; prevention of flares when urate-lowering therapy starts	Diarrhea or vomiting are early signs of toxicity; check for interacting drugs such as clarithromycin; extra care in older adults and kidney or liver disease; keep away from children
Urate-lowering therapy	allopurinol, febuxostat	Long-term gout control to a serum urate target	Taken every day for life; dose raised with blood tests; report any rash at once (allopurinol); expect early flares
Antimalarial DMARD	hydroxychloroquine	SLE (nearly everyone); RA	Eye examination before long-term use and at least yearly; can cause severe hypoglycemia; keep away from children
Conventional DMARDs	methotrexate, sulfasalazine, leflunomide	RA and other inflammatory arthritis; methotrexate also in SLE and PMR	Methotrexate once a week only; blood tests as ordered (section 34.3)
TNF inhibitors (biologics)	adalimumab, etanercept, infliximab, golimumab, and their biosimilars	RA and other inflammatory arthritis	TB and hepatitis B screening first; no live vaccines; report fever or infection before the next dose
Other biologics	rituximab, belimumab; tocilizumab (an IL-6 blocker)	RA (rituximab, tocilizumab); GCA (tocilizumab); SLE and lupus nephritis (belimumab)	Infusion or injection reactions; infection watch; belimumab: watch mood and report depression or suicidal thoughts
JAK inhibitors	tofacitinib, upadacitinib	RA and other inflammatory arthritis	Health Canada warnings: heart problems, blood clots, cancer; stop and seek care for chest pain, breathlessness or a swollen, painful limb
Corticosteroids	prednisone; corticosteroid joint injections	Flares; PMR; GCA; SLE	Lowest dose for the shortest time; never stop suddenly after long-term use; check blood glucose and blood pressure; bone protection

GOING DEEPER

Biologics, JAK Inhibitors and Screening Before Starting

Required for RN students; optional for PN students.

Biologics are large proteins that act outside cells. TNF inhibitors bind tumour necrosis factor, a messenger that drives joint inflammation; IL-6 blockers such as tocilizumab block the receptor for interleukin-6; rituximab binds a marker on B cells and removes them; belimumab blocks a factor that helps B cells survive. JAK inhibitors are small molecules that act inside the cell, where JAK enzymes relay signals from many cytokine receptors, so one tablet dampens several pathways at once.

Because both groups weaken defences against intracellular infections, screening is part of the plan. The Canadian Tuberculosis Standards place people receiving immunosuppressing drugs, such as TNF inhibitors or corticosteroids, in a high-risk group for progression from TB infection to TB disease; low-dose corticosteroids do not appear to raise the risk significantly. A TST induration of 5 mm or more counts as positive in people about to start biologics or other immunosuppressive therapy. Both the TST and the IGRA are less sensitive in people whose immune systems are already suppressed, so a negative result does not fully exclude infection. A positive result leads to a medical evaluation, and preventive treatment starts once TB disease has been excluded (Campbell et al., 2022).

For JAK inhibitors, the RN checks the person's history for smoking, heart disease, clots and cancer before the first dose and reports these to the prescriber, since Health Canada advises extra caution in these groups (Health Canada, 2022).

34.7 Living Well With Chronic Arthritis

Arthritis Society Canada reports that arthritis is one of the main causes of disability and work limitation in this country. Drawing on Canadian Community Health Survey data, it reports that pain limits the activities of more than 40% of people with arthritis, that roughly 4 out of 5 also live with another chronic health condition, and that working-age adults with arthritis report not taking part in the workforce at twice the rate of their peers. Depending on the age group, people with arthritis are as much as two to three times more likely than others to have depression or another mood disorder (Arthritis Society Canada, n.d.-a). Living well with arthritis therefore means caring for the whole person, not only the joints.

Pain, Fatigue, Sleep and Mood

Chronic pain and fatigue are often the problems people with arthritis most want help with. The nurse assesses both at each contact, using the approaches in Chapter 5, and asks how they affect sleep, work and daily life. Poor sleep can worsen pain and fatigue, so the nurse asks about sleep and teaches regular routines. Physical activity helps across these conditions: exercise is a first step in osteoarthritis (section 34.2), it is part of EULAR's advice for lupus (Fanouriakis et al., 2024), and it helps people with PMR keep muscle strength and avoid falls (Dejaco et al., 2015). Activity is paced: the person plans rest breaks, spreads tasks across the day and increases activity gradually.

Depression and anxiety are common and often missed. EULAR recommends that nurses address psychosocial issues to reduce symptoms of anxiety and depression (Bech et al., 2020). The nurse asks about mood using a screening tool the setting uses, listens for hopelessness, and refers the person for support. Some medicines, such as belimumab, carry warnings about depression and suicidal thoughts (GlaxoSmithKline, 2025). A person who describes thoughts of suicide is not left alone, and the nurse escalates at once.

Work, Income and Self-Management

Arthritis often begins in working years. People may need workplace accommodations, such as adjusted hours, modified tasks or equipment, and they may need help applying for benefits when they cannot work. The nurse asks about work early and links the person with an occupational therapist or a social worker when needed.

Self-management means the day-to-day skills a person uses to live with a chronic condition, including taking medicines, pacing activity, solving problems and knowing when to seek help. EULAR recommends that nurses support self-management skills to increase self-efficacy, a person's confidence that they can manage their condition (Bech et al., 2020). The nurse sets goals with the person, not for them, and builds on what the person already does well.

A written flare plan is one practical tool. Made with the rheumatology team, it lists the early signs of a flare, which medicines to start or continue, comfort measures such as rest, heat or ice, and whom to call and when. Joint protection and energy conservation (section 34.3) help the person keep up valued activities during a flare. Some people track pain, fatigue and stiffness in a diary or an

app and bring it to visits, which helps the team adjust treatment. The nurse checks that the person can read and use written material, offers it in the person's preferred language, including French, and includes family members when the person wishes.

The Team and Nurse-Led Care

Care for inflammatory arthritis and connective tissue disease is multidisciplinary (Fanouriakis et al., 2024; Ramos-Casals et al., 2020). The rheumatologist leads diagnosis and treatment; the physiotherapist plans exercise; the occupational therapist teaches joint protection and suggests aids; the pharmacist reviews medicines and interactions. The person's primary care provider and community nurses complete the team.

EULAR's recommendations on the nurse's role describe nurse-delivered education matched to the person's needs, nurse consultations, timely access to a nurse by telephone or virtual care, nurse participation in disease management and comorbidity screening, and extended roles for nurses with specialized training, according to national regulations (Bech et al., 2020). The US gout guideline similarly supports nurse-led titration of ULT under a protocol (FitzGerald et al., 2020).

Distance, Access and Cultural Safety

People in rural, remote and northern communities may need to travel long distances for specialist visits, infusions and eye examinations. EULAR recommends timely access to a nurse, including by telehealth (Bech et al., 2020), and telephone and virtual follow-up can reduce some travel. In SLE, documented lower specialist contact among Indigenous people and the link between low income and organ damage suggest that income and access shape outcomes (Peschken et al., 2009). Culturally safe care (Chapter 2) means that the nurse asks what matters to the person, respects their knowledge of their own body, welcomes family and community supports, including traditional healing when the person wants it, and helps them navigate coverage such as NIHB (section 34.6). For older adults, the nurse also watches for falls, isolation and the medicine burden of several conditions at once (Chapter 8).

SCOPE IN PRACTICE

Arthritis Care and Who Does What

Every nurse, RN or registered practical nurse (RPN), assesses joints, pain, function and mood, teaches about medicines and self-management, and monitors for infection and side effects. In Ontario, "administering a substance by injection" is a controlled act authorized to both RNs and RPNs when there is an order, so either may give methotrexate or a biologic injection and teach self-injection (College of Nurses of Ontario [CNO], 2025). Using CNO's Scope of Practice standard, the nurse needs the **authority** (the controlled act is within the nurse's legislated scope, and there is an order), the **competence** (the knowledge, skill and judgment for the specific product and device) and a **context** whose policies and resources support the activity. An employer may, for example, limit intravenous biologic infusions to nurses with infusion education in a clinic that is equipped to manage reactions; an employer may narrow, but never widen, a nurse's scope.

Injections into joints are usually done by physicians or nurse practitioners (NPs), not by nurses in most settings; employer policy applies. Recognizing danger is everyone's job. A nurse who notices possible GCA, a hot joint with fever, a severe infection in a person on a biologic, or chest pain or leg swelling in a person on a JAK inhibitor acts at once and escalates. An RPN consults the RN or the prescriber as the person's needs change. Employer policy and province or territory matter, and CNO's revised Scope of Practice and Medication standards take effect March 1, 2027 (CNO, 2026).

Chapter 34 Summary

34.1 Joints, Inflammation and Arthritis in Canada

- Synovial joints rely on smooth cartilage and a synovial lining that makes lubricating fluid; arthritis is broadly non-inflammatory (mainly osteoarthritis) or inflammatory (such as rheumatoid arthritis and gout).
- About 6 million people in Canada, or 1 in 5 adults, report arthritis; in one Alberta study, rheumatoid arthritis affected about three times as many First Nations residents, who had fewer specialist visits.
- Assessment covers onset, pattern, morning stiffness, pain, whole-body symptoms and function; morning stiffness of 30 minutes or more suggests inflammatory arthritis.
- On darker skin tones, the nurse relies on warmth, swelling and tenderness compared with the other side, not on redness alone.

- A single hot, swollen, painful joint is treated as septic arthritis until proven otherwise, even without fever; the nurse reports it at once, and fluid is aspirated before antibiotics.

34.2 Osteoarthritis

- Osteoarthritis, the most common arthritis in Canada, is a progressive disease of the whole joint; about 3.9 million adults had diagnosed OA in 2016–2017.
- Pain is worse with use and morning stiffness is brief; diagnosis rests on symptoms and examination, and imaging is often not needed.
- Education, structured exercise and, for knee OA, weight management are core treatments; movement, not rest, protects the joint.
- Topical NSAIDs are strongly recommended for knee OA; oral NSAIDs are not recommended with cardiovascular disease or frailty; the OARSI guideline advises against acetaminophen (conditionally) and opioids (strongly).
- Before an oral NSAID, the nurse checks kidney function, blood pressure, fluid status, bleeding and the medication list, with extra care in older adults.

34.3 Rheumatoid Arthritis

- Rheumatoid arthritis is an autoimmune synovitis that usually affects the same small joints on both sides, with long morning stiffness, fatigue and possible effects on the eyes, lungs and heart.
- Early and equitable access to rheumatology care matters; persistent joint swelling for 6 weeks or more warrants urgent referral.
- Treat-to-target aims for remission or minimal disease activity, starting with methotrexate and changing treatment if the response is not good enough after 3 to 6 months.
- Methotrexate for RA is taken once a week on a named day; daily use by mistake has caused deaths, so nurses check every order at reconciliation, hold and clarify any daily order, and teach with a calendar.
- Teaching covers folic acid as ordered, regular blood tests, no alcohol, reporting fever, sore throat, mouth sores, cough or bleeding, and planning any pregnancy with the rheumatologist.
- Joint protection, energy conservation, splints, therapy, mental health support and help with work are part of nursing care.

34.4 Gout

- Gout is caused by monosodium urate crystals deposited when urate levels stay high; flares bring sudden pain, swelling and warmth, often at the base of the big toe.
- In 2016–2017, about 681,000 people in Canada aged 20 and older (2.4%) had diagnosed gout or another crystal arthritis, with higher rates in males and with age.
- Flares are treated early with colchicine, an NSAID or a corticosteroid; colchicine toxicity begins with stomach and bowel symptoms, and drug interactions are checked.
- The US guideline recommends urate-lowering therapy, usually allopurinol, raised step by step to keep serum urate below 360 µmol/L, with flare prevention for 3 to 6 months at the start.
- A new hot joint with fever is reported promptly, because septic arthritis must be ruled out.

34.5 Lupus and Other Connective Tissue Disorders

- SLE is a multi-organ autoimmune disease that affects women far more than men; in a Canadian cohort, low income, not ethnicity, predicted organ damage.
- Lupus nephritis is often silent at first and is found through urine protein, creatinine and blood pressure; fever may be a flare or an infection.
- EULAR recommends hydroxychloroquine for nearly everyone with SLE, with eye examinations before and at least yearly during treatment, sun protection and the lowest corticosteroid dose possible.
- Systemic sclerosis causes Raynaud phenomenon and organ fibrosis; Sjögren disease causes dry eyes and mouth; PMR causes shoulder and hip stiffness in people 50 and older.

- Giant cell arteritis is an emergency: a new headache, scalp tenderness, jaw pain on chewing or any vision change needs same-day escalation; EULAR (2025) advises urgent referral and corticosteroids without delay when suspicion is strong.

34.6 Medicines for Inflammatory Arthritis

- DMARDs include conventional drugs (methotrexate once weekly), biologics and JAK inhibitors; biosimilars are highly similar, less expensive versions of biologics.
- In 2022, Health Canada announced updated labelling for all JAK inhibitors warning of serious heart-related problems, fatal blood clots and cancer, with particular caution for older adults, smokers and people with heart, clot or cancer risk factors.
- Screening for TB infection and hepatitis B, and vaccines given before treatment, precede biologics and JAK inhibitors; live vaccines are avoided.
- Long-term corticosteroids are never stopped suddenly; immunosuppressive medicines are held or continued only as the prescriber directs.
- Provincial and territorial plans, private insurance and NIHB shape access to these medicines.

34.7 Living Well With Chronic Arthritis

- Arthritis Society Canada reports arthritis as a leading cause of disability and work limitation in Canada, and people with arthritis are more likely to have a mood disorder such as depression.
- The nurse assesses pain, fatigue, sleep and mood, and supports paced physical activity.
- EULAR recommends nurse-led education, consultations, telephone and virtual access, psychosocial support and self-management support.
- Rural, remote and northern communities and Indigenous people face access barriers; culturally safe care and help with coverage are part of nursing care.

Key Terms (41)

anti-CCP antibodies: Antibodies to cyclic citrullinated peptides; a blood test that is more specific for rheumatoid arthritis than rheumatoid factor, although a negative result does not rule the disease out.

arthritis: Inflammation of a joint; used as a general term for many conditions that affect joints and the tissues around them.

articular cartilage: The smooth, firm tissue covering the ends of bones in a synovial joint, which lets them glide and spreads the load.

autoimmune disease: A disease in which the immune system attacks the body's own tissues.

biologic: A medicine made in living cells, usually a protein such as an antibody, that blocks one specific part of the immune response.

biosimilar: A highly similar and generally less expensive version of an originator biologic, approved by Health Canada after showing no meaningful differences in safety and effectiveness.

C-reactive protein (CRP): A protein the liver makes during inflammation; a non-specific blood marker of inflammation from any cause.

corticosteroid: A medicine related to the body's own cortisol that quickly reduces inflammation and immune activity; long-term use suppresses the body's cortisol production.

disease-modifying antirheumatic drug (DMARD): A medicine that slows or stops the immune process that damages joints, rather than only relieving symptoms.

energy conservation: Planning, pacing and resting before exhaustion to manage fatigue in chronic arthritis.

erythrocyte sedimentation rate (ESR): A blood test of how quickly red blood cells settle in a tube; it rises with inflammation but is not specific.

flare: A period when symptoms of a chronic inflammatory disease suddenly return or worsen.

giant cell arteritis: A vasculitis of large arteries, including those of the head, in adults older than 50 that can cause permanent vision loss if not treated at once.

gout: A form of inflammatory arthritis caused by deposits of monosodium urate crystals in and around joints and in other tissues.

gout flare: A sudden attack of pain, swelling and warmth in a joint caused by the immune response to urate crystals.

JAK inhibitor: An oral targeted synthetic DMARD that blocks Janus kinase enzymes inside immune cells, interrupting signals from many inflammatory messengers.

joint protection: Ways of doing daily tasks that reduce strain on painful joints, such as using larger joints, avoiding tight gripping and using aids.

lupus nephritis: Inflammation of the kidneys caused by systemic lupus erythematosus.

methotrexate: The most commonly used disease-modifying drug for rheumatoid arthritis, taken once a week on a named day; daily use by mistake has caused fatal toxicity.

morning stiffness: Joint stiffness after waking; lasting 30 minutes or more suggests inflammatory arthritis, while osteoarthritis stiffness usually eases in less than 30 minutes.

nonsteroidal anti-inflammatory drug (NSAID): A medicine that reduces pain and inflammation; risks include stomach bleeding, kidney injury, fluid retention and cardiovascular events.

osteoarthritis (OA): A progressive disease of the whole joint in which cartilage and underlying bone break down; the most common type of arthritis in Canada.

pain sensitization: A state in which the nervous system amplifies pain signals, so pain is felt more strongly than tissue changes alone would explain.

photosensitivity: An abnormal skin reaction, such as a rash, after exposure to sunlight.

polymyalgia rheumatica: An inflammatory condition of adults aged 50 and older that causes aching and stiffness of the shoulders and hips.

Raynaud phenomenon: Episodes in which small arteries of the fingers or toes spasm in cold or stress, so that the skin changes colour and may feel numb or painful.

rheumatoid arthritis (RA): A chronic autoimmune disease that inflames the joint lining, usually in the same joints on both sides of the body, and can affect other organs.

rheumatoid factor (RF): An antibody often present in rheumatoid arthritis; it also appears in some other conditions and is absent in some people with RA.

self-management: The day-to-day skills a person uses to live with a chronic condition, such as taking medicines, pacing activity, solving problems and knowing when to seek help.

septic arthritis: Infection inside a joint; a single hot, swollen, painful joint is treated as septic arthritis until proven otherwise.

Sjögren disease: A systemic autoimmune disease marked by dry eyes and dry mouth, with fatigue, pain and sometimes involvement of other organs.

synovial joint: A freely movable joint in which cartilage-covered bone ends sit inside a capsule lined with synovium and filled with synovial fluid.

synovitis: Inflammation of the synovium, the lining of a synovial joint.

synovium: The inner lining of a joint capsule, which makes the fluid that lubricates the joint and nourishes the cartilage.

systemic lupus erythematosus: A chronic autoimmune disease in which antibodies against the body's own cell parts cause inflammation in many organs.

systemic sclerosis: A rare autoimmune disease that damages small blood vessels and causes thickening and scarring of the skin and internal organs.

tophus: A firm, chalk-like deposit of urate crystals under the skin, often on the ear, elbow or finger pads (plural tophi).

treat-to-target: An approach that sets a goal such as remission, measures disease activity regularly and adjusts treatment until the goal is reached.

urate-lowering therapy: A long-term medicine, such as allopurinol, that lowers the body's urate level to dissolve crystals and prevent gout flares.

uric acid: A waste product of purine breakdown that the kidneys remove; a high blood level can lead to urate crystal deposits.

vasculitis: Inflammation of the walls of blood vessels.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Ingrid Solberg (Questions 1–4): Ingrid Solberg, 58, was diagnosed with rheumatoid arthritis three weeks ago. Today, at a community rheumatology clinic in Ontario, she is starting oral methotrexate once weekly, with folic acid as ordered. She works full time as a bank teller, lives with her husband and mentions that she usually has a glass of wine with dinner. The RPN is providing her teaching.

1. [CORE] Which statement by Ms. Solberg shows that she understands how to take methotrexate?

a. "I'll take my methotrexate tablets every morning with breakfast, because a routine will help me remember them."

b. "I'll take my methotrexate tablets on Saturdays only, and I'll mark each dose on the calendar on my fridge."

c. "If I forget my methotrexate on my usual day, I'll take two days' worth together the next morning to catch up."

d. "I'll take my methotrexate tablets on any day my hands feel stiff and swollen, but never more than once a day."

Answer: b — For rheumatoid arthritis, methotrexate is taken once a week on the same named day, and a calendar is a recommended way to track doses (section 34.3, Nursing Care and Medicines). Option a describes daily use, the error that has caused fatal toxicity. Option c doubles the dose; a missed dose is discussed with the pharmacist or prescriber, not made up on her own. Option d makes the medicine symptom-driven and could lead to daily use; methotrexate works by steady weekly dosing, not as a pain reliever.

2. [CORE] Ms. Solberg asks why she also has to take folic acid. Which response by the RPN is accurate?

a. "Folic acid makes the methotrexate work faster on your joints, so you will feel better within the first few days."

b. "Folic acid takes the place of methotrexate on the days in between, so the treatment keeps working all week long."

c. "Folic acid protects your bones from thinning, which is the most common problem people have when taking methotrexate."

d. "Folic acid may reduce some side effects of methotrexate, such as mouth sores and stomach upset, so take it as ordered."

Answer: d — According to the Canadian monograph, folic or folinic acid may lessen some methotrexate side effects, such as mouth sores and stomach upset, and folic acid is taken exactly as the prescriber orders (section 34.3, Nursing Care and Medicines). Option a is wrong; folic acid does not speed the effect on the joints. Option b is wrong; folic acid is not a substitute for methotrexate. Option c is wrong; bone thinning is not the purpose of folic acid with methotrexate.

3. [CORE] Ms. Solberg says, "I usually have a glass of wine with dinner. Is that still okay?" Which response by the RPN is best?

a. "The monograph says not to drink alcohol with methotrexate. Your regular blood tests will include liver tests to check for harm."

b. "One glass of wine with dinner is fine, as long as you avoid drinking any alcohol on the same day that you take your weekly dose."

c. "Alcohol is only a concern with methotrexate if you already have liver disease, so you can keep your usual routine."

d. "Wine is safer than beer or spirits with methotrexate, so you can switch to wine if you want to have a drink."

Answer: a — The Canadian monograph lists alcohol use with methotrexate as contraindicated and tells patients not to drink alcohol; liver tests are part of the regular monitoring schedule (section 34.3, Nursing Care and Medicines). Options b and c give permission the monograph does not support. Option d is wrong; the type of alcohol does not change the caution.

4. [CORE] Two months later, Ms. Solberg phones the clinic. She has a temperature of 38.4 °C, a sore throat and new sores in her mouth. Her weekly dose is due tomorrow. Which action should the RPN take?

a. Advise her to take her usual dose tomorrow and to gargle with warm salt water until the sore throat passes.

b. Advise her to double her folic acid for the rest of the week and to call back if she is not better by then.

c. Notify the rheumatologist or NP today, so that she is assessed and the prescriber decides about tomorrow's dose.

d. Advise her to stop taking methotrexate permanently, because these symptoms show that she cannot safely take it again.

Answer: c — Fever, sore throat and mouth sores can signal infection or methotrexate toxicity and must be reported promptly; decisions about holding or continuing a dose belong to the prescriber (section 34.3, Nursing Care and Medicines). Option a delays assessment and gives a dose that may be unsafe. Option b changes a medicine without an order and delays care. Option d is a decision the RPN cannot make alone, and stopping permanently may not be needed.

5. [CORE] A nurse is taking a history from an adult with joint pain. Which finding most suggests an inflammatory arthritis such as rheumatoid arthritis?

a. Knee pain that worsens on stairs and eases after the person sits and rests for a while.

b. Stiffness in the hip that lasts about 10 minutes after getting out of bed each morning.

c. Stiffness in both hands that lasts about 90 minutes each morning, with swelling of the knuckles.

d. Grinding in one knee during deep squatting, with no visible swelling and no stiffness in the morning.

Answer: c — Morning stiffness lasting 30 minutes or more, with swelling in the same joints on both sides, suggests inflammatory arthritis (section 34.1, Assessing the Person With Joint Symptoms). Options a, b and d describe pain with use, brief stiffness and crepitus, which are typical of osteoarthritis.

6. [CORE] A nurse is assessing a swollen wrist in a patient with dark skin. Which approach is best for detecting inflammation?

a. Compare warmth, swelling and tenderness with the other wrist, using the back of the hand to feel for warmth.

b. Look for bright redness over the joint, because redness is the most reliable sign of inflammation on all skin tones.

c. Record that no inflammation is present if the skin over the joint looks the same colour as the surrounding skin.

d. Ask the patient to rate the pain only, because swelling and warmth cannot be assessed on darker skin tones.

Answer: a — Redness can be hard to see on darker skin, so the nurse also checks warmth, swelling and tenderness and compares them with the same joint on the other side (section 34.1, Assessing the Person With Joint Symptoms). Option b relies on colour alone. Option c could miss inflammation. Option d is wrong; warmth and swelling can be assessed on every skin tone.

7. [CORE] An RPN is caring for a 74-year-old man on a medical unit. This morning his left knee became hot, swollen and very painful, and he cannot bend it. His temperature is 37.6 °C. Which action should the RPN take first?

a. Apply a heat pack to the knee and encourage gentle range-of-motion exercises to reduce the stiffness.

b. Give the as-needed acetaminophen that is ordered and reassess the knee at the end of the shift.

c. Document the findings and wait until the next scheduled assessment to see whether the swelling settles.

d. Report the findings promptly to the RN and the prescriber, because the joint may be infected.

Answer: d — A single hot, swollen, painful joint that develops over a short time is treated as septic arthritis until proven otherwise, even without a high fever, and needs prompt reporting so fluid can be aspirated before antibiotics (section 34.1, Assessing the Person With Joint Symptoms). Option a applies heat to an inflamed joint. Options b and c delay escalation of a possible emergency.

8. [CORE] A 62-year-old woman with knee osteoarthritis asks what will help most. According to the OARSI guideline, which treatment is part of the core plan for everyone with knee osteoarthritis?

a. An oral opioid at bedtime, so that pain does not interrupt her sleep at night.

b. Education about arthritis and a structured exercise program, with weight management if needed.

c. Bed rest for several days during each flare, so that the cartilage in the knee has enough time to heal fully.

d. Regular joint injections every few weeks, so that the inflammation in the knee stays low.

Answer: b — The OARSI guideline names arthritis education and a structured land-based exercise program, which may be combined with dietary weight management, as core treatments for knee osteoarthritis (section 34.2, Care and Self-Management). Option a is strongly recommended against. Option c is wrong; movement, not rest, is advised, with gentle range of motion during flares. Option d is not a core treatment; injections are conditionally recommended and are not given routinely every few weeks.

9. [CORE] A 70-year-old man with knee osteoarthritis has heart failure and had a heart attack two years ago. He asks which medicine he could use for knee pain. According to the OARSI guideline, which option is recommended for people with cardiovascular disease?

a. Oral naproxen taken regularly with meals, because food reduces the risk to the heart.

b. Oral celecoxib, because a COX-2 inhibitor is safer for the heart than other NSAIDs.

c. A topical NSAID applied to the knee, because little of the drug reaches the bloodstream.

d. An oral opioid, because opioids do not affect the heart or blood pressure in older adults.

Answer: c — The OARSI guideline strongly recommends topical NSAIDs for knee osteoarthritis, including in people with cardiovascular conditions, and does not recommend oral NSAIDs for them; only a small amount of a topical NSAID is absorbed (section 34.2, Care and Self-Management). Options a and b are oral NSAIDs, which raise cardiovascular risk and can worsen heart failure. Option d is strongly recommended against for osteoarthritis.

10. [CORE] A patient with hip osteoarthritis says, "When my hip is sore, I stay in bed for the whole day so I don't wear it out." Which response by the nurse is best?

a. "Long rest tends to worsen stiffness and weakness. Gentle movement, even on a sore day, helps protect your hip."

b. "Resting in bed whenever it hurts is a good idea, because every single movement wears away a little more of the cartilage."

c. "Staying in bed is fine for now, and you can start exercising once your hip has stopped hurting completely."

d. "Resting is the main treatment for osteoarthritis, so you should limit your walking to short trips at home."

Answer: a — Movement, not rest, protects joints in osteoarthritis; during flares, gentle range-of-motion exercise continues (section 34.2, Care and Self-Management; Patient Education box). Options b, c and d all encourage prolonged rest, which worsens stiffness and weakness and delays the core treatment.

11. [CORE] A nurse is about to give the first dose of oral naproxen to a hospitalized adult with osteoarthritis. Which findings should the nurse report to the prescriber before giving the dose? Select all that apply.

a. Serum creatinine has risen from 78 to 121 µmol/L since admission.

b. The patient had a black, tarry stool this morning.

c. The patient has heart failure, and new ankle swelling and a weight gain of 2 kg are noted.

d. The patient rates knee pain at 6 out of 10 when walking.

e. The patient takes a daily multivitamin at home.

f. The patient takes warfarin.

Answer: a, b, c, f — A rising creatinine suggests kidney injury, which NSAIDs can worsen; black stools suggest bleeding; fluid retention in heart failure can be worsened by NSAIDs; and anticoagulants raise the risk of serious bleeding (section 34.2, Care and Self-Management). Option d is the reason for the medicine, not a reason to hold it. Option e is not a known NSAID risk.

12. [CORE] A patient with knee osteoarthritis asks how to use heat and cold at home. Which instruction is accurate?

a. "Apply heat to the knee whenever it is hot and swollen, because the warmth helps draw the swelling out of the joint."

b. "Use heat only, because cold packs can damage cartilage and make osteoarthritis worse over time."

c. "Use cold packs only at night, and never use heat on the knee, because heat speeds up joint damage."

d. "Cold packs may relieve swelling and brief pain; heat may relieve stiffness but is not put on an inflamed joint."

Answer: d — Cold packs may relieve swelling and brief pain, and heat may relieve stiffness, but heat is not used on an inflamed joint (section 34.2, Care and Self-Management). Option a applies heat to an inflamed joint. Options b and c contain false claims about cartilage damage.

13. [CORE] Which presentation is most typical of rheumatoid arthritis?

a. Pain and grinding in one knee that worsen after a day of gardening and ease overnight.

b. Swelling and tenderness of the knuckles and wrists of both hands, with long morning stiffness and fatigue.

c. Sudden, severe pain and swelling in one big toe that began during the night after a large meal with several drinks.

d. Pain in the lower back that radiates down one leg after lifting a heavy box at work.

Answer: b — Rheumatoid arthritis typically affects the same small joints on both sides, with morning stiffness of 30 minutes or more and whole-body symptoms such as fatigue (section 34.3, What Happens in Rheumatoid Arthritis). Option a suggests osteoarthritis. Option c suggests a gout flare (section 34.4). Option d suggests a back injury.

14. [CORE] A patient newly diagnosed with rheumatoid arthritis asks what "treat-to-target" means. Which explanation is accurate?

a. "Your treatment stays the same for at least two years before the rheumatologist decides whether it is working."

b. "Medicines are given only when your joints flare, and stopped as soon as the swelling in your joints goes down."

c. "You and your team set a goal, such as remission, measure your disease regularly and adjust treatment until you reach it."

d. "Your rheumatologist chooses the strongest medicine available on the very first day, so that no changes are needed later on."

Answer: c — Treat-to-target means setting a goal of remission or minimal disease activity, measuring disease activity regularly and changing treatment until the goal is met, through shared decisions (section 34.3, Diagnosis and Treat-to-Target). Option a delays change; the EULAR update adds a biologic if the response is not good enough after 3 to 6 months. Option b describes on-and-off treatment, which does not control the disease. Option d is wrong; treatment starts with methotrexate and is adjusted over time.

15. [CORE] A patient with rheumatoid arthritis has painful, swollen hands and severe fatigue. Which teaching about joint protection and energy conservation is appropriate?

a. "Carry bags over your forearm instead of gripping them, and plan rest breaks before you become exhausted."

b. "Push through tiredness to finish all your housework in the morning, while your energy is at its peak."

c. "Grip objects as tightly as you can, because strengthening your fingers will prevent joint damage."

d. "Avoid using any aids such as jar openers, because they make your hand muscles weaker over time."

Answer: a — Joint protection reduces strain on inflamed joints and uses assistive devices, and energy conservation means pacing and resting before exhaustion (section 34.3, Nursing Care and Medicines). Option b leads to exhaustion. Option c strains inflamed joints. Option d is wrong; aids such as jar openers protect joints.

16. [CORE] During admission medication reconciliation, an RPN notices that a patient's home methotrexate for rheumatoid arthritis has been ordered "once daily." The patient's blister pack shows one dose each Saturday. Which action should the RPN take?

a. Give the dose as ordered, because the prescriber may have changed the schedule while the patient was in emergency.

b. Change the order to weekly on the medication record and document that the error was corrected.

c. Give half of the dose today and the rest on Saturday, so that the patient receives a safe amount this week.

d. Hold the dose, report the discrepancy to the RN and prescriber, and involve the pharmacist to clarify the order.

Answer: d — Daily use of weekly methotrexate has caused fatal toxicity. Any nurse who finds a discrepancy at medication reconciliation holds the dose and clarifies the order with the prescriber and pharmacist; the RPN also informs the RN (section 34.3, Nursing Care and Medicines; Practice Story; section 1.3). Option a risks giving a dangerous dose. Option b is outside the nurse's authority; nurses do not change orders themselves. Option c changes the dose without an order.

17. [CORE] A 29-year-old woman with rheumatoid arthritis has taken methotrexate for a year. She tells the nurse she would like to become pregnant next year. Which response is best?

a. "You can stop your birth control now, because methotrexate only affects a pregnancy in the first few days."

b. "Talk with your rheumatologist well before you stop birth control, because methotrexate can harm a pregnancy."

c. "Stop your methotrexate the week you decide to try to conceive, and restart it once you know you are pregnant."

d. "Methotrexate is a concern only if your partner takes it, so you can plan a pregnancy without changing anything."

Answer: b — Methotrexate can cause fetal death and birth defects; pregnancy is avoided if either partner takes it, and published advice on the waiting time after stopping ranges from 3 months to one year, so planning with the rheumatologist is essential (section 34.3, Nursing Care and Medicines). Options a, c and d are all unsafe or false.

18. [RN] An adult has had swelling in several small joints of both hands for 8 weeks. Results: RF negative; anti-CCP antibodies more than three times the upper limit of normal; CRP raised. Which interpretation by the RN is most accurate?

a. The results support rheumatoid arthritis, because anti-CCP is highly specific, and a negative RF does not rule the disease out.

b. The results rule out rheumatoid arthritis, because a positive rheumatoid factor is required before the diagnosis can be made.

c. The results confirm an infection, because a raised CRP is specific to bacterial infection rather than to joint inflammation.

d. The results point to osteoarthritis, because anti-CCP antibodies are a marker of cartilage breakdown in the small joints.

Answer: a — Anti-CCP is more specific for rheumatoid arthritis than RF, many people with RA are RF-negative, and a raised CRP reflects inflammation of any cause (section 34.1, Going Deeper; Table 34.2). Option b is wrong; RF is not required. Option c is wrong; CRP is not specific to infection. Option d is wrong; anti-CCP is an autoimmune antibody, and no blood test diagnoses osteoarthritis.

19. [RN] A 79-year-old woman with chronic kidney disease takes furosemide and ramipril. She asks the RN for oral ibuprofen for knee osteoarthritis pain. Which response is best?

a. "Ibuprofen is safe with your kidney disease if you take it with food and drink plenty of water."

b. "Ibuprofen is a safe choice for you, because it is sold without a prescription at every pharmacy."

c. "Oral ibuprofen could harm your kidneys with these medicines. I'll ask your prescriber about a skin gel."

d. "You should take acetaminophen and ibuprofen together, because that combination protects your kidneys."

Answer: c — Older age, kidney disease, diuretics and ACE inhibitors all raise the risk of NSAID-related kidney injury; a topical NSAID delivers little drug to the blood and is the guideline's strongly recommended medicine for knee osteoarthritis (section 34.2, Care and Self-Management; Lifespan Considerations box; section 27.3). Option a does not remove the kidney risk. Option b confuses over-the-counter availability with safety. Option d is wrong; acetaminophen does not protect the kidneys.

20. [RN] A 55-year-old man with rheumatoid arthritis who takes methotrexate is admitted with a right knee that is hot, much more swollen than his other joints and too painful to bend. His temperature is 38.2 °C and his heart rate is 108 beats/min. His other joints are at their usual level of stiffness. Which hypothesis should the RN treat as the priority?

a. A flare of rheumatoid arthritis, because a flare often begins in one large joint and causes a fever.

b. Osteoarthritis of the knee, because long-standing rheumatoid arthritis often turns into osteoarthritis.

c. Methotrexate toxicity, because high fever and swelling of one knee are the first signs of toxicity.

d. Septic arthritis, because one hot joint out of proportion to the others, with fever, needs urgent assessment.

Answer: d — A single hot, swollen joint out of proportion to the person's other joints, with fever and a fast heart rate in someone whose immune defences are lowered, is treated as septic arthritis until proven otherwise; fluid is aspirated before antibiotics, and the RN watches for sepsis (section 34.1, Assessing the Person With Joint Symptoms; section 4.6). Option a is less likely and would delay urgent care. Option b does not explain the fever. Option c is wrong; mouth sores are often the first sign of toxicity, and toxicity does not explain one hot joint.

Case: Leila Haddad (Questions 21–26): Leila Haddad, 34, has systemic lupus erythematosus treated with hydroxychloroquine and daily prednisone. She is admitted to a medical unit with 2 days of fever and sharp left-sided chest pain that is worse when she breathes in. She says she stopped her hydroxychloroquine a month ago because she "felt fine." Vital signs: temperature 38.4 °C, heart rate 108, respiratory rate 22, blood pressure 148/94 mm Hg (her usual is 118/74 mm Hg) and oxygen saturation 95% on room air. Both ankles have pitting edema, and her weight is up 3 kg in a week. Urinalysis shows 3+ protein, which was negative at her last clinic visit. Her creatinine is 142 µmol/L (68 µmol/L 3 months ago). Over the first 24 hours, her intake is 2,100 mL and her urine output is 650 mL.

21. [CORE] Which findings should the nurse recognize as cues that need follow-up? Select all that apply.

a. Temperature of 38.4 °C

b. Chest pain that is worse when she breathes in

c. Blood pressure of 148/94 mm Hg

d. New 3+ protein in the urine

e. Creatinine of 142 µmol/L, up from 68 µmol/L

f. Oxygen saturation of 95% on room air

g. She is 34 years old and works as a teacher

Answer: a, b, c, d, e — Fever in a person taking prednisone may mean infection or a lupus flare and needs follow-up (a; section 34.5). Chest pain that worsens with breathing suggests serositis, a lupus feature, though other causes must be considered (b). A blood pressure well above her usual, new protein in the urine and a doubled creatinine point to kidney involvement (c, d, e; section 34.5; Chapter 27). An oxygen saturation of 95% on room air is within a normal range (f). Her age and job are background, not findings that need follow-up (g).

22. [CORE] Which explanation best links Ms. Haddad's blood pressure, ankle edema, proteinuria and rising creatinine?

a. Dehydration from her fever has reduced blood flow to her kidneys, and the ankle swelling reflects a low protein intake.

b. Daily prednisone has caused fluid retention, which raises her blood pressure and pushes protein out into her urine.

c. Lupus nephritis, inflammation of the kidneys from SLE, is causing protein loss, fluid retention and falling kidney function.

d. Pericarditis has led to heart failure, which explains her ankle edema, her 3 kg weight gain, her higher blood pressure and her creatinine.

Answer: c — New proteinuria, edema, higher blood pressure and a rising creatinine together fit lupus nephritis, a serious form of SLE that is found by checking urine, creatinine and blood pressure (c; section 34.5). Dehydration does not cause edema, weight gain or heavy proteinuria (a). Corticosteroids can raise blood pressure, but they do not cause new heavy proteinuria or a doubled creatinine (b). She has no findings of heart failure, such as low oxygen saturation or crackles, and heart failure does not explain heavy proteinuria (d).

23. [RN] The team is considering both an infection and a lupus flare as causes of Ms. Haddad's fever. Which statement best guides the nurse's priorities?

a. Fever in SLE is almost always a sign of a flare, so the nurse should ask the prescriber to increase her prednisone dose before any other tests are done tonight.

b. Infection and a flare can look alike in a person taking prednisone, so the nurse reports promptly so that infection can be looked for before immunosuppression is increased.

c. Daily prednisone protects her against infection, so an infection is unlikely, and the nurse should focus all of the assessment on her kidney findings for now.

d. Her chest pain is most likely a pulmonary embolism, so the nurse should give a dose of anticoagulant right away and leave the question of her fever until the medical team rounds in the morning.

Answer: b — In a person taking corticosteroids, infection and a lupus flare can look alike, and giving more immunosuppression to someone with an untreated infection can be dangerous, so infection is looked for first (b; section 34.5; Chapter 4). Assuming a flare without testing could miss an infection (a). Corticosteroids raise, not lower, infection risk (c; section 34.6). The team does consider other causes of chest pain, but nurses do not start anticoagulation without an order, and the fever cannot be set aside (d).

24. [CORE] Which plan best supports monitoring of Ms. Haddad's fluid balance?

a. Weigh her daily on the same scale at the same time, keep a strict intake and output record, and report output below the ordered limit or further weight gain.

b. Encourage her to drink at least 3 L of fluid each day to flush her kidneys, and record her intake on the bedside sheet each time she finishes a full glass of water.

c. Hold her ordered blood pressure medicines so that her kidneys receive more blood flow, and recheck her blood pressure once at the end of the shift to see whether it has risen.

d. Insert a urinary catheter on the nurse's own judgment so that hourly output can be measured, and remove it once her creatinine returns to her usual level.

Answer: a — Daily weights and accurate intake and output show fluid retention and falling urine output, which the nurse reports according to the orders (a; section 34.5; Chapter 3). Extra fluid could worsen edema when kidney function is falling; fluid intake follows the prescriber's order (b). Blood pressure medicines are not held without an order, and rising blood pressure in lupus nephritis needs treatment (c). A urinary catheter needs an order and adds infection risk, and it is not routine for this purpose (d).

25. [CORE] The nurse calls the internal medicine resident. Which report best follows SBAR?

a. "Ms. Haddad in bed 4 has lupus and a fever. Can you order some acetaminophen and maybe an antibiotic for her?"

b. "I'm calling about Ms. Haddad. She stopped her hydroxychloroquine and her lupus is flaring, so she probably needs more prednisone tonight."

c. "Ms. Haddad's creatinine is 142. Is that high for her? She also has some ankle swelling, but she has been lying in bed all day."

d. "Ms. Haddad, 34, with SLE on prednisone, has a temperature of 38.4, pleuritic chest pain, BP 148/94 from 118/74, new 3+ proteinuria, creatinine 142 from 68 and 650 mL of urine in 24 hours. I'm concerned about infection and kidney involvement. Please assess her within the hour."

Answer: d — Option d gives the situation, background, an assessment with specific values and the nurse's concern, and a clear request with a time frame (d; section 34.5; Chapter 6). Option a asks for treatment without data or a concern (a). Option b offers a conclusion about a flare without data and leaves out the possibility of infection (b). Option c gives one value without context and dismisses a finding that matters (c).

26. [CORE] Before discharge, Ms. Haddad's infection screen is negative, and she has started treatment for lupus nephritis. Which statement shows that her teaching has been effective?

a. "Once my kidney tests are back to normal, I can stop taking the prednisone on my own, because I really don't like the way it makes me feel."

b. "My eyes are fine right now, so I can skip the eye checks for hydroxychloroquine until I notice a problem with my vision."

c. "I'll take my hydroxychloroquine every day even when I feel well, and I'll call if my ankles swell or I pass less urine."

d. "Lupus doesn't seem to affect my skin, so I don't need to worry about sunscreen or covering up when I'm outside this summer."

Answer: c — Taking hydroxychloroquine every day, even in remission, and reporting signs of kidney involvement show understanding (c; section 34.5). Stopping prednisone suddenly after long-term use can cause adrenal crisis, and changes are made with the prescriber (a; section 34.6). Eye examinations are needed before and at least yearly during long-term hydroxychloroquine, because the drug can damage the retina (b). Lupus is photosensitive, and EULAR advises people with SLE to avoid sun exposure in particular (d).

27. [CORE] Which description best fits a gout flare?

a. Sudden, severe pain, swelling and warmth in the joint at the base of the big toe that came on over a few hours

b. Gradual stiffness in both knees that is worse after activity and eases after a few minutes of rest

c. Aching and stiffness in both shoulders and hips each morning for more than an hour in a person older than 50

d. Swelling in the small joints of both hands, with morning stiffness each day that has lasted for several months now

Answer: a — A gout flare comes on over a few hours, with a swollen, warm and very painful joint, commonly the first metatarsophalangeal joint (a; section 34.4). Gradual stiffness that eases with rest suggests osteoarthritis (b; section 34.2). Shoulder aching and stiffness in an older adult suggests polymyalgia rheumatica (c; section 34.5). Symmetric small-joint swelling with long morning stiffness suggests rheumatoid arthritis (d; section 34.3).

28. [CORE] A 70-year-old man with gout takes colchicine to prevent flares. Which teaching is most important?

a. Take an extra dose of colchicine whenever a joint begins to ache, since the medicine works best when it is given early in a flare.

b. Stop colchicine whenever you start a new blood pressure medicine, since the two kinds of medicine always interact with each other.

c. Expect some mild diarrhea while taking colchicine, and keep taking it every day until the end of the prescription.

d. Tell your prescriber and pharmacist that you take colchicine before starting any new medicine, such as an antibiotic.

Answer: d — Some medicines, such as clarithromycin, can raise colchicine to dangerous levels, and older adults face higher risk, so every new prescription must be checked (d; section 34.4). Extra doses are taken only as prescribed, and higher doses increase toxicity (a). Not all blood pressure medicines interact, and stopping is decided with the prescriber (b). Diarrhea can be an early sign of toxicity and is reported, not ignored (c).

29. [CORE] A man newly diagnosed with gout asks whether he will have to give up all meat. Which response by the nurse is best?

a. "Yes. Purines in meat are the cause of gout, so a strict meat-free diet is the main treatment and can replace your medicines."

b. "Limiting alcohol, sweet drinks and purine-rich foods can help, and your medicines will do most of the work of lowering urate."

c. "No. Diet makes no difference to gout at all, so you can eat and drink whatever you like as long as you take your medicine."

d. "Taking a vitamin C supplement every day will lower your urate level enough that you can keep eating and drinking as you do now."

Answer: b — The US guideline suggests limiting alcohol, purine-rich foods and high-fructose corn syrup, alongside medicines that lower urate to the target, and the nurse avoids blaming language (b; section 34.4). A strict diet is not presented as a replacement for urate-lowering therapy (a). Diet and alcohol do matter as part of care (c). The guideline does not support vitamin C supplements (d).

30. [CORE] On day 2 after a bowel resection, a 66-year-old man with a history of gout has a hot, swollen right knee, a temperature of 38.6 °C and a heart rate of 112. What should the nurse do first?

a. Apply ice, raise the knee and give the as-needed analgesic that is ordered, then reassess the knee and his temperature in 4 hours.

b. Ask the patient to stop taking his allopurinol, since restarting it after surgery has probably caused this flare of gout.

c. Report the findings to the prescriber promptly, because the knee could be infected and needs urgent assessment.

d. Encourage the patient to walk on the knee to prevent stiffness, since gout flares settle faster when the joint keeps moving.

Answer: c — A hot joint with fever and a fast heart rate may be septic arthritis, which is an emergency, so the nurse reports it promptly so that the joint can be assessed (c; sections 34.1 and 34.4; Chapter 4). Comfort measures help, but waiting 4 hours could delay treatment of a septic joint (a). Urate-lowering therapy is not stopped without the prescriber's direction, and the cause is not yet known (b). Walking on an acutely inflamed joint is not advised (d).

31. [CORE] A woman with SLE asks how she can lower her risk of a flare this summer. Which response is best?

a. "Protect your skin from the sun with clothing, a hat and sunscreen, since lupus makes the skin sensitive to sunlight."

b. "Spend some time in the sun each day, since the vitamin D you make from sunlight helps to calm the immune system in lupus."

c. "Stop taking your hydroxychloroquine during the summer months, since it makes your skin burn much more easily in the sun."

d. "Avoid all exercise during hot weather, since physical activity is one of the most common triggers for lupus flares."

Answer: a — Lupus is characteristically photosensitive, and EULAR advises people with SLE to avoid sun exposure in particular (a; section 34.5). Sun exposure is something to avoid, not a treatment (b). EULAR advises against stopping hydroxychloroquine (c). Regular exercise is part of EULAR's advice for lupus (d; section 34.7).

32. [CORE] A woman starting long-term hydroxychloroquine for SLE asks why she has been referred to an eye specialist. Which response is accurate?

a. "Hydroxychloroquine causes cataracts in most people who take it, so the specialist will plan your cataract surgery in advance."

b. "The eye check is needed only if you notice blurred vision or other changes in your sight after you start taking the medicine."

c. "Lupus always affects the eyes sooner or later, so the specialist will be treating your lupus rather than checking the drug."

d. "The medicine can damage the retina, so you need an eye exam before you start and at least once a year."

Answer: d — A current Canadian monograph calls for an eye examination before long-term treatment and at least yearly afterward, because hydroxychloroquine can damage the retina (d; section 34.5). Cataract surgery is not planned for people taking this medicine (a). The monograph schedules the checks regardless of symptoms, so they do not wait for vision changes (b). The referral is for medicine safety, not because lupus always involves the eyes (c).

33. [CORE] A man with systemic sclerosis has Raynaud phenomenon. Which teaching is most helpful?

a. Soak your hands in very hot water at the start of each attack so that the narrowed blood vessels open up as quickly as possible.

b. Keep your whole body and hands warm in cold weather, and report any finger sore or a finger that stays pale or dark.

c. Avoid using your hands for any tasks during the winter months, since hand movement is what triggers attacks of Raynaud phenomenon.

d. Expect your fingers to stay white for several hours during each attack, since this is the usual pattern and does not need to be reported.

Answer: b — Cold triggers attacks, so warmth helps, and finger ulcers or a finger that does not regain its colour need prompt care (b; section 34.5; Table 34.3). Very hot water can burn skin with reduced sensation (a). Movement is not the trigger, and avoiding all hand use is not needed (c). Colour returns as blood flow returns; a finger that stays pale or dark is a danger sign (d).

34. [CORE] A woman with Sjögren disease says her mouth is so dry that she has trouble eating. Which suggestion is most appropriate?

a. Suck on hard candies that contain sugar throughout the day to keep the saliva flowing.

b. Rinse with an alcohol-based mouthwash several times a day to keep the mouth clean.

c. Chew sugar-free gum or use a saliva substitute, and keep regular dental visits.

d. Limit fluids with meals so that the small amount of saliva your glands make is not diluted.

Answer: c — Sugar-free gum or lozenges and saliva substitutes ease dryness, and dental care protects teeth, which are at risk when saliva is low (c; section 34.5). Sugar increases the risk of tooth decay in a dry mouth (a). Alcohol-based mouthwash can worsen dryness (b). Sips of fluid with meals help with chewing and swallowing (d).

35. [CORE] A 72-year-old woman with polymyalgia rheumatica calls the clinic. Which findings need same-day assessment for possible giant cell arteritis? Select all that apply.

a. A new headache over one temple

b. Pain in the jaw that starts when she chews

c. Tenderness of the scalp when she brushes her hair

d. Blurred vision in one eye that lasted 5 minutes

e. Shoulder stiffness for 30 minutes in the morning, unchanged for months

f. Mild ache in both knees after an afternoon of gardening

Answer: a, b, c, d — A new headache, jaw pain with chewing, scalp tenderness and any visual symptom can be features of GCA, an emergency that threatens vision, so they need same-day escalation (a, b, c, d; section 34.5). Brief blurred vision is especially urgent, because people with cranial symptoms are at high risk of permanent vision loss and EULAR advises immediate referral. Stable, mild morning stiffness is her usual PMR pattern (e). A knee ache after activity is not a feature of GCA (f).

36. [CORE] A man with rheumatoid arthritis covered by the Ontario Drug Benefit program is told that his originator adalimumab will be changed to a biosimilar. He asks whether the new product will work as well. Which response is best?

a. "Health Canada approves a biosimilar only when it does not differ in any meaningful way in safety or effectiveness, and I'll show you how to use the new pen."

b. "A biosimilar is an exact copy of your current medicine sold under a different name, so nothing about your treatment, your pen or your injection routine will change at all."

c. "A biosimilar is a weaker version of your current medicine, so your rheumatologist will probably need to increase how often you inject it to keep your arthritis controlled."

d. "Switching is entirely your choice, so you can keep taking the original product under the drug plan if you would rather not change."

Answer: a — Health Canada approves a biosimilar only after finding no meaningful difference from the originator in safety or effectiveness, and the nurse teaches the new device (a; section 34.6). A biosimilar is highly similar but not identical, and the device may differ (b). Biosimilars are not weaker versions (c). Under the Ontario policy, coverage of originator adalimumab requires an exemption, so continuing it is not simply the person's choice (d).

37. [CORE] An RPN in a rheumatology clinic is asked to give a patient's first dose of a new subcutaneous biologic using an autoinjector device the RPN has never used. There is an order, and the clinic's policy allows RPNs to give this medicine. What should the RPN do?

a. Decline, because only RNs are authorized to give biologic medicines by injection in Ontario.

b. Give the dose using general injection skills, since the order and clinic policy provide the needed authority.

c. Ask the patient to give the first dose alone, since the patient will be self-injecting at home anyway.

d. Learn the device from the product teaching material or an experienced colleague before giving the dose.

Answer: d — The RPN has the authority (the controlled act and an order) and a supportive context (clinic policy) but must also have the competence for the specific product and device, so the RPN gets the needed education first (d; section 34.7, Scope in Practice box; Chapter 1, section 1.3). Administering a substance by injection is a controlled act authorized to both RNs and RPNs (a). Authority alone is not enough; competence is also needed (b). Teaching self-injection still requires a nurse who knows the device, and the first self-injection is supervised (c).

38. [CORE] A woman with polymyalgia rheumatica has taken prednisone for 10 months. She says, "I feel so much better that I'm going to stop the prednisone tomorrow." Which response by the nurse is best?

a. "That's a good plan, since your symptoms have gone away and long-term prednisone has many side effects you would be glad to avoid."

b. "Please don't stop it suddenly; after months of use, your body needs a gradual taper that your prescriber plans."

c. "Cut your dose in half tomorrow, and stop it completely next week if your shoulders and hips still feel fine by then."

d. "Switch to an anti-inflammatory such as ibuprofen instead, since it treats polymyalgia rheumatica just as well."

Answer: b — Long-term corticosteroids suppress the body's own cortisol production, so stopping suddenly can cause adrenal crisis, and the taper is planned by the prescriber (b; section 34.6; Chapter 23). Stopping suddenly is unsafe (a). The nurse does not invent a taper schedule (c). PMR is treated with corticosteroids rather than NSAIDs (d; section 34.5).

39. [RN] A man with recurrent gout started allopurinol and colchicine prophylaxis 6 weeks ago. He has a flare in his ankle and says, "The allopurinol is making my gout worse, so I'm stopping it." Which response is best?

a. "You're right. Allopurinol should be stopped during every flare and then restarted once the joint has settled down completely."

b. "That suggests you are allergic to allopurinol, so the prescriber will need to switch you to a different urate-lowering medicine."

c. "Flares can happen in the first months of treatment, so keep taking it, treat the flare as planned and let your prescriber know."

d. "A flare means your dose is already too high, so take half of your usual allopurinol dose each day until your next blood test."

Answer: c — Flares can occur in the early months of urate-lowering therapy, which is why the US guideline recommends prophylaxis for 3 to 6 months and supports continuing ULT toward the target (c; section 34.4). Stopping and restarting ULT with each flare delays reaching the urate target (a). A flare is not a sign of allergy; a rash is the warning sign to report (b). Dose changes are made by the prescriber, and the dose is usually raised, not lowered, to reach the target (d).

40. [RN] A 52-year-old woman with rheumatoid arthritis is scheduled to start adalimumab. Which pre-treatment finding should the nurse report to the prescriber before the first dose?

a. A positive interferon-gamma release assay (IGRA), with no cough or other symptoms

b. A raised C-reactive protein level that matches the amount of swelling in her joints

c. A positive rheumatoid factor test on the diagnostic bloodwork done last month

d. An inactivated influenza vaccine given 3 weeks before the planned start date

Answer: a — A positive IGRA suggests TB infection; active TB must be ruled out, and TB infection is treated before a TNF inhibitor starts (a; section 34.6, Going Deeper box). A raised CRP reflects active RA, which is why treatment is starting (b; section 34.1). A positive rheumatoid factor supports the diagnosis and does not delay treatment (c). Giving non-live vaccines before immunosuppression starts is recommended when possible (d).

References

AbbVie Corporation. (2022). *Humira (adalimumab injection)* [Product monograph]. https://www.abbvie.ca/content/dam/abbvie-dotcom/ca/en/documents/products/HUMIRA_PM_EN.pdf

Aringer, M., Costenbader, K., Daikh, D., Brinks, R., Mosca, M., Ramsey-Goldman, R., Smolen, J. S., Wofsy, D., Boumpas, D. T., Kamen, D. L., Jayne, D., Cervera, R., Costedoat-Chalumeau, N., Diamond, B., Gladman, D. D., Hahn, B., Hiepe, F., Jacobsen, S., Khanna, D., … Johnson, S. R. (2019). 2019 European League Against Rheumatism/American College of Rheumatology classification criteria for systemic lupus erythematosus. *Annals of the Rheumatic Diseases, 78*(9), 1151–1159. https://doi.org/10.1136/annrheumdis-2018-214819

Arthritis Society Canada. (n.d.-a). *Arthritis facts and figures*. Retrieved October 27, 2026, from https://arthritis.ca/understand-arthritis/arthritis-facts-figures

Arthritis Society Canada. (n.d.-b). *Osteoarthritis*. Retrieved October 27, 2026, from https://arthritis.ca/about-arthritis/arthritis-types-(a-z)/types/osteoarthritis

Arthritis Society Canada. (n.d.-c). *Rheumatoid arthritis*. Retrieved October 27, 2026, from https://arthritis.ca/about-arthritis/arthritis-types-(a-z)/types/rheumatoid-arthritis

Auro Pharma Inc. (2026). *Auro-Hydroxychloroquine (hydroxychloroquine sulfate tablets)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00086286.PDF

Bannuru, R. R., Osani, M. C., Vaysbrot, E. E., Arden, N. K., Bennell, K., Bierma-Zeinstra, S. M. A., Kraus, V. B., Lohmander, L. S., Abbott, J. H., Bhandari, M., Blanco, F. J., Espinosa, R., Haugen, I. K., Lin, J., Mandl, L. A., Moilanen, E., Nakamura, N., Snyder-Mackler, L., Trojian, T., … McAlindon, T. E. (2019). OARSI guidelines for the non-surgical management of knee, hip, and polyarticular osteoarthritis. *Osteoarthritis and Cartilage, 27*(11), 1578–1589. https://doi.org/10.1016/j.joca.2019.06.011

Barnabe, C., Jones, C. A., Bernatsky, S., Peschken, C. A., Voaklander, D., Homik, J., Crowshoe, L. F., Esdaile, J. M., El-Gabalawy, H., & Hemmelgarn, B. (2017). Inflammatory arthritis prevalence and health services use in the First Nations and non–First Nations populations of Alberta, Canada. *Arthritis Care & Research, 69*(4), 467–474. https://doi.org/10.1002/acr.22959

Barnabe, C., Joseph, L., Belisle, P., Labrecque, J., Edworthy, S., Barr, S. G., Fritzler, M., Svenson, L. W., Hemmelgarn, B., & Bernatsky, S. (2012). Prevalence of systemic lupus erythematosus and systemic sclerosis in the First Nations population of Alberta, Canada. *Arthritis Care & Research, 64*(1), 138–143. https://doi.org/10.1002/acr.20656

Bech, B., Primdahl, J., van Tubergen, A., Voshaar, M., Zangi, H. A., Barbosa, L., Boström, C., Boteva, B., Carubbi, F., Fayet, F., Ferreira, R. J. O., Hoeper, K., Kocher, A., Kukkurainen, M. L., Lion, V., Minnock, P., Moretti, A., Ndosi, M., Pavic Nikolic, M., … van Eijk-Hustings, Y. (2020). 2018 update of the EULAR recommendations for the role of the nurse in the management of chronic inflammatory arthritis. *Annals of the Rheumatic Diseases, 79*(1), 61–68. https://doi.org/10.1136/annrheumdis-2019-215458

Beuschlein, F., Else, T., Bancos, I., Hahner, S., Hamidi, O., van Hulsteijn, L., Husebye, E. S., Karavitaki, N., Prete, A., Vaidya, A., Yedinak, C., & Dekkers, O. M. (2024). European Society of Endocrinology and Endocrine Society joint clinical guideline: Diagnosis and therapy of glucocorticoid-induced adrenal insufficiency. *European Journal of Endocrinology, 190*(5), G25–G51. https://doi.org/10.1093/ejendo/lvae029

Blinova, E., Volling, J., Koczmara, C., & Greenall, J. (2008). Oral methotrexate: Preventing inadvertent daily administration. *Canadian Journal of Hospital Pharmacy, 61*(4), 275–277. https://cjhp-online.ca/index.php/cjhp/article/download/67/64/262

Campbell, J. R., Pease, C., Daley, P., Pai, M., & Menzies, D. (2022). Chapter 4: Diagnosis of tuberculosis infection. *Canadian Journal of Respiratory, Critical Care, and Sleep Medicine, 6*(sup1), 49–65. https://doi.org/10.1080/24745332.2022.2036503

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

Dasgupta, B., Cimmino, M. A., Maradit-Kremers, H., Schmidt, W. A., Schirmer, M., Salvarani, C., Bachta, A., Dejaco, C., Duftner, C., Jensen, H. S., Duhaut, P., Poór, G., Kaposi, N. P., Mandl, P., Balint, P. V., Schmidt, Z., Iagnocco, A., Nannini, C., Cantini, F., … Matteson, E. L. (2012). 2012 provisional classification criteria for polymyalgia rheumatica: A European League Against Rheumatism/American College of Rheumatology collaborative initiative. *Annals of the Rheumatic Diseases, 71*(4), 484–492. https://doi.org/10.1136/annrheumdis-2011-200329

Dejaco, C., Singh, Y. P., Perel, P., Hutchings, A., Camellino, D., Mackie, S., Abril, A., Bachta, A., Balint, P., Barraclough, K., Bianconi, L., Buttgereit, F., Carsons, S., Ching, D., Cid, M., Cimmino, M., Diamantopoulos, A., Docken, W., Duftner, C., … Dasgupta, B. (2015). 2015 recommendations for the management of polymyalgia rheumatica: A European League Against Rheumatism/American College of Rheumatology collaborative initiative. *Annals of the Rheumatic Diseases, 74*(10), 1799–1807. https://doi.org/10.1136/annrheumdis-2015-207492

Del Galdo, F., Lescoat, A., Conaghan, P. G., Bertoldo, E., Čolić, J., Santiago, T., Suliman, Y. A., Matucci-Cerinic, M., Gabrielli, A., Distler, O., Hoffmann-Vold, A. M., Castellví, I., Balbir-Gurman, A., Vonk, M., Ananyeva, L., Rednic, S., Tarasova, A., Ostojic, P., Boyadzhieva, V., … Allanore, Y. (2025). EULAR recommendations for the treatment of systemic sclerosis: 2023 update. *Annals of the Rheumatic Diseases, 84*(1), 29–40. https://doi.org/10.1136/ard-2024-226430

Fanouriakis, A., Kostopoulou, M., Andersen, J., Aringer, M., Arnaud, L., Bae, S.-C., Boletis, J., Bruce, I. N., Cervera, R., Doria, A., Dörner, T., Furie, R. A., Gladman, D. D., Houssiau, F. A., Inês, L. S., Jayne, D., Kouloumas, M., Kovács, L., Mok, C. C., … Boumpas, D. T. (2024). EULAR recommendations for the management of systemic lupus erythematosus: 2023 update. *Annals of the Rheumatic Diseases, 83*(1), 15–29. https://doi.org/10.1136/ard-2023-224762

FitzGerald, J. D., Dalbeth, N., Mikuls, T., Brignardello-Petersen, R., Guyatt, G., Abeles, A. M., Gelber, A. C., Harrold, L. R., Khanna, D., King, C., Levy, G., Libbey, C., Mount, D., Pillinger, M. H., Rosenthal, A., Singh, J. A., Sims, J. E., Smith, B. J., Wenger, N. S., … Neogi, T. (2020). 2020 American College of Rheumatology guideline for the management of gout. *Arthritis Care & Research, 72*(6), 744–760. https://doi.org/10.1002/acr.24180

Ghebrial, M., Papasotiriou, C., Kadhim, M.-H., & Peschken, C. A. (2026). Jaw claudication progressing to scalp and tongue necrosis in giant cell arteritis [Letter]. *The Journal of Rheumatology*. Advance online publication. https://doi.org/10.3899/jrheum.2026-0614

GlaxoSmithKline Inc. (2025). *Benlysta (belimumab)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00083088.PDF

Government of Ontario. (2025). *Biosimilars*. https://www.ontario.ca/page/biosimilars

Haleon Canada ULC. (2026). *Voltaren Emulgel Extra Strength and Voltaren Emulgel Joint Pain Extra Strength (diclofenac diethylamine gel)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00084171.PDF

Health Canada. (2022, November 1). *Canadian labelling for all JAK inhibitors to include risks of serious heart-related problems, fatal blood clots and cancer* [Public advisory]. https://recalls-rappels.canada.ca/en/alert-recall/canadian-labelling-all-jak-inhibitors-include-risks-serious-heart-related-problems

Indigenous Services Canada. (n.d.). *Drugs and pharmacy benefits for First Nations and Inuit*. Retrieved October 27, 2026, from https://sac-isc.gc.ca/eng/1574784515492/1574784549876

JAMP Pharma Corporation. (2024). *JAMP Methotrexate Tablets (methotrexate tablets USP)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00077942.PDF

Jung, M., & Barra, L. (2015). Pain and swelling in the hands and wrists of a 45-year-old woman. *CMAJ, 187*(1), E53–E54. https://doi.org/10.1503/cmaj.131017

Mukhtyar, C. B., Nikiphorou, E., Bartoletti, A., Dey, M., Ducker, G., Misra, D. P., Monti, S., Studenic, P., Berti, A., Blockmans, D., Brouwer, E., Buttgereit, F., Cannings, K., Cid, M. C., Conway, R., Christ, L., Dejaco, C., Keller, K. K., Kingham, L., … Hellmich, B. (2026). 2025 EULAR recommendations for the management of polymyalgia rheumatica and primary large vessel vasculitis. *Annals of the Rheumatic Diseases*. Advance online publication. https://doi.org/10.1016/j.ard.2026.06.009

Neogi, T., Jansen, T. L. T. A., Dalbeth, N., Fransen, J., Schumacher, H. R., Berendsen, D., Brown, M., Choi, H., Edwards, N. L., Janssens, H. J. E. M., Lioté, F., Naden, R. P., Nuki, G., Ogdie, A., Perez-Ruiz, F., Saag, K., Singh, J. A., Sundy, J. S., Tausche, A.-K., … Taylor, W. J. (2015). 2015 gout classification criteria: An American College of Rheumatology/European League Against Rheumatism collaborative initiative. *Annals of the Rheumatic Diseases, 74*(10), 1789–1798. https://doi.org/10.1136/annrheumdis-2015-208237

Nikolic, R. P. A., Agarwal, A., Pardo Pardo, J., Akhavan, P., Allard-Chamard, H., Barber, C. E. H., Barnabe, C., Jamal, S., Kuriya, B., Legge, A., Pope, J. E., Proulx, L., Richards, D. P., Schieir, O., Taylor-Gjevre, R., Thorne, J. C., Tugwell, P., & Hazlewood, G. S. (2026). Canadian Rheumatology Association living guidelines for rheumatoid arthritis: Update #3 [Letter]. *The Journal of Rheumatology, 53*(8), 932–934. https://doi.org/10.3899/jrheum.2026-0228

Nora Pharma Inc. (2026). *NRA-Celecoxib (celecoxib capsules)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00084512.PDF

Peschken, C. A., Katz, S. J., Silverman, E., Pope, J. E., Fortin, P. R., Pineau, C., Smith, C. D., Arbillaga, H. O., Gladman, D. D., Urowitz, M., Zummer, M., Clarke, A., Bernatsky, S., & Hudson, M. (2009). The 1000 Canadian Faces of Lupus: Determinants of disease outcome in a large multiethnic cohort. *The Journal of Rheumatology, 36*(6), 1200–1208. https://doi.org/10.3899/jrheum.080912

Pharmascience Inc. (2016). *pms-Colchicine (colchicine tablets USP)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00035611.PDF

Public Health Agency of Canada. (2020a). *Gout and other crystal arthropathies in Canada*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/gout-crystal-arthropathies.html

Public Health Agency of Canada. (2020b). *Osteoarthritis in Canada*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/osteoarthritis.html

Public Health Agency of Canada. (2020c). *Rheumatoid arthritis in Canada*. https://www.canada.ca/en/public-health/services/publications/diseases-conditions/rheumatoid-arthritis.html

Public Health Agency of Canada. (2026). *Canadian immunization guide: Part 3. Vaccination of specific populations. Immunization of immunocompromised persons*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-3-vaccination-specific-populations/page-8-immunization-immunocompromised-persons.html

Ramos-Casals, M., Brito-Zerón, P., Bombardieri, S., Bootsma, H., De Vita, S., Dörner, T., Fisher, B. A., Gottenberg, J.-E., Hernandez-Molina, G., Kocher, A., Kostov, B., Kruize, A. A., Mandl, T., Ng, W.-F., Retamozo, S., Seror, R., Shoenfeld, Y., Sisó-Almirall, A., Tzioufas, A. G., … Mariette, X. (2020). EULAR recommendations for the management of Sjögren's syndrome with topical and systemic therapies. *Annals of the Rheumatic Diseases, 79*(1), 3–18. https://doi.org/10.1136/annrheumdis-2019-216114

Smolen, J. S., Edwards, C. J., Konzett, V., Laskou, F., Aletaha, D., Caporali, R., Dörner, T., Hyrich, K. L., Mateus, E., Pope, J. E., Primdahl, J., de Souza, S., Stamm, T., Takeuchi, T., van der Heijde, D., Verschueren, P., Winthrop, K. L., Alvaro-Gracia, J. M., Askling, J., … Landewé, R. B. M. (2026). EULAR recommendations for the management of rheumatoid arthritis with synthetic and biologic disease-modifying antirheumatic drugs: 2025 update. *Annals of the Rheumatic Diseases, 85*(6), 991–1009. https://doi.org/10.1016/j.ard.2026.01.023

Weston, V., & Coakley, G. (2006). Guideline for the management of the hot swollen joint in adults with a particular focus on septic arthritis. *Journal of Antimicrobial Chemotherapy, 58*(3), 492–493. https://doi.org/10.1093/jac/dkl295

35 Skin, Wounds and Burns

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Assess skin accurately on a range of skin tones and prevent moisture damage and skin tears.
2. Assess pressure injury risk, prevent pressure injuries and describe their stages, including deep tissue injury on darker skin.
3. Assess wounds and choose care that matches the cause and the wound's needs, and recognize wound infection.
4. Care for surgical wounds and skin infections, and recognize dehiscence, evisceration and necrotizing infection as emergencies, using the CJMM.
5. Give first aid and early care after a burn, recognize airway threats and support burn recovery.
6. Recognize warning signs of skin cancer and common skin conditions in adults, and teach skin protection.
7. Distinguish RN and RPN roles in skin and wound care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 5	Clinician; Leader	Foundations of Practice
6	Educator; Advocate	Foundations of Practice
7	Professional; Collaborator	Legal Practice; Collaborative Practice

Introduction

Skin is the body's largest organ and the one nurses see and touch most often. Every bath, turn, dressing change and admission assessment is a chance to notice a problem early: a warm, firm patch over a hip, a torn flap of skin on a forearm, a wound that has stopped getting smaller. Many skin injuries that happen during care can be prevented, and those that do occur heal better when they are found, described and treated early. Because so much of this work happens at the bedside, skin and wound care belongs to every nurse.

This chapter is the book's home for skin, wounds and burns. Section 35.1 reviews how skin works and how to assess it accurately on every skin tone, then covers moisture damage and skin tears. Section 35.2 explains how pressure injuries develop and how to prevent, stage and care for them. Section 35.3 covers wound healing, wound assessment, cleansing, dressings and wound infection. The second half of the chapter turns to surgical wounds and skin infections such as cellulitis (section 35.4), burns (section 35.5), and skin cancer and other common skin conditions (section 35.6).

The chapter builds on earlier ones. Scope of practice for registered nurses (RNs) and registered practical nurses (RPNs) is taught in section 1.3, and the Clinical Judgment Measurement Model (CJMM) in section 1.4. Outside Ontario, practical nurses (PNs) are often called licensed practical nurses (LPNs); this chapter uses "the nurse" unless the roles differ. Inflammation, infection prevention and control (IPAC) and sepsis are in Chapter 4, pain in Chapter 5, and recognizing deterioration and SBAR (Situation, Background, Assessment, Recommendation) communication in Chapter 6. Older adults and frailty are in Chapter 8, nutrition in section 24.1, vascular disease in Chapter 19, the diabetic foot in Chapter 22 and continence in Chapter 28.

35.1 Skin Structure and Assessment

How Skin Works

Skin has three layers (Orsted et al., 2025b). The **epidermis** is the thin outer layer. It has no blood vessels of its own and is fed by diffusion from the layer below. Its outermost cells form a waterproof barrier that is shed and replaced all the time; the whole epidermis renews itself over about 35 to 45 days. Melanocytes in its base make melanin, the pigment that gives skin its colour and absorbs ultraviolet light. The **dermis** lies beneath. It holds collagen and elastic fibres, capillaries, nerve endings, hair follicles, and sweat and oil glands. Small ridges called rete pegs lock the epidermis into the dermis and help the layers resist shear. Below the dermis is the **hypodermis**, or subcutaneous tissue, made mostly of fat. It insulates, cushions and stores energy, but its blood supply is poor, so wounds that reach it heal more slowly (Orsted et al., 2025b; Figure 35.1).



Figure 35.1 Cross-section of human skin showing the epidermal layers, dermal structures (hair follicles, glands, nerve endings, blood vessels) and the deeper subcutaneous hypodermis. (credit: “Figure 5.2, Layers of Skin” by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Together these layers protect the body from water loss, chemicals, microorganisms, mechanical force and radiation. Skin also senses touch, pressure, temperature and pain, helps control body temperature through sweating, makes vitamin D and takes part in immune defence (Orsted et al., 2025b).

Skin changes with age. In older adults, the epidermis thins and renews itself about half as fast. The rete pegs flatten, so the layers separate more easily under friction and shear. Collagen falls by about 1% a year and elastin declines, so skin wrinkles and loses its spring. The dermis has fewer blood vessels, the fat layer shrinks, and skin becomes drier and more alkaline, which favours bacterial growth. Older skin also senses light touch and pressure less well. The result is skin that is injured easily, heals slowly and dries out quickly (Orsted et al., 2025b).

Assessing Skin on a Range of Skin Tones

The nurse assesses skin from head to toe at admission and regularly after that, with a focused check of high-risk areas at each contact (Forest-Lalande et al., 2025; Norton et al., 2025). Assessment must work on every skin tone. Methods that depend on spotting redness miss problems on darker skin; Wounds Canada notes that judging by sight alone is a challenge on darkly pigmented skin and is often wrong (Norton et al., 2025). The nurse uses sight, touch and the person's own description together.

- **Lighting:** natural, halogen or indirect light shows colour best; fluorescent light casts a bluish tint that can hide changes (Black & Simende, 2020; Pusey-Reid et al., 2023).
- **Baseline skin tone:** at the first assessment, the nurse records the person's usual skin tone in descriptive words or with a colour chart, not with an ethnic or racial label (Black & Simende, 2020; Norton et al., 2025).
- **Colour:** on darkly pigmented skin, redness may not be visible; it may show instead as a patch darker than the person's usual skin, and changes in pigment are more useful than redness (Black & Simende, 2020; Forest-Lalande et al., 2025). Wet, macerated skin can look grey-white and wrinkled on darker skin (Forest-Lalande et al., 2025). The nurse compares a suspicious area with the same area on the other side of the body or with nearby healthy skin (Pusey-Reid et al., 2023).
- **Touch:** the nurse feels for warmth or coolness, moisture, texture, swelling, and firmness or bogginess compared with nearby skin. Bruising, **induration** (hardening), bogginess and changes in turgor can signal deep damage even when the skin is intact (Orsted et al., 2025a). Palpation is especially important on darker skin, where differences in temperature, consistency and pain guide the assessment (Norton et al., 2025).
- **The person's own words:** the nurse asks whether any area is sore, itchy, burning or different from usual.

- **Turgor:** pinched skin should spring back quickly. Because ageing skin loses elastin, slow recoil is harder to interpret in older adults, so turgor is never used alone to judge hydration (Chapter 3).

The nurse describes any lesion in plain terms: where it is, its size in millimetres or centimetres, its shape and colour compared with the person's usual skin, whether it is raised or flat and dry or weeping, and whether it is new. Warning signs of skin cancer are in section 35.6.

Documentation uses words and measurements, not only labels (Chapter 1). Some services add serial digital photographs to follow a wound over time (Orsted et al., 2025a). Photographs are taken only where employer policy allows, with the person's consent and with privacy protected (Chapter 1).

Moisture and Fragile Skin

Moisture-associated skin damage (MASD) is inflammation and erosion of skin caused by long contact with urine, stool, sweat, wound drainage or stoma output (Forest-Lalande et al., 2025). Wet skin swells, its barrier weakens, its pH rises, and friction and shear damage it more easily. Wounds Canada describes four types:

- **Incontinence-associated dermatitis (IAD):** irritation from urine, stool or both, usually on the perineum, buttocks and upper inner thighs, with inflammation and pain as the main features. Bacteria convert urea in urine to ammonia, which raises skin pH and weakens the skin's protective acid layer.
- **Intertriginous dermatitis:** damage from sweat and friction in skin folds, such as under the breasts or in the groin, often complicated by yeast (*Candida*).
- **Periwound MASD:** damage from drainage to the skin within a few centimetres of a wound.
- **Peristomal MASD:** damage around a stoma (Chapter 25).

Care follows three steps: cleanse gently with a pH-balanced, soap-free cleanser and pat dry; protect with a barrier such as a film-forming spray or a petrolatum, zinc oxide or dimethicone product; and restore the barrier with a moisturizer (Forest-Lalande et al., 2025). Controlling the source of moisture matters most; continence care is in Chapter 28.

A **skin tear** is a wound from trauma caused by mechanical force, such as handling during care or pulling off an adhesive; its depth varies, but it does not go through the subcutaneous layer (Nokaneng et al., 2025). People who need help with daily activities are at higher risk. The International Skin Tear Advisory Panel (ISTAP) classifies tears by the skin flap: Type 1, no skin loss (a linear tear, or a flap that can be laid back over the wound bed); Type 2, partial flap loss (the flap cannot cover the whole bed); and Type 3, total flap loss with the whole wound bed exposed. Moisturizing twice a day has been shown to cut the number of skin tears by half. Gentle handling with glide sheets rather than fingertip grips, long sleeves or shin guards, and silicone tape also help. When a tear happens, the nurse applies gentle pressure, cleanses, eases a living flap back into place and covers it with a silicone dressing marked with an arrow showing which way to remove it. Adhesive closure strips are no longer preferred, and films or hydrocolloids with acrylic or rubber adhesives and iodine-based products are not recommended (Nokaneng et al., 2025).

LIFESPAN CONSIDERATIONS

Skin in Older Adults

- **Thinner, drier skin:** ageing skin tears, bruises and breaks down more easily and heals more slowly (Orsted et al., 2025b). Bathing with warm rather than hot water, using soap-free cleansers and moisturizing twice a day protect it (Nokaneng et al., 2025).
- **Reduced sensation:** an older adult may not feel pressure building on a heel or under a device. The nurse checks these areas rather than waiting for a complaint (Orsted et al., 2025b).
- **Cognitive impairment:** a person with dementia or delirium may not report pain from a pressure area or skin tear. Restlessness, guarding or resisting care can be the first sign (Chapter 8).
- **Medicines:** anticoagulants, antiplatelet drugs, systemic corticosteroids and immunosuppressants can increase bruising or slow healing (BC Provincial Nursing Skin and Wound Committee, 2011; Orsted et al., 2025b). The nurse notes them in the skin assessment.
- **Help with daily activities:** people who need assistance are at higher risk of skin tears, so safe handling matters at every transfer (Nokaneng et al., 2025).

- **Younger adults:** pressure injury is not only a problem of age. Adults of any age with reduced mobility or sensation, such as after spinal cord injury (Chapter 32), are at high risk (Norton et al., 2025).

35.2 Pressure Injuries

How Pressure Injuries Develop

A **pressure injury** is localized damage to the skin and underlying soft tissue, usually over a bony prominence or under a medical or other device. It results from pressure, or pressure combined with shear (Edsberg et al., 2016; Norton et al., 2025). Pressure squeezes small blood vessels between bone and the surface beneath, so tissue is starved of oxygen. Pressure is greatest deep down: next to a bony prominence it can reach three to five times the pressure at the skin surface. Damage can therefore start in muscle and show on the skin later. A pressure injury can begin in as little as two hours, and emergency departments are one setting where this happens (Norton et al., 2025).

Shear is the force created when the skeleton slides one way while the skin is held in place by the surface, as when a person slides down in bed with the head raised. Shear distorts deeper tissue and roughly doubles the harm of pressure. Friction does not cause pressure injuries by itself, but it grips the skin so that shear can occur (Norton et al., 2025). Conditions at the skin where it meets a mattress or chair, sometimes called the **microclimate**, also matter, especially moisture. Moisture weakens the skin and increases friction between skin and sheets, so sweat, incontinence and wound drainage add to the risk (Forest-Lalande et al., 2025; Norton et al., 2025).

Risk comes from both the person and the environment. Wounds Canada lists reduced mobility, sensory loss, incontinence, malnutrition and dehydration, anemia, a previous pressure injury, vascular disease, a reduced level of consciousness, hypoxia, pain, serious chronic illness or the end of life, extremes of age, sedating medicines, polypharmacy and restraint use (Norton et al., 2025).

A **device-related pressure injury** forms under or around a medical device, such as oxygen tubing, a splint or tracheostomy equipment, and usually takes the shape of the device. It is staged with the same system as other pressure injuries. A **mucosal membrane pressure injury** forms on a moist lining, such as the lips or the inside of the nose, where a device has been in use; because of the tissue's structure it cannot be staged (Edsberg et al., 2016; National Pressure Injury Advisory Panel [NPIAP], n.d.).

Pressure injuries remain a problem in Canadian care. A Canadian analysis published in 2004, which pooled prevalence data gathered from 1990 to 2003, estimated an overall pressure ulcer prevalence of 26% across health-care settings, ranging from about 15% in community care to about 30% in non-acute care (Woodbury & Houghton, 2004). Wounds Canada, citing that study, reports that about 70% of these wounds were considered preventable and that pressure injury incidence in Canada has not decreased significantly (Norton et al., 2025). The Canadian Institute for Health Information (CIHI) tracks two indicators for long-term care residents: the percentage with a newly occurring stage 2 to 4 pressure ulcer, and the percentage with a stage 2 to 4 pressure ulcer that has become worse. Both come from standardized interRAI resident assessments and are adjusted for resident characteristics (CIHI, n.d.-a, n.d.-b). Wounds Canada notes higher rates of severe pressure injuries in people with darkly pigmented skin (Norton et al., 2025), and these higher rates are partly due to difficulty detecting injuries at earlier stages (Black & Simende, 2020). Early signs are harder to see on darker skin, so assessment that relies on redness delays detection. Using methods that work on every skin tone is part of equitable care (Chapter 2).

Prevention

Prevention starts at the first contact and continues for as long as the person is at risk.

- **Risk assessment:** Wounds Canada recommends screening when a person enters any care setting and again as risk, acuity or condition changes (Norton et al., 2025). Validated tools include the Braden Scale, the Norton Scale and the Waterlow Score. The employer chooses the tool for the setting, and no score replaces clinical judgment: a person with a "low-risk" score who cannot move after sedation is still at risk.
- **Skin checks:** the nurse inspects and palpates bony areas such as the sacrum, coccyx, heels, hips, elbows and back of the head, and skin under and around every device, whenever the person is repositioned and as policy requires (Norton et al., 2025).

- **Repositioning:** each person needs a written schedule matched to their condition. Wounds Canada gives the example of repositioning every 2 to 4 hours in bed and shifting weight every 15 minutes when sitting. Lift sheets and wedges reduce friction and shear, and keeping the head of the bed below about 30 to 35 degrees, unless the person's condition requires it to be higher, limits sliding (Norton et al., 2025).
- **Heels:** heels carry high pressure over a small area. **Offloading** means removing pressure from an area completely. Heels are managed separately from the mattress and floated off the bed; a wedge-shaped cushion or device that suspends the heels works better than a standard pillow, and the Achilles tendon is protected too (Norton et al., 2025).
- **Support surfaces:** a **support surface** is a mattress, overlay or cushion designed to redistribute pressure. It reduces pressure but does not replace repositioning. A person at risk who sits needs a pressure-redistributing cushion, and a person who uses a wheelchair needs a seating assessment by a skilled clinician such as an occupational therapist (Norton et al., 2025).
- **Prophylactic dressings:** some programs place multilayer silicone foam dressings over the sacrum or heels of people at risk to reduce friction and shear (Norton et al., 2025). The skin under them is still checked.
- **Moisture:** prompt cleansing and skin protection after incontinence or sweating, as described in section 35.1, and an individualized bowel and bladder plan (Chapter 28).
- **Nutrition and hydration:** screening with a validated tool and a dietitian referral when intake is poor (Norton et al., 2025); see section 24.1.
- **Mobility and teaching:** the nurse encourages safe movement, involves physiotherapy and occupational therapy, and teaches the person and family why position changes matter and how to check skin.

Staging and Care

Wounds Canada recommends classifying pressure injuries with the revised staging system of the National Pressure Injury Advisory Panel (NPIAP), which grades injuries by the deepest tissue damaged (Edsberg et al., 2016; Norton et al., 2025). Wounds Canada uses the paired term "category/stage"; this chapter uses "stage", as NPIAP does. Only pressure injuries are staged with this system; skin tears and burns have their own classifications, and MASD is not staged (Edsberg et al., 2016). Table 35.1 summarizes the stages. Three rules guide staging: (Figure 35.2)

- **No reverse staging:** the stage describes the deepest damage when the injury was first assessed. A stage 3 injury that fills with new tissue is documented as a healing stage 3, never as a stage 2 (Norton et al., 2025).
- **Unstageable pressure injury:** the base is hidden by **slough** (soft yellow, tan or grey dead tissue) or **eschar** (dry, dark, leathery dead tissue), so depth cannot be judged. Once the covering is removed, the injury will prove to be stage 3 or 4. Stable eschar on a heel or a limb with poor blood flow, meaning dry, attached and intact with no redness or softness around it, is not softened or removed (NPIAP, n.d.).
- **Deep tissue pressure injury (DTPI):** damage that starts at the bone–muscle interface and shows as persistent, non-blanching discolouration of intact or broken skin, or a blood-filled blister. Changes in pain and temperature often appear before any colour change. It may resolve or may open quickly to reveal deeper damage (NPIAP, n.d.). On darkly pigmented skin, a DTPI does not always look purple or maroon; in one study of African American patients, most DTPIs looked purple, but others looked grey, black, brown, blue or maroon (Black & Simende, 2020). The nurse therefore also relies on touch and on the person's report of pain.



Figure 35.2 Stage 1 pressure injury: intact skin with localized, non-blanchable erythema, illustrated in clinical photograph (a) and comparative cross-sections of light skin (b) and dark skin (c). (credit: "Figure 28.5, Stage 1 Pressure Injury" by OpenStax, Medical-Surgical Nursing, CC BY 4.0 / CC BY-NC-SA 4.0)



Figure 35.3 Stage 2 pressure injury: partial-thickness skin loss with exposed dermis, showing a viable, pink/red, moist wound bed without slough or granulation tissue. (credit: "Figure 28.6, Stage 2 Pressure Injury" by OpenStax, Medical-Surgical Nursing, CC BY 4.0 / CC BY-NC-SA 4.0)



Figure 35.4 Stage 3 pressure injury: full-thickness skin loss with visible subcutaneous fat in the ulcer crater; bone, tendon and muscle are not exposed. (credit: "Figure 28.7, Stage 3 Pressure Injury" by OpenStax, Medical-Surgical Nursing, CC BY 4.0 / CC BY-NC-SA 4.0)



Figure 35.5 Stage 4 pressure injury: full-thickness skin and tissue loss with directly exposed and palpable fascia, muscle, tendon or bone. (credit: "Figure 28.8, Stage 4 Pressure Injury" by OpenStax, Medical-Surgical Nursing, CC BY 4.0 / CC BY-NC-SA 4.0)



Figure 35.6 (a) Unstageable pressure injury with the true depth of tissue damage obscured by slough and eschar, alongside (b) a deep tissue pressure injury (DTPI) on a heel presenting as persistent, non-blanchable deep red/purple discoloration. (credit: panel [a] from "Figure 28.9, Unstageable Pressure Injury" and panel [b] from "Figure 28.10, Deep Tissue Pressure Injury" by OpenStax, Medical-Surgical Nursing, CC BY 4.0 / CC BY-NC-SA 4.0)

Care at every stage starts with removing the cause. The nurse keeps all pressure off the injury, floats injured heels, and addresses shear, moisture and nutrition; goals are set with the person and family (Norton et al., 2025). Local wound care then follows the wound bed preparation approach in section 35.3. Stage 3, stage 4 and unstageable injuries, and any injury that is not improving, are referred to the wound care team, which may include a Nurse Specialized in Wound, Ostomy and Continence (NSWOC), a dietitian and an occupational therapist. Surgical closure may be an option for some stage 3 and 4 injuries if it fits the person's goals (Norton et al., 2025). A wound that is not 20% to 40% smaller by week 4 is unlikely to heal by week 12 and is reassessed (Norton et al., 2025; Sibbald et al., 2022).

Documentation records the location, stage, size, wound bed, drainage, edges, surrounding skin, pain, the person's baseline skin tone, the prevention plan and who was notified, and whether the injury was present on admission (Norton et al., 2025; Chapter 1).

Table 35.1 Pressure injury stages (based on Edsberg et al., 2016; NPIAP, n.d.; Norton et al., 2025; Black & Simende, 2020)

Stage	What the nurse sees and feels	On darker skin tones	Care focus
Stage 1	Intact skin with a local area of colour change that does not blanch; the area may feel warmer, cooler, firmer or softer than nearby skin, and may be painful	Redness may not show; look for a patch darker than the person's usual skin and rely on temperature, firmness and pain compared with the other side	Offload completely, protect the skin, manage moisture, reassess often as policy requires
Stage 2	Shallow, partial-thickness loss of skin with exposed dermis; moist pink or red base, or an intact or broken fluid-filled blister; no fat, slough or eschar	Judge depth and the wound base as for any skin; redness in the surrounding skin may not show, so compare warmth and firmness with nearby skin	Offload, keep the wound moist and protected, control incontinence and moisture so the wound is not mistaken for or worsened by MASD

Stage	What the nurse sees and feels	On darker skin tones	Care focus
Stage 3	Full-thickness skin loss with fat visible; slough or eschar may be present; undermining and tunnelling may occur; no bone, tendon or muscle exposed	Depth is judged the same way; check the surrounding skin for warmth, firmness and colour change against baseline	Offload, follow wound bed preparation, manage drainage and dead space, refer to the wound care team
Stage 4	Full-thickness loss of skin and tissue with bone, cartilage, tendon, ligament, muscle or fascia visible or felt; slough, eschar, rolled edges, undermining or tunnelling common	Assess as for stage 3; watch for signs of deep infection	Offload, refer to the wound care team, watch for bone infection, consider surgical options with the person
Unstageable	Full-thickness loss whose depth is hidden by slough or eschar	Surrounding colour change may be subtle; touch and pain guide assessment	Do not stage until the base is visible; leave stable dry heel eschar in place; refer
Deep tissue pressure injury	Persistent, non-blanching deep red, maroon or purple area, or a blood-filled blister, over intact or broken skin; pain and temperature change often come first	May not look purple or maroon; may look grey, brown, black or blue, or be found mainly as a painful, firm, boggy, warm or cool area	Offload completely, protect, monitor closely for rapid change, report and document

PRACTICE STORY

Feel the Heel

Names and details are fictional; this is a composite story.

Nurse: Ruth Asamoah, RPN. Years in practice: 6. Setting: medical unit, Ontario.

Mr. Winston Sterling was 74 and on day three of treatment for pneumonia. He was a retired transit mechanic, a Black man with deep brown skin, and he hated being in bed. His Braden score that morning put him at moderate risk, and the night nurse's note read "skin intact, no redness."

When I helped him turn after breakfast, I did what I always do: I took his socks off and held each heel in my hand. The left heel felt like the right one. The right heel did not. It was warmer, and there was a firm, slightly spongy area about the size of a loonie on the back of the heel. In the window light, the skin there looked a shade darker than the rest of his heel, almost plum. Under the ceiling lights, I would have walked past it.

"Does that hurt?" I asked. He said it had ached all night, "like a bruise," but he hadn't wanted to bother anyone.

I didn't know exactly what it was yet, but I knew it was new, and I knew pressure was the likely cause. I floated both heels with the heel-suspension cushion our unit stocks, checked that his Achilles tendons were free, and lowered the head of the bed as far as his breathing allowed. Then I found Lindiwe, the RN on our team, and told her what I had felt, seen and heard, and that I had offloaded the heel. She came and assessed it with me, and we sent a referral to our wound care nurse that morning. I charted the size, colour against his usual skin tone, warmth, firmness, his pain and the actions taken.

The wound care nurse saw him that afternoon and documented a suspected deep tissue pressure injury. Over the next week the area stayed closed. Mr. Sterling started calling me "the heel detective."

Reflect: What helped Ruth find this injury when an earlier check had not? Using authority, competence and context (section 1.3), which parts of this care were within Ruth's own practice, and when did she need to consult the RN?

35.3 Wound Healing and Wound Care

How Wounds Heal

Healing follows four overlapping phases (Orsted et al., 2025b):

- **Hemostasis:** within minutes, platelets plug damaged vessels, a clot forms and growth factors are released.
- **Inflammation:** for up to about four days, white blood cells clear debris and bacteria. Warmth, swelling, pain and colour change around a new wound are expected at this stage (Chapter 4).
- **Proliferation:** from about day 4 to about day 21 in an acute wound, fibroblasts lay down collagen and new capillaries grow, forming **granulation tissue**, the moist, bumpy new connective tissue that fills a wound from its base. The wound then contracts,

and new epithelial cells cover the surface. Healthy granulation forms a firm, level base; granulation that is bright red, fragile and bleeds easily can signal infection (Sibbald et al., 2022).

- **Remodelling:** collagen is reorganized for up to two years. A healed scar regains only about 70% to 80% of the strength of uninjured skin.

Wounds close in one of three ways (BC Provincial Nursing Skin and Wound Committee, 2011). In **primary intention**, the wound edges are brought together with sutures, staples or tape and heal without the need to fill with granulation tissue, as in most surgical incisions. In **secondary intention**, the wound is left open and fills with granulation tissue from the base up, as most pressure injuries do. In **delayed primary intention**, or delayed primary closure, a contaminated wound is left open for about 4 to 6 days and then closed. Surgical wounds are covered in section 35.4.

An acute wound moves through the phases in order once its cause is removed. A **chronic wound**, also called a wound of long duration, stalls, usually in the inflammatory phase, because something that blocks healing has not been corrected (Orsted et al., 2025b). Common barriers include:

- poor blood supply and oxygen (Chapter 19);
- high blood glucose (Chapter 22);
- poor intake of protein, energy and micronutrients such as iron, zinc and vitamins A and C (section 24.1);
- persistent bacteria and infection;
- smoking;
- pressure that is not offloaded;
- some medicines, including systemic corticosteroids, anticoagulants, antiplatelet drugs, immunosuppressants and cancer drugs (BC Provincial Nursing Skin and Wound Committee, 2011; Orsted et al., 2025a, 2025b).

Assessing a Wound

Wound bed preparation is a framework for wound care that starts with the whole person, not the dressing. Its first steps are to identify and treat the cause, address the person's concerns such as pain and quality of life, and decide whether the wound can heal (Sibbald et al., 2022). A wound is:

- **healable** when its cause can be corrected and its blood supply is adequate;
- **maintenance**, or non-healing, when the blood supply is adequate but the person cannot follow the plan or lacks the resources to do so;
- **non-healable** when the blood supply is inadequate or the cause cannot be corrected.

This decision sets the goal: closure for a healable wound, and stability, comfort and infection control for the others (Orsted et al., 2025a; Sibbald et al., 2022).

The nurse then assesses the wound itself, the same way each time, using the employer's assessment form (Orsted et al., 2025a):

- **Location:** marked on a body map, with several wounds numbered.
- **Size:** length, width and depth in centimetres, measured with the same method and position at each assessment so that change is real.
- **Undermining and tunnelling: undermining** is tissue destroyed under intact skin at the wound edge, forming a shelf; **tunnelling** is a narrow channel from the wound into deeper tissue. Both are measured and their direction recorded.
- **Wound bed:** the type of tissue present (granulation, slough, eschar or new epithelium), often as approximate percentages.
- **Exudate: exudate** is fluid that drains from a wound; the nurse records its amount, type and colour.
- **Edges and surrounding skin:** whether the edges are attached or rolled; and maceration, induration, edema, warmth and colour change compared with the person's baseline.
- **Pain and odour:** pain at rest and during dressing changes, and odour after cleansing. Pain that is new or increasing can signal infection or deterioration (Orsted et al., 2025a).

A wound that is shrinking by 20% to 40% by week 4 is on track; one that is not is reassessed with the team (Sibbald et al., 2022).

Cleansing and Dressings

Cleansing removes debris and loose bacteria with as little harm to new tissue as possible. Options include sterile normal saline, sterile water and potable (drinkable) tap water, at body temperature. Irrigation at 4 to 15 pounds per square inch (psi), roughly 28 to 103 kPa, is effective and generally safe, while scrubbing with gauze is discouraged. When infection is suspected, a cleanser with an antiseptic, such as polyhexamethylene biguanide (PHMB), a hypochlorous acid solution or povidone-iodine, may be used, short term and with caution, because antiseptics can also damage healthy cells (Orsted et al., 2025a). The surrounding skin is also cleansed well and patted dry (Forest-Lalande et al., 2025). The order and employer policy set the solution.

No single dressing suits every wound. The choice depends on the goal (healable, maintenance or non-healable), the phase of healing, the amount of drainage, signs of infection, and the person's comfort, lifestyle, skills and costs (Orsted et al., 2025a). In a healable wound the aim is **moisture balance**: enough moisture for cells to move across the wound bed, but not so much that the edges macerate. A dry wound needs a dressing that adds moisture, and a wet wound needs one that absorbs (Orsted et al., 2025a; Sibbald et al., 2022). Table 35.2 matches dressing categories to wound needs.

Maintenance and non-healable wounds are handled differently. Because moisture can encourage bacterial overgrowth in a wound that cannot heal, the aim is to reduce moisture and bacteria with low-toxicity antiseptics such as povidone-iodine, chlorhexidine or PHMB, and to remove only loose slough conservatively (Sibbald et al., 2022). Dry, stable eschar on a heel or a limb with poor blood flow is kept dry and left in place (Norton et al., 2025; NPIAP, n.d.).

At a dressing change, the nurse follows the employer's hand hygiene and technique (Chapter 4), offers analgesia beforehand when changes are painful, and removes dressings gently (Chapter 5). Dressing choice itself is a key to pain control at removal and application (Orsted et al., 2025a). The nurse protects the surrounding skin, labels and documents the change, and gives a product a fair trial before switching (Orsted et al., 2025a). Cleansing, irrigating or packing a wound below the dermis is a controlled act. In Ontario, RNs and RPNs may perform it with an order, or initiate it without one where the setting allows; nurses in public hospitals cannot initiate controlled acts. The nurse also needs the competence, and employer policy sets the context (College of Nurses of Ontario [CNO], 2025; section 1.3).

Table 35.2 Matching the dressing to the wound (based on Orsted et al., 2025a; Sibbald et al., 2022; Nokaneng et al., 2025; Norton et al., 2025)

Wound need	Dressing category	Examples of when used	Nursing points
Add moisture	Hydrogels	Dry wound bed in a healable wound; helps soften dry slough	Protect surrounding skin from maceration; not used for MASD; not for stable heel eschar or a non-healable wound
Keep moisture in and protect	Films, hydrocolloids, contact layers	Shallow wounds with little drainage	Avoid films and hydrocolloids with acrylic or rubber adhesives on skin tears or skin at high risk of tearing; check edges for rolling or lifting
Absorb drainage	Foams, alginates, gelling fibres, superabsorbents	Moderate to heavy drainage; fibres can loosely fill dead space	Change before the dressing leaks; never pack tightly; record the amount and type of drainage
Reduce bacteria	Antimicrobial dressings and antiseptics (silver, iodine products such as povidone-iodine, PHMB, chlorhexidine)	Local infection in a healable wound; ongoing bacterial control in maintenance and non-healable wounds	Use for a set trial and reassess; iodine is not used on skin tears; report signs of spreading infection rather than relying on a dressing
Protect fragile skin and prevent injury	Silicone contact layers and silicone foams	Skin tears; prophylaxis over the sacrum or heels in people at risk	Mark the direction of removal on skin tear dressings; lift the dressing to check the skin underneath as policy requires

Wound need	Dressing category	Examples of when used	Nursing points
Reduce moisture in a non-healable wound	Antiseptic tulle, povidone-iodine, PHMB gauze	Wounds with inadequate blood supply or a cause that cannot be corrected	Goal is a dry, stable, comfortable wound; leave stable dry eschar in place

Wound Infection

All open wounds contain bacteria. Wounds Canada describes a continuum from contamination and colonization to local infection, spreading infection and systemic infection (Orsted et al., 2025a):

- **Local infection** is confined to the wound. Its signs may be subtle, especially in wounds of long duration: delayed healing, more drainage, granulation that is bright red and bleeds easily, and bridges of tissue across the wound. Classic signs are redness, warmth, swelling, pus, wound breakdown, new or increasing pain and increasing odour; redness can be hard to see on darker skin or with edema (Orsted et al., 2025a; Sibbald et al., 2022).
- **Spreading infection** extends beyond the wound: inflammation more than 2 cm from the edge, spreading hardness, or streaks along lymph vessels (lymphangitis). Cellulitis is covered in section 35.4.
- **Systemic infection** adds malaise, loss of appetite and fever, and can progress to sepsis (Chapter 4).

Infection is diagnosed mainly from these clinical signs. The nurse reports new or increasing pain, a wound that deteriorates or stops improving, and any sign of spreading infection promptly, using SBAR (Chapter 6). Signs of systemic infection or sepsis call for immediate escalation (Chapter 4). When the team needs laboratory confirmation, a wound swab is collected as ordered. Wounds Canada prefers the Levine technique: the nurse cleanses the wound first, moistens the swab with sterile saline if the wound is dry, then presses the swab firmly into the cleanest viable tissue and rotates it, avoiding pus, slough and dead tissue (Orsted et al., 2025a).

GOING DEEPER

Biofilm, Infection and the Wound Swab

Required for RN students; optional for PN students.

Biofilm is a complex community of bacteria and fungi held together in a thick, slimy coating made of sugars and proteins. Wounds Canada reports biofilm in roughly 60% to 90% of wounds of long duration, where it delays healing (Orsted et al., 2025a). A standard wound culture cannot detect biofilm. Clues include a wound that fails to respond to appropriate antibiotics, delayed healing that returns once antibiotics stop, fragile overgrown granulation, increased drainage and low-grade inflammation.

The wound bed preparation authors offer two memory aids for separating surface from deeper infection (Sibbald et al., 2022). **NERDS** signals local infection: Nonhealing, Exudate increase, Red friable granulation, Debris, Smell. **STONEES** signals deeper or surrounding infection: Size increase, Temperature increase, Os (probing to bone), New areas of breakdown, Exudate increase, Erythema or Edema, Smell. Three or more NERDS signs suggest topical antimicrobial treatment; three or more STONEES signs suggest the prescriber should consider systemic antibiotics. Because colour change can be hard to see on darker skin or with edema, warmth is checked against the matching skin on the other side.

Wounds Canada directs that a swab is not taken from pus, slough or dead tissue; the Levine technique samples the cleanest area after the wound is cleansed (Orsted et al., 2025a). The swab label includes the site, time, collector and relevant history, such as current antibiotics or diabetes.

PATIENT EDUCATION

Caring for a Wound at Home

- **Clean hands first:** wash your hands before and after touching your wound or dressing. Keep dressing supplies clean and dry.
- **Follow your dressing plan:** change the dressing as your nurse showed you. Ask before showering or soaking the wound.
- **Take pressure off:** if your wound is on a heel, hip or tailbone, keep weight off it and change position often.
- **Eat and drink well:** protein, fruit, vegetables and fluids help skin repair (section 24.1). If you have diabetes, keeping your blood sugar in your target range helps your wound heal (Chapter 22).
- **Stop smoking if you can:** smoking slows healing. Ask your team about help to quit.
- **Manage pain:** take pain medicine as advised before dressing changes if they hurt, and tell your nurse if pain is getting worse.

- **Call your nurse or health-care provider if:** the wound is more painful, warm or swollen; there is pus, a bad smell or more drainage; a change in colour is spreading around the wound; the wound is getting bigger; or you feel feverish or unwell.
- **Call 9-1-1 if:** you feel very unwell, confused, short of breath or faint.
- **Keep follow-up visits,** even if the wound looks better.

35.4 Surgical Wounds and Skin Infections

A surgical incision is a planned wound, yet it can still become infected, open or heal slowly, and a small crack in the skin can let in a spreading infection. This section covers incision care, complications that need fast action and common skin infections. Infection control, antimicrobial resistance and sepsis are taught in Chapter 4, and perioperative care in Chapter 7.

Surgical Wounds

Most incisions are closed with sutures, staples, skin glue or adhesive strips and heal by primary intention (section 35.3). Wounds Canada's 2025 recommendations give the nurse a timeline to check against. The edges should be sealed by new epithelium along the whole incision by about day 4. Between days 5 and 9, the nurse should be able to feel a **healing ridge**, a firm band of new collagen under the full length of the incision. A missing ridge, or any drainage after day 9, is not expected and is reported (Tecson et al., 2025). A complete assessment looks at the incision line and the skin around it (Figure 35.7).

Figure 35.7 A surgical incision closed with metal staples seven days after surgery, healing by primary intention with well-approximated edges. (credit: “Surgical staples2” by Llywrch/Wikimedia Commons, CC BY-SA 2.5)

In the first days, mild swelling, warmth and tenderness are part of normal inflammation. Colour change is easy to see on lighter skin but may be hard to see on darker skin, so the nurse feels for warmth and firmness, compares the area with nearby skin and asks the person what feels different (Wounds International, 2023). A closed incision usually needs only a dry, sterile cover dressing for the first 24 to 48 hours. Most patients may shower after 48 hours, but the surgeon decides. Sutures and staples usually stay in for 7 to 10 days and are removed sometime between days 9 and 14, later if healing is slow (Tecson et al., 2025).

A **surgical site infection (SSI)** is an infection of the incision or of the deeper tissues or organ space after an operation. Wounds Canada notes that superficial SSIs are watched for 30 days after surgery, deeper SSIs for 30 to 90 days depending on the operation, and infections around implants such as a hip or knee replacement for up to a year (Tecson et al., 2025). Signs include pain or tenderness that is new or increasing (pain or tenderness by itself can signal infection), spreading swelling and warmth, cloudy or foul-smelling drainage, fever and breakdown of the incision (British Columbia Provincial Nursing Skin and Wound Committee, 2011; Tecson et al., 2025). Confirming infection and recognizing sepsis are covered in Chapter 4.

Dehiscence is a partial or complete separation of the edges of a closed incision. It can expose the tissue beneath or allow organs to push through. Wounds Canada describes it as most likely between days 5 and 8, often around day 7 (Tecson et al., 2025), and an international consensus places most cases between days 4 and 14 (World Union of Wound Healing Societies [WUWHS], 2018). Risk factors include obesity, diabetes, smoking, emergency surgery, age over 65, a long operation, low body temperature during surgery and wound infection (WUWHS, 2018). Coughing, abdominal distension and ileus raise the pressure on an abdominal incision (Downey, 2020). Warning signs are a sudden rise in pain, new pink, watery (serosanguineous) drainage, swelling or a fluid collection under the incision, and no healing ridge by days 5 to 9. Patients sometimes say they felt something "give way" when they coughed

Figure 35.8 Dehiscence of an inguinal hernia repair incision, with separated wound edges and a red granulation bed healing by secondary intention. (credit: "Wound Dehiscence post inguinal hernia repair 2014-05-27 00-46" by Phoenix119/Wikimedia Commons, CC BY-SA 3.0)

(Downey, 2020; WUWHS, 2018). Even a small opening is reported, and a separated incision is never irrigated before the nurse has spoken with the surgeon (Tecson et al., 2025; Figure 35.8).

Evisceration is the protrusion of organs, such as bowel, through a separated abdominal incision. It is a surgical emergency (Tecson et al., 2025). A Canadian provincial guideline directs the nurse to stay with the patient and have the physician or nurse practitioner (NP) called at once (9-1-1 outside hospital), cover any exposed tissue with a dressing wet with warm sterile normal saline, place the patient in a low Fowler's position (20 degrees or less) with the knees bent, never try to push the organs back, and watch vital signs for shock until help arrives (British Columbia Provincial Nursing Skin and Wound Committee, 2011). Oral intake is withheld in case surgery is needed (Downey, 2020). The nurse calls the rapid response team if signs of shock appear (Chapter 6; Table 35.3).

Table 35.3 Surgical wound problems and first actions (British Columbia Provincial Nursing Skin and Wound Committee, 2011; Downey, 2020; Tecson et al., 2025; WUWHS, 2018)

Problem	What the nurse sees	First actions	Who to tell
Healing slower than expected	No healing ridge by days 5 to 9; drainage still present after day 9; edges not fully sealed	Measure and describe the incision; check nutrition, glucose and other factors that slow healing (section 35.3)	Surgeon or most responsible provider; wound care nurse if the employer has one
Possible surgical site infection	New or increasing pain; spreading warmth and swelling; colour change (red on lighter skin; on darker skin, a patch darker than the usual skin or no visible change); cloudy or foul-smelling drainage; fever	Assess vital signs and the whole incision; document drainage; follow the infection prevention steps in Chapter 4	Surgeon promptly; rapid response team if signs of sepsis
Dehiscence	Edges pulling apart; sudden pink, watery drainage; patient felt something give way	Cover with sterile gauze moistened with sterile normal saline; low Fowler's position, knees bent; do not irrigate before speaking with the surgeon; check vital signs	Surgeon at once
Evisceration	Bowel or other organs visible through the opened incision	Stay with the patient and call for help; cover with a dressing wet with warm sterile normal saline; do not push organs back; low Fowler's position, knees bent; nothing by mouth; watch for shock	Surgeon or NP at once; rapid response team if unstable

Negative pressure wound therapy (NPWT) uses a sealed dressing connected by tubing to a pump that applies suction to a wound. It is widely used for open wounds, including dehisced wounds that are deep or produce a lot of exudate, and Wounds Canada advises considering it as a first-line treatment for a dehisced breastbone (sternal) wound after cardiac surgery (Tecson et al., 2025; WUWHS, 2018). A special dressing may also be placed over a closed incision in the operating room for patients at high risk of complications and left in place for 5 to 7 days. NPWT is not placed directly over exposed organs, blood vessels, nerves or bowel joins (anastomoses), and each device has its own warnings (WUWHS, 2018; Figure 35.9).

Cellulitis and Other Skin and Soft Tissue Infections

Cellulitis is a spreading infection of the skin and the tissue just beneath it. Most cases are caused by streptococci; *Staphylococcus aureus* is more likely when there is an open wound, a penetrating injury or injection drug use (Stevens et al., 2014). The affected area

is warm, swollen and tender, and a change in colour spreads outward. On lighter skin it looks red. On darker skin, redness may not be visible; the change may show as a patch darker than the person's usual skin or be hard to see, and the skin may feel tighter to the touch (Black & Simende, 2020; Wounds International, 2023). Some people also have fever, a fast heart rate or confusion (Stevens et al., 2014; Figure 35.10).

People who have had cellulitis often have it again. Edema, obesity, eczema, venous insufficiency and cracked, scaly or moist skin between the toes all raise the risk (Stevens et al., 2014). The diagnosis is usually clinical, and blood cultures are not routinely needed (Stevens et al., 2014).

The nurse assesses the whole limb and compares it with the other side. A UK consensus advises marking the edge of the affected area and writing the date beside it when possible (British Lymphology Society & Lymphoedema Support Network, 2016). Because colour may not show the edge on darker skin, the nurse also records the extent of warmth, swelling and tenderness. Elevating the limb and treating edema and toe-web problems are recommended (Stevens et al., 2014). A person with typical cellulitis and no signs of systemic illness usually receives an oral antibiotic active against streptococci, such as a penicillin or a first-generation cephalosporin (for example, cephalexin). Intravenous (IV) antibiotics, hospital care and, in some cases, coverage for methicillin-resistant *S. aureus* (MRSA) are considered when there are signs of systemic illness, a penetrating injury or injection drug use (Stevens et al., 2014; Chapter 4). Low blood pressure, new confusion or a rising heart rate are escalated as possible sepsis.

Figure 35.9 Negative pressure wound therapy applied over a midline abdominal surgical incision, with a sealed foam dressing and suction tubing kept separate from the adjacent colostomy pouch. (credit: "Colostomy with wound vacuum (negative-pressure wound therapy) applied" by Hu Nhu/Wikimedia Commons, CC BY 4.0)

Figure 35.10 Cellulitis of the toes and forefoot, with spreading redness and swelling of the skin.

An **abscess** is a walled-off collection of pus. Its main treatment is incision and drainage; antibiotics are added for people with systemic signs or weakened immune systems (Stevens et al., 2014).

A **necrotizing soft tissue infection (NSTI)** destroys the deeper tissues, such as the fat and the fascia around the muscles, and can be fatal. Invasive group A streptococcal disease, which causes about 35% to 40% of these infections, has been rising in Canada (Deb et al., 2024). At first it can look like ordinary cellulitis. Red flags are pain that seems out of proportion to what the nurse can see, rapid spread, hard, wooden-feeling tissue beyond the visible skin change, blisters (bullae), dusky or dead-looking skin, a crackling feel under the skin (crepitus), confusion and signs of shock (Deb et al., 2024; Stevens et al., 2014). Blisters and crepitus are late signs, so their absence does not rule out NSTI. Because death is directly related to the time to surgery, the nurse escalates at once; urgent surgical removal of dead tissue is the main treatment, and imaging should not delay it (Deb et al., 2024). Cases caused by group A streptococci are reported to public health.

CLINICAL JUDGMENT

Red and Spreading

Names and details are fictional; this is a composite story.

Raymond Tessier, 58, has type 2 diabetes and was admitted 18 hours ago with cellulitis of the right lower leg. He is receiving IV antibiotics. The edge of the affected area was marked and dated on admission.

- **Recognize cues:** At 0300, he rates his leg pain 10 out of 10, up from 4, and says the pain "goes all the way up." The skin above the marked edge feels hard and is darker and dusky in two places. His blood pressure is 88/50 mm Hg (usually 134/80), heart rate 124, and he is slow to answer questions.
- **Analyze cues:** Pain far worse than the skin findings, spread past the marked edge despite antibiotics, hard tissue and low blood pressure do not fit improving cellulitis. They fit a necrotizing soft tissue infection with septic shock.
- **Prioritize hypotheses:** Septic shock from a necrotizing infection is the most urgent problem; poor glucose control and pain matter but come after.
- **Generate solutions:** Get immediate help, support circulation as ordered and arrange an urgent surgical assessment.
- **Take action:** The nurse calls the rapid response team, stays with Mr. Tessier, gives the ordered IV fluid bolus, checks his capillary blood glucose and gives a situation, background, assessment, recommendation (SBAR) report (Chapter 6) that names the concern: "I am worried this is necrotizing fasciitis." The team calls the surgeon.
- **Evaluate outcomes:** The nurse rechecks blood pressure, heart rate, mental status and the leg every 15 minutes until he goes to the operating room, and documents the times of each finding and call.

Reflect: Which cue would you have found first, and why does the time of escalation matter so much in this infection?

35.5 Burns

A **burn** is damage to the skin or deeper tissues caused by heat, chemicals, electricity, radiation, friction or extreme cold. A small scald can be cared for at home, while a large burn affects every body system. This section covers how burns are classified, first aid and emergency care, and nursing care through recovery.

Types and Depth of Burns

Most burns come from heat: scalds from hot liquids, steam or grease, contact with hot objects, and flame or flash. Electrical burns come from current flowing through the body. Chemical burns depend on the agent, its strength and the contact time; alkalis can cause deeper damage than acids. Radiation burns include sunburn and skin reactions to radiation therapy (Wallace et al., 2025).

Wounds Canada's 2025 burn chapter, drawing on national fire, injury-cost and emergency department data, reports about 220 fire-related deaths a year in Canada from 2011 to 2020 and burn and fire injury costs of $299 million in 2018. In 2013, just over half (52.3%) of the burns recorded by the Canadian Hospitals Injury Reporting and Prevention Program (CHIRPP), an emergency department injury surveillance system, were scalds. The same chapter cites Canadian data (2001 to 2006, outside Quebec) showing disproportionately high age-standardized rates of hospitalization for fire-related injuries among children and youth aged 0 to 19 in areas where at least 33% of residents identified as First Nations or Métis, especially First Nations and Métis children under 10 (Wallace et al., 2025). These differences reflect housing, income and access to services, not the people themselves (Chapter 2). This book follows the OCAP® principles (ownership, control, access and possession) for First Nations data (Chapter 2).

Burn depth is described by the layers of skin destroyed (Table 35.4; Figure 35.11).



Figure 35.11 Classification of burn depth: superficial (first degree, affecting the epidermis), partial thickness (second degree, extending into the dermis with blisters), and full thickness (third degree, destroying all epidermal and dermal layers into subcutaneous tissue). (credit: "Figure 8.14, Burn Depth" by Persian Poet Gal/OpenStax, Clinical Nursing Skills, CC BY 3.0)] A **superficial burn** involves only the epidermis. A **partial-thickness burn** extends into the dermis: a superficial partial-thickness burn involves the upper dermis, and a deep partial-thickness burn reaches deeper into it. A **full-thickness burn** destroys the epidermis and the whole dermis and can extend to fat, muscle, tendon or bone (Wallace et al., 2025). Older terms number these as first, second and third degree, with fourth degree used when muscle or bone is involved (Trauma New Brunswick, 2025). Depth is hard to judge: even burn experts are accurate only 64% to 76% of the time, so early estimates are rechecked (Wallace et al., 2025). Healed superficial partial-thickness burns can stay sensitive to sun, cold and friction for months, and they may itch (Wallace et al., 2025). Redness and blanching can be harder to see on darker skin, so the nurse also notes blisters, moisture, texture, capillary refill and sensation (Black & Simende, 2020).

Table 35.4 Burn depth compared (Jeschke et al., 2020; Trauma New Brunswick, 2025; Wallace et al., 2025; original wording)

Depth	Layers involved	Appearance and feel	Pain	Usual healing
Superficial	Epidermis only	Red; skin intact; blanches; no blisters	Painful, from itching to sharp	Heals without surgery
Superficial partial-thickness	Epidermis and upper dermis	Pink to red; thin-walled blisters; blanches with brisk capillary refill	Very painful	Needs dressings and wound care; may scar; no surgery
Deep partial-thickness	Epidermis and deeper dermis	Mottled or cherry red; blanching reduced or absent; sluggish refill; thick-walled blisters possible	Varies; deep pressure felt, pinprick may not be	Usually needs surgery; will scar
Full-thickness	All layers of skin, sometimes deeper	White, pale, leathery, dry or charred (eschar); does not blanch	Little or no pain in the centre; may hurt at the edges	Needs surgery unless very small

First Aid and Emergency Care

The first step is to stop the burning and remove the person from the source safely (Trauma New Brunswick, 2025). Wounds Canada advises cooling thermal burns for 20 minutes, with clean running water at a tepid temperature or with wet towels and compresses, and never using ice or very cold water, which narrow the blood vessels. Early cooling helps keep the burn from becoming deeper

(Wallace et al., 2025). Cooling must not make the person cold. Trauma New Brunswick's emergency consensus accepts cooling with cool tap water for up to 30 minutes for burns of 5% of total body surface area or less, and it puts keeping the person warm ahead of applying dressings in the acute phase (Trauma New Brunswick, 2025). Clothing, jewellery and piercings are removed before swelling starts. The burns are covered with clean, dry sheets, and in the emergency department dressings are not applied until the burn team has been consulted (Trauma New Brunswick, 2025).

Inhalation injury is damage to the airway and lungs from heat, smoke or toxic gases. The risk is highest after a fire in an enclosed space such as a house or car. Cues include soot in the nose or mouth, a hoarse voice, cough, wheezing, stridor (a high-pitched sound on breathing in), burns of the face or neck and singed nasal hairs, but not every patient has these signs (Beyene & Hayhurst, 2026). The upper airway can swell and close, so the nurse raises the head of the bed to a Fowler's or semi-Fowler's position, watches the airway closely and reports changes at once (Wallace et al., 2025). Stridor, respiratory distress, deep facial burns, burns inside the mouth and a change in level of consciousness are among the reasons the team may need to secure the airway early (Trauma New Brunswick, 2025). Inhalation injury also increases the risk of pneumonia during mechanical ventilation, the volume of fluid needed and the risk of death (Jeschke et al., 2020).

Carbon monoxide poisoning is a common danger after smoke exposure. Carbon monoxide binds to hemoglobin and forms carboxyhemoglobin, which cannot carry oxygen. Pulse oximetry is unreliable in carbon monoxide poisoning: carboxyhemoglobin falsely raises the reading, so it can look normal while tissues are short of oxygen (Beyene & Hayhurst, 2026). Headache, nausea and confusion are cues. Oxygen at 15 L/min by non-rebreather mask is started at the first point of care, and blood tests include a carboxyhemoglobin level (Trauma New Brunswick, 2025). On 100% oxygen, the carboxyhemoglobin level falls by half in about an hour (Beyene & Hayhurst, 2026). Burning plastics can also release cyanide, which is suspected when shock and acid build-up in the blood persist despite oxygen and fluids (Trauma New Brunswick, 2025).

Total body surface area (TBSA) burned is estimated by adding only partial-thickness and full-thickness areas; superficial burns are not counted. The **rule of nines** divides the adult body into areas worth 9% or a multiple of 9%. For scattered burns, the person's palm and fingers equal about 1% of their TBSA. The **Lund and Browder chart** is the most accurate method and is preferred for children (Trauma New Brunswick, 2025; Wallace et al., 2025; Figure 35.12).



Figure 35.12 Body regions used in the adult Wallace rule of nines: the head and neck and each upper limb are 9% each, the anterior trunk, posterior trunk and each lower limb are 18% each (9% front and 9% back), and the perineum is 1%.

The American Burn Association (ABA) referral guidelines, which Canadian programs also use, list situations that call for immediate consultation with a burn centre and consideration of transfer. These include full-thickness burns; partial-thickness burns of 10% TBSA or more; deep burns of the face, hands, feet, genitals, perineum or joints; any suspected inhalation injury; all chemical burns; high-voltage electrical injury (1,000 volts or more) and lightning; burns with other injuries or serious health conditions; and pain that is hard to control. Smaller partial-thickness burns, any burn that may be deep and low-voltage electrical injuries still call for a consultation, and people with low-voltage injuries may need burn centre follow-up to check for symptoms that start later and for vision problems. The ABA states that its guidelines are meant to aid referral decisions and do not replace professional judgment (American Burn Association [ABA], 2025; Trauma New Brunswick, 2025).

After a high-voltage injury, a 12-lead electrocardiogram (ECG) and 24 hours of cardiac monitoring are indicated, and the team watches for compartment syndrome and muscle breakdown (rhabdomyolysis), with blood tests for creatine kinase and urine tests for myoglobin. For chemical

burns, staff first protect themselves with personal protective equipment, remove contaminated clothing, brush off any dry powder and then rinse the skin continuously with water. A poison centre can advise on specific chemicals (Trauma New Brunswick, 2025).

Burn Care in Hospital

A large burn causes fluid to leak from blood vessels into the tissues, which can lead to burn shock (Chapter 6). Adults with burns over 20% TBSA need planned fluid resuscitation with warmed lactated Ringer's solution and a urinary catheter to measure hourly urine output. Mortality rises if resuscitation is delayed more than 2 hours after a major burn (Trauma New Brunswick, 2025); the details are in the Going Deeper box. The nurse also watches circulation in limbs with deep burns that go all the way around (circumferential burns), because stiff, dead tissue called eschar (section 35.3) can act like a tourniquet as the tissues swell. Cool skin, slow or absent capillary refill, tense compartments and a clawed hand are warning signs; absent pulses are a late sign (Wallace et al., 2025). Deep burns around the chest or neck can limit breathing (Trauma New Brunswick, 2025). An **escharotomy**, a surgical cut through the eschar, releases the pressure.

Pain is severe. In the emergency phase, intravenous analgesia is given early in small, repeated doses; intramuscular opioids are avoided in burns over 10% TBSA because absorption is unreliable (Trauma New Brunswick, 2025). Pain and anxiety at dressing changes are planned for (Chapter 5). Burn survivors may also have itching as wounds heal (Wallace et al., 2025).

The burn team chooses the dressings. Deep partial-thickness and most full-thickness burns need surgery (Jeschke et al., 2020; Wallace et al., 2025): early removal of dead tissue (excision) followed by a **skin graft**, healthy skin moved from another part of the body (the donor site) to cover the wound. Sepsis is the leading cause of death in people with burns (Wallace et al., 2025), so strict infection prevention is essential (Chapter 4). Sepsis is harder to recognize after a major burn, and standard sepsis definitions miss some cases (Jeschke et al., 2020). Antibiotics are not given to prevent infection, and burns are treated as tetanus-prone wounds (Trauma New Brunswick, 2025). Tetanus immunization follows the Canadian Immunization Guide: for wounds other than clean, minor ones, a tetanus booster is given if 5 or more years have passed since the last dose, and tetanus immune globulin is added for people with fewer than three doses or an unknown history (Public Health Agency of Canada [PHAC], 2026).

A major burn sets off a hypermetabolic response that raises energy use and breaks down muscle and can last up to 36 months (Jeschke et al., 2020). Wounds Canada recommends starting nutrition early, ideally within 24 hours and no later than 48 hours, and keeping the room warm to reduce energy loss (Wallace et al., 2025; section 24.1). A core (internal) temperature below 36.5 °C counts as hypothermia in a person with burns (Trauma New Brunswick, 2025).

Recovery depends on a team. At Ontario's main adult burn centre, burn surgeons and nurses work with dietitians, pharmacists, physiotherapists, occupational and respiratory therapists, speech-language pathologists and social workers (Sunnybrook Health Sciences Centre, n.d.). Burns that heal by scarring tighten over joints. A **contracture** is a shortening of skin and tissue that limits movement. Occupational therapists and physiotherapists use positioning, splints, stretching and exercise to keep full range of motion, and many survivors wear compression garments for several years (Wallace et al., 2025). Raised (hypertrophic) scars develop in 30% to 90% of people with burns, and keloids occur mainly in people with darker skin (Jeschke et al., 2020). Anxiety, depression and post-traumatic stress symptoms are common and lower quality of life (Jeschke et al., 2020), so the nurse asks about mood, sleep, body image and peer support. Before discharge, the team plans wound care, follow-up (sometimes by telemedicine for rural and remote communities) and a return to work and daily life (Wallace et al., 2025). Prevention teaching matters: Wounds Canada reports that residential fires with no life-safety system present or working, such as a smoke alarm or sprinkler, accounted for 80% of deaths in residential fires (Wallace et al., 2025).

GOING DEEPER

Fluid Resuscitation After a Major Burn

Required for RN students; optional for PN students.

The ABA's 2024 burn shock resuscitation guideline covers adults with burns of 20% TBSA or more. It recommends that clinicians consider starting fluid at 2 mL/kg/%TBSA burned, lower than the older 4 mL/kg/%TBSA, to reduce total volume (Cartotto et al., 2024). Trauma New Brunswick's 2025 consensus applies this approach: the 24-hour estimate is 2 mL of lactated Ringer's × weight in kilograms × %TBSA, and the starting hourly rate is the 24-hour estimate divided by 16, which gives half the estimate in the first 8 hours if unchanged. Electrical injuries start at 4 mL instead of 2 mL (Trauma New Brunswick, 2025).

The formula only sets the starting rate; the burn team adjusts it hourly, mainly to urine output. The ABA recommendations set no adult urine output target; the guideline's text calls 0.5 mL/kg/h the standard target, and studies it reviewed aimed for 0.5 mL/kg/h or 30 to 50 mL/h (Cartotto et al., 2024). The Canadian consensus sets 30 to 50 mL/h for adults (75 to 100 mL/h when an electrical injury causes dark, myoglobin-stained urine) and adjusts the rate by up to one-third when output is more than one-third off target, in consultation with the physician (Trauma New Brunswick, 2025).

Too little fluid leads to organ failure and death. Too much, sometimes called fluid creep, causes edema, pulmonary edema and compartment syndromes of the abdomen, limbs and eye sockets (orbits); the guideline recommends selective monitoring of pressure inside the abdomen and eyes and suggests considering albumin, especially in larger burns (Cartotto et al., 2024). The nurse measures urine output every hour and reports output outside the target promptly so the team can adjust the rate.

CANADIAN CONTEXT

Burn Care Across Canada

Canada has far fewer burn centres than trauma centres: in 2010, there were about three adult trauma centres (levels 1 and 2) for every burn centre (Bell et al., 2012). In Ontario, Sunnybrook's Ross Tilley Burn Centre in Toronto provides tertiary care for most people with burn injuries in the province. About 70% of its patients come from outside the Greater Toronto Area, arriving by ambulance, plane or helicopter (Sunnybrook Health Sciences Centre, n.d.). A British Columbia study found that nearly 40% of that province's population would need transport over hundreds or thousands of kilometres to reach one of its two adult burn centres. People burned in rural areas had higher total mortality, but patients first treated at another hospital and then transferred had outcomes similar to those taken directly to a burn centre (Bell et al., 2012). Good early care in the first hospital therefore matters.

In rural, remote and northern communities, distance, weather and time of day affect transfer by helicopter or fixed-wing aircraft (Bell et al., 2012). Burn centres can support local teams with consultation, and follow-up assessments can be done by telemedicine (Wallace et al., 2025). Provincial systems differ; in New Brunswick, emergency teams consult through a provincial trauma line (Trauma New Brunswick, 2025). Housing and other social determinants of health shape both burn risk and recovery (Wallace et al., 2025; Chapter 2).

35.6 Skin Cancer and Other Common Skin Conditions

Nurses see more of a patient's skin than almost anyone else on the care team. A bath, a position change or a skin check for pressure injury is a chance to notice a lesion that is new or changing.

Skin Cancer

Non-melanoma skin cancer is diagnosed more often than any other cancer in Canada, but most cancer registries do not collect data on it because it is usually diagnosed and treated in a doctor's office. **Basal cell carcinoma** starts in the round basal cells at the bottom of the epidermis and makes up about 75% to 80% of skin cancers. **Squamous cell carcinoma** starts in the flat squamous cells of the outer epidermis and makes up about 20%. Basal cell carcinoma usually grows slowly and is often found early, and non-melanoma skin cancers rarely spread. Actinic keratosis is a precancerous skin condition that may become cancer if it is not treated (Canadian Cancer Society, 2024, n.d.-c).

Melanoma starts in melanocytes, the skin cells that make the pigment melanin, and is less common than non-melanoma skin cancer (Canadian Cancer Society, n.d.-b). For 2026, the Canadian Cancer Society estimates 11,300 new melanoma diagnoses in Canada (6,200 in men and 5,100 in women) and 1,250 deaths from melanoma (820 men and 450 women) (Brenner et al., 2026; Canadian Cancer Society, 2026). The Canadian Cancer Society teaches the ABCDE warning signs of a mole: **A**symmetry, when one half does not match the other; an irregular **B**order that is jagged, notched or blurry; uneven **C**olour, with shades of tan, brown and black; a **D**iameter larger than 6 mm, roughly the width of a pencil eraser; and **E**volving, meaning a change in colour, size, shape or feel, or new itching, burning or tingling. A sore that does not heal, oozes or bleeds is also a warning sign (Canadian Cancer Society, n.d.-a).

Acral melanoma is the most common type of melanoma in people with darker skin. It grows on the palms, the soles of the feet and the nails, areas that get little sun, and, unlike other melanomas of the skin, is not linked to ultraviolet (UV) exposure. Under a nail, it can appear as a dark streak running toward the nail fold. It is often diagnosed late, partly because patients and clinicians are less aware of it and most public education images show light skin; the ABCDE signs are less useful for these lesions (Nadelmann et al.,

2025). During care, the nurse looks at the soles, between the toes and at the nails of every patient, asks whether any spot is new or changing, and reports what they find (Figure 35.13).

Figure 35.13 Acral lentiginous melanoma: (a) a large asymmetric pigmented lesion with irregular borders and varied brown-to-black colour on the sole of the foot; (b) subungual melanoma of the thumb. Checking the palms, soles and nail beds is part of a complete skin assessment across all skin tones. (credit: (a) "Photography of a large acral lentiginous melanoma" by José C. C. Xavier-Júnior et al./Diagnostic Pathology, CC BY 4.0; (b) "Melanoma of thumb" by Wawjak/Wikimedia Commons, CC BY 4.0)

Sun protection is the main way to prevent most skin cancers. Health Canada advises protecting the skin whenever the UV Index is 3 or higher, even on cloudy days: staying out of the sun from 11 a.m. to 3 p.m., using shade, wearing long sleeves, long pants, a wide-brimmed hat and sunglasses that block UVA and UVB rays, and using a broad-spectrum, water-resistant sunscreen with a sun protection factor (SPF) of at least 30. Tanning equipment damages the skin and raises the risk of melanoma (Health Canada, 2023). Skin cancer risk after a kidney transplant is covered in Chapter 27, and cancer care in general in Chapter 9.

Other Common Conditions

Herpes zoster (shingles) is a reactivation of the varicella-zoster virus, which stays in the nerve roots after chickenpox. Tingling or pain begins 1 to 5 days before a rash of blisters appears in a band on one side of the body, usually without crossing the midline (MacFadden & Gold, 2012). Its risk rises with age as the immune system weakens, and with immune suppression; the lifetime risk in the general population in Canada may be as high as 30% (Krishnan et al., 2026). The most common complication is pain lasting more than 30 days after the rash begins, called postherpetic neuralgia. Antiviral medicines, such as valacyclovir, work best when started within 72 hours of the rash appearing; antivirals are started for zoster near the eye even after 72 hours, to reduce eye complications (MacFadden & Gold, 2012). The Canadian Immunization Guide recommends a two-dose series of the recombinant zoster vaccine for adults 50 and older without contraindications and for adults aged 18 and older whose immune systems are, or will be, suppressed (Krishnan et al., 2026; PHAC, 2025; Figure 35.14).

Psoriasis is a chronic inflammatory skin condition that affects about 1 million people in Canada. It causes raised patches (plaques) that look red to violet depending on the person's skin tone. It is not contagious. About one in three people with psoriasis can develop psoriatic arthritis (Chapter 34), and psoriasis is linked with a higher risk of heart attack, stroke and depression. Stigma, embarrassment and discomfort can lower quality of life (Canadian Dermatology Association, 2026b). **Atopic dermatitis** is a form of eczema, the name for a group of conditions that inflame the skin. Up to 17% of people in Canada are estimated to have it at some point in life, and on darker skin it often looks ashen brown or greyish rather than red (Canadian Dermatology Association, 2026a). A Canadian consensus guideline advises assessing severity with both clinician measures and the person's own report of symptoms, teaching people to avoid triggers and use moisturizers, and limiting topical corticosteroids to short, intermittent courses (Gooderham et al., 2025). For both conditions, the nurse asks how the skin affects sleep, work and mood, and avoids reacting to visible skin in ways that add to stigma.



Figure 35.14 Herpes zoster (shingles): clustered vesicles on an erythematous base following a single unilateral dermatome on the back without crossing the midline. (credit: “Herpes Zoster Rash” by BruceBlaus/Wikimedia Commons, CC BY-SA 4.0)

SCOPE IN PRACTICE

Skin and Wound Care and Who Does What

Every nurse assesses skin, prevents pressure injuries and skin tears, and reports wounds that are new, worse or infected. Who does more depends on authority, competence and context (College of Nurses of Ontario [CNO], 2025; Chapter 1, section 1.3).

- **Authority:** In Ontario, RNs and RPNs are authorized to perform the controlled act of a prescribed procedure below the dermis, such as packing a deep wound, and nurses may initiate such wound care without an order where the regulation's conditions are met and the setting allows. Nurses cannot initiate controlled acts in public hospitals, where an order is needed (CNO, 2025).
- **Competence:** Choosing dressings, managing negative pressure wound therapy and conservative sharp debridement (removing dead tissue with sterile instruments) need specific knowledge, skill and judgment. Wounds Canada wants policies and education in place before NPWT is used (Tecson et al., 2025), and Nurses Specialized in Wound, Ostomy and Continence Canada (NSWOCC, 2021) recommends advanced education and a clinical preceptorship before sharp debridement. A nurse without that education asks for support.
- **Context:** Employer policies set which nurses may do advanced wound skills (NSWOCC, 2021); employers can limit but not expand a nurse's legislated scope (CNO, 2025). Wound care specialists help where available.

Any nurse who notices spreading infection, dehiscence, evisceration or signs of sepsis acts at once and escalates; the RPN consults the RN as the patient's needs change. Rules differ by province and territory, and CNO's revised Scope of Practice standard takes effect on March 1, 2027 (CNO, 2026).

PATIENT EDUCATION

Caring for Your Incision at Home

- Wash your hands before and after you touch your incision or dressing.
- Keep the dressing on for as long as your team tells you. Most people can shower 48 hours after surgery, but ask your surgeon first.
- Stitches or staples usually come out 1 to 2 weeks after surgery. Keep that appointment.

- Hold a pillow firmly over a belly or chest incision when you cough, sneeze or get up. Follow your team's advice on lifting and activity.
- You may feel a firm ridge under the incision in the first week or so. This is normal healing.
- Call your surgeon or clinic the same day if you notice pain that gets worse instead of better; swelling or warmth that spreads; a change in skin colour around the incision that spreads (red on lighter skin; on darker skin, a patch darker than your usual skin); drainage that is cloudy, smelly or increasing; edges that pull apart; or a fever.
- Call 9-1-1 if the incision opens and you can see tissue underneath, or if you feel faint or confused.
- New scars on lighter skin often turn pink, then white or silver. On darker skin, scars may become darker than your usual skin colour.

Keep your team's phone numbers handy, and ask for information in the language you read best (Tecson et al., 2025; WUWHS, 2018).

Chapter 35 Summary

35.1 Skin Structure and Assessment

- Skin has three layers: the epidermis, the dermis and the fatty hypodermis. With age, skin thins, its layers separate more easily, and it heals more slowly.
- Skin assessment must work on every skin tone: good lighting, a recorded baseline skin tone, comparison with the other side, and touch for warmth, firmness and moisture, together with the person's own report of pain or change.
- Redness may not be visible on darker skin; inflammation may show as a patch darker than the person's usual skin, or may be found mainly by touch.
- Moisture-associated skin damage, including incontinence-associated dermatitis, is prevented and treated by gentle cleansing, a barrier product and moisturizing, plus control of the source of moisture.
- Skin tears are classified by ISTAP as Types 1 to 3 and are prevented by twice-daily moisturizing and gentle handling; they are dressed with silicone dressings marked for direction of removal, not adhesive strips.

35.2 Pressure Injuries

- Pressure injuries result from pressure or pressure with shear, often beginning deep near the bone; moisture and heat at the skin surface add to the risk.
- Prevention combines risk screening with a tool the employer chooses plus clinical judgment, regular skin checks, repositioning on a written schedule, heel offloading, support surfaces, moisture management, nutrition and teaching.
- Stages 1 to 4, unstageable and deep tissue pressure injury are defined by the deepest tissue involved; stages are never reversed as a wound heals.
- On darker skin, a deep tissue pressure injury may not look purple or maroon and may be found mainly by temperature, firmness and pain.
- Care starts with removing the cause; stage 3, stage 4, unstageable and non-improving injuries are referred to the wound care team.

35.3 Wound Healing and Wound Care

- Wounds heal through hemostasis, inflammation, proliferation and remodelling, by primary, secondary or delayed primary intention; chronic wounds stall because a barrier to healing persists.
- Wound bed preparation starts with the cause and the person, then decides whether the wound is healable, maintenance or non-healable, which sets the goal of care.
- Wound assessment covers location, size, undermining and tunnelling, wound bed tissue, exudate, edges, surrounding skin, pain and odour, measured the same way each time.

- Healable wounds need moisture balance; maintenance and non-healable wounds need moisture and bacterial reduction, and stable dry eschar is left in place.
- Local, spreading and systemic infection differ in their signs; spreading or systemic signs are reported promptly using SBAR, and swabs follow the Levine technique when ordered.

35.4 Surgical Wounds and Skin Infections

- A closed incision should be sealed by about day 4, with a healing ridge along its whole length between days 5 and 9; drainage after day 9 is not expected.
- Signs of surgical site infection include new or increasing pain, spreading warmth and swelling, cloudy or foul-smelling drainage and fever; on darker skin, colour change may not show.
- Dehiscence is separation of the incision; evisceration is a surgical emergency in which the nurse stays, calls for help, covers the organs with sterile saline-moistened gauze and positions the patient in low Fowler's with the knees bent.
- Cellulitis causes warmth, swelling, tenderness and a spreading colour change; the nurse marks the edge, records warmth and swelling, elevates the limb and escalates signs of sepsis.
- Pain out of proportion to the skin findings, rapid spread and hard tissue beyond the visible change suggest a necrotizing soft tissue infection, which needs urgent surgery.

35.5 Burns

- Burns are classified as superficial, superficial partial-thickness, deep partial-thickness or full-thickness; only partial-thickness and full-thickness areas count toward TBSA.
- First aid is to stop the burning, cool with tepid running water for about 20 minutes without ice, remove jewellery, cover with clean dry sheets and keep the person warm.
- After a fire in an enclosed space, soot, a hoarse voice and stridor point to inhalation injury; pulse oximetry can be falsely normal in carbon monoxide poisoning, so high-flow oxygen is given and carboxyhemoglobin is measured.
- ABA criteria call for immediate burn centre consultation for full-thickness burns, partial-thickness burns of 10% TBSA or more, deep burns of the face, hands, feet, genitals, perineum or joints, inhalation injury, chemical burns and high-voltage injuries.
- Adults with burns over 20% TBSA receive planned fluid resuscitation that the burn team adjusts to hourly urine output.
- Hospital care includes pain control, surgery and grafting, infection prevention, early nutrition, warmth, contracture prevention and mental health support.

35.6 Skin Cancer and Other Common Skin Conditions

- Non-melanoma skin cancer is the most common cancer in Canada; an estimated 11,300 people will be diagnosed with melanoma in 2026 and 1,250 will die from it.
- The ABCDE signs (asymmetry, border, colour, diameter, evolving) guide what to report; acral melanoma on the palms, soles and nails is the most common type in people with darker skin.
- Health Canada advises sun protection whenever the UV Index is 3 or higher, including broad-spectrum, water-resistant sunscreen with an SPF of at least 30.
- Shingles antivirals work best within 72 hours of the rash; the Canadian Immunization Guide recommends two doses of the recombinant zoster vaccine for adults 50 and older.
- Psoriasis and atopic dermatitis are long-term conditions that can lower quality of life; care includes skin care, treatment as prescribed and a non-stigmatizing approach.

Key Terms (56)

abscess: A walled-off collection of pus in the skin or the tissue beneath it, treated mainly by incision and drainage.

acral melanoma: A type of melanoma on the palms, soles or nails that is not linked to ultraviolet exposure; the most common type in people with darker skin.

basal cell carcinoma: The most common skin cancer, starting in the basal cells of the epidermis; it usually grows slowly and rarely spreads.

biofilm: A complex community of bacteria and fungi held together on a wound in a slimy coating made of sugars and proteins; it delays healing and cannot be detected by standard culture.

burn: Damage to the skin or deeper tissues caused by heat, chemicals, electricity, radiation, friction or extreme cold.

carbon monoxide poisoning: Harm caused when inhaled carbon monoxide binds to hemoglobin and forms carboxyhemoglobin, which cannot carry oxygen; pulse oximetry can read falsely normal.

cellulitis: A spreading infection of the skin and the tissue just beneath it, causing warmth, swelling, tenderness and a spreading change in colour.

chronic wound: A wound, also called a wound of long duration, that has stalled in healing because a barrier to healing has not been corrected.

contracture: A shortening of scarred skin and tissue that limits the movement of a joint.

deep tissue pressure injury (DTPI): A pressure injury that starts near the bone and shows as persistent, non-blanching discolouration or a blood blister; on darker skin it may not look purple or maroon.

dehiscence: Partial or complete separation of the edges of a closed surgical incision.

delayed primary intention: Closure of a contaminated wound after it has been left open for several days.

dermis: The layer of skin beneath the epidermis that contains collagen and elastic fibres, capillaries, nerve endings, hair follicles and glands.

device-related pressure injury: A pressure injury caused by a medical device, usually shaped like the device, and staged with the same system as other pressure injuries.

epidermis: The thin outer layer of skin, without its own blood vessels, that forms a waterproof barrier and contains the pigment-making melanocytes.

eschar: Dry, dark, leathery dead tissue in a wound.

escharotomy: A surgical cut through the eschar of a deep circumferential burn to relieve pressure on a limb, the chest or the neck.

evisceration: Protrusion of organs, such as bowel, through a separated abdominal incision; a surgical emergency.

exudate: Fluid that drains from a wound.

fluid resuscitation: Planned intravenous fluid given after a major burn to replace fluid that leaks out of the blood vessels, adjusted to urine output.

full-thickness burn: A burn that destroys the epidermis and the whole dermis and may extend deeper; it looks white, leathery or charred and has little pain at its centre.

granulation tissue: Moist, bumpy new connective tissue with many capillaries that fills a wound from its base during healing.

healing ridge: A firm band of new collagen that can be felt under a healing incision, normally along its whole length between days 5 and 9.

herpes zoster: Reactivation of the varicella-zoster virus, causing pain and a band of blisters on one side of the body; also called shingles.

hypodermis: The fatty subcutaneous layer beneath the dermis that insulates, cushions and stores energy; it has a poor blood supply.

incontinence-associated dermatitis (IAD): A form of MASD caused by urine, stool or both, usually affecting the perineum, buttocks and upper inner thighs.

induration: Hardening of tissue that can be felt on palpation, often a sign of inflammation or deep damage.

inhalation injury: Damage to the airway and lungs from heat, smoke or toxic gases, suspected after a fire in an enclosed space.

Lund and Browder chart: A body diagram used to estimate the percentage of body surface burned; the most accurate method and the preferred one for children.

melanoma: A cancer that starts in melanocytes, the skin cells that make the pigment melanin; less common than non-melanoma skin cancer.

microclimate: The conditions, especially moisture and warmth, at the skin where it meets a surface such as a mattress or chair.

moisture balance: Keeping a healable wound moist enough for cells to migrate but not so wet that the edges macerate.

moisture-associated skin damage (MASD): Inflammation and erosion of skin caused by long contact with urine, stool, sweat, wound drainage or stoma output.

mucosal membrane pressure injury: A pressure injury on a moist lining, such as the lips or nose, where a device has been used; it cannot be staged.

necrotizing soft tissue infection: A rapidly spreading infection that destroys deep tissues such as fat and fascia; a surgical emergency.

negative pressure wound therapy: Wound treatment that uses a sealed dressing connected to a pump that applies suction to the wound.

offloading: Removing pressure from an area of the body completely, for example by floating the heels off the bed.

partial-thickness burn: A burn that destroys the epidermis and part of the dermis; superficial partial-thickness burns blister and are very painful, and deep partial-thickness burns usually need surgery.

postherpetic neuralgia: Pain lasting more than 30 days after the rash of herpes zoster begins.

pressure injury: Localized damage to skin and underlying soft tissue, usually over a bony prominence or under a device, caused by pressure or pressure combined with shear.

primary intention: Healing of a wound whose edges have been brought together with sutures, staples or tape, without the need to fill with granulation tissue.

rule of nines: A method of estimating the burned body surface in adults that divides the body into areas of 9% or multiples of 9%.

secondary intention: Healing of an open wound that fills with granulation tissue from the base up.

shear: The force created when deeper tissue slides in one direction while the skin is held in place by a surface, distorting tissue and blood vessels.

skin graft: Healthy skin moved from one part of the body (the donor site) to cover a wound.

skin tear: A traumatic wound caused by mechanical force, such as handling or adhesive removal, that does not go through the subcutaneous layer; classified as ISTAP Type 1, 2 or 3.

slough: Soft, moist dead tissue in a wound that may be yellow, tan or grey.

squamous cell carcinoma: A skin cancer that starts in the flat squamous cells of the outer epidermis.

superficial burn: A burn involving only the epidermis; the skin is intact, painful and without blisters.

support surface: A mattress, overlay or cushion designed to redistribute pressure; it does not replace repositioning.

surgical site infection: An infection of a surgical incision or of the deeper tissues or organ space after an operation.

total body surface area: The whole skin surface of the body, used as the basis for expressing the extent of a burn as a percentage (TBSA).

tunnelling: A narrow channel extending from a wound into deeper tissue.

undermining: Tissue destroyed under intact skin at a wound's edge, forming a shelf.

unstageable pressure injury: A full-thickness pressure injury whose depth cannot be seen because slough or eschar covers the base.

wound bed preparation: A framework for wound care that starts by treating the cause, addressing the person's concerns and deciding whether a wound can heal, then guides local care.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mrs. Olive Bertrand (Questions 1–4): Mrs. Olive Bertrand, 79, has moderate dementia and was admitted to a medical unit in Ontario five days ago with a urinary tract infection. She needs help to turn, is incontinent of urine and stool, and eats about one-quarter of each meal. Today the RPN finds a shallow, open area over the sacrum with a moist pink base and no slough, about 2 cm by 1.5 cm. The surrounding skin is intact.

1. [CORE] The RPN plans care to prevent further pressure damage to Mrs. Bertrand's sacrum. Which plan is most appropriate?

a. Keep her on her back with the head of the bed raised to 45 degrees so that she can watch television and stay more oriented to the day

b. Turn her off her sacrum on a written schedule, using a lift sheet to move her and keeping the head of the bed low when possible

c. Reduce repositioning to once a shift now that she has a pressure redistribution mattress, to avoid waking her during the night

d. Sit her up in a chair for most of the day without a cushion, because getting her out of bed removes pressure from the sacrum

Answer: b — A written repositioning schedule that keeps her off the injured area, moving her with a lift sheet to limit friction and shear, and a low head of bed to limit sliding, follows Wounds Canada's recommendations (section 35.2, Prevention). Option a raises the head of the bed well above about 30 to 35 degrees and keeps weight on the sacrum, increasing shear and pressure. Option c is wrong because a support surface reduces pressure but does not replace repositioning. Option d moves the pressure to the sacrum and buttocks while seated; a person at risk who sits needs a pressure-redistributing cushion and regular weight shifts.

2. [CORE] After an episode of fecal incontinence, which skin care does the RPN provide for Mrs. Bertrand?

a. Wash the area with bar soap and a washcloth, scrubbing firmly to remove all stool, and leave the skin open to air until it is dry

b. Apply a hydrogel to the perineum and buttocks so the skin stays moist and does not crack between episodes of incontinence

c. Cover the buttocks and the sacral wound with a thick layer of zinc oxide paste so that a separate wound dressing is not needed

d. Cleanse gently with a pH-balanced, soap-free cleanser, pat dry, and apply a barrier product to the surrounding intact skin

Answer: d — Wounds Canada's approach to incontinence-associated skin damage is to cleanse gently with a pH-balanced, soap-free cleanser, pat dry, protect with a barrier and restore with a moisturizer (section 35.1, Moisture and Fragile Skin). Option a uses alkaline soap and friction, which further damage fragile skin. Option b adds moisture; moisture-donating products such as hydrogels are not recommended for moisture-associated skin damage. Option c treats an open stage 2 wound as if it were intact skin; the wound itself needs a moist, protective dressing, while barrier products protect the intact skin around it.

3. [CORE] Mrs. Bertrand continues to eat about one-quarter of her meals. Which action by the RPN is most appropriate?

a. Report her poor intake to the RN and suggest a nutrition screen and a referral to the dietitian, as nutrition supports healing

b. Wait until her urinary tract infection has been treated, because her appetite is likely to return on its own once she feels better

c. Encourage her daughter to bring in her favourite takeout meals, because the hospital diet does not need to change at all

d. Record her intake as "poor" each day so the team can review the pattern at discharge, since nutrition is not a skin issue

Answer: a — Poor intake is a risk factor for pressure injury and delays healing; Wounds Canada recommends nutrition screening with a validated tool and involving a dietitian, and the RPN consults the RN as the patient's needs change (sections 35.2 and 24.1). Option b delays action while a wound is already present. Option c may help her eat but ignores the need for a nutrition assessment, and family food may not meet her needs. Option d documents the problem without acting on it and is wrong about nutrition's role in skin health.

4. [CORE] Two weeks later, the sacral wound is smaller, 1.2 cm by 0.8 cm, with a pink moist base and new skin growing in from the edges. Which documentation entry by the RPN is most accurate?

a. "Sacral pressure injury now stage 1, 1.2 x 0.8 cm, pink and moist, no drainage, healing well; continue the same turning plan."

b. "Sacral wound improving and looks much better than last week; dressing changed; patient settled; family updated."

c. "Healing stage 2 pressure injury, sacrum, 1.2 x 0.8 cm, pink moist base, no drainage, periwound skin intact; turning plan continued."

d. "Sacral ulcer reversed to a stage 1 pressure injury, 1.2 x 0.8 cm, with good new tissue and no odour; patient tolerated care well."

Answer: c — A pressure injury keeps the stage it had when first assessed and is documented as a healing stage 2; good documentation records location, stage, size, wound bed, drainage, surrounding skin and the plan (section 35.2, Staging and Care, and section 35.3, Assessing a Wound). Options a and d use reverse staging, which is incorrect even though they include measurements. Option b is vague and gives no measurements or description that another nurse could compare with.

5. [CORE] A nurse is assessing the sacrum of a patient with dark brown skin who has been on bed rest for two days. Which finding is the strongest sign of early pressure damage?

a. The skin over the sacrum looks the same colour as the lower back under the room's fluorescent ceiling light

b. The skin over the sacrum is dry and slightly flaky, and the patient says it has felt this way for several months

c. An area over the sacrum feels warmer and firmer than nearby skin, and the patient says it is tender when touched

d. The skin over the sacrum blanches and returns to its usual colour within a few seconds after gentle fingertip pressure

Answer: c — On darker skin, redness may not be visible, so temperature, firmness or bogginess, and pain compared with nearby skin are key signs of early pressure damage (sections 35.1 and 35.2). Option a relies on colour alone under fluorescent light, which casts a bluish tint that can hide changes. Option b describes long-standing dry skin, not a new pressure change. Option d describes normal blanching, which suggests no pressure injury at this site.

6. [CORE] A student asks why older adults develop skin tears so easily. Which explanation by the nurse is most accurate?

a. "The ridges that anchor the outer skin layer to the layer below flatten with age, so the layers separate more easily."

b. "Older adults make more collagen in the dermis, which makes the skin stiff and likely to crack when it is moved."

c. "The outer skin layer thickens with age and loses its blood vessels, so it splits when it is pulled during a transfer."

d. "Older skin becomes more acidic over time, and the acid weakens the skin so it tears with even light pressure."

Answer: a — With age, the rete pegs that lock the epidermis to the dermis flatten, so the layers separate under friction and shear (section 35.1, How Skin Works). Option b is wrong because collagen declines, by about 1% a year. Option c is wrong because the epidermis thins with age, and it never has its own blood vessels. Option d is wrong because older skin becomes more alkaline, not more acidic.

7. [CORE] Which finding suggests incontinence-associated dermatitis rather than a pressure injury?

a. A single round wound with a defined edge directly over the bony part of the sacrum and coccyx

b. A purple area of intact skin over the heel in a patient who cannot move their legs

c. A deep crater on the hip with yellow slough at the base and tunnelling toward the bone

d. Diffuse, painful inflammation spreading across the perineum, buttocks and inner thighs

Answer: d — Incontinence-associated dermatitis is irritation from urine or stool that usually affects the perineum, buttocks and upper inner thighs, with inflammation and pain (section 35.1, Moisture and Fragile Skin). Options a, b and c describe damage over bony prominences that is typical of pressure injury: a defined wound over the sacrum, a possible deep tissue pressure injury on the heel, and a full-thickness injury on the hip.

8. [CORE] A resident bumps her forearm on a wheelchair arm. The nurse finds a skin tear with a flap that covers about half of the wound bed; the rest of the flap is missing. How does the nurse classify this skin tear?

a. ISTAP Type 1, because there is still a skin flap present at the wound

b. ISTAP Type 2, because part of the flap is lost and it cannot cover the whole bed

c. ISTAP Type 3, because the wound bed can be seen through part of the flap

d. A stage 2 pressure injury, because the wound is a partial-thickness loss of skin

Answer: b — In the ISTAP classification, Type 2 is partial flap loss: what remains of the flap is not enough to cover all of the wound bed (section 35.1, Moisture and Fragile Skin). Type 1 (option a) has no skin loss: the tear is linear or the flap can cover the whole bed. Type 3 (option c) is total flap loss with the entire bed exposed. Option d is wrong because skin tears are traumatic wounds classified by ISTAP; the pressure injury staging system is used only for pressure injuries.

9. [CORE] Which action is correct when the nurse dresses a Type 1 skin tear on an older adult's lower arm?

a. Close the wound edges with adhesive closure strips so that the flap stays firmly in place while it heals

b. Cover the area with a transparent film dressing so that staff can see the flap without removing the dressing

c. Ease the flap back into place, apply a silicone dressing and mark an arrow showing the direction of removal

d. Apply a povidone-iodine dressing to prevent infection, because older adults are at high risk of wound infection

Answer: c — ISTAP recommends easing a viable flap back into place, using a silicone dressing and marking the direction of removal so the flap is not lifted at the next change (section 35.1, Moisture and Fragile Skin). Adhesive closure strips (option a) are no longer preferred, films with acrylic or rubber adhesives (option b) are not recommended for people with or at high risk of skin tears, and iodine-based products (option d) should not be used for skin tears.

10. [CORE] A patient with a hip fracture is at high risk of heel pressure injury. Which action best protects the heels?

a. Float the heels clear of the mattress with a wedge-shaped cushion or heel-suspension device, keeping the Achilles tendon free of pressure

b. Place a folded towel directly under each heel so that the heels sink less deeply into the surface of the pressure redistribution mattress below

c. Massage the heels firmly with lotion every two hours to improve blood flow to the skin and the tissue that lies just under it

d. Rely on the pressure redistribution mattress alone, because the mattress spreads the patient's weight evenly across the heels

Answer: a — Heels are managed separately from the support surface and floated off the bed; a wedge-shaped cushion or device that suspends the heels is more effective than a standard pillow, and the Achilles tendon is protected (section 35.2, Prevention). Option b keeps pressure on the heel. Option c adds friction and force to tissue that may already be damaged and does not remove pressure. Option d is wrong because heels need separate offloading.

11. [CORE] A nurse assesses a sacral pressure injury. The wound is a full-thickness skin loss with yellow fat visible at the base and some slough at one edge. No muscle, tendon or bone can be seen or felt. How is the injury staged?

a. Stage 2, because the wound is moist and there is no eschar

b. Unstageable, because slough is present in part of the wound

c. Deep tissue pressure injury, because damage extends deeply

d. Stage 3, because fat is visible but deeper structures are not

Answer: d — A stage 3 pressure injury is full-thickness skin loss with fat visible, with or without slough, and no exposed bone, cartilage, tendon, ligament, muscle or fascia (section 35.2, Table 35.1). Option a is wrong because a stage 2 injury is partial-thickness with no visible fat or slough. Option b applies only when slough or eschar hides the depth; here the base is visible. Option c describes discolouration or a blood blister with or without intact skin, not an open wound with visible fat.

12. [CORE] A patient with peripheral arterial disease has a pressure injury on the heel covered with dry, black, firmly attached eschar. The surrounding skin shows no redness, swelling or drainage. Which action is most appropriate?

a. Apply a hydrogel and a moist dressing to soften the eschar so that it can be removed at the next dressing change

b. Keep the eschar dry and intact, offload the heel completely, and report and document the injury as unstageable

c. Gently lift the edge of the eschar with forceps to see how deep the wound is so that it can be staged accurately

d. Soak the foot in warm water twice a day so that the eschar loosens on its own and the wound can begin to heal

Answer: b — Stable eschar on a heel or a limb with poor blood flow (dry, attached, intact, with no redness or softness around it) acts as a natural cover and is not softened or removed; the injury is unstageable while the base is hidden, and the heel is offloaded (sections 35.2 and 35.3). Options a and d would soften the eschar and risk infection in a limb with poor blood supply. Option c removes protective eschar and is outside safe practice for staging.

13. [CORE] A patient receiving oxygen by nasal cannula for three days reports that the tops of both ears are sore. Which action is the priority?

a. Ask the respiratory therapist to switch the patient to a face mask, because masks do not cause pressure injuries on the face

b. Remove the oxygen to rest the skin for several hours, then reapply it once the soreness has completely settled

c. Inspect and palpate the skin under the tubing, pad or reposition the tubing as policy allows, and report findings

d. Record the complaint and reassess at the end of the shift, because pain under tubing is expected with oxygen use

Answer: c — Medical devices can cause pressure injuries, so the nurse checks the skin under and around every device and relieves pressure as policy allows (section 35.2, How Pressure Injuries Develop). Option a is wrong because any device, including a mask, can cause a device-related pressure injury. Option b stops prescribed oxygen, which may be unsafe. Option d delays assessment of a possible pressure injury.

14. [CORE] During a dressing change, the nurse sees soft, moist, yellow-tan tissue attached to part of the wound base. How does the nurse describe this tissue?

a. Slough, a soft, moist dead tissue that may be yellow, tan or grey

b. Eschar, a soft, moist tissue that signals the wound is healing well

c. Granulation, a yellow tissue that forms early in normal wound healing

d. Epithelium, new tissue that grows inward from the wound edges

Answer: a — Slough is soft, moist, dead tissue that may be yellow, tan or grey (section 35.2, Staging and Care). Option b is wrong because eschar is dry, dark, leathery dead tissue, and neither slough nor eschar shows healing. Option c is wrong because granulation tissue is moist, bumpy new tissue that is red or pink. Option d is wrong because new epithelium is thin new skin at the edges, not yellow tissue on the base.

15. [CORE] An RPN on a medical unit is changing the dressing on a patient's leg wound and notes that the area of warmth and swelling now extends about 4 cm beyond the wound edge. The patient's temperature is 38.4 °C. What is the RPN's most appropriate action?

a. Apply a silver dressing and reassess the wound at the next scheduled dressing change in two days

b. Document the findings and ask the next shift to measure the area again before calling anyone

c. Take a wound swab from the pus on the dressing and send it to the laboratory before reporting

d. Report the findings promptly to the RN and the prescriber using SBAR, and monitor for sepsis

Answer: d — Inflammation more than 2 cm beyond the wound edge with fever suggests spreading infection that needs prompt assessment and possible systemic treatment; the RPN reports promptly using SBAR, consults the RN as the patient's needs change, and watches for sepsis (section 35.3, Wound Infection; Chapters 4 and 6). Option a relies on a dressing for an infection that has spread beyond the wound. Option b delays escalation. Option c delays reporting, and a swab is taken as ordered by the Levine technique from cleansed viable tissue, not from pus.

16. [CORE] An RPN on a surgical unit in an Ontario public hospital is asked to pack a deep stage 4 sacral pressure injury that extends below the dermis. Using CNO's authority, competence and context, which statement is most accurate?

a. The RPN may pack the wound without an order, because wound care is a basic nursing skill for every nurse

b. The RPN may pack it with an order, if she has the competence and the employer's policy and setting allow it

c. The RPN may not pack the wound, because only an RN may perform any procedure below the dermis in Ontario hospitals

d. The RPN may pack the wound only if the wound care nurse is physically present for the entire procedure

Answer: b — Performing a prescribed procedure below the dermis is a controlled act that RNs and RPNs are authorized to perform with an order; the nurse must also have the competence, and employer policy and setting (context) must allow it (section 35.3; section 1.3). Option a is wrong because nurses cannot initiate controlled acts in a public hospital, so an order is needed. Option c is wrong because RPNs share this authority. Option d adds a requirement that is not part of CNO's standard; supervision may be set by employer policy but is not a general rule.

17. [CORE] Which actions help prevent pressure injuries in an adult admitted to hospital with reduced mobility? Select all that apply.

a. Screening pressure injury risk on admission with the tool the employer has chosen, and again when the patient's condition changes

b. Repositioning on a written schedule that is matched to the patient, using a lift sheet rather than dragging the patient up the bed

c. Floating the heels off the mattress with a device that suspends them, while keeping pressure off the Achilles tendon

d. Raising the head of the bed to 60 degrees at all times so that the patient does not slide down toward the foot of the bed

e. Stopping repositioning once the patient is placed on a pressure redistribution mattress, so that the patient can rest

f. Managing incontinence promptly by cleansing gently and applying a barrier product to protect the skin

Answer: a, b, c, f — Risk screening on admission and with change, an individualized repositioning schedule with lift sheets, heel offloading, and prompt moisture management are all recommended prevention measures (section 35.2, Prevention). Option d increases sliding and shear; the head of the bed is kept below about 30 to 35 degrees unless the patient's condition requires otherwise. Option e is wrong because support surfaces reduce pressure but do not replace repositioning.

18. [RN] An RN assesses the heel of a patient with deep brown skin who has been immobile after a stroke. The skin is intact and looks slightly darker than the other heel, with no purple or maroon colour. The area is firm and boggy, cooler than the other heel, and painful to touch. Which conclusion is most appropriate?

a. The findings suggest a deep tissue pressure injury, because colour change may be subtle on darker skin and firmness, temperature change and pain often come first

b. The findings rule out a deep tissue pressure injury, because that diagnosis requires a purple or maroon colour change that would be visible on any skin tone

c. The findings describe a stage 1 pressure injury only, because the skin is intact, and intact skin cannot have damage to deeper tissue below it

d. The findings are most likely from the stroke itself, because changes in temperature and sensation on the affected side are expected after a stroke

Answer: a — A deep tissue pressure injury may not appear purple or maroon on darkly pigmented skin; pain, temperature change and changes in firmness often come before visible colour change (section 35.2, Staging and Care; Table 35.1). Option b is wrong because the colour may not show on darker skin. Option c is wrong because a deep tissue pressure injury can occur under intact skin. Option d attributes new local findings to the stroke and misses a pressure injury that needs offloading and reporting.

19. [RN] An RN assesses a healable venous leg wound that has stalled for three weeks. Drainage has increased, the granulation tissue is bright red and bleeds easily, and there is a new odour. The surrounding skin is not warm, swollen or discoloured, and the patient has no fever. How does the RN interpret these findings?

a. Systemic infection that requires blood cultures and immediate intravenous antibiotics

b. Normal inflammation that is expected during the proliferative phase of wound healing

c. Local infection in the wound that may warrant a topical antimicrobial and reassessment

d. Spreading infection, because increased drainage means that bacteria have left the wound

Answer: c — Three or more NERDS signs (nonhealing, exudate increase, red friable granulation, smell) without surrounding warmth, swelling or systemic signs point to local infection, for which topical antimicrobial treatment and reassessment may be appropriate (section 35.3, Wound Infection; Going Deeper box). Option a would need systemic signs such as fever or malaise. Option b is wrong because inflammation should settle after about four days and friable granulation is not normal. Option d is wrong because spreading infection involves signs beyond the wound edge, such as inflammation more than 2 cm from the edge.

20. [RN] An RN cares for a patient with severe peripheral arterial disease and no surgical options who has a dry wound on the toe. The vascular team has documented the wound as non-healable. Which plan fits wound bed preparation principles?

a. Apply a hydrogel and a moisture-retentive dressing to promote moist healing and encourage the growth of granulation tissue

b. Request sharp debridement at the bedside to remove all dead tissue so that the wound bed can be fully prepared for moist healing

c. Change to an absorbent foam dressing each day to draw out moisture from the wound and speed up the closure of the wound

d. Keep the wound dry and stable with a low-toxicity antiseptic, remove only loose slough conservatively, and focus on comfort

Answer: d — For a non-healable wound, wound bed preparation aims for moisture reduction, bacterial control with low-toxicity antiseptics and conservative removal of only loose slough, with goals centred on comfort and stability (section 35.3, Cleansing and Dressings). Option a promotes moisture, which can encourage bacterial overgrowth in a wound that cannot heal. Option b is wrong because only conservative debridement is appropriate for non-healable wounds. Option c expects closure, which is not the goal for a non-healable wound.

Case: Daniel Okafor (Questions 21–26): Daniel Okafor, 46, is brought to the emergency department of a community hospital in northern Ontario 40 minutes after escaping a house fire. He has partial-thickness burns to his face, the front of his chest and both arms, estimated at about 27% of total body surface area. His voice is hoarse, and there is soot around his nostrils and in his mouth. He says he has a headache and feels sick to his stomach. Vital signs: temperature 37.0 °C, heart rate 116, respiratory rate 24, blood pressure 128/78 mm Hg and oxygen saturation 98% on room air. He weighs 80 kg. He rates his pain 9 out of 10 and keeps asking whether his dog got out of the house.

21. [CORE] Which findings should the nurse recognize as cues that need immediate follow-up? Select all that apply.

a. Hoarse voice

b. Soot around his nostrils and in his mouth

c. Headache and nausea after being in a house fire

d. Heart rate of 116 and respiratory rate of 24

e. Pain rated 9 out of 10

f. Temperature of 37.0 °C

g. Asking whether his dog got out of the house

Answer: a, b, c, d, e — A hoarse voice and soot in the nose and mouth after a fire in an enclosed space are cues of inhalation injury, which can make the airway swell and close (a, b; section 35.5). Headache and nausea after smoke exposure are cues of carbon monoxide poisoning (c). A fast heart rate and breathing rate may reflect pain, airway injury, carbon monoxide or early fluid loss and need follow-up (d). Severe pain needs prompt treatment (e). A temperature of 37.0 °C is normal now, although the nurse keeps him warm (f). His worry about his dog matters for emotional support but is not a physical cue that needs immediate follow-up (g).

22. [CORE] Mr. Okafor's oxygen saturation is 98% on room air. Which interpretation is most accurate?

a. The reading rules out carbon monoxide poisoning, because his blood is fully saturated with oxygen right now.

b. The reading may be falsely high if carbon monoxide is present, so a blood carboxyhemoglobin level is needed.

c. The reading shows that his hoarse voice is from shouting for help rather than from an airway injury.

d. The reading means that oxygen can be held until an arterial blood gas shows a low oxygen level.

Answer: b — Pulse oximetry is unreliable in carbon monoxide poisoning because carboxyhemoglobin falsely raises the reading, so it can read normal; a blood carboxyhemoglobin level is measured (b; section 35.5). A normal reading does not rule out carbon monoxide poisoning (a). Oximetry says nothing about the cause of hoarseness, which is a cue of inhalation injury here (c). Oxygen at 15 L/min by non-rebreather mask is started at once after smoke exposure, not held for test results (d).

23. [CORE] Which problem should the nurse treat as the highest priority for Mr. Okafor?

a. Fluid moving out of his blood vessels into the tissues, leading to burn shock

b. Bacteria entering the open burn wounds and spreading through the blood

c. Severe pain and fear that are raising both his heart rate and his breathing rate

d. Swelling of the upper airway from inhalation injury that could block breathing

Answer: d — Airway comes first; a hoarse voice and soot after an enclosed-space fire point to inhalation injury, and swelling can close the airway (d; section 35.5). Burn shock is a real risk and fluid resuscitation is started early, but an obstructed airway would kill sooner (a). Infection is the leading cause of death later in burn care, not in the first hour (b). Pain and fear need treatment, but they do not outrank a threatened airway (c).

24. [CORE] Which plan for Mr. Okafor's first hour best fits his needs?

a. Oxygen at 15 L/min by non-rebreather mask, preparation for early airway management, IV access, small repeated doses of IV analgesia and a call to the burn centre

b. Oxygen at 2 L/min by nasal prongs, ice packs wrapped in towels on the burns, intramuscular morphine for pain and admission to the medical unit for observation

c. Room air until the carboxyhemoglobin result returns, moist dressings on all of the burns, oral analgesia and a referral to plastic surgery as an outpatient next week

d. Oxygen at 15 L/min by non-rebreather mask, cold water poured over all of the burns for 60 minutes, oral analgesia and discharge home once the pain is controlled

Answer: a — High-flow oxygen treats carbon monoxide exposure, the airway may need to be secured early, IV access is needed for fluids, IV analgesia in small doses works reliably, and his burns (partial-thickness burns of 10% TBSA or more and suspected inhalation injury) meet criteria for immediate burn centre consultation (a; section 35.5). Low-flow oxygen, ice and intramuscular opioids are unsafe; intramuscular absorption is unreliable in burns over 10% TBSA (b). Oxygen must not wait for test results, and dressings are not applied before burn team consultation (c). Long cooling of a large burn with cold water risks hypothermia, and he needs transfer, not discharge (d).

25. [RN] The burn centre advises lactated Ringer's at 270 mL/h, a urinary catheter and an adult urine output target of 30 to 50 mL/h. Over the next 2 hours, Mr. Okafor's urine output is 18 mL and then 20 mL. What should the nurse do?

a. Double the IV rate on their own and keep it there until his urine output rises above 50 mL/h.

b. Ask the physician for a diuretic so that his kidneys will make more urine during resuscitation.

c. Report the low output promptly so the team can adjust the fluid rate, and keep measuring hourly.

d. Keep the same rate and recheck in 4 hours, because urine output is often low in the first hours.

Answer: c — The fluid rate is adjusted to urine output by the burn team; output well below 30 mL/h is reported promptly, and hourly measurement continues (c; section 35.5, Going Deeper box). The nurse does not change the ordered rate on their own, and too much fluid causes edema and compartment syndromes (a). A diuretic would not treat low circulating volume and could make it worse (b). Waiting 4 hours with low output risks under-resuscitation and organ failure (d).

26. [CORE] Two hours after arrival, while Mr. Okafor waits for air transfer to the burn centre, which finding shows that his condition is getting worse and needs immediate action?

a. His pain has gone down from 9 to 5 out of 10 after two doses of IV analgesia.

b. He now makes a high-pitched sound when breathing in and is drooling.

c. His urine output for the past hour is 40 mL with the adjusted fluid rate.

d. New thin-walled blisters have formed on the burns on both of his forearms.

Answer: b — Stridor and drooling show that his upper airway is swelling; the nurse calls for help at once so the airway can be secured before transfer (b; section 35.5). Falling pain shows that analgesia is working (a). Urine output of 40 mL/h is within the 30 to 50 mL/h target (c). Blisters are expected in superficial partial-thickness burns (d).

27. [CORE] On day 6 after abdominal surgery, a 64-year-old man coughs and says, "Something just gave way." The nurse finds the incision open, with loops of bowel visible. What should the nurse do first?

a. Gently push the bowel back into the abdomen and close the edges with adhesive strips.

b. Go to the supply room for a suture kit and page the wound care nurse to come and assess him.

c. Stay, call for help, and cover the bowel with sterile gauze moistened with sterile saline.

d. Irrigate the open wound with sterile saline, then cover it with a dry gauze dressing.

Answer: c — Evisceration is a surgical emergency; the nurse stays with the patient, has the surgeon called and covers the organs with sterile saline-moistened gauze (c; section 35.4). Nurses do not try to replace the organs or close the wound (a). Leaving the patient delays help and leaves him alone in an emergency (b). A separated incision is not irrigated without the surgeon, and exposed organs are covered with moist, not dry, gauze (d).

28. [CORE] The nurse assesses a 55-year-old woman's abdominal incision on day 7 after surgery. Which finding is expected?

a. A firm ridge can be felt under the whole length of the incision.

b. Clear yellow fluid is draining from one end of the incision line.

c. The edges of the incision have separated by 1 cm at the centre.

d. The skin around the incision feels warmer than it did on day 3.

Answer: a — A healing ridge of new collagen should be felt along the whole incision between days 5 and 9 (a; section 35.4). Ongoing drainage at this stage is not expected and is reported (b). Separation of the edges is dehiscence (c). Warmth that increases after the first days suggests infection rather than normal inflammation (d).

29. [CORE] A patient with very dark skin is 5 days after a bowel resection. Which approach best helps the nurse find an early surgical site infection?

a. Look for bright redness along the incision under the room's overhead fluorescent light.

b. Ask the patient to call the nurse only if the incision starts to bleed through the dressing.

c. Wait for the white blood cell count result before deciding whether to look at the incision.

d. Feel for warmth and firmness, check swelling and pain, and ask the patient what has changed.

Answer: d — On darker skin, redness may not show, so the nurse relies on warmth, firmness, swelling, pain and the person's own report, compared with nearby skin (d; section 35.4). Looking only for redness misses early infection on darker skin (a). Bleeding is not the main sign of infection, and waiting for it delays detection (b). The nurse assesses the incision directly; a blood test does not replace it (c).

30. [CORE] A 47-year-old man with brown skin is admitted with cellulitis of the left lower leg. Which action best helps the team judge whether the infection is spreading?

a. Wrap the leg firmly from the toes to the knee with an elastic bandage to limit the swelling.

b. Mark the edge of the area and date it, and record how far the warmth and swelling extend.

c. Take one photograph of the leg on admission so the team can compare it at discharge.

d. Keep the leg hanging over the side of the bed to bring more blood flow to the infection.

Answer: b — Marking and dating the edge, and recording warmth and swelling because colour may be hard to see on brown skin, lets the team see spread over time (b; section 35.4). Wrapping the leg does not show whether the infection is spreading and covers the skin the nurse needs to see (a). One photograph cannot show change during the stay (c). The limb is elevated, not kept dependent (d).

31. [CORE] A woman with obesity and long-standing leg edema is recovering from her second episode of leg cellulitis this year. Which teaching is most likely to lower her risk of another episode?

a. Stop taking the antibiotic as soon as the colour of the leg returns to its usual shade.

b. Soak your feet in hot water every evening to keep the skin soft and clean.

c. Check between your toes daily for cracks or moist skin, and manage the swelling.

d. Avoid walking until the swelling in both legs has gone down completely.

Answer: c — Edema and cracked, scaly or moist skin between the toes are risk factors for repeated cellulitis, and treating them lowers the risk (c; section 35.4). Antibiotics are taken as prescribed, not stopped early (a). Daily soaking can leave the skin between the toes moist, which is itself a risk factor (b). Avoiding walking does not treat her risk factors and is not recommended (d).

32. [CORE] A man is going home 3 days after an open hernia repair. Which findings should the nurse teach him to report to his surgeon? Select all that apply.

a. Pain in the incision that is increasing rather than easing

b. Drainage from the incision that is cloudy or smells bad

c. Edges of the incision that are pulling apart

d. A temperature of 38.3 °C

e. A firm ridge felt under the incision during the first week

f. Staples still in place 5 days after surgery

Answer: a, b, c, d — Increasing pain, cloudy or foul-smelling drainage, separating edges and fever are signs of infection or dehiscence and are reported (a, b, c, d; section 35.4, Patient Education box). A healing ridge is a normal sign of healing (e). Staples usually stay in for 7 to 10 days (f).

33. [CORE] A woman calls a telehealth line 5 minutes after spilling boiling water on her forearm. The burn is about the size of her palm. Which advice is best?

a. Hold the forearm under cool running tap water for about 20 minutes and take off any rings or bracelets.

b. Hold a bag of ice wrapped in a thin towel on the forearm for 20 minutes to stop the burning more quickly.

c. Spread butter or cooking oil over the burn to seal out the air, then cover it with plastic wrap.

d. Break any blisters that form with a clean needle, then wrap the forearm in a tight bandage.

Answer: a — Cool or tepid running water for about 20 minutes is the recommended first aid, and jewellery is removed before swelling starts (a; section 35.5). Ice and very cold water are avoided because they can deepen the injury and cause cold injury (b). Butter or oil is not part of recommended first aid, which is cooling with running water (c). Blisters are left for the care team to manage, and a tight wrap can restrict circulation as the tissue swells (d).

34. [CORE] A worker arrives at an emergency department with dry lime powder on both forearms. What should the nurse do first?

a. Pour water over his forearms right away to dilute the chemical as fast as possible.

b. Apply vinegar to the forearms to neutralize the lime before rinsing with water.

c. Cover the forearms with dry sterile dressings and wait for advice from a poison centre.

d. Put on protective equipment, remove his clothing, brush off the powder, then irrigate.

Answer: d — Staff protect themselves, remove contaminated clothing and brush off dry powder before rinsing continuously with water (d; section 35.5). Dry lime is brushed off before any water is applied (a). The recommended first aid is to remove the chemical and rinse with water, not to apply another chemical (b). Waiting without removing the chemical lets the burn deepen; a poison centre can be called while care continues (c).

35. [CORE] During a bed bath, the nurse notices a mole on a 70-year-old man's back. Which finding is most important to report?

a. The mole is round, evenly brown and about 3 mm across.

b. The man says the mole has grown and become itchy in recent months.

c. The man says the mole has looked the same for more than 20 years.

d. Several small, flat, evenly coloured freckles are on both shoulders.

Answer: b — Evolving, a change in size, shape, colour or feel or new itching, is one of the ABCDE warning signs of melanoma (b; section 35.6). A small, round, evenly coloured mole has none of the warning signs (a). A mole that has not changed in years is less concerning (c). Evenly coloured freckles are not warning signs (d).

36. [CORE] A 62-year-old Black man says that a dark streak appeared in his big toenail during the past year and now extends onto the skin next to the nail. What should the nurse do?

a. Explain that dark streaks in the nails are common and harmless in people with darker skin tones.

b. Teach him to apply sunscreen to his feet, because sun exposure causes this kind of change.

c. Report the finding so that he can be assessed promptly for a possible melanoma of the nail.

d. Advise him to keep the toenail trimmed short and to watch the streak for another year.

Answer: c — Acral melanoma is the most common melanoma in people with darker skin and can appear as a dark nail streak extending toward the nail fold; it needs prompt assessment (c; section 35.6). Dismissing the change contributes to late diagnosis (a). Acral melanoma is not linked to sun exposure, so sunscreen would not address it (b). Waiting a year delays diagnosis (d).

37. [CORE] A 74-year-old woman has had a painful band of blisters on the right side of her chest for 1 day. Which statement by the nurse is accurate?

a. "Antiviral medicine works best when started within 72 hours of the rash, so you should be seen today."

b. "Shingles usually spreads to both sides of the chest, so check the left side every day this week."

c. "Antiviral medicine only helps if you start it before the rash appears, so it will not do anything for you now."

d. "Shingles pain always ends when the blisters heal, so you will not need follow-up for pain."

Answer: a — Antivirals are started within 72 hours of rash onset, so same-day assessment matters (a; section 35.6). The rash usually stays on one side and does not cross the midline (b). Antivirals are started after the rash appears, ideally within 72 hours (c). Pain lasting more than 30 days after the rash, postherpetic neuralgia, is the most common complication (d).

38. [CORE] An RPN on a surgical unit is assigned a patient with negative pressure wound therapy on an open abdominal wound. The RPN has never managed this device, and the unit's policy requires education before a nurse cares for it. What should the RPN do?

a. Read the device manual quickly at the bedside, and then change the dressing at the scheduled time.

b. Ask the patient to explain how the dressing was changed and follow those instructions.

c. Turn off the pump until the next shift, when a nurse with education can restart it.

d. Tell the charge nurse about the gap, ask for that task to be reassigned and arrange education.

Answer: d — A nurse performs an activity only with the competence to do it safely, and this unit requires education first; the RPN speaks up and asks for support (d; section 35.6, Scope in Practice box). A quick read does not provide the knowledge, skill and judgment required (a). The patient's description cannot replace education (b). Stopping therapy without an order or assessment could harm the wound (c).

39. [RN] A 70-kg adult has partial-thickness and full-thickness burns covering 30% of total body surface area. The burn team orders lactated Ringer's at 2 mL/kg/%TBSA for the first 24 hours, with the starting hourly rate set at the 24-hour total divided by 16. Which is correct?

a. The 24-hour total is 2,100 mL, and the starting rate is about 131 mL/h.

b. The 24-hour total is 4,200 mL, and the starting rate is about 263 mL/h.

c. The 24-hour total is 4,200 mL, and the starting rate is about 175 mL/h.

d. The 24-hour total is 8,400 mL, and the starting rate is about 525 mL/h.

Answer: b — 2 mL × 70 kg × 30 = 4,200 mL; 4,200 ÷ 16 is about 263 mL/h, which gives half the estimate in the first 8 hours, and the team then adjusts the rate to urine output (b; section 35.5, Going Deeper box). Option a halves the formula (a). Option c spreads the volume evenly over 24 hours (c). Option d uses 4 mL/kg/%TBSA, the older starting point (d).

40. [RN] A 40-year-old man was admitted yesterday with cellulitis of the thigh after a small cut and is receiving IV antibiotics. Which finding most strongly suggests a necrotizing soft tissue infection?

a. The colour change is still inside the edge that was marked and dated on admission.

b. His temperature has come down from 38.4 °C to 37.6 °C since the IV antibiotics were started.

c. He has mild tenderness over the area when the nurse gently presses on the thigh.

d. He has severe pain out of proportion to the skin, with hard tissue past the marked edge.

Answer: d — Pain out of proportion to the visible findings and hard, wooden-feeling tissue beyond the skin change are red flags for necrotizing infection, which needs urgent surgical assessment (d; section 35.4). A change that stays inside the marked edge suggests the infection is not spreading (a). A falling temperature suggests a response to treatment (b). Mild tenderness is expected in cellulitis (c).

References

American Burn Association. (2025). *Guidelines for burn patient referral*. https://ameriburn.org/burnreferral

BC Provincial Nursing Skin and Wound Committee. (2011). *Guideline: Assessment and treatment of surgical wounds healing by primary and secondary intention in adults & children*. https://www.clwk.ca/get-resource/surgical-wounds-incision-surgical-dehiscence-guideline

Bell, N., Simons, R., Hameed, S. M., Schuurman, N., & Wheeler, S. (2012). Does direct transport to provincial burn centres improve outcomes? A spatial epidemiology of severe burn injury in British Columbia, 2001–2006. *Canadian Journal of Surgery, 55*(2), 110–116. https://doi.org/10.1503/cjs.014708

Beyene, R., & Hayhurst, C. (2026). *Adult inhalation injury* [Clinical practice guideline]. Vanderbilt University Medical Center Burn Center. https://www.vumc.org/burn/sites/default/files/public_files/Protocols/Adult-Inhalation-Injury-May-2026.pdf

Black, J., & Simende, A. (2020). Ten top tips: Assessing darkly pigmented skin. *Wounds International, 11*(3), 8–11. https://woundsinternational.com/wp-content/uploads/2023/02/d34b6a6f02b2659b00636c49b453046c.pdf

Brenner, D. R., Gillis, J., Demers, A. A., Ellison, L. F., Ng, C., Zhang, S. X., Finley, C., Fitzgerald, N., Saint-Jacques, N., Shack, L., Turner, D., Urquhart, R., & Woods, R. R. (2026). Projected estimates of cancer in Canada in 2026. *CMAJ, 198*(14), E526–E534. https://doi.org/10.1503/cmaj.252152

British Lymphology Society & Lymphoedema Support Network. (2016). *Consensus document on the management of cellulitis in lymphoedema*. https://legsmatter.org/wp-content/uploads/2018/04/CellulitisConsensus.pdf

Canadian Cancer Society. (2024). *Non-melanoma skin cancer statistics*. https://cancer.ca/en/cancer-information/cancer-types/skin-non-melanoma/statistics

Canadian Cancer Society. (2026). *Melanoma skin cancer statistics*. https://cancer.ca/en/cancer-information/cancer-types/melanoma-skin/statistics

Canadian Cancer Society. (n.d.-a). *Signs and symptoms of melanoma skin cancer*. Retrieved October 27, 2026, from https://cancer.ca/en/cancer-information/cancer-types/melanoma-skin/signs-and-symptoms

Canadian Cancer Society. (n.d.-b). *What is melanoma skin cancer?* Retrieved October 27, 2026, from https://cancer.ca/en/cancer-information/cancer-types/melanoma-skin/what-is-melanoma

Canadian Cancer Society. (n.d.-c). *What is non-melanoma skin cancer?* Retrieved October 27, 2026, from https://cancer.ca/en/cancer-information/cancer-types/skin-non-melanoma/what-is-non-melanoma-skin-cancer

Canadian Dermatology Association. (2026a). *Eczema*. https://dermatology.ca/public-patients/skin/eczema/

Canadian Dermatology Association. (2026b). *Psoriasis*. https://dermatology.ca/public-patients/skin/psoriasis/

Canadian Institute for Health Information. (n.d.-a). *Patient safety: Indicators*. Retrieved October 27, 2026, from https://www.cihi.ca/en/book/export/html/10200

Canadian Institute for Health Information. (n.d.-b). *Worsened pressure ulcer in long-term care*. Retrieved October 27, 2026, from https://www.cihi.ca/en/indicators/worsened-pressure-ulcer-in-long-term-care

Cartotto, R., Johnson, L. S., Savetamal, A., Greenhalgh, D., Kubasiak, J. C., Pham, T. N., Rizzo, J. A., Sen, S., & Main, E. (2024). American Burn Association clinical practice guidelines on burn shock resuscitation. *Journal of Burn Care & Research, 45*(3), 565–589. https://doi.org/10.1093/jbcr/irad125

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

Deb, S., Leis, J. A., & Mason, S. A. (2024). Necrotizing soft-tissue infections caused by invasive group A *Streptococcus*. *CMAJ, 196*(38), E1291. https://doi.org/10.1503/cmaj.240267

Downey, W. R. (2020, February 9). Wound dehiscence. *American Nurse Journal*. https://www.myamericannurse.com/wound-dehiscence/

Edsberg, L. E., Black, J. M., Goldberg, M., McNichol, L., Moore, L., & Sieggreen, M. (2016). Revised National Pressure Ulcer Advisory Panel pressure injury staging system: Revised pressure injury staging system. *Journal of Wound, Ostomy and Continence Nursing, 43*(6), 585–597. https://doi.org/10.1097/WON.0000000000000281

Forest-Lalande, L., Parsons, L., McPhee, S., Kuhnke, J. L., Hoover, J., Lillington, T., & Dann, L. J. (2025). Best practice recommendations for the prevention and management of moisture-associated skin damage. In J. L. Kuhnke, C. A. Burrows, R. M. Evans, H. L. Orsted, & S. Rosenthal (Eds.), *Best practice recommendations for skin health and wound management 2025*. Wounds Canada. https://doi.org/10.56885/JWRY3671

Gooderham, M. J., Hong, H. C., Lynde, C., Papp, K. A., Yeung, J., Lui, H., Miller-Monthrope, Y., Ringuet, J., Turchin, I., & Prajapati, V. H. (2025). Canadian consensus guidelines for the management of atopic dermatitis with topical therapies. *Dermatology and Therapy, 15*(6), 1467–1485. https://doi.org/10.1007/s13555-025-01386-2

Health Canada. (2023). *Sun safety basics*. https://www.canada.ca/en/health-canada/services/sun-safety/sun-safety-basics.html

Jeschke, M. G., van Baar, M. E., Choudhry, M. A., Chung, K. K., Gibran, N. S., & Logsetty, S. (2020). Burn injury. *Nature Reviews Disease Primers, 6*(1). https://doi.org/10.1038/s41572-020-0145-5

Krishnan, R., Baclic, O., Howarth, A., Tuite, A. R., & Andrew, M. K., on behalf of the National Advisory Committee on Immunization. (2026). Summary of the National Advisory Committee on Immunization (NACI) statement: Updated recommendations on herpes zoster vaccination for adults who are immunocompromised. *Canada Communicable Disease Report, 52*(1/2), 1–7. https://doi.org/10.14745/ccdr.v52i0102a01

MacFadden, D. R., & Gold, W. L. (2012). A 69-year-old man with a painful vesicular rash. *CMAJ, 184*(13), 1489–1491. https://doi.org/10.1503/cmaj.120480

Nadelmann, E. R., Singh, A. K., Abbruzzese, M., Adeuyan, O. O., Kenchappa, D. B., Kovrizhkin, K., Lightman, M., Samouha, A., Tao, K. L., Yun, J., Zhu, T., McLellan, B., & Saenger, Y. M. (2025). Acral melanoma in skin of color: Current insights and future directions: A narrative review. *Cancers, 17*(3), Article 468. https://doi.org/10.3390/cancers17030468

National Pressure Injury Advisory Panel. (n.d.). *NPIAP pressure injury stages*. Retrieved October 27, 2026, from https://cdn.ymaws.com/npiap.com/resource/resmgr/online_store/npiap_pressure_injury_stages.pdf

Nokaneng, E., Heerschap, C., Thayer, D., Ousey, K., Holloway, S., LeBlanc, K., Netsch, D., Vance, H., Emmons, K. R., & Woo, K. (2025). *Best practice recommendations for the prevention and management of skin tears in aged skin* (2nd ed.). Wounds International. https://woundsinternational.com/wp-content/uploads/2025/05/ISTAP25_CD_Skin-tears_WINT_web.pdf

Norton, L., Parslow, N., Ho, C., O'Sullivan-Drombolis, D., Rogers, A., Parsons, A., & Moss, L. (2025). Best practice recommendations for the prevention and management of pressure injuries. In J. L. Kuhnke, C. A. Burrows, R. M. Evans, H. L. Orsted, & S. Rosenthal (Eds.), *Best practice recommendations for skin health and wound management 2025*. Wounds Canada. https://doi.org/10.56885/GRYI5585

Nurses Specialized in Wound, Ostomy and Continence Canada. (2021). *Debridement: Canadian best practice recommendations for nurses* (1st ed.). https://www.nswoc.ca/_files/ugd/9d080f_10b9866b6a984dffb93c3f63cff7cf3d.pdf

Orsted, H. L., Keast, D. H., Forest-Lalande, L., Kuhnke, J. L., O'Sullivan-Drombolis, D., Jin, S., & Evans, R. (2025a). Best practice recommendations for the prevention and management of wounds: An overview. In J. L. Kuhnke, C. A. Burrows, R. M. Evans, H. L. Orsted, & S. Rosenthal (Eds.), *Best practice recommendations for skin health and wound management 2025*. Wounds Canada. https://doi.org/10.56885/CVEU6924

Orsted, H. L., Keast, D. H., Forest-Lalande, L., Kuhnke, J. L., O'Sullivan-Drombolis, D., Jin, S., & Evans, R. (2025b). Skin: Anatomy, physiology and wound healing. In J. L. Kuhnke, C. A. Burrows, R. M. Evans, H. L. Orsted, & S. Rosenthal (Eds.), *Best practice recommendations for skin health and wound management 2025*. Wounds Canada. https://doi.org/10.56885/PEWY3827

Public Health Agency of Canada. (2025). *Herpes zoster (shingles) vaccine: Canadian immunization guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-4-active-vaccines/page-8-herpes-zoster-(shingles)-vaccine.html

Public Health Agency of Canada. (2026). *Tetanus toxoid: Canadian immunization guide*. https://www.canada.ca/en/public-health/services/publications/healthy-living/canadian-immunization-guide-part-4-active-vaccines/page-22-tetanus-toxoid.html

Pusey-Reid, E., Quinn, L., Samost, M. E., & Reidy, P. A. (2023). Skin assessment in patients with dark skin tone. *American Journal of Nursing, 123*(3), 36–43. https://doi.org/10.1097/01.NAJ.0000921800.61980.7e

Sibbald, R. G., Elliott, J. A., Persaud-Jaimangal, R., Goodman, L., Armstrong, D. G., Harley, C., Coelho, S., Xi, N., Evans, R., Mayer, D. O., Zhao, X., Heil, J., Kotru, B., Delmore, B., LeBlanc, K., Ayello, E. A., Smart, H., Tariq, G., Alavi, A., & Somayaji, R. (2022). Wound bed preparation. *WCET Journal, 42*(1), 16–28. https://doi.org/10.33235/wcet.42.1.16-28

Stevens, D. L., Bisno, A. L., Chambers, H. F., Dellinger, E. P., Goldstein, E. J. C., Gorbach, S. L., Hirschmann, J. V., Kaplan, S. L., Montoya, J. G., & Wade, J. C. (2014). Practice guidelines for the diagnosis and management of skin and soft tissue infections: 2014 update by the Infectious Diseases Society of America. *Clinical Infectious Diseases, 59*(2), e10–e52. https://doi.org/10.1093/cid/ciu296

Sunnybrook Health Sciences Centre. (n.d.). *About the Ross Tilley Burn Centre*. Retrieved October 27, 2026, from https://sunnybrook.ca/content/?page=ross-tilley-burn-centre

Tecson, A., Lewis, K., Somayaji, R., Arsenault, A., Fry, N., & Kuhnke, J. L. (2025). Best practice recommendations for the prevention and management of surgical wound complications. In J. L. Kuhnke, C. A. Burrows, R. M. Evans, H. L. Orsted, & S. Rosenthal (Eds.), *Best practice recommendations for skin health and wound management 2025*. Wounds Canada. https://doi.org/10.56885/PULG8219

Trauma New Brunswick. (2025). *Consensus statement: Emergency burn care* (Version 2). https://traumanb.ca/wp-content/uploads/2025/10/Consensus-Statement-Emergency-Burn-Care-AUGUST-2025-FINAL.pdf

Wallace, D., Chadwick, S., Rasmussen, J., Jeschke, M., McCallum, C., Godleski, M., Shahrokhi, S., Forest-Lalande, L., Radhakrishnan, M., & Kuhnke, J. L. (2025). Best practice recommendations for the prevention and management of burns. In J. L. Kuhnke, C. A. Burrows, R. M. Evans, H. L. Orsted, & S. Rosenthal (Eds.), *Best practice recommendations for skin health and wound management 2025*. Wounds Canada. https://doi.org/10.56885/WQUR3382

Woodbury, M. G., & Houghton, P. E. (2004). Prevalence of pressure ulcers in Canadian healthcare settings. *Ostomy/Wound Management, 50*(10), 22–24, 26, 28, 30, 32, 34, 36–38.

World Union of Wound Healing Societies. (2018). *Surgical wound dehiscence: Improving prevention and outcomes* [Consensus document]. Wounds International. https://woundsinternational.com/wp-content/uploads/2023/02/3bc56168ce170d2745c58ebf922a75e1.pdf

Wounds International. (2023). *Wound care and skin tone made easy*. https://woundsinternational.com/wp-content/uploads/2023/05/MULTI23_ME_SkinTones_WINT-web.pdf

36 Eye and Ear Disorders

LEARNING OUTCOMES & COMPETENCY MAPPING

By the end of this chapter, you will be able to:

1. Assess vision and the eyes, and care for adults with vision loss in ways that support safety and independence.
2. Care for adults with cataract, glaucoma, macular degeneration and diabetic retinopathy, including safe use of eye drops.
3. Recognize eye emergencies and give first actions and care after eye surgery, using the CJMM.
4. Assess hearing and recognize types of hearing loss, including hearing loss from ototoxic medicines.
5. Provide communication access for people with hearing loss and Deaf people, and care for hearing aids and cochlear implants in hospital.
6. Care for adults with ear and balance disorders and after ear surgery, including fall prevention.
7. Distinguish RN and RPN roles in eye and ear care using CNO's authority, competence and context.

How the outcomes map to the CNO entry-to-practice competencies

Outcome	RN competency role (CNO, 2019a)	RPN competency category (CNO, 2019b)
1, 2, 3, 4, 6	Clinician; Communicator	Foundations of Practice
5	Advocate; Communicator	Foundations of Practice; Ethical Practice
7	Professional; Collaborator	Legal Practice; Collaborative Practice

Introduction

Sight and hearing link people to everything around them: faces, voices, print, traffic, alarms and the nurse at the bedside. When either sense is impaired, a hospital stay becomes harder and less safe. A person who cannot read a label, find the call bell or hear a question may be judged confused, may fall, or may agree to care they have not understood. Vision loss is common in Canada. Nearly 2.2 million Canadians aged 15 and older (7.4%) reported a seeing disability in 2022 (Statistics Canada, 2025). Much vision loss can be prevented or treated if found early (Fighting Blindness Canada, 2021), and nurses are often first to notice a change.

This chapter is the book's home for eye and ear care. Section 36.1 explains how the eye works, how to assess vision and the eyes, and how to care for people with vision loss. Section 36.2 covers cataract, glaucoma, age-related macular degeneration and diabetic retinopathy. Section 36.3 covers eye emergencies, eye injuries and care after eye surgery. The second half of the chapter turns to hearing and ear assessment (section 36.4), communication access for people with hearing loss and Deaf people, including hearing aids and cochlear implants (section 36.5), and ear and balance disorders and ear surgery (section 36.6).

The chapter builds on earlier ones. Scope of practice for registered nurses (RNs) and registered practical nurses (RPNs) is taught in section 1.3, and the Clinical Judgment Measurement Model (CJMM) in section 1.4. Outside Ontario, practical nurses (PNs) are often called licensed practical nurses (LPNs); this chapter uses "the nurse" unless the roles differ. Disability, accessibility and cultural safety are in Chapter 2, recognizing deterioration and SBAR (Situation, Background, Assessment, Recommendation) in Chapter 6, perioperative care in Chapter 7, and delirium, dementia and falls in Chapter 8. Pupil and cranial nerve assessment are in Chapter 30, stroke and visual field loss in Chapter 31, and diabetes in Chapter 22.

36.1 Vision and Eye Assessment

How the Eye Works

Light enters the eye through the **cornea**, the clear, curved front surface of the eye, which bends incoming light to help focus it. The iris, the coloured part of the eye, controls how much light passes through the pupil. Behind the pupil, the **lens**, a clear structure, works with the cornea to focus light onto the **retina**, the light-sensitive layer at the back of the eye. Photoreceptor cells in the retina turn light into electrical signals, and the **optic nerve** carries these signals to the brain, which turns them into the images we see (National Eye Institute [NEI], 2022). Near the centre of the retina is the **macula**, the area that gives sharp central vision; disease of the macula causes loss of central vision (Eiselen et al., 2026; Figure 36.1).

The front of the eye is filled with a clear fluid called **aqueous humour**. The ciliary processes behind the iris secrete it continuously (Sandoz Canada, 2026). It leaves the eye mainly through a drainage angle at the front of the eye (Royal Victorian Eye and Ear Hospital [RVEEH], 2017) and partly through a second route called uveoscleral outflow (Bausch & Lomb, 2022). The balance between how much fluid is made and how much drains away sets the **intraocular pressure (IOP)**, the pressure inside the eye. Raised IOP is a major risk factor for optic nerve damage and the visual field loss of glaucoma (Sandoz Canada, 2026). A pressure above about 22 mm Hg raises the risk of glaucoma, yet about half of people with glaucoma have normal pressure (Basilious & Buys, 2015). Glaucoma medicines change this balance (Going Deeper box, section 36.3).



Figure 36.1 Cross-sectional anatomy of the human eye showing refractive structures (cornea, lens), anterior and posterior chambers, vascular uvea (iris, ciliary body, choroid), neurosensory retina and optic nerve. (credit: “Figure 14.15, Structure of the Eye” by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Assessing Vision and the Eyes

Assessment starts with the person's own account. The nurse asks:

- **Usual vision:** whether the person wears glasses or contact lenses, uses a magnifier or other aids, and has them in hospital.
- **Change:** whether vision has changed, in one eye or both, and whether the change was sudden or gradual. Sudden change is treated as urgent (section 36.3).
- **Symptoms:** pain, redness, discharge, sensitivity to light, new flashes of light or floaters (section 36.3), halos around lights (section 36.2), and straight lines that look wavy or distorted (Eiselen et al., 2026).
- **History:** eye conditions and every eye drop used, diabetes, high blood pressure, corticosteroid use, family history of glaucoma, and the last eye examination (Basilious & Buys, 2015).

People often do not notice or report gradual vision loss, especially when it develops slowly or occurs with cognitive impairment (US Preventive Services Task Force [USPSTF], 2022). The nurse therefore also watches how the person manages: reading a menu, finding the call bell, recognizing faces and moving around the room.

Visual acuity is the sharpness of vision at a set distance. The most common tools in primary care are standard letter charts such as the Snellen chart; other tools include the pinhole test and the Amsler grid, a square grid of lines used to check central vision (USPSTF, 2022). The nurse follows the setting's procedure for the test and notes whether the person wore their usual glasses or contact lenses (Figure 36.2).

The nurse then inspects the outer eye in good light: eyelids and lashes, the white of the eye, the clarity of the cornea, any discharge, swelling or injury, and whether the eyes look the same. Redness of the white of the eye is visible on every skin tone, but redness of the eyelid skin may show only as a patch darker than the person's usual skin on darkly pigmented skin, so the nurse compares both sides and asks about pain and itching (Chapter 35). Pupil assessment is taught in Chapter 30.



Figure 36.2 A Snellen letter chart used to measure distance visual acuity. (credit: "Snellen Chart" by Creative magnet/Wikimedia Commons, CC BY-SA 4.0)

Caring for People With Vision Loss

In 2022, the share of Canadians aged 15 and older with a seeing disability rose with age, from 4.3% at ages 15 to 24 to 11.4% at age 65 and older. It was higher among women+ (8.8%) than men+ (5.9%) (Statistics Canada, 2025). A 2021 report commissioned by Fighting Blindness Canada estimated that 1.2 million people in Canada are living with vision loss and that more than 8 million have one of the four main eye diseases that cause blindness: age-related macular degeneration, glaucoma, diabetic retinopathy and cataract (Fighting Blindness Canada, 2021).

In this chapter, **low vision** means vision loss that cannot be fully corrected with glasses, contact lenses, medicine or surgery and that limits everyday activities. Many people with low vision live independently and know what help they want. The nurse asks rather than assumes and builds care around the person's own methods. Accessibility rights and accommodation are covered in Chapter 2.

- **Introductions:** the nurse says their name and role on entering, speaks directly to the person, and says when they are leaving the room.
- **Orientation:** the nurse describes the surroundings in detail (CNIB, n.d.-b), including the bed controls, call bell, bathroom and the person's belongings, and leaves items where the person put them.
- **Sighted guide: sighted guide** is a way of walking with a person who is blind or partially sighted. The nurse first asks whether the person wants help. If they do, the nurse lightly touches the back of the person's hand with their own hand to signal where the guiding arm is. The person holds the nurse's arm just above the elbow and walks about half a step behind. The nurse describes doors, steps and turns before reaching them and, when leaving, makes sure the person is beside a tangible reference point, such as a wall. The nurse never grabs, pushes or pulls the person, their white cane or their guide dog, and does not pet a guide dog without the owner's permission (CNIB, n.d.-a, n.d.-b).
- **Accessible information:** large print, audio and electronic formats that work with the person's own devices. Among Canadians with a seeing disability who used adaptations, common ones were speech-to-text or text-to-speech, screen magnification and screen readers (Statistics Canada, 2025). Consent forms and discharge teaching are read aloud when needed (Chapter 1).
- **Meals and medications:** the nurse says what is on the tray and where, opens packages if asked, and offers large-print or audio medication information.
- **Safety:** impaired vision is linked with falls and other injuries (USPSTF, 2022). Falls prevention is taught in Chapter 8.

Some people with significant vision loss see images of people, landscapes or patterns that are not there. This is called **Charles Bonnet syndrome**; it follows vision loss from conditions such as macular degeneration and glaucoma, and it is often mistaken for dementia or a mental health problem (Perceptual Neuroscience Laboratory, n.d.). The nurse listens without judgment, reports it and connects the person with vision loss services such as CNIB.

LIFESPAN CONSIDERATIONS

Vision Loss in Older Adults

- **Older adults:** seeing disability is most common at age 65 and older (Statistics Canada, 2025). Cataract, macular degeneration, glaucoma and diabetic retinopathy are the four major blinding eye diseases in Canada (Fighting Blindness Canada, 2021).

- **Hidden loss:** older adults may not notice or report gradual loss, especially when they also have cognitive impairment (USPSTF, 2022). A person who cannot see the clock, the menu or the nurse's face may look disoriented. Vision is checked, and glasses found, before confusion is assumed; delirium and dementia are compared in Chapter 8.
- **Falls:** impaired vision is linked with falls (USPSTF, 2022). Glasses are kept clean, labelled and within reach; the path to the bathroom is lit and clear.
- **Treatment helps:** cataract surgery is associated with fewer falls and lower rates of dementia (Chen et al., 2025). Age alone is never a reason to accept poor vision as normal.
- **Hallucinations:** Charles Bonnet syndrome can be mistaken for dementia (Perceptual Neuroscience Laboratory, n.d.). The nurse asks whether the images are new, whether the person knows they are not real, and reports them so the team can assess.
- **Younger adults:** seeing disability also affects working-age adults; 4.5% of Canadians aged 25 to 44 reported one in 2022 (Statistics Canada, 2025).

36.2 Cataract, Glaucoma and Other Causes of Vision Loss

Cataract

A **cataract** is a clouding of the lens of the eye. Cataract is one of the main causes of impaired vision and blindness. Older age is the main risk factor. Genetics, some medicines such as corticosteroids, eye injury, ultraviolet light exposure, radiation therapy and poorly controlled diabetes also contribute (Chen et al., 2025). Vision becomes gradually blurred or cloudy in one or both eyes. Diagnosis is made by an optometrist or ophthalmologist during an eye examination (Figure 36.3).



Figure 36.3 Slit-lamp view of a dense cataract clouding the crystalline lens behind the pupil. (credit: “Cataract in human eye” by Rakesh Ahuja, MD/Wikimedia Commons, CC BY-SA 3.0)

Surgery is offered when poor vision interferes with daily activities. The cloudy lens is removed and replaced with a clear artificial lens called an intraocular lens. Antibiotic given inside the eye during surgery has greatly reduced **endophthalmitis**, a sight-threatening infection inside the eye (Chen et al., 2025). Cataract surgery is one of the procedures for which the Canadian Institute for Health Information (CIHI) reports wait times against a benchmark of surgery within 16 weeks (CIHI, 2026). Most people go home the same day (CIUSSS du Nord-de-l'Île-de-Montréal [CIUSSS NIM], 2020); perioperative care is in Chapter 7.

After surgery, teaching follows the surgeon's written instructions. One Canadian hospital network's instructions give a typical plan (CIUSSS NIM, 2020):

- **Shield:** worn at all times on the day of surgery except while drops are given, then at night for the next 7 nights. Nothing is placed between the shield and the eye.
- **Drops:** the prescribed drops are used exactly as ordered, with clean hands, and with 5 minutes between different drops (Figure 36.4).
- **For 2 weeks:** no lifting over about 4.5 kg (10 lb), no bending the head below the shoulders, no rubbing, pressing or squeezing the eye shut, no soap, shampoo, dust or soil in the eye, no gardening, no swimming and no eye makeup.
- **Driving:** not on the day of surgery or for the next few days, and only when the surgeon says it is safe.
- **Warning signs:** unusual or persistent pain, blurred vision, redness or thick greenish discharge need prompt contact with the surgical team or an emergency department.

Figure 36.4 Instilling eye drops: the patient looks up while the nurse gently pulls down the lower lid to form a pocket and holds the dropper tip clear of the eye and eyelashes. (credit: "Instilling eye medication" by British Columbia Institute of Technology (BCIT)/BCcampus, CC BY 4.0)

The nurse treats rising pain or worsening vision after eye surgery as a possible complication, not as expected discomfort, and reports it at once.

Glaucoma

Glaucoma is a group of eye diseases in which the optic nerve is damaged and the visual field shrinks; the loss is progressive, chronic and irreversible (Basilious & Buys, 2015). The two main types are open-angle glaucoma and angle-closure glaucoma.

Open-angle glaucoma develops slowly. It is typically painless and without symptoms until it is advanced, and it may be undiagnosed in about half of the people who have it (Basilious & Buys, 2015). Risk factors include older age, African descent, glaucoma in a parent or sibling, corticosteroid use in or around the eye, myopia (near-sightedness), migraine and raised IOP (Basilious & Buys, 2015). Because the disease is silent, finding it depends on eye examinations. A Canadian Medical Association Journal (CMAJ) article reports that the Canadian Ophthalmological Society (COS) recommends glaucoma screening for people at high risk, and a complete eye examination every 5 years from age 41 to 55, every 3 years from 56 to 65 and every year after 65. People who use corticosteroids (eye drops, injections around the eye or systemic) for more than 2 weeks need a baseline eye examination and regular monitoring (Basilious & Buys, 2015). Public coverage for comprehensive eye examinations varies by province and territory (Fighting Blindness Canada, 2021), so the nurse helps people find out what is covered.

Treatment lowers IOP to slow nerve damage, usually with eye drops (Basilious & Buys, 2015); laser and surgical treatments are also used (Gedde et al., 2026). The main drug classes are named here; how they work is explained in the Going Deeper box in section 36.3.

- **Prostaglandin analogues** such as latanoprost: may permanently darken the iris and change the eyelashes (Bausch & Lomb, 2022).
- **Beta-blockers** such as timolol: see the next paragraph.
- **Carbonic anhydrase inhibitors** such as dorzolamide drops (which may sting and leave a bitter taste) and acetazolamide, given systemically in emergencies (RVEEH, 2017; Sandoz Canada, 2026).
- **Alpha agonists** such as brimonidine: may cause dry mouth and drowsiness, so the person waits until drowsiness or blurring clears before driving (Apotex, 2024).
- **Pilocarpine,** a drop that constricts the pupil, used in acute angle closure (RVEEH, 2017).

Eye drops reach the bloodstream. The Canadian monograph for timolol eye drops warns that it may be absorbed systemically; that cardiac reactions, rarely fatal, and deaths from bronchospasm in people with asthma have been reported; and that it may mask the signs of low blood glucose and of an overactive thyroid. Its contraindications include asthma or a history of asthma, chronic obstructive pulmonary disease (COPD), sinus bradycardia, some forms of heart block, overt heart failure and cardiogenic shock (Sandoz Canada, 2023). Before giving timolol drops, the nurse checks the person's history, heart rate and breathing and reports concerns to the prescriber. Pressing on the inner corner of the eye, or simply closing the eyelid gently, for 2 minutes after each drop reduces systemic absorption (Sandoz Canada, 2023).

Glaucoma drops prevent vision loss but do not restore what is lost, and people feel no different when they skip them. The nurse asks how drops fit the person's day, checks technique, and teaches that stopping drops lets damage continue without warning.

Acute angle-closure glaucoma is an emergency in which the drainage angle closes and IOP rises quickly, usually above 35 mm Hg (RVEEH, 2017). A US guideline from the American Academy of Ophthalmology lists its symptoms as eye pain, headache, nausea or vomiting, and blurred vision with halos around lights (Gedde et al., 2026). The eye may be red, the cornea cloudy and the pupil mid-

dilated and poorly reactive (RVEEH, 2017). Risk factors include older age, female sex, a family history of angle closure, long-sightedness and Inuit or Asian descent (Gedde et al., 2026). In eyes at risk, medicines that dilate the pupil, such as some decongestants, motion sickness medicines and anticholinergic drugs, can trigger an attack (RVEEH, 2017). Treatment lowers IOP promptly, usually with medicines, and is followed by a procedure such as laser peripheral iridotomy; the other eye usually needs prompt treatment too (Gedde et al., 2026). The nurse notifies the prescriber at once, gives ordered medicines and antiemetics, and checks that kidney function has been reviewed before acetazolamide (RVEEH, 2017; Chapter 27; Figure 36.5).

Figure 36.5 Acute angle-closure glaucoma of the right eye, showing conjunctival redness, corneal haziness and a mid-dilated, non-reactive pupil (cropped to the affected eye). (credit: modification of "Acute angle closure glaucoma" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

CLINICAL JUDGMENT

Sudden Eye Pain and Halos

Names and details are fictional; this is a composite story.

Mr. Anton Petrakis, 71, is on a medical unit on day 2 of treatment for a urinary tract infection. Early in the evening he calls the nurse, holding his left hand over his left eye.

- **Recognize cues:** severe aching pain in the left eye and brow, a headache, blurred vision with "rainbow rings" around the ceiling lights, and two episodes of vomiting. The left eye is red and the pupil is larger than the right and reacts sluggishly. That afternoon he received an anticholinergic medicine for bladder spasm.
- **Analyze cues:** sudden pain, halos, vomiting and a mid-dilated pupil fit acute angle-closure glaucoma. A pupil-dilating medicine may have triggered it (RVEEH, 2017).
- **Prioritize hypotheses:** acute angle closure is the most urgent problem because vision can be lost; stroke and raised intracranial pressure are also considered because of the headache and unequal pupils (Chapters 30 and 31). His speech, limb strength and level of consciousness are unchanged.
- **Generate solutions:** urgent assessment, ordered pressure-lowering medicines, an antiemetic and analgesia; hold further doses of the anticholinergic until reviewed.
- **Take action:** the nurse completes a neurologic check, which is otherwise unchanged, and calls the most responsible provider using SBAR (Chapter 6): "I am concerned about acute angle-closure glaucoma." Ophthalmology is called urgently. The RN gives the ordered drops and medicines and checks his kidney function results.
- **Evaluate outcomes:** pain, nausea and vision are reassessed; the ophthalmologist measures his IOP and plans laser treatment, likely for both eyes (Gedde et al., 2026). The nurse documents the timeline, flags the anticholinergic for review and explains to Mr. Petrakis why his other eye needs checking too.

PATIENT EDUCATION

Using Eye Drops

- Wash your hands. Shake the bottle if told to (CIUSSS NIM, 2020).
- Tilt your head back, look up and pull down the lower eyelid to make a pocket.
- Let one drop fall into the pocket without touching your eye, eyelid or lashes with the tip of the bottle (Nova Scotia Health, 2026).
- Close your eye gently. Press a finger on the inner corner of the eye, beside the nose, for 2 minutes. This keeps more of the medicine in the eye and less in the bloodstream (Sandoz Canada, 2026). Blot extra liquid; do not rub.
- If you use more than one kind of drop, wait between them. Your pharmacist will tell you how long; monographs for different drops say at least 5 or at least 10 minutes (Bausch & Lomb, 2022; Sandoz Canada, 2023).

- Remove contact lenses before drops and wait at least 15 minutes before putting them back in (Bausch & Lomb, 2022).
- Store each bottle as the label says. Some bottles are kept in the refrigerator before opening (Bausch & Lomb, 2022).
- Do not stop drops for your other eye unless your eye doctor tells you to (Nova Scotia Health, 2026).
- Tell your health care team if drops make you dizzy, short of breath or very tired.

Macular Degeneration and Diabetic Retinopathy

Age-related macular degeneration (AMD) damages the macula and causes loss of central vision. Early and intermediate AMD are marked by drusen, yellow deposits beneath the retina, and may cause few symptoms or trouble seeing in dim light. Late AMD takes two forms that often occur together. In dry AMD, retinal cells waste away slowly. In wet AMD, abnormal blood vessels grow under the retina and leak fluid or blood. Straight lines may look wavy, and a blurred or missing patch may appear in the centre of vision. Age is the strongest risk factor; smoking is the main one a person can change, and a family history of AMD roughly triples the risk (Eiselen et al., 2026; Figure 36.6).

Figure 36.6 Retinal fundus photograph showing clustered yellow drusen in the macula in age-related macular degeneration. (credit: "MacularDegenerationFundus" by Tmhlee/Wikimedia Commons, CC BY-SA 3.0)

People with AMD may be asked to check each eye with an Amsler grid regularly. Any new distortion or central blur needs review by an eye specialist within 24 hours. Wet AMD is treated with **anti-VEGF therapy**, medicines that block vascular endothelial growth factor, given by injection into the eye. Examples include ranibizumab, aflibercept and faricimab. Treatment continues over the long term, and many people stop or miss treatment; studies have found that 17.5% to 30% of patients do not keep to it (Eiselen et al., 2026). The nurse supports transportation and appointments and offers low-vision services such as CNIB.

Diabetic retinopathy is damage to the retina caused by diabetes. Good glucose control lowers the risk that it starts or worsens. Diabetes Canada recommends screening by an optometrist or ophthalmologist, either at an in-person examination or by reading retinal photographs taken after the pupils are dilated. Adults with type 1 diabetes are screened every year, starting 5 years after diabetes begins. Adults with type 2 diabetes are screened at diagnosis, then every 1 to 2 years if no or minimal retinopathy is found. Results are shared with the whole diabetes care team. Treatment includes anti-VEGF injections and laser (Altomare et al., 2018). Diabetes care and its screening programs are taught in Chapter 22.

Higher rates of diabetic retinopathy have been reported in Indigenous populations in Canada (Altomare et al., 2018). Diabetes Canada's chapter on type 2 diabetes and Indigenous peoples names colonization, including residential schools and forced relocation, along with poverty, food insecurity, racism and inequities in health services, as drivers of the higher burden of type 2 diabetes (Crowshoe et al., 2018). Many First Nations, Inuit and Métis people live in rural, remote or northern communities where specialist eye care may be hard to reach or absent. On Vancouver Island, a First Nations teleophthalmology service brought retinal photography to communities with First Nations technicians and an eye care nurse. During the 1-year project, clinics were held in 43 of 51 communities and 524 people were screened. Data were stored at a First Nations-operated facility, following the First Nations principles of ownership, control, access and possession (OCAP®) (Kim & Driver, 2015). Services designed with communities, close to home, are one way to close these gaps. The main causes of vision loss in this section are compared below (Table 36.1).

Table 36.1 Common causes of vision loss in adults compared (Altomare et al., 2018; Basilious & Buys, 2015; Chen et al., 2025; Eiselen et al., 2026; Gedde et al., 2026)

Condition	What changes	How vision is affected	Key nursing points

Condition	What changes	How vision is affected	Key nursing points
Cataract	The lens becomes cloudy, mostly with age	Gradual blurring or clouding; reversible with surgery	Teach shield, drops and activity limits after surgery; report rising pain or worsening vision
Open-angle glaucoma	Slow optic nerve damage, often with raised IOP	No symptoms until late; visual field loss that cannot be restored	Encourage eye examinations for people at risk; support lifelong drop use; watch for systemic effects of drops
Acute angle-closure glaucoma	The drainage angle closes and IOP rises quickly	Sudden blurring with halos, eye pain, headache, nausea and vomiting	Treat as an emergency; notify at once; give ordered medicines and antiemetics
Age-related macular degeneration	Deposits and cell loss in the macula; in the wet form, leaking new vessels	Central blur or distortion; side vision usually kept	Teach Amsler grid checks; urgent review of new distortion; support injection visits and low-vision services
Diabetic retinopathy	Diabetes damages the retina	May have no symptoms until advanced	Promote screening on schedule; support glucose control; share results with the team

36.3 Eye Emergencies, Trauma and Eye Surgery

Eye Emergencies

Sudden vision loss, a chemical in the eye, a penetrating injury and new flashes with a shadow over vision are emergencies. Every nurse who notices one acts at once and escalates (College of Nurses of Ontario [CNO], 2025): the RPN consults the RN as the patient's needs change, and the most responsible provider is notified using SBAR (Chapter 6). Common emergencies and first actions are compared below (Table 36.2).

- **Chemical injury:** a chemical splash is irrigated at once, before anything else, and irrigation continues while help is called. Workplace safety guidance calls for flushing to start within 10 seconds and continue for at least 15 minutes with the eyelids held open (WorkSafeNB, 2024). In hospital, normal saline or lactated Ringer's solution is used, or water if nothing else is at hand, through an irrigation lens or intravenous tubing. At least 2 L are given; the pH of the eye surface is rechecked about 5 minutes after starting, and irrigation continues until it is 7.0 to 7.5. Alkali burns are generally more harmful than acid burns because alkali penetrates the surface of the eye faster. Ophthalmology sees the person as soon as the eye is neutralized (Gelston & Deitz, 2020). The nurse records the time irrigation began, the fluid and volume used, and each pH result.

Figure 36.7 Prominent hyphema filling the anterior chamber in front of the iris, with surrounding ciliary injection. (credit: “12886 2014 Article 436 Fig1 HTML” by Yoko Okunuki et al./BMC Ophthalmology, CC BY 4.0)

- **Penetrating injury and foreign objects:** a rigid metal shield is placed over the eye without pressing on it. An object sticking out of the eye is never removed. The person avoids coughing and straining, receives an antiemetic so they do not vomit, and has tetanus status checked. Urgent ophthalmology is needed, because surgery within 24 hours lowers the risk of infection inside the eye (Gelston & Deitz, 2020).
- **Blunt trauma and hyphema:** a blow to the eye can cause bleeding inside the front of the eye, seen as blood in front of the iris; this is called **hyphema**. The sources list hyphema as a possible sign of a serious injury to the eyeball and as a reason for referral (Gelston & Deitz, 2020; Wipperman & Dorsch, 2013; Figure 36.7).

- **Corneal abrasion:** a **corneal abrasion** is a scratch in the outer layer of the cornea from injury, a foreign body or contact lens wear. It causes pain, tearing, light sensitivity and a feeling that something is in the eye. Patching is not recommended, and numbing drops are not given for home use because they delay healing and mask worsening. Contact lens wearers stop wearing lenses until healed. Most abrasions heal in 24 to 48 hours; worsening pain, loss of vision or no improvement within 24 hours needs referral (Wipperman & Dorsch, 2013).
- **Retinal detachment:** in **retinal detachment**, the retina separates from the back of the eye. Warning signs are sudden flashes of light and new floaters in one eye, with a shadow or patch of lost vision that may spread. People with these symptoms need assessment within 24 hours (Gelston & Deitz, 2020).
- **Sudden painless vision loss:** sudden loss of vision without pain may mean a blocked artery to the retina. It needs immediate ophthalmology referral and assessment for stroke (Chapter 31). In people over 50, especially with jaw or scalp tenderness, fever, fatigue or weight loss, giant cell arteritis is considered (Gelston & Deitz, 2020; Chapter 34).

Table 36.2 Eye emergencies and first nursing actions (based on Gelston & Deitz, 2020; Gedde et al., 2026; Wipperman & Dorsch, 2013; WorkSafeNB, 2024)

Emergency	Signs	First actions	Do not
Chemical injury	Splash of a chemical; pain, redness, tearing, blurred vision	Irrigate at once and keep going while help is called; check pH as ordered; urgent ophthalmology	Delay irrigation to identify the chemical or find a provider
Penetrating injury or embedded object	Injury by a sharp or high-speed object; object may be visible; vision loss	Place a rigid shield without pressure; give ordered antiemetic; urgent ophthalmology	Press on the eye, patch it tightly or remove the object
Hyphema after blunt trauma	Blood in the front of the eye after a blow; pain; blurred vision	Protect the eye; report promptly for referral	Assume a black eye is minor without checking vision
Corneal abrasion	Pain, tearing, light sensitivity, foreign body feeling	Check vision; report; teach ordered treatment and when to return	Patch the eye or send the person home with numbing drops
Retinal detachment	Sudden flashes, new floaters, spreading shadow over vision	Report the same day for assessment within 24 hours	Reassure the person that floaters are always harmless
Acute angle-closure glaucoma	Eye pain, headache, halos, nausea and vomiting, red eye	Notify at once; give ordered pressure-lowering medicines and antiemetic	Give pupil-dilating medicines or wait to see if it settles
Sudden painless vision loss	Loss of all or part of vision in one eye	Escalate immediately; consider stroke and giant cell arteritis	Wait until morning or treat it as a non-urgent referral

Care After Eye Surgery

Cataract surgery is usually day surgery (section 36.2), and after other eye operations, too, much of the recovery happens at home. Nursing care protects the eye, controls pain and nausea, prevents falls and prepares the person to manage alone.

- **Protecting the eye:** no pressure on the eye, no rubbing, and a shield at night for about the first week as the surgeon directs; a cloth eye pad or patch is not used (Nova Scotia Health, 2026).
- **Pain and nausea:** pain that is not relieved by acetaminophen or ibuprofen, worsening vision, marked swelling, or nausea and vomiting that do not settle are reported to the surgeon right away (Nova Scotia Health, 2026).
- **Falls:** with one eye shielded or blurred, the person is at higher risk of falls. The nurse keeps the call bell and glasses within reach, asks the person to call before getting up the first time, and applies the falls prevention plan in Chapter 8.

After surgery for retinal detachment, the surgeon may place a bubble of gas inside the eye to hold the retina in place. The person's position matters. They lie face down or on one side exactly as the surgeon directs and must not lie flat on their back, which can cause serious complications (Nova Scotia Health, 2026). Incorrect positioning can make the surgery fail (Alcon, 2022). Vision in the eye is blurred while the bubble is present, and as it shrinks, its edge may look like a dark line at the top of the person's vision (Nova Scotia Health, 2026).

Until the bubble is gone, the person must not travel by air or drive through high-altitude areas, because the gas expands at altitude and can cause eye pain and pressure (Nova Scotia Health, 2026). US labelling for one gas product adds that a rise in eye pressure from a change in elevation can result in blindness, and that the person must not receive nitrous oxide, sometimes used in anesthesia, until the gas has dissolved, because it can also raise the pressure in the eye and cause blindness (Alcon, 2022). The person wears a gas bubble wristband and carries a card until the gas is gone, and tells any surgeon or anesthetist about the bubble before another procedure (Alcon, 2022; Nova Scotia Health, 2026). The nurse checks for this wristband during admission and before any anesthetic, and includes it in every handover (Chapter 7). How long the gas lasts depends on the gas used; one product's labelling gives about 6 to 8 weeks (Alcon, 2022), so the person follows their surgeon's time frame.

Before discharge, the nurse confirms who will drive the person home and that they will not drive until the surgeon allows (Nova Scotia Health, 2026). Activity limits after retinal surgery last longer than after cataract surgery: one Canadian program advises avoiding dirt, dust and chemicals, lifting more than about 4.5 kg, heavy exercise, sports and swimming for the first 4 weeks (Nova Scotia Health, 2026). People who use glaucoma drops keep using drops in the other eye unless told otherwise. The nurse reviews eye drop technique, activity limits and warning signs, and checks that the person can manage positioning, meals and medications at home or has help arranged.

GOING DEEPER

Intraocular Pressure and How Glaucoma Medicines Work

Required for RN students; optional for PN students.

IOP reflects a balance between aqueous humour made by the ciliary processes and aqueous humour leaving the eye through the drainage angle and the uveoscleral route. Each class of glaucoma medicine acts on one side of that balance or both.

- **Less fluid made:** beta-blockers such as timolol and carbonic anhydrase inhibitors such as dorzolamide reduce aqueous humour secretion. Combining them lowers IOP more than either alone (Sandoz Canada, 2026).
- **More fluid out:** prostaglandin analogues such as latanoprost increase outflow, mainly by the uveoscleral route (Bausch & Lomb, 2022).
- **Both:** brimonidine, an alpha agonist, reduces production and increases uveoscleral outflow (Apotex, 2024).
- **In acute angle closure,** pressure must fall quickly, so several medicines are given together: a carbonic anhydrase inhibitor such as acetazolamide given systemically, pilocarpine and other pressure-lowering drops. Kidney function is checked before acetazolamide (RVEEH, 2017). Laser peripheral iridotomy then gives fluid a new path (Gedde et al., 2026).

Systemic effects follow from drug class: a beta-blocker drop can slow the heart or tighten the airways (Sandoz Canada, 2023); dorzolamide is a sulfonamide, and serious skin reactions have been reported (Sandoz Canada, 2026); brimonidine adds to the effect of sedatives and must not be used with monoamine oxidase (MAO) inhibitors (Apotex, 2024). **Punctal occlusion,** pressing on the inner corner of the eye after a drop, reduces how much drug reaches the bloodstream (Sandoz Canada, 2023).

36.4 Hearing and Ear Assessment

Hearing loss is one of the most common conditions the nurse meets in adult care, and one of the easiest to miss. A person who cannot hear the questions may give answers that do not fit, agree to things they did not understand or seem withdrawn. This section reviews how the ear works, the main types and causes of hearing loss in adults, including loss caused by medicines, and how the nurse assesses hearing. Testing of the cranial nerves is covered in Chapter 30.

How the Ear Works

The ear has three parts. The **outer ear** is the visible ear and the ear canal, which ends at the **tympanic membrane** (eardrum). Glands in the outer third of the canal make **cerumen** (earwax), which protects and lubricates the canal and slowly moves outward on its own as the jaw moves (American Academy of Otolaryngology–Head and Neck Surgery Foundation [AAO-HNSF], 2018a). Sound travels down the canal and makes the eardrum vibrate (Figure 36.8).

The **middle ear** is a small air-filled space behind the eardrum. Its three tiny bones, the malleus, incus and stapes, pass the vibrations along and make them stronger. The **inner ear** holds the **cochlea**, a fluid-filled, snail-shaped organ lined with hair cells. Movement of the fluid bends the hair cells, which turn the vibration into an electrical signal. Hair cells at one end of the cochlea respond to high-

pitched sounds and those farther along respond to lower ones. The auditory nerve carries the signal to the brain, which hears it as sound (National Institute on Deafness and Other Communication Disorders [NIDCD], 2022).

The inner ear also senses balance. Its vestibular organs, including the semicircular canals, detect movement of the head and its position relative to gravity (Bhattacharyya et al., 2017; NIDCD, 2022). This is why some inner ear disorders cause both hearing loss and dizziness (section 36.6).



Figure 36.8 Anatomy of the human ear showing the external ear, the air-filled middle ear containing the auditory ossicles (malleus, incus, stapes) and tympanic membrane, and the fluid-filled inner ear (cochlea and vestibular apparatus). (credit: "Figure 14.5, Ear Structures" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Hearing Loss in Adults

Hearing loss is grouped by where the problem lies (Table 36.3). **Conductive hearing loss** occurs when sound cannot get through the outer or middle ear to a normal inner ear, for example because of impacted wax, fluid or a damaged eardrum. It may be temporary or permanent and can often be treated. **Sensorineural hearing loss** comes from damage to the cochlea or the hearing nerve and is usually permanent. **Mixed hearing loss** combines the two (University Hospitals Sussex NHS Foundation Trust, 2026; World Health Organization [WHO], 2026).

The most common pattern in older adults is **presbycusis**, age-related sensorineural hearing loss. It starts at the highest pitches and later spreads to lower ones. Consonants become hard to hear, so speech sounds mumbled, and conversation in a noisy or echoing room becomes difficult (Feder et al., 2015). Loud noise is another preventable cause (WHO, 2026). A Statistics Canada survey analysis found more hearing loss in men than in women and linked the gap partly to noise at work and in leisure (Feder et al., 2015).

Ototoxicity is damage to the inner ear, affecting hearing, balance or both, caused by a medicine or chemical. Aminoglycoside antibiotics such as gentamicin are a key example. The Canadian monograph warns that they can damage the eighth cranial nerve, mostly with high blood levels and poor kidney function. Early signs are **tinnitus** (ringing or roaring in the ears) and loss of high-pitched hearing, which may show only on a hearing test; balance damage causes nausea, vomiting, dizziness, **vertigo** (a false sense of movement) and an unsteady gait. Hearing loss can be permanent and may appear after treatment ends. Older age, dehydration, kidney disease, long courses and loop diuretics such as furosemide add to the risk. The monograph calls for peak and trough drug levels, kidney function tests and an audiology referral if tinnitus or hearing loss is reported (Baxter Corporation, 2019). The cancer drug cisplatin can cause cumulative, high-pitched hearing loss and tinnitus, and its monograph calls for a hearing test before treatment and before each dose (Accord Healthcare, 2024). Acetylsalicylic acid (ASA) in excess can cause tinnitus and vertigo (Pharmascience, 2018). Kidney function and drug clearance are covered in Chapter 27.

Hearing loss is common in Canada. In the Canadian Health Measures Survey (2012 to 2015), about 38% of adults aged 20 to 79 had hearing loss measured by audiometry, rising from 9% at ages 20 to 39 to 94% at ages 70 to 79 (Statistics Canada, 2021). Among adults aged 40 to 79, about 54% had high-frequency hearing loss that was at least mild, yet only about 6% had a self-reported hearing impairment, and about 77% of those with measured loss did not perceive it (Ramage-Morin et al., 2019). Hearing loss is linked to social isolation, depression, falls, cognitive decline and dementia (Ramage-Morin et al., 2019). Hearing impairment also raises the risk of delirium in hospital (Chapter 8, section 8.2).

Assessing Hearing

Because most hearing loss goes unnoticed, the nurse asks every adult directly rather than waiting to be told. Useful questions are: Do you have trouble hearing? Do you use hearing aids or a cochlear implant, and are they with you? Which ear is better? Do you lip-read or use sign language? How do you prefer to communicate? The history also covers whether the change was sudden or gradual, one ear or both, tinnitus, dizziness, ear pain, discharge or fullness, noise exposure and current medicines. A sudden loss in one ear is urgent (section 36.6).



Figure 36.9 Otoscopic view of a right tympanic membrane showing the translucent pearly grey eardrum and landmarks (the small black dot is India ink placed to demonstrate normal outward migration of the canal epithelium). (credit: "Ink Dot on the surface of the tympanic membrane 1 week later" by Michael Hawke, MD/Wikimedia Commons, CC BY 4.0)

The **whispered voice test** is a quick bedside screen. In the method described in a systematic review, the examiner stands about an arm's length behind the seated person so they cannot lip-read, masks the other ear by closing it gently with a finger and rubbing in a small circle, breathes out quietly and then whispers a mix of numbers and letters for the person to repeat. Each ear is tested separately. In adults the test was simple and accurate, but results depend on doing it the same way each time (Pirozzo et al., 2003). A failed screen leads to referral, not a diagnosis.

With an otoscope, the nurse who has the competence looks at the canal and eardrum for wax, redness, swelling or discharge. **Cerumen impaction** is a build-up of wax that blocks the canal or causes symptoms such as fullness, muffled hearing, tinnitus, itching or ear pain (AAO-HNSF, 2018a). In the Canadian survey, wax or pus blocked the ear canal in 13% of adults, rising to 21% at ages 70 to 79 (Feder et al., 2015). Cotton swabs push wax deeper and can injure the eardrum, and hearing aid users are advised to have their ears checked every 6 to 12 months (AAO-HNSF, 2018a). Removing wax is covered in section 36.6 (Figure 36.9).

People with suspected hearing loss are referred to an audiologist, who measures hearing with a pure-tone test and records it on an **audiogram**.

Table 36.3 Types of hearing loss compared (Feder et al., 2015; Milchard, n.d.; University Hospitals Sussex NHS Foundation Trust, 2026; WHO, 2026)

Type	Where the problem is	Common causes	What helps
Conductive	Outer ear or middle ear; sound cannot reach an inner ear that works normally	Impacted earwax, a swollen ear canal from infection, fluid or infection in the middle ear, a hole in the eardrum, a middle ear bone that cannot move	Treating the cause, such as wax removal, treating infection or surgery; hearing aids
Sensorineural	Inner ear (cochlea) or the hearing nerve	Aging, loud noise, ototoxic medicines, sudden sensorineural hearing loss, Ménière disease	Usually permanent; hearing aids, cochlear implants for severe loss, communication strategies; urgent assessment if the loss is sudden
Mixed	Both the outer or middle ear and the inner ear	For example, age-related loss plus impacted wax	Treating the conductive part and supporting hearing for the rest

GOING DEEPER

Reading an Audiogram

Required for RN students; optional for PN students.

An audiogram charts the softest sounds a person can hear in each ear. Pitch, in hertz (Hz), runs across the top from low (left) to high (right); testing usually covers 250 to 8,000 Hz. Loudness, in decibels hearing level (dB HL), runs down the side, softest at the top. The lower the marks fall, the greater the loss (Milchard, n.d.; University Hospitals Sussex NHS Foundation Trust, 2026).

- **Air conduction:** sounds through headphones, marked O for the right ear and X for the left; they show how the whole ear hears.
- **Bone conduction:** sounds sent by a small vibrator behind the ear straight to the inner ear, bypassing the outer and middle ear.

- **Air–bone gap:** when bone conduction is clearly better than air conduction in the same ear, the problem lies in the outer or middle ear (conductive loss). When bone conduction thresholds are also above 20 dB HL and there is no real gap, the loss is sensorineural; when bone conduction is above 20 dB HL and a gap remains, it is mixed (Milchard, n.d.).
- **Degree:** one hospital audiology service describes thresholds of up to 20 dB as within normal limits, 20 to 40 dB as mild, 40 to 70 dB as moderate, 70 to 95 dB as severe and above 95 dB as profound (University Hospitals Sussex NHS Foundation Trust, 2026). Cut-offs differ slightly between organizations.

Age-related loss usually slopes downward toward the right side of the chart, because high pitches go first (Feder et al., 2015).

36.5 Communication Access, Hearing Aids and Cochlear Implants

Communication access means a person can understand and be understood in the way that works for them. Without it, consent is not truly informed, teaching does not land and a person who cannot hear may be wrongly labelled confused. Consent and capacity are covered in Chapter 1, and disability and accessibility in Chapter 2. This section applies those principles to people who are hard of hearing, deafened or Deaf.

Communicating With People Who Have Hearing Loss

The nurse starts by asking how the person communicates best and records it in the health record so the whole team uses it (Arora et al., 2026; Southlake Regional Health Centre, n.d.). Simple habits then make a large difference (Banks, 2020; Southlake Regional Health Centre, n.d.):

- Get the person's attention before speaking, face them and keep the face in full view.
- Talk in a well-lit place so the face is easy to see.
- Turn off the television, close the door or move to a quieter spot.
- Speak a little louder and a little slower, as clearly as possible.
- Check understanding by asking the person to say the plan back; if they have not understood, rephrase, write it down or use a speech-to-text app.
- Answer call bells in person, and explain any emergency face to face.

Lip-reading helps but has limits. Only about 30% to 40% of spoken English can be seen on the lips (Steinberg et al., 2006). Writing helps many hard-of-hearing people, but it is not a substitute for an interpreter for a Deaf person whose first language is a signed language, since American Sign Language has no written form and English may be a second language (Steinberg et al., 2006).

A **personal amplifier**, a small handheld device that makes nearby speech louder through headphones or earphones, can make bedside conversation easier when hearing aids are not available. In a Toronto hospital, staff reported that amplifiers made conversations easier and clearer, reduced the need to raise their voices and helped older patients take part in decisions, including discussions of capacity. The same study noted that at least two in three older adults in hospital have hearing loss, yet patients often do not mention it, and staff often had trouble finding the devices on the unit (Arora et al., 2026).

Masks add another barrier. They muffle sound, especially high pitches, and hide the lips and facial expressions; for Deaf signers they also hide facial grammar. Masks with a clear window let a person see the lips but muffle sound the most, and a face shield over a mask adds more distortion (Banks, 2020). The nurse follows infection prevention and control requirements (Chapter 4) and adds the other supports above. Mask loops can also pull off hearing aids or cochlear implant processors, so devices are checked after a mask is removed (Banks, 2020).

Deaf People and Sign Language Interpreters

Words matter to this community. **Deaf** with a capital D describes people who share Deaf culture and use a signed language as their main language; it is a cultural identity, not a hearing level. Lowercase "deaf" describes severe hearing loss, "hard of hearing" covers mild to severe loss in people who often use speech, and "deafened" describes people who lost their hearing, usually as adults. "Hearing impaired" is best avoided, and the nurse uses the terms people choose for themselves (Sexton, 2022). Many Deaf people do not see themselves as disabled but as members of a language and cultural group (Sexton, 2022).

American Sign Language (ASL) and **langue des signes québécoise (LSQ)** are full languages with their own grammar. The federal *Accessible Canada Act* recognizes ASL, LSQ (called Quebec Sign Language in the Act) and Indigenous sign languages as the primary languages of communication for deaf persons in Canada (*Accessible Canada Act*, 2019). That Act applies to federally regulated bodies; hospitals are governed mainly by provincial and territorial laws.

A Deaf patient who signs needs a qualified sign language interpreter for assessments, consent discussions, teaching and discharge planning. In Ontario, hospitals book interpreters through their own process; one hospital's policy uses a central scheduling service with interpreters available around the clock for emergencies, and groups teaching and assessments into each booking (Southlake Regional Health Centre, n.d.). **Video remote interpreting (VRI)** brings an interpreter into the room on a screen. It depends on a connection good enough to show fingerspelling clearly (Steinberg et al., 2006).

Family members should not interpret. In a study of Deaf adults, family members were often inadequate go-betweens, patients felt left out of their own care and privacy was lost (Steinberg et al., 2006). A qualified interpreter is impartial and does not edit what is said (Southlake Regional Health Centre, n.d.). If an interpreter is not yet available in an urgent situation, the nurse uses the best interim method, such as a staff member who signs or writing, and keeps trying to reach an interpreter (Southlake Regional Health Centre, n.d.). Interpreters are part of care, not visitors, and the nurse keeps a signer's hands free whenever possible. Each interpreter session is documented with the interpreter's name, date and time (Southlake Regional Health Centre, n.d.).

Figure 36.10 An external behind-the-ear cochlear implant sound processor and its round magnetic transmitting headpiece, which sits over the internal receiver under the scalp. (credit: “Advanced Bionics cochlear implant processor BTE (first-generation behind-the-ear processor)” by MikeCore9918/Wikimedia Commons, CC BY-SA 4.0)

These duties have a legal basis. In 1997 the Supreme Court of Canada ruled that when sign language interpretation is needed for effective communication in health care, not providing it breaches the equality rights of Deaf people under section 15 of the *Canadian Charter of Rights and Freedoms* (*Eldridge v. British Columbia (Attorney General)*, 1997). In Ontario, the customer service requirements under the *Accessibility for Ontarians with Disabilities Act, 2005* (AODA) and its Integrated Accessibility Standards expect organizations to communicate in a way that takes a person's disability into account, and to provide accessible formats and communication supports when asked, promptly and at no extra cost (Government of Ontario, 2026).

Hearing Aids and Cochlear Implants in Hospital

A **hearing aid** is a small electronic device worn in or behind the ear that makes sound louder. A **cochlear implant** is an electronic device for people who are severely hard of hearing or profoundly deaf. An external sound processor worn behind the ear works with a part placed under the skin by surgery; together they work around the damaged inner ear and send signals straight to the hearing nerve. It does not restore normal hearing (NIDCD, 2024; Figure 36.11; Figure 36.10).

At admission, the nurse asks about devices and whether they came to hospital. Patients often leave hearing aids at home, partly because they fear losing them (Arora et al., 2026), so the nurse asks family to bring them when needed. The nurse records the devices, which ears they are for and how the person uses them. Hearing aids and processors are worn during waking hours and always for assessments, teaching and consent discussions. The nurse checks that batteries are charged or replaced, follows the person's routine for cleaning, and stores devices that are out in a labelled container kept in the same place each time; one Ontario

Figure 36.11 A behind-the-ear hearing aid with tubing leading to an earmold in the ear canal. (credit: “Behind-the-Ear Hearing Aid grayscale photo” by Steve Johnson/Wikimedia Commons, CC BY 2.0)

hospital's hearing toolkit includes a cup for devices and storage instructions (Southlake Regional Health Centre, n.d.). Devices are named in handover and on transfers.

Cochlear implants contain a magnet, which matters for magnetic resonance imaging (MRI). Many implants are labelled "MR Conditional", meaning a scan is possible only under the manufacturer's specific conditions. Some newer magnets can rotate in place; others need a splint or bandage kit made for that implant, or surgical removal of the magnet before the scan. Risks include movement of the magnet with pain or injury, and heating (U.S. Food and Drug Administration [FDA], 2021). The nurse makes sure the MRI team knows about the implant, asks for the person's implant card with the brand and model, and leaves the decisions to the MRI team following the manufacturer's instructions (FDA, 2021).

CANADIAN CONTEXT

Deaf, deaf and Hard of Hearing People in Canada

Canada recognizes signed languages in law. The *Accessible Canada Act* (2019) names American Sign Language, Quebec Sign Language and Indigenous sign languages as the primary languages of communication for deaf persons in Canada. In *Eldridge* (1997), the Supreme Court of Canada ruled that not providing sign language interpretation needed for effective communication in health care breached the Charter's equality rights.

Hearing loss is also widespread among people who do not identify as Deaf. In 2012 to 2015, about 38% of adults aged 20 to 79 had measured hearing loss and about 37% reported tinnitus in the past year (Statistics Canada, 2021). Only about 12% of adults with hearing loss used hearing aids. Cost is a commonly cited barrier, and hearing aid subsidies and eligibility vary by province (Feder et al., 2015). People with lower household income and less education had more hearing loss (Feder et al., 2015).

Access to interpreters is uneven. In rural, remote and northern communities, video remote interpreting may be the only option, and it depends on a reliable connection (Steinberg et al., 2006). The nurse asks which language a person uses, including an Indigenous sign language, rather than assuming ASL, and plans ahead for appointments and discharge teaching.

PRACTICE STORY

The Missing Hearing Aid

Names and details are fictional; this is a composite story.

Nurse: Fiona MacInnis, RN. Years in practice: 6. Setting: medical unit, Ontario.

Night report on Mr. Gilles Moreau, 83, admitted with a urinary tract infection, was short: "Pleasantly confused. Doesn't follow instructions. Tried to get up alone twice." The plan suggested a bed alarm and a geriatric psychiatry consult.

When I said good morning, he smiled and said, "Fine, fine." I asked whether he had pain, and he said, "Fine." Then I noticed he was watching my mouth and turning his left ear toward me. I stood in front of the window light, faced him and wrote on the whiteboard: "Can you hear me?" He laughed and wrote back, "Not without my hearing aids. They're in the top drawer at home."

I brought the unit's personal amplifier. Within minutes he told me his full name, where he was, why he had come in and that he had been getting up at night because he needed to urinate and no one answered his questions. He knew the date. I completed the delirium screen we use with him now able to hear me, and it was negative. I told the team I could not rule delirium out completely and that we would keep watching, but what we had seen fit a communication problem.

I called his daughter, who brought both hearing aids and the charger that afternoon. We put them in a labelled case on his bedside table. I updated the care plan: "Hard of hearing; hearing aids both ears; face him in good light; use amplifier if aids are out." I added it to the whiteboard and the handover tool, offered him a urinal and a bedside commode at night, and told the physician, who cancelled the psychiatry consult. At discharge teaching two days later, Mr. Moreau repeated back every step.

Reflect: What cues might the night team have missed, and how could the unit make hearing needs visible to everyone? Within authority, competence and context, when should an RPN caring for Mr. Moreau consult the RN?

36.6 Ear Disorders and Ear Surgery

Ear disorders range from a painful ear canal to sudden deafness and disabling vertigo. Many affect older adults and raise the risk of falls. This section covers common ear problems, balance disorders and nursing care after ear surgery. Falls prevention in full is in Chapter 8, and perioperative care in Chapter 7.

Common Ear Disorders

Otitis externa is infection or inflammation of the ear canal, often after water is trapped in the ear. Risks include swimming, overcleaning with swabs, skin conditions such as eczema, and hearing aids or earbuds that fit poorly or are not cleaned. The ear itches and feels full, and pain worsens when the outer ear is tugged; there may be drainage and muffled hearing. Treatment is careful cleaning of the canal and prescribed ear drops, sometimes with a wick if the canal is swollen shut. Older adults, people with diabetes and people with weakened immunity are at higher risk of a dangerous form that spreads to bone at the base of the skull (AAO-HNSF, 2018b). The nurse reports severe or spreading pain, fever or swelling around the ear (Figure 36.12).

Figure 36.12 Instilling ear drops in an adult: the patient lies with the affected ear up while the nurse gently pulls the pinna upward and backward to straighten the ear canal and holds the dropper tip clear of the skin. (credit: “Instilling ear medication” by British Columbia Institute of Technology (BCIT)/BCcampus, CC BY 4.0)

Otitis media, infection or fluid in the middle ear, is listed mainly as a cause of hearing loss in childhood (WHO, 2026). When fluid or infection fills the middle ear, sound cannot pass through well, so the result is a conductive loss (Table 36.3).

Sudden sensorineural hearing loss (SSNHL) is a rapid loss of hearing in one or both ears, developing over up to 72 hours; it is commonly defined as a loss of 30 decibels (dB) or more across three neighbouring pitches (AAO-HNSF, n.d.). More than 90% of cases have no known cause. The US guideline on sudden hearing loss asks clinicians to tell sensorineural from conductive loss at the first visit, so that a sudden nerve loss is not dismissed as wax. It recommends a hearing test as soon as possible and within 14 days, and corticosteroids may be offered within 2 weeks of onset (Chandrasekhar et al., 2019). Loss in both ears, repeated episodes or other neurologic signs call for prompt medical review, because they can point to other causes (Chandrasekhar et al., 2019); stroke is covered in Chapter 31. The nurse treats sudden hearing loss as urgent and arranges prompt medical assessment rather than a routine appointment.

Tinnitus is the perception of sound with no outside source (AAO-HNSF, 2026). It is common: about 37% of Canadian adults aged 20 to 79 reported tinnitus in the past year (Statistics Canada, 2021). The 2026 US guideline update focuses on bothersome tinnitus lasting 6 months or more. It calls for a full hearing evaluation and direct questions about distress and thoughts of self-harm, supports sound enrichment and cognitive behavioural therapy, and recommends against routine medicines or supplements (AAO-HNSF, 2026). New tinnitus in a person taking an ototoxic medicine is reported at once (section 36.4).

Wax that causes symptoms can be softened with drops, washed out by irrigation or removed by a trained clinician with suction or small instruments. Irrigation calls for caution, and removal by a specialist is preferred, when the eardrum has a hole or a tube, the

canal skin is damaged, or the person has diabetes or a weakened immune system (AAO-HNSF, 2018a). The nurse removes wax only as employer policy and competence allow (Scope in Practice box).

Vertigo and Balance Disorders

Vertigo is a false sense that the person or the room is moving (Bhattacharyya et al., 2017). Any new vertigo raises the risk of falls, and vertigo with new neurologic signs is assessed as a possible stroke (Chapter 31).

Benign paroxysmal positional vertigo (BPPV) is the most common inner ear balance disorder. Brief spells of vertigo, usually a minute or less, start with changes in head position, such as rolling over in bed, looking up or bending forward. Some people feel only light-headed, unsteady or nauseated. BPPV is more common in women and in middle and later life, and older adults with it have more falls; in one clinic study, about three quarters of older adults with undiagnosed BPPV had fallen in the previous 3 months. The diagnosis rests on the history and a positioning test done by a trained clinician. For the most common type (posterior canal BPPV), a US guideline strongly recommends a **canalith repositioning manoeuvre**, such as the Epley manoeuvre, done by a trained clinician; it recommends against routine use of vestibular suppressant drugs, such as antihistamines or benzodiazepines, and against activity restrictions after the manoeuvre. It also calls for checking factors that change management, such as poor balance, lack of support at home and fall risk, reassessment within a month and teaching about recurrence and safety (Bhattacharyya et al., 2017).

Ménière disease causes spontaneous vertigo attacks, each 20 minutes to 12 hours long, with sensorineural hearing loss, tinnitus and a feeling of pressure or fullness in the affected ear. Hearing may fluctuate. The diagnostic criteria were set by the Bárány Society with US and international partners (Lopez-Escamez et al., 2015) and are used in the 2020 US guideline. Onset peaks in the 40s and 50s. Short courses of vertigo-suppressing medicine are used only during attacks. Teaching covers diet and lifestyle changes that may reduce attacks. Diuretics or betahistine may be offered to prevent attacks, and injections into the middle ear or surgery are options when these fail. **Vestibular rehabilitation**, exercises that help the brain adapt to balance problems, is offered for ongoing imbalance but not during an acute attack, and people with hearing loss are counselled about hearing aids and assistive technology (Basura et al., 2020). Attacks come without warning, so the nurse helps the person plan for safety at home, at work and when driving. During an attack in hospital, the nurse keeps the person safe in bed with the call bell in reach, gives prescribed medicine for vertigo and nausea, and records how long the attack lasted and any change in hearing or tinnitus, since the guideline asks clinicians to track these outcomes (Basura et al., 2020).

Older adults carry more of the burden of ear disorders. Wax blocking the canal is more common with age (Feder et al., 2015), older age adds to the risk of hearing damage from aminoglycosides (Baxter Corporation, 2019), and older adults are more likely to develop the dangerous, spreading form of otitis externa (AAO-HNSF, 2018b). Older adults with BPPV have more falls, depression and difficulty with daily activities (Bhattacharyya et al., 2017), so the nurse links any dizziness to the falls plan (Chapter 8).

Ear Surgery

Tympanoplasty repairs a hole in the eardrum. **Stapedectomy** replaces a stapes that cannot move with a tiny piston; hearing improves in more than 90% of people (Royal Berkshire NHS Foundation Trust, 2022). Cochlear implant surgery places the internal part of the implant. Perioperative care is covered in Chapter 7.

After middle ear surgery, a dissolving or removable packing usually sits in the ear canal, and some blood-tinged drainage is expected for several days. To protect the repair, instructions from one Ontario surgeon include no nose blowing for 3 weeks, sneezing and coughing with the mouth open and no bending over for a week (Beyea, n.d.). A UK hospital's stapedectomy instructions add no straining, heavy lifting or constipation for 2 weeks (Royal Berkshire NHS Foundation Trust, 2022). Advice on flying varies widely, from 3 days after tympanoplasty in one Ontario handout to 5 weeks after stapedectomy in a UK leaflet, so the person follows their own surgeon's instructions (Beyea, n.d.; Royal Berkshire NHS Foundation Trust, 2022). Water is kept out of the ear.

Short-lived dizziness is expected, so fall precautions apply (Beyea, n.d.; Royal Berkshire NHS Foundation Trust, 2022). The facial nerve runs close to the middle ear (Royal Berkshire NHS Foundation Trust, 2022), so the nurse checks facial movement against the baseline, asking the person to raise the eyebrows, close the eyes tightly and smile (Chapter 30), and reports new weakness at once. A metallic taste on one side of the tongue may follow and usually settles over months (Beyea, n.d.). The nurse reports fever, heavy bleeding, foul or pus-like drainage, pain not relieved by the prescribed medicine, severe vertigo or vomiting and sudden loss of hearing (Beyea, n.d.; Royal Berkshire NHS Foundation Trust, 2022).

Table 36.4 summarizes the ear and balance disorders in this section and the nursing focus for each.

Table 36.4 Ear and balance disorders and nursing focus (AAO-HNSF, 2018b; AAO-HNSF, 2026; Basura et al., 2020; Bhattacharyya et al., 2017; Chandrasekhar et al., 2019)

Disorder	Key features	Danger signs to report	Nursing focus
Otitis externa	Itchy, full ear canal; pain when the outer ear is tugged; drainage	Severe or spreading pain, fever, swelling around the ear, especially in older adults or people with diabetes	Keep the ear dry; give ear drops as prescribed; teach avoiding cotton swabs
Sudden sensorineural hearing loss	Hearing loss developing over up to 72 hours in one or both ears	Any sudden loss; loss in both ears or with neurologic signs	Prompt medical assessment; do not assume wax; communication support
Tinnitus	Ringing, buzzing or hissing with no outside source	New tinnitus on an ototoxic medicine; distress or thoughts of self-harm	Ask about distress; hearing evaluation; sound enrichment; referral for counselling
Benign paroxysmal positional vertigo	Spells of vertigo of a minute or less with changes in head position	Vertigo with neurologic signs; falls	Fall precautions; help with getting up; repositioning manoeuvre by a trained clinician
Ménière disease	Vertigo attacks, each 20 minutes to 12 hours long, with fluctuating hearing loss, tinnitus and ear fullness	Falls during attacks; vomiting that prevents fluid intake	Safety during attacks; medicines as prescribed; diet and lifestyle teaching; hearing support

PATIENT EDUCATION

After Ear Surgery

Your surgeon will give you instructions for your own operation; follow them first. Common advice after middle ear surgery includes (Beyea, n.d.; Royal Berkshire NHS Foundation Trust, 2022):

- **Protect the repair:** do not blow your nose until your surgeon says you may. Sneeze and cough with your mouth open. Avoid bending over, straining and heavy lifting, and prevent constipation.
- **Keep water out:** keep the ear dry when you shower or wash your hair, as your surgeon shows you. Do not put cotton swabs in the ear. Leave any packing in place.
- **Expect some changes:** some blood-tinged drainage, popping sounds, mild dizziness and a metallic taste can happen and usually settle.
- **Stay safe:** get up slowly and hold on to something while you are dizzy. Do not drive until you can turn your head quickly without feeling unsteady.
- **Travel:** ask your surgeon before flying; advice ranges from days to weeks.
- **Call your surgeon or get help** for a fever (as your surgeon's instructions define it), heavy bleeding, pus or foul-smelling drainage, pain your medicine does not relieve, severe dizziness or vomiting, new weakness of your face, or sudden loss of hearing.

SCOPE IN PRACTICE

Eye and Ear Care and Who Does What

Every nurse assesses vision and hearing, provides communication access and acts at once on eye emergencies and sudden hearing loss. Who does more depends on authority, competence and context (College of Nurses of Ontario [CNO], 2025; Chapter 1, section 1.3).

- **Authority:** In Ontario, putting an instrument, hand or finger beyond the external ear canal is a controlled act authorized to RNs and RPNs; it needs an order unless the nurse may initiate it, and nurses cannot initiate controlled acts in public hospitals (CNO, 2025). Wax removal and ear irrigation work within the ear canal; the nurse follows employer policy and any order the setting requires. Prescription eye and ear drops are given with the order or prescription the setting requires (Chapter 1, section 1.3).
- **Competence:** Eye irrigation, cerumen removal and ear irrigation need knowledge, skill and judgment, including checking for reasons not to irrigate, such as a hole in the eardrum (section 36.6). A nurse without that competence asks for support.

- **Context:** Employer policy sets which nurses may remove wax or irrigate ears, and employers can limit but not expand a nurse's legislated scope (CNO, 2025).

Arranging a qualified interpreter and other communication supports is every nurse's duty. Any nurse who notices a chemical eye injury, sudden vision or hearing loss, or new tinnitus or dizziness on an ototoxic medicine acts at once and escalates; the RPN consults the RN as the patient's needs change. Rules differ by province and territory, and CNO's revised Scope of Practice and Medication standards take effect on March 1, 2027 (CNO, 2026).

Chapter 36 Summary

36.1 Vision and Eye Assessment

- The cornea and lens focus light on the retina; the macula gives central vision, and the optic nerve carries signals to the brain. Intraocular pressure reflects the balance between aqueous humour made and drained.
- Assessment covers usual vision and aids, sudden or gradual change, pain, flashes, floaters, halos and distortion, plus visual acuity and outer eye inspection. Gradual loss often goes unnoticed or unreported.
- In 2022, 7.4% of Canadians aged 15 and older reported a seeing disability, rising to 11.4% at age 65 and older.
- Care for people with low vision includes introductions, orientation, CNIB's sighted guide technique, accessible formats and falls prevention. Charles Bonnet syndrome can be mistaken for dementia or mental illness.

36.2 Cataract, Glaucoma and Other Causes of Vision Loss

- Cataract is clouding of the lens; day surgery replaces it with an intraocular lens. After surgery, teaching covers the shield, drops, activity limits and warning signs such as rising pain, redness and worsening vision.
- Open-angle glaucoma is silent until advanced; people at high risk need eye examinations. Drops lower intraocular pressure, and beta-blocker drops such as timolol can have serious systemic effects.
- Acute angle-closure glaucoma, with eye pain, headache, halos, blurred vision and vomiting, is an emergency.
- New distortion in AMD needs review within 24 hours; wet AMD is treated with anti-VEGF injections. Diabetes Canada sets retinopathy screening intervals by diabetes type.
- Colonization and other structural causes, plus distance from specialists, limit eye care access for many First Nations, Inuit and Métis people; community-designed teleophthalmology is one response.

36.3 Eye Emergencies, Trauma and Eye Surgery

- A chemical in the eye is irrigated at once and for a prolonged time. A penetrating injury is shielded without pressure, and any protruding object is left in place.
- Sudden flashes, new floaters and a spreading shadow suggest retinal detachment; sudden painless vision loss needs immediate escalation, with stroke and giant cell arteritis considered.
- Corneal abrasions are not patched, and numbing drops are not sent home.
- After retinal surgery with a gas bubble, the person follows positioning exactly, avoids lying flat on the back, does not fly, travel to higher elevations or receive nitrous oxide, and wears the alert wristband until the gas is gone.

36.4 Hearing and Ear Assessment

- The outer and middle ear carry sound to the cochlea, which turns it into nerve signals; the inner ear also senses balance.
- Conductive loss comes from the outer or middle ear and is often treatable; sensorineural loss comes from the cochlea or nerve and is usually permanent; mixed loss combines both.
- Presbycusis starts at high pitches, making speech sound mumbled, especially in noise; noise and ototoxic medicines are preventable causes.
- Aminoglycosides such as gentamicin can cause tinnitus, high-pitched hearing loss and balance damage, which may be permanent; the nurse reports new symptoms at once and supports drug level and kidney monitoring.

- In Canada, about 38% of adults aged 20 to 79 had measured hearing loss, and about 77% of adults aged 40 to 79 with measured loss did not perceive it, so the nurse asks every adult about hearing.
- The whispered voice test is a quick screen; wax, sudden loss and suspected hearing loss are followed up, and audiologists confirm loss with an audiogram.

36.5 Communication Access, Hearing Aids and Cochlear Implants

- Communication access underpins consent, teaching and safety; unaddressed hearing loss can be mistaken for confusion.
- The nurse asks how the person communicates best, faces them in good light, reduces noise, speaks a little louder and slower and checks understanding; personal amplifiers help when hearing aids are absent.
- Masks muffle sound and hide the lips; clear-window masks allow lip-reading but muffle sound more.
- Deaf people who sign need qualified ASL, LSQ or Indigenous sign language interpreters, in person or by video; family members do not interpret.
- The Accessible Canada Act recognizes signed languages, the Eldridge decision made interpretation in health care a Charter equality issue, and Ontario's AODA requires communication supports.
- Hearing aids and cochlear implant processors are recorded, kept in use, charged and stored safely; the MRI team must be told about a cochlear implant and its model.

36.6 Ear Disorders and Ear Surgery

- Otitis externa causes ear canal pain that worsens when the ear is tugged; older adults and people with diabetes are at higher risk of a dangerous spreading form.
- Sudden sensorineural hearing loss is urgent: it is not assumed to be wax, and hearing testing and any treatment start early.
- Bothersome tinnitus calls for a hearing evaluation and direct questions about distress and self-harm; routine medicines and supplements are not recommended.
- BPPV causes brief positional vertigo and is treated with a repositioning manoeuvre by a trained clinician; Ménière disease causes attacks of vertigo lasting hours with fluctuating hearing loss, tinnitus and ear fullness.
- After ear surgery, patients avoid nose blowing and straining, sneeze with the mouth open, keep water out of the ear and follow their surgeon's travel advice; new facial weakness, severe vertigo or sudden hearing loss are reported at once.
- Every nurse provides communication access and escalates eye and ear emergencies; cerumen removal and ear irrigation depend on authority, competence and employer policy.

Key Terms (57)

acute angle-closure glaucoma: An eye emergency in which the drainage angle closes and intraocular pressure rises quickly, causing eye pain, headache, halos, blurred vision, nausea and vomiting.

age-related macular degeneration (AMD): Age-related disease of the macula that causes loss of central vision; it occurs in a dry (atrophic) form and a wet (neovascular) form.

American Sign Language (ASL): A full signed language with its own grammar, used by many Deaf people in English-speaking Canada; recognized in the Accessible Canada Act as one of the primary languages of communication for deaf persons in Canada.

anti-VEGF therapy: Medicines that block vascular endothelial growth factor, injected into the eye to treat wet AMD and diabetic eye disease.

aqueous humour: The clear fluid made by the ciliary processes that fills the front of the eye and drains through the drainage angle and the uveoscleral route.

audiogram: A chart of the softest sounds a person can hear in each ear across a range of pitches, produced by a hearing test.

benign paroxysmal positional vertigo (BPPV): An inner ear disorder causing brief spells of vertigo, usually a minute or less, triggered by changes in head position.

canalith repositioning manoeuvre: A series of head and body movements, such as the Epley manoeuvre, done by a trained clinician to treat BPPV.

cataract: Clouding of the lens of the eye, most often with age.

cerumen: Earwax, made by glands in the outer ear canal to protect and lubricate the canal.

cerumen impaction: A build-up of earwax that blocks the ear canal or causes symptoms such as fullness, muffled hearing, tinnitus or ear pain.

Charles Bonnet syndrome: Seeing images of people, landscapes or patterns that are not there, after significant vision loss; it is often mistaken for dementia or a mental health problem.

chemical eye injury: Damage to the eye from a chemical splash; alkali injuries are generally more harmful than acid injuries.

cochlea: The fluid-filled, snail-shaped organ of the inner ear whose hair cells turn sound vibrations into nerve signals.

cochlear implant: An electronic device, partly placed by surgery, that sends signals straight to the hearing nerve so that people who are severely hard of hearing or profoundly deaf can perceive sound.

communication access: The ability of a person to understand and be understood in the way that works for them, with the supports they need.

conductive hearing loss: Hearing loss caused by a problem in the outer or middle ear that stops sound from reaching a normal inner ear.

cornea: The clear, curved front surface of the eye, which bends incoming light to help focus it.

corneal abrasion: A scratch in the outer layer of the cornea that causes pain, tearing and light sensitivity.

Deaf: A cultural identity, written with a capital D, of people who share Deaf culture and use a signed language as their main language.

diabetic retinopathy: Damage to the retina caused by diabetes.

endophthalmitis: A sight-threatening infection inside the eye that can follow eye surgery or a penetrating eye injury.

glaucoma: A group of eye diseases in which the optic nerve is progressively and irreversibly damaged and the visual field shrinks.

hearing aid: A small electronic device worn in or behind the ear that makes sound louder.

hyphema: Bleeding inside the front of the eye, usually after blunt injury; a possible sign of serious injury to the eyeball.

inner ear: The innermost part of the ear, containing the cochlea for hearing and the vestibular organs for balance.

intraocular pressure (IOP): The pressure inside the eye, set by the balance between aqueous humour production and drainage.

langue des signes québécoise (LSQ): A full signed language used by many Deaf people in Quebec and French-speaking communities; recognized in the Accessible Canada Act.

lens: The clear structure behind the pupil that works with the cornea to focus light onto the retina.

low vision: As used in this chapter, vision loss that cannot be fully corrected with glasses, contact lenses, medicine or surgery and that limits everyday activities.

macula: The central area of the retina that gives sharp central vision.

middle ear: The air-filled space behind the eardrum containing three small bones that carry sound vibrations to the inner ear.

mixed hearing loss: Hearing loss with both conductive and sensorineural parts.

Ménière disease: An inner ear disorder with vertigo attacks, each 20 minutes to 12 hours long, with sensorineural hearing loss, tinnitus and a feeling of fullness in the affected ear.

open-angle glaucoma: A slowly progressive form of glaucoma that typically causes no symptoms until it is advanced.

optic nerve: The nerve that carries signals from the retina to the brain.

otitis externa: Infection or inflammation of the ear canal, often after water is trapped in the ear; pain worsens when the outer ear is tugged.

otitis media: Infection or fluid in the middle ear, listed mainly as a cause of hearing loss in childhood; it causes a conductive hearing loss.

ototoxicity: Damage to the inner ear, affecting hearing, balance or both, caused by a medicine or chemical.

outer ear: The visible ear and the ear canal, ending at the eardrum.

personal amplifier: A small handheld device that makes nearby speech louder through headphones or earphones for a person with hearing loss.

presbycusis: Age-related sensorineural hearing loss that starts at the highest pitches and later spreads to lower ones.

punctal occlusion: Pressing on the inner corner of the eye after instilling a drop to reduce the amount of drug that reaches the bloodstream.

retina: The light-sensitive layer at the back of the eye, whose photoreceptor cells turn light into electrical signals.

retinal detachment: Separation of the retina from the back of the eye, signalled by sudden flashes, new floaters and a spreading shadow over vision.

sensorineural hearing loss: Hearing loss caused by damage to the cochlea or the hearing nerve; usually permanent.

sighted guide: A technique for walking with a person who is blind or partially sighted, in which the person holds the guide's arm just above the elbow and walks about half a step behind.

stapedectomy: Surgery that replaces a stapes bone that cannot move with a tiny piston to improve hearing.

sudden sensorineural hearing loss (SSNHL): A rapid sensorineural hearing loss developing over up to 72 hours, commonly defined as a loss of 30 dB or more across three neighbouring pitches; an urgent problem.

tinnitus: The perception of sound, such as ringing, buzzing or hissing, with no outside source.

tympanic membrane: The eardrum, the thin membrane at the end of the ear canal that vibrates with sound.

tympanoplasty: Surgery to repair a hole in the eardrum.

vertigo: A false sense that the person or the surroundings are moving.

vestibular rehabilitation: Exercises that help the brain adapt to balance problems; offered for ongoing imbalance but not during an acute attack of vertigo.

video remote interpreting (VRI): Sign language interpretation provided by an interpreter who joins by video on a screen.

visual acuity: The sharpness of vision at a set distance, often measured with a letter chart such as the Snellen chart.

whispered voice test: A bedside hearing screen in which the examiner, out of the person's sight, whispers a mix of numbers and letters for the person to repeat, testing each ear separately.

Licensure Review & Clinical Judgment Questions (40)

Questions tagged **[Core]** apply to all nursing students (NCLEX-RN, REx-PN, and CPNRE). Questions tagged **[RN]** draw on *Going Deeper* content.

Case: Mrs. Huguette Desrosiers (Questions 1–4): Mrs. Huguette Desrosiers, 72, had day-surgery cataract removal from her right eye this morning in Ontario. She lives with her husband, wears reading glasses and has type 2 diabetes. Her surgeon has ordered two kinds of eye drops for the right eye. The registered practical nurse (RPN) is completing her discharge teaching.

1. [CORE] The RPN teaches Mrs. Desrosiers how to use her two kinds of eye drops. Which statement shows that she has understood the teaching?

a. "I'll put both kinds of drops in one right after the other so I don't forget the second one before bedtime."

b. "I'll wash my hands, put one drop in the pocket of my lower lid, and wait before using the second kind of drop."

c. "I'll hold the bottle tip against my lower lid so the drop goes in the right place and doesn't run down my cheek."

d. "I'll rub my eye gently after each drop so the medicine spreads over the whole eye and starts working faster."

Answer: b — Clean hands, one drop into the lower-lid pocket, and a wait between different drops (5 minutes in the hospital's instructions) is correct technique (section 36.2, Cataract, and the Patient Education box). Option a skips the wait between different drops that the instructions require. Option c risks touching and contaminating the eye and the bottle tip. Option d is wrong because rubbing or pressing on the eye is avoided after cataract surgery.

2. [CORE] Mrs. Desrosiers asks how to use the plastic shield she was given. Which instruction is consistent with typical post-cataract instructions?

a. "Wear the shield only when you go outside for the next month, and leave it off when you are at home indoors."

b. "Put a folded gauze pad under the shield tonight so that it fits snugly and puts gentle pressure on the eye."

c. "You can stop wearing the shield tonight, once the eye feels comfortable and you can see better than before."

d. "Wear it all the time today except when putting in drops, then wear it at night for about the next week."

Answer: d — The Canadian instructions read for this chapter direct wearing the shield at all times on the day of surgery except during drops, then at night for the next 7 nights, always following the surgeon's instructions (section 36.2, Cataract). Option a gets the timing backwards; the shield protects the eye during sleep, when the person may rub it. Option b is unsafe because nothing is placed between the shield and the eye and pressure on the eye is avoided. Option c stops protection too early.

3. [CORE] Mrs. Desrosiers says she plans to get back to her garden and weed her flower beds this weekend. Which response by the RPN is best?

a. "Avoid gardening, heavy lifting and bending your head below your shoulders for about 2 weeks, or as your surgeon advises."

b. "Gardening is fine as long as you wear your sunglasses outdoors, since the main risk after this surgery is bright sunlight."

c. "You can garden right away if you kneel instead of bending, because kneeling takes the strain off the eye."

d. "Gardening is safe after 2 days, as long as you put in an extra dose of your antibiotic drops before you go outside."

Answer: a — Typical instructions restrict gardening and handling soil, lifting more than about 4.5 kg (10 lb), and bending the head below the shoulders for 2 weeks, with the surgeon's own instructions taking priority (section 36.2, Cataract). Option b ignores the infection risk from soil. Option c still exposes the eye to soil and dust. Option d adds an unordered dose and does not remove the risk.

4. [CORE] On the second day after surgery, Mrs. Desrosiers's husband calls the day-surgery unit. Which report needs the most urgent follow-up?

a. Her eye feels a little scratchy, and she has a small amount of watery tearing when she first wakes up in the morning.

b. She has trouble reading her newspaper and plans to wait for new reading glasses after her follow-up visit next week.

c. Her eye pain has been getting worse since last night, the eye is redder, and her vision in that eye seems blurrier.

d. She has worn her shield at night, has used her drops as directed, and says the eye feels comfortable today.

Answer: c — Rising pain, increasing redness and worsening vision after cataract surgery are warning signs that need prompt contact with the surgical team or an emergency department; they can signal a complication such as infection inside the eye (endophthalmitis) (section 36.2, Cataract). Options a and b describe common, non-urgent concerns that can be addressed at follow-up. Option d describes expected recovery with correct self-care.

5. [CORE] Mr. Idris Kamara, 58, has been blind since a workplace injury and walks with a white cane. He asks the nurse to walk with him to the patient lounge. Which action follows the sighted guide technique?

a. The nurse takes his elbow firmly from behind and steers him gently around chairs and other obstacles in the hallway.

b. The nurse holds the end of his white cane and walks in front of him so that he can follow the cane through the hallway.

c. The nurse lightly touches the back of his hand with her own, lets him hold just above her elbow, and walks half a step ahead.

d. The nurse walks beside him and calls out "left" or "right" whenever he starts to drift toward the hallway walls.

Answer: c — CNIB's sighted guide technique has the person hold the guide's arm just above the elbow and walk about half a step behind, after the guide signals by touching the back of the hand (section 36.1, Caring for People With Vision Loss). Option a pushes and steers him, which CNIB says never to do. Option b takes control of his cane, which should never be grabbed or pulled. Option d gives late directions without describing obstacles ahead.

6. [CORE] Which person has the most risk factors for open-angle glaucoma, as described in this chapter?

a. A 63-year-old man of African descent whose sister has glaucoma and who uses corticosteroid eye drops for eye inflammation

b. A 35-year-old woman with long-sightedness who wears contact lenses every day and works long hours at a computer screen

c. A 45-year-old man who had cataract surgery in one eye last year and who now wears reading glasses for close work at his desk

d. A 50-year-old woman with seasonal allergies who takes an antihistamine tablet daily and uses lubricating eye drops each spring

Answer: a — Older age, African descent, a first-degree relative with glaucoma and corticosteroid use in or around the eye are all risk factors for open-angle glaucoma (section 36.2, Glaucoma). Option b is younger, and long-sightedness is a risk factor for angle closure rather than open-angle glaucoma. Option c describes cataract surgery and age-related reading glasses, which are not listed risk factors. Option d describes allergy treatment, not a listed risk factor.

7. [CORE] A patient starting latanoprost eye drops for glaucoma asks about side effects. Which teaching is accurate?

a. The drops often cause a dry mouth and drowsiness, so the patient should avoid driving for the first month of treatment.

b. The drops can slow the heart rate and cause wheezing, so the patient should check their pulse before every single dose.

c. The drops may leave a bitter taste in the mouth and should be stopped right away if the taste becomes unpleasant.

d. The drops may gradually darken the coloured part of the eye, and this change is likely to be permanent if it occurs.

Answer: d — The latanoprost monograph warns that darkening of the iris increases with continued use and probably will not reverse after the drug is stopped; the eyelashes may also change (section 36.2, Glaucoma). Option a describes brimonidine. Option b describes systemic effects of beta-blocker drops such as timolol. Option c describes dorzolamide, and no drop is stopped without the prescriber's advice.

8. [CORE] Why does the nurse teach a patient to press on the inner corner of the eye for 2 minutes after instilling timolol drops?

a. To stop the drop from stinging the surface of the eye as it spreads across the cornea

b. To reduce how much of the drug drains into the nose and reaches the bloodstream

c. To keep the eyelid closed so the patient does not blink the drop out right away

d. To lower the pressure inside the eye by pushing aqueous humour out of the eye

Answer: b — Nasolacrimal (punctal) occlusion or gentle eyelid closure for 2 minutes reduces systemic absorption, which matters for beta-blocker drops (section 36.2, Glaucoma, and the Going Deeper box). Option a confuses occlusion with comfort measures. Option c describes eyelid closure, not the purpose of pressing on the inner corner. Option d is wrong: pressing on the eye does not treat glaucoma, and pressure on the eye is avoided after eye surgery.

9. [CORE] Ms. Colleen Ouellette, 77, has wet age-related macular degeneration and receives regular eye injections. During a home visit, she tells the nurse that since yesterday the lines on her Amsler grid look bent in her left eye. Which action is best?

a. Advise her to contact her eye specialist today, because new distortion needs review within 24 hours.

b. Reassure her that bent lines are expected with macular degeneration and record the change in her chart.

c. Suggest she stop checking the grid, since it is not accurate and is likely to make her feel more anxious.

d. Tell her to mention the change at her next scheduled injection appointment, which is in 3 weeks' time.

Answer: a — New distortion or central blur in AMD is urgent and needs review by an eye specialist within 24 hours, because wet AMD can progress quickly (section 36.2, Macular Degeneration and Diabetic Retinopathy). Option b treats a new change as expected. Option c removes a self-monitoring tool that is still recommended despite its limits. Option d delays assessment.

10. [CORE] Mr. Ruben Ramírez, 52, was diagnosed with type 2 diabetes last month. Which statement about retinopathy screening is consistent with Diabetes Canada's guideline?

a. "You won't need an eye examination until you have had diabetes for 5 years, unless your vision changes."

b. "Your family doctor will check your eyes with a light at your yearly physical, and that is all the eye screening you will need."

c. "You should have a retinal examination now, then every 1 to 2 years if no retinopathy or only minimal retinopathy is found."

d. "You need an eye examination every 3 months for the first year, because newly diagnosed diabetes damages the retina quickly."

Answer: c — For type 2 diabetes, Diabetes Canada recommends screening at diagnosis by an optometrist or ophthalmologist, then every 1 to 2 years when there is no or minimal retinopathy (section 36.2). Option a describes the start of screening in type 1 diabetes. Option b is wrong because screening is done by an optometrist or ophthalmologist, who examines the eye directly or reads retinal photographs taken after the pupils are dilated. Option d is not a recommended interval.

11. [CORE] A cleaner on a hospital unit splashes a disinfectant concentrate into her eyes and calls for help. What is the nurse's first action?

a. Find the product's safety data sheet to identify the chemical before choosing which eye treatment to use

b. Cover both eyes with dry gauze pads and walk her straight down to the emergency department for an urgent assessment

c. Call the most responsible provider for an order for anesthetic eye drops before touching or rinsing her eyes

d. Begin flushing her eyes with water or saline at once, holding the lids open, and keep going while help is called

Answer: d — Chemical eye injury is irrigated immediately and for a prolonged time, with the eyelids held open; irrigation is not delayed to identify the chemical or obtain orders (section 36.3, Eye Emergencies). Options a and c delay irrigation, and option b covers the eyes without removing the chemical.

12. [CORE] A patient arrives in the emergency department with a small metal fragment protruding from the right eye after using a grinder. Which action is appropriate while waiting for ophthalmology?

a. Remove the fragment carefully with sterile forceps so that it cannot be pushed any further into the eye during transfer

b. Tape a rigid shield over the eye so it does not touch the fragment or press on the eye, and give the ordered antiemetic

c. Apply a firm pressure patch over both eyes to stop eye movement and to reduce any bleeding from inside the injured eye

d. Irrigate the eye with large volumes of saline to wash out any small metal particles left around the protruding fragment

Answer: b — With a penetrating injury, the eye is covered with a rigid shield without pressure, a protruding object is left in place, and vomiting and straining are prevented (section 36.3, Eye Emergencies). Option a risks further damage to the eye. Option c puts pressure on an injured eye. Option d is used for chemical injury, not a penetrating injury.

13. [CORE] An RPN on a surgical unit is caring for Mrs. Agnes Gallant, 66. At 2100 she says she has seen sudden flashes of light and "a swarm of black specks" in her left eye for the past hour, and a grey shadow is creeping across the top of her vision. What should the RPN do?

a. Consult the RN and notify the most responsible provider now, because these are warning signs of retinal detachment.

b. Dim the lights, encourage her to rest her eyes, and reassess her vision after she has had a full and restful night's sleep.

c. Explain that floaters are common with age, and suggest she mention them at her next visit to her optometrist.

d. Instil lubricating eye drops from her supply and document the symptoms for the day team to review in the morning.

Answer: a — Sudden flashes, new floaters and a spreading shadow over vision suggest retinal detachment and need assessment within 24 hours; the RPN acts at once, consults the RN and escalates (section 36.3, Eye Emergencies). Options b, c and d all delay assessment, and option d also treats with a product that will not help.

14. [CORE] A patient was diagnosed with a corneal abrasion after a branch scratched his eye. He asks whether he can take home the numbing drops used during his examination. Which response is accurate?

a. "Yes, use them whenever the pain comes back, because they will help the scratch heal more quickly."

b. "Yes, but only at bedtime, so the pain does not wake you up during the night while the eye heals."

c. "You can use them for the first 2 days only, and then switch to a regular pain reliever by mouth."

d. "No, numbing drops are not used at home because they slow healing and can hide signs of worsening."

Answer: d — Topical anesthetic drops are not recommended for home use because they are toxic to the corneal surface, delay healing and mask worsening symptoms (section 36.3, Eye Emergencies). Options a, b and c all send the patient home with numbing drops, and option a wrongly claims they speed healing.

15. [CORE] An RPN in a long-term care home finds Mr. Walter Abernathy, 81, upset because he "suddenly can't see anything" out of his right eye. He has no eye pain. His vital signs are within his usual range. What is the RPN's priority?

a. Clean his glasses, improve the lighting in his room, and recheck his vision later in the shift once he has calmed down.

b. Arrange an appointment with his optometrist for the next available date and continue to monitor him until then.

c. Consult the RN and contact the physician or NP immediately, because sudden painless vision loss is an emergency.

d. Document the new finding in his chart and ask the next shift to reassess his vision in the morning after breakfast.

Answer: c — Sudden painless vision loss may mean a blocked retinal artery, stroke or giant cell arteritis; it needs immediate escalation and ophthalmology referral (section 36.3, Eye Emergencies; Chapters 31 and 34). The RPN acts at once and consults the RN as needs change. Options a, b and d delay assessment of an emergency.

16. [CORE] The nurse is caring for a patient who has low vision from glaucoma and is newly admitted to a medical unit. Which actions support the patient's safety and independence? Select all that apply.

a. Say your name and role each time you enter the room, and tell the patient when you are leaving.

b. Move the patient's belongings to the places staff usually keep them so that everything is easy for staff to find.

c. Describe the layout of the room, including the call bell, bed controls and the route to the bathroom.

d. Ask the patient which formats they prefer for written information, such as large print or audio.

e. Speak to the patient's daughter instead of the patient when explaining the plan of care, to save time.

f. Keep the path to the bathroom clear and well lit, and keep the patient's glasses within reach.

Answer: a, c, d, f — Introducing yourself and saying when you leave, orienting the patient to the room, offering accessible formats and keeping a clear, lit path with glasses within reach support safety and independence (section 36.1, Caring for People With Vision Loss). Option b is wrong because items are kept where the patient puts them. Option e is wrong because the nurse speaks directly to the patient.

17. [CORE] Mrs. Odile Sauvé, 84, has advanced macular degeneration. She tells the nurse that she keeps seeing small children in old-fashioned clothes standing in the corner of her room, although she knows they cannot really be there. She is alert and oriented. Which response is most appropriate?

a. "These images can be a sign of a new mental illness, so I will ask for a psychiatric consultation to be booked for you today."

b. "Some people with vision loss see images that aren't there. I'll let your team know, and we can talk about supports."

c. "It is probably a side effect of your eye injections, so you should cancel your next injection appointment."

d. "You are probably becoming confused at night, so I will keep the lights off to help you sleep better."

Answer: b — Images of people or patterns that are not there, in an alert, oriented person with significant vision loss, fit Charles Bonnet syndrome; it is often mistaken for dementia or a mental health problem (section 36.1). The nurse listens without judgment, reports it and connects the person with support. Option a assumes mental illness. Option c gives unsafe advice about stopping treatment. Option d assumes confusion, and darkness does not help.

18. [RN] An RN on a medical unit assesses a 69-year-old patient who has sudden severe pain in the left eye, a headache, vomiting and blurred vision with halos around lights. The left pupil is mid-dilated and reacts poorly. Earlier that day the patient received an anticholinergic medicine. Which action is the priority?

a. Give an analgesic for the headache, dim the room lights, and reassess the pain and the vision in the left eye in about an hour.

b. Instil the patient's lubricating eye drops and place a cool compress over the left eye to relieve the pain and the redness.

c. Give the next scheduled dose of the anticholinergic medicine, then document the eye findings for the team.

d. Notify the most responsible provider and ophthalmology at once, and prepare to give ordered pressure-lowering medicines.

Answer: d — Eye pain, headache, vomiting, halos and a mid-dilated, poorly reactive pupil suggest acute angle-closure glaucoma, an emergency that needs prompt IOP-lowering treatment followed by laser iridotomy; a pupil-dilating medicine may have triggered it (section 36.2, Glaucoma). Option a delays treatment of an emergency. Option b treats symptoms only. Option c gives more of a possible trigger.

19. [RN] A patient with COPD and type 2 diabetes is ordered timolol eye drops for open-angle glaucoma. Before the first dose, the RN finds a heart rate of 48 beats per minute. What is the best action?

a. Hold the dose and contact the prescriber, because timolol can be absorbed systemically and is contraindicated here.

b. Give the dose as ordered, because eye drops act only in the eye and do not affect the heart rate or breathing.

c. Give the dose and press on the inner corner of the eye for 2 minutes, which removes all risk of systemic effects from the drug.

d. Give half the dose to each eye so that the total amount of drug absorbed into the bloodstream is reduced.

Answer: a — The Canadian timolol monograph states that the drug may be absorbed systemically and lists COPD and sinus bradycardia among its contraindications; beta-blockers can also mask the signs of hypoglycemia (section 36.2, Glaucoma). Option b ignores systemic absorption. Option c is wrong because punctal occlusion reduces, but does not remove, absorption. Option d changes the order without authority.

20. [RN] A patient had vitrectomy with a gas bubble for retinal detachment 10 days ago and is now admitted for an urgent laparoscopic cholecystectomy under general anesthesia. She is wearing a gas bubble wristband. Which action by the RN is most important?

a. Remove the wristband before surgery, because all jewellery and bands must come off before going to the operating room.

b. Position her flat on her back after surgery to reduce strain on the new abdominal incisions.

c. Make sure the anesthesia and surgical teams know about the gas bubble, because nitrous oxide must not be used.

d. Ask the surgical team to cancel the upcoming eye follow-up visit, because it is not relevant to this hospital admission.

Answer: c — Until an intraocular gas bubble has dissolved, nitrous oxide can raise the pressure in the eye and cause blindness; the wristband alerts staff and stays on, and the anesthesia team must be told (section 36.3, Care After Eye Surgery). Option a removes the alert. Option b breaks her positioning instructions, since lying flat on the back is avoided. Option d ignores ongoing eye care that is still needed.

Case: Elias Vogt (Questions 21–26): Elias Vogt, 74, is admitted to a medical unit in a small Ontario hospital with community-acquired pneumonia and started on IV antibiotics, including gentamicin. He lives with his wife and normally wears hearing aids in both ears, but they were left at home in the rush to the hospital. The night nurse reports that he "seems confused": he answered "yes" to most questions, gave the wrong year when asked his date of birth and got out of bed without calling. On the day shift he is awake, watches the nurse's face closely when spoken to and often says "What?" He coughs up yellow sputum. Vital signs: temperature 37.8 °C, heart rate 92, respiratory rate 20, blood pressure 132/78 mm Hg and oxygen saturation 94% on 2 L/min by nasal prongs. His admission serum creatinine is 98 µmol/L.

21. [CORE] Which findings should the nurse recognize as cues that a hearing problem may explain Mr. Vogt's apparent confusion? Select all that apply.

a. His hearing aids were left at home.

b. He watches the nurse's face closely when spoken to.

c. He often says "What?" during conversation.

d. He answered "yes" to most questions overnight.

e. His temperature is 37.8 °C.

f. His oxygen saturation is 94% on 2 L/min.

g. He coughs up yellow sputum.

Answer: a, b, c, d — Hearing aids left at home, watching the speaker's face (lip-reading), asking "What?" and answering "yes" to everything are cues that he may not be hearing the questions (a, b, c, d; sections 36.4 and 36.5). The low-grade fever and oxygen saturation are cues about the pneumonia and raise his delirium risk, but they do not point to a hearing problem (e, f). Yellow sputum is a cue about the infection, not about hearing (g).

22. [CORE] Which interpretation of Mr. Vogt's overnight behaviour is most accurate?

a. His answers confirm delirium caused by pneumonia, so the nurse asks for a sedative to keep him in bed tonight.

b. His answers show long-standing dementia, so the nurse records it and simplifies all teaching from now on.

c. He may not be hearing questions, so the nurse restores communication first and then screens for delirium.

d. His answers are expected at his age and during an infection, so no further assessment is needed at this time.

Answer: c — Unaddressed hearing loss can look like confusion, so the nurse first makes sure he can hear (amplifier, facing him, hearing aids brought in) and then screens for delirium, which is still possible with pneumonia (c; section 36.5; Chapter 8). Labelling him delirious and sedating him without checking communication risks harm (a). Nothing supports a diagnosis of dementia (b). Confusion is never assumed to be normal for age (d).

23. [CORE] On day 4, Mr. Vogt's daughter has brought his hearing aids and he is oriented. He now reports a constant ringing in both ears, says he feels dizzy and unsteady when he stands and nearly fell walking to the bathroom. His serum creatinine has risen from 98 to 156 µmol/L. Which concern should the nurse treat as the priority?

a. Damage to the inner ear from gentamicin, affecting hearing and balance and raising his risk of falls

b. Hearing aids with low batteries, which can produce whistling sounds that the patient hears as a ringing noise

c. Worry about being in hospital, which can make a person notice ringing in the ears and feel light-headed

d. Weakness from several days of lying in bed, which can make a person unsteady when standing to walk

Answer: a — New tinnitus, dizziness and unsteadiness in a patient on an aminoglycoside, with worsening kidney function that raises drug levels, point to ototoxicity, and the near-fall makes it urgent (a; section 36.4). Battery problems do not explain dizziness, unsteadiness or a rising creatinine (b). Anxiety does not account for the full picture or the creatinine rise (c). Deconditioning may add to unsteadiness but does not explain the tinnitus (d).

24. [CORE] Which actions should the nurse include in Mr. Vogt's plan of care now? Select all that apply.

a. Report the tinnitus, dizziness and rising creatinine to the prescriber promptly.

b. Tell him the ringing is a normal part of pneumonia and will go away on its own.

c. Put fall precautions in place, including help with walking and the call bell within reach.

d. Make sure the latest gentamicin levels and kidney function results are available for review.

e. Take out his hearing aids for the rest of the day so that his ears can rest.

f. Ask about hearing changes in each ear and document what he reports.

g. Encourage him to walk to the bathroom alone to rebuild his strength.

Answer: a, c, d, f — The nurse reports signs of ototoxicity and the rising creatinine at once, has drug levels and kidney results ready, keeps him safe from falls and documents his hearing symptoms (a, c, d, f; sections 36.4 and 36.6). Ringing is not a normal part of pneumonia, and false reassurance delays action (b). Removing his hearing aids takes away his communication access without treating anything (e). Walking alone while dizzy invites a fall (g).

25. [RN] The trough gentamicin level drawn before Mr. Vogt's next dose is 3.1 mcg/mL; the product monograph advises avoiding troughs above 2 mcg/mL. The dose is due in 30 minutes. What should the nurse do first?

a. Give the dose on time, since a missed dose could let the pneumonia worsen, and report the level at morning rounds.

b. Contact the prescriber before the dose is due and report the level, creatinine, tinnitus and dizziness using SBAR.

c. Give half of the dose, since the trough is only a little above target, and ask for another level tomorrow morning.

d. Ask the pharmacist to replace gentamicin with an antibiotic that does not harm hearing, then give the new drug.

Answer: b — A high trough, rising creatinine and new symptoms of ototoxicity need the prescriber's decision before another dose; SBAR gives a clear, complete report (b; section 36.4; Chapter 6). Giving the dose risks permanent hearing and balance damage (a). The nurse does not change a dose without an order (c). The pharmacist can help, but changing the antibiotic needs a prescriber's order, and the prescriber must be told first (d).

26. [CORE] Gentamicin is stopped and another antibiotic started. Before discharge, which statement by Mr. Vogt shows that the teaching was effective?

a. "The ringing means my hearing aids are wearing out, so I will buy a new pair once I get home."

b. "Now that the antibiotic has been stopped, my hearing and balance are sure to be back to normal within a week."

c. "I will stay in bed most of the day at home until the dizziness is completely gone, to be safe."

d. "I will tell my doctor and pharmacist that gentamicin affected my ears and report any new hearing change."

Answer: d — He should make sure his providers know about the ototoxic reaction so it can be avoided in future, and report new or worse symptoms (d; section 36.4). The ringing is from the drug, not the hearing aids (a). Ototoxic damage may be permanent and can even appear after the drug is stopped, so full recovery cannot be promised (b). Staying in bed causes deconditioning; safe, supported activity and follow-up are better (c).

27. [CORE] An 80-year-old woman reports that hearing in her right ear has become gradually muffled. Otoscopy shows the right ear canal completely blocked by wax. Which statement about her hearing loss is most accurate?

a. It is a conductive loss, because sound cannot reach the inner ear; it often improves once wax is removed.

b. It is a sensorineural loss, because the wax has damaged the hair cells in the cochlea and the loss is permanent.

c. It is a mixed loss, because any hearing loss in a person over 80 combines nerve damage with a blockage.

d. It is age-related hearing loss, because wax build-up is the first stage of presbycusis in older adults.

Answer: a — Impacted wax blocks sound in the outer ear, a conductive loss that often improves when the wax is removed (a; section 36.4, Table 36.3). Wax does not damage the hair cells (b). A mixed loss needs both components and is not assumed from age (c). Presbycusis is sensorineural damage that starts at high pitches; it is not caused by wax (d).

28. [CORE] The nurse screens a patient's hearing with the whispered voice test. Which technique is correct?

a. Stand in front of the patient at a distance of 3 metres and whisper a short sentence while the patient watches.

b. Whisper a series of single numbers into each ear from 15 cm away while the patient keeps both eyes closed.

c. Stand beside the patient and say a mix of words in a normal voice, testing both ears together to save time.

d. Stand about an arm's length behind the patient, mask the other ear and whisper a mix of numbers and letters.

Answer: d — The test is done from about arm's length behind the person, so they cannot lip-read, with the other ear masked and a mix of numbers and letters whispered after a quiet breath out (d; section 36.4). Standing in front allows lip-reading (a). Whispering close to the ear is not the arm's-length method the review describes, and the other ear is not masked (b). A normal voice and testing both ears together miss a loss in one ear (c).

29. [CORE] A patient who is hard of hearing does not use sign language and is having trouble following the admission questions. Which approach by the nurse is best?

a. Raise the voice to a shout so the patient can hear, and stand at the side nearest the better ear.

b. Ask the patient's adult son to answer the questions, since he knows the history and hears well.

c. Face the patient in good light, turn off the television and check understanding as the talk goes on.

d. Give the patient the admission form to complete alone and collect it at the end of the shift.

Answer: c — Facing the person in good light, reducing noise, speaking a little louder and slower and checking understanding all support communication (c; section 36.5). Speaking a little louder and slower is enough, and standing to the side hides the face and lips the patient may rely on (a). The patient can take part and has the right to answer for himself (b). A form alone gives no chance to clarify or check understanding (d).

30. [CORE] Odette Lavallée, 58, is Deaf and uses langue des signes québécoise (LSQ). She is to sign consent for surgery tomorrow, and her hearing son offers to interpret for the consent discussion. What is the nurse's best response?

a. Thank him, explain that a qualified LSQ interpreter will be booked in person or by video, and invite him to stay.

b. Accept his offer, because a family member knows her best and can explain the surgery in words she will understand.

c. Write the consent discussion out in English for her to read, since written notes avoid the need for an interpreter.

d. Ask the surgeon to postpone the consent discussion until a family member who signs better than her son is available.

Answer: a — Consent needs a qualified, impartial interpreter; family interpreting can leave the patient out of the conversation and reduces privacy, but family can stay as support (a; section 36.5). Family members are not used as interpreters (b). Written notes are not a substitute for an interpreter for a Deaf person whose first language is signed (c). Another family member is still not a qualified interpreter (d).

31. [CORE] Which actions help keep a hospitalized patient's hearing aids in use and prevent their loss? Select all that apply.

a. Record the devices, and which ears they are for, at admission.

b. Store them in a labelled container kept in the same place each time.

c. Wrap them in a tissue on the meal tray when the patient eats.

d. Check that the batteries are charged or replaced.

e. Take them out during teaching sessions to avoid feedback noise.

f. Check that they are still in place after removing a mask.

g. Keep them in the bedside drawer for the whole stay for safety.

Answer: a, b, d, f — Recording devices, using a labelled container in a set place, keeping batteries working and checking devices after mask removal all keep hearing aids working and found (a, b, d, f; section 36.5). A device wrapped in tissue on a meal tray can easily be thrown out with the tray (c). Hearing aids should be in during teaching, when hearing matters most (e). Devices left in a drawer do not help the patient hear (g).

32. [CORE] A patient with a cochlear implant is booked for magnetic resonance imaging (MRI) of the knee. What should the nurse do?

a. Cancel the MRI, because people with cochlear implants can never have magnetic resonance imaging of any part of the body.

b. Tell the MRI team about the implant and give them the implant card, brand and model so they can check its conditions.

c. Remove the implant's magnet at the bedside before the patient goes to the MRI department, then replace it afterward.

d. Send the patient to the MRI department without comment, because a scan of the knee is far from the implant in the head.

Answer: b — Many implants are MR Conditional; the MRI team needs the brand and model to follow the manufacturer's conditions (b; section 36.5). Some implants allow MRI under set conditions, so an MRI is not automatically ruled out (a). Magnet removal, when needed, is surgical and not a nursing task (c). The implant's conditions apply to any MRI, not only scans of the head (d).

33. [CORE] Rosalind Okonjo, 67, reports brief spells of spinning, each lasting less than a minute, when she rolls over in bed or looks up. She has no hearing change or other symptoms. Which teaching is most appropriate?

a. "These spells are caused by fluid pressure in the inner ear, so you should cut back on salt and caffeine."

b. "You will need medicine every day to stop the spinning, and you should avoid moving your head until it settles."

c. "This is a sign of hearing loss, so an audiology appointment is the main thing needed to treat the spinning."

d. "A trained clinician can do a head-positioning treatment; until then, get up slowly and hold on to something."

Answer: d — Brief vertigo triggered by head position fits BPPV; a repositioning manoeuvre done by a trained clinician is the recommended treatment, and fall safety matters (d; section 36.6). Diet changes are taught for Ménière disease, not BPPV (a). Vestibular suppressant drugs are not routinely used, and restrictions are not recommended (b). Her symptoms come from the balance organs, and an audiology visit alone would not treat them (c).

34. [CORE] Ines Ferland, 46, is being assessed for Ménière disease. Which history best fits this diagnosis?

a. Spells of vertigo lasting a few seconds whenever she turns her head quickly, with normal hearing between spells

b. Constant unsteadiness for several months with no spinning, no change in hearing and no tinnitus at any time

c. Attacks of vertigo lasting several hours, with fluctuating hearing loss, tinnitus and fullness in one ear

d. A single episode of hearing loss in both ears on waking, with a headache and new weakness of one arm

Answer: c — Ménière disease causes repeated vertigo attacks, each 20 minutes to 12 hours long, with sensorineural hearing loss, tinnitus and ear fullness, and hearing may fluctuate (c; section 36.6). Seconds-long, position-triggered vertigo suggests BPPV (a). Constant unsteadiness without these features does not fit (b). Sudden loss in both ears with neurologic signs needs urgent assessment for other causes such as stroke (d).

35. [CORE] After a tympanoplasty, which statement by the patient shows understanding of the discharge teaching?

a. "I'll blow my nose gently each morning so that the pressure in my ear stays even."

b. "If I need to sneeze, I'll keep my mouth open, and I won't blow my nose yet."

c. "I'll clean the ear canal with a cotton swab after showering to keep it dry."

d. "I'll pull the packing out of my ear canal if it starts to feel itchy or loose."

Answer: b — Sneezing with the mouth open and not blowing the nose protect the repair (b; section 36.6, Patient Education box). Nose blowing is avoided for weeks (a). Swabs are not put in the ear (c). Packing is left in place unless the surgeon says otherwise (d).

36. [CORE] The day after a stapedectomy on the right ear, the patient cannot close the right eye fully and the right side of the mouth droops when smiling. Both were normal before surgery. What should the nurse do?

a. Report the new facial weakness to the surgeon at once, describing the baseline and the change found.

b. Record the findings and recheck facial movement at the next routine assessment in four hours.

c. Reassure the patient that facial droop is an expected short-term effect of all ear surgery.

d. Place a patch over the right eye to protect it and ask the patient to rest quietly until the weakness settles.

Answer: a — The facial nerve runs close to the middle ear, and new facial weakness after ear surgery is reported at once (a; section 36.6). Waiting four hours delays assessment (b). Facial weakness is not an expected effect (c). Eye protection may be ordered, but the change must be reported first (d).

37. [CORE] On a medical unit in Ontario, an RPN is asked to irrigate the ears of a patient with impacted wax. Employer policy allows RPNs with the required education to irrigate ears, and the RPN has completed it. The patient has diabetes and a history of a hole in the left eardrum. What should the RPN do?

a. Irrigate both ears as asked, since the RPN has the education and the employer's policy permits it.

b. Irrigate only the right ear, since the hole is on the left, and leave the left ear for the physician.

c. Hold the irrigation and report the history to the RN or prescriber, since both call for caution with irrigation.

d. Remove the wax from both ears with a small instrument instead, since this avoids water in the ear.

Answer: c — Competence includes judgment about when not to act; a perforated eardrum and diabetes call for caution with irrigation, and removal by a specialist is preferred, so the RPN holds the procedure and consults (c; section 36.6, Scope in Practice box). Policy and training do not override these cautions (a). Diabetes calls for caution in either ear (b). Manual removal with instruments is done by a trained clinician, not substituted without an order and competence (d).

38. [CORE] Bogdan Kostiuk, 61, has had constant tinnitus for 8 months. He tells the nurse, "I can't take this noise anymore. Some nights I don't see the point of anything." What should the nurse do first?

a. Suggest he play quiet background sound at night, which many people find makes the noise easier to bear.

b. Explain that tinnitus is common and usually fades over time, so he can expect it to be gone soon.

c. Refer him to audiology for a full hearing evaluation and to discuss whether hearing aids could help.

d. Ask him directly whether he has had thoughts of harming himself or ending his life, and stay with him.

Answer: d — His words suggest distress and possible suicidal thoughts; the 2026 tinnitus guideline update calls for asking directly about thoughts of self-harm, and safety comes first (d; section 36.6). Sound enrichment can help later but does not address risk (a). False reassurance dismisses his distress (b). A hearing evaluation is part of care but is not the first action here (c).

39. [RN] An audiogram shows the following. Right ear: air conduction thresholds of 45 to 50 dB HL at all frequencies; bone conduction thresholds of 10 dB HL. Left ear: air and bone conduction thresholds of 15 dB HL at all frequencies. Which interpretation is correct?

a. Sensorineural hearing loss in the right ear, because the air conduction thresholds are lower on the chart

b. Mixed hearing loss in the right ear, because both air and bone conduction thresholds are abnormal

c. Sensorineural hearing loss in both ears, because the left ear thresholds are also above 10 dB HL

d. Conductive hearing loss in the right ear, because bone conduction is normal and there is an air–bone gap

Answer: d — Normal bone conduction with poorer air conduction in the same ear (an air–bone gap) shows that the inner ear works and the problem lies in the outer or middle ear (d; section 36.4, Going Deeper box). Sensorineural loss would lower bone conduction too (a). Bone conduction of 10 dB HL is normal, so the loss is not mixed (b). Thresholds of 15 dB HL are within normal limits (c).

40. [RN] Marguerite Kowal, 52, calls the clinic. She woke this morning with muffled hearing and ringing in her left ear. She thinks it is wax and plans to use softening drops for a week before seeing anyone. Which response by the nurse is best?

a. "Softening drops are a safe first step; if your hearing has not improved after the week, book a routine appointment."

b. "Sudden hearing loss in one ear needs prompt medical care, to tell a nerve problem from wax so treatment is not delayed."

c. "Ringing with hearing loss is usually caused by stress, so try to rest and call us back if it is still there in a month."

d. "Sudden hearing loss is always permanent, so there is no need to rush; an audiology test can be done in a few months."

Answer: b — Sudden hearing loss is urgent; the guideline asks clinicians to tell sensorineural from conductive loss at the first visit, test hearing as soon as possible and offer any treatment early, within 2 weeks of onset (b; section 36.6). Waiting a week assumes wax and delays care (a). Stress is not a safe explanation (c). Recovery is possible and timing matters (d).

References

Accessible Canada Act, S.C. 2019, c. 10. https://laws-lois.justice.gc.ca/eng/acts/A-0.6/page-1.html

Eldridge v. British Columbia (Attorney General), [1997] 3 S.C.R. 624. https://www.canlii.org/en/ca/scc/doc/1997/1997canlii327/1997canlii327.html

Accord Healthcare Inc. (2024). *PrCISplatin Injection BP (cisplatin) product monograph*. https://pdf.hres.ca/dpd_pm/00075403.PDF

Alcon Inc. (2022). *UNIPURE CF (C3F8) ophthalmic gas: Patient brochure* [Labelling, U.S. Food and Drug Administration premarket approval P220030]. https://www.accessdata.fda.gov/cdrh_docs/pdf22/P220030D.pdf

Altomare, F., Kherani, A., & Lovshin, J. (2018). Retinopathy. *Canadian Journal of Diabetes, 42*(Suppl. 1), S210–S216. https://doi.org/10.1016/j.jcjd.2017.10.027

American Academy of Otolaryngology–Head and Neck Surgery Foundation. (2018a). *Earwax (cerumen impaction)*. ENT Health. https://www.enthealth.org/conditions/earwax-cerumen/

American Academy of Otolaryngology–Head and Neck Surgery Foundation. (2018b). *Swimmer's ear (otitis externa)*. ENT Health. https://www.enthealth.org/conditions/swimmers-ear/

American Academy of Otolaryngology–Head and Neck Surgery Foundation. (2026, October 12). *Living with ringing in your ears? Updated guideline supports a personalized, evidence-based approach to tinnitus* [News release]. https://www.entnet.org/resource/living-with-ringing-in-your-ears-updated-guideline-supports-a-personalized-evidence-based-approach-to-tinnitus/

American Academy of Otolaryngology–Head and Neck Surgery Foundation. (n.d.). *Sudden hearing loss: Talking points for physicians*. https://www.entnet.org/sites/default/files/SHL-talking-points-physicians.pdf

Apotex Inc. (2024). *APO-BRIMONIDINE (brimonidine tartrate ophthalmic solution 0.2% w/v)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00074217.PDF

Arora, M. A., Xu, J., Kokorelias, K. M., Koerber, R., Krishnapillai, H., & Sinha, S. K. (2026). Barriers and facilitators in using personal hearing amplifiers from the perspective of healthcare providers. *Canadian Geriatrics Journal, 29*(3), 173–179. https://doi.org/10.5770/cgj.29.932

Banks, R. (2020, September 21). *Masked communication*. Canadian Hearing Services. https://www.chs.ca/page/masked-communication

Basilious, A., & Buys, Y. M. (2015). A woman with a family history of glaucoma. *CMAJ, 187*(12), 899–900. https://doi.org/10.1503/cmaj.140685

Basura, G. J., Adams, M. E., Monfared, A., Schwartz, S. R., Antonelli, P. J., Burkard, R., Bush, M. L., Bykowski, J., Colandrea, M., Derebery, J., Kelly, E. A., Kerber, K. A., Koopman, C. F., Kuch, A. A., Marcolini, E., McKinnon, B. J., Ruckenstein, M. J., Valenzuela, C. V., Vosooney, A., . . . Buchanan, E. M. (2020). Clinical practice guideline: Ménière's disease. *Otolaryngology–Head and Neck Surgery, 162*(2_suppl), S1–S55. https://doi.org/10.1177/0194599820909438

Bausch & Lomb Inc. (2022). *BL LATANOPROST (latanoprost ophthalmic solution 50 mcg/mL)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00066572.PDF

Baxter Corporation. (2019). *Gentamicin(e) (gentamicin as sulfate in 0.9% sodium chloride injection) product monograph*. https://pdf.hres.ca/dpd_pm/00053131.PDF

Beyea, J. A. (n.d.). *Post operative instructions – Tympanoplasty / mastoidectomy* [Patient handout]. Hotel Dieu Hospital; Queen's University Department of Surgery. https://surgery.queensu.ca/sites/surgery/files/inline-files/Post%20Operative%20Instructions%20-%20Tympanoplasty%2C%20Mastoidectomy.pdf

Bhattacharyya, N., Gubbels, S. P., Schwartz, S. R., Edlow, J. A., El-Kashlan, H., Fife, T., Holmberg, J. M., Mahoney, K., Hollingsworth, D. B., Roberts, R., Seidman, M. D., Steiner, R. W. P., Tsai Do, B., Voelker, C. C. J., Waguespack, R. W., & Corrigan, M. D. (2017). Clinical practice guideline: Benign paroxysmal positional vertigo (update). *Otolaryngology–Head and Neck Surgery, 156*(3_suppl), S1–S47. https://doi.org/10.1177/0194599816689667

Canadian Institute for Health Information. (2026). *Wait times for cataract surgery (percentage meeting benchmark)* [Indicator]. https://www.cihi.ca/en/indicators/wait-times-for-cataract-surgery-percentage-meeting-benchmark

Chandrasekhar, S. S., Tsai Do, B. S., Schwartz, S. R., Bontempo, L. J., Faucett, E. A., Finestone, S. A., Hollingsworth, D. B., Kelley, D. M., Kmucha, S. T., Moonis, G., Poling, G. L., Roberts, J. K., Stachler, R. J., Zeitler, D. M., Corrigan, M. D., Nnacheta, L. C., & Satterfield, L. (2019). Clinical practice guideline: Sudden hearing loss (update). *Otolaryngology–Head and Neck Surgery, 161*(1_suppl), S1–S45. https://doi.org/10.1177/0194599819859885

Chen, S. P., Woreta, F., & Chang, D. F. (2025). Cataracts: A review. *JAMA, 333*(23), 2093. https://doi.org/10.1001/jama.2025.1597

CIUSSS du Nord-de-l'Île-de-Montréal. (2020). *Taking care of yourself after cataract surgery* [Patient information sheet]. https://cdn.ciusssnordmtl.ca/Fichiers/07Usagers_Visiteurs/Fiches_usagers/NIM-DSI-FicheInfoPatient-Cataracte-PostOp-Ang-Fev20-V3.pdf

CNIB. (n.d.-a). *Guiding someone*. Retrieved October 27, 2026, from https://cnib.ca/en/node/342

CNIB. (n.d.-b). *Step-by-step: A how-to manual for guiding someone who is blind or partially sighted*. Retrieved October 27, 2026, from https://cnib.ca/sites/default/files/2022-01/Step-By-Step%20Guide_ENG_0.pdf

College of Nurses of Ontario. (2025). *Scope of practice* [Practice standard]. https://cno.org/Assets/CNO/Documents/Standard-and-Learning/Practice-Standards/49041-scope-of-practice.pdf

College of Nurses of Ontario. (2026). *Council approves changes to Scope of Practice and Medication standards*. https://www.cno.org/news/council-approves-changes-scope-of-practice-and-medication-standards

Crowshoe, L., Dannenbaum, D., Green, M., Henderson, R., Naqshbandi Hayward, M., & Toth, E. (2018). Type 2 diabetes and Indigenous peoples. *Canadian Journal of Diabetes, 42*(Suppl. 1), S296–S306. https://doi.org/10.1016/j.jcjd.2017.10.022

Eiselen, C., Long, M., & Chong, E. W. (2026). Age-related macular degeneration: Updates for general practitioners. *Australian Journal of General Practice, 55*(7), 455–460. https://www1.racgp.org.au/getattachment/122d8dd7-d5ee-4212-adf6-6930890b1a1d/Age-related-macular-degeneration.aspx

Feder, K., Michaud, D., Ramage-Morin, P., McNamee, J., & Beauregard, Y. (2015). Prevalence of hearing loss among Canadians aged 20 to 79: Audiometric results from the 2012/2013 Canadian Health Measures Survey. *Health Reports, 26*(7), 18–25. https://www150.statcan.gc.ca/n1/pub/82-003-x/2015007/article/14206-eng.htm

Fighting Blindness Canada. (2021, May 11). *New report reveals vision loss costs Canada almost $33 billion annually* [News release]. https://www.fightingblindness.ca/news/new-report-reveals-vision-loss-costs-canada-almost-33-billion-annually/

Gedde, S. J., Chopra, V., Vinod, K., Bowden, E. C., Kolomeyer, N. N., Challa, P., & Budenz, D. L. (2026). Primary angle-closure disease Preferred Practice Pattern®. *Ophthalmology, 133*(4), P153–P201. https://doi.org/10.1016/j.ophtha.2025.12.030

Gelston, C. D., & Deitz, G. A. (2020). Eye emergencies. *American Family Physician, 102*(9), 539–545. https://www.aafp.org/pubs/afp/issues/2020/1101/p539.html

Government of Ontario. (2026, September 21). *How to make customer service accessible*. https://www.ontario.ca/page/how-make-customer-service-accessible

Kim, J., & Driver, D. D. (2015). Teleophthalmology for First Nations clients at risk of diabetic retinopathy: A mixed methods evaluation. *JMIR Medical Informatics, 3*(1), Article e10. https://doi.org/10.2196/medinform.3872

Lopez-Escamez, J. A., Carey, J., Chung, W.-H., Goebel, J. A., Magnusson, M., Mandalà, M., Newman-Toker, D. E., Strupp, M., Suzuki, M., Trabalzini, F., & Bisdorff, A. (2015). Diagnostic criteria for Menière's disease. *Journal of Vestibular Research, 25*(1), 1–7. https://doi.org/10.3233/VES-150549

Milchard, A. (n.d.). *Pure tone audiometry* [Training module: Basic hearing assessment]. Audiology Department, Royal South Hants Hospital. https://www.bradfordvts.co.uk/wp-content/onlineresources/clinical-knowledge/ent/audiometry.doc

National Eye Institute. (2022). *How the eyes work*. https://www.nei.nih.gov/eye-health-information/healthy-vision/how-eyes-work

National Institute on Deafness and Other Communication Disorders. (2022). *How do we hear?* https://www.nidcd.nih.gov/health/how-do-we-hear

National Institute on Deafness and Other Communication Disorders. (2024). *Cochlear implants*. https://www.nidcd.nih.gov/health/cochlear-implants

Nova Scotia Health. (2026). *After your retina surgery* [Patient & family guide WW85-0463]. https://www.nshealth.ca/sites/default/files/documents/0463-2026.03.23.pdf

Perceptual Neuroscience Laboratory. (n.d.). *Charles Bonnet syndrome*. York University. Retrieved October 27, 2026, from https://www.yorku.ca/health/lab/steeves/charles-bonnet-syndrome/

Pharmascience Inc. (2018). *Asaphen and Asaphen E.C. (acetylsalicylic acid) product monograph*. https://pdf.hres.ca/dpd_pm/00053978.PDF

Pirozzo, S., Papinczak, T., & Glasziou, P. (2003). Whispered voice test for screening for hearing impairment in adults and children: Systematic review. *BMJ, 327*(7421), 967. https://doi.org/10.1136/bmj.327.7421.967

Ramage-Morin, P. L., Banks, R., Pineault, D., & Atrach, M. (2019). Unperceived hearing loss among Canadians aged 40 to 79. *Health Reports, 30*(8), 11–20. https://doi.org/10.25318/82-003-x201900800002-eng

Royal Berkshire NHS Foundation Trust. (2022). *Stapedectomy (middle ear repair)* [Patient information leaflet]. https://royalberkshire.nhs.uk/media/jakpjmqn/stapedectomy_nov22.pdf

Royal Victorian Eye and Ear Hospital. (2017). *Acute primary angle closure (APAC) clinical practice guideline*. https://eyeandear.org.au/wp-content/uploads/2021/11/Acute-Primary-Angle-Closure-APAC-Clinical-Practice-Guideline.pdf

Sandoz Canada Inc. (2023). *T-LO (timolol maleate ophthalmic solution) and TIMOLOL MALEATE-EX (timolol ophthalmic gel-forming solution)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00073920.PDF

Sandoz Canada Inc. (2026). *Sandoz Dorzolamide/Timolol (dorzolamide hydrochloride and timolol maleate ophthalmic solution)* [Product monograph]. https://pdf.hres.ca/dpd_pm/00086348.PDF

Sexton, M. (2022, February 7). *Writing about people with hearing loss: A primer on terminology*. Our Languages blog, Language Portal of Canada. https://www.noslangues-ourlanguages.gc.ca/en/blogue-blog/perte-auditive-terminologie-hearing-loss-terminology-eng

Southlake Regional Health Centre. (n.d.). *Deaf, deafened and hard of hearing clients – Support for* [Policy and procedure]. https://southlake.ca/wp-content/uploads/2022/10/Deaf-Deafened-and-Hard-of-Hearing-Clients-%E2%80%93-Support-for55.pdf

Statistics Canada. (2021). *Hearing health of Canadian adults* [Infographic]. https://www150.statcan.gc.ca/n1/pub/11-627-m/11-627-m2021077-eng.htm

Statistics Canada. (2025, January 3). *Infographic: Seeing disabilities, 2022* (Catalogue no. 11-627-M2025002). https://www.statcan.gc.ca/o1/en/app/7590-infographic-seeing-disabilities-2022

Steinberg, A. G., Barnett, S., Meador, H. E., Wiggins, E. A., & Zazove, P. (2006). Health care system accessibility: Experiences and perceptions of deaf people. *Journal of General Internal Medicine, 21*(3), 260–266. https://doi.org/10.1111/j.1525-1497.2006.00340.x

U.S. Food and Drug Administration. (2021). *Cochlear implants and MRI safety*. https://www.fda.gov/medical-devices/cochlear-implants/cochlear-implants-and-mri-safety

U.S. Preventive Services Task Force. (2022). *Impaired visual acuity in older adults: Screening* [Final recommendation statement]. https://www.uspreventiveservicestaskforce.org/uspstf/recommendation/impaired-visual-acuity-screening-older-adults

University Hospitals Sussex NHS Foundation Trust. (2026). *How to read your hearing test results* [Patient leaflet]. https://www.uhsussex.nhs.uk/wp-content/uploads/2026/05/How-to-Read-Your-hearing-Test-Results.pdf

Wipperman, J. L., & Dorsch, J. N. (2013). Evaluation and management of corneal abrasions. *American Family Physician, 87*(2), 114–120. https://www.aafp.org/pubs/afp/issues/2013/0115/p114.html

WorkSafeNB. (2024). *Emergency showers and eyewash stations*. https://www.worksafenb.ca/media/2734/emergencyshowers-and-eyewashstations.pdf

World Health Organization. (2026, March 3). *Deafness and hearing loss* [Fact sheet]. https://www.who.int/news-room/fact-sheets/detail/deafness-and-hearing-loss

A Adult Canadian SI Reference Laboratory Intervals

Canadian clinical laboratories report hematologic, biochemical, and endocrine analytes using Système International (SI) units (**mmol/L**, **µmol/L**, **g/L**, and **× 10^9/L**) harmonized with the Canadian Society of Clinical Chemists (CSCC) and Medical Council of Canada reference intervals. Always verify patient results against the local hospital laboratory's specific assay reference range.

Analyte	Specimen	Adult SI Reference Interval	Critical / Escalation Threshold	Primary Chapters
Sodium (Na^+)	Serum / Plasma	**135–145 mmol/L**	< 120 or > 160 mmol/L	Ch. 3, 27, 30
Potassium (K^+)	Serum / Plasma	**3.5–5.0 mmol/L**	< 2.8 or > 6.0 mmol/L	Ch. 3, 16, 27
Chloride (Cl^-)	Serum / Plasma	**98–107 mmol/L**	< 80 or > 115 mmol/L	Ch. 3
Bicarbonate (HCO_3^- / Total CO_2)	Serum / Venous	**22–26 mmol/L**	< 15 or > 40 mmol/L	Ch. 3, 15, 27
Calcium, Total (Ca^{2+})	Serum	**2.15–2.55 mmol/L**	< 1.75 or > 3.25 mmol/L	Ch. 3, 23, 27
Calcium, Ionized	Whole Blood	**1.15–1.30 mmol/L**	< 0.80 or > 1.60 mmol/L	Ch. 3, 20, 23
Magnesium (Mg^{2+})	Serum	**0.70–1.05 mmol/L**	< 0.50 or > 2.00 mmol/L	Ch. 3, 16
Phosphate (PO_4^{3-})	Serum	**0.80–1.45 mmol/L**	< 0.32 mmol/L	Ch. 3, 27
Glucose (Fasting)	Plasma	**4.0–6.0 mmol/L**	< 2.8 or > 25.0 mmol/L	Ch. 22
HbA1c	Whole Blood	**4.5%–5.9% (Target ≤ 7.0%)**	—	Ch. 22
Urea (BUN equivalent)	Serum / Plasma	**2.5–7.1 mmol/L**	> 35.0 mmol/L	Ch. 27
Creatinine	Serum / Plasma	**50–110 µmol/L**	> 400 µmol/L (acute)	Ch. 27
eGFR	Calculated	**≥ 90 mL/min/1.73 m²**	< 15 mL/min/1.73 m² (G5)	Ch. 27
Lactate (Arterial / Venous)	Plasma	**0.5–2.0 mmol/L**	≥ 4.0 mmol/L (septic shock)	Ch. 4, 6
Serum Osmolality	Serum	**275–295 mOsm/kg**	< 250 or > 325 mOsm/kg	Ch. 3, 22, 30
Hemoglobin (Hb)	Whole Blood	**120–160 g/L (F) / 135–175 g/L (M)**	< 70 g/L (transfusion threshold)	Ch. 20, 24
Hematocrit (Hct)	Whole Blood	**0.36–0.46 L/L (F) / 0.40–0.50 L/L (M)**	< 0.21 L/L	Ch. 20
White Blood Cell Count (WBC)	Whole Blood	**4.0–11.0 × 10^9/L**	< 1.5 or > 30.0 × 10^9/L	Ch. 4, 9, 20
Absolute Neutrophil Count (ANC)	Whole Blood	**2.0–7.5 × 10^9/L**	< 0.5 × 10^9/L (febrile neutropenia)	Ch. 9, 20
Platelets	Whole Blood	**150–400 × 10^9/L**	< 20 × 10^9/L or > 1,000 × 10^9/L	Ch. 20, 26
INR (International Normalized Ratio)	Citrated Plasma	**0.9–1.2 (Warfarin target 2.0–3.0)**	> 4.5 (major bleeding risk)	Ch. 16, 19, 20
aPTT	Citrated Plasma	**25–35 seconds**	> 100 seconds	Ch. 15, 19, 20
D-Dimer	Plasma	**< 500 µg/L FEU**	Age-adjusted cutoff over 50 yr	Ch. 15, 19

Analyte	Specimen	Adult SI Reference Interval	Critical / Escalation Threshold	Primary Chapters
Troponin I / T (High-Sensitivity)	Plasma	**< 99th percentile URL (ng/L)**	Dynamic rise/fall (ACS)	Ch. 17
BNP / NT-proBNP	Plasma	**BNP < 100 pg/mL; NT-proBNP < 300 pg/mL**	Acute decompensated HF	Ch. 18
Total Bilirubin	Serum	**3–21 µmol/L**	> 250 µmol/L	Ch. 20, 26
ALT / AST	Serum	**ALT 7–40 U/L; AST 10–40 U/L**	> 1,000 U/L (acute hepatic injury)	Ch. 26
Albumin	Serum	**35–50 g/L**	< 20 g/L	Ch. 24, 26, 27
Ammonia (NH_3)	Plasma	**15–45 µmol/L**	> 100 µmol/L (encephalopathy)	Ch. 26
Lipase	Serum	**10–140 U/L**	> 3 × ULN (acute pancreatitis)	Ch. 26
TSH (Thyroid-Stimulating Hormone)	Serum	**0.40–4.50 mIU/L**	< 0.01 or > 20.0 mIU/L	Ch. 23
Uric Acid (Urate)	Serum	**180–420 µmol/L (Target < 360 µmol/L)**	> 540 µmol/L	Ch. 34
Arterial pH	Arterial Blood	**7.35–7.45**	< 7.20 or > 7.60	Ch. 3, 15
$PaCO_2$	Arterial Blood	**35–45 mmHg**	< 20 or > 65 mmHg	Ch. 3, 12, 15
PaO_2	Arterial Blood	**80–100 mmHg**	< 60 mmHg (hypoxemic failure)	Ch. 12, 15

BACK MATTER — CUMULATIVE LEXICON *Appendix B*

B Cumulative Glossary of Medical-Surgical Terms (1651 Terms)

2SLGBTQI+: An umbrella term for Two-Spirit, lesbian, gay, bisexual, transgender, queer and intersex people and others who are sexually and gender diverse; "2S" is placed first in recognition that Two-Spirit people formed the first of these communities. *(Ch. 2)*

4AT: a brief delirium screening test, usually taking less than two minutes, that looks at alertness, orientation, attention and acute change. *(Ch. 8)*

5-alpha reductase inhibitor (5-ARI): a drug that shrinks the prostate over months and lowers the PSA level by about half. *(Ch. 28)*

A1C: the percentage of hemoglobin with glucose attached, reflecting average glucose over the previous 8 to 12 weeks *(Ch. 22)*

abdominal aortic aneurysm (AAA): a weak area in the wall of the abdominal aorta that balloons outward. *(Ch. 19)*

abdominoperineal resection: surgery that removes the lower rectum and anal sphincter for a tumour near the anus, leaving a permanent colostomy. *(Ch. 25)*

abnormal extension: A motor response in which the arm straightens at the elbow in response to a stimulus; it ranks lower on the GCS than abnormal flexion. *(Ch. 30)*

abnormal flexion: A slow, stereotyped motor response with the arm bent across the chest, forearm turning, thumb clenched and leg extended; a sign of severe brain dysfunction. *(Ch. 30)*

abnormal uterine bleeding: Uterine bleeding that differs from a person's usual menstrual pattern in amount, duration, frequency or regularity, or that occurs between periods. *(Ch. 29)*

abscess: A walled-off collection of pus in the skin or the tissue beneath it, treated mainly by incision and drainage. *(Ch. 35)*

absolute neutrophil count (ANC): The number of neutrophils per litre of blood, reported in × 10^9/L. *(Ch. 9)*

acanthosis nigricans: thick, velvety, darker skin in body folds such as the neck and armpits; a sign of insulin resistance *(Ch. 22)*

acidemia: A blood pH below the normal range. *(Ch. 3)*

acidosis: A process that adds acid or removes base, tending to lower pH. *(Ch. 3)*

acquired immunodeficiency syndrome (AIDS) / advanced HIV disease: the most advanced stage of HIV infection, defined for surveillance as a CD4 count below 200 cells/µL, a CD4 percentage below 14%, or an AIDS-defining opportunistic illness. *(Ch. 21)*

acral melanoma: A type of melanoma on the palms, soles or nails that is not linked to ultraviolet exposure; the most common type in people with darker skin. *(Ch. 35)*

acromegaly: a condition caused by excess growth hormone in adults, usually from a pituitary adenoma, with enlarged hands, feet and facial features. *(Ch. 23)*

action plan: A written, personalized guide that tells a person with heart failure which signs to watch for and what to do, often organized in green, yellow and red zones. *(Ch. 18)*

active offer: Making services in French visible and available from the first contact so that Francophone patients do not have to ask for them. *(Ch. 1)*

active surveillance: planned monitoring of a low-risk prostate cancer with PSA tests, examinations and biopsies, with treatment offered if the cancer changes. *(Ch. 28)*

acute angle-closure glaucoma: An eye emergency in which the drainage angle closes and intraocular pressure rises quickly, causing eye pain, headache, halos, blurred vision, nausea and vomiting. *(Ch. 36)*

acute aortic syndrome: A life-threatening injury to the wall of the aorta, such as aortic dissection, that causes sudden severe pain. *(Ch. 19)*

acute chest syndrome: a new lung infiltrate with fever or respiratory symptoms in a person with sickle cell disease; an emergency *(Ch. 20)*

acute cholecystitis: Inflammation of the gallbladder, usually because a stone is stuck in its neck; the pain persists for longer than biliary colic and is often accompanied by fever and right upper quadrant tenderness. *(Ch. 26)*

acute colonic pseudo-obstruction: marked widening of the colon without a mechanical blockage, usually in older, seriously ill or postoperative patients. *(Ch. 25)*

acute coronary syndrome (ACS): a sudden fall in blood flow to the heart muscle, usually from plaque rupture or erosion with thrombus; includes unstable angina, NSTEMI and STEMI. *(Ch. 17)*

acute decompensated heart failure (ADHF): Worsening of known heart failure that needs urgent treatment, usually in hospital. *(Ch. 18)*

acute exacerbation of COPD: A sudden flare-up in which symptoms such as breathlessness, sputum volume or sputum purulence get worse over a period of days, 14 days at most. *(Ch. 14)*

acute heart failure: A sudden or gradual change in heart failure symptoms and signs that calls for urgent treatment. *(Ch. 18)*

acute hemolytic transfusion reaction: rapid destruction of transfused red cells, most often from ABO incompatibility, causing fever, pain, hypotension and dark urine. *(Ch. 20)*

acute HIV infection: the first weeks after HIV enters the body, when the viral load is very high, the person is highly infectious and a flu-like illness may occur. *(Ch. 21)*

acute inflammation: A short-lived inflammatory response, dominated by neutrophils, that removes the cause of injury and then resolves. *(Ch. 4)*

acute kidney injury (AKI): a sudden fall in kidney function over hours to days, defined by KDIGO by a rise in creatinine or a fall in urine output *(Ch. 27)*

acute limb ischemia: sudden loss of blood flow to a limb that threatens its survival and needs emergency treatment. *(Ch. 19)*

acute liver failure (ALF): A sudden, severe loss of liver function in a person without cirrhosis, with an INR of 1.5 or higher and any degree of encephalopathy, arising within 26 weeks of the start of the illness. *(Ch. 26)*

acute pain: pain of recent onset, usually from injury, illness, surgery or trauma, that settles as the cause heals *(Ch. 5)*

acute pancreatitis: Acute inflammation of the pancreas, diagnosed when two of three features are present: typical pain, lipase or amylase at least three times the upper limit of normal, and typical imaging findings. *(Ch. 26)*

acute pulmonary edema: An emergency in which fluid floods the alveoli, causing severe breathlessness and hypoxemia. *(Ch. 18)*

acute respiratory distress syndrome: A sudden, widespread inflammatory injury to both lungs that causes noncardiogenic pulmonary edema and hypoxemic respiratory failure within 1 week of a trigger. *(Ch. 15)*

acute respiratory failure: Failure of the lungs to keep blood oxygen and carbon dioxide within safe limits, developing over minutes to days. *(Ch. 15)*

acute severe ulcerative colitis: A flare of UC with frequent bloody stools and signs of systemic illness that needs hospital admission and IV corticosteroids. *(Ch. 25)*

acute tubular injury: damage to the kidney tubule cells from prolonged low blood flow, sepsis or toxins; a common form of intrinsic AKI in hospital *(Ch. 27)*

adaptive immunity: the slower, antigen-specific part of the immune system, carried out by B cells and T cells, that develops memory after exposure. *(Ch. 21)*

Addison disease: primary adrenal insufficiency, in which the adrenal cortex is damaged, most often by autoimmune disease, so cortisol and usually aldosterone are low. *(Ch. 23)*

additional precautions: Infection control measures used on top of routine practices for certain organisms or clinical presentations; contact, droplet and airborne precautions. *(Ch. 4)*

adenoma: a type of polyp in the colon or rectum that can become cancer over time. *(Ch. 25)*

adhesions: bands of scar tissue inside the abdomen, usually after surgery or inflammation; the most common cause of small bowel obstruction. *(Ch. 25)*

adjuvant analgesic: a drug whose main use is not pain relief but which relieves some types of pain, especially neuropathic pain *(Ch. 5)*

adjuvant therapy: treatment given after surgery to destroy cancer cells that may remain. *(Ch. 9)*

adrenal cortex: the outer part of the adrenal gland, which makes the steroid hormones cortisol and aldosterone. *(Ch. 23)*

adrenal crisis: a life-threatening emergency in which cortisol supply cannot meet the body's needs, causing hypotension, volume depletion, vomiting and confusion; treated at once with parenteral hydrocortisone and isotonic saline. *(Ch. 23)*

adrenal insufficiency: a condition in which the adrenal glands do not supply enough cortisol, with or without enough aldosterone. *(Ch. 23)*

adrenal medulla: the inner part of the adrenal gland, which releases the catecholamines epinephrine and norepinephrine. *(Ch. 23)*

advance care planning: The ongoing process of reflecting on values and wishes for future care, sharing them with family and the care team, and choosing a substitute decision-maker. *(Ch. 32)*

advance care planning (ACP): A voluntary process in which a capable person confirms or chooses a substitute decision-maker and shares wishes, values and beliefs about future care; in Ontario it is not consent. *(Ch. 10)*

adverse event following immunization (AEFI): any unwanted or unexpected health effect that follows a vaccine, whether or not the vaccine caused it. *(Ch. 21)*

afterload: the resistance the ventricle must pump against to eject blood. *(Ch. 6)*

age-adjusted D-dimer cut-off: A D-dimer threshold for patients over 50, calculated as age × 10 mcg/L, that reduces false-positive results in older adults. *(Ch. 15)*

age-related macular degeneration (AMD): Age-related disease of the macula that causes loss of central vision; it occurs in a dry (atrophic) form and a wet (neovascular) form. *(Ch. 36)*

ageism: stereotyping, prejudice or discrimination against people because of their age. *(Ch. 8)*

agent: Under PHIPA, a person, such as a nurse employed by a hospital, who handles personal health information on behalf of a health information custodian. *(Ch. 1)*

agranulocytosis: A severe drop in neutrophils, a rare but life-threatening adverse effect of antithyroid drugs. *(Ch. 23)*

air leak: Air entering a chest drainage system from the lung or through a loose connection, seen as bubbling in the water seal chamber. *(Ch. 15)*

air trapping: Air left behind in the lungs at the end of each breath because narrowed or unsupported small airways close early during exhalation. *(Ch. 14)*

airborne infection isolation room (AIIR): A single room designed and ventilated (negative pressure) to keep airborne organisms from spreading beyond it. *(Ch. 4)*

airborne precautions: Precautions for organisms carried on small particles that stay suspended in the air; they require a negative pressure room with the door closed and a fit-tested N95 respirator. *(Ch. 4)*

airway hyperresponsiveness: A tendency of the airways to narrow quickly and strongly in response to stimuli that barely affect other people. *(Ch. 14)*

airway resistance: how much the airways oppose airflow; narrowing from spasm, swelling or secretions raises it. *(Ch. 12)*

alarm fatigue: Desensitization of clinicians exposed to many false or non-actionable alarms, leading to slower or missed responses. *(Ch. 16)*

alarm features: symptoms such as dysphagia, unplanned weight loss, bleeding, anemia or persistent vomiting that suggest a serious cause and call for prompt assessment. *(Ch. 24)*

albumin: A plasma protein, also given as a colloid solution made from pooled human plasma, that raises plasma oncotic pressure and holds fluid in the blood vessels. *(Ch. 3)*

albuminuria: albumin in the urine, an early marker of kidney damage; classified by KDIGO as A1, A2 or A3 *(Ch. 27)*

alcohol withdrawal: the signs and symptoms of an overexcited nervous system that follow stopping or sharply reducing heavy, prolonged alcohol use. *(Ch. 11)*

alcohol-associated hepatitis: The acute inflammatory stage of alcohol-related liver disease, typically with new jaundice in a person who has been drinking heavily. *(Ch. 26)*

alcohol-related liver disease (ALD): Liver injury caused by drinking alcohol over time, ranging from fatty liver through alcohol-associated hepatitis and fibrosis to cirrhosis and liver cancer. *(Ch. 26)*

alcoholic hallucinosis: hallucinations during alcohol withdrawal in a person who otherwise remains oriented. *(Ch. 11)*

aldosterone: A hormone from the adrenal cortex that causes the kidneys to keep sodium, and with it water. *(Ch. 3)*

alkalemia: A blood pH above the normal range. *(Ch. 3)*

alkalosis: A process that removes acid or adds base, tending to raise pH. *(Ch. 3)*

allergy: a hypersensitivity reaction to a substance that is harmless to most people, such as a food, pollen or drug. *(Ch. 21)*

allergy (drug): an immune reaction to a drug, such as hives, swelling, wheezing or a severe skin reaction. *(Ch. 4)*

allodynia: pain from a stimulus that does not normally cause pain, such as light touch *(Ch. 5)*

alpha-1 antitrypsin deficiency: An inherited lack of a protein that protects the lungs from damage; a genetic risk factor for COPD. *(Ch. 14)*

alpha-blocker: a drug that relaxes smooth muscle in the prostate and bladder neck, improving urine flow; can cause dizziness and low blood pressure. *(Ch. 28)*

alternate level of care (ALC): A designation for a patient who remains in a hospital bed but no longer needs acute care and is waiting for a more suitable setting. *(Ch. 1)*

alveolar–capillary membrane: the thin barrier between alveolar air and capillary blood across which oxygen and carbon dioxide diffuse. *(Ch. 12)*

alveoli: the tiny air sacs at the ends of the smallest airways, where gas exchange takes place. *(Ch. 12)*

ambulatory blood pressure monitoring (ABPM): Blood pressure measured automatically every 20 to 30 minutes over a day and night by a device the person wears. *(Ch. 19)*

ambulatory surgery: Surgery after which the patient goes home on the same day; also called day surgery or same-day surgery. *(Ch. 7)*

American Sign Language (ASL): A full signed language with its own grammar, used by many Deaf people in English-speaking Canada; recognized in the Accessible Canada Act as one of the primary languages of communication for deaf persons in Canada. *(Ch. 36)*

amputation: The removal of all or part of a limb. *(Ch. 33)*

amyotrophic lateral sclerosis (ALS): A progressive disease in which the motor nerve cells of the brain and spinal cord degenerate, causing weakness, muscle wasting and, eventually, respiratory failure. *(Ch. 32)*

anaphylaxis: a severe, potentially life-threatening allergic reaction with sudden onset, usually involving two or more body systems. *(Ch. 6)*

anastomosis: a surgical join between two ends of bowel after a segment is removed. *(Ch. 25)*

anastomotic leak: escape of stomach or intestinal contents through a surgical staple or suture line. *(Ch. 24)*

androgen deprivation therapy (ADT): treatment that lowers testosterone to slow the growth of prostate cancer. *(Ch. 28)*

anemia: a hemoglobin below the reference range for the person's age and sex; a sign with an underlying cause *(Ch. 20)*

anemia of inflammation: anemia caused by inflammatory signals that block iron absorption and trap iron in storage cells *(Ch. 20)*

anesthesia assistant: A formally designated team member with specific training in anesthesia assistance who carries out tasks approved by the department of anesthesia and the facility. *(Ch. 7)*

anginal equivalent: a symptom other than chest pain, such as breathlessness or unusual fatigue on exertion, that reflects myocardial ischemia. *(Ch. 17)*

angioedema: Swelling of the lips, tongue, face or throat; an emergency that can follow ACE inhibitors, ARBs or an ARNI. *(Ch. 18)*

angiotensin receptor–neprilysin inhibitor (ARNI): A drug combining neprilysin inhibition with angiotensin II receptor blockade; sacubitril/valsartan. *(Ch. 18)*

anion gap: A calculated value (sodium minus chloride and bicarbonate, with or without potassium) that estimates unmeasured anions; a high gap suggests added acid. *(Ch. 3)*

ankle-brachial index (ABI): the ratio of ankle to arm systolic pressure; the CCS states that a value below 0.9 suggests PAD. *(Ch. 19)*

anogenital warts: Skin growths in the genital or anal area caused mainly by HPV types 6 and 11. *(Ch. 29)*

anti-Black racism: The discrimination, stereotyping and prejudice that people of African descent face, built into the policies, practices and institutions of Canadian society and often unseen because it is so normal. *(Ch. 2)*

anti-CCP antibodies: Antibodies to cyclic citrullinated peptides; a blood test that is more specific for rheumatoid arthritis than rheumatoid factor, although a negative result does not rule the disease out. *(Ch. 34)*

anti-racism: Active practice that names racism, including racism built into systems, and works to reduce the power differences that disadvantage racialized people. *(Ch. 2)*

anti-VEGF therapy: Medicines that block vascular endothelial growth factor, injected into the eye to treat wet AMD and diabetic eye disease. *(Ch. 36)*

antibiotic-resistant organism (ARO): a microorganism that has changed so that one or more antibiotics that once treated it no longer work well against it. *(Ch. 4)*

antibody: a protein (immunoglobulin) made by plasma cells that binds one specific antigen. *(Ch. 21)*

anticholinergic burden: The cumulative effect of all the drugs a person takes that have anticholinergic properties. *(Ch. 8)*

anticipatory grief: Grief that begins before a death, as the patient and family face coming losses. *(Ch. 10)*

anticipatory medications: Drugs ordered in advance for expected end-of-life symptoms so that relief can be given at any hour. *(Ch. 10)*

anticoagulant: a drug that slows clot formation and stops existing clots from growing. *(Ch. 19)*

antidiuretic hormone (ADH): A hormone, also called vasopressin, released from the posterior pituitary when osmolality rises or blood volume falls; it makes the kidneys return more water to the blood. *(Ch. 3)*

antifibrotic: A drug, such as nintedanib or pirfenidone, that slows the loss of lung function in pulmonary fibrosis without reversing scarring. *(Ch. 14)*

antigen: any molecule that the immune system can recognize as a target and respond to. *(Ch. 21)*

antimicrobial stewardship: coordinated actions to use antimicrobials only when needed, with the right drug, dose, route and duration, to improve outcomes and limit harm and resistance. *(Ch. 4)*

antiplatelet therapy: Medicines, such as ASA or clopidogrel, that keep platelets from clumping to form clots. *(Ch. 31)*

antiretroviral therapy (ART): a combination of drugs from different classes that stops HIV from multiplying. *(Ch. 21)*

antiseizure medication: A medicine used to prevent or stop seizures, such as levetiracetam, phenytoin or lacosamide. *(Ch. 30)*

antiviral: a drug that stops a virus from multiplying, such as oseltamivir for influenza or nirmatrelvir–ritonavir for COVID-19. *(Ch. 13)*

aortic dissection: A tear in the inner lining of the aorta that lets blood track between the layers of its wall. *(Ch. 19)*

aortic stenosis: Narrowing of the aortic valve that obstructs blood flow out of the left ventricle. *(Ch. 18)*

aphasia: A disorder of language from damage to the brain's language areas that can affect speaking, understanding, reading and writing. *(Ch. 30)*

aplastic anemia: failure of the bone marrow to produce enough red cells, white cells and platelets *(Ch. 20)*

apnea: A pause in breathing. *(Ch. 10)*

apolipoprotein B (ApoB): the protein on each atherogenic lipoprotein particle; its level, in g/L, reflects the number of particles that can enter the artery wall. *(Ch. 17)*

apoptosis: orderly, programmed cell death that removes damaged or unneeded cells. *(Ch. 9)*

appendicitis: Inflammation of the appendix, usually after its opening is blocked. *(Ch. 25)*

appendicolith: A hard stone of stool in the appendix that raises the risk of perforation and of failure of antibiotic treatment. *(Ch. 25)*

aqueous humour: The clear fluid made by the ciliary processes that fills the front of the eye and drains through the drainage angle and the uveoscleral route. *(Ch. 36)*

areflexia: Absence of deep tendon reflexes. *(Ch. 32)*

arginine vasopressin deficiency (AVP-D): the current name for central diabetes insipidus, in which too little vasopressin is released, so large volumes of dilute urine are passed. *(Ch. 23)*

arginine vasopressin resistance (AVP-R): the current name for nephrogenic diabetes insipidus, in which the kidneys do not respond to vasopressin. *(Ch. 23)*

arterial blood gas (ABG): A test of arterial blood that measures pH, $PaCO_2$, PaO_2 and bicarbonate. *(Ch. 3)*

arteriovenous fistula (AV fistula): a surgical joining of an artery and a vein, usually in the arm, that creates a large, strong vein for hemodialysis needles. *(Ch. 27)*

arteriovenous graft (AV graft): a tube of synthetic or biological material that joins an artery to a vein and is used for hemodialysis needles. *(Ch. 27)*

arthritis: Inflammation of a joint; used as a general term for many conditions that affect joints and the tissues around them. *(Ch. 34)*

articular cartilage: The smooth, firm tissue covering the ends of bones in a synovial joint, which lets them glide and spreads the load. *(Ch. 34)*

artifact: A signal on an ECG or monitor that does not come from the heart's electrical activity, such as interference from movement or loose electrodes. *(Ch. 16)*

artificial nutrition and hydration: Nutrition and fluids given by tube or by the intravenous or subcutaneous route; a medical treatment that requires a values-based decision and consent. *(Ch. 10)*

ASA Physical Status classification: A six-class system used by anesthesiologists to describe a patient's overall health before anesthesia, with "E" added for emergency surgery. *(Ch. 7)*

ascending paralysis: Weakness that starts in the legs and spreads upward to the arms and the muscles of breathing, swallowing and the face. *(Ch. 32)*

ascites: A build-up of fluid in the peritoneal cavity, most often caused by portal hypertension in cirrhosis. *(Ch. 26)*

aspiration: the passage of material from the mouth, throat or stomach into the airways. *(Ch. 13)*

aspiration pneumonia: a lung infection that follows the breathing in of mouth and throat secretions that carry bacteria, usually in a person with dysphagia. *(Ch. 13)*

aspiration pneumonitis: a chemical lung injury caused by breathing in a large volume of stomach contents, usually in a person with reduced consciousness. *(Ch. 13)*

asterixis: A flapping movement of the outstretched hands with the wrists bent back, caused by brief loss of muscle tone; a sign of hepatic encephalopathy. *(Ch. 26)*

asthma: A chronic, usually inflammatory airway disease with variable symptoms and variable airflow limitation. *(Ch. 14)*

asthma control: How well treatment keeps asthma symptoms and exacerbations away, judged against set criteria. *(Ch. 14)*

asthma exacerbation: A flare in which asthma symptoms and lung function worsen beyond the person's usual variation. *(Ch. 14)*

asymptomatic bacteriuria: Bacteria in the urine without symptoms of urinary tract infection; screened for and treated in pregnancy but not in most other adults. *(Ch. 29)*

asymptomatic bacteriuria (ASB): Bacteria in the urine at a significant count in a person with no signs or symptoms of urinary tract infection; usually not screened for or treated. *(Ch. 28)*

asystole: The absence of electrical activity in the ventricles, seen as a flat line; a non-shockable arrest rhythm. *(Ch. 16)*

atelectasis: collapse of the small air sacs (alveoli) in part of the lung, common after surgery when breathing is shallow. *(Ch. 7)*

atherosclerosis: a chronic inflammatory disease of the artery wall in which lipids, immune cells and fibrous tissue build up beneath the lining to form plaque. *(Ch. 17)*

atrial fibrillation (AF): A dysrhythmia in which disorganized atrial activity produces an irregularly irregular ventricular rhythm with no clear P waves. *(Ch. 16)*

atrial flutter: A dysrhythmia caused by an organized loop of atrial activity that produces regular sawtooth flutter waves. *(Ch. 16)*

atrioventricular (AV) node: Conduction tissue low in the right atrium that delays the impulse before it reaches the ventricles; with the bundle of His, the normal route from atria to ventricles. *(Ch. 16)*

atypical bacteria: bacteria such as Legionella that cause pneumonia but need special tests, such as urine antigen tests or selective cultures, to detect. *(Ch. 13)*

audiogram: A chart of the softest sounds a person can hear in each ear across a range of pitches, produced by a hearing test. *(Ch. 36)*

AUDIT-C: a short alcohol screening tool built from the consumption questions of the Alcohol Use Disorders Identification Test. *(Ch. 11)*

authorizing mechanism: A legal means, such as an order, a directive or delegation, that gives a nurse authority to perform a controlled act or other activity the nurse cannot start alone. *(Ch. 1)*

autoimmune disease: A disease in which the immune system attacks the body's own tissues. *(Ch. 34)*

autoimmunity: an immune response against the body's own tissues that results from a breakdown of self-tolerance. *(Ch. 21)*

automated external defibrillator (AED): A portable device that analyzes the heart rhythm, decides whether a shock is needed and guides the rescuer with prompts. *(Ch. 16)*

automated office blood pressure (AOBP): Several readings taken and averaged by a validated automated upper-arm device in a health care setting. *(Ch. 19)*

autonomic dysfunction: Damage to the nerves that control heart rate, blood pressure, bowel and bladder, causing swings in vital signs and other problems. *(Ch. 32)*

autonomic dysreflexia: A sudden, dangerous rise in blood pressure, triggered by a stimulus below a spinal cord injury, usually at T6 or above. *(Ch. 32)*

autonomic neuropathy: damage to the nerves that control internal organs, causing problems such as orthostatic hypotension, gastroparesis, bladder dysfunction and sweating changes. *(Ch. 22)*

autoregulation: The ability of cerebral blood vessels to widen or narrow to keep brain blood flow fairly steady when blood pressure changes. *(Ch. 30)*

axillary lymph node dissection: Surgery that removes lymph nodes from the armpit, usually when breast cancer has spread to them. *(Ch. 29)*

axis: A chain of control in which the hypothalamus and pituitary stimulate a target gland, such as the thyroid or adrenal cortex. *(Ch. 23)*

B symptoms: unexplained fever above 38 °C, drenching night sweats and unexplained loss of more than 10% of body weight in the 6 months before diagnosis. *(Ch. 20)*

back slab: A plaster or fibreglass splint moulded along one side of a limb and held on with a bandage, leaving room for swelling. *(Ch. 33)*

bacterial meningitis: A bacterial infection of the meninges that cover the brain and spinal cord; a medical emergency. *(Ch. 30)*

balanced solution: An isotonic crystalloid, such as Plasma-Lyte A, whose electrolyte content is closer to plasma than that of 0.9% sodium chloride. *(Ch. 3)*

bariatric surgery: surgery on the stomach, intestine or both to support long-term weight loss and improve obesity-related disease. *(Ch. 24)*

Barrett esophagus: a precancerous change in the lining of the lower esophagus, linked with long-term reflux, that raises the risk of esophageal cancer. *(Ch. 24)*

basal cell carcinoma: The most common skin cancer, starting in the basal cells of the epidermis; it usually grows slowly and rarely spreads. *(Ch. 35)*

basal insulin: background insulin that controls glucose between meals and overnight *(Ch. 22)*

basal-bolus insulin: an insulin plan that combines background (basal) insulin, mealtime (bolus) insulin and correction insulin for high readings. *(Ch. 22)*

Beck's triad: Low blood pressure, distended neck veins and muffled heart sounds, a classic but often incomplete sign of cardiac tamponade. *(Ch. 18)*

Beers Criteria: The American Geriatrics Society's list of medications to avoid or use with caution in adults aged 65 and older, last updated in 2023. *(Ch. 8)*

benign paroxysmal positional vertigo (BPPV): An inner ear disorder causing brief spells of vertigo, usually a minute or less, triggered by changes in head position. *(Ch. 36)*

benign prostatic hyperplasia (BPH): non-cancerous enlargement of the prostate that can narrow the urethra. *(Ch. 28)*

bereavement: The state of having lost someone through death. *(Ch. 10)*

best possible medication history: A medication history built from a structured interview with the patient or family and at least one other reliable source, covering all prescribed and non-prescribed medications. *(Ch. 1)*

bilateral salpingo-oophorectomy: Surgical removal of both ovaries and both fallopian tubes. *(Ch. 29)*

bilevel positive airway pressure: A form of NIV that gives a higher pressure on inspiration and a lower pressure on expiration, resting the breathing muscles and helping clear CO2. *(Ch. 15)*

biliary colic: Pain, usually lasting about 30 minutes to 4 hours, caused when a gallstone briefly blocks the cystic duct; felt in the right upper quadrant or epigastrium, often after a meal. *(Ch. 26)*

bilirubin: A yellow pigment made when old red blood cells break down; the liver conjugates it and secretes it into bile. *(Ch. 26)*

biofilm: A complex community of bacteria and fungi held together on a wound in a slimy coating made of sugars and proteins; it delays healing and cannot be detected by standard culture. *(Ch. 35)*

biologic: An injected antibody medicine that blocks a specific step in airway inflammation, used for some people with severe asthma. *(Ch. 14)*

biologic therapy: A drug made from living cells, such as an anti-TNF agent, given by infusion or injection to block a specific part of the immune response. *(Ch. 25)*

bioprosthetic valve: A replacement heart valve made from animal tissue; it does not need lifelong anticoagulation but wears out over time. *(Ch. 18)*

biopsy: Removal of a tissue sample for examination by a pathologist; the only test that confirms breast cancer. *(Ch. 29)*

biosimilar: a lower-cost insulin highly similar to an original brand-name insulin *(Ch. 22)*

biphasic reaction: a return of anaphylaxis symptoms after the first reaction has settled, without new exposure to the trigger. *(Ch. 6)*

bitemporal visual field loss: loss of the outer (temporal) visual fields of both eyes, caused by pressure on the optic chiasm. *(Ch. 23)*

bladder diary: A record of fluid intake, voids, urgency and leaks kept over several days to assess bladder problems. *(Ch. 28)*

bladder scanner: A portable ultrasound device that estimates the volume of urine in the bladder. *(Ch. 28)*

bladder training: A schedule of voiding at set times, with intervals lengthened gradually, combined with urge-suppression techniques. *(Ch. 28)*

blood component: a part of donated blood separated after collection, such as red cells, platelets, plasma or cryoprecipitate. *(Ch. 20)*

blood culture: a blood sample placed in culture bottles to detect and identify bacteria or fungi in the bloodstream, collected before the first antibiotic dose when possible. *(Ch. 13)*

blood–brain barrier: Tightly joined cells that limit which substances pass from the blood into brain tissue. *(Ch. 30)*

bolus: A soft, cohesive mass of chewed food or fluid that the tongue shapes and moves to the back of the mouth for swallowing. *(Ch. 24)*

bolus (prandial) insulin: insulin given with meals to cover the rise in glucose from food *(Ch. 22)*

bone mineral density (BMD): The amount of mineral in a given area of bone, measured with dual-energy X-ray absorptiometry (DXA). *(Ch. 33)*

bowel obstruction: any problem that stops intestinal contents from moving forward, either a mechanical blockage or a loss of bowel movement (ileus). *(Ch. 25)*

bowel regimen: a scheduled laxative plan started with regular opioids to prevent constipation. *(Ch. 5)*

brachytherapy: radiation therapy in which a sealed radioactive source is placed inside or next to a tumour. *(Ch. 9)*

bradykinesia: Slowness of movement, seen as small steps, a soft voice and small handwriting. *(Ch. 32)*

brainstem: The midbrain, pons and medulla, which link the brain to the spinal cord and control breathing, heart rate, many reflexes and arousal. *(Ch. 30)*

breast-conserving surgery: Surgery that takes out a breast tumour with a rim of healthy tissue and keeps the rest of the breast; usually followed by radiation. *(Ch. 29)*

brief intervention: a short, structured conversation, based on motivational interviewing, that helps a person consider their substance use and choose a change. *(Ch. 11)*

briefing: The checklist phase completed before anesthesia begins. *(Ch. 7)*

Bristol Stool Form Scale: A seven-type picture chart that describes stool form, from separate hard lumps (type 1) to entirely liquid stool (type 7), and gives a rough guide to transit time. *(Ch. 25)*

bronchiectasis: Permanent widening of the bronchi, seen on CT, with chronic symptoms and recurrent exacerbations. *(Ch. 14)*

bronchoconstriction: Tightening of the smooth muscle around the airways, which narrows them. *(Ch. 14)*

bruit: the sound of blood flow through a fistula or graft heard with a stethoscope; normally low-pitched and continuous. *(Ch. 27)*

buffer: A chemical system, such as bicarbonate and carbonic acid, that takes up or releases hydrogen ions to limit changes in pH. *(Ch. 3)*

buprenorphine: a partial mu-opioid agonist used as a first-line opioid agonist treatment, often combined with naloxone or given as an extended-release injection. *(Ch. 5)*

burn: Damage to the skin or deeper tissues caused by heat, chemicals, electricity, radiation, friction or extreme cold. *(Ch. 35)*

C-reactive protein (CRP): An acute-phase protein whose blood level rises with inflammation of any cause; it is not specific to infection. *(Ch. 4)*

cachexia: A syndrome of continuing skeletal muscle loss (with or without loss of fat) that usual nutritional support cannot fully reverse and that steadily worsens function. *(Ch. 10)*

Cairo–Bishop criteria: A widely used set of laboratory and clinical criteria that define tumour lysis syndrome. *(Ch. 9)*

Calls to Action: The 94 specific steps issued by the Truth and Reconciliation Commission of Canada in 2015 to redress the legacy of residential schools and advance reconciliation; Calls 18 to 24 address health. *(Ch. 2)*

Canada Health Act: The federal law that sets the criteria and conditions provincial and territorial health insurance plans must meet to receive full federal cash contributions for insured health services. *(Ch. 1)*

Canadian Nosocomial Infection Surveillance Program (CNISP): the Public Health Agency of Canada's surveillance program, with sentinel hospitals, for healthcare-associated infections and antimicrobial resistance. *(Ch. 4)*

Canadian Nutrition Screening Tool (CNST): A two-question screen asking about unintended weight loss over the last six months and eating less than usual for over a week; a yes to both shows nutrition risk. *(Ch. 24)*

Canadian Problem Checklist: A screening checklist of emotional, practical and physical concerns used with the ESAS-r. *(Ch. 9)*

Canadian Triage and Acuity Scale (CTAS): Canada's five-level emergency department triage scale, maintained by a national committee of CAEP and NENA. *(Ch. 6)*

canalith repositioning manoeuvre: A series of head and body movements, such as the Epley manoeuvre, done by a trained clinician to treat BPPV. *(Ch. 36)*

cancer-related fatigue: A distressing, persistent sense of physical, emotional or mental exhaustion, out of proportion to activity and not relieved by rest. *(Ch. 9)*

cannabinoid hyperemesis syndrome (CHS): repeated episodes of severe nausea, vomiting and abdominal pain in people with heavy long-term cannabis use, often eased by hot showers and resolved by stopping cannabis. *(Ch. 11)*

Cannabis Act: the federal law under which non-medical cannabis has been legal and regulated in Canada since October 17, 2018. *(Ch. 11)*

capacity: The ability to understand information relevant to a specific treatment decision and to appreciate the reasonably foreseeable consequences of deciding or not deciding; it is presumed and treatment-specific, and it can change over time. *(Ch. 1)*

capnography: continuous measurement of exhaled carbon dioxide, which detects hypoventilation directly. *(Ch. 5)*

carbapenemase-producing organism (CPO): a bacterium that makes enzymes that break down carbapenem antibiotics, leaving few effective drugs; carbapenemase-producing Enterobacterales (CPE) are the main group. *(Ch. 4)*

carbon monoxide poisoning: Harm caused when inhaled carbon monoxide binds to hemoglobin and forms carboxyhemoglobin, which cannot carry oxygen; pulse oximetry can read falsely normal. *(Ch. 35)*

carcinogen: an agent, such as a chemical, radiation or a virus, that can damage DNA and cause cancer. *(Ch. 9)*

carcinogenesis: the multistep process by which a normal cell becomes a cancer cell. *(Ch. 9)*

cardiac amyloidosis: A restrictive cardiomyopathy in which misfolded proteins, often transthyretin, deposit in the heart muscle and stiffen it. *(Ch. 18)*

cardiac output: the volume of blood the heart pumps each minute; heart rate × stroke volume. *(Ch. 6)*

cardiac rehabilitation: A structured program of assessment, exercise, education and psychosocial support after a heart event or heart surgery. *(Ch. 17)*

cardiac resynchronization therapy (CRT): Pacing of both ventricles so they contract together. *(Ch. 18)*

cardiac tamponade: fluid or blood in the pericardial sac that compresses the heart and prevents it from filling. *(Ch. 6)*

cardiogenic shock: Shock caused by failure of the heart as a pump. *(Ch. 6)*

cardiomyopathy: A disease of the heart muscle itself that is not explained by coronary disease, hypertension or valve disease alone. *(Ch. 18)*

Care Coordination Service: Ontario's provincial service that gives information about MAID and other options at the end of life and connects people, including those who refer themselves, with physicians and NPs who provide MAID. *(Ch. 10)*

caregiver: A family member or friend who provides unpaid care and support to a person with an illness or disability. *(Ch. 32)*

caregiver strain: The physical, emotional and financial toll that caring for a family member or friend can take on the caregiver. *(Ch. 8)*

carotid bodies: small clusters of sensing cells beside the carotid arteries that respond to low arterial oxygen and to acidity. *(Ch. 12)*

cast: A rigid shell of plaster or fibreglass that wraps around a limb to hold a fracture still. *(Ch. 33)*

cataract: Clouding of the lens of the eye, most often with age. *(Ch. 36)*

catheter-associated urinary tract infection (CAUTI): A urinary tract infection in a person who has, or recently had, a urinary catheter. *(Ch. 28)*

CD4 T cell: a helper T cell that directs the immune response by releasing cytokines; the cell HIV infects and depletes. *(Ch. 21)*

cellulitis: A spreading infection of the skin and the tissue just beneath it, causing warmth, swelling, tenderness and a spreading change in colour. *(Ch. 35)*

central cyanosis: a bluish or greyish colour of the tongue, lips and oral lining that signals low arterial oxygen. *(Ch. 12)*

central nervous system (CNS): The brain and spinal cord. *(Ch. 30)*

central sensitization: increased responsiveness of pain neurons in the spinal cord and brain to normal or weak input *(Ch. 5)*

central venous access device: An IV catheter whose tip lies in a large central vein, such as a peripherally inserted central catheter (PICC), used for concentrated solutions such as most parenteral nutrition. *(Ch. 24)*

central venous catheter for dialysis: a large catheter in a central vein, usually in the neck, used for hemodialysis and reserved for dialysis staff. *(Ch. 27)*

cerebellum: The part of the brain at the back, below the cerebrum, that coordinates movement and learned motor skills. *(Ch. 30)*

cerebral amyloid angiopathy: A condition in which a protein called beta-amyloid builds up in the walls of small blood vessels in the outer brain and its coverings; a leading cause of bleeds in the outer lobes of the brain in older adults. *(Ch. 31)*

cerebral aneurysm: A weak, bulging area in the wall of a brain artery that can rupture and bleed. *(Ch. 31)*

cerebral edema: Swelling of brain tissue, for example around a tumour or after an injury. *(Ch. 30)*

cerebral perfusion pressure: The pressure that drives blood into the brain; mean arterial pressure minus intracranial pressure. *(Ch. 30)*

cerebrospinal fluid (CSF): The clear fluid made mainly in the choroid plexus of the ventricles that cushions the brain and spinal cord and carries away waste. *(Ch. 30)*

cerebrospinal fluid (CSF) leak: escape of the fluid around the brain, seen after transsphenoidal surgery as clear, watery nasal drainage or salty fluid in the throat. *(Ch. 23)*

cerebrum: The main part of the forebrain, the largest part of the brain, made of two hemispheres and four lobes; it controls conscious thought, memory, language and voluntary movement. *(Ch. 30)*

cerumen: Earwax, made by glands in the outer ear canal to protect and lubricate the canal. *(Ch. 36)*

cerumen impaction: A build-up of earwax that blocks the ear canal or causes symptoms such as fullness, muffled hearing, tinnitus or ear pain. *(Ch. 36)*

CHADS-65: The Canadian Cardiovascular Society algorithm that recommends oral anticoagulation for people with AF who are 65 or older or who have any CHADS2 risk factor. *(Ch. 16)*

chain of infection: A model of the six links needed for infection to spread (agent, reservoir, portal of exit, mode of transmission, portal of entry, susceptible host); breaking any link stops transmission. *(Ch. 4)*

Charcot triad: Fever, jaundice and abdominal pain; a highly specific but insensitive combination of signs of acute cholangitis. *(Ch. 26)*

Charles Bonnet syndrome: Seeing images of people, landscapes or patterns that are not there, after significant vision loss; it is often mistaken for dementia or a mental health problem. *(Ch. 36)*

chemical eye injury: Damage to the eye from a chemical splash; alkali injuries are generally more harmful than acid injuries. *(Ch. 36)*

chemical restraint: A medication given to control behaviour rather than to treat a diagnosed condition. *(Ch. 8)*

chemotherapy: treatment with cytotoxic drugs that kill cancer cells or slow their growth, along with other rapidly dividing cells. *(Ch. 9)*

chest physiotherapy: External chest wall techniques (percussion, vibration and postural drainage) used to help move secretions. *(Ch. 12)*

chest tube: A flexible tube placed between the ribs into the pleural space to drain air, blood or fluid and let the lung re-expand; also called an intercostal chest drain. *(Ch. 15)*

Cheyne-Stokes respiration: A cyclic breathing pattern of deepening and then shallower breaths followed by a pause. *(Ch. 10)*

Cheyne–Stokes breathing: a repeating cycle of breaths that deepen, then fade, followed by a pause in breathing. *(Ch. 12)*

chlamydia: A sexually transmitted infection caused by Chlamydia trachomatis; the sexually transmitted infection reported most often in Canada. *(Ch. 29)*

cholangitis: Infection of the bile ducts behind a blockage, most often a stone; severe cases cause organ dysfunction and need urgent drainage. *(Ch. 26)*

choledocholithiasis: A stone in the common bile duct. *(Ch. 26)*

cholelithiasis: Stones in the biliary tract, most often in the gallbladder. *(Ch. 26)*

cholinergic crisis: Severe weakness, with excess secretions and other cholinergic effects, caused by too much cholinesterase inhibitor. *(Ch. 32)*

chosen family: People a person chooses as family, such as close friends or partners, who may provide support in place of or alongside relatives by birth. *(Ch. 2)*

chosen name: The name a person uses, which may differ from the name on a health card or other legal record. *(Ch. 2)*

chronic bronchitis: Long-standing airway inflammation with thickened airway walls, excess mucus and a cough that brings up sputum on most days. *(Ch. 14)*

chronic inflammation: Inflammation that persists because the cause is not removed or the response fails to switch off, with ongoing tissue damage and scarring. *(Ch. 4)*

chronic kidney disease (CKD): an abnormality of kidney structure or function lasting more than three months with implications for health, classified by cause, GFR category and albuminuria category *(Ch. 27)*

chronic limb-threatening ischemia (CLTI): advanced PAD with ischemic rest pain, ulcers or gangrene. *(Ch. 19)*

chronic obstructive pulmonary disease (COPD): A long-term lung condition in which damaged airways, damaged alveoli or both cause airflow obstruction that does not fully reverse and often worsens over time. *(Ch. 14)*

chronic pain: pain that lasts, or keeps returning, for longer than 3 months *(Ch. 5)*

chronic pancreatitis: A long-lasting fibroinflammatory disease in which ongoing injury scars the pancreas and slowly destroys its digestive and hormone-producing function. *(Ch. 26)*

chronic postsurgical pain: pain that begins or worsens after surgery and persists beyond healing, at least 3 months after surgery *(Ch. 5)*

chronic venous insufficiency (CVI): persistently high pressure in the leg veins from failed valves or blocked veins, causing edema, skin changes and ulcers. *(Ch. 19)*

chronic wound: A wound, also called a wound of long duration, that has stalled in healing because a barrier to healing has not been corrected. *(Ch. 35)*

Chvostek's sign: Twitching of the facial muscles when the facial nerve is tapped; a sign of hypocalcemia, though less specific than Trousseau's sign. *(Ch. 3)*

circle of care: A common term, not defined in PHIPA, for situations in which custodians may assume a patient's implied consent to share personal health information with one another for the patient's health care. *(Ch. 1)*

cirrhosis: Advanced scarring of the liver, with nodules of regenerating cells, that impairs blood flow through the liver and liver function. *(Ch. 26)*

cisgender: Describes a person whose gender identity matches the sex they were assigned at birth. *(Ch. 2)*

CIWA-Ar: the Clinical Institute Withdrawal Assessment for Alcohol, revised; a 10-area scale that measures the current severity of alcohol withdrawal. *(Ch. 11)*

CKD–mineral and bone disorder (CKD–MBD): imbalance of calcium, phosphate, parathyroid hormone and vitamin D in CKD that affects bone and blood vessels *(Ch. 27)*

clinical deterioration: A worsening of a patient's physiological condition that can lead to serious harm or death if it is not recognized and treated. *(Ch. 6)*

Clinical Frailty Scale (CFS): a Canadian, judgment-based nine-level scale that summarizes an older adult's usual fitness or frailty after a clinical encounter. *(Ch. 8)*

clinical judgment: The reasoning a nurse uses to interpret a patient's situation and decide how to respond, observed as the result of critical thinking and decision-making. *(Ch. 1)*

Clinical Judgment Measurement Model (CJMM): NCSBN's layered framework for measuring clinical judgment on the NCLEX; its core is six cognitive skills from recognizing cues to evaluating outcomes. *(Ch. 1)*

Clinical Opiate Withdrawal Scale (COWS): an 11-item clinician-rated scale that rates the severity of opioid withdrawal and tracks it over time. *(Ch. 11)*

clinician-administered MAID: The form of MAID in which a physician or NP gives the substance. *(Ch. 10)*

clipping: Surgery in which the skull is opened and a clip is placed across the neck of an aneurysm. *(Ch. 31)*

closed fracture: A fracture in which the skin over the break is intact. *(Ch. 33)*

closed suction drain: A soft tube from a wound to a compressible bulb that draws out blood and lymph by suction. *(Ch. 29)*

closed-loop communication: An exchange in which the receiver repeats back the message and the sender confirms it, so both know it was understood. *(Ch. 6)*

closed-loop obstruction: an obstruction in which a segment of bowel is blocked at both ends, as in volvulus; it carries a high risk of strangulation. *(Ch. 25)*

closed-system drug-transfer device (CSTD): A device that connects drug containers and tubing so that hazardous drug cannot escape into the air or onto the skin. *(Ch. 9)*

Clostridioides difficile: a spore-forming, toxin-producing anaerobic bacterium that causes diarrhea and colitis, most often after antibiotic use. *(Ch. 4)*

clot retention: blockage of a urinary catheter by blood clots, so the bladder fills and cannot drain. *(Ch. 28)*

clubbing: painless enlargement of the fingertips with loss of the normal angle at the nail bed, linked to lung cancer and chronic lung and heart disease. *(Ch. 12)*

cochlea: The fluid-filled, snail-shaped organ of the inner ear whose hair cells turn sound vibrations into nerve signals. *(Ch. 36)*

cochlear implant: An electronic device, partly placed by surgery, that sends signals straight to the hearing nerve so that people who are severely hard of hearing or profoundly deaf can perceive sound. *(Ch. 36)*

Code of Conduct: CNO's overarching practice standard; it summarizes the behaviour and ethical conduct the public can expect from every Ontario nurse. *(Ch. 1)*

code stroke: A hospital emergency process that brings the stroke team, imaging and laboratory together at once for a person with suspected acute stroke. *(Ch. 31)*

coffee-ground emesis: dark, granular vomit containing blood that has been altered by stomach acid. *(Ch. 24)*

coiling: An endovascular treatment in which a catheter places small coils inside an aneurysm so that blood no longer enters it. *(Ch. 31)*

cold chain: the system that keeps vaccines at the correct temperature, usually +2 °C to +8 °C, from manufacturer to patient. *(Ch. 21)*

colloid: An IV solution containing large molecules, such as albumin, that stay mostly in the blood vessels. *(Ch. 3)*

colonization: The presence of an organism on or in the body without signs of illness; a colonized person can still spread the organism. *(Ch. 4)*

colonoscopy: examination of the whole colon with a flexible scope, which allows polyps to be removed and tissue samples taken. *(Ch. 25)*

colorectal cancer: cancer of the colon or rectum, which can develop from an adenomatous polyp. *(Ch. 25)*

colostomy: an ostomy that brings part of the colon to the abdominal surface. *(Ch. 25)*

commercial tobacco: Manufactured tobacco products, such as cigarettes, chew and snuff, that contain added chemicals and cause addiction and disease. *(Ch. 14)*

comminuted fracture: A fracture in which the bone breaks into three or more pieces. *(Ch. 33)*

communication access: The ability of a person to understand and be understood in the way that works for them, with the supports they need. *(Ch. 36)*

community-acquired pneumonia (CAP): pneumonia that begins outside hospital, including in long-term care. *(Ch. 13)*

compartment syndrome: A rise in pressure within a closed muscle compartment that cuts off blood flow to the muscles and nerves inside it; a surgical emergency. *(Ch. 33)*

compassion fatigue: The emotions and behaviours that can result from repeatedly learning about, and caring for, other people's suffering and trauma. *(Ch. 10)*

compensated cirrhosis: Cirrhosis without overt ascites, variceal bleeding or overt hepatic encephalopathy. *(Ch. 26)*

compensated respiratory acidosis: A high PaCO2 balanced by a rise in bicarbonate retained by the kidneys, so the pH is near normal. *(Ch. 14)*

compensated shock: An early stage of shock in which the body's responses keep blood pressure near normal while signs such as a fast heart rate and cool skin appear. *(Ch. 6)*

compensation: The body's response to a primary acid–base disorder, in which the other system (lungs or kidneys) changes in the opposite direction to move pH back toward normal. *(Ch. 3)*

competence: The knowledge, skill and judgment an individual nurse needs to perform an activity safely; it changes over time and is maintained through continuing learning. *(Ch. 1)*

complete blood count (CBC): a blood test that reports hemoglobin, hematocrit, red cell count and indices, white cell count and differential, and platelet count *(Ch. 20)*

complete injury: A spinal cord injury with no sensation or movement preserved in the lowest sacral segments (S4–S5). *(Ch. 32)*

compliance: how easily the lungs and chest wall stretch; low compliance makes each breath take more effort. *(Ch. 12)*

comprehensive pain assessment: an in-depth assessment of pain's onset, location, quality, intensity, timing, aggravating and relieving factors, effects on function, the person's goals and treatment history *(Ch. 5)*

compression ultrasound: ultrasound in which a vein that will not collapse under probe pressure shows a clot. *(Ch. 19)*

computed tomography (CT): An imaging test that uses a rotating X-ray beam to build cross-sectional images; fast and useful for finding bleeding in the head. *(Ch. 30)*

concern about falling: Worry about falling, the term the World Falls Guidelines prefer to "fear of falling"; it can lead a person to avoid activity and lose strength and balance. *(Ch. 8)*

concussion: A type of mild traumatic brain injury from a force that moves the brain within the skull, causing neurologic changes that usually resolve on their own, with normal standard imaging. *(Ch. 32)*

conductive hearing loss: Hearing loss caused by a problem in the outer or middle ear that stops sound from reaching a normal inner ear. *(Ch. 36)*

Confusion Assessment Method (CAM): a widely used delirium screening approach that judges acute change or fluctuation, inattention, disorganized thinking and level of consciousness. *(Ch. 8)*

Confusion Assessment Method for the ICU: A delirium screening tool for critically ill patients, including those who cannot speak, based on four features. *(Ch. 15)*

congenital syphilis: Syphilis passed from a pregnant person to the fetus. *(Ch. 29)*

conscientious objection: A health professional's refusal, for reasons of conscience or religion, to take part in a lawful service such as MAID; nurses must transfer care without abandoning the patient. *(Ch. 10)*

Consent and Capacity Board: An independent Ontario tribunal that hears disputes about capacity findings, substitute decision-making and withdrawal of life-sustaining treatment. *(Ch. 10)*

conservative kidney management (CKM): planned, active, person-centred care for kidney failure that does not include dialysis, combining kidney care with palliative care principles. *(Ch. 27)*

consolidation: the filling of alveoli with fluid, cells and debris so that part of the lung becomes solid and airless. *(Ch. 13)*

constipation: Stools that are infrequent, hard or difficult to pass, often with straining or a sense of incomplete emptying. *(Ch. 25)*

contact precautions: Precautions for organisms spread by direct or indirect contact; they include a gown, gloves, dedicated equipment and, usually, a single room. *(Ch. 4)*

contingency management: a non-drug treatment that gives small tangible rewards for meeting treatment goals. *(Ch. 11)*

continuous bladder irrigation (CBI): constant flow of sterile 0.9% sodium chloride into and out of the bladder through a three-way catheter to prevent clots. *(Ch. 28)*

continuous glucose monitoring (CGM): measurement of interstitial glucose every few minutes by a sensor under the skin *(Ch. 22)*

continuous positive airway pressure: A form of NIV that delivers one steady pressure throughout the breath to keep airways and alveoli open. *(Ch. 15)*

continuous positive airway pressure (CPAP): A machine that delivers air through a mask at a set pressure to hold the upper airway open during sleep. *(Ch. 14)*

contractility: The strength of the heart muscle's contraction, apart from how much it was stretched by filling. *(Ch. 16)*

contracture: A fixed shortening of muscles and joint tissues that stops a joint from straightening fully. *(Ch. 33)*

contrast-associated acute kidney injury: A decline in kidney function after contrast dye, a concern mainly when eGFR is 30 mL/min/1.73 m² or less or acute kidney injury is already present. *(Ch. 17)*

controlled act: An activity listed in the Regulated Health Professions Act, 1991 that may cause harm and that only authorized people may perform. *(Ch. 1)*

controller: An inhaled medicine used regularly to reduce airway inflammation or keep airways open, preventing symptoms and flare-ups. *(Ch. 14)*

COPD Assessment Test (CAT): A short questionnaire that measures the effect of COPD on daily life; a score of 10 or more shows a moderate to high symptom burden. *(Ch. 14)*

cornea: The clear, curved front surface of the eye, which bends incoming light to help focus it. *(Ch. 36)*

corneal abrasion: A scratch in the outer layer of the cornea that causes pain, tearing and light sensitivity. *(Ch. 36)*

coronary artery bypass grafting (CABG): Surgery that carries blood around blocked coronary arteries using arterial or venous grafts. *(Ch. 17)*

correction insulin: extra rapid- or short-acting insulin added to the scheduled dose when glucose is above target *(Ch. 22)*

corticosteroid: A medicine related to the body's own cortisol that quickly reduces inflammation and immune activity; long-term use suppresses the body's cortisol production. *(Ch. 34)*

corticosteroid-dependent: Unable to stop corticosteroids within three months, relapsing within three months of stopping, or needing two or more courses in a year. *(Ch. 25)*

cortisol: the main glucocorticoid hormone; released under ACTH control, it helps maintain blood pressure and blood glucose and rises during stress. *(Ch. 23)*

costovertebral angle: The angle on the back between the lowest rib and the spine; tenderness here suggests kidney involvement. *(Ch. 28)*

COVID-19: the respiratory illness caused by the SARS-CoV-2 virus. *(Ch. 13)*

COX-2 inhibitor: an NSAID that acts mainly on the COX-2 form of the enzyme, such as celecoxib *(Ch. 5)*

crackles: brief, non-musical, discontinuous popping sounds, usually heard when breathing in; described as fine or coarse. *(Ch. 12)*

craniotomy: Surgery in which part of the skull is opened to reach the brain. *(Ch. 30)*

creatinine: a waste product of muscle activity, filtered by the kidneys; its blood level rises as GFR falls and depends on muscle mass *(Ch. 27)*

critical value: a laboratory result far enough outside the reference range that the laboratory reports it to the care team at once *(Ch. 20)*

Critical-Care Pain Observation Tool (CPOT): an observational tool scoring four behaviours from 0 to 8 for critically ill adults who cannot self-report *(Ch. 5)*

Crohn disease: A form of IBD that can affect any part of the gut from mouth to anus, in patchy segments, with inflammation through the full thickness of the bowel wall. *(Ch. 25)*

crossmatch: a test, serologic or electronic, that confirms donor red cells are compatible with the patient's plasma. *(Ch. 20)*

cryoprecipitate: a small-volume plasma component rich in fibrinogen. *(Ch. 20)*

crystalloid: An IV solution of water with electrolytes, glucose or both. *(Ch. 3)*

CT angiography (CTA): CT imaging with contrast dye that shows the arteries of the neck and brain and where an artery is blocked. *(Ch. 31)*

CT pulmonary angiography (CTPA): A CT scan with IV contrast that shows clots in the pulmonary arteries; the usual imaging test for pulmonary embolism. *(Ch. 15)*

cue: A piece of patient information, such as a sign, symptom, test result or comment, that may signal a problem. *(Ch. 1)*

cuff: A balloon near the tip of some tracheostomy and endotracheal tubes that seals the trachea when inflated. *(Ch. 12)*

Cullen sign: Bruising around the umbilicus caused by blood tracking from behind the peritoneum; rare and not specific to pancreatitis, but a sign of serious disease. *(Ch. 26)*

cultural competence: The ability to reflect on one's own cultural values and to build the knowledge and skills to plan care that respects other people's values and beliefs. *(Ch. 2)*

cultural humility: A lifelong process of self-reflection on one's own biases, privilege and power, in which the provider approaches each person as a learner. *(Ch. 2)*

cultural safety: An outcome, judged by the person receiving care, in which care is respectful, free of racism and discrimination, and attentive to power imbalances in the health system. *(Ch. 2)*

CURB-65: a five-item pneumonia severity score (confusion, urea, respiratory rate, blood pressure, age 65 or older) that helps decide where a patient should be treated. *(Ch. 13)*

Cushing disease: Cushing syndrome caused by an ACTH-secreting pituitary adenoma. *(Ch. 23)*

Cushing syndrome: the signs and symptoms of prolonged, inappropriately high glucocorticoid exposure, most often from prescribed glucocorticoids. *(Ch. 23)*

Cushing triad: A late sign of raised intracranial pressure: high blood pressure, a slow heart rate and an irregular breathing pattern or apnea. *(Ch. 30)*

cystitis: Infection limited to the bladder, usually causing dysuria, urgency, frequency and suprapubic pain. *(Ch. 28)*

cytokine release syndrome: a surge of inflammatory signals after some immune therapies, such as CAR T-cell therapy, causing high fever and low blood pressure. *(Ch. 9)*

cytokines: Small proteins released by immune cells that carry signals between cells and promote or damp down inflammation. *(Ch. 4)*

D-dimer: A fragment released when fibrin breaks down; a normal level makes pulmonary embolism unlikely when pretest probability is not high. *(Ch. 15)*

daily weight: A weight taken at the same time each day on the same scale with similar clothing, used to track short-term changes in body fluid. *(Ch. 3)*

data sovereignty: The right of a People to govern the collection, ownership and use of data about themselves. *(Ch. 2)*

dead space: air that reaches alveoli with little or no blood flow and so takes no part in gas exchange. *(Ch. 12)*

Deaf: A cultural identity, written with a capital D, of people who share Deaf culture and use a signed language as their main language. *(Ch. 36)*

debriefing: The checklist phase completed at the end of an operation, before the patient is moved out of the operating room, covering counts, specimens, equipment problems and the recovery plan. *(Ch. 7)*

decannulation: Removal of a tracheostomy tube from the trachea, planned or accidental. *(Ch. 12)*

decompensated cirrhosis: Cirrhosis in which overt ascites, variceal bleeding or overt hepatic encephalopathy has developed. *(Ch. 26)*

decompression: drainage of a kidney blocked by a stone, by ureteral stent or nephrostomy tube; urgent when the blocked kidney is infected. *(Ch. 28)*

deep tissue pressure injury (DTPI): A pressure injury that starts near the bone and shows as persistent, non-blanching discolouration or a blood blister; on darker skin it may not look purple or maroon. *(Ch. 35)*

deep vein thrombosis (DVT): A blood clot in a deep vein, usually of the leg or pelvis, and the usual source of a pulmonary embolism. *(Ch. 15)*

defibrillation: An unsynchronized shock delivered immediately to treat ventricular fibrillation, pulseless VT or polymorphic VT. *(Ch. 16)*

dehiscence: separation of the edges of a closed surgical incision, with or without exposure of the tissues or organs beneath. *(Ch. 7)*

delabelling: removing an inaccurate allergy label after the history is reviewed and, when needed, testing or a supervised challenge is done. *(Ch. 21)*

delayed cerebral ischemia: New brain ischemia that develops days after an aneurysmal subarachnoid hemorrhage, often linked to narrowing of brain arteries. *(Ch. 31)*

delayed primary intention: Closure of a contaminated wound after it has been left open for several days. *(Ch. 35)*

delegation: Passing the authority for a controlled act from a regulated professional who holds it, and can perform the act competently, to someone who does not hold it; the delegating professional stays accountable. *(Ch. 1)*

delirium: a sudden, fluctuating disturbance of attention and awareness, with changes in thinking or perception, caused by a medical condition, a drug or several factors together. *(Ch. 8)*

delirium tremens: the most severe form of alcohol withdrawal, with delirium, hallucinations, agitation and autonomic overactivity, usually beginning 48 to 72 hours after the last drink; also called alcohol withdrawal delirium. *(Ch. 11)*

dementia: a group of conditions in which memory and other thinking abilities decline gradually and steadily enough to interfere with daily life. *(Ch. 8)*

demyelination: Damage to or loss of the myelin covering of nerve fibres, which slows or blocks nerve signals. *(Ch. 32)*

dependent rubor: dusky red colour of the foot when the leg hangs down, a sign of advanced arterial disease. *(Ch. 19)*

depolarization: Electrical activation of heart muscle cells, which triggers contraction. *(Ch. 16)*

deprescribing: The planned and supervised process of lowering the dose of, or stopping, a drug that may be doing harm or is no longer helping. *(Ch. 8)*

depression: a sustained disturbance of mood, often with loss of interest or pleasure, that changes how a person thinks, feels and functions. *(Ch. 8)*

dermis: The layer of skin beneath the epidermis that contains collagen and elastic fibres, capillaries, nerve endings, hair follicles and glands. *(Ch. 35)*

desmopressin: a synthetic form of vasopressin used to treat arginine vasopressin deficiency; its most serious adverse effect is hyponatremia. *(Ch. 23)*

determinants of health: The conditions and factors, social, economic, physical, biological and structural, that shape the health of individuals and populations. *(Ch. 2)*

device-related pressure injury: A pressure injury caused by a medical device, usually shaped like the device, and staged with the same system as other pressure injuries. *(Ch. 35)*

diabetes distress: the negative emotions and burden of self-management that come from living with diabetes. *(Ch. 22)*

diabetic foot ulcer: a break in the skin of the foot in a person with diabetes, usually from pressure on a foot that has lost sensation. *(Ch. 22)*

diabetic ketoacidosis (DKA): a hyperglycemic emergency in which insulin deficiency leads to ketone production, metabolic acidosis with a high anion gap, and dehydration. *(Ch. 22)*

diabetic retinopathy: Damage to the retina caused by diabetes. *(Ch. 36)*

diagnostic overshadowing: Attributing a new symptom to an existing diagnosis, such as a disability or mental illness, so that the real cause is missed. *(Ch. 2)*

dialysis disequilibrium syndrome: headache, vomiting, confusion and, in severe cases, seizures caused by brain swelling when urea is removed quickly, most often in early treatments. *(Ch. 27)*

dialyzer: the filter in a hemodialysis machine, in which wastes move from the blood across a membrane into dialysate. *(Ch. 27)*

diarrhea: An increase in loose or watery stools above the person's usual pattern. *(Ch. 25)*

diastolic dysfunction: A stiff ventricle that does not relax and fill normally, raising pressure behind it. *(Ch. 18)*

diffuse axonal injury: Widespread stretching and tearing of nerve fibres caused by rapid acceleration and deceleration of the brain. *(Ch. 32)*

diffusing capacity: A test of how well gas crosses from the alveoli into the blood, measured with a small amount of carbon monoxide. *(Ch. 14)*

diffusion: the movement of a gas from an area of higher partial pressure to one of lower partial pressure, as across the alveolar–capillary membrane. *(Ch. 12)*

digital chest drainage: A chest drainage system that provides suction electronically and measures air leak continuously. *(Ch. 15)*

dilated cardiomyopathy: A cardiomyopathy in which the left ventricle enlarges and contracts weakly. *(Ch. 18)*

direct oral anticoagulant (DOAC): an oral drug that directly blocks factor Xa (apixaban, rivaroxaban, edoxaban) or thrombin (dabigatran). *(Ch. 19)*

direct order: An order given for one specific patient, usually in writing and verbally only in limited situations. *(Ch. 1)*

direct-acting antiviral: A drug that blocks a step in hepatitis C virus replication; taken as tablets for 8 to 24 weeks, these drugs cure most people. *(Ch. 26)*

directive: An order written in advance by an authorized provider for an activity that applies to any patient who meets specified conditions. *(Ch. 1)*

directly observed therapy (DOT): A method in which a trained person watches a patient take each dose of medication, used to support completion of TB treatment. *(Ch. 13)*

disability: An impairment of any kind, such as a physical, mental, cognitive, sensory, learning or communication impairment, that, when it meets a barrier, prevents a person from taking part fully and equally in society. *(Ch. 2)*

discectomy: Surgery that removes the part of a herniated disc that presses on a nerve root. *(Ch. 33)*

disclosure: The process of telling a patient or substitute decision-maker that a patient safety incident occurred, what is known and what will happen next. *(Ch. 1)*

disease-modifying antirheumatic drug (DMARD): A medicine that slows or stops the immune process that damages joints, rather than only relieving symptoms. *(Ch. 34)*

disease-modifying therapy (DMT): A long-term medication that changes the course of MS by acting on the immune system, reducing relapses and slowing disability. *(Ch. 32)*

diseases of public health significance: Infections that Ontario law says must be reported to the area's medical officer of health. *(Ch. 4)*

disseminated intravascular coagulation (DIC): uncontrolled activation of clotting throughout the circulation that consumes platelets and clotting factors and can cause both bleeding and clotting. *(Ch. 20)*

distinctions-based approach: An approach that recognizes First Nations, Inuit and Métis as distinct Peoples with their own histories, rights, governments and priorities, instead of treating them as one group. *(Ch. 2)*

distress: Emotional, social, spiritual, practical or physical suffering that makes coping with cancer harder; called the sixth vital sign. *(Ch. 9)*

distress screening: Routine use of a short standard tool to identify people with cancer who need further assessment or support. *(Ch. 9)*

distributive shock: Shock caused by loss of blood vessel tone and widespread vasodilation, as in sepsis, anaphylaxis or spinal cord injury. *(Ch. 6)*

diverticulitis: Inflammation of one or more diverticula, usually causing left lower quadrant pain and fever. *(Ch. 25)*

diverticulosis: The presence of diverticula, small pouches that bulge outward through weak points in the colon wall. *(Ch. 25)*

door-to-needle time: The time from hospital arrival to the start of thrombolysis. *(Ch. 31)*

DRESS: drug reaction with eosinophilia and systemic symptoms; a delayed, severe drug reaction with rash, fever, swollen lymph nodes, facial swelling, eosinophilia and organ involvement, usually 2 to 6 weeks after a drug is started. *(Ch. 21)*

droplet precautions: Precautions for organisms spread by large respiratory droplets over a short distance; they include a mask and eye protection within 2 metres and a single room or spatial separation. *(Ch. 4)*

drug checking: a service that tests a drug sample to show what it contains. *(Ch. 11)*

drug intolerance: an unwanted, non-immune effect of a drug that occurs at a low or below-therapeutic dose. *(Ch. 21)*

drug-resistant TB: TB caused by bacteria resistant to one or more TB drugs; multidrug-resistant TB is resistant to at least isoniazid and rifampin. *(Ch. 13)*

dry powder inhaler (DPI): A device that holds medicine as a powder released by the patient's own fast, forceful breath. *(Ch. 14)*

dry suction: A chest drainage design in which an adjustable control on the unit, rather than a column of water, sets the level of suction. *(Ch. 15)*

dual antiplatelet therapy (DAPT): Treatment with ASA plus a P2Y12 inhibitor to prevent clots after ACS or stent placement. *(Ch. 17)*

Duke-ISCVID criteria: The 2023 Duke-International Society for Cardiovascular Infectious Diseases criteria, which classify infective endocarditis as definite, possible or rejected using major and minor criteria. *(Ch. 18)*

dumping syndrome: cramping, nausea, diarrhea, faintness and fast heart rate after eating, caused by food moving too quickly into the small intestine. *(Ch. 24)*

duty to accommodate: The obligation under human rights law to adjust services to an individual's disability-related needs in ways that respect dignity and support full participation, short of undue hardship. *(Ch. 2)*

dysarthria: A speech disorder caused by weakness or poor control of the muscles used for talking, producing slurred, slow or soft speech with intact language. *(Ch. 30)*

dyskinesia: Involuntary writhing or jerking movements, often a side effect of long-term levodopa treatment. *(Ch. 32)*

dyspepsia: epigastric pain as the main symptom for at least 1 month. *(Ch. 24)*

dysphagia: A swallowing disorder involving the mouth, pharynx, esophagus or the junction of the esophagus and stomach. *(Ch. 24)*

dysphagia screening: A brief check of swallowing safety, done by a trained professional with a valid tool before a patient with stroke takes anything by mouth. *(Ch. 31)*

dyspnea: The subjective experience of breathing discomfort. *(Ch. 10)*

dysrhythmia: Any heart rhythm other than normal sinus rhythm, whether too fast, too slow, irregular or started from an abnormal site. *(Ch. 16)*

dysuria: Pain or burning on urination. *(Ch. 28)*

early supported discharge: Rehabilitation provided at home by a specialized team so that a person with a mild or moderate stroke can leave hospital sooner. *(Ch. 31)*

early warning score: A number calculated from routine vital signs that reflects how sick a patient is and how urgently a response is needed. *(Ch. 6)*

ecchymosis: a bruise; bleeding under the skin that may look darker than the surrounding skin on darker skin tones. *(Ch. 20)*

echocardiography: Ultrasound imaging of the heart's structure and movement, done through the chest wall (transthoracic) or from the esophagus (transesophageal). *(Ch. 16)*

edema: Excess fluid in the interstitial space. *(Ch. 3)*

Edmonton Obesity Staging System: a five-stage tool that rates the metabolic, physical and mental health effects of obesity. *(Ch. 24)*

Edmonton Symptom Assessment System–revised (ESAS-r): A tool in which patients rate nine common symptoms from 0 to 10. *(Ch. 9)*

effluent: the fluid drained out of the abdomen at the end of a peritoneal dialysis dwell. *(Ch. 27)*

ejection fraction (EF): The percentage of blood in the left ventricle pumped out with each beat, usually measured by echocardiography. *(Ch. 18)*

elder abuse: Any act, single or repeated, or failure to act appropriately that harms or distresses an older person within a relationship in which trust is expected; it may be physical, sexual, psychological or emotional, or financial, or take the form of neglect or abandonment. *(Ch. 8)*

electroencephalography (EEG): A test that records the brain's electrical activity through electrodes on the scalp. *(Ch. 30)*

elevation pallor: blanching of the foot when the leg is raised, a sign of arterial disease. *(Ch. 19)*

embolectomy: Surgical removal of a clot from the pulmonary arteries. *(Ch. 15)*

emergence delirium: confusion, restlessness, agitation or unusual quietness and drowsiness that begins during or soon after waking from general anesthesia. *(Ch. 7)*

emphysema: Destruction of alveolar walls that reduces the surface for gas exchange and the lung's elastic recoil. *(Ch. 14)*

empyema: Infected fluid or pus in the pleural space. *(Ch. 13)*

encephalitis: Inflammation of the brain tissue itself, with signs of neurologic dysfunction such as confusion, behaviour change or seizures. *(Ch. 30)*

end-of-life care: The part of palliative care given when death is expected in the near future, focused on comfort, dignity and family support. *(Ch. 10)*

end-tidal carbon dioxide: The level of CO2 at the end of each exhaled breath; a sustained waveform confirms that an endotracheal tube is in the trachea. *(Ch. 15)*

endocrine therapy: Treatment that blocks the production or action of hormones that some cancers use to grow, such as tamoxifen or an aromatase inhibitor for breast cancer. *(Ch. 29)*

endogenous opioids: the body's own opioid substances, which help reduce pain signals *(Ch. 5)*

endometriosis: A chronic inflammatory condition in which tissue similar to the uterine lining grows outside the uterus, causing pain and sometimes infertility. *(Ch. 29)*

endophthalmitis: A sight-threatening infection inside the eye that can follow eye surgery or a penetrating eye injury. *(Ch. 36)*

endoscopic retrograde cholangiopancreatography (ERCP): A procedure in which an endoscope passed through the mouth into the duodenum is used to image and treat the bile and pancreatic ducts, for example by removing stones. *(Ch. 26)*

endotracheal tube: A tube passed through the mouth or nose and the larynx into the trachea, usually for mechanical ventilation. *(Ch. 12)*

endovascular aneurysm repair (EVAR): repair of an aneurysm with a stent graft placed through the femoral arteries. *(Ch. 19)*

endovascular thrombectomy (EVT): Removal of a clot from a large brain artery with a catheter threaded from an artery in the groin or wrist. *(Ch. 31)*

energy conservation: Planning, pacing and resting before exhaustion to manage fatigue in chronic arthritis. *(Ch. 34)*

ENFit: A connector design for enteral feeding equipment that does not fit IV or other non-enteral ports, used to prevent tubing misconnections. *(Ch. 24)*

enhanced recovery after surgery (ERAS): a set of evidence-based practices across the surgical journey that reduce the stress of surgery and speed recovery. *(Ch. 7)*

enteral nutrition: Feeding into the GI tract; in this chapter, liquid formula given through a feeding tube. *(Ch. 24)*

epidermis: The thin outer layer of skin, without its own blood vessels, that forms a waterproof barrier and contains the pigment-making melanocytes. *(Ch. 35)*

epidural analgesia: delivery of a local anesthetic, often with an opioid, through a catheter into the epidural space. *(Ch. 5)*

epidural anesthesia: local anesthetic given into the epidural space, usually through a catheter that can stay in place for pain relief after surgery. *(Ch. 7)*

epidural hematoma: A collection of blood between the skull and the dura. *(Ch. 32)*

epilepsy: A brain disease marked by a lasting tendency to have seizures, diagnosed by the ILAE's practical definition. *(Ch. 30)*

epinephrine autoinjector: a prefilled, spring-loaded device that injects a fixed dose of epinephrine into the thigh muscle for emergency treatment of anaphylaxis. *(Ch. 6)*

equality: Giving every person the same resources or treatment, whatever their needs. *(Ch. 2)*

equity: Giving people what they need so that each person has a fair chance at good outcomes. *(Ch. 2)*

erectile dysfunction: The inability to get or keep an erection firm enough for satisfying sex. *(Ch. 29)*

erythema nodosum: Tender, warm, raised lumps, usually on the shins, that look pink to red on lighter skin and violet, brown or darker than surrounding skin on darker skin. *(Ch. 25)*

erythrocyte sedimentation rate (ESR): A blood test of how quickly red blood cells settle in a tube; it rises with inflammation but is not specific. *(Ch. 34)*

erythropoiesis-stimulating agent: a drug that acts like erythropoietin to raise red blood cell production in anemia of CKD *(Ch. 27)*

escalation: Moving a concern about a patient to a person or team who can act on it, quickly enough to make a difference. *(Ch. 6)*

eschar: Dry, dark, leathery dead tissue in a wound. *(Ch. 35)*

escharotomy: A surgical cut through the eschar of a deep circumferential burn to relieve pressure on a limb, the chest or the neck. *(Ch. 35)*

esophageal varices: Enlarged, thin-walled veins in the lower esophagus caused by portal hypertension, which can bleed heavily. *(Ch. 26)*

essential care partner: A person the patient or substitute decision-maker identifies to give the physical, psychological and emotional support the patient considers important, whose role differs from that of a visitor. *(Ch. 1)*

estimated glomerular filtration rate (eGFR): a GFR calculated by the laboratory from serum creatinine, age and sex; in Canada increasingly with the race-free 2021 CKD-EPI equation *(Ch. 27)*

euglycemic diabetic ketoacidosis: ketoacidosis with glucose only mildly raised or normal, a rare risk with SGLT2 inhibitors *(Ch. 22)*

evisceration: protrusion of abdominal organs through a dehisced surgical wound; a surgical emergency. *(Ch. 7)*

expressive aphasia: Aphasia in which the person understands more than they can say and struggles to find or form words. *(Ch. 31)*

external beam radiation: radiation delivered from a machine outside the body and aimed at the tumour; the patient does not become radioactive. *(Ch. 9)*

external breast form: A breast prosthesis of foam, silicone or another material, worn inside a bra to restore shape after breast tissue is removed. *(Ch. 29)*

external catheter: A device that collects urine from outside the body, such as a sheath over the penis or a suction device against the vulva. *(Ch. 28)*

external fixator: A frame outside the body joined to the bone by pins or wires that pass through the skin, used to hold a fracture still. *(Ch. 33)*

external ventricular drain: A catheter placed through the skull into a ventricle that measures intracranial pressure and drains cerebrospinal fluid into a closed system. *(Ch. 30)*

extracellular fluid (ECF): All body water outside the cells, made up mainly of interstitial fluid and plasma. *(Ch. 3)*

extraintestinal manifestations: Features of IBD outside the gut, such as joint pain, eye inflammation, mouth ulcers and erythema nodosum. *(Ch. 25)*

extravasation: Leakage of a drug or solution that can damage tissue from a vein into the surrounding tissue. *(Ch. 3)*

exudate: Fluid, proteins and cells that leave blood vessels and collect in inflamed tissue. *(Ch. 4)*

Faces Pain Scale–Revised (FPS-R): a self-report scale of six faces scored 0 to 10, developed for children *(Ch. 5)*

failure to capture: A pacemaker problem in which a pacing spike is not followed by a P wave or QRS. *(Ch. 16)*

failure to rescue: Death of a patient after a complication that develops in hospital; used as a measure of how well a hospital recognizes and treats complications. *(Ch. 6)*

fall: An unintentional event that ends with a person resting on the ground, the floor or another lower level, whether or not an injury occurs. *(Ch. 8)*

fasciotomy: Surgery that cuts open the fascia along a muscle compartment to relieve pressure. *(Ch. 33)*

FAST: Heart & Stroke's memory aid for the most common stroke signs: Face: is it drooping? Arms: can you raise both? Speech: is it slurred or jumbled? Time: to call 9-1-1. *(Ch. 31)*

fat embolism syndrome (FES): An illness, usually after a long-bone or pelvic fracture, in which fat droplets in the blood cause breathing problems, neurologic changes and a petechial rash. *(Ch. 33)*

fear of recurrence: Worry that cancer will return, common after treatment and sometimes severe enough to disrupt daily life. *(Ch. 9)*

febrile neutropenia: Fever in a person with a low neutrophil count, usually after chemotherapy; a medical emergency treated with IV antibiotics within 1 hour. *(Ch. 9)*

febrile non-hemolytic transfusion reaction: fever and chills during or up to 4 hours after a transfusion without destruction of red cells. *(Ch. 20)*

fecal calprotectin: A protein released by white blood cells into the stool; a sensitive but non-specific marker of bowel inflammation. *(Ch. 25)*

fecal immunochemical test (FIT): an at-home screening test that detects tiny amounts of human blood in a stool sample. *(Ch. 25)*

fecal impaction: A mass of hard stool in the rectum or colon that the person cannot pass. *(Ch. 25)*

fecal incontinence: The involuntary loss of liquid or solid stool. *(Ch. 25)*

femoral access: Entry to the arterial system through the femoral artery in the groin for catheterization or PCI. *(Ch. 17)*

femoral neck fracture: A break in the narrow neck of the femur just below the femoral head, inside the hip joint capsule (an intracapsular fracture). *(Ch. 33)*

ferritin: the storage form of iron; serum ferritin is the screening test laboratories prefer when iron deficiency is suspected *(Ch. 20)*

fertility preservation: Storing sperm, eggs, embryos or reproductive tissue, or protecting reproductive organs, before or after cancer treatment so that a person may have biological children later. *(Ch. 9)*

FEV1/FVC ratio: The share of the forced vital capacity blown out in the first second; a reduced ratio shows airflow obstruction. *(Ch. 14)*

fever: A rise in body temperature that occurs as part of the inflammatory response; the threshold for action is set by policy, and older adults may have lower readings. *(Ch. 4)*

fibrinolysis: reperfusion with an intravenous drug that dissolves the fibrin in a coronary clot, used when primary PCI would be delayed. *(Ch. 17)*

fine-needle aspiration (FNA): A procedure in which cells are drawn from a thyroid nodule through a thin needle for examination. *(Ch. 23)*

finger thoracostomy: An emergency procedure in which a provider makes a small incision in the chest wall and opens the pleura with a finger to release trapped air. *(Ch. 15)*

First Nations: The many distinct Indigenous Nations across Canada, each with its own language, laws and protocols; a First Nations person may or may not have Indian status. *(Ch. 2)*

first-degree AV block: Delayed AV conduction in which every P wave is conducted but the PR interval is longer than 0.20 seconds. *(Ch. 16)*

fistula: An abnormal tunnel between the bowel and the skin, bladder, vagina or another loop of bowel. *(Ch. 25)*

flail chest: Three or more ribs each broken in two or more places, leaving a loose segment of chest wall that can move inward on inspiration. *(Ch. 15)*

flare: A period when symptoms of a chronic inflammatory disease suddenly return or worsen. *(Ch. 34)*

fluid resuscitation: Planned intravenous fluid given after a major burn to replace fluid that leaks out of the blood vessels, adjusted to urine output. *(Ch. 35)*

fluid volume deficit: A loss of extracellular fluid volume (hypovolemia). *(Ch. 3)*

fluid volume excess: Too much sodium and water in the extracellular fluid (hypervolemia). *(Ch. 3)*

flutter valve: A one-way valve attached to a chest drain that lets air out of the pleural space without a water seal; sometimes called a Heimlich valve. *(Ch. 15)*

focal seizure: A seizure that starts in networks limited to one hemisphere of the brain. *(Ch. 30)*

food insecurity: Not being able to count on enough food, in quantity or quality, because money is short. *(Ch. 2)*

forced expiratory volume in 1 second (FEV1): The volume of air blown out in the first second of a forced breath. *(Ch. 14)*

forced vital capacity (FVC): The total volume of air blown out in one full, forced breath. *(Ch. 14)*

fracture: A break in the continuity of a bone. *(Ch. 33)*

fracture liaison service: A coordinated program that identifies people with a recent fragility fracture and makes sure they are assessed and treated to prevent another fracture. *(Ch. 33)*

fragility fracture: A fracture from low trauma, such as a fall from standing height, that would not normally break a healthy bone. *(Ch. 33)*

frailty: Reduced physiological reserve that leaves a person less able to recover from a stressor such as surgery. *(Ch. 7)*

free T4: The small unbound fraction of thyroxine in the blood that is available to cells. *(Ch. 23)*

frozen plasma: plasma that contains all the clotting factors, frozen after collection and thawed before use. *(Ch. 20)*

full agonist: an opioid that fully activates the mu receptor, with effects that keep increasing as the dose rises. *(Ch. 5)*

full-thickness burn: A burn that destroys the epidermis and the whole dermis and may extend deeper; it looks white, leathery or charred and has little pain at its centre. *(Ch. 35)*

functional asplenia: loss of the spleen's ability to filter bacteria even though the spleen is present, as in sickle cell disease *(Ch. 20)*

functional decline: Loss of the ability to carry out daily activities such as walking, bathing, dressing and toileting. *(Ch. 8)*

functional incontinence: Leakage because a person cannot reach or use the toilet in time, for example because of limited mobility or dementia. *(Ch. 28)*

gabapentinoid: gabapentin or pregabalin, anticonvulsants used for neuropathic pain that raise the risk of opioid overdose and slowed breathing when combined with opioids *(Ch. 5)*

gastric residual volume (GRV): The volume of fluid drawn back from a gastric feeding tube; no longer checked routinely unless ordered or when signs of intolerance appear. *(Ch. 24)*

gastritis: inflammation of the stomach lining. *(Ch. 24)*

gastroesophageal reflux disease (GERD): a condition in which stomach contents flow back into the esophagus and cause troublesome symptoms, complications or both. *(Ch. 24)*

gastrostomy tube: A feeding tube that passes through the abdominal wall into the stomach, used for longer-term feeding. *(Ch. 24)*

gender identity: A person's internal sense of their own gender, such as being a man, a woman, both or neither. *(Ch. 2)*

gender-affirming care: Care that respects and supports a person's gender identity. *(Ch. 29)*

general anesthesia: a drug-induced state of unconsciousness from which the patient cannot be roused, even by pain. *(Ch. 7)*

generalized seizure: A seizure that starts in networks spread across both hemispheres of the brain. *(Ch. 30)*

genital herpes: A lifelong infection with herpes simplex virus that causes recurrent genital sores and can spread without symptoms. *(Ch. 29)*

genitourinary syndrome of menopause: A group of vulvar, vaginal and lower urinary tract symptoms, such as dryness, painful intercourse and urgency, caused by falling estrogen. *(Ch. 29)*

giant cell arteritis: A vasculitis of large arteries, including those of the head, in adults older than 50 that can cause permanent vision loss if not treated at once. *(Ch. 34)*

Glasgow Coma Scale (GCS): A standard scale that rates eye opening, verbal response and motor response to describe level of consciousness; the components are reported separately, and the total ranges from 3 to 15. *(Ch. 30)*

Glasgow-Blatchford score: a pre-endoscopy risk score for upper GI bleeding that predicts the need for treatment; a score of 1 or less marks very low risk. *(Ch. 24)*

glaucoma: A group of eye diseases in which the optic nerve is progressively and irreversibly damaged and the visual field shrinks. *(Ch. 36)*

Global Leadership Initiative on Malnutrition (GLIM) criteria: International criteria that diagnose malnutrition when a person at risk meets at least one phenotypic criterion (weight loss, low BMI or reduced muscle mass) and at least one etiologic criterion (reduced intake or absorption, or inflammation). *(Ch. 24)*

glomerular filtration rate (GFR): the volume of plasma filtered by the glomeruli each minute; the main measure of kidney function, reported in mL/min/1.73 m^2 *(Ch. 27)*

GLP-1 receptor agonist: a drug that copies the incretin GLP-1, boosting glucose-dependent insulin release, lowering glucagon and slowing stomach emptying *(Ch. 22)*

glucagon: the alpha-cell hormone that raises glucose between meals by making the liver release and produce glucose *(Ch. 22)*

glucocorticoid-induced adrenal insufficiency: adrenal insufficiency caused by long-term glucocorticoid medication suppressing the hypothalamic–pituitary–adrenal axis; it appears when the drug is stopped, reduced or not absorbed, or when stress raises cortisol needs. *(Ch. 23)*

glucose management indicator (GMI): an estimate of A1C calculated from the mean glucose on a CGM report *(Ch. 22)*

goals of care: A discussion during a serious illness about the illness, its likely course and what matters most to the person, used to match treatment options to the person's goals. *(Ch. 10)*

goitre: An enlarged thyroid gland, seen or felt as fullness at the front of the neck. *(Ch. 23)*

gonorrhea: A sexually transmitted infection caused by Neisseria gonorrhoeae, a bacterium that can quickly develop antibiotic resistance. *(Ch. 29)*

Good Samaritan Drug Overdose Act: a 2017 federal law that, when someone calls for emergency help with an overdose, protects the caller and others at the scene from charges of simple possession and related breaches of conditions. *(Ch. 11)*

gout: A form of inflammatory arthritis caused by deposits of monosodium urate crystals in and around joints and in other tissues. *(Ch. 34)*

gout flare: A sudden attack of pain, swelling and warmth in a joint caused by the immune response to urate crystals. *(Ch. 34)*

grade: a description of how abnormal cancer cells look under a microscope, reflecting how well differentiated they are. *(Ch. 9)*

graft-versus-host disease: a complication of allogeneic transplant in which the donor's immune cells react against the recipient's tissues. *(Ch. 20)*

granulation tissue: Moist, bumpy new connective tissue with many capillaries that fills a wound from its base during healing. *(Ch. 35)*

Graves disease: An autoimmune disorder in which antibodies stimulate the TSH receptor and cause hyperthyroidism. *(Ch. 23)*

Grey Turner sign: Bruising of the flanks caused by blood tracking from behind the peritoneum; rare and not specific to pancreatitis, but a sign of serious disease. *(Ch. 26)*

grief: The emotional, physical and spiritual response to loss. *(Ch. 10)*

grievous and irremediable medical condition: An illness, disease or disability that is serious and incurable, with an advanced, irreversible decline in capability and enduring, intolerable suffering that cannot be relieved under conditions the person considers acceptable. *(Ch. 10)*

group and screen: laboratory ABO and RhD typing with a screen for antibodies against red cells; also called type and screen. *(Ch. 20)*

Guillain–Barré syndrome (GBS): An acute immune attack on the peripheral nerves, often after an infection, causing rapidly rising weakness and loss of reflexes. *(Ch. 32)*

Hamilton Early Warning Score (HEWS): A Canadian early warning score developed at hospitals affiliated with Hamilton Health Sciences that adds a delirium screen and graded oxygen scoring to vital signs and level of consciousness. *(Ch. 6)*

hand hygiene: Removing or killing microorganisms on the hands with alcohol-based hand rub or soap and running water. *(Ch. 4)*

harm reduction: practical measures that reduce the harms of substance use without requiring the person to stop using. *(Ch. 5)*

harmful incident: A patient safety incident that reached the patient and caused harm. *(Ch. 1)*

Hashimoto thyroiditis: Chronic autoimmune thyroiditis, the most common cause of hypothyroidism where diets contain enough iodine. *(Ch. 23)*

hazardous drug: A drug that can harm people who handle it because it may damage genes, cause cancer or birth defects, harm fertility, damage organs at low doses, or resembles drugs with these effects. *(Ch. 9)*

healing by primary intention: Healing of a wound whose edges are brought together with sutures, staples or tape, without the need for granulation tissue. *(Ch. 4)*

healing by secondary intention: Healing of an open wound that fills with granulation tissue from the base up. *(Ch. 4)*

healing by tertiary intention: Healing of a wound that is left open for several days and then closed (delayed primary closure), often used for contaminated wounds. *(Ch. 4)*

healing ridge: A firm area of new collagen under a healing incision that is a normal sign of the proliferation phase. *(Ch. 4)*

health care-associated infection (HAI): An infection a person acquires while receiving health care. *(Ch. 4)*

health equity: A state in which every person has a fair opportunity to reach their best possible health, regardless of the social and structural conditions of their lives. *(Ch. 2)*

health inequality: A measurable difference in health between groups of people. *(Ch. 2)*

health inequity: A systematic difference in health between groups that is avoidable and unjust because it results from how resources, power and opportunities are distributed. *(Ch. 2)*

health information custodian: Under PHIPA, a person or organization, such as a hospital, that has custody or control of personal health information while providing health care. *(Ch. 1)*

health literacy: A person's ability to find, understand, judge and share health information in ways that support and improve their health. *(Ch. 1)*

hearing aid: A small electronic device worn in or behind the ear that makes sound louder. *(Ch. 36)*

heart failure (HF): A clinical syndrome in which a structural or functional problem of the heart causes symptoms and signs, supported by raised natriuretic peptides or evidence of congestion. *(Ch. 18)*

heart failure with improved ejection fraction (HFimpEF): Heart failure in which a previously reduced ejection fraction has risen above 40% by at least 10 percentage points. *(Ch. 18)*

heart failure with mildly reduced ejection fraction (HFmrEF): An international term for heart failure with an ejection fraction of 41% to 49%. *(Ch. 18)*

heart failure with nonreduced ejection fraction (HFnrEF): The Canadian term for heart failure with an ejection fraction above 40%, combining HFmrEF and HFpEF. *(Ch. 18)*

heart failure with preserved ejection fraction (HFpEF): An international term for heart failure with an ejection fraction of 50% or more. *(Ch. 18)*

heart failure with reduced ejection fraction (HFrEF): Heart failure with an ejection fraction of 40% or less. *(Ch. 18)*

Heart Team: A multidisciplinary group, including cardiologists, cardiac surgeons, imaging specialists and nurses, that plans valve treatment with the patient. *(Ch. 18)*

Helicobacter pylori (H. pylori): a bacterium that lives in the stomach and causes gastritis, peptic ulcers and some stomach cancers. *(Ch. 24)*

hematemesis: vomiting of bright red blood or clots. *(Ch. 24)*

hematochezia: red or maroon blood passed from the rectum. *(Ch. 24)*

hematocrit: the fraction of blood volume made up of red blood cells; reported in L/L *(Ch. 20)*

hematoma: a collection of blood in the tissues, such as under a surgical incision. *(Ch. 7)*

hematopoiesis: the production of blood cells, which in adults takes place in the bone marrow *(Ch. 20)*

hematuria: blood in the urine, which may make it pink, red or brown or be seen only on testing. *(Ch. 28)*

hemiarthroplasty: Surgery that replaces the femoral head and neck with a prosthesis while leaving the hip socket in place. *(Ch. 33)*

hemiparesis: Weakness of the face, arm or leg on one side of the body. *(Ch. 31)*

hemiplegic shoulder: The shoulder on the weak side after a stroke, which can partly dislocate and become painful. *(Ch. 31)*

hemodialysis: dialysis in which blood passes through a filter (dialyzer) outside the body to remove wastes and extra fluid, then returns to the body. *(Ch. 27)*

hemoglobin: the iron-containing protein in red blood cells that carries oxygen; reported in g/L *(Ch. 20)*

hemolysis: destruction of red blood cells before the end of their normal lifespan *(Ch. 20)*

hemophilia: an inherited lack of clotting factor VIII (hemophilia A) or factor IX (hemophilia B), usually affecting males. *(Ch. 20)*

hemoptysis: coughing up blood. *(Ch. 12)*

hemorrhagic shock: hypovolemic shock caused by bleeding. *(Ch. 6)*

hemorrhagic stroke: A stroke caused by a blood vessel that ruptures and bleeds into or around the brain. *(Ch. 31)*

hemosiderin staining: grey-brown or dark discoloration of the lower leg from iron pigment left by broken-down red blood cells. *(Ch. 19)*

hemothorax: Blood in the pleural space. *(Ch. 15)*

hemovigilance: the surveillance of transfusions and their outcomes to improve safety. *(Ch. 20)*

heparin-induced thrombocytopenia (HIT): an immune reaction to heparin that lowers the platelet count and greatly increases the risk of clotting. *(Ch. 19)*

hepatic encephalopathy (HE): Brain dysfunction caused by liver failure, blood bypassing the liver, or both, ranging from subtle changes to coma. *(Ch. 26)*

hepatitis: Inflammation of the liver. *(Ch. 26)*

hepatitis A: A liver infection spread by the fecal-oral route that does not become chronic and is prevented by vaccine and hand hygiene. *(Ch. 26)*

hepatitis B: A liver infection spread through blood and body fluids that becomes chronic in a minority of infected adults and most infected infants; preventable by vaccine. *(Ch. 26)*

hepatitis C: A liver infection spread mainly through blood that often becomes chronic and is curable with direct-acting antivirals; no vaccine exists. *(Ch. 26)*

hepatocellular carcinoma: Cancer arising from liver cells, a long-term risk of cirrhosis and chronic hepatitis B. *(Ch. 26)*

hepatorenal syndrome: Acute kidney injury in a person with cirrhosis, caused by constriction of the kidneys' blood vessels rather than kidney damage, shock or nephrotoxic drugs. *(Ch. 26)*

HER2: Human epidermal growth factor receptor 2, a cell-surface protein that some breast cancers make in excess; these cancers may respond to HER2-targeted drugs. *(Ch. 29)*

herniation: The displacement of brain tissue, under pressure, from one compartment of the skull into another or through the opening at the base of the skull. *(Ch. 30)*

herpes zoster: Reactivation of the varicella-zoster virus, causing pain and a band of blisters on one side of the body; also called shingles. *(Ch. 35)*

high-alert medication: A drug, such as insulin, an opioid or an anticoagulant, whose errors are especially likely to cause serious harm. *(Ch. 1)*

high-flow device: An oxygen device that delivers a fixed FiO2 whatever the patient's breathing pattern, such as a Venturi mask or high-flow nasal cannula. *(Ch. 12)*

high-flow nasal cannula (HFNC): A system that delivers heated, humidified, blended air and oxygen through wide-bore nasal prongs at high flows and a set FiO2. *(Ch. 12)*

high-output ileostomy: ileostomy output large enough to cause water and sodium depletion, generally more than about 1.5 to 2 L in 24 hours. *(Ch. 25)*

high-sensitivity troponin: A blood test that measures very low levels of cardiac troponin, a protein released from injured heart muscle; reported in ng/L. *(Ch. 16)*

hip dislocation: Displacement of the ball of a hip prosthesis (or a natural femoral head) out of the socket. *(Ch. 33)*

hip fracture: A break in the upper part of the femur near the hip joint. *(Ch. 33)*

HIV non-disclosure: not telling a sexual partner about one's HIV status; a criminal matter in Canada only when there is a realistic possibility of transmission. *(Ch. 21)*

home blood pressure monitoring (HBPM): Readings taken by the person at home with a validated device, using a set schedule such as two readings morning and evening for 1 week. *(Ch. 19)*

homelessness: The situation of a person, family or community that lacks stable, permanent and suitable housing and has no immediate prospect, means or ability to obtain it. *(Ch. 2)*

hormone: A chemical messenger released into the blood by a gland that acts on target cells elsewhere in the body. *(Ch. 23)*

hormone receptor status: Whether cancer cells carry estrogen receptors, progesterone receptors or both, which predicts whether hormone-blocking treatment will work. *(Ch. 29)*

hormone therapy: cancer treatment that blocks the production or action of hormones that some cancers need to grow. *(Ch. 9)*

hospice: In Canada, a term used interchangeably with palliative care and often applied to community-based care; a hospice residence is one setting for care near the end of life. *(Ch. 10)*

hospital-acquired pneumonia (HAP): pneumonia that was not incubating at admission and appears 48 hours or more after admission. *(Ch. 13)*

hospital-associated disability: a new loss of ability to perform a basic activity of daily living that develops during a hospital stay and is not caused directly by the illness itself. *(Ch. 8)*

huff cough: A forced breath out through an open mouth and throat (the forced expiratory technique), used to move secretions. *(Ch. 12)*

human immunodeficiency virus (HIV): a retrovirus that infects CD4 T helper cells and, without treatment, gradually destroys the immune system. *(Ch. 21)*

human papillomavirus: A common sexually transmitted virus; persistent infection with high-risk types causes cervical cancer. *(Ch. 29)*

humidification: Adding water vapour to inspired gas to prevent drying of the airway. *(Ch. 12)*

hydrocephalus: A buildup of cerebrospinal fluid in the ventricles of the brain, often because its flow is blocked. *(Ch. 30)*

hydroxyurea: an oral drug that raises fetal hemoglobin and reduces sickling; handled as a hazardous drug *(Ch. 20)*

hyperactive delirium: delirium in which the person is restless, agitated or fearful and may have hallucinations. *(Ch. 8)*

hyperalgesia: more pain than expected from a stimulus that normally causes pain *(Ch. 5)*

hypercalcemia: A serum calcium above the reference range. *(Ch. 3)*

hypercalcemia of malignancy: A high blood calcium level caused by cancer, often through parathyroid hormone–related peptide or bone metastases. *(Ch. 9)*

hypercapnia: A raised level of carbon dioxide in arterial blood (PaCO2 above 45 mm Hg). *(Ch. 12)*

hypercapnic respiratory failure: Type 2 respiratory failure; ventilation fails, so the PaCO2 rises above the normal range, often with a low pH. *(Ch. 15)*

hyperglycemic hyperosmolar state (HHS): a hyperglycemic emergency with very high glucose, high plasma osmolality and severe dehydration, but minimal or no acidosis. *(Ch. 22)*

hyperinflation: An abnormally large lung volume caused by air trapping, which flattens the diaphragm and makes breathing less efficient. *(Ch. 14)*

hyperkalemia: A serum potassium above the reference range; it can cause peaked T waves and fatal dysrhythmias. *(Ch. 3)*

hypernatremia: A serum sodium above the reference range, usually from too little water relative to sodium. *(Ch. 3)*

hyperoxia: More oxygen in the blood than the body needs; in acutely ill adults, liberal oxygen use is linked to higher mortality. *(Ch. 12)*

hyperpigmentation: darkening of the skin and mucous membranes caused by high ACTH in primary adrenal insufficiency, most visible in creases, gums, scars and sun-exposed skin. *(Ch. 23)*

hypersensitivity: an excessive or misdirected immune response that damages the body's own tissues; grouped into types I to IV. *(Ch. 21)*

hypertension: Blood pressure persistently at or above 130/80 mm Hg, taken with a validated device and standardized technique (Goupil et al., 2025). *(Ch. 19)*

hypertensive emergency: Severe hypertension with new or worsening damage to the brain, eyes, heart, kidneys or large arteries. *(Ch. 19)*

hypertensive urgency: Severe hypertension without acute target-organ damage; treated with oral drugs and gradual lowering. *(Ch. 19)*

hyperthyroidism: Thyrotoxicosis caused by a thyroid gland that makes too much hormone. *(Ch. 23)*

hypertonic: Having a higher tonicity than plasma, so water moves out of cells. *(Ch. 3)*

hypertrophic cardiomyopathy: An often inherited cardiomyopathy in which the ventricular wall thickens abnormally and may block outflow from the left ventricle. *(Ch. 18)*

hyphema: Bleeding inside the front of the eye, usually after blunt injury; a possible sign of serious injury to the eyeball. *(Ch. 36)*

hypoactive delirium: delirium in which the person is quiet, drowsy, slow and withdrawn; it is often missed. *(Ch. 8)*

hypocalcemia: A serum calcium below the reference range, causing nerve and muscle overexcitability. *(Ch. 3)*

hypodermis: The fatty subcutaneous layer beneath the dermis that insulates, cushions and stores energy; it has a poor blood supply. *(Ch. 35)*

hypoglycemia: a blood glucose level low enough to cause symptoms or risk harm; Diabetes Canada's 2023 update uses an alert value below 3.9 mmol/L and grades severity in three levels. *(Ch. 22)*

hypokalemia: A serum potassium below the reference range; it can cause weakness, ileus and dysrhythmias. *(Ch. 3)*

hypomagnesemia: A serum magnesium below the reference range, often with low potassium and low calcium. *(Ch. 3)*

hyponatremia: A serum sodium below the reference range, usually from too much water relative to sodium. *(Ch. 3)*

hypoparathyroidism: Too little PTH, causing low calcium; most often caused by neck surgery. *(Ch. 23)*

hypothesis: A possible explanation for a group of cues that the nurse tests against further information. *(Ch. 1)*

hypothyroidism: A deficiency of thyroid hormone that slows metabolism throughout the body. *(Ch. 23)*

hypotonic: Having a lower tonicity than plasma, so water moves into cells. *(Ch. 3)*

hypovolemic shock: Shock caused by too little blood or fluid volume in the vessels. *(Ch. 6)*

hypoxemia: a low level of oxygen in the arterial blood. *(Ch. 12)*

hypoxemic respiratory failure: Type 1 respiratory failure; oxygenation fails, with a PaO2 below about 60 mm Hg and a normal or low PaCO2. *(Ch. 15)*

hypoxia: too little oxygen in the body's tissues. *(Ch. 12)*

hypoxic pulmonary vasoconstriction: narrowing of small pulmonary arteries in poorly ventilated lung, which steers blood toward better-ventilated alveoli. *(Ch. 12)*

hysterectomy: Surgical removal of the uterus; a total hysterectomy also removes the cervix. *(Ch. 29)*

ICS–formoterol reliever: Budesonide–formoterol used as needed for symptoms, so each reliever dose also treats inflammation. *(Ch. 14)*

idiopathic pulmonary fibrosis (IPF): A scarring interstitial lung disease of unknown cause. *(Ch. 14)*

IgE: the antibody class that binds mast cells and basophils and drives type I allergic reactions. *(Ch. 21)*

ileal conduit: a channel made from a short piece of small intestine that carries urine from the ureters to a stoma on the abdomen. *(Ch. 28)*

ileostomy: an ostomy that brings the end of the ileum to the abdominal surface; its output is liquid to paste-like. *(Ch. 25)*

illness trajectory: The path a health condition takes over time, from prevention through acute illness, recovery, chronic management and end of life, and the care needed at each point. *(Ch. 1)*

immune checkpoint inhibitor: a drug that blocks signals cancer cells use to switch off T cells, allowing the immune system to attack the cancer. *(Ch. 9)*

immune reconstitution inflammatory syndrome (IRIS): an inflammatory worsening of an infection's signs, usually in the first weeks to months after ART starts, caused by the recovering immune system reacting to organisms already present. *(Ch. 21)*

immune thrombocytopenia (ITP): an acquired autoimmune disorder with a low platelet count, causing bruising, petechiae and sometimes mucosal bleeding. *(Ch. 20)*

immune-related adverse event: an inflammatory reaction in a healthy organ caused by immune checkpoint inhibitor therapy, such as colitis, pneumonitis, hepatitis, endocrine disorders or rash. *(Ch. 9)*

immunocompromised: having immune defences weakened by a disease or its treatment. *(Ch. 21)*

immunodeficiency: a state in which the immune system cannot defend the body adequately; primary when built into the immune system, secondary when acquired. *(Ch. 21)*

immunosenescence: the natural, gradual decline in immune function that comes with age. *(Ch. 21)*

immunotherapy: Cancer treatment, such as immune checkpoint inhibitors, that helps the immune system attack cancer cells. *(Ch. 13)*

impaired awareness of hypoglycemia: weak or absent warning symptoms of a low glucose, so that confusion or loss of consciousness may be the first sign. *(Ch. 22)*

implantable cardioverter-defibrillator (ICD): An implanted device that detects VT or VF and treats it with rapid pacing or a shock. *(Ch. 16)*

implicit bias: An attitude or stereotype that operates outside a person's awareness and shapes judgments and actions without the person intending it. *(Ch. 2)*

inactivated vaccine: a vaccine containing an organism or its parts that cannot replicate; non-live vaccines also include toxoid, subunit and recombinant vaccines. *(Ch. 21)*

inadvertent perioperative hypothermia: an unplanned core body temperature below 36.0 °C around the time of surgery. *(Ch. 7)*

incentive spirometer: A hand-held device that shows how deeply a patient breathes in, encouraging slow, full breaths. *(Ch. 7)*

incomplete injury: A spinal cord injury with some sensation or voluntary movement preserved in the lowest sacral segments. *(Ch. 32)*

incontinence-associated dermatitis (IAD): A form of MASD caused by urine, stool or both, usually affecting the perineum, buttocks and upper inner thighs. *(Ch. 35)*

incretins: gut hormones, mainly GLP-1 and GIP, released after meals that boost insulin release when glucose is high *(Ch. 22)*

independent double check: A safety check in which a second practitioner separately verifies a medication, dose, route, calculation and pump settings against the order without seeing the first practitioner's result, before the results are compared. *(Ch. 1)*

Indian Act: The federal law, first passed in 1876, that defines who is registered as an "Indian" and has governed many aspects of First Nations life, including reserves and band governance. *(Ch. 2)*

Indian hospitals: Racially segregated federal hospitals for Indigenous patients, operated from 1936 to 1981 and first set up to isolate people with tuberculosis; patients experienced abuse in them. *(Ch. 2)*

Indian status: The legal standing of a First Nations person registered under the Indian Act; a legal category, not an identity. *(Ch. 2)*

Indigenous patient navigator: A hospital or health-system staff member who supports Indigenous patients and families, improves communication with the care team and connects patients with cultural, spiritual and community services. *(Ch. 2)*

Indigenous-specific racism: The particular stereotyping, bias and prejudice directed at Indigenous Peoples, rooted in settler colonialism, that sustains power imbalances and unequal outcomes. *(Ch. 2)*

induration: Hardening of tissue that can be felt on palpation, often a sign of inflammation or deep damage. *(Ch. 35)*

indwelling urinary catheter: A tube passed into the bladder through the urethra or abdominal wall, held by a balloon and draining continuously into a closed bag. *(Ch. 28)*

infection: Entry of microorganisms into body tissues, where they multiply. *(Ch. 4)*

infective endocarditis (IE): Infection of the inner lining of the heart, usually a valve or implanted material. *(Ch. 18)*

infiltration: Leakage of IV fluid from the vein into the surrounding tissue. *(Ch. 3)*

inflammation: The body's protective response to tissue injury or infection, which brings fluid, proteins and white cells to the area, removes the cause and prepares for repair. *(Ch. 4)*

inflammatory bowel disease (IBD): A group of chronic, relapsing conditions in which the immune system keeps the lining of the gut inflamed; the main forms are Crohn disease and ulcerative colitis. *(Ch. 25)*

inflammatory myopericardial syndrome: The 2025 ESC umbrella term for pericarditis and myocarditis, which share causes and often overlap. *(Ch. 18)*

influenza: an acute respiratory illness caused by influenza viruses, classically with sudden fever, cough and muscle aches. *(Ch. 13)*

informed consent: Agreement to a treatment that relates to that treatment, is given voluntarily, is not obtained by misrepresentation or fraud, and is based on information about the treatment's nature, benefits, risks, side effects, alternatives and the consequences of refusing it. *(Ch. 1)*

inhalation injury: Damage to the airway and lungs from heat, smoke or toxic gases, suspected after a fire in an enclosed space. *(Ch. 35)*

inhaled corticosteroid (ICS): An inhaled anti-inflammatory controller, such as fluticasone or budesonide. *(Ch. 14)*

initiation: The authority, set out in regulation, for RNs and RPNs to decide on their own to perform certain controlled acts without an order; not available in Ontario public hospitals. *(Ch. 1)*

innate immunity: the inborn, rapid first line of defence, including barriers, phagocytes and complement, which responds the same way each time and has no memory. *(Ch. 21)*

inner cannula: A removable tube inside a tracheostomy tube that can be cleaned or replaced, or removed at once if secretions block it. *(Ch. 12)*

inner ear: The innermost part of the ear, containing the cochlea for hearing and the vestibular organs for balance. *(Ch. 36)*

inpatient surgery: Surgery after which the patient is admitted to hospital. *(Ch. 7)*

insulin: the beta-cell hormone that moves glucose into cells, stops the liver releasing glucose and holds back fat breakdown and ketone formation *(Ch. 22)*

insulin resistance: a reduced response of body cells to insulin, so more insulin is needed to keep glucose normal *(Ch. 22)*

insulin secretagogue: a drug, such as a sulfonylurea or meglitinide, that makes the pancreas release insulin whatever the glucose level *(Ch. 22)*

insured health services: Under the Canada Health Act, medically necessary hospital services, medically required physician services and surgical-dental services that require a hospital. *(Ch. 1)*

Integrated Nutrition Pathway for Acute Care (INPAC): A Canadian pathway for hospital nutrition care that moves from screening with the CNST to assessment, standard, advanced and specialized nutrition care, and discharge planning. *(Ch. 24)*

interdialytic weight gain: weight gained from fluid between hemodialysis sessions. *(Ch. 27)*

interferon-gamma release assay (IGRA): A blood test that detects TB infection by measuring interferon-gamma released by T cells exposed to M. tuberculosis proteins; not affected by BCG vaccine. *(Ch. 13)*

intergenerational effects: Harms of colonial policies that pass from one generation to the next, for example through disrupted families, lost languages and unresolved trauma. *(Ch. 2)*

Interim Federal Health Program (IFHP): A federal program, run by Immigration, Refugees and Citizenship Canada, that provides limited, temporary health coverage to eligible refugees, refugee claimants and certain others until they qualify for provincial or territorial insurance. *(Ch. 2)*

intermittent catheterization: Passing a catheter into the bladder to drain it and then removing it; done with sterile technique in hospital and clean technique at home. *(Ch. 28)*

intermittent claudication: cramping or aching leg pain that comes on with walking at a predictable distance and eases with rest. *(Ch. 19)*

intermittent pneumatic compression (IPC): leg sleeves that inflate in cycles to squeeze the legs and move blood toward the heart, used to prevent venous thromboembolism. *(Ch. 7)*

internal fixation: Plates, screws, rods or nails placed in surgery to hold a broken bone from inside. *(Ch. 33)*

International Dysphagia Diet Standardisation Initiative (IDDSI): The international framework that describes drink thickness and food texture on a continuum of eight levels numbered 0 to 7. *(Ch. 24)*

international normalized ratio (INR): A standardized blood test of clotting time used to adjust warfarin. *(Ch. 18)*

International Prostate Symptom Score (IPSS): a short questionnaire used to rate the severity of lower urinary tract symptoms and follow the response to treatment. *(Ch. 28)*

intersectionality: A way of understanding how a person's social positions, such as race, gender, disability, age, income and immigration status, combine to shape experiences of advantage and disadvantage. *(Ch. 2)*

interstitial fluid: Fluid in the spaces between cells in the tissues. *(Ch. 3)*

interstitial lung disease (ILD): A group of disorders that inflame or scar the lung tissue between the alveoli and blood vessels, causing a restrictive pattern. *(Ch. 14)*

intertrochanteric fracture: A break in the femur between the greater and lesser trochanters, outside the hip joint capsule. *(Ch. 33)*

intolerance (drug): an expected, non-immune side effect of a drug, such as nausea, diarrhea or headache. *(Ch. 4)*

intracellular fluid (ICF): Body water inside the cells, about two-thirds of the total. *(Ch. 3)*

intracerebral hemorrhage (ICH): Bleeding into the brain tissue itself that is not caused by trauma. *(Ch. 31)*

intracranial pressure: The pressure inside the skull, produced by the brain tissue, blood and cerebrospinal fluid it contains. *(Ch. 30)*

intradialytic hypotension: a fall in blood pressure during hemodialysis, linked with rapid fluid removal and with poorer outcomes. *(Ch. 27)*

intraocular pressure (IOP): The pressure inside the eye, set by the balance between aqueous humour production and drainage. *(Ch. 36)*

intraoperative: The phase from arrival in the operating room until transfer to the recovery area. *(Ch. 7)*

intraoperative floppy iris syndrome: a problem with the iris during cataract or glaucoma surgery linked to alpha-blockers such as tamsulosin. *(Ch. 28)*

intravascular fluid: The fluid within blood vessels; the plasma. *(Ch. 3)*

intravesical BCG: live, weakened bacillus Calmette-Guérin bacteria instilled into the bladder to treat non-muscle-invasive bladder cancer. *(Ch. 28)*

intubation: Placement of an endotracheal tube through the mouth into the trachea. *(Ch. 15)*

Inuit: The Indigenous People of Inuit Nunangat, many of whom now also live in southern cities; one person is an Inuk. *(Ch. 2)*

Inuit Child First Initiative: A federal initiative that helps Inuit children get the health, social and educational services and supports they need. *(Ch. 2)*

Inuit Nunangat: The Inuit homeland of land, water and ice, made up of the Inuvialuit Settlement Region, Nunavut, Nunavik and Nunatsiavut. *(Ch. 2)*

ionized calcium: The free, physiologically active fraction of plasma calcium, about half of the total. *(Ch. 3)*

iron chelation: drug treatment that binds excess iron so that it can be excreted *(Ch. 20)*

iron deficiency anemia: anemia caused by too little iron for hemoglobin production, with small, pale red cells and low ferritin *(Ch. 20)*

iron overload: excess body iron, usually from repeated transfusion, that damages the heart, liver and endocrine glands *(Ch. 20)*

irritant: A drug that causes pain or inflammation at the IV site or along the vein, usually without lasting tissue damage. *(Ch. 9)*

ischemic core: The central area of an ischemic stroke, where blood flow is lowest and damage quickly becomes permanent. *(Ch. 31)*

ischemic stroke: A stroke in which a blocked artery deprives part of the brain, spinal cord or retina of blood until cells die. *(Ch. 31)*

isotonic: Having about the same tonicity as plasma, so cells keep their size. *(Ch. 3)*

JAK inhibitor: An oral targeted synthetic DMARD that blocks Janus kinase enzymes inside immune cells, interrupting signals from many inflammatory messengers. *(Ch. 34)*

jaundice: yellow colour of the sclera, mucous membranes and skin caused by raised bilirubin *(Ch. 20)*

jejunostomy tube: A feeding tube that passes through the abdominal wall into the jejunum, usually used with a continuous feed by pump. *(Ch. 24)*

joint protection: Ways of doing daily tasks that reduce strain on painful joints, such as using larger joints, avoiding tight gripping and using aids. *(Ch. 34)*

Jordan's Principle: A principle that aims to ensure First Nations children can get essential government services without gaps or delays caused by their identity or where they live. *(Ch. 2)*

Joyce's Principle: A principle set out in 2020 by the Council of the Atikamekw of Manawan and the Atikamekw Nation Council, after the death of Joyce Echaquan, that aims to guarantee Indigenous people equitable access to health and social services without discrimination, and respect for Indigenous knowledge in health. *(Ch. 2)*

jugular venous distension: Visible filling of the neck veins with the head raised 30 to 45 degrees, a sign of high venous pressure. *(Ch. 3)*

jugular venous pressure (JVP): The vertical height of the internal jugular venous pulsation above the sternal angle; an estimate of right-sided filling pressure. *(Ch. 16)*

Jurisprudence Examination: CNO's online, open-book examination on the legislation, by-laws, practice standards and guidelines that apply to Ontario nurses. *(Ch. 1)*

just culture: An organizational culture that responds to honest errors with learning and system improvement while holding people accountable for reckless choices. *(Ch. 1)*

Kaposi sarcoma: a cancer linked to human herpesvirus 8 that causes patches or nodules on the skin or in the mouth; classically violet, with colour that varies by skin tone. *(Ch. 21)*

ketones: acids made by the liver from fatty acids when insulin is lacking; beta-hydroxybutyrate is the main one in ketoacidosis *(Ch. 22)*

kidney replacement therapy (KRT): treatment that takes over the work of failed kidneys: hemodialysis, peritoneal dialysis or a kidney transplant. *(Ch. 27)*

kidney transplant: surgery to place a healthy kidney from a living or deceased donor into a person with kidney failure. *(Ch. 27)*

kindling: the tendency for each episode of alcohol withdrawal to be more severe than the last after repeated cycles of heavy drinking and withdrawal. *(Ch. 11)*

Korsakoff syndrome: a lasting memory disorder, often following untreated Wernicke encephalopathy, in which the person cannot form new memories. *(Ch. 11)*

Kussmaul breathing: deep, rapid breathing seen in metabolic acidosis. *(Ch. 12)*

Kussmaul respirations: deep, rapid breathing that removes carbon dioxide to offset a metabolic acidosis, as in DKA. *(Ch. 22)*

lactate: a product of glucose metabolism; a level above 2 mmol/L in sepsis marks greater severity and risk of death. *(Ch. 4)*

laminectomy: Surgery that removes part of the lamina, the bony arch at the back of a vertebra, to relieve pressure on the spinal cord or nerves. *(Ch. 33)*

langue des signes québécoise (LSQ): A full signed language used by many Deaf people in Quebec and French-speaking communities; recognized in the Accessible Canada Act. *(Ch. 36)*

laparoscopic cholecystectomy: Removal of the gallbladder through small abdominal incisions using a camera and instruments. *(Ch. 26)*

large vessel occlusion (LVO): A blockage of a major brain artery, which may be treated with endovascular thrombectomy. *(Ch. 31)*

laryngectomy: Surgical removal of the larynx, after which the trachea opens to the neck as an end stoma. *(Ch. 12)*

last known well (LKW): The last time a person was known to be at their usual self without the new stroke signs; used to time treatment when onset was not witnessed. *(Ch. 31)*

latex allergy: an allergic reaction to natural rubber latex, either delayed (type IV contact dermatitis) or immediate (type I, including anaphylaxis). *(Ch. 21)*

LDL cholesterol (LDL-C): cholesterol carried in low-density lipoprotein particles, reported in mmol/L; the main target of lipid-lowering treatment. *(Ch. 17)*

least restraint: Trying alternatives first and, if a restraint cannot be avoided, using the least restrictive form for the shortest possible time. *(Ch. 8)*

left ventricular assist device (LVAD): An implanted pump that moves blood from the left ventricle into the aorta in advanced heart failure. *(Ch. 18)*

left-sided heart failure: Failure of the left ventricle, raising pressure in the pulmonary veins and causing lung congestion. *(Ch. 18)*

lens: The clear structure behind the pupil that works with the cornea to focus light onto the retina. *(Ch. 36)*

leukemia: a cancer that starts in the blood-forming stem cells of the bone marrow, in which immature cells crowd out normal blood cells. *(Ch. 20)*

leukocyte esterase: An enzyme from white blood cells; a positive dipstick result suggests pyuria. *(Ch. 28)*

level of consciousness: How awake a person is (arousal) and how well the person understands self and surroundings (awareness). *(Ch. 30)*

levodopa: A medication that the brain converts to dopamine; combined with carbidopa, it is the most effective treatment for the motor symptoms of Parkinson disease. *(Ch. 32)*

licensed practical nurse (LPN): The title for a practical nurse in most Canadian provinces and territories outside Ontario. *(Ch. 1)*

lipase: A pancreatic digestive enzyme; a blood level at least three times the upper limit of normal is one of the diagnostic features of acute pancreatitis. *(Ch. 26)*

lipohypertrophy: a lump of thickened fatty tissue at an overused injection site, from which insulin is absorbed poorly and unpredictably *(Ch. 22)*

lipoprotein(a) [Lp(a)]: an inherited lipoprotein particle that adds cardiovascular risk; measured once in a lifetime. *(Ch. 17)*

live attenuated vaccine: a vaccine containing a weakened organism that can still replicate, such as MMR or varicella vaccine. *(Ch. 21)*

live vaccine: a vaccine containing a weakened form of a living microbe; generally avoided in people who are severely immunocompromised. *(Ch. 21)*

liver transplant: Replacement of a failing liver with a whole liver from a deceased donor or part of a liver from a living donor. *(Ch. 26)*

lobectomy: Surgical removal of one lobe of a lung. *(Ch. 13)*

local anesthetic systemic toxicity (LAST): a toxic reaction of the brain and heart when local anesthetic reaches a high level in the blood. *(Ch. 7)*

local infiltration: injection of local anesthetic into the tissue at the site of a minor procedure. *(Ch. 7)*

lockbox: An informal term for a patient's instruction that limits how some or all of their personal health information may be used or shared. *(Ch. 1)*

log roll: Turning a patient so that the head, shoulders, trunk and hips move together as one unit and the spine does not twist. *(Ch. 32)*

long-acting beta2-agonist (LABA): A bronchodilator that keeps airways open for many hours; in asthma it is always combined with an inhaled corticosteroid. *(Ch. 14)*

long-acting muscarinic antagonist (LAMA): A long-acting bronchodilator, such as tiotropium, used mainly in COPD and as an add-on in asthma. *(Ch. 14)*

loop ostomy: an ostomy made by bringing a loop of bowel to the surface and opening it, often as a temporary diversion. *(Ch. 25)*

low anterior resection: surgery that removes a tumour in the middle or upper rectum, usually joining the colon to the remaining rectum. *(Ch. 25)*

low vision: As used in this chapter, vision loss that cannot be fully corrected with glasses, contact lenses, medicine or surgery and that limits everyday activities. *(Ch. 36)*

low-dose buprenorphine initiation: starting buprenorphine with very small, gradually increasing doses while the usual opioid continues until an effective dose is reached; also called microdosing. *(Ch. 11)*

low-flow device: An oxygen device whose delivered concentration varies with the patient's breathing pattern, such as a nasal cannula, simple face mask or non-rebreather mask. *(Ch. 12)*

low-molecular-weight heparin (LMWH): a subcutaneous heparin, such as enoxaparin, dalteparin or tinzaparin, that acts mainly against factor Xa. *(Ch. 19)*

lower limit of normal (LLN): The value below which only 5% of healthy people fall; used to judge whether a lung function result is abnormal. *(Ch. 14)*

lower urinary tract symptoms (LUTS): voiding symptoms (weak stream, hesitancy, straining, incomplete emptying) and storage symptoms (urgency, frequency, nocturia). *(Ch. 28)*

lucid interval: A period after a head injury when the person wakes and seems well before deteriorating, typical of an epidural hematoma. *(Ch. 32)*

lumbar puncture (LP): A procedure in which a needle is passed between lower back vertebrae into the CSF space to measure pressure and collect fluid. *(Ch. 30)*

Lund and Browder chart: A body diagram used to estimate the percentage of body surface burned; the most accurate method and the preferred one for children. *(Ch. 35)*

lung-protective ventilation: Ventilation with small tidal volumes and limited pressures to avoid further injury to the lungs. *(Ch. 15)*

lupus nephritis: Inflammation of the kidneys caused by systemic lupus erythematosus. *(Ch. 34)*

lymphedema: Swelling caused by a build-up of lymph in the tissues when lymph cannot drain normally, often after lymph nodes are removed or treated with radiation. *(Ch. 29)*

lymphoma: a cancer of lymphocytes that usually grows in lymph nodes or other lymphatic tissue; the two main groups are Hodgkin and non-Hodgkin lymphoma. *(Ch. 20)*

macrocytic anemia: anemia with large red cells, typically from vitamin B12 or folate deficiency *(Ch. 20)*

macula: The central area of the retina that gives sharp central vision. *(Ch. 36)*

magnetic resonance imaging (MRI): An imaging test that uses a strong magnetic field and radio waves to make detailed images of soft tissues such as the brain and spinal cord. *(Ch. 30)*

maintenance and reliever therapy (MART): Use of one budesonide–formoterol inhaler both as the daily controller and as the reliever for symptoms. *(Ch. 14)*

malignant hyperthermia (MH): an inherited, life-threatening hypermetabolic reaction of skeletal muscle triggered by volatile anesthetic gases and succinylcholine. *(Ch. 7)*

malignant spinal cord compression: Pressure on the spinal cord or nerve roots from cancer in the spine, causing pain and possible loss of strength, sensation and bladder or bowel control. *(Ch. 9)*

malnutrition: In this chapter, undernutrition: a state in which the body does not take in or use enough energy and nutrients, so muscle and fat are lost and function declines. *(Ch. 24)*

masked hypertension: Normal blood pressure in the office with raised readings at home or on ambulatory monitoring. *(Ch. 19)*

massive hemorrhage protocol: a hospital protocol that rapidly delivers blood components to a patient with life-threatening bleeding until the bleeding is controlled. *(Ch. 6)*

massive pulmonary embolism: High-risk pulmonary embolism, in which the circulation is unstable (persistent hypotension, obstructive shock or cardiac arrest). *(Ch. 15)*

mastectomy: Surgery that removes all of the breast tissue. *(Ch. 29)*

mean arterial pressure (MAP): The average arterial pressure over one cardiac cycle, reflecting the pressure that drives blood into the organs; commonly estimated as diastolic pressure plus one third of the pulse pressure. *(Ch. 6)*

mean corpuscular volume (MCV): the average size of red blood cells, in femtolitres, used to sort anemias into small-cell, normal-cell and large-cell patterns *(Ch. 20)*

mechanical complications of MI: Rare tears in heart structures weakened by infarction, including papillary muscle rupture, ventricular septal rupture and free wall rupture. *(Ch. 17)*

mechanical lift: A device that raises and moves a person in a sling, from the floor or a ceiling track, so that staff do not bear the person's weight. *(Ch. 33)*

mechanical obstruction: a bowel obstruction caused by something that blocks, compresses or twists the bowel, such as adhesions, a hernia, a tumour or volvulus. *(Ch. 25)*

mechanical valve: A durable replacement heart valve made of synthetic materials that requires lifelong anticoagulation with warfarin. *(Ch. 18)*

mechanical ventilation: Use of a machine to move air into the lungs through an endotracheal or tracheostomy tube. *(Ch. 15)*

medical assistance in dying (MAID): Under the Criminal Code, a physician or NP either giving a person, at their request, a substance that causes death, or prescribing or providing one that the person takes themselves. *(Ch. 10)*

medical directive: An order written in advance by an authorized prescriber that applies to any patient who meets set conditions. *(Ch. 12)*

medical expulsive therapy (MET): use of a drug to help a ureteral stone pass; any benefit is for larger (5 to 10 mm) stones in the lower ureter. *(Ch. 28)*

medical-surgical nursing: The nursing care of adults who are acutely ill, living through an exacerbation of a chronic illness, or preparing for or recovering from surgery, in hospital and across other settings. *(Ch. 1)*

medication reconciliation: A structured process in which providers, patients and families make sure accurate, complete medication information goes with the patient at admission, transfer and discharge. *(Ch. 1)*

melanoma: A cancer that starts in melanocytes, the skin cells that make the pigment melanin; less common than non-melanoma skin cancer. *(Ch. 35)*

melena: black, sticky, tar-like stool containing digested blood. *(Ch. 24)*

menopausal hormone therapy: Estrogen, alone or with a progestogen, used to relieve menopause symptoms. *(Ch. 29)*

menopause: The permanent end of menstruation caused by the loss of ovarian follicles, confirmed after 12 months in a row with no period and no other cause. *(Ch. 29)*

metabolic acidosis: An acid–base disorder with a low pH caused by a primary fall in bicarbonate. *(Ch. 3)*

metabolic alkalosis: An acid–base disorder with a high pH caused by a primary rise in bicarbonate. *(Ch. 3)*

metabolic dysfunction-associated steatohepatitis (MASH): MASLD with inflammation and liver cell injury; formerly called nonalcoholic steatohepatitis (NASH). *(Ch. 26)*

metabolic dysfunction-associated steatotic liver disease (MASLD): Fat build-up in the liver with at least one cardiometabolic risk factor and no other cause; formerly called nonalcoholic fatty liver disease (NAFLD). *(Ch. 26)*

metastasis: spread of cancer from its primary site to a distant site, where it forms a new tumour. *(Ch. 9)*

methadone: a long-acting full opioid agonist used as a first-line opioid agonist treatment; its long duration of action calls for prolonged monitoring after excess doses. *(Ch. 5)*

methicillin-resistant Staphylococcus aureus (MRSA): a strain of S. aureus that resists methicillin and related antibiotics; spread mainly by contact. *(Ch. 4)*

methotrexate: The most commonly used disease-modifying drug for rheumatoid arthritis, taken once a week on a named day; daily use by mistake has caused fatal toxicity. *(Ch. 34)*

microclimate: The conditions, especially moisture and warmth, at the skin where it meets a surface such as a mattress or chair. *(Ch. 35)*

middle ear: The air-filled space behind the eardrum containing three small bones that carry sound vibrations to the inner ear. *(Ch. 36)*

midstream clean-catch specimen: A urine sample collected from the middle of the stream after the genital area is cleaned, to reduce contamination by skin bacteria. *(Ch. 28)*

mineralocorticoid receptor antagonist (MRA): A drug that blocks aldosterone, such as spironolactone or eplerenone; its main risk is hyperkalemia. *(Ch. 18)*

mitral regurgitation: Backward leakage of blood from the left ventricle into the left atrium through a mitral valve that does not close fully; primary when the valve itself is diseased and secondary when chamber enlargement pulls the leaflets apart. *(Ch. 18)*

mitral stenosis: Narrowing of the mitral valve, most often caused by rheumatic heart disease. *(Ch. 18)*

mixed delirium: delirium in which the person moves between hyperactive and hypoactive patterns. *(Ch. 8)*

mixed hearing loss: Hearing loss with both conductive and sensorineural parts. *(Ch. 36)*

Mobitz I: Second-degree AV block in which the PR interval lengthens progressively until a P wave is not conducted (also called Wenckebach). *(Ch. 16)*

Mobitz II: Second-degree AV block in which the PR interval stays constant but some P waves are suddenly not conducted. *(Ch. 16)*

modulation: the nervous system's ability to increase or decrease pain signals, largely through pathways descending from the brainstem *(Ch. 5)*

moisture balance: Keeping a healable wound moist enough for cells to migrate but not so wet that the edges macerate. *(Ch. 35)*

moisture-associated skin damage (MASD): Inflammation and erosion of skin caused by long contact with urine, stool, sweat, wound drainage or stoma output. *(Ch. 35)*

monofilament testing: a screening test of protective sensation in which a 10 g nylon filament is pressed against the foot; loss of sensation predicts ulcers and amputation. *(Ch. 22)*

moral distress: Psychological distress, such as guilt, anger or powerlessness, caused by a moral event such as a constraint, conflict, dilemma or uncertainty. *(Ch. 10)*

morning stiffness: Joint stiffness after waking; lasting 30 minutes or more suggests inflammatory arthritis, while osteoarthritis stiffness usually eases in less than 30 minutes. *(Ch. 34)*

morphine milligram equivalent (MME): a way of expressing different opioids as an equivalent amount of oral morphine, so that total opioid exposure can be compared. *(Ch. 5)*

mottling: patchy, lace-like skin discolouration, usually starting at the knees, that signals poor skin perfusion; harder to see on darker skin. *(Ch. 4)*

mu-opioid receptor: the opioid receptor most responsible for pain relief, found in pain-modulating areas of the brain and spinal cord and in the gut wall. *(Ch. 5)*

mucosal membrane pressure injury: A pressure injury on a moist lining, such as the lips or nose, where a device has been used; it cannot be staged. *(Ch. 35)*

mucositis: inflammation and ulceration of the lining of the mouth or gastrointestinal tract caused by cancer treatment. *(Ch. 9)*

multicomponent prevention: a bundle of non-drug measures, such as orientation, sensory aids, sleep, hydration, nutrition and mobility, used together to prevent delirium. *(Ch. 8)*

multimodal analgesia: the combined use of medications, procedures and non-drug measures that act on different parts of the pain pathway *(Ch. 5)*

multimorbidity: Living with two or more chronic health conditions at the same time. *(Ch. 1)*

Multinational Association for Supportive Care in Cancer (MASCC) risk index: A validated score prescribers use to estimate the risk of serious complications in febrile neutropenia. *(Ch. 9)*

multiple myeloma: a cancer of plasma cells in the bone marrow that can cause high calcium, kidney problems, anemia and bone disease. *(Ch. 20)*

multiple sclerosis (MS): A chronic autoimmune disease in which the immune system damages myelin in the optic nerves, brain and spinal cord. *(Ch. 32)*

murmur: A heart sound made by turbulent blood flow, described by its timing, location, loudness and quality. *(Ch. 16)*

Murphy sign: A sudden stop in breathing in, caused by pain, when the examiner presses under the right rib margin; a local sign of acute cholecystitis. *(Ch. 26)*

myasthenia gravis (MG): An autoimmune disease in which antibodies block signals at the neuromuscular junction, causing weakness that worsens with use and improves with rest. *(Ch. 32)*

myasthenic crisis: MG weakness that worsens until the person needs intubation, or noninvasive ventilation to prevent intubation. *(Ch. 32)*

myelin: The fatty covering that insulates nerve fibres and lets signals travel quickly. *(Ch. 32)*

myelosuppression: reduced production of blood cells by the bone marrow, causing neutropenia, anemia and thrombocytopenia. *(Ch. 9)*

myocardial infarction (MI): death of heart muscle cells from ischemia, shown by a rise and/or fall in cardiac troponin with at least one value above the 99th percentile plus clinical evidence of ischemia. *(Ch. 17)*

myocarditis: Inflammation of the heart muscle. *(Ch. 18)*

myxedema coma: The most severe form of hypothyroidism, an emergency with a falling level of consciousness, hypothermia, bradycardia, hypoventilation and low sodium. *(Ch. 23)*

Ménière disease: An inner ear disorder with vertigo attacks, each 20 minutes to 12 hours long, with sensorineural hearing loss, tinnitus and a feeling of fullness in the affected ear. *(Ch. 36)*

Métis: A distinct Indigenous People who emerged from the 18th-century fur trade, with their own culture, language (Michif) and nationhood; being Métis is not the same as having mixed ancestry. *(Ch. 2)*

N-acetylcysteine (NAC): The antidote for acetaminophen overdose (marketed in Canada as acetylcysteine), given whenever overdose is suspected, even if the timing is unknown. *(Ch. 26)*

N95 respirator: A close-fitting respirator that filters 95% of particles about 1 micron in size; it must be fit-tested and seal-checked. *(Ch. 4)*

nadir: the lowest point that a blood count reaches after a cancer treatment. *(Ch. 9)*

naloxone: an opioid antagonist that reverses opioid effects, including respiratory depression. *(Ch. 5)*

nasal cannula: Two short prongs in the nostrils that deliver low-flow oxygen; the most common oxygen device. *(Ch. 12)*

nasogastric (NG) tube: A tube passed through the nose and esophagus into the stomach, used for short-term feeding, medications or drainage. *(Ch. 24)*

nasogastric decompression: drainage of swallowed air and gastrointestinal fluid through a nasogastric tube to relieve distension and vomiting. *(Ch. 25)*

nasopharyngeal airway: A soft tube passed through a nostril into the pharynx to keep the upper airway open. *(Ch. 12)*

National Overdose Response Service (NORS): a confidential national phone and text line that provides overdose response for people who use drugs alone. *(Ch. 11)*

natriuretic peptide: A hormone (BNP or NT-proBNP) released by heart muscle under increased wall stress; used in assessing heart failure. *(Ch. 16)*

natriuretic peptides: Hormones (ANP and BNP) released by stretched heart muscle that increase sodium and water excretion and oppose the renin–angiotensin–aldosterone system. *(Ch. 3)*

near miss: A patient safety incident that did not reach the patient. *(Ch. 1)*

nebulizer: A device that turns liquid medicine into a mist breathed in through a mouthpiece or mask. *(Ch. 14)*

neck breather: A person who breathes only through a neck stoma after laryngectomy and cannot be oxygenated or ventilated through the mouth or nose. *(Ch. 12)*

neck hematoma: A collection of blood under a neck incision that can compress the airway; an emergency after thyroid or parathyroid surgery. *(Ch. 23)*

necrotizing soft tissue infection: A rapidly spreading infection that destroys deep tissues such as fat and fascia; a surgical emergency. *(Ch. 35)*

negative feedback: The control loop in which a rising level of a final hormone reduces release of the hormones that stimulate it, and a falling level increases their release. *(Ch. 23)*

negative pressure wound therapy: Wound treatment that uses a sealed dressing connected to a pump that applies suction to the wound. *(Ch. 35)*

neglect: A disorder in which a person does not attend to one side of space or of their own body, most often the left side after a right hemisphere stroke. *(Ch. 31)*

neoadjuvant therapy: treatment given before surgery to shrink a tumour. *(Ch. 9)*

nephron: one of about a million filtering units in each kidney, made up of a glomerulus and a tubule *(Ch. 27)*

nephrostomy tube: a tube placed through the skin of the back into the kidney to drain urine. *(Ch. 28)*

nephrotoxic: able to damage the kidneys, as some drugs and contrast agents can *(Ch. 27)*

neuraxial anesthesia: anesthesia produced by placing local anesthetic near the spinal cord, as in spinal and epidural anesthesia. *(Ch. 7)*

neurogenic shock: low blood pressure with a slow heart rate after a cervical or high-thoracic spinal cord injury, caused by loss of sympathetic tone. *(Ch. 6)*

neuromuscular junction: The site where a motor nerve passes its signal to a muscle fibre. *(Ch. 32)*

neuron: A nerve cell that receives, processes and sends signals; it has a cell body, dendrites and an axon. *(Ch. 30)*

neuropathic pain: pain resulting from damage to, or disease of, the nerves that carry sensation *(Ch. 5)*

neurovascular assessment: A check of blood flow and nerve function in a limb below an injury, cast, splint, bandage or surgical site. *(Ch. 33)*

NEWS2: The National Early Warning Score 2 (Royal College of Physicians, 2017), which scores respiratory rate, oxygen saturation, supplemental oxygen, systolic blood pressure, pulse, level of consciousness (including new confusion) and temperature. *(Ch. 6)*

Next Generation NCLEX (NGN): The version of the NCLEX, launched in April 2023, that uses case studies and new item formats to measure clinical judgment. *(Ch. 1)*

nicotine replacement therapy (NRT): Medication that supplies nicotine without tobacco smoke, as a patch or short-acting forms such as gum and lozenges, to ease withdrawal and cravings. *(Ch. 14)*

nimodipine: A medicine given by the enteral route after aneurysmal subarachnoid hemorrhage to help prevent delayed cerebral ischemia. *(Ch. 31)*

nitrites: Chemicals formed when certain bacteria convert nitrate in urine; a negative result does not rule out bacteriuria. *(Ch. 28)*

no-harm incident: A patient safety incident that reached the patient without detectable harm. *(Ch. 1)*

nociception: the nervous system's process of detecting and encoding harmful stimuli; it is not the same as pain *(Ch. 5)*

nociceptive pain: pain from actual or threatened damage to tissue other than nerves, with a normally working nervous system *(Ch. 5)*

nociceptor: a sensory nerve ending that responds to strong heat, pressure or chemical stimuli and converts them into nerve signals *(Ch. 5)*

nociplastic pain: pain from altered pain processing without clear tissue damage or nerve disease to explain it *(Ch. 5)*

nocturia: waking at night to pass urine. *(Ch. 28)*

non-HDL cholesterol (non-HDL-C): total cholesterol minus HDL cholesterol; the cholesterol in all atherogenic particles. *(Ch. 17)*

Non-Insured Health Benefits (NIHB): An Indigenous Services Canada program that covers specified health benefits, including medical transportation, for registered First Nations and recognized Inuit when other plans do not. *(Ch. 1)*

non-invasive ventilation: Breathing support delivered through a tight-fitting mask rather than a tube in the airway. *(Ch. 15)*

non-rebreather mask: A face mask with a reservoir bag, run at 15 L/min, that delivers a high oxygen concentration to a seriously ill patient. *(Ch. 12)*

non-small cell lung cancer (NSCLC): The group of lung cancers other than small cell, including adenocarcinoma, squamous cell carcinoma and large cell carcinoma. *(Ch. 13)*

noncardiogenic pulmonary edema: Fluid in the alveoli caused by leaky lung capillaries rather than by heart failure or fluid overload. *(Ch. 15)*

noninvasive ventilation (NIV): Breathing support given through a mask rather than a tube in the airway. *(Ch. 32)*

nonsteroidal anti-inflammatory drug (NSAID): a drug that reduces pain and inflammation by blocking cyclooxygenase enzymes *(Ch. 5)*

nonunion: A fracture that fails to heal. *(Ch. 33)*

normal sinus rhythm: A regular rhythm from the SA node at 60 to 100 bpm, with an upright P wave before each QRS, a PR interval of 0.12 to 0.20 seconds and a QRS under 0.12 seconds. *(Ch. 16)*

NSTEMI (non-ST-elevation myocardial infarction): an MI confirmed by troponin without persistent ST elevation on the ECG. *(Ch. 17)*

nucleic acid amplification test: A laboratory test that detects an organism's genetic material; the most sensitive test for chlamydia and gonorrhea. *(Ch. 29)*

nucleic acid amplification test (NAAT): A rapid laboratory test that detects the genetic material of M. tuberculosis in a specimen and can identify rifampin resistance. *(Ch. 13)*

numeric rating scale (NRS): a self-report scale on which the patient rates pain from 0 (no pain) to 10 (worst pain imaginable) *(Ch. 5)*

Nurse Specialized in Wound, Ostomy and Continence (NSWOC): a registered nurse with advanced education and clinical skills in wound, ostomy and continence care. *(Ch. 25)*

nurse-driven catheter removal protocol: A protocol, often a medical directive, that lets nurses remove a urinary catheter when no listed indication remains. *(Ch. 28)*

NYHA functional class: A four-level scale describing how much heart failure symptoms limit activity. *(Ch. 18)*

obesity: a chronic, complex disease in which excess or abnormal body fat harms health. *(Ch. 24)*

obstructive lung disease: Lung disease in which narrowed airways slow the flow of air out of the lungs and trap air, as in asthma and COPD. *(Ch. 14)*

obstructive shock: Shock caused by a physical blockage of blood flow into or out of the heart, as in pulmonary embolism, cardiac tamponade or tension pneumothorax. *(Ch. 6)*

obstructive sleep apnea (OSA): Repeated collapse of the upper airway during sleep that interrupts breathing. *(Ch. 7)*

obturator: A rounded guide placed inside a tracheostomy tube during insertion; kept at the bedside. *(Ch. 12)*

OCAP®: The First Nations principles of Ownership, Control, Access and Possession, which state that First Nations govern data about their communities; a registered trademark of the First Nations Information Governance Centre. *(Ch. 2)*

occult hypoxemia: Low arterial oxygen saturation (below 88%) that is hidden by a pulse oximeter reading in the normal-looking range (92% to 96%). *(Ch. 2)*

offloading: Removing pressure from an area of the body completely, for example by floating the heels off the bed. *(Ch. 35)*

oliguria: an abnormally low urine output *(Ch. 27)*

oncologic emergency: A sudden, life-threatening problem caused by cancer or its treatment that needs immediate recognition and action. *(Ch. 9)*

Ontario Health Team: A group of local providers, such as hospitals, primary care, home and community care and long-term care, that plans and delivers connected care for patients in a local area of Ontario. *(Ch. 1)*

open fracture: A fracture in which the bone breaks through the skin or a wound connects with the break, allowing bacteria to reach the bone. *(Ch. 33)*

open-angle glaucoma: A slowly progressive form of glaucoma that typically causes no symptoms until it is advanced. *(Ch. 36)*

opioid: a drug that acts on the body's opioid receptors to relieve pain; adverse effects include sedation, respiratory depression and constipation. *(Ch. 5)*

opioid agonist treatment (OAT): treatment of opioid use disorder with a long-acting opioid, such as methadone or buprenorphine, that prevents withdrawal and cravings. *(Ch. 5)*

opioid toxicity: a life-threatening depression of breathing and consciousness caused by opioids; often called an opioid overdose or poisoning. *(Ch. 11)*

opioid use disorder (OUD): a problematic pattern of opioid use causing significant problems or distress, diagnosed when at least 2 of 11 criteria occur within a year. *(Ch. 5)*

opioid withdrawal: the symptoms that follow stopping or sharply reducing opioids in a person who is physically dependent on them. *(Ch. 11)*

opioid-induced respiratory depression (OIRD): reduced drive and effort to breathe caused by an opioid, leading to carbon dioxide build-up and possibly respiratory arrest; usually preceded by increasing sedation. *(Ch. 5)*

opioid-naive: describes a patient who has not been taking opioids regularly. *(Ch. 5)*

opportunistic infection: an infection that takes advantage of a weakened immune system. *(Ch. 21)*

optic nerve: The nerve that carries signals from the retina to the brain. *(Ch. 36)*

organ inventory: A respectful record of the reproductive and sex organs a person has at present, used to guide screening and care without assumptions based on gender. *(Ch. 29)*

orolingual angioedema: Swelling of the lips, tongue or throat that can follow thrombolysis and threaten the airway. *(Ch. 31)*

oropharyngeal airway: A curved device placed in the mouth to hold the tongue off the back of the throat in a patient with a markedly reduced level of consciousness. *(Ch. 12)*

orthopnea: Breathlessness when lying flat that eases on sitting up. *(Ch. 18)*

orthostatic hypotension: A fall in systolic blood pressure of at least 20 mm Hg, or diastolic of at least 10 mm Hg, within 3 minutes of standing. *(Ch. 3)*

osmolality: The concentration of dissolved particles per kilogram of water, reported in mOsm/kg. *(Ch. 3)*

osmolarity: The concentration of dissolved particles per litre of solution, reported in mOsmol/L. *(Ch. 3)*

osmosis: Movement of water across a membrane from an area of lower to higher solute concentration. *(Ch. 3)*

osmotherapy: The use of a concentrated solution, such as mannitol or hypertonic saline, to draw water out of brain tissue and lower intracranial pressure. *(Ch. 30)*

osmotic demyelination syndrome (ODS): Damage to the myelin of brain nerve fibres caused by too rapid a rise in serum sodium in chronic hyponatremia. *(Ch. 3)*

osteoarthritis (OA): A progressive disease of the whole joint in which cartilage and underlying bone break down; the most common type of arthritis in Canada. *(Ch. 34)*

osteomyelitis: Infection of the bone. *(Ch. 33)*

osteoporosis: A disease in which bones lose mass and strength and break more easily. *(Ch. 33)*

ostomy: a surgically created opening into the bowel or urinary tract through which stool or urine leaves the body. *(Ch. 25)*

otitis externa: Infection or inflammation of the ear canal, often after water is trapped in the ear; pain worsens when the outer ear is tugged. *(Ch. 36)*

otitis media: Infection or fluid in the middle ear, listed mainly as a cause of hearing loss in childhood; it causes a conductive hearing loss. *(Ch. 36)*

ototoxicity: Damage to the inner ear, affecting hearing, balance or both, caused by a medicine or chemical. *(Ch. 36)*

Ottawa Model for Smoking Cessation: A hospital program that identifies every patient who smokes, provides bedside counselling and medication, and follows patients after discharge. *(Ch. 14)*

outbreak: A rise in cases of an infection above what is expected in a particular place and time, defined for each infection. *(Ch. 4)*

outer ear: The visible ear and the ear canal, ending at the eardrum. *(Ch. 36)*

outpatient parenteral antibiotic therapy (OPAT): Intravenous antibiotic treatment given outside hospital, at home or in a clinic. *(Ch. 18)*

overdiagnosis: detection through screening of a cancer that would never have caused symptoms or death. *(Ch. 9)*

overflow diarrhea: Liquid stool that leaks around a fecal impaction and can be mistaken for ordinary diarrhea. *(Ch. 25)*

overflow incontinence: Leakage from a bladder that overfills because it cannot empty. *(Ch. 28)*

oxygen target range: The SpO2 range the prescriber orders, within which the nurse adjusts oxygen. *(Ch. 12)*

oxygen–hemoglobin dissociation curve: the S-shaped curve relating PaO2 to hemoglobin saturation; flat above about 90% saturation and steep below a PaO2 of about 60 mm Hg. *(Ch. 12)*

P wave: The ECG wave produced by atrial depolarization. *(Ch. 16)*

P/F ratio: The ratio of arterial oxygen pressure (PaO2) to the fraction of inspired oxygen (FiO2), used to grade the severity of hypoxemia and ARDS. *(Ch. 15)*

P2Y12 inhibitor: A drug that blocks the P2Y12 receptor on platelets so they are less able to clump; clopidogrel, ticagrelor and prasugrel are examples. *(Ch. 17)*

$PaCO_2$: The partial pressure of carbon dioxide in arterial blood, the respiratory component of an ABG. *(Ch. 3)*

pain: an unpleasant sensory and emotional experience linked to, or resembling one linked to, actual or potential tissue damage (IASP definition, 2020) *(Ch. 5)*

Pain Assessment in Advanced Dementia (PAINAD) scale: an observational tool scoring five behaviours from 0 to 10 for people living with advanced dementia who cannot self-report *(Ch. 5)*

pain sensitization: A state in which the nervous system amplifies pain signals, so pain is felt more strongly than tissue changes alone would explain. *(Ch. 34)*

palliative approach: The integration of core palliative care principles into everyday care by all providers, early in a serious illness and in every setting, with specialists supporting complex needs. *(Ch. 10)*

palliative care: Care that aims to prevent and relieve suffering and improve quality of life for people who have a life-limiting illness and for those close to them, from diagnosis onward. *(Ch. 10)*

palliative sedation: The closely monitored use of medications to reduce consciousness, in proportion to need, so as to relieve refractory suffering in a person with a life-limiting disease. *(Ch. 10)*

palmar erythema: Redness of the palms, mostly at the base of the thumb and little finger, seen in advanced liver disease. *(Ch. 26)*

pancreatic enzyme replacement therapy (PERT): Capsules of pancreatic enzymes taken with meals and snacks to digest food when the pancreas no longer makes enough enzymes. *(Ch. 26)*

papillary muscle rupture: A tear in a muscle that anchors the mitral valve, causing sudden severe mitral leakage after MI. *(Ch. 17)*

paracentesis: Drainage of ascitic fluid through a needle or catheter in the abdominal wall, for diagnosis or to relieve a large or tense ascites. *(Ch. 26)*

paralytic ileus: a loss of the bowel's propulsive movement without any physical blockage, causing gas and fluid to build up. *(Ch. 25)*

paraneoplastic syndrome: Signs and symptoms caused by substances a tumour releases, such as hormones, rather than by the tumour's direct spread. *(Ch. 13)*

paraplegia: Weakness or paralysis of the trunk, legs or both, sparing the arms, from an injury below the cervical cord. *(Ch. 32)*

parastomal hernia: a bulge of abdominal contents through the abdominal wall opening around a stoma. *(Ch. 25)*

parathyroid hormone (PTH): The hormone from the parathyroid glands that raises blood calcium through bone, the kidneys and activated vitamin D. *(Ch. 23)*

parathyroid hormone–related peptide (PTHrP): A substance released by some tumours that increases bone breakdown and raises blood calcium. *(Ch. 9)*

parathyroidectomy: Surgical removal of one or more overactive parathyroid glands. *(Ch. 23)*

parenteral nutrition: Nutrition given into a vein, used when the gut cannot be used or cannot meet the person's needs. *(Ch. 24)*

Parkinson disease (PD): A chronic, progressive neurologic disease marked by tremor, rigidity, slow movement and poor balance, with many non-motor symptoms. *(Ch. 32)*

paroxysmal nocturnal dyspnea (PND): Waking from sleep suddenly short of breath and needing to sit up. *(Ch. 18)*

partial agonist: a drug, such as buprenorphine, that activates the mu receptor less fully than a full agonist. *(Ch. 5)*

partial-thickness burn: A burn that destroys the epidermis and part of the dermis; superficial partial-thickness burns blister and are very painful, and deep partial-thickness burns usually need surgery. *(Ch. 35)*

partner notification: The process of informing sexual partners of a possible exposure so they can be tested and treated. *(Ch. 29)*

pathologic fracture: A fracture through bone already weakened by disease, such as a tumour that has spread to bone. *(Ch. 33)*

patient safety incident: An event or circumstance that led to, or could have led to, unnecessary harm to a patient. *(Ch. 1)*

patient- and family-centred care: An approach to planning, giving and evaluating care built on partnership among patients, the people they define as family, and health care providers. *(Ch. 1)*

patient-controlled analgesia (PCA): a programmable pump that lets a patient give themselves set doses of analgesic, limited by a lockout interval. *(Ch. 5)*

PAWSS: the Prediction of Alcohol Withdrawal Severity Scale; a 10-item tool that estimates a hospitalized patient's risk of complicated alcohol withdrawal. *(Ch. 11)*

PCA by proxy: unauthorized pressing of a PCA button by someone other than the patient, which bypasses the pump's safety check. *(Ch. 5)*

PDE5 inhibitor: A drug that blocks phosphodiesterase type 5 to improve erections, such as sildenafil, tadalafil or vardenafil; contraindicated with nitrates. *(Ch. 29)*

PE response team (PERT): A group of specialists who advise on treatment choices when pulmonary embolism is intermediate or high risk. *(Ch. 15)*

peak expiratory flow (PEF): The fastest speed of air during a short, sharp blow into a hand-held meter. *(Ch. 14)*

pelvic floor muscle training (PFMT): Repeated, correctly performed contractions of the pelvic floor muscles to improve continence. *(Ch. 28)*

pelvic inflammatory disease: Infection of the uterus, fallopian tubes and nearby pelvic structures, often a complication of chlamydia or gonorrhea. *(Ch. 29)*

pelvic organ prolapse: Descent of the bladder, uterus, top of the vagina or rectum into or beyond the vaginal opening because their supports have weakened. *(Ch. 29)*

penumbra: Brain tissue around the ischemic core that has stopped working but can recover if blood flow returns in time. *(Ch. 31)*

peptic ulcer disease (PUD): a break through the lining of the stomach or duodenum, most often caused by H. pylori or NSAIDs. *(Ch. 24)*

perception: the point at which a person becomes aware of pain, involving areas of the brain for sensation, emotion and thinking *(Ch. 5)*

percutaneous coronary intervention (PCI): A catheter procedure that opens a narrowed or blocked coronary artery, usually with a balloon and a stent. *(Ch. 17)*

percutaneous endoscopic gastrostomy (PEG): A gastrostomy tube placed with the help of an endoscope passed through the mouth into the stomach. *(Ch. 24)*

perforation: erosion of an ulcer through the wall of the stomach or duodenum, letting contents leak into the abdomen; a surgical emergency. *(Ch. 24)*

perfusion: blood flow through the capillaries of the lungs. *(Ch. 12)*

pericardial effusion: An abnormal collection of fluid in the pericardial sac. *(Ch. 18)*

pericardial friction rub: A scratching or grating sound produced by inflamed pericardial layers rubbing together. *(Ch. 18)*

pericardiocentesis: Removal of fluid from the pericardial sac with a needle. *(Ch. 18)*

pericarditis: Inflammation of the pericardium. *(Ch. 18)*

perimenopause: The transition before menopause, when periods change and symptoms often begin; it can start 4 to 8 years before the final period and includes the 12 months after it. *(Ch. 29)*

perioperative nursing: Nursing care given across the whole surgical experience, from the decision to operate through recovery. *(Ch. 7)*

peripheral arterial disease (PAD): narrowing or blockage of the arteries that supply the limbs, usually from atherosclerosis. *(Ch. 19)*

peripheral cyanosis: a bluish colour limited to the fingers, toes or nail beds, usually from slow peripheral blood flow. *(Ch. 12)*

peripheral nerve block: injection of local anesthetic near a nerve or group of nerves that supply one limb or area. *(Ch. 7)*

peripheral neuropathy: nerve damage from prolonged high glucose, mainly in the feet and legs, causing numbness, tingling, pain or loss of protective sensation. *(Ch. 22)*

peripheral sensitization: increased responsiveness of nerve endings near damaged tissue, so they fire more easily *(Ch. 5)*

periprosthetic joint infection: An infection of an artificial joint and the tissue around it. *(Ch. 33)*

peristalsis: Waves of muscle contraction that move food along the GI tract. *(Ch. 24)*

peristomal skin: the skin around a stoma, which should look like the person's skin elsewhere on the abdomen. *(Ch. 25)*

peritoneal dialysis (PD): dialysis at home that uses the peritoneum as the filter, with dialysate drained in and out through an abdominal catheter. *(Ch. 27)*

peritonitis: inflammation of the lining of the abdominal cavity. *(Ch. 24)*

peritonitis (PD-related): infection of the peritoneum in a person on peritoneal dialysis, signalled by cloudy effluent and abdominal pain. *(Ch. 27)*

permanent pacemaker: An implanted device with a pulse generator and leads that senses the heart's activity and paces when the rate is too slow. *(Ch. 16)*

pernicious anemia: an autoimmune disease in which loss of intrinsic factor prevents absorption of vitamin B12 *(Ch. 20)*

person-centred care: care built on knowing the patient as a whole person, honouring their choices and sharing decisions with them and those close to them. *(Ch. 8)*

person-first language: wording that names the person before a condition, such as "person who uses drugs." *(Ch. 11)*

personal amplifier: A small handheld device that makes nearby speech louder through headphones or earphones for a person with hearing loss. *(Ch. 36)*

personal directive: In Alberta, a legal document naming an agent who will make personal decisions that are not financial; it takes effect only after the person is found to lack capacity. *(Ch. 10)*

personal protective equipment (PPE): Clothing and equipment, such as gloves, gowns, masks, respirators and eye protection, that form a barrier between the provider and infectious material. *(Ch. 4)*

personal support worker (PSW): In Ontario, the most common unregulated care provider; PSWs may register voluntarily with the Health and Supportive Care Providers Oversight Authority, which sets no scope of practice. *(Ch. 1)*

pessary: A removable device placed in the vagina to support prolapsed pelvic organs. *(Ch. 29)*

petechiae: tiny, flat, red or purple pinpoint spots caused by bleeding under the skin. *(Ch. 20)*

phantom limb pain: Pain felt in the part of a limb that has been removed. *(Ch. 33)*

pheochromocytoma: a catecholamine-secreting tumour of the adrenal medulla that can cause episodes of high blood pressure, headache, palpitations and sweating. *(Ch. 23)*

phlebitis: Inflammation of a vein, often related to IV therapy. *(Ch. 3)*

photosensitivity: An abnormal skin reaction, such as a rash, after exposure to sunlight. *(Ch. 34)*

physical dependence: the body's adaptation to a drug, so that stopping suddenly or reducing the dose quickly causes withdrawal. *(Ch. 5)*

physiological reserve: the spare capacity that body systems draw on when illness, surgery or other stress adds strain. *(Ch. 8)*

pin-site care: The cleaning and dressing of the skin where external fixator or traction pins enter the body. *(Ch. 33)*

pituitary adenoma: a benign tumour of the pituitary gland that may secrete a hormone, press on nearby structures, or both. *(Ch. 23)*

plaque rupture: a tear in the fibrous cap of a plaque that exposes its core to blood and triggers thrombus formation. *(Ch. 17)*

plasma protein product: a drug made from pooled donor plasma or by recombinant technology, such as albumin, IVIG, PCC or a factor concentrate. *(Ch. 20)*

plateau pressure: The pressure in the alveoli measured during a brief pause at the end of inspiration. *(Ch. 15)*

pleural effusion: An abnormal collection of fluid in the pleural space. *(Ch. 13)*

pleural friction rub: a grating or creaking sound in both phases of breathing, caused by inflamed pleural layers rubbing together. *(Ch. 12)*

pleuritic chest pain: sharp chest pain that worsens with deep breathing or coughing, caused by inflammation of the pleura. *(Ch. 13)*

pleuritic pain: Sharp chest pain that worsens with breathing in. *(Ch. 15)*

Pneumocystis pneumonia (PJP): a fungal lung infection that causes gradually worsening breathlessness, fever, dry cough and hypoxemia in people with low CD4 counts. *(Ch. 21)*

pneumonia: an acute infection of the lung tissue (alveoli and smallest airways) that causes inflammation and fills air spaces with fluid and cells. *(Ch. 13)*

Pneumonia Severity Index (PSI): a pneumonia prediction rule that sorts patients into five risk classes using age, coexisting diseases, vital signs and laboratory values. *(Ch. 13)*

pneumothorax: Air in the pleural space, which causes part or all of the lung to collapse. *(Ch. 15)*

point-of-care glucose testing: bedside measurement of capillary glucose with a meter approved and quality-checked under hospital policy *(Ch. 22)*

point-of-care risk assessment (PCRA): A check made before every patient interaction of the task, the patient and the environment to judge the risk of transmission and choose the right precautions. *(Ch. 4)*

polymyalgia rheumatica: An inflammatory condition of adults aged 50 and older that causes aching and stiffness of the shoulders and hips. *(Ch. 34)*

polypharmacy: The use of many medications at the same time, most often defined as five or more medications daily. *(Ch. 8)*

portal hypertension: Raised pressure in the portal vein system, usually caused by resistance to blood flow through a scarred liver. *(Ch. 26)*

portal vein: The vein that carries blood from the stomach, intestines, pancreas and spleen to the liver. *(Ch. 26)*

positive end-expiratory pressure: Pressure kept in the lungs at the end of each breath to stop alveoli from collapsing. *(Ch. 15)*

positive expiratory pressure (PEP) device: A device that makes the patient breathe out against resistance to help hold airways open; oscillating versions add vibration. *(Ch. 12)*

post-COVID-19 condition: in the WHO definition, symptoms that continue more than 3 months after SARS-CoV-2 infection, last at least 2 months and have no other explanation. *(Ch. 13)*

post-exposure prophylaxis (PEP): a 28-day course of antiretroviral drugs started as soon as possible, and within 72 hours, after a possible exposure to HIV. *(Ch. 21)*

post-fall assessment: A structured assessment after a fall to find injuries, including delayed ones, and the causes of the fall. *(Ch. 8)*

post-fall huddle: A short team meeting held soon after a fall to work out why it happened and change the plan to prevent another. *(Ch. 8)*

post-ictal state: The recovery period after a seizure, when the person may be drowsy or confused. *(Ch. 30)*

post-intensive care syndrome: New or worse physical, cognitive or mental health problems that begin after critical illness and last beyond the hospital stay. *(Ch. 15)*

post-intensive care syndrome–family: Anxiety, acute or posttraumatic stress, depression or complicated grief in family members of a critically ill patient. *(Ch. 15)*

post-mastectomy pain syndrome: Nerve pain in the chest, armpit or arm that persists after healing from breast surgery. *(Ch. 29)*

post-sepsis syndrome: lasting physical, cognitive and psychological problems after surviving sepsis. *(Ch. 4)*

post-stroke depression: Depression that develops after a stroke; about one-third of people show symptoms at some point. *(Ch. 31)*

post-thrombotic syndrome (PTS): lasting pain, swelling, heaviness and skin changes in a leg after DVT. *(Ch. 19)*

post-traumatic amnesia: A stage of recovery after TBI in which awareness is poor and fluctuates, the person is disoriented and new events are not reliably remembered. *(Ch. 32)*

post-void residual (PVR): The volume of urine left in the bladder right after voiding. *(Ch. 28)*

postanesthesia care unit (PACU): A unit that gives short-term, closely monitored care immediately after operations and invasive procedures. *(Ch. 7)*

postherpetic neuralgia: Pain lasting more than 30 days after the rash of herpes zoster begins. *(Ch. 35)*

postoperative: The phase from admission to the recovery area until the patient has recovered. *(Ch. 7)*

postoperative ileus: a temporary slowing of bowel movement after surgery. *(Ch. 7)*

postoperative nausea and vomiting (PONV): nausea, retching or vomiting after anesthesia and surgery. *(Ch. 7)*

postoperative urinary retention: inability to empty a full bladder after surgery. *(Ch. 7)*

postrenal acute kidney injury: AKI caused by blocked outflow of urine *(Ch. 27)*

post–dural puncture headache: A headache that starts in the 5 days after a lumbar puncture, caused by CSF leaking through the puncture, often worse upright and better lying down. *(Ch. 30)*

potentially inappropriate medication (PIM): A drug that, for most older adults, is ineffective, carries an unnecessarily high risk or has a safer alternative. *(Ch. 8)*

pouching system: the skin barrier and pouch that protect the skin and collect stoma output; one-piece or two-piece. *(Ch. 25)*

power of attorney for personal care: In Ontario, a legal document under the Substitute Decisions Act, 1992 that names an attorney to make personal care decisions, including health care, if the person becomes incapable. *(Ch. 10)*

PR interval: The time from the start of the P wave to the start of the QRS complex; normally 0.12 to 0.20 seconds. *(Ch. 16)*

pre-emptive transplant: a kidney transplant done before dialysis has started. *(Ch. 27)*

pre-exposure prophylaxis (PrEP): antiretroviral medication taken by an HIV-negative person before possible exposure to prevent HIV. *(Ch. 21)*

precipitated withdrawal: sudden, often severe withdrawal triggered when naloxone or buprenorphine displaces a full opioid agonist from its receptors. *(Ch. 11)*

prediabetes: impaired fasting glucose, impaired glucose tolerance or an A1C of 6.0% to 6.4%; a high risk of developing diabetes *(Ch. 22)*

predicted body weight: A weight calculated from height and sex and used to set tidal volume. *(Ch. 15)*

prehabilitation: Improving physical and mental fitness in the weeks before surgery to build reserve for recovery. *(Ch. 7)*

preload: how much the ventricle is filled and stretched before it contracts. *(Ch. 6)*

premature ventricular contraction (PVC): An early beat that starts in the ventricles, seen as a wide, oddly shaped QRS with no P wave before it. *(Ch. 16)*

preoperative: The phase from the decision to operate until transfer to the operating room. *(Ch. 7)*

prerenal acute kidney injury: AKI caused by reduced blood flow to the kidneys *(Ch. 27)*

presbycusis: Age-related sensorineural hearing loss that starts at the highest pitches and later spreads to lower ones. *(Ch. 36)*

prescribing cascade: A sequence in which an adverse drug effect is mistaken for a new condition and treated with another drug. *(Ch. 8)*

pressure injury: Localized damage to skin and underlying soft tissue, usually over a bony prominence or under a device, caused by pressure or pressure combined with shear. *(Ch. 35)*

pressurized metered-dose inhaler (pMDI): A device that releases a measured puff of medicine in a propellant spray. *(Ch. 14)*

pretest probability: the estimated likelihood of a disease before testing, used to choose the testing path. *(Ch. 19)*

priapism: A prolonged erection not linked to sexual desire; an erection lasting more than 4 hours is an emergency. *(Ch. 29)*

primary aldosteronism: Excess aldosterone production by the adrenal glands, a cause of secondary hypertension. *(Ch. 19)*

primary brain injury: Damage that occurs at the moment of impact or sudden acceleration and deceleration. *(Ch. 32)*

primary brain tumour: A tumour that starts in the brain or its coverings, as opposed to one that spreads to the brain from elsewhere. *(Ch. 30)*

primary hyperparathyroidism: Excess PTH from one or more parathyroid glands, most often a single benign adenoma, causing high calcium. *(Ch. 23)*

primary hypertension: Hypertension without a single identifiable cause. *(Ch. 19)*

primary intention: Healing of a wound whose edges have been brought together with sutures, staples or tape, without the need to fill with granulation tissue. *(Ch. 35)*

primary PCI: emergency coronary angiography with balloon and stent opening of a blocked artery, without fibrinolysis first. *(Ch. 17)*

primary spontaneous pneumothorax: A pneumothorax in a person with no known lung disease. *(Ch. 15)*

principle of double effect: The ethical principle that an act aimed at a good effect may be acceptable even if a harmful effect is foreseen but not intended, provided the harm is not how the good is achieved and the act is proportionate. *(Ch. 10)*

procalcitonin: A blood marker used with clinical assessment when the likelihood of bacterial infection is uncertain and to help decide when antibiotics can be stopped. *(Ch. 4)*

procedural sedation: the use of drugs to depress consciousness so a patient can tolerate a procedure, on a continuum from minimal to deep sedation. *(Ch. 7)*

professional boundaries: The limits that keep a nurse-patient relationship therapeutic rather than personal; keeping them is always the nurse's responsibility. *(Ch. 1)*

professional interpreter: A trained interpreter who conveys health information accurately and confidentially between languages; preferred over family members. *(Ch. 1)*

progressive (decompensated) shock: The stage of shock in which compensation fails, blood pressure falls and organ hypoperfusion becomes evident. *(Ch. 6)*

progressive multifocal leukoencephalopathy (PML): A rare, serious brain infection caused by the JC virus; a risk with some immune-modifying drugs such as natalizumab. *(Ch. 32)*

prolactinoma: a prolactin-secreting pituitary adenoma, the most common type, usually treated first with a dopamine agonist. *(Ch. 23)*

prolonged grief disorder: A DSM-5-TR diagnosis of intense, disabling grief lasting at least 12 months after a death in adults (6 months in children and adolescents) and exceeding cultural norms. *(Ch. 10)*

prompted voiding: A toileting approach for frail or cognitively impaired people in which staff check regularly, ask about the need to void, help to the toilet and give praise. *(Ch. 28)*

pronator drift: A sign of subtle arm weakness in which one outstretched arm, held palm up with the eyes closed, turns palm-down and drifts downward. *(Ch. 30)*

prone positioning: Placing a ventilated patient face down for long periods to improve gas exchange in severe ARDS. *(Ch. 15)*

pronouncement of death: Determining and recording that a person has died; distinct from certifying the cause of death on the medical certificate of death. *(Ch. 10)*

prostate-specific antigen (PSA): a protein made by the prostate and measured in a blood test, used in prostate cancer screening and follow-up. *(Ch. 28)*

prosthesis: An artificial device that replaces a missing body part. *(Ch. 33)*

prothrombin complex concentrate (PCC): a concentrate of vitamin K–dependent clotting factors used to reverse warfarin and, in Canadian practice, for major bleeding on factor Xa inhibitors. *(Ch. 19)*

proto-oncogene: a normal gene that promotes cell growth and division and can become a cancer-driving oncogene when mutated. *(Ch. 9)*

proton pump inhibitor (PPI): a drug that blocks the final step of acid production in the stomach. *(Ch. 24)*

provoked seizure: A seizure caused by a temporary problem, such as a concussion, a fever or alcohol withdrawal, acting on an otherwise normal brain. *(Ch. 30)*

pruritus: Itching; in liver disease, often caused by cholestasis. *(Ch. 26)*

pseudo-relapse: A short-lived return or worsening of earlier MS symptoms caused by heat, fever, infection or fatigue, without new inflammation. *(Ch. 32)*

pseudohyperkalemia: A falsely high potassium result caused by release of potassium from blood cells after the sample is drawn. *(Ch. 3)*

ptosis: Drooping of the upper eyelid. *(Ch. 32)*

pulmonary embolism (PE): Blockage of the pulmonary artery or one of its branches, usually by a clot from a deep vein thrombosis. *(Ch. 15)*

pulmonary embolism rule-out criteria (PERC): Eight clinical checks used for patients already judged at low risk; a patient who meets all eight needs no further testing for pulmonary embolism. *(Ch. 15)*

pulmonary rehabilitation: A supervised, tailored program of exercise training, education and behaviour change for people with chronic lung disease. *(Ch. 14)*

pulse deficit: The apical rate minus the radial rate, counted at the same time by two nurses; a sign that some beats do not reach the periphery. *(Ch. 16)*

pulse oximetry: a non-invasive method that estimates arterial oxygen saturation (SpO2) from the absorption of red and infrared light by pulsing arterial blood. *(Ch. 12)*

pulse pressure: the difference between the systolic and diastolic blood pressures. *(Ch. 6)*

pulseless electrical activity (PEA): An organized rhythm on the monitor without a palpable pulse; a non-shockable arrest rhythm. *(Ch. 16)*

pulsus paradoxus: An exaggerated fall in systolic blood pressure during inspiration; when an effusion is present, a fall of more than 10 mm Hg suggests tamponade. *(Ch. 18)*

punctal occlusion: Pressing on the inner corner of the eye after instilling a drop to reduce the amount of drug that reaches the bloodstream. *(Ch. 36)*

pupillary response: The size, shape and reaction to light of the pupils; a new unequal or sluggish pupil is an urgent cue. *(Ch. 30)*

purpura: patches of bleeding under the skin that are larger than petechiae. *(Ch. 20)*

pyelonephritis: Infection that has reached the kidney, usually with fever, rigors and flank pain or costovertebral angle tenderness. *(Ch. 28)*

pyuria: White blood cells in the urine; it occurs with both infection and asymptomatic bacteriuria. *(Ch. 28)*

QRS complex: The ECG complex produced by ventricular depolarization; normally under 0.12 seconds wide. *(Ch. 16)*

QT interval: The time from the start of the QRS complex to the end of the T wave; corrected for heart rate as the QTc. *(Ch. 16)*

quick SOFA (qSOFA): a three-item bedside score (respiratory rate 22 or more, altered mentation, systolic blood pressure 100 mm Hg or less); not recommended as a single screening tool. *(Ch. 4)*

race: A social category that sorts people by features such as skin colour, name or origin and ranks them unequally; it is not a biological measure. *(Ch. 2)*

race-free equations: Equations for estimated glomerular filtration rate (eGFR) that do not use race, such as the 2021 CKD-EPI equations. *(Ch. 2)*

racialization: The process by which a society treats races as real and distinct and ranks them unequally, with effects on people's economic, political and social lives. *(Ch. 2)*

racialized: Describes a person or group that society treats as belonging to a race and treats unequally because of it; preferred over older terms such as "visible minority." *(Ch. 2)*

radial access: Entry to the arterial system through the radial artery at the wrist for catheterization or PCI. *(Ch. 17)*

radial artery occlusion: Blockage of the radial artery after radial access, a common complication that patent hemostasis helps prevent. *(Ch. 17)*

radical prostatectomy: surgical removal of the whole prostate and some nearby tissue, including the seminal vesicles. *(Ch. 28)*

radioactive iodine therapy (RAI): An oral dose of radioactive iodine that destroys overactive thyroid tissue. *(Ch. 23)*

radon: A colourless, odourless radioactive gas from the breakdown of uranium in soil and rock; the second leading cause of lung cancer in Canada. *(Ch. 13)*

rapid response team: A team with critical care skills that assesses and treats deteriorating patients on general units before cardiac arrest; in Ontario, often called a Critical Care Response Team (CCRT). *(Ch. 6)*

rapid ventricular response (RVR): A ventricular rate above 100 per minute in atrial fibrillation or flutter. *(Ch. 16)*

rate control: An AF treatment strategy that slows the ventricular rate, usually with beta-blockers, nondihydropyridine calcium channel blockers or digoxin. *(Ch. 16)*

Raynaud phenomenon: Episodes in which small arteries of the fingers or toes spasm in cold or stress, so that the skin changes colour and may feel numb or painful. *(Ch. 34)*

re-expansion pulmonary edema: A rare, potentially fatal fluid build-up in a lung that re-expands quickly after removal of pleural fluid or air. *(Ch. 13)*

reasonably foreseeable natural death: The test that decides which set of MAID safeguards applies; it is no longer an eligibility criterion. *(Ch. 10)*

receptive aphasia: Aphasia in which the person has trouble understanding spoken or written language. *(Ch. 31)*

reciprocal changes: ST depression in leads facing the wall opposite an area of ST elevation, supporting acute coronary occlusion. *(Ch. 17)*

recurrent laryngeal nerve: A nerve running close behind the thyroid that controls the vocal cords; injury can cause hoarseness. *(Ch. 23)*

recurrent toxicity: the return of sedation and slow breathing after naloxone wears off, because most opioids act longer than naloxone. *(Ch. 11)*

red blood cell concentrate: a unit of donated red cells with most plasma and white cells removed. *(Ch. 20)*

reduction: The return of broken bone ends to their normal position, either by hand without an incision (closed) or in surgery (open). *(Ch. 33)*

refeeding syndrome: A fall of 10% or more in serum phosphate, potassium or magnesium, with or without organ dysfunction, within 5 days of starting or increasing nutrition after starvation or malnutrition. *(Ch. 3)*

referred pain: pain felt in a body region away from the site of the harmful stimulus, such as pain from an internal organ felt elsewhere *(Ch. 5)*

refractory (irreversible) shock: Shock that persists despite fluids and vasopressors, with cell and organ damage that may be permanent. *(Ch. 6)*

registered psychiatric nurse: A separately regulated nursing profession, found in the western provinces, Yukon and several other jurisdictions, that also uses the letters RPN. *(Ch. 1)*

regurgitation: Backward leakage of blood through a valve that does not close fully. *(Ch. 18)*

rehabilitation: Coordinated, goal-directed care that helps a person regain function and take part in daily life after illness or injury. *(Ch. 31)*

rejection: an immune attack on a transplanted organ; acute rejection is most common in the first year and may cause no symptoms. *(Ch. 27)*

relapse: In MS, new symptoms or a clear worsening of existing ones lasting at least 24 to 48 hours when no outside factor such as infection or heat explains it. *(Ch. 32)*

reliever: An inhaled medicine that opens narrowed airways within minutes and is used for symptoms. *(Ch. 14)*

remodelling: Changes in the size, shape and function of the heart caused by neurohormonal activation, cell loss and scarring. *(Ch. 18)*

renal colic: severe, often wave-like pain in the back, side, lower abdomen or groin caused by a stone moving through or blocking the ureter. *(Ch. 28)*

renin–angiotensin–aldosterone system (RAAS): A hormone system, started by renin from the kidney, that raises blood pressure and keeps sodium and water. *(Ch. 3)*

reperfusion: restoring blood flow through a blocked coronary artery by primary PCI or fibrinolysis. *(Ch. 17)*

repolarization: The return of heart muscle cells to their resting electrical state after depolarization. *(Ch. 16)*

Required Organizational Practices (ROPs): Standardized patient safety practices that organizations accredited by Accreditation Canada must have in place. *(Ch. 1)*

residential schools: Church-run, government-funded schools that removed at least 150,000 First Nations, Inuit and Métis children from their families to assimilate them; the last federally supported schools closed in the late 1990s. *(Ch. 2)*

residual limb: The part of a limb that remains after amputation. *(Ch. 33)*

respiratory acidosis: An acid–base disorder with a low pH caused by a primary rise in $PaCO_2$ from inadequate breathing. *(Ch. 3)*

respiratory alkalosis: An acid–base disorder with a high pH caused by a primary fall in $PaCO_2$ from excessive breathing. *(Ch. 3)*

respiratory fluoroquinolone: a fluoroquinolone antibiotic, such as levofloxacin or moxifloxacin, that is active against the common bacterial causes of pneumonia. *(Ch. 13)*

respiratory secretions: Saliva and secretions that pool in the upper airway near death, causing noisy breathing (the "death rattle") when the person can no longer swallow or cough effectively. *(Ch. 10)*

respiratory syncytial virus (RSV): a common respiratory virus that can cause severe lower respiratory tract disease in older adults and people with chronic conditions. *(Ch. 13)*

responsive behaviours: actions, words and gestures through which a person living with dementia or another neurological, mental health or substance use condition reacts to something that matters to them in their surroundings, often communicating an unmet need. *(Ch. 8)*

resting tremor: Rhythmic shaking, often of one hand, that is present when the limb is at rest. *(Ch. 32)*

restraint: Anything that restricts a person's movement or behaviour in a way the person cannot easily undo, whether physical, environmental or chemical. *(Ch. 8)*

restrictive lung disease: Lung disease in which stiff lungs or a limited chest wall keep the lungs from filling, so lung volumes are small. *(Ch. 14)*

reticulocyte: a young red blood cell recently released from the marrow; the count shows whether the marrow is responding to anemia *(Ch. 20)*

retina: The light-sensitive layer at the back of the eye, whose photoreceptor cells turn light into electrical signals. *(Ch. 36)*

retinal detachment: Separation of the retina from the back of the eye, signalled by sudden flashes, new floaters and a spreading shadow over vision. *(Ch. 36)*

retrograde ejaculation: flow of semen backward into the bladder rather than out through the urethra, common after TURP. *(Ch. 28)*

retroperitoneal bleeding: Bleeding into the space behind the abdominal organs, a hidden complication of femoral access shown by back or flank pain, rising heart rate and falling blood pressure. *(Ch. 17)*

reversibility: A meaningful improvement in airflow after a bronchodilator or a course of controller treatment; in the CTS asthma guideline, an FEV1 rise of at least 12% and 200 mL. *(Ch. 14)*

revised Atlanta classification: An international system that defines acute pancreatitis and grades it as mild, moderately severe or severe according to organ failure and complications. *(Ch. 26)*

rheumatic heart disease: Lasting heart valve damage after acute rheumatic fever, an immune reaction to group A streptococcal throat infection. *(Ch. 18)*

rheumatoid arthritis (RA): A chronic autoimmune disease that inflames the joint lining, usually in the same joints on both sides of the body, and can affect other organs. *(Ch. 34)*

rheumatoid factor (RF): An antibody often present in rheumatoid arthritis; it also appears in some other conditions and is absent in some people with RA. *(Ch. 34)*

rhonchi: low-pitched, continuous, snoring sounds; used interchangeably with "low-pitched wheeze." *(Ch. 12)*

rhythm control: An AF treatment strategy that restores and maintains sinus rhythm with cardioversion, antiarrhythmic drugs or catheter ablation. *(Ch. 16)*

Richmond Agitation–Sedation Scale: A 10-level scale from +4 (combative) to −5 (unarousable), with 0 meaning alert and calm, used to measure sedation and agitation. *(Ch. 15)*

right ventricular infarction: MI involving the right ventricle, often with inferior STEMI; nitroglycerin is used with great caution or avoided. *(Ch. 17)*

right-sided heart failure: Failure of the right ventricle, raising pressure in the systemic veins and causing edema, a raised JVP and organ congestion. *(Ch. 18)*

rigidity: Stiffness of the muscles felt when another person moves the limb. *(Ch. 32)*

routine practices: The infection prevention and control practices used with every patient during all care, including risk assessment, hand hygiene, personal protective equipment, environmental controls and administrative controls. *(Ch. 1)*

Roux-en-Y gastric bypass: bariatric surgery that creates a small stomach pouch joined to the small intestine, bypassing the rest of the stomach. *(Ch. 24)*

rule of nines: A method of estimating the burned body surface in adults that divides the body into areas of 9% or multiples of 9%. *(Ch. 35)*

S3: An extra heart sound in early diastole, just after S2, from rapid ventricular filling. *(Ch. 16)*

S4: An extra heart sound in late diastole, just before S1; always abnormal. *(Ch. 16)*

safe patient handling: An organized approach that uses assessment, equipment, policy and training to move patients without manual lifting where possible. *(Ch. 33)*

same-day admission: Arrival from home on the morning of surgery, with admission to a surgical unit afterwards. *(Ch. 7)*

SBAR: A structured communication tool: Situation, Background, Assessment, Recommendation. *(Ch. 6)*

scope of practice: The range of activities a nurse is permitted and able to perform safely, shaped by authority, competence and context. *(Ch. 1)*

screening: testing people without symptoms to find cancer or precancerous changes early. *(Ch. 9)*

screening mammogram: An X-ray of the breasts in a person with no symptoms, taken to find breast cancer early. *(Ch. 29)*

secondary brain injury: Further brain damage in the hours and days after injury from low oxygen, poor blood flow, swelling and harmful chemical changes. *(Ch. 32)*

secondary fracture prevention: Care that aims to prevent another fracture after a fragility fracture by finding and treating osteoporosis and reducing falls. *(Ch. 33)*

secondary hypertension: Hypertension caused by an identifiable condition or drug. *(Ch. 19)*

secondary intention: Healing of an open wound that fills with granulation tissue from the base up. *(Ch. 35)*

secondary prevention: Care that lowers the risk of another event in a person who already has coronary disease. *(Ch. 17)*

secondary spontaneous pneumothorax: A pneumothorax in a person with established lung disease, or, under BTS guidance, a person over 50 with a smoking history. *(Ch. 15)*

sedation scale: a structured tool for rating how drowsy a patient is, such as the Pasero Opioid-induced Sedation Scale outside critical care or the Richmond Agitation-Sedation Scale in intensive care. *(Ch. 5)*

seizure: A short-lived event of signs or symptoms caused by abnormal, excessive or synchronized electrical activity of neurons in the brain. *(Ch. 30)*

seizure precautions: Safety measures set by employer policy for patients at risk of seizures. *(Ch. 30)*

self-administered MAID: The form of MAID in which the person takes a substance prescribed or provided by a physician or NP. *(Ch. 10)*

self-care: In heart failure, the daily activities of keeping the condition stable, watching for change and responding to it. *(Ch. 18)*

self-management: The day-to-day skills a person uses to live with a chronic condition, such as taking medicines, pacing activity, solving problems and knowing when to seek help. *(Ch. 34)*

self-regulated profession: A profession that the government allows to govern its own members, on condition that it acts in the public interest; in Ontario, nursing is regulated through the College of Nurses of Ontario. *(Ch. 1)*

sensorineural hearing loss: Hearing loss caused by damage to the cochlea or the hearing nerve; usually permanent. *(Ch. 36)*

sentinel lymph node biopsy: Removal of the first lymph node or nodes that drain a tumour, to check whether cancer has spread to them. *(Ch. 29)*

sepsis: Organ dysfunction that threatens life, caused by the body's dysregulated response to an infection. *(Ch. 4)*

septic arthritis: Infection inside a joint; a single hot, swollen, painful joint is treated as septic arthritis until proven otherwise. *(Ch. 34)*

septic shock: a subset of sepsis with severe circulatory, cellular and metabolic changes; clinically, a vasopressor is needed to keep MAP at 65 mm Hg or higher and lactate is above 2 mmol/L despite adequate fluids. *(Ch. 4)*

Sequential Organ Failure Assessment (SOFA) score: a score that grades dysfunction in six organ systems; a rise of 2 or more points with infection defines sepsis. *(Ch. 4)*

serious illness conversation: A structured discussion with a seriously ill person about understanding, prognosis, goals, fears, sources of strength and acceptable trade-offs, used to guide future care. *(Ch. 10)*

seroma: A collection of fluid under the skin after surgery, such as under the skin flap after mastectomy. *(Ch. 29)*

severe asthma: Asthma that stays uncontrolled despite high-level inhaled treatment, needing specialist assessment. *(Ch. 14)*

sexual health history: A focused set of questions about a person's sexual activity, partners, protection, past sexually transmitted and blood-borne infections, symptoms and reproductive health. *(Ch. 29)*

sexually transmitted and blood-borne infection: An infection spread through sexual contact, blood or both. *(Ch. 29)*

SGLT2 inhibitor: a drug that lowers glucose by making the kidneys excrete it, and protects the heart and kidneys *(Ch. 22)*

shear: The force created when deeper tissue slides in one direction while the skin is held in place by a surface, distorting tissue and blood vessels. *(Ch. 35)*

shock: A life-threatening failure of the circulation in which cells cannot get or use enough oxygen. *(Ch. 6)*

shock wave lithotripsy (SWL): use of shock waves from outside the body to break a stone into fragments that pass in the urine. *(Ch. 28)*

short-acting beta2-agonist (SABA): A reliever, such as salbutamol, that relaxes airway smooth muscle within minutes. *(Ch. 14)*

short-acting muscarinic antagonist (SAMA): A short-acting bronchodilator, such as ipratropium, that blocks the nerve signals that tighten airway muscle. *(Ch. 14)*

shunt: blood flow past alveoli that receive no air, so the blood returns to the heart without gaining oxygen. *(Ch. 12)*

sick-day medication guidance: advice on which medications to pause for a short time when a person with diabetes is ill and cannot keep up fluids. *(Ch. 22)*

sick-day rules: instructions for people who take glucocorticoids to increase the dose during illness and to use an emergency injection when tablets cannot be taken. *(Ch. 23)*

sickle cell disease: inherited disorders in which hemoglobin S makes red cells rigid and sickle-shaped, causing hemolysis and blocked blood vessels *(Ch. 20)*

sickle cell trait: carrying one hemoglobin S gene; carriers generally do not have the disease but can pass the gene on *(Ch. 20)*

sighted guide: A technique for walking with a person who is blind or partially sighted, in which the person holds the guide's arm just above the elbow and walks about half a step behind. *(Ch. 36)*

silent aspiration: Aspiration that occurs without coughing or other obvious signs. *(Ch. 24)*

silent chest: A life-threatening sign in asthma in which so little air moves that wheeze can no longer be heard. *(Ch. 14)*

single-pill combination: A tablet that contains two or more blood-pressure-lowering drugs. *(Ch. 19)*

sinoatrial (SA) node: The heart's normal pacemaker, in the high right atrium; its cells fire faster than any others. *(Ch. 16)*

sinus bradycardia: A sinus rhythm slower than normal; the 2018 ACC/AHA/HRS guideline defines it as a sinus rate below 50 per minute. *(Ch. 16)*

sinus tachycardia: A sinus rhythm faster than 100 per minute, usually a response to another problem such as fever, pain or low blood volume. *(Ch. 16)*

site marking: Marking the operative site on the patient's skin before surgery, as policy requires, to prevent wrong-site surgery. *(Ch. 7)*

Sixties Scoop: The removal of many Indigenous children from their families by child welfare authorities, from about the 1960s to the 1980s, and their placement in non-Indigenous foster and adoptive homes. *(Ch. 2)*

Sjögren disease: A systemic autoimmune disease marked by dry eyes and dry mouth, with fatigue, pain and sometimes involvement of other organs. *(Ch. 34)*

skin graft: Healthy skin moved from one part of the body (the donor site) to cover a wound. *(Ch. 35)*

skin tear: A traumatic wound caused by mechanical force, such as handling or adhesive removal, that does not go through the subcutaneous layer; classified as ISTAP Type 1, 2 or 3. *(Ch. 35)*

sleeve gastrectomy: bariatric surgery that removes a large part of the stomach, leaving a narrow tube. *(Ch. 24)*

sliding-scale insulin: a correction-only approach that gives insulin only after glucose is already high; discouraged as the sole treatment in hospital. *(Ch. 22)*

slough: Soft, moist dead tissue in a wound that may be yellow, tan or grey. *(Ch. 35)*

small cell lung cancer (SCLC): A fast-growing lung cancer, about 15% of cases, that has usually spread by the time it is diagnosed. *(Ch. 13)*

snooping: Accessing a person's health information without a professional reason; a privacy breach whatever the motive. *(Ch. 1)*

social determinants of health: The everyday conditions in which people live and work, such as income, education, work, housing, social support and freedom from discrimination and violence. *(Ch. 2)*

sodium–glucose cotransporter 2 (SGLT2) inhibitor: A drug that makes the kidneys excrete glucose and sodium; reduces heart failure hospitalization across ejection fraction categories. *(Ch. 18)*

soft mist inhaler: A device that releases a slow-moving mist of liquid medicine during a slow, deep breath. *(Ch. 14)*

somatic pain: nociceptive pain arising in skin, muscle, bone or joints, often well localized *(Ch. 5)*

spacer: A tube, often with a valve (valved holding chamber), that attaches to a pMDI and holds the puff so it can be breathed in without precise timing. *(Ch. 14)*

spasticity: Increased muscle tone with involuntary spasms and overactive reflexes after damage to the brain or spinal cord. *(Ch. 32)*

speaking valve: A one-way valve on a tracheostomy tube that lets air in and directs exhaled air up through the larynx for speech; used only with the cuff deflated. *(Ch. 12)*

specialist palliative care: Care given by interprofessional teams with advanced palliative training, usually for patients with complex needs. *(Ch. 10)*

speech-language pathologist (SLP): A regulated health professional who assesses swallowing and recommends food textures, drink thickness and swallowing strategies. *(Ch. 24)*

spider angioma: A small red spot with fine vessels radiating outward that fades when the centre is pressed; seen in advanced liver disease. *(Ch. 26)*

spinal anesthesia: a single injection of local anesthetic into the cerebrospinal fluid that numbs and weakens the lower body. *(Ch. 7)*

spinal cord injury (SCI): Damage to the spinal cord that interrupts messages between the brain and the body below the injury. *(Ch. 32)*

spinal fusion: Surgery that joins two or more vertebrae with a bone graft, often held with screws and rods, so that they heal as one bone. *(Ch. 33)*

spinal motion restriction: Keeping the spine as still as possible, for example with a cervical collar and careful movement, when a spine injury is possible. *(Ch. 32)*

spinal shock: A temporary state, beginning immediately after a spinal cord injury, in which spinal reflexes are lost below the injury. *(Ch. 32)*

spirometry: A breathing test that measures how much air a person can blow out after a full breath in, and how fast. *(Ch. 14)*

splinting: Pressing a pillow or hands over an incision to reduce pain during coughing or movement. *(Ch. 7)*

spontaneous awakening trial: A planned daily pause in sedation to let the patient wake. *(Ch. 15)*

spontaneous bacterial peritonitis (SBP): Infection of ascitic fluid without an obvious source, diagnosed by a fluid neutrophil count above 250/mm³. *(Ch. 26)*

spontaneous breathing trial: A daily test in which the ventilated patient breathes with little or no ventilator support to judge readiness for extubation. *(Ch. 15)*

spore: a dormant, hardy form of a bacterium that survives for months on surfaces and resists many disinfectants; hand washing with soap and water is preferred because it physically removes spores. *(Ch. 4)*

squamous cell carcinoma: A skin cancer that starts in the flat squamous cells of the outer epidermis. *(Ch. 35)*

stable angina: predictable chest discomfort brought on by exertion or emotional stress and eased by rest or nitroglycerin, caused by a fixed coronary narrowing. *(Ch. 17)*

stage: a description of the size and extent of a cancer in the body, including spread to lymph nodes or distant sites. *(Ch. 9)*

standard induction: starting buprenorphine after other opioids have been stopped and withdrawal is clearly present. *(Ch. 11)*

stapedectomy: Surgery that replaces a stapes bone that cannot move with a tiny piston to improve hearing. *(Ch. 36)*

Starling forces: The hydrostatic and oncotic pressures that govern fluid movement between plasma and the interstitial space. *(Ch. 3)*

statin: a lipid-lowering drug that is the first-line treatment for people with ASCVD or another statin-indicated condition. *(Ch. 17)*

status epilepticus: A seizure that lasts too long, or repeated seizures without recovery between them; for a convulsive seizure, treatment starts at 5 minutes. *(Ch. 30)*

steatorrhea: Bulky, greasy, foul-smelling stools caused by undigested fat. *(Ch. 26)*

steatotic liver disease: The umbrella term for fat build-up in the liver from any cause. *(Ch. 26)*

stem cell transplant: replacement of blood-forming stem cells with the patient's own (autologous) or a donor's (allogeneic) stem cells. *(Ch. 20)*

STEMI (ST-elevation myocardial infarction): an MI with new ST elevation in at least two contiguous leads, usually from acute occlusion of a coronary artery. *(Ch. 17)*

stenosis: Narrowing and stiffening of a valve opening that obstructs forward blood flow. *(Ch. 18)*

stent: A small mesh tube left in a coronary artery to hold it open after PCI. *(Ch. 17)*

stent thrombosis: A clot that forms inside a stent and suddenly blocks the artery; it presents like a new MI. *(Ch. 17)*

sternal precautions: Limits on arm and upper-body movement that protect the breastbone while it heals after sternotomy. *(Ch. 17)*

steroid emergency card: a card carried by a person who depends on glucocorticoids, telling health care providers how to recognize and treat adrenal crisis. *(Ch. 23)*

Stevens-Johnson syndrome: a severe, usually drug-induced reaction in which the epidermis dies and separates over less than 10% of the body surface, with mucosal ulcers. *(Ch. 21)*

stigma: negative attitudes, beliefs and behaviours directed at a group because of their situation, expressed as stereotypes, prejudice and discrimination at self, social and structural levels. *(Ch. 11)*

stimulant toxicity: an exaggerated sympathetic response to a stimulant, with agitation, fast heart rate, high blood pressure, high body temperature and possible seizures or psychosis. *(Ch. 11)*

stoma: the end of bowel brought through the abdominal wall and folded back at the skin; healthy stomas are moist and pink to red. *(Ch. 25)*

stoma site marking: choosing and marking the best location for a planned stoma before surgery, with the person sitting, standing and bending. *(Ch. 25)*

STOP-Bang: An eight-item yes-or-no screening questionnaire for obstructive sleep apnea. *(Ch. 7)*

STOPP/START: European criteria that flag drugs that may harm older adults (STOPP) and helpful drugs that may have been missed (START); version 3 was published in 2023. *(Ch. 8)*

strangulation: loss of blood supply to a trapped segment of bowel, leading to ischemia, necrosis and perforation; a surgical emergency. *(Ch. 25)*

stress incontinence: Leakage of urine with coughing, sneezing, laughing, lifting or other exertion. *(Ch. 28)*

striae: stretch marks; in Cushing syndrome they may be wide, appearing red to purple on lighter skin and often brown to black on darker skin. *(Ch. 23)*

stridor: a loud, high-pitched, musical sound, mainly on breathing in, that signals a narrowed upper airway and is an emergency. *(Ch. 12)*

stroke: A sudden loss of brain, spinal cord or retinal function caused by a blocked or bleeding blood vessel, with evidence of injury on imaging. *(Ch. 31)*

stroke mimic: A condition, such as low blood glucose, seizure or migraine, that causes sudden stroke-like signs but is not a stroke. *(Ch. 31)*

stroke unit: A hospital unit in one fixed location, set aside for people with stroke, where a stroke-trained interprofessional team provides care. *(Ch. 31)*

stroke volume: the volume of blood the ventricle ejects with each beat. *(Ch. 6)*

structural determinants of health: The large systems, laws, policies and institutional practices, such as governments, labour markets and health, education, immigration and financial systems, that shape how resources and opportunities are distributed and so shape the social determinants. *(Ch. 2)*

subarachnoid hemorrhage (SAH): Bleeding into the space between the brain and its thin covering membranes, often from a ruptured aneurysm. *(Ch. 31)*

subclinical hypothyroidism: A TSH above the reference range with a normal free T4. *(Ch. 23)*

subcutaneous emphysema: air trapped under the skin, felt as crackling under the fingertips. *(Ch. 12)*

subdural hematoma: A collection of blood between the dura and the surface of the brain; it may be acute or chronic. *(Ch. 32)*

Subjective Global Assessment (SGA): A structured bedside assessment that classifies nutrition status using weight change, intake, symptoms, function and physical signs of muscle and fat loss. *(Ch. 24)*

substance use disorder: a health condition in which a person keeps using a substance despite significant problems linked to that use, diagnosed when at least 2 of 11 criteria occur within 12 months and graded mild, moderate or severe. *(Ch. 11)*

substitute decision-maker (SDM): The person who makes a treatment decision for a patient who is incapable for that decision, chosen according to the ranked list in Ontario's Health Care Consent Act, 1996. *(Ch. 1)*

substitute decision-making: An approach in which another person makes a decision on behalf of a person who is incapable of making it. *(Ch. 2)*

sudden sensorineural hearing loss (SSNHL): A rapid sensorineural hearing loss developing over up to 72 hours, commonly defined as a loss of 30 dB or more across three neighbouring pitches; an urgent problem. *(Ch. 36)*

superficial burn: A burn involving only the epidermis; the skin is intact, painful and without blisters. *(Ch. 35)*

superficial vein thrombosis (SVT): a clot with inflammation in a vein near the skin surface. *(Ch. 19)*

superior vena cava syndrome: Swelling of the face, neck and arms with shortness of breath caused by narrowing of the superior vena cava by a tumour or clot. *(Ch. 9)*

supervised consumption site: a service where people use drugs they bring with them in the presence of trained staff who can respond to an overdose; it operates under a federal exemption. *(Ch. 11)*

support surface: A mattress, overlay or cushion designed to redistribute pressure; it does not replace repositioning. *(Ch. 35)*

supported decision-making: An approach in which trusted people help a person understand choices and express a decision, while the decision remains the person's own. *(Ch. 2)*

supraventricular tachycardia (SVT): A regular, narrow-complex tachycardia that starts above the ventricles, often from a loop involving the AV node. *(Ch. 16)*

surgical aortic valve replacement (SAVR): Open-heart surgery to replace the aortic valve. *(Ch. 18)*

surgical menopause: Menopause that begins abruptly when both ovaries are removed before natural menopause. *(Ch. 29)*

Surgical Safety Checklist: A structured set of checks completed aloud by the whole surgical team at three set points during each operation. *(Ch. 7)*

surgical site infection: An infection of a surgical incision or of the deeper tissues or organ space after an operation. *(Ch. 35)*

survivorship care plan: A written summary of a person's cancer diagnosis and treatment with a plan for follow-up, signs to report, late effects and wellness. *(Ch. 9)*

sustained virologic response: No hepatitis C virus found in the blood 12 weeks after treatment ends; considered a cure. *(Ch. 26)*

swallowing screen: A brief pass-or-fail check, done by a trained team member with a validated protocol, that identifies people who need a full swallowing assessment. *(Ch. 24)*

symptom-triggered treatment: giving withdrawal medication when a patient's withdrawal score reaches a set threshold, rather than on a fixed schedule. *(Ch. 11)*

symptomatic intracranial hemorrhage: Bleeding in the brain that worsens the person's condition, the most serious complication of thrombolysis. *(Ch. 31)*

synchronized cardioversion: A shock timed to the QRS complex, used for tachycardias with a pulse. *(Ch. 16)*

syndrome of inappropriate antidiuretic hormone secretion (SIADH): Continued ADH action despite dilute plasma, causing water retention and hyponatremia in a patient with normal volume status. *(Ch. 3)*

synovial joint: A freely movable joint in which cartilage-covered bone ends sit inside a capsule lined with synovium and filled with synovial fluid. *(Ch. 34)*

synovitis: Inflammation of the synovium, the lining of a synovial joint. *(Ch. 34)*

synovium: The inner lining of a joint capsule, which makes the fluid that lubricates the joint and nourishes the cartilage. *(Ch. 34)*

syphilis: A sexually transmitted infection caused by Treponema pallidum that progresses through primary, secondary, latent and tertiary stages. *(Ch. 29)*

systemic inflammatory response syndrome (SIRS): a set of criteria (temperature, heart rate, respiratory rate, white cell count) once used to define sepsis; no longer part of the definition. *(Ch. 4)*

systemic lupus erythematosus: A chronic autoimmune disease in which antibodies against the body's own cell parts cause inflammation in many organs. *(Ch. 34)*

systemic sclerosis: A rare autoimmune disease that damages small blood vessels and causes thickening and scarring of the skin and internal organs. *(Ch. 34)*

systemic vascular resistance: the resistance to blood flow created by the tone of the small arteries. *(Ch. 6)*

systolic dysfunction: Weak contraction of the ventricle, so a smaller share of its blood is ejected with each beat. *(Ch. 18)*

tactile fremitus: the vibration felt through the chest wall when a patient speaks. *(Ch. 12)*

takotsubo cardiomyopathy: Sudden, temporary weakness of the left ventricle, usually triggered by emotional or physical stress, that can mimic a myocardial infarction; also called stress cardiomyopathy. *(Ch. 18)*

target-organ damage: Injury to the brain, eyes, heart, kidneys or large arteries caused by high blood pressure. *(Ch. 19)*

targeted interventions: Fall prevention measures matched to a person's own risk factors, such as scheduled toileting, supervised mobility or medication review. *(Ch. 8)*

targeted therapy: treatment that acts on specific proteins that drive the growth and spread of cancer cells. *(Ch. 9)*

TB disease: Active illness from M. tuberculosis multiplying in the body; TB disease in the lungs or larynx can spread to others. *(Ch. 13)*

TB infection: A state in which M. tuberculosis is alive but held in check by the immune system; the person has no symptoms and cannot spread TB (formerly called latent TB infection). *(Ch. 13)*

teach-back: A technique in which the patient or caregiver explains or shows, in their own words, what they have been taught; it checks how clearly the nurse taught. *(Ch. 1)*

telemetry: Continuous ECG monitoring that sends the signal from a wireless transmitter to a central station. *(Ch. 16)*

telestroke: A video assessment by a stroke physician at another centre to support treatment and transfer decisions. *(Ch. 31)*

tenesmus: A painful feeling of needing to pass stool even when the rectum is empty. *(Ch. 25)*

tension pneumothorax: air trapped in the pleural space under rising pressure, which collapses the lung and impairs blood return to the heart. *(Ch. 6)*

terminal delirium: Delirium in the last days of life that is part of the dying process and usually not reversible; care focuses on comfort and safety. *(Ch. 10)*

terminal restlessness: Agitation or delirium in the last days of life that has no reversible cause. *(Ch. 10)*

tetraplegia: Weakness or paralysis of the arms, trunk and legs from an injury to the cervical spinal cord. *(Ch. 32)*

texture-modified diet: A diet that changes food texture, drink thickness or both to make swallowing safer. *(Ch. 24)*

thalassemia: inherited disorders in which too little of one hemoglobin protein chain is made *(Ch. 20)*

third spacing: A shift of fluid out of the circulation into spaces where it cannot support blood pressure, such as the bowel, abdomen or inflamed tissue. *(Ch. 3)*

third-degree AV block: Complete AV block in which no atrial impulses reach the ventricles, so P waves and QRS complexes are unrelated. *(Ch. 16)*

thoracentesis: Removal of fluid from the pleural space with a needle or small catheter, for diagnosis or relief of symptoms. *(Ch. 13)*

three-way catheter: an indwelling urinary catheter with separate channels for the balloon, drainage and irrigation inflow. *(Ch. 28)*

thrill: the vibration felt over a working fistula or graft; normally soft and continuous. *(Ch. 27)*

thrombocytopenia: a platelet count below the laboratory's reference range, from decreased production or from increased destruction, consumption or sequestration of platelets. *(Ch. 20)*

thrombolysis: Treatment with a drug that dissolves a blood clot, such as alteplase. *(Ch. 15)*

thrombophilia: An inherited or acquired tendency for blood to clot more readily than normal. *(Ch. 15)*

thunderclap headache: A severe headache that reaches its peak almost at once; it needs emergency assessment. *(Ch. 30)*

thyroid eye disease: An autoimmune disorder of the tissues around the eyes, closely linked to Graves disease, that causes eyelid retraction, proptosis, swelling and double vision. *(Ch. 23)*

thyroid storm: Life-threatening thyrotoxicosis with failure of one or more organs, usually triggered by another illness. *(Ch. 23)*

thyroid-stimulating hormone (TSH): The pituitary hormone that drives the thyroid to make thyroid hormone; the most reliable single test of thyroid function in most people. *(Ch. 23)*

thyroidectomy: Surgical removal of all (total) or part of the thyroid gland. *(Ch. 23)*

thyrotoxicosis: The state caused by too much thyroid hormone acting on the tissues, whatever the cause. *(Ch. 23)*

tidal volume: The volume of air delivered with each breath. *(Ch. 15)*

tidalling: The rise and fall of fluid in the water seal or tubing with breathing, which shows that a chest drain is open to the pleural space. *(Ch. 15)*

time in range: the percentage of CGM readings between 3.9 and 10.0 mmol/L *(Ch. 22)*

time-out: The checklist phase completed just before the skin incision, in which the team confirms patient, procedure and site aloud. *(Ch. 7)*

tinnitus: The perception of sound, such as ringing, buzzing or hissing, with no outside source. *(Ch. 36)*

TNM: an international staging system describing the primary tumour (T), regional lymph nodes (N) and distant metastasis (M). *(Ch. 9)*

tolerance: the need for more of a drug to produce the same effect after repeated use. *(Ch. 5)*

tonic-clonic seizure: A seizure with a stiffening phase followed by rhythmic jerking of the limbs. *(Ch. 30)*

tonicity: The effect of a fluid on cell volume, determined by solutes that cannot cross cell membranes freely. *(Ch. 3)*

tophus: A firm, chalk-like deposit of urate crystals under the skin, often on the ear, elbow or finger pads (plural tophi). *(Ch. 34)*

total body surface area: The whole skin surface of the body, used as the basis for expressing the extent of a burn as a percentage (TBSA). *(Ch. 35)*

total hip arthroplasty: Surgery that replaces the femoral head and lines the hip socket with artificial parts. *(Ch. 33)*

total knee arthroplasty: Surgery that resurfaces the worn ends of the femur and tibia, and often the kneecap, with artificial parts. *(Ch. 33)*

total pain: Cicely Saunders's concept of suffering with physical, psychological, social, emotional and spiritual parts. *(Ch. 10)*

toxic epidermal necrolysis: the most extensive form of the same reaction as Stevens-Johnson syndrome, with detachment of more than 30% of the body surface. *(Ch. 21)*

toxic megacolon: Marked widening of an inflamed colon, seen on X-ray, with systemic illness and a risk of perforation. *(Ch. 25)*

tracheostomy: A surgical opening into the front of the trachea, held open by a tube. *(Ch. 12)*

Track 1: The MAID pathway for a person whose natural death is reasonably foreseeable. *(Ch. 10)*

Track 2: The MAID pathway for a person whose natural death is not reasonably foreseeable; it adds consultation with an expert when neither assessor has expertise in the condition, discussion of other means of relief and at least 90 clear days from the first assessment to provision. *(Ch. 10)*

track-and-trigger system: A system in which nurses track a patient's early warning score over time and preset scores trigger a defined response, such as more frequent monitoring or urgent review. *(Ch. 6)*

traction: A pulling force applied to a limb, through the skin or through a pin in the bone, to restore and keep a broken bone's alignment and length. *(Ch. 33)*

traditional tobacco: Tobacco used by many First Nations as a sacred medicine in ceremony, offerings and gifts; distinct from commercial tobacco. *(Ch. 14)*

transcatheter aortic valve implantation (TAVI): Placement of a replacement aortic valve through a catheter, usually inserted in the femoral artery. *(Ch. 18)*

transcatheter edge-to-edge repair (TEER): A catheter-delivered clip that joins the mitral valve leaflets to reduce regurgitation. *(Ch. 18)*

transcutaneous pacing: Emergency pacing through adhesive pads on the chest, used as a bridge to transvenous or permanent pacing. *(Ch. 16)*

transduction: the conversion of a harmful stimulus into an electrical signal by nociceptors *(Ch. 5)*

transfusion reaction: any harmful response to a blood component or product. *(Ch. 20)*

transfusion-associated circulatory overload (TACO): fluid overload from transfusion, during or up to 12 hours after it, that causes breathlessness and signs of volume overload such as pulmonary edema. *(Ch. 20)*

transfusion-related acute lung injury (TRALI): sudden lung injury, with fluid in the lungs that is not caused by heart failure, during a transfusion or within 6 hours after it. *(Ch. 20)*

transgender: Describes a person whose gender identity differs from the sex they were assigned at birth. *(Ch. 2)*

transient ischemic attack (TIA): A brief episode of stroke-like symptoms caused by ischemia, with no infarct on imaging; symptoms resolve within 24 hours, usually within an hour. *(Ch. 31)*

transition in care: Any move of a patient between settings or care teams, including admission, transfer and discharge. *(Ch. 1)*

transitions of care: Moves of a patient from one setting or team to another, such as from the stroke unit to rehabilitation or home. *(Ch. 31)*

transmission: the movement of pain signals from the periphery through the spinal cord to the brain *(Ch. 5)*

transsphenoidal surgery: removal of a pituitary tumour through the nose and sphenoid sinus. *(Ch. 23)*

transudate: Low-protein pleural fluid caused by pressure or low blood protein, as in heart failure. *(Ch. 13)*

transurethral resection of bladder tumour (TURBT): removal of a bladder tumour through a scope passed into the bladder, with a sample of the muscle beneath. *(Ch. 28)*

transurethral resection of the prostate (TURP): removal of the inner prostate tissue with an electrical wire loop passed through the urethra. *(Ch. 28)*

transurethral resection syndrome (TUR syndrome): dilutional hyponatremia and fluid overload caused by absorption of irrigating fluid during transurethral surgery. *(Ch. 28)*

trauma- and violence-informed care (TVIC): An approach to care that recognizes the links between violence, trauma and health, including ongoing and structural violence, and focuses on creating safety, choice and control without requiring disclosure. *(Ch. 2)*

traumatic brain injury (TBI): Damage to the brain from an outside force, such as a blow to the head or a jolt that moves the brain quickly inside the skull. *(Ch. 32)*

treat-to-target: An approach that sets a goal such as remission, measures disease activity regularly and adjusts treatment until the goal is reached. *(Ch. 34)*

trichomoniasis: A sexually transmitted infection caused by the parasite Trichomonas vaginalis. *(Ch. 29)*

triple therapy: Maintenance treatment with a LAMA, a LABA and an ICS, usually in one inhaler, for people with COPD at high risk of exacerbations. *(Ch. 14)*

troponin: A blood marker of heart muscle injury; a raised level in pulmonary embolism suggests right ventricular strain. *(Ch. 15)*

Trousseau's sign: Spasm of the hand and wrist within 3 minutes of inflating a blood pressure cuff above systolic pressure; a sign of hypocalcemia. *(Ch. 3)*

true urine output: during bladder irrigation, the total volume drained minus the volume of irrigation instilled. *(Ch. 28)*

tuberculin skin test (TST): A test in which purified protein derivative is injected into the skin and the induration is measured 48 to 72 hours later to detect TB infection. *(Ch. 13)*

tuberculosis (TB): An infection caused by Mycobacterium tuberculosis that spreads through the air and most often affects the lungs. *(Ch. 13)*

tumour lysis syndrome (TLS): Metabolic imbalances (high potassium, phosphate and uric acid, low calcium) and possible kidney injury caused by the rapid breakdown of many cancer cells. *(Ch. 9)*

tumour marker: a substance made by cancer cells, or by the body in response to cancer, that can be measured to help monitor the disease. *(Ch. 9)*

tumour suppressor gene: a gene that normally slows cell division, repairs DNA or triggers apoptosis; loss of its function allows uncontrolled growth. *(Ch. 9)*

tunnelling: A narrow channel extending from a wound into deeper tissue. *(Ch. 35)*

Two-Spirit: An English umbrella term used by some Indigenous people for an identity rooted in their own cultures, which may include gender, spiritual and sexual identity. *(Ch. 2)*

tympanic membrane: The eardrum, the thin membrane at the end of the ear canal that vibrates with sound. *(Ch. 36)*

tympanoplasty: Surgery to repair a hole in the eardrum. *(Ch. 36)*

type 1 diabetes: diabetes caused mainly by destruction of the pancreatic beta cells, usually autoimmune, leading to insulin deficiency and a tendency to ketoacidosis *(Ch. 22)*

type 2 diabetes: diabetes caused by insulin resistance together with a beta-cell defect that leaves insulin output too low *(Ch. 22)*

type 2 myocardial infarction: MI caused by an imbalance between the heart's oxygen supply and demand, such as severe anemia or hypotension, without acute plaque disruption. *(Ch. 17)*

ulcerative colitis (UC): A form of IBD limited to the colon, starting in the rectum and spreading upward without gaps, that inflames the inner lining. *(Ch. 25)*

ultrafiltration: removal of extra water from the blood by pressure during dialysis. *(Ch. 27)*

undermining: Tissue destroyed under intact skin at a wound's edge, forming a shelf. *(Ch. 35)*

undetectable = untransmittable (U=U): the scientific consensus that a person living with HIV who takes treatment and keeps a viral load below 200 copies/mL does not transmit HIV through sex. *(Ch. 21)*

unfractionated heparin (UFH): an anticoagulant given IV or subcutaneously that boosts antithrombin; monitored by aPTT or anti-Xa level. *(Ch. 19)*

United Nations Declaration on the Rights of Indigenous Peoples (UNDRIP): A declaration adopted by the United Nations General Assembly in 2007, which sets minimum standards for Indigenous rights, including the right to traditional medicines and to health services without discrimination (Article 24). *(Ch. 2)*

universal fall precautions: Basic safety measures used for every patient regardless of fall risk, such as a low, locked bed, a call bell within reach, good lighting and non-slip footwear. *(Ch. 8)*

unregulated care provider (UCP): A care provider who is not regulated under the Regulated Health Professions Act, 1991 and has no legally defined scope of practice; in Ontario, most often a personal support worker. *(Ch. 1)*

unregulated drug supply: drugs made and sold outside legal and quality controls, often containing fentanyl and other toxic substances of unknown strength. *(Ch. 11)*

unstable angina: myocardial ischemia at rest or on minimal exertion without heart muscle cell death. *(Ch. 17)*

unstageable pressure injury: A full-thickness pressure injury whose depth cannot be seen because slough or eschar covers the base. *(Ch. 35)*

upper gastrointestinal bleeding (UGIB): bleeding from the esophagus, stomach or duodenum. *(Ch. 24)*

urate-lowering therapy: A long-term medicine, such as allopurinol, that lowers the body's urate level to dissolve crystals and prevent gout flares. *(Ch. 34)*

uremia: the effects of wastes retained when the kidneys fail, such as reduced appetite, nausea, fatigue and itch, and in severe cases bleeding, encephalopathy and pericarditis *(Ch. 27)*

ureteral stent: a thin, flexible tube placed in the ureter, from the kidney to the bladder, to keep urine draining. *(Ch. 28)*

ureteroscopy: passing a thin scope through the urethra and bladder into the ureter to break up or remove a stone. *(Ch. 28)*

urge incontinence: Leakage of urine with or right after a sudden, strong urge to void that is hard to delay; also called urgency incontinence. *(Ch. 28)*

uric acid: A waste product of purine breakdown that the kidneys remove; a high blood level can lead to urate crystal deposits. *(Ch. 34)*

urinary incontinence: Any involuntary leakage of urine. *(Ch. 28)*

urinary retention: Inability to empty the bladder completely or at all; it may be acute or chronic. *(Ch. 28)*

urinary tract infection (UTI): An infection anywhere in the urinary tract, from the urethra to the kidneys. *(Ch. 28)*

urine albumin-to-creatinine ratio (ACR): a random urine test, reported in mg/mmol, that measures albumin in the urine and is used to detect and classify kidney damage *(Ch. 27)*

urine culture: A laboratory test that identifies bacteria in urine, counts them and tests their susceptibility to antibiotics. *(Ch. 28)*

urine specific gravity: A measure of urine concentration compared with water. *(Ch. 3)*

urolithiasis: stones anywhere in the urinary tract. *(Ch. 28)*

urosepsis: Sepsis that starts from an infection of the urinary tract. *(Ch. 28)*

urostomy: a stoma that drains urine into a pouch on the abdomen. *(Ch. 28)*

uterine fibroids: Non-cancerous growths of the muscle of the uterus. *(Ch. 29)*

vaccine hesitancy: a delay in or refusal of vaccination because of concerns about vaccines. *(Ch. 21)*

vagal manoeuvre: An action that increases vagal tone to slow AV node conduction, such as a Valsalva manoeuvre, used first for stable regular narrow-complex tachycardia. *(Ch. 16)*

vaginal estrogen: Low-dose estrogen placed in the vagina to treat genitourinary syndrome of menopause. *(Ch. 29)*

vancomycin-resistant enterococci (VRE): bowel bacteria (enterococci) that no longer respond to vancomycin. *(Ch. 4)*

varenicline: A prescription cessation medication that partly stimulates nicotine receptors, easing cravings and withdrawal. *(Ch. 14)*

vasculitis: Inflammation of the walls of blood vessels. *(Ch. 34)*

vaso-occlusive crisis: an episode of acute pain caused by sickled cells blocking blood flow *(Ch. 20)*

vasomotor symptoms: Hot flashes and night sweats, the most common symptoms of menopause. *(Ch. 29)*

vasopressor: a drug that constricts blood vessels to raise blood pressure. *(Ch. 6)*

vegetation: A mass of clot, bacteria and inflammatory cells attached to a heart valve or other endocardial surface in infective endocarditis. *(Ch. 18)*

venous thromboembolism (VTE): a blood clot in a vein, including deep vein thrombosis and pulmonary embolism. *(Ch. 7)*

ventilation: the movement of air into and out of the lungs. *(Ch. 12)*

ventilation–perfusion (V/Q) mismatch: an imbalance between the air reaching parts of the lung and the blood flowing past them; it causes hypoxemia more often than any other mechanism. *(Ch. 12)*

ventilation–perfusion (V/Q) scan: A nuclear medicine scan that compares where air and blood reach the lungs; preferred when contrast or radiation is a concern. *(Ch. 15)*

ventilator-associated pneumonia: Pneumonia that develops in a patient receiving invasive mechanical ventilation. *(Ch. 15)*

ventilator-associated pneumonia (VAP): pneumonia that develops more than 48 hours after endotracheal intubation. *(Ch. 13)*

ventricular fibrillation (VF): Chaotic electrical activity in the ventricles with no organized QRS complexes and no cardiac output. *(Ch. 16)*

ventricular tachycardia (VT): A fast rhythm from the ventricles with wide QRS complexes that may or may not produce a pulse. *(Ch. 16)*

Venturi mask: An air-entrainment mask that mixes oxygen with room air through a valve to give a fixed oxygen concentration. *(Ch. 12)*

verbal descriptor scale: a self-report scale on which the patient chooses a word, such as mild, moderate or severe, to describe pain intensity *(Ch. 5)*

vertigo: A false sense that the person or the surroundings are moving. *(Ch. 36)*

vesicant: a drug that can blister and destroy tissue if it leaks out of a vein. *(Ch. 9)*

vestibular rehabilitation: Exercises that help the brain adapt to balance problems; offered for ongoing imbalance but not during an acute attack of vertigo. *(Ch. 36)*

video remote interpreting (VRI): Sign language interpretation provided by an interpreter who joins by video on a screen. *(Ch. 36)*

viral load: the amount of HIV RNA in the blood, used to judge whether antiretroviral therapy is working. *(Ch. 21)*

Virchow's triad: The three conditions that promote clotting: stasis of blood, injury to the vessel wall and hypercoagulability. *(Ch. 15)*

visceral pain: nociceptive pain arising in internal organs, often harder to locate than somatic pain *(Ch. 5)*

visual acuity: The sharpness of vision at a set distance, often measured with a letter chart such as the Snellen chart. *(Ch. 36)*

vital capacity: The largest volume of air a person can breathe out after a full breath in; a bedside measure of breathing muscle strength. *(Ch. 32)*

volvulus: a twist of a loop of bowel, most often the sigmoid colon or cecum, on its own mesentery. *(Ch. 25)*

von Willebrand disease (VWD): the most common inherited bleeding disorder, caused by a lack or defect of von Willebrand factor; it often causes nosebleeds, bruising and heavy menstrual bleeding. *(Ch. 20)*

waiver of final consent: A written arrangement, available only in Track 1, that allows MAID to proceed on a set date if the person loses capacity, unless they refuse or resist by words, sounds or gestures; also called Audrey's Amendment. *(Ch. 10)*

water seal: The chamber of a chest drainage unit in which a column of water lets air leave the chest but stops it from flowing back, acting as a one-way valve. *(Ch. 15)*

weaning: The process of reducing ventilator support until the patient breathes without it. *(Ch. 15)*

wearing off: The return of Parkinson symptoms before the next dose of medication is due. *(Ch. 32)*

weight bias: negative attitudes, beliefs or actions toward people because of their body weight. *(Ch. 24)*

weight stigma: The social devaluing of people because of their body size, which can show up as stereotypes, judgmental language and equipment or practices that do not fit them. *(Ch. 2)*

Wells rule: A structured clinical rule that estimates the pretest probability of pulmonary embolism from findings such as signs of DVT, heart rate, recent surgery or immobility, and past VTE. *(Ch. 15)*

Wernicke encephalopathy: an acute, potentially fatal brain disorder caused by thiamine deficiency, classically with confusion, ataxia and abnormal eye movements. *(Ch. 11)*

wet suction: A chest drainage design in which the height of a water column limits the level of suction. *(Ch. 15)*

wheeze: a continuous, musical sound produced by narrowed airways, usually heard when breathing out. *(Ch. 12)*

whispered voice test: A bedside hearing screen in which the examiner, out of the person's sight, whispers a mix of numbers and letters for the person to repeat, testing each ear separately. *(Ch. 36)*

white-coat hypertension: Raised blood pressure in the office with normal readings at home or on ambulatory monitoring. *(Ch. 19)*

window period: the time between HIV infection and the point when a test can reliably detect it; up to 12 weeks. *(Ch. 21)*

withdrawal seizure: a generalized tonic-clonic seizure caused by alcohol withdrawal, usually within the first two days after the last drink. *(Ch. 11)*

work of breathing: the effort the breathing muscles spend to move air; signs of increased work include accessory muscle use, retractions and speaking in short phrases. *(Ch. 12)*

wound bed preparation: A framework for wound care that starts by treating the cause, addressing the person's concerns and deciding whether a wound can heal, then guides local care. *(Ch. 35)*

written action plan: A personal written guide that tells a person with asthma how to recognize worsening, step up treatment and seek help. *(Ch. 14)*

YEARS: A diagnostic approach for suspected pulmonary embolism that combines three clinical items with a D-dimer threshold that depends on whether any item is present. *(Ch. 15)*

BACK MATTER — OPEN EDUCATIONAL RESOURCE ATTRIBUTIONS *Appendix C*

C Complete Figure Credits & Licences (246 Figures)

Figure 1.1 (Ch. 1): A nurse measures a patient's blood pressure at the bedside. Regular, careful assessment underlies every other part of medical-surgical nursing care. (credit: “Blood Pressure Monitoring” by NIH Clinical Center/Flickr, CC BY 2.0)

Figure 1.2 (Ch. 1): A nurse checks an older man's blood pressure in his home. Medical-surgical nursing continues after discharge through home care, telephone follow-up and remote monitoring. (credit: “Telehealth - Older man and nurse using blood pressure” by Tunstall Telehealthcare/Flickr, CC BY 2.0)

Figure 1.3 (Ch. 1): (a) Qikiqtani General Hospital, the territorial hospital in Iqaluit, Nunavut. (b) Tammaativvik, a boarding home in Iqaluit for Inuit patients who travel from other communities for care at the hospital. (credit: (a) “Qikiqtani General Hospital” by OhanaUnited/Wikimedia Commons, CC BY-SA 4.0; (b) “Tammaativvik boarding home” by OhanaUnited/Wikimedia Commons, CC BY-SA 4.0)

Figure 1.4 (Ch. 1): An Ornge helicopter departs St. Michael's Hospital in Toronto. Ornge provides air ambulance service and medical transport in Ontario for people who are critically ill or injured (Ornge, n.d.). (credit: “Ornge Agusta Westland AW 139 C-GYNN” by BriYYZ/Wikimedia Commons, CC BY-SA 2.0)

Figure 1.5 (Ch. 1): A health care assistant helps a patient with fluids. Unregulated care providers, such as PSWs in Ontario, give much of the personal care on medical-surgical units, within the role their employer sets. (credit: “A healthcare assistant pouring water for a patient” by Adrian Wressell, Heart of England NHS FT/Wellcome Collection, CC BY 4.0)

Figure 1.6 (Ch. 1): A nurse records a patient's vital signs, including oxygen saturation from a finger probe. Recognizing cues begins with accurate, regular assessment. (credit: “A nurse carrying out observations on a patient” by Adrian Wressell, Heart of England NHS FT/Wellcome Collection, CC BY 4.0)

Figure 1.7 (Ch. 1): A nurse documents in the electronic health record on a mobile workstation in the patient's room. The patient's face and the screen have been blurred to protect privacy. (credit: modification of “Princess Alexandra Hospital nurse with mobile computer work station” by Kgbo/Wikimedia Commons, CC BY-SA 4.0)

Figure 1.8 (Ch. 1): A nurse prepares medications from a locked medication cart. Each medication is checked against the order and the patient before it is given. (credit: “Nurse during a drug administration on a UK hospital ward” by Adrian Wressell, Heart of England NHS FT/Wellcome Collection, CC BY 4.0)

Figure 1.9 (Ch. 1): A hospital identification band. The nurse confirms at least two person-specific identifiers, such as name and date of birth, before giving a medication or treatment (Health Standards Organization, 2024). Identifying details have been blurred. (credit: modification of “Wrist Identification Band” by Whoisjohngalt/Wikimedia Commons, CC BY-SA 4.0)

Figure 1.10 (Ch. 1): A weekly pill organizer. A best possible medication history asks how the patient actually takes each medication at home, including what goes into an organizer like this one. (credit: “Heptagonal objects A weekly medicine box” by יוח יוסי/Wikimedia Commons, CC BY-SA 4.0)

Figure 1.11 (Ch. 1): An older adult walks with a walking frame and a physiotherapist. Getting up early and often during a hospital stay helps prevent hospitalization-associated disability. (credit: “Female physiotherapist with elderly female patient” by Adrian Wressell, Heart of England NHS FT/Wellcome Collection, CC BY 4.0)

Figure 2.1 (Ch. 2): Braided sweetgrass (Hierochloe odorata), one of the sacred medicines used in First Nations, Inuit and Métis smudging and healing ceremonies. (credit: “Braided Sweet Grass” by Jamfam1000/Wikimedia Commons, CC BY-SA 4.0)

Figure 2.2 (Ch. 2): The health centre in Cambridge Bay, Nunavut. When a patient from a northern or remote community is discharged, the nurse connects with the community's health centre so that care continues at home. (credit: “38 Health centre” by CambridgeBayWeather/Wikimedia Commons, CC BY-SA 4.0)

Figure 2.3 (Ch. 2): A mobile community health and wellness clinic van, one model used to bring primary care, wound care and harm reduction directly to underserved neighbourhoods. (credit: “Mobile health van - 2021-08-27 - Sarah Stierch” by Sarah Stierch [Missvain]/Wikimedia Commons, CC BY 4.0)

Figure 3.1 (Ch. 3): Pitting edema of the lower leg: pressing with a finger leaves dents that fill slowly. (credit: “Oedema, finger marks” by John Campbell/Flickr, public domain)

Figure 3.2 (Ch. 3): An electronic infusion pump delivers IV fluid at a set rate. The nurse checks the fluid, rate and volume on the pump against the order. (credit: “Electronic infusion device (EID)” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 3.3 (Ch. 3): A peripheral IV catheter in the forearm, held in place with a clear dressing so the site can be seen. The nurse looks at the site and the skin around it at every assessment. (credit: “Peripheral intravenous (IV) catheter (PIV)” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 3.4 (Ch. 3): A 12-lead ECG from a patient with a serum potassium of 7.0 mmol/L, showing tall, peaked T waves. (credit: “ECG Hyperkalaemia peaked T waves serum potassium 7.0” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 3.5 (Ch. 3): A re-creation of the hand posture of a positive Trousseau's sign: the wrist and knuckles flex, the fingers straighten and the thumb draws in. (credit: “Trousseau's Sign of Latent Tetany” by Tmdswan/Wikimedia Commons, CC BY-SA 4.0)

Figure 3.6 (Ch. 3): (a) Blood samples in syringes: venous blood is darker and arterial blood brighter red. (b) A blood gas analyzer, which measures pH, blood gases and electrolytes in a small sample of blood. (credit: (a) “Venous and arterial blood rotated and cropped” by Wesalius/Wikimedia Commons, CC BY 4.0; (b) “Cobas221A” by J3D3/Wikimedia Commons, CC BY-SA 3.0)

Figure 4.1 (Ch. 4): Cellulitis of the toes and forefoot. Spreading redness and swelling are local signs of inflammation and infection; on darker skin, redness can be harder to see, so the nurse also checks warmth, swelling and pain.

Figure 4.2 (Ch. 4): A blood culture bottle that has turned cloudy because organisms are growing in it. The laboratory then identifies the organism and tests which antimicrobials work against it.

Figure 4.3 (Ch. 4): A wall-mounted alcohol-based hand rub dispenser in a hospital in the United States. (credit: “Purell hand sanitizer device at Memorial Regional Hospital” by Claudia Brauer/Wikimedia Commons, CC BY 2.0)

Figure 4.4 (Ch. 4): (a) *Clostridioides difficile* bacteria from a stool sample, seen with a scanning electron microscope. (b) Methicillin-resistant *Staphylococcus aureus* (MRSA, gold) and a dead human neutrophil (red), with colour added. (credit: (b) “Scanning electron micrograph of Methicillin-resistant Staphylococcus aureus (MRSA) and a dead Human neutrophil” by NIAID/Wikimedia Commons, CC BY 2.0)

Figure 5.1 (Ch. 5): (a) A patient-controlled analgesia (PCA) pump with a morphine cassette for intravenous use. (b) A pump set up for an epidural infusion of fentanyl with bupivacaine; the label reads “Epidural Use Only.” These labels are from the United States; Canadian products are labelled differently. (credit: (a) “PCA-02” and (b) “PCA-01” by DiverDave/Wikimedia Commons, CC BY-SA 3.0)

Figure 5.2 (Ch. 5): A take-home naloxone kit as distributed in British Columbia. (credit: “NaloxoneKit” by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

Figure 6.1 (Ch. 6): (a) A bedside monitor showing heart rate, oxygen saturation and blood pressure for a simulated patient. (b) A pulse oximeter with a finger sensor. Monitors show single readings; the nurse looks at the trend over time. (credit: (b) “Pulse oximeter” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 6.2 (Ch. 6): Raised red welts on light skin during a skin reaction, similar to hives. On darker skin, redness can be harder to see. (credit: “Rash” by Enochlau/Wikimedia Commons, CC BY-SA 3.0)

Figure 6.3 (Ch. 6): An epinephrine autoinjector held in the fist, with the blue safety release at the top and the orange tip pointing down toward the outer thigh. (credit: “Adrenalina autoinyector9” by AngelHM/Wikimedia Commons, CC BY-SA 4.0)

Figure 6.4 (Ch. 6): A non-rebreather mask with its reservoir bag, used to give high-concentration oxygen as ordered. (credit: “Non re-breather mask” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 7.1 (Ch. 7): An incentive spirometer, which encourages slow, deep breaths after surgery.

Figure 7.2 (Ch. 7): A surgical team at work in an operating room. Before the first incision, the team pauses for the time-out. (credit: “AfS surgical team at the operating room” by Almondbite3/Wikimedia Commons, CC BY-SA 4.0)

Figure 7.3 (Ch. 7): A nurse opens the package of a sterile indwelling urinary catheter. A catheter is inserted only on an order and removed as early as possible. (credit: “Choose smallest catheter size possible” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 7.4 (Ch. 7): A surgical incision closed with staples, 7 days after shoulder surgery. (credit: “Surgical staples2” by Llywrch/Wikimedia Commons, CC BY-SA 2.5)

Figure 8.1 (Ch. 8): Placing a hearing aid. Glasses and hearing aids that are in use, clean and working help prevent delirium and falls, and help the person take part in care.

Figure 8.2 (Ch. 8): A two-wheeled folding walker used to support balance and safe mobilization in hospital and at home. (credit: “Walker. frame” by High Plains Drifter/Wikimedia Commons, Public domain)

Figure 8.3 (Ch. 8): A hip protector: fitted underwear with a pad over the outer hip to cushion a fall. Hip protectors can be considered for people at risk of hip fracture after a discussion of benefits and drawbacks. (credit: “AHIP Protector” by Lkshlzr/Wikimedia Commons, CC BY-SA 3.0)

Figure 9.1 (Ch. 9): Cancer cells under the microscope (squamous cell carcinoma of the skin). In this poorly differentiated, high-grade example, the cells look very different from normal skin cells and grow into the surrounding tissue. (credit: “Micrograph of clear-cell squamous-cell carcinoma” by Valerie R. Yanofsky, Stephen E. Mercer and Robert G. Phelps/Wikimedia Commons, CC BY 4.0)

Figure 9.2 (Ch. 9): A mammogram, the breast screening test, labelled to show normal fibroglandular tissue, a calcification and a mass. (credit: “Low intensity mass on mammography MLO view” by Cerevisae/Wikimedia Commons, CC BY-SA 4.0)

Figure 9.3 (Ch. 9): A home stool test kit for bowel cancer screening (Australia's national program, 2022). Provincial programs mail similar kits for a fecal immunochemical test; contents and instructions vary by program. (credit: “Bowel cancer Home Test Kit Instructions and test tubes in Australia, 2022” by Kgbo/Wikimedia Commons, CC BY-SA 4.0)

Figure 9.4 (Ch. 9): A radiation therapist marks a custom mesh mask fitted to a patient model. For radiation to the head or neck, the mask holds the head in the same position for each treatment.

Figure 9.5 (Ch. 9): A single-lumen peripherally inserted central catheter (PICC) before insertion. (credit: “Peripherally inserted central catheter (PICC) with one lumen” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 9.6 (Ch. 9): An implanted port under the skin of the upper chest, shown on a training manikin. (credit: “Chest with ICVC inserted” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 11.1 (Ch. 11): Ventilating with a bag-valve-mask during resuscitation training. In opioid toxicity, supporting breathing comes first while naloxone takes effect.

Figure 11.2 (Ch. 11): A rapid fentanyl test strip and interpretation guide used in community and hospital harm-reduction drug checking (one red line = positive for fentanyl; two red lines = negative). (credit: “Fentanyl-test-strip” by WikiLinuz/Wikimedia Commons, CC BY-SA 4.0)

Figure 11.3 (Ch. 11): A harm reduction table at a community event in Portland, Oregon, offering free naloxone and fentanyl test strips. (credit: “Harm Reduction Drug Testing Table” by Sarahmirk/Wikimedia Commons, CC BY-SA 4.0)

Figure 11.4 (Ch. 11): A public needle disposal box in a parking lot in Denver, Colorado. Safe disposal sites for used needles are part of harm reduction services. (credit: “Needle disposal box” by Jeffrey Beall/Wikimedia Commons, CC BY 4.0)

Figure 12.1 (Ch. 12): The main structures of the respiratory system, from the nose and mouth to the lungs and diaphragm. (credit: Figure 22.2, “Major Respiratory Structures,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 12.2 (Ch. 12): The respiratory zone: bronchioles end in alveolar ducts and clusters of alveoli, each wrapped in capillaries where gas exchange takes place. (credit: Figure 22.10, “Respiratory Zone,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 12.3 (Ch. 12): Clubbing of the fingers with cyanosis of the nail beds. On darker skin, cyanosis may look grey rather than blue. (credit: modification of “Showing bilateral grade III clubbing with cyanosis of the extremities” by Twayana et al./BMC Research Notes, CC BY 4.0)

Figure 12.4 (Ch. 12): Listening to the lungs from the back, on bare skin, comparing side to side.

Figure 12.5 (Ch. 12): A nasal cannula, the most common low-flow oxygen device. (credit: “Nasal cannula” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 12.6 (Ch. 12): (a) A simple face mask. (b) A Venturi mask; the colour-coded valve sets the oxygen concentration. (credit: (a) “Simple face mask” and (b) “Venturi mask” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 12.7 (Ch. 12): A high-flow nasal cannula system on a pole stand, with an oxygen–air blender, a heated humidifier and heated tubing. Hospital policy decides where it is used. (credit: “High Flow Nasal Cannula Classic” by BreathDriver/Wikimedia Commons, CC BY-SA 4.0)

Figure 12.8 (Ch. 12): Home oxygen equipment: (a) an oxygen concentrator, which runs on electricity; (b) a portable oxygen cylinder with a regulator. (credit: (a) “Invacare Perfecto 2 Oxygen Concentrator” by BrokenSphere/Wikimedia Commons, CC BY-SA 3.0)

Figure 12.9 (Ch. 12): Oral suctioning with a rigid Yankauer suction tip on a manikin. (credit: “Suctioning with a yankauer” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 12.10 (Ch. 12): Tracheostomy equipment, from left: obturator, cuffed tube, uncuffed tube and tracheal dilators. (credit: “Obturator, cuffed tracheostomy tube, non-cuffed tracheostomy tube, tracheal dilators” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 13.1 (Ch. 13): Chest X-ray of lobar pneumonia. Consolidation fills the right middle lobe, the white area beside the right heart border (on the viewer's left).

Figure 13.2 (Ch. 13): Influenza A (H1N1) virus particles, coloured blue, seen with a transmission electron microscope.

Figure 13.3 (Ch. 13): Mycobacterium tuberculosis bacteria seen with a scanning electron microscope, magnified about 15,500 times.

Figure 13.4 (Ch. 13): A room pressure monitor beside a negative-pressure isolation room. The green "normal" display shows that air is flowing into the room; the nurse checks it as policy directs and reports an alarm. (credit: “Joondalup Hospital negative pressure room” by Orderinchaos/Wikimedia Commons, CC BY-SA 4.0)

Figure 13.5 (Ch. 13): Three things an N95 respirator needs to protect the wearer: it is put on and worn correctly, it seals snugly against the face, and its filter captures more than 95% of particles. (credit: “Three Key Factors Required for a Respirator to be Effective” by Centers for Disease Control and Prevention/NIOSH, public domain)

Figure 13.6 (Ch. 13): Radon detectors from a home test kit. Because radon has no colour or smell, testing is the only way to know a home's level.

Figure 13.7 (Ch. 13): A packaged thoracentesis kit: a drainage bag and tubing, syringes, and the needle and catheter used to drain pleural fluid. (credit: “ThoracentesisEquip” by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

Figure 14.1 (Ch. 14): The mouthpiece and flow sensor of a hospital pulmonary function testing system, used for spirometry and related breathing tests. (credit: “Device for Spirometry or Body Plethysmography 02” by Joe Mabel/Wikimedia Commons, CC BY-SA 3.0)

Figure 14.2 (Ch. 14): A peak flow meter. The patient blows into it in a short, sharp blow, and a marker moves along the scale to show the peak expiratory flow.

Figure 14.3 (Ch. 14): Smoke from the June 2023 wildfires in Quebec over New York City. Wildfire smoke can travel far from the fires and trigger asthma attacks. (credit: “Wildfire Smoke” by Marc A. Hermann/Metropolitan Transportation Authority, CC BY 2.0)

Figure 14.4 (Ch. 14): Three dry powder inhalers: a Turbuhaler, an Accuhaler (sold in Canada as Diskus) and an Ellipta. Each is loaded differently, so the nurse checks technique with the patient's own device. (credit: “Dry powder inhalers” by Brett Montgomery/Wikimedia Commons, CC BY-SA 4.0)

Figure 14.5 (Ch. 14): A cut slice of lung with centrilobular emphysema, the pattern typical of smoking: many small spaces where alveolar walls have been destroyed, lined with black carbon deposits. The specimen number on the ruler is pixelated. (credit: modification of “Centrilobular emphysema 865 lores” by Edwin P. Ewing, Jr./Centers for Disease Control and Prevention, public domain)

Figure 14.6 (Ch. 14): A nicotine patch on the upper arm. It gives a steady dose of nicotine through the skin; a short-acting form such as gum or a lozenge can be added for cravings. (credit: “Nicoderm” by RegBarc/Wikimedia Commons, CC BY 2.5)

Figure 14.7 (Ch. 14): A home CPAP machine with its tubing and mask. People who use CPAP at home are encouraged to bring their machine to hospital and use it whenever they sleep. (credit: “ResMed CPAP machine and mask” by Infrogmation/Wikimedia Commons, CC BY-SA 4.0)

Figure 15.1 (Ch. 15): Non-invasive ventilation through a full face mask that covers the nose and mouth, connected to a ventilator. This is a posed demonstration; the person's eyes are pixelated. (credit: modification of “BIPAP” by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

Figure 15.2 (Ch. 15): An endotracheal tube in a teaching model of the airway. The tube passes through the mouth into the trachea, and its inflated cuff seals the trachea around it. (credit: “Endotracheal tube” by John Campbell/Flickr, public domain)

Figure 15.3 (Ch. 15): A BC Emergency Health Services critical care helicopter on the rooftop helipad of Vancouver General Hospital. (credit: “BCEHSHeli2017” by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

Figure 15.4 (Ch. 15): Chest X-ray of a large left pneumothorax, labelled: no lung markings in the air-filled space, the collapsed left lung, and the mediastinum shifted to the right. A shift like this, with signs of shock, points to tension pneumothorax, which is treated at once without waiting for an X-ray. (credit: “X-ray of pneumothorax signs” by Karthik Easvur/Wikimedia Commons, CC BY-SA 3.0)

Figure 15.5 (Ch. 15): A chest drainage unit with its parts labelled. (credit: “Chest tube drainage system with labelled parts” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 15.6 (Ch. 15): A portable digital chest drainage unit at the bedside. It applies suction electronically and measures air leak continuously. (credit: “P4053296 logo” by TKiefer/Wikimedia Commons, CC BY-SA 4.0)

Figure 16.1 (Ch. 16): The inside of the heart, front view: the four chambers, the four valves and the great vessels. (credit: Figure 19.9, “Internal Structures of the Heart,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 16.2 (Ch. 16): The coronary arteries and cardiac veins on the surface of the heart, front view (top) and back view (bottom). (credit: Figure 19.15, “Coronary Circulation,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 16.3 (Ch. 16): The conduction system of the heart, from the sinoatrial (SA) node through the atrioventricular (AV) node and bundle of His to the bundle branches and Purkinje fibres. (credit: Figure 19.18, “Conduction System of the Heart,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 16.4 (Ch. 16): A normal ECG cycle with its waves, intervals and segments labelled. (credit: Figure 19.23, “Electrocardiogram,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 16.5 (Ch. 16): Where to listen to the heart: the aortic, pulmonic, tricuspid and mitral areas. (credit: “2030 Stethoscope Placement” by OpenStax College/Wikimedia Commons, CC BY 3.0)

Figure 16.6 (Ch. 16): A 12-lead ECG in normal sinus rhythm. Each row shows four leads; the long strip along the bottom is lead II. (credit: “Normal sinus rhythm” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.7 (Ch. 16): Placement of the six chest (precordial) electrodes, V1 to V6, for a 12-lead ECG. The dotted line marks the left midclavicular line. (credit: “ECG lead positioning” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.8 (Ch. 16): A 12-lead ECG showing sinus bradycardia: a P wave before every QRS complex, at a slow rate. (credit: “Sinus bradycardia” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.9 (Ch. 16): A 12-lead ECG showing sinus tachycardia at about 150 per minute. At fast rates the P waves can merge into the T waves before them. (credit: “Sinus tachycardia” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.10 (Ch. 16): A 12-lead ECG showing ventricular bigeminy: a wide, early premature ventricular contraction (PVC) after every normal beat. (credit: “ECG Premature Ventricular Complex (PVC) Bigeminy” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.11 (Ch. 16): Rhythm strip of monomorphic ventricular tachycardia: a fast, regular rhythm of wide QRS complexes that look alike. (credit: “Monomorphic ventricular tachycardia” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.12 (Ch. 16): Rhythm strip of ventricular fibrillation: chaotic, irregular waves with no identifiable P waves, QRS complexes or T waves. (credit: “VF rhythm strip” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.13 (Ch. 16): Rhythm strip in which a slow rhythm ends in a flat line (asystole). The nurse confirms that the electrodes are attached and that the patient has no pulse. (credit: Figure 12.18 in Medical-Surgical Nursing by OpenStax, CC BY-NC-SA 4.0)

Figure 16.14 (Ch. 16): A 12-lead ECG showing atrial fibrillation with a rapid ventricular response: an irregularly irregular rhythm with no clear P waves. (credit: “AF with rapid ventricular response” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.15 (Ch. 16): A 12-lead ECG showing atrial flutter with 4:1 block: sawtooth flutter waves, with one QRS complex for every four flutter waves. (credit: “Atrial flutter with 4:1 block” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.16 (Ch. 16): Rhythm strip showing first-degree AV block: every P wave is followed by a QRS complex, but the PR interval (marked) is longer than 0.20 seconds. (credit: “Rhythm strip: PR interval prolonged, first-degree AV block” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.17 (Ch. 16): A 12-lead ECG showing second-degree AV block, Mobitz I (Wenckebach): the PR interval lengthens from beat to beat until a P wave is not conducted and a QRS complex is dropped. (credit: “Mobitz I AV block” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.18 (Ch. 16): Rhythm strip showing second-degree AV block, Mobitz II: the PR interval stays the same, and the arrows mark P waves that are suddenly not conducted. (credit: “Mobitz II AV block” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.19 (Ch. 16): Rhythm strip showing complete (third-degree) AV block: P waves (small arrows) at about 100 per minute, unrelated to wide QRS complexes (R) at about 40 per minute. (credit: “Complete heart block” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 16.20 (Ch. 16): Chest X-ray of a single-chamber permanent pacemaker: the pulse generator under the skin of the upper chest and one lead in the heart. A label in the corner is pixelated. (credit: modification of “VVI Schrittmacher THWZ” by Th. Zimmermann/Wikimedia Commons, CC BY-SA 3.0 DE)

Figure 16.21 (Ch. 16): Anterolateral pad placement: one pad below the right clavicle and one on the left side of the chest, so the current passes through the heart. (credit: “Defib electrode placement” by Owain Davies/Wikimedia Commons, CC BY 3.0)

Figure 16.22 (Ch. 16): A public-access AED in a wall cabinet. (credit: modification of Figure 19.26, “Defibrillators,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0; panel (a) only)

Figure 17.1 (Ch. 17): Three-dimensional images of the heart built from a coronary computed tomography angiography scan, showing the coronary arteries on its surface. (credit: “Coronary CT Angiography Scan” by Goleisureintl/Wikimedia Commons, CC BY 4.0)

Figure 17.2 (Ch. 17): Three forms of nitroglycerin: an intravenous solution (used in hospital), a sublingual spray and a transdermal patch. (credit: “Nitro” by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 17.3 (Ch. 17): A 12-lead ECG showing an acute extensive anterior STEMI: ST elevation across the chest leads and in I and aVL, with reciprocal ST depression in the inferior leads. (credit: “Extensive Anterior STEMI (acute)” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 17.4 (Ch. 17): A 12-lead ECG showing an inferior STEMI: ST elevation in leads II, III and aVF, with reciprocal ST depression in aVL. (credit: “Inferior STEMI” by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 17.5 (Ch. 17): An expanded coronary stent holding a narrowed artery open (enlarged view). (credit: “Cobalt Chromium Coronary Stent in Heart” by ETTon/Wikimedia Commons, CC BY-SA 4.0)

Figure 18.1 (Ch. 18): A markedly raised jugular venous pressure: the distended external jugular vein (arrow) runs up the side of the neck. The face was masked by the photographer, and the Commons page records the person's consent. (credit: “Elevated JVP1” by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 18.2 (Ch. 18): Chest X-ray in heart failure, labelled: an enlarged heart, upper-lobe vessels that are more prominent than usual, Kerley B lines from fluid in the lung tissue, and a small pleural effusion.

Figure 18.3 (Ch. 18): Chest X-ray of a cardiac resynchronization pacemaker: the generator in the upper chest and three leads, one in the right atrium and one in each ventricle. (credit: "CRT-P-THWZ" by Th. Zimmermann/Wikimedia Commons, CC BY-SA 3.0 DE)

Figure 18.4 (Ch. 18): A left ventricular assist device: the pump draws blood from the left ventricle and returns it to the aorta; a driveline through the skin connects it to an external controller and batteries. (credit: "Ventricular assist device" by Madhero88/Wikimedia Commons, CC BY-SA 3.0)

Figure 18.5 (Ch. 18): A mechanical heart valve shown in place in the heart (illustration). Clots can form on its surfaces, so lifelong anticoagulation is needed. (credit: "3D Medical Animation still shot Artificial Heart Valve" by Scientific Animations/Wikimedia Commons, CC BY-SA 4.0)

Figure 18.6 (Ch. 18): Janeway lesions on the palm of a man with staphylococcal endocarditis: small, flat, painless red spots. On darker skin they look purple to dark brown. (credit: "Janeway lesion" by Warfieldian/Wikimedia Commons, CC BY-SA 4.0)

Figure 18.7 (Ch. 18): Echocardiogram showing a vegetation (arrow) on the tricuspid valve in infective endocarditis. (credit: "Endocarditis ultrasound" by Daisuke Koya, Kazuyuki Shibuya, Ryuichi Kikkawa and Masakazu Haneda; derivative work by Materialscientist/Wikimedia Commons, CC BY 2.0)

Figure 18.8 (Ch. 18): A peripherally inserted central catheter (PICC) after removal at the end of two months of treatment, with its hub and securement dressing. (credit: "Peripherally inserted central catheter (PICC or PIC line) after use in a patient for two months 2018 The Netherlands" by Hansmuller/Wikimedia Commons, CC BY-SA 4.0)

Figure 18.9 (Ch. 18): A 12-lead ECG in acute pericarditis, with ST elevation in many leads. Because pericarditis can mimic acute coronary syndrome, the patient with chest pain is assessed for both. (credit: "ECG Pericarditis" by LITFL/Life in the Fast Lane, CC BY-NC-SA 4.0)

Figure 18.10 (Ch. 18): A normal heart compared with hypertrophic cardiomyopathy (thickened muscle) and dilated cardiomyopathy (enlarged chamber with thin, stretched muscle). (credit: "Illustration of an enlarged heart (Cardiomegaly)" by myUpchar/Wikimedia Commons, CC BY-SA 4.0)

Figure 19.1 (Ch. 19): An aneroid sphygmomanometer: an adult cuff with its size label and range marks, a dial gauge and an inflation bulb. The range marks show whether the cuff fits the arm.

Figure 19.2 (Ch. 19): Blood pressure cuffs come in many sizes, from neonatal to large adult and thigh cuffs. A cuff of the wrong size makes readings unreliable, so the arm is measured to choose the size. (credit: "Sizes of blood pressure cuffs" by Chippewa Valley Technical College, CC BY 4.0)

Figure 19.3 (Ch. 19): A foot with peripheral arterial disease: a dry ulcer at the tip of the big toe and thickened nails. (credit: "Peripheral artery disease" by Milorad Dimić (Intermedichbo)/Wikimedia Commons, CC BY-SA 4.0)

Figure 19.4 (Ch. 19): Contrast-enhanced CT of an abdominal aortic aneurysm measuring about 4.8 by 3.8 cm (green measurement lines). (credit: "Contrast-enhanced CT scan demonstrating abdominal aortic aneurysm" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 19.5 (Ch. 19): Deep vein thrombosis of the right leg (arrow): the leg is swollen and redder than the other. On darker skin, the change may look darker or purplish, or be hard to see. (credit: "Deep vein thrombosis of the right leg" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 19.6 (Ch. 19): Varicose veins: raised, twisted surface veins over the lower leg and ankle.

Figure 19.7 (Ch. 19): Chronic venous insufficiency on darker skin: dark hyperpigmentation and thickened skin above the ankle, with an open venous ulcer. (credit: "Chronic venous insufficiency & Venous ulcer" by Ahmed Shawky Mohammedin, MD (Ashashyou)/Wikimedia Commons, CC BY-SA 4.0)

Figure 19.8 (Ch. 19): Medical compression stockings come in different lengths, strengths and colours; the type is prescribed after an arterial assessment. (credit: "Medizinische Kompressionsstrümpfe" by Enter/Wikimedia Commons, CC BY-SA 3.0)

Figure 20.1 (Ch. 20): Hematopoiesis: one stem cell population in the bone marrow gives rise to two lines. The myeloid line makes red cells, platelets and most white cells; the lymphoid line makes lymphocytes. (credit: Figure 18.4, "Hematopoietic System of Bone Marrow," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 20.2 (Ch. 20): A blood smear in severe iron deficiency anemia: the red cells are small (microcytic) and pale (hypochromic), with wide pale centres. (credit: "Iron-deficiency Anemia, Peripheral Blood Smear" by Ed Uthman/Wikimedia Commons, CC BY 2.0)

Figure 20.3 (Ch. 20): Koilonychia: thin nails that curve up at the edges into a spoon shape, a sign of long-standing iron deficiency. Nail and skin changes are useful cues on every skin tone. (credit: "Koilonychia iron deficiency anemia" by CHeitz/Wikimedia Commons, CC BY 2.0)

Figure 20.4 (Ch. 20): Red blood cells seen with a scanning electron microscope: normal round, dimpled discs and one rigid, crescent-shaped sickle cell. (credit: Janice Haney Carr/Centers for Disease Control and Prevention, public domain)

Figure 20.5 (Ch. 20): Petechiae on the lower leg of a person with immune thrombocytopenia and a very low platelet count. On darker skin, petechiae may look darker than the surrounding skin rather than red, and are easier to find in good light. (credit: "Petechia lower leg" by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

Figure 20.6 (Ch. 20): A myeloblast with an Auer rod, a thin rod in the cell's cytoplasm. Auer rods are a feature of acute myeloid leukemia, and blasts on a smear are often the first clue to leukemia. (credit: "Myeloblast with Auer Rod smear 2009-11-23" by Paulo Henrique Orlandi Mourao/Wikimedia Commons, CC BY-SA 3.0)

Figure 20.7 (Ch. 20): Sites that can be used for bone marrow aspiration and biopsy: the sternum, the tibia, and the posterior and anterior iliac crests. (credit: "Site for procedure of Bone Marrow" by Scientific Animations (scientificanimations.com)/Wikimedia Commons, CC BY-SA 4.0)

Figure 20.8 (Ch. 20): A unit of red blood cell concentrate connected to a blood administration set with an in-line filter. The nurse checks the unit tag against the patient and the order at the bedside before starting. (credit: "Red blood cells and blood IV tubing" by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 21.1 (Ch. 21): The lymphatic system. Lymphocytes are made in the bone marrow, T cells mature in the thymus, and both gather in the lymph nodes, spleen and tonsils, where they meet antigens carried in lymph and blood. (credit: Figure 21.2, “Anatomy of the Lymphatic System,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 21.2 (Ch. 21): Skin prick testing on the forearms. Each pen mark labels one allergen, and a raised, red wheal at a site suggests sensitization to that allergen; redness is harder to judge on darker skin. A positive test is interpreted with the history.

Figure 21.3 (Ch. 21): Herpes zoster (shingles): clustered red papules and vesicles in a band that follows one or two dermatomes on one side of the trunk. (credit: CDC/K.L. Herrmann, Public Health Image Library, public domain)

Figure 21.4 (Ch. 21): The structure of HIV: an outer envelope with docking proteins that attach to the CD4 receptor on a host cell, and a capsid holding the viral RNA and the enzymes reverse transcriptase and integrase. (credit: National Institute of Allergy and Infectious Diseases, public domain)

Figure 21.5 (Ch. 21): The HIV replication cycle. Antiretroviral drug classes act at different steps: entry, reverse transcription, integration and maturation by protease (section 21.5). (credit: “HI-Virus Replication Cycle” by NIAID/Wikimedia Commons, CC BY 2.0)

Figure 21.6 (Ch. 21): Oral candidiasis (thrush): creamy white patches on red, inflamed mucosa. Unlike food debris, the patches do not rinse away. (credit: Centers for Disease Control and Prevention, Public Health Image Library, public domain)

Figure 21.7 (Ch. 21): Kaposi sarcoma on the skin of a person with advanced HIV: raised, red-purple patches and nodules. On darker skin the lesions may look brown or black. (credit: unknown author/Wikimedia Commons, public domain)

Figure 22.1 (Ch. 22): A point-of-care glucose meter with lancets, test strips and cotton balls. The meter must be one the laboratory approves, and the nurse follows the unit's quality-control routine. (credit: “A blood glucose monitoring machine with cotton balls, lancets, and reagent strips” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 22.2 (Ch. 22): An intermittently scanned (flash) glucose sensor on the upper arm. Holding the reader or a phone near the sensor shows the current glucose and its trend. (credit: “FreeStyle libre am Oberarm und Auslesegerät-4” by Thirunavukkarasye-Raveendran/Wikimedia Commons, CC BY 4.0)

Figure 22.3 (Ch. 22): An insulin pen with a pen needle and its outer cap. A new needle is attached for every injection, and the pen is labelled for one patient only. The round device on the left is an injection port, which some people use to reduce skin punctures. (credit: “I-Port Advance and insulin pen (Novorapid), with needle cover” by Marius Vassnes/Wikimedia Commons, CC BY-SA 4.0)

Figure 22.4 (Ch. 22): An adult with type 1 diabetes wearing an insulin pump on his waistband, with tubing to an infusion set on the abdomen, and a continuous glucose sensor. Pumps deliver rapid-acting insulin continuously, plus doses for meals. (credit: “Diabetic Type 1 adult man with insulin pump and CGM sensor” by Medtd1/Wikimedia Commons, CC BY-SA 4.0)

Figure 22.5 (Ch. 22): A foot ulcer over a Charcot deformity, a collapse of the midfoot bones that can follow neuropathy. The ulcer sits where pressure falls on a foot that has lost sensation. (credit: “Diabetic Charcot Foot Deformity” by Medicalpal/Wikimedia Commons, CC BY-SA 4.0)

Figure 22.6 (Ch. 22): An arterial ulcer for comparison: a round, punched-out wound on the foot with little drainage, caused by poor blood flow rather than pressure. Many people with diabetes have both neuropathy and arterial disease (Chapter 19). (credit: “Arterial ulcer peripheral vascular disease” by Jonathan Moore/Wikimedia Commons, CC BY 3.0)

Figure 23.1 (Ch. 23): The main endocrine glands. The hypothalamus and pituitary at the base of the brain control the thyroid, adrenal cortex and gonads through feedback loops; the parathyroid glands respond directly to blood calcium. (credit: Figure 17.2, “Endocrine System,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 23.2 (Ch. 23): Ultrasound of the thyroid, viewed in cross-section: a fluid-filled cyst and a small nodule with bright calcifications. Ultrasound features help decide which nodules need fine-needle aspiration. (credit: “Ultrasound of thyroid showing right lower pole cyst and a calcified nodule” by Cerevisae/Wikimedia Commons, CC BY-SA 4.0)

Figure 23.3 (Ch. 23): A healing scar 2 months after total thyroidectomy. The incision lies low across the front of the neck.

Figure 23.4 (Ch. 23): Striae in a person with Cushing syndrome. On lighter skin, new striae are often red-purple, as here; on darker skin they are often brown to black, or may look pale. (credit: “Striae” by PanaromicTiger/Wikimedia Commons, CC BY-SA 3.0)

Figure 23.5 (Ch. 23): MRI of the head from the side, with an arrow marking a pituitary microadenoma, a tumour smaller than 1 cm. MRI is the main imaging test for pituitary tumours. (credit: “Adenome hypophyse esp” by Yakafaucon/Wikimedia Commons, CC BY-SA 4.0)

Figure 24.1 (Ch. 24): The digestive system: the alimentary canal from mouth to anus and the accessory organs (salivary glands, liver, gallbladder and pancreas). (credit: Figure 23.2, “Components of the Digestive System,” in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 24.2 (Ch. 24): Supplies gathered for nasogastric tube insertion, including the tube, lubricant, a securement device, pH strips, a large syringe and water for the patient to sip. Placement is confirmed before the tube is first used, as described later in this section. (credit: “Gather supplies” by Glynda Rees Doyle and Jodie Anita McCutcheon/BCcampus, CC BY 4.0)

Figure 24.3 (Ch. 24): Equipment for placing a percutaneous endoscopic gastrostomy (PEG) tube: the tube with its internal disc (bumper), which holds it inside the stomach, an introducer needle and a guidewire. (credit: “PEG tube kit” by Gilo1969/Wikimedia Commons, CC BY-SA 3.0)

Figure 24.4 (Ch. 24): An enteral feeding pump with its feeding set. Enteral equipment is kept apart from IV lines, and ENFit connectors are designed so the two cannot be joined. (credit: “Enteral feeding pumps” by Ahmed Shawky Mohammedin, MD (Ashashyou)/Wikimedia Commons, CC BY-SA 3.0)

Figure 24.5 (Ch. 24): A three-chamber parenteral nutrition bag. Amino acids, dextrose and lipid are kept in separate compartments until the seals between them are opened and the contents mixed, just before use. (credit: “Smofkabiven Zentral Bag” by Ibrahim Husain Meraj/Wikimedia Commons, CC BY-SA 4.0)

Figure 24.6 (Ch. 24): Roux-en-Y gastric bypass anatomy: a small proximal stomach pouch is created with surgical staples and anastomosed directly to a Roux limb of the jejunum, bypassing the distal stomach and duodenum. (credit: “Blausen 0776 Roux-En-Y 01” by BruceBlaus/Wikimedia Commons, CC BY 3.0)

Figure 25.1 (Ch. 25): An upright abdominal X-ray in small bowel obstruction: dilated loops with many air-fluid levels. X-rays like this may be taken, but CT is the preferred test because it shows the level and cause and signs of ischemia. (credit: "Upright X-ray demonstrating small bowel obstruction" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 25.2 (Ch. 25): A colon polyp seen during colonoscopy. Removing adenomatous polyps during colonoscopy can prevent them from becoming cancer.

Figure 25.3 (Ch. 25): A permanent colostomy after surgery for rectal cancer (inset). The end of the descending colon is brought out through the left lower abdomen, where stool is collected in a pouch. (credit: National Cancer Institute, public domain)

Figure 25.4 (Ch. 25): A healthy ileostomy stoma: moist and red, with the skin barrier cut to fit closely around it. (credit: "Ostomy wafer being worn by an ileostomy patient" by Eric Polsinelli (VeganOstomy)/Wikimedia Commons, CC BY 4.0)

Figure 25.5 (Ch. 25): A large parastomal hernia around a colostomy in an older man: the abdominal wall bulges around the stoma, under the pouch. A flexible pouching system is preferred over a firm, convex one.

Figure 25.6 (Ch. 25): A one-piece, drainable pouch over an ileostomy. The pouch is emptied when it is about one-third full. (credit: "Ileostomy with bag" by Remedios44/Wikimedia Commons, CC BY-SA 4.0)

Figure 26.1 (Ch. 26): The liver, gallbladder and pancreas, with the ducts that carry bile and pancreatic juice to the duodenum. The image is cropped to the upper abdomen. (credit: modification of Figure 23.24, "Accessory Organs," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 26.2 (Ch. 26): Yellow sclerae in jaundice. The sclerae are a reliable place to look for jaundice on every skin tone. The image is cropped to the eye. (credit: modification of "Jaundice" by OpenRN/Nursing Skills, 2e, CC BY 4.0)

Figure 26.3 (Ch. 26): Spider angiomas on lighter skin: a red central point with fine vessels radiating outward. (credit: "SpiderAngioma" by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

Figure 26.4 (Ch. 26): Palmar erythema in a 79-year-old woman: redness of the palms, most marked at the base of the thumb and little finger. (credit: "Palmar erythema" by Jmarchn/Wikimedia Commons, CC BY-SA 3.0)

Figure 26.5 (Ch. 26): Massive ascites from portal hypertension in cirrhosis: a tense, rounded abdomen with prominent surface veins. (credit: "Hepaticfailure" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 26.6 (Ch. 26): Abdominal paracentesis: a needle or catheter in the abdominal wall drains ascitic fluid into a collection container. (credit: "Blausen 0004 AbdominalParacentesis" by BruceBlaus/Wikimedia Commons, CC BY 3.0)

Figure 26.7 (Ch. 26): Esophageal varices and endoscopic band ligation: elastic bands are placed around the enlarged veins to stop or prevent bleeding. (credit: "Endoscopic Banding for Esophageal Varices" by Kel898/Wikimedia Commons, CC BY-SA 4.0)

Figure 26.8 (Ch. 26): Gallstones removed from one patient, on a 1 mm grid. (credit: "Human gallstones 2015 G1" by George Chernilevsky/Wikimedia Commons, CC BY-SA 4.0)

Figure 26.9 (Ch. 26): Endoscopic retrograde cholangiopancreatography (ERCP): the endoscope enters through the mouth and passes through the stomach to the duodenum, where instruments reach the common bile duct. (credit: "ERCP" by Drus1a/Wikimedia Commons, CC BY-SA 4.0)

Figure 27.1 (Ch. 27): A frontal section of the left kidney: the outer cortex, the pyramids of the medulla, and the calyces and renal pelvis that collect urine into the ureter. (credit: Figure 25.8, "Left Kidney," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 27.2 (Ch. 27): A nephron and its blood supply. Blood is filtered in the glomerulus, and the tubule then reclaims water and solutes into the peritubular capillaries; what remains flows on as urine. (credit: Figure 25.10, "Blood Flow in the Nephron," in Anatomy and Physiology 2e by J. Gordon Betts et al./OpenStax, CC BY-NC-SA 4.0)

Figure 27.3 (Ch. 27): Two urine dipsticks: one with colour changes on several pads (left) beside one with little reaction (right). Each pad is compared with the colour chart on the container at the time stated. (credit: "Comp.Urine.Test.Strip" by J3D3/Wikimedia Commons, CC BY-SA 3.0)

Figure 27.4 (Ch. 27): Uremic frost on the forehead and scalp of a young Black man: fine white crystals left on the skin as sweat evaporates. It is a rare sign of severe, untreated uremia. (credit: "Uremic frost on forehead and scalp of young Afro-Caribbean male" by Fythrion/Wikimedia Commons, CC BY-SA 3.0)

Figure 27.5 (Ch. 27): A hemodialysis machine beside a treatment chair. The blood pump moves blood through the dialyzer, and the screen shows pressures, flow and fluid removal. (credit: "Hemodialysis machine INNOVA" by Vitaly Pospelov (Виталий Поспелов) at Russian Wikipedia/Wikimedia Commons, CC BY-SA 3.0)

Figure 27.6 (Ch. 27): Peritoneal dialysis: sterile dialysate flows through an indwelling catheter into the peritoneal cavity, where water and uremic solutes diffuse across the semipermeable peritoneal membrane before the effluent is drained. (credit: "Peritoneal dialysis" by Manu5 [Scientific Animations]/Wikimedia Commons, CC BY-SA 4.0)

Figure 28.1 (Ch. 28): Emptying a urinary drainage bag: the spout drains into a separate measuring container without touching it, and the bag stays below the level of the bladder. (credit: "Empty the Urinary Drainage Bag" by BruceBlaus/Wikimedia Commons, CC BY-SA 4.0)

Figure 28.2 (Ch. 28): Non-contrast CT showing a stone in the upper right ureter (the bright white spot) causing mild blockage. CT is used carefully, preferably at a low dose. (credit: "KidneyStone" by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 28.3 (Ch. 28): Kidney stone fragments after shock wave lithotripsy, beside a millimetre scale. Patients may be asked to strain their urine so that fragments can be analyzed. (credit: "Kidney stones" by Arconsoli/Wikimedia Commons, CC BY-SA 4.0)

Figure 28.4 (Ch. 28): Comparison of a normal prostate and urethra (top) with benign prostatic hyperplasia (bottom), in which nodular enlargement of the prostate compresses the prostatic urethra and obstructs bladder outflow. (credit: "Benign Prostatic Hyperplasia (BPH)" by BruceBlaus/Wikimedia Commons, CC BY-SA 4.0)

Figure 28.5 (Ch. 28): Visible blood in the urine (gross hematuria), with a dipstick that is positive for blood. Visible hematuria in an adult is always reported and investigated.

Figure 29.1 (Ch. 29): Craniocaudal (CC) and mediolateral oblique (MLO) mammogram views showing grouped microcalcifications (arrows) that warrant diagnostic follow-up. (credit: “Mammogram images of clustered calcifications at CC view and MLO view” by Cerevisae/Wikimedia Commons, CC BY-SA 4.0)

Figure 29.2 (Ch. 29): Healed surgical scar across the breast mound and lateral chest wall following mastectomy and breast reconstruction. (credit: “Breast reconstruction (1)” by Linda Bartlett/National Cancer Institute, Public domain)

Figure 29.3 (Ch. 29): Lateral (sagittal) and anterior views of the internal and external female reproductive organs within the pelvis. (credit: “Figure 27.9, Female Reproductive System” by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 29.4 (Ch. 29): Axial (left) and coronal (right) pelvic CT scans showing a vaginal ring pessary in place supporting the pelvic organs. (credit: “Vaginaler Pessar in der Computertomografie 78W - CT axial und koronar arterielle Phase - 001” by Hellerhoff/Wikimedia Commons, CC BY-SA 4.0)

Figure 29.5 (Ch. 29): A primary syphilitic chancre on the tongue, showing the characteristic firm, round, painless ulcerated lesion at the site of inoculation. (credit: “Circular primary syphilitic chancre on the tongue” by CDC/Robert E. Sumpter, Public Health Image Library #12623, Public domain)

Figure 29.6 (Ch. 29): Sagittal view of the male reproductive and lower urinary structures, including the erectile tissue of the corpus cavernosum and corpus spongiosum (cropped to panel [c]). (credit: modification of “Figure 27.2, Male Reproductive System” by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 30.1 (Ch. 30): Structure of a multipolar neuron in the central nervous system, showing the cell body (soma), dendrites, axon, myelin sheath formed by an oligodendrocyte, nodes of Ranvier and synaptic terminals. (credit: “Figure 12.8, Parts of a Neuron” by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 30.2 (Ch. 30): Lateral view of the cerebral cortex showing the frontal, parietal, occipital and temporal lobes and major sulci and gyri. (credit: “Figure 13.7, Lobes of the Cerebral Cortex” by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 30.3 (Ch. 30): Inferior view of the brain showing where the 12 pairs of cranial nerves (CN I to CN XII) emerge from the forebrain and brainstem. (credit: “Figure 13.23, The Cranial Nerves” by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 30.4 (Ch. 30): Lateral recumbent and seated positions for lumbar puncture, flexing the lumbar spine to widen the interspinous space for needle entry into the subarachnoid space. (credit: “Blausen 0617 LumbarPuncture” by BruceBlaus/Wikimedia Commons, CC BY 3.0)

Figure 30.5 (Ch. 30): Non-contrast head CT showing an acute left-sided subdural hematoma (solid arrows) with mass effect, ventricular compression and midline shift to the right (open arrows). (credit: “Trauma subdural arrows” by Glitzy queen00/Wikimedia Commons, Public domain)

Figure 30.6 (Ch. 30): An external ventricular drain (EVD) system mounted on a bedside pole with the pressure transducer levelled at the external auditory meatus and blood-tinged cerebrospinal fluid in the collection chamber. (credit: “EVD-ICH” by Rmosler2100/Wikimedia Commons, CC BY-SA 3.0)

Figure 31.1 (Ch. 31): Intraparenchymal hemorrhagic stroke: (a) schematic axial view and (b) corresponding non-contrast head CT showing a large hemorrhage compressing the ipsilateral ventricle and shifting the midline. (credit: “1602 The Hemorrhagic Stroke-02” by OpenStax College/Wikimedia Commons, CC BY 3.0)

Figure 31.2 (Ch. 31): Unilateral facial droop—asymmetry of the lower face and mouth—one of the core signs in the FAST™ stroke recognition tool. (credit: “Stroke-facial-droop” by Another-anon-artist-234/Wikimedia Commons, CC0)

Figure 31.3 (Ch. 31): A mobile telestroke system with a high-definition camera and two-way video screen, enabling a remote stroke specialist to examine the patient and review imaging in real time with the bedside team. (credit: “10.1.15 FCC Connect2Health Task Force Beyond the Beltway Series – Jacksonville, FL (22193326376)” by Federal Communications Commission/Wikimedia Commons, Public domain)

Figure 31.4 (Ch. 31): Non-contrast head CT showing an acute intracerebral hemorrhage with intraventricular extension. (credit: “Intracerebral hemorrage (CT scan)” by Glitzy queen00/Wikimedia Commons, Public domain)

Figure 31.5 (Ch. 31): Non-contrast head CT showing acute subarachnoid hemorrhage filling the basal cisterns and left Sylvian fissure, along with a left temporal hemorrhage. (credit: “CT brain showing subarachnoid haemorrhage and left temporal haemorrhage” by Cerevisae/Wikimedia Commons, CC BY-SA 4.0)

Figure 31.6 (Ch. 31): Vascular surgeons performing a carotid endarterectomy to remove atherosclerotic plaque from the internal carotid artery for secondary stroke prevention. (credit: “David Grant USAF Medical Center 110523-F-ML202-008” by Staff Sgt. Liliana Moreno/U.S. Air Force, Public domain)

Figure 32.1 (Ch. 32): Cross-section of the thoracic spinal cord showing the sensory (posterior), autonomic (lateral) and motor (anterior) grey-matter horns and the surrounding white-matter tracts (cropped to the anatomical diagram panel). (credit: modification of “Figure 13.14, Cross-section of Spinal Cord” by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 32.2 (Ch. 32): Human dermatome map showing the cutaneous sensory territories supplied by spinal nerves C2 through S5, used alongside key muscle testing to determine the neurologic level of spinal cord injury. (credit: “1611 Dermatomes-02” by OpenStax Anatomy and Physiology/Wikimedia Commons, CC BY 4.0)

Figure 32.3 (Ch. 32): A rigid cervical collar applied to restrict cervical spine motion until spinal injury is ruled out or stabilized (upper facial profile pixelated). (credit: modification of “LateralCollar” by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 32.4 (Ch. 32): Progression of posture, gait and mobility across the five stages of Parkinson disease on the Hoehn and Yahr scale. (credit: “5 Stages of Parkinson's Disease, Hoehn & Yahr Scale” by Bbmime/Wikimedia Commons, CC BY 4.0)

Figure 32.5 (Ch. 32): Asymmetric ptosis (drooping upper eyelid, right greater than left) and strabismus causing diplopia in a person with myasthenia gravis attempting to open the eyes. (credit: “DiplopiaMG1” by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 32.6 (Ch. 32): Distribution of upper motor neuron (UMN) and lower motor neuron (LMN) involvement across classical spinal-onset, bulbar-onset and variant subtypes of amyotrophic lateral sclerosis (ALS). (credit: "ALS subtypes UMN LMN distribution" by PaulWicks/Wikimedia Commons, CC BY-SA 4.0)

Figure 33.1 (Ch. 33): Anterior and posterior views of the adult human skeleton, showing the 80 bones of the axial skeleton (cranium, vertebral column, thoracic cage) and the 126 bones of the appendicular skeleton (pectoral girdle, pelvic girdle, upper and lower limbs). (credit: "Figure 7.2, Axial and Appendicular Skeleton" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 33.2 (Ch. 33): Common fracture patterns compared with intact bone: (a) closed, (b) open, (c) transverse, (d) spiral, (e) comminuted, (f) impacted, (g) greenstick and (h) oblique. (credit: "612 Types of Fractures" by OpenStax College/Wikimedia Commons, CC BY 4.0)

Figure 33.3 (Ch. 33): Anterior and posterior views of the major skeletal muscles of the human body. (credit: "Figure 11.5, Overview of the Muscular System" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 33.4 (Ch. 33): A short-leg fibreglass cast immobilizing the ankle and foot while leaving the toes exposed for neurovascular checks. (credit: "Purple short leg cast" by Pagemaker787/Wikimedia Commons, CC BY-SA 4.0)

Figure 33.5 (Ch. 33): A unilateral external fixator stabilizing the femur, with metal pins passing through the skin and clamped to an external frame. (credit: "Patient with external fixator in the femur" by Ortopedikus/Wikimedia Commons, CC BY-SA 4.0)

Figure 33.6 (Ch. 33): Lateral spine X-ray showing osteoporotic wedge compression fractures of the L1 and L2 vertebrae, which can cause height loss and a stooped posture.

Figure 33.7 (Ch. 33): (a) Hip X-ray showing a mildly compressed femoral neck fracture (white arrows) in an older adult after an indoor fall; (b) postoperative X-ray after internal fixation with two parallel pins.

Figure 33.8 (Ch. 33): Anteroposterior pelvic X-ray showing a right total hip arthroplasty, with a metal stem in the femur and a prosthetic ball seated in the replaced hip socket.

Figure 33.9 (Ch. 33): A transtibial (below-knee) prosthesis in use during outdoor walking, cropped to the lower limbs. (credit: modification of "Transtibial amputee with Lunaris foot prosthesis" by Axiles Bionics/Wikimedia Commons, CC BY-SA 2.0)

Figure 34.1 (Ch. 34): Structure of a synovial joint, showing the articulating bones, hyaline articular cartilage, joint cavity containing synovial fluid, and the articular capsule composed of an outer fibrous membrane and an inner synovial membrane. (credit: "Figure 9.8, Synovial Joints" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 34.2 (Ch. 34): Bony enlargements at the distal interphalangeal joints (Heberden nodes) in hand osteoarthritis. (credit: "Heberden-Arthrose" by Drahreg01/Wikimedia Commons, CC BY-SA 3.0)

Figure 34.3 (Ch. 34): Anteroposterior X-ray of the left knee showing features of osteoarthritis: joint-space narrowing, increased density of the bone beneath the cartilage and marginal osteophytes (bone spurs). (credit: "Osteoarthritis on X-ray" by James Heilman, MD/Wikimedia Commons, CC BY-SA 4.0)

Figure 34.4 (Ch. 34): Chronic joint changes of rheumatoid arthritis on both hands, including swelling and subluxation at the metacarpophalangeal joints and ulnar deviation of the fingers.

Figure 34.5 (Ch. 34): Tophaceous gout at the first metatarsophalangeal joint with hallux valgus in an older adult; cropped to the foot for patient privacy. (credit: modification of "Tophaceous gout of Lt MTP joint, elder female patient, Thailand" by Chainwit./Wikimedia Commons, CC BY 4.0)

Figure 34.6 (Ch. 34): Systemic lupus erythematosus: (a) common organ and tissue involvement across the body; (b) a butterfly (malar) rash across the cheeks and nasal bridge, sparing the creases beside the nose. (credit: "OSC Microbio 19 02 Lupus" by CNX OpenStax/Wikimedia Commons, CC BY 4.0)

Figure 34.7 (Ch. 34): Well-demarcated digital pallor on exposure to cold in Raynaud phenomenon.

Figure 35.1 (Ch. 35): Cross-section of human skin showing the epidermal layers, dermal structures (hair follicles, glands, nerve endings, blood vessels) and the deeper subcutaneous hypodermis. (credit: "Figure 5.2, Layers of Skin" by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 35.2 (Ch. 35): Stage 1 pressure injury: intact skin with localized, non-blanchable erythema, illustrated in clinical photograph (a) and comparative cross-sections of light skin (b) and dark skin (c). (credit: "Figure 28.5, Stage 1 Pressure Injury" by OpenStax, Medical-Surgical Nursing, CC BY 4.0 / CC BY-NC-SA 4.0)

Figure 35.3 (Ch. 35): Stage 2 pressure injury: partial-thickness skin loss with exposed dermis, showing a viable, pink/red, moist wound bed without slough or granulation tissue. (credit: "Figure 28.6, Stage 2 Pressure Injury" by OpenStax, Medical-Surgical Nursing, CC BY 4.0 / CC BY-NC-SA 4.0)

Figure 35.4 (Ch. 35): Stage 3 pressure injury: full-thickness skin loss with visible subcutaneous fat in the ulcer crater; bone, tendon and muscle are not exposed. (credit: "Figure 28.7, Stage 3 Pressure Injury" by OpenStax, Medical-Surgical Nursing, CC BY 4.0 / CC BY-NC-SA 4.0)

Figure 35.5 (Ch. 35): Stage 4 pressure injury: full-thickness skin and tissue loss with directly exposed and palpable fascia, muscle, tendon or bone. (credit: "Figure 28.8, Stage 4 Pressure Injury" by OpenStax, Medical-Surgical Nursing, CC BY 4.0 / CC BY-NC-SA 4.0)

Figure 35.6 (Ch. 35): (a) Unstageable pressure injury with the true depth of tissue damage obscured by slough and eschar, alongside (b) a deep tissue pressure injury (DTPI) on a heel presenting as persistent, non-blanchable deep red/purple discoloration. (credit: panel [a] from "Figure 28.9, Unstageable Pressure Injury" and panel [b] from "Figure 28.10, Deep Tissue Pressure Injury" by OpenStax, Medical-Surgical Nursing, CC BY 4.0 / CC BY-NC-SA 4.0)

Figure 35.7 (Ch. 35): A surgical incision closed with metal staples seven days after surgery, healing by primary intention with well-approximated edges. (credit: "Surgical staples2" by Llywrch/Wikimedia Commons, CC BY-SA 2.5)

Figure 35.8 (Ch. 35): Dehiscence of an inguinal hernia repair incision, with separated wound edges and a red granulation bed healing by secondary intention. (credit: "Wound Dehiscence post inguinal hernia repair 2014-05-27 00-46" by Phoenix119/Wikimedia Commons, CC BY-SA 3.0)

Figure 35.9 (Ch. 35): Negative pressure wound therapy applied over a midline abdominal surgical incision, with a sealed foam dressing and suction tubing kept separate from the adjacent colostomy pouch. (credit: "Colostomy with wound vacuum (negative-pressure wound therapy) applied" by Hu Nhu/Wikimedia Commons, CC BY 4.0)

Figure 35.10 (Ch. 35): Cellulitis of the toes and forefoot, with spreading redness and swelling of the skin.

Figure 35.11 (Ch. 35): Classification of burn depth: superficial (first degree, affecting the epidermis), partial thickness (second degree, extending into the dermis with blisters), and full thickness (third degree, destroying all epidermal and dermal layers into subcutaneous tissue). (credit: “Figure 8.14, Burn Depth” by Persian Poet Gal/OpenStax, Clinical Nursing Skills, CC BY 3.0)] A **superficial burn** involves only the epidermis. A **partial-thickness burn** extends into the dermis: a superficial partial-thickness burn involves the upper dermis, and a deep partial-thickness burn reaches deeper into it. A **full-thickness burn** destroys the epidermis and the whole dermis and can extend to fat, muscle, tendon or bone (Wallace et al., 2025). Older terms number these as first, second and third degree, with fourth degree used when muscle or bone is involved (Trauma New Brunswick, 2025). Depth is hard to judge: even burn experts are accurate only 64% to 76% of the time, so early estimates are rechecked (Wallace et al., 2025). Healed superficial partial-thickness burns can stay sensitive to sun, cold and friction for months, and they may itch (Wallace et al., 2025). Redness and blanching can be harder to see on darker skin, so the nurse also notes blisters, moisture, texture, capillary refill and sensation (Black & Simende, 2020).

Figure 35.12 (Ch. 35): Body regions used in the adult Wallace rule of nines: the head and neck and each upper limb are 9% each, the anterior trunk, posterior trunk and each lower limb are 18% each (9% front and 9% back), and the perineum is 1%.

Figure 35.13 (Ch. 35): Acral lentiginous melanoma: (a) a large asymmetric pigmented lesion with irregular borders and varied brown-to-black colour on the sole of the foot; (b) subungual melanoma of the thumb. Checking the palms, soles and nail beds is part of a complete skin assessment across all skin tones. (credit: (a) “Photography of a large acral lentiginous melanoma” by José C. C. Xavier-Júnior et al./Diagnostic Pathology, CC BY 4.0; (b) “Melanoma of thumb” by Wawjak/Wikimedia Commons, CC BY 4.0)

Figure 35.14 (Ch. 35): Herpes zoster (shingles): clustered vesicles on an erythematous base following a single unilateral dermatome on the back without crossing the midline. (credit: “Herpes Zoster Rash” by BruceBlaus/Wikimedia Commons, CC BY-SA 4.0)

Figure 36.1 (Ch. 36): Cross-sectional anatomy of the human eye showing refractive structures (cornea, lens), anterior and posterior chambers, vascular uvea (iris, ciliary body, choroid), neurosensory retina and optic nerve. (credit: “Figure 14.15, Structure of the Eye” by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 36.2 (Ch. 36): A Snellen letter chart used to measure distance visual acuity. (credit: “Snellen Chart” by Creative magnet/Wikimedia Commons, CC BY-SA 4.0)

Figure 36.3 (Ch. 36): Slit-lamp view of a dense cataract clouding the crystalline lens behind the pupil. (credit: “Cataract in human eye” by Rakesh Ahuja, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 36.4 (Ch. 36): Instilling eye drops: the patient looks up while the nurse gently pulls down the lower lid to form a pocket and holds the dropper tip clear of the eye and eyelashes. (credit: “Instilling eye medication” by British Columbia Institute of Technology (BCIT)/BCcampus, CC BY 4.0)

Figure 36.5 (Ch. 36): Acute angle-closure glaucoma of the right eye, showing conjunctival redness, corneal haziness and a mid-dilated, non-reactive pupil (cropped to the affected eye). (credit: modification of “Acute angle closure glaucoma” by James Heilman, MD/Wikimedia Commons, CC BY-SA 3.0)

Figure 36.6 (Ch. 36): Retinal fundus photograph showing clustered yellow drusen in the macula in age-related macular degeneration. (credit: “MacularDegenerationFundus” by Tmhlee/Wikimedia Commons, CC BY-SA 3.0)

Figure 36.7 (Ch. 36): Prominent hyphema filling the anterior chamber in front of the iris, with surrounding ciliary injection. (credit: “12886 2014 Article 436 Fig1 HTML” by Yoko Okunuki et al./BMC Ophthalmology, CC BY 4.0)

Figure 36.8 (Ch. 36): Anatomy of the human ear showing the external ear, the air-filled middle ear containing the auditory ossicles (malleus, incus, stapes) and tympanic membrane, and the fluid-filled inner ear (cochlea and vestibular apparatus). (credit: “Figure 14.5, Ear Structures” by J. Gordon Betts et al./OpenStax, Anatomy and Physiology 2e, CC BY-NC-SA 4.0)

Figure 36.9 (Ch. 36): Otoscopic view of a right tympanic membrane showing the translucent pearly grey eardrum and landmarks (the small black dot is India ink placed to demonstrate normal outward migration of the canal epithelium). (credit: “Ink Dot on the surface of the tympanic membrane 1 week later” by Michael Hawke, MD/Wikimedia Commons, CC BY 4.0)

Figure 36.10 (Ch. 36): An external behind-the-ear cochlear implant sound processor and its round magnetic transmitting headpiece, which sits over the internal receiver under the scalp. (credit: “Advanced Bionics cochlear implant processor BTE (first-generation behind-the-ear processor)” by MikeCore9918/Wikimedia Commons, CC BY-SA 4.0)

Figure 36.11 (Ch. 36): A behind-the-ear hearing aid with tubing leading to an earmold in the ear canal. (credit: “Behind-the-Ear Hearing Aid grayscale photo” by Steve Johnson/Wikimedia Commons, CC BY 2.0)

Figure 36.12 (Ch. 36): Instilling ear drops in an adult: the patient lies with the affected ear up while the nurse gently pulls the pinna upward and backward to straighten the ear canal and holds the dropper tip clear of the skin. (credit: “Instilling ear medication” by British Columbia Institute of Technology (BCIT)/BCcampus, CC BY 4.0)

BACK MATTER — ALPHABETICAL SUBJECT & CONCEPT INDEX *Index*

IX Comprehensive Subject & Clinical Concept Index

2SLGBTQI+ — Ch. 2, p. 35
4AT — Ch. 8, p. 206
5-alpha reductase inhibitor (5-ARI) — Ch. 28, p. 822
A1C — Ch. 22, p. 635
Abdominal Aortic Aneurysm — s. 19.5, p. 538
abdominal aortic aneurysm (AAA) — Ch. 19, p. 538
abdominoperineal resection — Ch. 25, p. 727
abnormal extension — Ch. 30, p. 883
abnormal flexion — Ch. 30, p. 883
abnormal uterine bleeding — Ch. 29, p. 852
abscess — Ch. 35, p. 1040
absolute neutrophil count (ANC) — Ch. 9, p. 234
acanthosis nigricans — Ch. 22, p. 635
acidemia — Ch. 3, p. 67
acidosis — Ch. 3, p. 67
Acid–Base Balance — s. 3.7, p. 67
acquired immunodeficiency syndrome (AIDS) / advanced HIV disease — Ch. 21, p. 601
acral melanoma — Ch. 35, p. 1040
acromegaly — Ch. 23, p. 665
action plan — Ch. 18, p. 504
active offer — Ch. 1, p. 2
active surveillance — Ch. 28, p. 822
Acute and Chronic Pancreatitis — s. 26.6, p. 759
acute angle-closure glaucoma — Ch. 36, p. 1075
acute aortic syndrome — Ch. 19, p. 538
acute chest syndrome — Ch. 20, p. 569
acute cholecystitis — Ch. 26, p. 759
acute colonic pseudo-obstruction — Ch. 25, p. 727
acute coronary syndrome (ACS) — Ch. 17, p. 476
acute decompensated heart failure (ADHF) — Ch. 18, p. 504
acute exacerbation of COPD — Ch. 14, p. 380
acute heart failure — Ch. 18, p. 504
acute hemolytic transfusion reaction — Ch. 20, p. 569
acute HIV infection — Ch. 21, p. 601
acute inflammation — Ch. 4, p. 97
Acute Kidney Injury — s. 27.2, p. 791
acute kidney injury (AKI) — Ch. 27, p. 791
Acute Kidney Injury and Chronic Kidney Disease — Ch. 27, p. 791
acute limb ischemia — Ch. 19, p. 538
acute liver failure (ALF) — Ch. 26, p. 759
acute pain — Ch. 5, p. 125
acute pancreatitis — Ch. 26, p. 759
acute pulmonary edema — Ch. 18, p. 504
Acute Respiratory Distress Syndrome — s. 15.2, p. 409
acute respiratory distress syndrome — Ch. 15, p. 409
Acute Respiratory Failure — s. 15.1, p. 409
acute respiratory failure — Ch. 15, p. 409
Acute Respiratory Failure and Pulmonary Embolism — Ch. 15, p. 409
acute severe ulcerative colitis — Ch. 25, p. 727
acute tubular injury — Ch. 27, p. 791
adaptive immunity — Ch. 21, p. 601
Addison disease — Ch. 23, p. 665
additional precautions — Ch. 4, p. 97
adenoma — Ch. 25, p. 727
adhesions — Ch. 25, p. 727
adjuvant analgesic — Ch. 5, p. 125
adjuvant therapy — Ch. 9, p. 234
adrenal cortex — Ch. 23, p. 665
adrenal crisis — Ch. 23, p. 665
Adrenal Disorders — s. 23.4, p. 665
adrenal insufficiency — Ch. 23, p. 665
adrenal medulla — Ch. 23, p. 665
advance care planning — Ch. 32, p. 943
advance care planning (ACP) — Ch. 10, p. 264
Advance Care Planning and Goals of Care — s. 10.2, p. 264
adverse event following immunization (AEFI) — Ch. 21, p. 601
afterload — Ch. 6, p. 152
age-adjusted D-dimer cut-off — Ch. 15, p. 409
age-related macular degeneration (AMD) — Ch. 36, p. 1075
ageism — Ch. 8, p. 206
agent — Ch. 1, p. 2
Aging, Frailty and Acute Care — s. 8.1, p. 206
agranulocytosis — Ch. 23, p. 665
air leak — Ch. 15, p. 409
air trapping — Ch. 14, p. 380
airborne infection isolation room (AIIR) — Ch. 4, p. 97
airborne precautions — Ch. 4, p. 97
Airway Clearance — s. 12.5, p. 318
airway hyperresponsiveness — Ch. 14, p. 380
airway resistance — Ch. 12, p. 318
alarm fatigue — Ch. 16, p. 439
alarm features — Ch. 24, p. 696
albumin — Ch. 3, p. 67
albuminuria — Ch. 27, p. 791
Alcohol Withdrawal — s. 11.3, p. 290
alcohol withdrawal — Ch. 11, p. 290
alcohol-associated hepatitis — Ch. 26, p. 759
alcohol-related liver disease (ALD) — Ch. 26, p. 759
Alcohol-Related Liver Disease, Acute Liver Failure and Transplant — s. 26.4, p. 759
alcoholic hallucinosis — Ch. 11, p. 290
aldosterone — Ch. 3, p. 67
alkalemia — Ch. 3, p. 67
alkalosis — Ch. 3, p. 67
allergy — Ch. 21, p. 601
allergy (drug) — Ch. 4, p. 97
allodynia — Ch. 5, p. 125
alpha-1 antitrypsin deficiency — Ch. 14, p. 380
alpha-blocker — Ch. 28, p. 822
alternate level of care (ALC) — Ch. 1, p. 2
alveolar–capillary membrane — Ch. 12, p. 318
alveoli — Ch. 12, p. 318
ambulatory blood pressure monitoring (ABPM) — Ch. 19, p. 538
ambulatory surgery — Ch. 7, p. 179
American Sign Language (ASL) — Ch. 36, p. 1075
Amputation — s. 33.6, p. 976
amputation — Ch. 33, p. 976
amyotrophic lateral sclerosis (ALS) — Ch. 32, p. 943
Amyotrophic Lateral Sclerosis and Living With Progressive Neurologic Disease — s. 32.6, p. 943
anaphylaxis — Ch. 6, p. 152
anastomosis — Ch. 25, p. 727
anastomotic leak — Ch. 24, p. 696
androgen deprivation therapy (ADT) — Ch. 28, p. 822
anemia — Ch. 20, p. 569
anemia of inflammation — Ch. 20, p. 569
Anemias — s. 20.2, p. 569
Anesthesia and Sedation — s. 7.4, p. 179
anesthesia assistant — Ch. 7, p. 179
anginal equivalent — Ch. 17, p. 476
angioedema — Ch. 18, p. 504
angiotensin receptor–neprilysin inhibitor (ARNI) — Ch. 18, p. 504
anion gap — Ch. 3, p. 67
ankle-brachial index (ABI) — Ch. 19, p. 538
anogenital warts — Ch. 29, p. 852
anti-Black racism — Ch. 2, p. 35
anti-CCP antibodies — Ch. 34, p. 1008
anti-racism — Ch. 2, p. 35
anti-VEGF therapy — Ch. 36, p. 1075
antibiotic-resistant organism (ARO) — Ch. 4, p. 97
Antibiotic-Resistant Organisms and C. difficile — s. 4.4, p. 97
antibody — Ch. 21, p. 601
anticholinergic burden — Ch. 8, p. 206
anticipatory grief — Ch. 10, p. 264

anticipatory medications — Ch. 10, p. 264
anticoagulant — Ch. 19, p. 538
Anticoagulation — s. 19.7, p. 538
antidiuretic hormone (ADH) — Ch. 3, p. 67
antifibrotic — Ch. 14, p. 380
antigen — Ch. 21, p. 601
antimicrobial stewardship — Ch. 4, p. 97
Antimicrobial Stewardship and the Nurse — s. 4.5, p. 97
antiplatelet therapy — Ch. 31, p. 913
antiretroviral therapy (ART) — Ch. 21, p. 601
antiseizure medication — Ch. 30, p. 883
antiviral — Ch. 13, p. 349
aortic dissection — Ch. 19, p. 538
aortic stenosis — Ch. 18, p. 504
aphasia — Ch. 30, p. 883
aplastic anemia — Ch. 20, p. 569
apnea — Ch. 10, p. 264
apolipoprotein B (ApoB) — Ch. 17, p. 476
apoptosis — Ch. 9, p. 234
appendicitis — Ch. 25, p. 727
appendicolith — Ch. 25, p. 727
aqueous humour — Ch. 36, p. 1075
areflexia — Ch. 32, p. 943
arginine vasopressin deficiency (AVP-D) — Ch. 23, p. 665
arginine vasopressin resistance (AVP-R) — Ch. 23, p. 665
arterial blood gas (ABG) — Ch. 3, p. 67
arteriovenous fistula (AV fistula) — Ch. 27, p. 791
arteriovenous graft (AV graft) — Ch. 27, p. 791
arthritis — Ch. 34, p. 1008
Arthritis and Connective Tissue Disorders — Ch. 34, p. 1008
articular cartilage — Ch. 34, p. 1008
artifact — Ch. 16, p. 439
Artificial Airways and Tracheostomy Care — s. 12.6, p. 318
artificial nutrition and hydration — Ch. 10, p. 264
ASA Physical Status classification — Ch. 7, p. 179
ascending paralysis — Ch. 32, p. 943
ascites — Ch. 26, p. 759
aspiration — Ch. 13, p. 349
aspiration pneumonia — Ch. 13, p. 349
aspiration pneumonitis — Ch. 13, p. 349
asterixis — Ch. 26, p. 759
Asthma — s. 14.2, p. 380
asthma — Ch. 14, p. 380
asthma control — Ch. 14, p. 380
asthma exacerbation — Ch. 14, p. 380
asymptomatic bacteriuria — Ch. 29, p. 852
asymptomatic bacteriuria (ASB) — Ch. 28, p. 822
asystole — Ch. 16, p. 439
atelectasis — Ch. 7, p. 179
atherosclerosis — Ch. 17, p. 476
Atherosclerosis and Cardiovascular Risk — s. 17.1, p. 476
atrial fibrillation (AF) — Ch. 16, p. 439
Atrial Fibrillation and Flutter — s. 16.6, p. 439
atrial flutter — Ch. 16, p. 439
atrioventricular (AV) node — Ch. 16, p. 439
atypical bacteria — Ch. 13, p. 349
audiogram — Ch. 36, p. 1075
AUDIT-C — Ch. 11, p. 290
authorizing mechanism — Ch. 1, p. 2
autoimmune disease — Ch. 34, p. 1008
autoimmunity — Ch. 21, p. 601
Autoimmunity and Adult Immunization — s. 21.6, p. 601
automated external defibrillator (AED) — Ch. 16, p. 439
automated office blood pressure (AOBP) — Ch. 19, p. 538
autonomic dysfunction — Ch. 32, p. 943
autonomic dysreflexia — Ch. 32, p. 943
autonomic neuropathy — Ch. 22, p. 635
autoregulation — Ch. 30, p. 883
axillary lymph node dissection — Ch. 29, p. 852
axis — Ch. 23, p. 665
B symptoms — Ch. 20, p. 569
back slab — Ch. 33, p. 976
bacterial meningitis — Ch. 30, p. 883
balanced solution — Ch. 3, p. 67
bariatric surgery — Ch. 24, p. 696
Barrett esophagus — Ch. 24, p. 696
basal cell carcinoma — Ch. 35, p. 1040
basal insulin — Ch. 22, p. 635
basal-bolus insulin — Ch. 22, p. 635
Beck's triad — Ch. 18, p. 504
Beers Criteria — Ch. 8, p. 206
benign paroxysmal positional vertigo (BPPV) — Ch. 36, p. 1075
benign prostatic hyperplasia (BPH) — Ch. 28, p. 822
Benign Prostatic Hyperplasia and Prostate Surgery — s. 28.5, p. 822
bereavement — Ch. 10, p. 264
best possible medication history — Ch. 1, p. 2
bilateral salpingo-oophorectomy — Ch. 29, p. 852
bilevel positive airway pressure — Ch. 15, p. 409
biliary colic — Ch. 26, p. 759
bilirubin — Ch. 26, p. 759
biofilm — Ch. 35, p. 1040
biologic — Ch. 14, p. 380
biologic therapy — Ch. 25, p. 727
bioprosthetic valve — Ch. 18, p. 504
biopsy — Ch. 29, p. 852
biosimilar — Ch. 22, p. 635
biphasic reaction — Ch. 6, p. 152
bitemporal visual field loss — Ch. 23, p. 665
bladder diary — Ch. 28, p. 822
bladder scanner — Ch. 28, p. 822
bladder training — Ch. 28, p. 822
Bleeding and Clotting Disorders — s. 20.4, p. 569
Blood and Its Tests — s. 20.1, p. 569
blood component — Ch. 20, p. 569
Blood Components and Transfusion — s. 20.6, p. 569
blood culture — Ch. 13, p. 349
blood–brain barrier — Ch. 30, p. 883
Body Fluids and How They Are Regulated — s. 3.1, p. 67
bolus — Ch. 24, p. 696
bolus (prandial) insulin — Ch. 22, p. 635
bone mineral density (BMD) — Ch. 33, p. 976
Bowel Function, Constipation and Diarrhea — s. 25.1, p. 727
bowel obstruction — Ch. 25, p. 727
Bowel Obstruction and Ileus — s. 25.4, p. 727
bowel regimen — Ch. 5, p. 125
brachytherapy — Ch. 9, p. 234
bradykinesia — Ch. 32, p. 943
brainstem — Ch. 30, p. 883
Breast Cancer Care — s. 29.2, p. 852
breast-conserving surgery — Ch. 29, p. 852
Breathing and Gas Exchange: A Brief Review — s. 12.1, p. 318
brief intervention — Ch. 11, p. 290
briefing — Ch. 7, p. 179
Bristol Stool Form Scale — Ch. 25, p. 727
bronchiectasis — Ch. 14, p. 380
Bronchiectasis, Interstitial Lung Disease and Sleep Apnea — s. 14.6, p. 380
bronchoconstriction — Ch. 14, p. 380
bruit — Ch. 27, p. 791
buffer — Ch. 3, p. 67
buprenorphine — Ch. 5, p. 125
burn — Ch. 35, p. 1040
Burns — s. 35.5, p. 1040
C-reactive protein (CRP) — Ch. 4, p. 97
cachexia — Ch. 10, p. 264
Cairo–Bishop criteria — Ch. 9, p. 234
Calcium, Magnesium and Phosphate — s. 3.6, p. 67
Calls to Action — Ch. 2, p. 35
Canada Health Act — Ch. 1, p. 2
Canadian Nosocomial Infection Surveillance Program (CNISP) — Ch. 4, p. 97
Canadian Nutrition Screening Tool (CNST) — Ch. 24, p. 696
Canadian Problem Checklist — Ch. 9, p. 234
Canadian Triage and Acuity Scale (CTAS) — Ch. 6, p. 152
canalith repositioning manoeuvre — Ch. 36, p. 1075
Cancer Biology — s. 9.1, p. 234
Cancer Care — Ch. 9, p. 234
Cancer in Canada: Risk, Prevention and Screening — s. 9.2, p. 234
Cancer Treatments — s. 9.3, p. 234
cancer-related fatigue — Ch. 9, p. 234
cannabinoid hyperemesis syndrome (CHS) — Ch. 11, p. 290
Cannabis Act — Ch. 11, p. 290
capacity — Ch. 1, p. 2

capnography — Ch. 5, p. 125
carbapenemase-producing organism (CPO) — Ch. 4, p. 97
carbon monoxide poisoning — Ch. 35, p. 1040
carcinogen — Ch. 9, p. 234
carcinogenesis — Ch. 9, p. 234
cardiac amyloidosis — Ch. 18, p. 504
Cardiac Assessment and Dysrhythmias — Ch. 16, p. 439
Cardiac Monitoring and Reading a Rhythm Strip — s. 16.4, p. 439
cardiac output — Ch. 6, p. 152
cardiac rehabilitation — Ch. 17, p. 476
Cardiac Rehabilitation and Living With Coronary Disease — s. 17.6, p. 476
cardiac resynchronization therapy (CRT) — Ch. 18, p. 504
cardiac tamponade — Ch. 6, p. 152
Cardiac Tests — s. 16.3, p. 439
cardiogenic shock — Ch. 6, p. 152
cardiomyopathy — Ch. 18, p. 504
Care After Anesthesia (PACU) — s. 7.5, p. 179
Care Around PCI and CABG — s. 17.5, p. 476
Care Coordination Service — Ch. 10, p. 264
caregiver — Ch. 32, p. 943
caregiver strain — Ch. 8, p. 206
Caring for Other Equity-Deserving Adults — s. 2.5, p. 35
carotid bodies — Ch. 12, p. 318
cast — Ch. 33, p. 976
cataract — Ch. 36, p. 1075
Cataract, Glaucoma and Other Causes of Vision Loss — s. 36.2, p. 1075
catheter-associated urinary tract infection (CAUTI) — Ch. 28, p. 822
CD4 T cell — Ch. 21, p. 601
cellulitis — Ch. 35, p. 1040
central cyanosis — Ch. 12, p. 318
central nervous system (CNS) — Ch. 30, p. 883
central sensitization — Ch. 5, p. 125
central venous access device — Ch. 24, p. 696
central venous catheter for dialysis — Ch. 27, p. 791
cerebellum — Ch. 30, p. 883
cerebral amyloid angiopathy — Ch. 31, p. 913
cerebral aneurysm — Ch. 31, p. 913
cerebral edema — Ch. 30, p. 883
cerebral perfusion pressure — Ch. 30, p. 883
cerebrospinal fluid (CSF) — Ch. 30, p. 883
cerebrospinal fluid (CSF) leak — Ch. 23, p. 665
cerebrum — Ch. 30, p. 883
cerumen — Ch. 36, p. 1075
cerumen impaction — Ch. 36, p. 1075
CHADS-65 — Ch. 16, p. 439
chain of infection — Ch. 4, p. 97
Charcot triad — Ch. 26, p. 759
Charles Bonnet syndrome — Ch. 36, p. 1075
chemical eye injury — Ch. 36, p. 1075
chemical restraint — Ch. 8, p. 206
chemotherapy — Ch. 9, p. 234
chest physiotherapy — Ch. 12, p. 318
chest tube — Ch. 15, p. 409
Chest Tubes and Chest Drainage — s. 15.5, p. 409
Cheyne-Stokes respiration — Ch. 10, p. 264
Cheyne–Stokes breathing — Ch. 12, p. 318
chlamydia — Ch. 29, p. 852
cholangitis — Ch. 26, p. 759
choledocholithiasis — Ch. 26, p. 759
cholelithiasis — Ch. 26, p. 759
cholinergic crisis — Ch. 32, p. 943
chosen family — Ch. 2, p. 35
chosen name — Ch. 2, p. 35
chronic bronchitis — Ch. 14, p. 380
chronic inflammation — Ch. 4, p. 97
Chronic Kidney Disease — s. 27.3, p. 791
chronic kidney disease (CKD) — Ch. 27, p. 791
chronic limb-threatening ischemia (CLTI) — Ch. 19, p. 538
Chronic Obstructive Pulmonary Disease — s. 14.4, p. 380
chronic obstructive pulmonary disease (COPD) — Ch. 14, p. 380
chronic pain — Ch. 5, p. 125
chronic pancreatitis — Ch. 26, p. 759
chronic postsurgical pain — Ch. 5, p. 125
chronic venous insufficiency (CVI) — Ch. 19, p. 538
chronic wound — Ch. 35, p. 1040
Chvostek's sign — Ch. 3, p. 67
circle of care — Ch. 1, p. 2
cirrhosis — Ch. 26, p. 759
Cirrhosis and Its Complications — s. 26.3, p. 759
cisgender — Ch. 2, p. 35
CIWA-Ar — Ch. 11, p. 290
CKD–mineral and bone disorder (CKD–MBD) — Ch. 27, p. 791
clinical deterioration — Ch. 6, p. 152
Clinical Frailty Scale (CFS) — Ch. 8, p. 206
clinical judgment — Ch. 1, p. 2
Clinical Judgment Measurement Model (CJMM) — Ch. 1, p. 2
Clinical Judgment: The Clinical Judgment Measurement Model — s. 1.4, p. 2
Clinical Opiate Withdrawal Scale (COWS) — Ch. 11, p. 290
clinician-administered MAID — Ch. 10, p. 264
clipping — Ch. 31, p. 913
closed fracture — Ch. 33, p. 976
closed suction drain — Ch. 29, p. 852
closed-loop communication — Ch. 6, p. 152
closed-loop obstruction — Ch. 25, p. 727
closed-system drug-transfer device (CSTD) — Ch. 9, p. 234
Clostridioides difficile — Ch. 4, p. 97
clot retention — Ch. 28, p. 822
clubbing — Ch. 12, p. 318
cochlea — Ch. 36, p. 1075
cochlear implant — Ch. 36, p. 1075
Code of Conduct — Ch. 1, p. 2
code stroke — Ch. 31, p. 913
coffee-ground emesis — Ch. 24, p. 696
coiling — Ch. 31, p. 913
cold chain — Ch. 21, p. 601
colloid — Ch. 3, p. 67
colonization — Ch. 4, p. 97
colonoscopy — Ch. 25, p. 727
colorectal cancer — Ch. 25, p. 727
Colorectal Cancer Care — s. 25.5, p. 727
colostomy — Ch. 25, p. 727
commercial tobacco — Ch. 14, p. 380
comminuted fracture — Ch. 33, p. 976
Common Dysrhythmias and How to Respond — s. 16.5, p. 439
communication access — Ch. 36, p. 1075
Communication Access, Hearing Aids and Cochlear Implants — s. 36.5, p. 1075
Community-Acquired Pneumonia — s. 13.1, p. 349
community-acquired pneumonia (CAP) — Ch. 13, p. 349
compartment syndrome — Ch. 33, p. 976
compassion fatigue — Ch. 10, p. 264
compensated cirrhosis — Ch. 26, p. 759
compensated respiratory acidosis — Ch. 14, p. 380
compensated shock — Ch. 6, p. 152
compensation — Ch. 3, p. 67
competence — Ch. 1, p. 2
complete blood count (CBC) — Ch. 20, p. 569
complete injury — Ch. 32, p. 943
compliance — Ch. 12, p. 318
Complications After Musculoskeletal Injury — s. 33.2, p. 976
comprehensive pain assessment — Ch. 5, p. 125
compression ultrasound — Ch. 19, p. 538
computed tomography (CT) — Ch. 30, p. 883
concern about falling — Ch. 8, p. 206
concussion — Ch. 32, p. 943
conductive hearing loss — Ch. 36, p. 1075
Confusion Assessment Method (CAM) — Ch. 8, p. 206
Confusion Assessment Method for the ICU — Ch. 15, p. 409
congenital syphilis — Ch. 29, p. 852
conscientious objection — Ch. 10, p. 264
Consent and Capacity Board — Ch. 10, p. 264
Consent and the Day of Surgery — s. 7.3, p. 179
conservative kidney management (CKM) — Ch. 27, p. 791
consolidation — Ch. 13, p. 349
constipation — Ch. 25, p. 727
contact precautions — Ch. 4, p. 97
contingency management — Ch. 11, p. 290
continuous bladder irrigation (CBI) — Ch. 28, p. 822
continuous glucose monitoring (CGM) — Ch. 22, p. 635

continuous positive airway pressure — Ch. 15, p. 409
continuous positive airway pressure (CPAP) — Ch. 14, p. 380
contractility — Ch. 16, p. 439
contracture — Ch. 33, p. 976
contrast-associated acute kidney injury — Ch. 17, p. 476
controlled act — Ch. 1, p. 2
controller — Ch. 14, p. 380
COPD Assessment Test (CAT) — Ch. 14, p. 380
cornea — Ch. 36, p. 1075
corneal abrasion — Ch. 36, p. 1075
coronary artery bypass grafting (CABG) — Ch. 17, p. 476
Coronary Artery Disease and Acute Coronary Syndromes — Ch. 17, p. 476
correction insulin — Ch. 22, p. 635
corticosteroid — Ch. 34, p. 1008
corticosteroid-dependent — Ch. 25, p. 727
cortisol — Ch. 23, p. 665
costovertebral angle — Ch. 28, p. 822
COVID-19 — Ch. 13, p. 349
COX-2 inhibitor — Ch. 5, p. 125
crackles — Ch. 12, p. 318
craniotomy — Ch. 30, p. 883
creatinine — Ch. 27, p. 791
critical value — Ch. 20, p. 569
Critical-Care Pain Observation Tool (CPOT) — Ch. 5, p. 125
Crohn disease — Ch. 25, p. 727
crossmatch — Ch. 20, p. 569
cryoprecipitate — Ch. 20, p. 569
crystalloid — Ch. 3, p. 67
CT angiography (CTA) — Ch. 31, p. 913
CT pulmonary angiography (CTPA) — Ch. 15, p. 409
cue — Ch. 1, p. 2
cuff — Ch. 12, p. 318
Cullen sign — Ch. 26, p. 759
cultural competence — Ch. 2, p. 35
cultural humility — Ch. 2, p. 35
cultural safety — Ch. 2, p. 35
Cultural Safety, Humility and Trauma- and Violence-Informed Care — s. 2.2, p. 35
CURB-65 — Ch. 13, p. 349
Cushing disease — Ch. 23, p. 665
Cushing syndrome — Ch. 23, p. 665
Cushing triad — Ch. 30, p. 883
cystitis — Ch. 28, p. 822
cytokine release syndrome — Ch. 9, p. 234
cytokines — Ch. 4, p. 97
D-dimer — Ch. 15, p. 409
daily weight — Ch. 3, p. 67
data sovereignty — Ch. 2, p. 35
dead space — Ch. 12, p. 318
Deaf — Ch. 36, p. 1075
debriefing — Ch. 7, p. 179
decannulation — Ch. 12, p. 318
decompensated cirrhosis — Ch. 26, p. 759
decompression — Ch. 28, p. 822
deep tissue pressure injury (DTPI) — Ch. 35, p. 1040
deep vein thrombosis (DVT) — Ch. 15, p. 409
defibrillation — Ch. 16, p. 439
dehiscence — Ch. 7, p. 179
delabelling — Ch. 21, p. 601
delayed cerebral ischemia — Ch. 31, p. 913
delayed primary intention — Ch. 35, p. 1040
delegation — Ch. 1, p. 2
Delirium — s. 8.2, p. 206
delirium — Ch. 8, p. 206
delirium tremens — Ch. 11, p. 290
dementia — Ch. 8, p. 206
Dementia and Depression in Hospital — s. 8.3, p. 206
demyelination — Ch. 32, p. 943
dependent rubor — Ch. 19, p. 538
depolarization — Ch. 16, p. 439
deprescribing — Ch. 8, p. 206
depression — Ch. 8, p. 206
dermis — Ch. 35, p. 1040
desmopressin — Ch. 23, p. 665
determinants of health — Ch. 2, p. 35
device-related pressure injury — Ch. 35, p. 1040
Diabetes — Ch. 22, p. 635
diabetes distress — Ch. 22, p. 635
Diabetes in Hospital, Complications and Living Well — s. 22.6, p. 635
diabetic foot ulcer — Ch. 22, p. 635
diabetic ketoacidosis (DKA) — Ch. 22, p. 635
diabetic retinopathy — Ch. 36, p. 1075
diagnostic overshadowing — Ch. 2, p. 35
Dialysis — s. 27.4, p. 791
dialysis disequilibrium syndrome — Ch. 27, p. 791
dialyzer — Ch. 27, p. 791
diarrhea — Ch. 25, p. 727
diastolic dysfunction — Ch. 18, p. 504
diffuse axonal injury — Ch. 32, p. 943
diffusing capacity — Ch. 14, p. 380
diffusion — Ch. 12, p. 318
Digestion and Nutrition Assessment — s. 24.1, p. 696
digital chest drainage — Ch. 15, p. 409
dilated cardiomyopathy — Ch. 18, p. 504
direct oral anticoagulant (DOAC) — Ch. 19, p. 538
direct order — Ch. 1, p. 2
direct-acting antiviral — Ch. 26, p. 759
directive — Ch. 1, p. 2
directly observed therapy (DOT) — Ch. 13, p. 349
disability — Ch. 2, p. 35
discectomy — Ch. 33, p. 976
disclosure — Ch. 1, p. 2
disease-modifying antirheumatic drug (DMARD) — Ch. 34, p. 1008
disease-modifying therapy (DMT) — Ch. 32, p. 943
diseases of public health significance — Ch. 4, p. 97
disseminated intravascular coagulation (DIC) — Ch. 20, p. 569
distinctions-based approach — Ch. 2, p. 35
distress — Ch. 9, p. 234
distress screening — Ch. 9, p. 234
Distributive and Obstructive Shock — s. 6.5, p. 152
distributive shock — Ch. 6, p. 152
Diverticular Disease and Appendicitis — s. 25.3, p. 727
diverticulitis — Ch. 25, p. 727
diverticulosis — Ch. 25, p. 727
door-to-needle time — Ch. 31, p. 913
DRESS — Ch. 21, p. 601
droplet precautions — Ch. 4, p. 97
drug checking — Ch. 11, p. 290
drug intolerance — Ch. 21, p. 601
drug-resistant TB — Ch. 13, p. 349
dry powder inhaler (DPI) — Ch. 14, p. 380
dry suction — Ch. 15, p. 409
dual antiplatelet therapy (DAPT) — Ch. 17, p. 476
Duke-ISCVID criteria — Ch. 18, p. 504
dumping syndrome — Ch. 24, p. 696
duty to accommodate — Ch. 2, p. 35
dysarthria — Ch. 30, p. 883
dyskinesia — Ch. 32, p. 943
dyspepsia — Ch. 24, p. 696
dysphagia — Ch. 24, p. 696
Dysphagia and Texture-Modified Diets — s. 24.3, p. 696
dysphagia screening — Ch. 31, p. 913
dyspnea — Ch. 10, p. 264
dysrhythmia — Ch. 16, p. 439
dysuria — Ch. 28, p. 822
Ear Disorders and Ear Surgery — s. 36.6, p. 1075
early supported discharge — Ch. 31, p. 913
Early Treatment and Complications of ACS — s. 17.4, p. 476
early warning score — Ch. 6, p. 152
Early Warning Scores and Escalation — s. 6.2, p. 152
ecchymosis — Ch. 20, p. 569
echocardiography — Ch. 16, p. 439
edema — Ch. 3, p. 67
Edmonton Obesity Staging System — Ch. 24, p. 696
Edmonton Symptom Assessment System–revised (ESAS-r) — Ch. 9, p. 234
effluent — Ch. 27, p. 791
ejection fraction (EF) — Ch. 18, p. 504
elder abuse — Ch. 8, p. 206
electroencephalography (EEG) — Ch. 30, p. 883
elevation pallor — Ch. 19, p. 538
embolectomy — Ch. 15, p. 409
emergence delirium — Ch. 7, p. 179
emphysema — Ch. 14, p. 380

empyema — Ch. 13, p. 349
encephalitis — Ch. 30, p. 883
end-of-life care — Ch. 10, p. 264
end-tidal carbon dioxide — Ch. 15, p. 409
Endocrine Feedback and Testing — s. 23.1, p. 665
endocrine therapy — Ch. 29, p. 852
endogenous opioids — Ch. 5, p. 125
endometriosis — Ch. 29, p. 852
endophthalmitis — Ch. 36, p. 1075
endoscopic retrograde cholangiopancreatography (ERCP) — Ch. 26, p. 759
endotracheal tube — Ch. 12, p. 318
endovascular aneurysm repair (EVAR) — Ch. 19, p. 538
endovascular thrombectomy (EVT) — Ch. 31, p. 913
energy conservation — Ch. 34, p. 1008
ENFit — Ch. 24, p. 696
enhanced recovery after surgery (ERAS) — Ch. 7, p. 179
Enteral and Parenteral Nutrition — s. 24.2, p. 696
enteral nutrition — Ch. 24, p. 696
epidermis — Ch. 35, p. 1040
epidural analgesia — Ch. 5, p. 125
epidural anesthesia — Ch. 7, p. 179
epidural hematoma — Ch. 32, p. 943
epilepsy — Ch. 30, p. 883
epinephrine autoinjector — Ch. 6, p. 152
equality — Ch. 2, p. 35
equity — Ch. 2, p. 35
Equity in Everyday Medical-Surgical Practice — s. 2.6, p. 35
Equity, Cultural Safety and Indigenous Health in Adult Care — Ch. 2, p. 35
erectile dysfunction — Ch. 29, p. 852
Erectile Dysfunction and Gender-Affirming Care — s. 29.6, p. 852
erythema nodosum — Ch. 25, p. 727
erythrocyte sedimentation rate (ESR) — Ch. 34, p. 1008
erythropoiesis-stimulating agent — Ch. 27, p. 791
escalation — Ch. 6, p. 152
eschar — Ch. 35, p. 1040
escharotomy — Ch. 35, p. 1040
esophageal varices — Ch. 26, p. 759
essential care partner — Ch. 1, p. 2
estimated glomerular filtration rate (eGFR) — Ch. 27, p. 791
euglycemic diabetic ketoacidosis — Ch. 22, p. 635
evisceration — Ch. 7, p. 179
expressive aphasia — Ch. 31, p. 913
external beam radiation — Ch. 9, p. 234
external breast form — Ch. 29, p. 852
external catheter — Ch. 28, p. 822
external fixator — Ch. 33, p. 976
external ventricular drain — Ch. 30, p. 883
extracellular fluid (ECF) — Ch. 3, p. 67
extraintestinal manifestations — Ch. 25, p. 727
extravasation — Ch. 3, p. 67
exudate — Ch. 4, p. 97
Eye and Ear Disorders — Ch. 36, p. 1075
Eye Emergencies, Trauma and Eye Surgery — s. 36.3, p. 1075
Faces Pain Scale–Revised (FPS-R) — Ch. 5, p. 125
failure to capture — Ch. 16, p. 439
failure to rescue — Ch. 6, p. 152
fall — Ch. 8, p. 206
Falls and Functional Decline — s. 8.4, p. 206
fasciotomy — Ch. 33, p. 976
FAST — Ch. 31, p. 913
fat embolism syndrome (FES) — Ch. 33, p. 976
fear of recurrence — Ch. 9, p. 234
febrile neutropenia — Ch. 9, p. 234
febrile non-hemolytic transfusion reaction — Ch. 20, p. 569
fecal calprotectin — Ch. 25, p. 727
fecal immunochemical test (FIT) — Ch. 25, p. 727
fecal impaction — Ch. 25, p. 727
fecal incontinence — Ch. 25, p. 727
femoral access — Ch. 17, p. 476
femoral neck fracture — Ch. 33, p. 976
ferritin — Ch. 20, p. 569
fertility preservation — Ch. 9, p. 234
FEV1/FVC ratio — Ch. 14, p. 380
fever — Ch. 4, p. 97
fibrinolysis — Ch. 17, p. 476
fine-needle aspiration (FNA) — Ch. 23, p. 665
finger thoracostomy — Ch. 15, p. 409
First Nations — Ch. 2, p. 35
First Nations, Inuit and Métis Health — s. 2.3, p. 35
first-degree AV block — Ch. 16, p. 439
fistula — Ch. 25, p. 727
flail chest — Ch. 15, p. 409
flare — Ch. 34, p. 1008
fluid resuscitation — Ch. 35, p. 1040
fluid volume deficit — Ch. 3, p. 67
Fluid Volume Deficit and Excess — s. 3.2, p. 67
fluid volume excess — Ch. 3, p. 67
Fluids, Electrolytes and Acid–Base Balance — Ch. 3, p. 67
flutter valve — Ch. 15, p. 409
focal seizure — Ch. 30, p. 883
Focused Cardiovascular Assessment — s. 16.2, p. 439
Focused Neurologic Assessment — s. 30.2, p. 883
Focused Respiratory Assessment — s. 12.2, p. 318
food insecurity — Ch. 2, p. 35
forced expiratory volume in 1 second (FEV1) — Ch. 14, p. 380
forced vital capacity (FVC) — Ch. 14, p. 380
fracture — Ch. 33, p. 976
fracture liaison service — Ch. 33, p. 976
Fractures and Their Care — s. 33.1, p. 976
fragility fracture — Ch. 33, p. 976
frailty — Ch. 7, p. 179
free T4 — Ch. 23, p. 665
frozen plasma — Ch. 20, p. 569
full agonist — Ch. 5, p. 125
full-thickness burn — Ch. 35, p. 1040
functional asplenia — Ch. 20, p. 569
functional decline — Ch. 8, p. 206
functional incontinence — Ch. 28, p. 822
gabapentinoid — Ch. 5, p. 125
Gallbladder and Biliary Disease — s. 26.5, p. 759
gastric residual volume (GRV) — Ch. 24, p. 696
gastritis — Ch. 24, p. 696
gastroesophageal reflux disease (GERD) — Ch. 24, p. 696
gastrostomy tube — Ch. 24, p. 696
gender identity — Ch. 2, p. 35
gender-affirming care — Ch. 29, p. 852
general anesthesia — Ch. 7, p. 179
generalized seizure — Ch. 30, p. 883
genital herpes — Ch. 29, p. 852
genitourinary syndrome of menopause — Ch. 29, p. 852
GERD, Gastritis and Peptic Ulcer Disease — s. 24.4, p. 696
giant cell arteritis — Ch. 34, p. 1008
Glasgow Coma Scale (GCS) — Ch. 30, p. 883
Glasgow-Blatchford score — Ch. 24, p. 696
glaucoma — Ch. 36, p. 1075
Global Leadership Initiative on Malnutrition (GLIM) criteria — Ch. 24, p. 696
glomerular filtration rate (GFR) — Ch. 27, p. 791
GLP-1 receptor agonist — Ch. 22, p. 635
glucagon — Ch. 22, p. 635
glucocorticoid-induced adrenal insufficiency — Ch. 23, p. 665
glucose management indicator (GMI) — Ch. 22, p. 635
Glucose Regulation and Types of Diabetes — s. 22.1, p. 635
goals of care — Ch. 10, p. 264
goitre — Ch. 23, p. 665
gonorrhea — Ch. 29, p. 852
Good Samaritan Drug Overdose Act — Ch. 11, p. 290
Gout — s. 34.4, p. 1008
gout — Ch. 34, p. 1008
gout flare — Ch. 34, p. 1008
grade — Ch. 9, p. 234
graft-versus-host disease — Ch. 20, p. 569
granulation tissue — Ch. 35, p. 1040
Graves disease — Ch. 23, p. 665
Grey Turner sign — Ch. 26, p. 759
grief — Ch. 10, p. 264
Grief and Caring for Ourselves — s. 10.6, p. 264
grievous and irremediable medical condition — Ch. 10, p. 264

group and screen — Ch. 20, p. 569
Guillain–Barré syndrome (GBS) — Ch. 32, p. 943
Gynecologic Conditions and Surgery — s. 29.3, p. 852
Hamilton Early Warning Score (HEWS) — Ch. 6, p. 152
hand hygiene — Ch. 4, p. 97
harm reduction — Ch. 5, p. 125
Harm Reduction and Transitions — s. 11.6, p. 290
harmful incident — Ch. 1, p. 2
Hashimoto thyroiditis — Ch. 23, p. 665
hazardous drug — Ch. 9, p. 234
Headache, Central Nervous System Infections and Brain Tumours — s. 30.6, p. 883
healing by primary intention — Ch. 4, p. 97
healing by secondary intention — Ch. 4, p. 97
healing by tertiary intention — Ch. 4, p. 97
healing ridge — Ch. 4, p. 97
health care-associated infection (HAI) — Ch. 4, p. 97
health equity — Ch. 2, p. 35
Health Equity and the Determinants of Health — s. 2.1, p. 35
health inequality — Ch. 2, p. 35
health inequity — Ch. 2, p. 35
health information custodian — Ch. 1, p. 2
health literacy — Ch. 1, p. 2
hearing aid — Ch. 36, p. 1075
Hearing and Ear Assessment — s. 36.4, p. 1075
Heart Blocks, Pacemakers and Implantable Devices — s. 16.7, p. 439
heart failure (HF) — Ch. 18, p. 504
heart failure with improved ejection fraction (HFimpEF) — Ch. 18, p. 504
heart failure with mildly reduced ejection fraction (HFmrEF) — Ch. 18, p. 504
heart failure with nonreduced ejection fraction (HFnrEF) — Ch. 18, p. 504
heart failure with preserved ejection fraction (HFpEF) — Ch. 18, p. 504
heart failure with reduced ejection fraction (HFrEF) — Ch. 18, p. 504
Heart Failure, Valvular and Inflammatory Heart Disease — Ch. 18, p. 504
Heart Failure: How It Develops — s. 18.1, p. 504
Heart Team — Ch. 18, p. 504
Helicobacter pylori (H. pylori) — Ch. 24, p. 696
hematemesis — Ch. 24, p. 696
hematochezia — Ch. 24, p. 696
hematocrit — Ch. 20, p. 569
Hematologic Disorders and Transfusion — Ch. 20, p. 569
hematoma — Ch. 7, p. 179
hematopoiesis — Ch. 20, p. 569
hematuria — Ch. 28, p. 822
hemiarthroplasty — Ch. 33, p. 976
hemiparesis — Ch. 31, p. 913
hemiplegic shoulder — Ch. 31, p. 913
hemodialysis — Ch. 27, p. 791
hemoglobin — Ch. 20, p. 569
hemolysis — Ch. 20, p. 569
hemophilia — Ch. 20, p. 569
hemoptysis — Ch. 12, p. 318
hemorrhagic shock — Ch. 6, p. 152
Hemorrhagic Stroke — s. 31.4, p. 913
hemorrhagic stroke — Ch. 31, p. 913
hemosiderin staining — Ch. 19, p. 538
hemothorax — Ch. 15, p. 409
hemovigilance — Ch. 20, p. 569
heparin-induced thrombocytopenia (HIT) — Ch. 19, p. 538
hepatic encephalopathy (HE) — Ch. 26, p. 759
hepatitis — Ch. 26, p. 759
hepatitis A — Ch. 26, p. 759
hepatitis B — Ch. 26, p. 759
hepatitis C — Ch. 26, p. 759
hepatocellular carcinoma — Ch. 26, p. 759
hepatorenal syndrome — Ch. 26, p. 759
HER2 — Ch. 29, p. 852
herniation — Ch. 30, p. 883
herpes zoster — Ch. 35, p. 1040
high-alert medication — Ch. 1, p. 2
high-flow device — Ch. 12, p. 318
high-flow nasal cannula (HFNC) — Ch. 12, p. 318
high-output ileostomy — Ch. 25, p. 727
high-sensitivity troponin — Ch. 16, p. 439
hip dislocation — Ch. 33, p. 976
hip fracture — Ch. 33, p. 976
Hip Fracture in Older Adults — s. 33.4, p. 976
HIV non-disclosure — Ch. 21, p. 601
HIV: Infection, Testing and Prevention — s. 21.4, p. 601
home blood pressure monitoring (HBPM) — Ch. 19, p. 538
homelessness — Ch. 2, p. 35
hormone — Ch. 23, p. 665
hormone receptor status — Ch. 29, p. 852
hormone therapy — Ch. 9, p. 234
hospice — Ch. 10, p. 264
Hospital-Acquired and Aspiration Pneumonia — s. 13.2, p. 349
hospital-acquired pneumonia (HAP) — Ch. 13, p. 349
hospital-associated disability — Ch. 8, p. 206
huff cough — Ch. 12, p. 318
human immunodeficiency virus (HIV) — Ch. 21, p. 601
human papillomavirus — Ch. 29, p. 852
humidification — Ch. 12, p. 318
hydrocephalus — Ch. 30, p. 883
hydroxyurea — Ch. 20, p. 569
hyperactive delirium — Ch. 8, p. 206
Hyperacute Treatment — s. 31.3, p. 913
hyperalgesia — Ch. 5, p. 125
hypercalcemia — Ch. 3, p. 67
hypercalcemia of malignancy — Ch. 9, p. 234
hypercapnia — Ch. 12, p. 318
hypercapnic respiratory failure — Ch. 15, p. 409
Hyperglycemic Emergencies: DKA and HHS — s. 22.5, p. 635
hyperglycemic hyperosmolar state (HHS) — Ch. 22, p. 635
hyperinflation — Ch. 14, p. 380
hyperkalemia — Ch. 3, p. 67
hypernatremia — Ch. 3, p. 67
hyperoxia — Ch. 12, p. 318
hyperpigmentation — Ch. 23, p. 665
hypersensitivity — Ch. 21, p. 601
Hypersensitivity and Allergy — s. 21.2, p. 601
hypertension — Ch. 19, p. 538
Hypertension and Vascular Disorders — Ch. 19, p. 538
Hypertension: Measurement and Risk — s. 19.1, p. 538
Hypertensive Emergencies and Acute Aortic Syndromes — s. 19.3, p. 538
hypertensive emergency — Ch. 19, p. 538
hypertensive urgency — Ch. 19, p. 538
hyperthyroidism — Ch. 23, p. 665
hypertonic — Ch. 3, p. 67
hypertrophic cardiomyopathy — Ch. 18, p. 504
hyphema — Ch. 36, p. 1075
hypoactive delirium — Ch. 8, p. 206
hypocalcemia — Ch. 3, p. 67
hypodermis — Ch. 35, p. 1040
Hypoglycemia — s. 22.4, p. 635
hypoglycemia — Ch. 22, p. 635
hypokalemia — Ch. 3, p. 67
hypomagnesemia — Ch. 3, p. 67
hyponatremia — Ch. 3, p. 67
hypoparathyroidism — Ch. 23, p. 665
hypothesis — Ch. 1, p. 2
hypothyroidism — Ch. 23, p. 665
hypotonic — Ch. 3, p. 67
Hypovolemic and Cardiogenic Shock — s. 6.4, p. 152
hypovolemic shock — Ch. 6, p. 152
hypoxemia — Ch. 12, p. 318
hypoxemic respiratory failure — Ch. 15, p. 409
hypoxia — Ch. 12, p. 318
hypoxic pulmonary vasoconstriction — Ch. 12, p. 318
hysterectomy — Ch. 29, p. 852
ICS–formoterol reliever — Ch. 14, p. 380
idiopathic pulmonary fibrosis (IPF) — Ch. 14, p. 380
IgE — Ch. 21, p. 601
ileal conduit — Ch. 28, p. 822
ileostomy — Ch. 25, p. 727
illness trajectory — Ch. 1, p. 2
immune checkpoint inhibitor — Ch. 9, p. 234
immune reconstitution inflammatory syndrome (IRIS) — Ch. 21, p. 601
immune thrombocytopenia (ITP) — Ch. 20, p. 569
immune-related adverse event — Ch. 9, p. 234
Immunity, Allergy and HIV — Ch. 21, p. 601
immunocompromised — Ch. 21, p. 601
immunodeficiency — Ch. 21, p. 601

Immunodeficiency and the Immunocompromised Patient — s. 21.3, p. 601
immunosenescence — Ch. 21, p. 601
immunotherapy — Ch. 13, p. 349
impaired awareness of hypoglycemia — Ch. 22, p. 635
implantable cardioverter-defibrillator (ICD) — Ch. 16, p. 439
implicit bias — Ch. 2, p. 35
inactivated vaccine — Ch. 21, p. 601
inadvertent perioperative hypothermia — Ch. 7, p. 179
incentive spirometer — Ch. 7, p. 179
incomplete injury — Ch. 32, p. 943
incontinence-associated dermatitis (IAD) — Ch. 35, p. 1040
Increased Intracranial Pressure — s. 30.4, p. 883
incretins — Ch. 22, p. 635
independent double check — Ch. 1, p. 2
Indian Act — Ch. 2, p. 35
Indian hospitals — Ch. 2, p. 35
Indian status — Ch. 2, p. 35
Indigenous patient navigator — Ch. 2, p. 35
Indigenous-specific racism — Ch. 2, p. 35
induration — Ch. 35, p. 1040
indwelling urinary catheter — Ch. 28, p. 822
infection — Ch. 4, p. 97
Infection Prevention and Control on the Unit — s. 4.3, p. 97
Infection: Recognition and Diagnostics — s. 4.2, p. 97
Infective Endocarditis — s. 18.6, p. 504
infective endocarditis (IE) — Ch. 18, p. 504
infiltration — Ch. 3, p. 67
inflammation — Ch. 4, p. 97
Inflammation and Healing — s. 4.1, p. 97
Inflammation, Infection and Sepsis — Ch. 4, p. 97
Inflammatory Bowel Disease — s. 25.2, p. 727
inflammatory bowel disease (IBD) — Ch. 25, p. 727
inflammatory myopericardial syndrome — Ch. 18, p. 504
influenza — Ch. 13, p. 349
Influenza, COVID-19 and RSV — s. 13.3, p. 349
informed consent — Ch. 1, p. 2
inhalation injury — Ch. 35, p. 1040
inhaled corticosteroid (ICS) — Ch. 14, p. 380
Inhaled Medications and Devices — s. 14.3, p. 380
initiation — Ch. 1, p. 2
innate immunity — Ch. 21, p. 601
inner cannula — Ch. 12, p. 318
inner ear — Ch. 36, p. 1075
inpatient surgery — Ch. 7, p. 179
insulin — Ch. 22, p. 635
Insulin and Non-Insulin Medications — s. 22.3, p. 635
insulin resistance — Ch. 22, p. 635
insulin secretagogue — Ch. 22, p. 635
insured health services — Ch. 1, p. 2
Integrated Nutrition Pathway for Acute Care (INPAC) — Ch. 24, p. 696
interdialytic weight gain — Ch. 27, p. 791
interferon-gamma release assay (IGRA) — Ch. 13, p. 349
intergenerational effects — Ch. 2, p. 35
Interim Federal Health Program (IFHP) — Ch. 2, p. 35
intermittent catheterization — Ch. 28, p. 822
intermittent claudication — Ch. 19, p. 538
intermittent pneumatic compression (IPC) — Ch. 7, p. 179
internal fixation — Ch. 33, p. 976
International Dysphagia Diet Standardisation Initiative (IDDSI) — Ch. 24, p. 696
international normalized ratio (INR) — Ch. 18, p. 504
International Prostate Symptom Score (IPSS) — Ch. 28, p. 822
intersectionality — Ch. 2, p. 35
interstitial fluid — Ch. 3, p. 67
interstitial lung disease (ILD) — Ch. 14, p. 380
intertrochanteric fracture — Ch. 33, p. 976
intolerance (drug) — Ch. 4, p. 97
intracellular fluid (ICF) — Ch. 3, p. 67
intracerebral hemorrhage (ICH) — Ch. 31, p. 913
intracranial pressure — Ch. 30, p. 883
intradialytic hypotension — Ch. 27, p. 791
intraocular pressure (IOP) — Ch. 36, p. 1075
intraoperative — Ch. 7, p. 179
intraoperative floppy iris syndrome — Ch. 28, p. 822
intravascular fluid — Ch. 3, p. 67
intravesical BCG — Ch. 28, p. 822
Introduction — s. Introduction, p. 2
Introduction — s. Introduction, p. 35
Introduction — s. Introduction, p. 67
Introduction — s. Introduction, p. 97
Introduction — s. Introduction, p. 125
Introduction — s. Introduction, p. 152
Introduction — s. Introduction, p. 179
Introduction — s. Introduction, p. 206
Introduction — s. Introduction, p. 234
Introduction — s. Introduction, p. 264
Introduction — s. Introduction, p. 290
Introduction — s. Introduction, p. 318
Introduction — s. Introduction, p. 349
Introduction — s. Introduction, p. 380
Introduction — s. Introduction, p. 409
Introduction — s. Introduction, p. 439
Introduction — s. Introduction, p. 476
Introduction — s. Introduction, p. 504
Introduction — s. Introduction, p. 538
Introduction — s. Introduction, p. 569
Introduction — s. Introduction, p. 601
Introduction — s. Introduction, p. 635
Introduction — s. Introduction, p. 665
Introduction — s. Introduction, p. 696
Introduction — s. Introduction, p. 727
Introduction — s. Introduction, p. 759
Introduction — s. Introduction, p. 791
Introduction — s. Introduction, p. 822
Introduction — s. Introduction, p. 852
Introduction — s. Introduction, p. 883
Introduction — s. Introduction, p. 913
Introduction — s. Introduction, p. 943
Introduction — s. Introduction, p. 976
Introduction — s. Introduction, p. 1008
Introduction — s. Introduction, p. 1040
Introduction — s. Introduction, p. 1075
intubation — Ch. 15, p. 409
Inuit — Ch. 2, p. 35
Inuit Child First Initiative — Ch. 2, p. 35
Inuit Nunangat — Ch. 2, p. 35
ionized calcium — Ch. 3, p. 67
iron chelation — Ch. 20, p. 569
iron deficiency anemia — Ch. 20, p. 569
iron overload — Ch. 20, p. 569
irritant — Ch. 9, p. 234
ischemic core — Ch. 31, p. 913
ischemic stroke — Ch. 31, p. 913
isotonic — Ch. 3, p. 67
IV Fluids and Fluid Management — s. 3.3, p. 67
JAK inhibitor — Ch. 34, p. 1008
jaundice — Ch. 20, p. 569
jejunostomy tube — Ch. 24, p. 696
joint protection — Ch. 34, p. 1008
Joint Replacement and Spine Surgery — s. 33.5, p. 976
Joints, Inflammation and Arthritis in Canada — s. 34.1, p. 1008
Jordan's Principle — Ch. 2, p. 35
Joyce's Principle — Ch. 2, p. 35
jugular venous distension — Ch. 3, p. 67
jugular venous pressure (JVP) — Ch. 16, p. 439
Jurisprudence Examination — Ch. 1, p. 2
just culture — Ch. 1, p. 2
Kaposi sarcoma — Ch. 21, p. 601
ketones — Ch. 22, p. 635
Kidney Function and Kidney Tests — s. 27.1, p. 791
Kidney Health in Canada and Living Well With CKD — s. 27.6, p. 791
kidney replacement therapy (KRT) — Ch. 27, p. 791
Kidney Stones — s. 28.4, p. 822
Kidney Transplant — s. 27.5, p. 791
kidney transplant — Ch. 27, p. 791
kindling — Ch. 11, p. 290
Korsakoff syndrome — Ch. 11, p. 290
Kussmaul breathing — Ch. 12, p. 318
Kussmaul respirations — Ch. 22, p. 635
lactate — Ch. 4, p. 97
laminectomy — Ch. 33, p. 976
langue des signes québécoise (LSQ) — Ch. 36, p. 1075
laparoscopic cholecystectomy — Ch. 26, p. 759

large vessel occlusion (LVO) — Ch. 31, p. 913
laryngectomy — Ch. 12, p. 318
last known well (LKW) — Ch. 31, p. 913
latex allergy — Ch. 21, p. 601
LDL cholesterol (LDL-C) — Ch. 17, p. 476
least restraint — Ch. 8, p. 206
left ventricular assist device (LVAD) — Ch. 18, p. 504
left-sided heart failure — Ch. 18, p. 504
lens — Ch. 36, p. 1075
leukemia — Ch. 20, p. 569
Leukemia, Lymphoma and Myeloma — s. 20.5, p. 569
leukocyte esterase — Ch. 28, p. 822
level of consciousness — Ch. 30, p. 883
levodopa — Ch. 32, p. 943
licensed practical nurse (LPN) — Ch. 1, p. 2
lipase — Ch. 26, p. 759
lipohypertrophy — Ch. 22, p. 635
lipoprotein(a) [Lp(a)] — Ch. 17, p. 476
live attenuated vaccine — Ch. 21, p. 601
live vaccine — Ch. 21, p. 601
liver transplant — Ch. 26, p. 759
Liver, Biliary and Pancreatic Disorders — Ch. 26, p. 759
Living Well With Chronic Arthritis — s. 34.7, p. 1008
Living With Cancer: Support and Survivorship — s. 9.6, p. 234
Living With HIV: Treatment and Nursing Care — s. 21.5, p. 601
lobectomy — Ch. 13, p. 349
local anesthetic systemic toxicity (LAST) — Ch. 7, p. 179
local infiltration — Ch. 7, p. 179
lockbox — Ch. 1, p. 2
log roll — Ch. 32, p. 943
long-acting beta2-agonist (LABA) — Ch. 14, p. 380
long-acting muscarinic antagonist (LAMA) — Ch. 14, p. 380
loop ostomy — Ch. 25, p. 727
low anterior resection — Ch. 25, p. 727
low vision — Ch. 36, p. 1075
low-dose buprenorphine initiation — Ch. 11, p. 290
low-flow device — Ch. 12, p. 318
low-molecular-weight heparin (LMWH) — Ch. 19, p. 538
Lower Gastrointestinal Disorders — Ch. 25, p. 727
lower limit of normal (LLN) — Ch. 14, p. 380
Lower Respiratory Infections and Lung Cancer — Ch. 13, p. 349
lower urinary tract symptoms (LUTS) — Ch. 28, p. 822
lucid interval — Ch. 32, p. 943
lumbar puncture (LP) — Ch. 30, p. 883
Lund and Browder chart — Ch. 35, p. 1040
Lung Cancer — s. 13.5, p. 349
lung-protective ventilation — Ch. 15, p. 409
Lupus and Other Connective Tissue Disorders — s. 34.5, p. 1008
lupus nephritis — Ch. 34, p. 1008
lymphedema — Ch. 29, p. 852
lymphoma — Ch. 20, p. 569
macrocytic anemia — Ch. 20, p. 569
macula — Ch. 36, p. 1075
magnetic resonance imaging (MRI) — Ch. 30, p. 883
maintenance and reliever therapy (MART) — Ch. 14, p. 380
malignant hyperthermia (MH) — Ch. 7, p. 179
malignant spinal cord compression — Ch. 9, p. 234
malnutrition — Ch. 24, p. 696
Managing Symptoms — s. 10.3, p. 264
masked hypertension — Ch. 19, p. 538
massive hemorrhage protocol — Ch. 6, p. 152
massive pulmonary embolism — Ch. 15, p. 409
mastectomy — Ch. 29, p. 852
mean arterial pressure (MAP) — Ch. 6, p. 152
mean corpuscular volume (MCV) — Ch. 20, p. 569
mechanical complications of MI — Ch. 17, p. 476
mechanical lift — Ch. 33, p. 976
mechanical obstruction — Ch. 25, p. 727
mechanical valve — Ch. 18, p. 504
mechanical ventilation — Ch. 15, p. 409
Medical Assistance in Dying — s. 10.4, p. 264
medical assistance in dying (MAID) — Ch. 10, p. 264
medical directive — Ch. 12, p. 318
medical expulsive therapy (MET) — Ch. 28, p. 822
medical-surgical nursing — Ch. 1, p. 2
Medical-Surgical Nursing in Canada — Ch. 1, p. 2
medication reconciliation — Ch. 1, p. 2
Medications and Devices — s. 18.3, p. 504
Medications in Older Adults — s. 8.5, p. 206
Medicines for Inflammatory Arthritis — s. 34.6, p. 1008
melanoma — Ch. 35, p. 1040
melena — Ch. 24, p. 696
menopausal hormone therapy — Ch. 29, p. 852
menopause — Ch. 29, p. 852
Menopause and Midlife Health — s. 29.4, p. 852
metabolic acidosis — Ch. 3, p. 67
metabolic alkalosis — Ch. 3, p. 67
metabolic dysfunction-associated steatohepatitis (MASH) — Ch. 26, p. 759
metabolic dysfunction-associated steatotic liver disease (MASLD) — Ch. 26, p. 759
metastasis — Ch. 9, p. 234
methadone — Ch. 5, p. 125
methicillin-resistant Staphylococcus aureus (MRSA) — Ch. 4, p. 97
methotrexate — Ch. 34, p. 1008
microclimate — Ch. 35, p. 1040
middle ear — Ch. 36, p. 1075
midstream clean-catch specimen — Ch. 28, p. 822
mineralocorticoid receptor antagonist (MRA) — Ch. 18, p. 504
mitral regurgitation — Ch. 18, p. 504
mitral stenosis — Ch. 18, p. 504
mixed delirium — Ch. 8, p. 206
mixed hearing loss — Ch. 36, p. 1075
Mobility and Safe Patient Handling — s. 33.7, p. 976
Mobitz I — Ch. 16, p. 439
Mobitz II — Ch. 16, p. 439
modulation — Ch. 5, p. 125
moisture balance — Ch. 35, p. 1040
moisture-associated skin damage (MASD) — Ch. 35, p. 1040
Monitoring Glucose — s. 22.2, p. 635
monofilament testing — Ch. 22, p. 635
moral distress — Ch. 10, p. 264
morning stiffness — Ch. 34, p. 1008
morphine milligram equivalent (MME) — Ch. 5, p. 125
mottling — Ch. 4, p. 97
mu-opioid receptor — Ch. 5, p. 125
mucosal membrane pressure injury — Ch. 35, p. 1040
mucositis — Ch. 9, p. 234
multicomponent prevention — Ch. 8, p. 206
multimodal analgesia — Ch. 5, p. 125
Multimodal and Non-Opioid Analgesia — s. 5.3, p. 125
multimorbidity — Ch. 1, p. 2
Multinational Association for Supportive Care in Cancer (MASCC) risk index — Ch. 9, p. 234
multiple myeloma — Ch. 20, p. 569
Multiple Sclerosis — s. 32.3, p. 943
multiple sclerosis (MS) — Ch. 32, p. 943
murmur — Ch. 16, p. 439
Murphy sign — Ch. 26, p. 759
Musculoskeletal Trauma and Orthopedic Surgery — Ch. 33, p. 976
myasthenia gravis (MG) — Ch. 32, p. 943
Myasthenia Gravis and Guillain–Barré Syndrome — s. 32.5, p. 943
myasthenic crisis — Ch. 32, p. 943
myelin — Ch. 32, p. 943
myelosuppression — Ch. 9, p. 234
myocardial infarction (MI) — Ch. 17, p. 476
myocarditis — Ch. 18, p. 504
myxedema coma — Ch. 23, p. 665
Ménière disease — Ch. 36, p. 1075
Métis — Ch. 2, p. 35
N-acetylcysteine (NAC) — Ch. 26, p. 759
N95 respirator — Ch. 4, p. 97
nadir — Ch. 9, p. 234
naloxone — Ch. 5, p. 125
nasal cannula — Ch. 12, p. 318
nasogastric (NG) tube — Ch. 24, p. 696
nasogastric decompression — Ch. 25, p. 727
nasopharyngeal airway — Ch. 12, p. 318

National Overdose Response Service (NORS) — Ch. 11, p. 290
natriuretic peptide — Ch. 16, p. 439
natriuretic peptides — Ch. 3, p. 67
near miss — Ch. 1, p. 2
nebulizer — Ch. 14, p. 380
neck breather — Ch. 12, p. 318
neck hematoma — Ch. 23, p. 665
necrotizing soft tissue infection — Ch. 35, p. 1040
negative feedback — Ch. 23, p. 665
negative pressure wound therapy — Ch. 35, p. 1040
neglect — Ch. 31, p. 913
neoadjuvant therapy — Ch. 9, p. 234
nephron — Ch. 27, p. 791
nephrostomy tube — Ch. 28, p. 822
nephrotoxic — Ch. 27, p. 791
neuraxial anesthesia — Ch. 7, p. 179
neurogenic shock — Ch. 6, p. 152
Neurologic Assessment and Increased Intracranial Pressure — Ch. 30, p. 883
Neurologic Diagnostics — s. 30.3, p. 883
neuromuscular junction — Ch. 32, p. 943
neuron — Ch. 30, p. 883
neuropathic pain — Ch. 5, p. 125
neurovascular assessment — Ch. 33, p. 976
NEWS2 — Ch. 6, p. 152
Next Generation NCLEX (NGN) — Ch. 1, p. 2
nicotine replacement therapy (NRT) — Ch. 14, p. 380
nimodipine — Ch. 31, p. 913
nitrites — Ch. 28, p. 822
no-harm incident — Ch. 1, p. 2
nociception — Ch. 5, p. 125
nociceptive pain — Ch. 5, p. 125
nociceptor — Ch. 5, p. 125
nociplastic pain — Ch. 5, p. 125
nocturia — Ch. 28, p. 822
non-HDL cholesterol (non-HDL-C) — Ch. 17, p. 476
Non-Insured Health Benefits (NIHB) — Ch. 1, p. 2
Non-invasive and Mechanical Ventilation — s. 15.3, p. 409
non-invasive ventilation — Ch. 15, p. 409
non-rebreather mask — Ch. 12, p. 318
non-small cell lung cancer (NSCLC) — Ch. 13, p. 349
noncardiogenic pulmonary edema — Ch. 15, p. 409
noninvasive ventilation (NIV) — Ch. 32, p. 943
nonsteroidal anti-inflammatory drug (NSAID) — Ch. 5, p. 125
nonunion — Ch. 33, p. 976
normal sinus rhythm — Ch. 16, p. 439
NSTEMI (non-ST-elevation myocardial infarction) — Ch. 17, p. 476
nucleic acid amplification test — Ch. 29, p. 852
nucleic acid amplification test (NAAT) — Ch. 13, p. 349
numeric rating scale (NRS) — Ch. 5, p. 125
Nurse Specialized in Wound, Ostomy and Continence (NSWOC) — Ch. 25, p. 727
nurse-driven catheter removal protocol — Ch. 28, p. 822
Nursing Care of the Patient in Shock — s. 6.6, p. 152
NYHA functional class — Ch. 18, p. 504
obesity — Ch. 24, p. 696
Obesity and Bariatric Surgery — s. 24.6, p. 696
Obstructive and Restrictive Lung Disease — Ch. 14, p. 380
Obstructive and Restrictive Patterns — s. 14.1, p. 380
obstructive lung disease — Ch. 14, p. 380
obstructive shock — Ch. 6, p. 152
obstructive sleep apnea (OSA) — Ch. 7, p. 179
obturator — Ch. 12, p. 318
OCAP® — Ch. 2, p. 35
occult hypoxemia — Ch. 2, p. 35
offloading — Ch. 35, p. 1040
Older Adults in Acute Care — Ch. 8, p. 206
oliguria — Ch. 27, p. 791
Oncologic Emergencies — s. 9.4, p. 234
oncologic emergency — Ch. 9, p. 234
Ontario Health Team — Ch. 1, p. 2
open fracture — Ch. 33, p. 976
open-angle glaucoma — Ch. 36, p. 1075
opioid — Ch. 5, p. 125
opioid agonist treatment (OAT) — Ch. 5, p. 125
opioid toxicity — Ch. 11, p. 290
Opioid Toxicity and Withdrawal — s. 11.4, p. 290
opioid use disorder (OUD) — Ch. 5, p. 125
opioid withdrawal — Ch. 11, p. 290
opioid-induced respiratory depression (OIRD) — Ch. 5, p. 125
opioid-naive — Ch. 5, p. 125
Opioids: Safe Use in Hospital — s. 5.4, p. 125
opportunistic infection — Ch. 21, p. 601
optic nerve — Ch. 36, p. 1075
organ inventory — Ch. 29, p. 852
orolingual angioedema — Ch. 31, p. 913
oropharyngeal airway — Ch. 12, p. 318
orthopnea — Ch. 18, p. 504
orthostatic hypotension — Ch. 3, p. 67
osmolality — Ch. 3, p. 67
osmolarity — Ch. 3, p. 67
osmosis — Ch. 3, p. 67
osmotherapy — Ch. 30, p. 883
osmotic demyelination syndrome (ODS) — Ch. 3, p. 67
Osteoarthritis — s. 34.2, p. 1008
osteoarthritis (OA) — Ch. 34, p. 1008
osteomyelitis — Ch. 33, p. 976
osteoporosis — Ch. 33, p. 976
Osteoporosis and Bone Health — s. 33.3, p. 976
ostomy — Ch. 25, p. 727
Ostomy Care and Teaching — s. 25.6, p. 727
otitis externa — Ch. 36, p. 1075
otitis media — Ch. 36, p. 1075
ototoxicity — Ch. 36, p. 1075
Ottawa Model for Smoking Cessation — Ch. 14, p. 380
outbreak — Ch. 4, p. 97
outer ear — Ch. 36, p. 1075
outpatient parenteral antibiotic therapy (OPAT) — Ch. 18, p. 504
overdiagnosis — Ch. 9, p. 234
overflow diarrhea — Ch. 25, p. 727
overflow incontinence — Ch. 28, p. 822
oxygen target range — Ch. 12, p. 318
Oxygen Therapy — s. 12.4, p. 318
oxygen–hemoglobin dissociation curve — Ch. 12, p. 318
P wave — Ch. 16, p. 439
P/F ratio — Ch. 15, p. 409
P2Y12 inhibitor — Ch. 17, p. 476
$PaCO_2$ — Ch. 3, p. 67
Pain — Ch. 5, p. 125
pain — Ch. 5, p. 125
Pain Assessment — s. 5.2, p. 125
Pain Assessment in Advanced Dementia (PAINAD) scale — Ch. 5, p. 125
pain sensitization — Ch. 34, p. 1008
Palliative and End-of-Life Care — Ch. 10, p. 264
palliative approach — Ch. 10, p. 264
palliative care — Ch. 10, p. 264
palliative sedation — Ch. 10, p. 264
palmar erythema — Ch. 26, p. 759
pancreatic enzyme replacement therapy (PERT) — Ch. 26, p. 759
papillary muscle rupture — Ch. 17, p. 476
paracentesis — Ch. 26, p. 759
paralytic ileus — Ch. 25, p. 727
paraneoplastic syndrome — Ch. 13, p. 349
paraplegia — Ch. 32, p. 943
parastomal hernia — Ch. 25, p. 727
parathyroid hormone (PTH) — Ch. 23, p. 665
parathyroid hormone–related peptide (PTHrP) — Ch. 9, p. 234
parathyroidectomy — Ch. 23, p. 665
parenteral nutrition — Ch. 24, p. 696
Parkinson Disease — s. 32.4, p. 943
Parkinson disease (PD) — Ch. 32, p. 943
paroxysmal nocturnal dyspnea (PND) — Ch. 18, p. 504
partial agonist — Ch. 5, p. 125
partial-thickness burn — Ch. 35, p. 1040
partner notification — Ch. 29, p. 852
Partnering with Patients Across Transitions — s. 1.7, p. 2
pathologic fracture — Ch. 33, p. 976
patient safety incident — Ch. 1, p. 2
patient- and family-centred care — Ch. 1, p. 2
patient-controlled analgesia (PCA) — Ch. 5, p. 125
Patients Living With Chronic Pain or Opioid Use Disorder — s. 5.5, p. 125
PAWSS — Ch. 11, p. 290

PCA by proxy — Ch. 5, p. 125
PDE5 inhibitor — Ch. 29, p. 852
PE response team (PERT) — Ch. 15, p. 409
peak expiratory flow (PEF) — Ch. 14, p. 380
pelvic floor muscle training (PFMT) — Ch. 28, p. 822
pelvic inflammatory disease — Ch. 29, p. 852
pelvic organ prolapse — Ch. 29, p. 852
penumbra — Ch. 31, p. 913
peptic ulcer disease (PUD) — Ch. 24, p. 696
perception — Ch. 5, p. 125
percutaneous coronary intervention (PCI) — Ch. 17, p. 476
percutaneous endoscopic gastrostomy (PEG) — Ch. 24, p. 696
perforation — Ch. 24, p. 696
perfusion — Ch. 12, p. 318
pericardial effusion — Ch. 18, p. 504
pericardial friction rub — Ch. 18, p. 504
pericardiocentesis — Ch. 18, p. 504
pericarditis — Ch. 18, p. 504
Pericarditis, Myocarditis and Cardiomyopathies — s. 18.7, p. 504
perimenopause — Ch. 29, p. 852
Perioperative Nursing — Ch. 7, p. 179
perioperative nursing — Ch. 7, p. 179
Peripheral Arterial Disease — s. 19.4, p. 538
peripheral arterial disease (PAD) — Ch. 19, p. 538
peripheral cyanosis — Ch. 12, p. 318
peripheral nerve block — Ch. 7, p. 179
peripheral neuropathy — Ch. 22, p. 635
peripheral sensitization — Ch. 5, p. 125
periprosthetic joint infection — Ch. 33, p. 976
peristalsis — Ch. 24, p. 696
peristomal skin — Ch. 25, p. 727
peritoneal dialysis (PD) — Ch. 27, p. 791
peritonitis — Ch. 24, p. 696
peritonitis (PD-related) — Ch. 27, p. 791
permanent pacemaker — Ch. 16, p. 439
pernicious anemia — Ch. 20, p. 569
person-centred care — Ch. 8, p. 206
person-first language — Ch. 11, p. 290
personal amplifier — Ch. 36, p. 1075
personal directive — Ch. 10, p. 264
personal protective equipment (PPE) — Ch. 4, p. 97
personal support worker (PSW) — Ch. 1, p. 2
pessary — Ch. 29, p. 852
petechiae — Ch. 20, p. 569
phantom limb pain — Ch. 33, p. 976
pheochromocytoma — Ch. 23, p. 665
phlebitis — Ch. 3, p. 67
photosensitivity — Ch. 34, p. 1008
physical dependence — Ch. 5, p. 125
physiological reserve — Ch. 8, p. 206
pin-site care — Ch. 33, p. 976
pituitary adenoma — Ch. 23, p. 665
Pituitary Disorders and Water Balance — s. 23.5, p. 665
plaque rupture — Ch. 17, p. 476
plasma protein product — Ch. 20, p. 569
plateau pressure — Ch. 15, p. 409
pleural effusion — Ch. 13, p. 349
Pleural Effusion and Empyema — s. 13.6, p. 349
pleural friction rub — Ch. 12, p. 318
pleuritic chest pain — Ch. 13, p. 349
pleuritic pain — Ch. 15, p. 409
Pneumocystis pneumonia (PJP) — Ch. 21, p. 601
pneumonia — Ch. 13, p. 349
Pneumonia Severity Index (PSI) — Ch. 13, p. 349
pneumothorax — Ch. 15, p. 409
Pneumothorax and Chest Injury — s. 15.4, p. 409
point-of-care glucose testing — Ch. 22, p. 635
point-of-care risk assessment (PCRA) — Ch. 4, p. 97
polymyalgia rheumatica — Ch. 34, p. 1008
polypharmacy — Ch. 8, p. 206
portal hypertension — Ch. 26, p. 759
portal vein — Ch. 26, p. 759
positive end-expiratory pressure — Ch. 15, p. 409
positive expiratory pressure (PEP) device — Ch. 12, p. 318
post-COVID-19 condition — Ch. 13, p. 349
post-exposure prophylaxis (PEP) — Ch. 21, p. 601
post-fall assessment — Ch. 8, p. 206
post-fall huddle — Ch. 8, p. 206
post-ictal state — Ch. 30, p. 883
post-intensive care syndrome — Ch. 15, p. 409
post-intensive care syndrome–family — Ch. 15, p. 409
post-mastectomy pain syndrome — Ch. 29, p. 852
post-sepsis syndrome — Ch. 4, p. 97
post-stroke depression — Ch. 31, p. 913
post-thrombotic syndrome (PTS) — Ch. 19, p. 538
post-traumatic amnesia — Ch. 32, p. 943
post-void residual (PVR) — Ch. 28, p. 822
postanesthesia care unit (PACU) — Ch. 7, p. 179
postherpetic neuralgia — Ch. 35, p. 1040
postoperative — Ch. 7, p. 179
Postoperative Care and Complications — s. 7.6, p. 179
postoperative ileus — Ch. 7, p. 179
postoperative nausea and vomiting (PONV) — Ch. 7, p. 179
postoperative urinary retention — Ch. 7, p. 179
postrenal acute kidney injury — Ch. 27, p. 791
post–dural puncture headache — Ch. 30, p. 883
Potassium Imbalances — s. 3.5, p. 67
potentially inappropriate medication (PIM) — Ch. 8, p. 206
pouching system — Ch. 25, p. 727
power of attorney for personal care — Ch. 10, p. 264
PR interval — Ch. 16, p. 439
pre-emptive transplant — Ch. 27, p. 791
pre-exposure prophylaxis (PrEP) — Ch. 21, p. 601
precipitated withdrawal — Ch. 11, p. 290
prediabetes — Ch. 22, p. 635
predicted body weight — Ch. 15, p. 409
prehabilitation — Ch. 7, p. 179
preload — Ch. 6, p. 152
premature ventricular contraction (PVC) — Ch. 16, p. 439
preoperative — Ch. 7, p. 179
Preoperative Assessment and Preparation — s. 7.2, p. 179
prerenal acute kidney injury — Ch. 27, p. 791
presbycusis — Ch. 36, p. 1075
prescribing cascade — Ch. 8, p. 206
Pressure Injuries — s. 35.2, p. 1040
pressure injury — Ch. 35, p. 1040
pressurized metered-dose inhaler (pMDI) — Ch. 14, p. 380
pretest probability — Ch. 19, p. 538
priapism — Ch. 29, p. 852
primary aldosteronism — Ch. 19, p. 538
primary brain injury — Ch. 32, p. 943
primary brain tumour — Ch. 30, p. 883
primary hyperparathyroidism — Ch. 23, p. 665
primary hypertension — Ch. 19, p. 538
primary intention — Ch. 35, p. 1040
primary PCI — Ch. 17, p. 476
primary spontaneous pneumothorax — Ch. 15, p. 409
principle of double effect — Ch. 10, p. 264
procalcitonin — Ch. 4, p. 97
procedural sedation — Ch. 7, p. 179
professional boundaries — Ch. 1, p. 2
professional interpreter — Ch. 1, p. 2
Professional, Legal and Ethical Foundations — s. 1.5, p. 2
progressive (decompensated) shock — Ch. 6, p. 152
progressive multifocal leukoencephalopathy (PML) — Ch. 32, p. 943
prolactinoma — Ch. 23, p. 665
prolonged grief disorder — Ch. 10, p. 264
prompted voiding — Ch. 28, p. 822
pronator drift — Ch. 30, p. 883
prone positioning — Ch. 15, p. 409
pronouncement of death — Ch. 10, p. 264
Prostate and Bladder Cancer — s. 28.6, p. 822
prostate-specific antigen (PSA) — Ch. 28, p. 822
prosthesis — Ch. 33, p. 976
prothrombin complex concentrate (PCC) — Ch. 19, p. 538
proto-oncogene — Ch. 9, p. 234
proton pump inhibitor (PPI) — Ch. 24, p. 696
provoked seizure — Ch. 30, p. 883
pruritus — Ch. 26, p. 759

pseudo-relapse — Ch. 32, p. 943
pseudohyperkalemia — Ch. 3, p. 67
ptosis — Ch. 32, p. 943
Pulmonary Embolism — s. 15.6, p. 409
pulmonary embolism (PE) — Ch. 15, p. 409
pulmonary embolism rule-out criteria (PERC) — Ch. 15, p. 409
pulmonary rehabilitation — Ch. 14, p. 380
pulse deficit — Ch. 16, p. 439
pulse oximetry — Ch. 12, p. 318
Pulse Oximetry and Other Measures — s. 12.3, p. 318
pulse pressure — Ch. 6, p. 152
pulseless electrical activity (PEA) — Ch. 16, p. 439
pulsus paradoxus — Ch. 18, p. 504
punctal occlusion — Ch. 36, p. 1075
pupillary response — Ch. 30, p. 883
purpura — Ch. 20, p. 569
pyelonephritis — Ch. 28, p. 822
pyuria — Ch. 28, p. 822
QRS complex — Ch. 16, p. 439
QT interval — Ch. 16, p. 439
quick SOFA (qSOFA) — Ch. 4, p. 97
race — Ch. 2, p. 35
race-free equations — Ch. 2, p. 35
racialization — Ch. 2, p. 35
racialized — Ch. 2, p. 35
radial access — Ch. 17, p. 476
radial artery occlusion — Ch. 17, p. 476
radical prostatectomy — Ch. 28, p. 822
radioactive iodine therapy (RAI) — Ch. 23, p. 665
radon — Ch. 13, p. 349
rapid response team — Ch. 6, p. 152
rapid ventricular response (RVR) — Ch. 16, p. 439
rate control — Ch. 16, p. 439
Raynaud phenomenon — Ch. 34, p. 1008
re-expansion pulmonary edema — Ch. 13, p. 349
reasonably foreseeable natural death — Ch. 10, p. 264
receptive aphasia — Ch. 31, p. 913
reciprocal changes — Ch. 17, p. 476
Recognizing Acute Coronary Syndromes — s. 17.3, p. 476
Recognizing and Managing Worsening Heart Failure — s. 18.2, p. 504
Recognizing Clinical Deterioration — s. 6.1, p. 152
Recognizing Deterioration and Shock — Ch. 6, p. 152
Recognizing Stroke and Code Stroke — s. 31.2, p. 913
recurrent laryngeal nerve — Ch. 23, p. 665
recurrent toxicity — Ch. 11, p. 290
red blood cell concentrate — Ch. 20, p. 569
reduction — Ch. 33, p. 976
refeeding syndrome — Ch. 3, p. 67
referred pain — Ch. 5, p. 125
refractory (irreversible) shock — Ch. 6, p. 152
registered psychiatric nurse — Ch. 1, p. 2
regurgitation — Ch. 18, p. 504
rehabilitation — Ch. 31, p. 913
Rehabilitation, Transitions and Living After Stroke — s. 31.6, p. 913
rejection — Ch. 27, p. 791
relapse — Ch. 32, p. 943
reliever — Ch. 14, p. 380
remodelling — Ch. 18, p. 504
renal colic — Ch. 28, p. 822
renin–angiotensin–aldosterone system (RAAS) — Ch. 3, p. 67
reperfusion — Ch. 17, p. 476
repolarization — Ch. 16, p. 439
Reproductive and Breast Health in Adult Care — Ch. 29, p. 852
Required Organizational Practices (ROPs) — Ch. 1, p. 2
residential schools — Ch. 2, p. 35
residual limb — Ch. 33, p. 976
respiratory acidosis — Ch. 3, p. 67
respiratory alkalosis — Ch. 3, p. 67
Respiratory Assessment and Oxygen Therapy — Ch. 12, p. 318
respiratory fluoroquinolone — Ch. 13, p. 349
respiratory secretions — Ch. 10, p. 264
respiratory syncytial virus (RSV) — Ch. 13, p. 349
responsive behaviours — Ch. 8, p. 206
resting tremor — Ch. 32, p. 943
restraint — Ch. 8, p. 206
Restraints, Capacity and Transitions — s. 8.6, p. 206
restrictive lung disease — Ch. 14, p. 380
reticulocyte — Ch. 20, p. 569
retina — Ch. 36, p. 1075
retinal detachment — Ch. 36, p. 1075
retrograde ejaculation — Ch. 28, p. 822
retroperitoneal bleeding — Ch. 17, p. 476
reversibility — Ch. 14, p. 380
revised Atlanta classification — Ch. 26, p. 759
rheumatic heart disease — Ch. 18, p. 504
Rheumatoid Arthritis — s. 34.3, p. 1008
rheumatoid arthritis (RA) — Ch. 34, p. 1008
rheumatoid factor (RF) — Ch. 34, p. 1008
rhonchi — Ch. 12, p. 318
rhythm control — Ch. 16, p. 439
Richmond Agitation–Sedation Scale — Ch. 15, p. 409
right ventricular infarction — Ch. 17, p. 476
right-sided heart failure — Ch. 18, p. 504
Rights, Policy and Data — s. 2.4, p. 35
rigidity — Ch. 32, p. 943
routine practices — Ch. 1, p. 2
Roux-en-Y gastric bypass — Ch. 24, p. 696
rule of nines — Ch. 35, p. 1040
S3 — Ch. 16, p. 439
S4 — Ch. 16, p. 439
Safe Handling of Hazardous Drugs — s. 9.5, p. 234
safe patient handling — Ch. 33, p. 976
Safety and Quality in Medical-Surgical Care — s. 1.6, p. 2
same-day admission — Ch. 7, p. 179
SBAR — Ch. 6, p. 152
scope of practice — Ch. 1, p. 2
screening — Ch. 9, p. 234
Screening and Brief Intervention in Hospital — s. 11.2, p. 290
screening mammogram — Ch. 29, p. 852
secondary brain injury — Ch. 32, p. 943
secondary fracture prevention — Ch. 33, p. 976
secondary hypertension — Ch. 19, p. 538
secondary intention — Ch. 35, p. 1040
secondary prevention — Ch. 17, p. 476
secondary spontaneous pneumothorax — Ch. 15, p. 409
sedation scale — Ch. 5, p. 125
seizure — Ch. 30, p. 883
seizure precautions — Ch. 30, p. 883
Seizures and Status Epilepticus — s. 30.5, p. 883
self-administered MAID — Ch. 10, p. 264
self-care — Ch. 18, p. 504
self-management — Ch. 34, p. 1008
Self-Management and Transitions — s. 18.4, p. 504
self-regulated profession — Ch. 1, p. 2
sensorineural hearing loss — Ch. 36, p. 1075
sentinel lymph node biopsy — Ch. 29, p. 852
Sepsis — s. 4.6, p. 97
sepsis — Ch. 4, p. 97
septic arthritis — Ch. 34, p. 1008
septic shock — Ch. 4, p. 97
Sequential Organ Failure Assessment (SOFA) score — Ch. 4, p. 97
serious illness conversation — Ch. 10, p. 264
seroma — Ch. 29, p. 852
severe asthma — Ch. 14, p. 380
sexual health history — Ch. 29, p. 852
Sexual Health in Medical-Surgical Care — s. 29.1, p. 852
sexually transmitted and blood-borne infection — Ch. 29, p. 852
Sexually Transmitted and Blood-Borne Infections — s. 29.5, p. 852
SGLT2 inhibitor — Ch. 22, p. 635
shear — Ch. 35, p. 1040
shock — Ch. 6, p. 152
shock wave lithotripsy (SWL) — Ch. 28, p. 822
Shock: How It Develops — s. 6.3, p. 152
short-acting beta2-agonist (SABA) — Ch. 14, p. 380
short-acting muscarinic antagonist (SAMA) — Ch. 14, p. 380
shunt — Ch. 12, p. 318
sick-day medication guidance — Ch. 22, p. 635
sick-day rules — Ch. 23, p. 665
sickle cell disease — Ch. 20, p. 569

Sickle Cell Disease and Thalassemia — s. 20.3, p. 569
sickle cell trait — Ch. 20, p. 569
sighted guide — Ch. 36, p. 1075
silent aspiration — Ch. 24, p. 696
silent chest — Ch. 14, p. 380
single-pill combination — Ch. 19, p. 538
sinoatrial (SA) node — Ch. 16, p. 439
sinus bradycardia — Ch. 16, p. 439
sinus tachycardia — Ch. 16, p. 439
site marking — Ch. 7, p. 179
Sixties Scoop — Ch. 2, p. 35
Sjögren disease — Ch. 34, p. 1008
Skin Cancer and Other Common Skin Conditions — s. 35.6, p. 1040
skin graft — Ch. 35, p. 1040
Skin Structure and Assessment — s. 35.1, p. 1040
skin tear — Ch. 35, p. 1040
Skin, Wounds and Burns — Ch. 35, p. 1040
sleeve gastrectomy — Ch. 24, p. 696
sliding-scale insulin — Ch. 22, p. 635
slough — Ch. 35, p. 1040
small cell lung cancer (SCLC) — Ch. 13, p. 349
Smoking and Vaping Cessation — s. 14.5, p. 380
snooping — Ch. 1, p. 2
social determinants of health — Ch. 2, p. 35
Sodium Imbalances — s. 3.4, p. 67
sodium–glucose cotransporter 2 (SGLT2) inhibitor — Ch. 18, p. 504
soft mist inhaler — Ch. 14, p. 380
somatic pain — Ch. 5, p. 125
spacer — Ch. 14, p. 380
spasticity — Ch. 32, p. 943
speaking valve — Ch. 12, p. 318
specialist palliative care — Ch. 10, p. 264
speech-language pathologist (SLP) — Ch. 24, p. 696
spider angioma — Ch. 26, p. 759
spinal anesthesia — Ch. 7, p. 179
Spinal Cord Injury — s. 32.2, p. 943
spinal cord injury (SCI) — Ch. 32, p. 943
spinal fusion — Ch. 33, p. 976
spinal motion restriction — Ch. 32, p. 943
spinal shock — Ch. 32, p. 943
spirometry — Ch. 14, p. 380
splinting — Ch. 7, p. 179
spontaneous awakening trial — Ch. 15, p. 409
spontaneous bacterial peritonitis (SBP) — Ch. 26, p. 759
spontaneous breathing trial — Ch. 15, p. 409
spore — Ch. 4, p. 97
squamous cell carcinoma — Ch. 35, p. 1040
stable angina — Ch. 17, p. 476
Stable Angina and Chronic Coronary Disease — s. 17.2, p. 476
stage — Ch. 9, p. 234
standard induction — Ch. 11, p. 290
stapedectomy — Ch. 36, p. 1075
Starling forces — Ch. 3, p. 67
statin — Ch. 17, p. 476
status epilepticus — Ch. 30, p. 883
steatorrhea — Ch. 26, p. 759
steatotic liver disease — Ch. 26, p. 759
stem cell transplant — Ch. 20, p. 569
STEMI (ST-elevation myocardial infarction) — Ch. 17, p. 476
stenosis — Ch. 18, p. 504
stent — Ch. 17, p. 476
stent thrombosis — Ch. 17, p. 476
sternal precautions — Ch. 17, p. 476
steroid emergency card — Ch. 23, p. 665
Stevens-Johnson syndrome — Ch. 21, p. 601
stigma — Ch. 11, p. 290
stimulant toxicity — Ch. 11, p. 290
Stimulants, Cannabis and Other Substances — s. 11.5, p. 290
stoma — Ch. 25, p. 727
stoma site marking — Ch. 25, p. 727
STOP-Bang — Ch. 7, p. 179
STOPP/START — Ch. 8, p. 206
strangulation — Ch. 25, p. 727
stress incontinence — Ch. 28, p. 822
striae — Ch. 23, p. 665
stridor — Ch. 12, p. 318
Stroke — Ch. 31, p. 913
stroke — Ch. 31, p. 913
stroke mimic — Ch. 31, p. 913
stroke unit — Ch. 31, p. 913
Stroke Unit Care — s. 31.5, p. 913
stroke volume — Ch. 6, p. 152
structural determinants of health — Ch. 2, p. 35
subarachnoid hemorrhage (SAH) — Ch. 31, p. 913
subclinical hypothyroidism — Ch. 23, p. 665
subcutaneous emphysema — Ch. 12, p. 318
subdural hematoma — Ch. 32, p. 943
Subjective Global Assessment (SGA) — Ch. 24, p. 696
substance use disorder — Ch. 11, p. 290
Substance Use in Acute Care — Ch. 11, p. 290
Substance Use, Stigma and Health — s. 11.1, p. 290
substitute decision-maker (SDM) — Ch. 1, p. 2
substitute decision-making — Ch. 2, p. 35
sudden sensorineural hearing loss (SSNHL) — Ch. 36, p. 1075
superficial burn — Ch. 35, p. 1040
superficial vein thrombosis (SVT) — Ch. 19, p. 538
superior vena cava syndrome — Ch. 9, p. 234
supervised consumption site — Ch. 11, p. 290
support surface — Ch. 35, p. 1040
supported decision-making — Ch. 2, p. 35
supraventricular tachycardia (SVT) — Ch. 16, p. 439
surgical aortic valve replacement (SAVR) — Ch. 18, p. 504
surgical menopause — Ch. 29, p. 852
Surgical Safety Checklist — Ch. 7, p. 179
surgical site infection — Ch. 35, p. 1040
Surgical Wounds and Skin Infections — s. 35.4, p. 1040
survivorship care plan — Ch. 9, p. 234
sustained virologic response — Ch. 26, p. 759
swallowing screen — Ch. 24, p. 696
symptom-triggered treatment — Ch. 11, p. 290
symptomatic intracranial hemorrhage — Ch. 31, p. 913
synchronized cardioversion — Ch. 16, p. 439
syndrome of inappropriate antidiuretic hormone secretion (SIADH) — Ch. 3, p. 67
synovial joint — Ch. 34, p. 1008
synovitis — Ch. 34, p. 1008
synovium — Ch. 34, p. 1008
syphilis — Ch. 29, p. 852
systemic inflammatory response syndrome (SIRS) — Ch. 4, p. 97
systemic lupus erythematosus — Ch. 34, p. 1008
systemic sclerosis — Ch. 34, p. 1008
systemic vascular resistance — Ch. 6, p. 152
systolic dysfunction — Ch. 18, p. 504
tactile fremitus — Ch. 12, p. 318
takotsubo cardiomyopathy — Ch. 18, p. 504
target-organ damage — Ch. 19, p. 538
targeted interventions — Ch. 8, p. 206
targeted therapy — Ch. 9, p. 234
TB disease — Ch. 13, p. 349
TB infection — Ch. 13, p. 349
teach-back — Ch. 1, p. 2
telemetry — Ch. 16, p. 439
telestroke — Ch. 31, p. 913
tenesmus — Ch. 25, p. 727
tension pneumothorax — Ch. 6, p. 152
terminal delirium — Ch. 10, p. 264
terminal restlessness — Ch. 10, p. 264
tetraplegia — Ch. 32, p. 943
texture-modified diet — Ch. 24, p. 696
thalassemia — Ch. 20, p. 569
The Heart and Its Rhythm: A Brief Review — s. 16.1, p. 439
The Immune System: A Focused Review — s. 21.1, p. 601
The Last Days and Care After Death — s. 10.5, p. 264
The Liver, Biliary Tree and Pancreas — s. 26.1, p. 759
The Medical-Surgical Team and Scope of Practice — s. 1.3, p. 2
The Nervous System: A Focused Review — s. 30.1, p. 883
The Palliative Approach — s. 10.1, p. 264
The Perioperative Journey — s. 7.1, p. 179
third spacing — Ch. 3, p. 67
third-degree AV block — Ch. 16, p. 439
thoracentesis — Ch. 13, p. 349
three-way catheter — Ch. 28, p. 822
thrill — Ch. 27, p. 791
thrombocytopenia — Ch. 20, p. 569

thrombolysis — Ch. 15, p. 409
thrombophilia — Ch. 15, p. 409
thunderclap headache — Ch. 30, p. 883
Thyroid and Parathyroid Surgery — s. 23.3, p. 665
Thyroid Disorders — s. 23.2, p. 665
thyroid eye disease — Ch. 23, p. 665
thyroid storm — Ch. 23, p. 665
Thyroid, Parathyroid, Adrenal and Pituitary Disorders — Ch. 23, p. 665
thyroid-stimulating hormone (TSH) — Ch. 23, p. 665
thyroidectomy — Ch. 23, p. 665
thyrotoxicosis — Ch. 23, p. 665
tidal volume — Ch. 15, p. 409
tidalling — Ch. 15, p. 409
time in range — Ch. 22, p. 635
time-out — Ch. 7, p. 179
tinnitus — Ch. 36, p. 1075
TNM — Ch. 9, p. 234
tolerance — Ch. 5, p. 125
tonic-clonic seizure — Ch. 30, p. 883
tonicity — Ch. 3, p. 67
tophus — Ch. 34, p. 1008
total body surface area — Ch. 35, p. 1040
total hip arthroplasty — Ch. 33, p. 976
total knee arthroplasty — Ch. 33, p. 976
total pain — Ch. 10, p. 264
toxic epidermal necrolysis — Ch. 21, p. 601
toxic megacolon — Ch. 25, p. 727
tracheostomy — Ch. 12, p. 318
Track 1 — Ch. 10, p. 264
Track 2 — Ch. 10, p. 264
track-and-trigger system — Ch. 6, p. 152
traction — Ch. 33, p. 976
traditional tobacco — Ch. 14, p. 380
transcatheter aortic valve implantation (TAVI) — Ch. 18, p. 504
transcatheter edge-to-edge repair (TEER) — Ch. 18, p. 504
transcutaneous pacing — Ch. 16, p. 439
transduction — Ch. 5, p. 125
transfusion reaction — Ch. 20, p. 569
transfusion-associated circulatory overload (TACO) — Ch. 20, p. 569
transfusion-related acute lung injury (TRALI) — Ch. 20, p. 569
transgender — Ch. 2, p. 35
transient ischemic attack (TIA) — Ch. 31, p. 913
transition in care — Ch. 1, p. 2
transitions of care — Ch. 31, p. 913
transmission — Ch. 5, p. 125
transsphenoidal surgery — Ch. 23, p. 665
transudate — Ch. 13, p. 349
transurethral resection of bladder tumour (TURBT) — Ch. 28, p. 822
transurethral resection of the prostate (TURP) — Ch. 28, p. 822
transurethral resection syndrome (TUR syndrome) — Ch. 28, p. 822
trauma- and violence-informed care (TVIC) — Ch. 2, p. 35
Traumatic Brain and Spinal Cord Injury and Chronic Neurologic Disorders — Ch. 32, p. 943
traumatic brain injury (TBI) — Ch. 32, p. 943
Traumatic Brain Injury and Concussion — s. 32.1, p. 943
treat-to-target — Ch. 34, p. 1008
Treating Hypertension — s. 19.2, p. 538
trichomoniasis — Ch. 29, p. 852
triple therapy — Ch. 14, p. 380
troponin — Ch. 15, p. 409
Trousseau's sign — Ch. 3, p. 67
true urine output — Ch. 28, p. 822
tuberculin skin test (TST) — Ch. 13, p. 349
Tuberculosis — s. 13.4, p. 349
tuberculosis (TB) — Ch. 13, p. 349
tumour lysis syndrome (TLS) — Ch. 9, p. 234
tumour marker — Ch. 9, p. 234
tumour suppressor gene — Ch. 9, p. 234
tunnelling — Ch. 35, p. 1040
Two-Spirit — Ch. 2, p. 35
tympanic membrane — Ch. 36, p. 1075
tympanoplasty — Ch. 36, p. 1075
type 1 diabetes — Ch. 22, p. 635
type 2 diabetes — Ch. 22, p. 635
type 2 myocardial infarction — Ch. 17, p. 476
ulcerative colitis (UC) — Ch. 25, p. 727
ultrafiltration — Ch. 27, p. 791
undermining — Ch. 35, p. 1040
Understanding Pain — s. 5.1, p. 125
Understanding Stroke — s. 31.1, p. 913
undetectable = untransmittable (U=U) — Ch. 21, p. 601
unfractionated heparin (UFH) — Ch. 19, p. 538
United Nations Declaration on the Rights of Indigenous Peoples (UNDRIP) — Ch. 2, p. 35
universal fall precautions — Ch. 8, p. 206
unregulated care provider (UCP) — Ch. 1, p. 2
unregulated drug supply — Ch. 11, p. 290
unstable angina — Ch. 17, p. 476
unstageable pressure injury — Ch. 35, p. 1040
Upper Gastrointestinal Bleeding — s. 24.5, p. 696
upper gastrointestinal bleeding (UGIB) — Ch. 24, p. 696
Upper Gastrointestinal Disorders and Nutrition — Ch. 24, p. 696
urate-lowering therapy — Ch. 34, p. 1008
uremia — Ch. 27, p. 791
ureteral stent — Ch. 28, p. 822
ureteroscopy — Ch. 28, p. 822
urge incontinence — Ch. 28, p. 822
uric acid — Ch. 34, p. 1008
Urinary Catheters and CAUTI Prevention — s. 28.2, p. 822
urinary incontinence — Ch. 28, p. 822
urinary retention — Ch. 28, p. 822
Urinary Retention and Incontinence — s. 28.3, p. 822
Urinary Tract and Prostate Disorders — Ch. 28, p. 822
Urinary Tract Infection — s. 28.1, p. 822
urinary tract infection (UTI) — Ch. 28, p. 822
urine albumin-to-creatinine ratio (ACR) — Ch. 27, p. 791
urine culture — Ch. 28, p. 822
urine specific gravity — Ch. 3, p. 67
urolithiasis — Ch. 28, p. 822
urosepsis — Ch. 28, p. 822
urostomy — Ch. 28, p. 822
Using This Book — s. 1.8, p. 2
uterine fibroids — Ch. 29, p. 852
vaccine hesitancy — Ch. 21, p. 601
vagal manoeuvre — Ch. 16, p. 439
vaginal estrogen — Ch. 29, p. 852
Valvular Heart Disease — s. 18.5, p. 504
vancomycin-resistant enterococci (VRE) — Ch. 4, p. 97
varenicline — Ch. 14, p. 380
vasculitis — Ch. 34, p. 1008
vaso-occlusive crisis — Ch. 20, p. 569
vasomotor symptoms — Ch. 29, p. 852
vasopressor — Ch. 6, p. 152
vegetation — Ch. 18, p. 504
Venous Disease and VTE — s. 19.6, p. 538
venous thromboembolism (VTE) — Ch. 7, p. 179
ventilation — Ch. 12, p. 318
ventilation–perfusion (V/Q) mismatch — Ch. 12, p. 318
ventilation–perfusion (V/Q) scan — Ch. 15, p. 409
ventilator-associated pneumonia — Ch. 15, p. 409
ventilator-associated pneumonia (VAP) — Ch. 13, p. 349
ventricular fibrillation (VF) — Ch. 16, p. 439
ventricular tachycardia (VT) — Ch. 16, p. 439
Venturi mask — Ch. 12, p. 318
verbal descriptor scale — Ch. 5, p. 125
vertigo — Ch. 36, p. 1075
vesicant — Ch. 9, p. 234
vestibular rehabilitation — Ch. 36, p. 1075
video remote interpreting (VRI) — Ch. 36, p. 1075
Viral Hepatitis and Steatotic Liver Disease — s. 26.2, p. 759
viral load — Ch. 21, p. 601
Virchow's triad — Ch. 15, p. 409
visceral pain — Ch. 5, p. 125
Vision and Eye Assessment — s. 36.1, p. 1075
visual acuity — Ch. 36, p. 1075
vital capacity — Ch. 32, p. 943
volvulus — Ch. 25, p. 727
von Willebrand disease (VWD) — Ch. 20, p. 569
waiver of final consent — Ch. 10, p. 264
water seal — Ch. 15, p. 409
weaning — Ch. 15, p. 409
wearing off — Ch. 32, p. 943
weight bias — Ch. 24, p. 696

weight stigma — Ch. 2, p. 35
Wells rule — Ch. 15, p. 409
Wernicke encephalopathy — Ch. 11, p. 290
wet suction — Ch. 15, p. 409
What Medical-Surgical Nursing Is — s. 1.1, p. 2
wheeze — Ch. 12, p. 318
Where Adults Receive Care in Canada — s. 1.2, p. 2
whispered voice test — Ch. 36, p. 1075
white-coat hypertension — Ch. 19, p. 538
window period — Ch. 21, p. 601
withdrawal seizure — Ch. 11, p. 290
work of breathing — Ch. 12, p. 318
wound bed preparation — Ch. 35, p. 1040
Wound Healing and Wound Care — s. 35.3, p. 1040
written action plan — Ch. 14, p. 380
YEARS — Ch. 15, p. 409

BUILT FROM THE GROUND UP FOR CANADIAN BSCN & PRACTICAL NURSING CURRICULA

Medical-Surgical Nursing: A Canadian Open Text

Medical-Surgical Nursing: A Canadian Open Text is a comprehensive, 36-chapter open textbook written specifically for Canadian undergraduate and practical nursing students. Every chapter is grounded in Canadian epidemiology, SI laboratory intervals (mmol/L, µmol/L, g/L), Health Canada Drug Product Database nomenclature, provincial and territorial regulatory standards, and national clinical practice guidelines.

Nine-Unit Clinical Structure (36 Chapters • 245 Clinical Figures)

Unit	Chapters	Clinical Scope
Unit I	Chapters 1–6	Canadian Health Systems, Indigenous Cultural Safety, Fluids/Electrolytes, Sepsis, Pain, Shock
Unit II	Chapters 7–11	Perioperative Care, Older Adults in Acute Care, Cancer Care, Palliative Care & MAID, Substance Use
Unit III	Chapters 12–15	Respiratory Assessment, Oxygen Therapy, Pneumonia, Lung Cancer, COPD, Asthma, ARDS & PE
Unit IV	Chapters 16–19	Cardiac Assessment, ECG Dysrhythmias, ACS, Heart Failure, Valvular Disease, Hypertension & Vascular
Unit V	Chapters 20–23	Hematology, Transfusion Therapy, Immunity, Allergy, HIV, Diabetes Mellitus & Endocrine Care
Unit VI	Chapters 24–26	Upper & Lower Gastrointestinal Disorders, Enteral/Parenteral Nutrition, Ostomies, Liver, Biliary & Pancreas
Unit VII	Chapters 27–29	Acute Kidney Injury, Chronic Kidney Disease, Dialysis, Urinary Tract, Prostate & Reproductive Care
Unit VIII	Chapters 30–32	Neurologic Assessment, Increased ICP, Ischemic & Hemorrhagic Stroke, TBI, SCI & Chronic Neurologic Care
Unit IX	Chapters 33–36	Musculoskeletal Trauma, Orthopedic Surgery, Arthritis, Connective Tissue, Wounds, Burns, Eye & Ear Care

Pedagogical Features in Every Chapter

Feature	Educational Purpose
Unfolding Practice Story	Follows 36 unique Canadian nurses (18 RNs, 18 RPNs/LPNs) and adult patients from presentation to discharge.
Canadian Context & OCAP®	Integrates TRC Calls to Action 18–24, Joyce's Principle, NIHB coverage, and rural/northern transport.
RN / RPN / LPN Scope Boxes	Applies CNO's Scope of Practice framework (authority, competence, and context) across provincial regulations.
1,310 Licensure Review Items	30 to 40 NCLEX-RN, REx-PN, and CPNRE questions per chapter (with unfolding case clusters and full rationales).

About the Author: Andrew Lee, BEd, BN, MN, RN, CCN(C) is a Professor of Nursing at Loyalist College in Belleville, Ontario. Holding degrees in Education and Nursing and Canadian Nurses Association certification in Cardiovascular Nursing (CCN(C)), his clinical and academic work focuses on adult acute medical-surgical nursing, clinical judgment, and open nursing education.

Licence: Creative Commons Attribution-NonCommercial-ShareAlike 4.0 International (CC BY-NC-SA 4.0)